

# [MS-CSOMSPT]:

## SharePoint Client-Side Object Model Protocol

---

### Intellectual Property Rights Notice for Open Specifications Documentation

- **Technical Documentation.** Microsoft publishes Open Specifications documentation (“this documentation”) for protocols, file formats, data portability, computer languages, and standards support. Additionally, overview documents cover inter-protocol relationships and interactions.
- **Copyrights.** This documentation is covered by Microsoft copyrights. Regardless of any other terms that are contained in the terms of use for the Microsoft website that hosts this documentation, you can make copies of it in order to develop implementations of the technologies that are described in this documentation and can distribute portions of it in your implementations that use these technologies or in your documentation as necessary to properly document the implementation. You can also distribute in your implementation, with or without modification, any schemas, IDLs, or code samples that are included in the documentation. This permission also applies to any documents that are referenced in the Open Specifications documentation.
- **No Trade Secrets.** Microsoft does not claim any trade secret rights in this documentation.
- **Patents.** Microsoft has patents that might cover your implementations of the technologies described in the Open Specifications documentation. Neither this notice nor Microsoft's delivery of this documentation grants any licenses under those patents or any other Microsoft patents. However, a given Open Specifications document might be covered by the Microsoft [Open Specifications Promise](#) or the [Microsoft Community Promise](#). If you would prefer a written license, or if the technologies described in this documentation are not covered by the Open Specifications Promise or Community Promise, as applicable, patent licenses are available by contacting [iplg@microsoft.com](mailto:iplg@microsoft.com).
- **License Programs.** To see all of the protocols in scope under a specific license program and the associated patents, visit the [Patent Map](#).
- **Trademarks.** The names of companies and products contained in this documentation might be covered by trademarks or similar intellectual property rights. This notice does not grant any licenses under those rights. For a list of Microsoft trademarks, visit [www.microsoft.com/trademarks](http://www.microsoft.com/trademarks).
- **Fictitious Names.** The example companies, organizations, products, domain names, email addresses, logos, people, places, and events that are depicted in this documentation are fictitious. No association with any real company, organization, product, domain name, email address, logo, person, place, or event is intended or should be inferred.

**Reservation of Rights.** All other rights are reserved, and this notice does not grant any rights other than as specifically described above, whether by implication, estoppel, or otherwise.

**Tools.** The Open Specifications documentation does not require the use of Microsoft programming tools or programming environments in order for you to develop an implementation. If you have access to Microsoft programming tools and environments, you are free to take advantage of them. Certain Open Specifications documents are intended for use in conjunction with publicly available standards specifications and network programming art and, as such, assume that the reader either is familiar with the aforementioned material or has immediate access to it.

**Support.** For questions and support, please contact [dochelp@microsoft.com](mailto:dochelp@microsoft.com).

## Revision Summary

Date	Revision History	Revision Class	Comments
7/13/2009	0.1	Major	Initial Availability
8/28/2009	0.2	Editorial	Revised and edited the technical content
11/6/2009	0.3	Editorial	Revised and edited the technical content
2/19/2010	1.0	Major	Updated and revised the technical content
3/31/2010	1.01	Editorial	Revised and edited the technical content
4/30/2010	1.02	Minor	Updated the technical content
6/7/2010	1.03	Editorial	Revised and edited the technical content
6/29/2010	1.04	Editorial	Changed language and formatting in the technical content.
7/23/2010	1.04	None	No changes to the meaning, language, or formatting of the technical content.
9/27/2010	1.04	None	No changes to the meaning, language, or formatting of the technical content.
11/15/2010	1.04	None	No changes to the meaning, language, or formatting of the technical content.
12/17/2010	1.04	None	No changes to the meaning, language, or formatting of the technical content.
3/18/2011	1.04	None	No changes to the meaning, language, or formatting of the technical content.
6/10/2011	1.04	None	No changes to the meaning, language, or formatting of the technical content.
1/20/2012	2.0	Major	Significantly changed the technical content.
4/11/2012	2.0	None	No changes to the meaning, language, or formatting of the technical content.
7/16/2012	2.0	None	No changes to the meaning, language, or formatting of the technical content.
9/12/2012	2.0	None	No changes to the meaning, language, or formatting of the technical content.
10/8/2012	3.0	Major	Significantly changed the technical content.
2/11/2013	4.0	Major	Significantly changed the technical content.
7/30/2013	5.0	Major	Significantly changed the technical content.
11/18/2013	6.0	Major	Significantly changed the technical content.
2/10/2014	6.0	None	No changes to the meaning, language, or formatting of the technical content.
4/30/2014	6.1	Minor	Clarified the meaning of the technical content.
7/31/2014	7.0	Major	Significantly changed the technical content.

<b>Date</b>	<b>Revision History</b>	<b>Revision Class</b>	<b>Comments</b>
10/30/2014	7.0	None	No changes to the meaning, language, or formatting of the technical content.
2/26/2016	8.0	Major	Significantly changed the technical content.
7/1/2016	9.0	Major	Significantly changed the technical content.
10/13/2016	10.0	Major	Significantly changed the technical content.
11/14/2016	10.0	None	No changes to the meaning, language, or formatting of the technical content.
8/25/2017	11.0	Major	Significantly changed the technical content.
12/12/2017	12.0	Major	Significantly changed the technical content.
7/24/2018	13.0	Major	Significantly changed the technical content.
10/1/2018	14.0	Major	Significantly changed the technical content.
12/11/2018	14.1	Minor	Clarified the meaning of the technical content.
7/20/2021	15.0	Major	Significantly changed the technical content.
10/5/2021	16.0	Major	Significantly changed the technical content.

# Table of Contents

<b>1</b>	<b>Introduction</b>	<b>122</b>
1.1	Glossary	122
1.2	References	140
1.2.1	Normative References	140
1.2.2	Informative References	141
1.3	Overview	141
1.4	Relationship to Other Protocols	141
1.5	Prerequisites/Preconditions	142
1.6	Applicability Statement	142
1.7	Versioning and Capability Negotiation	142
1.8	Vendor-Extensible Fields	142
1.9	Standards Assignments	143
<b>2</b>	<b>Messages</b>	<b>144</b>
2.1	Transport	144
2.2	Message Syntax	144
2.2.1	Common Exceptions	144
<b>3</b>	<b>Protocol Details</b>	<b>145</b>
3.1	Common Details	145
3.2	Server Details	145
3.2.1	Abstract Data Model	145
3.2.1.1	Parent Type	145
3.2.1.2	Abstract Data Model for REST List Items Support	146
3.2.1.3	Field Type to Client Scalar Property Type	147
3.2.1.4	Social features	147
3.2.2	Timers	148
3.2.3	Initialization	149
3.2.4	Higher-Layer Triggered Events	149
3.2.5	Message Processing Events and Sequencing Rules	149
3.2.5.1	Microsoft.SharePoint.Client.AddFieldOptions	149
3.2.5.1.1	Field Values	149
3.2.5.1.1.1	DefaultValue	149
3.2.5.1.1.2	AddToDefaultContentType	149
3.2.5.1.1.3	AddToNoContentType	149
3.2.5.1.1.4	AddToAllContentTypes	149
3.2.5.1.1.5	AddFieldInternalNameHint	149
3.2.5.1.1.6	AddFieldToDefaultView	149
3.2.5.1.1.7	AddFieldCheckDisplayName	150
3.2.5.2	Microsoft.SharePoint.Client.BasePermissions	150
3.2.5.2.1	Properties	150
3.2.5.2.1.1	Scalar Properties	150
3.2.5.2.1.1.1	High	150
3.2.5.2.1.1.2	Low	150
3.2.5.2.1.2	ObjectPath Properties	152
3.2.5.3	Microsoft.SharePoint.Client.BaseType	152
3.2.5.3.1	Field Values	152
3.2.5.3.1.1	None	153
3.2.5.3.1.2	GenericList	153
3.2.5.3.1.3	DocumentLibrary	153
3.2.5.3.1.4	Unused	153
3.2.5.3.1.5	DiscussionBoard	153
3.2.5.3.1.6	Survey	153
3.2.5.3.1.7	Issue	153
3.2.5.4	Microsoft.SharePoint.Client.BrowserFileHandling	153

3.2.5.4.1	Field Values .....	153
3.2.5.4.1.1	Permissive .....	153
3.2.5.4.1.2	Strict.....	153
3.2.5.5	Microsoft.SharePoint.Client.CalendarType .....	154
3.2.5.5.1	Field Values .....	154
3.2.5.5.1.1	None .....	154
3.2.5.5.1.2	Gregorian .....	154
3.2.5.5.1.3	Japan .....	154
3.2.5.5.1.4	Taiwan .....	154
3.2.5.5.1.5	Korea .....	154
3.2.5.5.1.6	Hijri .....	154
3.2.5.5.1.7	Thai .....	154
3.2.5.5.1.8	Hebrew.....	154
3.2.5.5.1.9	GregorianMEFrench .....	155
3.2.5.5.1.10	GregorianArabic.....	155
3.2.5.5.1.11	GregorianXLITEnglish .....	155
3.2.5.5.1.12	GregorianXLITFrench.....	155
3.2.5.5.1.13	KoreaJapanLunar .....	155
3.2.5.5.1.14	ChineseLunar .....	155
3.2.5.5.1.15	SakaEra .....	155
3.2.5.5.1.16	UmAlQura .....	155
3.2.5.6	Microsoft.SharePoint.Client.CamlQuery .....	155
3.2.5.6.1	Properties.....	155
3.2.5.6.1.1	Scalar Properties.....	156
3.2.5.6.1.1.1	AllowIncrementalResults .....	156
3.2.5.6.1.1.2	DatesInUtc .....	156
3.2.5.6.1.1.3	FolderServerRelativePath.....	156
3.2.5.6.1.1.4	FolderServerRelativeUrl.....	156
3.2.5.6.1.1.5	ListItemCollectionPosition .....	156
3.2.5.6.1.1.6	ViewXml.....	156
3.2.5.6.1.2	ObjectPath Properties .....	156
3.2.5.7	Microsoft.SharePoint.Client.Change .....	157
3.2.5.7.1	Properties.....	157
3.2.5.7.1.1	Scalar Properties.....	157
3.2.5.7.1.1.1	ChangeToken .....	157
3.2.5.7.1.1.2	ChangeType .....	157
3.2.5.7.1.1.3	RelativeTime.....	157
3.2.5.7.1.1.4	SiteId .....	157
3.2.5.7.1.1.5	Time .....	157
3.2.5.7.1.2	ObjectPath Properties.....	158
3.2.5.7.2	Methods .....	158
3.2.5.7.2.1	Scalar Methods .....	158
3.2.5.7.2.2	ObjectPath Methods .....	158
3.2.5.8	Microsoft.SharePoint.Client.ChangeAlert .....	158
3.2.5.8.1	Properties.....	158
3.2.5.8.1.1	Scalar Properties.....	158
3.2.5.8.1.1.1	AlertId .....	158
3.2.5.8.1.1.2	ChangeToken .....	158
3.2.5.8.1.1.3	ChangeType .....	158
3.2.5.8.1.1.4	RelativeTime.....	159
3.2.5.8.1.1.5	SiteId .....	159
3.2.5.8.1.1.6	Time .....	159
3.2.5.8.1.1.7	WebId.....	159
3.2.5.8.1.2	ObjectPath Properties .....	159
3.2.5.8.2	Methods .....	159
3.2.5.8.2.1	Scalar Methods .....	159
3.2.5.8.2.2	ObjectPath Methods .....	159
3.2.5.9	Microsoft.SharePoint.Client.ChangeCollection .....	159

3.2.5.9.1	Properties.....	160
3.2.5.9.1.1	Scalar Properties.....	160
3.2.5.9.1.2	ObjectPath Properties.....	160
3.2.5.9.2	Methods.....	160
3.2.5.9.2.1	Scalar Methods.....	160
3.2.5.9.2.2	ObjectPath Methods.....	160
3.2.5.10	Microsoft.SharePoint.Client.ChangeContentType.....	160
3.2.5.10.1	Properties.....	160
3.2.5.10.1.1	Scalar Properties.....	160
3.2.5.10.1.1.1	ChangeToken.....	160
3.2.5.10.1.1.2	ChangeType.....	160
3.2.5.10.1.1.3	ContentTypeId.....	160
3.2.5.10.1.1.4	RelativeTime.....	161
3.2.5.10.1.1.5	SiteId.....	161
3.2.5.10.1.1.6	Time.....	161
3.2.5.10.1.1.7	WebId.....	161
3.2.5.10.1.2	ObjectPath Properties.....	161
3.2.5.10.2	Methods.....	161
3.2.5.10.2.1	Scalar Methods.....	161
3.2.5.10.2.2	ObjectPath Methods.....	161
3.2.5.11	Microsoft.SharePoint.Client.ChangeField.....	162
3.2.5.11.1	Properties.....	162
3.2.5.11.1.1	Scalar Properties.....	162
3.2.5.11.1.1.1	ChangeToken.....	162
3.2.5.11.1.1.2	ChangeType.....	162
3.2.5.11.1.1.3	FieldId.....	162
3.2.5.11.1.1.4	RelativeTime.....	162
3.2.5.11.1.1.5	SiteId.....	162
3.2.5.11.1.1.6	Time.....	163
3.2.5.11.1.1.7	WebId.....	163
3.2.5.11.1.2	ObjectPath Properties.....	163
3.2.5.11.2	Methods.....	163
3.2.5.11.2.1	Scalar Methods.....	163
3.2.5.11.2.2	ObjectPath Methods.....	163
3.2.5.12	Microsoft.SharePoint.Client.ChangeFile.....	163
3.2.5.12.1	Properties.....	163
3.2.5.12.1.1	Scalar Properties.....	163
3.2.5.12.1.1.1	ChangeToken.....	164
3.2.5.12.1.1.2	ChangeType.....	164
3.2.5.12.1.1.3	RelativeTime.....	164
3.2.5.12.1.1.4	SiteId.....	164
3.2.5.12.1.1.5	Time.....	164
3.2.5.12.1.1.6	UniqueId.....	164
3.2.5.12.1.1.7	WebId.....	164
3.2.5.12.1.2	ObjectPath Properties.....	165
3.2.5.12.2	Methods.....	165
3.2.5.12.2.1	Scalar Methods.....	165
3.2.5.12.2.2	ObjectPath Methods.....	165
3.2.5.13	Microsoft.SharePoint.Client.ChangeFolder.....	165
3.2.5.13.1	Properties.....	165
3.2.5.13.1.1	Scalar Properties.....	165
3.2.5.13.1.1.1	ChangeToken.....	165
3.2.5.13.1.1.2	ChangeType.....	165
3.2.5.13.1.1.3	RelativeTime.....	166
3.2.5.13.1.1.4	SiteId.....	166
3.2.5.13.1.1.5	Time.....	166
3.2.5.13.1.1.6	UniqueId.....	166
3.2.5.13.1.1.7	WebId.....	166

3.2.5.13.1.2	ObjectPath Properties	167
3.2.5.13.2	Methods	167
3.2.5.13.2.1	Scalar Methods	167
3.2.5.13.2.2	ObjectPath Methods	167
3.2.5.14	Microsoft.SharePoint.Client.ChangeGroup	167
3.2.5.14.1	Properties	167
3.2.5.14.1.1	Scalar Properties	167
3.2.5.14.1.1.1	ChangeToken	167
3.2.5.14.1.1.2	ChangeType	167
3.2.5.14.1.1.3	GroupId	167
3.2.5.14.1.1.4	RelativeTime	167
3.2.5.14.1.1.5	SiteId	168
3.2.5.14.1.1.6	Time	168
3.2.5.14.1.2	ObjectPath Properties	168
3.2.5.14.2	Methods	168
3.2.5.14.2.1	Scalar Methods	168
3.2.5.14.2.2	ObjectPath Methods	168
3.2.5.15	Microsoft.SharePoint.Client.ChangeItem	168
3.2.5.15.1	Properties	168
3.2.5.15.1.1	Scalar Properties	168
3.2.5.15.1.1.1	ActivityType	168
3.2.5.15.1.1.2	ChangeToken	169
3.2.5.15.1.1.3	ChangeType	169
3.2.5.15.1.1.4	ContentTypeId	169
3.2.5.15.1.1.5	Editor	169
3.2.5.15.1.1.6	EditorEmailHint	169
3.2.5.15.1.1.7	EditorLoginName	169
3.2.5.15.1.1.8	FileSystemObjectType	169
3.2.5.15.1.1.9	FileType	169
3.2.5.15.1.1.10	Hidden	170
3.2.5.15.1.1.11	ItemId	170
3.2.5.15.1.1.12	ListId	170
3.2.5.15.1.1.13	ListTemplate	170
3.2.5.15.1.1.14	ListTitle	170
3.2.5.15.1.1.15	RelativeTime	171
3.2.5.15.1.1.16	ServerRelativeUrl	171
3.2.5.15.1.1.17	SharedByUser	171
3.2.5.15.1.1.18	SharedWithUsers	171
3.2.5.15.1.1.19	SiteId	171
3.2.5.15.1.1.20	Time	171
3.2.5.15.1.1.21	Title	171
3.2.5.15.1.1.22	UniqueId	172
3.2.5.15.1.1.23	WebId	172
3.2.5.15.1.2	ObjectPath Properties	172
3.2.5.15.2	Methods	172
3.2.5.15.2.1	Scalar Methods	172
3.2.5.15.2.2	ObjectPath Methods	172
3.2.5.16	Microsoft.SharePoint.Client.ChangeList	172
3.2.5.16.1	Properties	172
3.2.5.16.1.1	Scalar Properties	172
3.2.5.16.1.1.1	BaseTemplate	172
3.2.5.16.1.1.2	ChangeToken	173
3.2.5.16.1.1.3	ChangeType	173
3.2.5.16.1.1.4	Editor	173
3.2.5.16.1.1.5	Hidden	173
3.2.5.16.1.1.6	ListId	173
3.2.5.16.1.1.7	RelativeTime	173
3.2.5.16.1.1.8	RootFolderUrl	174

3.2.5.16.1.1.9	SiteId .....	174
3.2.5.16.1.1.10	Time .....	174
3.2.5.16.1.1.11	Title .....	174
3.2.5.16.1.1.12	WebId .....	174
3.2.5.16.1.2	ObjectPath Properties .....	174
3.2.5.16.1.2.1	Creator .....	174
3.2.5.16.2	Methods .....	175
3.2.5.16.2.1	Scalar Methods .....	175
3.2.5.16.2.2	ObjectPath Methods .....	175
3.2.5.17	Microsoft.SharePoint.Client.ChangeQuery .....	175
3.2.5.17.1	Properties .....	175
3.2.5.17.1.1	Scalar Properties .....	175
3.2.5.17.1.1.1	Activity .....	175
3.2.5.17.1.1.2	Add .....	175
3.2.5.17.1.1.3	Alert .....	175
3.2.5.17.1.1.4	ChangeTokenEnd .....	175
3.2.5.17.1.1.5	ChangeTokenStart .....	175
3.2.5.17.1.1.6	ContentType .....	176
3.2.5.17.1.1.7	DeleteObject .....	176
3.2.5.17.1.1.8	FetchLimit .....	176
3.2.5.17.1.1.9	Field .....	176
3.2.5.17.1.1.10	File .....	176
3.2.5.17.1.1.11	Folder .....	176
3.2.5.17.1.1.12	Group .....	176
3.2.5.17.1.1.13	GroupMembershipAdd .....	177
3.2.5.17.1.1.14	GroupMembershipDelete .....	177
3.2.5.17.1.1.15	Item .....	177
3.2.5.17.1.1.16	LatestFirst .....	177
3.2.5.17.1.1.17	List .....	177
3.2.5.17.1.1.18	Move .....	177
3.2.5.17.1.1.19	Navigation .....	177
3.2.5.17.1.1.20	RecursiveAll .....	177
3.2.5.17.1.1.21	Rename .....	178
3.2.5.17.1.1.22	RequireSecurityTrim .....	178
3.2.5.17.1.1.23	Restore .....	178
3.2.5.17.1.1.24	RoleAssignmentAdd .....	178
3.2.5.17.1.1.25	RoleAssignmentDelete .....	178
3.2.5.17.1.1.26	RoleDefinitionAdd .....	178
3.2.5.17.1.1.27	RoleDefinitionDelete .....	178
3.2.5.17.1.1.28	RoleDefinitionUpdate .....	179
3.2.5.17.1.1.29	SecurityPolicy .....	179
3.2.5.17.1.1.30	Site .....	179
3.2.5.17.1.1.31	SystemUpdate .....	179
3.2.5.17.1.1.32	Update .....	179
3.2.5.17.1.1.33	User .....	179
3.2.5.17.1.1.34	View .....	179
3.2.5.17.1.1.35	Web .....	180
3.2.5.17.1.2	ObjectPath Properties .....	180
3.2.5.18	Microsoft.SharePoint.Client.ChangeSite .....	180
3.2.5.18.1	Properties .....	180
3.2.5.18.1.1	Scalar Properties .....	180
3.2.5.18.1.1.1	ChangeToken .....	180
3.2.5.18.1.1.2	ChangeType .....	180
3.2.5.18.1.1.3	RelativeTime .....	180
3.2.5.18.1.1.4	SiteId .....	180
3.2.5.18.1.1.5	Time .....	180
3.2.5.18.1.2	ObjectPath Properties .....	181
3.2.5.18.2	Methods .....	181



3.2.5.18.2.1	Scalar Methods .....	181
3.2.5.18.2.2	ObjectPath Methods .....	181
3.2.5.19	Microsoft.SharePoint.Client.ChangeToken.....	181
3.2.5.19.1	Properties.....	181
3.2.5.19.1.1	Scalar Properties.....	181
3.2.5.19.1.1.1	StringValue.....	181
3.2.5.19.1.2	ObjectPath Properties.....	182
3.2.5.20	Microsoft.SharePoint.Client.ChangeType .....	182
3.2.5.20.1	Field Values .....	182
3.2.5.20.1.1	NoChange .....	182
3.2.5.20.1.2	Add.....	182
3.2.5.20.1.3	Update .....	182
3.2.5.20.1.4	DeleteObject .....	183
3.2.5.20.1.5	Rename .....	183
3.2.5.20.1.6	MoveAway .....	183
3.2.5.20.1.7	MoveInto .....	183
3.2.5.20.1.8	Restore.....	183
3.2.5.20.1.9	RoleAdd.....	183
3.2.5.20.1.10	RoleDelete .....	183
3.2.5.20.1.11	RoleUpdate .....	183
3.2.5.20.1.12	AssignmentAdd.....	183
3.2.5.20.1.13	AssignmentDelete .....	184
3.2.5.20.1.14	MemberAdd.....	184
3.2.5.20.1.15	MemberDelete .....	184
3.2.5.20.1.16	SystemUpdate.....	184
3.2.5.20.1.17	Navigation .....	184
3.2.5.20.1.18	ScopeAdd .....	184
3.2.5.20.1.19	ScopeDelete.....	184
3.2.5.20.1.20	ListContentTypeAdd .....	184
3.2.5.20.1.21	ListContentTypeDelete.....	184
3.2.5.20.1.22	Dirty .....	185
3.2.5.20.1.23	Activity .....	185
3.2.5.21	Microsoft.SharePoint.Client.ChangeUser.....	185
3.2.5.21.1	Properties.....	185
3.2.5.21.1.1	Scalar Properties.....	185
3.2.5.21.1.1.1	Activate .....	185
3.2.5.21.1.1.2	ChangeToken.....	185
3.2.5.21.1.1.3	ChangeType .....	185
3.2.5.21.1.1.4	RelativeTime.....	185
3.2.5.21.1.1.5	SiteId .....	186
3.2.5.21.1.1.6	Time .....	186
3.2.5.21.1.1.7	UserId.....	186
3.2.5.21.1.2	ObjectPath Properties.....	186
3.2.5.21.2	Methods .....	186
3.2.5.21.2.1	Scalar Methods.....	186
3.2.5.21.2.2	ObjectPath Methods .....	186
3.2.5.22	Microsoft.SharePoint.Client.ChangeView .....	186
3.2.5.22.1	Properties.....	186
3.2.5.22.1.1	Scalar Properties.....	186
3.2.5.22.1.1.1	ChangeToken.....	186
3.2.5.22.1.1.2	ChangeType .....	187
3.2.5.22.1.1.3	ListId .....	187
3.2.5.22.1.1.4	RelativeTime.....	187
3.2.5.22.1.1.5	SiteId .....	187
3.2.5.22.1.1.6	Time .....	187
3.2.5.22.1.1.7	ViewId .....	187
3.2.5.22.1.1.8	WebId.....	188
3.2.5.22.1.2	ObjectPath Properties.....	188

3.2.5.22.2	Methods	188
3.2.5.22.2.1	Scalar Methods	188
3.2.5.22.2.2	ObjectPath Methods	188
3.2.5.23	Microsoft.SharePoint.Client.ChangeWeb	188
3.2.5.23.1	Properties	188
3.2.5.23.1.1	Scalar Properties	188
3.2.5.23.1.1.1	ChangeToken	188
3.2.5.23.1.1.2	ChangeType	188
3.2.5.23.1.1.3	RelativeTime	189
3.2.5.23.1.1.4	SiteId	189
3.2.5.23.1.1.5	Time	189
3.2.5.23.1.1.6	WebId	189
3.2.5.23.1.2	ObjectPath Properties	189
3.2.5.23.2	Methods	189
3.2.5.23.2.1	Scalar Methods	189
3.2.5.23.2.2	ObjectPath Methods	189
3.2.5.24	Microsoft.SharePoint.Client.CheckinType	190
3.2.5.24.1	Field Values	190
3.2.5.24.1.1	MinorCheckIn	190
3.2.5.24.1.2	MajorCheckIn	190
3.2.5.24.1.3	OverwriteCheckIn	190
3.2.5.25	Microsoft.SharePoint.Client.CheckOutType	190
3.2.5.25.1	Field Values	190
3.2.5.25.1.1	Online	190
3.2.5.25.1.2	Offline	190
3.2.5.25.1.3	None	190
3.2.5.26	Microsoft.SharePoint.Client.ChoiceFormatType	191
3.2.5.26.1	Field Values	191
3.2.5.26.1.1	Dropdown	191
3.2.5.26.1.2	RadioButtons	191
3.2.5.27	Microsoft.SharePoint.Client.ContentType	191
3.2.5.27.1	Properties	191
3.2.5.27.1.1	Scalar Properties	191
3.2.5.27.1.1.1	Description	191
3.2.5.27.1.1.2	DisplayFormTemplateName	191
3.2.5.27.1.1.3	DisplayFormUrl	191
3.2.5.27.1.1.4	DocumentTemplate	192
3.2.5.27.1.1.5	DocumentTemplateUrl	192
3.2.5.27.1.1.6	EditFormTemplateName	192
3.2.5.27.1.1.7	EditFormUrl	192
3.2.5.27.1.1.8	Group	192
3.2.5.27.1.1.9	Hidden	193
3.2.5.27.1.1.10	Id	193
3.2.5.27.1.1.11	Name	193
3.2.5.27.1.1.12	NewFormTemplateName	193
3.2.5.27.1.1.13	NewFormUrl	193
3.2.5.27.1.1.14	ReadOnly	193
3.2.5.27.1.1.15	SchemaXml	193
3.2.5.27.1.1.16	Scope	194
3.2.5.27.1.1.17	JSLink	194
3.2.5.27.1.1.18	Sealed	194
3.2.5.27.1.1.19	StringId	194
3.2.5.27.1.1.20	SchemaXmlWithResourceTokens	194
3.2.5.27.1.1.21	MobileDisplayFormUrl	194
3.2.5.27.1.1.22	MobileEditFormUrl	194
3.2.5.27.1.1.23	MobileNewFormUrl	194
3.2.5.27.1.2	ObjectPath Properties	195
3.2.5.27.1.2.1	DescriptionResource	195

3.2.5.27.1.2.2	FieldLinks .....	195
3.2.5.27.1.2.3	Fields .....	195
3.2.5.27.1.2.4	NameResource .....	195
3.2.5.27.1.2.5	Parent .....	195
3.2.5.27.1.2.6	WorkflowAssociations .....	195
3.2.5.27.2	Methods .....	195
3.2.5.27.2.1	Scalar Methods .....	195
3.2.5.27.2.1.1	DeleteObject .....	195
3.2.5.27.2.1.2	Update .....	196
3.2.5.27.2.2	ObjectPath Methods .....	196
3.2.5.28	Microsoft.SharePoint.Client.ContentValueCollection .....	196
3.2.5.28.1	Properties .....	196
3.2.5.28.1.1	Scalar Properties .....	196
3.2.5.28.1.2	ObjectPath Properties .....	196
3.2.5.28.2	Methods .....	196
3.2.5.28.2.1	Scalar Methods .....	196
3.2.5.28.2.2	ObjectPath Methods .....	196
3.2.5.28.2.2.1	Add .....	196
3.2.5.28.2.2.2	AddExistingContentType .....	197
3.2.5.28.2.2.3	GetById .....	197
3.2.5.28.2.2.4	AddAvailableContentType .....	198
3.2.5.29	Microsoft.SharePoint.Client.ContentTypeCreationInformation .....	198
3.2.5.29.1	Properties .....	198
3.2.5.29.1.1	Scalar Properties .....	198
3.2.5.29.1.1.1	Description .....	198
3.2.5.29.1.1.2	Group .....	198
3.2.5.29.1.1.3	Id .....	199
3.2.5.29.1.1.4	Name .....	199
3.2.5.29.1.2	ObjectPath Properties .....	199
3.2.5.29.1.2.1	ParentContentType .....	199
3.2.5.30	Microsoft.SharePoint.Client.ContentTypeId .....	199
3.2.5.30.1	Properties .....	199
3.2.5.30.1.1	Scalar Properties .....	199
3.2.5.30.1.1.1	StringValue .....	199
3.2.5.30.1.2	ObjectPath Properties .....	199
3.2.5.31	Microsoft.SharePoint.Client.CustomizedPageStatus .....	200
3.2.5.31.1	Field Values .....	200
3.2.5.31.1.1	None .....	200
3.2.5.31.1.2	Uncustomized .....	200
3.2.5.31.1.3	Customized .....	200
3.2.5.32	Microsoft.SharePoint.Client.DateTimeFieldFormatType .....	200
3.2.5.32.1	Field Values .....	200
3.2.5.32.1.1	DateOnly .....	200
3.2.5.32.1.2	DateTime .....	200
3.2.5.33	Microsoft.SharePoint.Client.DraftVisibilityType .....	200
3.2.5.33.1	Field Values .....	201
3.2.5.33.1.1	Reader .....	201
3.2.5.33.1.2	Author .....	201
3.2.5.33.1.3	Approver .....	201
3.2.5.34	Microsoft.SharePoint.Client.Feature .....	201
3.2.5.34.1	Properties .....	201
3.2.5.34.1.1	Scalar Properties .....	201
3.2.5.34.1.1.1	DefinitionId .....	201
3.2.5.34.1.1.2	DisplayName .....	201
3.2.5.34.1.2	ObjectPath Properties .....	202
3.2.5.34.2	Methods .....	202
3.2.5.34.2.1	Scalar Methods .....	202
3.2.5.34.2.2	ObjectPath Methods .....	202

3.2.5.35	Microsoft.SharePoint.Client.FeatureCollection	202
3.2.5.35.1	Properties	202
3.2.5.35.1.1	Scalar Properties	202
3.2.5.35.1.2	ObjectPath Properties	202
3.2.5.35.2	Methods	202
3.2.5.35.2.1	Scalar Methods	202
3.2.5.35.2.1.1	Remove	202
3.2.5.35.2.2	ObjectPath Methods	203
3.2.5.35.2.2.1	Add	203
3.2.5.35.2.2.2	GetById	203
3.2.5.36	Microsoft.SharePoint.Client.FeatureDefinitionScope	204
3.2.5.36.1	Field Values	204
3.2.5.36.1.1	None	204
3.2.5.36.1.2	Farm	204
3.2.5.36.1.3	Site	204
3.2.5.36.1.4	Web	204
3.2.5.37	Microsoft.SharePoint.Client.Field	204
3.2.5.37.1	Properties	204
3.2.5.37.1.1	Scalar Properties	204
3.2.5.37.1.1.1	CanBeDeleted	204
3.2.5.37.1.1.2	DefaultValue	204
3.2.5.37.1.1.3	Description	205
3.2.5.37.1.1.4	Direction	205
3.2.5.37.1.1.5	EnforceUniqueValues	205
3.2.5.37.1.1.6	FieldTypeKind	206
3.2.5.37.1.1.7	Filterable	206
3.2.5.37.1.1.8	FromBaseType	206
3.2.5.37.1.1.9	Group	207
3.2.5.37.1.1.10	Hidden	207
3.2.5.37.1.1.11	Id	207
3.2.5.37.1.1.12	InternalName	207
3.2.5.37.1.1.13	ReadOnlyField	207
3.2.5.37.1.1.14	Required	208
3.2.5.37.1.1.15	SchemaXml	208
3.2.5.37.1.1.16	Scope	208
3.2.5.37.1.1.17	Sealed	208
3.2.5.37.1.1.18	Sortable	208
3.2.5.37.1.1.19	StaticName	209
3.2.5.37.1.1.20	Title	209
3.2.5.37.1.1.21	TypeAsString	209
3.2.5.37.1.1.22	TypeDisplayName	209
3.2.5.37.1.1.23	TypeShortDescription	209
3.2.5.37.1.1.24	ValidationFormula	210
3.2.5.37.1.1.25	ValidationMessage	210
3.2.5.37.1.1.26	JSLink	210
3.2.5.37.1.1.27	EntityPropertyName	210
3.2.5.37.1.1.28	Indexed	210
3.2.5.37.1.1.29	SchemaXmlWithResourceTokens	210
3.2.5.37.1.1.30	AutoIndexed	211
3.2.5.37.1.1.31	ClientSideComponentId	211
3.2.5.37.1.1.32	ClientSideComponentProperties	211
3.2.5.37.1.1.33	CustomFormatter	211
3.2.5.37.1.1.34	DefaultFormula	211
3.2.5.37.1.1.35	NoCrawl	211
3.2.5.37.1.1.36	PinnedToFiltersPane	211
3.2.5.37.1.1.37	ShowInFiltersPane	212
3.2.5.37.1.2	ObjectPath Properties	212
3.2.5.37.1.2.1	DescriptionResource	212

3.2.5.37.1.2.2	TitleResource .....	212
3.2.5.37.2	Methods .....	212
3.2.5.37.2.1	Scalar Methods .....	212
3.2.5.37.2.1.1	DeleteObject .....	212
3.2.5.37.2.1.2	SetShowInDisplayForm .....	212
3.2.5.37.2.1.3	SetShowInEditForm .....	212
3.2.5.37.2.1.4	SetShowInNewForm .....	213
3.2.5.37.2.1.5	Update .....	213
3.2.5.37.2.1.6	UpdateAndPushChanges .....	213
3.2.5.37.2.1.7	ValidateSetValue .....	214
3.2.5.37.2.2	ObjectPath Methods .....	214
3.2.5.38	Microsoft.SharePoint.Client.FieldCalculated .....	214
3.2.5.38.1	Properties .....	214
3.2.5.38.1.1	Scalar Properties .....	214
3.2.5.38.1.1.1	CanBeDeleted .....	214
3.2.5.38.1.1.2	DateFormat .....	215
3.2.5.38.1.1.3	DefaultValue .....	215
3.2.5.38.1.1.4	Description .....	215
3.2.5.38.1.1.5	Direction .....	215
3.2.5.38.1.1.6	EnforceUniqueValues .....	215
3.2.5.38.1.1.7	FieldTypeKind .....	216
3.2.5.38.1.1.8	Filterable .....	216
3.2.5.38.1.1.9	Formula .....	216
3.2.5.38.1.1.10	FromBaseType .....	216
3.2.5.38.1.1.11	Group .....	216
3.2.5.38.1.1.12	Hidden .....	217
3.2.5.38.1.1.13	Id .....	217
3.2.5.38.1.1.14	InternalName .....	217
3.2.5.38.1.1.15	OutputType .....	217
3.2.5.38.1.1.16	ReadOnlyField .....	217
3.2.5.38.1.1.17	Required .....	218
3.2.5.38.1.1.18	SchemaXml .....	218
3.2.5.38.1.1.19	Scope .....	218
3.2.5.38.1.1.20	Sealed .....	218
3.2.5.38.1.1.21	Sortable .....	218
3.2.5.38.1.1.22	StaticName .....	219
3.2.5.38.1.1.23	Title .....	219
3.2.5.38.1.1.24	TypeAsString .....	219
3.2.5.38.1.1.25	TypeDisplayName .....	219
3.2.5.38.1.1.26	TypeShortDescription .....	219
3.2.5.38.1.1.27	ValidationFormula .....	220
3.2.5.38.1.1.28	ValidationMessage .....	220
3.2.5.38.1.1.29	JSLink .....	220
3.2.5.38.1.1.30	EntityPropertyName .....	220
3.2.5.38.1.1.31	Indexed .....	220
3.2.5.38.1.1.32	SchemaXmlWithResourceTokens .....	220
3.2.5.38.1.1.33	AutoIndexed .....	220
3.2.5.38.1.1.34	ClientSideComponentId .....	221
3.2.5.38.1.1.35	ClientSideComponentProperties .....	221
3.2.5.38.1.1.36	CurrencyLocaleId .....	221
3.2.5.38.1.1.37	CustomFormatter .....	221
3.2.5.38.1.1.38	DefaultFormula .....	221
3.2.5.38.1.1.39	DisplayFormat .....	221
3.2.5.38.1.1.40	NoCrawl .....	221
3.2.5.38.1.1.41	PinnedToFiltersPane .....	222
3.2.5.38.1.1.42	ShowAsPercentage .....	222
3.2.5.38.1.1.43	ShowInFiltersPane .....	222
3.2.5.38.1.2	ObjectPath Properties .....	222

3.2.5.38.1.2.1	DescriptionResource .....	222
3.2.5.38.1.2.2	TitleResource .....	222
3.2.5.38.2	Methods .....	222
3.2.5.38.2.1	Scalar Methods .....	222
3.2.5.38.2.1.1	DeleteObject .....	222
3.2.5.38.2.1.2	SetShowInDisplayForm .....	223
3.2.5.38.2.1.3	SetShowInEditForm .....	223
3.2.5.38.2.1.4	SetShowInNewForm .....	223
3.2.5.38.2.1.5	Update .....	223
3.2.5.38.2.1.6	UpdateAndPushChanges .....	224
3.2.5.38.2.1.7	ValidateSetValue .....	224
3.2.5.38.2.2	ObjectPath Methods .....	224
3.2.5.39	Microsoft.SharePoint.Client.FieldCalculatedErrorValue .....	225
3.2.5.39.1	Properties .....	225
3.2.5.39.1.1	Scalar Properties .....	225
3.2.5.39.1.1.1	ErrorMessage .....	225
3.2.5.39.1.2	ObjectPath Properties .....	225
3.2.5.40	Microsoft.SharePoint.Client.FieldChoice .....	225
3.2.5.40.1	Properties .....	225
3.2.5.40.1.1	Scalar Properties .....	225
3.2.5.40.1.1.1	CanBeDeleted .....	225
3.2.5.40.1.1.2	Choices .....	225
3.2.5.40.1.1.3	DefaultValue .....	225
3.2.5.40.1.1.4	Description .....	226
3.2.5.40.1.1.5	Direction .....	226
3.2.5.40.1.1.6	EditFormat .....	226
3.2.5.40.1.1.7	EnforceUniqueValues .....	226
3.2.5.40.1.1.8	FieldTypeKind .....	227
3.2.5.40.1.1.9	FillInChoice .....	227
3.2.5.40.1.1.10	Filterable .....	227
3.2.5.40.1.1.11	FromBaseType .....	227
3.2.5.40.1.1.12	Group .....	227
3.2.5.40.1.1.13	Hidden .....	228
3.2.5.40.1.1.14	Id .....	228
3.2.5.40.1.1.15	InternalName .....	228
3.2.5.40.1.1.16	Mappings .....	228
3.2.5.40.1.1.17	ReadOnlyField .....	228
3.2.5.40.1.1.18	Required .....	229
3.2.5.40.1.1.19	SchemaXml .....	229
3.2.5.40.1.1.20	Scope .....	229
3.2.5.40.1.1.21	Sealed .....	229
3.2.5.40.1.1.22	Sortable .....	230
3.2.5.40.1.1.23	StaticName .....	230
3.2.5.40.1.1.24	Title .....	230
3.2.5.40.1.1.25	TypeAsString .....	230
3.2.5.40.1.1.26	TypeDisplayName .....	230
3.2.5.40.1.1.27	TypeShortDescription .....	231
3.2.5.40.1.1.28	ValidationFormula .....	231
3.2.5.40.1.1.29	ValidationMessage .....	231
3.2.5.40.1.1.30	JSLink .....	231
3.2.5.40.1.1.31	EntityPropertyName .....	231
3.2.5.40.1.1.32	Indexed .....	231
3.2.5.40.1.1.33	SchemaXmlWithResourceTokens .....	232
3.2.5.40.1.1.34	AutoIndexed .....	232
3.2.5.40.1.1.35	ClientSideComponentId .....	232
3.2.5.40.1.1.36	ClientSideComponentProperties .....	232
3.2.5.40.1.1.37	CustomFormatter .....	232
3.2.5.40.1.1.38	DefaultFormula .....	232

3.2.5.40.1.1.39	NoCrawl .....	232
3.2.5.40.1.1.40	PinnedToFiltersPane .....	232
3.2.5.40.1.1.41	ShowInFiltersPane .....	233
3.2.5.40.1.2	ObjectPath Properties .....	233
3.2.5.40.1.2.1	DescriptionResource .....	233
3.2.5.40.1.2.2	TitleResource .....	233
3.2.5.40.2	Methods .....	233
3.2.5.40.2.1	Scalar Methods .....	233
3.2.5.40.2.1.1	DeleteObject .....	233
3.2.5.40.2.1.2	SetShowInDisplayForm .....	233
3.2.5.40.2.1.3	SetShowInEditForm .....	234
3.2.5.40.2.1.4	SetShowInNewForm .....	234
3.2.5.40.2.1.5	Update .....	234
3.2.5.40.2.1.6	UpdateAndPushChanges .....	234
3.2.5.40.2.1.7	ValidateSetValue .....	235
3.2.5.40.2.2	ObjectPath Methods .....	235
3.2.5.41	Microsoft.SharePoint.Client.FieldCollection .....	235
3.2.5.41.1	Properties .....	235
3.2.5.41.1.1	Scalar Properties .....	235
3.2.5.41.1.1.1	SchemaXml .....	235
3.2.5.41.1.2	ObjectPath Properties .....	236
3.2.5.41.2	Methods .....	236
3.2.5.41.2.1	Scalar Methods .....	236
3.2.5.41.2.2	ObjectPath Methods .....	236
3.2.5.41.2.2.1	Add .....	236
3.2.5.41.2.2.2	AddDependentLookup .....	236
3.2.5.41.2.2.3	AddFieldAsXml .....	236
3.2.5.41.2.2.4	GetById .....	237
3.2.5.41.2.2.5	GetByInternalNameOrTitle .....	237
3.2.5.41.2.2.6	GetByTitle .....	237
3.2.5.41.2.2.7	AddDependentLookupField .....	238
3.2.5.41.2.2.8	AddField .....	238
3.2.5.41.2.2.9	CreateFieldAsXml .....	239
3.2.5.42	Microsoft.SharePoint.Client.FieldComputed .....	240
3.2.5.42.1	Properties .....	240
3.2.5.42.1.1	Scalar Properties .....	240
3.2.5.42.1.1.1	CanBeDeleted .....	240
3.2.5.42.1.1.2	DefaultValue .....	240
3.2.5.42.1.1.3	Description .....	241
3.2.5.42.1.1.4	Direction .....	241
3.2.5.42.1.1.5	EnableLookup .....	241
3.2.5.42.1.1.6	EnforceUniqueValues .....	241
3.2.5.42.1.1.7	FieldTypeKind .....	242
3.2.5.42.1.1.8	Filterable .....	242
3.2.5.42.1.1.9	FromBaseType .....	242
3.2.5.42.1.1.10	Group .....	242
3.2.5.42.1.1.11	Hidden .....	242
3.2.5.42.1.1.12	Id .....	243
3.2.5.42.1.1.13	InternalName .....	243
3.2.5.42.1.1.14	ReadOnlyField .....	243
3.2.5.42.1.1.15	Required .....	243
3.2.5.42.1.1.16	SchemaXml .....	243
3.2.5.42.1.1.17	Scope .....	244
3.2.5.42.1.1.18	Sealed .....	244
3.2.5.42.1.1.19	Sortable .....	244
3.2.5.42.1.1.20	StaticName .....	244
3.2.5.42.1.1.21	Title .....	244
3.2.5.42.1.1.22	TypeAsString .....	244

3.2.5.42.1.1.23	TypeDisplayName	245
3.2.5.42.1.1.24	TypeShortDescription	245
3.2.5.42.1.1.25	ValidationFormula	245
3.2.5.42.1.1.26	ValidationMessage	245
3.2.5.42.1.1.27	JSLink	245
3.2.5.42.1.1.28	EntityPropertyName	246
3.2.5.42.1.1.29	Indexed	246
3.2.5.42.1.1.30	SchemaXmlWithResourceTokens	246
3.2.5.42.1.1.31	AutoIndexed	246
3.2.5.42.1.1.32	ClientSideComponentId	246
3.2.5.42.1.1.33	ClientSideComponentProperties	246
3.2.5.42.1.1.34	CustomFormatter	246
3.2.5.42.1.1.35	DefaultFormula	247
3.2.5.42.1.1.36	NoCrawl	247
3.2.5.42.1.1.37	PinnedToFiltersPane	247
3.2.5.42.1.1.38	ShowInFiltersPane	247
3.2.5.42.1.2	ObjectPath Properties	247
3.2.5.42.1.2.1	DescriptionResource	247
3.2.5.42.1.2.2	TitleResource	247
3.2.5.42.2	Methods	247
3.2.5.42.2.1	Scalar Methods	247
3.2.5.42.2.1.1	DeleteObject	247
3.2.5.42.2.1.2	SetShowInDisplayForm	248
3.2.5.42.2.1.3	SetShowInEditForm	248
3.2.5.42.2.1.4	SetShowInNewForm	248
3.2.5.42.2.1.5	Update	248
3.2.5.42.2.1.6	UpdateAndPushChanges	249
3.2.5.42.2.1.7	ValidateSetValue	249
3.2.5.42.2.2	ObjectPath Methods	249
3.2.5.43	Microsoft.SharePoint.Client.FieldCurrency	250
3.2.5.43.1	Properties	250
3.2.5.43.1.1	Scalar Properties	250
3.2.5.43.1.1.1	CanBeDeleted	250
3.2.5.43.1.1.2	CurrencyLocaleId	250
3.2.5.43.1.1.3	DefaultValue	250
3.2.5.43.1.1.4	Description	250
3.2.5.43.1.1.5	Direction	251
3.2.5.43.1.1.6	EnforceUniqueValues	251
3.2.5.43.1.1.7	FieldTypeKind	251
3.2.5.43.1.1.8	Filterable	251
3.2.5.43.1.1.9	FromBaseType	252
3.2.5.43.1.1.10	Group	252
3.2.5.43.1.1.11	Hidden	252
3.2.5.43.1.1.12	Id	252
3.2.5.43.1.1.13	InternalName	252
3.2.5.43.1.1.14	MaximumValue	252
3.2.5.43.1.1.15	MinimumValue	253
3.2.5.43.1.1.16	ReadOnlyField	253
3.2.5.43.1.1.17	Required	253
3.2.5.43.1.1.18	SchemaXml	253
3.2.5.43.1.1.19	Scope	254
3.2.5.43.1.1.20	Sealed	254
3.2.5.43.1.1.21	Sortable	254
3.2.5.43.1.1.22	StaticName	254
3.2.5.43.1.1.23	Title	254
3.2.5.43.1.1.24	TypeAsString	254
3.2.5.43.1.1.25	TypeDisplayName	255
3.2.5.43.1.1.26	TypeShortDescription	255



3.2.5.43.1.1.27	ValidationFormula	255
3.2.5.43.1.1.28	ValidationMessage	255
3.2.5.43.1.1.29	JSLink	255
3.2.5.43.1.1.30	EntityPropertyName	256
3.2.5.43.1.1.31	Indexed	256
3.2.5.43.1.1.32	SchemaXmlWithResourceTokens	256
3.2.5.43.1.1.33	AutoIndexed	256
3.2.5.43.1.1.34	ClientSideComponentId	256
3.2.5.43.1.1.35	ClientSideComponentProperties	256
3.2.5.43.1.1.36	CustomFormatter	256
3.2.5.43.1.1.37	DefaultFormula	257
3.2.5.43.1.1.38	DisplayFormat	257
3.2.5.43.1.1.39	NoCrawl	257
3.2.5.43.1.1.40	PinnedToFiltersPane	257
3.2.5.43.1.1.41	ShowAsPercentage	257
3.2.5.43.1.1.42	ShowInFiltersPane	257
3.2.5.43.1.2	ObjectPath Properties	257
3.2.5.43.1.2.1	DescriptionResource	257
3.2.5.43.1.2.2	TitleResource	258
3.2.5.43.2	Methods	258
3.2.5.43.2.1	Scalar Methods	258
3.2.5.43.2.1.1	DeleteObject	258
3.2.5.43.2.1.2	SetShowInDisplayForm	258
3.2.5.43.2.1.3	SetShowInEditForm	258
3.2.5.43.2.1.4	SetShowInNewForm	258
3.2.5.43.2.1.5	Update	259
3.2.5.43.2.1.6	UpdateAndPushChanges	259
3.2.5.43.2.1.7	ValidateSetValue	259
3.2.5.43.2.2	ObjectPath Methods	260
3.2.5.44	Microsoft.SharePoint.Client.FieldDateTime	260
3.2.5.44.1	Properties	260
3.2.5.44.1.1	Scalar Properties	260
3.2.5.44.1.1.1	CanBeDeleted	260
3.2.5.44.1.1.2	DateTimeCalendarType	260
3.2.5.44.1.1.3	DefaultValue	260
3.2.5.44.1.1.4	Description	261
3.2.5.44.1.1.5	Direction	261
3.2.5.44.1.1.6	DisplayFormat	261
3.2.5.44.1.1.7	EnforceUniqueValues	261
3.2.5.44.1.1.8	FieldTypeKind	262
3.2.5.44.1.1.9	Filterable	262
3.2.5.44.1.1.10	FromBaseType	262
3.2.5.44.1.1.11	Group	262
3.2.5.44.1.1.12	Hidden	262
3.2.5.44.1.1.13	Id	263
3.2.5.44.1.1.14	InternalName	263
3.2.5.44.1.1.15	ReadOnlyField	263
3.2.5.44.1.1.16	Required	263
3.2.5.44.1.1.17	SchemaXml	263
3.2.5.44.1.1.18	Scope	264
3.2.5.44.1.1.19	Sealed	264
3.2.5.44.1.1.20	Sortable	264
3.2.5.44.1.1.21	StaticName	264
3.2.5.44.1.1.22	Title	264
3.2.5.44.1.1.23	TypeAsString	265
3.2.5.44.1.1.24	TypeDisplayName	265
3.2.5.44.1.1.25	TypeShortDescription	265
3.2.5.44.1.1.26	ValidationFormula	265

3.2.5.44.1.1.27	ValidationMessage	265
3.2.5.44.1.1.28	FriendlyDisplayFormat	266
3.2.5.44.1.1.29	JSLink	266
3.2.5.44.1.1.30	EntityPropertyName	266
3.2.5.44.1.1.31	Indexed	266
3.2.5.44.1.1.32	SchemaXmlWithResourceTokens	266
3.2.5.44.1.1.33	AutoIndexed	266
3.2.5.44.1.1.34	ClientSideComponentId	266
3.2.5.44.1.1.35	ClientSideComponentProperties	267
3.2.5.44.1.1.36	CustomFormatter	267
3.2.5.44.1.1.37	DefaultFormula	267
3.2.5.44.1.1.38	NoCrawl	267
3.2.5.44.1.1.39	PinnedToFiltersPane	267
3.2.5.44.1.1.40	ShowInFiltersPane	267
3.2.5.44.1.2	ObjectPath Properties	267
3.2.5.44.1.2.1	DescriptionResource	267
3.2.5.44.1.2.2	TitleResource	268
3.2.5.44.2	Methods	268
3.2.5.44.2.1	Scalar Methods	268
3.2.5.44.2.1.1	DeleteObject	268
3.2.5.44.2.1.2	SetShowInDisplayForm	268
3.2.5.44.2.1.3	SetShowInEditForm	268
3.2.5.44.2.1.4	SetShowInNewForm	268
3.2.5.44.2.1.5	Update	269
3.2.5.44.2.1.6	UpdateAndPushChanges	269
3.2.5.44.2.1.7	ValidateSetValue	269
3.2.5.44.2.2	ObjectPath Methods	270
3.2.5.45	Microsoft.SharePoint.Client.FieldGuid	270
3.2.5.45.1	Properties	270
3.2.5.45.1.1	Scalar Properties	270
3.2.5.45.1.1.1	CanBeDeleted	270
3.2.5.45.1.1.2	DefaultValue	270
3.2.5.45.1.1.3	Description	270
3.2.5.45.1.1.4	Direction	271
3.2.5.45.1.1.5	EnforceUniqueValues	271
3.2.5.45.1.1.6	FieldTypeKind	271
3.2.5.45.1.1.7	Filterable	272
3.2.5.45.1.1.8	FromBaseType	272
3.2.5.45.1.1.9	Group	272
3.2.5.45.1.1.10	Hidden	272
3.2.5.45.1.1.11	Id	272
3.2.5.45.1.1.12	InternalName	272
3.2.5.45.1.1.13	ReadOnlyField	273
3.2.5.45.1.1.14	Required	273
3.2.5.45.1.1.15	SchemaXml	273
3.2.5.45.1.1.16	Scope	273
3.2.5.45.1.1.17	Sealed	274
3.2.5.45.1.1.18	Sortable	274
3.2.5.45.1.1.19	StaticName	274
3.2.5.45.1.1.20	Title	274
3.2.5.45.1.1.21	TypeAsString	274
3.2.5.45.1.1.22	TypeDisplayName	274
3.2.5.45.1.1.23	TypeShortDescription	275
3.2.5.45.1.1.24	ValidationFormula	275
3.2.5.45.1.1.25	ValidationMessage	275
3.2.5.45.1.1.26	JSLink	275
3.2.5.45.1.1.27	EntityPropertyName	275
3.2.5.45.1.1.28	Indexed	275

3.2.5.45.1.1.29	SchemaXmlWithResourceTokens .....	276
3.2.5.45.1.1.30	AutoIndexed .....	276
3.2.5.45.1.1.31	ClientSideComponentId .....	276
3.2.5.45.1.1.32	ClientSideComponentProperties .....	276
3.2.5.45.1.1.33	CustomFormatter .....	276
3.2.5.45.1.1.34	DefaultFormula .....	276
3.2.5.45.1.1.35	NoCrawl .....	276
3.2.5.45.1.1.36	PinnedToFiltersPane .....	277
3.2.5.45.1.1.37	ShowInFiltersPane .....	277
3.2.5.45.1.2	ObjectPath Properties .....	277
3.2.5.45.1.2.1	DescriptionResource .....	277
3.2.5.45.1.2.2	TitleResource .....	277
3.2.5.45.2	Methods .....	277
3.2.5.45.2.1	Scalar Methods .....	277
3.2.5.45.2.1.1	DeleteObject .....	277
3.2.5.45.2.1.2	SetShowInDisplayForm .....	277
3.2.5.45.2.1.3	SetShowInEditForm .....	278
3.2.5.45.2.1.4	SetShowInNewForm .....	278
3.2.5.45.2.1.5	Update .....	278
3.2.5.45.2.1.6	UpdateAndPushChanges .....	278
3.2.5.45.2.1.7	ValidateSetValue .....	279
3.2.5.45.2.2	ObjectPath Methods .....	279
3.2.5.46	Microsoft.SharePoint.Client.FieldLink .....	279
3.2.5.46.1	Properties .....	279
3.2.5.46.1.1	Scalar Properties .....	279
3.2.5.46.1.1.1	Hidden .....	279
3.2.5.46.1.1.2	Id .....	280
3.2.5.46.1.1.3	Name .....	280
3.2.5.46.1.1.4	Required .....	280
3.2.5.46.1.1.5	FieldInternalName .....	280
3.2.5.46.1.1.6	DisplayName .....	280
3.2.5.46.1.1.7	ReadOnly .....	280
3.2.5.46.1.1.8	ShowInDisplayForm .....	281
3.2.5.46.1.2	ObjectPath Properties .....	281
3.2.5.46.2	Methods .....	281
3.2.5.46.2.1	Scalar Methods .....	281
3.2.5.46.2.1.1	DeleteObject .....	281
3.2.5.46.2.2	ObjectPath Methods .....	281
3.2.5.47	Microsoft.SharePoint.Client.FieldLinkCollection .....	281
3.2.5.47.1	Properties .....	281
3.2.5.47.1.1	Scalar Properties .....	281
3.2.5.47.1.2	ObjectPath Properties .....	281
3.2.5.47.2	Methods .....	281
3.2.5.47.2.1	Scalar Methods .....	281
3.2.5.47.2.1.1	Reorder .....	281
3.2.5.47.2.2	ObjectPath Methods .....	282
3.2.5.47.2.2.1	Add .....	282
3.2.5.47.2.2.2	GetById .....	282
3.2.5.48	Microsoft.SharePoint.Client.FieldLinkCreationInformation .....	282
3.2.5.48.1	Properties .....	282
3.2.5.48.1.1	Scalar Properties .....	282
3.2.5.48.1.2	ObjectPath Properties .....	282
3.2.5.48.1.2.1	Field .....	282
3.2.5.49	Microsoft.SharePoint.Client.FieldLookup .....	283
3.2.5.49.1	Properties .....	283
3.2.5.49.1.1	Scalar Properties .....	283
3.2.5.49.1.1.1	AllowMultipleValues .....	283
3.2.5.49.1.1.2	CanBeDeleted .....	283

3.2.5.49.1.1.3	DefaultValue	283
3.2.5.49.1.1.4	Description	283
3.2.5.49.1.1.5	Direction	284
3.2.5.49.1.1.6	EnforceUniqueValues	284
3.2.5.49.1.1.7	FieldTypeKind	284
3.2.5.49.1.1.8	Filterable	284
3.2.5.49.1.1.9	FromBaseType	285
3.2.5.49.1.1.10	Group	285
3.2.5.49.1.1.11	Hidden	285
3.2.5.49.1.1.12	Id	285
3.2.5.49.1.1.13	InternalName	285
3.2.5.49.1.1.14	IsRelationship	285
3.2.5.49.1.1.15	LookupField	286
3.2.5.49.1.1.16	LookupList	286
3.2.5.49.1.1.17	LookupWebId	286
3.2.5.49.1.1.18	PrimaryFieldId	287
3.2.5.49.1.1.19	ReadOnlyField	287
3.2.5.49.1.1.20	RelationshipDeleteBehavior	287
3.2.5.49.1.1.21	Required	287
3.2.5.49.1.1.22	SchemaXml	288
3.2.5.49.1.1.23	Scope	288
3.2.5.49.1.1.24	Sealed	288
3.2.5.49.1.1.25	Sortable	288
3.2.5.49.1.1.26	StaticName	288
3.2.5.49.1.1.27	Title	289
3.2.5.49.1.1.28	TypeAsString	289
3.2.5.49.1.1.29	TypeDisplayName	289
3.2.5.49.1.1.30	TypeShortDescription	289
3.2.5.49.1.1.31	ValidationFormula	289
3.2.5.49.1.1.32	ValidationMessage	290
3.2.5.49.1.1.33	Indexed	290
3.2.5.49.1.1.34	JSLink	290
3.2.5.49.1.1.35	EntityPropertyName	290
3.2.5.49.1.1.36	SchemaXmlWithResourceTokens	290
3.2.5.49.1.1.37	AutoIndexed	290
3.2.5.49.1.1.38	ClientSideComponentId	290
3.2.5.49.1.1.39	ClientSideComponentProperties	291
3.2.5.49.1.1.40	CustomFormatter	291
3.2.5.49.1.1.41	DefaultFormula	291
3.2.5.49.1.1.42	DependentLookupInternalNames	291
3.2.5.49.1.1.43	IsDependentLookup	291
3.2.5.49.1.1.44	NoCrawl	291
3.2.5.49.1.1.45	PinnedToFiltersPane	291
3.2.5.49.1.1.46	ShowInFiltersPane	292
3.2.5.49.1.1.47	UnlimitedLengthInDocumentLibrary	292
3.2.5.49.1.2	ObjectPath Properties	292
3.2.5.49.1.2.1	DescriptionResource	292
3.2.5.49.1.2.2	TitleResource	292
3.2.5.49.2	Methods	292
3.2.5.49.2.1	Scalar Methods	292
3.2.5.49.2.1.1	DeleteObject	292
3.2.5.49.2.1.2	SetShowInDisplayForm	292
3.2.5.49.2.1.3	SetShowInEditForm	293
3.2.5.49.2.1.4	SetShowInNewForm	293
3.2.5.49.2.1.5	Update	293
3.2.5.49.2.1.6	UpdateAndPushChanges	293
3.2.5.49.2.1.7	ValidateSetValue	294
3.2.5.49.2.2	ObjectPath Methods	294

3.2.5.50	Microsoft.SharePoint.Client.FieldLookupValue	294
3.2.5.50.1	Properties	294
3.2.5.50.1.1	Scalar Properties	294
3.2.5.50.1.1.1	LookupId	294
3.2.5.50.1.1.2	LookupValue	295
3.2.5.50.1.2	ObjectPath Properties	295
3.2.5.51	Microsoft.SharePoint.Client.FieldMultiChoice	295
3.2.5.51.1	Properties	295
3.2.5.51.1.1	Scalar Properties	295
3.2.5.51.1.1.1	CanBeDeleted	295
3.2.5.51.1.1.2	Choices	295
3.2.5.51.1.1.3	DefaultValue	295
3.2.5.51.1.1.4	Description	296
3.2.5.51.1.1.5	Direction	296
3.2.5.51.1.1.6	EnforceUniqueValues	296
3.2.5.51.1.1.7	FieldTypeKind	296
3.2.5.51.1.1.8	FillInChoice	297
3.2.5.51.1.1.9	Filterable	297
3.2.5.51.1.1.10	FromBaseType	297
3.2.5.51.1.1.11	Group	297
3.2.5.51.1.1.12	Hidden	297
3.2.5.51.1.1.13	Id	298
3.2.5.51.1.1.14	InternalName	298
3.2.5.51.1.1.15	Mappings	298
3.2.5.51.1.1.16	ReadOnlyField	298
3.2.5.51.1.1.17	Required	298
3.2.5.51.1.1.18	SchemaXml	299
3.2.5.51.1.1.19	Scope	299
3.2.5.51.1.1.20	Sealed	299
3.2.5.51.1.1.21	Sortable	299
3.2.5.51.1.1.22	StaticName	299
3.2.5.51.1.1.23	Title	300
3.2.5.51.1.1.24	TypeAsString	300
3.2.5.51.1.1.25	TypeDisplayName	300
3.2.5.51.1.1.26	TypeShortDescription	300
3.2.5.51.1.1.27	ValidationFormula	300
3.2.5.51.1.1.28	ValidationMessage	300
3.2.5.51.1.1.29	JSLink	301
3.2.5.51.1.1.30	EntityPropertyName	301
3.2.5.51.1.1.31	Indexed	301
3.2.5.51.1.1.32	SchemaXmlWithResourceTokens	301
3.2.5.51.1.1.33	AutoIndexed	301
3.2.5.51.1.1.34	ClientSideComponentId	301
3.2.5.51.1.1.35	ClientSideComponentProperties	301
3.2.5.51.1.1.36	CustomFormatter	302
3.2.5.51.1.1.37	DefaultFormula	302
3.2.5.51.1.1.38	NoCrawl	302
3.2.5.51.1.1.39	PinnedToFiltersPane	302
3.2.5.51.1.1.40	ShowInFiltersPane	302
3.2.5.51.1.2	ObjectPath Properties	302
3.2.5.51.1.2.1	DescriptionResource	302
3.2.5.51.1.2.2	TitleResource	302
3.2.5.51.2	Methods	303
3.2.5.51.2.1	Scalar Methods	303
3.2.5.51.2.1.1	DeleteObject	303
3.2.5.51.2.1.2	SetShowInDisplayForm	303
3.2.5.51.2.1.3	SetShowInEditForm	303
3.2.5.51.2.1.4	SetShowInNewForm	303

3.2.5.51.2.1.5	Update .....	304
3.2.5.51.2.1.6	UpdateAndPushChanges .....	304
3.2.5.51.2.1.7	ValidateSetValue .....	304
3.2.5.51.2.2	ObjectPath Methods .....	305
3.2.5.52	Microsoft.SharePoint.Client.FieldMultiLineText .....	305
3.2.5.52.1	Properties .....	305
3.2.5.52.1.1	Scalar Properties .....	305
3.2.5.52.1.1.1	AllowHyperlink .....	305
3.2.5.52.1.1.2	AppendOnly .....	305
3.2.5.52.1.1.3	CanBeDeleted .....	305
3.2.5.52.1.1.4	DefaultValue .....	305
3.2.5.52.1.1.5	Description .....	306
3.2.5.52.1.1.6	Direction .....	306
3.2.5.52.1.1.7	EnforceUniqueValues .....	306
3.2.5.52.1.1.8	FieldTypeKind .....	306
3.2.5.52.1.1.9	Filterable .....	307
3.2.5.52.1.1.10	FromBaseType .....	307
3.2.5.52.1.1.11	Group .....	307
3.2.5.52.1.1.12	Hidden .....	307
3.2.5.52.1.1.13	Id .....	307
3.2.5.52.1.1.14	InternalName .....	308
3.2.5.52.1.1.15	NumberOfLines .....	308
3.2.5.52.1.1.16	ReadOnlyField .....	308
3.2.5.52.1.1.17	Required .....	308
3.2.5.52.1.1.18	RestrictedMode .....	308
3.2.5.52.1.1.19	RichText .....	309
3.2.5.52.1.1.20	SchemaXml .....	309
3.2.5.52.1.1.21	Scope .....	309
3.2.5.52.1.1.22	Sealed .....	309
3.2.5.52.1.1.23	Sortable .....	309
3.2.5.52.1.1.24	StaticName .....	309
3.2.5.52.1.1.25	Title .....	310
3.2.5.52.1.1.26	TypeAsString .....	310
3.2.5.52.1.1.27	TypeDisplayName .....	310
3.2.5.52.1.1.28	TypeShortDescription .....	310
3.2.5.52.1.1.29	ValidationFormula .....	310
3.2.5.52.1.1.30	ValidationMessage .....	311
3.2.5.52.1.1.31	WikiLinking .....	311
3.2.5.52.1.1.32	JSLink .....	311
3.2.5.52.1.1.33	EntityPropertyName .....	311
3.2.5.52.1.1.34	Indexed .....	311
3.2.5.52.1.1.35	SchemaXmlWithResourceTokens .....	311
3.2.5.52.1.1.36	AutoIndexed .....	312
3.2.5.52.1.1.37	ClientSideComponentId .....	312
3.2.5.52.1.1.38	ClientSideComponentProperties .....	312
3.2.5.52.1.1.39	CustomFormatter .....	312
3.2.5.52.1.1.40	DefaultFormula .....	312
3.2.5.52.1.1.41	NoCrawl .....	312
3.2.5.52.1.1.42	PinnedToFiltersPane .....	312
3.2.5.52.1.1.43	ShowInFiltersPane .....	313
3.2.5.52.1.1.44	UnlimitedLengthInDocumentLibrary .....	313
3.2.5.52.1.2	ObjectPath Properties .....	313
3.2.5.52.1.2.1	DescriptionResource .....	313
3.2.5.52.1.2.2	TitleResource .....	313
3.2.5.52.2	Methods .....	313
3.2.5.52.2.1	Scalar Methods .....	313
3.2.5.52.2.1.1	DeleteObject .....	313
3.2.5.52.2.1.2	SetShowInDisplayForm .....	314

3.2.5.52.2.1.3	SetShowInEditForm .....	314
3.2.5.52.2.1.4	SetShowInNewForm .....	314
3.2.5.52.2.1.5	Update .....	314
3.2.5.52.2.1.6	UpdateAndPushChanges .....	314
3.2.5.52.2.1.7	ValidateSetValue .....	315
3.2.5.52.2.2	ObjectPath Methods .....	315
3.2.5.53	Microsoft.SharePoint.Client.FieldNumber .....	315
3.2.5.53.1	Properties .....	316
3.2.5.53.1.1	Scalar Properties .....	316
3.2.5.53.1.1.1	CanBeDeleted .....	316
3.2.5.53.1.1.2	DefaultValue .....	316
3.2.5.53.1.1.3	Description .....	316
3.2.5.53.1.1.4	Direction .....	316
3.2.5.53.1.1.5	EnforceUniqueValues .....	316
3.2.5.53.1.1.6	FieldTypeKind .....	317
3.2.5.53.1.1.7	Filterable .....	317
3.2.5.53.1.1.8	FromBaseType .....	317
3.2.5.53.1.1.9	Group .....	317
3.2.5.53.1.1.10	Hidden .....	318
3.2.5.53.1.1.11	Id .....	318
3.2.5.53.1.1.12	InternalName .....	318
3.2.5.53.1.1.13	MaximumValue .....	318
3.2.5.53.1.1.14	MinimumValue .....	318
3.2.5.53.1.1.15	ReadOnlyField .....	318
3.2.5.53.1.1.16	Required .....	319
3.2.5.53.1.1.17	SchemaXml .....	319
3.2.5.53.1.1.18	Scope .....	319
3.2.5.53.1.1.19	Sealed .....	319
3.2.5.53.1.1.20	Sortable .....	320
3.2.5.53.1.1.21	StaticName .....	320
3.2.5.53.1.1.22	Title .....	320
3.2.5.53.1.1.23	TypeAsString .....	320
3.2.5.53.1.1.24	TypeDisplayName .....	320
3.2.5.53.1.1.25	TypeShortDescription .....	321
3.2.5.53.1.1.26	ValidationFormula .....	321
3.2.5.53.1.1.27	ValidationMessage .....	321
3.2.5.53.1.1.28	JSLink .....	321
3.2.5.53.1.1.29	EntityPropertyName .....	321
3.2.5.53.1.1.30	Indexed .....	321
3.2.5.53.1.1.31	SchemaXmlWithResourceTokens .....	321
3.2.5.53.1.1.32	AutoIndexed .....	322
3.2.5.53.1.1.33	ClientSideComponentId .....	322
3.2.5.53.1.1.34	ClientSideComponentProperties .....	322
3.2.5.53.1.1.35	CustomFormatter .....	322
3.2.5.53.1.1.36	DefaultFormula .....	322
3.2.5.53.1.1.37	DisplayFormat .....	322
3.2.5.53.1.1.38	NoCrawl .....	322
3.2.5.53.1.1.39	PinnedToFiltersPane .....	323
3.2.5.53.1.1.40	ShowAsPercentage .....	323
3.2.5.53.1.1.41	ShowInFiltersPane .....	323
3.2.5.53.1.2	ObjectPath Properties .....	323
3.2.5.53.1.2.1	DescriptionResource .....	323
3.2.5.53.1.2.2	TitleResource .....	323
3.2.5.53.2	Methods .....	323
3.2.5.53.2.1	Scalar Methods .....	323
3.2.5.53.2.1.1	DeleteObject .....	323
3.2.5.53.2.1.2	SetShowInDisplayForm .....	324
3.2.5.53.2.1.3	SetShowInEditForm .....	324

3.2.5.53.2.1.4	SetShowInNewForm .....	324
3.2.5.53.2.1.5	Update .....	324
3.2.5.53.2.1.6	UpdateAndPushChanges .....	325
3.2.5.53.2.1.7	ValidateSetValue .....	325
3.2.5.53.2.2	ObjectPath Methods .....	325
3.2.5.54	Microsoft.SharePoint.Client.FieldRatingScale .....	326
3.2.5.54.1	Properties .....	326
3.2.5.54.1.1	Scalar Properties .....	326
3.2.5.54.1.1.1	CanBeDeleted .....	326
3.2.5.54.1.1.2	Choices .....	326
3.2.5.54.1.1.3	DefaultValue .....	326
3.2.5.54.1.1.4	Description .....	326
3.2.5.54.1.1.5	Direction .....	326
3.2.5.54.1.1.6	EnforceUniqueValues .....	327
3.2.5.54.1.1.7	FieldTypeKind .....	327
3.2.5.54.1.1.8	FillInChoice .....	327
3.2.5.54.1.1.9	Filterable .....	328
3.2.5.54.1.1.10	FromBaseType .....	328
3.2.5.54.1.1.11	GridEndNumber .....	328
3.2.5.54.1.1.12	GridNAOptionText .....	328
3.2.5.54.1.1.13	GridStartNumber .....	328
3.2.5.54.1.1.14	GridTextRangeAverage .....	328
3.2.5.54.1.1.15	GridTextRangeHigh .....	328
3.2.5.54.1.1.16	GridTextRangeLow .....	328
3.2.5.54.1.1.17	Group .....	329
3.2.5.54.1.1.18	Hidden .....	329
3.2.5.54.1.1.19	Id .....	329
3.2.5.54.1.1.20	InternalName .....	329
3.2.5.54.1.1.21	Mappings .....	329
3.2.5.54.1.1.22	RangeCount .....	330
3.2.5.54.1.1.23	ReadOnlyField .....	330
3.2.5.54.1.1.24	Required .....	330
3.2.5.54.1.1.25	SchemaXml .....	330
3.2.5.54.1.1.26	Scope .....	331
3.2.5.54.1.1.27	Sealed .....	331
3.2.5.54.1.1.28	Sortable .....	331
3.2.5.54.1.1.29	StaticName .....	331
3.2.5.54.1.1.30	Title .....	331
3.2.5.54.1.1.31	TypeAsString .....	331
3.2.5.54.1.1.32	TypeDisplayName .....	332
3.2.5.54.1.1.33	TypeShortDescription .....	332
3.2.5.54.1.1.34	ValidationFormula .....	332
3.2.5.54.1.1.35	ValidationMessage .....	332
3.2.5.54.1.1.36	JSLink .....	332
3.2.5.54.1.1.37	EntityPropertyName .....	332
3.2.5.54.1.1.38	Indexed .....	333
3.2.5.54.1.1.39	SchemaXmlWithResourceTokens .....	333
3.2.5.54.1.1.40	AutoIndexed .....	333
3.2.5.54.1.1.41	ClientSideComponentId .....	333
3.2.5.54.1.1.42	ClientSideComponentProperties .....	333
3.2.5.54.1.1.43	CustomFormatter .....	333
3.2.5.54.1.1.44	DefaultFormula .....	333
3.2.5.54.1.1.45	NoCrawl .....	334
3.2.5.54.1.1.46	PinnedToFiltersPane .....	334
3.2.5.54.1.1.47	ShowInFiltersPane .....	334
3.2.5.54.1.2	ObjectPath Properties .....	334
3.2.5.54.1.2.1	DescriptionResource .....	334
3.2.5.54.1.2.2	TitleResource .....	334



3.2.5.54.2	Methods	334
3.2.5.54.2.1	Scalar Methods	334
3.2.5.54.2.1.1	DeleteObject	334
3.2.5.54.2.1.2	SetShowInDisplayForm	335
3.2.5.54.2.1.3	SetShowInEditForm	335
3.2.5.54.2.1.4	SetShowInNewForm	335
3.2.5.54.2.1.5	Update	335
3.2.5.54.2.1.6	UpdateAndPushChanges	336
3.2.5.54.2.1.7	ValidateSetValue	336
3.2.5.54.2.2	ObjectPath Methods	336
3.2.5.55	Microsoft.SharePoint.Client.FieldRatingScaleQuestionAnswer	337
3.2.5.55.1	Properties	337
3.2.5.55.1.1	Scalar Properties	337
3.2.5.55.1.1.1	Answer	337
3.2.5.55.1.1.2	Question	337
3.2.5.55.1.2	ObjectPath Properties	337
3.2.5.56	Microsoft.SharePoint.Client.FieldStringValues	337
3.2.5.56.1	Properties	337
3.2.5.56.1.1	Scalar Properties	337
3.2.5.56.1.2	ObjectPath Properties	337
3.2.5.56.2	Methods	337
3.2.5.56.2.1	Scalar Methods	337
3.2.5.56.2.2	ObjectPath Methods	338
3.2.5.57	Microsoft.SharePoint.Client.FieldText	338
3.2.5.57.1	Properties	338
3.2.5.57.1.1	Scalar Properties	338
3.2.5.57.1.1.1	CanBeDeleted	338
3.2.5.57.1.1.2	DefaultValue	338
3.2.5.57.1.1.3	Description	338
3.2.5.57.1.1.4	Direction	338
3.2.5.57.1.1.5	EnforceUniqueValues	339
3.2.5.57.1.1.6	FieldTypeKind	339
3.2.5.57.1.1.7	Filterable	339
3.2.5.57.1.1.8	FromBaseType	339
3.2.5.57.1.1.9	Group	340
3.2.5.57.1.1.10	Hidden	340
3.2.5.57.1.1.11	Id	340
3.2.5.57.1.1.12	InternalName	340
3.2.5.57.1.1.13	MaxLength	340
3.2.5.57.1.1.14	ReadOnlyField	340
3.2.5.57.1.1.15	Required	341
3.2.5.57.1.1.16	SchemaXml	341
3.2.5.57.1.1.17	Scope	341
3.2.5.57.1.1.18	Sealed	342
3.2.5.57.1.1.19	Sortable	342
3.2.5.57.1.1.20	StaticName	342
3.2.5.57.1.1.21	Title	342
3.2.5.57.1.1.22	TypeAsString	342
3.2.5.57.1.1.23	TypeDisplayName	342
3.2.5.57.1.1.24	TypeShortDescription	343
3.2.5.57.1.1.25	ValidationFormula	343
3.2.5.57.1.1.26	ValidationMessage	343
3.2.5.57.1.1.27	JSLink	343
3.2.5.57.1.1.28	EntityPropertyName	343
3.2.5.57.1.1.29	Indexed	343
3.2.5.57.1.1.30	SchemaXmlWithResourceTokens	344
3.2.5.57.1.1.31	AutoIndexed	344
3.2.5.57.1.1.32	ClientSideComponentId	344

3.2.5.57.1.1.33	ClientSideComponentProperties.....	344
3.2.5.57.1.1.34	CustomFormatter .....	344
3.2.5.57.1.1.35	DefaultFormula .....	344
3.2.5.57.1.1.36	NoCrawl .....	344
3.2.5.57.1.1.37	PinnedToFiltersPane.....	345
3.2.5.57.1.1.38	ShowInFiltersPane .....	345
3.2.5.57.1.2	ObjectPath Properties.....	345
3.2.5.57.1.2.1	DescriptionResource .....	345
3.2.5.57.1.2.2	TitleResource .....	345
3.2.5.57.2	Methods .....	345
3.2.5.57.2.1	Scalar Methods.....	345
3.2.5.57.2.1.1	DeleteObject.....	345
3.2.5.57.2.1.2	SetShowInDisplayForm .....	345
3.2.5.57.2.1.3	SetShowInEditForm .....	346
3.2.5.57.2.1.4	SetShowInNewForm .....	346
3.2.5.57.2.1.5	Update.....	346
3.2.5.57.2.1.6	UpdateAndPushChanges.....	346
3.2.5.57.2.1.7	ValidateSetValue .....	347
3.2.5.57.2.2	ObjectPath Methods .....	347
3.2.5.58	Microsoft.SharePoint.Client.FieldType .....	347
3.2.5.58.1	Field Values .....	347
3.2.5.58.1.1	Invalid.....	347
3.2.5.58.1.2	Integer .....	347
3.2.5.58.1.3	Text .....	348
3.2.5.58.1.4	Note.....	348
3.2.5.58.1.5	DateTime.....	348
3.2.5.58.1.6	Counter .....	348
3.2.5.58.1.7	Choice .....	348
3.2.5.58.1.8	Lookup .....	348
3.2.5.58.1.9	Boolean .....	348
3.2.5.58.1.10	Number .....	348
3.2.5.58.1.11	Currency.....	348
3.2.5.58.1.12	URL.....	348
3.2.5.58.1.13	Computed .....	349
3.2.5.58.1.14	Threading .....	349
3.2.5.58.1.15	Guid.....	349
3.2.5.58.1.16	MultiChoice .....	349
3.2.5.58.1.17	GridChoice .....	349
3.2.5.58.1.18	Calculated.....	349
3.2.5.58.1.19	File .....	349
3.2.5.58.1.20	Attachments.....	349
3.2.5.58.1.21	User.....	349
3.2.5.58.1.22	Recurrence.....	350
3.2.5.58.1.23	CrossProjectLink .....	350
3.2.5.58.1.24	ModStat.....	350
3.2.5.58.1.25	Error .....	350
3.2.5.58.1.26	ContentTypeId.....	350
3.2.5.58.1.27	PageSeparator.....	350
3.2.5.58.1.28	ThreadIndex.....	350
3.2.5.58.1.29	WorkflowStatus .....	350
3.2.5.58.1.30	AllDayEvent .....	350
3.2.5.58.1.31	WorkflowEventType.....	350
3.2.5.58.1.32	MaxItems .....	351
3.2.5.58.1.33	Geolocation.....	351
3.2.5.58.1.34	OutcomeChoice .....	351
3.2.5.59	Microsoft.SharePoint.Client.FieldUrl .....	351
3.2.5.59.1	Properties.....	351
3.2.5.59.1.1	Scalar Properties.....	351

3.2.5.59.1.1.1	CanBeDeleted .....	351
3.2.5.59.1.1.2	DefaultValue .....	351
3.2.5.59.1.1.3	Description .....	352
3.2.5.59.1.1.4	Direction .....	352
3.2.5.59.1.1.5	DisplayFormat.....	352
3.2.5.59.1.1.6	EnforceUniqueValues .....	352
3.2.5.59.1.1.7	FieldTypeKind .....	352
3.2.5.59.1.1.8	Filterable.....	353
3.2.5.59.1.1.9	FromBaseType .....	353
3.2.5.59.1.1.10	Group .....	353
3.2.5.59.1.1.11	Hidden .....	353
3.2.5.59.1.1.12	Id.....	353
3.2.5.59.1.1.13	InternalName.....	354
3.2.5.59.1.1.14	ReadOnlyField.....	354
3.2.5.59.1.1.15	Required .....	354
3.2.5.59.1.1.16	SchemaXml .....	354
3.2.5.59.1.1.17	Scope .....	355
3.2.5.59.1.1.18	Sealed .....	355
3.2.5.59.1.1.19	Sortable .....	355
3.2.5.59.1.1.20	StaticName.....	355
3.2.5.59.1.1.21	Title .....	355
3.2.5.59.1.1.22	TypeAsString .....	355
3.2.5.59.1.1.23	TypeDisplayName.....	356
3.2.5.59.1.1.24	TypeShortDescription.....	356
3.2.5.59.1.1.25	ValidationFormula.....	356
3.2.5.59.1.1.26	ValidationMessage .....	356
3.2.5.59.1.1.27	JSLink .....	356
3.2.5.59.1.1.28	EntityPropertyName.....	357
3.2.5.59.1.1.29	Indexed .....	357
3.2.5.59.1.1.30	SchemaXmlWithResourceTokens .....	357
3.2.5.59.1.1.31	AutoIndexed .....	357
3.2.5.59.1.1.32	ClientSideComponentId.....	357
3.2.5.59.1.1.33	ClientSideComponentProperties.....	357
3.2.5.59.1.1.34	CustomFormatter .....	357
3.2.5.59.1.1.35	DefaultFormula .....	358
3.2.5.59.1.1.36	NoCrawl .....	358
3.2.5.59.1.1.37	PinnedToFiltersPane.....	358
3.2.5.59.1.1.38	ShowInFiltersPane .....	358
3.2.5.59.1.2	ObjectPath Properties .....	358
3.2.5.59.1.2.1	DescriptionResource .....	358
3.2.5.59.1.2.2	TitleResource .....	358
3.2.5.59.2	Methods.....	358
3.2.5.59.2.1	Scalar Methods.....	358
3.2.5.59.2.1.1	DeleteObject.....	358
3.2.5.59.2.1.2	SetShowInDisplayForm .....	359
3.2.5.59.2.1.3	SetShowInEditForm .....	359
3.2.5.59.2.1.4	SetShowInNewForm .....	359
3.2.5.59.2.1.5	Update.....	359
3.2.5.59.2.1.6	UpdateAndPushChanges.....	360
3.2.5.59.2.1.7	ValidateSetValue .....	360
3.2.5.59.2.2	ObjectPath Methods .....	360
3.2.5.60	Microsoft.SharePoint.Client.FieldUrlValue .....	361
3.2.5.60.1	Properties.....	361
3.2.5.60.1.1	Scalar Properties.....	361
3.2.5.60.1.1.1	Description .....	361
3.2.5.60.1.1.2	Url.....	361
3.2.5.60.1.2	ObjectPath Properties.....	361
3.2.5.61	Microsoft.SharePoint.Client.FieldUser.....	361

3.2.5.61.1	Properties.....	361
3.2.5.61.1.1	Scalar Properties.....	361
3.2.5.61.1.1.1	AllowDisplay .....	361
3.2.5.61.1.1.2	AllowMultipleValues .....	362
3.2.5.61.1.1.3	CanBeDeleted .....	362
3.2.5.61.1.1.4	DefaultValue .....	362
3.2.5.61.1.1.5	Description .....	362
3.2.5.61.1.1.6	Direction .....	362
3.2.5.61.1.1.7	EnforceUniqueValues .....	363
3.2.5.61.1.1.8	FieldTypeKind .....	363
3.2.5.61.1.1.9	Filterable.....	363
3.2.5.61.1.1.10	FromBaseType .....	363
3.2.5.61.1.1.11	Group .....	363
3.2.5.61.1.1.12	Hidden .....	364
3.2.5.61.1.1.13	Id.....	364
3.2.5.61.1.1.14	InternalName.....	364
3.2.5.61.1.1.15	IsRelationship .....	364
3.2.5.61.1.1.16	LookupField .....	364
3.2.5.61.1.1.17	LookupList.....	365
3.2.5.61.1.1.18	LookupWebId.....	365
3.2.5.61.1.1.19	Presence .....	365
3.2.5.61.1.1.20	PrimaryFieldId.....	365
3.2.5.61.1.1.21	ReadOnlyField.....	366
3.2.5.61.1.1.22	RelationshipDeleteBehavior .....	366
3.2.5.61.1.1.23	Required .....	366
3.2.5.61.1.1.24	SchemaXml .....	367
3.2.5.61.1.1.25	Scope .....	367
3.2.5.61.1.1.26	Sealed .....	367
3.2.5.61.1.1.27	SelectionGroup.....	367
3.2.5.61.1.1.28	SelectionMode.....	367
3.2.5.61.1.1.29	Sortable .....	367
3.2.5.61.1.1.30	StaticName.....	368
3.2.5.61.1.1.31	Title.....	368
3.2.5.61.1.1.32	TypeAsString .....	368
3.2.5.61.1.1.33	TypeDisplayName.....	368
3.2.5.61.1.1.34	TypeShortDescription.....	368
3.2.5.61.1.1.35	ValidationFormula.....	369
3.2.5.61.1.1.36	ValidationMessage .....	369
3.2.5.61.1.1.37	Indexed .....	369
3.2.5.61.1.1.38	JSLink.....	369
3.2.5.61.1.1.39	EntityPropertyName.....	369
3.2.5.61.1.1.40	SchemaXmlWithResourceTokens .....	369
3.2.5.61.1.1.41	AutoIndexed .....	369
3.2.5.61.1.1.42	ClientSideComponentId.....	370
3.2.5.61.1.1.43	ClientSideComponentProperties.....	370
3.2.5.61.1.1.44	CustomFormatter .....	370
3.2.5.61.1.1.45	DefaultFormula .....	370
3.2.5.61.1.1.46	DependentLookupInternalNames .....	370
3.2.5.61.1.1.47	IsDependentLookup .....	370
3.2.5.61.1.1.48	NoCrawl .....	370
3.2.5.61.1.1.49	PinnedToFiltersPane.....	371
3.2.5.61.1.1.50	ShowInFiltersPane .....	371
3.2.5.61.1.1.51	UnlimitedLengthInDocumentLibrary .....	371
3.2.5.61.1.2	ObjectPath Properties.....	371
3.2.5.61.1.2.1	DescriptionResource .....	371
3.2.5.61.1.2.2	TitleResource .....	371
3.2.5.61.2	Methods.....	371
3.2.5.61.2.1	Scalar Methods.....	371

3.2.5.61.2.1.1	DeleteObject.....	371
3.2.5.61.2.1.2	SetShowInDisplayForm .....	372
3.2.5.61.2.1.3	SetShowInEditForm .....	372
3.2.5.61.2.1.4	SetShowInNewForm .....	372
3.2.5.61.2.1.5	Update .....	372
3.2.5.61.2.1.6	UpdateAndPushChanges .....	373
3.2.5.61.2.1.7	ValidateSetValue .....	373
3.2.5.61.2.2	ObjectPath Methods .....	373
3.2.5.62	Microsoft.SharePoint.Client.FieldUserSelectionMode.....	374
3.2.5.62.1	Field Values .....	374
3.2.5.62.1.1	PeopleOnly.....	374
3.2.5.62.1.2	PeopleAndGroups.....	374
3.2.5.63	Microsoft.SharePoint.Client.FieldUserValue .....	374
3.2.5.63.1	Properties.....	374
3.2.5.63.1.1	Scalar Properties.....	374
3.2.5.63.1.1.1	Email .....	374
3.2.5.63.1.1.2	LookupId.....	374
3.2.5.63.1.1.3	LookupValue .....	374
3.2.5.63.1.2	ObjectPath Properties.....	374
3.2.5.64	Microsoft.SharePoint.Client.File.....	375
3.2.5.64.1	Properties.....	375
3.2.5.64.1.1	Scalar Properties.....	375
3.2.5.64.1.1.1	CheckInComment.....	375
3.2.5.64.1.1.2	CheckOutType.....	375
3.2.5.64.1.1.3	CustomizedPageStatus .....	375
3.2.5.64.1.1.4	ETag .....	375
3.2.5.64.1.1.5	Exists.....	376
3.2.5.64.1.1.6	Level .....	376
3.2.5.64.1.1.7	MajorVersion.....	376
3.2.5.64.1.1.8	MinorVersion.....	376
3.2.5.64.1.1.9	Name.....	376
3.2.5.64.1.1.10	ServerRelativeUrl .....	377
3.2.5.64.1.1.11	TimeCreated .....	377
3.2.5.64.1.1.12	TimeLastModified.....	377
3.2.5.64.1.1.13	Title.....	377
3.2.5.64.1.1.14	UIVersion .....	378
3.2.5.64.1.1.15	UIVersionLabel .....	378
3.2.5.64.1.1.16	Length .....	378
3.2.5.64.1.1.17	ContentTag.....	379
3.2.5.64.1.1.18	IrmEnabled.....	379
3.2.5.64.1.1.19	LinkingUrl.....	379
3.2.5.64.1.1.20	UniqueId .....	379
3.2.5.64.1.1.21	LinkingUri.....	379
3.2.5.64.1.1.22	ListId .....	379
3.2.5.64.1.1.23	PageRenderType .....	380
3.2.5.64.1.1.24	ServerRelativePath .....	380
3.2.5.64.1.1.25	SiteId .....	380
3.2.5.64.1.1.26	WebId.....	380
3.2.5.64.1.2	ObjectPath Properties.....	380
3.2.5.64.1.2.1	Author .....	380
3.2.5.64.1.2.2	CheckedOutByUser .....	380
3.2.5.64.1.2.3	EffectiveInformationRightsManagementSettings .....	381
3.2.5.64.1.2.4	InformationRightsManagementSettings .....	381
3.2.5.64.1.2.5	ListItemAllFields .....	381
3.2.5.64.1.2.6	LockedByUser .....	381
3.2.5.64.1.2.7	ModifiedBy.....	381
3.2.5.64.1.2.8	Properties.....	382
3.2.5.64.1.2.9	VersionEvents .....	382

3.2.5.64.1.2.10	Versions .....	382
3.2.5.64.2	Methods .....	382
3.2.5.64.2.1	Scalar Methods .....	382
3.2.5.64.2.1.1	CheckIn .....	382
3.2.5.64.2.1.2	CheckOut .....	382
3.2.5.64.2.1.3	CopyTo .....	383
3.2.5.64.2.1.4	DeleteObject .....	383
3.2.5.64.2.1.5	MoveTo .....	384
3.2.5.64.2.1.6	Publish .....	384
3.2.5.64.2.1.7	Recycle .....	385
3.2.5.64.2.1.8	SaveBinary .....	385
3.2.5.64.2.1.9	UndoCheckOut .....	386
3.2.5.64.2.1.10	UnPublish .....	386
3.2.5.64.2.1.11	OpenBinaryStream .....	386
3.2.5.64.2.1.12	SaveBinaryStream .....	386
3.2.5.64.2.1.13	Approve .....	386
3.2.5.64.2.1.14	Deny .....	387
3.2.5.64.2.1.15	GetContentVerFromTag .....	387
3.2.5.64.2.1.16	CancelUpload .....	387
3.2.5.64.2.1.17	ContinueUpload .....	387
3.2.5.64.2.1.18	ExecuteCobaltRequest .....	388
3.2.5.64.2.1.19	GetImagePreviewUrl .....	388
3.2.5.64.2.1.20	GetPreAuthorizedAccessUrl .....	388
3.2.5.64.2.1.21	GetWOPIFrameUrl .....	388
3.2.5.64.2.1.22	StartUpload .....	389
3.2.5.64.2.1.23	Update .....	389
3.2.5.64.2.1.24	CopyToUsingPath .....	389
3.2.5.64.2.1.25	GetImagePreviewUri .....	390
3.2.5.64.2.1.26	MoveToUsingPath .....	390
3.2.5.64.2.1.27	OpenBinaryStreamWithOptions .....	391
3.2.5.64.2.1.28	RecycleWithETag .....	391
3.2.5.64.2.1.29	UpdateVirusInfo .....	391
3.2.5.64.2.2	ObjectPath Methods .....	391
3.2.5.64.2.2.1	GetLimitedWebPartManager .....	392
3.2.5.64.2.2.2	FinishUpload .....	392
3.2.5.64.2.2.3	GetUploadStatus .....	392
3.2.5.65	Microsoft.SharePoint.Client.FileCollection .....	392
3.2.5.65.1	Properties .....	393
3.2.5.65.1.1	Scalar Properties .....	393
3.2.5.65.1.2	ObjectPath Properties .....	393
3.2.5.65.2	Methods .....	393
3.2.5.65.2.1	Scalar Methods .....	393
3.2.5.65.2.2	ObjectPath Methods .....	393
3.2.5.65.2.2.1	Add .....	393
3.2.5.65.2.2.2	AddStub .....	393
3.2.5.65.2.2.3	AddStubUsingPath .....	394
3.2.5.65.2.2.4	AddTemplateFile .....	394
3.2.5.65.2.2.5	AddUsingPath .....	394
3.2.5.65.2.2.6	GetByPathOrAddStub .....	394
3.2.5.65.2.2.7	GetByUrl .....	395
3.2.5.65.2.2.8	GetByUrlOrAddStub .....	395
3.2.5.66	Microsoft.SharePoint.Client.FileCreationInformation .....	395
3.2.5.66.1	Properties .....	395
3.2.5.66.1.1	Scalar Properties .....	395
3.2.5.66.1.1.1	Content .....	395
3.2.5.66.1.1.2	Overwrite .....	395
3.2.5.66.1.1.3	Url .....	396
3.2.5.66.1.1.4	ContentStream .....	396

3.2.5.66.1.2	ObjectPath Properties.....	396
3.2.5.67	Microsoft.SharePoint.Client.FileLevel .....	396
3.2.5.67.1	Field Values .....	396
3.2.5.67.1.1	Published .....	396
3.2.5.67.1.2	Draft .....	396
3.2.5.67.1.3	Checkout .....	396
3.2.5.68	Microsoft.SharePoint.Client.FileSaveBinaryInformation.....	396
3.2.5.68.1	Properties.....	397
3.2.5.68.1.1	Scalar Properties.....	397
3.2.5.68.1.1.1	CheckRequiredFields .....	397
3.2.5.68.1.1.2	Content.....	397
3.2.5.68.1.1.3	ETag .....	397
3.2.5.68.1.1.4	ContentStream.....	397
3.2.5.68.1.1.5	FieldValues .....	397
3.2.5.68.1.2	ObjectPath Properties.....	397
3.2.5.69	Microsoft.SharePoint.Client.FileSystemObjectType .....	398
3.2.5.69.1	Field Values .....	398
3.2.5.69.1.1	Invalid.....	398
3.2.5.69.1.2	File .....	398
3.2.5.69.1.3	Folder.....	398
3.2.5.69.1.4	Web .....	398
3.2.5.70	Microsoft.SharePoint.Client.FileVersion .....	398
3.2.5.70.1	Properties.....	398
3.2.5.70.1.1	Scalar Properties.....	398
3.2.5.70.1.1.1	CheckInComment.....	398
3.2.5.70.1.1.2	Created .....	398
3.2.5.70.1.1.3	ID .....	399
3.2.5.70.1.1.4	IsCurrentVersion .....	399
3.2.5.70.1.1.5	Url.....	399
3.2.5.70.1.1.6	VersionLabel .....	399
3.2.5.70.1.1.7	Size .....	399
3.2.5.70.1.1.8	Length .....	399
3.2.5.70.1.2	ObjectPath Properties.....	400
3.2.5.70.1.2.1	CreatedBy .....	400
3.2.5.70.2	Methods.....	400
3.2.5.70.2.1	Scalar Methods.....	400
3.2.5.70.2.1.1	DeleteObject.....	400
3.2.5.70.2.1.2	OpenBinaryStream .....	400
3.2.5.70.2.2	ObjectPath Methods .....	400
3.2.5.71	Microsoft.SharePoint.Client.FileVersionCollection.....	400
3.2.5.71.1	Properties.....	400
3.2.5.71.1.1	Scalar Properties.....	400
3.2.5.71.1.2	ObjectPath Properties.....	401
3.2.5.71.2	Methods .....	401
3.2.5.71.2.1	Scalar Methods.....	401
3.2.5.71.2.1.1	DeleteAll .....	401
3.2.5.71.2.1.2	DeleteById .....	401
3.2.5.71.2.1.3	DeleteByLabel .....	401
3.2.5.71.2.1.4	RecycleById .....	402
3.2.5.71.2.1.5	RecycleByLabel .....	402
3.2.5.71.2.1.6	RestoreByLabel .....	402
3.2.5.71.2.2	ObjectPath Methods .....	403
3.2.5.71.2.2.1	GetById .....	403
3.2.5.72	Microsoft.SharePoint.Client.Folder .....	403
3.2.5.72.1	Properties.....	403
3.2.5.72.1.1	Scalar Properties.....	403
3.2.5.72.1.1.1	ContentTypeOrder .....	403
3.2.5.72.1.1.2	Exists.....	403

3.2.5.72.1.1.3	IsWOPIEnabled .....	404
3.2.5.72.1.1.4	ItemCount .....	404
3.2.5.72.1.1.5	Name .....	404
3.2.5.72.1.1.6	ProgID .....	404
3.2.5.72.1.1.7	ServerRelativePath .....	404
3.2.5.72.1.1.8	ServerRelativeUrl .....	404
3.2.5.72.1.1.9	TimeCreated .....	404
3.2.5.72.1.1.10	TimeLastModified.....	405
3.2.5.72.1.1.11	UniqueContentTypeOrder .....	405
3.2.5.72.1.1.12	UniqueId .....	405
3.2.5.72.1.1.13	WelcomePage .....	405
3.2.5.72.1.2	ObjectPath Properties.....	405
3.2.5.72.1.2.1	Files.....	405
3.2.5.72.1.2.2	Folders.....	406
3.2.5.72.1.2.3	ParentFolder .....	406
3.2.5.72.1.2.4	Properties.....	406
3.2.5.72.1.2.5	ListItemAllFields.....	406
3.2.5.72.1.2.6	StorageMetrics .....	406
3.2.5.72.2	Methods .....	406
3.2.5.72.2.1	Scalar Methods .....	406
3.2.5.72.2.1.1	AddSubFolder .....	406
3.2.5.72.2.1.2	AddSubFolderUsingPath .....	407
3.2.5.72.2.1.3	DeleteObject.....	407
3.2.5.72.2.1.4	MoveTo .....	407
3.2.5.72.2.1.5	MoveToUsingPath .....	407
3.2.5.72.2.1.6	Recycle .....	407
3.2.5.72.2.1.7	Update.....	408
3.2.5.72.2.2	ObjectPath Methods .....	408
3.2.5.72.2.2.1	GetListItemChanges .....	408
3.2.5.72.2.2.2	GetChanges .....	408
3.2.5.73	Microsoft.SharePoint.Client.FolderCollection .....	408
3.2.5.73.1	Properties.....	408
3.2.5.73.1.1	Scalar Properties.....	408
3.2.5.73.1.2	ObjectPath Properties.....	408
3.2.5.73.2	Methods .....	408
3.2.5.73.2.1	Scalar Methods.....	409
3.2.5.73.2.2	ObjectPath Methods .....	409
3.2.5.73.2.2.1	Add .....	409
3.2.5.73.2.2.2	AddUsingPath .....	409
3.2.5.73.2.2.3	AddWithOverwrite .....	409
3.2.5.73.2.2.4	GetByPath .....	409
3.2.5.73.2.2.5	GetByUrl .....	410
3.2.5.74	Microsoft.SharePoint.Client.Form .....	410
3.2.5.74.1	Properties.....	410
3.2.5.74.1.1	Scalar Properties.....	410
3.2.5.74.1.1.1	FormType.....	410
3.2.5.74.1.1.2	Id.....	410
3.2.5.74.1.1.3	ResourcePath.....	410
3.2.5.74.1.1.4	ServerRelativeUrl .....	410
3.2.5.74.1.2	ObjectPath Properties.....	411
3.2.5.74.2	Methods .....	411
3.2.5.74.2.1	Scalar Methods.....	411
3.2.5.74.2.2	ObjectPath Methods .....	411
3.2.5.75	Microsoft.SharePoint.Client.FormCollection .....	411
3.2.5.75.1	Properties.....	411
3.2.5.75.1.1	Scalar Properties.....	411
3.2.5.75.1.2	ObjectPath Properties.....	411
3.2.5.75.2	Methods .....	411



3.2.5.75.2.1	Scalar Methods	411
3.2.5.75.2.2	ObjectPath Methods	411
3.2.5.75.2.2.1	GetByPageType	411
3.2.5.75.2.2.2	GetById	412
3.2.5.76	Microsoft.SharePoint.Client.Group	412
3.2.5.76.1	Properties	412
3.2.5.76.1.1	Scalar Properties	412
3.2.5.76.1.1.1	AllowMembersEditMembership	412
3.2.5.76.1.1.2	AllowRequestToJoinLeave	412
3.2.5.76.1.1.3	AutoAcceptRequestToJoinLeave	412
3.2.5.76.1.1.4	CanCurrentUserEditMembership	412
3.2.5.76.1.1.5	CanCurrentUserManageGroup	413
3.2.5.76.1.1.6	CanCurrentUserViewMembership	413
3.2.5.76.1.1.7	Description	413
3.2.5.76.1.1.8	Id	413
3.2.5.76.1.1.9	LoginName	413
3.2.5.76.1.1.10	OnlyAllowMembersViewMembership	413
3.2.5.76.1.1.11	OwnerTitle	413
3.2.5.76.1.1.12	PrincipalType	414
3.2.5.76.1.1.13	RequestToJoinLeaveEmailSetting	414
3.2.5.76.1.1.14	Title	414
3.2.5.76.1.1.15	IsHiddenInUI	414
3.2.5.76.1.2	ObjectPath Properties	414
3.2.5.76.1.2.1	Owner	414
3.2.5.76.1.2.2	Users	414
3.2.5.76.2	Methods	415
3.2.5.76.2.1	Scalar Methods	415
3.2.5.76.2.1.1	Update	415
3.2.5.76.2.2	ObjectPath Methods	415
3.2.5.77	Microsoft.SharePoint.Client.GroupCollection	415
3.2.5.77.1	Properties	415
3.2.5.77.1.1	Scalar Properties	415
3.2.5.77.1.2	ObjectPath Properties	415
3.2.5.77.2	Methods	415
3.2.5.77.2.1	Scalar Methods	415
3.2.5.77.2.1.1	Remove	415
3.2.5.77.2.1.2	RemoveById	416
3.2.5.77.2.1.3	RemoveByLoginName	416
3.2.5.77.2.2	ObjectPath Methods	416
3.2.5.77.2.2.1	Add	416
3.2.5.77.2.2.2	GetById	417
3.2.5.77.2.2.3	GetByName	417
3.2.5.78	Microsoft.SharePoint.Client.GroupCreationInformation	417
3.2.5.78.1	Properties	417
3.2.5.78.1.1	Scalar Properties	417
3.2.5.78.1.1.1	Description	417
3.2.5.78.1.1.2	Title	417
3.2.5.78.1.2	ObjectPath Properties	418
3.2.5.79	Microsoft.SharePoint.Client.List	418
3.2.5.79.1	Properties	418
3.2.5.79.1.1	Scalar Properties	418
3.2.5.79.1.1.1	AllowContentTypes	418
3.2.5.79.1.1.2	BaseTemplate	418
3.2.5.79.1.1.3	BaseType	418
3.2.5.79.1.1.4	BrowserFileHandling	418
3.2.5.79.1.1.5	ContentTypesEnabled	419
3.2.5.79.1.1.6	Created	419
3.2.5.79.1.1.7	DataSource	419

3.2.5.79.1.1.8	DefaultContentApprovalWorkflowId.....	419
3.2.5.79.1.1.9	DefaultDisplayFormUrl .....	419
3.2.5.79.1.1.10	DefaultEditFormUrl .....	419
3.2.5.79.1.1.11	DefaultNewFormUrl.....	420
3.2.5.79.1.1.12	DefaultViewUrl .....	420
3.2.5.79.1.1.13	Description .....	420
3.2.5.79.1.1.14	Direction .....	420
3.2.5.79.1.1.15	DocumentTemplateUrl.....	420
3.2.5.79.1.1.16	DraftVersionVisibility.....	420
3.2.5.79.1.1.17	EffectiveBasePermissions.....	421
3.2.5.79.1.1.18	EnableAttachments .....	421
3.2.5.79.1.1.19	EnableFolderCreation .....	421
3.2.5.79.1.1.20	EnableMinorVersions.....	421
3.2.5.79.1.1.21	EnableModeration .....	421
3.2.5.79.1.1.22	EnableVersioning .....	421
3.2.5.79.1.1.23	ForceCheckout .....	422
3.2.5.79.1.1.24	HasExternalDataSource.....	422
3.2.5.79.1.1.25	HasUniqueRoleAssignments .....	422
3.2.5.79.1.1.26	Hidden .....	422
3.2.5.79.1.1.27	Id .....	422
3.2.5.79.1.1.28	ImageUrl.....	422
3.2.5.79.1.1.29	IsApplicationList .....	423
3.2.5.79.1.1.30	IsCatalog.....	423
3.2.5.79.1.1.31	IsSiteAssetsLibrary .....	423
3.2.5.79.1.1.32	ItemCount .....	423
3.2.5.79.1.1.33	LastItemDeletedDate .....	423
3.2.5.79.1.1.34	LastItemModifiedDate .....	423
3.2.5.79.1.1.35	MultipleDataList .....	423
3.2.5.79.1.1.36	NoCrawl .....	424
3.2.5.79.1.1.37	OnQuickLaunch .....	424
3.2.5.79.1.1.38	ParentWebUrl.....	424
3.2.5.79.1.1.39	SchemaXml .....	424
3.2.5.79.1.1.40	ServerTemplateCanCreateFolders .....	424
3.2.5.79.1.1.41	TemplateFeatureId .....	424
3.2.5.79.1.1.42	Title .....	425
3.2.5.79.1.1.43	ValidationFormula.....	425
3.2.5.79.1.1.44	ValidationMessage .....	425
3.2.5.79.1.1.45	EntityTypeFullName.....	425
3.2.5.79.1.1.46	ListItemEntityTypeFullName .....	425
3.2.5.79.1.1.47	IrmEnabled.....	425
3.2.5.79.1.1.48	IrmExpire .....	426
3.2.5.79.1.1.49	IrmReject .....	426
3.2.5.79.1.1.50	EffectiveBasePermissionsForUI .....	426
3.2.5.79.1.1.51	IsPrivate .....	426
3.2.5.79.1.1.52	CrawlNonDefaultViews .....	427
3.2.5.79.1.1.53	CurrentChangeToken .....	427
3.2.5.79.1.1.54	FileSavePostProcessingEnabled .....	427
3.2.5.79.1.1.55	MajorVersionLimit.....	427
3.2.5.79.1.1.56	MajorWithMinorVersionsLimit .....	427
3.2.5.79.1.1.57	ParserDisabled .....	427
3.2.5.79.1.1.58	AllowDeletion .....	428
3.2.5.79.1.1.59	CustomActionElements.....	428
3.2.5.79.1.1.60	DefaultItemOpenUseListSetting.....	428
3.2.5.79.1.1.61	DefaultViewPath .....	428
3.2.5.79.1.1.62	EnableAssignToEmail .....	428
3.2.5.79.1.1.63	ExcludeFromOfflineClient.....	428
3.2.5.79.1.1.64	ExemptFromBlockDownloadOfNonViewableFiles.....	429
3.2.5.79.1.1.65	ImagePath.....	429

3.2.5.79.1.1.66	IsEnterpriseGalleryLibrary .....	429
3.2.5.79.1.1.67	IsSystemList .....	429
3.2.5.79.1.1.68	LastItemUserModifiedDate .....	429
3.2.5.79.1.1.69	ListExperienceOptions .....	429
3.2.5.79.1.1.70	PageRenderType .....	430
3.2.5.79.1.1.71	ParentWebPath .....	430
3.2.5.79.1.1.72	ReadSecurity .....	430
3.2.5.79.1.1.73	WriteSecurity .....	430
3.2.5.79.1.2	ObjectPath Properties .....	430
3.2.5.79.1.2.1	ContentTypes .....	430
3.2.5.79.1.2.2	Fields .....	430
3.2.5.79.1.2.3	Forms .....	430
3.2.5.79.1.2.4	ParentWeb .....	431
3.2.5.79.1.2.5	RoleAssignments .....	431
3.2.5.79.1.2.6	RootFolder .....	431
3.2.5.79.1.2.7	UserCustomActions .....	431
3.2.5.79.1.2.8	Views .....	431
3.2.5.79.1.2.9	WorkflowAssociations .....	431
3.2.5.79.1.2.10	FirstUniqueAncestorSecurableObject .....	432
3.2.5.79.1.2.11	Items .....	432
3.2.5.79.1.2.12	InformationRightsManagementSettings .....	432
3.2.5.79.1.2.13	EventReceivers .....	432
3.2.5.79.1.2.14	DefaultView .....	432
3.2.5.79.1.2.15	CreatablesInfo .....	432
3.2.5.79.1.2.16	DescriptionResource .....	433
3.2.5.79.1.2.17	TitleResource .....	433
3.2.5.79.1.2.18	Activities .....	433
3.2.5.79.1.2.19	Subscriptions .....	433
3.2.5.79.2	Methods .....	433
3.2.5.79.2.1	Scalar Methods .....	433
3.2.5.79.2.1.1	BreakRoleInheritance .....	433
3.2.5.79.2.1.2	DeleteObject .....	434
3.2.5.79.2.1.3	Recycle .....	434
3.2.5.79.2.1.4	ResetRoleInheritance .....	434
3.2.5.79.2.1.5	Update .....	435
3.2.5.79.2.1.6	RenderListData .....	435
3.2.5.79.2.1.7	GetListItemChangesSinceToken .....	435
3.2.5.79.2.1.8	RenderListFormData .....	435
3.2.5.79.2.1.9	SaveAsNewView .....	436
3.2.5.79.2.1.10	GetUserEffectivePermissions .....	436
3.2.5.79.2.1.11	ReserveListItemId .....	437
3.2.5.79.2.1.12	RenderListDataAsStream .....	437
3.2.5.79.2.1.13	CreateDocumentAndGetEditLink .....	437
3.2.5.79.2.1.14	GetSpecialFolderUrl .....	437
3.2.5.79.2.1.15	GetWebDavUrl .....	438
3.2.5.79.2.1.16	RenderListContextMenuData .....	438
3.2.5.79.2.1.17	RenderListFilterData .....	438
3.2.5.79.2.1.18	AddValidateUpdateItem .....	438
3.2.5.79.2.1.19	AddValidateUpdateItemUsingPath .....	439
3.2.5.79.2.1.20	BulkValidateUpdateListItems .....	439
3.2.5.79.2.1.21	CreateDocumentWithDefaultName .....	440
3.2.5.79.2.1.22	GetListDataAsStream .....	440
3.2.5.79.2.1.23	RenderExtendedListFormData .....	441
3.2.5.79.2.1.24	SaveAsTemplate .....	441
3.2.5.79.2.1.25	SetExemptFromBlockDownloadOfNonViewableFiles .....	442
3.2.5.79.2.2	ObjectPath Methods .....	442
3.2.5.79.2.2.1	AddItem .....	442
3.2.5.79.2.2.2	GetChanges .....	442

3.2.5.79.2.2.3	GetItemById	442
3.2.5.79.2.2.4	GetItemByStringId	442
3.2.5.79.2.2.5	GetItems	443
3.2.5.79.2.2.6	GetRelatedFields	443
3.2.5.79.2.2.7	GetView	443
3.2.5.79.2.2.8	GetRelatedFieldsExtendedData	443
3.2.5.79.2.2.9	CreateDocument	444
3.2.5.79.2.2.10	CreateDocumentFromTemplate	444
3.2.5.79.2.2.11	CreateDocumentFromTemplateBytes	444
3.2.5.79.2.2.12	CreateDocumentFromTemplateStream	445
3.2.5.79.2.2.13	AddItemUsingPath	445
3.2.5.79.2.2.14	CreateDocumentFromTemplateUsingPath	445
3.2.5.79.2.2.15	GetBloomFilter	446
3.2.5.79.2.2.16	GetBloomFilterWithCustomFields	446
3.2.5.79.2.2.17	GetCheckedOutFiles	446
3.2.5.79.2.2.18	getFileExtendedActivities	446
3.2.5.79.2.2.19	GetItemByUniqueId	447
3.2.5.80	Microsoft.SharePoint.Client.ListCollection	447
3.2.5.80.1	Properties	447
3.2.5.80.1.1	Scalar Properties	447
3.2.5.80.1.2	ObjectPath Properties	447
3.2.5.80.2	Methods	447
3.2.5.80.2.1	Scalar Methods	447
3.2.5.80.2.2	ObjectPath Methods	447
3.2.5.80.2.2.1	Add	447
3.2.5.80.2.2.2	EnsureClientRenderedSitePagesLibrary	448
3.2.5.80.2.2.3	EnsureEventsList	448
3.2.5.80.2.2.4	EnsureSiteAssetsLibrary	448
3.2.5.80.2.2.5	EnsureSitePagesLibrary	448
3.2.5.80.2.2.6	GetById	448
3.2.5.80.2.2.7	GetByTitle	449
3.2.5.81	Microsoft.SharePoint.Client.ListCreationInformation	449
3.2.5.81.1	Properties	449
3.2.5.81.1.1	Scalar Properties	449
3.2.5.81.1.1.1	CustomSchemaXml	449
3.2.5.81.1.1.2	DataSourceProperties	449
3.2.5.81.1.1.3	Description	449
3.2.5.81.1.1.4	DocumentTemplateType	450
3.2.5.81.1.1.5	QuickLaunchOption	450
3.2.5.81.1.1.6	TemplateFeatureId	450
3.2.5.81.1.1.7	TemplateType	450
3.2.5.81.1.1.8	Title	450
3.2.5.81.1.1.9	Url	450
3.2.5.81.1.2	ObjectPath Properties	450
3.2.5.81.1.2.1	ListTemplate	450
3.2.5.82	Microsoft.SharePoint.Client.ListDataSource	451
3.2.5.82.1	Properties	451
3.2.5.82.1.1	Scalar Properties	451
3.2.5.82.1.1.1	Properties	451
3.2.5.82.1.2	ObjectPath Properties	451
3.2.5.83	Microsoft.SharePoint.Client.ListDataValidationExceptionValue	451
3.2.5.83.1	Properties	451
3.2.5.83.1.1	Scalar Properties	451
3.2.5.83.1.1.1	FieldFailures	451
3.2.5.83.1.1.2	ItemFailure	451
3.2.5.83.1.2	ObjectPath Properties	452
3.2.5.84	Microsoft.SharePoint.Client.ListDataValidationFailure	452
3.2.5.84.1	Properties	452

3.2.5.84.1.1	Scalar Properties.....	452
3.2.5.84.1.1.1	DisplayName .....	452
3.2.5.84.1.1.2	Message.....	452
3.2.5.84.1.1.3	Name.....	452
3.2.5.84.1.1.4	Reason.....	452
3.2.5.84.1.1.5	ValidationType .....	452
3.2.5.84.1.2	ObjectPath Properties.....	453
3.2.5.85	Microsoft.SharePoint.Client.ListDataValidationFailureReason.....	453
3.2.5.85.1	Field Values .....	453
3.2.5.85.1.1	DataFailure .....	453
3.2.5.85.1.2	FormulaError.....	453
3.2.5.86	Microsoft.SharePoint.Client.ListDataValidationType.....	453
3.2.5.86.1	Field Values .....	453
3.2.5.86.1.1	UserFormulaField .....	453
3.2.5.86.1.2	UserFormulaItem .....	453
3.2.5.86.1.3	RequiredField .....	453
3.2.5.86.1.4	ChoiceField .....	454
3.2.5.86.1.5	MinMaxField .....	454
3.2.5.86.1.6	TextField.....	454
3.2.5.87	Microsoft.SharePoint.Client.ListItem .....	454
3.2.5.87.1	Properties.....	456
3.2.5.87.1.1	Scalar Properties.....	456
3.2.5.87.1.1.1	DisplayName .....	456
3.2.5.87.1.1.2	EffectiveBasePermissions.....	456
3.2.5.87.1.1.3	FileSystemObjectType.....	456
3.2.5.87.1.1.4	HasUniqueRoleAssignments .....	457
3.2.5.87.1.1.5	Id .....	457
3.2.5.87.1.1.6	EffectiveBasePermissionsForUI .....	457
3.2.5.87.1.1.7	Client_Title .....	457
3.2.5.87.1.1.8	CommentsDisabled.....	457
3.2.5.87.1.1.9	CommentsDisabledScope .....	457
3.2.5.87.1.1.10	IconOverlay .....	458
3.2.5.87.1.1.11	ServerRedirectedEmbedUri .....	458
3.2.5.87.1.1.12	ServerRedirectedEmbedUrl .....	458
3.2.5.87.1.2	ObjectPath Properties.....	458
3.2.5.87.1.2.1	ContentType .....	458
3.2.5.87.1.2.2	FieldValuesAsHtml .....	458
3.2.5.87.1.2.3	FieldValuesAsText.....	458
3.2.5.87.1.2.4	FieldValuesForEdit .....	459
3.2.5.87.1.2.5	File .....	459
3.2.5.87.1.2.6	ParentList.....	459
3.2.5.87.1.2.7	RoleAssignments .....	459
3.2.5.87.1.2.8	AttachmentFiles .....	459
3.2.5.87.1.2.9	FirstUniqueAncestorSecurableObject .....	459
3.2.5.87.1.2.10	Folder .....	459
3.2.5.87.1.2.11	GetDlpPolicyTip .....	460
3.2.5.87.1.2.12	Activities .....	460
3.2.5.87.1.2.13	Properties.....	460
3.2.5.87.1.2.14	Versions.....	460
3.2.5.87.2	Methods .....	460
3.2.5.87.2.1	Scalar Methods.....	460
3.2.5.87.2.1.1	BreakRoleInheritance.....	460
3.2.5.87.2.1.2	DeleteObject.....	461
3.2.5.87.2.1.3	ParseAndSetFieldValue .....	461
3.2.5.87.2.1.4	Recycle .....	461
3.2.5.87.2.1.5	ResetRoleInheritance .....	462
3.2.5.87.2.1.6	SetFieldValue .....	462
3.2.5.87.2.1.7	Update.....	462

3.2.5.87.2.1.8	GetWOPIFrameUrl	463
3.2.5.87.2.1.9	ValidateUpdateListItem	463
3.2.5.87.2.1.10	GetUserEffectivePermissions	463
3.2.5.87.2.1.11	OverridePolicyTip	464
3.2.5.87.2.1.12	SetCommentsDisabled	464
3.2.5.87.2.1.13	SystemUpdate	464
3.2.5.87.2.1.14	UpdateOverwriteVersion	464
3.2.5.87.2.2	ObjectPath Methods	465
3.2.5.87.2.2.1	GetChanges	465
3.2.5.88	Microsoft.SharePoint.Client.ListItemCollection	465
3.2.5.88.1	Properties	465
3.2.5.88.1.1	Scalar Properties	465
3.2.5.88.1.1.1	ListItemCollectionPosition	465
3.2.5.88.1.2	ObjectPath Properties	465
3.2.5.88.2	Methods	465
3.2.5.88.2.1	Scalar Methods	465
3.2.5.88.2.2	ObjectPath Methods	465
3.2.5.88.2.2.1	GetById	465
3.2.5.88.2.2.2	GetByStringId	466
3.2.5.89	Microsoft.SharePoint.Client.ListItemCollectionPosition	466
3.2.5.89.1	Properties	466
3.2.5.89.1.1	Scalar Properties	466
3.2.5.89.1.1.1	PagingInfo	466
3.2.5.89.1.2	ObjectPath Properties	467
3.2.5.90	Microsoft.SharePoint.Client.ListItemCreationInformation	467
3.2.5.90.1	Properties	467
3.2.5.90.1.1	Scalar Properties	467
3.2.5.90.1.1.1	FolderUrl	467
3.2.5.90.1.1.2	LeafName	467
3.2.5.90.1.1.3	UnderlyingObjectType	467
3.2.5.90.1.2	ObjectPath Properties	467
3.2.5.91	Microsoft.SharePoint.Client.ListTemplate	468
3.2.5.91.1	Properties	468
3.2.5.91.1.1	Scalar Properties	468
3.2.5.91.1.1.1	AllowsFolderCreation	468
3.2.5.91.1.1.2	BaseType	468
3.2.5.91.1.1.3	Description	468
3.2.5.91.1.1.4	FeatureId	468
3.2.5.91.1.1.5	Hidden	468
3.2.5.91.1.1.6	ImageUrl	469
3.2.5.91.1.1.7	InternalName	469
3.2.5.91.1.1.8	IsCustomTemplate	469
3.2.5.91.1.1.9	ListTemplateTypeKind	469
3.2.5.91.1.1.10	Name	469
3.2.5.91.1.1.11	OnQuickLaunch	469
3.2.5.91.1.1.12	Unique	470
3.2.5.91.1.2	ObjectPath Properties	470
3.2.5.91.2	Methods	470
3.2.5.91.2.1	Scalar Methods	470
3.2.5.91.2.1.1	GetGlobalSchemaXml	470
3.2.5.91.2.2	ObjectPath Methods	470
3.2.5.92	Microsoft.SharePoint.Client.ListTemplateCollection	470
3.2.5.92.1	Properties	470
3.2.5.92.1.1	Scalar Properties	470
3.2.5.92.1.2	ObjectPath Properties	470
3.2.5.92.2	Methods	470
3.2.5.92.2.1	Scalar Methods	470
3.2.5.92.2.2	ObjectPath Methods	470

3.2.5.92.2.2.1	GetByName .....	470
3.2.5.93	Microsoft.SharePoint.Client.ListTemplateType .....	471
3.2.5.93.1	Field Values .....	471
3.2.5.93.1.1	NoListTemplate.....	471
3.2.5.93.1.2	GenericList.....	471
3.2.5.93.1.3	DocumentLibrary .....	471
3.2.5.93.1.4	Survey .....	471
3.2.5.93.1.5	Links .....	471
3.2.5.93.1.6	Announcements .....	471
3.2.5.93.1.7	Contacts .....	471
3.2.5.93.1.8	Events.....	472
3.2.5.93.1.9	Tasks .....	472
3.2.5.93.1.10	DiscussionBoard .....	472
3.2.5.93.1.11	PictureLibrary.....	472
3.2.5.93.1.12	DataSources.....	472
3.2.5.93.1.13	WebTemplateCatalog.....	472
3.2.5.93.1.14	UserInformation .....	472
3.2.5.93.1.15	WebPartCatalog .....	472
3.2.5.93.1.16	ListTemplateCatalog.....	472
3.2.5.93.1.17	XMLForm .....	472
3.2.5.93.1.18	MasterPageCatalog.....	473
3.2.5.93.1.19	NoCodeWorkflows .....	473
3.2.5.93.1.20	WorkflowProcess.....	473
3.2.5.93.1.21	WebPageLibrary.....	473
3.2.5.93.1.22	CustomGrid.....	473
3.2.5.93.1.23	SolutionCatalog .....	473
3.2.5.93.1.24	NoCodePublic .....	473
3.2.5.93.1.25	ThemeCatalog .....	473
3.2.5.93.1.26	DataConnectionLibrary .....	473
3.2.5.93.1.27	WorkflowHistory .....	473
3.2.5.93.1.28	GanttTasks .....	474
3.2.5.93.1.29	Meetings.....	474
3.2.5.93.1.30	Agenda.....	474
3.2.5.93.1.31	MeetingUser.....	474
3.2.5.93.1.32	Decision.....	474
3.2.5.93.1.33	MeetingObjective .....	474
3.2.5.93.1.34	TextBox.....	474
3.2.5.93.1.35	ThingsToBring .....	474
3.2.5.93.1.36	HomePageLibrary.....	474
3.2.5.93.1.37	Posts.....	474
3.2.5.93.1.38	Comments .....	475
3.2.5.93.1.39	Categories .....	475
3.2.5.93.1.40	Facility .....	475
3.2.5.93.1.41	Whereabouts.....	475
3.2.5.93.1.42	CallTrack .....	475
3.2.5.93.1.43	Circulation .....	475
3.2.5.93.1.44	Timecard .....	475
3.2.5.93.1.45	Holidays .....	475
3.2.5.93.1.46	IMEDic.....	475
3.2.5.93.1.47	ExternalList.....	475
3.2.5.93.1.48	IssueTracking.....	476
3.2.5.93.1.49	AdminTasks .....	476
3.2.5.93.1.50	HealthRules.....	476
3.2.5.93.1.51	HealthReports .....	476
3.2.5.93.1.52	InvalidType .....	476
3.2.5.93.1.53	AccessRequest.....	476
3.2.5.93.1.54	DesignCatalog .....	476
3.2.5.93.1.55	MaintenanceLogs .....	476

3.2.5.93.1.56	AppDataCatalog	476
3.2.5.93.1.57	TasksWithTimelineAndHierarchy	477
3.2.5.93.1.58	MySiteDocumentLibrary	477
3.2.5.93.1.59	DeveloperSiteDraftApps	477
3.2.5.93.1.60	HelpLibrary	477
3.2.5.93.1.61	AccessApp	477
3.2.5.93.1.62	SharingLinks	477
3.2.5.93.1.63	AppFilesCatalog	477
3.2.5.93.1.64	PromotedLinks	477
3.2.5.93.1.65	RecipesTable	477
3.2.5.93.1.66	FormulasTable	477
3.2.5.93.1.67	ItemReferenceCollection	478
3.2.5.93.1.68	ItemReferenceReference	478
3.2.5.93.1.69	ItemReferenceReferenceCollection	478
3.2.5.93.1.70	CertificateFileLists	478
3.2.5.94	Microsoft.SharePoint.Client.MoveOperations	478
3.2.5.94.1	Field Values	478
3.2.5.94.1.1	None	478
3.2.5.94.1.2	Overwrite	478
3.2.5.94.1.3	AllowBrokenThickets	478
3.2.5.94.1.4	BypassApprovePermission	478
3.2.5.95	Microsoft.SharePoint.Client.Navigation	479
3.2.5.95.1	Properties	479
3.2.5.95.1.1	Scalar Properties	479
3.2.5.95.1.1.1	UseShared	479
3.2.5.95.1.2	ObjectPath Properties	479
3.2.5.95.1.2.1	QuickLaunch	479
3.2.5.95.1.2.2	TopNavigationBar	479
3.2.5.95.2	Methods	479
3.2.5.95.2.1	Scalar Methods	479
3.2.5.95.2.2	ObjectPath Methods	479
3.2.5.95.2.2.1	GetNodeById	479
3.2.5.96	Microsoft.SharePoint.Client.NavigationNode	480
3.2.5.96.1	Properties	480
3.2.5.96.1.1	Scalar Properties	480
3.2.5.96.1.1.1	Id	480
3.2.5.96.1.1.2	Title	480
3.2.5.96.1.1.3	Url	480
3.2.5.96.1.1.4	IsExternal	480
3.2.5.96.1.1.5	IsVisible	481
3.2.5.96.1.1.6	IsDocLib	481
3.2.5.96.1.1.7	ListTemplateType	481
3.2.5.96.1.2	ObjectPath Properties	481
3.2.5.96.1.2.1	Children	481
3.2.5.96.2	Methods	481
3.2.5.96.2.1	Scalar Methods	481
3.2.5.96.2.1.1	DeleteObject	481
3.2.5.96.2.1.2	Update	481
3.2.5.96.2.2	ObjectPath Methods	481
3.2.5.97	Microsoft.SharePoint.Client.NavigationNodeCollection	482
3.2.5.97.1	Properties	482
3.2.5.97.1.1	Scalar Properties	482
3.2.5.97.1.2	ObjectPath Properties	482
3.2.5.97.2	Methods	482
3.2.5.97.2.1	Scalar Methods	482
3.2.5.97.2.1.1	MoveAfter	482
3.2.5.97.2.2	ObjectPath Methods	482
3.2.5.97.2.2.1	Add	482



3.2.5.97.2.2.2	GetById .....	482
3.2.5.97.2.2.3	GetByIndex .....	483
3.2.5.98	Microsoft.SharePoint.Client.NavigationNodeCreationInformation .....	483
3.2.5.98.1	Properties.....	483
3.2.5.98.1.1	Scalar Properties.....	483
3.2.5.98.1.1.1	AsLastNode .....	483
3.2.5.98.1.1.2	IsExternal.....	483
3.2.5.98.1.1.3	Title.....	483
3.2.5.98.1.1.4	Url.....	484
3.2.5.98.1.2	ObjectPath Properties.....	484
3.2.5.98.1.2.1	PreviousNode.....	484
3.2.5.99	Microsoft.SharePoint.Client.PageType .....	484
3.2.5.99.1	Field Values .....	484
3.2.5.99.1.1	Invalid.....	484
3.2.5.99.1.2	DefaultView.....	484
3.2.5.99.1.3	NormalView.....	484
3.2.5.99.1.4	DialogView .....	484
3.2.5.99.1.5	View.....	484
3.2.5.99.1.6	DisplayForm.....	485
3.2.5.99.1.7	DisplayFormDialog .....	485
3.2.5.99.1.8	EditForm.....	485
3.2.5.99.1.9	EditFormDialog .....	485
3.2.5.99.1.10	NewForm .....	485
3.2.5.99.1.11	NewFormDialog .....	485
3.2.5.99.1.12	SolutionForm.....	485
3.2.5.99.1.13	PAGE_MAXITEMS .....	485
3.2.5.100	Microsoft.SharePoint.Client.Principal.....	485
3.2.5.100.1	Properties.....	486
3.2.5.100.1.1	Scalar Properties.....	486
3.2.5.100.1.1.1	Id.....	486
3.2.5.100.1.1.2	LoginName .....	486
3.2.5.100.1.1.3	PrincipalType .....	486
3.2.5.100.1.1.4	Title.....	486
3.2.5.100.1.1.5	IsHiddenInUI .....	486
3.2.5.100.1.2	ObjectPath Properties.....	486
3.2.5.100.2	Methods .....	486
3.2.5.100.2.1	Scalar Methods.....	486
3.2.5.100.2.2	ObjectPath Methods .....	487
3.2.5.101	Microsoft.SharePoint.Client.PropertyValues .....	487
3.2.5.101.1	Properties.....	487
3.2.5.101.1.1	Scalar Properties.....	487
3.2.5.101.1.2	ObjectPath Properties.....	487
3.2.5.101.2	Methods .....	487
3.2.5.101.2.1	Scalar Methods.....	487
3.2.5.101.2.1.1	SetFieldValue .....	487
3.2.5.101.2.2	ObjectPath Methods .....	487
3.2.5.102	Microsoft.SharePoint.Client.QuickLaunchOptions .....	487
3.2.5.102.1	Field Values .....	487
3.2.5.102.1.1	Off.....	487
3.2.5.102.1.2	On .....	488
3.2.5.102.1.3	DefaultValue .....	488
3.2.5.103	Microsoft.SharePoint.Client.RecycleBinItem .....	488
3.2.5.103.1	Properties.....	488
3.2.5.103.1.1	Scalar Properties.....	488
3.2.5.103.1.1.1	AuthorEmail.....	488
3.2.5.103.1.1.2	AuthorName .....	488
3.2.5.103.1.1.3	DeletedByEmail.....	488
3.2.5.103.1.1.4	DeletedByName .....	488

3.2.5.103.1.1.5	DeletedDate	489
3.2.5.103.1.1.6	DeletedDateLocalFormatted	489
3.2.5.103.1.1.7	DirName	489
3.2.5.103.1.1.8	DirNamePath	489
3.2.5.103.1.1.9	Id	489
3.2.5.103.1.1.10	ItemState	489
3.2.5.103.1.1.11	ItemType	490
3.2.5.103.1.1.12	LeafName	490
3.2.5.103.1.1.13	LeafNamePath	490
3.2.5.103.1.1.14	Size	490
3.2.5.103.1.1.15	Title	490
3.2.5.103.1.2	ObjectPath Properties	490
3.2.5.103.1.2.1	Author	490
3.2.5.103.1.2.2	DeletedBy	491
3.2.5.103.2	Methods	491
3.2.5.103.2.1	Scalar Methods	491
3.2.5.103.2.1.1	DeleteObject	491
3.2.5.103.2.1.2	MoveToSecondStage	491
3.2.5.103.2.1.3	Restore	491
3.2.5.103.2.2	ObjectPath Methods	491
3.2.5.104	Microsoft.SharePoint.Client.RecycleBinItemCollection	492
3.2.5.104.1	Properties	492
3.2.5.104.1.1	Scalar Properties	492
3.2.5.104.1.2	ObjectPath Properties	492
3.2.5.104.2	Methods	492
3.2.5.104.2.1	Scalar Methods	492
3.2.5.104.2.1.1	DeleteAll	492
3.2.5.104.2.1.2	DeleteAllSecondStageItems	492
3.2.5.104.2.1.3	MoveAllToSecondStage	492
3.2.5.104.2.1.4	RestoreAll	492
3.2.5.104.2.2	ObjectPath Methods	493
3.2.5.104.2.2.1	GetById	493
3.2.5.105	Microsoft.SharePoint.Client.RecycleBinItemState	493
3.2.5.105.1	Field Values	493
3.2.5.105.1.1	None	493
3.2.5.105.1.2	FirstStageRecycleBin	493
3.2.5.105.1.3	SecondStageRecycleBin	493
3.2.5.106	Microsoft.SharePoint.Client.RecycleBinItemType	493
3.2.5.106.1	Field Values	494
3.2.5.106.1.1	None	494
3.2.5.106.1.2	File	494
3.2.5.106.1.3	FileVersion	494
3.2.5.106.1.4	ListItem	494
3.2.5.106.1.5	List	494
3.2.5.106.1.6	Folder	494
3.2.5.106.1.7	FolderWithLists	494
3.2.5.106.1.8	Attachment	494
3.2.5.106.1.9	ListItemVersion	494
3.2.5.106.1.10	CascadeParent	495
3.2.5.106.1.11	Web	495
3.2.5.106.1.12	App	495
3.2.5.107	Microsoft.SharePoint.Client.RelatedField	495
3.2.5.107.1	Properties	495
3.2.5.107.1.1	Scalar Properties	495
3.2.5.107.1.1.1	FieldId	495
3.2.5.107.1.1.2	ListId	495
3.2.5.107.1.1.3	RelationshipDeleteBehavior	495
3.2.5.107.1.1.4	WebId	495

3.2.5.107.1.2	ObjectPath Properties	496
3.2.5.107.1.2.1	LookupList	496
3.2.5.107.2	Methods	496
3.2.5.107.2.1	Scalar Methods	496
3.2.5.107.2.2	ObjectPath Methods	496
3.2.5.108	Microsoft.SharePoint.Client.RelatedFieldCollection	496
3.2.5.108.1	Properties	496
3.2.5.108.1.1	Scalar Properties	496
3.2.5.108.1.2	ObjectPath Properties	496
3.2.5.108.2	Methods	496
3.2.5.108.2.1	Scalar Methods	496
3.2.5.108.2.2	ObjectPath Methods	496
3.2.5.108.2.2.1	GetByFieldId	496
3.2.5.109	Microsoft.SharePoint.Client.RelationshipDeleteBehaviorType	497
3.2.5.109.1	Field Values	497
3.2.5.109.1.1	None	497
3.2.5.109.1.2	Cascade	497
3.2.5.109.1.3	Restrict	497
3.2.5.110	Microsoft.SharePoint.Client.RequestContext	497
3.2.5.110.1	Properties	497
3.2.5.110.1.1	Scalar Properties	497
3.2.5.110.1.2	ObjectPath Properties	497
3.2.5.110.1.2.1	Current	497
3.2.5.110.1.2.2	List	498
3.2.5.110.1.2.3	Site	498
3.2.5.110.1.2.4	Web	498
3.2.5.110.2	Methods	498
3.2.5.110.2.1	Scalar Methods	498
3.2.5.110.2.2	ObjectPath Methods	498
3.2.5.110.2.2.1	GetRemoteContext	498
3.2.5.111	Microsoft.SharePoint.Client.RoleAssignment	498
3.2.5.111.1	Properties	498
3.2.5.111.1.1	Scalar Properties	498
3.2.5.111.1.1.1	PrincipalId	499
3.2.5.111.1.2	ObjectPath Properties	499
3.2.5.111.1.2.1	Member	499
3.2.5.111.1.2.2	RoleDefinitionBindings	499
3.2.5.111.2	Methods	499
3.2.5.111.2.1	Scalar Methods	499
3.2.5.111.2.1.1	DeleteObject	499
3.2.5.111.2.1.2	ImportRoleDefinitionBindings	499
3.2.5.111.2.1.3	Update	499
3.2.5.111.2.2	ObjectPath Methods	500
3.2.5.112	Microsoft.SharePoint.Client.RoleAssignmentCollection	500
3.2.5.112.1	Properties	500
3.2.5.112.1.1	Scalar Properties	500
3.2.5.112.1.2	ObjectPath Properties	500
3.2.5.112.1.2.1	Groups	500
3.2.5.112.2	Methods	500
3.2.5.112.2.1	Scalar Methods	500
3.2.5.112.2.1.1	AddRoleAssignment	500
3.2.5.112.2.1.2	RemoveRoleAssignment	500
3.2.5.112.2.2	ObjectPath Methods	501
3.2.5.112.2.2.1	Add	501
3.2.5.112.2.2.2	GetByPrincipal	501
3.2.5.112.2.2.3	GetByPrincipalId	501
3.2.5.113	Microsoft.SharePoint.Client.RoleDefinition	501
3.2.5.113.1	Properties	502

3.2.5.113.1.1	Scalar Properties.....	502
3.2.5.113.1.1.1	BasePermissions.....	502
3.2.5.113.1.1.2	Description .....	502
3.2.5.113.1.1.3	Hidden .....	502
3.2.5.113.1.1.4	Id .....	502
3.2.5.113.1.1.5	Name.....	503
3.2.5.113.1.1.6	Order .....	503
3.2.5.113.1.1.7	RoleTypeKind.....	503
3.2.5.113.1.2	ObjectPath Properties.....	503
3.2.5.113.2	Methods .....	503
3.2.5.113.2.1	Scalar Methods.....	504
3.2.5.113.2.1.1	DeleteObject.....	504
3.2.5.113.2.1.2	Update .....	504
3.2.5.113.2.2	ObjectPath Methods .....	504
3.2.5.114	Microsoft.SharePoint.Client.RoleDefinitionBindingCollection .....	504
3.2.5.114.1	Properties.....	504
3.2.5.114.1.1	Scalar Properties.....	504
3.2.5.114.1.2	ObjectPath Properties.....	504
3.2.5.114.2	Methods .....	504
3.2.5.114.2.1	Scalar Methods .....	505
3.2.5.114.2.1.1	Add .....	505
3.2.5.114.2.1.2	Remove .....	505
3.2.5.114.2.1.3	RemoveAll .....	505
3.2.5.114.2.2	ObjectPath Methods .....	505
3.2.5.114.2.2.1	GetById .....	505
3.2.5.114.2.2.2	CSOM Constructor .....	506
3.2.5.115	Microsoft.SharePoint.Client.RoleDefinitionCollection.....	506
3.2.5.115.1	Properties.....	506
3.2.5.115.1.1	Scalar Properties.....	506
3.2.5.115.1.2	ObjectPath Properties.....	506
3.2.5.115.2	Methods .....	506
3.2.5.115.2.1	Scalar Methods.....	506
3.2.5.115.2.1.1	RecreateMissingDefaultRoleDefinitions .....	506
3.2.5.115.2.2	ObjectPath Methods .....	506
3.2.5.115.2.2.1	Add .....	506
3.2.5.115.2.2.2	GetById .....	507
3.2.5.115.2.2.3	GetByName .....	507
3.2.5.115.2.2.4	GetByType.....	507
3.2.5.116	Microsoft.SharePoint.Client.RoleDefinitionCreationInformation .....	507
3.2.5.116.1	Properties.....	507
3.2.5.116.1.1	Scalar Properties.....	507
3.2.5.116.1.1.1	BasePermissions.....	508
3.2.5.116.1.1.2	Description .....	508
3.2.5.116.1.1.3	Name.....	508
3.2.5.116.1.1.4	Order .....	508
3.2.5.116.1.2	ObjectPath Properties.....	508
3.2.5.117	Microsoft.SharePoint.Client.RoleType.....	508
3.2.5.117.1	Field Values .....	508
3.2.5.117.1.1	None .....	508
3.2.5.117.1.2	Guest .....	509
3.2.5.117.1.3	Reader .....	509
3.2.5.117.1.4	Contributor .....	509
3.2.5.117.1.5	WebDesigner.....	509
3.2.5.117.1.6	Administrator .....	509
3.2.5.117.1.7	Editor .....	509
3.2.5.117.1.8	Reviewer .....	510
3.2.5.117.1.9	RestrictedReader .....	510
3.2.5.117.1.10	System.....	510

3.2.5.118	Microsoft.SharePoint.Client.SecurableObject	510
3.2.5.118.1	Properties	510
3.2.5.118.1.1	Scalar Properties	510
3.2.5.118.1.1.1	HasUniqueRoleAssignments	510
3.2.5.118.1.2	ObjectPath Properties	510
3.2.5.118.1.2.1	RoleAssignments	510
3.2.5.118.1.2.2	FirstUniqueAncestorSecurableObject	510
3.2.5.118.2	Methods	511
3.2.5.118.2.1	Scalar Methods	511
3.2.5.118.2.1.1	BreakRoleInheritance	511
3.2.5.118.2.1.2	ResetRoleInheritance	511
3.2.5.118.2.2	ObjectPath Methods	512
3.2.5.119	Microsoft.SharePoint.Client.Site	512
3.2.5.119.1	Properties	512
3.2.5.119.1.1	Scalar Properties	512
3.2.5.119.1.1.1	AllowDesigner	512
3.2.5.119.1.1.2	AllowMasterPageEditing	512
3.2.5.119.1.1.3	AllowRevertFromTemplate	512
3.2.5.119.1.1.4	Id	513
3.2.5.119.1.1.5	MaxItemsPerThrottledOperation	513
3.2.5.119.1.1.6	ServerRelativeUrl	513
3.2.5.119.1.1.7	ShowUrlStructure	513
3.2.5.119.1.1.8	UIVersionConfigurationEnabled	513
3.2.5.119.1.1.9	Url	513
3.2.5.119.1.1.10	Usage	513
3.2.5.119.1.1.11	CompatibilityLevel	514
3.2.5.119.1.1.12	LockIssue	514
3.2.5.119.1.1.13	ReadOnly	514
3.2.5.119.1.1.14	CanUpgrade	514
3.2.5.119.1.1.15	AllowSelfServiceUpgrade	514
3.2.5.119.1.1.16	AllowSelfServiceUpgradeEvaluation	514
3.2.5.119.1.1.17	PrimaryUri	514
3.2.5.119.1.1.18	UpgradeReminderDate	515
3.2.5.119.1.1.19	UpgradeInfo	515
3.2.5.119.1.1.20	Upgrading	515
3.2.5.119.1.1.21	ShareByLinkEnabled	515
3.2.5.119.1.1.22	AllowCreateDeclarativeWorkflow	515
3.2.5.119.1.1.23	AllowSaveDeclarativeWorkflowAsTemplate	515
3.2.5.119.1.1.24	AllowSavePublishDeclarativeWorkflow	516
3.2.5.119.1.1.25	RequiredDesignerVersion	516
3.2.5.119.1.1.26	AuditLogTrimmingRetention	516
3.2.5.119.1.1.27	CurrentChangeToken	516
3.2.5.119.1.1.28	ExternalSharingTipsEnabled	516
3.2.5.119.1.1.29	NeedsB2BUpgrade	516
3.2.5.119.1.1.30	SandboxedCodeActivationCapability	517
3.2.5.119.1.1.31	ShareByEmailEnabled	517
3.2.5.119.1.1.32	TrimAuditLog	517
3.2.5.119.1.1.33	UpgradeScheduled	517
3.2.5.119.1.1.34	UpgradeScheduledDate	517
3.2.5.119.1.1.35	DisableCompanyWideSharingLinks	517
3.2.5.119.1.1.36	Classification	517
3.2.5.119.1.1.37	CommentsOnSitePagesDisabled	518
3.2.5.119.1.1.38	ResourcePath	518
3.2.5.119.1.1.39	ServerRelativePath	518
3.2.5.119.1.1.40	ShowPeoplePickerSuggestionsForGuestUsers	518
3.2.5.119.1.1.41	StatusBarLink	518
3.2.5.119.1.1.42	StatusBarText	518
3.2.5.119.1.1.43	ThicketSupportDisabled	518

3.2.5.119.1.2	ObjectPath Properties	518
3.2.5.119.1.2.1	Features	518
3.2.5.119.1.2.2	RecycleBin	519
3.2.5.119.1.2.3	RootWeb	519
3.2.5.119.1.2.4	UserCustomActions	519
3.2.5.119.1.2.5	Owner	519
3.2.5.119.1.2.6	EventReceivers	519
3.2.5.119.1.2.7	Audit	519
3.2.5.119.1.2.8	SecondaryContact	519
3.2.5.119.2	Methods	520
3.2.5.119.2.1	Scalar Methods	520
3.2.5.119.2.1.1	CreateMigrationJob	520
3.2.5.119.2.1.2	CreatePreviewSPSite	520
3.2.5.119.2.1.3	DeleteMigrationJob	521
3.2.5.119.2.1.4	Exists	521
3.2.5.119.2.1.5	ExtendUpgradeReminderDate	521
3.2.5.119.2.1.6	GetMigrationJobStatus	521
3.2.5.119.2.1.7	GetWebPath	522
3.2.5.119.2.1.8	Invalidate	522
3.2.5.119.2.1.9	NeedsUpgradeByType	522
3.2.5.119.2.1.10	RunUpgradeSiteSession	522
3.2.5.119.2.1.11	UpdateClientObjectModelUseRemoteAPIsPermissionSetting	523
3.2.5.119.2.2	ObjectPath Methods	523
3.2.5.119.2.2.1	GetCatalog	523
3.2.5.119.2.2.2	GetChanges	523
3.2.5.119.2.2.3	GetCustomListTemplates	524
3.2.5.119.2.2.4	OpenWeb	524
3.2.5.119.2.2.5	OpenWebById	524
3.2.5.119.2.2.6	GetWebTemplates	524
3.2.5.119.2.2.7	RunHealthCheck	524
3.2.5.119.2.2.8	GetMigrationStatus	525
3.2.5.119.2.2.9	GetRecycleBinItems	525
3.2.5.119.2.2.10	OpenWebUsingPath	526
3.2.5.120	Microsoft.SharePoint.Client.SubwebQuery	526
3.2.5.120.1	Properties	526
3.2.5.120.1.1	Scalar Properties	526
3.2.5.120.1.1.1	ConfigurationFilter	527
3.2.5.120.1.1.2	WebTemplateFilter	527
3.2.5.120.1.2	ObjectPath Properties	527
3.2.5.121	Microsoft.SharePoint.Client.TemplateFileType	527
3.2.5.121.1	Field Values	527
3.2.5.121.1.1	StandardPage	527
3.2.5.121.1.2	WikiPage	527
3.2.5.121.1.3	FormPage	527
3.2.5.121.1.4	Invalid	527
3.2.5.121.1.5	ClientSidePage	527
3.2.5.122	Microsoft.SharePoint.Client.UrlFieldFormatType	528
3.2.5.122.1	Field Values	528
3.2.5.122.1.1	Hyperlink	528
3.2.5.122.1.2	Image	528
3.2.5.123	Microsoft.SharePoint.Client.UsageInfo	528
3.2.5.123.1	Properties	528
3.2.5.123.1.1	Scalar Properties	528
3.2.5.123.1.1.1	Bandwidth	528
3.2.5.123.1.1.2	DiscussionStorage	528
3.2.5.123.1.1.3	Hits	529
3.2.5.123.1.1.4	Storage	529
3.2.5.123.1.1.5	StoragePercentageUsed	529

3.2.5.123.1.1.6	Visits .....	529
3.2.5.123.1.2	ObjectPath Properties .....	529
3.2.5.124	Microsoft.SharePoint.Client.User .....	529
3.2.5.124.1	Properties .....	529
3.2.5.124.1.1	Scalar Properties .....	530
3.2.5.124.1.1.1	Email .....	530
3.2.5.124.1.1.2	Id .....	530
3.2.5.124.1.1.3	LoginName .....	530
3.2.5.124.1.1.4	PrincipalType .....	531
3.2.5.124.1.1.5	Title .....	531
3.2.5.124.1.1.6	IsSiteAdmin .....	531
3.2.5.124.1.1.7	IsHiddenInUI .....	531
3.2.5.124.1.1.8	UserId .....	531
3.2.5.124.1.1.9	IsShareByEmailGuestUser .....	532
3.2.5.124.1.1.10	IsEmailAuthenticationGuestUser .....	532
3.2.5.124.1.2	ObjectPath Properties .....	532
3.2.5.124.1.2.1	Groups .....	532
3.2.5.124.1.2.2	Alerts .....	532
3.2.5.124.2	Methods .....	532
3.2.5.124.2.1	Scalar Methods .....	532
3.2.5.124.2.1.1	Update .....	532
3.2.5.124.2.2	ObjectPath Methods .....	533
3.2.5.125	Microsoft.SharePoint.Client.UserCollection .....	533
3.2.5.125.1	Properties .....	533
3.2.5.125.1.1	Scalar Properties .....	533
3.2.5.125.1.2	ObjectPath Properties .....	533
3.2.5.125.2	Methods .....	533
3.2.5.125.2.1	Scalar Methods .....	533
3.2.5.125.2.1.1	Remove .....	533
3.2.5.125.2.1.2	RemoveById .....	533
3.2.5.125.2.1.3	RemoveByLoginName .....	533
3.2.5.125.2.2	ObjectPath Methods .....	534
3.2.5.125.2.2.1	Add .....	534
3.2.5.125.2.2.2	AddUser .....	534
3.2.5.125.2.2.3	GetByEmail .....	534
3.2.5.125.2.2.4	GetById .....	535
3.2.5.125.2.2.5	GetByLoginName .....	535
3.2.5.126	Microsoft.SharePoint.Client.UserCreationInformation .....	535
3.2.5.126.1	Properties .....	535
3.2.5.126.1.1	Scalar Properties .....	535
3.2.5.126.1.1.1	Email .....	535
3.2.5.126.1.1.2	LoginName .....	535
3.2.5.126.1.1.3	Title .....	536
3.2.5.126.1.2	ObjectPath Properties .....	536
3.2.5.127	Microsoft.SharePoint.Client.UserCustomAction .....	536
3.2.5.127.1	Properties .....	536
3.2.5.127.1.1	Scalar Properties .....	536
3.2.5.127.1.1.1	ClientSideComponentId .....	536
3.2.5.127.1.1.2	ClientSideComponentProperties .....	536
3.2.5.127.1.1.3	CommandUIExtension .....	536
3.2.5.127.1.1.4	Description .....	537
3.2.5.127.1.1.5	Group .....	537
3.2.5.127.1.1.6	Id .....	537
3.2.5.127.1.1.7	ImageUrl .....	537
3.2.5.127.1.1.8	Location .....	537
3.2.5.127.1.1.9	Name .....	537
3.2.5.127.1.1.10	RegistrationId .....	537
3.2.5.127.1.1.11	RegistrationType .....	538

3.2.5.127.1.1.12	Rights	538
3.2.5.127.1.1.13	Scope	538
3.2.5.127.1.1.14	ScriptBlock	538
3.2.5.127.1.1.15	ScriptSrc	538
3.2.5.127.1.1.16	Sequence	539
3.2.5.127.1.1.17	Title	539
3.2.5.127.1.1.18	Url	539
3.2.5.127.1.1.19	VersionOfUserCustomAction	539
3.2.5.127.1.2	ObjectPath Properties	539
3.2.5.127.1.2.1	DescriptionResource	539
3.2.5.127.1.2.2	TitleResource	539
3.2.5.127.2	Methods	539
3.2.5.127.2.1	Scalar Methods	540
3.2.5.127.2.1.1	DeleteObject	540
3.2.5.127.2.1.2	Update	540
3.2.5.127.2.2	ObjectPath Methods	540
3.2.5.128	Microsoft.SharePoint.Client.UserCustomActionCollection	540
3.2.5.128.1	Properties	540
3.2.5.128.1.1	Scalar Properties	540
3.2.5.128.1.2	ObjectPath Properties	540
3.2.5.128.2	Methods	541
3.2.5.128.2.1	Scalar Methods	541
3.2.5.128.2.1.1	Clear	541
3.2.5.128.2.2	ObjectPath Methods	541
3.2.5.128.2.2.1	Add	541
3.2.5.128.2.2.2	GetById	541
3.2.5.129	Microsoft.SharePoint.Client.UserCustomActionRegistrationType	541
3.2.5.129.1	Field Values	541
3.2.5.129.1.1	None	541
3.2.5.129.1.2	List	542
3.2.5.129.1.3	ContentType	542
3.2.5.129.1.4	ProgId	542
3.2.5.129.1.5	FileType	542
3.2.5.130	Microsoft.SharePoint.Client.UserCustomActionScope	542
3.2.5.130.1	Field Values	542
3.2.5.130.1.1	Unknown	542
3.2.5.130.1.2	Site	542
3.2.5.130.1.3	Web	542
3.2.5.130.1.4	List	542
3.2.5.131	Microsoft.SharePoint.Client.Utilities.DateTimeFormat	543
3.2.5.131.1	Field Values	543
3.2.5.131.1.1	DateTime	543
3.2.5.131.1.2	DateOnly	543
3.2.5.131.1.3	TimeOnly	543
3.2.5.131.1.4	ISO8601	543
3.2.5.131.1.5	MonthDayOnly	543
3.2.5.131.1.6	MonthYearOnly	543
3.2.5.131.1.7	LongDate	543
3.2.5.131.1.8	UnknownFormat	543
3.2.5.132	Microsoft.SharePoint.Client.Utilities.IconSize	544
3.2.5.132.1	Field Values	544
3.2.5.132.1.1	Size16	544
3.2.5.132.1.2	Size32	544
3.2.5.132.1.3	Size256	544
3.2.5.133	Microsoft.SharePoint.Client.Utilities.PrincipalInfo	544
3.2.5.133.1	Properties	544
3.2.5.133.1.1	Scalar Properties	544
3.2.5.133.1.1.1	Department	544



3.2.5.133.1.1.2	DisplayName	544
3.2.5.133.1.1.3	Email	545
3.2.5.133.1.1.4	JobTitle	545
3.2.5.133.1.1.5	LoginName	545
3.2.5.133.1.1.6	Mobile	545
3.2.5.133.1.1.7	PrincipalId	545
3.2.5.133.1.1.8	PrincipalType	545
3.2.5.133.1.1.9	SIPAddress	545
3.2.5.133.1.2	ObjectPath Properties	546
3.2.5.134	Microsoft.SharePoint.Client.Utilities.PrincipalSource	546
3.2.5.134.1	Field Values	546
3.2.5.134.1.1	None	546
3.2.5.134.1.2	UserInfoList	546
3.2.5.134.1.3	Windows	546
3.2.5.134.1.4	MembershipProvider	546
3.2.5.134.1.5	RoleProvider	546
3.2.5.134.1.6	All	546
3.2.5.135	Microsoft.SharePoint.Client.Utilities.PrincipalType	546
3.2.5.135.1	Field Values	547
3.2.5.135.1.1	None	547
3.2.5.135.1.2	User	547
3.2.5.135.1.3	DistributionList	547
3.2.5.135.1.4	SecurityGroup	547
3.2.5.135.1.5	SharePointGroup	547
3.2.5.135.1.6	All	547
3.2.5.136	Microsoft.SharePoint.Client.Utilities.Utility	547
3.2.5.136.1	Properties	547
3.2.5.136.1.1	Scalar Properties	547
3.2.5.136.1.2	ObjectPath Properties	547
3.2.5.136.2	Methods	548
3.2.5.136.2.1	Scalar Methods	548
3.2.5.136.2.1.1	CreateEmailBodyForInvitation	548
3.2.5.136.2.1.2	FormatDateTime	548
3.2.5.136.2.1.3	GetCurrentUserEmailAddresses	548
3.2.5.136.2.1.4	ResolvePrincipal	548
3.2.5.136.2.1.5	SearchPrincipals	549
3.2.5.136.2.1.6	GetPeoplePickerURL	550
3.2.5.136.2.1.7	ResolvePrincipalInCurrentContext	550
3.2.5.136.2.1.8	MarkDiscussionAsFeatured	551
3.2.5.136.2.1.9	UnmarkDiscussionAsFeatured	552
3.2.5.136.2.1.10	SendEmail	552
3.2.5.136.2.1.11	LogCustomAppError	553
3.2.5.136.2.1.12	GetAppLicenseInformation	553
3.2.5.136.2.1.13	IsUserLicensedForEntityInContext	553
3.2.5.136.2.1.14	GetAppLicenseDeploymentId	554
3.2.5.136.2.1.15	ImportAppLicense	554
3.2.5.136.2.1.16	SearchPrincipalsUsingContextWeb	555
3.2.5.136.2.1.17	GetLocalizedString	556
3.2.5.136.2.1.18	GetLowerCaseString	556
3.2.5.136.2.1.19	LogCustomRemoteAppError	556
3.2.5.136.2.1.20	ExpandGroupsToPrincipals	557
3.2.5.136.2.1.21	GetUserPermissionLevels	557
3.2.5.136.2.1.22	IsEmailServerSet	557
3.2.5.136.2.2	ObjectPath Methods	558
3.2.5.136.2.2.1	CreateNewDiscussion	558
3.2.5.136.2.2.2	CreateNewDiscussionReply	558
3.2.5.136.2.2.3	CreateNewDiscussionItem	558
3.2.5.136.2.2.4	CreateWikiPageInContextWeb	559

3.2.5.136.2.2.5	LocalizeWebPartGallery .....	559
3.2.5.137	Microsoft.SharePoint.Client.View .....	559
3.2.5.137.1	Properties.....	559
3.2.5.137.1.1	Scalar Properties.....	559
3.2.5.137.1.1.1	Aggregations .....	559
3.2.5.137.1.1.2	AggregationsStatus .....	560
3.2.5.137.1.1.3	BaseViewId.....	560
3.2.5.137.1.1.4	ContentTypeId .....	560
3.2.5.137.1.1.5	DefaultView .....	560
3.2.5.137.1.1.6	DefaultViewForContentType .....	560
3.2.5.137.1.1.7	EditorModified .....	560
3.2.5.137.1.1.8	Formats .....	560
3.2.5.137.1.1.9	Hidden .....	561
3.2.5.137.1.1.10	HtmlSchemaXml.....	561
3.2.5.137.1.1.11	Id.....	561
3.2.5.137.1.1.12	ImageUrl.....	561
3.2.5.137.1.1.13	IncludeRootFolder .....	561
3.2.5.137.1.1.14	Method .....	561
3.2.5.137.1.1.15	MobileDefaultView .....	562
3.2.5.137.1.1.16	MobileView .....	562
3.2.5.137.1.1.17	ModerationType .....	562
3.2.5.137.1.1.18	OrderedView .....	562
3.2.5.137.1.1.19	Paged .....	562
3.2.5.137.1.1.20	PersonalView .....	562
3.2.5.137.1.1.21	ReadOnlyView.....	562
3.2.5.137.1.1.22	RequiresClientIntegration .....	563
3.2.5.137.1.1.23	RowLimit.....	563
3.2.5.137.1.1.24	Scope .....	563
3.2.5.137.1.1.25	ServerRelativeUrl .....	563
3.2.5.137.1.1.26	StyleId.....	563
3.2.5.137.1.1.27	Threaded.....	563
3.2.5.137.1.1.28	Title.....	563
3.2.5.137.1.1.29	Toolbar .....	564
3.2.5.137.1.1.30	ToolbarTemplateName .....	564
3.2.5.137.1.1.31	ViewData.....	564
3.2.5.137.1.1.32	ViewJoins .....	564
3.2.5.137.1.1.33	ViewProjectedFields .....	564
3.2.5.137.1.1.34	ViewQuery.....	565
3.2.5.137.1.1.35	ViewType .....	565
3.2.5.137.1.1.36	ListViewXml .....	565
3.2.5.137.1.1.37	JSLink.....	565
3.2.5.137.1.1.38	ColumnWidth .....	565
3.2.5.137.1.1.39	CustomFormatter .....	565
3.2.5.137.1.1.40	PageRenderType .....	566
3.2.5.137.1.1.41	ServerRelativePath .....	566
3.2.5.137.1.1.42	TabularView.....	566
3.2.5.137.1.1.43	VisualizationInfo.....	566
3.2.5.137.1.2	ObjectPath Properties .....	566
3.2.5.137.1.2.1	ViewFields .....	566
3.2.5.137.2	Methods.....	566
3.2.5.137.2.1	Scalar Methods.....	566
3.2.5.137.2.1.1	DeleteObject.....	566
3.2.5.137.2.1.2	RenderAsHtml .....	567
3.2.5.137.2.1.3	SetViewXml .....	567
3.2.5.137.2.1.4	Update.....	567
3.2.5.137.2.2	ObjectPath Methods .....	567
3.2.5.137.2.2.1	AddToSpotlight .....	567
3.2.5.137.2.2.2	RemoveFromSpotlight.....	568

3.2.5.138	Microsoft.SharePoint.Client.ViewCollection	568
3.2.5.138.1	Properties	568
3.2.5.138.1.1	Scalar Properties	568
3.2.5.138.1.2	ObjectPath Properties	568
3.2.5.138.2	Methods	568
3.2.5.138.2.1	Scalar Methods	568
3.2.5.138.2.2	ObjectPath Methods	568
3.2.5.138.2.2.1	Add	568
3.2.5.138.2.2.2	GetById	569
3.2.5.138.2.2.3	GetByTitle	569
3.2.5.139	Microsoft.SharePoint.Client.ViewCreationInformation	569
3.2.5.139.1	Properties	569
3.2.5.139.1.1	Scalar Properties	569
3.2.5.139.1.1.1	baseViewId	569
3.2.5.139.1.1.2	Paged	570
3.2.5.139.1.1.3	PersonalView	570
3.2.5.139.1.1.4	Query	570
3.2.5.139.1.1.5	RowLimit	570
3.2.5.139.1.1.6	SetAsDefaultView	570
3.2.5.139.1.1.7	Title	570
3.2.5.139.1.1.8	ViewFields	571
3.2.5.139.1.1.9	ViewTypeKind	571
3.2.5.139.1.2	ObjectPath Properties	571
3.2.5.140	Microsoft.SharePoint.Client.ViewFieldCollection	571
3.2.5.140.1	Properties	571
3.2.5.140.1.1	Scalar Properties	571
3.2.5.140.1.1.1	SchemaXml	571
3.2.5.140.1.2	ObjectPath Properties	571
3.2.5.140.2	Methods	571
3.2.5.140.2.1	Scalar Methods	571
3.2.5.140.2.1.1	Add	571
3.2.5.140.2.1.2	MoveFieldTo	572
3.2.5.140.2.1.3	Remove	572
3.2.5.140.2.1.4	RemoveAll	572
3.2.5.140.2.1.5	AddViewField	573
3.2.5.140.2.1.6	MoveViewFieldTo	573
3.2.5.140.2.1.7	RemoveAllViewFields	573
3.2.5.140.2.1.8	RemoveViewField	573
3.2.5.140.2.2	ObjectPath Methods	574
3.2.5.141	Microsoft.SharePoint.Client.ViewScope	574
3.2.5.141.1	Field Values	574
3.2.5.141.1.1	DefaultValue	574
3.2.5.141.1.2	Recursive	574
3.2.5.141.1.3	RecursiveAll	574
3.2.5.141.1.4	FilesOnly	574
3.2.5.142	Microsoft.SharePoint.Client.ViewType	574
3.2.5.142.1	Field Values	574
3.2.5.142.1.1	None	574
3.2.5.142.1.2	Html	575
3.2.5.142.1.3	Grid	575
3.2.5.142.1.4	Calendar	575
3.2.5.142.1.5	Recurrence	575
3.2.5.142.1.6	Chart	575
3.2.5.142.1.7	Gantt	575
3.2.5.143	Microsoft.SharePoint.Client.Web	575
3.2.5.143.1	Properties	575
3.2.5.143.1.1	Scalar Properties	576
3.2.5.143.1.1.1	AllowDesignerForCurrentUser	576

3.2.5.143.1.1.2	AllowMasterPageEditingForCurrentUser	576
3.2.5.143.1.1.3	AllowRevertFromTemplateForCurrentUser	576
3.2.5.143.1.1.4	AllowRssFeeds	576
3.2.5.143.1.1.5	Created	576
3.2.5.143.1.1.6	Description	576
3.2.5.143.1.1.7	EffectiveBasePermissions	576
3.2.5.143.1.1.8	HasUniqueRoleAssignments	577
3.2.5.143.1.1.9	Id	577
3.2.5.143.1.1.10	Language	577
3.2.5.143.1.1.11	LastItemModifiedDate	577
3.2.5.143.1.1.12	QuickLaunchEnabled	577
3.2.5.143.1.1.13	RecycleBinEnabled	577
3.2.5.143.1.1.14	ServerRelativeUrl	578
3.2.5.143.1.1.15	ShowUrlStructureForCurrentUser	578
3.2.5.143.1.1.16	SyndicationEnabled	578
3.2.5.143.1.1.17	Title	578
3.2.5.143.1.1.18	TreeViewEnabled	578
3.2.5.143.1.1.19	UIVersion	578
3.2.5.143.1.1.20	UIVersionConfigurationEnabled	579
3.2.5.143.1.1.21	EnableMinimalDownload	579
3.2.5.143.1.1.22	Url	579
3.2.5.143.1.1.23	CustomMasterUrl	579
3.2.5.143.1.1.24	MasterUrl	579
3.2.5.143.1.1.25	AppInstanceId	579
3.2.5.143.1.1.26	DocumentLibraryCalloutOfficeWebAppPreviewersDisabled	580
3.2.5.143.1.1.27	Configuration	580
3.2.5.143.1.1.28	WebTemplate	580
3.2.5.143.1.1.29	SaveSiteAsTemplateEnabled	580
3.2.5.143.1.1.30	SupportedUILanguageIds	580
3.2.5.143.1.1.31	AllowCreateDeclarativeWorkflowForCurrentUser	581
3.2.5.143.1.1.32	AllowSaveDeclarativeWorkflowAsTemplateForCurrentUser	581
3.2.5.143.1.1.33	AllowSavePublishDeclarativeWorkflowForCurrentUser	581
3.2.5.143.1.1.34	DesignerDownloadUrlForCurrentUser	581
3.2.5.143.1.1.35	MembersCanShare	581
3.2.5.143.1.1.36	SiteLogoUrl	581
3.2.5.143.1.1.37	AlternateCssUrl	581
3.2.5.143.1.1.38	ContainsConfidentialInfo	582
3.2.5.143.1.1.39	CurrentChangeToken	582
3.2.5.143.1.1.40	IsMultilingual	582
3.2.5.143.1.1.41	OverwriteTranslationsOnChange	582
3.2.5.143.1.1.42	ThemeData	582
3.2.5.143.1.1.43	ThirdPartyMdmEnabled	582
3.2.5.143.1.1.44	RequestAccessEmail	583
3.2.5.143.1.1.45	AllowAutomaticASPXPageIndexing	583
3.2.5.143.1.1.46	CommentsOnSitePagesDisabled	583
3.2.5.143.1.1.47	DesignPackageId	583
3.2.5.143.1.1.48	ExcludeFromOfflineClient	583
3.2.5.143.1.1.49	LastItemUserModifiedDate	583
3.2.5.143.1.1.50	NoCrawl	583
3.2.5.143.1.1.51	NotificationsInOneDriveForBusinessEnabled	584
3.2.5.143.1.1.52	NotificationsInSharePointEnabled	584
3.2.5.143.1.1.53	PreviewFeaturesEnabled	584
3.2.5.143.1.1.54	ResourcePath	584
3.2.5.143.1.1.55	ServerRelativePath	584
3.2.5.143.1.1.56	SiteLogoDescription	584
3.2.5.143.1.1.57	ThemedCssFolderUrl	584
3.2.5.143.1.1.58	WelcomePage	585
3.2.5.143.1.2	ObjectPath Properties	585

3.2.5.143.1.2.1	AllProperties	585
3.2.5.143.1.2.2	AssociatedMemberGroup	585
3.2.5.143.1.2.3	AssociatedOwnerGroup	585
3.2.5.143.1.2.4	AssociatedVisitorGroup	585
3.2.5.143.1.2.5	AvailableContentTypes	585
3.2.5.143.1.2.6	AvailableFields	586
3.2.5.143.1.2.7	ContentTypes	586
3.2.5.143.1.2.8	CurrentUser	586
3.2.5.143.1.2.9	Features	586
3.2.5.143.1.2.10	Fields	586
3.2.5.143.1.2.11	Folders	587
3.2.5.143.1.2.12	Lists	587
3.2.5.143.1.2.13	ListTemplates	587
3.2.5.143.1.2.14	Navigation	587
3.2.5.143.1.2.15	RoleAssignments	587
3.2.5.143.1.2.16	RoleDefinitions	587
3.2.5.143.1.2.17	RootFolder	588
3.2.5.143.1.2.18	SiteGroups	588
3.2.5.143.1.2.19	SiteUserInfoList	588
3.2.5.143.1.2.20	UserCustomActions	588
3.2.5.143.1.2.21	Webs	588
3.2.5.143.1.2.22	WorkflowAssociations	588
3.2.5.143.1.2.23	WorkflowTemplates	588
3.2.5.143.1.2.24	FirstUniqueAncestorSecurableObject	588
3.2.5.143.1.2.25	RecycleBin	589
3.2.5.143.1.2.26	WebInfos	589
3.2.5.143.1.2.27	ThemeInfo	589
3.2.5.143.1.2.28	EventReceivers	589
3.2.5.143.1.2.29	SiteUsers	589
3.2.5.143.1.2.30	RegionalSettings	589
3.2.5.143.1.2.31	PushNotificationSubscribers	589
3.2.5.143.1.2.32	ParentWeb	590
3.2.5.143.1.2.33	AppTiles	590
3.2.5.143.1.2.34	DataLeakagePreventionStatusInfo	590
3.2.5.143.1.2.35	DescriptionResource	590
3.2.5.143.1.2.36	TitleResource	590
3.2.5.143.1.2.37	Alerts	591
3.2.5.143.1.2.38	Author	591
3.2.5.143.1.2.39	BingMapsInformation	591
3.2.5.143.1.2.40	ClientWebParts	591
3.2.5.143.1.2.41	SiteCollectionAppCatalog	591
3.2.5.143.1.2.42	TenantAppCatalog	591
3.2.5.143.2	Methods	591
3.2.5.143.2.1	Scalar Methods	591
3.2.5.143.2.1.1	ApplyWebTemplate	592
3.2.5.143.2.1.2	BreakRoleInheritance	592
3.2.5.143.2.1.3	DeleteObject	592
3.2.5.143.2.1.4	DoesUserHavePermissions	592
3.2.5.143.2.1.5	GetWebUrlFromPageUrl	593
3.2.5.143.2.1.6	MapToIcon	593
3.2.5.143.2.1.7	ResetRoleInheritance	593
3.2.5.143.2.1.8	Update	594
3.2.5.143.2.1.9	ProcessExternalNotification	594
3.2.5.143.2.1.10	GetContextWebInformation	594
3.2.5.143.2.1.11	ExecuteRemoteLOB	594
3.2.5.143.2.1.12	DoesPushNotificationSubscriberExist	595
3.2.5.143.2.1.13	UnregisterPushNotificationSubscriber	595
3.2.5.143.2.1.14	ApplyTheme	595

3.2.5.143.2.1.15	GetUserEffectivePermissions	596
3.2.5.143.2.1.16	AddSupportedUILanguage	596
3.2.5.143.2.1.17	CreateAnonymousLink	596
3.2.5.143.2.1.18	CreateAnonymousLinkWithExpiration	597
3.2.5.143.2.1.19	CreateOrganizationSharingLink	598
3.2.5.143.2.1.20	DeleteAllAnonymousLinksForObject	598
3.2.5.143.2.1.21	DeleteAnonymousLinkForObject	598
3.2.5.143.2.1.22	DestroyOrganizationSharingLink	599
3.2.5.143.2.1.23	GetContextWebThemeData	599
3.2.5.143.2.1.24	GetDocumentLibraries	600
3.2.5.143.2.1.25	IncrementSiteClientTag	600
3.2.5.143.2.1.26	RemoveSupportedUILanguage	600
3.2.5.143.2.1.27	GetClientSideWebParts	600
3.2.5.143.2.1.28	CreateDefaultAssociatedGroups	601
3.2.5.143.2.1.29	DefaultDocumentLibraryUrl	601
3.2.5.143.2.1.30	GetClientSideComponents	601
3.2.5.143.2.1.31	GetClientSideComponentsById	601
3.2.5.143.2.1.32	GetDocumentAndMediaLibraries	602
3.2.5.143.2.1.33	GetOnePageContextAsStream	602
3.2.5.143.2.1.34	GetRegionalDateTimeSchema	602
3.2.5.143.2.1.35	GetSharingLinkData	602
3.2.5.143.2.1.36	GetSharingLinkKind	603
3.2.5.143.2.1.37	ParseDateTime	603
3.2.5.143.2.1.38	RemoveStorageEntity	603
3.2.5.143.2.1.39	SetStorageEntity	603
3.2.5.143.2.2	ObjectPath Methods	604
3.2.5.143.2.2.1	EnsureUser	604
3.2.5.143.2.2.2	GetAvailableWebTemplates	604
3.2.5.143.2.2.3	GetCatalog	604
3.2.5.143.2.2.4	GetChanges	605
3.2.5.143.2.2.5	GetFileByServerRelativeUrl	605
3.2.5.143.2.2.6	GetFolderByServerRelativeUrl	605
3.2.5.143.2.2.7	GetSubwebsForCurrentUser	606
3.2.5.143.2.2.8	GetEntity	606
3.2.5.143.2.2.9	GetUserById	606
3.2.5.143.2.2.10	GetCustomListTemplates	607
3.2.5.143.2.2.11	GetSubwebsFilteredForCurrentUser	607
3.2.5.143.2.2.12	GetAppBdcCatalog	607
3.2.5.143.2.2.13	GetAppBdcCatalogForAppInstance	607
3.2.5.143.2.2.14	GetAppInstanceById	608
3.2.5.143.2.2.15	LoadAndInstallApp	608
3.2.5.143.2.2.16	GetPushNotificationSubscriber	608
3.2.5.143.2.2.17	GetPushNotificationSubscribersByArgs	609
3.2.5.143.2.2.18	GetPushNotificationSubscribersByUser	609
3.2.5.143.2.2.19	RegisterPushNotificationSubscriber	609
3.2.5.143.2.2.20	GetAppInstancesByProductId	610
3.2.5.143.2.2.21	LoadAndInstallAppInSpecifiedLocale	610
3.2.5.143.2.2.22	LoadApp	610
3.2.5.143.2.2.23	DefaultDocumentLibrary	611
3.2.5.143.2.2.24	ForwardObjectLink	611
3.2.5.143.2.2.25	GetFileByGuestUrl	611
3.2.5.143.2.2.26	GetFileById	612
3.2.5.143.2.2.27	GetFileByLinkingUrl	612
3.2.5.143.2.2.28	GetFolderById	612
3.2.5.143.2.2.29	GetList	613
3.2.5.143.2.2.30	GetObjectSharingSettings	613
3.2.5.143.2.2.31	ShareObject	613
3.2.5.143.2.2.32	UnshareObject	614

3.2.5.143.2.2.33	GetRecycleBinItems	614
3.2.5.143.2.2.34	GetFileByGuestUrlEnsureAccess	615
3.2.5.143.2.2.35	GetFileByGuestUrlExtended	616
3.2.5.143.2.2.36	GetFileByServerRelativePath	616
3.2.5.143.2.2.37	GetFileByUrl	616
3.2.5.143.2.2.38	GetFileByWOPIFrameUrl	616
3.2.5.143.2.2.39	GetFolderByGuestUrl	617
3.2.5.143.2.2.40	GetFolderByGuestUrlExtended	617
3.2.5.143.2.2.41	GetFolderByServerRelativePath	617
3.2.5.143.2.2.42	GetListItem	618
3.2.5.143.2.2.43	GetListItemByResourceId	618
3.2.5.143.2.2.44	GetListItemUsingPath	618
3.2.5.143.2.2.45	GetListUsingPath	618
3.2.5.143.2.2.46	GetNewsList	619
3.2.5.143.2.2.47	GetRecycleBinItemsByQueryInfo	619
3.2.5.143.2.2.48	GetStorageEntity	619
3.2.5.143.2.2.49	GetViewFromPath	619
3.2.5.143.2.2.50	GetViewFromUrl	619
3.2.5.144	Microsoft.SharePoint.Client.WebCollection	620
3.2.5.144.1	Properties	620
3.2.5.144.1.1	Scalar Properties	620
3.2.5.144.1.2	ObjectPath Properties	620
3.2.5.144.2	Methods	620
3.2.5.144.2.1	Scalar Methods	620
3.2.5.144.2.2	ObjectPath Methods	620
3.2.5.144.2.2.1	Add	620
3.2.5.145	Microsoft.SharePoint.Client.WebCreationInformation	620
3.2.5.145.1	Properties	621
3.2.5.145.1.1	Scalar Properties	621
3.2.5.145.1.1.1	Description	621
3.2.5.145.1.1.2	Language	621
3.2.5.145.1.1.3	Title	621
3.2.5.145.1.1.4	Url	621
3.2.5.145.1.1.5	UseSamePermissionsAsParentSite	621
3.2.5.145.1.1.6	WebTemplate	621
3.2.5.145.1.2	ObjectPath Properties	622
3.2.5.146	Microsoft.SharePoint.Client.WebParts.LimitedWebPartManager	622
3.2.5.146.1	Properties	622
3.2.5.146.1.1	Scalar Properties	622
3.2.5.146.1.1.1	HasPersonalizedParts	622
3.2.5.146.1.1.2	Scope	622
3.2.5.146.1.2	ObjectPath Properties	622
3.2.5.146.1.2.1	WebParts	622
3.2.5.146.2	Methods	622
3.2.5.146.2.1	Scalar Methods	623
3.2.5.146.2.1.1	ExportWebPart	623
3.2.5.146.2.2	ObjectPath Methods	623
3.2.5.146.2.2.1	AddWebPart	623
3.2.5.146.2.2.2	ImportWebPart	623
3.2.5.147	Microsoft.SharePoint.Client.WebParts.PersonalizationScope	624
3.2.5.147.1	Field Values	624
3.2.5.147.1.1	User	624
3.2.5.147.1.2	Shared	624
3.2.5.148	Microsoft.SharePoint.Client.WebParts.WebPart	625
3.2.5.148.1	Properties	625
3.2.5.148.1.1	Scalar Properties	625
3.2.5.148.1.1.1	ExportMode	625
3.2.5.148.1.1.2	Hidden	625

3.2.5.148.1.1.3	IsClosed	625
3.2.5.148.1.1.4	Subtitle	625
3.2.5.148.1.1.5	Title	625
3.2.5.148.1.1.6	TitleUrl	626
3.2.5.148.1.1.7	ZoneIndex	626
3.2.5.148.1.2	ObjectPath Properties	626
3.2.5.148.1.2.1	Properties	626
3.2.5.148.2	Methods	626
3.2.5.148.2.1	Scalar Methods	626
3.2.5.148.2.2	ObjectPath Methods	626
3.2.5.149	Microsoft.SharePoint.Client.WebParts.WebPartDefinition	626
3.2.5.149.1	Properties	627
3.2.5.149.1.1	Scalar Properties	627
3.2.5.149.1.1.1	Id	627
3.2.5.149.1.1.2	ZoneId	627
3.2.5.149.1.2	ObjectPath Properties	627
3.2.5.149.1.2.1	WebPart	627
3.2.5.149.2	Methods	627
3.2.5.149.2.1	Scalar Methods	627
3.2.5.149.2.1.1	CloseWebPart	627
3.2.5.149.2.1.2	DeleteWebPart	627
3.2.5.149.2.1.3	MoveWebPartTo	628
3.2.5.149.2.1.4	OpenWebPart	628
3.2.5.149.2.1.5	SaveWebPartChanges	628
3.2.5.149.2.2	ObjectPath Methods	629
3.2.5.150	Microsoft.SharePoint.Client.WebParts.WebPartDefinitionCollection	629
3.2.5.150.1	Properties	629
3.2.5.150.1.1	Scalar Properties	629
3.2.5.150.1.2	ObjectPath Properties	629
3.2.5.150.2	Methods	629
3.2.5.150.2.1	Scalar Methods	629
3.2.5.150.2.2	ObjectPath Methods	629
3.2.5.150.2.2.1	GetById	629
3.2.5.150.2.2.2	GetByControlId	629
3.2.5.151	Microsoft.SharePoint.Client.WebTemplate	630
3.2.5.151.1	Properties	630
3.2.5.151.1.1	Scalar Properties	630
3.2.5.151.1.1.1	Description	630
3.2.5.151.1.1.2	DisplayCategory	630
3.2.5.151.1.1.3	Id	630
3.2.5.151.1.1.4	ImageUrl	631
3.2.5.151.1.1.5	IsHidden	631
3.2.5.151.1.1.6	IsRootWebOnly	631
3.2.5.151.1.1.7	IsSubWebOnly	631
3.2.5.151.1.1.8	Lcid	631
3.2.5.151.1.1.9	Name	631
3.2.5.151.1.1.10	Title	631
3.2.5.151.1.2	ObjectPath Properties	632
3.2.5.151.2	Methods	632
3.2.5.151.2.1	Scalar Methods	632
3.2.5.151.2.2	ObjectPath Methods	632
3.2.5.152	Microsoft.SharePoint.Client.WebTemplateCollection	632
3.2.5.152.1	Properties	632
3.2.5.152.1.1	Scalar Properties	632
3.2.5.152.1.2	ObjectPath Properties	632
3.2.5.152.2	Methods	632
3.2.5.152.2.1	Scalar Methods	632
3.2.5.152.2.2	ObjectPath Methods	632



3.2.5.152.2.2.1	GetByName .....	632
3.2.5.153	Microsoft.SharePoint.Client.Workflow.WorkflowAssociation .....	633
3.2.5.153.1	Properties.....	633
3.2.5.153.1.1	Scalar Properties.....	633
3.2.5.153.1.1.1	AllowManual .....	633
3.2.5.153.1.1.2	AssociationData.....	633
3.2.5.153.1.1.3	AutoStartChange.....	633
3.2.5.153.1.1.4	AutoStartCreate .....	633
3.2.5.153.1.1.5	BaseId .....	634
3.2.5.153.1.1.6	Created.....	634
3.2.5.153.1.1.7	Description .....	634
3.2.5.153.1.1.8	Enabled.....	634
3.2.5.153.1.1.9	HistoryListTitle .....	634
3.2.5.153.1.1.10	Id.....	634
3.2.5.153.1.1.11	InstantiationUrl .....	635
3.2.5.153.1.1.12	InternalName.....	635
3.2.5.153.1.1.13	IsDeclarative .....	635
3.2.5.153.1.1.14	ListId .....	635
3.2.5.153.1.1.15	Modified .....	635
3.2.5.153.1.1.16	Name.....	635
3.2.5.153.1.1.17	TaskListTitle .....	635
3.2.5.153.1.1.18	WebId.....	636
3.2.5.153.1.2	ObjectPath Properties.....	636
3.2.5.153.2	Methods.....	636
3.2.5.153.2.1	Scalar Methods.....	636
3.2.5.153.2.1.1	DeleteObject.....	636
3.2.5.153.2.1.2	Update.....	636
3.2.5.153.2.2	ObjectPath Methods .....	636
3.2.5.154	Microsoft.SharePoint.Client.Workflow.WorkflowAssociationCollection .....	636
3.2.5.154.1	Properties.....	636
3.2.5.154.1.1	Scalar Properties.....	637
3.2.5.154.1.2	ObjectPath Properties.....	637
3.2.5.154.2	Methods .....	637
3.2.5.154.2.1	Scalar Methods.....	637
3.2.5.154.2.2	ObjectPath Methods .....	637
3.2.5.154.2.2.1	Add .....	637
3.2.5.154.2.2.2	GetById .....	637
3.2.5.154.2.2.3	GetByName .....	637
3.2.5.155	Microsoft.SharePoint.Client.Workflow.WorkflowAssociationCreationInformation .....	638
3.2.5.155.1	Properties.....	638
3.2.5.155.1.1	Scalar Properties.....	638
3.2.5.155.1.1.1	ContentTypeAssociationHistoryListName.....	638
3.2.5.155.1.1.2	ContentTypeAssociationTaskListName .....	638
3.2.5.155.1.1.3	Name.....	638
3.2.5.155.1.2	ObjectPath Properties.....	638
3.2.5.155.1.2.1	HistoryList .....	638
3.2.5.155.1.2.2	TaskList .....	639
3.2.5.155.1.2.3	Template.....	639
3.2.5.156	Microsoft.SharePoint.Client.Workflow.WorkflowTemplate.....	639
3.2.5.156.1	Properties.....	639
3.2.5.156.1.1	Scalar Properties.....	639
3.2.5.156.1.1.1	AllowManual .....	639
3.2.5.156.1.1.2	AssociationUrl .....	639
3.2.5.156.1.1.3	AutoStartChange.....	640
3.2.5.156.1.1.4	AutoStartCreate .....	640
3.2.5.156.1.1.5	Description .....	640
3.2.5.156.1.1.6	Id.....	640

3.2.5.156.1.1.7	IsDeclarative .....	640
3.2.5.156.1.1.8	Name .....	640
3.2.5.156.1.1.9	PermissionsManual .....	641
3.2.5.156.1.2	ObjectPath Properties .....	641
3.2.5.156.2	Methods .....	641
3.2.5.156.2.1	Scalar Methods .....	641
3.2.5.156.2.2	ObjectPath Methods .....	641
3.2.5.157	Microsoft.SharePoint.Client.Workflow.WorkflowTemplateCollection .....	641
3.2.5.157.1	Properties .....	641
3.2.5.157.1.1	Scalar Properties .....	641
3.2.5.157.1.2	ObjectPath Properties .....	641
3.2.5.157.2	Methods .....	641
3.2.5.157.2.1	Scalar Methods .....	641
3.2.5.157.2.2	ObjectPath Methods .....	641
3.2.5.157.2.2.1	GetById .....	641
3.2.5.157.2.2.2	GetByName .....	642
3.2.5.158	Microsoft.BusinessData.MetadataModel.Collections.EntityFieldCollection .....	642
3.2.5.158.1	Properties .....	642
3.2.5.158.1.1	Scalar Properties .....	642
3.2.5.158.1.2	ObjectPath Properties .....	642
3.2.5.158.2	Methods .....	642
3.2.5.158.2.1	Scalar Methods .....	642
3.2.5.158.2.2	ObjectPath Methods .....	642
3.2.5.159	Microsoft.BusinessData.MetadataModel.Collections.EntityIdentifierCollection .....	642
3.2.5.159.1	Properties .....	643
3.2.5.159.1.1	Scalar Properties .....	643
3.2.5.159.1.2	ObjectPath Properties .....	643
3.2.5.159.2	Methods .....	643
3.2.5.159.2.1	Scalar Methods .....	643
3.2.5.159.2.2	ObjectPath Methods .....	643
3.2.5.160	Microsoft.BusinessData.MetadataModel.Collections.LobSystemInstanceCollection .....	643
3.2.5.160.1	Properties .....	643
3.2.5.160.1.1	Scalar Properties .....	643
3.2.5.160.1.2	ObjectPath Properties .....	643
3.2.5.160.2	Methods .....	643
3.2.5.160.2.1	Scalar Methods .....	643
3.2.5.160.2.2	ObjectPath Methods .....	643
3.2.5.161	Microsoft.BusinessData.MetadataModel.Collections.TypeDescriptorCollection .....	643
3.2.5.161.1	Properties .....	644
3.2.5.161.1.1	Scalar Properties .....	644
3.2.5.161.1.2	ObjectPath Properties .....	644
3.2.5.161.2	Methods .....	644
3.2.5.161.2.1	Scalar Methods .....	644
3.2.5.161.2.2	ObjectPath Methods .....	644
3.2.5.162	Microsoft.BusinessData.MetadataModel.EntityField .....	644
3.2.5.162.1	Properties .....	644
3.2.5.162.1.1	Scalar Properties .....	644
3.2.5.162.1.1.1	ContainsLocalizedDisplayName .....	644
3.2.5.162.1.1.2	DefaultDisplayName .....	644
3.2.5.162.1.1.3	LocalizedDisplayName .....	644
3.2.5.162.1.1.4	Name .....	645
3.2.5.162.1.2	ObjectPath Properties .....	645
3.2.5.162.2	Methods .....	645
3.2.5.162.2.1	Scalar Methods .....	645
3.2.5.162.2.2	ObjectPath Methods .....	645
3.2.5.163	Microsoft.BusinessData.MetadataModel.EntityView .....	645
3.2.5.163.1	Properties .....	645

3.2.5.163.1.1	Scalar Properties.....	645
3.2.5.163.1.1.1	Name.....	645
3.2.5.163.1.1.2	RelatedSpecificFinderName.....	645
3.2.5.163.1.2	ObjectPath Properties.....	645
3.2.5.163.1.2.1	Fields.....	646
3.2.5.163.2	Methods.....	646
3.2.5.163.2.1	Scalar Methods.....	646
3.2.5.163.2.1.1	GetType.....	646
3.2.5.163.2.1.2	GetXmlSchema.....	646
3.2.5.163.2.2	ObjectPath Methods.....	646
3.2.5.163.2.2.1	GetDefaultValues.....	646
3.2.5.163.2.2.2	GetTypeDescriptor.....	647
3.2.5.164	Microsoft.BusinessData.Runtime.EntityFieldValueDictionary.....	647
3.2.5.164.1	Properties.....	647
3.2.5.164.1.1	Scalar Properties.....	647
3.2.5.164.1.2	ObjectPath Properties.....	647
3.2.5.164.2	Methods.....	647
3.2.5.164.2.1	Scalar Methods.....	647
3.2.5.164.2.1.1	CreateCollectionInstance.....	647
3.2.5.164.2.1.2	CreateInstance.....	648
3.2.5.164.2.1.3	FromXml.....	648
3.2.5.164.2.1.4	GetCollectionSize.....	649
3.2.5.164.2.1.5	SetFieldValue.....	649
3.2.5.164.2.1.6	ToXml.....	650
3.2.5.164.2.2	ObjectPath Methods.....	650
3.2.5.165	Microsoft.BusinessData.Runtime.EntityIdentity.....	650
3.2.5.165.1	Properties.....	650
3.2.5.165.1.1	Scalar Properties.....	650
3.2.5.165.1.1.1	IdentifierCount.....	650
3.2.5.165.1.2	ObjectPath Properties.....	650
3.2.5.165.2	Methods.....	650
3.2.5.165.2.1	Scalar Methods.....	651
3.2.5.165.2.2	ObjectPath Methods.....	651
3.2.5.165.2.2.1	CSOM Constructor.....	651
3.2.5.166	Microsoft.BusinessData.Runtime.EntityInstance.....	651
3.2.5.166.1	Properties.....	651
3.2.5.166.1.1	Scalar Properties.....	651
3.2.5.166.1.2	ObjectPath Properties.....	651
3.2.5.166.2	Methods.....	651
3.2.5.166.2.1	Scalar Methods.....	651
3.2.5.166.2.1.1	CreateCollectionInstance.....	651
3.2.5.166.2.1.2	CreateInstance.....	652
3.2.5.166.2.1.3	DeleteObject.....	652
3.2.5.166.2.1.4	FromXml.....	652
3.2.5.166.2.1.5	SetFieldValue.....	653
3.2.5.166.2.1.6	ToXml.....	653
3.2.5.166.2.1.7	Update.....	653
3.2.5.166.2.2	ObjectPath Methods.....	654
3.2.5.166.2.2.1	GetIdentity.....	654
3.2.5.167	Microsoft.SharePoint.Client.AlternateUrl.....	654
3.2.5.167.1	Properties.....	654
3.2.5.167.1.1	Scalar Properties.....	654
3.2.5.167.1.1.1	Uri.....	654
3.2.5.167.1.1.2	UrlZone.....	654
3.2.5.167.1.2	ObjectPath Properties.....	654
3.2.5.167.2	Methods.....	654
3.2.5.167.2.1	Scalar Methods.....	654
3.2.5.167.2.2	ObjectPath Methods.....	655

3.2.5.168	Microsoft.SharePoint.Client.Analytics.EventTypeId	655
3.2.5.168.1	Field Values	655
3.2.5.168.1.1	View	655
3.2.5.168.1.2	First	655
3.2.5.168.1.3	RecommendationView	655
3.2.5.168.1.4	RecommendationClick	655
3.2.5.168.1.5	Last	655
3.2.5.168.1.6	None	655
3.2.5.169	Microsoft.SharePoint.Client.Attachment	655
3.2.5.169.1	Properties	656
3.2.5.169.1.1	Scalar Properties	656
3.2.5.169.1.1.1	ServerRelativeUrl	656
3.2.5.169.1.1.2	FileName	656
3.2.5.169.1.1.3	FileNameAsPath	656
3.2.5.169.1.1.4	ServerRelativePath	656
3.2.5.169.1.2	ObjectPath Properties	656
3.2.5.169.2	Methods	656
3.2.5.169.2.1	Scalar Methods	656
3.2.5.169.2.1.1	DeleteObject	656
3.2.5.169.2.1.2	RecycleObject	656
3.2.5.169.2.2	ObjectPath Methods	657
3.2.5.170	Microsoft.SharePoint.Client.AttachmentCollection	657
3.2.5.170.1	Properties	657
3.2.5.170.1.1	Scalar Properties	657
3.2.5.170.1.2	ObjectPath Properties	657
3.2.5.170.2	Methods	657
3.2.5.170.2.1	Scalar Methods	657
3.2.5.170.2.2	ObjectPath Methods	657
3.2.5.170.2.2.1	Add	657
3.2.5.170.2.2.2	AddUsingPath	658
3.2.5.170.2.2.3	GetByFileName	658
3.2.5.170.2.2.4	GetByFileNameAsPath	658
3.2.5.171	Microsoft.SharePoint.Client.AttachmentCreationInformation	658
3.2.5.171.1	Properties	659
3.2.5.171.1.1	Scalar Properties	659
3.2.5.171.1.1.1	ContentStream	659
3.2.5.171.1.1.2	FileName	659
3.2.5.171.1.2	ObjectPath Properties	659
3.2.5.172	Microsoft.SharePoint.Client.ServerSettings	659
3.2.5.172.1	Properties	659
3.2.5.172.1.1	Scalar Properties	659
3.2.5.172.1.2	ObjectPath Properties	659
3.2.5.172.2	Methods	659
3.2.5.172.2.1	Scalar Methods	659
3.2.5.172.2.1.1	GetBlockedFileExtensions	659
3.2.5.172.2.1.2	GetGlobalInstalledLanguages	660
3.2.5.172.2.1.3	IsSharePointOnline	660
3.2.5.172.2.2	ObjectPath Methods	660
3.2.5.172.2.2.1	GetAlternateUrls	660
3.2.5.173	Microsoft.SharePoint.Client.WebProxy	660
3.2.5.173.1	Properties	660
3.2.5.173.1.1	Scalar Properties	660
3.2.5.173.1.2	ObjectPath Properties	660
3.2.5.173.2	Methods	660
3.2.5.173.2.1	Scalar Methods	660
3.2.5.173.2.1.1	Invoke	661
3.2.5.173.2.2	ObjectPath Methods	661
3.2.5.174	Microsoft.SharePoint.Client.WebRequestInfo	661

3.2.5.174.1	Properties.....	661
3.2.5.174.1.1	Scalar Properties.....	661
3.2.5.174.1.1.1	Body.....	661
3.2.5.174.1.1.2	Headers.....	661
3.2.5.174.1.1.3	Method.....	661
3.2.5.174.1.1.4	Url.....	661
3.2.5.174.1.2	ObjectPath Properties.....	662
3.2.5.175	Microsoft.SharePoint.Client.WebResponseInfo.....	662
3.2.5.175.1	Properties.....	662
3.2.5.175.1.1	Scalar Properties.....	662
3.2.5.175.1.1.1	Body.....	662
3.2.5.175.1.1.2	Headers.....	662
3.2.5.175.1.1.3	StatusCode.....	662
3.2.5.175.1.2	ObjectPath Properties.....	662
3.2.5.176	Microsoft.BusinessData.MetadataModel.Entity.....	662
3.2.5.176.1	Properties.....	663
3.2.5.176.1.1	Scalar Properties.....	663
3.2.5.176.1.1.1	EstimatedInstanceCount.....	663
3.2.5.176.1.1.2	Name.....	663
3.2.5.176.1.1.3	Namespace.....	663
3.2.5.176.1.2	ObjectPath Properties.....	663
3.2.5.176.2	Methods.....	663
3.2.5.176.2.1	Scalar Methods.....	663
3.2.5.176.2.1.1	GetIdentifierCount.....	663
3.2.5.176.2.1.2	Unsubscribe.....	663
3.2.5.176.2.2	ObjectPath Methods.....	664
3.2.5.176.2.2.1	Create.....	664
3.2.5.176.2.2.2	FindSpecific.....	665
3.2.5.176.2.2.3	FindSpecificByBdcId.....	666
3.2.5.176.2.2.4	FindSpecificDefault.....	667
3.2.5.176.2.2.5	FindSpecificDefaultByBdcId.....	667
3.2.5.176.2.2.6	GetCreatorView.....	668
3.2.5.176.2.2.7	GetDefaultSpecificFinderView.....	668
3.2.5.176.2.2.8	GetIdentifiers.....	668
3.2.5.176.2.2.9	GetLobSystem.....	669
3.2.5.176.2.2.10	GetSpecificFinderView.....	669
3.2.5.176.2.2.11	GetUpdaterView.....	669
3.2.5.176.2.2.12	FindAssociated.....	670
3.2.5.176.2.2.13	FindFiltered.....	670
3.2.5.176.2.2.14	GetAssociationView.....	671
3.2.5.176.2.2.15	GetFilters.....	672
3.2.5.176.2.2.16	Execute.....	672
3.2.5.176.2.2.17	GetFinderView.....	673
3.2.5.176.2.2.18	Subscribe.....	673
3.2.5.177	Microsoft.BusinessData.MetadataModel.EntityIdentifier.....	674
3.2.5.177.1	Properties.....	674
3.2.5.177.1.1	Scalar Properties.....	674
3.2.5.177.1.1.1	IdentifierType.....	674
3.2.5.177.1.1.2	Name.....	674
3.2.5.177.1.2	ObjectPath Properties.....	675
3.2.5.177.2	Methods.....	675
3.2.5.177.2.1	Scalar Methods.....	675
3.2.5.177.2.1.1	ContainsLocalizedDisplayName.....	675
3.2.5.177.2.1.2	GetDefaultDisplayName.....	675
3.2.5.177.2.1.3	GetLocalizedDisplayName.....	675
3.2.5.177.2.2	ObjectPath Methods.....	675
3.2.5.178	Microsoft.BusinessData.MetadataModel.LobSystem.....	675
3.2.5.178.1	Properties.....	676

3.2.5.178.1.1	Scalar Properties.....	676
3.2.5.178.1.1.1	Name.....	676
3.2.5.178.1.2	ObjectPath Properties.....	676
3.2.5.178.2	Methods.....	676
3.2.5.178.2.1	Scalar Methods.....	676
3.2.5.178.2.2	ObjectPath Methods.....	676
3.2.5.178.2.2.1	GetLobSystemInstances.....	676
3.2.5.179	Microsoft.BusinessData.MetadataModel.LobSystemInstance.....	676
3.2.5.179.1	Properties.....	676
3.2.5.179.1.1	Scalar Properties.....	676
3.2.5.179.1.1.1	Name.....	676
3.2.5.179.1.2	ObjectPath Properties.....	676
3.2.5.179.2	Methods.....	677
3.2.5.179.2.1	Scalar Methods.....	677
3.2.5.179.2.2	ObjectPath Methods.....	677
3.2.5.180	Microsoft.BusinessData.MetadataModel.TypeDescriptor.....	677
3.2.5.180.1	Properties.....	677
3.2.5.180.1.1	Scalar Properties.....	677
3.2.5.180.1.1.1	ContainsReadOnly.....	677
3.2.5.180.1.1.2	IsCollection.....	677
3.2.5.180.1.1.3	IsReadOnly.....	677
3.2.5.180.1.1.4	Name.....	677
3.2.5.180.1.1.5	TypeName.....	677
3.2.5.180.1.2	ObjectPath Properties.....	678
3.2.5.180.2	Methods.....	678
3.2.5.180.2.1	Scalar Methods.....	678
3.2.5.180.2.1.1	ContainsLocalizedDisplayName.....	678
3.2.5.180.2.1.2	GetDefaultDisplayName.....	678
3.2.5.180.2.1.3	GetLocalizedDisplayName.....	678
3.2.5.180.2.1.4	IsLeaf.....	678
3.2.5.180.2.1.5	IsRoot.....	678
3.2.5.180.2.2	ObjectPath Methods.....	679
3.2.5.180.2.2.1	GetChildTypeDescriptors.....	679
3.2.5.180.2.2.2	GetParentTypeDescriptor.....	679
3.2.5.181	Microsoft.SharePoint.Client.AppCatalog.....	679
3.2.5.181.1	Properties.....	679
3.2.5.181.1.1	Scalar Properties.....	679
3.2.5.181.1.2	ObjectPath Properties.....	679
3.2.5.181.2	Methods.....	679
3.2.5.181.2.1	Scalar Methods.....	679
3.2.5.181.2.1.1	IsAppSideloadingEnabled.....	679
3.2.5.181.2.1.2	GetAppPermissionDescriptions.....	680
3.2.5.181.2.2	ObjectPath Methods.....	680
3.2.5.181.2.2.1	GetAppDetails.....	680
3.2.5.181.2.2.2	GetAppInstance.....	680
3.2.5.181.2.2.3	GetAppInstances.....	681
3.2.5.181.2.2.4	GetDeveloperSiteAppInstancesByIds.....	681
3.2.5.182	Microsoft.SharePoint.Client.AppInstance.....	681
3.2.5.182.1	Properties.....	681
3.2.5.182.1.1	Scalar Properties.....	681
3.2.5.182.1.1.1	Id.....	682
3.2.5.182.1.1.2	AppWebFullUrl.....	682
3.2.5.182.1.1.3	InError.....	682
3.2.5.182.1.1.4	RemoteAppUrl.....	682
3.2.5.182.1.1.5	SiteId.....	682
3.2.5.182.1.1.6	Status.....	682
3.2.5.182.1.1.7	Title.....	682
3.2.5.182.1.1.8	WebId.....	682

3.2.5.182.1.1.9	StartPage	683
3.2.5.182.1.1.10	AppPrincipalId	683
3.2.5.182.1.1.11	SettingsPageUrl	683
3.2.5.182.1.1.12	ImageFallbackUrl	683
3.2.5.182.1.1.13	ImageUrl	683
3.2.5.182.1.1.14	PackageFingerprint	683
3.2.5.182.1.1.15	ProductId	683
3.2.5.182.1.2	ObjectPath Properties	684
3.2.5.182.2	Methods	684
3.2.5.182.2.1	Scalar Methods	684
3.2.5.182.2.1.1	Uninstall	684
3.2.5.182.2.1.2	CancelAllJobs	684
3.2.5.182.2.1.3	RetryAllJobs	684
3.2.5.182.2.1.4	Upgrade	684
3.2.5.182.2.1.5	Install	684
3.2.5.182.2.1.6	RetrieveAppDatabaseConnectionString	684
3.2.5.182.2.1.7	GetAppDatabaseConnectionString	685
3.2.5.182.2.1.8	Recycle	685
3.2.5.182.2.1.9	Restore	685
3.2.5.182.2.2	ObjectPath Methods	685
3.2.5.182.2.2.1	GetPreviousAppVersion	685
3.2.5.182.2.2.2	GetErrorDetails	685
3.2.5.182.2.2.3	GetAppIcon	685
3.2.5.183	Microsoft.SharePoint.Client.ChangeLogItemQuery	686
3.2.5.183.1	Properties	686
3.2.5.183.1.1	Scalar Properties	686
3.2.5.183.1.1.1	ChangeToken	686
3.2.5.183.1.1.2	Contains	686
3.2.5.183.1.1.3	Query	686
3.2.5.183.1.1.4	QueryOptions	686
3.2.5.183.1.1.5	ViewName	687
3.2.5.183.1.1.6	RowLimit	687
3.2.5.183.1.1.7	ViewFields	687
3.2.5.183.1.2	ObjectPath Properties	687
3.2.5.184	Microsoft.SharePoint.Client.FieldCreationInformation	687
3.2.5.184.1	Properties	687
3.2.5.184.1.1	Scalar Properties	687
3.2.5.184.1.1.1	Choices	687
3.2.5.184.1.1.2	FieldTypeKind	687
3.2.5.184.1.1.3	IsCompactName	688
3.2.5.184.1.1.4	LookupFieldName	688
3.2.5.184.1.1.5	LookupListId	688
3.2.5.184.1.1.6	LookupWebId	688
3.2.5.184.1.1.7	Required	688
3.2.5.184.1.1.8	Title	688
3.2.5.184.1.2	ObjectPath Properties	688
3.2.5.185	Microsoft.SharePoint.Client.FieldGeolocation	688
3.2.5.185.1	Properties	689
3.2.5.185.1.1	Scalar Properties	689
3.2.5.185.1.1.1	CanBeDeleted	689
3.2.5.185.1.1.2	DefaultValue	689
3.2.5.185.1.1.3	Description	689
3.2.5.185.1.1.4	Direction	689
3.2.5.185.1.1.5	EnforceUniqueValues	690
3.2.5.185.1.1.6	FieldTypeKind	690
3.2.5.185.1.1.7	Filterable	690
3.2.5.185.1.1.8	FromBaseType	690
3.2.5.185.1.1.9	Group	690

3.2.5.185.1.1.10	Hidden	691
3.2.5.185.1.1.11	Id	691
3.2.5.185.1.1.12	InternalName	691
3.2.5.185.1.1.13	ReadOnlyField	691
3.2.5.185.1.1.14	Required	691
3.2.5.185.1.1.15	SchemaXml	692
3.2.5.185.1.1.16	Scope	692
3.2.5.185.1.1.17	Sealed	692
3.2.5.185.1.1.18	Sortable	692
3.2.5.185.1.1.19	StaticName	692
3.2.5.185.1.1.20	Title	693
3.2.5.185.1.1.21	TypeAsString	693
3.2.5.185.1.1.22	TypeDisplayName	693
3.2.5.185.1.1.23	TypeShortDescription	693
3.2.5.185.1.1.24	ValidationFormula	694
3.2.5.185.1.1.25	ValidationMessage	694
3.2.5.185.1.1.26	JSLink	694
3.2.5.185.1.1.27	EntityPropertyName	694
3.2.5.185.1.1.28	Indexed	694
3.2.5.185.1.1.29	SchemaXmlWithResourceTokens	694
3.2.5.185.1.1.30	AutoIndexed	694
3.2.5.185.1.1.31	ClientSideComponentId	695
3.2.5.185.1.1.32	ClientSideComponentProperties	695
3.2.5.185.1.1.33	CustomFormatter	695
3.2.5.185.1.1.34	DefaultFormula	695
3.2.5.185.1.1.35	NoCrawl	695
3.2.5.185.1.1.36	PinnedToFiltersPane	695
3.2.5.185.1.1.37	ShowInFiltersPane	695
3.2.5.185.1.2	ObjectPath Properties	696
3.2.5.185.1.2.1	DescriptionResource	696
3.2.5.185.1.2.2	TitleResource	696
3.2.5.185.2	Methods	696
3.2.5.185.2.1	Scalar Methods	696
3.2.5.185.2.1.1	DeleteObject	696
3.2.5.185.2.1.2	SetShowInDisplayForm	696
3.2.5.185.2.1.3	SetShowInEditForm	696
3.2.5.185.2.1.4	SetShowInNewForm	697
3.2.5.185.2.1.5	Update	697
3.2.5.185.2.1.6	UpdateAndPushChanges	697
3.2.5.185.2.1.7	ValidateSetValue	698
3.2.5.185.2.2	ObjectPath Methods	698
3.2.5.186	Microsoft.SharePoint.Client.FieldGeolocationValue	698
3.2.5.186.1	Properties	698
3.2.5.186.1.1	Scalar Properties	698
3.2.5.186.1.1.1	Altitude	698
3.2.5.186.1.1.2	Latitude	698
3.2.5.186.1.1.3	Longitude	699
3.2.5.186.1.1.4	Measure	699
3.2.5.186.1.2	ObjectPath Properties	699
3.2.5.187	Microsoft.SharePoint.Client.Sharing.DocumentSharingManager	699
3.2.5.187.1	Properties	699
3.2.5.187.1.1	Scalar Properties	699
3.2.5.187.1.2	ObjectPath Properties	699
3.2.5.187.2	Methods	699
3.2.5.187.2.1	Scalar Methods	699
3.2.5.187.2.1.1	UpdateDocumentSharingInfo	699
3.2.5.187.2.1.2	IsDocumentSharingEnabled	700
3.2.5.187.2.1.3	CanMemberShare	700



3.2.5.187.2.1.4	RemoveItemsFromSharedWithMeView .....	701
3.2.5.187.2.2	ObjectPath Methods .....	701
3.2.5.187.2.2.1	GetRoleDefinition .....	701
3.2.5.188	Microsoft.SharePoint.Client.Sharing.Role .....	701
3.2.5.188.1	Field Values .....	701
3.2.5.188.1.1	None .....	701
3.2.5.188.1.2	View .....	702
3.2.5.188.1.3	Edit .....	702
3.2.5.188.1.4	Owner .....	702
3.2.5.188.1.5	LimitedView .....	702
3.2.5.188.1.6	LimitedEdit .....	702
3.2.5.188.1.7	Review .....	702
3.2.5.188.1.8	RestrictedView .....	702
3.2.5.189	Microsoft.SharePoint.Client.Sharing.UserRoleAssignment .....	702
3.2.5.189.1	Properties .....	702
3.2.5.189.1.1	Scalar Properties .....	703
3.2.5.189.1.1.1	Role .....	703
3.2.5.189.1.1.2	UserId .....	703
3.2.5.189.1.2	ObjectPath Properties .....	703
3.2.5.190	Microsoft.SharePoint.Client.Sharing.UserSharingResult .....	703
3.2.5.190.1	Properties .....	703
3.2.5.190.1.1	Scalar Properties .....	703
3.2.5.190.1.1.1	AllowedRoles .....	703
3.2.5.190.1.1.2	CurrentRole .....	703
3.2.5.190.1.1.3	IsUserKnown .....	703
3.2.5.190.1.1.4	Status .....	704
3.2.5.190.1.1.5	User .....	704
3.2.5.190.1.1.6	Message .....	704
3.2.5.190.1.1.7	DisplayName .....	704
3.2.5.190.1.1.8	Email .....	704
3.2.5.190.1.1.9	InvitationLink .....	704
3.2.5.190.1.2	ObjectPath Properties .....	704
3.2.5.191	Microsoft.SharePoint.Client.WebInfoCreationInformation .....	704
3.2.5.191.1	Properties .....	705
3.2.5.191.1.1	Scalar Properties .....	705
3.2.5.191.1.1.1	Description .....	705
3.2.5.191.1.1.2	Language .....	705
3.2.5.191.1.1.3	Title .....	705
3.2.5.191.1.1.4	Url .....	705
3.2.5.191.1.1.5	UseUniquePermissions .....	705
3.2.5.191.1.1.6	WebTemplate .....	705
3.2.5.191.1.2	ObjectPath Properties .....	705
3.2.5.192	Microsoft.SharePoint.Client.WebInformation .....	706
3.2.5.192.1	Properties .....	706
3.2.5.192.1.1	Scalar Properties .....	706
3.2.5.192.1.1.1	Created .....	706
3.2.5.192.1.1.2	Description .....	706
3.2.5.192.1.1.3	Id .....	706
3.2.5.192.1.1.4	Language .....	706
3.2.5.192.1.1.5	LastItemModifiedDate .....	706
3.2.5.192.1.1.6	Title .....	706
3.2.5.192.1.1.7	WebTemplateId .....	707
3.2.5.192.1.1.8	ServerRelativeUrl .....	707
3.2.5.192.1.1.9	Configuration .....	707
3.2.5.192.1.1.10	WebTemplate .....	707
3.2.5.192.1.1.11	LastItemUserModifiedDate .....	707
3.2.5.192.1.2	ObjectPath Properties .....	707
3.2.5.192.2	Methods .....	707

3.2.5.192.2.1	Scalar Methods	707
3.2.5.192.2.2	ObjectPath Methods	707
3.2.5.193	Microsoft.SharePoint.Client.WebInformationCollection	708
3.2.5.193.1	Properties	708
3.2.5.193.1.1	Scalar Properties	708
3.2.5.193.1.2	ObjectPath Properties	708
3.2.5.193.2	Methods	708
3.2.5.193.2.1	Scalar Methods	708
3.2.5.193.2.2	ObjectPath Methods	708
3.2.5.193.2.2.1	Add	708
3.2.5.193.2.2.2	GetById	708
3.2.5.194	Microsoft.SharePoint.Client.XmlSchemaFieldCreationInformation	709
3.2.5.194.1	Properties	709
3.2.5.194.1.1	Scalar Properties	709
3.2.5.194.1.1.1	Options	709
3.2.5.194.1.1.2	SchemaXml	709
3.2.5.194.1.2	ObjectPath Properties	709
3.2.5.195	Microsoft.SharePoint.Client.ListItemEntityCollection	709
3.2.5.195.1	Properties	709
3.2.5.195.1.1	Scalar Properties	709
3.2.5.195.1.2	ObjectPath Properties	710
3.2.5.195.2	Methods	710
3.2.5.195.2.1	Scalar Methods	710
3.2.5.195.2.2	ObjectPath Methods	710
3.2.5.195.2.2.1	GetById	710
3.2.5.196	Microsoft.SharePoint.Client.ThemeInfo	710
3.2.5.196.1	Properties	710
3.2.5.196.1.1	Scalar Properties	710
3.2.5.196.1.1.1	AccessibleDescription	710
3.2.5.196.1.1.2	ThemeBackgroundImageUri	710
3.2.5.196.1.2	ObjectPath Properties	710
3.2.5.196.2	Methods	710
3.2.5.196.2.1	Scalar Methods	711
3.2.5.196.2.1.1	GetThemeFontByName	711
3.2.5.196.2.1.2	GetThemeShadeByName	711
3.2.5.196.2.2	ObjectPath Methods	711
3.2.5.197	Microsoft.SharePoint.Client.InformationRightsManagementSettings	711
3.2.5.197.1	Properties	711
3.2.5.197.1.1	Scalar Properties	711
3.2.5.197.1.1.1	AllowPrint	711
3.2.5.197.1.1.2	AllowScript	711
3.2.5.197.1.1.3	AllowWriteCopy	712
3.2.5.197.1.1.4	DocumentAccessExpireDays	712
3.2.5.197.1.1.5	DocumentLibraryProtectionExpireDate	712
3.2.5.197.1.1.6	EnableDocumentAccessExpire	712
3.2.5.197.1.1.7	EnableGroupProtection	712
3.2.5.197.1.1.8	EnableLicenseCacheExpire	712
3.2.5.197.1.1.9	GroupName	712
3.2.5.197.1.1.10	LicenseCacheExpireDays	713
3.2.5.197.1.1.11	PolicyDescription	713
3.2.5.197.1.1.12	PolicyTitle	713
3.2.5.197.1.1.13	EnableDocumentBrowserPublishingView	713
3.2.5.197.1.1.14	DisableDocumentBrowserView	713
3.2.5.197.1.1.15	TemplateId	713
3.2.5.197.1.2	ObjectPath Properties	713
3.2.5.197.2	Methods	713
3.2.5.197.2.1	Scalar Methods	713
3.2.5.197.2.1.1	Reset	713

3.2.5.197.2.1.2	Update	714
3.2.5.197.2.2	ObjectPath Methods	714
3.2.5.198	Microsoft.BusinessData.MetadataModel.Collections.EntityInstanceCollection	714
3.2.5.198.1	Properties	714
3.2.5.198.1.1	Scalar Properties	714
3.2.5.198.1.2	ObjectPath Properties	714
3.2.5.198.2	Methods	714
3.2.5.198.2.1	Scalar Methods	714
3.2.5.198.2.2	ObjectPath Methods	714
3.2.5.199	Microsoft.BusinessData.MetadataModel.Collections.FilterCollection	714
3.2.5.199.1	Properties	714
3.2.5.199.1.1	Scalar Properties	715
3.2.5.199.1.2	ObjectPath Properties	715
3.2.5.199.2	Methods	715
3.2.5.199.2.1	Scalar Methods	715
3.2.5.199.2.1.1	SetFilterValue	715
3.2.5.199.2.2	ObjectPath Methods	716
3.2.5.200	Microsoft.SharePoint.Client.ContextWebInformation	716
3.2.5.200.1	Properties	716
3.2.5.200.1.1	Scalar Properties	716
3.2.5.200.1.1.1	FormDigestTimeoutSeconds	716
3.2.5.200.1.1.2	FormDigestValue	716
3.2.5.200.1.1.3	LibraryVersion	716
3.2.5.200.1.1.4	SiteFullUrl	716
3.2.5.200.1.1.5	SupportedSchemaVersions	716
3.2.5.200.1.1.6	WebFullUrl	716
3.2.5.200.1.2	ObjectPath Properties	717
3.2.5.201	Microsoft.SharePoint.Client.EventReceiverDefinition	717
3.2.5.201.1	Properties	717
3.2.5.201.1.1	Scalar Properties	717
3.2.5.201.1.1.1	EventType	717
3.2.5.201.1.1.2	ReceiverAssembly	717
3.2.5.201.1.1.3	ReceiverClass	717
3.2.5.201.1.1.4	ReceiverName	717
3.2.5.201.1.1.5	ReceiverUrl	717
3.2.5.201.1.1.6	SequenceNumber	718
3.2.5.201.1.1.7	Synchronization	718
3.2.5.201.1.1.8	ReceiverId	718
3.2.5.201.1.2	ObjectPath Properties	718
3.2.5.201.2	Methods	718
3.2.5.201.2.1	Scalar Methods	718
3.2.5.201.2.1.1	DeleteObject	718
3.2.5.201.2.1.2	Update	718
3.2.5.201.2.2	ObjectPath Methods	718
3.2.5.202	Microsoft.SharePoint.Client.EventReceiverDefinitionCollection	718
3.2.5.202.1	Properties	719
3.2.5.202.1.1	Scalar Properties	719
3.2.5.202.1.2	ObjectPath Properties	719
3.2.5.202.2	Methods	719
3.2.5.202.2.1	Scalar Methods	719
3.2.5.202.2.2.1	Add	719
3.2.5.202.2.2.2	GetById	719
3.2.5.203	Microsoft.SharePoint.Client.EventReceiverDefinitionCreationInformation	719
3.2.5.203.1	Properties	719
3.2.5.203.1.1	Scalar Properties	719
3.2.5.203.1.1.1	EventType	720
3.2.5.203.1.1.2	ReceiverAssembly	720

3.2.5.203.1.1.3	ReceiverClass.....	720
3.2.5.203.1.1.4	ReceiverName.....	720
3.2.5.203.1.1.5	ReceiverUrl.....	720
3.2.5.203.1.1.6	SequenceNumber.....	720
3.2.5.203.1.1.7	Synchronization.....	720
3.2.5.203.1.2	ObjectPath Properties.....	720
3.2.5.204	Microsoft.SharePoint.Client.EventReceiverSynchronization.....	721
3.2.5.204.1	Field Values.....	721
3.2.5.204.1.1	DefaultSynchronization.....	721
3.2.5.204.1.2	Synchronous.....	721
3.2.5.204.1.3	Asynchronous.....	721
3.2.5.205	Microsoft.SharePoint.Client.EventReceiverType.....	721
3.2.5.205.1	Field Values.....	721
3.2.5.205.1.1	InvalidReceiver.....	721
3.2.5.205.1.2	ItemAdding.....	721
3.2.5.205.1.3	ItemUpdating.....	721
3.2.5.205.1.4	ItemDeleting.....	722
3.2.5.205.1.5	ItemCheckingIn.....	722
3.2.5.205.1.6	ItemCheckingOut.....	722
3.2.5.205.1.7	ItemUncheckingOut.....	722
3.2.5.205.1.8	ItemAttachmentAdding.....	722
3.2.5.205.1.9	ItemAttachmentDeleting.....	722
3.2.5.205.1.10	ItemFileMoving.....	722
3.2.5.205.1.11	ItemVersionDeleting.....	722
3.2.5.205.1.12	FieldAdding.....	722
3.2.5.205.1.13	FieldUpdating.....	722
3.2.5.205.1.14	FieldDeleting.....	723
3.2.5.205.1.15	ListAdding.....	723
3.2.5.205.1.16	ListDeleting.....	723
3.2.5.205.1.17	SiteDeleting.....	723
3.2.5.205.1.18	WebDeleting.....	723
3.2.5.205.1.19	WebMoving.....	723
3.2.5.205.1.20	WebAdding.....	723
3.2.5.205.1.21	GroupAdding.....	723
3.2.5.205.1.22	GroupUpdating.....	723
3.2.5.205.1.23	GroupDeleting.....	723
3.2.5.205.1.24	GroupUserAdding.....	724
3.2.5.205.1.25	GroupUserDeleting.....	724
3.2.5.205.1.26	RoleDefinitionAdding.....	724
3.2.5.205.1.27	RoleDefinitionUpdating.....	724
3.2.5.205.1.28	RoleDefinitionDeleting.....	724
3.2.5.205.1.29	RoleAssignmentAdding.....	724
3.2.5.205.1.30	RoleAssignmentDeleting.....	724
3.2.5.205.1.31	InheritanceBreaking.....	724
3.2.5.205.1.32	WorkflowStarting.....	724
3.2.5.205.1.33	ItemAdded.....	724
3.2.5.205.1.34	ItemUpdated.....	725
3.2.5.205.1.35	ItemDeleted.....	725
3.2.5.205.1.36	ItemCheckedIn.....	725
3.2.5.205.1.37	ItemCheckedOut.....	725
3.2.5.205.1.38	ItemUncheckedOut.....	725
3.2.5.205.1.39	ItemAttachmentAdded.....	725
3.2.5.205.1.40	ItemAttachmentDeleted.....	725
3.2.5.205.1.41	ItemFileMoved.....	725
3.2.5.205.1.42	ItemFileConverted.....	725
3.2.5.205.1.43	ItemVersionDeleted.....	725
3.2.5.205.1.44	FieldAdded.....	726
3.2.5.205.1.45	FieldUpdated.....	726

3.2.5.205.1.46	FieldDeleted	726
3.2.5.205.1.47	ListAdded	726
3.2.5.205.1.48	ListDeleted	726
3.2.5.205.1.49	SiteDeleted	726
3.2.5.205.1.50	WebDeleted	726
3.2.5.205.1.51	WebMoved	726
3.2.5.205.1.52	WebProvisioned	726
3.2.5.205.1.53	GroupAdded	726
3.2.5.205.1.54	GroupUpdated	727
3.2.5.205.1.55	GroupDeleted	727
3.2.5.205.1.56	GroupUserAdded	727
3.2.5.205.1.57	GroupUserDeleted	727
3.2.5.205.1.58	RoleDefinitionAdded	727
3.2.5.205.1.59	RoleDefinitionUpdated	727
3.2.5.205.1.60	RoleDefinitionDeleted	727
3.2.5.205.1.61	RoleAssignmentAdded	727
3.2.5.205.1.62	RoleAssignmentDeleted	727
3.2.5.205.1.63	InheritanceBroken	727
3.2.5.205.1.64	WorkflowStarted	728
3.2.5.205.1.65	WorkflowPostponed	728
3.2.5.205.1.66	WorkflowCompleted	728
3.2.5.205.1.67	EntityInstanceAdded	728
3.2.5.205.1.68	EntityInstanceUpdated	728
3.2.5.205.1.69	EntityInstanceDeleted	728
3.2.5.205.1.70	AppInstalled	728
3.2.5.205.1.71	AppUpgraded	728
3.2.5.205.1.72	AppUninstalling	728
3.2.5.205.1.73	EmailReceived	728
3.2.5.205.1.74	ContextEvent	729
3.2.5.205.1.75	InheritanceResetting	729
3.2.5.205.1.76	InheritanceReset	729
3.2.5.205.1.77	WebRestored	729
3.2.5.206	Microsoft.SharePoint.Client.RelatedItem	729
3.2.5.206.1	Properties	729
3.2.5.206.1.1	Scalar Properties	729
3.2.5.206.1.1.1	IconUrl	729
3.2.5.206.1.1.2	ItemId	729
3.2.5.206.1.1.3	ListId	729
3.2.5.206.1.1.4	Title	730
3.2.5.206.1.1.5	Url	730
3.2.5.206.1.1.6	WebId	730
3.2.5.206.1.2	ObjectPath Properties	730
3.2.5.207	Microsoft.SharePoint.Client.RelatedItemManager	730
3.2.5.207.1	Properties	730
3.2.5.207.1.1	Scalar Properties	730
3.2.5.207.1.2	ObjectPath Properties	730
3.2.5.207.2	Methods	731
3.2.5.207.2.1	Scalar Methods	731
3.2.5.207.2.1.1	AddSingleLink	731
3.2.5.207.2.1.2	DeleteSingleLink	731
3.2.5.207.2.1.3	GetPageOneRelatedItems	732
3.2.5.207.2.1.4	GetRelatedItems	732
3.2.5.207.2.1.5	AddSingleLinkFromUrl	733
3.2.5.207.2.1.6	AddSingleLinkToUrl	733
3.2.5.207.2.2	ObjectPath Methods	734
3.2.5.208	Microsoft.SharePoint.Client.UpgradeType	734
3.2.5.208.1	Field Values	734
3.2.5.208.1.1	BuildUpgrade	734

3.2.5.208.1.2	VersionUpgrade .....	734
3.2.5.209	Microsoft.SharePoint.Client.Utilities.WikiPageCreationInformation .....	734
3.2.5.209.1	Properties.....	734
3.2.5.209.1.1	Scalar Properties.....	734
3.2.5.209.1.1.1	ServerRelativeUrl .....	734
3.2.5.209.1.1.2	WikiHtmlContent .....	734
3.2.5.209.1.2	ObjectPath Properties.....	734
3.2.5.210	Microsoft.BusinessData.MetadataModel.AppBdcCatalog .....	735
3.2.5.210.1	Properties.....	735
3.2.5.210.1.1	Scalar Properties.....	735
3.2.5.210.1.2	ObjectPath Properties.....	735
3.2.5.210.2	Methods .....	735
3.2.5.210.2.1	Scalar Methods.....	735
3.2.5.210.2.1.1	GetConnectionId .....	735
3.2.5.210.2.1.2	GetLobSystemInstanceProperty.....	736
3.2.5.210.2.1.3	GetLobSystemProperty.....	736
3.2.5.210.2.1.4	GetPermissibleConnections .....	737
3.2.5.210.2.1.5	SetConnectionId.....	737
3.2.5.210.2.1.6	SetLobSystemInstanceProperty .....	738
3.2.5.210.2.1.7	SetLobSystemProperty .....	739
3.2.5.210.2.2	ObjectPath Methods .....	740
3.2.5.210.2.2.1	GetEntity.....	740
3.2.5.211	Microsoft.SharePoint.Client.SiteHealth.SiteHealthSummary .....	740
3.2.5.211.1	Properties.....	740
3.2.5.211.1.1	Scalar Properties.....	740
3.2.5.211.1.1.1	FailedErrorCount .....	740
3.2.5.211.1.1.2	FailedWarningCount.....	741
3.2.5.211.1.1.3	PassedCount.....	741
3.2.5.211.1.1.4	Results.....	741
3.2.5.211.1.2	ObjectPath Properties.....	741
3.2.5.211.2	Methods .....	741
3.2.5.211.2.1	Scalar Methods.....	741
3.2.5.211.2.2	ObjectPath Methods .....	741
3.2.5.212	Microsoft.SharePoint.Client.Utilities.EmailProperties .....	741
3.2.5.212.1	Properties.....	741
3.2.5.212.1.1	Scalar Properties.....	741
3.2.5.212.1.1.1	AdditionalHeaders .....	741
3.2.5.212.1.1.2	BCC .....	742
3.2.5.212.1.1.3	Body.....	742
3.2.5.212.1.1.4	CC.....	742
3.2.5.212.1.1.5	From.....	742
3.2.5.212.1.1.6	Subject .....	742
3.2.5.212.1.1.7	To .....	742
3.2.5.212.1.2	ObjectPath Properties.....	742
3.2.5.213	Microsoft.BusinessData.MetadataModel.Filter .....	742
3.2.5.213.1	Properties.....	743
3.2.5.213.1.1	Scalar Properties.....	743
3.2.5.213.1.1.1	DefaultDisplayName .....	743
3.2.5.213.1.1.2	FilterField .....	743
3.2.5.213.1.1.3	FilterType .....	743
3.2.5.213.1.1.4	LocalizedDisplayName.....	743
3.2.5.213.1.1.5	Name.....	743
3.2.5.213.1.1.6	ValueCount.....	744
3.2.5.213.1.2	ObjectPath Properties.....	744
3.2.5.213.2	Methods .....	744
3.2.5.213.2.1	Scalar Methods.....	744
3.2.5.213.2.2	ObjectPath Methods .....	744
3.2.5.214	Microsoft.BusinessData.MetadataModel.MethodExecutionResult .....	744

3.2.5.214.1	Properties.....	744
3.2.5.214.1.1	Scalar Properties.....	744
3.2.5.214.1.2	ObjectPath Properties.....	744
3.2.5.214.1.2.1	ReturnParameterCollection .....	744
3.2.5.214.2	Methods .....	744
3.2.5.214.2.1	Scalar Methods.....	744
3.2.5.214.2.2	ObjectPath Methods .....	744
3.2.5.215	Microsoft.BusinessData.MetadataModel.ReturnParameterCollection .....	745
3.2.5.215.1	Properties.....	745
3.2.5.215.1.1	Scalar Properties.....	745
3.2.5.215.1.2	ObjectPath Properties.....	745
3.2.5.215.2	Methods .....	745
3.2.5.215.2.1	Scalar Methods.....	745
3.2.5.215.2.2	ObjectPath Methods .....	745
3.2.5.216	Microsoft.SharePoint.Client.SiteHealth.SiteHealthResult .....	745
3.2.5.216.1	Properties.....	745
3.2.5.216.1.1	Scalar Properties.....	745
3.2.5.216.1.1.1	Status.....	745
3.2.5.216.1.1.2	TimeStamp.....	745
3.2.5.216.1.1.3	MessageAsText .....	745
3.2.5.216.1.1.4	RuleHelpLink.....	746
3.2.5.216.1.1.5	RuleId.....	746
3.2.5.216.1.1.6	RuleIsRepairable .....	746
3.2.5.216.1.1.7	RuleName.....	746
3.2.5.216.1.2	ObjectPath Properties.....	746
3.2.5.217	Microsoft.SharePoint.ApplicationPages.ClientPickerQuery.ClientPeoplePickerQueryParameters.....	746
3.2.5.217.1	Properties.....	746
3.2.5.217.1.1	Scalar Properties.....	746
3.2.5.217.1.1.1	AllowEmailAddresses.....	746
3.2.5.217.1.1.2	AllowMultipleEntities .....	747
3.2.5.217.1.1.3	AllUrlZones .....	747
3.2.5.217.1.1.4	EnabledClaimProviders .....	747
3.2.5.217.1.1.5	MaximumEntitySuggestions .....	747
3.2.5.217.1.1.6	PrincipalSource .....	747
3.2.5.217.1.1.7	PrincipalType .....	747
3.2.5.217.1.1.8	QueryString .....	747
3.2.5.217.1.1.9	Required .....	748
3.2.5.217.1.1.10	SharePointGroupID.....	748
3.2.5.217.1.1.11	UrlZone.....	748
3.2.5.217.1.1.12	UrlZoneSpecified .....	748
3.2.5.217.1.1.13	WebApplicationID .....	748
3.2.5.217.1.1.14	ForceClaims.....	748
3.2.5.217.1.1.15	AllowOnlyEmailAddresses .....	748
3.2.5.217.1.1.16	QuerySettings.....	749
3.2.5.217.1.2	ObjectPath Properties.....	749
3.2.5.217.1.2.1	Web.....	749
3.2.5.218	Microsoft.SharePoint.Client.DateTimeFieldFriendlyFormatType .....	749
3.2.5.218.1	Field Values .....	749
3.2.5.218.1.1	Unspecified .....	749
3.2.5.218.1.2	Disabled .....	749
3.2.5.218.1.3	Relative .....	749
3.2.5.219	Microsoft.SharePoint.Client.RegionalSettings .....	749
3.2.5.219.1	Properties.....	749
3.2.5.219.1.1	Scalar Properties.....	749
3.2.5.219.1.1.1	AdjustHijriDays .....	750
3.2.5.219.1.1.2	AlternateCalendarType .....	750

3.2.5.219.1.1.3	AM.....	750
3.2.5.219.1.1.4	CalendarType.....	750
3.2.5.219.1.1.5	Collation.....	751
3.2.5.219.1.1.6	CollationLCID.....	751
3.2.5.219.1.1.7	DateFormat.....	751
3.2.5.219.1.1.8	DateSeparator.....	751
3.2.5.219.1.1.9	DecimalSeparator.....	751
3.2.5.219.1.1.10	DigitGrouping.....	751
3.2.5.219.1.1.11	FirstDayOfWeek.....	752
3.2.5.219.1.1.12	FirstWeekOfYear.....	752
3.2.5.219.1.1.13	IsEastAsia.....	752
3.2.5.219.1.1.14	IsRightToLeft.....	753
3.2.5.219.1.1.15	IsUIRightToLeft.....	753
3.2.5.219.1.1.16	LocaleId.....	753
3.2.5.219.1.1.17	NegativeSign.....	753
3.2.5.219.1.1.18	NegNumberMode.....	753
3.2.5.219.1.1.19	PM.....	754
3.2.5.219.1.1.20	PositiveSign.....	754
3.2.5.219.1.1.21	ShowWeeks.....	754
3.2.5.219.1.1.22	ThousandSeparator.....	754
3.2.5.219.1.1.23	Time24.....	754
3.2.5.219.1.1.24	TimeMarkerPosition.....	754
3.2.5.219.1.1.25	TimeSeparator.....	755
3.2.5.219.1.1.26	WorkDayEndHour.....	755
3.2.5.219.1.1.27	WorkDays.....	756
3.2.5.219.1.1.28	WorkDayStartHour.....	756
3.2.5.219.1.1.29	ListSeparator.....	757
3.2.5.219.1.2	ObjectPath Properties.....	757
3.2.5.219.1.2.1	TimeZone.....	758
3.2.5.219.1.2.2	TimeZones.....	758
3.2.5.219.2	Methods.....	758
3.2.5.219.2.1	Scalar Methods.....	758
3.2.5.219.2.1.1	Update.....	758
3.2.5.219.2.2	ObjectPath Methods.....	758
3.2.5.220	Microsoft.SharePoint.Client.TimeZone.....	758
3.2.5.220.1	Properties.....	758
3.2.5.220.1.1	Scalar Properties.....	758
3.2.5.220.1.1.1	Description.....	758
3.2.5.220.1.1.2	Id.....	758
3.2.5.220.1.1.3	Information.....	759
3.2.5.220.1.2	ObjectPath Properties.....	759
3.2.5.220.2	Methods.....	759
3.2.5.220.2.1	Scalar Methods.....	759
3.2.5.220.2.1.1	LocalTimeToUTC.....	759
3.2.5.220.2.1.2	UTCToLocalTime.....	759
3.2.5.220.2.2	ObjectPath Methods.....	759
3.2.5.221	Microsoft.SharePoint.Client.TimeZoneCollection.....	759
3.2.5.221.1	Properties.....	759
3.2.5.221.1.1	Scalar Properties.....	759
3.2.5.221.1.2	ObjectPath Properties.....	759
3.2.5.221.2	Methods.....	760
3.2.5.221.2.1	Scalar Methods.....	760
3.2.5.221.2.2	ObjectPath Methods.....	760
3.2.5.221.2.2.1	GetById.....	760
3.2.5.222	Microsoft.SharePoint.Client.TimeZoneInformation.....	760
3.2.5.222.1	Properties.....	760
3.2.5.222.1.1	Scalar Properties.....	760
3.2.5.222.1.1.1	Bias.....	760



3.2.5.222.1.1.2	DaylightBias .....	760
3.2.5.222.1.1.3	StandardBias .....	760
3.2.5.222.1.2	ObjectPath Properties .....	761
3.2.5.223	Microsoft.SharePoint.ApplicationPages.ClientPickerQuery.ClientPeoplePickerWebServiceInterface .....	761
3.2.5.223.1	Properties.....	761
3.2.5.223.1.1	Scalar Properties.....	761
3.2.5.223.1.2	ObjectPath Properties .....	761
3.2.5.223.2	Methods .....	761
3.2.5.223.2.1	Scalar Methods .....	761
3.2.5.223.2.1.1	ClientPeoplePickerResolveUser .....	761
3.2.5.223.2.1.2	ClientPeoplePickerSearchUser .....	761
3.2.5.223.2.2	ObjectPath Methods .....	762
3.2.5.223.2.2.1	GetPickerEntityInformation .....	762
3.2.5.224	Microsoft.SharePoint.ApplicationPages.PickerQuery.PeoplePickerWebServiceInterface .....	762
3.2.5.224.1	Properties.....	762
3.2.5.224.1.1	Scalar Properties.....	762
3.2.5.224.1.2	ObjectPath Properties .....	762
3.2.5.224.2	Methods .....	762
3.2.5.224.2.1	Scalar Methods .....	762
3.2.5.224.2.1.1	GetSearchResults .....	762
3.2.5.224.2.1.2	GetSearchResultsByHierarchy .....	763
3.2.5.224.2.2	ObjectPath Methods .....	763
3.2.5.225	Microsoft.SharePoint.Client.RelatedFieldExtendedData .....	763
3.2.5.225.1	Properties.....	763
3.2.5.225.1.1	Scalar Properties.....	763
3.2.5.225.1.1.1	FieldId .....	763
3.2.5.225.1.1.2	ListId .....	764
3.2.5.225.1.1.3	ListImageUrl .....	764
3.2.5.225.1.1.4	ResolvedListTitle .....	764
3.2.5.225.1.1.5	ToolTipDescription .....	764
3.2.5.225.1.1.6	WebId.....	764
3.2.5.225.1.2	ObjectPath Properties.....	764
3.2.5.225.2	Methods .....	764
3.2.5.225.2.1	Scalar Methods .....	764
3.2.5.225.2.2	ObjectPath Methods .....	764
3.2.5.226	Microsoft.SharePoint.Client.RelatedFieldExtendedDataCollection .....	765
3.2.5.226.1	Properties.....	765
3.2.5.226.1.1	Scalar Properties.....	765
3.2.5.226.1.2	ObjectPath Properties .....	765
3.2.5.226.2	Methods .....	765
3.2.5.226.2.1	Scalar Methods .....	765
3.2.5.226.2.2	ObjectPath Methods .....	765
3.2.5.227	Microsoft.SharePoint.Client.ObjectSharingInformation .....	765
3.2.5.227.1	Properties.....	765
3.2.5.227.1.1	Scalar Properties.....	765
3.2.5.227.1.1.1	IsSharedWithCurrentUser .....	765
3.2.5.227.1.1.2	IsSharedWithGuest.....	765
3.2.5.227.1.1.3	IsSharedWithMany .....	765
3.2.5.227.1.1.4	IsSharedWithSecurityGroup .....	766
3.2.5.227.1.1.5	AnonymousEditLink .....	766
3.2.5.227.1.1.6	AnonymousViewLink .....	766
3.2.5.227.1.1.7	CanManagePermissions .....	766
3.2.5.227.1.1.8	HasPendingAccessRequests .....	766
3.2.5.227.1.1.9	PendingAccessRequestsLink .....	766

3.2.5.227.1.1.10	HasPermissionLevels	767
3.2.5.227.1.1.11	CanBeShared	767
3.2.5.227.1.1.12	CanBeUnshared	767
3.2.5.227.1.1.13	SharingLinks	767
3.2.5.227.1.1.14	IsFolder	767
3.2.5.227.1.1.15	TotalFileCount	767
3.2.5.227.1.2	ObjectPath Properties	767
3.2.5.227.1.2.1	SharedWithUsersCollection	767
3.2.5.227.2	Methods	768
3.2.5.227.2.1	Scalar Methods	768
3.2.5.227.2.1.1	CanCurrentUserShare	768
3.2.5.227.2.1.2	CanCurrentUserShareRemote	768
3.2.5.227.2.2	ObjectPath Methods	768
3.2.5.227.2.2.1	GetObjectSharingInformation	768
3.2.5.227.2.2.2	GetListItemSharingInformation	769
3.2.5.227.2.2.3	GetSharedWithUsers	770
3.2.5.227.2.2.4	GetWebSharingInformation	770
3.2.5.227.2.2.5	GetObjectSharingInformation2	771
3.2.5.227.2.2.6	GetObjectSharingInformationByUrl	772
3.2.5.228	Microsoft.SharePoint.Client.PushNotificationSubscriber	772
3.2.5.228.1	Properties	773
3.2.5.228.1.1	Scalar Properties	773
3.2.5.228.1.1.1	CustomArgs	773
3.2.5.228.1.1.2	DeviceAppInstanceId	773
3.2.5.228.1.1.3	LastModifiedTimeStamp	773
3.2.5.228.1.1.4	RegistrationTimeStamp	773
3.2.5.228.1.1.5	ServiceToken	773
3.2.5.228.1.1.6	SubscriberType	773
3.2.5.228.1.2	ObjectPath Properties	773
3.2.5.228.1.2.1	User	774
3.2.5.228.2	Methods	774
3.2.5.228.2.1	Scalar Methods	774
3.2.5.228.2.1.1	Update	774
3.2.5.228.2.2	ObjectPath Methods	774
3.2.5.229	Microsoft.SharePoint.Client.PushNotificationSubscriberCollection	774
3.2.5.229.1	Properties	774
3.2.5.229.1.1	Scalar Properties	774
3.2.5.229.1.2	ObjectPath Properties	774
3.2.5.229.2	Methods	774
3.2.5.229.2.1	Scalar Methods	774
3.2.5.229.2.2	ObjectPath Methods	774
3.2.5.229.2.2.1	GetByStoreId	774
3.2.5.230	Microsoft.BusinessData.Runtime.EntityEventType	775
3.2.5.230.1	Field Values	775
3.2.5.230.1.1	None	775
3.2.5.230.1.2	ItemAdded	775
3.2.5.230.1.3	ItemUpdated	775
3.2.5.230.1.4	ItemDeleted	775
3.2.5.231	Microsoft.BusinessData.Runtime.NotificationCallback	775
3.2.5.231.1	Properties	775
3.2.5.231.1.1	Scalar Properties	775
3.2.5.231.1.1.1	NotificationContext	775
3.2.5.231.1.1.2	NotificationEndpoint	776
3.2.5.231.1.1.3	NotificationForwarderType	776
3.2.5.231.1.2	ObjectPath Properties	776
3.2.5.231.2	Methods	776
3.2.5.231.2.1	Scalar Methods	776
3.2.5.231.2.2	ObjectPath Methods	776

3.2.5.231.2.2.1 CSOM Constructor .....	776
3.2.5.232 Microsoft.BusinessData.Runtime.Subscription .....	776
3.2.5.232.1 Properties.....	777
3.2.5.232.1.1 Scalar Properties.....	777
3.2.5.232.1.1.1 Hash.....	777
3.2.5.232.1.1.2 ID .....	777
3.2.5.232.1.2 ObjectPath Properties.....	777
3.2.5.232.2 Methods.....	777
3.2.5.232.2.1 Scalar Methods.....	777
3.2.5.232.2.2 ObjectPath Methods .....	777
3.2.5.232.2.2.1 CSOM Constructor .....	777
3.2.5.233 Microsoft.SharePoint.Administration.SPAnalyticsUsageService .....	777
3.2.5.233.1 Properties.....	778
3.2.5.233.1.1 Scalar Properties.....	778
3.2.5.233.1.2 ObjectPath Properties.....	778
3.2.5.233.2 Methods .....	778
3.2.5.233.2.1 Scalar Methods.....	778
3.2.5.233.2.1.1 logevent.....	778
3.2.5.233.2.2 ObjectPath Methods .....	778
3.2.5.233.2.2.1 CSOM Constructor .....	778
3.2.5.234 Microsoft.SharePoint.Administration.UsageEntry .....	778
3.2.5.234.1 Properties.....	778
3.2.5.234.1.1 Scalar Properties.....	778
3.2.5.234.1.1.1 EventTypeId .....	778
3.2.5.234.1.1.2 ItemId .....	779
3.2.5.234.1.1.3 ScopeId .....	779
3.2.5.234.1.1.4 Site .....	779
3.2.5.234.1.1.5 User .....	779
3.2.5.234.1.2 ObjectPath Properties.....	779
3.2.5.235 Microsoft.BusinessData.Infrastructure.EntityInstanceIdEncoder .....	779
3.2.5.235.1 Properties.....	779
3.2.5.235.1.1 Scalar Properties.....	779
3.2.5.235.1.2 ObjectPath Properties.....	779
3.2.5.235.2 Methods .....	779
3.2.5.235.2.1 Scalar Methods.....	780
3.2.5.235.2.1.1 EncodeEntityInstanceId.....	780
3.2.5.235.2.2 ObjectPath Methods .....	780
3.2.5.236 Microsoft.BusinessData.Infrastructure.ExternalSubscriptionStore .....	780
3.2.5.236.1 Properties.....	780
3.2.5.236.1.1 Scalar Properties.....	780
3.2.5.236.1.2 ObjectPath Properties.....	780
3.2.5.236.2 Methods .....	780
3.2.5.236.2.1 Scalar Methods.....	780
3.2.5.236.2.1.1 IndexStore .....	780
3.2.5.236.2.2 ObjectPath Methods .....	781
3.2.5.236.2.2.1 CSOM Constructor .....	781
3.2.5.237 Microsoft.SharePoint.Client.App .....	781
3.2.5.237.1 Properties.....	781
3.2.5.237.1.1 Scalar Properties.....	781
3.2.5.237.1.1.1 AssetId .....	781
3.2.5.237.1.1.2 ContentMarket .....	781
3.2.5.237.1.1.3 VersionString .....	782
3.2.5.237.1.2 ObjectPath Properties.....	782
3.2.5.237.2 Methods .....	782
3.2.5.237.2.1 Scalar Methods.....	782
3.2.5.237.2.2 ObjectPath Methods .....	782
3.2.5.238 Microsoft.SharePoint.Client.AppInstanceStatus .....	782
3.2.5.238.1 Field Values .....	782

3.2.5.238.1.1	InvalidStatus	782
3.2.5.238.1.2	Installing	782
3.2.5.238.1.3	Canceling	782
3.2.5.238.1.4	Uninstalling	782
3.2.5.238.1.5	Installed	783
3.2.5.238.1.6	Upgrading	783
3.2.5.238.1.7	Initialized	783
3.2.5.238.1.8	UpgradeCanceling	783
3.2.5.238.1.9	Disabling	783
3.2.5.238.1.10	Disabled	783
3.2.5.238.1.11	SecretRolling	783
3.2.5.238.1.12	Recycling	783
3.2.5.238.1.13	Recycled	783
3.2.5.238.1.14	Restoring	783
3.2.5.238.1.15	RestoreCanceling	784
3.2.5.239	Microsoft.SharePoint.Client.AppLicense	784
3.2.5.239.1	Properties	784
3.2.5.239.1.1	Scalar Properties	784
3.2.5.239.1.1.1	RawXMLLicenseToken	784
3.2.5.239.1.2	ObjectPath Properties	784
3.2.5.240	Microsoft.SharePoint.Client.AppLicenseCollection	784
3.2.5.240.1	Properties	784
3.2.5.240.1.1	Scalar Properties	784
3.2.5.240.1.2	ObjectPath Properties	784
3.2.5.241	Microsoft.SharePoint.Client.AppLicenseType	784
3.2.5.241.1	Field Values	785
3.2.5.241.1.1	PerpetualMultiUser	785
3.2.5.241.1.2	PerpetualAllUsers	785
3.2.5.241.1.3	TrialMultiUser	785
3.2.5.241.1.4	TrialAllUsers	785
3.2.5.242	Microsoft.SharePoint.Client.Language	785
3.2.5.242.1	Properties	785
3.2.5.242.1.1	Scalar Properties	785
3.2.5.242.1.1.1	DisplayName	785
3.2.5.242.1.1.2	LanguageTag	785
3.2.5.242.1.1.3	Lcid	786
3.2.5.242.1.2	ObjectPath Properties	786
3.2.5.243	Microsoft.SharePoint.Client.ListItemFormUpdateValue	786
3.2.5.243.1	Properties	786
3.2.5.243.1.1	Scalar Properties	786
3.2.5.243.1.1.1	ErrorMessage	786
3.2.5.243.1.1.2	FieldName	786
3.2.5.243.1.1.3	FieldValue	786
3.2.5.243.1.1.4	HasException	786
3.2.5.243.1.1.5	ItemId	787
3.2.5.243.1.2	ObjectPath Properties	787
3.2.5.244	Microsoft.SharePoint.Client.MenuNode	787
3.2.5.244.1	Properties	787
3.2.5.244.1.1	Scalar Properties	787
3.2.5.244.1.1.1	CustomProperties	787
3.2.5.244.1.1.2	FriendlyUrlSegment	787
3.2.5.244.1.1.3	IsDeleted	787
3.2.5.244.1.1.4	IsHidden	787
3.2.5.244.1.1.5	Key	788
3.2.5.244.1.1.6	Nodes	788
3.2.5.244.1.1.7	NodeType	788
3.2.5.244.1.1.8	SimpleUrl	788
3.2.5.244.1.1.9	Title	788

3.2.5.244.1.2	ObjectPath Properties	788
3.2.5.245	Microsoft.SharePoint.Client.MenuNodeType	788
3.2.5.245.1	Field Values	789
3.2.5.245.1.1	SimpleLink	789
3.2.5.245.1.2	FriendlyUrl	789
3.2.5.246	Microsoft.SharePoint.Client.MenuState	789
3.2.5.246.1	Properties	789
3.2.5.246.1.1	Scalar Properties	789
3.2.5.246.1.1.1	FriendlyUrlPrefix	789
3.2.5.246.1.1.2	Nodes	789
3.2.5.246.1.1.3	SimpleUrl	789
3.2.5.246.1.1.4	SPSitePrefix	790
3.2.5.246.1.1.5	SPWebPrefix	790
3.2.5.246.1.1.6	StartingNodeKey	790
3.2.5.246.1.1.7	StartingNodeTitle	790
3.2.5.246.1.1.8	Version	790
3.2.5.246.1.2	ObjectPath Properties	790
3.2.5.247	Microsoft.SharePoint.Client.ObjectSharingInformationUser	790
3.2.5.247.1	Properties	790
3.2.5.247.1.1	Scalar Properties	790
3.2.5.247.1.1.1	Department	791
3.2.5.247.1.1.2	Email	791
3.2.5.247.1.1.3	Id	791
3.2.5.247.1.1.4	JobTitle	791
3.2.5.247.1.1.5	Name	791
3.2.5.247.1.1.6	Picture	791
3.2.5.247.1.1.7	SipAddress	791
3.2.5.247.1.1.8	CustomRoleNames	792
3.2.5.247.1.1.9	HasEditPermission	792
3.2.5.247.1.1.10	HasViewPermission	792
3.2.5.247.1.1.11	IsSiteAdmin	792
3.2.5.247.1.1.12	LoginName	792
3.2.5.247.1.1.13	IsDomainGroup	792
3.2.5.247.1.1.14	IsMemberOfGroup	793
3.2.5.247.1.1.15	HasReviewPermission	793
3.2.5.247.1.1.16	IsExternalUser	793
3.2.5.247.1.2	ObjectPath Properties	793
3.2.5.247.1.2.1	User	793
3.2.5.247.1.2.2	Principal	793
3.2.5.247.2	Methods	793
3.2.5.247.2.1	Scalar Methods	793
3.2.5.247.2.2	ObjectPath Methods	793
3.2.5.248	Microsoft.SharePoint.Client.OpenWebOptions	793
3.2.5.248.1	Field Values	794
3.2.5.248.1.1	None	794
3.2.5.248.1.2	InitNavigationCache	794
3.2.5.249	Microsoft.SharePoint.Client.RequestVariable	794
3.2.5.249.1	Properties	794
3.2.5.249.1.1	Scalar Properties	794
3.2.5.249.1.1.1	Value	794
3.2.5.249.1.2	ObjectPath Properties	794
3.2.5.249.2	Methods	794
3.2.5.249.2.1	Scalar Methods	794
3.2.5.249.2.1.1	Append	794
3.2.5.249.2.1.2	Set	795
3.2.5.249.2.2	ObjectPath Methods	795
3.2.5.249.2.2.1	CSOM Constructor	795
3.2.5.250	Microsoft.SharePoint.Client.SiteUrl	795

3.2.5.250.1	Properties.....	795
3.2.5.250.1.1	Scalar Properties.....	795
3.2.5.250.1.2	ObjectPath Properties.....	795
3.2.5.250.2	Methods.....	795
3.2.5.250.2.1	Scalar Methods.....	795
3.2.5.250.2.2	ObjectPath Methods.....	795
3.2.5.251	Microsoft.SharePoint.Client.UserIdInfo.....	795
3.2.5.251.1	Properties.....	796
3.2.5.251.1.1	Scalar Properties.....	796
3.2.5.251.1.1.1	NameId.....	796
3.2.5.251.1.1.2	NameIdIssuer.....	796
3.2.5.251.1.2	ObjectPath Properties.....	796
3.2.5.252	Microsoft.SharePoint.Client.Utilities.SPWOPIFrameAction.....	796
3.2.5.252.1	Field Values.....	796
3.2.5.252.1.1	View.....	796
3.2.5.252.1.2	Edit.....	796
3.2.5.252.1.3	MobileView.....	796
3.2.5.252.1.4	InteractivePreview.....	796
3.2.5.252.1.5	Syndicate.....	797
3.2.5.252.1.6	LegacyWebService.....	797
3.2.5.253	Microsoft.SharePoint.Navigation.REST.NavigationServiceRest.....	797
3.2.5.253.1	Properties.....	797
3.2.5.253.1.1	Scalar Properties.....	797
3.2.5.253.1.2	ObjectPath Properties.....	797
3.2.5.253.2	Methods.....	797
3.2.5.253.2.1	Scalar Methods.....	797
3.2.5.253.2.1.1	GetPublishingNavigationProviderType.....	797
3.2.5.253.2.1.2	MenuNodeKey.....	797
3.2.5.253.2.1.3	MenuState.....	798
3.2.5.253.2.2	ObjectPath Methods.....	798
3.2.5.253.2.2.1	CSOM Constructor.....	798
3.2.5.254	Microsoft.SharePoint.Client.UpgradeInfo.....	798
3.2.5.254.1	Properties.....	798
3.2.5.254.1.1	Scalar Properties.....	798
3.2.5.254.1.1.1	ErrorFile.....	798
3.2.5.254.1.1.2	Errors.....	799
3.2.5.254.1.1.3	LastUpdated.....	799
3.2.5.254.1.1.4	LogFile.....	799
3.2.5.254.1.1.5	RequestDate.....	799
3.2.5.254.1.1.6	RetryCount.....	799
3.2.5.254.1.1.7	StartTime.....	799
3.2.5.254.1.1.8	Status.....	799
3.2.5.254.1.1.9	UpgradeType.....	799
3.2.5.254.1.1.10	Warnings.....	800
3.2.5.254.1.2	ObjectPath Properties.....	800
3.2.5.255	Microsoft.SharePoint.Client.UpgradeStatus.....	800
3.2.5.255.1	Field Values.....	800
3.2.5.255.1.1	None.....	800
3.2.5.255.1.2	InProgress.....	800
3.2.5.255.1.3	Failed.....	800
3.2.5.255.1.4	Completed.....	800
3.2.5.256	Microsoft.SharePoint.Client.AppInstanceErrorDetails.....	800
3.2.5.256.1	Properties.....	801
3.2.5.256.1.1	Scalar Properties.....	801
3.2.5.256.1.1.1	CorrelationId.....	801
3.2.5.256.1.1.2	ErrorDetail.....	801
3.2.5.256.1.1.3	ErrorType.....	801
3.2.5.256.1.1.4	ErrorTypeName.....	801

3.2.5.256.1.1.5	ExceptionMessage	801
3.2.5.256.1.1.6	Source	801
3.2.5.256.1.1.7	SourceName	801
3.2.5.256.1.2	ObjectPath Properties	802
3.2.5.256.2	Methods	802
3.2.5.256.2.1	Scalar Methods	802
3.2.5.256.2.2	ObjectPath Methods	802
3.2.5.257	Microsoft.SharePoint.Client.AppInstanceErrorSource	802
3.2.5.257.1	Field Values	802
3.2.5.257.1.1	Common	802
3.2.5.257.1.2	AppWeb	802
3.2.5.257.1.3	ParentWeb	802
3.2.5.257.1.4	RemoteWebSite	802
3.2.5.257.1.5	Database	802
3.2.5.257.1.6	OfficeExtension	802
3.2.5.257.1.7	EventCallouts	803
3.2.5.257.1.8	Finalization	803
3.2.5.258	Microsoft.SharePoint.Client.AppInstanceErrorType	803
3.2.5.258.1	Field Values	803
3.2.5.258.1.1	Transient	803
3.2.5.258.1.2	Configuration	803
3.2.5.258.1.3	App	803
3.2.5.259	Microsoft.SharePoint.Client.CompatibilityRange	803
3.2.5.259.1	Properties	803
3.2.5.259.1.1	Scalar Properties	803
3.2.5.259.1.2	ObjectPath Properties	804
3.2.5.259.2	Methods	804
3.2.5.259.2.1	Scalar Methods	804
3.2.5.259.2.2	ObjectPath Methods	804
3.2.5.260	Microsoft.SharePoint.Client.AccessRequests	804
3.2.5.260.1	Properties	804
3.2.5.260.1.1	Scalar Properties	804
3.2.5.260.1.2	ObjectPath Properties	804
3.2.5.260.2	Methods	804
3.2.5.260.2.1	Scalar Methods	804
3.2.5.260.2.1.1	ChangeRequestStatus	804
3.2.5.260.2.1.2	ChangeRequestStatusBulk	805
3.2.5.260.2.1.3	QuickActionChangeRequestStatus	805
3.2.5.260.2.1.4	UpdateConversation	806
3.2.5.260.2.2	ObjectPath Methods	806
3.2.5.261	Microsoft.SharePoint.Client.AppContextSite	806
3.2.5.261.1	Properties	806
3.2.5.261.1.1	Scalar Properties	806
3.2.5.261.1.2	ObjectPath Properties	806
3.2.5.261.1.2.1	Site	806
3.2.5.261.1.2.2	Web	807
3.2.5.261.2	Methods	807
3.2.5.261.2.1	Scalar Methods	807
3.2.5.261.2.2	ObjectPath Methods	807
3.2.5.261.2.2.1	CSOM Constructor	807
3.2.5.262	Microsoft.SharePoint.Client.Analytics.AnalyticsUsageEntry	807
3.2.5.262.1	Properties	807
3.2.5.262.1.1	Scalar Properties	807
3.2.5.262.1.2	ObjectPath Properties	807
3.2.5.262.2	Methods	807
3.2.5.262.2.1	Scalar Methods	807
3.2.5.262.2.1.1	LogAnalyticsAppEvent	808
3.2.5.262.2.1.2	LogAnalyticsAppEvent2	808

3.2.5.262.2.1.3	LogAnalyticsEvent .....	808
3.2.5.262.2.1.4	LogAnalyticsEvent2.....	809
3.2.5.262.2.2	ObjectPath Methods .....	809
3.2.5.263	Microsoft.SharePoint.Client.UrlZone.....	809
3.2.5.263.1	Field Values .....	810
3.2.5.263.1.1	DefaultZone .....	810
3.2.5.263.1.2	Intranet .....	810
3.2.5.263.1.3	Internet .....	810
3.2.5.263.1.4	Custom.....	810
3.2.5.263.1.5	Extranet .....	810
3.2.5.264	Microsoft.SharePoint.Client.WebParts.TileData .....	810
3.2.5.264.1	Properties.....	810
3.2.5.264.1.1	Scalar Properties.....	810
3.2.5.264.1.1.1	BackgroundCollageImageLocations .....	810
3.2.5.264.1.1.2	BackgroundImageLocation.....	810
3.2.5.264.1.1.3	BackgroundImageRendersAsIcon.....	811
3.2.5.264.1.1.4	BodyText.....	811
3.2.5.264.1.1.5	Description .....	811
3.2.5.264.1.1.6	HoverDisabled.....	811
3.2.5.264.1.1.7	ID .....	811
3.2.5.264.1.1.8	IsWide .....	811
3.2.5.264.1.1.9	LinkLocation .....	811
3.2.5.264.1.1.10	TileOrder.....	811
3.2.5.264.1.1.11	Title.....	812
3.2.5.264.1.1.12	TransparentOverlay .....	812
3.2.5.264.1.2	ObjectPath Properties.....	812
3.2.5.265	Microsoft.SharePoint.Client.AppPrincipal .....	812
3.2.5.265.1	Properties.....	812
3.2.5.265.1.1	Scalar Properties.....	812
3.2.5.265.1.1.1	DisplayName .....	812
3.2.5.265.1.1.2	EndpointAuthorities .....	812
3.2.5.265.1.1.3	NameIdentifier .....	812
3.2.5.265.1.1.4	RedirectAddresses .....	813
3.2.5.265.1.2	ObjectPath Properties.....	813
3.2.5.265.2	Methods .....	813
3.2.5.265.2.1	Scalar Methods.....	813
3.2.5.265.2.2	ObjectPath Methods .....	813
3.2.5.266	Microsoft.SharePoint.Client.AppPrincipalConfiguration.....	813
3.2.5.266.1	Properties.....	813
3.2.5.266.1.1	Scalar Properties.....	813
3.2.5.266.1.1.1	ApplicationEndpointAuthorities .....	813
3.2.5.266.1.1.2	ApplicationPrincipalNames .....	813
3.2.5.266.1.1.3	NameIdentifier .....	813
3.2.5.266.1.1.4	RedirectAddresses .....	814
3.2.5.266.1.2	ObjectPath Properties.....	814
3.2.5.267	Microsoft.SharePoint.Client.AppPrincipalCredential .....	814
3.2.5.267.1	Properties.....	814
3.2.5.267.1.1	Scalar Properties.....	814
3.2.5.267.1.2	ObjectPath Properties.....	814
3.2.5.267.2	Methods .....	814
3.2.5.267.2.1	Scalar Methods.....	814
3.2.5.267.2.2	ObjectPath Methods .....	814
3.2.5.267.2.2.1	CreateFromKeyGroup.....	814
3.2.5.267.2.2.2	CreateFromSymmetricKey .....	815
3.2.5.268	Microsoft.SharePoint.Client.AppPrincipalCredentialReference .....	815
3.2.5.268.1	Properties.....	815
3.2.5.268.1.1	Scalar Properties.....	815
3.2.5.268.1.1.1	Id.....	815



3.2.5.268.1.1.2	NameIdentifier .....	815
3.2.5.268.1.1.3	NotAfter .....	815
3.2.5.268.1.1.4	NotBefore .....	815
3.2.5.268.1.2	ObjectPath Properties .....	816
3.2.5.269	Microsoft.SharePoint.Client.AppPrincipalIdentityProvider .....	816
3.2.5.269.1	Properties .....	816
3.2.5.269.1.1	Scalar Properties .....	816
3.2.5.269.1.2	ObjectPath Properties .....	816
3.2.5.269.1.2.1	External .....	816
3.2.5.269.2	Methods .....	816
3.2.5.269.2.1	Scalar Methods .....	816
3.2.5.269.2.2	ObjectPath Methods .....	816
3.2.5.270	Microsoft.SharePoint.Client.AppPrincipalManager .....	816
3.2.5.270.1	Properties .....	816
3.2.5.270.1.1	Scalar Properties .....	816
3.2.5.270.1.2	ObjectPath Properties .....	817
3.2.5.270.2	Methods .....	817
3.2.5.270.2.1	Scalar Methods .....	817
3.2.5.270.2.1.1	AddAppPrincipalCredential .....	817
3.2.5.270.2.1.2	DeleteAppPrincipal .....	817
3.2.5.270.2.1.3	DeleteAppPrincipalCredential .....	817
3.2.5.270.2.1.4	GetAppPrincipalConfiguration .....	817
3.2.5.270.2.1.5	GetAppPrincipalCredentials .....	818
3.2.5.270.2.1.6	SetAppPrincipalConfiguration .....	818
3.2.5.270.2.2	ObjectPath Methods .....	818
3.2.5.270.2.2.1	CreateAppPrincipal .....	818
3.2.5.270.2.2.2	GetManager .....	818
3.2.5.270.2.2.3	LookupAppPrincipal .....	818
3.2.5.271	Microsoft.SharePoint.Client.AppPrincipalName .....	819
3.2.5.271.1	Properties .....	819
3.2.5.271.1.1	Scalar Properties .....	819
3.2.5.271.1.2	ObjectPath Properties .....	819
3.2.5.271.2	Methods .....	819
3.2.5.271.2.1	Scalar Methods .....	819
3.2.5.271.2.2	ObjectPath Methods .....	819
3.2.5.271.2.2.1	CreateFromAppPrincipalIdentifier .....	819
3.2.5.271.2.2.2	CreateFromNameIdentifier .....	819
3.2.5.272	Microsoft.SharePoint.Client.ExternalAppPrincipalCreationParameters .....	820
3.2.5.272.1	Properties .....	820
3.2.5.272.1.1	Scalar Properties .....	820
3.2.5.272.1.1.1	AppIdentifier .....	820
3.2.5.272.1.1.2	ApplicationEndpointAuthorities .....	820
3.2.5.272.1.1.3	DisplayName .....	820
3.2.5.272.1.1.4	RedirectAddresses .....	820
3.2.5.272.1.1.5	TrustedForDelegation .....	820
3.2.5.272.1.2	ObjectPath Properties .....	820
3.2.5.272.1.2.1	Credential .....	820
3.2.5.273	Microsoft.SharePoint.Client.SiteHealth.SiteHealthStatusType .....	821
3.2.5.273.1	Field Values .....	821
3.2.5.273.1.1	Passed .....	821
3.2.5.273.1.2	FailedWarning .....	821
3.2.5.273.1.3	FailedError .....	821
3.2.5.274	Microsoft.SharePoint.Client.Utilities.LogAppErrorResult .....	821
3.2.5.274.1	Field Values .....	821
3.2.5.274.1.1	Success .....	821
3.2.5.274.1.2	ErrorsThrottled .....	821
3.2.5.274.1.3	AccessDenied .....	821
3.2.5.275	Microsoft.SharePoint.Client.RenderListDataParameters .....	822

3.2.5.275.1	Properties.....	822
3.2.5.275.1.1	Scalar Properties.....	822
3.2.5.275.1.1.1	AddRequiredFields .....	822
3.2.5.275.1.1.2	AllowMultipleValueFilterForTaxonomyFields.....	822
3.2.5.275.1.1.3	DatesInUtc .....	822
3.2.5.275.1.1.4	ExpandGroups .....	822
3.2.5.275.1.1.5	FirstGroupOnly .....	822
3.2.5.275.1.1.6	FolderServerRelativeUrl.....	822
3.2.5.275.1.1.7	ImageFieldsToTryRewriteToCdnUrls .....	823
3.2.5.275.1.1.8	OverrideViewXml.....	823
3.2.5.275.1.1.9	Paging .....	823
3.2.5.275.1.1.10	RenderOptions .....	823
3.2.5.275.1.1.11	ReplaceGroup .....	823
3.2.5.275.1.1.12	ViewXml.....	823
3.2.5.275.1.2	ObjectPath Properties.....	823
3.2.5.276	Microsoft.SharePoint.Client.TenantAppUtility_manual .....	824
3.2.5.276.1	Properties.....	824
3.2.5.276.1.1	Scalar Properties.....	824
3.2.5.276.1.2	ObjectPath Properties.....	824
3.2.5.276.2	Methods .....	824
3.2.5.276.2.1	Scalar Methods .....	824
3.2.5.276.2.2	ObjectPath Methods .....	824
3.2.5.276.2.2.1	GetTenantAppInformationCollection .....	824
3.2.5.277	Microsoft.SharePoint.Client.TenantAppInformation_manual .....	824
3.2.5.277.1	Properties.....	824
3.2.5.277.1.1	Scalar Properties.....	824
3.2.5.277.1.1.1	Id .....	824
3.2.5.277.1.1.2	CreationTime .....	825
3.2.5.277.1.1.3	LaunchUrl .....	825
3.2.5.277.1.1.4	RemoteAppUrl.....	825
3.2.5.277.1.1.5	AppPrincipalId.....	825
3.2.5.277.1.1.6	Status.....	825
3.2.5.277.1.1.7	Title.....	825
3.2.5.277.1.1.8	ProductId .....	825
3.2.5.277.1.1.9	IconAbsoluteUrl.....	825
3.2.5.277.1.1.10	IconFallbackAbsoluteUrl .....	826
3.2.5.277.1.1.11	AppWebFullUrl .....	826
3.2.5.277.1.1.12	PackageFingerprint .....	826
3.2.5.277.1.2	ObjectPath Properties.....	826
3.2.5.277.2	Methods .....	826
3.2.5.277.2.1	Scalar Methods .....	826
3.2.5.277.2.2	ObjectPath Methods .....	826
3.2.5.278	Microsoft.SharePoint.Client.AppTile .....	826
3.2.5.278.1	Properties.....	826
3.2.5.278.1.1	Scalar Properties.....	826
3.2.5.278.1.1.1	AppId .....	826
3.2.5.278.1.1.2	AppPrincipalId.....	827
3.2.5.278.1.1.3	AppSource.....	827
3.2.5.278.1.1.4	AppStatus .....	827
3.2.5.278.1.1.5	AppType.....	827
3.2.5.278.1.1.6	AssetId .....	827
3.2.5.278.1.1.7	BaseTemplate .....	827
3.2.5.278.1.1.8	ChildCount.....	827
3.2.5.278.1.1.9	ContentMarket .....	828
3.2.5.278.1.1.10	CustomSettingsUrl.....	828
3.2.5.278.1.1.11	Description .....	828
3.2.5.278.1.1.12	IsCorporateCatalogSite .....	828
3.2.5.278.1.1.13	LastModified .....	828

3.2.5.278.1.1.14	LastModifiedDate	828
3.2.5.278.1.1.15	ProductId	828
3.2.5.278.1.1.16	Target	828
3.2.5.278.1.1.17	Thumbnail	829
3.2.5.278.1.1.18	Title	829
3.2.5.278.1.1.19	Version	829
3.2.5.278.1.2	ObjectPath Properties	829
3.2.5.278.2	Methods	829
3.2.5.278.2.1	Scalar Methods	829
3.2.5.278.2.2	ObjectPath Methods	829
3.2.5.279	Microsoft.SharePoint.Client.AppTileCollection	829
3.2.5.279.1	Properties	829
3.2.5.279.1.1	Scalar Properties	829
3.2.5.279.1.2	ObjectPath Properties	830
3.2.5.279.2	Methods	830
3.2.5.279.2.1	Scalar Methods	830
3.2.5.279.2.2	ObjectPath Methods	830
3.2.5.280	Microsoft.SharePoint.Client.AppType	830
3.2.5.280.1	Field Values	830
3.2.5.280.1.1	Doclib	830
3.2.5.280.1.2	List	830
3.2.5.280.1.3	Tenant	830
3.2.5.280.1.4	Instance	830
3.2.5.280.1.5	Feature	830
3.2.5.280.1.6	CommonList	830
3.2.5.281	Microsoft.SharePoint.Client.Audit	831
3.2.5.281.1	Properties	831
3.2.5.281.1.1	Scalar Properties	831
3.2.5.281.1.1.1	AuditFlags	831
3.2.5.281.1.2	ObjectPath Properties	831
3.2.5.281.2	Methods	831
3.2.5.281.2.1	Scalar Methods	831
3.2.5.281.2.1.1	Update	831
3.2.5.281.2.2	ObjectPath Methods	831
3.2.5.282	Microsoft.SharePoint.Client.AuditMaskType	831
3.2.5.282.1	Field Values	831
3.2.5.282.1.1	None	831
3.2.5.282.1.2	CheckOut	832
3.2.5.282.1.3	CheckIn	832
3.2.5.282.1.4	View	832
3.2.5.282.1.5	ObjectDelete	832
3.2.5.282.1.6	Update	832
3.2.5.282.1.7	ProfileChange	832
3.2.5.282.1.8	ChildDelete	832
3.2.5.282.1.9	SchemaChange	832
3.2.5.282.1.10	SecurityChange	832
3.2.5.282.1.11	Undelete	832
3.2.5.282.1.12	Workflow	833
3.2.5.282.1.13	Copy	833
3.2.5.282.1.14	Move	833
3.2.5.282.1.15	Search	833
3.2.5.282.1.16	All	833
3.2.5.283	Microsoft.SharePoint.Client.CreatableItemInfo	833
3.2.5.283.1	Properties	833
3.2.5.283.1.1	Scalar Properties	833
3.2.5.283.1.1.1	DocumentTemplate	833
3.2.5.283.1.1.2	FileExtension	833
3.2.5.283.1.1.3	ItemType	834

3.2.5.283.1.2	ObjectPath Properties	834
3.2.5.284	Microsoft.SharePoint.Client.CreatableItemInfoCollection	834
3.2.5.284.1	Properties	834
3.2.5.284.1.1	Scalar Properties	834
3.2.5.284.1.2	ObjectPath Properties	834
3.2.5.285	Microsoft.SharePoint.Client.CreatablesInfo	834
3.2.5.285.1	Properties	834
3.2.5.285.1.1	Scalar Properties	834
3.2.5.285.1.1.1	CanCreateFolders	834
3.2.5.285.1.1.2	CanCreateItems	835
3.2.5.285.1.1.3	CanUploadFiles	835
3.2.5.285.1.1.4	CreatablesCollection	835
3.2.5.285.1.2	ObjectPath Properties	835
3.2.5.285.2	Methods	835
3.2.5.285.2.1	Scalar Methods	835
3.2.5.285.2.2	ObjectPath Methods	835
3.2.5.286	Microsoft.SharePoint.Client.DlpPolicyTip	835
3.2.5.286.1	Properties	835
3.2.5.286.1.1	Scalar Properties	835
3.2.5.286.1.1.1	AppliedActionsText	835
3.2.5.286.1.1.2	ComplianceUrl	836
3.2.5.286.1.1.3	GeneralText	836
3.2.5.286.1.1.4	LastProcessedTime	836
3.2.5.286.1.1.5	MatchedConditionDescriptions	836
3.2.5.286.1.1.6	OverrideOptions	836
3.2.5.286.1.1.7	TwoLetterISOLanguageName	836
3.2.5.286.1.2	ObjectPath Properties	836
3.2.5.286.2	Methods	836
3.2.5.286.2.1	Scalar Methods	836
3.2.5.286.2.2	ObjectPath Methods	837
3.2.5.287	Microsoft.SharePoint.Client.DocumentLibraryInformation	837
3.2.5.287.1	Properties	837
3.2.5.287.1.1	Scalar Properties	837
3.2.5.287.1.1.1	AbsoluteUrl	837
3.2.5.287.1.1.2	Modified	837
3.2.5.287.1.1.3	ModifiedFriendlyDisplay	837
3.2.5.287.1.1.4	ServerRelativeUrl	837
3.2.5.287.1.1.5	Title	837
3.2.5.287.1.2	ObjectPath Properties	837
3.2.5.288	Microsoft.SharePoint.Client.DocumentTemplateType	838
3.2.5.288.1	Field Values	838
3.2.5.288.1.1	Invalid	838
3.2.5.288.1.2	Word	838
3.2.5.288.1.3	Excel	838
3.2.5.288.1.4	PowerPoint	838
3.2.5.288.1.5	OneNote	838
3.2.5.288.1.6	ExcelForm	838
3.2.5.288.1.7	Max	838
3.2.5.288.1.8	Visio	838
3.2.5.289	Microsoft.SharePoint.Client.EffectiveInformationRightsManagementSettings	839
3.2.5.289.1	Properties	839
3.2.5.289.1.1	Scalar Properties	839
3.2.5.289.1.1.1	AllowPrint	839
3.2.5.289.1.1.2	AllowScript	839
3.2.5.289.1.1.3	AllowWriteCopy	839
3.2.5.289.1.1.4	DisableDocumentBrowserView	839
3.2.5.289.1.1.5	DocumentAccessExpireDays	839
3.2.5.289.1.1.6	DocumentLibraryProtectionExpireDate	839

3.2.5.289.1.1.7	EnableDocumentAccessExpire	840
3.2.5.289.1.1.8	EnableDocumentBrowserPublishingView	840
3.2.5.289.1.1.9	EnableGroupProtection	840
3.2.5.289.1.1.10	EnableLicenseCacheExpire	840
3.2.5.289.1.1.11	GroupName	840
3.2.5.289.1.1.12	IrmEnabled	840
3.2.5.289.1.1.13	LicenseCacheExpireDays	840
3.2.5.289.1.1.14	PolicyDescription	841
3.2.5.289.1.1.15	PolicyTitle	841
3.2.5.289.1.1.16	SettingSource	841
3.2.5.289.1.1.17	TemplateId	841
3.2.5.289.1.2	ObjectPath Properties	841
3.2.5.289.2	Methods	841
3.2.5.289.2.1	Scalar Methods	841
3.2.5.289.2.2	ObjectPath Methods	841
3.2.5.290	Microsoft.SharePoint.Client.FolderEntityData	841
3.2.5.290.1	Properties	841
3.2.5.290.1.1	Scalar Properties	841
3.2.5.290.1.1.1	Overwrite	842
3.2.5.290.1.1.2	ServerRelativeUrl	842
3.2.5.290.1.2	ObjectPath Properties	842
3.2.5.291	Microsoft.SharePoint.Client.InformationRightsManagementFileSettings	842
3.2.5.291.1	Properties	842
3.2.5.291.1.1	Scalar Properties	842
3.2.5.291.1.1.1	AllowPrint	842
3.2.5.291.1.1.2	AllowScript	842
3.2.5.291.1.1.3	AllowWriteCopy	842
3.2.5.291.1.1.4	DisableDocumentBrowserView	843
3.2.5.291.1.1.5	DocumentAccessExpireDays	843
3.2.5.291.1.1.6	EnableDocumentAccessExpire	843
3.2.5.291.1.1.7	EnableDocumentBrowserPublishingView	843
3.2.5.291.1.1.8	EnableGroupProtection	843
3.2.5.291.1.1.9	EnableLicenseCacheExpire	844
3.2.5.291.1.1.10	GroupName	844
3.2.5.291.1.1.11	IrmEnabled	844
3.2.5.291.1.1.12	LicenseCacheExpireDays	844
3.2.5.291.1.1.13	PolicyDescription	844
3.2.5.291.1.1.14	PolicyTitle	844
3.2.5.291.1.1.15	TemplateId	844
3.2.5.291.1.2	ObjectPath Properties	844
3.2.5.291.2	Methods	845
3.2.5.291.2.1	Scalar Methods	845
3.2.5.291.2.1.1	Reset	845
3.2.5.291.2.1.2	Update	845
3.2.5.291.2.2	ObjectPath Methods	845
3.2.5.292	Microsoft.SharePoint.Client.IngestionTaskKey	845
3.2.5.292.1	Properties	845
3.2.5.292.1.1	Scalar Properties	845
3.2.5.292.1.1.1	IngestionTableAccountKey	845
3.2.5.292.1.1.2	IngestionTableAccountName	845
3.2.5.292.1.1.3	JobId	845
3.2.5.292.1.1.4	TaskId	846
3.2.5.292.1.1.5	TenantName	846
3.2.5.292.1.2	ObjectPath Properties	846
3.2.5.293	Microsoft.SharePoint.Client.MigrationJobState	846
3.2.5.293.1	Field Values	846
3.2.5.293.1.1	None	846
3.2.5.293.1.2	Queued	846

3.2.5.293.1.3	Processing .....	846
3.2.5.294	Microsoft.SharePoint.Client.MountedFolderInfo .....	847
3.2.5.294.1	Properties.....	847
3.2.5.294.1.1	Scalar Properties.....	847
3.2.5.294.1.1.1	FolderUrl .....	847
3.2.5.294.1.1.2	HasEditPermission .....	847
3.2.5.294.1.1.3	ItemId .....	847
3.2.5.294.1.1.4	ListTemplateType .....	847
3.2.5.294.1.1.5	ListViewUrl .....	847
3.2.5.294.1.1.6	WebUrl.....	847
3.2.5.294.1.2	ObjectPath Properties .....	848
3.2.5.294.2	Methods .....	848
3.2.5.294.2.1	Scalar Methods.....	848
3.2.5.294.2.2	ObjectPath Methods .....	848
3.2.5.295	Microsoft.SharePoint.Client.MountPoint .....	848
3.2.5.295.1	Properties.....	848
3.2.5.295.1.1	Scalar Properties.....	848
3.2.5.295.1.2	ObjectPath Properties .....	848
3.2.5.295.2	Methods .....	848
3.2.5.295.2.1	Scalar Methods .....	848
3.2.5.295.2.1.1	CreateMountPoint .....	848
3.2.5.295.2.1.2	GetMountedFolderUrls.....	849
3.2.5.295.2.2	ObjectPath Methods .....	849
3.2.5.295.2.2.1	GetMountedFolderInfo.....	849
3.2.5.296	Microsoft.SharePoint.Client.MountPointInfo .....	849
3.2.5.296.1	Properties.....	849
3.2.5.296.1.1	Scalar Properties.....	849
3.2.5.296.1.1.1	Name.....	850
3.2.5.296.1.1.2	RedirectUrl .....	850
3.2.5.296.1.2	ObjectPath Properties .....	850
3.2.5.296.2	Methods .....	850
3.2.5.296.2.1	Scalar Methods .....	850
3.2.5.296.2.2	ObjectPath Methods .....	850
3.2.5.297	Microsoft.SharePoint.Client.MoveCopyUtil.....	850
3.2.5.297.1	Properties.....	850
3.2.5.297.1.1	Scalar Properties.....	850
3.2.5.297.1.2	ObjectPath Properties .....	850
3.2.5.297.2	Methods .....	850
3.2.5.297.2.1	Scalar Methods .....	850
3.2.5.297.2.1.1	CopyFile .....	850
3.2.5.297.2.1.2	CopyFileByPath .....	851
3.2.5.297.2.1.3	CopyFolder .....	852
3.2.5.297.2.1.4	CopyFolderByPath .....	853
3.2.5.297.2.1.5	MoveFile.....	854
3.2.5.297.2.1.6	MoveFileByPath .....	855
3.2.5.297.2.1.7	MoveFolder.....	855
3.2.5.297.2.1.8	MoveFolderByPath .....	856
3.2.5.297.2.2	ObjectPath Methods .....	857
3.2.5.298	Microsoft.SharePoint.Client.OAuth.NativeClient .....	857
3.2.5.298.1	Properties.....	857
3.2.5.298.1.1	Scalar Properties.....	857
3.2.5.298.1.2	ObjectPath Properties .....	857
3.2.5.298.2	Methods .....	857
3.2.5.298.2.1	Scalar Methods .....	857
3.2.5.298.2.1.1	Authenticate .....	857
3.2.5.298.2.2	ObjectPath Methods .....	858
3.2.5.298.2.2.1	CSOM Constructor .....	858
3.2.5.299	Microsoft.SharePoint.Client.ObjectSharingInformationUserCollection .....	858

3.2.5.299.1	Properties.....	858
3.2.5.299.1.1	Scalar Properties.....	858
3.2.5.299.1.2	ObjectPath Properties.....	858
3.2.5.299.2	Methods.....	858
3.2.5.299.2.1	Scalar Methods.....	858
3.2.5.299.2.2	ObjectPath Methods.....	858
3.2.5.300	Microsoft.SharePoint.Client.ObjectSharingSettings.....	858
3.2.5.300.1	Properties.....	858
3.2.5.300.1.1	Scalar Properties.....	858
3.2.5.300.1.1.1	AccessRequestMode.....	858
3.2.5.300.1.1.2	BlockPeoplePickerAndSharing.....	859
3.2.5.300.1.1.3	CanCurrentUserManageOrganizationReadOnlyLink.....	859
3.2.5.300.1.1.4	CanCurrentUserManageOrganizationReadWriteLink.....	859
3.2.5.300.1.1.5	CanCurrentUserManageReadOnlyLink.....	859
3.2.5.300.1.1.6	CanCurrentUserManageReadWriteLink.....	859
3.2.5.300.1.1.7	CanCurrentUserRetrieveOrganizationReadOnlyLink.....	859
3.2.5.300.1.1.8	CanCurrentUserRetrieveOrganizationReadWriteLink.....	859
3.2.5.300.1.1.9	CanCurrentUserRetrieveReadOnlyLink.....	860
3.2.5.300.1.1.10	CanCurrentUserRetrieveReadWriteLink.....	860
3.2.5.300.1.1.11	CanCurrentUserShareExternally.....	860
3.2.5.300.1.1.12	CanCurrentUserShareInternally.....	860
3.2.5.300.1.1.13	CanSendEmail.....	860
3.2.5.300.1.1.14	CanSendLink.....	860
3.2.5.300.1.1.15	CanShareFolder.....	861
3.2.5.300.1.1.16	DefaultShareLinkPermission.....	861
3.2.5.300.1.1.17	DefaultShareLinkType.....	861
3.2.5.300.1.1.18	GroupsList.....	861
3.2.5.300.1.1.19	HasEditRole.....	861
3.2.5.300.1.1.20	HasReadRole.....	861
3.2.5.300.1.1.21	InheritingWebLink.....	861
3.2.5.300.1.1.22	IsGuestUser.....	861
3.2.5.300.1.1.23	IsPictureLibrary.....	862
3.2.5.300.1.1.24	IsUserSiteAdmin.....	862
3.2.5.300.1.1.25	ItemId.....	862
3.2.5.300.1.1.26	ItemName.....	862
3.2.5.300.1.1.27	ItemUrl.....	862
3.2.5.300.1.1.28	ListId.....	862
3.2.5.300.1.1.29	PermissionsOnlyMode.....	862
3.2.5.300.1.1.30	RequiredAnonymousLinkExpirationInDays.....	863
3.2.5.300.1.1.31	Roles.....	863
3.2.5.300.1.1.32	ShareByEmailEnabled.....	863
3.2.5.300.1.1.33	ShowExternalSharingWarning.....	863
3.2.5.300.1.1.34	SimplifiedRoles.....	863
3.2.5.300.1.1.35	SupportsAclPropagation.....	863
3.2.5.300.1.1.36	WebUrl.....	863
3.2.5.300.1.2	ObjectPath Properties.....	863
3.2.5.300.1.2.1	ObjectSharingInformation.....	864
3.2.5.300.1.2.2	SharePointSettings.....	864
3.2.5.300.1.2.3	SharingPermissions.....	864
3.2.5.300.2	Methods.....	864
3.2.5.300.2.1	Scalar Methods.....	864
3.2.5.300.2.2	ObjectPath Methods.....	864
3.2.5.301	Microsoft.SharePoint.Client.PickerSettings.....	864
3.2.5.301.1	Properties.....	864
3.2.5.301.1.1	Scalar Properties.....	864
3.2.5.301.1.1.1	AllowEmailAddresses.....	864
3.2.5.301.1.1.2	AllowOnlyEmailAddresses.....	864
3.2.5.301.1.1.3	PrincipalAccountType.....	865

3.2.5.301.1.1.4	PrincipalSource .....	865
3.2.5.301.1.1.5	QuerySettings .....	865
3.2.5.301.1.1.6	VisibleSuggestions .....	865
3.2.5.301.1.2	ObjectPath Properties .....	865
3.2.5.301.2	Methods .....	865
3.2.5.301.2.1	Scalar Methods .....	865
3.2.5.301.2.2	ObjectPath Methods .....	865
3.2.5.302	Microsoft.SharePoint.Client.PolicyTipUserAction .....	865
3.2.5.302.1	Field Values .....	866
3.2.5.302.1.1	Override .....	866
3.2.5.302.1.2	ReportFalsePositive .....	866
3.2.5.303	Microsoft.SharePoint.Client.PolicyTipUserActionResult .....	866
3.2.5.303.1	Field Values .....	866
3.2.5.303.1.1	None .....	866
3.2.5.303.1.2	FalsePositiveReported .....	866
3.2.5.303.1.3	Overridden .....	866
3.2.5.303.1.4	FalsePositiveReportedAndOverridden .....	866
3.2.5.304	Microsoft.SharePoint.Client.RemoteWeb .....	866
3.2.5.304.1	Properties .....	867
3.2.5.304.1.1	Scalar Properties .....	867
3.2.5.304.1.1.1	CanSendEmail .....	867
3.2.5.304.1.1.2	ShareByEmailEnabled .....	867
3.2.5.304.1.1.3	ShareByLinkEnabled .....	867
3.2.5.304.1.2	ObjectPath Properties .....	867
3.2.5.304.1.2.1	Web .....	867
3.2.5.304.2	Methods .....	867
3.2.5.304.2.1	Scalar Methods .....	867
3.2.5.304.2.2	ObjectPath Methods .....	867
3.2.5.304.2.2.1	CSOM Constructor .....	867
3.2.5.304.2.2.2	GetFileByServerRelativePath .....	868
3.2.5.304.2.2.3	GetFileByServerRelativeUrl .....	868
3.2.5.304.2.2.4	GetFileByUrl .....	868
3.2.5.304.2.2.5	GetFolderByServerRelativeUrl .....	868
3.2.5.304.2.2.6	GetGroupById .....	869
3.2.5.304.2.2.7	GetListById .....	869
3.2.5.304.2.2.8	GetListByServerRelativeUrl .....	869
3.2.5.305	Microsoft.SharePoint.Client.RenderListContextMenuDataParameters .....	869
3.2.5.305.1	Properties .....	869
3.2.5.305.1.1	Scalar Properties .....	869
3.2.5.305.1.1.1	CascDelWarnMessage .....	869
3.2.5.305.1.1.2	CustomAction .....	870
3.2.5.305.1.1.3	Field .....	870
3.2.5.305.1.1.4	ID .....	870
3.2.5.305.1.1.5	InplaceFullListSearch .....	870
3.2.5.305.1.1.6	InplaceSearchQuery .....	870
3.2.5.305.1.1.7	IsCSR .....	870
3.2.5.305.1.1.8	IsXslView .....	870
3.2.5.305.1.1.9	ItemId .....	871
3.2.5.305.1.1.10	ListViewPageUrl .....	871
3.2.5.305.1.1.11	OverrideScope .....	871
3.2.5.305.1.1.12	RootFolder .....	871
3.2.5.305.1.1.13	View .....	871
3.2.5.305.1.1.14	ViewCount .....	871
3.2.5.305.1.2	ObjectPath Properties .....	871
3.2.5.306	Microsoft.SharePoint.Client.RenderListDataOptions .....	871
3.2.5.306.1	Field Values .....	872
3.2.5.306.1.1	None .....	872
3.2.5.306.1.2	ContextInfo .....	872



3.2.5.306.1.3	ListData	872
3.2.5.306.1.4	ListSchema	872
3.2.5.306.1.5	MenuView	872
3.2.5.306.1.6	ListContentType	872
3.2.5.306.1.7	FileSystemItemId	872
3.2.5.306.1.8	ClientFormSchema	872
3.2.5.306.1.9	QuickLaunch	872
3.2.5.306.1.10	Spotlight	872
3.2.5.306.1.11	Visualization	873
3.2.5.306.1.12	ViewMetadata	873
3.2.5.306.1.13	DisableAutoHyperlink	873
3.2.5.306.1.14	EnableMediaTARUrls	873
3.2.5.306.1.15	ParentInfo	873
3.2.5.306.1.16	PageContextInfo	873
3.2.5.306.1.17	ClientSideComponentManifest	873
3.2.5.307	Microsoft.SharePoint.Client.RenderListDataOverrideParameters	873
3.2.5.307.1	Properties	873
3.2.5.307.1.1	Scalar Properties	873
3.2.5.307.1.1.1	CascDelWarnMessage	874
3.2.5.307.1.1.2	CustomAction	874
3.2.5.307.1.1.3	DrillDown	874
3.2.5.307.1.1.4	Field	874
3.2.5.307.1.1.5	FieldInternalName	874
3.2.5.307.1.1.6	Filter	874
3.2.5.307.1.1.7	FilterData	874
3.2.5.307.1.1.8	FilterData1	874
3.2.5.307.1.1.9	FilterData10	875
3.2.5.307.1.1.10	FilterData2	875
3.2.5.307.1.1.11	FilterData3	875
3.2.5.307.1.1.12	FilterData4	875
3.2.5.307.1.1.13	FilterData5	875
3.2.5.307.1.1.14	FilterData6	875
3.2.5.307.1.1.15	FilterData7	875
3.2.5.307.1.1.16	FilterData8	876
3.2.5.307.1.1.17	FilterData9	876
3.2.5.307.1.1.18	FilterField	876
3.2.5.307.1.1.19	FilterField1	876
3.2.5.307.1.1.20	FilterField10	876
3.2.5.307.1.1.21	FilterField2	876
3.2.5.307.1.1.22	FilterField3	876
3.2.5.307.1.1.23	FilterField4	876
3.2.5.307.1.1.24	FilterField5	877
3.2.5.307.1.1.25	FilterField6	877
3.2.5.307.1.1.26	FilterField7	877
3.2.5.307.1.1.27	FilterField8	877
3.2.5.307.1.1.28	FilterField9	877
3.2.5.307.1.1.29	FilterFields	877
3.2.5.307.1.1.30	FilterFields1	877
3.2.5.307.1.1.31	FilterFields10	878
3.2.5.307.1.1.32	FilterFields2	878
3.2.5.307.1.1.33	FilterFields3	878
3.2.5.307.1.1.34	FilterFields4	878
3.2.5.307.1.1.35	FilterFields5	878
3.2.5.307.1.1.36	FilterFields6	878
3.2.5.307.1.1.37	FilterFields7	878
3.2.5.307.1.1.38	FilterFields8	878
3.2.5.307.1.1.39	FilterFields9	879
3.2.5.307.1.1.40	FilterLookupId	879

3.2.5.307.1.1.41	FilterLookupId1	879
3.2.5.307.1.1.42	FilterLookupId10	879
3.2.5.307.1.1.43	FilterLookupId2	879
3.2.5.307.1.1.44	FilterLookupId3	879
3.2.5.307.1.1.45	FilterLookupId4	879
3.2.5.307.1.1.46	FilterLookupId5	880
3.2.5.307.1.1.47	FilterLookupId6	880
3.2.5.307.1.1.48	FilterLookupId7	880
3.2.5.307.1.1.49	FilterLookupId8	880
3.2.5.307.1.1.50	FilterLookupId9	880
3.2.5.307.1.1.51	FilterOp	880
3.2.5.307.1.1.52	FilterOp1	881
3.2.5.307.1.1.53	FilterOp10	881
3.2.5.307.1.1.54	FilterOp2	881
3.2.5.307.1.1.55	FilterOp3	881
3.2.5.307.1.1.56	FilterOp4	881
3.2.5.307.1.1.57	FilterOp5	881
3.2.5.307.1.1.58	FilterOp6	881
3.2.5.307.1.1.59	FilterOp7	881
3.2.5.307.1.1.60	FilterOp8	882
3.2.5.307.1.1.61	FilterOp9	882
3.2.5.307.1.1.62	FilterValue	882
3.2.5.307.1.1.63	FilterValue1	882
3.2.5.307.1.1.64	FilterValue10	882
3.2.5.307.1.1.65	FilterValue2	882
3.2.5.307.1.1.66	FilterValue3	882
3.2.5.307.1.1.67	FilterValue4	883
3.2.5.307.1.1.68	FilterValue5	883
3.2.5.307.1.1.69	FilterValue6	883
3.2.5.307.1.1.70	FilterValue7	883
3.2.5.307.1.1.71	FilterValue8	883
3.2.5.307.1.1.72	FilterValue9	883
3.2.5.307.1.1.73	FilterValues	883
3.2.5.307.1.1.74	FilterValues1	884
3.2.5.307.1.1.75	FilterValues10	884
3.2.5.307.1.1.76	FilterValues2	884
3.2.5.307.1.1.77	FilterValues3	884
3.2.5.307.1.1.78	FilterValues4	884
3.2.5.307.1.1.79	FilterValues5	884
3.2.5.307.1.1.80	FilterValues6	884
3.2.5.307.1.1.81	FilterValues7	885
3.2.5.307.1.1.82	FilterValues8	885
3.2.5.307.1.1.83	FilterValues9	885
3.2.5.307.1.1.84	GroupString	885
3.2.5.307.1.1.85	HasOverrideSelectCommand	885
3.2.5.307.1.1.86	ID	885
3.2.5.307.1.1.87	InplaceFullListSearch	885
3.2.5.307.1.1.88	InplaceSearchQuery	885
3.2.5.307.1.1.89	IsCSR	886
3.2.5.307.1.1.90	IsGroupRender	886
3.2.5.307.1.1.91	IsXslView	886
3.2.5.307.1.1.92	ListViewPageUrl	886
3.2.5.307.1.1.93	OverrideScope	886
3.2.5.307.1.1.94	OverrideSelectCommand	886
3.2.5.307.1.1.95	PageFirstRow	886
3.2.5.307.1.1.96	PageLastRow	887
3.2.5.307.1.1.97	RootFolder	887
3.2.5.307.1.1.98	SortDir	887

3.2.5.307.1.1.99	SortDir1	887
3.2.5.307.1.1.100	SortDir10	887
3.2.5.307.1.1.101	SortDir2	887
3.2.5.307.1.1.102	SortDir3	887
3.2.5.307.1.1.103	SortDir4	887
3.2.5.307.1.1.104	SortDir5	888
3.2.5.307.1.1.105	SortDir6	888
3.2.5.307.1.1.106	SortDir7	888
3.2.5.307.1.1.107	SortDir8	888
3.2.5.307.1.1.108	SortDir9	888
3.2.5.307.1.1.109	SortField	888
3.2.5.307.1.1.110	SortField1	888
3.2.5.307.1.1.111	SortField10	889
3.2.5.307.1.1.112	SortField2	889
3.2.5.307.1.1.113	SortField3	889
3.2.5.307.1.1.114	SortField4	889
3.2.5.307.1.1.115	SortField5	889
3.2.5.307.1.1.116	SortField6	889
3.2.5.307.1.1.117	SortField7	889
3.2.5.307.1.1.118	SortField8	889
3.2.5.307.1.1.119	SortField9	890
3.2.5.307.1.1.120	SortFields	890
3.2.5.307.1.1.121	SortFieldValues	890
3.2.5.307.1.1.122	View	890
3.2.5.307.1.1.123	ViewCount	890
3.2.5.307.1.1.124	ViewId	890
3.2.5.307.1.1.125	ViewPath	890
3.2.5.307.1.1.126	WebPartId	891
3.2.5.307.1.2	ObjectPath Properties	891
3.2.5.308	Microsoft.SharePoint.Client.RenderListFilterDataParameters	891
3.2.5.308.1	Properties	891
3.2.5.308.1.1	Scalar Properties	891
3.2.5.308.1.1.1	ExcludeFieldFilteringHtml	891
3.2.5.308.1.1.2	FieldInternalName	891
3.2.5.308.1.1.3	OverrideScope	891
3.2.5.308.1.1.4	ProcessQStringToCAML	891
3.2.5.308.1.1.5	ViewId	892
3.2.5.308.1.2	ObjectPath Properties	892
3.2.5.309	Microsoft.SharePoint.Client.RequestUserContext	892
3.2.5.309.1	Properties	892
3.2.5.309.1.1	Scalar Properties	892
3.2.5.309.1.2	ObjectPath Properties	892
3.2.5.309.1.2.1	Current	892
3.2.5.309.1.2.2	User	892
3.2.5.309.2	Methods	892
3.2.5.309.2.1	Scalar Methods	892
3.2.5.309.2.2	ObjectPath Methods	892
3.2.5.310	Microsoft.SharePoint.Client.RuleOverrideOptions	893
3.2.5.310.1	Field Values	893
3.2.5.310.1.1	None	893
3.2.5.310.1.2	Allow	893
3.2.5.310.1.3	AllowWithJustification	893
3.2.5.311	Microsoft.SharePoint.Client.SandboxedCodeActivationCapabilities	893
3.2.5.311.1	Field Values	893
3.2.5.311.1.1	Check	893
3.2.5.311.1.2	Disabled	893
3.2.5.311.1.3	Enabled	894
3.2.5.312	Microsoft.SharePoint.Client.SharePointSharingSettings	894

3.2.5.312.1	Properties.....	894
3.2.5.312.1.1	Scalar Properties.....	894
3.2.5.312.1.1.1	AddToGroupModeName .....	894
3.2.5.312.1.1.2	GroupNameLines .....	894
3.2.5.312.1.1.3	GroupRoleDefinitionNamesLines .....	894
3.2.5.312.1.1.4	IsMobileView.....	894
3.2.5.312.1.1.5	PanelGivePermissionsVisible .....	894
3.2.5.312.1.1.6	PanelShowHideMoreOptionsVisible.....	895
3.2.5.312.1.1.7	PanelSimplifiedRoleSelectorVisible .....	895
3.2.5.312.1.1.8	RequiredScriptFileLinks .....	895
3.2.5.312.1.1.9	RoleDefinitionNameLines .....	895
3.2.5.312.1.1.10	SelectedGroup .....	895
3.2.5.312.1.1.11	SharedWithEnabled .....	895
3.2.5.312.1.1.12	SharingCssLink .....	895
3.2.5.312.1.1.13	TabbedDialogEnabled.....	895
3.2.5.312.1.1.14	TabToShow.....	896
3.2.5.312.1.1.15	txtEmailSubjectText.....	896
3.2.5.312.1.1.16	UserDisplayUrl .....	896
3.2.5.312.1.2	ObjectPath Properties.....	896
3.2.5.312.1.2.1	PickerProperties .....	896
3.2.5.312.2	Methods.....	896
3.2.5.312.2.1	Scalar Methods .....	896
3.2.5.312.2.2	ObjectPath Methods .....	896
3.2.5.313	Microsoft.SharePoint.Client.Sharing.WebSharingManager .....	896
3.2.5.313.1	Properties.....	897
3.2.5.313.1.1	Scalar Properties.....	897
3.2.5.313.1.2	ObjectPath Properties.....	897
3.2.5.313.2	Methods.....	897
3.2.5.313.2.1	Scalar Methods.....	897
3.2.5.313.2.1.1	CanMemberShare .....	897
3.2.5.313.2.1.2	UpdateWebSharingInformation .....	897
3.2.5.313.2.2	ObjectPath Methods .....	898
3.2.5.314	Microsoft.SharePoint.Client.SharingLinkInfo .....	898
3.2.5.314.1	Properties.....	898
3.2.5.314.1.1	Scalar Properties.....	898
3.2.5.314.1.1.1	AllowsAnonymousAccess .....	898
3.2.5.314.1.1.2	Created.....	898
3.2.5.314.1.1.3	CreatedBy .....	898
3.2.5.314.1.1.4	Expiration.....	898
3.2.5.314.1.1.5	HasExternalGuestInvitees.....	899
3.2.5.314.1.1.6	Invitations .....	899
3.2.5.314.1.1.7	IsActive.....	899
3.2.5.314.1.1.8	IsEditLink .....	899
3.2.5.314.1.1.9	IsFormsLink.....	899
3.2.5.314.1.1.10	IsReviewLink .....	899
3.2.5.314.1.1.11	IsUnhealthy .....	900
3.2.5.314.1.1.12	LastModified .....	900
3.2.5.314.1.1.13	LastModifiedBy .....	900
3.2.5.314.1.1.14	LinkKind.....	900
3.2.5.314.1.1.15	RequiresPassword.....	900
3.2.5.314.1.1.16	RestrictedShareMembership.....	900
3.2.5.314.1.1.17	ShareId.....	901
3.2.5.314.1.1.18	Url.....	901
3.2.5.314.1.2	ObjectPath Properties .....	901
3.2.5.315	Microsoft.SharePoint.Client.SharingLinkKind .....	901
3.2.5.315.1	Field Values .....	901
3.2.5.315.1.1	Uninitialized .....	901
3.2.5.315.1.2	Direct.....	901

3.2.5.315.1.3	OrganizationView	901
3.2.5.315.1.4	OrganizationEdit	901
3.2.5.315.1.5	AnonymousView	901
3.2.5.315.1.6	AnonymousEdit	902
3.2.5.315.1.7	Flexible	902
3.2.5.316	Microsoft.SharePoint.Client.SharingOperationStatusCode	902
3.2.5.316.1	Field Values	902
3.2.5.316.1.1	CompletedSuccessfully	902
3.2.5.316.1.2	AccessRequestsQueued	902
3.2.5.316.1.3	NoResolvedUsers	902
3.2.5.316.1.4	AccessDenied	902
3.2.5.316.1.5	CrossSiteRequestNotSupported	902
3.2.5.316.1.6	UnknowError	902
3.2.5.316.1.7	EmailBodyTooLong	902
3.2.5.316.1.8	ListUniqueScopesExceeded	903
3.2.5.316.1.9	CapabilityDisabled	903
3.2.5.316.1.10	ObjectNotSupported	903
3.2.5.316.1.11	NestedGroupsNotSupported	903
3.2.5.316.1.12	QuotaExceeded	903
3.2.5.316.1.13	InvalidValue	903
3.2.5.316.1.14	UserDoesNotExist	903
3.2.5.316.1.15	TooManyChildItemsWithUniqueScopes	903
3.2.5.317	Microsoft.SharePoint.Client.SharingPermissionInformation	903
3.2.5.317.1	Properties	904
3.2.5.317.1.1	Scalar Properties	904
3.2.5.317.1.1.1	IsDefaultPermission	904
3.2.5.317.1.1.2	PermissionDescription	904
3.2.5.317.1.1.3	PermissionId	904
3.2.5.317.1.1.4	PermissionKind	904
3.2.5.317.1.1.5	PermissionName	904
3.2.5.317.1.1.6	PermissionRoleType	904
3.2.5.317.1.2	ObjectPath Properties	905
3.2.5.317.2	Methods	905
3.2.5.317.2.1	Scalar Methods	905
3.2.5.317.2.2	ObjectPath Methods	905
3.2.5.318	Microsoft.SharePoint.Client.SharingPermissionInformationCollection	905
3.2.5.318.1	Properties	905
3.2.5.318.1.1	Scalar Properties	905
3.2.5.318.1.2	ObjectPath Properties	905
3.2.5.318.2	Methods	905
3.2.5.318.2.1	Scalar Methods	905
3.2.5.318.2.2	ObjectPath Methods	905
3.2.5.319	Microsoft.SharePoint.Client.SharingPermissionKind	905
3.2.5.319.1	Field Values	905
3.2.5.319.1.1	Group	906
3.2.5.319.1.2	Role	906
3.2.5.320	Microsoft.SharePoint.Client.SharingResult	906
3.2.5.320.1	Properties	906
3.2.5.320.1.1	Scalar Properties	906
3.2.5.320.1.1.1	ErrorMessage	906
3.2.5.320.1.1.2	IconUrl	906
3.2.5.320.1.1.3	InvitedUsers	906
3.2.5.320.1.1.4	Name	906
3.2.5.320.1.1.5	PermissionsPageRelativeUrl	906
3.2.5.320.1.1.6	StatusCode	907
3.2.5.320.1.1.7	UniquelyPermissionedUsers	907
3.2.5.320.1.1.8	Url	907
3.2.5.320.1.1.9	UsersAddedToGroup	907

3.2.5.320.1.2	ObjectPath Properties	907
3.2.5.320.1.2.1	GroupsSharedWith	907
3.2.5.320.1.2.2	GroupUsersAddedTo	907
3.2.5.320.1.2.3	UsersWithAccessRequests	907
3.2.5.320.2	Methods	908
3.2.5.320.2.1	Scalar Methods	908
3.2.5.320.2.2	ObjectPath Methods	908
3.2.5.321	Microsoft.SharePoint.Client.SharingUserCollection	908
3.2.5.321.1	Properties	908
3.2.5.321.1.1	Scalar Properties	908
3.2.5.321.1.2	ObjectPath Properties	908
3.2.5.321.2	Methods	908
3.2.5.321.2.1	Scalar Methods	908
3.2.5.321.2.2	ObjectPath Methods	908
3.2.5.322	Microsoft.SharePoint.Client.SPDataLeakagePreventionStatusInfo	908
3.2.5.322.1	Properties	908
3.2.5.322.1.1	Scalar Properties	908
3.2.5.322.1.1.1	ContainsConfidentialInfo	908
3.2.5.322.1.1.2	ContainsConfidentialInfoLearnMoreUrl	909
3.2.5.322.1.1.3	ExternalSharingTipsEnabled	909
3.2.5.322.1.1.4	ExternalSharingTipsLearnMoreUrl	909
3.2.5.322.1.2	ObjectPath Properties	909
3.2.5.322.2	Methods	909
3.2.5.322.2.1	Scalar Methods	909
3.2.5.322.2.2	ObjectPath Methods	909
3.2.5.323	Microsoft.SharePoint.Client.SpecialFolderType	909
3.2.5.323.1	Field Values	909
3.2.5.323.1.1	Attachment	909
3.2.5.323.1.2	Photos	910
3.2.5.323.1.3	CameraRoll	910
3.2.5.323.1.4	Music	910
3.2.5.323.1.5	Apps	910
3.2.5.323.1.6	AppRoot	910
3.2.5.323.1.7	Desktop	910
3.2.5.323.1.8	Documents	910
3.2.5.323.1.9	ScreenShots	910
3.2.5.323.1.10	Templates	910
3.2.5.324	Microsoft.SharePoint.Client.SPEffectiveInformationRightsManagementSettingsSource	911
3.2.5.324.1	Field Values	911
3.2.5.324.1.1	None	911
3.2.5.324.1.2	File	911
3.2.5.324.1.3	List	911
3.2.5.324.1.4	Rule	911
3.2.5.325	Microsoft.SharePoint.Client.SPInvitationCreationResult	911
3.2.5.325.1	Properties	911
3.2.5.325.1.1	Scalar Properties	911
3.2.5.325.1.1.1	Email	911
3.2.5.325.1.1.2	InvitationLink	911
3.2.5.325.1.1.3	Succeeded	912
3.2.5.325.1.2	ObjectPath Properties	912
3.2.5.326	Microsoft.SharePoint.Client.SPMigrationJobStatus	912
3.2.5.326.1	Properties	912
3.2.5.326.1.1	Scalar Properties	912
3.2.5.326.1.1.1	JobId	912
3.2.5.326.1.1.2	JobState	912
3.2.5.326.1.2	ObjectPath Properties	912

3.2.5.326.2	Methods	912
3.2.5.326.2.1	Scalar Methods	912
3.2.5.326.2.2	ObjectPath Methods	912
3.2.5.327	Microsoft.SharePoint.Client.SPMigrationJobStatusCollection	913
3.2.5.327.1	Properties	913
3.2.5.327.1.1	Scalar Properties	913
3.2.5.327.1.2	ObjectPath Properties	913
3.2.5.327.2	Methods	913
3.2.5.327.2.1	Scalar Methods	913
3.2.5.327.2.2	ObjectPath Methods	913
3.2.5.328	Microsoft.SharePoint.Client.StorageMetrics	913
3.2.5.328.1	Properties	913
3.2.5.328.1.1	Scalar Properties	913
3.2.5.328.1.1.1	LastModified	913
3.2.5.328.1.1.2	TotalFileCount	913
3.2.5.328.1.1.3	TotalFileStreamSize	913
3.2.5.328.1.1.4	TotalSize	914
3.2.5.328.1.2	ObjectPath Properties	914
3.2.5.328.2	Methods	914
3.2.5.328.2.1	Scalar Methods	914
3.2.5.328.2.2	ObjectPath Methods	914
3.2.5.329	Microsoft.SharePoint.Client.TenantAppInformation	914
3.2.5.329.1	Properties	914
3.2.5.329.1.1	Scalar Properties	914
3.2.5.329.1.1.1	AppPrincipalId	914
3.2.5.329.1.1.2	AppWebFullUrl	914
3.2.5.329.1.1.3	CreationTime	915
3.2.5.329.1.1.4	IconAbsoluteUrl	915
3.2.5.329.1.1.5	IconFallbackAbsoluteUrl	915
3.2.5.329.1.1.6	Id	915
3.2.5.329.1.1.7	LaunchUrl	915
3.2.5.329.1.1.8	PackageFingerprint	915
3.2.5.329.1.1.9	ProductId	915
3.2.5.329.1.1.10	RemoteAppUrl	915
3.2.5.329.1.1.11	Status	916
3.2.5.329.1.1.12	Title	916
3.2.5.329.1.2	ObjectPath Properties	916
3.2.5.330	Microsoft.SharePoint.Client.TenantAppInstance	916
3.2.5.330.1	Properties	916
3.2.5.330.1.1	Scalar Properties	916
3.2.5.330.1.1.1	Id	916
3.2.5.330.1.1.2	SiteId	916
3.2.5.330.1.1.3	WebId	916
3.2.5.330.1.2	ObjectPath Properties	917
3.2.5.330.2	Methods	917
3.2.5.330.2.1	Scalar Methods	917
3.2.5.330.2.2	ObjectPath Methods	917
3.2.5.331	Microsoft.SharePoint.Client.TenantAppUtility	917
3.2.5.331.1	Properties	917
3.2.5.331.1.1	Scalar Properties	917
3.2.5.331.1.2	ObjectPath Properties	917
3.2.5.331.2	Methods	917
3.2.5.331.2.1	Scalar Methods	917
3.2.5.331.2.1.1	GetAppPermissionDescriptions	917
3.2.5.331.2.1.2	GetTenantAppInformationCollection	917
3.2.5.331.2.2	ObjectPath Methods	918
3.2.5.331.2.2.1	GetAppDetails	918
3.2.5.331.2.2.2	GetAppIcon	918

3.2.5.331.2.2.3	GetTenantAppInstance .....	918
3.2.5.332	Microsoft.SharePoint.Client.TenantSettings .....	919
3.2.5.332.1	Properties .....	919
3.2.5.332.1.1	Scalar Properties .....	919
3.2.5.332.1.1.1	CorporateCatalogUrl .....	919
3.2.5.332.1.2	ObjectPath Properties .....	919
3.2.5.332.1.2.1	Current .....	919
3.2.5.332.2	Methods .....	919
3.2.5.332.2.1	Scalar Methods .....	919
3.2.5.332.2.2	ObjectPath Methods .....	919
3.2.5.333	Microsoft.SharePoint.Client.UserResource .....	919
3.2.5.333.1	Properties .....	920
3.2.5.333.1.1	Scalar Properties .....	920
3.2.5.333.1.2	ObjectPath Properties .....	920
3.2.5.333.2	Methods .....	920
3.2.5.333.2.1	Scalar Methods .....	920
3.2.5.333.2.1.1	GetValueForUICulture .....	920
3.2.5.333.2.1.2	SetValueForUICulture .....	920
3.2.5.333.2.2	ObjectPath Methods .....	921
3.2.5.334	Microsoft.SharePoint.Client.UserResourceScope .....	921
3.2.5.334.1	Field Values .....	921
3.2.5.334.1.1	Web .....	921
3.2.5.334.1.2	List .....	921
3.2.5.335	Microsoft.SharePoint.Client.UserResourceType .....	921
3.2.5.335.1	Field Values .....	921
3.2.5.335.1.1	SingleLine .....	921
3.2.5.335.1.2	MultiLine .....	921
3.2.5.336	Microsoft.SharePoint.Client.UserSharingCapabilities .....	922
3.2.5.336.1	Field Values .....	922
3.2.5.336.1.1	None .....	922
3.2.5.336.1.2	CanShareInternally .....	922
3.2.5.336.1.3	CanShareExternally .....	922
3.2.5.336.1.4	CanUseReadOnlyLink .....	922
3.2.5.336.1.5	CanManageReadOnlyLink .....	922
3.2.5.336.1.6	CanUseReadWriteLink .....	922
3.2.5.336.1.7	CanManageReadWriteLink .....	922
3.2.5.336.1.8	CanUseOrganizationReadOnlyLink .....	922
3.2.5.336.1.9	CanManageOrganizationReadOnlyLink .....	923
3.2.5.336.1.10	CanUseOrganizationReadWriteLink .....	923
3.2.5.336.1.11	CanManageOrganizationReadWriteLink .....	923
3.2.5.336.1.12	CanUsePeopleSharingReadOnlyLink .....	923
3.2.5.336.1.13	CanManagePeopleSharingReadOnlyLink .....	923
3.2.5.336.1.14	CanUsePeopleSharingReadWriteLink .....	923
3.2.5.336.1.15	CanManagePeopleSharingReadWriteLink .....	923
3.2.5.337	Microsoft.SharePoint.Client.Utilities.WopiProperties .....	923
3.2.5.337.1	Properties .....	924
3.2.5.337.1.1	Scalar Properties .....	924
3.2.5.337.1.1.1	AccessToken .....	924
3.2.5.337.1.1.2	AccessTokenTtl .....	924
3.2.5.337.1.1.3	AppIconUrl .....	924
3.2.5.337.1.1.4	ErrorMessageToDisplay .....	924
3.2.5.337.1.1.5	RedirectUrl .....	924
3.2.5.337.1.1.6	WebApplicationUrl .....	924
3.2.5.337.1.2	ObjectPath Properties .....	924
3.2.5.337.2	Methods .....	924
3.2.5.337.2.1	Scalar Methods .....	924
3.2.5.337.2.2	ObjectPath Methods .....	925
3.2.5.338	Microsoft.SharePoint.Packaging.AppDetails .....	925



3.2.5.338.1	Properties.....	925
3.2.5.338.1.1	Scalar Properties.....	925
3.2.5.338.1.1.1	EulaUrl.....	925
3.2.5.338.1.1.2	PrivacyUrl.....	925
3.2.5.338.1.1.3	Publisher.....	925
3.2.5.338.1.1.4	ShortDescription.....	925
3.2.5.338.1.1.5	SupportUrl.....	925
3.2.5.338.1.2	ObjectPath Properties.....	926
3.2.5.338.2	Methods.....	926
3.2.5.338.2.1	Scalar Methods.....	926
3.2.5.338.2.2	ObjectPath Methods.....	926
3.2.5.339	Microsoft.SharePoint.Packaging.AppIconInfo.....	926
3.2.5.339.1	Properties.....	926
3.2.5.339.1.1	Scalar Properties.....	926
3.2.5.339.1.1.1	Content.....	926
3.2.5.339.1.1.2	MimeType.....	926
3.2.5.339.1.2	ObjectPath Properties.....	926
3.2.5.339.2	Methods.....	926
3.2.5.339.2.1	Scalar Methods.....	926
3.2.5.339.2.2	ObjectPath Methods.....	926
3.2.5.340	Microsoft.SharePoint.WebControls.ModuleLink.....	927
3.2.5.340.1	Properties.....	927
3.2.5.340.1.1	Scalar Properties.....	927
3.2.5.340.1.2	ObjectPath Properties.....	927
3.2.5.340.2	Methods.....	927
3.2.5.340.2.1	Scalar Methods.....	927
3.2.5.340.2.2	ObjectPath Methods.....	927
3.2.5.340.2.2.1	GetResourceManifestInformation.....	927
3.2.5.341	Microsoft.SharePoint.WebControls.ResourceManifestInformation.....	927
3.2.5.341.1	Properties.....	927
3.2.5.341.1.1	Scalar Properties.....	927
3.2.5.341.1.1.1	RequireJsScriptBlock.....	927
3.2.5.341.1.1.2	ScenarioMapping.....	928
3.2.5.341.1.2	ObjectPath Properties.....	928
3.2.5.341.2	Methods.....	928
3.2.5.341.2.1	Scalar Methods.....	928
3.2.5.341.2.2	ObjectPath Methods.....	928
3.2.5.342	Microsoft.SharePoint.Client.RecycleBinOrderBy.....	928
3.2.5.342.1	Field Values.....	928
3.2.5.342.1.1	Min.....	928
3.2.5.342.1.2	DefaultOrderBy.....	928
3.2.5.342.1.3	Title.....	928
3.2.5.342.1.4	DirName.....	928
3.2.5.342.1.5	Author.....	929
3.2.5.342.1.6	DeletedDate.....	929
3.2.5.342.1.7	Size.....	929
3.2.5.342.1.8	DeletedBy.....	929
3.2.5.342.1.9	None.....	929
3.2.5.342.1.10	Max.....	929
3.2.5.343	Microsoft.SharePoint.Client.Sharing.RemoveItemsFromSharedWithMeViewError Code.....	929
3.2.5.343.1	Field Values.....	929
3.2.5.343.1.1	Success.....	929
3.2.5.343.1.2	InvalidListItem.....	930
3.2.5.343.1.3	InvalidItemSharing.....	930
3.2.5.343.1.4	UnableToRemoveItem.....	930
3.2.5.344	Microsoft.SharePoint.Client.Sharing.SharedWithMeViewItemRemovalResult.....	930

3.2.5.344.1	Properties.....	930
3.2.5.344.1.1	Scalar Properties.....	930
3.2.5.344.1.1.1	ErrorCode.....	930
3.2.5.344.1.1.2	ErrorMessage.....	930
3.2.5.344.1.1.3	Success.....	930
3.2.5.344.1.2	ObjectPath Properties.....	930
3.2.5.345	Microsoft.SharePoint.ClientSideComponent.SPClientSideComponentQueryResult .....	931
3.2.5.345.1	Properties.....	931
3.2.5.345.1.1	Scalar Properties.....	931
3.2.5.345.1.1.1	ComponentType.....	931
3.2.5.345.1.1.2	Id.....	931
3.2.5.345.1.1.3	Manifest.....	931
3.2.5.345.1.1.4	ManifestType.....	931
3.2.5.345.1.1.5	Name.....	931
3.2.5.345.1.1.6	Status.....	931
3.2.5.345.1.2	ObjectPath Properties.....	932
3.2.5.346	Microsoft.SharePoint.ClientSideComponent.SPClientSideComponentType ....	932
3.2.5.346.1	Field Values.....	932
3.2.5.346.1.1	Unknown.....	932
3.2.5.346.1.2	WebPart.....	932
3.2.5.346.1.3	Application.....	932
3.2.5.346.1.4	Library.....	932
3.2.5.346.1.5	Extension.....	932
3.2.5.347	Microsoft.SharePoint.ClientSideComponent.SPClientSideManifestType .....	932
3.2.5.347.1	Field Values.....	932
3.2.5.347.1.1	Unknown.....	932
3.2.5.347.1.2	Component.....	933
3.2.5.347.1.3	Container.....	933
3.2.5.348	Microsoft.SharePoint.ClientSideComponent.SPClientSideQueryStatus .....	933
3.2.5.348.1	Field Values.....	933
3.2.5.348.1.1	Success.....	933
3.2.5.348.1.2	ErrorNotFound.....	933
3.2.5.348.1.3	ErrorDisabled.....	933
3.2.5.348.1.4	ErrorInvalidManifest.....	933
3.2.5.348.1.5	ErrorCustomScriptDisabled.....	933
3.2.5.348.1.6	ErrorFeatureNotEnabled.....	933
3.2.5.349	Microsoft.SharePoint.Activities.ActivityCapabilities.....	934
3.2.5.349.1	Properties.....	934
3.2.5.349.1.1	Scalar Properties.....	934
3.2.5.349.1.2	ObjectPath Properties.....	934
3.2.5.350	Microsoft.SharePoint.Activities.ActivityClientIdentity.....	934
3.2.5.350.1	Properties.....	934
3.2.5.350.1.1	Scalar Properties.....	934
3.2.5.350.1.2	ObjectPath Properties.....	934
3.2.5.351	Microsoft.SharePoint.Activities.ActivityClientRequest.....	934
3.2.5.351.1	Properties.....	934
3.2.5.351.1.1	Scalar Properties.....	934
3.2.5.351.1.2	ObjectPath Properties.....	934
3.2.5.352	Microsoft.SharePoint.Activities.ActivityClientResponse .....	935
3.2.5.352.1	Properties.....	935
3.2.5.352.1.1	Scalar Properties.....	935
3.2.5.352.1.2	ObjectPath Properties.....	935
3.2.5.353	Microsoft.SharePoint.Activities.CommentFacet.....	935
3.2.5.353.1	Properties.....	935
3.2.5.353.1.1	Scalar Properties.....	935
3.2.5.353.1.1.1	commentText.....	935
3.2.5.353.1.1.2	parentAuthor.....	935

3.2.5.353.1.2	ObjectPath Properties	935
3.2.5.354	Microsoft.SharePoint.Activities.MentionFacet	935
3.2.5.354.1	Properties	936
3.2.5.354.1.1	Scalar Properties	936
3.2.5.354.1.2	ObjectPath Properties	936
3.2.5.355	Microsoft.SharePoint.Activities.RevisionInfo	936
3.2.5.355.1	Properties	936
3.2.5.355.1.1	Scalar Properties	936
3.2.5.355.1.2	ObjectPath Properties	936
3.2.5.356	Microsoft.SharePoint.Activities.RevisionSetFacet	936
3.2.5.356.1	Properties	936
3.2.5.356.1.1	Scalar Properties	936
3.2.5.356.1.2	ObjectPath Properties	936
3.2.5.357	Microsoft.SharePoint.Activities.SPActivityEntitySet	936
3.2.5.357.1	Properties	936
3.2.5.357.1.1	Scalar Properties	937
3.2.5.357.1.2	ObjectPath Properties	937
3.2.5.357.2	Methods	937
3.2.5.357.2.1	Scalar Methods	937
3.2.5.357.2.2	ObjectPath Methods	937
3.2.5.358	Microsoft.SharePoint.Activities.SPActivityResponseStatus	937
3.2.5.358.1	Field Values	937
3.2.5.359	Microsoft.SharePoint.Administration.AppSource	937
3.2.5.359.1	Field Values	937
3.2.5.359.1.1	InvalidSource	937
3.2.5.359.1.2	Marketplace	937
3.2.5.359.1.3	CorporateCatalog	937
3.2.5.359.1.4	DeveloperSite	938
3.2.5.359.1.5	ObjectModel	938
3.2.5.359.1.6	RemoteObjectModel	938
3.2.5.359.1.7	SiteCollectionCorporateCatalog	938
3.2.5.360	Microsoft.SharePoint.ApplicationPages.ClientPickerQuery.PeoplePickerQuerySettings	938
3.2.5.360.1	Properties	938
3.2.5.360.1.1	Scalar Properties	938
3.2.5.360.1.1.1	ExcludeAllUsersOnTenantClaim	938
3.2.5.360.1.1.2	IsSharing	938
3.2.5.360.1.2	ObjectPath Properties	938
3.2.5.361	Microsoft.SharePoint.ApplicationPages.ClientPickerQuery.PickerEntityInformation	939
3.2.5.361.1	Properties	939
3.2.5.361.1.1	Scalar Properties	939
3.2.5.361.1.1.1	Entity	939
3.2.5.361.1.1.2	TotalMemberCount	939
3.2.5.361.1.2	ObjectPath Properties	939
3.2.5.361.2	Methods	939
3.2.5.361.2.1	Scalar Methods	939
3.2.5.361.2.2	ObjectPath Methods	939
3.2.5.362	Microsoft.SharePoint.ApplicationPages.ClientPickerQuery.PickerEntityInformationRequest	939
3.2.5.362.1	Properties	939
3.2.5.362.1.1	Scalar Properties	939
3.2.5.362.1.1.1	EmailAddress	940
3.2.5.362.1.1.2	GroupId	940
3.2.5.362.1.1.3	Key	940

3.2.5.362.1.1.4	PrincipalType .....	940
3.2.5.362.1.2	ObjectPath Properties .....	940
3.2.5.363	Microsoft.SharePoint.Client.Alert .....	940
3.2.5.363.1	Properties .....	940
3.2.5.363.1.1	Scalar Properties .....	940
3.2.5.363.1.1.1	AlertFrequency .....	940
3.2.5.363.1.1.2	AlertTemplateName .....	941
3.2.5.363.1.1.3	AlertTime .....	941
3.2.5.363.1.1.4	AlertType .....	941
3.2.5.363.1.1.5	AlwaysNotify .....	941
3.2.5.363.1.1.6	DeliveryChannels .....	941
3.2.5.363.1.1.7	EventType .....	941
3.2.5.363.1.1.8	Filter .....	941
3.2.5.363.1.1.9	ID .....	942
3.2.5.363.1.1.10	ItemID .....	942
3.2.5.363.1.1.11	ListID .....	942
3.2.5.363.1.1.12	ListUrl .....	942
3.2.5.363.1.1.13	Properties .....	942
3.2.5.363.1.1.14	Status .....	942
3.2.5.363.1.1.15	Title .....	942
3.2.5.363.1.1.16	UserId .....	942
3.2.5.363.1.2	ObjectPath Properties .....	943
3.2.5.363.1.2.1	AllProperties .....	943
3.2.5.363.1.2.2	Item .....	943
3.2.5.363.1.2.3	List .....	943
3.2.5.363.1.2.4	User .....	943
3.2.5.363.2	Methods .....	943
3.2.5.363.2.1	Scalar Methods .....	943
3.2.5.363.2.1.1	UpdateAlert .....	943
3.2.5.363.2.2	ObjectPath Methods .....	943
3.2.5.364	Microsoft.SharePoint.Client.AlertCollection .....	943
3.2.5.364.1	Properties .....	944
3.2.5.364.1.1	Scalar Properties .....	944
3.2.5.364.1.2	ObjectPath Properties .....	944
3.2.5.364.2	Methods .....	944
3.2.5.364.2.1	Scalar Methods .....	944
3.2.5.364.2.1.1	Add .....	944
3.2.5.364.2.1.2	Contains .....	944
3.2.5.364.2.1.3	DeleteAlert .....	944
3.2.5.364.2.1.4	DeleteAlertAtIndex .....	944
3.2.5.364.2.2	ObjectPath Methods .....	945
3.2.5.364.2.2.1	GetById .....	945
3.2.5.365	Microsoft.SharePoint.Client.AlertCreationInformation .....	945
3.2.5.365.1	Properties .....	945
3.2.5.365.1.1	Scalar Properties .....	945
3.2.5.365.1.1.1	AlertFrequency .....	945
3.2.5.365.1.1.2	AlertTemplateName .....	945
3.2.5.365.1.1.3	AlertTime .....	945
3.2.5.365.1.1.4	AlertType .....	946
3.2.5.365.1.1.5	AlwaysNotify .....	946
3.2.5.365.1.1.6	DeliveryChannels .....	946
3.2.5.365.1.1.7	EventType .....	946
3.2.5.365.1.1.8	EventTypeBitmask .....	946
3.2.5.365.1.1.9	Filter .....	946
3.2.5.365.1.1.10	Properties .....	946
3.2.5.365.1.1.11	Status .....	946
3.2.5.365.1.1.12	Title .....	947
3.2.5.365.1.2	ObjectPath Properties .....	947

3.2.5.365.1.2.1	Item .....	947
3.2.5.365.1.2.2	List .....	947
3.2.5.365.1.2.3	User .....	947
3.2.5.366	Microsoft.SharePoint.Client.AlertDeliveryChannel .....	947
3.2.5.366.1	Field Values .....	947
3.2.5.366.1.1	Email.....	947
3.2.5.366.1.2	Sms .....	947
3.2.5.367	Microsoft.SharePoint.Client.AlertEventType .....	948
3.2.5.367.1	Field Values .....	948
3.2.5.367.1.1	AddObject.....	948
3.2.5.367.1.2	ModifyObject.....	948
3.2.5.367.1.3	DeleteObject .....	948
3.2.5.367.1.4	Discussion.....	948
3.2.5.367.1.5	All.....	948
3.2.5.368	Microsoft.SharePoint.Client.AlertFrequency .....	948
3.2.5.368.1	Field Values .....	948
3.2.5.368.1.1	Immediate .....	948
3.2.5.368.1.2	Daily .....	949
3.2.5.368.1.3	Weekly .....	949
3.2.5.369	Microsoft.SharePoint.Client.AlertStatus .....	949
3.2.5.369.1	Field Values .....	949
3.2.5.369.1.1	On .....	949
3.2.5.369.1.2	Off .....	949
3.2.5.369.1.3	Error .....	949
3.2.5.370	Microsoft.SharePoint.Client.AlertType .....	949
3.2.5.370.1	Field Values .....	949
3.2.5.370.1.1	List .....	949
3.2.5.370.1.2	Item.....	950
3.2.5.370.1.3	Custom.....	950
3.2.5.371	Microsoft.SharePoint.Client.AnonymousLinkType.....	950
3.2.5.371.1	Field Values .....	950
3.2.5.371.1.1	None .....	950
3.2.5.371.1.2	View.....	950
3.2.5.371.1.3	Edit.....	950
3.2.5.372	Microsoft.SharePoint.Client.APIHubConnector .....	950
3.2.5.372.1	Properties.....	950
3.2.5.372.1.1	Scalar Properties.....	950
3.2.5.372.1.2	ObjectPath Properties.....	951
3.2.5.372.2	Methods .....	951
3.2.5.372.2.1	Scalar Methods .....	951
3.2.5.372.2.2	ObjectPath Methods .....	951
3.2.5.372.2.2.1	CreateListItem .....	951
3.2.5.372.2.2.2	DeleteListItem .....	951
3.2.5.372.2.2.3	GetDeletedListItems .....	951
3.2.5.372.2.2.4	GetEntities.....	952
3.2.5.372.2.2.5	GetEntityValues.....	952
3.2.5.372.2.2.6	GetListItem .....	952
3.2.5.372.2.2.7	GetListItems .....	953
3.2.5.372.2.2.8	GetNewListItems.....	953
3.2.5.372.2.2.9	GetTableMetadata .....	953
3.2.5.372.2.2.10	GetTables.....	954
3.2.5.372.2.2.11	GetUpdatedListItems .....	954
3.2.5.372.2.2.12	ResolveEntityValue .....	954
3.2.5.372.2.2.13	SetApprovalStatus.....	955
3.2.5.372.2.2.14	UpdateListItem .....	955
3.2.5.373	Microsoft.SharePoint.Client.AppProperties .....	956
3.2.5.373.1	Properties.....	956
3.2.5.373.1.1	Scalar Properties.....	956

3.2.5.373.1.1.1	AppSettingsEnabled	956
3.2.5.373.1.1.2	Description	956
3.2.5.373.1.1.3	EulaUrl	956
3.2.5.373.1.1.4	IsAnonymous	956
3.2.5.373.1.1.5	IsDisabled	956
3.2.5.373.1.1.6	ManagedDeploymentEnabled	956
3.2.5.373.1.1.7	ManagePermissionsEnabled	957
3.2.5.373.1.1.8	ManageSeatsEnabled	957
3.2.5.373.1.1.9	MonitoringEnabled	957
3.2.5.373.1.1.10	Publisher	957
3.2.5.373.1.1.11	RemoveEnabled	957
3.2.5.373.1.1.12	SideLoadEnabled	957
3.2.5.373.1.1.13	SupportUrl	957
3.2.5.373.1.1.14	ViewInMarketPlaceEnabled	957
3.2.5.373.1.2	ObjectPath Properties	958
3.2.5.374	Microsoft.SharePoint.Client.AppSiteContext	958
3.2.5.374.1	Properties	958
3.2.5.374.1.1	Scalar Properties	958
3.2.5.374.1.1.1	SiteUrl	958
3.2.5.374.1.2	ObjectPath Properties	958
3.2.5.375	Microsoft.SharePoint.Client.AppSiteContextUtility	958
3.2.5.375.1	Properties	958
3.2.5.375.1.1	Scalar Properties	958
3.2.5.375.1.2	ObjectPath Properties	958
3.2.5.375.2	Methods	958
3.2.5.375.2.1	Scalar Methods	958
3.2.5.375.2.1.1	GetAppSiteContextCollection	958
3.2.5.375.2.2	ObjectPath Methods	959
3.2.5.376	Microsoft.SharePoint.Client.AppStatus	959
3.2.5.376.1	Field Values	959
3.2.5.376.1.1	InvalidStatus	959
3.2.5.376.1.2	Installing	959
3.2.5.376.1.3	Canceling	959
3.2.5.376.1.4	Uninstalling	959
3.2.5.376.1.5	Installed	959
3.2.5.376.1.6	Upgrading	959
3.2.5.376.1.7	Initialized	960
3.2.5.376.1.8	UpgradeCanceling	960
3.2.5.376.1.9	Disabling	960
3.2.5.376.1.10	Disabled	960
3.2.5.376.1.11	SecretRolling	960
3.2.5.376.1.12	Recycling	960
3.2.5.376.1.13	Recycled	960
3.2.5.376.1.14	Restoring	960
3.2.5.376.1.15	RestoreCanceling	960
3.2.5.377	Microsoft.SharePoint.Client.AppTileProperties	960
3.2.5.377.1	Properties	961
3.2.5.377.1.1	Scalar Properties	961
3.2.5.377.1.2	ObjectPath Properties	961
3.2.5.377.2	Methods	961
3.2.5.377.2.1	Scalar Methods	961
3.2.5.377.2.1.1	GetAppProperties	961
3.2.5.377.2.2	ObjectPath Methods	961
3.2.5.378	Microsoft.SharePoint.Client.AppViewCreationInfo	962
3.2.5.378.1	Properties	962
3.2.5.378.1.1	Scalar Properties	962
3.2.5.378.1.2	ObjectPath Properties	962
3.2.5.379	Microsoft.SharePoint.Client.CheckedOutFile	962

3.2.5.379.1	Properties.....	962
3.2.5.379.1.1	Scalar Properties.....	962
3.2.5.379.1.1.1	CheckedOutById .....	962
3.2.5.379.1.1.2	ServerRelativePath .....	962
3.2.5.379.1.2	ObjectPath Properties .....	962
3.2.5.379.1.2.1	CheckedOutBy .....	962
3.2.5.379.2	Methods.....	962
3.2.5.379.2.1	Scalar Methods.....	963
3.2.5.379.2.1.1	TakeOverCheckOut.....	963
3.2.5.379.2.2	ObjectPath Methods .....	963
3.2.5.380	Microsoft.SharePoint.Client.CheckedOutFileCollection .....	963
3.2.5.380.1	Properties.....	963
3.2.5.380.1.1	Scalar Properties.....	963
3.2.5.380.1.2	ObjectPath Properties.....	963
3.2.5.380.2	Methods.....	963
3.2.5.380.2.1	Scalar Methods.....	963
3.2.5.380.2.2	ObjectPath Methods .....	963
3.2.5.380.2.2.1	GetByPath .....	963
3.2.5.381	Microsoft.SharePoint.Client.ClientWebPart.....	963
3.2.5.381.1	Properties.....	964
3.2.5.381.1.1	Scalar Properties.....	964
3.2.5.381.1.1.1	Id.....	964
3.2.5.381.1.1.2	Name.....	964
3.2.5.381.1.2	ObjectPath Properties.....	964
3.2.5.381.2	Methods.....	964
3.2.5.381.2.1	Scalar Methods.....	964
3.2.5.381.2.1.1	Render.....	964
3.2.5.381.2.2	ObjectPath Methods .....	965
3.2.5.382	Microsoft.SharePoint.Client.ClientWebPartCollection .....	965
3.2.5.382.1	Properties.....	965
3.2.5.382.1.1	Scalar Properties.....	965
3.2.5.382.1.2	ObjectPath Properties.....	965
3.2.5.382.2	Methods.....	965
3.2.5.382.2.1	Scalar Methods.....	965
3.2.5.382.2.2	ObjectPath Methods .....	965
3.2.5.382.2.2.1	GetById .....	965
3.2.5.383	Microsoft.SharePoint.Client.ConnectorResult.....	965
3.2.5.383.1	Properties.....	965
3.2.5.383.1.1	Scalar Properties.....	965
3.2.5.383.1.1.1	ContextData .....	966
3.2.5.383.1.1.2	Value .....	966
3.2.5.383.1.2	ObjectPath Properties.....	966
3.2.5.383.2	Methods.....	966
3.2.5.383.2.1	Scalar Methods.....	966
3.2.5.383.2.2	ObjectPath Methods .....	966
3.2.5.384	Microsoft.SharePoint.Client.CopyJobProgress.....	966
3.2.5.384.1	Properties.....	966
3.2.5.384.1.1	Scalar Properties.....	966
3.2.5.384.1.2	ObjectPath Properties.....	966
3.2.5.385	Microsoft.SharePoint.Client.CopyMigrationInfo .....	966
3.2.5.385.1	Properties.....	966
3.2.5.385.1.1	Scalar Properties.....	967
3.2.5.385.1.2	ObjectPath Properties.....	967
3.2.5.386	Microsoft.SharePoint.Client.CopyMigrationOptions .....	967
3.2.5.386.1	Properties.....	967
3.2.5.386.1.1	Scalar Properties.....	967
3.2.5.386.1.2	ObjectPath Properties.....	967
3.2.5.387	Microsoft.SharePoint.Client.CurrencyInformation .....	967

3.2.5.387.1	Properties.....	967
3.2.5.387.1.1	Scalar Properties.....	967
3.2.5.387.1.1.1	DisplayString .....	967
3.2.5.387.1.1.2	LCID .....	967
3.2.5.387.1.2	ObjectPath Properties .....	967
3.2.5.388	Microsoft.SharePoint.Client.CurrencyInformationCollection .....	968
3.2.5.388.1	Properties.....	968
3.2.5.388.1.1	Scalar Properties.....	968
3.2.5.388.1.2	ObjectPath Properties .....	968
3.2.5.389	Microsoft.SharePoint.Client.CurrencyList .....	968
3.2.5.389.1	Properties.....	968
3.2.5.389.1.1	Scalar Properties.....	968
3.2.5.389.1.2	ObjectPath Properties .....	968
3.2.5.389.2	Methods .....	968
3.2.5.389.2.1	Scalar Methods .....	968
3.2.5.389.2.1.1	GetList .....	968
3.2.5.389.2.2	ObjectPath Methods .....	968
3.2.5.390	Microsoft.SharePoint.Client.CustomActionElement .....	969
3.2.5.390.1	Properties.....	969
3.2.5.390.1.1	Scalar Properties.....	969
3.2.5.390.1.1.1	ClientSideComponentId .....	969
3.2.5.390.1.1.2	ClientSideComponentProperties.....	969
3.2.5.390.1.1.3	CommandUIExtension .....	969
3.2.5.390.1.1.4	EnabledScript.....	969
3.2.5.390.1.1.5	ImageUrl.....	969
3.2.5.390.1.1.6	Location .....	969
3.2.5.390.1.1.7	RegistrationId .....	970
3.2.5.390.1.1.8	RegistrationType .....	970
3.2.5.390.1.1.9	RequireSiteAdministrator.....	970
3.2.5.390.1.1.10	Rights .....	970
3.2.5.390.1.1.11	Title .....	970
3.2.5.390.1.1.12	UrlAction .....	970
3.2.5.390.1.2	ObjectPath Properties .....	970
3.2.5.391	Microsoft.SharePoint.Client.CustomActionElementCollection .....	971
3.2.5.391.1	Properties.....	971
3.2.5.391.1.1	Scalar Properties.....	971
3.2.5.391.1.2	ObjectPath Properties .....	971
3.2.5.392	Microsoft.SharePoint.Client.CustomerKeyInfo .....	971
3.2.5.392.1	Properties.....	971
3.2.5.392.1.1	Scalar Properties.....	971
3.2.5.392.1.2	ObjectPath Properties .....	971
3.2.5.393	Microsoft.SharePoint.Client.CustomerKeyStatus .....	971
3.2.5.393.1	Field Values .....	971
3.2.5.394	Microsoft.SharePoint.Client.CustomerKeyStatusInfo .....	971
3.2.5.394.1	Properties.....	971
3.2.5.394.1.1	Scalar Properties.....	972
3.2.5.394.1.2	ObjectPath Properties .....	972
3.2.5.395	Microsoft.SharePoint.Client.CustomerKeyVaultInfo .....	972
3.2.5.395.1	Properties.....	972
3.2.5.395.1.1	Scalar Properties.....	972
3.2.5.395.1.2	ObjectPath Properties .....	972
3.2.5.396	Microsoft.SharePoint.Client.CustomerKeyVaultKeyType .....	972
3.2.5.396.1	Field Values .....	972
3.2.5.397	Microsoft.SharePoint.Client.EncryptionOption .....	972
3.2.5.397.1	Properties.....	972
3.2.5.397.1.1	Scalar Properties.....	972
3.2.5.397.1.2	ObjectPath Properties .....	972
3.2.5.398	Microsoft.SharePoint.Client.FileCollectionAddParameters .....	973



3.2.5.398.1	Properties.....	973
3.2.5.398.1.1	Scalar Properties.....	973
3.2.5.398.1.1.1	Overwrite .....	973
3.2.5.398.1.2	ObjectPath Properties.....	973
3.2.5.399	Microsoft.SharePoint.Client.FileVersionEvent .....	973
3.2.5.399.1	Properties.....	973
3.2.5.399.1.1	Scalar Properties.....	973
3.2.5.399.1.1.1	Editor.....	973
3.2.5.399.1.1.2	EditorEmail .....	973
3.2.5.399.1.1.3	EventType .....	973
3.2.5.399.1.1.4	SharedByUser .....	974
3.2.5.399.1.1.5	SharedWithUsers.....	974
3.2.5.399.1.1.6	Time.....	974
3.2.5.399.1.2	ObjectPath Properties.....	974
3.2.5.399.2	Methods.....	974
3.2.5.399.2.1	Scalar Methods.....	974
3.2.5.399.2.2	ObjectPath Methods .....	974
3.2.5.400	Microsoft.SharePoint.Client.FileVersionEventCollection .....	974
3.2.5.400.1	Properties.....	974
3.2.5.400.1.1	Scalar Properties.....	974
3.2.5.400.1.2	ObjectPath Properties.....	974
3.2.5.400.2	Methods .....	974
3.2.5.400.2.1	Scalar Methods.....	975
3.2.5.400.2.2	ObjectPath Methods .....	975
3.2.5.401	Microsoft.SharePoint.Client.FileVersionEventType.....	975
3.2.5.401.1	Field Values .....	975
3.2.5.401.1.1	Share .....	975
3.2.5.401.1.2	Rename .....	975
3.2.5.401.1.3	Restore.....	975
3.2.5.401.1.4	MaxServerType.....	975
3.2.5.401.1.5	FromClient .....	975
3.2.5.402	Microsoft.SharePoint.Client.FlowSynchronizationResult .....	975
3.2.5.402.1	Properties.....	975
3.2.5.402.1.1	Scalar Properties.....	976
3.2.5.402.1.2	ObjectPath Properties.....	976
3.2.5.402.2	Methods .....	976
3.2.5.402.2.1	Scalar Methods.....	976
3.2.5.402.2.2	ObjectPath Methods .....	976
3.2.5.403	Microsoft.SharePoint.Client.FlowSynchronizationStatus .....	976
3.2.5.403.1	Field Values .....	976
3.2.5.404	Microsoft.SharePoint.Client.FolderCollectionAddParameters .....	976
3.2.5.404.1	Properties.....	976
3.2.5.404.1.1	Scalar Properties.....	976
3.2.5.404.1.1.1	Overwrite .....	976
3.2.5.404.1.2	ObjectPath Properties.....	976
3.2.5.405	Microsoft.SharePoint.Client.FormRenderMode .....	976
3.2.5.405.1	Field Values .....	977
3.2.5.405.1.1	Classic.....	977
3.2.5.405.1.2	Modern .....	977
3.2.5.405.1.3	Customized .....	977
3.2.5.406	Microsoft.SharePoint.Client.Hashtag .....	977
3.2.5.406.1	Properties.....	977
3.2.5.406.1.1	Scalar Properties.....	977
3.2.5.406.1.2	ObjectPath Properties.....	977
3.2.5.407	Microsoft.SharePoint.Client.LanguageCollection .....	977
3.2.5.407.1	Properties.....	977
3.2.5.407.1.1	Scalar Properties.....	977
3.2.5.407.1.2	ObjectPath Properties.....	977

3.2.5.407.2	Methods	978
3.2.5.407.2.1	Scalar Methods	978
3.2.5.407.2.2	ObjectPath Methods	978
3.2.5.408	Microsoft.SharePoint.Client.ListBloomFilter	978
3.2.5.408.1	Properties	978
3.2.5.408.1.1	Scalar Properties	978
3.2.5.408.1.1.1	BloomFilterSize	978
3.2.5.408.1.1.2	FalsePositiveRate	978
3.2.5.408.1.1.3	HashedValueSet	978
3.2.5.408.1.1.4	IndexMap	978
3.2.5.408.1.1.5	ItemProcessedCount	978
3.2.5.408.1.1.6	K	979
3.2.5.408.1.1.7	LastListItemIdProcessed	979
3.2.5.408.1.1.8	MaxItemCount	979
3.2.5.408.1.2	ObjectPath Properties	979
3.2.5.408.2	Methods	979
3.2.5.408.2.1	Scalar Methods	979
3.2.5.408.2.2	ObjectPath Methods	979
3.2.5.409	Microsoft.SharePoint.Client.ListExperience	979
3.2.5.409.1	Field Values	979
3.2.5.409.1.1	Auto	979
3.2.5.409.1.2	NewExperience	980
3.2.5.409.1.3	ClassicExperience	980
3.2.5.410	Microsoft.SharePoint.Client.ListItemCreationInformationUsingPath	980
3.2.5.410.1	Properties	980
3.2.5.410.1.1	Scalar Properties	980
3.2.5.410.1.1.1	FolderPath	980
3.2.5.410.1.1.2	LeafName	980
3.2.5.410.1.1.3	UnderlyingObjectType	980
3.2.5.410.1.2	ObjectPath Properties	981
3.2.5.411	Microsoft.SharePoint.Client.ListItemVersion	981
3.2.5.411.1	Properties	981
3.2.5.411.1.1	Scalar Properties	981
3.2.5.411.1.1.1	Created	981
3.2.5.411.1.1.2	IsCurrentVersion	981
3.2.5.411.1.1.3	VersionId	981
3.2.5.411.1.1.4	VersionLabel	981
3.2.5.411.1.2	ObjectPath Properties	981
3.2.5.411.1.2.1	CreatedBy	981
3.2.5.411.1.2.2	Fields	982
3.2.5.411.1.2.3	FileVersion	982
3.2.5.411.2	Methods	982
3.2.5.411.2.1	Scalar Methods	982
3.2.5.411.2.1.1	DeleteObject	982
3.2.5.411.2.2	ObjectPath Methods	982
3.2.5.412	Microsoft.SharePoint.Client.ListItemVersionCollection	982
3.2.5.412.1	Properties	982
3.2.5.412.1.1	Scalar Properties	982
3.2.5.412.1.2	ObjectPath Properties	983
3.2.5.412.2	Methods	983
3.2.5.412.2.1	Scalar Methods	983
3.2.5.412.2.2	ObjectPath Methods	983
3.2.5.412.2.2.1	GetById	983
3.2.5.413	Microsoft.SharePoint.Client.ListPageRenderType	983
3.2.5.413.1	Field Values	983
3.2.5.413.1.1	Undefined	983
3.2.5.413.1.2	MultipleWePart	983
3.2.5.413.1.3	JSLinkCustomization	983

3.2.5.413.1.4	XsLinkCustomization.....	983
3.2.5.413.1.5	NoSPList.....	984
3.2.5.413.1.6	HasBusinessDataField.....	984
3.2.5.413.1.7	HasTaskOutcomeField.....	984
3.2.5.413.1.8	HasPublishingfield.....	984
3.2.5.413.1.9	HasGeolocationField.....	984
3.2.5.413.1.10	HasCustomActionWithCode.....	984
3.2.5.413.1.11	HasMetadataNavFeature.....	984
3.2.5.413.1.12	SpecialViewType.....	984
3.2.5.413.1.13	ListTypeNoSupportForModernMode.....	984
3.2.5.413.1.14	AnonymousUser.....	984
3.2.5.413.1.15	ListSettingOff.....	985
3.2.5.413.1.16	SiteSettingOff.....	985
3.2.5.413.1.17	WebSettingOff.....	985
3.2.5.413.1.18	TenantSettingOff.....	985
3.2.5.413.1.19	CustomizedForm.....	985
3.2.5.413.1.20	DocLibNewForm.....	985
3.2.5.413.1.21	UnsupportedFieldTypeInForm.....	985
3.2.5.413.1.22	InvalidFieldTypeInForm.....	985
3.2.5.413.1.23	InvalidControModeInForm.....	985
3.2.5.413.1.24	CustomizedPage.....	985
3.2.5.413.1.25	ListTemplateNotSupported.....	986
3.2.5.413.1.26	WikiPage.....	986
3.2.5.413.1.27	DropOffLibrary.....	986
3.2.5.413.1.28	IsUnghosted.....	986
3.2.5.413.1.29	Modern.....	986
3.2.5.414	Microsoft.SharePoint.Client.MigrationNameConflictBehavior.....	986
3.2.5.414.1	Field Values.....	986
3.2.5.415	Microsoft.SharePoint.Client.MoveCopyOptions.....	986
3.2.5.415.1	Properties.....	986
3.2.5.415.1.1	Scalar Properties.....	986
3.2.5.415.1.2	ObjectPath Properties.....	987
3.2.5.416	Microsoft.SharePoint.Client.ProvisionedMigrationContainersInfo.....	987
3.2.5.416.1	Properties.....	987
3.2.5.416.1.1	Scalar Properties.....	987
3.2.5.416.1.2	ObjectPath Properties.....	987
3.2.5.417	Microsoft.SharePoint.Client.ProvisionedMigrationQueueInfo.....	987
3.2.5.417.1	Properties.....	987
3.2.5.417.1.1	Scalar Properties.....	987
3.2.5.417.1.2	ObjectPath Properties.....	987
3.2.5.418	Microsoft.SharePoint.Client.RecycleBinQueryInformation.....	987
3.2.5.418.1	Properties.....	987
3.2.5.418.1.1	Scalar Properties.....	987
3.2.5.418.1.1.1	IsAscending.....	987
3.2.5.418.1.1.2	ItemState.....	988
3.2.5.418.1.1.3	OrderBy.....	988
3.2.5.418.1.1.4	PagingInfo.....	988
3.2.5.418.1.1.5	RowLimit.....	988
3.2.5.418.1.1.6	ShowOnlyMyItems.....	988
3.2.5.418.1.2	ObjectPath Properties.....	988
3.2.5.419	Microsoft.SharePoint.Client.RenderListFormDataOptions.....	988
3.2.5.419.1	Field Values.....	988
3.2.5.419.1.1	None.....	988
3.2.5.419.1.2	ExcludeListSchema.....	989
3.2.5.419.1.3	IncludeAttachments.....	989
3.2.5.419.1.4	IncludeListViewData.....	989
3.2.5.419.1.5	IncludeAppendOnlyData.....	989
3.2.5.420	Microsoft.SharePoint.Client.ResourcePath.....	989

3.2.5.420.1	Properties.....	989
3.2.5.420.1.1	Scalar Properties.....	989
3.2.5.420.1.1.1	DecodedUrl.....	989
3.2.5.420.1.2	ObjectPath Properties.....	989
3.2.5.421	Microsoft.SharePoint.Client.ScriptSafeDomain .....	989
3.2.5.421.1	Properties.....	990
3.2.5.421.1.1	Scalar Properties.....	990
3.2.5.421.1.2	ObjectPath Properties.....	990
3.2.5.421.2	Methods .....	990
3.2.5.421.2.1	Scalar Methods .....	990
3.2.5.421.2.2	ObjectPath Methods .....	990
3.2.5.422	Microsoft.SharePoint.Client.ScriptSafeDomainEntityData .....	990
3.2.5.422.1	Properties.....	990
3.2.5.422.1.1	Scalar Properties.....	990
3.2.5.422.1.2	ObjectPath Properties.....	990
3.2.5.423	Microsoft.SharePoint.Client.ScriptSafeExternalEmbedding .....	990
3.2.5.423.1	Field Values .....	990
3.2.5.424	Microsoft.SharePoint.Client.SharedWithUser .....	990
3.2.5.424.1	Properties.....	991
3.2.5.424.1.1	Scalar Properties.....	991
3.2.5.424.1.1.1	Email .....	991
3.2.5.424.1.1.2	Name.....	991
3.2.5.424.1.2	ObjectPath Properties.....	991
3.2.5.425	Microsoft.SharePoint.Client.SharedWithUserCollection .....	991
3.2.5.425.1	Properties.....	991
3.2.5.425.1.1	Scalar Properties.....	991
3.2.5.425.1.2	ObjectPath Properties.....	991
3.2.5.426	Microsoft.SharePoint.Client.Sharing.AccessRequestSettings.....	991
3.2.5.426.1	Properties.....	991
3.2.5.426.1.1	Scalar Properties.....	991
3.2.5.426.1.1.1	hasPendingAccessRequests .....	991
3.2.5.426.1.1.2	pendingAccessRequestsLink .....	992
3.2.5.426.1.1.3	requiresAccessApproval.....	992
3.2.5.426.1.2	ObjectPath Properties.....	992
3.2.5.427	Microsoft.SharePoint.Client.Sharing.DirectSharingAbilities .....	992
3.2.5.427.1	Properties.....	992
3.2.5.427.1.1	Scalar Properties.....	992
3.2.5.427.1.1.1	canAddExternalPrincipal .....	992
3.2.5.427.1.1.2	canAddInternalPrincipal.....	992
3.2.5.427.1.1.3	canRequestGrantAccess .....	992
3.2.5.427.1.2	ObjectPath Properties.....	993
3.2.5.428	Microsoft.SharePoint.Client.Sharing.DomainRestrictionSettings .....	993
3.2.5.428.1	Properties.....	993
3.2.5.428.1.1	Scalar Properties.....	993
3.2.5.428.1.1.1	domainRestrictionMode .....	993
3.2.5.428.1.1.2	domainRestrictionModeAtSite .....	993
3.2.5.428.1.1.3	restrictedDomains .....	993
3.2.5.428.1.1.4	restrictedDomainsAtSite .....	993
3.2.5.428.1.2	ObjectPath Properties.....	993
3.2.5.429	Microsoft.SharePoint.Client.Sharing.EmailData.....	994
3.2.5.429.1	Properties.....	994
3.2.5.429.1.1	Scalar Properties.....	994
3.2.5.429.1.1.1	body .....	994
3.2.5.429.1.1.2	subject.....	994
3.2.5.429.1.2	ObjectPath Properties.....	994
3.2.5.430	Microsoft.SharePoint.Client.Sharing.EntityPermission.....	994
3.2.5.430.1	Properties.....	994
3.2.5.430.1.1	Scalar Properties.....	994

3.2.5.430.1.1.1	hasAccess.....	994
3.2.5.430.1.1.2	inputEntity.....	995
3.2.5.430.1.1.3	resolvedEntity.....	995
3.2.5.430.1.1.4	role .....	995
3.2.5.430.1.2	ObjectPath Properties.....	995
3.2.5.431	Microsoft.SharePoint.Client.Sharing.LinkInfo .....	995
3.2.5.431.1	Properties.....	995
3.2.5.431.1.1	Scalar Properties.....	995
3.2.5.431.1.1.1	isInherited.....	995
3.2.5.431.1.1.2	linkDetails .....	995
3.2.5.431.1.1.3	linkMembers .....	996
3.2.5.431.1.2	ObjectPath Properties.....	996
3.2.5.432	Microsoft.SharePoint.Client.Sharing.LinkInvitation.....	996
3.2.5.432.1	Properties.....	996
3.2.5.432.1.1	Scalar Properties.....	996
3.2.5.432.1.1.1	invitedBy.....	996
3.2.5.432.1.1.2	invitedOn .....	996
3.2.5.432.1.1.3	invitee .....	996
3.2.5.432.1.2	ObjectPath Properties.....	996
3.2.5.433	Microsoft.SharePoint.Client.Sharing.OversharedWebInfo .....	997
3.2.5.433.1	Properties.....	997
3.2.5.433.1.1	Scalar Properties.....	997
3.2.5.433.1.1.1	hasUniqueRoleAssignmentsForList .....	997
3.2.5.433.1.1.2	principals .....	997
3.2.5.433.1.2	ObjectPath Properties.....	997
3.2.5.434	Microsoft.SharePoint.Client.Sharing.PermissionCollection .....	997
3.2.5.434.1	Properties.....	997
3.2.5.434.1.1	Scalar Properties.....	997
3.2.5.434.1.1.1	links .....	997
3.2.5.434.1.1.2	principals .....	997
3.2.5.434.1.1.3	siteAdmins .....	998
3.2.5.434.1.2	ObjectPath Properties.....	998
3.2.5.435	Microsoft.SharePoint.Client.Sharing.PersonalWeb .....	998
3.2.5.435.1	Properties.....	998
3.2.5.435.1.1	Scalar Properties.....	998
3.2.5.435.1.2	ObjectPath Properties.....	998
3.2.5.435.2	Methods.....	998
3.2.5.435.2.1	Scalar Methods.....	998
3.2.5.435.2.1.1	FixPermissionInheritance.....	998
3.2.5.435.2.1.2	GetOversharedWebInfo .....	998
3.2.5.435.2.1.3	RemovePermissionForUsers .....	999
3.2.5.435.2.2	ObjectPath Methods .....	999
3.2.5.436	Microsoft.SharePoint.Client.Sharing.Principal .....	999
3.2.5.436.1	Properties.....	999
3.2.5.436.1.1	Scalar Properties.....	999
3.2.5.436.1.1.1	email .....	999
3.2.5.436.1.1.2	id .....	999
3.2.5.436.1.1.3	isActive .....	999
3.2.5.436.1.1.4	isExternal .....	1000
3.2.5.436.1.1.5	jobTitle .....	1000
3.2.5.436.1.1.6	loginName .....	1000
3.2.5.436.1.1.7	name .....	1000
3.2.5.436.1.1.8	principalType .....	1000
3.2.5.436.1.1.9	userId.....	1000
3.2.5.436.1.2	ObjectPath Properties.....	1000
3.2.5.437	Microsoft.SharePoint.Client.Sharing.PrincipalInfo .....	1000
3.2.5.437.1	Properties.....	1001
3.2.5.437.1.1	Scalar Properties.....	1001

3.2.5.437.1.1.1	principal	1001
3.2.5.437.1.1.2	role	1001
3.2.5.437.1.2	ObjectPath Properties	1001
3.2.5.438	Microsoft.SharePoint.Client.Sharing.Recipient	1001
3.2.5.438.1	Properties	1001
3.2.5.438.1.1	Scalar Properties	1001
3.2.5.438.1.1.1	alias	1001
3.2.5.438.1.1.2	email	1001
3.2.5.438.1.1.3	objectId	1001
3.2.5.438.1.2	ObjectPath Properties	1002
3.2.5.439	Microsoft.SharePoint.Client.Sharing.SecurableObjectExtensions	1002
3.2.5.439.1	Properties	1002
3.2.5.439.1.1	Scalar Properties	1002
3.2.5.439.1.2	ObjectPath Properties	1002
3.2.5.439.2	Methods	1002
3.2.5.439.2.1	Scalar Methods	1002
3.2.5.439.2.1.1	CheckPermissions	1002
3.2.5.439.2.1.2	DeleteLinkByKind	1002
3.2.5.439.2.1.3	ShareLink	1003
3.2.5.439.2.1.4	UnshareLink	1003
3.2.5.439.2.1.5	UpdateDocumentSharingInfo	1004
3.2.5.439.2.2	ObjectPath Methods	1005
3.2.5.439.2.2.1	ForwardObjectLink	1005
3.2.5.439.2.2.2	GetObjectSharingSettings	1005
3.2.5.439.2.2.3	GetSharingInformation	1006
3.2.5.439.2.2.4	ShareObject	1006
3.2.5.439.2.2.5	UnshareObject	1007
3.2.5.440	Microsoft.SharePoint.Client.Sharing.SharedDocInfoSet	1007
3.2.5.440.1	Properties	1007
3.2.5.440.1.1	Scalar Properties	1007
3.2.5.440.1.2	ObjectPath Properties	1007
3.2.5.440.2	Methods	1007
3.2.5.440.2.1	Scalar Methods	1007
3.2.5.440.2.2	ObjectPath Methods	1007
3.2.5.441	Microsoft.SharePoint.Client.Sharing.SharedObjectType	1007
3.2.5.441.1	Field Values	1008
3.2.5.441.1.1	Unknown	1008
3.2.5.441.1.2	File	1008
3.2.5.441.1.3	Folder	1008
3.2.5.441.1.4	Item	1008
3.2.5.441.1.5	List	1008
3.2.5.441.1.6	Web	1008
3.2.5.441.1.7	Max	1008
3.2.5.442	Microsoft.SharePoint.Client.Sharing.ShareLinkRequest	1008
3.2.5.442.1	Properties	1008
3.2.5.442.1.1	Scalar Properties	1008
3.2.5.442.1.1.1	createLink	1009
3.2.5.442.1.1.2	emailData	1009
3.2.5.442.1.1.3	expiration	1009
3.2.5.442.1.1.4	linkKind	1009
3.2.5.442.1.1.5	peoplePickerInput	1010
3.2.5.442.1.1.6	settings	1010
3.2.5.442.1.2	ObjectPath Properties	1010
3.2.5.443	Microsoft.SharePoint.Client.Sharing.ShareLinkResponse	1010
3.2.5.443.1	Properties	1010
3.2.5.443.1.1	Scalar Properties	1010
3.2.5.443.1.1.1	sharingLinkInfo	1010
3.2.5.443.1.2	ObjectPath Properties	1010

3.2.5.444	Microsoft.SharePoint.Client.Sharing.ShareLinkSettings	1011
3.2.5.444.1	Properties	1011
3.2.5.444.1.1	Scalar Properties	1011
3.2.5.444.1.1.1	allowAnonymousAccess	1011
3.2.5.444.1.1.2	expiration	1011
3.2.5.444.1.1.3	inviteesToRemove	1011
3.2.5.444.1.1.4	linkKind	1011
3.2.5.444.1.1.5	password	1011
3.2.5.444.1.1.6	restrictShareMembership	1012
3.2.5.444.1.1.7	role	1012
3.2.5.444.1.1.8	shareId	1012
3.2.5.444.1.1.9	updatePassword	1012
3.2.5.444.1.2	ObjectPath Properties	1012
3.2.5.445	Microsoft.SharePoint.Client.Sharing.SharingAbilities	1013
3.2.5.445.1	Properties	1013
3.2.5.445.1.1	Scalar Properties	1013
3.2.5.445.1.1.1	anonymousLinkAbilities	1013
3.2.5.445.1.1.2	directSharingAbilities	1013
3.2.5.445.1.1.3	organizationLinkAbilities	1013
3.2.5.445.1.1.4	peopleSharingLinkAbilities	1013
3.2.5.445.1.2	ObjectPath Properties	1013
3.2.5.446	Microsoft.SharePoint.Client.Sharing.SharingAbilityStatus	1013
3.2.5.446.1	Properties	1013
3.2.5.446.1.1	Scalar Properties	1014
3.2.5.446.1.1.1	disabledReason	1014
3.2.5.446.1.1.2	enabled	1014
3.2.5.446.1.2	ObjectPath Properties	1014
3.2.5.447	Microsoft.SharePoint.Client.Sharing.SharingCapabilityDisabledReason	1014
3.2.5.447.1	Field Values	1014
3.2.5.447.1.1	Unavailable	1014
3.2.5.447.1.2	None	1014
3.2.5.447.1.3	Disabled	1014
3.2.5.447.1.4	NotShareableByLink	1015
3.2.5.447.1.5	ParentListIsPrivate	1015
3.2.5.447.1.6	ParentListIsCatalogDocLib	1015
3.2.5.447.1.7	NotSupportedByWOPI	1015
3.2.5.447.1.8	IRMIsEnabled	1015
3.2.5.447.1.9	DocumentIsProtectedByDLP	1015
3.2.5.447.1.10	ForceCheckoutEditLink	1015
3.2.5.447.1.11	AnonymousEditLinkNotAllowedByTenant	1015
3.2.5.447.1.12	NonClaimsWebapp	1015
3.2.5.447.1.13	AccessDeniedToAnonGuest	1015
3.2.5.447.1.14	BlockedByWhoCanShareSettings	1016
3.2.5.447.1.15	BlockedByExternalShareSettings	1016
3.2.5.447.1.16	AccessDeniedNotEnoughPermissions	1016
3.2.5.447.1.17	AccessDeniedToExternalUser	1016
3.2.5.448	Microsoft.SharePoint.Client.Sharing.SharingDomainRestrictionMode	1016
3.2.5.448.1	Field Values	1016
3.2.5.448.1.1	None	1016
3.2.5.448.1.2	AllowList	1016
3.2.5.448.1.3	BlockList	1016
3.2.5.449	Microsoft.SharePoint.Client.Sharing.SharingInformation	1017
3.2.5.449.1	Properties	1017
3.2.5.449.1.1	Scalar Properties	1017
3.2.5.449.1.1.1	accessRequestSettings	1017
3.2.5.449.1.1.2	anonymousLinkExpirationRestrictionDays	1017
3.2.5.449.1.1.3	blockPeoplePickerAndSharing	1017
3.2.5.449.1.1.4	canAddExternalPrincipal	1017

3.2.5.449.1.1.5	canAddInternalPrincipal	1017
3.2.5.449.1.1.6	canRequestAccessForGrantAccess	1017
3.2.5.449.1.1.7	canSendEmail	1018
3.2.5.449.1.1.8	canUseSimplifiedRoles	1018
3.2.5.449.1.1.9	currentRole	1018
3.2.5.449.1.1.10	defaultLinkKind	1018
3.2.5.449.1.1.11	defaultShareLinkPermission	1018
3.2.5.449.1.1.12	directUrl	1018
3.2.5.449.1.1.13	domainRestrictionSettings	1018
3.2.5.449.1.1.14	hasUniquePermissions	1019
3.2.5.449.1.1.15	microserviceShareUiUrl	1019
3.2.5.449.1.1.16	permissionsInformation	1019
3.2.5.449.1.1.17	sharedObjectType	1019
3.2.5.449.1.1.18	shareUiUrl	1019
3.2.5.449.1.1.19	sharingAbilities	1019
3.2.5.449.1.1.20	sharingStatus	1019
3.2.5.449.1.1.21	showExternalSharingWarning	1019
3.2.5.449.1.1.22	webUrl	1020
3.2.5.449.1.2	ObjectPath Properties	1020
3.2.5.449.1.2.1	pickerSettings	1020
3.2.5.449.2	Methods	1020
3.2.5.449.2.1	Scalar Methods	1020
3.2.5.449.2.2	ObjectPath Methods	1020
3.2.5.450	Microsoft.SharePoint.Client.Sharing.SharingInformationRequest	1020
3.2.5.450.1	Properties	1020
3.2.5.450.1.1	Scalar Properties	1020
3.2.5.450.1.1.1	clientSupportedFeatures	1020
3.2.5.450.1.1.2	maxPrincipalsToReturn	1020
3.2.5.450.1.2	ObjectPath Properties	1021
3.2.5.451	Microsoft.SharePoint.Client.Sharing.SharingLinkAbilities	1021
3.2.5.451.1	Properties	1021
3.2.5.451.1.1	Scalar Properties	1021
3.2.5.451.1.1.1	canGetEditLink	1021
3.2.5.451.1.1.2	canGetReadLink	1021
3.2.5.451.1.1.3	canHaveExternalUsers	1021
3.2.5.451.1.1.4	canManageEditLink	1021
3.2.5.451.1.1.5	canManageReadLink	1021
3.2.5.451.1.1.6	linkExpiration	1022
3.2.5.451.1.1.7	passwordProtected	1022
3.2.5.451.1.2	ObjectPath Properties	1022
3.2.5.452	Microsoft.SharePoint.Client.Sharing.SharingLinkAccessRequest	1022
3.2.5.452.1	Properties	1022
3.2.5.452.1.1	Scalar Properties	1022
3.2.5.452.1.1.1	ensureAccess	1022
3.2.5.452.1.1.2	password	1022
3.2.5.452.1.2	ObjectPath Properties	1023
3.2.5.453	Microsoft.SharePoint.Client.Sharing.SharingLinkExpirationAbilityStatus	1023
3.2.5.453.1	Properties	1023
3.2.5.453.1.1	Scalar Properties	1023
3.2.5.453.1.1.1	defaultExpirationInDays	1023
3.2.5.453.1.1.2	disabledReason	1023
3.2.5.453.1.1.3	enabled	1023
3.2.5.453.1.2	ObjectPath Properties	1023
3.2.5.454	Microsoft.SharePoint.Client.Sharing.SharingLinkPasswordAbilityStatus	1024
3.2.5.454.1	Properties	1024
3.2.5.454.1.1	Scalar Properties	1024
3.2.5.454.1.1.1	disabledReason	1024
3.2.5.454.1.1.2	enabled	1024



3.2.5.454.1.2	ObjectPath Properties	1024
3.2.5.455	Microsoft.SharePoint.Client.Sharing.SharingStatus	1024
3.2.5.455.1	Field Values	1024
3.2.5.455.1.1	Unavailable	1024
3.2.5.455.1.2	Private	1024
3.2.5.455.1.3	Shared	1025
3.2.5.456	Microsoft.SharePoint.Client.Sharing.UserDirectoryInfo	1025
3.2.5.456.1	Properties	1025
3.2.5.456.1.1	Scalar Properties	1025
3.2.5.456.1.1.1	Name	1025
3.2.5.456.1.1.2	NetId	1025
3.2.5.456.1.1.3	PrimaryEmail	1025
3.2.5.456.1.1.4	PrincipalName	1025
3.2.5.456.1.2	ObjectPath Properties	1025
3.2.5.457	Microsoft.SharePoint.Client.SharingLinkData	1026
3.2.5.457.1	Properties	1026
3.2.5.457.1.1	Scalar Properties	1026
3.2.5.457.1.1.1	Expiration	1026
3.2.5.457.1.1.2	HasExternalGuestInvitees	1026
3.2.5.457.1.1.3	IsAnonymous	1026
3.2.5.457.1.1.4	IsFormsLink	1026
3.2.5.457.1.1.5	IsOriginatedFromSharingFlow	1027
3.2.5.457.1.1.6	IsReviewLink	1027
3.2.5.457.1.1.7	IsSharingLink	1027
3.2.5.457.1.1.8	IsWritable	1027
3.2.5.457.1.1.9	LinkKind	1027
3.2.5.457.1.1.10	ObjectType	1027
3.2.5.457.1.1.11	ObjectUniqueId	1028
3.2.5.457.1.1.12	RequiresPassword	1028
3.2.5.457.1.1.13	RestrictedShareMembership	1028
3.2.5.457.1.1.14	ShareId	1028
3.2.5.457.1.2	ObjectPath Properties	1028
3.2.5.458	Microsoft.SharePoint.Client.SharingState	1028
3.2.5.458.1	Field Values	1029
3.2.5.458.1.1	Unspecified	1029
3.2.5.458.1.2	On	1029
3.2.5.458.1.3	Off	1029
3.2.5.459	Microsoft.SharePoint.Client.SharingUtility	1029
3.2.5.459.1	Properties	1029
3.2.5.459.1.1	Scalar Properties	1029
3.2.5.459.1.2	ObjectPath Properties	1029
3.2.5.459.2	Methods	1029
3.2.5.459.2.1	Scalar Methods	1029
3.2.5.459.2.1.1	GetUserDirectoryInfoByEmail	1029
3.2.5.459.2.1.2	ValidateSameUserEmails	1030
3.2.5.459.2.2	ObjectPath Methods	1030
3.2.5.460	Microsoft.SharePoint.Client.ShowInFiltersPaneStatus	1030
3.2.5.460.1	Field Values	1030
3.2.5.460.1.1	Auto	1030
3.2.5.460.1.2	Pinned	1030
3.2.5.460.1.3	Removed	1030
3.2.5.461	Microsoft.SharePoint.Client.SP BingMapsInformation	1030
3.2.5.461.1	Properties	1031
3.2.5.461.1.1	Scalar Properties	1031
3.2.5.461.1.1.1	IsBlockedInCurrentRegion	1031
3.2.5.461.1.1.2	Key	1031
3.2.5.461.1.2	ObjectPath Properties	1031
3.2.5.461.2	Methods	1031

3.2.5.461.2.1	Scalar Methods .....	1031
3.2.5.461.2.2	ObjectPath Methods .....	1031
3.2.5.462	Microsoft.SharePoint.Client.SPChangeActivityType .....	1031
3.2.5.462.1	Field Values .....	1031
3.2.5.462.1.1	NoActivity .....	1031
3.2.5.462.1.2	Hashtag .....	1032
3.2.5.462.1.3	Spotlight .....	1032
3.2.5.462.1.4	Comment .....	1032
3.2.5.463	Microsoft.SharePoint.Client.SPOpenBinaryOptions .....	1032
3.2.5.463.1	Field Values .....	1032
3.2.5.463.1.1	None .....	1032
3.2.5.463.1.2	Unprotected .....	1032
3.2.5.463.1.3	SkipVirusScan .....	1032
3.2.5.463.1.4	MinimizeProcessing .....	1032
3.2.5.464	Microsoft.SharePoint.Client.SPScriptSafeDomainsCollection .....	1033
3.2.5.464.1	Properties .....	1033
3.2.5.464.1.1	Scalar Properties .....	1033
3.2.5.464.1.2	ObjectPath Properties .....	1033
3.2.5.464.2	Methods .....	1033
3.2.5.464.2.1	Scalar Methods .....	1033
3.2.5.464.2.2	ObjectPath Methods .....	1033
3.2.5.464.2.2.1	GetByDomainName .....	1033
3.2.5.465	Microsoft.SharePoint.Client.SPVariantThemeType .....	1033
3.2.5.465.1	Field Values .....	1033
3.2.5.466	Microsoft.SharePoint.Client.SPVirusCheckStatus .....	1033
3.2.5.466.1	Field Values .....	1034
3.2.5.466.1.1	Clean .....	1034
3.2.5.466.1.2	Infected .....	1034
3.2.5.466.1.3	InfectedCleanable .....	1034
3.2.5.466.1.4	Cleaned .....	1034
3.2.5.466.1.5	CleanFailed .....	1034
3.2.5.466.1.6	Deleted .....	1034
3.2.5.466.1.7	Timeout .....	1034
3.2.5.467	Microsoft.SharePoint.Client.TeamChannelManager .....	1034
3.2.5.467.1	Properties .....	1034
3.2.5.467.1.1	Scalar Properties .....	1034
3.2.5.467.1.2	ObjectPath Properties .....	1035
3.2.5.467.2	Methods .....	1035
3.2.5.467.2.1	Scalar Methods .....	1035
3.2.5.467.2.1.1	DemoteTeamChannelById .....	1035
3.2.5.467.2.1.2	DemoteTeamChannelByPath .....	1035
3.2.5.467.2.1.3	PromoteToTeamChannelById .....	1035
3.2.5.467.2.1.4	PromoteToTeamChannelByPath .....	1036
3.2.5.467.2.2	ObjectPath Methods .....	1036
3.2.5.467.2.2.1	AddTeamChannel .....	1036
3.2.5.468	Microsoft.SharePoint.Client.Utilities.FileHandlerWopiProperties .....	1036
3.2.5.468.1	Properties .....	1037
3.2.5.468.1.1	Scalar Properties .....	1037
3.2.5.468.1.2	ObjectPath Properties .....	1037
3.2.5.468.2	Methods .....	1037
3.2.5.468.2.1	Scalar Methods .....	1037
3.2.5.468.2.2	ObjectPath Methods .....	1037
3.2.5.469	Microsoft.SharePoint.Client.Utilities.JsonTheme .....	1037
3.2.5.469.1	Properties .....	1037
3.2.5.469.1.1	Scalar Properties .....	1037
3.2.5.469.1.2	ObjectPath Properties .....	1037
3.2.5.470	Microsoft.SharePoint.Client.Utilities.NewsItem .....	1037
3.2.5.470.1	Properties .....	1037

3.2.5.470.1.1	Scalar Properties.....	1037
3.2.5.470.1.1.1	backupPictureUrl .....	1037
3.2.5.470.1.1.2	caption.....	1038
3.2.5.470.1.1.3	fileExtension .....	1038
3.2.5.470.1.1.4	itemId.....	1038
3.2.5.470.1.1.5	newsType.....	1038
3.2.5.470.1.1.6	pictureAltText .....	1038
3.2.5.470.1.1.7	pictureUrl .....	1038
3.2.5.470.1.1.8	progId.....	1038
3.2.5.470.1.1.9	properties.....	1039
3.2.5.470.1.1.10	siteId .....	1039
3.2.5.470.1.1.11	title .....	1039
3.2.5.470.1.1.12	uniqueId .....	1039
3.2.5.470.1.1.13	url.....	1039
3.2.5.470.1.1.14	webId .....	1039
3.2.5.470.1.2	ObjectPath Properties.....	1039
3.2.5.471	Microsoft.SharePoint.Client.Utilities.NewsItemFlags .....	1039
3.2.5.471.1	Field Values .....	1040
3.2.5.471.1.1	None.....	1040
3.2.5.471.1.2	DefaultItem.....	1040
3.2.5.472	Microsoft.SharePoint.Client.Utilities.NewsItemMetaData .....	1040
3.2.5.472.1	Properties.....	1040
3.2.5.472.1.1	Scalar Properties.....	1040
3.2.5.472.1.1.1	fileExtension .....	1040
3.2.5.472.1.1.2	newsType.....	1040
3.2.5.472.1.1.3	progId.....	1040
3.2.5.472.1.1.4	siteId .....	1040
3.2.5.472.1.1.5	title .....	1041
3.2.5.472.1.1.6	uniqueId .....	1041
3.2.5.472.1.1.7	url.....	1041
3.2.5.472.1.1.8	webId .....	1041
3.2.5.472.1.2	ObjectPath Properties.....	1041
3.2.5.473	Microsoft.SharePoint.Client.Utilities.NewsType .....	1041
3.2.5.473.1	Field Values .....	1041
3.2.5.473.1.1	File .....	1041
3.2.5.473.1.2	Folder.....	1042
3.2.5.473.1.3	Link .....	1042
3.2.5.473.1.4	ListItem.....	1042
3.2.5.473.1.5	List .....	1042
3.2.5.473.1.6	DocumentLibrary .....	1042
3.2.5.474	Microsoft.SharePoint.Client.Utilities.NewsUtility.....	1042
3.2.5.474.1	Properties.....	1042
3.2.5.474.1.1	Scalar Properties.....	1042
3.2.5.474.1.2	ObjectPath Properties.....	1042
3.2.5.474.2	Methods .....	1042
3.2.5.474.2.1	Scalar Methods.....	1042
3.2.5.474.2.1.1	CreateOrUpdateNewsItem .....	1042
3.2.5.474.2.1.2	DeleteNewsItem.....	1043
3.2.5.474.2.1.3	GetMetadataForUrl .....	1043
3.2.5.474.2.2	ObjectPath Methods .....	1043
3.2.5.475	Microsoft.SharePoint.Client.Utilities.ShortcutLink .....	1043
3.2.5.475.1	Properties.....	1043
3.2.5.475.1.1	Scalar Properties.....	1044
3.2.5.475.1.2	ObjectPath Properties.....	1044
3.2.5.475.2	Methods .....	1044
3.2.5.475.2.1	Scalar Methods.....	1044
3.2.5.475.2.2	ObjectPath Methods .....	1044
3.2.5.475.2.2.1	GetShortcutLink .....	1044

3.2.5.476	Microsoft.SharePoint.Client.Utilities.ShortcutTargetInfo	1044
3.2.5.476.1	Properties	1044
3.2.5.476.1.1	Scalar Properties	1044
3.2.5.476.1.1.1	siteId	1044
3.2.5.476.1.1.2	uniqueId	1044
3.2.5.476.1.1.3	url	1045
3.2.5.476.1.1.4	webId	1045
3.2.5.476.1.2	ObjectPath Properties	1045
3.2.5.476.2	Methods	1045
3.2.5.476.2.1	Scalar Methods	1045
3.2.5.476.2.2	ObjectPath Methods	1045
3.2.5.477	Microsoft.SharePoint.Client.Utilities.SpotlightResult	1045
3.2.5.477.1	Properties	1045
3.2.5.477.1.1	Scalar Properties	1045
3.2.5.477.1.1.1	Order	1045
3.2.5.477.1.1.2	ResultCode	1046
3.2.5.477.1.2	ObjectPath Properties	1046
3.2.5.477.2	Methods	1046
3.2.5.477.2.1	Scalar Methods	1046
3.2.5.477.2.2	ObjectPath Methods	1046
3.2.5.478	Microsoft.SharePoint.Client.Utilities.SpotlightResultCode	1046
3.2.5.478.1	Field Values	1046
3.2.5.478.1.1	Success	1046
3.2.5.478.1.2	FolderDoesNotExist	1046
3.2.5.478.1.3	ItemDoesNotExist	1046
3.2.5.478.1.4	TooManyItems	1046
3.2.5.478.1.5	ItemNotInSpotlight	1047
3.2.5.478.1.6	InvalidArgument	1047
3.2.5.478.1.7	ServerError	1047
3.2.5.479	Microsoft.SharePoint.Client.Utilities.SPSocialSwitch	1047
3.2.5.479.1	Properties	1047
3.2.5.479.1.1	Scalar Properties	1047
3.2.5.479.1.2	ObjectPath Properties	1047
3.2.5.479.2	Methods	1047
3.2.5.479.2.1	Scalar Methods	1047
3.2.5.479.2.1.1	IsFollowingFeatureEnabled	1047
3.2.5.479.2.2	ObjectPath Methods	1047
3.2.5.480	Microsoft.SharePoint.Client.Utilities.ThemingOptions	1048
3.2.5.480.1	Properties	1048
3.2.5.480.1.1	Scalar Properties	1048
3.2.5.480.1.2	ObjectPath Properties	1048
3.2.5.481	Microsoft.SharePoint.Client.Utilities.UploadStatus	1048
3.2.5.481.1	Properties	1048
3.2.5.481.1.1	Scalar Properties	1048
3.2.5.481.1.1.1	ExpectedContentRange	1048
3.2.5.481.1.1.2	ExpirationDateTime	1048
3.2.5.481.1.1.3	UploadId	1048
3.2.5.481.1.2	ObjectPath Properties	1048
3.2.5.481.2	Methods	1049
3.2.5.481.2.1	Scalar Methods	1049
3.2.5.481.2.2	ObjectPath Methods	1049
3.2.5.482	Microsoft.SharePoint.Client.Utilities.WebAppExtUriPair	1049
3.2.5.482.1	Properties	1049
3.2.5.482.1.1	Scalar Properties	1049
3.2.5.482.1.1.1	Ext	1049
3.2.5.482.1.1.2	WacUrl	1049
3.2.5.482.1.2	ObjectPath Properties	1049
3.2.5.483	Microsoft.SharePoint.Client.Utilities.WebAppUrlsByAction	1049

3.2.5.483.1	Properties.....	1049
3.2.5.483.1.1	Scalar Properties.....	1049
3.2.5.483.1.2	ObjectPath Properties.....	1049
3.2.5.484	Microsoft.SharePoint.Client.Utilities.WopiWebAppProperties.....	1050
3.2.5.484.1	Properties.....	1050
3.2.5.484.1.1	Scalar Properties.....	1050
3.2.5.484.1.2	ObjectPath Properties.....	1050
3.2.5.485	Microsoft.SharePoint.Client.Visualization.....	1050
3.2.5.485.1	Properties.....	1050
3.2.5.485.1.1	Scalar Properties.....	1050
3.2.5.485.1.2	ObjectPath Properties.....	1050
3.2.5.486	Microsoft.SharePoint.Client.VisualizationAppInfo.....	1050
3.2.5.486.1	Properties.....	1050
3.2.5.486.1.1	Scalar Properties.....	1050
3.2.5.486.1.2	ObjectPath Properties.....	1050
3.2.5.487	Microsoft.SharePoint.Client.VisualizationAppMappedViewCollection.....	1051
3.2.5.487.1	Properties.....	1051
3.2.5.487.1.1	Scalar Properties.....	1051
3.2.5.487.1.2	ObjectPath Properties.....	1051
3.2.5.487.2	Methods.....	1051
3.2.5.487.2.1	Scalar Methods.....	1051
3.2.5.487.2.2	ObjectPath Methods.....	1051
3.2.5.488	Microsoft.SharePoint.Client.VisualizationAppSynchronizationResult.....	1051
3.2.5.488.1	Properties.....	1051
3.2.5.488.1.1	Scalar Properties.....	1051
3.2.5.488.1.2	ObjectPath Properties.....	1051
3.2.5.488.2	Methods.....	1051
3.2.5.488.2.1	Scalar Methods.....	1051
3.2.5.488.2.2	ObjectPath Methods.....	1051
3.2.5.489	Microsoft.SharePoint.Client.VisualizationAppSynchronizationStatus.....	1052
3.2.5.489.1	Field Values.....	1052
3.2.5.490	Microsoft.SharePoint.Client.VisualizationAppTarget.....	1052
3.2.5.490.1	Field Values.....	1052
3.2.5.491	Microsoft.SharePoint.Client.VisualizationField.....	1052
3.2.5.491.1	Properties.....	1052
3.2.5.491.1.1	Scalar Properties.....	1052
3.2.5.491.1.1.1	InternalName.....	1052
3.2.5.491.1.1.2	Style.....	1052
3.2.5.491.1.2	ObjectPath Properties.....	1052
3.2.5.492	Microsoft.SharePoint.Client.VisualizationStyleSet.....	1053
3.2.5.492.1	Properties.....	1053
3.2.5.492.1.1	Scalar Properties.....	1053
3.2.5.492.1.2	ObjectPath Properties.....	1053
3.2.5.493	Microsoft.SharePoint.Client.VisualizationType.....	1053
3.2.5.493.1	Field Values.....	1053
3.2.5.493.1.1	Standard.....	1053
3.2.5.493.1.2	Custom.....	1053
3.2.5.494	Microsoft.SharePoint.Client.WebParts.WebPartExportMode.....	1053
3.2.5.494.1	Field Values.....	1053
3.2.5.494.1.1	None.....	1053
3.2.5.494.1.2	All.....	1053
3.2.5.494.1.3	NonSensitiveData.....	1054
3.2.5.495	Microsoft.SharePoint.ClientSideComponent.SPClientSideComponentIdentifier.....	1054
3.2.5.495.1	Properties.....	1054
3.2.5.495.1.1	Scalar Properties.....	1054
3.2.5.495.1.1.1	id.....	1054
3.2.5.495.1.1.2	version.....	1054

3.2.5.495.1.2	ObjectPath Properties	1054
3.2.5.496	Microsoft.SharePoint.ClientSideComponent.SPExtensionType	1054
3.2.5.496.1	Field Values	1054
3.2.5.496.1.1	Unknown	1054
3.2.5.496.1.2	FieldCustomizer	1055
3.2.5.496.1.3	ApplicationCustomizer	1055
3.2.5.496.1.4	ListViewCommandSet	1055
3.2.5.497	Microsoft.SharePoint.ClientSideComponent.StorageEntity	1055
3.2.5.497.1	Properties	1055
3.2.5.497.1.1	Scalar Properties	1055
3.2.5.497.1.1.1	Comment	1055
3.2.5.497.1.1.2	Description	1055
3.2.5.497.1.1.3	Value	1055
3.2.5.497.1.2	ObjectPath Properties	1055
3.2.5.497.2	Methods	1056
3.2.5.497.2.1	Scalar Methods	1056
3.2.5.497.2.2	ObjectPath Methods	1056
3.2.5.498	Microsoft.SharePoint.Comments.CommentsDisabledScope	1056
3.2.5.498.1	Field Values	1056
3.2.5.499	Microsoft.SharePoint.Internal.ActivityLogger	1056
3.2.5.499.1	Properties	1056
3.2.5.499.1.1	Scalar Properties	1056
3.2.5.499.1.2	ObjectPath Properties	1056
3.2.5.499.2	Methods	1056
3.2.5.499.2.1	Scalar Methods	1056
3.2.5.499.2.2	ObjectPath Methods	1056
3.2.5.500	Microsoft.SharePoint.Internal.ClientSideComponent.ComponentContextInfo	1056
3.2.5.500.1	Properties	1057
3.2.5.500.1.1	Scalar Properties	1057
3.2.5.500.1.1.1	SerializedData	1057
3.2.5.500.1.2	ObjectPath Properties	1057
3.2.5.500.2	Methods	1057
3.2.5.500.2.1	Scalar Methods	1057
3.2.5.500.2.2	ObjectPath Methods	1057
3.2.5.500.2.2.1	CSOM Constructor	1057
3.2.5.501	Microsoft.SharePoint.Likes.likedByInformation	1057
3.2.5.501.1	Properties	1057
3.2.5.501.1.1	Scalar Properties	1057
3.2.5.501.1.1.1	isLikedByUser	1057
3.2.5.501.1.1.2	likeCount	1057
3.2.5.501.1.2	ObjectPath Properties	1058
3.2.5.501.1.2.1	likedBy	1058
3.2.5.501.2	Methods	1058
3.2.5.501.2.1	Scalar Methods	1058
3.2.5.501.2.2	ObjectPath Methods	1058
3.2.5.502	Microsoft.SharePoint.Likes.LikeEntitySet	1058
3.2.5.502.1	Properties	1058
3.2.5.502.1.1	Scalar Properties	1058
3.2.5.502.1.2	ObjectPath Properties	1058
3.2.5.502.2	Methods	1058
3.2.5.502.2.1	Scalar Methods	1058
3.2.5.502.2.2	ObjectPath Methods	1058
3.2.5.503	Microsoft.SharePoint.Likes.LikesAPI	1059
3.2.5.503.1	Properties	1059
3.2.5.503.1.1	Scalar Properties	1059
3.2.5.503.1.2	ObjectPath Properties	1059
3.2.5.503.2	Methods	1059
3.2.5.503.2.1	Scalar Methods	1059

3.2.5.503.2.1.1	Like .....	1059
3.2.5.503.2.1.2	Unlike .....	1059
3.2.5.503.2.2	ObjectPath Methods .....	1059
3.2.5.503.2.2.1	likedBy.....	1059
3.2.5.504	Microsoft.SharePoint.Likes.userEntity .....	1060
3.2.5.504.1	Properties.....	1060
3.2.5.504.1.1	Scalar Properties.....	1060
3.2.5.504.1.1.1	creationDate .....	1060
3.2.5.504.1.1.2	email .....	1060
3.2.5.504.1.1.3	id .....	1060
3.2.5.504.1.1.4	loginName .....	1060
3.2.5.504.1.1.5	name .....	1060
3.2.5.504.1.2	ObjectPath Properties.....	1061
3.2.5.504.2	Methods .....	1061
3.2.5.504.2.1	Scalar Methods.....	1061
3.2.5.504.2.2	ObjectPath Methods .....	1061
3.2.5.505	Microsoft.SharePoint.Marketplace.CorporateCuratedGallery.CorporateCatalogAppMetadata.....	1061
3.2.5.505.1	Properties.....	1061
3.2.5.505.1.1	Scalar Properties.....	1061
3.2.5.505.1.1.1	AppCatalogVersion .....	1061
3.2.5.505.1.1.2	CanUpgrade.....	1061
3.2.5.505.1.1.3	CurrentVersionDeployed .....	1061
3.2.5.505.1.1.4	Deployed.....	1062
3.2.5.505.1.1.5	ID .....	1062
3.2.5.505.1.1.6	InstalledVersion .....	1062
3.2.5.505.1.1.7	IsClientSideSolution.....	1062
3.2.5.505.1.1.8	Title.....	1062
3.2.5.505.1.2	ObjectPath Properties.....	1062
3.2.5.505.2	Methods .....	1062
3.2.5.505.2.1	Scalar Methods.....	1062
3.2.5.505.2.1.1	Deploy .....	1062
3.2.5.505.2.1.2	Install .....	1063
3.2.5.505.2.1.3	Remove .....	1063
3.2.5.505.2.1.4	Retract.....	1063
3.2.5.505.2.1.5	Uninstall.....	1063
3.2.5.505.2.1.6	Upgrade.....	1063
3.2.5.505.2.2	ObjectPath Methods .....	1063
3.2.5.506	Microsoft.SharePoint.Marketplace.CorporateCuratedGallery.CorporateCatalogAppMetadataCollection .....	1063
3.2.5.506.1	Properties.....	1063
3.2.5.506.1.1	Scalar Properties.....	1063
3.2.5.506.1.2	ObjectPath Properties.....	1064
3.2.5.506.2	Methods .....	1064
3.2.5.506.2.1	Scalar Methods.....	1064
3.2.5.506.2.2	ObjectPath Methods .....	1064
3.2.5.506.2.2.1	GetById .....	1064
3.2.5.507	Microsoft.SharePoint.Marketplace.CorporateCuratedGallery.SiteCollectionAppCatalogAllowedCollection .....	1064
3.2.5.507.1	Properties.....	1064
3.2.5.507.1.1	Scalar Properties.....	1064
3.2.5.507.1.2	ObjectPath Properties.....	1064
3.2.5.507.2	Methods .....	1064
3.2.5.507.2.1	Scalar Methods.....	1064
3.2.5.507.2.1.1	Remove .....	1064

3.2.5.507.2.1.2	RemoveById .....	1065
3.2.5.507.2.2	ObjectPath Methods .....	1065
3.2.5.507.2.2.1	Add .....	1065
3.2.5.507.2.2.2	GetByAbsoluteUrl .....	1065
3.2.5.508	Microsoft.SharePoint.Marketplace.CorporateCuratedGallery.SiteCollectionAppCatalogAllowedItem .....	1065
3.2.5.508.1	Properties.....	1065
3.2.5.508.1.1	Scalar Properties.....	1065
3.2.5.508.1.1.1	AbsoluteUrl.....	1066
3.2.5.508.1.1.2	SiteID .....	1066
3.2.5.508.1.2	ObjectPath Properties.....	1066
3.2.5.508.2	Methods .....	1066
3.2.5.508.2.1	Scalar Methods.....	1066
3.2.5.508.2.2	ObjectPath Methods .....	1066
3.2.5.509	Microsoft.SharePoint.Marketplace.CorporateCuratedGallery.SiteCollectionCorporateCatalogAccessor .....	1066
3.2.5.509.1	Properties.....	1066
3.2.5.509.1.1	Scalar Properties.....	1066
3.2.5.509.1.2	ObjectPath Properties.....	1066
3.2.5.509.1.2.1	AvailableApps .....	1066
3.2.5.509.2	Methods .....	1066
3.2.5.509.2.1	Scalar Methods.....	1067
3.2.5.509.2.2	ObjectPath Methods .....	1067
3.2.5.509.2.2.1	Add .....	1067
3.2.5.510	Microsoft.SharePoint.Marketplace.CorporateCuratedGallery.TenantCorporateCatalogAccessor .....	1067
3.2.5.510.1	Properties.....	1067
3.2.5.510.1.1	Scalar Properties.....	1067
3.2.5.510.1.2	ObjectPath Properties.....	1067
3.2.5.510.1.2.1	AvailableApps .....	1067
3.2.5.510.1.2.2	SiteCollectionAppCatalogsSites.....	1067
3.2.5.510.2	Methods .....	1067
3.2.5.510.2.1	Scalar Methods.....	1068
3.2.5.510.2.2	ObjectPath Methods .....	1068
3.2.5.510.2.2.1	Add .....	1068
3.2.5.511	Microsoft.SharePoint.Navigation.REST.PublishingNavigationProviderType ..	1068
3.2.5.511.1	Field Values .....	1068
3.2.5.511.1.1	InvalidSiteMapProvider .....	1068
3.2.5.511.1.2	PortalSiteMapProvider .....	1068
3.2.5.511.1.3	TaxonomySiteMapProvider .....	1068
3.2.5.512	Microsoft.SharePoint.QuickActionMessageCard.HeroImage .....	1068
3.2.5.512.1	Properties.....	1068
3.2.5.512.1.1	Scalar Properties.....	1069
3.2.5.512.1.2	ObjectPath Properties.....	1069
3.2.5.513	Microsoft.SharePoint.QuickActionMessageCard.MessageCard .....	1069
3.2.5.513.1	Properties.....	1069
3.2.5.513.1.1	Scalar Properties.....	1069
3.2.5.513.1.2	ObjectPath Properties.....	1069
3.2.5.514	Microsoft.SharePoint.QuickActionMessageCard.MessageCardAction .....	1069
3.2.5.514.1	Properties.....	1069
3.2.5.514.1.1	Scalar Properties.....	1069
3.2.5.514.1.2	ObjectPath Properties.....	1069
3.2.5.515	Microsoft.SharePoint.QuickActionMessageCard.Section .....	1069
3.2.5.515.1	Properties.....	1069
3.2.5.515.1.1	Scalar Properties.....	1069



3.2.5.515.1.2	ObjectPath Properties.....	1070
3.2.5.516	Microsoft.SharePoint.QuickActionMessageCard.SPAccessRequestRefreshStatus .....	1070
3.2.5.516.1	Properties.....	1070
3.2.5.516.1.1	Scalar Properties.....	1070
3.2.5.516.1.2	ObjectPath Properties.....	1070
3.2.5.517	Microsoft.SharePoint.Webhooks.Subscription .....	1070
3.2.5.517.1	Properties.....	1070
3.2.5.517.1.1	Scalar Properties.....	1070
3.2.5.517.1.1.1	clientState.....	1070
3.2.5.517.1.1.2	expirationDateTime .....	1070
3.2.5.517.1.1.3	id .....	1070
3.2.5.517.1.1.4	notificationUrl .....	1071
3.2.5.517.1.1.5	resource.....	1071
3.2.5.517.1.1.6	resourceData .....	1071
3.2.5.517.1.2	ObjectPath Properties.....	1071
3.2.5.517.2	Methods.....	1071
3.2.5.517.2.1	Scalar Methods.....	1071
3.2.5.517.2.1.1	Delete.....	1071
3.2.5.517.2.1.2	Update.....	1071
3.2.5.517.2.2	ObjectPath Methods .....	1072
3.2.5.518	Microsoft.SharePoint.Webhooks.SubscriptionCollection .....	1072
3.2.5.518.1	Properties.....	1072
3.2.5.518.1.1	Scalar Properties.....	1072
3.2.5.518.1.2	ObjectPath Properties.....	1072
3.2.5.518.2	Methods.....	1072
3.2.5.518.2.1	Scalar Methods.....	1072
3.2.5.518.2.1.1	Remove .....	1072
3.2.5.518.2.2	ObjectPath Methods .....	1072
3.2.5.518.2.2.1	Add .....	1072
3.2.5.518.2.2.2	GetById .....	1072
3.2.5.519	Microsoft.SharePoint.Webhooks.SubscriptionInformation .....	1073
3.2.5.519.1	Properties.....	1073
3.2.5.519.1.1	Scalar Properties.....	1073
3.2.5.519.1.1.1	clientState.....	1073
3.2.5.519.1.1.2	expirationDateTime .....	1073
3.2.5.519.1.1.3	notificationUrl .....	1073
3.2.5.519.1.1.4	resource.....	1073
3.2.5.519.1.1.5	resourceData .....	1073
3.2.5.519.1.2	ObjectPath Properties.....	1074
3.2.6	Timer Events.....	1074
3.2.7	Other Local Events.....	1074
<b>4</b>	<b>Protocol Examples.....</b>	<b>1075</b>
4.1	Get the Title of a Web.....	1075
4.2	Update the Description of a List .....	1076
4.3	Add a List to a ListCollection .....	1077
4.4	Add a Lookup Field.....	1078
4.5	Attempt to Delete a Site With an Account That Does Not Have Permissions for the Operation.....	1080
<b>5</b>	<b>Security.....</b>	<b>1081</b>
5.1	Security Considerations for Implementers .....	1081
5.2	Index of Security Parameters .....	1081
<b>6</b>	<b>Appendix A: Product Behavior .....</b>	<b>1082</b>
<b>7</b>	<b>Change Tracking.....</b>	<b>1094</b>
<b>8</b>	<b>Index.....</b>	<b>1098</b>



# 1 Introduction

This document specifies types, methods, and properties of the SharePoint Client-Side Object Model Protocol that can be used to communicate with and manipulate aspects of a collaboration server.

Sections 1.5, 1.8, 1.9, 2, and 3 of this specification are normative. All other sections and examples in this specification are informative.

## 1.1 Glossary

This document uses the following terms:

**absolute path:** A string that identifies the location of a file and that begins with a drive identifier and root directory or network share and ends with the complete file name. Examples are C:\Documents\Work\example.txt and \\netshare\Documents\Work\example.txt.

**absolute URL:** The full Internet address of a page or other World Wide Web resource. The absolute URL includes a protocol, such as "http," a network location, and an optional path and file name — for example, <http://www.treyresearch.net/>.

**access control list (ACL):** A list of access control entries (ACEs) that collectively describe the security rules for authorizing access to some resource; for example, an object or set of objects.

**alert:** An Internet message that is sent to subscribers automatically to notify them when user-defined criteria are met. Alerts are generated automatically when items such as documents, webpages, list items, sites, or other resources on a server are changed.

**anchor text:** The text that is included with a hyperlink to describe the target content of a hyperlink.

**anonymous access link:** An implementation of tokenized sharing link that can allow users to gain guest access to content, such as a document or folder, without sign-in when using the specific tokenized sharing link.

**app:** (1) See **web application**.

(2) See **SharePoint Add-in**.

**app instance:** An instantiation of an **app** on a specific site.

**app package:** An implementation-specific file that specifies an **app**.

**app principal:** Designates an authenticated entity that is not a user.

**app product identifier:** A unique designation that is shared by all versions of an **app**.

**application:** A participant that is responsible for beginning, propagating, and completing an atomic transaction. An application communicates with a transaction manager in order to begin and complete transactions. An application communicates with a transaction manager in order to marshal transactions to and from other applications. An application also communicates in application-specific ways with a resource manager in order to submit requests for work on resources.

**attachment:** An external file that is included with an Internet message or associated with an item in a SharePoint list.

**authentication:** The act of proving an identity to a server while providing key material that binds the identity to subsequent communications.

**back-end database server:** A server that hosts data, configuration settings, and stored procedures that are associated with one or more applications.

**base field type:** An XML-based schema that defines the type of data, such as formatted text or an integer, that can be entered and stored in a field in a **list**. Every field in a **list** is derived from a specific base field type.

**base type:** An XML-based schema that defines the data and rendering fields that can be used in a **list**. Every list is derived from a specific base type.

**base view identifier:** An integer that uniquely identifies a view definition for a **list**.

**blind carbon copy (Bcc) recipient:** An addressee on a Message object that is not visible to recipients of the Message object.

**blog:** A website that contains a series of posts about a subject and is arranged in reverse chronological order. Also referred to as web log.

**Boolean:** An operation or expression that can be evaluated only as either true or false.

**Business Connectivity Services (BCS):** A set of services that enables interaction and integration with back-end data in a **line-of-business (LOB) system**, including external data and related services. BCS includes the **Business Data Connectivity (BDC)** service.

**Business Data Connectivity (BDC):** A shared service that stores information about business application data that exists outside a server farm. It can be used to display business data in lists, Web Parts, search results, user profiles, and custom applications. Previously referred to as Business Data Catalog.

**calculated field:** A user-defined field that can perform calculations by using the contents of other fields.

**calendar type:** A 2-byte integer value that specifies the type of calendar to use in a specific context.

**canonical URL:** An **absolute URL** that identifies a space, tool, or component the same way on any device.

**carbon copy (Cc) recipient:** An address on a Message object that is visible to recipients of the Message object but is not necessarily expected to take any action.

**cascading style sheet (CSS):** An extension to **HTML** that enables authors and users of HTML documents to attach style sheets to those documents, as described in [\[CSS-LEVEL1\]](#) and [\[CSS-LEVEL2\]](#). A style sheet includes typographical information about the appearance of a page, including the font for text on the page.

**change log:** A log of changes, such as add and delete, that are made to objects that are stored on a **back-end database server**. Applications can use this information to identify changes that occurred on those objects.

**change token:** A serialized token that can be used to determine whether changes occurred in the system. It can also be used to deserialize packages in the correct sequence during import or restore operations.

**check out:** The process of retrieving a writable copy of a file or project from a source repository. This locks the file for editing to prevent other users from overwriting or editing it inadvertently.

**checked out:** A **publishing level** that indicates that a document has been created and locked for exclusive editing by a user in a version control system.

**child:** An object that is immediately below the current object in a hierarchy.

**claims provider:** A software component or service that can be used to issue a claim during sign-in operations and to display, resolve, and provide search capabilities for claims in a card selector.

**Collaborative Application Markup Language (CAML):** An XML-based language that is used to describe various elements, such as queries and views, in sites that are based on SharePoint Products and Technologies.

**collation:** A set of rules that determines how data is compared, ordered, and presented.

**color scheme:** A table of color values that enables colors to be referenced by an index value in the table instead of a color value. See also color palette.

**column:** See field.

**comment:** An annotation that is associated with a cell, text, or other object to provide context-specific information or reviewer feedback.

**computed field:** A field that can perform data manipulation and display functions by using the contents of other fields.

**configuration database:** A database that is stored on a **back-end database server** and contains both persisted objects and site collection metadata for lookup purposes.

**content database:** A database that is stored on a **back-end database server** and contains stored procedures, site collections, and the contents of those site collections.

**content type:** A named and uniquely identifiable collection of settings and fields that store metadata for individual items in a SharePoint list. One or more content types can be associated with a list, which restricts the contents to items of those types.

**content type group:** A named category of **content types** that is used to organize content types of a similar purpose.

**content type identifier:** A unique identifier that is assigned to a **content type**.

**content type order:** The sequence in which **content types** are displayed.

**Coordinated Universal Time (UTC):** A high-precision atomic time standard that approximately tracks Universal Time (UT). It is the basis for legal, civil time all over the Earth. Time zones around the world are expressed as positive and negative offsets from UTC. In this role, it is also referred to as Zulu time (Z) and Greenwich Mean Time (GMT). In these specifications, all references to UTC refer to the time at UTC-0 (or GMT).

**crawl:** The process of traversing a URL space to acquire items to record in a search catalog.

**crawler:** A process that browses and indexes content from a content source.

**creator:** The user who creates protected content.

**CSOM array:** An ordered collection of values that can be used in an **XML** request or **JSON** response text. The values are identified by their position and their position is determined by a zero-based integer index.

**CSOM binary:** An array of 8-bit, unsigned integers that can be used in an **XML** request or as a string in **JSON** response text.

**CSOM Boolean:** A **Boolean** value that can be used in an **XML** request or **JSON** response text. A CSOM Boolean value is either "true" or "false".

**CSOM DateTime:** An Int64 value that represents the number of 100-nanosecond time intervals that have elapsed since 12:00:00, January 1, 0001. It can be used in an **XML** request or as a

string in **JSON** response text. The value can represent time intervals through 23:59:59.9999999, December 31, 9999. It can also specify whether a local, **UTC**, or no **time zone** applies.

**CSOM dictionary**: An object that contains an unordered collection of key/value pairs that can be used in an **XML** request or **JSON** response text. Each key in a CSOM dictionary has a unique name.

**CSOM Double**: A 64-bit, double-precision, floating-point value, which is the DOUBLE type described in [\[MS-DTYP\]](#), that can be used in an **XML** request or as a number in **JSON** response text. The range of CSOM Double values is from "-1.79769313486232e308" to "1.79769313486232e308".

**CSOM error**: An object that contains information about an error that occurred on a protocol server when processing a request.

**CSOM expando field**: A field that stores data for an instance of a **CSOM Object** and is not defined explicitly in the corresponding CSOM Object type.

**CSOM GUID**: A **GUID**, as described in [\[MS-DTYP\]](#), that can be used in an **XML** request or as a string in **JSON** response text.

**CSOM Int16**: A 16-bit, signed integer value, which is the INT16 type described in [\[MS-DTYP\]](#), that can be used in an **XML** request or as a number in **JSON** response text. The range of CSOM Int16 values is from "-32768" to "32767".

**CSOM Int32**: A 32-bit, signed integer value, which is the INT32 type described in [\[MS-DTYP\]](#), that can be used in an **XML** request or as a number in **JSON** response text. The range of CSOM Int32 values is from "-2147483648" to "2147483647".

**CSOM Int64**: A 64-bit, signed integer value, which is the INT64 type described in [\[MS-DTYP\]](#), that can be used in an **XML** request or as a number in **JSON** response text. The range of CSOM Int64 values is from "-9223372036854775808" to "9223372036854775807".

**CSOM Object**: An object that contains a set of members, which are named values and methods. It has a Unicode string value, which is referred to as a CSOM type name, that identifies its type.

**CSOM Stream**: A series of bytes that is used to transfer data and that supports reading, writing, and seeking.

**CSOM String**: A representation of text as a series of Unicode characters. It can be used in an **XML** request or **JSON** response text.

**CSOM UInt32**: A 32-bit, unsigned integer value, which is the UINT32 type described in [\[MS-DTYP\]](#), that can be used in an **XML** request or as a number in **JSON** response text. The range of CSOM UInt32 values is from "0" to "4294967295".

**CSOM UInt64**: A 64-bit, unsigned integer value, which is the UINT64 type described in [\[MS-DTYP\]](#), that can be used in an **XML** request or as a number in **JSON** response text. The range of CSOM UInt64 values is from "0" to "18446744073709551615".

**culture name**: A part of a language identification tagging system, as described in [\[RFC1766\]](#). Culture names adhere to the format "<languagecode2>-<country/regioncode2>." If a two-letter language code is not available, a three-letter code that is derived from [\[ISO-639\]](#) is used.

**current user**: The user who is authenticated during processing operations on a front-end web server or a **back-end database server**.

**current version**: The latest version of a document that is available to a user, based on the permissions of the user and the publishing level of the document.

**custom action:** An extension to the user interface, such as a button on a toolbar or a link on a site settings page.

**custom list:** A user-defined list or enumeration that can be used to sort data in a worksheet.

**data connection library:** A SharePoint library that contains a collection of universal data connection (.udcx) and Office data connection (.odc) files.

**data source:** A database, web service, disk, file, or other collection of information from which data is queried or submitted. Supported data sources vary based on application and data provider.

**data validation:** The process of testing the accuracy of data; a set of rules that specify the type and range of data that users can enter.

**data validation criteria:** See **data validation**.

**datasheet:** A worksheet window that contains the source data for a Microsoft Graph chart object.

**datetime:** A data type that represents the date and time when a document can be normalized and indexed as a numeric value by a search application. The range and degree of granularity varies according to search application and implementation.

**declarative workflow:** A workflow that is created with XAML (Extensible Application Markup Language) files and does not require precompiled code to run.

**default list view:** The view of a SharePoint list that the owner of the list selected to appear when users browse to the list without specifying a view.

**default mobile list view:** The view of a SharePoint list that the owner of the list selected to appear when users browse to the list by using a mobile device and without specifying a view.

**default scalar property set:** A set of properties that are retrieved by default for an object. The properties map to fields in a storage schema.

**default view:** The layout and organization of a document or list that appears automatically when users open that document or display that list.

**dependent lookup field:** A lookup field that displays additional data for an item that is returned by a primary lookup field. See also **primary lookup field**.

**designer:** A visual design surface for adding and arranging controls on a user form and writing code for those controls.

**dictionary:** A collection of key/value pairs. Each pair consists of a unique key and an associated value. Values in the dictionary are retrieved by providing a key for which the dictionary returns the associated value.

**discussion board:** A list in which users can read, post, and reply to messages from other users who are members of the same discussion board.

**discussion item:** A remark or response that is posted to an online discussion forum such as a newsgroup, SharePoint list, or electronic bulletin board.

**display form:** A form that is used to display a list item.

**display name:** A text string that is used to identify a principal or other object in the user interface. Also referred to as title.

**document:** An object in a **content database** such as a file, folder, **list**, or **site (2)**. Each object is identified by a **URI**.

**document identifier:** A GUID that identifies a document.

**document library:** A type of list that is a container for documents and folders.

**document template:** (1) A file that serves as the basis for new documents.

(2) A file that contains predefined formatting, layout, text, or graphics and that serves as the basis for new documents with a similar design or purpose.

**domain name:** The name given by an administrator to a collection of networked computers that share a common directory. Part of the domain naming service naming structure, domain names consist of a sequence of name labels separated by periods.

**draft:** A version of a document or list item that does not have a publishing level of "Published" or "Checked Out".

**edit form:** A form that enables users to edit a list item.

**editor:** The user who last modified an item or document in a SharePoint list.

**email address:** A string that identifies a user and enables the user to receive Internet messages.

**empty GUID:** A 128-bit, 16-byte identification number that is represented by all zeros.

**End User License Agreement (EULA):** A textual description of the terms that a user or administrator accepts before an update is installed. Each **EULA** is identified by a **GUID**, and each update revision might be associated with a **EULA**.

**endpoint:** A client that is on a network and is requesting access to a network access server (NAS).

**entity:** An instance of an EntityType element that has a unique identity and an independent existence. An entity is an operational unit of consistency.

**EntityInstance:** A set of **Field (3)** values that have a unique identity that represents a specific instance of an Entity, and are stored in a line-of-business (LOB) system.

**event:** (1) Any significant occurrence in a system or an application that requires users to be notified or an entry to be added to a log.

(2) An action or occurrence to which an application might respond. Examples include state changes, data transfers, key presses, and mouse movements.

**event receiver:** A structured modular component that enables built-in or user-defined managed code classes to act upon objects, such as list items, **lists**, or content types, when specific triggering actions occur.

**exclusive lock:** A condition in which one protocol client or protocol server can read or write data, but no transaction can acquire a **shared lock** on the data until the exclusive lock is released.

**Extensible Stylesheet Language (XSL):** An **XML** vocabulary that is used to transform XML data to another form, such as **HTML**, by means of a style sheet that defines presentation rules.

**external content type:** A type of DataClass object that is stored in a line-of-business (LOB) system and whose instances have a persistent EntityInstanceId. Also referred to as Entity.

**external list:** A container that is within a SharePoint site and that references a set of **EntityInstances** that are sourced from a line-of-business (LOB) system. It has a customizable schema that is composed of one or more **Fields (3)**.

**farm:** A group of computers that work together as a single system to help ensure that applications and resources are available. Also referred to as server farm.



**feature:** A package of SharePoint elements that can be activated or deactivated for a specific feature scope.

**feature identifier:** A **GUID** that identifies a **feature**.

**feature scope:** The scope at which a **feature** can be activated.

**field:** (1) An element or attribute in a data source that can contain data.

(2) A container for metadata within a SharePoint list and associated list items.

(3) The data elements that constitute an **Entity** in a line-of-business (LOB) system.

**field definition:** The definition of a field in the **Collaborative Application Markup Language (CAML)**.

**field group:** A named collection of related fields.

**field identifier:** A GUID that is used to identify a field.

**field internal name:** A string that uniquely identifies a field in a content type or a SharePoint list.

**field link:** A property that specifies a reference from a **content type** to a **field (2)** or **field definition**.

**field type:** A name that identifies the action or effect that a field has within a document. Examples of field types are Author, Page, Comments, and Date.

**file:** A single, discrete unit of content.

**file extension:** The sequence of characters in a **file's** name between the end of the **file's** name and the last "." character. Vendors of applications choose such sequences for the applications to uniquely identify **files** that were created by those applications. This allows file management software to determine which application are to be used to open a **file**.

**file system:** A set of data structures for naming, organizing, and storing files in a volume. NTFS, FAT, and FAT32 are examples of file system types.

**Finder:** A type of **MethodInstance** that can be called to return a collection of zero or more EntityInstances of a specific Entity. Finder input is defined by the FilterDescriptors that are contained in the Method that contains the Finder.

**first-stage Recycle Bin:** A container for items that were deleted. Items in this container are visible only to users with the appropriate permission and site collection administrators.

**floating-point number:** A number that is represented by a mantissa and an exponent according to a given base. The mantissa is typically a value between "0" and "1". To find the value of a floating-point number, the base is raised to the power of the exponent, and the mantissa is multiplied by the result.

**folder:** A **file system** construct. File systems organize a volume's data by providing a hierarchy of objects, which are referred to as folders or directories, that contain files and can also contain other folders.

**font:** An object that defines the graphic design, or formatting, of a collection of numbers, symbols, and letters. A font specifies the style (such as bold and strikeout), size, family (a typeface such as Times New Roman), and other qualities to describe how the collection is drawn.

**font scheme:** A combination of complementary fonts in a **theme**.

**form:** A structured document with controls and spaces that are reserved for entering and displaying information. Forms can contain special coding for actions such as submitting and querying data.

**form digest:** An object that is inserted into a page and is used by a protocol server to validate client requests. The validation is specific to a user, site, and time period.

**form library:** A type of document library that is optimized for storing and displaying data in XML-based forms.

**form template (.xsn) file:** A cabinet (.cab) file with an .xsn file name extension that contains the files that comprise a form template.

**full URL:** A string of characters in a standardized format that identifies a document or resource on the World Wide Web.

**gallery:** A library that is used to store a collection of site resources, such as Web Parts, list templates, and site templates.

**globally unique identifier (GUID):** A term used interchangeably with universally unique identifier (UUID) in Microsoft protocol technical documents (TDs). Interchanging the usage of these terms does not imply or require a specific algorithm or mechanism to generate the value. Specifically, the use of this term does not imply or require that the algorithms described in [\[RFC4122\]](#) or [\[C706\]](#) must be used for generating the **GUID**. See also universally unique identifier (UUID).

**group:** A named collection of users who share similar access permissions or roles.

**hidden:** A condition of an object that prevents it from being displayed in rendered output.

**historical version:** Any version of a document or list item that is not one of the current versions. Depending on configuration settings, historical versions can be retained in a **back-end database server**, and might not be visible to specific users.

**host name:** The name of a physical server, as described in [\[RFC952\]](#).

**HTTP method:** In an HTTP message, a token that specifies the method to be performed on the resource that is identified by the Request-URI, as described in [\[RFC2616\]](#).

**HTTP referer:** A string in an HTTP request-header field that identifies the address of the resource that is making the current request, as described in [\[RFC2616\]](#).

**hyperlink:** A relationship between two anchors, as described in [\[RFC1866\]](#).

**Hypertext Markup Language (HTML):** An application of the Standard Generalized Markup Language (SGML) that uses tags to mark elements in a document, as described in [\[HTML\]](#).

**Hypertext Transfer Protocol (HTTP):** An application-level protocol for distributed, collaborative, hypermedia information systems (text, graphic images, sound, video, and other multimedia files) on the World Wide Web.

**icon:** A graphical image used to supplement alphanumeric text in the visual identification of an object on a computer monitor. **Icons** are typically small, relative to the size of the area on which they are displayed.

**image:** A rectangular grid of pixels that has a definite height and a definite width and that can be displayed in a report.

**indexed field:** A field that stores values in a separate indexed table.

**Information Rights Management (IRM):** A technology that provides persistent protection to digital data by using encryption, certificates, and **authentication**. Authorized recipients or users acquire a license to gain access to the protected files according to the rights or business rules that are set by the content owner.

**Input Method Editor (IME):** An application that is used to enter characters in written Asian languages by using a standard 101-key keyboard. An IME consists of both an engine that converts keystrokes into phonetic and ideographic characters and a dictionary of commonly used ideographic words.

**item:** A unit of content that can be indexed and searched by a search application.

**item identifier:** An integer that uniquely identifies an item in a SharePoint list.

**JavaScript Object Notation (JSON):** A text-based, data interchange format that is used to transmit structured data, typically in Asynchronous JavaScript + XML (AJAX) web applications, as described in [\[RFC7159\]](#). The JSON format is based on the structure of ECMAScript (Jscript, JavaScript) objects.

**key value pair (KVP):** A set of two linked data items: a key that is an identifier for some data item, and a value that is a value associated with the data item for the identifier represented by the key.

**language code identifier (LCID):** A 32-bit number that identifies the user interface human language dialect or variation that is supported by an application or a client computer.

**leaf name:** The segment of a URL that follows the last slash. If the resource is a directory, the leaf name can be an empty string.

**line-of-business (LOB) system:** A software system that is used to store business data and can also contain business rules and business logic that support business processes.

**link:** An attribute value that refers to a directory object and whose Attribute-Schema object specifies an even value for the linkId attribute. Also referred to as forward link.

**link bar:** A non-hierarchical, user-defined collection of graphical or text buttons that represent hyperlinks to pages within the same website and external sites.

**list:** A container within a SharePoint site that stores list items. A list has a customizable schema that is composed of one or more fields.

**list folder:** A folder that is contained within a SharePoint list. A list folder can contain documents or list items, and it retains the characteristics of other items in the list, such as a customizable schema.

**list form:** A page that enables users to create, view, or edit an item in a list.

**list identifier:** A GUID that is used to identify a **list** in a site collection.

**list item:** An individual entry within a SharePoint list. Each list item has a schema that maps to fields in the list that contains the item, depending on the content type of the item.

**list item attachment:** A file that is contained within a list item and is stored in a folder in the **list** with the segment "Attachments".

**list item identifier:** See **item identifier**.

**list schema:** The **Collaborative Application Markup Language (CAML)** schema of a list.

**list server template:** A value that identifies the template that is used for a SharePoint list.

**list template:** An XML-based definition of list settings, including fields and views, and optionally list items. List templates are stored in .stp files in the content database.

**list view:** A named collection of settings for querying and displaying items in a SharePoint list. There are two types of views: Personal, which can be used only by the user who created the view; and Public, which can be used by all users who have permission to access to the site.

**list view page:** A Web Parts Page that displays a view of a SharePoint list.

**LobSystemInstance:** A type of MetadataObject that represents a specific deployed instance of a **line-of-business (LOB) system**, as represented by a LobSystem. LobSystemInstances are contained by LobSystems. LobSystemInstance Properties describe how to connect to an instance of the LobSystem that contains them by providing information such as the server name, connection string, and authentication mode.

**locale:** A collection of rules and data that are specific to a language and a geographical area. A locale can include information about sorting rules, date and time formatting, numeric and monetary conventions, and character classification.

**locked:** The condition of a cell, worksheet, or other object that restricts edits or modifications to it by users.

**login name:** A string that is used to identify a user or entity to an operating system, directory service, or distributed system. For example, in Windows-integrated authentication, a login name uses the form "DOMAIN\username".

**lookup field:** A field of the Lookup type that enables users to select an item from another data source.

**major version:** An iteration of a software component, document, or list item that is ready for a larger group to see, or has changed significantly from the previous major version. For an item on a SharePoint site, the **minor version** is always "0" (zero) for a major version.

**marketplace billing market:** A specifier that identifies the region of the credit card used to buy apps.

**marketplace content market:** A collection of metadata associated with each individual app that contains information such as the region and locale of the app.

**marketplace deployment identifier:** The identifier of the location to which app licenses are sold.

**marketplace license:** The proof of an app purchase that defines the usage pattern that is allowed for the app.

**marketplace license token:** An implementation-specific identifier used to serialize a marketplace license.

**master page:** An ASP.NET file that has a predefined layout that can include static text, **HTML** elements, and server controls.

**Meeting Workspace site:** A SharePoint site that is based on a Meeting Workspace site template and has a template ID value of "2". A Meeting Workspace site is used for planning, posting, and working together on meeting materials.

**member:** A user in the Members group of a site.

**membership:** The state or status of being a member of a member group. A membership contains additional metadata such as the privacy level that is associated with the membership.

**message body:** The main message text of an email message. A few properties of a Message object represent its message body, with one property containing the text itself and others defining its code page and its relationship to alternative body formats.

**MetadataCatalog:** A MetadataObject that represents a Metadata partition.

**MethodInstance:** A type of MetadataObject that associates a normalized or stereotypical semantic with a Method that represents a native API in a line-of-business (LOB) system. MethodInstances identify which part of the data that is returned by a Method is relevant for the semantic by defining a ReturnPropertyDescriptor. MethodInstances are contained by Methods.

**MIME type:** A method that is used by protocol clients to associate files of a certain type with applications that can open or access files of that type.

**minor version:** An iteration of a software component, document, or list item that is in progress or has changed only slightly from the previous version. For an item on a SharePoint site, the minor version number is never "0" (zero) and is incremented for each new version of an item, unless a **major version** is explicitly published. When minor versioning is disabled on a SharePoint site, only major version numbers are incremented, and the minor version is always "0" (zero).

**mobile device:** A small computing device that is easily portable and can be used in various environments.

**mobile list view:** A view of a SharePoint list that can be accessed by using a mobile device.

**moderation status:** A content approval status that indicates whether a list item was approved by a moderator.

**Mount:** To move physical media from a library slot to a drive.

**mount point:** See **mounted folder**.

**mounted folder:** A file system directory that contains a linked path to a second volume. A user can link a path on one volume to another. For example, given two volumes C: and D:, a user can create a directory or folder C:\mountD and link that directory with volume D:. The path C:\MountD can then be used to access the root folder of volume D:.

**navigation node:** An element in the navigational structure of a site. The element is a link or a series of links to a specific page in the site.

**new form:** A form that enables users to create a list item.

**notification:** A process in which a subscribing **Session Initiation Protocol (SIP)** client is notified of the state of a subscribed resource by sending a NOTIFY message to the subscriber.

**OAuth:** The OAuth 2.0 authorization framework [\[RFC6749\]](#).

**object:** (1) A set of attributes, each with its associated values. Two attributes of an object have special significance: an identifying attribute and a parent-identifying attribute. An identifying attribute is a designated single-valued attribute that appears on every object; the value of this attribute identifies the object. For the set of objects in a replica, the values of the identifying attribute are distinct. A parent-identifying attribute is a designated single-valued attribute that appears on every object; the value of this attribute identifies the object's parent. That is, this attribute contains the value of the parent's identifying attribute, or a reserved value identifying no object. For the set of objects in a replica, the values of this parent-identifying attribute define a tree with objects as vertices and child-parent references as directed edges with the **child** as an edge's tail and the parent as an edge's head. Note that an object is a value, not a variable; a replica is a variable. The process of adding, modifying, or deleting an object in a replica replaces the entire value of the replica with a new value. As the word replica suggests, it is often the case that two replicas contain "the same objects". In this usage, objects in two replicas are

considered the same if they have the same value of the identifying attribute and if there is a process in place (replication) to converge the values of the remaining attributes. When the members of a set of replicas are considered to be the same, it is common to say "an object" as shorthand referring to the set of corresponding objects in the replicas.

(2) In COM, a software entity that implements the IUnknown interface and zero or more additional interfaces that may be obtained from each other using the IUnknown interface. A COM **object** can be exposed to remote clients via the DCOM protocol, in which case it is also a DCOM object.

**Office Add-in:** A cloud-enabled app that integrates rich, scenario-focused content and services into an Office application or equivalent protocol client.

**organization access link:** An implementation of tokenized sharing link that can grant a signed-in user explicit access to content, such as a document or folder, when using the specific tokenized sharing link, so that they can directly access the content in future requests.

**owner:** A security principal who has the requisite permission to manage a security group.

**page type:** An integer that specifies the type of a page.

**paged view:** A view that supports one or more visual pages. A paged view is used to break large sets of data into smaller sets for increased performance and manageability.

**parent list:** A **list** that contains a list item or list folder.

**parent site:** The site that is above the current site in the hierarchy of the site collection.

**permission:** A rule that is associated with an object and that regulates which users can gain access to the object and in what manner. See also **rights**.

**permission level:** A set of permissions that can be granted to principals or SharePoint groups on an entity such as a site, list, folder, item, or document.

**personal view:** A view of a list that is created by a user for personal use. The view is unavailable to other users.

**personalization data:** Customized data that is stored for a set of **Web Parts**. The data can be shared by all users or be specific to an individual user.

**personalization scope:** A mode of the Web Part Manager that indicates whether the available data is shared by all users or specific to an individual user.

**personalized Web Parts:** A Web Part that has been modified by a user for personal use. The view of the Web Part is unavailable to other users.

**picture library:** A type of **document library** that is optimized for storing digital pictures or graphics.

**policy:** A set of rules that governs all interactions with an object such as a document or item.

**policy tip:** A message that is displayed in the client user interface to inform the user that an email does not comply with an email policy configured on the server.

**presence:** A setting for the User field that determines whether instant-messaging status information appears with user names in that field.

**primary lookup field:** A lookup field that returns all of the information that is needed to support lookup operations from one list to another. See also **dependent lookup field**.

**principal:** An authenticated **entity** that initiates a message or channel in a distributed system.

**ProgID:** An identifier that is used by the Windows registry to uniquely identify an object and is in the form OLEServerName.ObjectName, for example, "Excel.Sheet" or "PowerPoint.Slide."

**public view:** A view of a list that is available to all users who have permission to access that list.

**published:** A condition of portions of a workbook that are marked as being available to the user when that workbook is processed by a protocol server.

**publishing level:** An integer that is assigned to a document to indicate the publishing status of that version of the document.

**query:** A formalized instruction to a data source to either extract data or perform a specified action. A query can be in the form of a query expression, a method-based query, or a combination of the two. The data source can be in different forms, such as a relational database, **XML document**, or in-memory object. See also search query.

**Quick Launch:** A collection of links to lists and pages in a SharePoint site. By default, it appears on the side of all pages, except site administration pages, in the site.

**reading order:** The positioning of characters in words and the positioning of words in sentences. This can be left-to-right or right-to-left.

**recycle:** A process in which SMP releases a Session object so that the session identifier (SID) in use is made available again for a new session.

**Recycle Bin:** The location where deleted files are stored until they are either restored, if they were deleted erroneously, or destroyed permanently.

**Recycle Bin item:** An item that was deleted and appears in the Recycle Bin. Items in the Recycle Bin can include a document, a version of a document, a list item, a list, a folder, a folder containing lists, an attachment to a list item, or a version of a list item.

**recycling:** To permanently disable the creation of new component instances in an instance container.

**reference:** A means by which cells, objects, and chart elements can be referenced in a formula.

**regional settings:** See locale settings.

**relationship behavior constraint:** A setting that defines any dependent relationships, such as cascading or restrict behaviors, between list items.

**relationship delete behavior:** An 8-bit integer that specifies how to delete a list item that has related child items. It can be a cascading operation, which deletes all related child items when the parent item is deleted, or a restrict operation, which indicates that a parent item can be deleted only after all related child items are deleted.

**relationship lookup field:** A **lookup field** in a **back-end database server** that defines a relationship between two SharePoint lists.

**resource folder:** A folder that contains images, templates, and other resource files for a **content type**.

**rich text:** Text that is formatted in the Rich Text Format, as described in [\[MSFT-RTF\]](#).

**rights:** Tasks that a user is permitted to perform on a computer, site, domain, or other system resource. See also **permission**.

**role:** A symbolic name that defines a class of users for a set of components. A role defines which users can call interfaces on a component.

**role assignment:** An association between a principal or a site group and a role definition.

**role definition:** A named set of permissions for a SharePoint site. See also **permission level**.

**root element:** The top-level element in an **XML document**. It contains all other elements and is not contained by any other element, as described in [\[XML\]](#).

**root folder:** The folder at the top of a hierarchy of folders in a list.

**schema version:** An integer value that represents the version number of the schema for a deployment package.

**second-stage Recycle Bin:** A container for items that were deleted from a **first-stage Recycle Bin**. Items in a second-stage Recycle Bin are visible only to site collection administrators.

**securable object:** An object that can have unique security permissions associated with it.

**security group:** A named group of principals on a SharePoint site.

**security scope:** A tree structure of objects in which every object has the same security settings as the root.

**security trimming:** The process of filtering search results by checking the access control list (ACL) for a resource and displaying only those resources that a user has permission to view.

**server-relative URL:** A relative URL that does not specify a scheme or host, and assumes a base URI of the root of the host, as described in [\[RFC3986\]](#).

**Session Initiation Protocol (SIP):** An application-layer control (signaling) protocol for creating, modifying, and terminating sessions with one or more participants. **SIP** is defined in [\[RFC3261\]](#).

**shared lock:** A condition in which multiple protocol clients or protocol servers can read or write data concurrently, but no transaction can acquire an **exclusive lock** on the data until all of the shared locks have been released.

**SharePoint Add-in:** A cloud-enabled software module that uses HTML, JavaScript, or other industry-standard web technologies, in addition to possible server components, to integrate rich, scenario-focused content and services into SharePoint.

**site:** (1) A group of related webpages that is hosted by a server on the World Wide Web or an intranet. Each website has its own entry points, metadata, administration settings, and workflows. Also referred to as web site.

(2) A group of related pages and data within a SharePoint site collection. The structure and content of a site is based on a site definition. Also referred to as SharePoint site and web site.

**site collection:** A set of websites that are in the same **content database**, have the same owner, and share administration settings. A site collection can be identified by a **GUID** or the **URL** of the **top-level site** for the site collection. Each site collection contains a top-level site, can contain one or more subsites, and can have a shared navigational structure.

**site collection administrator:** A user who has administrative permissions for a site collection.

**site collection group:** A named collection of users and domain groups that can be managed for a site collection or site. A group can be used to assign permission levels, send email messages, and indicate site membership for multiple users simultaneously.

**site collection quota:** An option for a site collection that enables administrators to set levels for maximum storage allowed, maximum number of users allowed, and warnings that are associated with the maximum levels.



**site content type:** A named and uniquely identifiable collection of settings and fields that store metadata for lists within individual sites.

**site definition:** A family of site definition configurations. Each site definition specifies a name and contains a list of associated site definition configurations.

**site definition configuration:** An XML-based definition of lists, features, modules, and other data that collectively define a type of SharePoint site. Site definition configurations are stored in the ONET.xml file.

**site identifier:** A GUID that is used to identify a site in a **site collection**.

**site solution:** A deployable, reusable package that contains a set of features, site definitions, and assemblies that apply to sites, and can be enabled or disabled individually.

**site subscription:** A logical grouping of **site collections** that share a common set of features and service data.

**site template:** An XML-based definition of site settings, including formatting, lists, views, and elements such as text, graphics, page layout, and styles. Site templates are stored in .stp files in the content database.

**site-relative URL:** A URL that is relative to the site that contains a resource and does not begin with a leading slash (/).

**SOAP:** A lightweight protocol for exchanging structured information in a decentralized, distributed environment. **SOAP** uses **XML** technologies to define an extensible messaging framework, which provides a message construct that can be exchanged over a variety of underlying protocols. The framework has been designed to be independent of any particular programming model and other implementation-specific semantics. SOAP 1.2 supersedes SOAP 1.1. See [\[SOAP1.2-1/2003\]](#).

**SpecificFinder:** A type of **MethodInstance** that can be called to return a specific EntityInstance of a specific Entity given its EntityInstanceId. SpecificFinder input is defined and ordered by the Identifiers that are associated with the Entity that is associated with the Method that is associated with the SpecificFinder.

**static CSOM method:** A class method that is accessed through the type name rather than an instance of the class.

**Status-Code:** A 3-digit integer result code in an HTTP response message, as described in [\[RFC2616\]](#).

**stream:** An element of a compound file, as described in [\[MS-CFB\]](#). A stream contains a sequence of bytes that can be read from or written to by an application, and they can exist only in storages.

**strong name:** A name that consists of the simple text name, version number, and culture information of an assembly, strengthened by a public key and a digital signature that is generated over the assembly.

**subscription:** The result of a SUBSCRIBE request from a **Session Initiation Protocol (SIP)** element.

**subsite:** A complete website that is stored in a named subdirectory of another website. The parent website can be the top-level site of a site collection or another subsite. Also referred to as subweb.

**survey list:** A list that is preconfigured and optimized for conducting surveys and compiling survey results into graphical views.

**task:** A component of an action that defines the work that actors need to do within a workflow system. An action can have zero or more tasks that are each assigned to different targets. There is a one-to-one correlation between tasks and targets.

**taxonomy navigation:** A hierarchy of navigation menus that represents the navigation menus in terms and term sets and are independent of where their underlying objects, such as pages, are located.

**template:** A file that contains pre-defined formatting including layout, text and graphics. It serves as the basis for new documents that have a similar look or purpose. See also form template (Microsoft InfoPath) and **site template** (SharePoint Products and Technologies).

**theme:** A set of unified design elements, such as colors, fonts, graphics, and styles, that define the appearance of a website, document, or data visualization.

**thicket supporting file:** A file that contains a graphic element, a picture, or other media that is referenced by the thicket main file and is stored in the thicket folder.

**time zone:** A geographical area that observes the same local time. The local time has a positive, zero, or negative offset from **Coordinated Universal Time (UTC)**. The offset can be different during standard time and daylight saving time.

**tokenized sharing link:** A specialized URL where a unique server generated opaque string value for a resource is embedded within the path or as a parameter, for the purposes of granting access whenever the URL is used to access the content. Depending on the supported abilities of the server, a tokenized sharing link can potentially behave like an anonymous access link, an organization access link, or with other behaviors as defined by the implementor.

**toolbar:** A row, column, or block of controls that represent tasks or commands within an application. A toolbar can be either a menu toolbar, which provides access to menu commands, or a basic toolbar, which contains buttons that provide shortcuts to tasks that are frequently accessed from menus.

**tooltip:** A window displaying text that is created when the mouse is moved over a window or notification icon.

**top-level site:** The first site in a site collection. All other sites within a site collection are child sites of the top-level site. The URL of the top-level site is also the URL of the site collection.

**TypeDescriptor:** A type of MetadataObject that describes a subset of the structure of a Parameter of a Method of the native API of a line-of-business (LOB) system. A TypeDescriptor can contain TypeDescriptors to form hierarchies that describe Parameters representing complex types, where the leaf TypeDescriptors describe simple or primitive types. A root TypeDescriptor, together with DefaultValues for leaf TypeDescriptors can be used to instantiate an instance of a Parameter value to send to a LOB system to execute a Method.

**uncustomized:** A condition of a document whose content is stored in a location other than the content database. If a document is uncustomized, the front-end web server determines the location of the content by using the SetupPath value for the document. Also referred to as ghosted.

**Uniform Resource Identifier (URI):** A string that identifies a resource. The URI is an addressing mechanism defined in Internet Engineering Task Force (IETF) Uniform Resource Identifier (URI): Generic Syntax [RFC3986].

**Uniform Resource Locator (URL):** A string of characters in a standardized format that identifies a document or resource on the World Wide Web. The format is as specified in [\[RFC1738\]](#).

**unique column constraint:** A property of a field that requires all of the values in that field to be unique.

**Updater:** A type of **MethodInstance** that can be called to update an EntityInstance identified by a specified EntityInstanceId. The set of **Fields (3)** that is required to update the EntityInstance is referred to as the Updater View.

**upgrade evaluation site collection:** A copy of the current **site collection**, used to evaluate the functionality of a site collection after it is upgraded.

**URL encode:** The process of encoding characters that have reserved meanings for a **Uniform Resource Locator (URL)**, as described in [RFC1738].

**user:** (1) A person who employs a web browser requestor to access a WS resource.

(2) The real person who has a member account. The user is **authenticated** by being asked to prove knowledge of the secret password associated with the user name.

**user custom action:** An extension to the user interface, such as a button on a toolbar or a link on a site settings page, that is submitted by a user of a site collection. Unlike a custom action, the definition of a user custom action is stored in a **back-end database server**.

**user display name:** A user profile property that contains the preferred name of a user. See also **display name**.

**user information list:** A list that contains items, each of which represents a security principal in a site collection. Each site collection has only one such list and it resides in the top-level site of the site collection.

**UTC (Coordinated Universal Time):** A high-precision atomic time standard that approximately tracks Universal Time (UT). It is the basis for legal, civil time all over the Earth. Time zones around the world are expressed as positive and negative offsets from UTC. In this role, it is also referred to as Zulu time (Z) and Greenwich Mean Time (GMT). In these specifications, all references to UTC refer to the time at UTC-0 (or GMT).

**value:** A data element associated with a key.

**version:** See displayed version, **historical version**, **major version**, and **minor version**.

**view:** See form view (Microsoft InfoPath), **list view** (SharePoint Products and Technologies), or **View** (Microsoft Business Connectivity Services).

**view identifier:** A GUID that is used to uniquely identify a view.

**view style:** A pre-defined, named collection of settings that specify how to lay out data in a list view.

**visual upgrade:** A feature that enables a protocol server to display an earlier version of a user interface to support backward compatibility with existing solutions.

**web application:** A container in a configuration database that stores administrative settings and entry-point **URLs** for **site collections**.

**web discussion:** A component and add-in that enables users to enter comments about documents and pages without modifying the actual content of those documents or pages.

**web discussion comment:** An individual comment that is added to a web discussion.

**Web Distributed Authoring and Versioning Protocol (WebDAV):** The Web Distributed Authoring and Versioning Protocol, as described in [\[RFC2518\]](#) or [\[RFC4918\]](#).

**Web Part:** A reusable component that contains or generates web-based content such as **XML**, **HTML**, and scripting code. It has a standard property schema and displays that content in a cohesive unit on a webpage. See also Web Parts Page.

**Web Part identifier:** A GUID that identifies a Web Part.

**Web Part Page:** An ASP.NET webpage that includes Web Part controls that enable users to customize the page, such as specifying which information to display. Referred to as Web Parts Page in Microsoft SharePoint Foundation 2010.

**Web Part zone:** A structured HTML section of a Web Parts Page that contains zero or more Web Parts and can be configured to control the organization and format of those Web Parts.

**Web Part zone index:** An integer that specifies the relative position of a Web Part in a Web Part zone. Web Parts are positioned from the smallest to the largest zone index. If two or more Web Parts have the same zone index they are positioned adjacent to each other in an undefined order.

**website:** A group of related pages and data within a SharePoint site collection. The structure and content of a site is based on a site definition. Also referred to as SharePoint site and site.

**Welcome page:** A page, such as default.aspx, that can be specified as the default redirect target when users browse to a URL without specifying a **leaf name**.

**workflow:** A structured modular component that enables the automated movement of documents or items through a specific sequence of actions or tasks that are related to built-in or user-defined business processes.

**workflow association:** An association of a workflow template to a specific list or content type.

**workflow history list:** A list that stores the history of actions or tasks for a business process.

**workflow identifier:** A GUID that is used to identify a workflow.

**workflow initiation form:** An implementation-specific file, typically an ASPX page, that is a part of a workflow. It contains fields and other elements that can be used to initiate a process for a list item, based on the rules and settings in a workflow template that is associated with the list that contains the item.

**workflow instance:** An instance of a workflow association that performs on a list item the process that is defined in a workflow template.

**workflow task:** An action or task in a sequence that is related to a built-in or user-defined business process.

**workflow task list:** A list that stores the sequence of actions or tasks for a business process.

**workflow template:** A definition of operations, the sequence of operations, constraints, and timing for a specific process.

**XML:** The Extensible Markup Language, as described in [\[XML1.0\]](#).

**XML document:** A document object that is well formed, as described in [\[XML10/5\]](#), and might be valid. An XML document has a logical structure that is composed of declarations, elements, comments, character references, and processing instructions. It also has a physical structure that is composed of entities, starting with the root, or document, entity.

**XML element:** An **XML** structure that typically consists of a start tag, an end tag, and the information between those tags. Elements can have attributes and can contain other elements.

**XML fragment:** Lines of text that adhere to **XML** tag rules, as described in [XML], but do not have a Document Type Definition (DTD) or schema, processing instructions, or any other header information.

**XML schema:** A description of a type of **XML document** that is typically expressed in terms of constraints on the structure and content of documents of that type, in addition to the basic syntax constraints that are imposed by **XML** itself. An XML schema provides a view of a document type at a relatively high level of abstraction.

**MAY, SHOULD, MUST, SHOULD NOT, MUST NOT:** These terms (in all caps) are used as defined in [\[RFC2119\]](#). All statements of optional behavior use either MAY, SHOULD, or SHOULD NOT.

## 1.2 References

Links to a document in the Microsoft Open Specifications library point to the correct section in the most recently published version of the referenced document. However, because individual documents in the library are not updated at the same time, the section numbers in the documents may not match. You can confirm the correct section numbering by checking the [Errata](#).

### 1.2.1 Normative References

We conduct frequent surveys of the normative references to assure their continued availability. If you have any issue with finding a normative reference, please contact [dochelp@microsoft.com](mailto:dochelp@microsoft.com). We will assist you in finding the relevant information.

[ECMA-262-1999] Ecma International, "ECMAScript Language Specification", Standard ECMA-262 3rd Edition - December 1999, <http://www.ecma-international.org/publications/files/ECMA-ST-ARCH/ECMA-262,%203rd%20edition,%20December%201999.pdf>

[HTML] World Wide Web Consortium, "HTML 4.01 Specification", W3C Recommendation, December 1999, <http://www.w3.org/TR/html4/>

[ISO-3166] International Organization for Standardization, "Codes for the representation of names of countries and their subdivisions -- Part1: Country codes", ISO 3166-1:2013, November 2013, [http://www.iso.org/iso/home/store/catalogue\\_tc/catalogue\\_detail.htm?csnumber=63545](http://www.iso.org/iso/home/store/catalogue_tc/catalogue_detail.htm?csnumber=63545)

**Note** There is a charge to download the specification.

[ISO-8601] International Organization for Standardization, "Data Elements and Interchange Formats - Information Interchange - Representation of Dates and Times", ISO/IEC 8601:2004, December 2004, <http://www.iso.org/iso/en/CatalogueDetailPage.CatalogueDetail?CSNUMBER=40874&ICS1=1&ICS2=140&ICS3=30>

**Note** There is a charge to download the specification.

[MC-CSDL] Microsoft Corporation, "[Conceptual Schema Definition File Format](#)".

[MS-CSOMREST] Microsoft Corporation, "[SharePoint Client Query OData Protocol](#)".

[MS-CSOM] Microsoft Corporation, "[SharePoint Client Query Protocol](#)".

[MS-ECTPWPS] Microsoft Corporation, "[External Content Type Picker Web Service Protocol](#)".

[MS-FPSE] Microsoft Corporation, "[FrontPage Server Extensions Remote Protocol](#)".

[MS-FSSHTTPB] Microsoft Corporation, "[Binary Requests for File Synchronization via SOAP Protocol](#)".

[MS-FSSHTTP] Microsoft Corporation, "[File Synchronization via SOAP over HTTP Protocol](#)".

[MS-LCID] Microsoft Corporation, "[Windows Language Code Identifier \(LCID\) Reference](#)".

[MS-LISTSWS] Microsoft Corporation, "[Lists Web Service Protocol](#)".

[MS-ODATA] Microsoft Corporation, "[Open Data Protocol \(OData\)](#)".

[MS-SITEST] Microsoft Corporation, "[Sites Web Service Protocol](#)".

[MS-WPPS] Microsoft Corporation, "[Web Part Pages Web Service Protocol](#)".

[MS-WSSCAML] Microsoft Corporation, "[Collaborative Application Markup Language \(CAML\) Structure](#)".

[MS-WSSCAP] Microsoft Corporation, "[Windows SharePoint Services Collaborative Application Protocol](#)".

[MS-WSSFO2] Microsoft Corporation, "[Windows SharePoint Services \(WSS\): File Operations Database Communications Version 2 Protocol](#)".

[MS-WSSFO3] Microsoft Corporation, "[Windows SharePoint Services \(WSS\): File Operations Database Communications Version 3 Protocol](#)".

[MS-WSSHP] Microsoft Corporation, "[HTTP Windows SharePoint Services Headers Protocol](#)".

[MS-WSSTS] Microsoft Corporation, "[Windows SharePoint Services](#)".

[RFC2119] Bradner, S., "Key words for use in RFCs to Indicate Requirement Levels", BCP 14, RFC 2119, March 1997, <http://www.rfc-editor.org/rfc/rfc2119.txt>

[RFC2616] Fielding, R., Gettys, J., Mogul, J., et al., "Hypertext Transfer Protocol -- HTTP/1.1", RFC 2616, June 1999, <http://www.rfc-editor.org/rfc/rfc2616.txt>

[RFC4646] Phillips, A., and Davis, M., Eds., "Tags for Identifying Languages", BCP 47, RFC 4646, September 2006, <http://www.rfc-editor.org/rfc/rfc4646.txt>

[RFC5234] Crocker, D., Ed., and Overell, P., "Augmented BNF for Syntax Specifications: ABNF", STD 68, RFC 5234, January 2008, <http://www.rfc-editor.org/rfc/rfc5234.txt>

[RSS2.0] Winer, D., "RSS 2.0 Specification", Fall 2002, version 2.0.1: July 2003, <http://cyber.law.harvard.edu/rss/rss.html>

## 1.2.2 Informative References


[MS-BDCMFFS] Microsoft Corporation, "[Business Data Connectivity Model File Format](#)".

## 1.3 Overview

This protocol defines types, methods, and properties that protocol clients use to access **site (2)**, **list**, and other types of data associated with a collaboration server. The set of types and **members** provide a means for remote clients to perform collaboration and communication **tasks**, such as updating **items** or checking in **documents**.

## 1.4 Relationship to Other Protocols

This protocol is a set of types, properties, and methods that can be accessed by using the SharePoint Client Query protocol, as described in [\[MS-CSOM\]](#), and the SharePoint Client Query OData Protocol, as described in [\[MS-CSOMREST\]](#). This protocol specifies properties, methods, and types used to access a collaboration server as described in [\[MS-WSSTS\]](#).



**Figure 1: This protocol in relation to other protocols**

### 1.5 Prerequisites/Preconditions

This protocol operates against a **site (2)** that is identified by a **URL** that is known by protocol clients. This protocol assumes that **authentication** has been performed by underlying protocols.

### 1.6 Applicability Statement

This protocol can be used by a protocol client to read data from, write data to, and execute operations against a protocol server. The protocol is optimized to enable a protocol client to specify the exact set of data and operations to perform in a single batch, making it suitable for situations where the connection speed between the protocol client and the protocol server can be slow.

Because of the complexity of the structure of requests and responses, it is not suitable for cases where the inputs and outputs need to be quickly understood and specified by a human. Because the protocol features minimal services for type and operation discovery, it is not suitable for protocol servers that implement a different set of functionality compared to the set of functionality described for a collaboration server in [\[MS-WSSTS\]](#).

### 1.7 Versioning and Capability Negotiation

This protocol operates in the context of the authenticated user that made a request to the service and in the context of a particular **site (2)**. Localization-specific properties, such as the title of a **list**, are returned by using the preferred language of the user, if available, or by using the default language of the site (2) as a fallback. Certain properties can be read or written for specific locales, and are listed in the **document**.

### 1.8 Vendor-Extensible Fields

A protocol server can provide additional properties and methods beyond those specified in this document to provide extended collaboration server functionality; however, because no means are

provided for a protocol client to discover that extended functionality, the functionality is taken advantage of only by protocol clients that have built-in knowledge of the extensions.

A protocol client is expected to be tolerant of the situation where certain methods and properties specified in this specification are not available, because either the protocol server does not support the functionality or the administrator has disabled certain functionalities.

## **1.9 Standards Assignments**

None.



## 2 Messages

### 2.1 Transport

Messages are transported by using the SharePoint Client Query Protocol, as specified in [\[MS-CSOM\]](#), or the SharePoint Client Query OData Protocol, as specified in [\[MS-CSOMREST\]](#).

### 2.2 Message Syntax

#### 2.2.1 Common Exceptions

The protocol server MUST validate the request from the protocol client and return the exception listed in the following table to the protocol client under the specified conditions.

Error Code	Error Type Name	Condition
- 2130575251	Microsoft.SharePoint.SPException	The protocol server requires a <b>form digest</b> but the form digest in the <b>X-RequestDigest</b> HTTP header is not as same as the one generated by the protocol server.
- 2130575252	Microsoft.SharePoint.Exception	The protocol client sent a valid form digest in the <b>X-RequestDigest</b> ( <a href="#">[MS-WSSHP]</a> section 2.2.11 and <a href="#">[MS-SITESS]</a> section 3.1.4) HTTP header, but the form digest is expired.
- 2146232832	Microsoft.SharePoint.SPException	The protocol server requires a form digest but the protocol client did not send an <b>X-RequestDigest</b> ( <a href="#">[MS-WSSHP]</a> section 2.2.11) HTTP header.

When a protocol server processes a CSOM operation in the request, the following table lists common exceptions that could occur when accessing or updating a property or invoking a method.

Error Code	Error Type Name	Condition
- 2147024891	System.UnauthorizedAccessException	The user does not have <b>permission</b> to access a property, update a property or call a method.

Besides the preceding exceptions and the exceptions that are listed for the specific properties or methods, the protocol server can return other exceptions to the protocol client, for which the protocol client could use the error message for display purposes but could not use the error code or error type to determine the causes of the exception.

Unless specified, exceptions listed for the specific properties are thrown for both read and write operations.

## 3 Protocol Details

### 3.1 Common Details

The protocol server endpoint is formed by appending "\_vti\_bin/client.svc/ProcessQuery" to the URL of the **site (2)**, for example [http://www.contoso.com/Repository/\\_vti\\_bin/client.svc/ProcessQuery](http://www.contoso.com/Repository/_vti_bin/client.svc/ProcessQuery).

The length of a **CSOM String** is the number of characters in its value. The length of a **CSOM array** is the number of elements in the array.

ObjectPath Properties are properties of type CSOM Object as defined in [\[MS-CSOM\]](#) section 2.2.4.4, Scalar Properties are properties of any type except of type CSOM Object as defined in [\[MS-CSOM\]](#) section 2.2.4 and [\[MS-CSOM\]](#) section 2.2.5.

### 3.2 Server Details

#### 3.2.1 Abstract Data Model

This protocol shares the abstract data model used by the SharePoint Client Query protocol, as described in [\[MS-CSOM\]](#) section 3.1.1, to communicate with the protocol server.

This section describes a conceptual model of possible data organization that an implementation maintains to participate in this protocol. The described organization is provided to facilitate the explanation of how the protocol behaves. This specification does not mandate that implementations adhere to this model as long as their external behavior is consistent with that described in this specification.

This protocol deals with various structures associated with **sites (2)**, **lists**, **items**, navigation, and other structures as specified in [\[MS-WSSTS\]](#).

##### 3.2.1.1 Parent Type

This protocol deals with various types that are logically derived from a parent type. The following table lists the relation between such types.

Parent Type	Derived Type(s)
3.2.5.118 Microsoft.SharePoint.Client.SecurableObject	3.2.5.79 Microsoft.SharePoint.Client.List 3.2.5.87 Microsoft.SharePoint.Client.ListItem 3.2.5.143 Microsoft.SharePoint.Client.Web
3.2.5.37 Microsoft.SharePoint.Client.Field	3.2.5.38 Microsoft.SharePoint.Client.FieldCalculated 3.2.5.42 Microsoft.SharePoint.Client.FieldComputed 3.2.5.44 Microsoft.SharePoint.Client.FieldDateTime 3.2.5.45 Microsoft.SharePoint.Client.FieldGuid 3.2.5.49 Microsoft.SharePoint.Client.FieldLookup 3.2.5.51 Microsoft.SharePoint.Client.FieldMultiChoice 3.2.5.52 Microsoft.SharePoint.Client.FieldMultiLineText 3.2.5.53 Microsoft.SharePoint.Client.FieldNumber 3.2.5.57 Microsoft.SharePoint.Client.FieldText 3.2.5.59 Microsoft.SharePoint.Client.FieldUrl <a href="#">3.2.5.185</a> Microsoft.SharePoint.Client.FieldGeolocation
3.2.5.49 Microsoft.SharePoint.Client.FieldLookup	3.2.5.61 Microsoft.SharePoint.Client.FieldUser

Parent Type	Derived Type(s)
3.2.5.51 Microsoft.SharePoint.Client.FieldMultiChoice	3.2.5.40 Microsoft.SharePoint.Client.FieldChoice 3.2.5.54 Microsoft.SharePoint.Client.FieldRatingScale
3.2.5.53 Microsoft.SharePoint.Client.FieldNumber	3.2.5.43 Microsoft.SharePoint.Client.FieldCurrency
3.2.5.50 Microsoft.SharePoint.Client.FieldLookupValue	3.2.5.63 Microsoft.SharePoint.Client.FieldUserValue
3.2.5.7 Microsoft.SharePoint.Client.Change	3.2.5.8 Microsoft.SharePoint.Client.ChangeAlert 3.2.5.10 Microsoft.SharePoint.Client.ChangeContentType 3.2.5.11 Microsoft.SharePoint.Client.ChangeField 3.2.5.12 Microsoft.SharePoint.Client.ChangeFile 3.2.5.13 Microsoft.SharePoint.Client.ChangeFolder 3.2.5.14 Microsoft.SharePoint.Client.ChangeGroup 3.2.5.15 Microsoft.SharePoint.Client.ChangeItem 3.2.5.16 Microsoft.SharePoint.Client.ChangeList 3.2.5.18 Microsoft.SharePoint.Client.ChangeSite 3.2.5.21 Microsoft.SharePoint.Client.ChangeUser 3.2.5.22 Microsoft.SharePoint.Client.ChangeView 3.2.5.23 Microsoft.SharePoint.Client.ChangeWeb

### 3.2.1.2 Abstract Data Model for REST List Items Support

This section describes the relationship between the abstract data model as specified in [\[MS-WSSTS\]](#) section 2.1.2.10 and the Entity Data Model as specified in [\[MC-CSDL\]](#) section 1.0.<1>. The mapping between Entity Data Model concepts and those of the AtomPub specification is specified in [\[MS-ODATA\]](#) section 2.2.1. The described relationship is provided to facilitate the explanation of how the protocol behaves. This document does not mandate that implementations adhere to this model, as long as their external behavior is consistent with the behavior specified in [\[MS-ODATA\]](#) and [\[MC-CSDL\]](#).

Data structures as specified in [\[MS-WSSTS\]](#) map to Entity Data Model terms as shown in the following table:

List Item Data Structure	Entity Data Model Term
List Item	<b>Entity</b>
Lookup Field	<b>Integer and NavigationProperty</b>
Choice Field	<b>Multi-Value Property</b>
Attachments Field	<b>Bool</b>
ID Field	<b>EntityKey</b>
Content Type	<b>Entity</b>
All other fields of a list item	<b>NavigationProperty</b>

### 3.2.1.3 Field Type to Client Scalar Property Type

The mapping from a **list item** entity field type to a client scalar property type is shown in the following table:

Field Type	Client Scalar Property Type
Boolean Attachments AllDayEvent CrossProjectLink Recurrence	<b>bool</b>
Calculated Choice Computed ContentTypeId File Note Text WorkflowEventType	<b>String</b>
Counter Integer ModStat WorkflowStatus	<b>Int</b>
Currency Number	<b>Double</b>
DateTime	<b>DateTime</b>
Error PageSeparator ThreadIndex Threading	<b>Object</b>
Guid	<b>Guid</b>
Lookup User	<b>Int or int[]</b>
GridChoice	<b>FieldRatingScaleQuestionAnswer[]</b>
MultiChoice	<b>String[]</b>
URL	<b>FieldUrlValue</b>

### 3.2.1.4 Social features

The server maintains a store of social signals associated with each **list item**. Social features allow the users to comment or like a list item or a **documents**.

Likes and comments MAY be allowed to be added on the list item by any user with read permissions.

For likes, the server maintains a list of Like entries for each list item. Each like entry includes:

Field	Description
Name	Name of the user who liked the list item
LoginName	<b>login name</b> of the user who liked the item
Id	Internal identifier of the user who liked the item. Each user MUST have unique internal identifier within a <b>sites (2)</b>
Email	<b>email address</b> of the user who liked the item
CreationDate	<b>Datetime</b> of when the user has liked the item

The server MUST NOT allow multiple like entries for the same user on the same list item.

Likes are maintained on any list item, including comment list items.

For comments, the server maintains a list of Comment entries for each list item. Each comment entry includes:

Field	Description
Id	<b>list item identifier</b> of the comment entry. MUST be unique for each comment entry on a site.
Text	Text of the comment
Author	User who made the comment
ListId	<b>list identifier</b> of the list item for which the comment is made
ItemId	list item identifier of the list item for which the comment is made
CreatedDate	Datetime when the comment was made
ParentId	Id of the parent comment. MUST be 0 for top level comments.
IsReply	MUST be TRUE for reply comments
ReplyCount	Number of reply comments. MUST be set on the parent comments of the reply comments.
IsLikedByUser	MUST be TRUE if the current user has liked the comment
LikedBy	List of users who liked the comment
Mentions	List of users mentioned in the comment

### 3.2.2 Timers

None.

### 3.2.3 Initialization

None.

### 3.2.4 Higher-Layer Triggered Events

None.

### 3.2.5 Message Processing Events and Sequencing Rules

#### 3.2.5.1 Microsoft.SharePoint.Client.AddFieldOptions

**ShortName:** SP.AddFieldOptions

**Flag:** true

Specifies the control settings while adding a field.

##### 3.2.5.1.1 Field Values

###### 3.2.5.1.1.1 DefaultValue

**Value:** 0

Same as **AddToDefaultContentType**.

###### 3.2.5.1.1.2 AddToDefaultContentType

**Value:** 1

Specifies that a new field added to the list MUST also be added to the default content type in the site collection.

###### 3.2.5.1.1.3 AddToNoContentType

**Value:** 2

Specifies that a new field MUST NOT be added to any other content type.

###### 3.2.5.1.1.4 AddToAllContentTypes

**Value:** 4

Specifies that a new field that is added to the specified list MUST also be added to all content types in the site collection.

###### 3.2.5.1.1.5 AddFieldInternalNameHint

**Value:** 8

Specifies adding an internal field name hint for the purpose of avoiding possible database locking or field renaming operations.

###### 3.2.5.1.1.6 AddFieldToDefaultView

**Value:** 16

Specifies that a new field that is added to the specified list MUST also be added to the default list view.

### 3.2.5.1.1.7 AddFieldCheckDisplayName

**Value:** 32

Specifies to confirm that no other field has the same display name.

### 3.2.5.2 Microsoft.SharePoint.Client.BasePermissions

**TypeId:** {DB780E5A-6BC6-41AD-8E64-9DFA761AFB6D}

**ShortName:** SP.BasePermissions

Specifies a set of built-in permissions.

#### 3.2.5.2.1 Properties

##### 3.2.5.2.1.1 Scalar Properties

###### 3.2.5.2.1.1.1 High

**Type:** CSOM UInt32

**Accessibility:** Read/Write

Specifies the most-significant 32 bits of the **BasePermissions** uint. The following table indicates the significance of having a particular bit set. Bits are numbered 1 to 32 from right to left.

Bit Number	Permission Name	Explanation
5	<b>UseClientIntegration</b>	Enables user to launch client applications.
6	<b>UseRemoteAPIs</b>	Allow use of <b>Simple Object Access Protocol (SOAP)</b> , <b>WebDAV</b> , or <a href="#">[MS-FPSE]</a> to access the <b>site (2)</b> .
7	<b>ManageAlerts</b>	Manage <b>alerts</b> for all users of the site (2).
8	<b>CreateAlerts</b>	Create e-mail alerts.
9	<b>EditMyUserInfo</b>	Allows a user to change his or her user information, such as adding a picture.
31	<b>EnumeratePermissions</b>	Enumerate permissions on site (2), <b>list</b> , <b>folder</b> , document, or <b>list item</b> .

###### 3.2.5.2.1.1.2 Low

**Type:** CSOM UInt32

**Accessibility:** Read/Write

Specifies the least-significant 32 bits of the **BasePermissions** uint. The following table indicates the significance of having a particular bit set. Bits are numbered 1 to 32 from right to left.

Bit Number	Permission Name	Explanation
1	<b>ViewListItems</b>	View <b>items</b> in <b>lists</b> , <b>documents</b> in <b>document libraries</b> , and <b>Web discussion comments</b> .
2	<b>AddListItems</b>	Add items to lists, documents to document libraries, and <b>Web discussion</b> .
3	<b>EditListItems</b>	Edit items in lists, edit documents in document libraries, edit Web discussion comments in documents, and customize <b>Web Part Pages</b> in document libraries.
4	<b>DeleteListItems</b>	Delete items from a list, documents from a document library, and Web discussion comments in documents.
5	<b>ApproveItems</b>	Approve a <b>minor version</b> of a <b>list item</b> or document.
6	<b>OpenItems</b>	View the source of documents with <b>file</b> handlers from the protocol server.
7	<b>ViewVersions</b>	View past <b>versions</b> of a list item or document.
8	<b>DeleteVersions</b>	Delete past versions of a list item or document.
9	<b>CancelCheckout</b>	Discard or check in a document that is <b>checked out</b> to another user.
10	<b>ManagePersonalViews</b>	Create, change, and delete <b>personal views</b> of lists.
12	<b>ManageLists</b>	Create and delete lists, add or remove columns in a list, and add or remove <b>public views</b> of a list.
13	<b>ViewFormPages</b>	View <b>forms</b> , <b>views</b> , and application pages, and enumerate lists.
17	<b>Open</b>	Allow users to open a <b>site (2)</b> , list, or <b>folder</b> to access items inside that container.
18	<b>ViewPages</b>	View pages in a site (2).
19	<b>AddAndCustomizePages</b>	Add, change, or delete <b>HTML</b> pages or Web Part Pages, and edit the site (2) by using a compatible editor.
20	<b>ApplyThemeAndBorder</b>	Apply a <b>theme</b> or borders to the entire site (2).



Bit Number	Permission Name	Explanation
21	<b>ApplyStyleSheets</b>	Apply a style sheet (.css file) to the site (2).
22	<b>ViewUsageData</b>	View reports on site (2) usage.
23	<b>CreateSSCSite</b>	Create a site (2) by using the self-service <b>site collection</b> creation feature.
24	<b>ManageSubwebs</b>	Create <b>subsites</b> such as team sites (2), <b>Meeting Workspace sites</b> , and Document Workspace sites (2).
25	<b>CreateGroups</b>	Create a <b>group</b> of users that can be used anywhere within the site collection.
26	<b>ManagePermissions</b>	Create and change <b>permission levels</b> on the site (2) and assign permissions to users and groups.
27	<b>BrowseDirectories</b>	Enumerate files and folders in a site (2) by using <a href="#">[MS-FPSE]</a> and <b>WebDAV</b> interfaces.
28	<b>BrowseUserInfo</b>	View information about users of the site (2).
29	<b>AddDelPrivateWebParts</b>	Add or remove personal <b>Web Parts</b> on a Web Part Page.
30	<b>UpdatePersonalWebParts</b>	Update Web Parts to display personalized information.
31	<b>ManageWeb</b>	Grant the ability for a <b>site collection administrator</b> to perform all administration <b>tasks</b> for the site (2) as well as manage content, activate, deactivate, or edit properties of site (2) scoped features through the <b>object (2)</b> model or through the user interface (UI).

### 3.2.5.2.1.2 ObjectPath Properties

None.

### 3.2.5.3 Microsoft.SharePoint.Client.BaseType

**ShortName:** SP.BaseType

**Flag:** false

Specified in [\[MS-WSSTS\]](#) section 2.5.

#### 3.2.5.3.1 Field Values

#### **3.2.5.3.1.1 None**

**Value:** -1

Specifies that no **base type** is specified.

#### **3.2.5.3.1.2 GenericList**

**Value:** 0

Specifies a **base type** for **lists** that do not correspond to another base type in this enumeration.

#### **3.2.5.3.1.3 DocumentLibrary**

**Value:** 1

Specifies a **base type** for a **document library**.

#### **3.2.5.3.1.4 Unused**

**Value:** 2

Reserved. MUST NOT be used.

#### **3.2.5.3.1.5 DiscussionBoard**

**Value:** 3

Specifies a **base type** that SHOULD NOT be used, but MAY [<2>](#) be used for a **discussion board**.

#### **3.2.5.3.1.6 Survey**

**Value:** 4

Specifies a **base type** for a **survey list**.

#### **3.2.5.3.1.7 Issue**

**Value:** 5

Specifies a base type for an issue tracking **list**.

### **3.2.5.4 Microsoft.SharePoint.Client.BrowserFileHandling**

**ShortName:** SP.BrowserFileHandling

**Flag:** false

Specifies the mode of handling files in the list.

#### **3.2.5.4.1 Field Values**

##### **3.2.5.4.1.1 Permissive**

**Value:** 0

Permissive mode of handling files. Value is 0.

##### **3.2.5.4.1.2 Strict**

**Value:** 1

Strict mode of handling files. Value is 1.

### **3.2.5.5 Microsoft.SharePoint.Client.CalendarType**

**ShortName:** SP.CalendarType

**Flag:** false

As specified in [\[MS-WSSFO2\]](#) section 2.2.3.3 or [\[MS-WSSFO3\]](#) section 2.2.1.2.3.

#### **3.2.5.5.1 Field Values**

##### **3.2.5.5.1.1 None**

**Value:** 0

Specifies that the **calendar type** is not specified.

##### **3.2.5.5.1.2 Gregorian**

**Value:** 1

Specifies a Gregorian (localized) **calendar type**.

##### **3.2.5.5.1.3 Japan**

**Value:** 3

Specifies a Japanese Emperor Era **calendar type**.

##### **3.2.5.5.1.4 Taiwan**

**Value:** 4

Specifies a Year of Taiwan **calendar type**.

##### **3.2.5.5.1.5 Korea**

**Value:** 5

Specifies a Korean Tangun Era **calendar type**.

##### **3.2.5.5.1.6 Hijri**

**Value:** 6

Specifies a Hijri (Arabic Lunar) **calendar type**.

##### **3.2.5.5.1.7 Thai**

**Value:** 7

Specifies a Thai **calendar type**.

##### **3.2.5.5.1.8 Hebrew**

**Value:** 8

Specifies a Hebrew (Lunar) **calendar type**.

#### **3.2.5.5.1.9 GregorianMEFrench**

**Value:** 9

Specifies a Gregorian (Middle East French) **calendar type**.

#### **3.2.5.5.1.10 GregorianArabic**

**Value:** 10

Specifies a Gregorian (Arabic) **calendar type**.

#### **3.2.5.5.1.11 GregorianXLITEnglish**

**Value:** 11

Specifies a Gregorian (transliterated English) **calendar type**.

#### **3.2.5.5.1.12 GregorianXLITFrench**

**Value:** 12

Specifies a Gregorian (transliterated French) **calendar type**.

#### **3.2.5.5.1.13 KoreaJapanLunar**

**Value:** 14

Specifies a Korean and Japanese Lunar **calendar type**.

#### **3.2.5.5.1.14 ChineseLunar**

**Value:** 15

Specifies a Chinese Lunar **calendar type**.

#### **3.2.5.5.1.15 SakaEra**

**Value:** 16

Specifies a Saka Era **calendar type**.

#### **3.2.5.5.1.16 UmAlQura**

**Value:** 23

Specifies an Umm al-Qura **calendar type**.[<3>](#)

### **3.2.5.6 Microsoft.SharePoint.Client.CamlQuery**

**TypeId:** {3D248D7B-FC86-40A3-AA97-02A75D69FB8A}

**ShortName:** SP.CamlQuery

Specifies a **query** on a **list**.

#### **3.2.5.6.1 Properties**

### 3.2.5.6.1.1 Scalar Properties

#### 3.2.5.6.1.1.1 AllowIncrementalResults

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Specifies whether the incremental results can be returned.

#### 3.2.5.6.1.1.2 DatesInUtc

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Specifies whether the **query** returns dates in **Coordinated Universal Time (UTC)** format.

#### 3.2.5.6.1.1.3 FolderServerRelativePath

**Type:** Microsoft.SharePoint.Client.ResourcePath

**Accessibility:** Read/Write

Specifies the path to the folder from which to return items in the query.

#### 3.2.5.6.1.1.4 FolderServerRelativeUrl

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies the **server-relative URL** of a **list folder** from which results are to be returned.

It MUST be a URL of server-relative form.

#### 3.2.5.6.1.1.5 ListItemCollectionPosition

**Type:** Microsoft.SharePoint.Client.ListItemCollectionPosition

**Accessibility:** Read/Write

Specifies the information required to get the next page of data for the **list view**.

#### 3.2.5.6.1.1.6 ViewXml

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies the **XML schema** that defines the **list view**.

It MUST be NULL, empty, or an **XML fragment** that conforms to the **ViewDefinition** type as defined in [\[MS-WSSCAML\]](#) section 2.3.2.17.

### 3.2.5.6.1.2 ObjectPath Properties

None.

### 3.2.5.7 Microsoft.SharePoint.Client.Change

**TypeId:** {C717121B-F82F-4AFB-A2B7-25F67522120F}

**ShortName:** SP.Change

Base class for a change. installation.

The RelativeTime property is not included in the **default scalar property set** for this type.

#### 3.2.5.7.1 Properties

##### 3.2.5.7.1.1 Scalar Properties

###### 3.2.5.7.1.1.1 ChangeToken

**Type:** Microsoft.SharePoint.Client.ChangeToken

**Accessibility:** Read Only

Returns an SP.ChangeToken that represents the change.

###### 3.2.5.7.1.1.2 ChangeType

**Type:** Microsoft.SharePoint.Client.ChangeType

**Accessibility:** Read Only

Returns an SP.ChangeType that indicates the type of change, including adding, updating, deleting, or renaming changes, but also moving items away from or into lists and folders.

###### 3.2.5.7.1.1.3 RelativeTime

**Type:** CSOM String

**Accessibility:** Read Only

A string representing a relative value of time.

The value is composed of two parts in the format "mode|timevalue".

If Mode is 0, the timevalue MUST be the text passed through as the display text for end user display.

If Mode is 1, the timevalue MUST be a relative display mode in the format "bFuture|bucket|args" using the following values:

- bFuture refers to whether time is later than UtcNow
- bucket indicates the type of string to output
- args contains the values that will be inserted into the string referenced by the bucket

###### 3.2.5.7.1.1.4 SiteId

**Type:** CSOM GUID

**Accessibility:** Read Only

SiteId Returns the Id of the site of the changed item

###### 3.2.5.7.1.1.5 Time

**Type:** CSOM DateTime

**Accessibility:** Read Only

Time Returns the time the item was modified. This is not the same as the time that the change was committed to the change log.

### 3.2.5.7.1.2 ObjectPath Properties

None.

### 3.2.5.7.2 Methods

#### 3.2.5.7.2.1 Scalar Methods

None.

#### 3.2.5.7.2.2 ObjectPath Methods

None.

### 3.2.5.8 Microsoft.SharePoint.Client.ChangeAlert

**TypeId:** {04F51EF5-013C-4E05-B23F-A9719E69A49A}

**ShortName:** SP.ChangeAlert

Specifies a change from an **alert**.

The RelativeTime property is not included in the **default scalar property set** for this type.

### 3.2.5.8.1 Properties

#### 3.2.5.8.1.1 Scalar Properties

##### 3.2.5.8.1.1.1 AlertId

**Type:** CSOM GUID

**Accessibility:** Read Only

Identifies the changed **alert**.

##### 3.2.5.8.1.1.2 ChangeToken

**Type:** Microsoft.SharePoint.Client.ChangeToken

**Accessibility:** Read Only

See **Microsoft.SharePoint.Client.Change.ChangeToken**, as specified in section [3.2.5.7.1.1.1](#).

##### 3.2.5.8.1.1.3 ChangeType

**Type:** Microsoft.SharePoint.Client.ChangeType

**Accessibility:** Read Only

See **Microsoft.SharePoint.Client.Change.ChangeType**, as specified in section [3.2.5.7.1.1.2](#).

#### 3.2.5.8.1.1.4 RelativeTime

Type: **CSOM String**

Accessibility: Read Only

See Microsoft.SharePoint.Client.Change.RelativeTime, as specified in section [3.2.5.7.1.1.3](#).

#### 3.2.5.8.1.1.5 SiteId

Type: **CSOM GUID**

Accessibility: Read Only

See **Microsoft.SharePoint.Client.Change.SiteId**, as specified in section [3.2.5.7.1.1.4](#).

#### 3.2.5.8.1.1.6 Time

Type: **CSOM DateTime**

Accessibility: Read Only

See **Microsoft.SharePoint.Client.Change.Time**, as specified in section [3.2.5.7.1.1.5](#).

#### 3.2.5.8.1.1.7 WebId

Type: **CSOM GUID**

Accessibility: Read Only

Identifies the **site (2)** that contains the changed **alert**.

#### Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	The <b>site identifier</b> in the change <b>fields (2)</b> item of the change collection is NULL.

#### 3.2.5.8.1.2 ObjectPath Properties

None.

#### 3.2.5.8.2 Methods

##### 3.2.5.8.2.1 Scalar Methods

None.

##### 3.2.5.8.2.2 ObjectPath Methods

None.

#### 3.2.5.9 Microsoft.SharePoint.Client.ChangeCollection

**TypeId:** {2BA7A459-EEDA-42D0-90E2-FAD3487AD0D3}



**ShortName:** SP.ChangeCollection

Represents a collection of **Change objects (1)**.

### 3.2.5.9.1 Properties

#### 3.2.5.9.1.1 Scalar Properties

None.

#### 3.2.5.9.1.2 ObjectPath Properties

None.

### 3.2.5.9.2 Methods

#### 3.2.5.9.2.1 Scalar Methods

None.

#### 3.2.5.9.2.2 ObjectPath Methods

None.

### 3.2.5.10 Microsoft.SharePoint.Client.ChangeContentType

**TypeId:** {B50EF7A3-7F78-4AFC-91EF-616591DE9E4D}

**ShortName:** SP.ChangeContentType

Specifies a change on a **content type**.

The RelativeTime property is not included in the **default scalar property set** for this type.

#### 3.2.5.10.1 Properties

##### 3.2.5.10.1.1 Scalar Properties

###### 3.2.5.10.1.1.1 ChangeToken

**Type:** Microsoft.SharePoint.Client.ChangeToken

**Accessibility:** Read Only

See **Microsoft.SharePoint.Client.Change.ChangeToken**, as specified in section [3.2.5.7.1.1.1](#).

###### 3.2.5.10.1.1.2 ChangeType

**Type:** Microsoft.SharePoint.Client.ChangeType

**Accessibility:** Read Only

See **Microsoft.SharePoint.Client.Change.ChangeType**, as specified in section [3.2.5.7.1.1.2](#).

###### 3.2.5.10.1.1.3 ContentTypeId

**Type:** Microsoft.SharePoint.Client.ContentTypeId

**Accessibility:** Read Only

Identifies the **content type** that has changed.

#### 3.2.5.10.1.1.4 RelativeTime

**Type:** CSOM String

**Accessibility:** Read Only

See Microsoft.SharePoint.Client.Change.RelativeTime, as specified in section [3.2.5.7.1.1.3](#).

#### 3.2.5.10.1.1.5 SiteId

**Type:** CSOM GUID

**Accessibility:** Read Only

See Microsoft.SharePoint.Client.Change.SiteId, as specified in section [3.2.5.7.1.1.4](#).

#### 3.2.5.10.1.1.6 Time

**Type:** CSOM DateTime

**Accessibility:** Read Only

See Microsoft.SharePoint.Client.Change.Time, as specified in section [3.2.5.7.1.1.5](#).

#### 3.2.5.10.1.1.7 WebId

**Type:** CSOM GUID

**Accessibility:** Read Only

Identifies the **site (2)** that contains the changed **content type**.

#### Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	The <b>site identifier</b> in the change <b>fields (2)</b> item of the change collection is NULL.

#### 3.2.5.10.1.2 ObjectPath Properties

None.

#### 3.2.5.10.2 Methods

##### 3.2.5.10.2.1 Scalar Methods

None.

##### 3.2.5.10.2.2 ObjectPath Methods

None.

### 3.2.5.11 Microsoft.SharePoint.Client.ChangeField

**TypeId:** {8D687151-6601-4AD0-9E94-91448E3E2749}

**ShortName:** SP.ChangeField

Specifies a change on a **field (2)**.

The RelativeTime property is not included in the **default scalar property set** for this type.

#### 3.2.5.11.1 Properties

##### 3.2.5.11.1.1 Scalar Properties

###### 3.2.5.11.1.1.1 ChangeToken

**Type:** Microsoft.SharePoint.Client.ChangeToken

**Accessibility:** Read Only

See **Microsoft.SharePoint.Client.Change.ChangeToken**, as specified in section [3.2.5.7.1.1.1](#).

###### 3.2.5.11.1.1.2 ChangeType

**Type:** Microsoft.SharePoint.Client.ChangeType

**Accessibility:** Read Only

See **Microsoft.SharePoint.Client.Change.ChangeType**, as specified in section [3.2.5.7.1.1.2](#).

###### 3.2.5.11.1.1.3 FieldId

**Type:** **CSOM GUID**

**Accessibility:** Read Only

Identifies the changed **field (2)**.

#### Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	The <b>field identifier</b> in the change fields (2) item of the change collection is NULL.

###### 3.2.5.11.1.1.4 RelativeTime

**Type:** **CSOM String**

**Accessibility:** Read Only

See Microsoft.SharePoint.Client.Change.RelativeTime, as specified in section [3.2.5.7.1.1.3](#).

###### 3.2.5.11.1.1.5 SiteId

**Type:** **CSOM GUID**

**Accessibility:** Read Only

See **Microsoft.SharePoint.Client.Change.SiteId**, as specified in section [3.2.5.7.1.1.4](#).

### 3.2.5.11.1.1.6 Time

**Type:** CSOM DateTime

**Accessibility:** Read Only

See Microsoft.SharePoint.Client.Change.Time, as specified in section [3.2.5.7.1.1.5](#).

### 3.2.5.11.1.1.7 WebId

**Type:** CSOM GUID

**Accessibility:** Read Only

Identifies the **site (2)** that contains the changed **field (2)**.

#### Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	The <b>site identifier</b> in the change fields (2) item of the change collection is NULL.

### 3.2.5.11.1.2 ObjectPath Properties

None.

### 3.2.5.11.2 Methods

#### 3.2.5.11.2.1 Scalar Methods

None.

#### 3.2.5.11.2.2 ObjectPath Methods

None.

### 3.2.5.12 Microsoft.SharePoint.Client.ChangeFile

**TypeId:** {59DD36EB-9235-4DAD-A8FD-26D3C11A6A18}

**ShortName:** SP.ChangeFile

Specifies a change on a file not contained in a document library.

The RelativeTime property is not included in the **default scalar property set** for this type.

### 3.2.5.12.1 Properties

#### 3.2.5.12.1.1 Scalar Properties

### 3.2.5.12.1.1.1 ChangeToken

**Type:** Microsoft.SharePoint.Client.ChangeToken

**Accessibility:** Read Only

See **Microsoft.SharePoint.Client.Change.ChangeToken**, as specified in section [3.2.5.7.1.1.1](#).

### 3.2.5.12.1.1.2 ChangeType

**Type:** Microsoft.SharePoint.Client.ChangeType

**Accessibility:** Read Only

See **Microsoft.SharePoint.Client.Change.ChangeType**, as specified in section [3.2.5.7.1.1.2](#).

### 3.2.5.12.1.1.3 RelativeTime

**Type:** CSOM String

**Accessibility:** Read Only

See Microsoft.SharePoint.Client.Change.RelativeTime, as specified in section [3.2.5.7.1.1.3](#).

### 3.2.5.12.1.1.4 SiteId

**Type:** CSOM GUID

**Accessibility:** Read Only

See **Microsoft.SharePoint.Client.Change.SiteId**, as specified in section [3.2.5.7.1.1.4](#).

### 3.2.5.12.1.1.5 Time

**Type:** CSOM DateTime

**Accessibility:** Read Only

See **Microsoft.SharePoint.Client.Change.Time**, as specified in section [3.2.5.7.1.1.5](#).

### 3.2.5.12.1.1.6 UniqueId

**Type:** CSOM GUID

**Accessibility:** Read Only

Identifies the **file** that changed.

#### Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	The <b>document identifier</b> in the change <b>fields (2)</b> item of the change collection is NULL.

### 3.2.5.12.1.1.7 WebId

Type: **CSOM GUID**

Accessibility: Read Only

Identifies the **site (2)** that contains the changed **file**.

Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	The <b>site identifier</b> in the change <b>fields (2)</b> item of the change collection is NULL.

### 3.2.5.12.1.2 ObjectPath Properties

None.

### 3.2.5.12.2 Methods

#### 3.2.5.12.2.1 Scalar Methods

None.

#### 3.2.5.12.2.2 ObjectPath Methods

None.

### 3.2.5.13 Microsoft.SharePoint.Client.ChangeFolder

**TypeId:** {3B97573D-CEE5-446A-853D-57EA0ACF8AA4}

**ShortName:** SP.ChangeFolder

Specifies a change on a **folder** not contained in a **list** or **document library**.

The RelativeTime property is not included in the **default scalar property set** for this type.

#### 3.2.5.13.1 Properties

##### 3.2.5.13.1.1 Scalar Properties

###### 3.2.5.13.1.1.1 ChangeToken

**Type:** Microsoft.SharePoint.Client.ChangeToken

**Accessibility:** Read Only

See **Microsoft.SharePoint.Client.Change.ChangeToken**, as specified in section [3.2.5.7.1.1.1](#).

###### 3.2.5.13.1.1.2 ChangeType

**Type:** Microsoft.SharePoint.Client.ChangeType

**Accessibility:** Read Only

See **Microsoft.SharePoint.Client.Change.ChangeType**, as specified in section [3.2.5.7.1.1.2](#).

### 3.2.5.13.1.1.3 RelativeTime

Type: **CSOM String**

Accessibility: Read Only

See Microsoft.SharePoint.Client.Change.RelativeTime, as specified in section [3.2.5.7.1.1.3](#).

### 3.2.5.13.1.1.4 SiteId

Type: **CSOM GUID**

Accessibility: Read Only

See **Microsoft.SharePoint.Client.Change.SiteId**, as specified in section [3.2.5.7.1.1.4](#).

### 3.2.5.13.1.1.5 Time

Type: **CSOM DateTime**

Accessibility: Read Only

See **Microsoft.SharePoint.Client.Change.Time**, as specified in section [3.2.5.7.1.1.5](#).

### 3.2.5.13.1.1.6 UniqueId

Type: **CSOM GUID**

Accessibility: Read Only

Identifies the **folder** that has changed.

#### Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	The <b>document identifier</b> in the change <b>fields (2)</b> item of the change collection is NULL.

### 3.2.5.13.1.1.7 WebId

Type: **CSOM GUID**

Accessibility: Read Only

Identifies the **site (2)** that contains the changed **folder**.

#### Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	The <b>site identifier</b> in the change <b>fields (2)</b> item of the change collection is NULL.

### 3.2.5.13.1.2 ObjectPath Properties

None.

### 3.2.5.13.2 Methods

#### 3.2.5.13.2.1 Scalar Methods

None.

#### 3.2.5.13.2.2 ObjectPath Methods

None.

### 3.2.5.14 Microsoft.SharePoint.Client.ChangeGroup

**TypeId:** {8C377687-4E62-4DDB-B244-20A832DE16DD}

**ShortName:** SP.ChangeGroup

Specifies a change on a **group**.

The RelativeTime property is not included in the **default scalar property set** for this type.

#### 3.2.5.14.1 Properties

##### 3.2.5.14.1.1 Scalar Properties

###### 3.2.5.14.1.1.1 ChangeToken

**Type:** Microsoft.SharePoint.Client.ChangeToken

**Accessibility:** Read Only

See **Microsoft.SharePoint.Client.Change.ChangeToken**, as specified in section [3.2.5.7.1.1.1](#).

###### 3.2.5.14.1.1.2 ChangeType

**Type:** Microsoft.SharePoint.Client.ChangeType

**Accessibility:** Read Only

See **Microsoft.SharePoint.Client.Change.ChangeType**, as specified in section [3.2.5.7.1.1.2](#).

###### 3.2.5.14.1.1.3 GroupId

**Type:** **CSOM Int32**

**Accessibility:** Read Only

Identifies the changed **group**.

###### 3.2.5.14.1.1.4 RelativeTime

**Type:** **CSOM String**



**Accessibility:** Read Only

See `Microsoft.SharePoint.Client.Change.RelativeTime`, as specified in section [3.2.5.7.1.1.3](#).

### 3.2.5.14.1.1.5 **SiteId**

**Type:** **CSOM GUID**

**Accessibility:** Read Only

See `Microsoft.SharePoint.Client.Change.SiteId`, as specified in section [3.2.5.7.1.1.4](#).

### 3.2.5.14.1.1.6 **Time**

**Type:** **CSOM DateTime**

**Accessibility:** Read Only

See `Microsoft.SharePoint.Client.Change.Time`, as specified in section [3.2.5.7.1.1.5](#).

## 3.2.5.14.1.2 **ObjectPath Properties**

None.

## 3.2.5.14.2 **Methods**

### 3.2.5.14.2.1 **Scalar Methods**

None.

### 3.2.5.14.2.2 **ObjectPath Methods**

None.

## 3.2.5.15 **Microsoft.SharePoint.Client.ChangeItem**

**TypeId:** {3E4716AC-A622-4D48-BC14-3FECABD52E21}

**ShortName:** SP.ChangeItem

Specifies a change on an **item**.

The `ActivityType`, `ContentTypeId`, `EditorLoginName`, `FileSystemObjectType`, `FileType`, `Hidden`, `ListTemplate`, `ListTitle`, `RelativeTime` and `Title` properties are not included in the **default scalar property set** for this type.

### 3.2.5.15.1 **Properties**

#### 3.2.5.15.1.1 **Scalar Properties**

##### 3.2.5.15.1.1.1 **ActivityType**

**Type:** `Microsoft.SharePoint.Client.SPChangeActivityType`

**Accessibility:** Read Only

Returns activity type defined in section [3.2.5.462](#)

### **3.2.5.15.1.1.2      ChangeToken**

**Type:** Microsoft.SharePoint.Client.ChangeToken

**Accessibility:** Read Only

See **Microsoft.SharePoint.Client.Change.ChangeToken**, as specified in section [3.2.5.7.1.1.1](#).

### **3.2.5.15.1.1.3      ChangeType**

**Type:** Microsoft.SharePoint.Client.ChangeType

**Accessibility:** Read Only

See **Microsoft.SharePoint.Client.Change.ChangeType**, as specified in section [3.2.5.7.1.1.2](#).

### **3.2.5.15.1.1.4      ContentTypeId**

**Type:** Microsoft.SharePoint.Client.ContentTypeId

**Accessibility:** Read Only

Specifies an identifier for the **content type** as specified in [\[MS-WSSTS\]](#) section 2.1.2.8.1.

### **3.2.5.15.1.1.5      Editor**

**Type:** **CSOM String**

**Accessibility:** Read Only

Specifies the editor of the changed **item**.

### **3.2.5.15.1.1.6      EditorEmailHint**

**Type:** **CSOM String**

**Accessibility:** Read Only

Returns the email corresponding to **Editor**.

### **3.2.5.15.1.1.7      EditorLoginName**

**Type:** **CSOM String**

**Accessibility:** Read Only

Returns **login name** of the **Editor**.

### **3.2.5.15.1.1.8      FileSystemObjectType**

**Type:** Microsoft.SharePoint.Client.FileSystemObjectType

**Accessibility:** Read Only

Returns the **list item's** object type in **file system**.

### **3.2.5.15.1.1.9      FileType**

**Type:** **CSOM String**

**Accessibility:** Read Only

Returns the **list item's file** type.

### 3.2.5.15.1.1.10 Hidden

**Type:** CSOM Boolean

**Accessibility:** Read Only

Returns a **Boolean** value that indicates whether the parent **list** is a **hidden** list.

### 3.2.5.15.1.1.11 ItemId

**Type:** CSOM Int32

**Accessibility:** Read Only

Identifies the changed **item**.

**Exceptions:**

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	The <b>item identifier</b> in the change <b>fields (2)</b> item of the change collection is NULL.

### 3.2.5.15.1.1.12 ListId

**Type:** CSOM GUID

**Accessibility:** Read Only

Identifies the **list** that contains the changed **item**. In the case of a change that includes moving the item between lists, **ListId** MUST contain the value it had before the move.

**Exceptions:**

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	The <b>list identifier</b> in the change <b>fields (2)</b> item of the change collection is NULL.

### 3.2.5.15.1.1.13 ListTemplate

**Type:** Microsoft.SharePoint.Client.ListTemplateType

**Accessibility:** Read Only

An SP.ListTemplateType object that returns the **list template** type of the **list**.

### 3.2.5.15.1.1.14 ListTitle

**Type:** CSOM String

**Accessibility:** Read Only

A string representing the title of the **list**.

### **3.2.5.15.1.1.15      RelativeTime**

**Type:** **CSOM String**

**Accessibility:** Read Only

See `Microsoft.SharePoint.Client.Change.RelativeTime`, as specified in section [3.2.5.7.1.1.3](#).

### **3.2.5.15.1.1.16      ServerRelativeUrl**

**Type:** **CSOM String**

**Accessibility:** Read Only

Specifies the **server-relative URL** of the **item**.

### **3.2.5.15.1.1.17      SharedByUser**

**Type:** `Microsoft.SharePoint.Client.SharedWithUser`

**Accessibility:** Read Only

Return the sharedBy User Information in sharing action for change log.

### **3.2.5.15.1.1.18      SharedWithUsers**

**Type:** `Microsoft.SharePoint.Client.SharedWithUserCollection`

**Accessibility:** Read Only

Returns the array of users that have been shared in sharing action for the change log.

### **3.2.5.15.1.1.19      SiteId**

**Type:** **CSOM GUID**

**Accessibility:** Read Only

See `Microsoft.SharePoint.Client.Change.SiteId`, as specified in section [3.2.5.7.1.1.4](#).

### **3.2.5.15.1.1.20      Time**

**Type:** **CSOM DateTime**

**Accessibility:** Read Only

See `Microsoft.SharePoint.Client.Change.Time`, as specified in section [3.2.5.7.1.1.5](#).

### **3.2.5.15.1.1.21      Title**

**Type:** **CSOM String**

**Accessibility:** Read Only

Returns the **list item's** title.

### 3.2.5.15.1.1.22 UniqueId

**Type:** CSOM GUID

**Accessibility:** Read Only

The **Document identifier** of the item.

### 3.2.5.15.1.1.23 WebId

**Type:** CSOM GUID

**Accessibility:** Read Only

Identifies the **site (2)** that contains the changed **item**.

#### Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	The <b>site identifier</b> in the change <b>fields (2)</b> item of the change collection is NULL.

### 3.2.5.15.1.2 ObjectPath Properties

None.

### 3.2.5.15.2 Methods

#### 3.2.5.15.2.1 Scalar Methods

None.

#### 3.2.5.15.2.2 ObjectPath Methods

None.

### 3.2.5.16 Microsoft.SharePoint.Client.ChangeList

**TypeId:** {D3EF3368-FF71-4DE1-867C-19693C781587}

**ShortName:** SP.ChangeList

Specifies a change on a **list**.

The RelativeTime and RootFolderUrl properties are not included in the **default scalar property set** for this type.

#### 3.2.5.16.1 Properties

##### 3.2.5.16.1.1 Scalar Properties

###### 3.2.5.16.1.1.1 BaseTemplate

**Type:** Microsoft.SharePoint.Client.ListTemplateType

**Accessibility:** Read Only

An SP.ListTemplateType object that returns the **list template** type of the **list**.

### 3.2.5.16.1.1.2 ChangeToken

**Type:** Microsoft.SharePoint.Client.ChangeToken

**Accessibility:** Read Only

See **Microsoft.SharePoint.Client.Change.ChangeToken**, as specified in section [3.2.5.7.1.1.1](#).

### 3.2.5.16.1.1.3 ChangeType

**Type:** Microsoft.SharePoint.Client.ChangeType

**Accessibility:** Read Only

See **Microsoft.SharePoint.Client.Change.ChangeType**, as specified in section [3.2.5.7.1.1.2](#).

### 3.2.5.16.1.1.4 Editor

**Type:** CSOM String

**Accessibility:** Read Only

A string that returns the name of the **user (2)** who modified the **list**.

### 3.2.5.16.1.1.5 Hidden

**Type:** CSOM Boolean

**Accessibility:** Read Only

Returns a **Boolean** value that indicates whether a **list** is a hidden **hidden** list.

### 3.2.5.16.1.1.6 ListId

**Type:** CSOM GUID

**Accessibility:** Read Only

Identifies the changed **list**.

#### Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	The <b>list identifier</b> contained in the change <b>fields (2)</b> item of the change collection is NULL.

### 3.2.5.16.1.1.7 RelativeTime

**Type:** CSOM String

**Accessibility:** Read Only

See `Microsoft.SharePoint.Client.Change.RelativeTime`, as specified in section [3.2.5.7.1.1.3](#).

### 3.2.5.16.1.1.8 RootFolderUrl

**Type:** CSOM String

**Accessibility:** Read Only

A string that returns the **root folder URL** of the **list**.

### 3.2.5.16.1.1.9 SiteId

**Type:** CSOM GUID

**Accessibility:** Read Only

See `Microsoft.SharePoint.Client.Change.SiteId`, as specified in section [3.2.5.7.1.1.4](#).

### 3.2.5.16.1.1.10 Time

**Type:** CSOM DateTime

**Accessibility:** Read Only

See `Microsoft.SharePoint.Client.Change.Time`, as specified in section [3.2.5.7.1.1.5](#).

### 3.2.5.16.1.1.11 Title

**Type:** CSOM String

**Accessibility:** Read Only

A string that returns the **list** title.

### 3.2.5.16.1.1.12 WebId

**Type:** CSOM GUID

**Accessibility:** Read Only

Identifies the **site (2)** that contains the changed **list**.

#### Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	The <b>site identifier</b> in the change <b>fields (2)</b> item of the change collection is NULL.

## 3.2.5.16.1.2 ObjectPath Properties

### 3.2.5.16.1.2.1 Creator

**Type:** `Microsoft.SharePoint.Client.User`

**Accessibility:** Read Only

An SP.User **object (1)** that represents information about the **user (2)** who created the **list**.

### **3.2.5.16.2 Methods**

#### **3.2.5.16.2.1 Scalar Methods**

None.

#### **3.2.5.16.2.2 ObjectPath Methods**

None.

### **3.2.5.17 Microsoft.SharePoint.Client.ChangeQuery**

**TypeId:** {887A7218-1232-4CFC-B78F-88D54E9D8EC7}

**ShortName:** SP.ChangeQuery

Defines a query that is performed against the change log.

#### **3.2.5.17.1 Properties**

##### **3.2.5.17.1.1 Scalar Properties**

###### **3.2.5.17.1.1.1 Activity**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Specifies whether activities are included in the query.

###### **3.2.5.17.1.1.2 Add**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Specifies whether add changes are included in the query.

###### **3.2.5.17.1.1.3 Alert**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Specifies whether changes to alerts are included in the query.

###### **3.2.5.17.1.1.4 ChangeTokenEnd**

**Type:** Microsoft.SharePoint.Client.ChangeToken

**Accessibility:** Read/Write

Specifies the end date and end time for changes that are returned through the query.

###### **3.2.5.17.1.1.5 ChangeTokenStart**



**Type:** Microsoft.SharePoint.Client.ChangeToken

**Accessibility:** Read/Write

Specifies the start date and start time for changes that are returned through the query.

#### **3.2.5.17.1.1.6      ContentType**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Specifies whether changes to content types are included in the query.

#### **3.2.5.17.1.1.7      DeleteObject**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Specifies whether delete changes are included in the query.

#### **3.2.5.17.1.1.8      FetchLimit**

**Type:** CSOM Int64

**Accessibility:** Read/Write

Specifies the maximum number of changes to fetch from the database.

#### **3.2.5.17.1.1.9      Field**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Specifies whether changes to site columns are included in the query.

#### **3.2.5.17.1.1.10    File**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Specifies whether changes to files are included in the query.

#### **3.2.5.17.1.1.11    Folder**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Specifies whether changes to folders are included in the query.

#### **3.2.5.17.1.1.12    Group**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Specifies whether changes to groups are included in the query.

#### **3.2.5.17.1.1.13 GroupMembershipAdd**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Specifies whether adding users to groups is included in the change query.

#### **3.2.5.17.1.1.14 GroupMembershipDelete**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Specifies whether deleting users from groups is included in the change query.

#### **3.2.5.17.1.1.15 Item**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Specifies whether general changes to list or site items are included in the query.

#### **3.2.5.17.1.1.16 LatestFirst**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Specifies whether or not logs are returned in chronological order or in reverse order. If true, the latest logs are returned first.

#### **3.2.5.17.1.1.17 List**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Specifies whether changes to lists are included in the query.

#### **3.2.5.17.1.1.18 Move**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Specifies whether move changes are included in the query.

#### **3.2.5.17.1.1.19 Navigation**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Specifies whether changes to the navigation structure of a site collection are included in the query.

#### **3.2.5.17.1.1.20 RecursiveAll**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Specifies whether all **change logs** are returned for the folder scoped query. This flag will only work for a Folder query. If true, all changes in the current folder and all sub folders will be returned. Otherwise, only changes in the current folder will be returned.

### **3.2.5.17.1.1.21 Rename**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Specifies whether renaming changes are included in the query.

### **3.2.5.17.1.1.22 RequireSecurityTrim**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Specifies whether **change logs** are returned with **security trimming**. If true, only the change logs that **current user** has **permission** to view are returned.

### **3.2.5.17.1.1.23 Restore**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Specifies whether restoring items from the Recycle Bin is included in the query.

### **3.2.5.17.1.1.24 RoleAssignmentAdd**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Specifies whether adding role assignments is included in the query.

### **3.2.5.17.1.1.25 RoleAssignmentDelete**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Specifies whether deleting role assignments is included in the query.

### **3.2.5.17.1.1.26 RoleDefinitionAdd**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Specifies whether adding role definitions is included in the query.

### **3.2.5.17.1.1.27 RoleDefinitionDelete**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Specifies whether deleting role definitions is included in the query.

### **3.2.5.17.1.1.28 RoleDefinitionUpdate**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Specifies whether modifying role definitions is included in the query.

### **3.2.5.17.1.1.29 SecurityPolicy**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Specifies whether modifications to security policies are included in the query.

### **3.2.5.17.1.1.30 Site**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Specifies whether changes to site collections are included in the query.

### **3.2.5.17.1.1.31 SystemUpdate**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Specifies whether changes that are global within the scope of the change collection are included in the query.

### **3.2.5.17.1.1.32 Update**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Specifies whether update changes are included in the query.

### **3.2.5.17.1.1.33 User**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Specifies whether changes to users are included in the query.

### **3.2.5.17.1.1.34 View**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Specifies whether changes to views are included in the query.

### 3.2.5.17.1.1.35 Web

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Specifies whether changes to Web sites are included in the query.

### 3.2.5.17.1.2 ObjectPath Properties

None.

## 3.2.5.18 Microsoft.SharePoint.Client.ChangeSite

**TypeId:** {81AFF0DE-302E-4D01-91D5-96192F77BC29}

**ShortName:** SP.ChangeSite

Specifies a change on a **site collection**.

The RelativeTime property is not included in the **default scalar property set** for this type.

### 3.2.5.18.1 Properties

#### 3.2.5.18.1.1 Scalar Properties

##### 3.2.5.18.1.1.1 ChangeToken

**Type:** Microsoft.SharePoint.Client.ChangeToken

**Accessibility:** Read Only

See **Microsoft.SharePoint.Client.Change.ChangeToken**, as specified in section [3.2.5.7.1.1.1](#)

##### 3.2.5.18.1.1.2 ChangeType

**Type:** Microsoft.SharePoint.Client.ChangeType

**Accessibility:** Read Only

See **Microsoft.SharePoint.Client.Change.ChangeType**, as specified in section [3.2.5.7.1.1.2](#).

##### 3.2.5.18.1.1.3 RelativeTime

**Type:** CSOM String

**Accessibility:** Read Only

See Microsoft.SharePoint.Client.Change.RelativeTime, as specified in section [3.2.5.7.1.1.3](#).

##### 3.2.5.18.1.1.4 SiteId

**Type:** CSOM GUID

**Accessibility:** Read Only

See **Microsoft.SharePoint.Client.Change.SiteId**, as specified in section [3.2.5.7.1.1.4](#).

##### 3.2.5.18.1.1.5 Time

Type: **CSOM DateTime**

Accessibility: Read Only

See **Microsoft.SharePoint.Client.Change.Time**, as specified in section [3.2.5.7.1.1.5](#).

### 3.2.5.18.1.2 ObjectPath Properties

None.

### 3.2.5.18.2 Methods

#### 3.2.5.18.2.1 Scalar Methods

None.

#### 3.2.5.18.2.2 ObjectPath Methods

None.

### 3.2.5.19 Microsoft.SharePoint.Client.ChangeToken

**TypeId:** {41C5BE82-B5BF-4B5A-9712-97111FB87686}

**ShortName:** SP.ChangeToken

Represents the unique sequential location of a change within the **change log**. Client applications can use the **change token** as a starting point for retrieving changes.

#### 3.2.5.19.1 Properties

##### 3.2.5.19.1.1 Scalar Properties

###### 3.2.5.19.1.1.1 StringValue

Type: **CSOM String**

Accessibility: Read/Write

Contains the serialized representation of the **change token** generated by the protocol server. When setting **StringValue**, the protocol client MUST use a value previously returned by the protocol server.

Represented as a semicolon-separated list containing the following, in order:

1. The version number of the change token.
2. The change token's collection scope.
3. The collection scope **GUID**.
4. The time of the change token in ticks.
5. The change number.

The collection scope MUST be one of the values listed in the following table.

Value	Description
0	The change token refers to a <b>content database</b> .

Value	Description
1	The change token refers to a <b>site collection</b> .
2	The change token refers to a <b>site (2)</b> .
3	The change token refers to a <b>list</b> .

#### Exceptions:

Error Code	Error Type Name	Condition
-1	System.FormatException	Input string for any of the 5 sections in the change token is not in a correct format. This could happen if the first, second, fourth, or fifth section doesn't have a string representation for number, or the third section doesn't have a string representation for a <b>CSOM GUID</b> that contains 32 digits with 4 dashes {xxxxxxxx-xxxx-xxxx-xxxx-xxxxxxxxxxxxxx}.
-1	System.InvalidOperationException	The number of semicolon separated tokens is not 5, or the version number for the first token value is not 1.
-1	System.OverflowException	Input string for the first or second section is either too large or too small for a CSOM Int32. Input string for the fourth or fifth section is either too large or too small for a <b>CSOM Int64</b> .

### 3.2.5.19.1.2 ObjectPath Properties

None.

### 3.2.5.20 Microsoft.SharePoint.Client.ChangeType

**ShortName:** SP.ChangeType

**Flag:** false

Enumeration of the possible types of changes.

#### 3.2.5.20.1 Field Values

##### 3.2.5.20.1.1 NoChange

**Value:** 0

Indicates that no change has taken place.

##### 3.2.5.20.1.2 Add

**Value:** 1

Specifies that an **object (1)** has been added within the scope of a **list**, **site (2)**, **site collection**, or **content database**.

##### 3.2.5.20.1.3 Update

**Value:** 2

Specifies that an **object (1)** has been modified within the scope of a **list, site (2), site collection,** or **content database.**

#### **3.2.5.20.1.4 DeleteObject**

**Value:** 3

Specifies that an **object (1)** has been deleted within the scope of a **list, site (2), site collection,** or **content database.**

#### **3.2.5.20.1.5 Rename**

**Value:** 4

The leaf in a **URL** has been renamed.

#### **3.2.5.20.1.6 MoveAway**

**Value:** 5

Specifies that a non-leaf segment within a **URL** has been renamed. The **object (1)** was moved away from the location within the **site (2)** specified by the change.

#### **3.2.5.20.1.7 MoveInto**

**Value:** 6

Specifies that a non-leaf segment within a **URL** has been renamed. The **object (1)** was moved into the location within the **site (2)** specified by the change.

#### **3.2.5.20.1.8 Restore**

**Value:** 7

Specifies that an **object (1)** has restored from a backup or from the **Recycle Bin.**

#### **3.2.5.20.1.9 RoleAdd**

**Value:** 8

Specifies that a **role definition** has been added.

#### **3.2.5.20.1.10 RoleDelete**

**Value:** 9

Specifies that a **role definition** has been deleted.

#### **3.2.5.20.1.11 RoleUpdate**

**Value:** 10

Specifies that a **role definition** has been updated.

#### **3.2.5.20.1.12 AssignmentAdd**

**Value:** 11



Specifies that a user has been given permissions to a **list**. The list MUST have different permissions from its parent.

#### **3.2.5.20.1.13AssignmentDelete**

**Value:** 12

Specifies that a user has lost permissions to a **list**. The list MUST have different permissions from its parent.

#### **3.2.5.20.1.14MemberAdd**

**Value:** 13

Specifies that a user has been added to a **group**.

#### **3.2.5.20.1.15MemberDelete**

**Value:** 14

Specifies that a user has been removed from a **group**.

#### **3.2.5.20.1.16SystemUpdate**

**Value:** 15

Specifies that a change has been made to an **item** by using the protocol server method.

#### **3.2.5.20.1.17Navigation**

**Value:** 16

Specifies that a change in the navigation structure of a **site collection** has been made.

#### **3.2.5.20.1.18ScopeAdd**

**Value:** 17

Specifies that a change in **permissions** scope has been made to break inheritance from the parent of an **object (1)**.

#### **3.2.5.20.1.19ScopeDelete**

**Value:** 18

Specifies that a change in permissions scope has been made to revert back to inheriting **permissions** from the parent of an **object (1)**.

#### **3.2.5.20.1.20ListContentTypeAdd**

**Value:** 19

Specifies that a **list content type** has been added.

#### **3.2.5.20.1.21ListContentTypeDelete**

**Value:** 20

Specifies that a **list content type** has been deleted.

### 3.2.5.20.1.22 Dirty

**Value:** 21

Specifies that this item has a pending modification due to an operation on another item.

### 3.2.5.20.1.23 Activity

**Value:** 22

Specifies that an activity change as specified in section [3.2.5.462](#) has been made to the **object (1)**.

## 3.2.5.21 Microsoft.SharePoint.Client.ChangeUser

**TypeId:** {9BCB7ADB-5A47-426E-886F-3CE841554CD9}

**ShortName:** SP.ChangeUser

Specifies a change on a user.

The RelativeTime property is not included in the **default scalar property set** for this type.

### 3.2.5.21.1 Properties

#### 3.2.5.21.1.1 Scalar Properties

##### 3.2.5.21.1.1.1 Activate

**Type:** CSOM Boolean

**Accessibility:** Read Only

Specifies whether a user has changed from an inactive state to an active state.

When a user is added to a **site (2)** and only has browse **permissions**, the user is in an inactive state. However, once the user can author **list items**, add **documents**, be assigned **tasks**, or make any contribution to the site (2), the user is in an active state.

##### 3.2.5.21.1.1.2 ChangeToken

**Type:** Microsoft.SharePoint.Client.ChangeToken

**Accessibility:** Read Only

See **Microsoft.SharePoint.Client.Change.ChangeToken**, as specified in section [3.2.5.7.1.1.1](#).

##### 3.2.5.21.1.1.3 ChangeType

**Type:** Microsoft.SharePoint.Client.ChangeType

**Accessibility:** Read Only

See **Microsoft.SharePoint.Client.Change.ChangeType**, as specified in section [3.2.5.7.1.1.2](#).

##### 3.2.5.21.1.1.4 RelativeTime

**Type:** CSOM String

**Accessibility:** Read Only

See `Microsoft.SharePoint.Client.Change.RelativeTime`, as specified in section [3.2.5.7.1.1.3](#).

#### **3.2.5.21.1.1.5 SiteId**

**Type:** CSOM GUID

**Accessibility:** Read Only

See `Microsoft.SharePoint.Client.Change.SiteId`, as specified in section [3.2.5.7.1.1.4](#).

#### **3.2.5.21.1.1.6 Time**

**Type:** CSOM DateTime

**Accessibility:** Read Only

See `Microsoft.SharePoint.Client.Change.Time`, as specified in section [3.2.5.7.1.1.5](#).

#### **3.2.5.21.1.1.7 UserId**

**Type:** CSOM Int32

**Accessibility:** Read Only

Uniquely identifies the changed user.

### **3.2.5.21.1.2 ObjectPath Properties**

None.

### **3.2.5.21.2 Methods**

#### **3.2.5.21.2.1 Scalar Methods**

None.

#### **3.2.5.21.2.2 ObjectPath Methods**

None.

### **3.2.5.22 Microsoft.SharePoint.Client.ChangeView**

**TypeId:** {865F3490-F526-4452-88E2-6E33357BAE50}

**ShortName:** SP.ChangeView

Specifies a change on a **view**.

The `RelativeTime` property is not included in the **default scalar property set** for this type.

#### **3.2.5.22.1 Properties**

##### **3.2.5.22.1.1 Scalar Properties**

###### **3.2.5.22.1.1.1 ChangeToken**

**Type:** `Microsoft.SharePoint.Client.ChangeToken`

**Accessibility:** Read Only

See **Microsoft.SharePoint.Client.Change.ChangeToken**, as specified in section [3.2.5.7.1.1.1](#).

### 3.2.5.22.1.1.2 ChangeType

**Type:** Microsoft.SharePoint.Client.ChangeType

**Accessibility:** Read Only

See **Microsoft.SharePoint.Client.Change.ChangeType**, as specified in section [3.2.5.7.1.1.2](#).

### 3.2.5.22.1.1.3 ListId

**Type:** CSOM GUID

**Accessibility:** Read Only

Identifies the **list** that contains the changed **view**.

**Exceptions:**

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	The <b>list identifier</b> in the change <b>fields (2)</b> item of the change collection is NULL.

### 3.2.5.22.1.1.4 RelativeTime

**Type:** CSOM String

**Accessibility:** Read Only

See Microsoft.SharePoint.Client.Change.RelativeTime, as specified in section [3.2.5.7.1.1.3](#).

### 3.2.5.22.1.1.5 SiteId

**Type:** CSOM GUID

**Accessibility:** Read Only

See **Microsoft.SharePoint.Client.Change.SiteId**, as specified in section [3.2.5.7.1.1.4](#).

### 3.2.5.22.1.1.6 Time

**Type:** CSOM DateTime

**Accessibility:** Read Only

See **Microsoft.SharePoint.Client.Change.Time**, as specified in section [3.2.5.7.1.1.5](#).

### 3.2.5.22.1.1.7 ViewId

**Type:** CSOM GUID

**Accessibility:** Read Only

Identifies the changed **view**.

### 3.2.5.22.1.1.8 WebId

**Type:** CSOM GUID

**Accessibility:** Read Only

Identifies the **site (2)** that contains the changed **view**.

#### Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	The <b>site identifier</b> in the change <b>fields (2)</b> item of the change collection is NULL.

### 3.2.5.22.1.2 ObjectPath Properties

None.

### 3.2.5.22.2 Methods

#### 3.2.5.22.2.1 Scalar Methods

None.

#### 3.2.5.22.2.2 ObjectPath Methods

None.

### 3.2.5.23 Microsoft.SharePoint.Client.ChangeWeb

**TypeId:** {E7FA8647-BDE1-474C-93B1-1EF9CE5CF02C}

**ShortName:** SP.ChangeWeb

Specifies a change on a **site (2)**.

The RelativeTime property is not included in the **default scalar property set** for this type.

#### 3.2.5.23.1 Properties

##### 3.2.5.23.1.1 Scalar Properties

###### 3.2.5.23.1.1.1 ChangeToken

**Type:** Microsoft.SharePoint.Client.ChangeToken

**Accessibility:** Read Only

See **Microsoft.SharePoint.Client.Change.ChangeToken**, as specified in section [3.2.5.7.1.1.1](#).

###### 3.2.5.23.1.1.2 ChangeType

**Type:** Microsoft.SharePoint.Client.ChangeType

**Accessibility:** Read Only

See **Microsoft.SharePoint.Client.Change.ChangeType**, as specified in section [3.2.5.7.1.1.2](#).

### 3.2.5.23.1.1.3 RelativeTime

**Type:** CSOM String

**Accessibility:** Read Only

See Microsoft.SharePoint.Client.Change.RelativeTime, as specified in section [3.2.5.7.1.1.3](#).

### 3.2.5.23.1.1.4 SiteId

**Type:** CSOM GUID

**Accessibility:** Read Only

See **Microsoft.SharePoint.Client.Change.SiteId**, as specified in section [3.2.5.7.1.1.4](#).

### 3.2.5.23.1.1.5 Time

**Type:** CSOM DateTime

**Accessibility:** Read Only

See **Microsoft.SharePoint.Client.Change.Time**, as specified in section [3.2.5.7.1.1.5](#).

### 3.2.5.23.1.1.6 WebId

**Type:** CSOM GUID

**Accessibility:** Read Only

Identifies the **site (2)** that has changed.

#### Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	The <b>site identifier</b> in the change <b>fields (2)</b> item of the change collection is NULL.

### 3.2.5.23.1.2 ObjectPath Properties

None.

### 3.2.5.23.2 Methods

#### 3.2.5.23.2.1 Scalar Methods

None.

#### 3.2.5.23.2.2 ObjectPath Methods

None.

### **3.2.5.24 Microsoft.SharePoint.Client.CheckinType**

**ShortName:** SP.CheckinType

**Flag:** false

Specifies the type of check in for a file.

#### **3.2.5.24.1 Field Values**

##### **3.2.5.24.1.1 MinorCheckIn**

**Value:** 0

Incremented as a minor version. Value=0.

##### **3.2.5.24.1.2 MajorCheckIn**

**Value:** 1

Incremented as a major version. Value=1.

##### **3.2.5.24.1.3 OverwriteCheckIn**

**Value:** 2

Overwrite the file. Value=2.

### **3.2.5.25 Microsoft.SharePoint.Client.CheckOutType**

**ShortName:** SP.CheckOutType

**Flag:** false

An enumeration describing the different checkout states for the file, independent of any lock state.

#### **3.2.5.25.1 Field Values**

##### **3.2.5.25.1.1 Online**

**Value:** 0

The file is checked out for editing on the server.

##### **3.2.5.25.1.2 Offline**

**Value:** 1

The file is checked out for editing on the local computer.

##### **3.2.5.25.1.3 None**

**Value:** 2

The file is not checked out.

### 3.2.5.26 Microsoft.SharePoint.Client.ChoiceFormatType

**ShortName:** SP.ChoiceFormatType

**Flag:** false

Specifies how options for how to display selections in a choice field.

#### 3.2.5.26.1 Field Values

##### 3.2.5.26.1.1 Dropdown

**Value:** 0

Drop-down list box.

##### 3.2.5.26.1.2 RadioButtons

**Value:** 1

Option buttons.

### 3.2.5.27 Microsoft.SharePoint.Client.ContentType

**TypeId:** {91B5BD2D-E133-486F-B727-197CE5EB2C0D}

**ShortName:** SP.ContentType

Specifies a **content type**.

The SchemaXmlWithResourceTokens property is not included in the **default scalar property set** for this type.

#### 3.2.5.27.1 Properties

##### 3.2.5.27.1.1 Scalar Properties

###### 3.2.5.27.1.1.1 Description

**Type:** **CSOM String**

**Accessibility:** Read/Write

Specifies the description of the **content type**.

It MUST NOT be NULL.

###### 3.2.5.27.1.1.2 DisplayFormTemplateName

**Type:** **CSOM String**

**Accessibility:** Read/Write

Specifies the name of a custom **display form** template to use for **list items** that have been assigned the **content type**.

###### 3.2.5.27.1.1.3 DisplayFormUrl

**Type:** **CSOM String**



**Accessibility:** Read/Write

Specifies the **URL** of a custom **display form** to use for **list items** that have been assigned the **content type**.

#### 3.2.5.27.1.1.4 DocumentTemplate

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies the file path to the **document template (1)** used for a new **list item** that has been assigned the **content type**.

It MUST NOT be NULL. It MUST be either an **absolute URL**, a **server-relative URL**, or a URL relative to the content type **resource folder** for the content type

#### Exceptions:

Error Code	Error Type Name	Condition
-2130575338	Microsoft.SharePoint.SPException	<b>List</b> is not found or has been deleted

#### 3.2.5.27.1.1.5 DocumentTemplateUrl

**Type:** CSOM String

**Accessibility:** Read Only

Specifies the **URL** of the **document template (1)** assigned to the **content type**.

#### 3.2.5.27.1.1.6 EditFormTemplateName

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies the name of a custom **edit form template** to use for **list items** that have been assigned the **content type**.

#### 3.2.5.27.1.1.7 EditFormUrl

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies the URL of a custom **edit form** to use for **list items** that have been assigned the **content type**.

#### 3.2.5.27.1.1.8 Group

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies the **content type group** for the **content type**.

It MUST NOT be empty. Its length MUST be equal to or less than 128.

### 3.2.5.27.1.1.9 Hidden

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Specifies whether the **content type** is unavailable for creation or usage directly from a user interface.

### 3.2.5.27.1.1.10 Id

**Type:** Microsoft.SharePoint.Client.ContentTypeId

**Accessibility:** Read Only

Specifies an identifier for the **content type** as specified in [\[MS-WSSTS\]](#) section 2.1.2.8.1.

### 3.2.5.27.1.1.11 Name

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies the name of the **content type**.

It MUST NOT be NULL.

### 3.2.5.27.1.1.12 NewFormTemplateName

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies the name of a custom **new form** template to use for **list items** that have been assigned the **content type**.

### 3.2.5.27.1.1.13 NewFormUrl

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies the **URL** of a custom **new form** to use for **list items** that have been assigned the **content type**.

### 3.2.5.27.1.1.14 ReadOnly

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Specifies whether changes to the **content type** properties are denied.

### 3.2.5.27.1.1.15 SchemaXml

**Type:** CSOM String

**Accessibility:** Read Only

Specifies the **XML schema** that represents the **content type**.

### **3.2.5.27.1.1.16 Scope**

**Type:** CSOM String

**Accessibility:** Read Only

Specifies a server-relative path to the **content type** scope of the content type.

### **3.2.5.27.1.1.17 JSLink**

**Type:** CSOM String

**Accessibility:** Read/Write

Gets or sets the JSLink for the content type custom form template. <4>

### **3.2.5.27.1.1.18 Sealed**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

**Sealed**<5> specifies whether the content type is sealed. Only a **site collection administrator** can set this value.

### **3.2.5.27.1.1.19 StringId**

**Type:** CSOM String

**Accessibility:** Read Only

A string representation of the value of the **Id** (section [3.2.5.27.1.1.10](#)). <6>

### **3.2.5.27.1.1.20 SchemaXmlWithResourceTokens**

**Type:** CSOM String

**Accessibility:** Read/Write

Gets the unlocalized schema XML for the **content type**.

### **3.2.5.27.1.1.21 MobileDisplayFormUrl**

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies the URL of a custom mobile Display form page to use for items assigned this content type.

### **3.2.5.27.1.1.22 MobileEditFormUrl**

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies the URL of a custom mobile edit form page to use for items assigned this content type.

### **3.2.5.27.1.1.23 MobileNewFormUrl**

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies the URL of a custom mobile new form page to use for items assigned this content type.

### **3.2.5.27.1.2 ObjectPath Properties**

#### **3.2.5.27.1.2.1 DescriptionResource**

**Type:** Microsoft.SharePoint.Client.UserResource

**Accessibility:** Read Only

Gets the SP.UserResource object (section [3.2.5.333](#)) for the description of this content type.

#### **3.2.5.27.1.2.2 FieldLinks**

**Type:** Microsoft.SharePoint.Client.FieldLinkCollection

**Accessibility:** Read Only

Specifies the collection of **field links** for the **content type**.

#### **3.2.5.27.1.2.3 Fields**

**Type:** Microsoft.SharePoint.Client.FieldCollection

**Accessibility:** Read Only

Specifies the collection of **fields (2)** for the **content type**.

#### **3.2.5.27.1.2.4 NameResource**

**Type:** Microsoft.SharePoint.Client.UserResource

**Accessibility:** Read Only

Specifies the SP.UserResource object for the name of this content type.

#### **3.2.5.27.1.2.5 Parent**

**Type:** Microsoft.SharePoint.Client.ContentType

**Accessibility:** Read Only

Specifies the parent **content type** of the content type.

#### **3.2.5.27.1.2.6 WorkflowAssociations**

**Type:** Microsoft.SharePoint.Client.Workflow.WorkflowAssociationCollection

**Accessibility:** Read Only

Specifies the collection of **workflow associations** for the **content type**.

### **3.2.5.27.2 Methods**

#### **3.2.5.27.2.1 Scalar Methods**

##### **3.2.5.27.2.1.1 DeleteObject**

**Return Type:** None

Deletes the **content type**.

**Parameters:** None

### 3.2.5.27.2.1.2 Update

**Return Type:** None

Updates the **content type**, and any **child objects (1)** of the content type if specified, with any changes made to the content type.

**Parameters:**

*updateChildren*: Specifies whether changes propagate to child objects (1) of the content type.

Type: **CSOM Boolean**

### 3.2.5.27.2.2 ObjectPath Methods

None.

## 3.2.5.28 Microsoft.SharePoint.Client.ContentTypeCollection

**TypeId:** {653E9412-6245-4A3F-829B-CFDBF7FD86A5}

**ShortName:** SP.ContentTypeCollection

Represents a collection of **content types**.

### 3.2.5.28.1 Properties

#### 3.2.5.28.1.1 Scalar Properties

None.

#### 3.2.5.28.1.2 ObjectPath Properties

None.

### 3.2.5.28.2 Methods

#### 3.2.5.28.2.1 Scalar Methods

None.

#### 3.2.5.28.2.2 ObjectPath Methods

##### 3.2.5.28.2.2.1 Add

**Return Type:** Microsoft.SharePoint.Client.ContentType

Adds a new **content type** to the collection and returns a **reference** to the added SP.ContentType.

**Parameters:**

*parameters*: Specifies properties that is to be used to construct the new content type.

Type: Microsoft.SharePoint.Client.ContentTypeCreationInformation

It MUST NOT be NULL. The content type scope of its *ParentContentType* property, as specified in section [3.2.5.29.1.2.1](#) MUST NOT be an ancestor of the parent (the SP.List or SP.Web that this collection is attached to) of the content type collection.

**Exceptions:**

Error Code	Error Type Name	Condition
183	Microsoft.SharePoint.SPException	A content type with a name specified by the <b>Name</b> property of <i>parameters</i> exists in the collection.

### 3.2.5.28.2.2.2 AddExistingContentType

**Return Type:** Microsoft.SharePoint.Client.ContentType

Adds an existing **content type** to the collection. The name of the given content type MUST NOT be the same as any of the content types in the collection. A **reference** to the SP.ContentType that was added is returned.

**Parameters:**

*contentType*: Specifies the content type to be added to the collection.

Type: Microsoft.SharePoint.Client.ContentType

It MUST NOT be NULL.

**Exceptions:**

Error Code	Error Type Name	Condition
183	Microsoft.SharePoint.SPException	A content type with same name as the given content type exists in the collection.

### 3.2.5.28.2.2.3 GetById

**Return Type:** Microsoft.SharePoint.Client.ContentType

Returns the **content type** with the given identifier from the collection. If a content type with the given identifier is not found in the collection, the server MUST return null.

**Parameters:**

*contentTypeId*: A hexadecimal value representing the identifier of a content type.

Type: **CSOM String**

It MUST NOT be NULL.

It MUST conform to the following ABNF as defined in [\[RFC5234\]](#):

```
nonzero-digit = "1" / "2" / "3" / "4" / "5" / "6" / "7" / "8" / "9"
```

```

digit = "0" / nonzero-digit
nonzero-hexdigit = nonzero-digit / "A" / "B" / "C" / "D" / "E" / "F"
hexdigit = "0" / nonzero-hexdigit
id = *(nonzero-hexdigit hexdigit / "0" nonzero-hexdigit)
parentids = *(16(hexdigit hexdigit))
contentTypeId = id [ "00" parentids]

```

### 3.2.5.28.2.2.4 AddAvailableContentType

**Return Type:** Microsoft.SharePoint.Client.ContentType

Adds the specified **content type** to the content type collection.

**Parameters:**

*contentTypeId*: Specifies the identifier of the content type to be added to the content type collection. It MUST exist in the web's available content types.

Type: **CSOM String**

It MUST NOT be NULL.

**Exceptions:**

Error Code	Error Type Name	Condition
183	Microsoft.SharePoint.SPException	A ContentType with the same name exists.

### 3.2.5.29 Microsoft.SharePoint.Client.ContentTypeCreationInformation

**TypeId:** {168F3091-4554-4F14-8866-B20D48E45B54}

**ShortName:** SP.ContentTypeCreationInformation

Specifies properties that are used as parameters to initialize a new **content type**.

#### 3.2.5.29.1 Properties

##### 3.2.5.29.1.1 Scalar Properties

###### 3.2.5.29.1.1.1 Description

Type: **CSOM String**

**Accessibility:** Read/Write

Specifies the description of the **content type** to be constructed.

###### 3.2.5.29.1.1.2 Group

Type: **CSOM String**

**Accessibility:** Read/Write

Specifies the **content type group** of the **content type** to be constructed.

Its length MUST be equal to or greater than 1. Its length MUST be equal to or less than 128.

### 3.2.5.29.1.1.3 Id

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies the **ContentTypeId** (section [3.2.5.30](#)) of the **content type** to be constructed.

This property MUST NOT be set at the same time as the **ParentContentType** (section [3.2.5.29.1.2.1](#)) property.

### 3.2.5.29.1.1.4 Name

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies the name of the **content type** to be constructed.

It MUST NOT be NULL.

## 3.2.5.29.1.2 ObjectPath Properties

### 3.2.5.29.1.2.1 ParentContentType

**Type:** Microsoft.SharePoint.Client.ContentType

**Accessibility:** Read/Write

Specifies the parent **content type** for the content type to be constructed.

The **list** the parent content type belongs to MUST be null.

## 3.2.5.30 Microsoft.SharePoint.Client.ContentTypeId

**TypeId:** {DA0F1E90-296F-480E-BC27-CEFE51EFF241}

**ShortName:** SP.ContentTypeId

Represents the **content type identifier** (ID) of a **content type**.

### 3.2.5.30.1 Properties

#### 3.2.5.30.1.1 Scalar Properties

##### 3.2.5.30.1.1.1 StringValue

**Type:** CSOM String

**Accessibility:** Read Only

Hexadecimal string value of **content type identifier**. String value MUST start with "0x".

It MUST NOT be NULL.

#### 3.2.5.30.1.2 ObjectPath Properties

None.



### **3.2.5.31 Microsoft.SharePoint.Client.CustomizedPageStatus**

**ShortName:** SP.CustomizedPageStatus

**Flag:** true

Specifies the customization (ghost) status of the SPFile.

#### **3.2.5.31.1 Field Values**

##### **3.2.5.31.1.1 None**

**Value:** 0

The page was never cached. Value is 0.

##### **3.2.5.31.1.2 Uncustomized**

**Value:** 1

The page is cached and has not been customized. Value is 1.

##### **3.2.5.31.1.3 Customized**

**Value:** 2

The page was cached but has been customized. Value is 2.

### **3.2.5.32 Microsoft.SharePoint.Client.DateTimeFieldFormatType**

**ShortName:** SP.DateTimeFieldFormatType

**Flag:** false

Specifies the format to use in displaying date and time fields.

#### **3.2.5.32.1 Field Values**

##### **3.2.5.32.1.1 DateOnly**

**Value:** 0

Only the date is displayed.

##### **3.2.5.32.1.2 DateTime**

**Value:** 1

Both the date and the time are displayed.

### **3.2.5.33 Microsoft.SharePoint.Client.DraftVisibilityType**

**ShortName:** SP.DraftVisibilityType

**Flag:** false

Specifies the kind of user who can view the minor version of a document draft.

### 3.2.5.33.1 Field Values

#### 3.2.5.33.1.1 Reader

**Value:** 0

Reader. Value = 0.

#### 3.2.5.33.1.2 Author

**Value:** 1

Author. Value = 1.

#### 3.2.5.33.1.3 Approver

**Value:** 2

Approver. Value = 2.

### 3.2.5.34 Microsoft.SharePoint.Client.Feature

**TypeId:** {4E46B28C-E27F-4964-A8D4-FC25658D86D1}

**ShortName:** SP.Feature

The top level object representing a SharePoint Feature activation.

The presence of a Feature object in a collection at the server farm, Web application, site collection, or Web site levels indicates that the feature is activated. Lack of a Feature object indicates that the object has not been activated.

Use the Features properties of the Site (section [3.2.5.119](#)) and Web (section [3.2.5.143](#)) classes to get the collection of features that are activated in the server farm, Web application, site collection, or Web site. Use the Site (section [3.2.5.110.1.2.3](#)) and Web (section [3.2.5.110.1.2.4](#)) properties of the RequestContext (section [3.2.5.110](#)) class to get the collection of features for the current site collection or site.

The DisplayName property is not included in the **default scalar property set** for this type.

#### 3.2.5.34.1 Properties

##### 3.2.5.34.1.1 Scalar Properties

###### 3.2.5.34.1.1.1 DefinitionId

**Type:** CSOM GUID

**Accessibility:** Read Only

Gets the GUID that identifies this feature.

It MUST NOT be NULL.

###### 3.2.5.34.1.1.2 DisplayName

**Type:** CSOM String

**Accessibility:** Read Only

Gets the display name of this feature.

### 3.2.5.34.1.2 ObjectPath Properties

None.

### 3.2.5.34.2 Methods

#### 3.2.5.34.2.1 Scalar Methods

None.

#### 3.2.5.34.2.2 ObjectPath Methods

None.

### 3.2.5.35 Microsoft.SharePoint.Client.FeatureCollection

**TypeId:** {8B9C0015-193D-4062-8E98-8D23C303EEDD}

**ShortName:** SP.FeatureCollection

Represents a collection of activated **features**.

#### 3.2.5.35.1 Properties

##### 3.2.5.35.1.1 Scalar Properties

None.

##### 3.2.5.35.1.2 ObjectPath Properties

None.

#### 3.2.5.35.2 Methods

##### 3.2.5.35.2.1 Scalar Methods

###### 3.2.5.35.2.1.1 Remove

**Return Type:** None

Removes the **feature** from the collection of features.

**Parameters:**

*featureId*: The **feature identifier** of the feature to be removed.

Type: **CSOM GUID**

It MUST NOT be NULL.

*force*: Specifies whether to force the operation to continue even if there are errors.

Type: **CSOM Boolean**

This parameter is ignored if there are no errors.

### Exceptions:

Error Code	Error Type Name	Condition
-1	System.InvalidOperationException	The given feature is not an activated feature or the given feature cannot be deactivated and the force parameter was not set to "true".

## 3.2.5.35.2.2 ObjectPath Methods

### 3.2.5.35.2.2.1 Add

**Return Type:** Microsoft.SharePoint.Client.Feature

Adds the **feature** to the collection of activated features and returns the added feature.

#### Parameters:

*featureId*: The **feature identifier** of the feature to be added.

Type: **CSOM GUID**

It MUST NOT be NULL.

*force*: Specifies whether to continue with the operation even if there are errors.

Type: **CSOM Boolean**

*featdefScope*: The **feature scope** for this feature.

Type: Microsoft.SharePoint.Client.FeatureDefinitionScope

It MUST have the value of FeatureDefinitionScope.Site or FeatureDefinitionScope.Farm [<7>](#).

### Exceptions:

Error Code	Error Type Name	Condition
-1	System.InvalidOperationException	The given feature is not installed at the feature scope.

### 3.2.5.35.2.2.2 GetById

**Return Type:** Microsoft.SharePoint.Client.Feature

Returns the **feature** for the given **feature identifier**. Returns NULL if no feature is available for the given feature identifier.

#### Parameters:

*featureId*: The feature identifier of the feature to be returned.

Type: **CSOM GUID**

### 3.2.5.36 Microsoft.SharePoint.Client.FeatureDefinitionScope

**ShortName:** SP.FeatureDefinitionScope

**Flag:** false

Scope of the SPFeatureDefinition

#### 3.2.5.36.1 Field Values

##### 3.2.5.36.1.1 None

**Value:** 0

Specifies no scope.

##### 3.2.5.36.1.2 Farm

**Value:** 1

Specifies farm scope.

##### 3.2.5.36.1.3 Site

**Value:** 2

Specifies site collection scope.

##### 3.2.5.36.1.4 Web

**Value:** 3

Specifies web scope.

### 3.2.5.37 Microsoft.SharePoint.Client.Field

**TypeId:** {C4121B04-0F57-4B1D-A145-D25426B16480}

**ShortName:** SP.Field

Represent a **field (2)** that is specified in [\[MS-WSSTS\]](#) section 2.1.2.9.

The NoCrawl and SchemaXmlWithResourceTokens properties are not included in the **default scalar property set** for this type.

#### 3.2.5.37.1 Properties

##### 3.2.5.37.1.1 Scalar Properties

###### 3.2.5.37.1.1.1 CanBeDeleted

**Type:** CSOM Boolean

**Accessibility:** Read Only

Specifies whether the **field (2)** can be deleted.

###### 3.2.5.37.1.1.2 DefaultValue

Type: **CSOM String**

Accessibility: Read/Write

Specifies the default value for the **field (2)**.

Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed, and the <b>list</b> is an <b>external list</b> .

### 3.2.5.37.1.1.3 Description

Type: **CSOM String**

Accessibility: Read/Write

Specifies the description of the **field (2)**.

### 3.2.5.37.1.1.4 Direction

Type: **CSOM String**

Accessibility: Read/Write

Specifies the **reading order** of the **field (2)**. Its value is implementation-specific to the client used to browse instances of this field (2).

If the value is set to "none", **Microsoft.SharePoint.Client.List.Direction** specifies the reading order of the field (2) that is specified in section [3.2.5.79.1.1.14](#).

Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed to a value other than "none," and the <b>list</b> is an <b>external list</b> .

### 3.2.5.37.1.1.5 EnforceUniqueValues

Type: **CSOM Boolean**

Accessibility: Read/Write

Specifies whether the **field (2)** enforces unique values.

The value MUST NOT be set to "true" for the following built-in fields (2)

Field Identifier	Field Name
{1df5e554-ec7e-46a6-901d-d85a3881cb18}	Author

Field Identifier	Field Name
{d31655d1-1d5b-4511-95a1-7a09e9b75bf2}	Editor
{28cf69c5-fa48-462a-b5cd-27b6f9d2bd5f}	Modified
{7841bf41-43d0-4434-9f50-a673baef7631}	_UIVersion
{8c06beca-0777-48f7-91c7-6da68bc07b69}	Created
{26d0756c-986a-48a7-af35-bf18ab85ff4a}	_HasCopyDestinations
{3881510a-4e4a-4ee8-b102-8ee8e2d0dd4b}	CheckoutUser
{c042a256-787d-4a6f-8a8a-cf6ab767f12d}	ContentType

#### Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Adding <b>unique column constraints</b> to the field (2) where the <b>list</b> is an <b>external list</b> .

#### 3.2.5.37.1.1.6 FieldTypeKind

**Type:** Microsoft.SharePoint.Client.FieldType

**Accessibility:** Read/Write

Specifies the type of the **field (2)**.

#### Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed, and the <b>list</b> is an <b>external list</b> .

#### 3.2.5.37.1.1.7 Filterable

**Type:** CSOM Boolean

**Accessibility:** Read Only

Specifies whether **list items** in the **list** can be filtered by the **field (2)** value.

#### 3.2.5.37.1.1.8 FromBaseType

**Type:** CSOM Boolean

**Accessibility:** Read Only

Gets a **Boolean** value that indicates whether the **field (2)** derives from a **base field type**.

### 3.2.5.37.1.1.9 Group

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies the **field group**.

It MUST NOT be NULL. It MUST NOT be empty. Its length MUST be equal to or less than 128.

#### Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed, and the <b>list</b> is an <b>external list</b> .

### 3.2.5.37.1.1.10 Hidden

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Specifies whether the **field (2)** is **hidden** in **list views** and **list forms**.

### 3.2.5.37.1.1.11 Id

**Type:** CSOM GUID

**Accessibility:** Read Only

Specifies the **field identifier**.

### 3.2.5.37.1.1.12 InternalName

**Type:** CSOM String

**Accessibility:** Read Only

Specifies the **field internal name**.

It MUST NOT be NULL. It MUST NOT be empty.

### 3.2.5.37.1.1.13 ReadOnlyField

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Specifies whether the value of the **field (2)** is read-only.

#### Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed, and the <b>list</b> is an <b>external list</b> .



### 3.2.5.37.1.1.14 Required

Type: **CSOM Boolean**

Accessibility: Read/Write

Specifies whether the **field (2)** requires a value. If the field (2) requires a value, this value MUST be set to "true". Otherwise, it MUST be set to "false".

#### Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is set to "true", and the <b>list</b> is an <b>external list</b> .

### 3.2.5.37.1.1.15 SchemaXml

Type: **CSOM String**

Accessibility: Read/Write

Specifies the **XML schema** that defines the **field (2)**.

It MUST be NULL, empty, or an **XML fragment** that conforms to the **FieldDefinition** type as defined in [\[MS-WSSFO2\]](#) section 2.2.8.3.3 or [\[MS-WSSFO3\]](#) section 2.2.7.3.3.

#### Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed to a non-NULL or non-empty value, and the <b>list</b> is an <b>external list</b> .

### 3.2.5.37.1.1.16 Scope

Type: **CSOM String**

Accessibility: Read Only

Specifies the **server-relative URL** of the **list** or the **site (2)** that the **field (2)** belongs to.

### 3.2.5.37.1.1.17 Sealed

Type: **CSOM Boolean**

Accessibility: Read/Write

Specifies whether properties on the **field (2)** cannot be changed and whether the field (2) cannot be deleted.

### 3.2.5.37.1.1.18 Sortable

Type: **CSOM Boolean**

Accessibility: Read Only

Specifies whether **list items** in the **list** can be sorted by the **field (2)** value.

### 3.2.5.37.1.1.19 StaticName

Type: **CSOM String**

Accessibility: Read/Write

Specifies a customizable identifier of the **field (2)**. If the value is NULL or empty, the protocol server MUST use the value of *InternalName*.

#### Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed, and the <b>list</b> is an <b>external list</b> .

### 3.2.5.37.1.1.20 Title

Type: **CSOM String**

Accessibility: Read/Write

Specifies the **display name** of the **field (2)**.

### 3.2.5.37.1.1.21 TypeAsString

Type: **CSOM String**

Accessibility: Read/Write

Specifies the type of the **field (2)**.

It MUST NOT be NULL. It MUST NOT be empty.

#### Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed, and the <b>list</b> is an <b>external list</b> .

### 3.2.5.37.1.1.22 TypeDisplayName

Type: **CSOM String**

Accessibility: Read Only

Specifies the **display name** for the type of the **field (2)**.

It MUST NOT be NULL. It MUST NOT be empty.

### 3.2.5.37.1.1.23 TypeShortDescription

**Type:** CSOM String

**Accessibility:** Read Only

Specifies the description for the type of the **field (2)**.

It MUST NOT be NULL. It MUST NOT be empty.

#### **3.2.5.37.1.1.24 ValidationFormula**

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies the **data validation criteria** for the value of the **field (2)**.

#### **3.2.5.37.1.1.25 ValidationMessage**

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies the error message returned when **data validation** fails for the **field (2)**.

Its length MUST be equal to or less than 1024.

#### **3.2.5.37.1.1.26 JSLink**

**Type:** CSOM String

**Accessibility:** Read/Write

Gets the name of an external ECMAScript ([\[ECMA-262-1999\]](#)) file containing any client rendering logic for **fields (2)** of this type.

#### **3.2.5.37.1.1.27 EntityPropertyName**

**Type:** CSOM String

**Accessibility:** Read Only

Gets the name of the entity property of this **field (2)** in the **list item** entity that uses this field (2).

It MUST NOT be NULL. It MUST NOT be empty.

#### **3.2.5.37.1.1.28 Indexed**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Gets or sets a Boolean value that specifies whether the field is indexed.

#### **3.2.5.37.1.1.29 SchemaXmlWithResourceTokens**

**Type:** CSOM String

**Accessibility:** Read Only

Gets the unlocalized schema XML for this **field (2)**.

### **3.2.5.37.1.1.30      AutoIndexed**

**Type:** CSOM Boolean

**Accessibility:** Read Only

Gets a Boolean value that specifies whether the field is auto-indexed.

True to specify that the field is auto-indexed; otherwise, false.

### **3.2.5.37.1.1.31      ClientSideComponentId**

**Type:** CSOM GUID

**Accessibility:** Read/Write

The unique identifier of the client-side component defined with SharePoint Framework.

### **3.2.5.37.1.1.32      ClientSideComponentProperties**

**Type:** CSOM String

**Accessibility:** Read/Write

This property is only used when a **ClientSideComponentId** is specified. It is optional. If non-empty, the string **MUST** contain a JSON object with custom initialization properties whose format and meaning are defined by the client-side component.

### **3.2.5.37.1.1.33      CustomFormatter**

**Type:** CSOM String

**Accessibility:** Read/Write

A JSON string representing the custom rendering format of the field.

### **3.2.5.37.1.1.34      DefaultFormula**

**Type:** CSOM String

**Accessibility:** Read/Write

Gets or sets the default formula for a calculated field.

### **3.2.5.37.1.1.35      NoCrawl**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Gets or sets a Boolean value that specifies whether the field can be crawled by a search engine.

### **3.2.5.37.1.1.36      PinnedToFiltersPane**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Boolean value that indicates whether the field pins to filter pane.

### 3.2.5.37.1.1.37 ShowInFiltersPane

**Type:** Microsoft.SharePoint.Client.ShowInFiltersPaneStatus

**Accessibility:** Read/Write

Indicates whether the field will be shown.

### 3.2.5.37.1.2 ObjectPath Properties

#### 3.2.5.37.1.2.1 DescriptionResource

**Type:** Microsoft.SharePoint.Client.UserResource

**Accessibility:** Read Only

Gets the resource object corresponding to the **Description** property for a field.

#### 3.2.5.37.1.2.2 TitleResource

**Type:** Microsoft.SharePoint.Client.UserResource

**Accessibility:** Read Only

Gets the resource object corresponding to the **Title** property for a field.

### 3.2.5.37.2 Methods

#### 3.2.5.37.2.1 Scalar Methods

##### 3.2.5.37.2.1.1 DeleteObject

**Return Type:** None

Deletes the **field (2)** from the **list**, from the **site (2)**, or from the **content types** within the list.

**Parameters:** None

**Exceptions:**

Error Code	Error Type Name	Condition
-1	System.InvalidOperationException	<b>CanBeDeleted</b> is "false".

##### 3.2.5.37.2.1.2 setShowInDisplayForm

**Return Type:** None

Sets this field to show or hide in the display form.

**Parameters:**

*value*: A Boolean value that indicates whether this field is shown in the display form.

Type: **CSOM Boolean**

##### 3.2.5.37.2.1.3 setShowInEditForm

**Return Type:** None

Sets this field to show or hide in the edit form.

**Parameters:**

*value*: A Boolean value that indicates whether this field is shown in the edit form.

Type: **CSOM Boolean**

### 3.2.5.37.2.1.4 SetShowInNewForm

**Return Type:** None

Sets this field to show or hide in the new form.

**Parameters:**

*value*: A Boolean value that indicates whether this field is shown in the new form.

Type: **CSOM Boolean**

### 3.2.5.37.2.1.5 Update

**Return Type:** None

Commits changed properties of the **field (2)**.

**Parameters:** None

**Exceptions:**

Error Code	Error Type Name	Condition
- 2130246331	Microsoft.SharePoint.SPException	Type of the field (2) is changed for an <b>indexed field</b> . The field type of indexed fields cannot be changed.
- 2130246238	Microsoft.SharePoint.SPException	Field (2) is set to not be an indexed field, and <b>EnforceUniqueValues</b> is "true".
- 2130246236	Microsoft.SharePoint.SPException	Type of the field (2) is being changed and <b>EnforceUniqueValues</b> of the field (2) is "true".

### 3.2.5.37.2.1.6 UpdateAndPushChanges

**Return Type:** None

Commits changed properties of the **field (2)** and propagates changes to all **lists** that use the field (2).

**Parameters:**

*pushChangesToLists*: Specifies whether to propagate changes to all lists that use the field (2).

Type: **CSOM Boolean**

**Exceptions:**

Error Code	Error Type Name	Condition
- 2130246331	Microsoft.SharePoint.SPException	Type of the field (2) is changed for an <b>indexed field</b> . The field type of indexed fields cannot be changed.
- 2130246238	Microsoft.SharePoint.SPException	Field (2) is set to not be an indexed field, and <b>EnforceUniqueValues</b> is "true".
- 2130246236	Microsoft.SharePoint.SPException	Type of the field (2) is being changed and <b>EnforceUniqueValues</b> of the field (2) is "true".

### 3.2.5.37.2.1.7 ValidateSetValue

**Return Type:** None

Validates and sets the value of the **field (2)** for the **list item** based on an implementation-specific transformation of the value. [<8>](#)

**Parameters:**

*item*: Specifies the list item to be updated with the new value.

Type: Microsoft.SharePoint.Client.ListItem

It MUST NOT be NULL.

*value*: Specifies the new value for the field (2).

Type: **CSOM String**

### 3.2.5.37.2.2 ObjectPath Methods

None.

### 3.2.5.38 Microsoft.SharePoint.Client.FieldCalculated

**TypeId:** {F9EE4627-2914-46CD-806A-4921F96A0C72}

**ShortName:** SP.FieldCalculated

Specifies a **calculated field** in a list. To set properties, call the **Update** method (section [3.2.5.38.2.1.5](#)).

The NoCrawl and SchemaXmlWithResourceTokens properties are not included in the **default scalar property set** for this type.

### 3.2.5.38.1 Properties

#### 3.2.5.38.1.1 Scalar Properties

##### 3.2.5.38.1.1.1 CanBeDeleted

**Type:** **CSOM Boolean**

**Accessibility:** Read Only

See **Microsoft.SharePoint.Client.Field.CanBeDeleted**, as specified in section [3.2.5.37.1.1.1](#).

### 3.2.5.38.1.1.2 DateFormat

**Type:** Microsoft.SharePoint.Client.DateTimeFieldFormatType

**Accessibility:** Read/Write

Specifies the date and time format that is used in the **field (2)**.

### 3.2.5.38.1.1.3 DefaultValue

**Type:** CSOM String

**Accessibility:** Read/Write

See **Microsoft.SharePoint.Client.Field.DefaultValue**, as specified in section [3.2.5.37.1.1.2](#).

#### Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	The <b>field (2)</b> value is being set, and the <b>list</b> is an <b>external list</b> .

### 3.2.5.38.1.1.4 Description

**Type:** CSOM String

**Accessibility:** Read/Write

See **Microsoft.SharePoint.Client.Field.Description**, as specified in section [3.2.5.37.1.1.3](#).

### 3.2.5.38.1.1.5 Direction

**Type:** CSOM String

**Accessibility:** Read/Write

See **Microsoft.SharePoint.Client.Field.Direction**, as specified in section [3.2.5.37.1.1.4](#).

#### Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed to a value other than "none," and the <b>list</b> is an <b>external list</b> .

### 3.2.5.38.1.1.6 EnforceUniqueValues

**Type:** CSOM Boolean

**Accessibility:** Read/Write

See **Microsoft.SharePoint.Client.Field.EnforceUniqueValues**, as specified in section [3.2.5.37.1.1.5](#)



### Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Adding <b>unique column constraints</b> to the <b>field (2)</b> where the <b>list</b> is an <b>external list</b> .

### 3.2.5.38.1.1.7 FieldTypeKind

**Type:** Microsoft.SharePoint.Client.FieldType

**Accessibility:** Read/Write

See **Microsoft.SharePoint.Client.Field.FieldTypeKind**, as specified in section [3.2.5.37.1.1.6](#).

### Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed, and the <b>list</b> is an <b>external list</b> .

### 3.2.5.38.1.1.8 Filterable

**Type:** **CSOM Boolean**

**Accessibility:** Read Only

See **Microsoft.SharePoint.Client.Field.Filterable**, as specified in section [3.2.5.37.1.1.7](#).

### 3.2.5.38.1.1.9 Formula

**Type:** **CSOM String**

**Accessibility:** Read/Write

Specifies the formula for the **field (2)**.

It MUST NOT be empty.

### 3.2.5.38.1.1.10 FromBaseType

**Type:** **CSOM Boolean**

**Accessibility:** Read Only

Gets a **Boolean** value that indicates whether the **field (2)** derives from a **base field type**.

### 3.2.5.38.1.1.11 Group

**Type:** **CSOM String**

**Accessibility:** Read/Write

See **Microsoft.SharePoint.Client.Field.Group**, as specified in section [3.2.5.37.1.1.9](#).

It MUST NOT be NULL. It MUST NOT be empty. Its length MUST be equal to or less than 128.

**Exceptions:**

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed, and the <b>list</b> is an <b>external list</b> .

**3.2.5.38.1.1.12 Hidden**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

See **Microsoft.SharePoint.Client.Field.Hidden**, as specified in section [3.2.5.37.1.1.10](#).

**3.2.5.38.1.1.13 Id**

**Type:** CSOM GUID

**Accessibility:** Read Only

See **Microsoft.SharePoint.Client.Field.Id**, as specified in section [3.2.5.37.1.1.11](#).

**3.2.5.38.1.1.14 InternalName**

**Type:** CSOM String

**Accessibility:** Read Only

See **Microsoft.SharePoint.Client.Field.InternalName**, as specified in section [3.2.5.37.1.1.12](#).

It MUST NOT be NULL. It MUST NOT be empty.

**3.2.5.38.1.1.15 OutputType**

**Type:** Microsoft.SharePoint.Client.FieldType

**Accessibility:** Read/Write

Specifies the output format for the **field (2)**.

It MUST be one of the following values: Text, Number, Integer, Currency, Boolean, or DateTime.

**3.2.5.38.1.1.16 ReadOnlyField**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

See **Microsoft.SharePoint.Client.Field.ReadOnlyField**, as specified in section [3.2.5.37.1.1.13](#).

**Exceptions:**

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed, and the <b>list</b> is an <b>external list</b> .

### 3.2.5.38.1.1.17 Required

Type: **CSOM Boolean**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.Required**, as specified in section [3.2.5.37.1.1.14](#).

#### Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is set to "true", and the <b>list</b> is an <b>external list</b> .

### 3.2.5.38.1.1.18 SchemaXml

Type: **CSOM String**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.SchemaXml**, as specified in section [3.2.5.37.1.1.15](#).

It MUST be NULL, empty, or an **XML fragment** that conforms to the **FieldDefinition** type as defined in [\[MS-WSSFO2\]](#) section 2.2.8.3.3 or [\[MS-WSSFO3\]](#) section 2.2.7.3.3.

#### Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed to a non-NULL or non-empty value, and the <b>list</b> is an <b>external list</b> .

### 3.2.5.38.1.1.19 Scope

Type: **CSOM String**

Accessibility: Read Only

See **Microsoft.SharePoint.Client.Field.Scope**, as specified in section [3.2.5.37.1.1.16](#).

### 3.2.5.38.1.1.20 Sealed

Type: **CSOM Boolean**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.Sealed**, as specified in section [3.2.5.37.1.1.17](#).

### 3.2.5.38.1.1.21 Sortable

Type: **CSOM Boolean**

Accessibility: Read Only

See **Microsoft.SharePoint.Client.Field.Sortable**, as specified in section [3.2.5.37.1.1.18](#).

### 3.2.5.38.1.1.22 StaticName

Type: **CSOM String**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.StaticName**, as specified in section [3.2.5.37.1.1.19](#).

#### Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed, and the <b>list</b> is an <b>external list</b> .

### 3.2.5.38.1.1.23 Title

Type: **CSOM String**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.Title**, as specified in section [3.2.5.37.1.1.20](#).

### 3.2.5.38.1.1.24 TypeAsString

Type: **CSOM String**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.TypeAsString**, as specified in section [3.2.5.37.1.1.21](#).

It MUST NOT be NULL. It MUST NOT be empty.

#### Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed, and the <b>list</b> is an <b>external list</b> .

### 3.2.5.38.1.1.25 TypeDisplayName

Type: **CSOM String**

Accessibility: Read Only

See **Microsoft.SharePoint.Client.Field.TypeDisplayName**, as specified in section [3.2.5.37.1.1.22](#).

It MUST NOT be NULL. It MUST NOT be empty.

### 3.2.5.38.1.1.26 TypeShortDescription

Type: **CSOM String**

Accessibility: Read Only

See **Microsoft.SharePoint.Client.Field.TypeShortDescription**, as specified in section [3.2.5.37.1.1.23](#).

It MUST NOT be NULL. It MUST NOT be empty.

#### **3.2.5.38.1.1.27 ValidationFormula**

Type: **CSOM String**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.ValidationFormula**, as specified in section [3.2.5.37.1.1.24](#).

#### **3.2.5.38.1.1.28 ValidationMessage**

Type: **CSOM String**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.ValidationMessage**, as specified in section [3.2.5.37.1.1.25](#).

Its length MUST be equal to or less than 1024.

#### **3.2.5.38.1.1.29 JSLink**

Type: **CSOM String**

Accessibility: Read/Write

Gets the name of an external ECMAScript ([\[ECMA-262-1999\]](#)) file containing any logic for this **field (2)**.

#### **3.2.5.38.1.1.30 EntityPropertyName**

Type: **CSOM String**

Accessibility: Read Only

Gets the name of the entity property of this **field (2)** in the **list item** entity that uses this field (2).

It MUST NOT be NULL. It MUST NOT be empty.

#### **3.2.5.38.1.1.31 Indexed**

Type: **CSOM Boolean**

Accessibility: Read/Write

Gets or sets a Boolean value that specifies whether the field is indexed.

#### **3.2.5.38.1.1.32 SchemaXmlWithResourceTokens**

Type: **CSOM String**

Accessibility: Read Only

Gets the unlocalized schema XML for this **field (2)**.

#### **3.2.5.38.1.1.33 AutoIndexed**

**Type:** CSOM Boolean

**Accessibility:** Read Only

Gets the Boolean value that specifies whether or not the field is auto-indexed. Specify a value of true if the field is auto-indexed; false if otherwise.

#### **3.2.5.38.1.1.34 ClientSideComponentId**

**Type:** CSOM GUID

**Accessibility:** Read/Write

The unique identifier of the client-side component defined with SharePoint Framework.

#### **3.2.5.38.1.1.35 ClientSideComponentProperties**

**Type:** CSOM String

**Accessibility:** Read/Write

This property is only used when a **ClientSideComponentId** is specified. It is optional. If non-empty, the string MUST contain a JSON object with custom initialization properties whose format and meaning are defined by the client-side component.

#### **3.2.5.38.1.1.36 CurrencyLocaleId**

**Type:** CSOM Int32

**Accessibility:** Read/Write

Gets or sets the locale ID that is used for currency on the Web site.

#### **3.2.5.38.1.1.37 CustomFormatter**

**Type:** CSOM String

**Accessibility:** Read/Write

A JSON string representing the custom rendering format of the field.

#### **3.2.5.38.1.1.38 DefaultFormula**

**Type:** CSOM String

**Accessibility:** Read/Write

Gets or sets the default formula for a calculated field.

#### **3.2.5.38.1.1.39 DisplayFormat**

**Type:** CSOM Int32

**Accessibility:** Read Only

Gets the number of decimal places to be used when displaying the field.

#### **3.2.5.38.1.1.40 NoCrawl**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Gets or sets a Boolean value that specifies whether the field can be crawled by a search engine.

#### **3.2.5.38.1.1.41 PinnedToFiltersPane**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Boolean value that indicates whether the field pins to filter pane.

#### **3.2.5.38.1.1.42 ShowAsPercentage**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Gets or sets a Boolean value that determines whether values in the field are displayed as percentages.

#### **3.2.5.38.1.1.43 ShowInFiltersPane**

**Type:** Microsoft.SharePoint.Client.ShowInFiltersPaneStatus

**Accessibility:** Read/Write

Indicates whether the field will be shown.

### **3.2.5.38.1.2 ObjectPath Properties**

#### **3.2.5.38.1.2.1 DescriptionResource**

**Type:** Microsoft.SharePoint.Client.UserResource

**Accessibility:** Read Only

Gets the resource object corresponding to the **Description** property for a field.

#### **3.2.5.38.1.2.2 TitleResource**

**Type:** Microsoft.SharePoint.Client.UserResource

**Accessibility:** Read Only

Gets the resource object corresponding to the **Title** property for a field.

### **3.2.5.38.2 Methods**

#### **3.2.5.38.2.1 Scalar Methods**

##### **3.2.5.38.2.1.1 DeleteObject**

**Return Type:** None

Deletes the **field (2)** from the **list**, from the **site (2)**, or from the **content types** within the list.

**Parameters:** None

**Exceptions:**

Error Code	Error Type Name	Condition
-1	System.InvalidOperationException	<b>CanBeDeleted</b> is "false".

### 3.2.5.38.2.1.2 SetShowInDisplayForm

**Return Type:** None

Sets this field to show or hide in the display form.

**Parameters:**

*value:* A Boolean value that indicates whether this field is shown in the display form.

Type: **CSOM Boolean**

### 3.2.5.38.2.1.3 SetShowInEditForm

**Return Type:** None

Sets this field to show or hide in the edit form.

**Parameters:**

*value:* A Boolean value that indicates whether this field is shown in the edit form.

Type: **CSOM Boolean**

### 3.2.5.38.2.1.4 SetShowInNewForm

**Return Type:** None

Sets this field to show or hide in the new form.

**Parameters:**

*value:* A Boolean value that indicates whether this field is shown in the new form.

Type: **CSOM Boolean**

### 3.2.5.38.2.1.5 Update

**Return Type:** None

Commits changed properties of the **field (2)**.

**Parameters:** None

**Exceptions:**

Error Code	Error Type Name	Condition
-2130246331	Microsoft.SharePoint.SPException	Type of the field (2) is changed for an <b>indexed field</b> . The field type of indexed fields cannot be changed.
-2130246238	Microsoft.SharePoint.SPException	Field (2) is set to not be an indexed field, and <b>EnforceUniqueValues</b> is "true".



Error Code	Error Type Name	Condition
- 2130246236	Microsoft.SharePoint.SPException	Type of the field (2) is being changed and <b>EnforceUniqueValues</b> of the field (2) is "true".

### 3.2.5.38.2.1.6 UpdateAndPushChanges

**Return Type:** None

Commits changed properties of the **field (2)** and propagates changes to all **lists** that use the field (2).

**Parameters:**

*pushChangesToLists*: Specifies whether to propagate changes to all lists that use the field (2).

Type: **CSOM Boolean**

**Exceptions:**

Error Code	Error Type Name	Condition
- 2130246331	Microsoft.SharePoint.SPException	Type of the field (2) is changed for an <b>indexed field</b> . The field type of indexed fields cannot be changed.
- 2130246238	Microsoft.SharePoint.SPException	Field (2) is set to not be an indexed field, and <b>EnforceUniqueValues</b> is "true".
- 2130246236	Microsoft.SharePoint.SPException	Type of the field (2) is being changed and <b>EnforceUniqueValues</b> of the field (2) is "true".

### 3.2.5.38.2.1.7 ValidateSetValue

**Return Type:** None

Validates and sets the value of the **field (2)** for the **list item** based on an implementation-specific transformation of the value. [<9>](#)

**Parameters:**

*item*: Specifies the list item to be updated with the new value.

Type: Microsoft.SharePoint.Client.ListItem

It MUST NOT be NULL.

*value*: Specifies the new value for the field (2).

Type: **CSOM String**

### 3.2.5.38.2.2 ObjectPath Methods

None.

### 3.2.5.39 Microsoft.SharePoint.Client.FieldCalculatedErrorValue

**TypeId:** {3387286B-36E3-4199-BDCA-F20048CE8328}

**ShortName:** SP.FieldCalculatedErrorValue

The value of a calculated field when the field value is actually a calculation error, such as division by zero, or overflow.

#### 3.2.5.39.1 Properties

##### 3.2.5.39.1.1 Scalar Properties

###### 3.2.5.39.1.1.1 ErrorMessage

**Type:** CSOM String

**Accessibility:** Read Only

Error message.

##### 3.2.5.39.1.2 ObjectPath Properties

None.

### 3.2.5.40 Microsoft.SharePoint.Client.FieldChoice

**TypeId:** {A0B73943-FABC-47D3-B2C8-EC41B1216B1D}

**ShortName:** SP.FieldChoice

Represents a choice **field (2)**. To set properties on this class, call the **Update** method (section [3.2.5.40.2.1.5](#)).

The NoCrawl and SchemaXmlWithResourceTokens properties are not included in the **default scalar property set** for this type.

#### 3.2.5.40.1 Properties

##### 3.2.5.40.1.1 Scalar Properties

###### 3.2.5.40.1.1.1 CanBeDeleted

**Type:** CSOM Boolean

**Accessibility:** Read Only

See **Microsoft.SharePoint.Client.Field.CanBeDeleted**, as specified in section [3.2.5.37.1.1.1](#).

###### 3.2.5.40.1.1.2 Choices

**Type:** CSOM array of CSOM String

**Accessibility:** Read/Write

Specifies the collection of choices that are used in this choice **field (2)**.

###### 3.2.5.40.1.1.3 DefaultValue

Type: **CSOM String**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.DefaultValue**, as specified in section [3.2.5.37.1.1.2](#).

Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	The <b>field (2)</b> value is being set, and the <b>list</b> is an <b>external list</b> .

#### 3.2.5.40.1.1.4 Description

Type: **CSOM String**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.Description**, as specified in section [3.2.5.37.1.1.3](#).

#### 3.2.5.40.1.1.5 Direction

Type: **CSOM String**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.Direction**, as specified in section [3.2.5.37.1.1.4](#).

Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	The <b>list</b> that the <b>field (2)</b> belongs to has an external <b>data source</b> and direction is not equal to none.

#### 3.2.5.40.1.1.6 EditFormat

Type: Microsoft.SharePoint.Client.ChoiceFormatType

Accessibility: Read/Write

Specifies whether to display the choice **field (2)** as radio buttons or as a drop-down list.

#### 3.2.5.40.1.1.7 EnforceUniqueValues

Type: **CSOM Boolean**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.EnforceUniqueValues**, as specified in section [3.2.5.37.1.1.5](#)

Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	If the <b>field (2)</b> belongs to a <b>list</b> that has an external <b>data source</b> and trying to set to "true".

### 3.2.5.40.1.1.8 FieldTypeKind

**Type:** Microsoft.SharePoint.Client.FieldType

**Accessibility:** Read/Write

See **Microsoft.SharePoint.Client.Field.FieldTypeKind**, as specified in section [3.2.5.37.1.1.6](#).

**Exceptions:**

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	The <b>field (2)</b> belongs to a <b>list</b> that has an external <b>data source</b> and <b>FieldTypeKind</b> is modified.

### 3.2.5.40.1.1.9 FillInChoice

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Specifies whether users can fill in their own values for the **field (2)**.

### 3.2.5.40.1.1.10 Filterable

**Type:** CSOM Boolean

**Accessibility:** Read Only

See **Microsoft.SharePoint.Client.Field.Filterable**, as specified in section [3.2.5.37.1.1.7](#).

### 3.2.5.40.1.1.11 FromBaseType

**Type:** CSOM Boolean

**Accessibility:** Read Only

Specifies whether the **field (2)** derives from a **base field type**.

### 3.2.5.40.1.1.12 Group

**Type:** CSOM String

**Accessibility:** Read/Write

See **Microsoft.SharePoint.Client.Field.Group**, as specified in section [3.2.5.37.1.1.9](#).

It MUST NOT be NULL. It MUST NOT be empty. Its length MUST be equal to or less than 128.

## Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	If this <b>field (2)</b> belongs to a <b>list</b> that has an external <b>data source</b> .

### 3.2.5.40.1.1.13 Hidden

Type: **CSOM Boolean**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.Hidden**, as specified in section [3.2.5.37.1.1.10](#).

### 3.2.5.40.1.1.14 Id

Type: **CSOM GUID**

Accessibility: Read Only

See **Microsoft.SharePoint.Client.Field.Id**, as specified in section [3.2.5.37.1.1.11](#).

### 3.2.5.40.1.1.15 InternalName

Type: **CSOM String**

Accessibility: Read Only

See **Microsoft.SharePoint.Client.Field.InternalName**, as specified in section [3.2.5.37.1.1.12](#).

It MUST NOT be NULL. It MUST NOT be empty.

### 3.2.5.40.1.1.16 Mappings

Type: **CSOM String**

Accessibility: Read Only

Specifies the canonical values for the specified choices.

It MUST be NULL or an XML fragment that conforms to **MAPPINGDEFINITION**, as specified in [\[MS-WSSFO3\]](#) section 2.2.7.3.13.

### 3.2.5.40.1.1.17 ReadOnlyField

Type: **CSOM Boolean**

Accessibility: Read/Write

Specifies whether values in the **field (2)** can be modified.

## Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Thrown when attempting to change the value of <b>ReadOnlyField</b> when this field (2) has an external <b>data source</b> .

### 3.2.5.40.1.1.18 Required

Type: **CSOM Boolean**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.Required**, as specified in section [3.2.5.37.1.1.14](#).

Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	If this <b>field (2)</b> belongs to a <b>list</b> that has an external <b>data source</b> and <b>Required</b> is set to "true".

### 3.2.5.40.1.1.19 SchemaXml

Type: **CSOM String**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.SchemaXml**, as specified in section [3.2.5.37.1.1.15](#).

It MUST be an **XML document** that conforms to the **FieldDefinition type** as defined in [\[MS-WSSCAML\]](#) or a string that is NULL or empty.

Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	The <b>list</b> that the <b>field (2)</b> belongs to has an external <b>data source</b> and the set value is not an empty or a null string.

### 3.2.5.40.1.1.20 Scope

Type: **CSOM String**

Accessibility: Read Only

See **Microsoft.SharePoint.Client.Field.Scope**, as specified in section [3.2.5.37.1.1.16](#).

### 3.2.5.40.1.1.21 Sealed

Type: **CSOM Boolean**

**Accessibility:** Read/Write

See **Microsoft.SharePoint.Client.Field.Sealed**, as specified in section [3.2.5.37.1.1.17](#).

### 3.2.5.40.1.1.22 Sortable

**Type:** CSOM Boolean

**Accessibility:** Read Only

See **Microsoft.SharePoint.Client.Field.Sortable**, as specified in section [3.2.5.37.1.1.18](#).

### 3.2.5.40.1.1.23 StaticName

**Type:** CSOM String

**Accessibility:** Read/Write

See **Microsoft.SharePoint.Client.Field.StaticName**, as specified in section [3.2.5.37.1.1.19](#).

**Exceptions:**

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	If this <b>field (2)</b> belongs to a <b>list</b> that has an external <b>data source</b> and <b>StaticName</b> is changed.

### 3.2.5.40.1.1.24 Title

**Type:** CSOM String

**Accessibility:** Read/Write

See **Microsoft.SharePoint.Client.Field.Title**, as specified in section [3.2.5.37.1.1.20](#).

### 3.2.5.40.1.1.25 TypeAsString

**Type:** CSOM String

**Accessibility:** Read/Write

See **Microsoft.SharePoint.Client.Field.TypeAsString**, as specified in section [3.2.5.37.1.1.21](#).

It MUST NOT be NULL. It MUST NOT be empty.

**Exceptions:**

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	If the <b>list</b> has an external <b>data source</b> .

### 3.2.5.40.1.1.26 TypeDisplayName

**Type:** CSOM String

**Accessibility:** Read Only

See **Microsoft.SharePoint.Client.Field.TypeDisplayName**, as specified in section [3.2.5.37.1.1.22](#).

It MUST NOT be NULL. It MUST NOT be empty.

### **3.2.5.40.1.1.27      TypeShortDescription**

**Type:** CSOM String

**Accessibility:** Read Only

See **Microsoft.SharePoint.Client.Field.TypeShortDescription**, as specified in section [3.2.5.37.1.1.23](#).

It MUST NOT be NULL. It MUST NOT be empty.

### **3.2.5.40.1.1.28      ValidationFormula**

**Type:** CSOM String

**Accessibility:** Read/Write

See **Microsoft.SharePoint.Client.Field.ValidationFormula**, as specified in section [3.2.5.37.1.1.24](#).

### **3.2.5.40.1.1.29      ValidationMessage**

**Type:** CSOM String

**Accessibility:** Read/Write

See **Microsoft.SharePoint.Client.Field.ValidationMessage**, as specified in section [3.2.5.37.1.1.25](#).

Its length MUST be equal to or less than 1024.

### **3.2.5.40.1.1.30      JSLink**

**Type:** CSOM String

**Accessibility:** Read/Write

Gets the name of an external ECMAScript ([\[ECMA-262-1999\]](#)) file containing any logic for this **field (2)**.

### **3.2.5.40.1.1.31      EntityPropertyName**

**Type:** CSOM String

**Accessibility:** Read Only

Gets the name of the entity property of this **field (2)** in the **list item** entity that uses this field (2).

It MUST NOT be NULL. It MUST NOT be empty.

### **3.2.5.40.1.1.32      Indexed**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Gets or sets a Boolean value that specifies whether the field is indexed.



### **3.2.5.40.1.1.33 SchemaXmlWithResourceTokens**

**Type:** CSOM String

**Accessibility:** Read Only

Gets the unlocalized schema XML for this **field (2)**.

### **3.2.5.40.1.1.34 AutoIndexed**

**Type:** CSOM Boolean

**Accessibility:** Read Only

Gets the Boolean value that specifies whether or not the field is auto-indexed. Specify a value of true if the field is auto-indexed; false if otherwise.

### **3.2.5.40.1.1.35 ClientSideComponentId**

**Type:** CSOM GUID

**Accessibility:** Read/Write

The unique identifier of the client-side component defined with SharePoint Framework.

### **3.2.5.40.1.1.36 ClientSideComponentProperties**

**Type:** CSOM String

**Accessibility:** Read/Write

This property is only used when a **ClientSideComponentId** is specified. It is optional. If non-empty, the string **MUST** contain a JSON object with custom initialization properties whose format and meaning are defined by the client-side component.

### **3.2.5.40.1.1.37 CustomFormatter**

**Type:** CSOM String

**Accessibility:** Read/Write

A JSON string representing the custom rendering format of the field.

### **3.2.5.40.1.1.38 DefaultFormula**

**Type:** CSOM String

**Accessibility:** Read/Write

Gets or sets the default formula for a calculated field.

### **3.2.5.40.1.1.39 NoCrawl**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Gets or sets a Boolean value that specifies whether the field can be crawled by a search engine.

### **3.2.5.40.1.1.40 PinnedToFiltersPane**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Boolean value that indicates whether the field pins to filter pane.

### 3.2.5.40.1.1.41 ShowInFiltersPane

**Type:** Microsoft.SharePoint.Client.ShowInFiltersPaneStatus

**Accessibility:** Read/Write

Indicates whether the field will be shown.

### 3.2.5.40.1.2 ObjectPath Properties

#### 3.2.5.40.1.2.1 DescriptionResource

**Type:** Microsoft.SharePoint.Client.UserResource

**Accessibility:** Read Only

Gets the resource object corresponding to the **Description** property for a field.

#### 3.2.5.40.1.2.2 TitleResource

**Type:** Microsoft.SharePoint.Client.UserResource

**Accessibility:** Read Only

Gets the resource object corresponding to the **Title** property for a field.

### 3.2.5.40.2 Methods

#### 3.2.5.40.2.1 Scalar Methods

##### 3.2.5.40.2.1.1 DeleteObject

**Return Type:** None

Deletes the **field (2)**.

**Parameters:** None

**Exceptions:**

Error Code	Error Type Name	Condition
-1	System.InvalidOperationException	The field (2) does not allow deletion.

##### 3.2.5.40.2.1.2 SetShowInDisplayForm

**Return Type:** None

Sets this field to show or hide in the display form.

**Parameters:**

*value*: A Boolean value that indicates whether this field is shown in the display form.

Type: **CSOM Boolean**

### 3.2.5.40.2.1.3 SetShowInEditForm

**Return Type:** None

Sets this field to show or hide in the edit form.

**Parameters:**

*value*: A Boolean value that indicates whether this field is shown in the edit form.

Type: **CSOM Boolean**

### 3.2.5.40.2.1.4 SetShowInNewForm

**Return Type:** None

Sets this field to show or hide in the new form.

**Parameters:**

*value*: A Boolean value that indicates whether this field is shown in the new form.

Type: **CSOM Boolean**

### 3.2.5.40.2.1.5 Update

**Return Type:** None

Updates the **field (2)**.

**Parameters:** None

**Exceptions:**

Error Code	Error Type Name	Condition
- 2130246331	Microsoft.SharePoint.SPException	Changing the field type on an indexed field (2) or changing the field type and indexing the field (2) at the same time.
- 2130246238	Microsoft.SharePoint.SPException	Changing a field (2) to stop indexing that does not allow duplicate values.
- 2130246236	Microsoft.SharePoint.SPException	Changing the field type of the field (2) that does not allow duplicate values.

### 3.2.5.40.2.1.6 UpdateAndPushChanges

**Return Type:** None

Updates the **field (2)**, optionally propagating the changes to **lists** containing the field (2).

**Parameters:**

*pushChangesToLists*: "true" to propagate changes to lists that contain the field (2); otherwise, "false".

Type: **CSOM Boolean**

**Exceptions:**

Error Code	Error Type Name	Condition
- 2130246331	Microsoft.SharePoint.SPException	Changing the field type on an indexed field (2) or changing the field type and indexing the field (2) at the same time.
- 2130246238	Microsoft.SharePoint.SPException	Changing a field (2) to stop indexing that does not allow duplicate values.
- 2130246236	Microsoft.SharePoint.SPException	Changing the field type of a field (2) that does not allow duplicate values.

### 3.2.5.40.2.1.7 ValidateSetValue

**Return Type:** None

Validates and sets the value of the **field (2)** for the **list item** based on an implementation-specific transformation of the value. [<10>](#)

**Parameters:**

*item*: Specifies the list item to be updated with the new value.

Type: Microsoft.SharePoint.Client.ListItem

It MUST NOT be NULL.

*value*: Specifies the new value for the field (2).

Type: **CSOM String**

### 3.2.5.40.2.2 ObjectPath Methods

None.

### 3.2.5.41 Microsoft.SharePoint.Client.FieldCollection

**TypeId:** {D449D756-E113-4D27-A5E7-609CBC3EBA7E}

**ShortName:** SP.FieldCollection

Represents a read only Collection of **fields (2)**

#### 3.2.5.41.1 Properties

##### 3.2.5.41.1.1 Scalar Properties

###### 3.2.5.41.1.1.1 SchemaXml

Type: **CSOM String**

**Accessibility:** Read Only

Specifies the **XML schema** of the collection of **fields (2)**.

It MUST NOT be NULL. It MUST NOT be empty. It MUST be an **XML document** in which each field (2) in **SchemaXml** conforms to the **FieldDefinition** type as defined in [\[MS-WSSFO2\]](#) section 2.2.8.3.3 or [\[MS-WSSFO3\]](#) section 2.2.7.3.3.

### 3.2.5.41.1.2 ObjectPath Properties

None.

### 3.2.5.41.2 Methods

#### 3.2.5.41.2.1 Scalar Methods

None.

#### 3.2.5.41.2.2 ObjectPath Methods

##### 3.2.5.41.2.2.1 Add

**Return Type:** Microsoft.SharePoint.Client.Field

Adds a **field (2)** to the field (2) collection. A **reference** to the SP.Field that was added is returned.

**Parameters:**

*field:* A Microsoft.Sharepoint.Field **object (1)**.

Type: Microsoft.SharePoint.Client.Field

It MUST NOT be NULL.

##### 3.2.5.41.2.2.2 AddDependentLookup

**Return Type:** Microsoft.SharePoint.Client.Field

Adds a secondary **lookup field** to a **field (2)** collection. A **reference** to the SP.Field that was added is returned.

**Parameters:**

*displayName:* Title of the added field (2).

Type: **CSOM String**

*primaryLookupField:* Main lookup field to associate the dependent lookup field with. A dependent lookup field will include data from the **list item** referred to from the instance of the main lookup field.

Type: Microsoft.SharePoint.Client.Field

*lookupField:* Name of the field (2) from the target **list** to include data from.

Type: CSOM String

##### 3.2.5.41.2.2.3 AddFieldAsXml

**Return Type:** Microsoft.SharePoint.Client.Field

Creates a **field (2)** in the field (2) collection. A **reference** to the SP.Field that was added is returned.

**Parameters:**

*schemaXml*: XML string that specifies the field (2) definition.

Type: **CSOM String**

It MUST be a valid XML string corresponding to the following schema:

```
<s:element name="Field" minOccurs="1" maxOccurs="1" type="core:FieldDefinition">
```

The **FieldDefinition** type is specified in [\[MS-WSSFO2\]](#) section 2.2.8.3.3 or [\[MS-WSSFO3\]](#) section 2.2.7.3.3.

It MUST NOT be NULL. It MUST NOT be empty.

*addToDefaultView*: Specifies to add the field (2) to the default **list view**.

Type: **CSOM Boolean**

*options*: A value that specifies the field (2) options.

Type: Microsoft.SharePoint.Client.AddFieldOptions

**Exceptions:**

Error Code	Error Type Name	Condition
-2147024891	System.UnauthorizedAccessException	The <b>current user</b> has insufficient permissions.

### 3.2.5.41.2.2.4 GetById

**Return Type:** Microsoft.SharePoint.Client.Field

Returns the **field (2)** specified by the identifier as represented by the parameter.

**Parameters:**

*id*: The field (2) identifier.

Type: **CSOM GUID**

### 3.2.5.41.2.2.5 GetByInternalNameOrTitle

**Return Type:** Microsoft.SharePoint.Client.Field

Returns the first **field (2)** in the collection based on the internal name or the title specified by the parameter.

**Parameters:**

*strName*: The title or internal name to look up the field (2) by.

Type: **CSOM String**

It MUST NOT be NULL. It MUST NOT be empty.

### 3.2.5.41.2.2.6 GetByTitle

**Return Type:** Microsoft.SharePoint.Client.Field

Returns the first **field (2) object (1)** in the collection based on the title of the specified field (2).

**Parameters:**

*title*: The title to look up the field (2) by.

Type: **CSOM String**

It MUST NOT be NULL. It MUST NOT be empty.

### 3.2.5.41.2.2.7 AddDependentLookupField

**Return Type:** Microsoft.SharePoint.Client.Field

Adds a secondary **lookup field** to a **field (2)** collection. [<11>](#) A **reference** to the SP.Field that was added is returned.

**Parameters:**

*displayName*: Title of the added field (2).

Type: **CSOM String**

*primaryLookupFieldId*: Main lookup field to associate the dependent lookup field with. A dependent lookup field will include data from the **list item** referred to from the instance of the main lookup field.

Type: **CSOM GUID**

*showField*: A string that contains the internal name of the new field (2).

Type: CSOM String

### 3.2.5.41.2.2.8 AddField

**Return Type:** Microsoft.SharePoint.Client.Field

Adds a **field (2)** to the field (2) collection. [<12>](#) A **reference** to the **SP.Field** (section [3.2.5.37](#)) that was added is returned.

**Parameters:**

*parameters*: The metadata of the field (2) to be added.

Type: Microsoft.SharePoint.Client.FieldCreationInformation

It MUST NOT be NULL.

**Exceptions:**

Error Code	Error Type Name	Condition
- 2146232832	Microsoft.SharePoint.SPException	Functionality is unavailable for fields not associated with a <b>list</b> , a user tried to add a new field (2) using a duplicate identifier, a user tried to add a relationship behavior to a <b>site (2)</b> column, a user tried to update a <b>configuration database</b> while object had been changed by another user, a user tried to add a field (2) without specifying a display name, or a user tried to set <b>unique column constraints</b> to "true" for a field (2) that cannot be set to "false".

Error Code	Error Type Name	Condition
- 2130575340	Microsoft.SharePoint.SPException	One or more field (2) types are not installed properly.
- 2130575199	Microsoft.SharePoint.SPException	Formula is empty for the calculated field (2) type.
- 2147024860	Microsoft.SharePoint.SPQueryThrottledException	There is a throttle failure.
- 2147024749	Microsoft.SharePoint.SPQueryThrottledException	There is a join throttle failure.
- 2147024809	System.ArgumentException	Field (2) with the specified internal name or title does not exist in the collection at the given scope.
- 2147024891	System.UnauthorizedAccessException	User does not have permissions to get the field (2).

### 3.2.5.41.2.2.9 CreateFieldAsXml

**Return Type:** Microsoft.SharePoint.Client.Field

Creates a field based on the values defined in the *parameters* input parameter. <13>

**Parameters:**

*parameters*: Defines the information needed to create a **field (2)** using an **XML schema**.

Type: Microsoft.SharePoint.Client.XmlSchemaFieldCreationInformation

It MUST NOT be NULL.

**Exceptions:**

Error Code	Error Type Name	Condition
- 214623283 2	Microsoft.SharePoint.SPException	Functionality is unavailable for fields (2) not associated with a list, or a user tried to add a new field using a duplicate identifies, or a user tried to add a field with a duplicate name and the <b>AddFieldOptions.AddFieldCheckDisplayName</b> input parameter is specified, or a user tried to add a relationship behavior to a <b>site (2)</b> column, or a user tried to update a <b>configuration database</b> while object has been changed by another user, or a user tried to add a field (2) without specifying a display name, or a user tried to set <b>unique column constraints</b> to "true" for a field (2) that cannot be set to "false".
- 213057534 0	Microsoft.SharePoint.SPException	One or more field types are not installed properly.
- 213057519	Microsoft.SharePoint.SPException	Formula is empty for the calculated field type.



Error Code	Error Type Name	Condition
9		
-2147024860	Microsoft.SharePoint.SPQueryThrottledException	There is a throttle failure.
-2147024749	Microsoft.SharePoint.SPQueryThrottledException	There is a join throttle failure.
-2147024809	System.ArgumentException	The field (2) with the specified internal name or title does not exist in the collection at the given scope.
-2147024891	System.UnauthorizedAccessException	User does not have permissions to get the field (2).

### 3.2.5.42 Microsoft.SharePoint.Client.FieldComputed

**TypeId:** {379B8994-F0E7-4C74-A1E6-185EB8600C3C}

**ShortName:** SP.FieldComputed

Specifies a **computed field**. To set the properties of this class, call the **Update** method (section [3.2.5.42.2.1.5](#)).

The NoCrawl and SchemaXmlWithResourceTokens properties are not included in the **default scalar property set** for this type.

#### 3.2.5.42.1 Properties

##### 3.2.5.42.1.1 Scalar Properties

###### 3.2.5.42.1.1.1 CanBeDeleted

**Type:** CSOM Boolean

**Accessibility:** Read Only

See **Microsoft.SharePoint.Client.Field.CanBeDeleted**, as specified in section [3.2.5.37.1.1.1](#).

###### 3.2.5.42.1.1.2 DefaultValue

**Type:** CSOM String

**Accessibility:** Read/Write

See **Microsoft.SharePoint.Client.Field.DefaultValue**, as specified in section [3.2.5.37.1.1.2](#).

#### Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed, and the <b>list</b> is an <b>external list</b> .

### 3.2.5.42.1.1.3 Description

Type: **CSOM String**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.Description**, as specified in section [3.2.5.37.1.1.3](#).

### 3.2.5.42.1.1.4 Direction

Type: **CSOM String**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.Direction**, as specified in section [3.2.5.37.1.1.4](#).

#### Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed to a value other than "none", and the <b>list</b> is an <b>external list</b> .

### 3.2.5.42.1.1.5 EnableLookup

Type: **CSOM Boolean**

Accessibility: Read/Write

Specifies whether a **lookup field** can reference the **field (2)**.

### 3.2.5.42.1.1.6 EnforceUniqueValues

Type: **CSOM Boolean**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.EnforceUniqueValues**, as specified in section [3.2.5.37.1.1.5](#).

#### Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Adding <b>unique column constraints</b> to the <b>field (2)</b> where the <b>list</b> is an <b>external list</b> .

### 3.2.5.42.1.1.7 FieldTypeKind

Type: Microsoft.SharePoint.Client.FieldType

**Accessibility:** Read/Write

See **Microsoft.SharePoint.Client.Field.FieldTypeKind**, as specified in section [3.2.5.37.1.1.6](#).

**Exceptions:**

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed, and the <b>list</b> is an <b>external list</b> .

### 3.2.5.42.1.1.8 Filterable

**Type:** CSOM Boolean

**Accessibility:** Read Only

See **Microsoft.SharePoint.Client.Field.Filterable**, as specified in section [3.2.5.37.1.1.7](#).

### 3.2.5.42.1.1.9 FromBaseType

**Type:** CSOM Boolean

**Accessibility:** Read Only

Gets a **Boolean** value that indicates whether the **field (2)** derives from a **base field type**.

### 3.2.5.42.1.1.10 Group

**Type:** CSOM String

**Accessibility:** Read/Write

See **Microsoft.SharePoint.Client.Field.Group**, as specified in section [3.2.5.37.1.1.9](#).

It MUST NOT be NULL. It MUST NOT be empty. Its length MUST be equal to or less than 128.

**Exceptions:**

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed, and the <b>list</b> is an <b>external list</b> .

### 3.2.5.42.1.1.11 Hidden

**Type:** CSOM Boolean

**Accessibility:** Read/Write

See **Microsoft.SharePoint.Client.Field.Hidden**, as specified in section [3.2.5.37.1.1.10](#).

### 3.2.5.42.1.1.12 Id

**Type:** CSOM GUID

**Accessibility:** Read Only

See **Microsoft.SharePoint.Client.Field.Id**, as specified in section [3.2.5.37.1.1.11](#).

### 3.2.5.42.1.1.13 InternalName

Type: **CSOM String**

Accessibility: Read Only

See **Microsoft.SharePoint.Client.Field.InternalName**, as specified in section [3.2.5.37.1.1.12](#).

It MUST NOT be NULL. It MUST NOT be empty.

### 3.2.5.42.1.1.14 ReadOnlyField

Type: **CSOM Boolean**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.ReadOnlyField**, as specified in section [3.2.5.37.1.1.13](#).

Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed, and the <b>list</b> is an <b>external list</b> .

### 3.2.5.42.1.1.15 Required

Type: **CSOM Boolean**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.Required**, as specified in section [3.2.5.37.1.1.14](#).

Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is set to "true", and the <b>list</b> is an <b>external list</b> .

### 3.2.5.42.1.1.16 SchemaXml

Type: **CSOM String**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.SchemaXml**, as specified in section [3.2.5.37.1.1.15](#).

It MUST be NULL, empty, or an **XML fragment** that conforms to the **FieldDefinition** type as defined in [\[MS-WSSFO2\]](#) section 2.2.8.3.3 or [\[MS-WSSFO3\]](#) section 2.2.7.3.3.

Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed to a non-NULL or non-empty value, and the <b>list</b> is an <b>external list</b> .

### 3.2.5.42.1.1.17 Scope

Type: **CSOM String**

Accessibility: Read Only

See **Microsoft.SharePoint.Client.Field.Scope**, as specified in section [3.2.5.37.1.1.16](#).

### 3.2.5.42.1.1.18 Sealed

Type: **CSOM Boolean**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.Sealed**, as specified in section [3.2.5.37.1.1.17](#).

### 3.2.5.42.1.1.19 Sortable

Type: **CSOM Boolean**

Accessibility: Read Only

See **Microsoft.SharePoint.Client.Field.Sortable**, as specified in section [3.2.5.37.1.1.18](#).

### 3.2.5.42.1.1.20 StaticName

Type: **CSOM String**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.StaticName**, as specified in section [3.2.5.37.1.1.19](#).

#### Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed, and the <b>list</b> is an <b>external list</b> .

### 3.2.5.42.1.1.21 Title

Type: **CSOM String**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.Title**, as specified in section [3.2.5.37.1.1.20](#).

### 3.2.5.42.1.1.22 TypeAsString

Type: **CSOM String**

**Accessibility:** Read/Write

See **Microsoft.SharePoint.Client.Field.TypeAsString**, as specified in section [3.2.5.37.1.1.21](#).

It MUST NOT be NULL. It MUST NOT be empty.

**Exceptions:**

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed, and the <b>list</b> is an <b>external list</b> .

### 3.2.5.42.1.1.23 TypeDisplayName

**Type:** CSOM String

**Accessibility:** Read Only

See **Microsoft.SharePoint.Client.Field.TypeDisplayName**, as specified in section [3.2.5.37.1.1.22](#).

It MUST NOT be NULL. It MUST NOT be empty.

### 3.2.5.42.1.1.24 TypeShortDescription

**Type:** CSOM String

**Accessibility:** Read Only

See **Microsoft.SharePoint.Client.Field.TypeShortDescription**, as specified in section [3.2.5.37.1.1.23](#).

It MUST NOT be NULL. It MUST NOT be empty.

### 3.2.5.42.1.1.25 ValidationFormula

**Type:** CSOM String

**Accessibility:** Read/Write

See **Microsoft.SharePoint.Client.Field.ValidationFormula**, as specified in section [3.2.5.37.1.1.24](#).

### 3.2.5.42.1.1.26 ValidationMessage

**Type:** CSOM String

**Accessibility:** Read/Write

See **Microsoft.SharePoint.Client.Field.ValidationMessage**, as specified in section [3.2.5.37.1.1.25](#).

Its length MUST be equal to or less than 1024.

### 3.2.5.42.1.1.27 JSLink

**Type:** CSOM String

**Accessibility:** Read/Write

Gets the name of an external ECMAScript ([\[ECMA-262-1999\]](#)) file containing any logic for this **field (2)**.

#### **3.2.5.42.1.1.28 EntityPropertyName**

**Type:** CSOM String

**Accessibility:** Read Only

Gets the name of the entity property of this **field (2)** in the **list item** entity that uses this field (2).

It MUST NOT be NULL. It MUST NOT be empty.

#### **3.2.5.42.1.1.29 Indexed**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Gets or sets a Boolean value that specifies whether the field is indexed.

#### **3.2.5.42.1.1.30 SchemaXmlWithResourceTokens**

**Type:** CSOM String

**Accessibility:** Read Only

Gets the unlocalized schema XML for this **field (2)**.

#### **3.2.5.42.1.1.31 AutoIndexed**

**Type:** CSOM Boolean

**Accessibility:** Read Only

Gets the Boolean value that specifies whether or not the field is auto-indexed. Specify a value of true if the field is auto-indexed; false if otherwise.

#### **3.2.5.42.1.1.32 ClientSideComponentId**

**Type:** CSOM GUID

**Accessibility:** Read/Write

The unique identifier of the client-side component defined with SharePoint Framework.

#### **3.2.5.42.1.1.33 ClientSideComponentProperties**

**Type:** CSOM String

**Accessibility:** Read/Write

This property is only used when a **ClientSideComponentId** is specified. It is optional. If non-empty, the string MUST contain a JSON object with custom initialization properties whose format and meaning are defined by the client-side component.

#### **3.2.5.42.1.1.34 CustomFormatter**

**Type:** CSOM String

**Accessibility:** Read/Write

A JSON string representing the custom rendering format of the field.

### **3.2.5.42.1.1.35 DefaultFormula**

**Type:** CSOM String

**Accessibility:** Read/Write

Gets or sets the default formula for a calculated field.

### **3.2.5.42.1.1.36 NoCrawl**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Gets or sets a Boolean value that specifies whether the field can be crawled by a search engine.

### **3.2.5.42.1.1.37 PinnedToFiltersPane**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Boolean value that indicates whether the field pins to filter pane.

### **3.2.5.42.1.1.38 ShowInFiltersPane**

**Type:** Microsoft.SharePoint.Client.ShowInFiltersPaneStatus

**Accessibility:** Read/Write

Indicates whether the field will be shown.

## **3.2.5.42.1.2 ObjectPath Properties**

### **3.2.5.42.1.2.1 DescriptionResource**

**Type:** Microsoft.SharePoint.Client.UserResource

**Accessibility:** Read Only

Gets the resource object corresponding to the **Description** property for a field.

### **3.2.5.42.1.2.2 TitleResource**

**Type:** Microsoft.SharePoint.Client.UserResource

**Accessibility:** Read Only

Gets the resource object corresponding to the **Title** property for a field.

## **3.2.5.42.2 Methods**

### **3.2.5.42.2.1 Scalar Methods**

#### **3.2.5.42.2.1.1 DeleteObject**



**Return Type:** None

Deletes the **field (2)** from the **list**, from the **site (2)**, or from the **content types** within the list.

**Parameters:** None

**Exceptions:**

Error Code	Error Type Name	Condition
-1	System.InvalidOperationException	<b>CanBeDeleted</b> is "false".

### **3.2.5.42.2.1.2 SetShowInDisplayForm**

**Return Type:** None

Sets this field to show or hide in the display form.

**Parameters:**

*value:* A Boolean value that indicates whether this field is shown in the display form.

Type: **CSOM Boolean**

### **3.2.5.42.2.1.3 SetShowInEditForm**

**Return Type:** None

Sets this field to show or hide in the edit form.

**Parameters:**

*value:* A Boolean value that indicates whether this field is shown in the edit form.

Type: **CSOM Boolean**

### **3.2.5.42.2.1.4 SetShowInNewForm**

**Return Type:** None

Sets this field to show or hide in the new form.

**Parameters:**

*value:* A Boolean value that indicates whether this field is shown in the new form.

Type: **CSOM Boolean**

### **3.2.5.42.2.1.5 Update**

**Return Type:** None

Commits changed properties of the **field (2)**.

**Parameters:** None

**Exceptions:**

Error Code	Error Type Name	Condition
- 2130246331	Microsoft.SharePoint.SPException	Type of the field (2) is changed for an <b>indexed field</b> . The field type of indexed fields cannot be changed.
- 2130246238	Microsoft.SharePoint.SPException	Field (2) is set to not be an indexed field, and <b>EnforceUniqueValues</b> is "true".
- 2130246236	Microsoft.SharePoint.SPException	Type of the field (2) is being changed and <b>EnforceUniqueValues</b> of the_field (2) is "true".

### 3.2.5.42.2.1.6 UpdateAndPushChanges

**Return Type:** None

Commits changed properties of the **field (2)** and propagates changes to all **lists** that use the field (2).

**Parameters:**

*pushChangesToLists*: Specifies whether to propagate changes to all lists that use the field (2).

Type: **CSOM Boolean**

**Exceptions:**

Error Code	Error Type Name	Condition
- 2130246331	Microsoft.SharePoint.SPException	Type of the field (2) is changed for an <b>indexed field</b> . The field type of indexed fields cannot be changed.
- 2130246238	Microsoft.SharePoint.SPException	Field (2) is set to not be an indexed field, and <b>EnforceUniqueValues</b> is "true".
- 2130246236	Microsoft.SharePoint.SPException	Type of the field (2) is being changed and <b>EnforceUniqueValues</b> of the field (2) is "true".

### 3.2.5.42.2.1.7 ValidateSetValue

**Return Type:** None

Validates and sets the value of the **field (2)** for the **list item** based on an implementation-specific transformation of the value. [<14>](#)

**Parameters:**

*item*: Specifies the list item to be updated with the new value.

Type: Microsoft.SharePoint.Client.ListItem

It MUST NOT be NULL.

*value*: Specifies the new value for the field (2).

Type: **CSOM String**

### 3.2.5.42.2.2 ObjectPath Methods

None.

### 3.2.5.43 Microsoft.SharePoint.Client.FieldCurrency

**TypeId:** {E03CA5F6-5F18-47F3-8AB4-74CABA56EE1E}

**ShortName:** SP.FieldCurrency

Specifies a **field (2)** that contains currency values. To set properties, call the Update method (section [3.2.5.43.2.1.5](#)).

The NoCrawl and SchemaXmlWithResourceTokens properties are not included in the **default scalar property set** for this type.

#### 3.2.5.43.1 Properties

##### 3.2.5.43.1.1 Scalar Properties

###### 3.2.5.43.1.1.1 CanBeDeleted

**Type:** CSOM Boolean

**Accessibility:** Read Only

See **Microsoft.SharePoint.Client.Field.CanBeDeleted**, as specified in section [3.2.5.37.1.1.1](#).

###### 3.2.5.43.1.1.2 CurrencyLocaleId

**Type:** CSOM Int32

**Accessibility:** Read/Write

Specifies the **language code identifier (LCID)** used to format the value of the **field (2)**.

It MUST be a valid language code identifier (LCID) as specified in [\[MS-LCID\]](#) section [2](#).

###### 3.2.5.43.1.1.3 DefaultValue

**Type:** CSOM String

**Accessibility:** Read/Write

See **Microsoft.SharePoint.Client.Field.DefaultValue**, as specified in section [3.2.5.37.1.1.2](#).

#### Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed, and the <b>list</b> is an <b>external list</b> .

##### 3.2.5.43.1.1.4 Description

**Type:** CSOM String

**Accessibility:** Read/Write

See **Microsoft.SharePoint.Client.Field.Description**, as specified in section [3.2.5.37.1.1.3](#).

### 3.2.5.43.1.1.5 Direction

Type: **CSOM String**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.Direction**, as specified in section [3.2.5.37.1.1.4](#).

#### Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed to a value other than "none," and the <b>list</b> is an <b>external list</b> .

### 3.2.5.43.1.1.6 EnforceUniqueValues

Type: **CSOM Boolean**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.EnforceUniqueValues**, as specified in section [3.2.5.37.1.1.5](#).

#### Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Adding <b>unique column constraints</b> to the <b>field (2)</b> where the <b>list</b> is an <b>external list</b> .

### 3.2.5.43.1.1.7 FieldTypeKind

Type: Microsoft.SharePoint.Client.FieldType

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.FieldTypeKind**, as specified in section [3.2.5.37.1.1.6](#).

#### Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed, and the <b>list</b> is an <b>external list</b> .

### 3.2.5.43.1.1.8 Filterable

Type: **CSOM Boolean**

Accessibility: Read Only

See **Microsoft.SharePoint.Client.Field.Filterable**, as specified in section [3.2.5.37.1.1.7](#).

### 3.2.5.43.1.1.9 FromBaseType

Type: **CSOM Boolean**

Accessibility: Read Only

Gets a **Boolean** value that indicates whether the **field (2)** derives from a **base field type**.

### 3.2.5.43.1.1.10 Group

Type: **CSOM String**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.Group**, as specified in section [3.2.5.37.1.1.9](#).

It MUST NOT be NULL. It MUST NOT be empty. Its length MUST be equal to or less than 128.

Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed, and the <b>list</b> is an <b>external list</b> .

### 3.2.5.43.1.1.11 Hidden

Type: **CSOM Boolean**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.Hidden**, as specified in section [3.2.5.37.1.1.10](#).

### 3.2.5.43.1.1.12 Id

Type: **CSOM GUID**

Accessibility: Read Only

See **Microsoft.SharePoint.Client.Field.Id**, as specified in section [3.2.5.37.1.1.11](#).

### 3.2.5.43.1.1.13 InternalName

Type: **CSOM String**

Accessibility: Read Only

See **Microsoft.SharePoint.Client.Field.InternalName**, as specified in section [3.2.5.37.1.1.12](#).

It MUST NOT be NULL. It MUST NOT be empty.

### 3.2.5.43.1.1.14 MaximumValue

Type: **CSOM Double**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.FieldNumber.MaximumValue**, as specified in section [3.2.5.53.1.1.13](#).

### 3.2.5.43.1.1.15 MinimumValue

Type: **CSOM Double**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.FieldNumber.MinimumValue**, as specified in section [3.2.5.53.1.1.14](#).

### 3.2.5.43.1.1.16 ReadOnlyField

Type: **CSOM Boolean**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.ReadOnlyField**, as specified in section [3.2.5.37.1.1.13](#).

Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed, and the <b>list</b> is an <b>external list</b> .

### 3.2.5.43.1.1.17 Required

Type: **CSOM Boolean**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.Required**, as specified in section [3.2.5.37.1.1.14](#).

Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is set to "true", and the <b>list</b> is an <b>external list</b> .

### 3.2.5.43.1.1.18 SchemaXml

Type: **CSOM String**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.SchemaXml**, as specified in section [3.2.5.37.1.1.15](#).

It MUST be NULL, empty, or an **XML fragment** that conforms to the **FieldDefinition** type, as specified in [\[MS-WSSFO2\]](#) section 2.2.8.3.3 or [\[MS-WSSFO3\]](#) section 2.2.7.3.3.

Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed to a non-NULL or non-empty value, and the <b>list</b> is an <b>external list</b> .

### 3.2.5.43.1.1.19 Scope

Type: **CSOM String**

Accessibility: Read Only

See **Microsoft.SharePoint.Client.Field.Scope**, as specified in section [3.2.5.37.1.1.16](#).

### 3.2.5.43.1.1.20 Sealed

Type: **CSOM Boolean**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.Sealed**, as specified in section [3.2.5.37.1.1.17](#).

### 3.2.5.43.1.1.21 Sortable

Type: **CSOM Boolean**

Accessibility: Read Only

See **Microsoft.SharePoint.Client.Field.Sortable**, as specified in section [3.2.5.37.1.1.18](#).

### 3.2.5.43.1.1.22 StaticName

Type: **CSOM String**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.StaticName**, as specified in section [3.2.5.37.1.1.19](#).

#### Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed, and the <b>list</b> is an <b>external list</b> .

### 3.2.5.43.1.1.23 Title

Type: **CSOM String**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.Title**, as specified in section [3.2.5.37.1.1.20](#).

### 3.2.5.43.1.1.24 TypeAsString

Type: **CSOM String**

**Accessibility:** Read/Write

See **Microsoft.SharePoint.Client.Field.TypeAsString**, as specified in section [3.2.5.37.1.1.21](#).

It MUST NOT be NULL. It MUST NOT be empty.

**Exceptions:**

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed, and the <b>list</b> is an <b>external list</b> .

**3.2.5.43.1.1.25 TypeDisplayName**

**Type:** CSOM String

**Accessibility:** Read Only

See **Microsoft.SharePoint.Client.Field.TypeDisplayName**, as specified in section [3.2.5.37.1.1.22](#).

It MUST NOT be NULL. It MUST NOT be empty.

**3.2.5.43.1.1.26 TypeShortDescription**

**Type:** CSOM String

**Accessibility:** Read Only

See **Microsoft.SharePoint.Client.Field.TypeShortDescription**, as specified in section [3.2.5.37.1.1.23](#).

It MUST NOT be NULL. It MUST NOT be empty.

**3.2.5.43.1.1.27 ValidationFormula**

**Type:** CSOM String

**Accessibility:** Read/Write

See **Microsoft.SharePoint.Client.Field.ValidationFormula**, as specified in section [3.2.5.37.1.1.24](#).

**3.2.5.43.1.1.28 ValidationMessage**

**Type:** CSOM String

**Accessibility:** Read/Write

See **Microsoft.SharePoint.Client.Field.ValidationMessage**, as specified in section [3.2.5.37.1.1.25](#).

Its length MUST be equal to or less than 1024.

**3.2.5.43.1.1.29 JSLink**

**Type:** CSOM String

**Accessibility:** Read/Write



Gets the name of an external ECMAScript ([\[ECMA-262-1999\]](#)) file containing any logic for this **field (2)**.

#### **3.2.5.43.1.1.30 EntityPropertyName**

**Type:** CSOM String

**Accessibility:** Read Only

Gets the name of the entity property of this **field (2)** in the **list item** entity that uses this field (2).

It MUST NOT be NULL. It MUST NOT be empty.

#### **3.2.5.43.1.1.31 Indexed**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Gets or sets a Boolean value that specifies whether the field is indexed.

#### **3.2.5.43.1.1.32 SchemaXmlWithResourceTokens**

**Type:** CSOM String

**Accessibility:** Read Only

Gets the unlocalized schema XML for this **field (2)**.

#### **3.2.5.43.1.1.33 AutoIndexed**

**Type:** CSOM Boolean

**Accessibility:** Read Only

Gets the Boolean value that specifies whether or not the field is auto-indexed. Specify a value of true if the field is auto-indexed; false if otherwise.

#### **3.2.5.43.1.1.34 ClientSideComponentId**

**Type:** CSOM GUID

**Accessibility:** Read/Write

The unique identifier of the client-side component defined with SharePoint Framework.

#### **3.2.5.43.1.1.35 ClientSideComponentProperties**

**Type:** CSOM String

**Accessibility:** Read/Write

This property is only used when a **ClientSideComponentId** is specified. It is optional. If non-empty, the string MUST contain a JSON object with custom initialization properties whose format and meaning are defined by the client-side component.

#### **3.2.5.43.1.1.36 CustomFormatter**

**Type:** CSOM String

**Accessibility:** Read/Write

A JSON string representing the custom rendering format of the field.

#### **3.2.5.43.1.1.37 DefaultFormula**

**Type:** CSOM String

**Accessibility:** Read/Write

Gets or sets the default formula for a calculated field.

#### **3.2.5.43.1.1.38 DisplayFormat**

**Type:** CSOM Int32

**Accessibility:** Read Only

Gets the number of decimal places to be used when displaying the field.

#### **3.2.5.43.1.1.39 NoCrawl**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Gets or sets a Boolean value that specifies whether the field can be crawled by a search engine.

#### **3.2.5.43.1.1.40 PinnedToFiltersPane**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Boolean value that indicates whether the field pins to filter pane.

#### **3.2.5.43.1.1.41 ShowAsPercentage**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Gets or sets a Boolean value that specifies whether to render the field as a percentage.

#### **3.2.5.43.1.1.42 ShowInFiltersPane**

**Type:** Microsoft.SharePoint.Client.ShowInFiltersPaneStatus

**Accessibility:** Read/Write

Indicates whether the field will be shown.

### **3.2.5.43.1.2 ObjectPath Properties**

#### **3.2.5.43.1.2.1 DescriptionResource**

**Type:** Microsoft.SharePoint.Client.UserResource

**Accessibility:** Read Only

Gets the resource object corresponding to the **Description** property for a field.

### 3.2.5.43.1.2.2 TitleResource

**Type:** Microsoft.SharePoint.Client.UserResource

**Accessibility:** Read Only

Gets the resource object corresponding to the **Title** property for a field.

## 3.2.5.43.2 Methods

### 3.2.5.43.2.1 Scalar Methods

#### 3.2.5.43.2.1.1 DeleteObject

**Return Type:** None

Deletes the **field (2)** from the **list**, from the **site (2)**, or from the **content types** within the list.

**Parameters:** None

**Exceptions:**

Error Code	Error Type Name	Condition
-1	System.InvalidOperationException	<b>CanBeDeleted</b> is "false".

#### 3.2.5.43.2.1.2 setShowInDisplayForm

**Return Type:** None

Sets this field to show or hide in the display form.

**Parameters:**

*value:* A Boolean value that indicates whether this field is shown in the display form.

Type: **CSOM Boolean**

#### 3.2.5.43.2.1.3 setShowInEditForm

**Return Type:** None

Sets this field to show or hide in the edit form.

**Parameters:**

*value:* A Boolean value that indicates whether this field is shown in the edit form.

Type: **CSOM Boolean**

#### 3.2.5.43.2.1.4 setShowInNewForm

**Return Type:** None

Sets this field to show or hide in the new form.

**Parameters:**

*value*: A Boolean value that indicates whether this field is shown in the new form.

Type: **CSOM Boolean**

**3.2.5.43.2.1.5 Update**

**Return Type:** None

Commits changed properties of the **field (2)**.

**Parameters:** None

**Exceptions:**

Error Code	Error Type Name	Condition
- 2130246331	Microsoft.SharePoint.SPException	Type of the field (2) is changed for an <b>indexed field</b> . The field type of indexed fields cannot be changed.
- 2130246238	Microsoft.SharePoint.SPException	Field (2) is set to not be an indexed field, and <b>EnforceUniqueValues</b> is "true".
- 2130246236	Microsoft.SharePoint.SPException	Type of the field (2) is being changed and <b>EnforceUniqueValues</b> of the field (2) is "true".

**3.2.5.43.2.1.6 UpdateAndPushChanges**

**Return Type:** None

Commits changed properties of the **field (2)** and propagates changes to all **lists** that use the field (2).

**Parameters:**

*pushChangesToLists*: Specifies whether to propagate changes to all lists that use the field (2).

Type: **CSOM Boolean**

**Exceptions:**

Error Code	Error Type Name	Condition
- 2130246331	Microsoft.SharePoint.SPException	Type of the field (2) is changed for an <b>indexed field</b> . The field type of indexed fields cannot be changed.
- 2130246238	Microsoft.SharePoint.SPException	Field (2) is set to not be an indexed field, and <b>EnforceUniqueValues</b> is "true".
- 2130246236	Microsoft.SharePoint.SPException	Type of the field (2) is being changed and <b>EnforceUniqueValues</b> of the field (2) is "true".

**3.2.5.43.2.1.7 ValidateSetValue**

**Return Type:** None

Validates and sets the value of the **field (2)** for the **list item** based on an implementation-specific transformation of the value. <15>

**Parameters:**

*item*: Specifies the list item to be updated with the new value.

Type: Microsoft.SharePoint.Client.ListItem

It MUST NOT be NULL.

*value*: Specifies the new value for the field (2).

Type: **CSOM String**

### 3.2.5.43.2.2 ObjectPath Methods

None.

### 3.2.5.44 Microsoft.SharePoint.Client.FieldDateTime

**TypeId**: {4F9DC9B4-D900-40EB-94B9-008ABBFB22E1}

**ShortName**: SP.FieldDateTime

Specifies a **field (2)** that contains date and time values. To set properties, call the **Update** method (section [3.2.5.44.2.1.5](#)).

The NoCrawl and SchemaXmlWithResourceTokens properties are not included in the **default scalar property set** for this type.

#### 3.2.5.44.1 Properties

##### 3.2.5.44.1.1 Scalar Properties

###### 3.2.5.44.1.1.1 CanBeDeleted

Type: **CSOM Boolean**

**Accessibility**: Read Only

See **Microsoft.SharePoint.Client.Field.CanBeDeleted**, as specified in section [3.2.5.37.1.1.1](#).

###### 3.2.5.44.1.1.2 DateTimeCalendarType

Type: Microsoft.SharePoint.Client.CalendarType

**Accessibility**: Read/Write

Specifies the **calendar type** of the **field (2)**.

It MUST be None if the field (2) is in an **external list**.

###### 3.2.5.44.1.1.3 DefaultValue

Type: **CSOM String**

**Accessibility**: Read/Write

See **Microsoft.SharePoint.Client.Field.DefaultValue**, as specified in section [3.2.5.37.1.1.2](#).

**Exceptions:**

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed, and the <b>list</b> is an <b>external list</b> .

**3.2.5.44.1.1.4 Description****Type:** CSOM String**Accessibility:** Read/WriteSee **Microsoft.SharePoint.Client.Field.Description**, as specified in section [3.2.5.37.1.1.3](#).**3.2.5.44.1.1.5 Direction****Type:** CSOM String**Accessibility:** Read/WriteSee **Microsoft.SharePoint.Client.Field.Direction**, as specified in section [3.2.5.37.1.1.4](#).**Exceptions:**

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed to a value other than "none," and the <b>list</b> is an <b>external list</b> .

**3.2.5.44.1.1.6 DisplayFormat****Type:** Microsoft.SharePoint.Client.DateTimeFieldFormatType**Accessibility:** Read/WriteSpecifies the type of date and time format that is used in the **field (2)**.**3.2.5.44.1.1.7 EnforceUniqueValues****Type:** CSOM Boolean**Accessibility:** Read/WriteSee **Microsoft.SharePoint.Client.Field.EnforceUniqueValues**, as specified in section [3.2.5.37.1.1.5](#)**Exceptions:**

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Adding <b>unique column constraints</b> to the <b>field (2)</b> where the

Error Code	Error Type Name	Condition
		<b>list</b> is an <b>external list</b> .

### 3.2.5.44.1.1.8 FieldTypeKind

**Type:** Microsoft.SharePoint.Client.FieldType

**Accessibility:** Read/Write

See **Microsoft.SharePoint.Client.Field.FieldTypeKind**, as specified in section [3.2.5.37.1.1.6](#).

**Exceptions:**

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed, and the <b>list</b> is an <b>external list</b> .

### 3.2.5.44.1.1.9 Filterable

**Type:** CSOM Boolean

**Accessibility:** Read Only

See **Microsoft.SharePoint.Client.Field.Filterable**, as specified in section [3.2.5.37.1.1.7](#).

### 3.2.5.44.1.1.10 FromBaseType

**Type:** CSOM Boolean

**Accessibility:** Read Only

Gets a **Boolean** value that indicates whether the **field (2)** derives from a **base field type**.

### 3.2.5.44.1.1.11 Group

**Type:** CSOM String

**Accessibility:** Read/Write

See **Microsoft.SharePoint.Client.Field.Group**, as specified in section [3.2.5.37.1.1.9](#).

It MUST NOT be NULL. It MUST NOT be empty. Its length MUST be equal to or less than 128.

**Exceptions:**

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed, and the <b>list</b> is an <b>external list</b> .

### 3.2.5.44.1.1.12 Hidden

Type: **CSOM Boolean**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.Hidden**, as specified in section [3.2.5.37.1.1.10](#).

### 3.2.5.44.1.1.13 Id

Type: **CSOM GUID**

Accessibility: Read Only

See **Microsoft.SharePoint.Client.Field.Id**, as specified in section [3.2.5.37.1.1.11](#).

### 3.2.5.44.1.1.14 InternalName

Type: **CSOM String**

Accessibility: Read Only

See **Microsoft.SharePoint.Client.Field.InternalName**, as specified in section [3.2.5.37.1.1.12](#).

It MUST NOT be NULL. It MUST NOT be empty.

### 3.2.5.44.1.1.15 ReadOnlyField

Type: **CSOM Boolean**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.ReadOnlyField**, as specified in section [3.2.5.37.1.1.13](#).

Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed, and the <b>list</b> is an <b>external list</b> .

### 3.2.5.44.1.1.16 Required

Type: **CSOM Boolean**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.Required**, as specified in section [3.2.5.37.1.1.14](#).

Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is set to "true", and the <b>list</b> is an <b>external list</b> .

### 3.2.5.44.1.1.17 SchemaXml

Type: **CSOM String**



**Accessibility:** Read/Write

See **Microsoft.SharePoint.Client.Field.SchemaXml**, as specified in section [3.2.5.37.1.1.15](#).

It MUST be NULL, empty, or an **XML fragment** that conforms to the **FieldDefinition** type as defined in [\[MS-WSSFO2\]](#) section 2.2.8.3.3 or [\[MS-WSSFO3\]](#) section 2.2.7.3.3.

**Exceptions:**

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed to a non-NULL or non-empty value, and the <b>list</b> is an <b>external list</b> .

**3.2.5.44.1.1.18 Scope**

**Type:** **CSOM String**

**Accessibility:** Read Only

See **Microsoft.SharePoint.Client.Field.Scope**, as specified in section [3.2.5.37.1.1.16](#).

**3.2.5.44.1.1.19 Sealed**

**Type:** **CSOM Boolean**

**Accessibility:** Read/Write

See **Microsoft.SharePoint.Client.Field.Sealed**, as specified in section [3.2.5.37.1.1.17](#).

**3.2.5.44.1.1.20 Sortable**

**Type:** **CSOM Boolean**

**Accessibility:** Read Only

See **Microsoft.SharePoint.Client.Field.Sortable**, as specified in section [3.2.5.37.1.1.18](#).

**3.2.5.44.1.1.21 StaticName**

**Type:** **CSOM String**

**Accessibility:** Read/Write

See **Microsoft.SharePoint.Client.Field.StaticName**, as specified in section [3.2.5.37.1.1.19](#).

**Exceptions:**

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed, and the <b>list</b> is an <b>external list</b> .

**3.2.5.44.1.1.22 Title**

**Type:** **CSOM String**

**Accessibility:** Read/Write

See **Microsoft.SharePoint.Client.Field.Title**, as specified in section [3.2.5.37.1.1.20](#)

### 3.2.5.44.1.1.23 TypeAsString

**Type:** CSOM String

**Accessibility:** Read/Write

See **Microsoft.SharePoint.Client.Field.TypeAsString**, as specified in section [3.2.5.37.1.1.21](#).

It MUST NOT be NULL. It MUST NOT be empty.

**Exceptions:**

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed, and the <b>list</b> is an <b>external list</b> .

### 3.2.5.44.1.1.24 TypeDisplayName

**Type:** CSOM String

**Accessibility:** Read Only

Specifies the display name of the **field (2)** type.

It MUST NOT be NULL. It MUST NOT be empty.

### 3.2.5.44.1.1.25 TypeShortDescription

**Type:** CSOM String

**Accessibility:** Read Only

See **Microsoft.SharePoint.Client.Field.TypeShortDescription**, as specified in section [3.2.5.37.1.1.23](#).

It MUST NOT be NULL. It MUST NOT be empty.

### 3.2.5.44.1.1.26 ValidationFormula

**Type:** CSOM String

**Accessibility:** Read/Write

See **Microsoft.SharePoint.Client.Field.ValidationFormula**, as specified in section [3.2.5.37.1.1.24](#)

### 3.2.5.44.1.1.27 ValidationMessage

**Type:** CSOM String

**Accessibility:** Read/Write

See **Microsoft.SharePoint.Client.Field.ValidationMessage**, as specified in section [3.2.5.37.1.1.25](#).

Its length MUST be equal to or less than 1024.

### 3.2.5.44.1.1.28 FriendlyDisplayFormat

**Type:** Microsoft.SharePoint.Client.DateTimeFieldFriendlyFormatType

**Accessibility:** Read/Write

Gets or sets the type of friendly display format that is used in the **field**.<16>

### 3.2.5.44.1.1.29 JSLink

**Type:** CSOM String

**Accessibility:** Read/Write

Gets the name of an external ECMAScript ([\[ECMA-262-1999\]](#)) file containing any logic for this **field (2)**.

### 3.2.5.44.1.1.30 EntityPropertyName

**Type:** CSOM String

**Accessibility:** Read Only

Gets the name of the entity property of this **field (2)** in the **list item** entity that uses this field (2). It MUST NOT be NULL. It MUST NOT be empty.

### 3.2.5.44.1.1.31 Indexed

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Gets or sets a Boolean value that specifies whether the field is indexed.

### 3.2.5.44.1.1.32 SchemaXmlWithResourceTokens

**Type:** CSOM String

**Accessibility:** Read Only

Gets the unlocalized schema XML for this **field (2)**.

### 3.2.5.44.1.1.33 AutoIndexed

**Type:** CSOM Boolean

**Accessibility:** Read Only

Gets the Boolean value that specifies whether or not the field is auto-indexed. Specify a value of true if the field is auto-indexed; false if otherwise.

### 3.2.5.44.1.1.34 ClientSideComponentId

**Type:** CSOM GUID

**Accessibility:** Read/Write

The unique identifier of the client-side component defined with SharePoint Framework.

### 3.2.5.44.1.1.35 ClientSideComponentProperties

**Type:** CSOM String

**Accessibility:** Read/Write

This property is only used when a **ClientSideComponentId** is specified. It is optional. If non-empty, the string **MUST** contain a JSON object with custom initialization properties whose format and meaning are defined by the client-side component.

### 3.2.5.44.1.1.36 CustomFormatter

**Type:** CSOM String

**Accessibility:** Read/Write

A JSON string representing the custom rendering format of the field.

### 3.2.5.44.1.1.37 DefaultFormula

**Type:** CSOM String

**Accessibility:** Read/Write

Gets or sets the default formula for a calculated field.

### 3.2.5.44.1.1.38 NoCrawl

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Gets or sets a Boolean value that specifies whether the field can be crawled by a search engine.

### 3.2.5.44.1.1.39 PinnedToFiltersPane

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Boolean value that indicates whether the field pins to filter pane.

### 3.2.5.44.1.1.40 ShowInFiltersPane

**Type:** Microsoft.SharePoint.Client.ShowInFiltersPaneStatus

**Accessibility:** Read/Write

Indicates whether the field will be shown.

## 3.2.5.44.1.2 ObjectPath Properties

### 3.2.5.44.1.2.1 DescriptionResource

**Type:** Microsoft.SharePoint.Client.UserResource

**Accessibility:** Read Only

Gets the resource object corresponding to the **Description** property for a field.

### 3.2.5.44.1.2.2 TitleResource

**Type:** Microsoft.SharePoint.Client.UserResource

**Accessibility:** Read Only

Gets the resource object corresponding to the **Title** property for a field.

### 3.2.5.44.2 Methods

#### 3.2.5.44.2.1 Scalar Methods

##### 3.2.5.44.2.1.1 DeleteObject

**Return Type:** None

Deletes the **field (2)** from the **list**, from the **site (2)**, or from the **content types** within the list.

**Parameters:** None

**Exceptions:**

Error Code	Error Type Name	Condition
-1	System.InvalidOperationException	<b>CanBeDeleted</b> is "false".

##### 3.2.5.44.2.1.2 setShowInDisplayForm

**Return Type:** None

Sets this field to show or hide in the display form.

**Parameters:**

*value:* A Boolean value that indicates whether this field is shown in the display form.

Type: **CSOM Boolean**

##### 3.2.5.44.2.1.3 setShowInEditForm

**Return Type:** None

Sets this field to show or hide in the edit form.

**Parameters:**

*value:* A Boolean value that indicates whether this field is shown in the edit form.

Type: **CSOM Boolean**

##### 3.2.5.44.2.1.4 setShowInNewForm

**Return Type:** None

Sets this field to show or hide in the new form.

**Parameters:**

*value*: A Boolean value that indicates whether this field is shown in the new form.

Type: **CSOM Boolean**

### 3.2.5.44.2.1.5 Update

**Return Type:** None

Commits changed properties of the **field (2)**.

**Parameters:** None

**Exceptions:**

Error Code	Error Type Name	Condition
- 2130246331	Microsoft.SharePoint.SPException	Type of the field (2) is changed for an <b>indexed field</b> . The field type of indexed fields cannot be changed.
- 2130246238	Microsoft.SharePoint.SPException	Field (2) is set to not be an indexed field, and <b>EnforceUniqueValues</b> is "true".
- 2130246236	Microsoft.SharePoint.SPException	Type of the field (2) is being changed and <b>EnforceUniqueValues</b> of the field (2) is "true".

### 3.2.5.44.2.1.6 UpdateAndPushChanges

**Return Type:** None

Commits changed properties of the **field (2)** and propagates changes to all **lists** that use the field (2).

**Parameters:**

*pushChangesToLists*: Specifies whether to propagate changes to all lists that use the field (2).

Type: **CSOM Boolean**

**Exceptions:**

Error Code	Error Type Name	Condition
- 2130246331	Microsoft.SharePoint.SPException	Type of the field (2) is changed for an <b>indexed field</b> . The field type of indexed fields cannot be changed.
- 2130246238	Microsoft.SharePoint.SPException	Field (2) is set to not be an indexed field, and <b>EnforceUniqueValues</b> is "true".
- 2130246236	Microsoft.SharePoint.SPException	Type of the field (2) is being changed and <b>EnforceUniqueValues</b> of the field (2) is "true".

### 3.2.5.44.2.1.7 ValidateSetValue

**Return Type:** None

Validates and sets the value of the **field (2)** for the **list item** based on an implementation-specific transformation of the value. [<17>](#)

**Parameters:**

*item*: Specifies the list item to be updated with the new value.

Type: Microsoft.SharePoint.Client.ListItem

It MUST NOT be NULL.

*value*: Specifies the new value for the field (2).

Type: **CSOM String**

**3.2.5.44.2.2 ObjectPath Methods**

None.

**3.2.5.45 Microsoft.SharePoint.Client.FieldGuid**

**TypeId**: {768B27AA-A4E0-4CFB-9956-1F7F0E93FB42}

**ShortName**: SP.FieldGuid

Specifies a **field (2)** that contains global unique identifier (GUID) values.

The NoCrawl and SchemaXmlWithResourceTokens properties are not included in the **default scalar property set** for this type.

**3.2.5.45.1 Properties**

**3.2.5.45.1.1 Scalar Properties**

**3.2.5.45.1.1.1 CanBeDeleted**

Type: **CSOM Boolean**

**Accessibility**: Read Only

See **Microsoft.SharePoint.Client.Field.CanBeDeleted**, as specified in section [3.2.5.37.1.1.1](#).

**3.2.5.45.1.1.2 DefaultValue**

Type: **CSOM String**

**Accessibility**: Read/Write

See **Microsoft.SharePoint.Client.Field.DefaultValue**, as specified in section [3.2.5.37.1.1.2](#).

**Exceptions:**

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed, and the <b>list</b> is an <b>external list</b> .

**3.2.5.45.1.1.3 Description**

Type: **CSOM String**

**Accessibility:** Read/Write

See **Microsoft.SharePoint.Client.Field.Description**, as specified in section [3.2.5.37.1.1.3](#).

#### 3.2.5.45.1.1.4 Direction

**Type:** CSOM String

**Accessibility:** Read/Write

See **Microsoft.SharePoint.Client.Field.Direction**, as specified in section [3.2.5.37.1.1.4](#).

**Exceptions:**

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed to a value other than "none," and the <b>list</b> is an <b>external list</b> .

#### 3.2.5.45.1.1.5 EnforceUniqueValues

**Type:** CSOM Boolean

**Accessibility:** Read/Write

See **Microsoft.SharePoint.Client.Field.EnforceUniqueValues**, as specified in section [3.2.5.37.1.1.5](#)

**Exceptions:**

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Adding <b>unique column constraints</b> to the <b>field (2)</b> where the <b>list</b> is an <b>external list</b> .

#### 3.2.5.45.1.1.6 FieldTypeKind

**Type:** Microsoft.SharePoint.Client.FieldType

**Accessibility:** Read/Write

See **Microsoft.SharePoint.Client.Field.FieldTypeKind**, as specified in section [3.2.5.37.1.1.6](#).

**Exceptions:**

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed, and the <b>list</b> is an <b>external list</b> .



### 3.2.5.45.1.1.7 Filterable

Type: **CSOM Boolean**

Accessibility: Read Only

See **Microsoft.SharePoint.Client.Field.Filterable**, as specified section [3.2.5.37.1.1.7](#).

### 3.2.5.45.1.1.8 FromBaseType

Type: **CSOM Boolean**

Accessibility: Read Only

Gets a **Boolean** value that indicates whether the **field (2)** derives from a **base field type**.

### 3.2.5.45.1.1.9 Group

Type: **CSOM String**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.Group**, as specified in section [3.2.5.37.1.1.9](#).

It MUST NOT be NULL. It MUST NOT be empty. Its length MUST be equal to or less than 128.

#### Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed, and the <b>list</b> is an <b>external list</b> .

### 3.2.5.45.1.1.10 Hidden

Type: **CSOM Boolean**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.Hidden**, as specified in section [3.2.5.37.1.1.10](#).

### 3.2.5.45.1.1.11 Id

Type: **CSOM GUID**

Accessibility: Read Only

See **Microsoft.SharePoint.Client.Field.Id**, as specified in section [3.2.5.37.1.1.11](#).

### 3.2.5.45.1.1.12 InternalName

Type: **CSOM String**

Accessibility: Read Only

See **Microsoft.SharePoint.Client.Field.InternalName**, as specified in section [3.2.5.37.1.1.12](#).

It MUST NOT be NULL. It MUST NOT be empty.

### 3.2.5.45.1.1.13 ReadOnlyField

Type: **CSOM Boolean**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.ReadOnlyField**, as specified in section [3.2.5.37.1.1.13](#).

#### Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed, and the <b>list</b> is an <b>external list</b> .

### 3.2.5.45.1.1.14 Required

Type: **CSOM Boolean**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.Required**, as specified in section [3.2.5.37.1.1.14](#).

#### Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is set to "true", and the <b>list</b> is an <b>external list</b> .

### 3.2.5.45.1.1.15 SchemaXml

Type: **CSOM String**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.SchemaXml**, as specified in section [3.2.5.37.1.1.15](#).

It MUST be an XML document that conforms to the **FieldDefinition** type, as specified in [\[MS-WSSFO2\]](#) section 2.2.8.3.3 or [\[MS-WSSFO3\]](#) section 2.2.7.3.3, or a **string** that is NULL or empty.

#### Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed to a non-NULL or non-empty value, and the <b>list</b> is an <b>external list</b> .

### 3.2.5.45.1.1.16 Scope

Type: **CSOM String**

Accessibility: Read Only

See **Microsoft.SharePoint.Client.Field.Scope**, as specified in section [3.2.5.37.1.1.16](#).

### 3.2.5.45.1.1.17 Sealed

Type: **CSOM Boolean**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.Sealed**, as specified in section [3.2.5.37.1.1.17](#).

### 3.2.5.45.1.1.18 Sortable

Type: **CSOM Boolean**

Accessibility: Read Only

See **Microsoft.SharePoint.Client.Field.Sortable**, as specified in section [3.2.5.37.1.1.18](#).

### 3.2.5.45.1.1.19 StaticName

Type: **CSOM String**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.StaticName**, as specified in section [3.2.5.37.1.1.19](#).

Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed, and the <b>list</b> is an <b>external list</b> .

### 3.2.5.45.1.1.20 Title

Type: **CSOM String**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.Title**, as specified in section [3.2.5.37.1.1.20](#).

### 3.2.5.45.1.1.21 TypeAsString

Type: **CSOM String**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.TypeAsString**, as specified in section [3.2.5.37.1.1.21](#).

It MUST NOT be NULL. It MUST NOT be empty.

Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed, and the <b>list</b> is an <b>external list</b> .

### 3.2.5.45.1.1.22 TypeDisplayName

**Type:** CSOM String

**Accessibility:** Read Only

Specifies the display name for **FieldTypeKind** of the **field (2)**.

It MUST NOT be NULL. It MUST NOT be empty.

### **3.2.5.45.1.1.23      TypeShortDescription**

**Type:** CSOM String

**Accessibility:** Read Only

See **Microsoft.SharePoint.Client.Field.TypeShortDescription**, as specified in section [3.2.5.37.1.1.23](#).

It MUST NOT be NULL. It MUST NOT be empty.

### **3.2.5.45.1.1.24      ValidationFormula**

**Type:** CSOM String

**Accessibility:** Read/Write

See **Microsoft.SharePoint.Client.Field.ValidationFormula**, as specified in section [3.2.5.37.1.1.24](#).

### **3.2.5.45.1.1.25      ValidationMessage**

**Type:** CSOM String

**Accessibility:** Read/Write

See **Microsoft.SharePoint.Client.Field.ValidationMessage**, as specified in section [3.2.5.37.1.1.25](#).

Its length MUST be equal to or less than 1024.

### **3.2.5.45.1.1.26      JSLink**

**Type:** CSOM String

**Accessibility:** Read/Write

Gets the name of an external ECMAScript ([\[ECMA-262-1999\]](#)) file containing any logic for this **field (2)**.

### **3.2.5.45.1.1.27      EntityPropertyName**

**Type:** CSOM String

**Accessibility:** Read Only

Gets the name of the entity property of this **field (2)** in the **list item** entity that uses this field (2).

It MUST NOT be NULL. It MUST NOT be empty.

### **3.2.5.45.1.1.28      Indexed**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Gets or sets a Boolean value that specifies whether the field is indexed.

### **3.2.5.45.1.1.29      SchemaXmlWithResourceTokens**

**Type:** CSOM String

**Accessibility:** Read Only

Gets the unlocalized schema XML for this **field (2)**.

### **3.2.5.45.1.1.30      AutoIndexed**

**Type:** CSOM Boolean

**Accessibility:** Read Only

Gets the Boolean value that specifies whether or not the field is auto-indexed. Specify a value of true if the field is auto-indexed; false if otherwise.

### **3.2.5.45.1.1.31      ClientSideComponentId**

**Type:** CSOM GUID

**Accessibility:** Read/Write

The unique identifier of the client-side component defined with SharePoint Framework.

### **3.2.5.45.1.1.32      ClientSideComponentProperties**

**Type:** CSOM String

**Accessibility:** Read/Write

This property is only used when a **ClientSideComponentId** is specified. It is optional. If non-empty, the string MUST contain a JSON object with custom initialization properties whose format and meaning are defined by the client-side component.

### **3.2.5.45.1.1.33      CustomFormatter**

**Type:** CSOM String

**Accessibility:** Read/Write

A JSON string representing the custom rendering format of the field.

### **3.2.5.45.1.1.34      DefaultFormula**

**Type:** CSOM String

**Accessibility:** Read/Write

Gets or sets the default formula for a calculated field.

### **3.2.5.45.1.1.35      NoCrawl**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Gets or sets a Boolean value that specifies whether the field can be crawled by a search engine.

### 3.2.5.45.1.1.36 PinnedToFiltersPane

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Boolean value that indicates whether the field pins to filter pane.

### 3.2.5.45.1.1.37 ShowInFiltersPane

**Type:** Microsoft.SharePoint.Client.ShowInFiltersPaneStatus

**Accessibility:** Read/Write

Indicates whether the field will be shown.

## 3.2.5.45.1.2 ObjectPath Properties

### 3.2.5.45.1.2.1 DescriptionResource

**Type:** Microsoft.SharePoint.Client.UserResource

**Accessibility:** Read Only

Gets the resource object corresponding to the **Description** property for a field.

### 3.2.5.45.1.2.2 TitleResource

**Type:** Microsoft.SharePoint.Client.UserResource

**Accessibility:** Read Only

Gets the resource object corresponding to the **Title** property for a field.

## 3.2.5.45.2 Methods

### 3.2.5.45.2.1 Scalar Methods

#### 3.2.5.45.2.1.1 DeleteObject

**Return Type:** None

Deletes the **field (2)** from the **list**, from the **site (2)**, or from the **content types** within the list.

**Parameters:** None

**Exceptions:**

Error Code	Error Type Name	Condition
-1	System.InvalidOperationException	The field (2) cannot be deleted because it does not allow deletion.

#### 3.2.5.45.2.1.2 SetShowInDisplayForm

**Return Type:** None

Sets this field to show or hide in the display form.

**Parameters:**

*value*: A Boolean value that indicates whether this field is shown in the display form.

Type: **CSOM Boolean**

**3.2.5.45.2.1.3 SetShowInEditForm**

**Return Type:** None

Sets this field to show or hide in the edit form.

**Parameters:**

*value*: A Boolean value that indicates whether this field is shown in the edit form.

Type: **CSOM Boolean**

**3.2.5.45.2.1.4 SetShowInNewForm**

**Return Type:** None

Sets this field to show or hide in the new form.

**Parameters:**

*value*: A Boolean value that indicates whether this field is shown in the new form.

Type: **CSOM Boolean**

**3.2.5.45.2.1.5 Update**

**Return Type:** None

Commits changed properties of the **field (2)**.

**Parameters:** None

**Exceptions:**

Error Code	Error Type Name	Condition
- 2130246331	Microsoft.SharePoint.SPException	Changing the type of a field (2) that is being indexed or is already indexed is not allowed.
- 2130246238	Microsoft.SharePoint.SPException	Removing an index from a field (2) that does not allow duplicate values.
- 2130246236	Microsoft.SharePoint.SPException	Changing the type of a field (2) that does not allow duplicate values.

**3.2.5.45.2.1.6 UpdateAndPushChanges**

**Return Type:** None

Commits changed properties of the **field (2)** and propagates changes to all **lists** that use the field (2).

**Parameters:**

*pushChangesToLists*: Specifies whether to propagate changes to all lists that use the field (2).

Type: **CSOM Boolean**

**Exceptions:**

Error Code	Error Type Name	Condition
- 2130246331	Microsoft.SharePoint.SPException	Changing the type of a field (2) that is being indexed or is already indexed is not allowed.
- 2130246238	Microsoft.SharePoint.SPException	Removing an index from a field (2) that does not allow duplicate values.
- 2130246236	Microsoft.SharePoint.SPException	Changing the type of a field (2) that does not allow duplicate values.

**3.2.5.45.2.1.7 ValidateSetValue**

**Return Type:** None

Validates and sets the value of the **field (2)** for the **list item** based on an implementation-specific transformation of the value. <18>

**Parameters:**

*item*: Specifies the list item to be updated with the new value.

Type: Microsoft.SharePoint.Client.ListItem

It MUST NOT be NULL.

*value*: Specifies the new value for the field (2).

Type: **CSOM String**

**3.2.5.45.2.2 ObjectPath Methods**

None.

**3.2.5.46 Microsoft.SharePoint.Client.FieldLink**

**TypeId:** {E2D99203-868F-4211-AC76-F6BCA0FF94EE}

**ShortName:** SP.FieldLink

Specifies a **reference** to a **field (2)** or **field definition** for a **content type**.

The DisplayName, ReadOnly and ShowInDisplayForm properties are not included in the **default scalar property set** for this type.

**3.2.5.46.1 Properties****3.2.5.46.1.1 Scalar Properties****3.2.5.46.1.1.1 Hidden**



**Type:** CSOM Boolean

**Accessibility:** Read/Write

Specifies whether the **field (2)** corresponding to this **field link** is available in New/Edit **list forms**.

#### **3.2.5.46.1.1.2 Id**

**Type:** CSOM GUID

**Accessibility:** Read Only

Specifies the **GUID** identifier of the **field link**. The value of this property is identical to the value of the **Id** property of the **field (2)** or **field definition** that is being referenced.

It MUST NOT be an empty GUID.

#### **3.2.5.46.1.1.3 Name**

**Type:** CSOM String

**Accessibility:** Read Only

Specifies the name of the **field link**.

It MUST be less than or equal to 256 characters.

It MUST NOT be NULL.

#### **3.2.5.46.1.1.4 Required**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Specifies whether the **field (2)** requires a value. If the field (2) requires a value, this value MUST be set to "true". Otherwise, it MUST be set to "false".

#### **3.2.5.46.1.1.5 FieldInternalName**

**Type:** CSOM String

**Accessibility:** Read Only

Specifies the internal name of the **field (2)**.<19>

#### **3.2.5.46.1.1.6 DisplayName**

**Type:** CSOM String

**Accessibility:** Read/Write

Gets or sets the display name for the field reference.

#### **3.2.5.46.1.1.7 ReadOnly**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Gets and sets a value that indicates whether the **SP.FieldLink** object can be modified.

### 3.2.5.46.1.1.8 ShowInDisplayForm

Type: **CSOM Boolean**

Accessibility: Read/Write

Gets or sets a Boolean value that specifies whether the field reference is displayed in the form or displaying list items.

### 3.2.5.46.1.2 ObjectPath Properties

None.

### 3.2.5.46.2 Methods

#### 3.2.5.46.2.1 Scalar Methods

##### 3.2.5.46.2.1.1 DeleteObject

Return Type: None

Deletes this **field link** from the collection of the parent **content type**.

Parameters: None

#### 3.2.5.46.2.2 ObjectPath Methods

None.

### 3.2.5.47 Microsoft.SharePoint.Client.FieldLinkCollection

TypeId: {6D87E76A-B8A8-4634-8170-082B1D454BFD}

ShortName: SP.FieldLinkCollection

Specifies a Collection for **field links**.

#### 3.2.5.47.1 Properties

##### 3.2.5.47.1.1 Scalar Properties

None.

##### 3.2.5.47.1.2 ObjectPath Properties

None.

#### 3.2.5.47.2 Methods

##### 3.2.5.47.2.1 Scalar Methods

##### 3.2.5.47.2.1.1 Reorder

Return Type: None

Rearranges the collection of **field links** in the order in which **field internal names** are specified.

Parameters:

*internalNames*: Specifies field internal names that are arranged in the order in which the collection of field links is reordered.

Type: **CSOM array** of **CSOM String**

### 3.2.5.47.2.2 ObjectPath Methods

#### 3.2.5.47.2.2.1 Add

**Return Type:** Microsoft.SharePoint.Client.FieldLink

Add a **field link** with the specified link information to the collection. A **reference** to the SP.Field that was added is returned.

**Parameters:**

*parameters*: Specifies the field link information of the field link to be added to the collection.

Type: Microsoft.SharePoint.Client.FieldLinkCreationInformation

It MUST NOT be NULL.

#### 3.2.5.47.2.2.2 GetById

**Return Type:** Microsoft.SharePoint.Client.FieldLink

Gets the **field link** with the given *id* from this collection. [<20>](#) If the *id* is not found in the collection, returns **null**.

**Parameters:**

*id*: The GUID that specifies the **Microsoft.SharePoint.Client.FieldLink** (section [3.2.5.46](#)) that is returned.

Type: **CSOM GUID**

### 3.2.5.48 Microsoft.SharePoint.Client.FieldLinkCreationInformation

**TypeId:** {63FB2C92-8F65-4BBB-A658-B6CD294403F4}

**ShortName:** SP.FieldLinkCreationInformation

Contains properties that are used as parameters to initialize an **SP.FieldLink** object (section [3.2.5.46](#)).

#### 3.2.5.48.1 Properties

##### 3.2.5.48.1.1 Scalar Properties

None.

##### 3.2.5.48.1.2 ObjectPath Properties

###### 3.2.5.48.1.2.1 Field

**Type:** Microsoft.SharePoint.Client.Field

**Accessibility:** Read/Write

The Field information of the FieldLink to be created.

It MUST NOT be NULL.

### 3.2.5.49 Microsoft.SharePoint.Client.FieldLookup

**TypeId:** {EE47FF61-3260-43A9-BE22-829A1FA85B44}

**ShortName:** SP.FieldLookup

Represents a **lookup field**. The field value for this class is contained in **FieldLookupValue** (section [3.2.5.50](#)).

The NoCrawl and SchemaXmlWithResourceTokens properties are not included in the **default scalar property set** for this type.

#### 3.2.5.49.1 Properties

##### 3.2.5.49.1.1 Scalar Properties

###### 3.2.5.49.1.1.1 AllowMultipleValues

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Specifies whether the **lookup field** allows multiple values.

###### 3.2.5.49.1.1.2 CanBeDeleted

**Type:** CSOM Boolean

**Accessibility:** Read Only

See **Microsoft.SharePoint.Client.Field.CanBeDeleted**, as specified in section [3.2.5.37.1.1.1](#).

###### 3.2.5.49.1.1.3 DefaultValue

**Type:** CSOM String

**Accessibility:** Read/Write

See **Microsoft.SharePoint.Client.Field.DefaultValue**, as specified in section [3.2.5.37.1.1.2](#).

#### Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed, and the <b>list</b> is an <b>external list</b> .

###### 3.2.5.49.1.1.4 Description

**Type:** CSOM String

**Accessibility:** Read/Write

See **Microsoft.SharePoint.Client.Field.Description**, as specified in section [3.2.5.37.1.1.3](#).

### 3.2.5.49.1.1.5 Direction

Type: **CSOM String**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.Direction**, as specified in section [3.2.5.37.1.1.4](#).

#### Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed to a value other than "none," and the <b>list</b> is an <b>external list</b> .

### 3.2.5.49.1.1.6 EnforceUniqueValues

Type: **CSOM Boolean**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.EnforceUniqueValues**, as specified in section [3.2.5.37.1.1.5](#)

#### Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Adding <b>unique column constraints</b> to the <b>field (2)</b> where the <b>list</b> is an <b>external list</b> .

### 3.2.5.49.1.1.7 FieldTypeKind

Type: Microsoft.SharePoint.Client.FieldType

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.FieldTypeKind**, as specified in section [3.2.5.37.1.1.6](#).

#### Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed, and the <b>list</b> is an <b>external list</b> .

### 3.2.5.49.1.1.8 Filterable

Type: **CSOM Boolean**

Accessibility: Read Only

See **Microsoft.SharePoint.Client.Field.Filterable**, as specified in section [3.2.5.37.1.1.7](#).

### 3.2.5.49.1.1.9 FromBaseType

Type: **CSOM Boolean**

Accessibility: Read Only

Gets a **Boolean** value that indicates whether the **field (2)** derives from a **base field type**.

### 3.2.5.49.1.1.10 Group

Type: **CSOM String**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.Group**, as specified in section [3.2.5.37.1.1.9](#).

It MUST NOT be NULL. It MUST NOT be empty. Its length MUST be equal to or less than 128.

Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed, and the <b>list</b> is an <b>external list</b> .

### 3.2.5.49.1.1.11 Hidden

Type: **CSOM Boolean**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.Hidden**, as specified in section [3.2.5.37.1.1.10](#).

### 3.2.5.49.1.1.12 Id

Type: **CSOM GUID**

Accessibility: Read Only

See **Microsoft.SharePoint.Client.Field.Id**, as specified in section [3.2.5.37.1.1.11](#).

### 3.2.5.49.1.1.13 InternalName

Type: **CSOM String**

Accessibility: Read Only

See **Microsoft.SharePoint.Client.Field.InternalName**, as specified in section [3.2.5.37.1.1.12](#).

It MUST NOT be NULL. It MUST NOT be empty.

### 3.2.5.49.1.1.14 IsRelationship

Type: **CSOM Boolean**

Accessibility: Read/Write

Specifies whether the **lookup field** is a **relationship lookup field**. It determines whether this lookup field is returned by **Microsoft.SharePoint.Client.List.GetRelatedField**.

**Exceptions:**

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	The <b>list</b> that the <b>field (2)</b> belongs to is an <b>external list</b> .

### 3.2.5.49.1.1.15 LookupField

Type: **CSOM String**

Accessibility: Read/Write

Specifies the internal name of the **field (2)** in the target **list**, used to display lookup values.

**Exceptions:**

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	The list that this field (2) belongs to is an <b>external list</b> .

### 3.2.5.49.1.1.16 LookupList

Type: **CSOM String**

Accessibility: Read/Write

Specifies the **list identifier** of the target **list** that contains the **lookup field**.

**Exceptions:**

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	The list that this <b>field (2)</b> belongs to is an <b>external list</b> .

### 3.2.5.49.1.1.17 LookupWebId

Type: **CSOM GUID**

Accessibility: Read/Write

Specifies the GUID that identifies the **site (2)** containing the **list** that contains the **field (2)** used as the lookup values.

**Exceptions:**

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	The list that this field (2) belongs to is an <b>external list</b> .

### 3.2.5.49.1.1.18 PrimaryFieldId

Type: **CSOM String**

Accessibility: Read/Write

Specifies the **primary lookup field** identifier if this is a **dependent lookup field**. Otherwise, it is an empty string.

#### Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	When the <b>list</b> that this <b>field (2)</b> belongs to is an <b>external list</b> .

### 3.2.5.49.1.1.19 ReadOnlyField

Type: **CSOM Boolean**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.ReadOnlyField**, as specified in section [3.2.5.37.1.1.13](#).

#### Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed, and the <b>list</b> is an <b>external list</b> .

### 3.2.5.49.1.1.20 RelationshipDeleteBehavior

Type: Microsoft.SharePoint.Client.RelationshipDeleteBehaviorType

Accessibility: Read/Write

Gets or sets a value that specifies the **relationship delete behavior** of the **lookup field**.

#### Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	The <b>list</b> that the <b>field (2)</b> belongs to is an <b>external list</b> .

### 3.2.5.49.1.1.21 Required

Type: **CSOM Boolean**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.Required**, as specified in section [3.2.5.37.1.1.14](#).

#### Exceptions:



Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is set to "true", and the <b>list</b> is an <b>external list</b> .

### 3.2.5.49.1.1.22 SchemaXml

Type: **CSOM String**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.SchemaXml**, as specified in section [3.2.5.37.1.1.15](#).

It MUST be NULL, empty, or an **XML fragment** that conforms to the **FieldDefinition** type, as specified in [\[MS-WSSFO2\]](#) section 2.2.8.3.3 or [\[MS-WSSFO3\]](#) section 2.2.7.3.3.

#### Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed to a value that is not NULL or empty, and the <b>list</b> is an <b>external list</b> .

### 3.2.5.49.1.1.23 Scope

Type: **CSOM String**

Accessibility: Read Only

See **Microsoft.SharePoint.Client.Field.Scope**, as specified in section [3.2.5.37.1.1.16](#).

### 3.2.5.49.1.1.24 Sealed

Type: **CSOM Boolean**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.Sealed**, as specified in section [3.2.5.37.1.1.17](#).

### 3.2.5.49.1.1.25 Sortable

Type: **CSOM Boolean**

Accessibility: Read Only

See **Microsoft.SharePoint.Client.Field.Sortable**, as specified in section [3.2.5.37.1.1.18](#).

### 3.2.5.49.1.1.26 StaticName

Type: **CSOM String**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.StaticName**, as specified in section [3.2.5.37.1.1.19](#).

#### Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed, and the <b>list</b> is an <b>external list</b> .

### 3.2.5.49.1.1.27 Title

Type: **CSOM String**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.Title**, as specified in section [3.2.5.37.1.1.20](#).

### 3.2.5.49.1.1.28 TypeAsString

Type: **CSOM String**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.TypeAsString**, as specified in section [3.2.5.37.1.1.21](#).

It MUST NOT be NULL. It MUST NOT be empty.

Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed, and the <b>list</b> is an <b>external list</b> .

### 3.2.5.49.1.1.29 TypeDisplayName

Type: **CSOM String**

Accessibility: Read Only

See **Microsoft.SharePoint.Client.Field.TypeDisplayName**, as specified in section [3.2.5.37.1.1.22](#).

It MUST NOT be NULL. It MUST NOT be empty.

### 3.2.5.49.1.1.30 TypeShortDescription

Type: **CSOM String**

Accessibility: Read Only

See **Microsoft.SharePoint.Client.Field.TypeShortDescription**, as specified in section [3.2.5.37.1.1.23](#).

It MUST NOT be NULL. It MUST NOT be empty.

### 3.2.5.49.1.1.31 ValidationFormula

Type: **CSOM String**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.ValidationFormula**, as specified in section [3.2.5.37.1.1.24](#).

### 3.2.5.49.1.1.32 ValidationMessage

Type: **CSOM String**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.ValidationMessage**, as specified in section [3.2.5.37.1.1.25](#).

Its length MUST be equal to or less than 1024.

### 3.2.5.49.1.1.33 Indexed

Type: **CSOM Boolean**

Accessibility: Read Only

A bit that specifies whether the **field (2)** is an **indexed field**.[<21>](#)

### 3.2.5.49.1.1.34 JSLink

Type: **CSOM String**

Accessibility: Read/Write

Gets the name of an external ECMAScript ([\[ECMA-262-1999\]](#)) file containing any logic for this **field (2)**.

### 3.2.5.49.1.1.35 EntityPropertyName

Type: **CSOM String**

Accessibility: Read Only

Gets the name of the entity property of this **field (2)** in the **list item** entity that uses this field (2).

It MUST NOT be NULL. It MUST NOT be empty.

### 3.2.5.49.1.1.36 SchemaXmlWithResourceTokens

Type: **CSOM String**

Accessibility: Read Only

Gets the unlocalized schema XML for this **field (2)**.

### 3.2.5.49.1.1.37 AutoIndexed

Type: **CSOM Boolean**

Accessibility: Read Only

Gets the Boolean value that specifies whether or not the field is auto-indexed. Specify a value of true if the field is auto-indexed; false if otherwise.

### 3.2.5.49.1.1.38 ClientSideComponentId

Type: **CSOM GUID**

Accessibility: Read/Write

The unique identifier of the client-side component defined with SharePoint Framework.

#### **3.2.5.49.1.1.39 ClientSideComponentProperties**

**Type:** CSOM String

**Accessibility:** Read/Write

This property is only used when a **ClientSideComponentId** is specified. It is optional. If non-empty, the string **MUST** contain a JSON object with custom initialization properties whose format and meaning are defined by the client-side component.

#### **3.2.5.49.1.1.40 CustomFormatter**

**Type:** CSOM String

**Accessibility:** Read/Write

A JSON string representing the custom rendering format of the field.

#### **3.2.5.49.1.1.41 DefaultFormula**

**Type:** CSOM String

**Accessibility:** Read/Write

Gets or sets the default formula for a calculated field.

#### **3.2.5.49.1.1.42 DependentLookupInternalNames**

**Type:** CSOM array of CSOM String

**Accessibility:** Read Only

Specifies the internal names of all the dependent lookups based on this primary lookup.

#### **3.2.5.49.1.1.43 IsDependentLookup**

**Type:** CSOM Boolean

**Accessibility:** Read Only

Check whether a lookup field is a dependent lookup field.

#### **3.2.5.49.1.1.44 NoCrawl**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Gets or sets a Boolean value that specifies whether the field can be crawled by a search engine.

#### **3.2.5.49.1.1.45 PinnedToFiltersPane**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Boolean value that indicates whether the field pins to filter pane.

### 3.2.5.49.1.1.46 ShowInFiltersPane

**Type:** Microsoft.SharePoint.Client.ShowInFiltersPaneStatus

**Accessibility:** Read/Write

Indicates whether the field will be shown.

### 3.2.5.49.1.1.47 UnlimitedLengthInDocumentLibrary

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Gets or sets a Boolean value that specifies whether to allow values with unlimited text in the lookup field.

## 3.2.5.49.1.2 ObjectPath Properties

### 3.2.5.49.1.2.1 DescriptionResource

**Type:** Microsoft.SharePoint.Client.UserResource

**Accessibility:** Read Only

Gets the resource object corresponding to the **Description** property for a field.

### 3.2.5.49.1.2.2 TitleResource

**Type:** Microsoft.SharePoint.Client.UserResource

**Accessibility:** Read Only

Gets the resource object corresponding to the **Title** property for a field.

## 3.2.5.49.2 Methods

### 3.2.5.49.2.1 Scalar Methods

#### 3.2.5.49.2.1.1 DeleteObject

**Return Type:** None

Deletes the **field (2)** from the **list**, from the **site (2)**, or from the **content types** within the list.

**Parameters:** None

**Exceptions:**

Error Code	Error Type Name	Condition
-1	System.InvalidOperationException	<b>CanBeDeleted</b> is "false".

#### 3.2.5.49.2.1.2 SetShowInDisplayForm

**Return Type:** None

Sets this field to show or hide in the display form.

**Parameters:**

*value*: A Boolean value that indicates whether this field is shown in the display form.

Type: **CSOM Boolean**

### 3.2.5.49.2.1.3 SetShowInEditForm

**Return Type:** None

Sets this field to show or hide in the edit form.

**Parameters:**

*value*: A Boolean value that indicates whether this field is shown in the edit form.

Type: **CSOM Boolean**

### 3.2.5.49.2.1.4 SetShowInNewForm

**Return Type:** None

Sets this field to show or hide in the new form.

**Parameters:**

*value*: A Boolean value that indicates whether this field is shown in the new form.

Type: **CSOM Boolean**

### 3.2.5.49.2.1.5 Update

**Return Type:** None

Commits changed properties of the **field (2)**.

**Parameters:** None

**Exceptions:**

Error Code	Error Type Name	Condition
- 2130246331	Microsoft.SharePoint.SPException	Type of the field (2) is changed for an <b>indexed field</b> . The field type of indexed fields cannot be changed.
- 2130246238	Microsoft.SharePoint.SPException	Field (2) is set to not be an indexed field, and <b>EnforceUniqueValues</b> is "true".
- 2130246236	Microsoft.SharePoint.SPException	Type of the field (2) is being changed and <b>EnforceUniqueValues</b> of the field (2) is "true".

### 3.2.5.49.2.1.6 UpdateAndPushChanges

**Return Type:** None

Commits changed properties of the **field (2)** and propagates changes to all **lists** that use the field (2).

**Parameters:**

*pushChangesToLists*: Specifies whether to propagate changes to all lists that use the field (2).

Type: **CSOM Boolean**

**Exceptions:**

Error Code	Error Type Name	Condition
- 2130246331	Microsoft.SharePoint.SPException	Type of the field (2) is changed for an <b>indexed field</b> . The field type of indexed fields cannot be changed.
- 2130246238	Microsoft.SharePoint.SPException	Field (2) is set to not be an indexed field, and <b>EnforceUniqueValues</b> is "true".
- 2130246236	Microsoft.SharePoint.SPException	Type of the field (2) is being changed and <b>EnforceUniqueValues</b> of the field (2) is "true".

**3.2.5.49.2.1.7 ValidateSetValue**

**Return Type:** None

Validates and sets the value of the **field (2)** for the **list item** based on an implementation-specific transformation of the value. <22>

**Parameters:**

*item*: Specifies the list item to be updated with the new value.

Type: Microsoft.SharePoint.Client.ListItem

It MUST NOT be NULL.

*value*: Specifies the new value for the field (2).

Type: **CSOM String**

**3.2.5.49.2.2 ObjectPath Methods**

None.

**3.2.5.50 Microsoft.SharePoint.Client.FieldLookupValue**

**TypeId:** {F1D34CC0-9B50-4A78-BE78-D5FACFCCCFB7}

**ShortName:** SP.FieldLookupValue

SP.FieldLookupValue: Field value class for SP.FieldLookup (Lookup field).

**3.2.5.50.1 Properties****3.2.5.50.1.1 Scalar Properties****3.2.5.50.1.1.1 LookupId**

Type: **CSOM Int32**

**Accessibility:** Read/Write

Gets or sets the identifier (ID) of the lookup field.

### **3.2.5.50.1.1.2 LookupValue**

**Type:** CSOM String

**Accessibility:** Read Only

Gets the value of the lookup field as a string.

### **3.2.5.50.1.2 ObjectPath Properties**

None.

## **3.2.5.51 Microsoft.SharePoint.Client.FieldMultiChoice**

**TypeId:** {284C160F-3783-4344-A471-80E032719F26}

**ShortName:** SP.FieldMultiChoice

Specifies a **field (2)** that contains one or more values from a set of specified values.

The NoCrawl and SchemaXmlWithResourceTokens properties are not included in the **default scalar property set** for this type.

### **3.2.5.51.1 Properties**

#### **3.2.5.51.1.1 Scalar Properties**

##### **3.2.5.51.1.1.1 CanBeDeleted**

**Type:** CSOM Boolean

**Accessibility:** Read Only

See **Microsoft.SharePoint.Client.Field.CanBeDeleted**, as specified in section [3.2.5.37.1.1.1](#).

##### **3.2.5.51.1.1.2 Choices**

**Type:** CSOM array of CSOM String

**Accessibility:** Read/Write

Specifies values that are available for selection in the **field (2)**.

##### **3.2.5.51.1.1.3 DefaultValue**

**Type:** CSOM String

**Accessibility:** Read/Write

See **Microsoft.SharePoint.Client.Field.DefaultValue**, as specified in section [3.2.5.37.1.1.2](#).

**Exceptions:**



Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed, and the <b>list</b> is an <b>external list</b> .

### 3.2.5.51.1.1.4 Description

**Type:** CSOM String

**Accessibility:** Read/Write

See **Microsoft.SharePoint.Client.Field.Description**, as specified in section [3.2.5.37.1.1.3](#).

### 3.2.5.51.1.1.5 Direction

**Type:** CSOM String

**Accessibility:** Read/Write

See **Microsoft.SharePoint.Client.Field.Direction**, as specified in section [3.2.5.37.1.1.4](#).

#### Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed to a value other than "none," and the <b>list</b> is an <b>external list</b> .

### 3.2.5.51.1.1.6 EnforceUniqueValues

**Type:** CSOM Boolean

**Accessibility:** Read/Write

See **Microsoft.SharePoint.Client.Field.EnforceUniqueValues**, as specified in section [3.2.5.37.1.1.5](#)

#### Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Adding <b>unique column constraints</b> to the <b>field (2)</b> where the <b>list</b> is an <b>external list</b> .

### 3.2.5.51.1.1.7 FieldTypeKind

**Type:** Microsoft.SharePoint.Client.FieldType

**Accessibility:** Read/Write

See **Microsoft.SharePoint.Client.Field.FieldTypeKind**, as specified in section [3.2.5.37.1.1.6](#).

**Exceptions:**

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed, and the <b>list</b> is an <b>external list</b> .

### 3.2.5.51.1.1.8 FillInChoice

Type: **CSOM Boolean**

Accessibility: Read/Write

Specifies whether the **field (2)** can accept values other than those specified in **Microsoft.Sharepoint.Client.FieldMultiChoice.Choices**, as specified in section [3.2.5.51.1.1.2](#).

### 3.2.5.51.1.1.9 Filterable

Type: **CSOM Boolean**

Accessibility: Read Only

See **Microsoft.SharePoint.Client.Field.Filterable**, as specified in section [3.2.5.37.1.1.7](#).

### 3.2.5.51.1.1.10 FromBaseType

Type: **CSOM Boolean**

Accessibility: Read Only

Gets a **Boolean** value that indicates whether the **field (2)** derives from a **base field type**.

### 3.2.5.51.1.1.11 Group

Type: **CSOM String**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.Group**, as specified in section [3.2.5.37.1.1.9](#).

It MUST NOT be NULL. It MUST NOT be empty. Its length MUST be equal to or less than 128.

**Exceptions:**

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed, and the <b>list</b> is an <b>external list</b> .

### 3.2.5.51.1.1.12 Hidden

Type: **CSOM Boolean**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.Hidden**, as specified in section [3.2.5.37.1.1.10](#).

### 3.2.5.51.1.1.13 Id

Type: **CSOM GUID**

Accessibility: Read Only

See **Microsoft.SharePoint.Client.Field.Id**, as specified in section [3.2.5.37.1.1.11](#).

### 3.2.5.51.1.1.14 InternalName

Type: **CSOM String**

Accessibility: Read Only

See **Microsoft.SharePoint.Client.Field.InternalName**, as specified in section [3.2.5.37.1.1.12](#).

It MUST NOT be NULL. It MUST NOT be empty.

### 3.2.5.51.1.1.15 Mappings

Type: **CSOM String**

Accessibility: Read Only

Specifies the internal values corresponding to **Choices**.

It MUST be NULL or an **XML fragment** that conforms to **MAPPINGDEFINITION**, as specified in [\[MS-WSSFO3\]](#) section 2.2.7.3.13.

### 3.2.5.51.1.1.16 ReadOnlyField

Type: **CSOM Boolean**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.ReadOnlyField**, as specified in section [3.2.5.37.1.1.13](#).

Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed, and the <b>list</b> is an <b>external list</b> .

### 3.2.5.51.1.1.17 Required

Type: **CSOM Boolean**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.Required**, as specified in section [3.2.5.37.1.1.14](#).

Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is set to "true", and the <b>list</b> is an <b>external list</b> .

### 3.2.5.51.1.1.18 SchemaXml

Type: **CSOM String**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.SchemaXml**, as specified in section [3.2.5.37.1.1.15](#).

It MUST be NULL, empty, or an **XML fragment** that conforms to the **FieldDefinition** type, as specified in [\[MS-WSSFO2\]](#) section 2.2.8.3.3 or [\[MS-WSSFO3\]](#) section 2.2.7.3.3.

#### Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed to a non-NULL or non-empty value, and the <b>list</b> is an <b>external list</b> .

### 3.2.5.51.1.1.19 Scope

Type: **CSOM String**

Accessibility: Read Only

See **Microsoft.SharePoint.Client.Field.Scope**, as specified in section [3.2.5.37.1.1.16](#).

### 3.2.5.51.1.1.20 Sealed

Type: **CSOM Boolean**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.Sealed**, as specified in section [3.2.5.37.1.1.17](#).

### 3.2.5.51.1.1.21 Sortable

Type: **CSOM Boolean**

Accessibility: Read Only

See **Microsoft.SharePoint.Client.Field.Sortable**, as specified in section [3.2.5.37.1.1.18](#).

### 3.2.5.51.1.1.22 StaticName

Type: **CSOM String**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.StaticName**, as specified in section [3.2.5.37.1.1.19](#).

#### Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed, and the <b>list</b> is an <b>external list</b> .

### 3.2.5.51.1.1.23 Title

Type: **CSOM String**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.Title**, as specified in section [3.2.5.37.1.1.20](#).

### 3.2.5.51.1.1.24 TypeAsString

Type: **CSOM String**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.TypeAsString**, as specified in section [3.2.5.37.1.1.21](#).

It MUST NOT be NULL. It MUST NOT be empty.

#### Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed, and the <b>list</b> is an <b>external list</b> .

### 3.2.5.51.1.1.25 TypeDisplayName

Type: **CSOM String**

Accessibility: Read Only

See **Microsoft.SharePoint.Client.Field.TypeDisplayName**, as specified in section [3.2.5.37.1.1.22](#).

It MUST NOT be NULL. It MUST NOT be empty.

### 3.2.5.51.1.1.26 TypeShortDescription

Type: **CSOM String**

Accessibility: Read Only

See **Microsoft.SharePoint.Client.Field.TypeShortDescription**, as specified in section [3.2.5.37.1.1.23](#).

It MUST NOT be NULL. It MUST NOT be empty.

### 3.2.5.51.1.1.27 ValidationFormula

Type: **CSOM String**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.ValidationFormula**, as specified in section [3.2.5.37.1.1.24](#).

### 3.2.5.51.1.1.28 ValidationMessage

Type: **CSOM String**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.ValidationMessage**, as specified in section [3.2.5.37.1.1.25](#).

Its length MUST be equal to or less than 1024.

### **3.2.5.51.1.1.29 JSLink**

**Type:** CSOM String

**Accessibility:** Read/Write

Gets the name of an external ECMAScript ([\[ECMA-262-1999\]](#)) file containing any logic for this **field (2)**.

### **3.2.5.51.1.1.30 EntityPropertyName**

**Type:** CSOM String

**Accessibility:** Read Only

Gets the name of the entity property of this **field (2)** in the **list item** entity that uses this field (2).

It MUST NOT be NULL. It MUST NOT be empty.

### **3.2.5.51.1.1.31 Indexed**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Gets or sets a Boolean value that specifies whether the field is indexed.

### **3.2.5.51.1.1.32 SchemaXmlWithResourceTokens**

**Type:** CSOM String

**Accessibility:** Read Only

Gets the unlocalized schema XML for this **field (2)**.

### **3.2.5.51.1.1.33 AutoIndexed**

**Type:** CSOM Boolean

**Accessibility:** Read Only

Gets the Boolean value that specifies whether or not the field is auto-indexed. Specify a value of true if the field is auto-indexed; false if otherwise.

### **3.2.5.51.1.1.34 ClientSideComponentId**

**Type:** CSOM GUID

**Accessibility:** Read/Write

The unique identifier of the client-side component defined with SharePoint Framework.

### **3.2.5.51.1.1.35 ClientSideComponentProperties**

**Type:** CSOM String

**Accessibility:** Read/Write

This property is only used when a **ClientSideComponentId** is specified. It is optional. If non-empty, the string MUST contain a JSON object with custom initialization properties whose format and meaning are defined by the client-side component.

### **3.2.5.51.1.1.36 CustomFormatter**

**Type:** CSOM String

**Accessibility:** Read/Write

A JSON string representing the custom rendering format of the field.

### **3.2.5.51.1.1.37 DefaultFormula**

**Type:** CSOM String

**Accessibility:** Read/Write

Gets or sets the default formula for a calculated field.

### **3.2.5.51.1.1.38 NoCrawl**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Gets or sets a Boolean value that specifies whether the field can be crawled by a search engine.

### **3.2.5.51.1.1.39 PinnedToFiltersPane**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Boolean value that indicates whether the field pins to filter pane.

### **3.2.5.51.1.1.40 ShowInFiltersPane**

**Type:** Microsoft.SharePoint.Client.ShowInFiltersPaneStatus

**Accessibility:** Read/Write

Indicates whether the field will be shown.

## **3.2.5.51.1.2 ObjectPath Properties**

### **3.2.5.51.1.2.1 DescriptionResource**

**Type:** Microsoft.SharePoint.Client.UserResource

**Accessibility:** Read Only

Gets the resource object corresponding to the **Description** property for a field.

### **3.2.5.51.1.2.2 TitleResource**

**Type:** Microsoft.SharePoint.Client.UserResource

**Accessibility:** Read Only

Gets the resource object corresponding to the **Title** property for a field.

### 3.2.5.51.2 Methods

#### 3.2.5.51.2.1 Scalar Methods

##### 3.2.5.51.2.1.1 DeleteObject

**Return Type:** None

Deletes the **field (2)** from the **list**, from the **site (2)**, or from the **content types** within the list.

**Parameters:** None

**Exceptions:**

Error Code	Error Type Name	Condition
-1	System.InvalidOperationException	<b>CanBeDeleted</b> is "false".

##### 3.2.5.51.2.1.2 SetShowInDisplayForm

**Return Type:** None

Sets this field to show or hide in the display form.

**Parameters:**

*value:* A Boolean value that indicates whether this field is shown in the display form.

Type: **CSOM Boolean**

##### 3.2.5.51.2.1.3 SetShowInEditForm

**Return Type:** None

Sets this field to show or hide in the edit form.

**Parameters:**

*value:* A Boolean value that indicates whether this field is shown in the edit form.

Type: **CSOM Boolean**

##### 3.2.5.51.2.1.4 SetShowInNewForm

**Return Type:** None

Sets this field to show or hide in the new form.

**Parameters:**

*value:* A Boolean value that indicates whether this field is shown in the new form.

Type: **CSOM Boolean**



### 3.2.5.51.2.1.5 Update

**Return Type:** None

Commits changed properties of the **field (2)**.

**Parameters:** None

**Exceptions:**

Error Code	Error Type Name	Condition
- 2130246331	Microsoft.SharePoint.SPException	Type of the field (2) is changed for an <b>indexed field</b> . The field type of indexed fields cannot be changed.
- 2130246238	Microsoft.SharePoint.SPException	Field (2) is set to not be an indexed field, and <b>EnforceUniqueValues</b> is "true".
- 2130246236	Microsoft.SharePoint.SPException	Type of the field (2) is being changed and <b>EnforceUniqueValues</b> of the field (2) is "true".

### 3.2.5.51.2.1.6 UpdateAndPushChanges

**Return Type:** None

Commits changed properties of the **field (2)** and propagates changes to all **lists** that use the field (2).

**Parameters:**

*pushChangesToLists*: Specifies whether to propagate changes to all lists that use the field (2).

Type: **CSOM Boolean**

**Exceptions:**

Error Code	Error Type Name	Condition
- 2130246331	Microsoft.SharePoint.SPException	Type of the field (2) is changed for an <b>indexed field</b> . The field type of indexed fields cannot be changed.
- 2130246238	Microsoft.SharePoint.SPException	Field (2) is set to not be an indexed field, and <b>EnforceUniqueValues</b> is "true".
- 2130246236	Microsoft.SharePoint.SPException	Type of the field (2) is being changed and <b>EnforceUniqueValues</b> of the field (2) is "true".

### 3.2.5.51.2.1.7 ValidateSetValue

**Return Type:** None

Validates and sets the value of the **field (2)** for the **list item** based on an implementation-specific transformation of the value. <23>

**Parameters:**

*item*: Specifies the list item to be updated with the new value.

Type: Microsoft.SharePoint.Client.ListItem

It MUST NOT be NULL.

*value*: Specifies the new value for the field (2).

Type: **CSOM String**

### 3.2.5.51.2.2 ObjectPath Methods

None.

### 3.2.5.52 Microsoft.SharePoint.Client.FieldMultiLineText

**TypeId**: {9AE17ECC-11A6-4433-8B51-7ECB865FFE05}

**ShortName**: SP.FieldMultiLineText

Specifies a **field (2)** that can contain multiple lines of text. To set properties, call the **Update** method (section [3.2.5.52.2.1.5](#)).

The NoCrawl and SchemaXmlWithResourceTokens properties are not included in the **default scalar property set** for this type.

#### 3.2.5.52.1 Properties

##### 3.2.5.52.1.1 Scalar Properties

###### 3.2.5.52.1.1.1 AllowHyperlink

Type: **CSOM Boolean**

**Accessibility**: Read/Write

Specifies whether a **hyperlink** is allowed as a value of the **field (2)**.

###### 3.2.5.52.1.1.2 AppendOnly

Type: **CSOM Boolean**

**Accessibility**: Read/Write

Specifies whether all changes to the value of the **field (2)** are displayed in **list forms**.

###### 3.2.5.52.1.1.3 CanBeDeleted

Type: **CSOM Boolean**

**Accessibility**: Read Only

See **Microsoft.SharePoint.Client.Field.CanBeDeleted**, as specified in section [3.2.5.37.1.1.1](#).

###### 3.2.5.52.1.1.4 DefaultValue

Type: **CSOM String**

**Accessibility**: Read/Write

See **Microsoft.SharePoint.Client.Field.DefaultValue**, as specified in section [3.2.5.37.1.1.2](#).

**Exceptions:**

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed, and the <b>list</b> is an <b>external list</b> .

**3.2.5.52.1.1.5 Description**

**Type:** CSOM String

**Accessibility:** Read/Write

See **Microsoft.SharePoint.Client.Field.Description**, as specified in section [3.2.5.37.1.1.3](#).

**3.2.5.52.1.1.6 Direction**

**Type:** CSOM String

**Accessibility:** Read/Write

See **Microsoft.SharePoint.Client.Field.Direction**, as specified in section [3.2.5.37.1.1.4](#).

**Exceptions:**

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed to a value other than "none," and the <b>list</b> is an <b>external list</b> .

**3.2.5.52.1.1.7 EnforceUniqueValues**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

See **Microsoft.SharePoint.Client.Field.EnforceUniqueValues**, as specified in section [3.2.5.37.1.1.5](#)

**Exceptions:**

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Adding <b>unique column constraints</b> to the <b>field (2)</b> where the <b>list</b> is an <b>external list</b> .

**3.2.5.52.1.1.8 FieldTypeKind**

**Type:** Microsoft.SharePoint.Client.FieldType

**Accessibility:** Read/Write

See **Microsoft.SharePoint.Client.Field.FieldTypeKind**, as specified in section [3.2.5.37.1.1.6](#).

**Exceptions:**

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed, and the <b>list</b> is an <b>external list</b> .

### 3.2.5.52.1.1.9 Filterable

**Type:** CSOM Boolean

**Accessibility:** Read Only

See **Microsoft.SharePoint.Client.Field.Filterable**, as specified in section [3.2.5.37.1.1.7](#).

### 3.2.5.52.1.1.10 FromBaseType

**Type:** CSOM Boolean

**Accessibility:** Read Only

Gets a **Boolean** value that indicates whether the **field (2)** derives from a **base field type**.

### 3.2.5.52.1.1.11 Group

**Type:** CSOM String

**Accessibility:** Read/Write

See **Microsoft.SharePoint.Client.Field.Group**, as specified in section [3.2.5.37.1.1.9](#).

It MUST NOT be NULL. It MUST NOT be empty. Its length MUST be equal to or less than 128.

**Exceptions:**

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed, and the <b>list</b> is an <b>external list</b> .

### 3.2.5.52.1.1.12 Hidden

**Type:** CSOM Boolean

**Accessibility:** Read/Write

See **Microsoft.SharePoint.Client.Field.Hidden**, as specified in section [3.2.5.37.1.1.10](#).

### 3.2.5.52.1.1.13 Id

**Type:** CSOM GUID

**Accessibility:** Read Only

See **Microsoft.SharePoint.Client.Field.Id**, as specified in section [3.2.5.37.1.1.11](#).

### 3.2.5.52.1.1.14 InternalName

Type: **CSOM String**

Accessibility: Read Only

See **Microsoft.SharePoint.Client.Field.InternalName**, as specified in section [3.2.5.37.1.1.12](#).

It MUST NOT be NULL. It MUST NOT be empty.

### 3.2.5.52.1.1.15 NumberOfLines

Type: **CSOM Int32**

Accessibility: Read/Write

Specifies the number of lines of text to display for the **field (2)**.

Its value MUST be equal to or greater than 1. Its value MUST be equal to or less than 1000.

### 3.2.5.52.1.1.16 ReadOnlyField

Type: **CSOM Boolean**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.ReadOnlyField**, as specified in section [3.2.5.37.1.1.13](#).

Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed, and the <b>list</b> is an <b>external list</b> .

### 3.2.5.52.1.1.17 Required

Type: **CSOM Boolean**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.Required**, as specified in section [3.2.5.37.1.1.14](#).

Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is set to "true", and the <b>list</b> is an <b>external list</b> .

### 3.2.5.52.1.1.18 RestrictedMode

Type: **CSOM Boolean**

Accessibility: Read/Write

Specifies whether the **field (2)** supports a subset of **rich text** formatting.

### 3.2.5.52.1.1.19 RichText

Type: **CSOM Boolean**

Accessibility: Read/Write

Specifies whether the **field (2)** supports **rich text** formatting.

### 3.2.5.52.1.1.20 SchemaXml

Type: **CSOM String**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.SchemaXml**, as specified in section [3.2.5.37.1.1.15](#).

It MUST be NULL, empty, or an **XML fragment** that conforms to the **FieldDefinition** type, as specified in [\[MS-WSSFO2\]](#) section 2.2.8.3.3 or [\[MS-WSSFO3\]](#) section 2.2.7.3.3.

#### Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed to a value that is not NULL or empty, and the <b>list</b> is an <b>external list</b> .

### 3.2.5.52.1.1.21 Scope

Type: **CSOM String**

Accessibility: Read Only

See **Microsoft.SharePoint.Client.Field.Scope**, as specified in section [3.2.5.37.1.1.16](#).

### 3.2.5.52.1.1.22 Sealed

Type: **CSOM Boolean**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.Sealed**, as specified in section [3.2.5.37.1.1.17](#).

### 3.2.5.52.1.1.23 Sortable

Type: **CSOM Boolean**

Accessibility: Read Only

See **Microsoft.SharePoint.Client.Field.Sortable**, as specified in section [3.2.5.37.1.1.18](#).

### 3.2.5.52.1.1.24 StaticName

Type: **CSOM String**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.StaticName**, as specified in section [3.2.5.37.1.1.19](#).

**Exceptions:**

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed, and the <b>list</b> is an <b>external list</b> .

**3.2.5.52.1.1.25 Title**

Type: **CSOM String**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.Title**, as specified in section [3.2.5.37.1.1.20](#).

**3.2.5.52.1.1.26 TypeAsString**

Type: **CSOM String**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.TypeAsString**, as specified in section [3.2.5.37.1.1.21](#).

It MUST NOT be NULL. It MUST NOT be empty.

**Exceptions:**

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed, and the <b>list</b> is an <b>external list</b> .

**3.2.5.52.1.1.27 TypeDisplayName**

Type: **CSOM String**

Accessibility: Read Only

See **Microsoft.SharePoint.Client.Field.TypeDisplayName**, as specified in section [3.2.5.37.1.1.22](#).

It MUST NOT be NULL. It MUST NOT be empty.

**3.2.5.52.1.1.28 TypeShortDescription**

Type: **CSOM String**

Accessibility: Read Only

See **Microsoft.SharePoint.Client.Field.TypeShortDescription**, as specified in section [3.2.5.37.1.1.23](#).

It MUST NOT be NULL. It MUST NOT be empty.

**3.2.5.52.1.1.29 ValidationFormula**

Type: **CSOM String**

**Accessibility:** Read/Write

See **Microsoft.SharePoint.Client.Field.ValidationFormula**, as specified in section [3.2.5.37.1.1.24](#).

### 3.2.5.52.1.1.30 ValidationMessage

**Type:** CSOM String

**Accessibility:** Read/Write

See **Microsoft.SharePoint.Client.Field.ValidationMessage**, as specified in section [3.2.5.37.1.1.25](#).

Its length MUST be equal to or less than 1024.

### 3.2.5.52.1.1.31 WikiLinking

**Type:** CSOM Boolean

**Accessibility:** Read Only

Specifies whether an implementation-specific mechanism for linking wiki pages is supported. It MUST be "false" if **RichText** is "false".

#### Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed, and the <b>list</b> is an <b>external list</b> .

### 3.2.5.52.1.1.32 JSLink

**Type:** CSOM String

**Accessibility:** Read/Write

Gets the name of an external ECMAScript ([\[ECMA-262-1999\]](#)) file containing any logic for this **field (2)**.

### 3.2.5.52.1.1.33 EntityPropertyName

**Type:** CSOM String

**Accessibility:** Read Only

Gets the name of the entity property of this **field (2)** in the **list item** entity that uses this field (2).

It MUST NOT be NULL. It MUST NOT be empty.

### 3.2.5.52.1.1.34 Indexed

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Gets or sets a Boolean value that specifies whether the field is indexed.

### 3.2.5.52.1.1.35 SchemaXmlWithResourceTokens



**Type:** CSOM String

**Accessibility:** Read Only

Gets the unlocalized schema XML for this **field (2)**.

### **3.2.5.52.1.1.36 AutoIndexed**

**Type:** CSOM Boolean

**Accessibility:** Read Only

Gets the Boolean value that specifies whether or not the field is auto-indexed. Specify a value of true if the field is auto-indexed; false if otherwise.

### **3.2.5.52.1.1.37 ClientSideComponentId**

**Type:** CSOM GUID

**Accessibility:** Read/Write

The unique identifier of the client-side component defined with SharePoint Framework.

### **3.2.5.52.1.1.38 ClientSideComponentProperties**

**Type:** CSOM String

**Accessibility:** Read/Write

This property is only used when a **ClientSideComponentId** is specified. It is optional. If non-empty, the string MUST contain a JSON object with custom initialization properties whose format and meaning are defined by the client-side component.

### **3.2.5.52.1.1.39 CustomFormatter**

**Type:** CSOM String

**Accessibility:** Read/Write

A JSON string representing the custom rendering format of the field.

### **3.2.5.52.1.1.40 DefaultFormula**

**Type:** CSOM String

**Accessibility:** Read/Write

Gets or sets the default formula for a calculated field.

### **3.2.5.52.1.1.41 NoCrawl**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Gets or sets a Boolean value that specifies whether the field can be crawled by a search engine.

### **3.2.5.52.1.1.42 PinnedToFiltersPane**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Boolean value that indicates whether the field pins to filter pane.

### 3.2.5.52.1.1.43 ShowInFiltersPane

**Type:** Microsoft.SharePoint.Client.ShowInFiltersPaneStatus

**Accessibility:** Read/Write

Indicates whether the field will be shown.

### 3.2.5.52.1.1.44 UnlimitedLengthInDocumentLibrary

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Gets or sets a Boolean value that specifies whether to allow unlimited field length in document libraries.

## 3.2.5.52.1.2 ObjectPath Properties

### 3.2.5.52.1.2.1 DescriptionResource

**Type:** Microsoft.SharePoint.Client.UserResource

**Accessibility:** Read Only

Gets the resource object corresponding to the **Description** property for a field.

### 3.2.5.52.1.2.2 TitleResource

**Type:** Microsoft.SharePoint.Client.UserResource

**Accessibility:** Read Only

Gets the resource object corresponding to the **Title** property for a field.

## 3.2.5.52.2 Methods

### 3.2.5.52.2.1 Scalar Methods

#### 3.2.5.52.2.1.1 DeleteObject

**Return Type:** None

Deletes the **field (2)** from the **list**, from the **site (2)**, or from the **content types** within the list.

**Parameters:** None

**Exceptions:**

Error Code	Error Type Name	Condition
-1	System.InvalidOperationException	<b>CanBeDeleted</b> is "false".

### 3.2.5.52.2.1.2 SetShowInDisplayForm

**Return Type:** None

Sets this field to show or hide in the display form.

**Parameters:**

*value:* A Boolean value that indicates whether this field is shown in the display form.

Type: **CSOM Boolean**

### 3.2.5.52.2.1.3 SetShowInEditForm

**Return Type:** None

Sets this field to show or hide in the edit form.

**Parameters:**

*value:* A Boolean value that indicates whether this field is shown in the edit form.

Type: **CSOM Boolean**

### 3.2.5.52.2.1.4 SetShowInNewForm

**Return Type:** None

Sets this field to show or hide in the new form.

**Parameters:**

*value:* A Boolean value that indicates whether this field is shown in the new form.

Type: **CSOM Boolean**

### 3.2.5.52.2.1.5 Update

**Return Type:** None

Commits changed properties of the **field (2)**.

**Parameters:** None

**Exceptions:**

Error Code	Error Type Name	Condition
- 2130246331	Microsoft.SharePoint.SPException	Type of the field (2) is changed for an <b>indexed field</b> . The field type of indexed fields cannot be changed.
- 2130246238	Microsoft.SharePoint.SPException	Field (2) is set to not be an indexed field, and <b>EnforceUniqueValues</b> is "true".
- 2130246236	Microsoft.SharePoint.SPException	Type of the field (2) is being changed and <b>EnforceUniqueValues</b> of the field (2) is "true".

### 3.2.5.52.2.1.6 UpdateAndPushChanges

**Return Type:** None

Commits changed properties of the **field (2)** and propagates changes to all **lists** that use the field (2).

**Parameters:**

*pushChangesToLists*: Specifies whether to propagate changes to all lists that use the field (2).

Type: **CSOM Boolean**

**Exceptions:**

Error Code	Error Type Name	Condition
- 2130246331	Microsoft.SharePoint.SPException	Type of the field (2) is changed for an <b>indexed field</b> . The field type of indexed fields cannot be changed.
- 2130246238	Microsoft.SharePoint.SPException	Field (2) is set to not be an indexed field, and <b>EnforceUniqueValues</b> is "true".
- 2130246236	Microsoft.SharePoint.SPException	Type of the field (2) is being changed and <b>EnforceUniqueValues</b> of the field (2) is "true".

### 3.2.5.52.2.1.7 ValidateSetValue

**Return Type:** None

Validates and sets the value of the **field (2)** for the **list item** based on an implementation-specific transformation of the value. <24>

**Parameters:**

*item*: Specifies the list item to be updated with the new value.

Type: Microsoft.SharePoint.Client.ListItem

It MUST NOT be NULL.

*value*: Specifies the new value for the field (2).

Type: **CSOM String**

### 3.2.5.52.2.2 ObjectPath Methods

None.

### 3.2.5.53 Microsoft.SharePoint.Client.FieldNumber

**TypeId:** {E32D2A19-D2A8-428C-B056-EA71EDE547CE}

**ShortName:** SP.FieldNumber

Specifies a **field (2)** that contains number values. To set properties, call the **Update** method (section [3.2.5.53.2.1.5](#)).

The NoCrawl and SchemaXmlWithResourceTokens properties are not included in the **default scalar property set** for this type.

### 3.2.5.53.1 Properties

#### 3.2.5.53.1.1 Scalar Properties

##### 3.2.5.53.1.1.1 CanBeDeleted

Type: **CSOM Boolean**

Accessibility: Read Only

See **Microsoft.SharePoint.Client.Field.CanBeDeleted**, as specified in section [3.2.5.37.1.1.1](#).

##### 3.2.5.53.1.1.2 DefaultValue

Type: **CSOM String**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.DefaultValue**, as specified in section [3.2.5.37.1.1.2](#).

Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed, and the <b>list</b> is an <b>external list</b> .

##### 3.2.5.53.1.1.3 Description

Type: **CSOM String**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.Description**, as specified in section [3.2.5.37.1.1.3](#).

##### 3.2.5.53.1.1.4 Direction

Type: **CSOM String**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.Direction**, as specified in section [3.2.5.37.1.1.4](#).

Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed to a value other than "none," and the <b>list</b> is an <b>external list</b> .

##### 3.2.5.53.1.1.5 EnforceUniqueValues

Type: **CSOM Boolean**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.EnforceUniqueValues**, as specified in section [3.2.5.37.1.1.5](#)

**Exceptions:**

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Adding <b>unique column constraints</b> to the <b>field (2)</b> where the <b>list</b> is an <b>external list</b> .

**3.2.5.53.1.1.6 FieldTypeKind**

**Type:** Microsoft.SharePoint.Client.FieldType

**Accessibility:** Read/Write

See **Microsoft.SharePoint.Client.Field.FieldTypeKind**, as specified in section [3.2.5.37.1.1.6](#).

**Exceptions:**

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed, and the <b>list</b> is an <b>external list</b> .

**3.2.5.53.1.1.7 Filterable**

**Type:** CSOM Boolean

**Accessibility:** Read Only

See **Microsoft.SharePoint.Client.Field.Filterable**, as specified in section [3.2.5.37.1.1.7](#).

**3.2.5.53.1.1.8 FromBaseType**

**Type:** CSOM Boolean

**Accessibility:** Read Only

Gets a **Boolean** value that indicates whether the **field (2)** derives from a **base field type**.

**3.2.5.53.1.1.9 Group**

**Type:** CSOM String

**Accessibility:** Read/Write

See **Microsoft.SharePoint.Client.Field.Group**, as specified in section [3.2.5.37.1.1.9](#).

It MUST NOT be NULL. It MUST NOT be empty. Its length MUST be equal to or less than 128.

**Exceptions:**

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed, and the <b>list</b> is an <b>external list</b> .

### 3.2.5.53.1.1.10 Hidden

Type: **CSOM Boolean**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.Hidden**, as specified in section [3.2.5.37.1.1.10](#).

### 3.2.5.53.1.1.11 Id

Type: **CSOM GUID**

Accessibility: Read Only

See **Microsoft.SharePoint.Client.Field.Id**, as specified in section [3.2.5.37.1.1.11](#).

### 3.2.5.53.1.1.12 InternalName

Type: **CSOM String**

Accessibility: Read Only

See **Microsoft.SharePoint.Client.Field.InternalName**, as specified in section [3.2.5.37.1.1.12](#).

It MUST NOT be NULL. It MUST NOT be empty.

### 3.2.5.53.1.1.13 MaximumValue

Type: **CSOM Double**

Accessibility: Read/Write

Specifies the maximum allowed value for the **field (2)**.

### 3.2.5.53.1.1.14 MinimumValue

Type: **CSOM Double**

Accessibility: Read/Write

Specifies the minimum allowed value for the **field (2)**.

### 3.2.5.53.1.1.15 ReadOnlyField

Type: **CSOM Boolean**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.ReadOnlyField**, as specified in section [3.2.5.37.1.1.13](#).

**Exceptions:**

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed, and the <b>list</b> is an <b>external list</b> .

### 3.2.5.53.1.1.16 Required

Type: **CSOM Boolean**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.Required**, as specified in section [3.2.5.37.1.1.14](#).

Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is set to "true", and the <b>list</b> is an <b>external list</b> .

### 3.2.5.53.1.1.17 SchemaXml

Type: **CSOM String**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.SchemaXml**, as specified in section [3.2.5.37.1.1.15](#).

It MUST be NULL, empty, or an **XML fragment** that conforms to the **FieldDefinition** type as specified in [\[MS-WSSFO2\]](#) section 2.2.8.3.3 or [\[MS-WSSFO3\]](#) section 2.2.7.3.3.

Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed to a value that is not NULL or empty value, and the <b>list</b> is an <b>external list</b> .

### 3.2.5.53.1.1.18 Scope

Type: **CSOM String**

Accessibility: Read Only

See **Microsoft.SharePoint.Client.Field.Scope**, as specified in section [3.2.5.37.1.1.16](#).

### 3.2.5.53.1.1.19 Sealed

Type: **CSOM Boolean**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.Sealed**, as specified in section [3.2.5.37.1.1.17](#).



### 3.2.5.53.1.1.20 Sortable

Type: **CSOM Boolean**

Accessibility: Read Only

See **Microsoft.SharePoint.Client.Field.Sortable**, as specified in section [3.2.5.37.1.1.18](#).

### 3.2.5.53.1.1.21 StaticName

Type: **CSOM String**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.StaticName**, as specified in section [3.2.5.37.1.1.19](#).

#### Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed, and the <b>list</b> is an <b>external list</b> .

### 3.2.5.53.1.1.22 Title

Type: **CSOM String**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.Title**, as specified in section [3.2.5.37.1.1.20](#).

### 3.2.5.53.1.1.23 TypeAsString

Type: **CSOM String**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.TypeAsString**, as specified in section [3.2.5.37.1.1.21](#).

It MUST NOT be NULL. It MUST NOT be empty.

#### Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed, and the <b>list</b> is an <b>external list</b> .

### 3.2.5.53.1.1.24 TypeDisplayName

Type: **CSOM String**

Accessibility: Read Only

See **Microsoft.SharePoint.Client.Field.TypeDisplayName**, as specified in section [3.2.5.37.1.1.22](#).

It MUST NOT be NULL. It MUST NOT be empty.

### 3.2.5.53.1.1.25 TypeShortDescription

Type: **CSOM String**

Accessibility: Read Only

See **Microsoft.SharePoint.Client.Field.TypeShortDescription**, as specified in section [3.2.5.37.1.1.23](#).

It MUST NOT be NULL. It MUST NOT be empty.

### 3.2.5.53.1.1.26 ValidationFormula

Type: **CSOM String**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.ValidationFormula**, as specified in section [3.2.5.37.1.1.24](#).

### 3.2.5.53.1.1.27 ValidationMessage

Type: **CSOM String**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.ValidationMessage**, as specified in section [3.2.5.37.1.1.25](#).

Its length MUST be equal to or less than 1024.

### 3.2.5.53.1.1.28 JSLink

Type: **CSOM String**

Accessibility: Read/Write

Gets the name of an external ECMAScript ([\[ECMA-262-1999\]](#)) file containing any logic for this **field (2)**.

### 3.2.5.53.1.1.29 EntityPropertyName

Type: **CSOM String**

Accessibility: Read Only

Gets the name of the entity property of this **field (2)** in the **list item** entity that uses this field (2).

It MUST NOT be NULL. It MUST NOT be empty.

### 3.2.5.53.1.1.30 Indexed

Type: **CSOM Boolean**

Accessibility: Read/Write

Gets or sets a Boolean value that specifies whether the field is indexed.

### 3.2.5.53.1.1.31 SchemaXmlWithResourceTokens

Type: **CSOM String**

**Accessibility:** Read Only

Gets the unlocalized schema XML for this **field (2)**.

### **3.2.5.53.1.1.32      AutoIndexed**

**Type:** CSOM Boolean

**Accessibility:** Read Only

Gets the Boolean value that specifies whether or not the field is auto-indexed. Specify a value of true if the field is auto-indexed; false if otherwise.

### **3.2.5.53.1.1.33      ClientSideComponentId**

**Type:** CSOM GUID

**Accessibility:** Read/Write

The unique identifier of the client-side component defined with SharePoint Framework.

### **3.2.5.53.1.1.34      ClientSideComponentProperties**

**Type:** CSOM String

**Accessibility:** Read/Write

This property is only used when a **ClientSideComponentId** is specified. It is optional. If non-empty, the string MUST contain a JSON object with custom initialization properties whose format and meaning are defined by the client-side component.

### **3.2.5.53.1.1.35      CustomFormatter**

**Type:** CSOM String

**Accessibility:** Read/Write

A JSON string representing the custom rendering format of the field.

### **3.2.5.53.1.1.36      DefaultFormula**

**Type:** CSOM String

**Accessibility:** Read/Write

Gets or sets the default formula for a calculated field.

### **3.2.5.53.1.1.37      DisplayFormat**

**Type:** CSOM Int32

**Accessibility:** Read Only

Gets the number of decimal places to be used when displaying the field.

### **3.2.5.53.1.1.38      NoCrawl**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Gets or sets a Boolean value that specifies whether the field can be crawled by a search engine.

### **3.2.5.53.1.1.39 PinnedToFiltersPane**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Boolean value that indicates whether the field pins to filter pane.

### **3.2.5.53.1.1.40 ShowAsPercentage**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Gets or sets a Boolean value that specifies whether to render the field as a percentage.

### **3.2.5.53.1.1.41 ShowInFiltersPane**

**Type:** Microsoft.SharePoint.Client.ShowInFiltersPaneStatus

**Accessibility:** Read/Write

Indicates whether the field will be shown.

## **3.2.5.53.1.2 ObjectPath Properties**

### **3.2.5.53.1.2.1 DescriptionResource**

**Type:** Microsoft.SharePoint.Client.UserResource

**Accessibility:** Read Only

Gets the resource object corresponding to the **Description** property for a field.

### **3.2.5.53.1.2.2 TitleResource**

**Type:** Microsoft.SharePoint.Client.UserResource

**Accessibility:** Read Only

Gets the resource object corresponding to the **Title** property for a field.

## **3.2.5.53.2 Methods**

### **3.2.5.53.2.1 Scalar Methods**

#### **3.2.5.53.2.1.1 DeleteObject**

**Return Type:** None

Deletes the **field (2)** from the **list**, from the **site (2)**, or from the **content types** within the list.

**Parameters:** None

**Exceptions:**

Error Code	Error Type Name	Condition
-1	System.InvalidOperationException	<b>CanBeDeleted</b> is "false".

### 3.2.5.53.2.1.2 SetShowInDisplayForm

**Return Type:** None

Sets this field to show or hide in the display form.

**Parameters:**

*value:* A Boolean value that indicates whether this field is shown in the display form.

Type: **CSOM Boolean**

### 3.2.5.53.2.1.3 SetShowInEditForm

**Return Type:** None

Sets this field to show or hide in the edit form.

**Parameters:**

*value:* A Boolean value that indicates whether this field is shown in the edit form.

Type: **CSOM Boolean**

### 3.2.5.53.2.1.4 SetShowInNewForm

**Return Type:** None

Sets this field to show or hide in the new form.

**Parameters:**

*value:* A Boolean value that indicates whether this field is shown in the new form.

Type: **CSOM Boolean**

### 3.2.5.53.2.1.5 Update

**Return Type:** None

Commits changed properties of the **field (2)**.

**Parameters:** None

**Exceptions:**

Error Code	Error Type Name	Condition
-2130246331	Microsoft.SharePoint.SPException	Type of the field (2) is changed for an <b>indexed field</b> . The field type of indexed fields cannot be changed.
-2130246238	Microsoft.SharePoint.SPException	Field (2) is set to not be an indexed field, and <b>EnforceUniqueValues</b> is "true".

Error Code	Error Type Name	Condition
- 2130246236	Microsoft.SharePoint.SPException	Type of the field (2) is being changed and <b>EnforceUniqueValues</b> of the field (2) is "true".

### 3.2.5.53.2.1.6 UpdateAndPushChanges

**Return Type:** None

Commits changed properties of the **field (2)** and propagates changes to all **lists** that use the field (2).

**Parameters:**

*pushChangesToLists*: Specifies whether to propagate changes to all lists that use the field (2).

Type: **CSOM Boolean**

**Exceptions:**

Error Code	Error Type Name	Condition
- 2130246331	Microsoft.SharePoint.SPException	Type of the field (2) is changed for an <b>indexed field</b> . The field type of indexed fields cannot be changed.
- 2130246238	Microsoft.SharePoint.SPException	Field (2) is set to not be an indexed field, and <b>EnforceUniqueValues</b> is "true".
- 2130246236	Microsoft.SharePoint.SPException	Type of the field (2) is being changed and <b>EnforceUniqueValues</b> of the field (2) is "true".

### 3.2.5.53.2.1.7 ValidateSetValue

**Return Type:** None

Validates and sets the value of the **field (2)** for the **list item** based on an implementation-specific transformation of the value. [<25>](#)

**Parameters:**

*item*: Specifies the list item to be updated with the new value.

Type: Microsoft.SharePoint.Client.ListItem

It MUST NOT be NULL.

*value*: Specifies the new value for the field (2).

Type: **CSOM String**

### 3.2.5.53.2.2 ObjectPath Methods

None.

### 3.2.5.54 Microsoft.SharePoint.Client.FieldRatingScale

**TypeId:** {66D84FDD-BDB2-4E21-BED0-67F3EAB33DE4}

**ShortName:** SP.FieldRatingScale

Specifies a **field (2)** that contains rating scale values for a **survey list**. To set properties, call the **Update** method (section [3.2.5.54.2.1.5](#)).

The NoCrawl and SchemaXmlWithResourceTokens properties are not included in the **default scalar property set** for this type.

#### 3.2.5.54.1 Properties

##### 3.2.5.54.1.1 Scalar Properties

###### 3.2.5.54.1.1.1 CanBeDeleted

**Type:** **CSOM Boolean**

**Accessibility:** Read Only

See **Microsoft.SharePoint.Client.Field.CanBeDeleted**, as specified in section [3.2.5.37.1.1.1](#).

###### 3.2.5.54.1.1.2 Choices

**Type:** **CSOM array** of **CSOM String**

**Accessibility:** Read/Write

See **Microsoft.SharePoint.Client.FieldMultiChoice.Choices**, as specified in section [3.2.5.51.1.1.2](#).

###### 3.2.5.54.1.1.3 DefaultValue

**Type:** **CSOM String**

**Accessibility:** Read/Write

See **Microsoft.SharePoint.Client.Field.DefaultValue**, as specified in section [3.2.5.37.1.1.2](#).

#### Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed, and the <b>list</b> is an <b>external list</b> .

###### 3.2.5.54.1.1.4 Description

**Type:** **CSOM String**

**Accessibility:** Read/Write

See **Microsoft.SharePoint.Client.Field.Description**, as specified in section [3.2.5.37.1.1.3](#).

###### 3.2.5.54.1.1.5 Direction

**Type:** **CSOM String**

**Accessibility:** Read/Write

See **Microsoft.SharePoint.Client.Field.Direction**, as specified in section [3.2.5.37.1.1.4](#).

**Exceptions:**

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed to a value other than "none", and the <b>list</b> is an <b>external list</b> .

### 3.2.5.54.1.1.6 EnforceUniqueValues

**Type:** CSOM Boolean

**Accessibility:** Read/Write

See **Microsoft.SharePoint.Client.Field.EnforceUniqueValues**, as specified in section [3.2.5.37.1.1.5](#)

**Exceptions:**

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Adding <b>unique column constraints</b> to the <b>field (2)</b> where the <b>list</b> is an <b>external list</b> .

### 3.2.5.54.1.1.7 FieldTypeKind

**Type:** Microsoft.SharePoint.Client.FieldType

**Accessibility:** Read/Write

See **Microsoft.SharePoint.Client.Field.FieldTypeKind**, specified in section [3.2.5.37.1.1.6](#).

**Exceptions:**

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed, and the <b>list</b> is an <b>external list</b> .

### 3.2.5.54.1.1.8 FillInChoice

**Type:** CSOM Boolean

**Accessibility:** Read/Write

See **Microsoft.SharePoint.Client.FieldMultiChoice.FillInChoice**, as specified in section [3.2.5.51.1.1.8](#).



### **3.2.5.54.1.1.9 Filterable**

**Type:** CSOM Boolean

**Accessibility:** Read Only

See **Microsoft.SharePoint.Client.Field.Filterable**, as specified in section [3.2.5.37.1.1.7](#).

### **3.2.5.54.1.1.10 FromBaseType**

**Type:** CSOM Boolean

**Accessibility:** Read Only

Gets a **Boolean** value that indicates whether the **field (2)** derives from a **base field type**.

### **3.2.5.54.1.1.11 GridEndNumber**

**Type:** CSOM Int32

**Accessibility:** Read/Write

Specifies the end number for the rating scale.

### **3.2.5.54.1.1.12 GridNAOptionText**

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies the display text corresponding to the choice in the rating scale that indicates the non-applicable option.

### **3.2.5.54.1.1.13 GridStartNumber**

**Type:** CSOM Int32

**Accessibility:** Read/Write

Specifies the start number for the rating scale.

### **3.2.5.54.1.1.14 GridTextRangeAverage**

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies the display text corresponding to the average of the rating scale.

### **3.2.5.54.1.1.15 GridTextRangeHigh**

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies the display text corresponding to the maximum of the rating scale.

### **3.2.5.54.1.1.16 GridTextRangeLow**

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies the display text corresponding to the minimum of the rating scale.

### 3.2.5.54.1.1.17 Group

**Type:** CSOM String

**Accessibility:** Read/Write

See **Microsoft.SharePoint.Client.Field.Group**, as specified in section [3.2.5.37.1.1.9](#).

It MUST NOT be NULL. It MUST NOT be empty. Its length MUST be equal to or less than 128.

#### Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed, and the <b>list</b> is an <b>external list</b> .

### 3.2.5.54.1.1.18 Hidden

**Type:** CSOM Boolean

**Accessibility:** Read/Write

See **Microsoft.SharePoint.Client.Field.Hidden**, as specified in section [3.2.5.37.1.1.10](#).

### 3.2.5.54.1.1.19 Id

**Type:** CSOM GUID

**Accessibility:** Read Only

See **Microsoft.SharePoint.Client.Field.Id**, as specified in section [3.2.5.37.1.1.11](#).

### 3.2.5.54.1.1.20 InternalName

**Type:** CSOM String

**Accessibility:** Read Only

See **Microsoft.SharePoint.Client.Field.InternalName**, as specified in section [3.2.5.37.1.1.12](#).

It MUST NOT be NULL. It MUST NOT be empty.

### 3.2.5.54.1.1.21 Mappings

**Type:** CSOM String

**Accessibility:** Read Only

See **Microsoft.SharePoint.Client.FieldMultiChoice.Mappings**, as specified in section [3.2.5.51.1.1.15](#).

MUST be NULL or an **XML fragment** that conforms to **MAPPINGDEFINITION**, as specified in [\[MS-WSSFO3\]](#) section 2.2.7.3.13.

### 3.2.5.54.1.1.22 RangeCount

Type: **CSOM Int32**

Accessibility: Read Only

Specifies the number of options in the rating scale.

### 3.2.5.54.1.1.23 ReadOnlyField

Type: **CSOM Boolean**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.ReadOnlyField**, as specified in section [3.2.5.37.1.1.13](#).

#### Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed, and the <b>list</b> is an <b>external list</b> .

### 3.2.5.54.1.1.24 Required

Type: **CSOM Boolean**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.Required**, as specified in section [3.2.5.37.1.1.14](#).

#### Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is set to "true", and the <b>list</b> is an <b>external list</b> .

### 3.2.5.54.1.1.25 SchemaXml

Type: **CSOM String**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.SchemaXml**, as specified in section [3.2.5.37.1.1.15](#).

It MUST be NULL, empty, or an **XML fragment** that conforms to the **FieldDefinition** type, as specified in [\[MS-WSSFO2\]](#) section 2.2.8.3.3 or [\[MS-WSSFO3\]](#) section 2.2.7.3.3.

#### Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed to a value that is not NULL or empty, and the <b>list</b> is an <b>external list</b> .

### 3.2.5.54.1.1.26 Scope

Type: **CSOM String**

Accessibility: Read Only

See **Microsoft.SharePoint.Client.Field.Scope**, as specified in section [3.2.5.37.1.1.16](#).

### 3.2.5.54.1.1.27 Sealed

Type: **CSOM Boolean**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.Sealed**, as specified in section [3.2.5.37.1.1.17](#).

### 3.2.5.54.1.1.28 Sortable

Type: **CSOM Boolean**

Accessibility: Read Only

See **Microsoft.SharePoint.Client.Field.Sortable**, as specified in section [3.2.5.37.1.1.18](#).

### 3.2.5.54.1.1.29 StaticName

Type: **CSOM String**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.StaticName**, as specified in section [3.2.5.37.1.1.19](#).

#### Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed, and the <b>list</b> is an <b>external list</b> .

### 3.2.5.54.1.1.30 Title

Type: **CSOM String**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.Title**, as specified in section [3.2.5.37.1.1.20](#).

### 3.2.5.54.1.1.31 TypeAsString

Type: **CSOM String**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.TypeAsString**, as specified in section [3.2.5.37.1.1.21](#).

It MUST NOT be NULL. It MUST NOT be empty.

#### Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed, and the <b>list</b> is an <b>external list</b> .

### 3.2.5.54.1.1.32 TypeDisplayName

Type: **CSOM String**

Accessibility: Read Only

See Microsoft.SharePoint.Client.Field.TypeDisplayName, as specified in section [3.2.5.37.1.1.22](#).

It MUST NOT be NULL. It MUST NOT be empty.

### 3.2.5.54.1.1.33 TypeShortDescription

Type: **CSOM String**

Accessibility: Read Only

See **Microsoft.SharePoint.Client.Field.TypeShortDescription**, as specified in section [3.2.5.37.1.1.23](#).

It MUST NOT be NULL. It MUST NOT be empty.

### 3.2.5.54.1.1.34 ValidationFormula

Type: **CSOM String**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.ValidationFormula**, as specified in section [3.2.5.37.1.1.24](#).

### 3.2.5.54.1.1.35 ValidationMessage

Type: **CSOM String**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.ValidationMessage**, as specified in section [3.2.5.37.1.1.25](#).

Its length MUST be equal to or less than 1024.

### 3.2.5.54.1.1.36 JSLink

Type: **CSOM String**

Accessibility: Read/Write

Gets the name of an external ECMAScript ([\[ECMA-262-1999\]](#)) file containing any logic for this **field (2)**.

### 3.2.5.54.1.1.37 EntityPropertyName

Type: **CSOM String**

Accessibility: Read Only

Gets the name of the entity property of this **field (2)** in the **list item** entity that uses this field (2).  
It MUST NOT be NULL. It MUST NOT be empty.

#### **3.2.5.54.1.1.38 Indexed**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Gets or sets a Boolean value that specifies whether the field is indexed.

#### **3.2.5.54.1.1.39 SchemaXmlWithResourceTokens**

**Type:** CSOM String

**Accessibility:** Read Only

Gets the unlocalized schema XML for this **field (2)**.

#### **3.2.5.54.1.1.40 AutoIndexed**

**Type:** CSOM Boolean

**Accessibility:** Read Only

Gets the Boolean value that specifies whether or not the field is auto-indexed. Specify a value of true if the field is auto-indexed; false if otherwise.

#### **3.2.5.54.1.1.41 ClientSideComponentId**

**Type:** CSOM GUID

**Accessibility:** Read/Write

The unique identifier of the client-side component defined with SharePoint Framework.

#### **3.2.5.54.1.1.42 ClientSideComponentProperties**

**Type:** CSOM String

**Accessibility:** Read/Write

This property is only used when a **ClientSideComponentId** is specified. It is optional. If non-empty, the string MUST contain a JSON object with custom initialization properties whose format and meaning are defined by the client-side component.

#### **3.2.5.54.1.1.43 CustomFormatter**

**Type:** CSOM String

**Accessibility:** Read/Write

A JSON string representing the custom rendering format of the field.

#### **3.2.5.54.1.1.44 DefaultFormula**

**Type:** CSOM String

**Accessibility:** Read/Write

Gets or sets the default formula for a calculated field.

#### **3.2.5.54.1.1.45 NoCrawl**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Gets or sets a Boolean value that specifies whether the field can be crawled by a search engine.

#### **3.2.5.54.1.1.46 PinnedToFiltersPane**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Boolean value that indicates whether the field pins to filter pane.

#### **3.2.5.54.1.1.47 ShowInFiltersPane**

**Type:** Microsoft.SharePoint.Client.ShowInFiltersPaneStatus

**Accessibility:** Read/Write

Indicates whether the field will be shown.

### **3.2.5.54.1.2 ObjectPath Properties**

#### **3.2.5.54.1.2.1 DescriptionResource**

**Type:** Microsoft.SharePoint.Client.UserResource

**Accessibility:** Read Only

Gets the resource object corresponding to the **Description** property for a field.

#### **3.2.5.54.1.2.2 TitleResource**

**Type:** Microsoft.SharePoint.Client.UserResource

**Accessibility:** Read Only

Gets the resource object corresponding to the **Title** property for a field.

### **3.2.5.54.2 Methods**

#### **3.2.5.54.2.1 Scalar Methods**

##### **3.2.5.54.2.1.1 DeleteObject**

**Return Type:** None

Deletes the **field (2)** from the **list**, from the **site (2)**, or from the **content types** within the list.

**Parameters:** None

**Exceptions:**

Error Code	Error Type Name	Condition
-1	System.InvalidOperationException	<b>CanBeDeleted</b> is "false".

### 3.2.5.54.2.1.2 SetShowInDisplayForm

**Return Type:** None

Sets this field to show or hide in the display form.

**Parameters:**

*value:* A Boolean value that indicates whether this field is shown in the display form.

Type: **CSOM Boolean**

### 3.2.5.54.2.1.3 SetShowInEditForm

**Return Type:** None

Sets this field to show or hide in the edit form.

**Parameters:**

*value:* A Boolean value that indicates whether this field is shown in the edit form.

Type: **CSOM Boolean**

### 3.2.5.54.2.1.4 SetShowInNewForm

**Return Type:** None

Sets this field to show or hide in the new form.

**Parameters:**

*value:* A Boolean value that indicates whether this field is shown in the new form.

Type: **CSOM Boolean**

### 3.2.5.54.2.1.5 Update

**Return Type:** None

Commits changed properties of the **field (2)**.

**Parameters:** None

**Exceptions:**

Error Code	Error Type Name	Condition
-2130246331	Microsoft.SharePoint.SPException	Type of the field (2) is changed for an <b>indexed field</b> . The field type of indexed fields cannot be changed.
-2130246238	Microsoft.SharePoint.SPException	Field (2) is set to not be an indexed field, and <b>EnforceUniqueValues</b> is "true".



Error Code	Error Type Name	Condition
- 2130246236	Microsoft.SharePoint.SPException	Type of the field (2) is being changed and <b>EnforceUniqueValues</b> of the field (2) is "true".

### 3.2.5.54.2.1.6 UpdateAndPushChanges

**Return Type:** None

Commits changed properties of the **field (2)** and propagates changes to all **lists** that use the field (2).

**Parameters:**

*pushChangesToLists*: Specifies whether to propagate changes to all lists that use the field (2).

Type: **CSOM Boolean**

**Exceptions:**

Error Code	Error Type Name	Condition
- 2130246331	Microsoft.SharePoint.SPException	Type of the field (2) is changed for an <b>indexed field</b> . The field type of indexed fields cannot be changed.
- 2130246238	Microsoft.SharePoint.SPException	Field (2) is set to not be an indexed field, and <b>EnforceUniqueValues</b> is "true".
- 2130246236	Microsoft.SharePoint.SPException	Type of the field (2) is being changed and <b>EnforceUniqueValues</b> of the field (2) is "true".

### 3.2.5.54.2.1.7 ValidateSetValue

**Return Type:** None

Validates and sets the value of the **field (2)** for the **list item** based on an implementation-specific transformation of the value. [<26>](#)

**Parameters:**

*item*: Specifies the list item to be updated with the new value.

Type: Microsoft.SharePoint.Client.ListItem

It MUST NOT be NULL.

*value*: Specifies the new value for the field (2).

Type: **CSOM String**

### 3.2.5.54.2.2 ObjectPath Methods

None.

### 3.2.5.55 Microsoft.SharePoint.Client.FieldRatingScaleQuestionAnswer

**TypeId:** {9B88FE8E-47CD-4DDC-9D66-0D12D70DDE28}

**ShortName:** SP.FieldRatingScaleQuestionAnswer

Represents a specific question and answer within a rating scale **field (2)** of a **list item**.

#### 3.2.5.55.1 Properties

##### 3.2.5.55.1.1 Scalar Properties

###### 3.2.5.55.1.1.1 Answer

**Type:** **CSOM Int32**

**Accessibility:** Read/Write

Specifies the answer for a sub-question. MUST be NULL if no answer has been provided for the sub-question within the rating scale **field (2)** for the **list item** this value is associated with.

###### 3.2.5.55.1.1.2 Question

**Type:** **CSOM String**

**Accessibility:** Read/Write

Specifies a sub-question within a rating scale.

##### 3.2.5.55.1.2 ObjectPath Properties

None.

### 3.2.5.56 Microsoft.SharePoint.Client.FieldStringValues

**TypeId:** {542FA9DF-AC22-4FDB-8BA3-DAB6060C2DE4}

**ShortName:** SP.FieldStringValues

Specifies a collection that contains key value pairs. The **FieldStringValues** type contains **CSOM expando fields**. The value type for the CSOM expando fields MUST be **CSOM String**.

#### 3.2.5.56.1 Properties

##### 3.2.5.56.1.1 Scalar Properties

None.

##### 3.2.5.56.1.2 ObjectPath Properties

None.

#### 3.2.5.56.2 Methods

##### 3.2.5.56.2.1 Scalar Methods

None.

## 3.2.5.56.2.2 ObjectPath Methods

None.

## 3.2.5.57 Microsoft.SharePoint.Client.FieldText

**TypeId:** {47CBA3A7-3327-4FA1-AC10-73A7A182FE05}

**ShortName:** SP.FieldText

Specifies a **field (2)** that contains a single line of text. To set properties, call the **Update** method (section [3.2.5.57.2.1.5](#)).

The NoCrawl and SchemaXmlWithResourceTokens properties are not included in the **default scalar property set** for this type.

### 3.2.5.57.1 Properties

#### 3.2.5.57.1.1 Scalar Properties

##### 3.2.5.57.1.1.1 CanBeDeleted

**Type:** **CSOM Boolean**

**Accessibility:** Read Only

See **Microsoft.SharePoint.Client.Field.CanBeDeleted**, as specified in section [3.2.5.37.1.1.1](#).

##### 3.2.5.57.1.1.2 DefaultValue

**Type:** **CSOM String**

**Accessibility:** Read/Write

See **Microsoft.SharePoint.Client.Field.DefaultValue**, as specified in section [3.2.5.37.1.1.2](#).

#### Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed, and the <b>list</b> is an <b>external list</b> .

##### 3.2.5.57.1.1.3 Description

**Type:** **CSOM String**

**Accessibility:** Read/Write

See **Microsoft.SharePoint.Client.Field.Description**, as specified in section [3.2.5.37.1.1.3](#).

##### 3.2.5.57.1.1.4 Direction

**Type:** **CSOM String**

**Accessibility:** Read/Write

See **Microsoft.SharePoint.Client.Field.Direction**, as specified in section [3.2.5.37.1.1.4](#).

**Exceptions:**

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed to a value other than "none", and the <b>list</b> is an <b>external list</b> .

**3.2.5.57.1.1.5 EnforceUniqueValues**

Type: **CSOM Boolean**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.EnforceUniqueValues**, as specified in section [3.2.5.37.1.1.5](#)

**Exceptions:**

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Adding <b>unique column constraints</b> to the <b>field (2)</b> where the <b>list</b> is an <b>external list</b> .

**3.2.5.57.1.1.6 FieldTypeKind**

Type: Microsoft.SharePoint.Client.FieldType

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.FieldTypeKind**, as specified in section [3.2.5.37.1.1.6](#).

**Exceptions:**

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed, and the <b>list</b> is an <b>external list</b> .

**3.2.5.57.1.1.7 Filterable**

Type: **CSOM Boolean**

Accessibility: Read Only

See **Microsoft.SharePoint.Client.Field.Filterable**, as specified in section [3.2.5.37.1.1.7](#).

**3.2.5.57.1.1.8 FromBaseType**

Type: **CSOM Boolean**

**Accessibility:** Read Only

Gets a **Boolean** value that indicates whether the **field (2)** derives from a **base field type**.

### 3.2.5.57.1.1.9 Group

**Type:** CSOM String

**Accessibility:** Read/Write

See **Microsoft.SharePoint.Client.Field.Group**, as specified in section [3.2.5.37.1.1.9](#).

It MUST NOT be NULL. It MUST NOT be empty. Its length MUST be equal to or less than 128.

#### Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed, and the <b>list</b> is an <b>external list</b> .

### 3.2.5.57.1.1.10 Hidden

**Type:** CSOM Boolean

**Accessibility:** Read/Write

See **Microsoft.SharePoint.Client.Field.Hidden**, as specified in section [3.2.5.37.1.1.10](#).

### 3.2.5.57.1.1.11 Id

**Type:** CSOM GUID

**Accessibility:** Read Only

See **Microsoft.SharePoint.Client.Field.Id**, as specified in section [3.2.5.37.1.1.11](#).

### 3.2.5.57.1.1.12 InternalName

**Type:** CSOM String

**Accessibility:** Read Only

See **Microsoft.SharePoint.Client.Field.InternalName**, as specified in section [3.2.5.37.1.1.12](#).

It MUST NOT be NULL. It MUST NOT be empty.

### 3.2.5.57.1.1.13 MaxLength

**Type:** CSOM Int32

**Accessibility:** Read/Write

Specifies the maximum number of characters allowed in the value of the **field (2)**.

Its value MUST be equal to or greater than 1. Its value MUST be equal to or less than 255.

### 3.2.5.57.1.1.14 ReadOnlyField

Type: **CSOM Boolean**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.ReadOnlyField**, as specified in section [3.2.5.37.1.1.13](#).

Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed, and the <b>list</b> is an <b>external list</b> .

### 3.2.5.57.1.1.15 Required

Type: **CSOM Boolean**

Accessibility: Read/Write

Specifies whether or not the **field (2)** requires values.

Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is set to "true", and the <b>list</b> is an <b>external list</b> .

### 3.2.5.57.1.1.16 SchemaXml

Type: **CSOM String**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.SchemaXml**, as specified in section [3.2.5.37.1.1.15](#).

It MUST be NULL, empty, or an **XML fragment** that conforms to the **FieldDefinition** type, as specified in [\[MS-WSSFO2\]](#) section 2.2.8.3.3 or [\[MS-WSSFO3\]](#) section 2.2.7.3.3.

Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed to a value that is not a NULL or an empty value, and the <b>list</b> is an <b>external list</b> .

### 3.2.5.57.1.1.17 Scope

Type: **CSOM String**

Accessibility: Read Only

See **Microsoft.SharePoint.Client.Field.Scope**, as specified in section [3.2.5.37.1.1.16](#).

### 3.2.5.57.1.1.18 Sealed

Type: **CSOM Boolean**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.Sealed**, as specified in section [3.2.5.37.1.1.17](#).

### 3.2.5.57.1.1.19 Sortable

Type: **CSOM Boolean**

Accessibility: Read Only

See **Microsoft.SharePoint.Client.Field.Sortable**, as specified in section [3.2.5.37.1.1.18](#).

### 3.2.5.57.1.1.20 StaticName

Type: **CSOM String**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.StaticName**, as specified in section [3.2.5.37.1.1.19](#).

Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed, and the <b>list</b> is an <b>external list</b> .

### 3.2.5.57.1.1.21 Title

Type: **CSOM String**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.Title**, as specified in section [3.2.5.37.1.1.20](#).

### 3.2.5.57.1.1.22 TypeAsString

Type: **CSOM String**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.TypeAsString**, as specified in section [3.2.5.37.1.1.21](#).

It MUST NOT be NULL. It MUST NOT be empty.

Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed, and the <b>list</b> is an <b>external list</b> .

### 3.2.5.57.1.1.23 TypeDisplayName

**Type:** CSOM String

**Accessibility:** Read Only

See Microsoft.SharePoint.Client.Field.TypeDisplayName, as specified in section [3.2.5.37.1.1.22](#).

It MUST NOT be NULL. It MUST NOT be empty.

### **3.2.5.57.1.1.24      TypeShortDescription**

**Type:** CSOM String

**Accessibility:** Read Only

See **Microsoft.SharePoint.Client.Field.TypeShortDescription**, as specified in section [3.2.5.37.1.1.23](#).

It MUST NOT be NULL. It MUST NOT be empty.

### **3.2.5.57.1.1.25      ValidationFormula**

**Type:** CSOM String

**Accessibility:** Read/Write

See **Microsoft.SharePoint.Client.Field.ValidationFormula**, as specified in section [3.2.5.37.1.1.24](#).

### **3.2.5.57.1.1.26      ValidationMessage**

**Type:** CSOM String

**Accessibility:** Read/Write

See **Microsoft.SharePoint.Client.Field.ValidationMessage**, as specified in section [3.2.5.37.1.1.25](#).

Its length MUST be equal to or less than 1024.

### **3.2.5.57.1.1.27      JSLink**

**Type:** CSOM String

**Accessibility:** Read/Write

Gets the name of an external ECMAScript ([\[ECMA-262-1999\]](#)) file containing any logic for this **field (2)**.

### **3.2.5.57.1.1.28      EntityPropertyName**

**Type:** CSOM String

**Accessibility:** Read Only

Gets the name of the entity property of this **field (2)** in the **list item** entity that uses this field (2).

It MUST NOT be NULL. It MUST NOT be empty.

### **3.2.5.57.1.1.29      Indexed**

**Type:** CSOM Boolean

**Accessibility:** Read/Write



Gets or sets a Boolean value that specifies whether the field is indexed.

### **3.2.5.57.1.1.30 SchemaXmlWithResourceTokens**

**Type:** CSOM String

**Accessibility:** Read Only

Gets the unlocalized schema XML for this **field (2)**.

### **3.2.5.57.1.1.31 AutoIndexed**

**Type:** CSOM Boolean

**Accessibility:** Read Only

Gets the Boolean value that specifies whether or not the field is auto-indexed. Specify a value of true if the field is auto-indexed; false if otherwise.

### **3.2.5.57.1.1.32 ClientSideComponentId**

**Type:** CSOM GUID

**Accessibility:** Read/Write

The unique identifier of the client-side component defined with SharePoint Framework.

### **3.2.5.57.1.1.33 ClientSideComponentProperties**

**Type:** CSOM String

**Accessibility:** Read/Write

This property is only used when a **ClientSideComponentId** is specified. It is optional. If non-empty, the string MUST contain a JSON object with custom initialization properties whose format and meaning are defined by the client-side component.

### **3.2.5.57.1.1.34 CustomFormatter**

**Type:** CSOM String

**Accessibility:** Read/Write

A JSON string representing the custom rendering format of the field.

### **3.2.5.57.1.1.35 DefaultFormula**

**Type:** CSOM String

**Accessibility:** Read/Write

Gets or sets the default formula for a calculated field.

### **3.2.5.57.1.1.36 NoCrawl**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Gets or sets a Boolean value that specifies whether the field can be crawled by a search engine.

### 3.2.5.57.1.1.37 PinnedToFiltersPane

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Boolean value that indicates whether the field pins to filter pane.

### 3.2.5.57.1.1.38 ShowInFiltersPane

**Type:** Microsoft.SharePoint.Client.ShowInFiltersPaneStatus

**Accessibility:** Read/Write

Indicates whether the field will be shown.

## 3.2.5.57.1.2 ObjectPath Properties

### 3.2.5.57.1.2.1 DescriptionResource

**Type:** Microsoft.SharePoint.Client.UserResource

**Accessibility:** Read Only

Gets the resource object corresponding to the **Description** property for a field.

### 3.2.5.57.1.2.2 TitleResource

**Type:** Microsoft.SharePoint.Client.UserResource

**Accessibility:** Read Only

Gets the resource object corresponding to the **Title** property for a field.

## 3.2.5.57.2 Methods

### 3.2.5.57.2.1 Scalar Methods

#### 3.2.5.57.2.1.1 DeleteObject

**Return Type:** None

Deletes the **field (2)** from the **list**, from the **site (2)**, or from the **content types** within the list.

**Parameters:** None

**Exceptions:**

Error Code	Error Type Name	Condition
-1	System.InvalidOperationException	<b>CanBeDeleted</b> is "false".

#### 3.2.5.57.2.1.2 SetShowInDisplayForm

**Return Type:** None

Sets this field to show or hide in the display form.

**Parameters:**

*value*: A Boolean value that indicates whether this field is shown in the display form.

Type: **CSOM Boolean**

**3.2.5.57.2.1.3 SetShowInEditForm**

**Return Type:** None

Sets this field to show or hide in the edit form.

**Parameters:**

*value*: A Boolean value that indicates whether this field is shown in the edit form.

Type: **CSOM Boolean**

**3.2.5.57.2.1.4 SetShowInNewForm**

**Return Type:** None

Sets this field to show or hide in the new form.

**Parameters:**

*value*: A Boolean value that indicates whether this field is shown in the new form.

Type: **CSOM Boolean**

**3.2.5.57.2.1.5 Update**

**Return Type:** None

Commits changed properties of the **field (2)**.

**Parameters:** None

**Exceptions:**

Error Code	Error Type Name	Condition
- 2130246331	Microsoft.SharePoint.SPException	Type of the field (2) is changed for an <b>indexed field</b> . The field type of indexed fields cannot be changed.
- 2130246238	Microsoft.SharePoint.SPException	Field (2) is set to not be an indexed field, and <b>EnforceUniqueValues</b> is "true".
- 2130246236	Microsoft.SharePoint.SPException	Type of the field (2) is being changed and <b>EnforceUniqueValues</b> of the field (2) is "true".

**3.2.5.57.2.1.6 UpdateAndPushChanges**

**Return Type:** None

Commits changed properties of the **field (2)** and propagates changes to all **lists** that use the field (2).

**Parameters:**

*pushChangesToLists*: Specifies whether to propagate changes to all lists that use the field (2).

Type: **CSOM Boolean**

**Exceptions:**

Error Code	Error Type Name	Condition
- 2130246331	Microsoft.SharePoint.SPException	Type of the field (2) is changed for an <b>indexed field</b> . The field type of indexed fields cannot be changed.
- 2130246238	Microsoft.SharePoint.SPException	Field (2) is set to not be an indexed field, and <b>EnforceUniqueValues</b> is "true".
- 2130246236	Microsoft.SharePoint.SPException	Type of the field (2) is being changed and <b>EnforceUniqueValues</b> of the field (2) is "true".

### 3.2.5.57.2.1.7 ValidateSetValue

**Return Type:** None

Validates and sets the value of the **field (2)** for the **list item** based on an implementation-specific transformation of the value. <27>

**Parameters:**

*item*: Specifies the list item to be updated with the new value.

Type: Microsoft.SharePoint.Client.ListItem

It MUST NOT be NULL.

*value*: Specifies the new value for the field (2).

Type: **CSOM String**

### 3.2.5.57.2.2 ObjectPath Methods

None.

### 3.2.5.58 Microsoft.SharePoint.Client.FieldType

**ShortName:** SP.FieldType

**Flag:** false

Specifies the type of the **field (2)**, as specified in [\[MS-WSSTS\]](#) section 2.3.1.

#### 3.2.5.58.1 Field Values

##### 3.2.5.58.1.1 Invalid

**Value:** 0

It MUST NOT be used.

##### 3.2.5.58.1.2 Integer

**Value:** 1

Specifies that the **field (2)** contains an **integer** value.

### **3.2.5.58.1.3 Text**

**Value:** 2

Specifies that the **field (2)** contains a single line of text.

### **3.2.5.58.1.4 Note**

**Value:** 3

Specifies that the **field (2)** contains multiple lines of text.

### **3.2.5.58.1.5 DateTime**

**Value:** 4

Specifies that the **field (2)** contains a date and time value or a date-only value.

### **3.2.5.58.1.6 Counter**

**Value:** 5

Specifies that the **field (2)** contains a monotonically increasing integer.

### **3.2.5.58.1.7 Choice**

**Value:** 6

Specifies that the **field (2)** contains a single value from a set of specified values.

### **3.2.5.58.1.8 Lookup**

**Value:** 7

Specifies that the **field (2)** is a **lookup field**.

### **3.2.5.58.1.9 Boolean**

**Value:** 8

Specifies that the **field (2)** contains a **Boolean** value.

### **3.2.5.58.1.10Number**

**Value:** 9

Specifies that the **field (2)** contains a **floating-point number** value.

### **3.2.5.58.1.11Currency**

**Value:** 10

Specifies that the **field (2)** contains a currency value.

### **3.2.5.58.1.12URL**

**Value:** 11

Specifies that the **field (2)** contains a **URI** and an optional description of the URI.

### **3.2.5.58.1.13Computed**

**Value:** 12

Specifies that the **field (2)** is a **computed field**.

### **3.2.5.58.1.14Threading**

**Value:** 13

Specifies that the **field (2)** indicates the thread for a **discussion item** in a threaded view of a **discussion board**.

### **3.2.5.58.1.15Guid**

**Value:** 14

Specifies that the **field (2)** contains a **GUID** value.

### **3.2.5.58.1.16MultiChoice**

**Value:** 15

Specifies that the **field (2)** contains one or more values from a set of specified values.

### **3.2.5.58.1.17GridChoice**

**Value:** 16

Specifies that the **field (2)** contains rating scale values for a **survey list**.

### **3.2.5.58.1.18Calculated**

**Value:** 17

Specifies that the **field (2)** is a **calculated field**.

### **3.2.5.58.1.19File**

**Value:** 18

Specifies that the **field (2)** contains the **leaf name** of a **document** as a value.

### **3.2.5.58.1.20Attachments**

**Value:** 19

Specifies that the **field (2)** indicates whether the **list item** has **attachments**.

### **3.2.5.58.1.21User**

**Value:** 20

Specifies that the **field (2)** contains one or more users and **groups** as values.

### **3.2.5.58.1.22Recurrence**

**Value:** 21

Specifies that the **field (2)** indicates whether a meeting in a calendar **list** recurs.

### **3.2.5.58.1.23CrossProjectLink**

**Value:** 22

Specifies that the **field (2)** contains a link between projects in a **Meeting Workspace site**.

### **3.2.5.58.1.24ModStat**

**Value:** 23

Specifies that the **field (2)** indicates **moderation status**.

### **3.2.5.58.1.25Error**

**Value:** 24

Specifies that the type of the **field (2)** was set to an invalid value.

### **3.2.5.58.1.26ContentTypeId**

**Value:** 25

Specifies that the **field (2)** contains a **content type identifier** as a value.

### **3.2.5.58.1.27PageSeparator**

**Value:** 26

Specifies that the **field (2)** separates questions in a **survey list** onto multiple pages.

### **3.2.5.58.1.28ThreadIndex**

**Value:** 27

Specifies that the **field (2)** indicates the position of a **discussion item** in a threaded view of a **discussion board**.

### **3.2.5.58.1.29WorkflowStatus**

**Value:** 28

Specifies that the **field (2)** indicates the status of a **workflow instance** on a **list item**.

### **3.2.5.58.1.30AllDayEvent**

**Value:** 29

Specifies that the **field (2)** indicates whether a meeting in a calendar **list** is an all-day event.

### **3.2.5.58.1.31WorkflowEventType**

**Value:** 30

Specifies that the **field (2)** contains the most recent **event (2)** in a **workflow instance**.

### 3.2.5.58.1.32MaxItems

**Value:** 33

It MUST NOT be used.

### 3.2.5.58.1.33Geolocation

**Value:** 31

Specifies that the **field (2)** contains geographical location values. [<28>](#)

### 3.2.5.58.1.34OutcomeChoice

**Value:** 32

Specifies that the **field (2)** contains a single value from a set of user-specified values used to determine the outcome of a **task list item**. [<29>](#)

## 3.2.5.59 Microsoft.SharePoint.Client.FieldUrl

**TypeId:** {B1AE9217-E0B0-4E34-9604-BD2462647EE9}

**ShortName:** SP.FieldUrl

Specifies a **field (2)** that contains a **URI**. To set properties, call the **Update** method (section [3.2.5.59.2.1.5](#)).

The NoCrawl and SchemaXmlWithResourceTokens properties are not included in the **default scalar property set** for this type.

### 3.2.5.59.1 Properties

#### 3.2.5.59.1.1 Scalar Properties

##### 3.2.5.59.1.1.1 CanBeDeleted

**Type:** **CSOM Boolean**

**Accessibility:** Read Only

See **Microsoft.SharePoint.Client.Field.CanBeDeleted**, as specified in section [3.2.5.37.1.1.1](#).

##### 3.2.5.59.1.1.2 DefaultValue

**Type:** **CSOM String**

**Accessibility:** Read/Write

See **Microsoft.SharePoint.Client.Field.DefaultValue**, as specified in section [3.2.5.37.1.1.2](#).

#### Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed, and the <b>list</b> is an <b>external list</b> .



### 3.2.5.59.1.1.3 Description

**Type:** CSOM String

**Accessibility:** Read/Write

See **Microsoft.SharePoint.Client.Field.Description**, as specified in section [3.2.5.37.1.1.3](#).

### 3.2.5.59.1.1.4 Direction

**Type:** CSOM String

**Accessibility:** Read/Write

See **Microsoft.SharePoint.Client.Field.Direction**, as specified in section [3.2.5.37.1.1.4](#).

#### Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed to a value other than "none", and the <b>list</b> is an <b>external list</b> .

### 3.2.5.59.1.1.5 DisplayFormat

**Type:** Microsoft.SharePoint.Client.UrlFieldFormatType

**Accessibility:** Read/Write

Specifies the display format for the value in the **field (2)**.

### 3.2.5.59.1.1.6 EnforceUniqueValues

**Type:** CSOM Boolean

**Accessibility:** Read/Write

See **Microsoft.SharePoint.Client.Field.EnforceUniqueValues**, as specified in section [3.2.5.37.1.1.5](#)

#### Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Adding <b>unique column constraints</b> to the <b>field (2)</b> where the <b>list</b> is an <b>external list</b> .

### 3.2.5.59.1.1.7 FieldTypeKind

**Type:** Microsoft.SharePoint.Client.FieldType

**Accessibility:** Read/Write

See **Microsoft.SharePoint.Client.Field.FieldTypeKind**, as specified in section [3.2.5.37.1.1.6](#).

**Exceptions:**

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed, and the <b>list</b> is an <b>external list</b> .

**3.2.5.59.1.1.8 Filterable**

**Type:** CSOM Boolean

**Accessibility:** Read Only

See **Microsoft.SharePoint.Client.Field.Filterable**, as specified in section [3.2.5.37.1.1.7](#).

**3.2.5.59.1.1.9 FromBaseType**

**Type:** CSOM Boolean

**Accessibility:** Read Only

Gets a **Boolean** value that indicates whether the **field (2)** derives from a **base field type**.

**3.2.5.59.1.1.10 Group**

**Type:** CSOM String

**Accessibility:** Read/Write

See **Microsoft.SharePoint.Client.Field.Group**, as specified in section [3.2.5.37.1.1.9](#).

It MUST NOT be NULL. It MUST NOT be empty. Its length MUST be equal to or less than 128.

**Exceptions:**

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed, and the <b>list</b> is an <b>external list</b> .

**3.2.5.59.1.1.11 Hidden**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

See **Microsoft.SharePoint.Client.Field.Hidden**, as specified in section [3.2.5.37.1.1.10](#).

**3.2.5.59.1.1.12 Id**

**Type:** CSOM GUID

**Accessibility:** Read Only

See **Microsoft.SharePoint.Client.Field.Id**, as specified in section [3.2.5.37.1.1.11](#).

### 3.2.5.59.1.1.13 InternalName

Type: **CSOM String**

Accessibility: Read Only

See **Microsoft.SharePoint.Client.Field.InternalName**, as specified in section [3.2.5.37.1.1.12](#).

It MUST NOT be NULL. It MUST NOT be empty.

### 3.2.5.59.1.1.14 ReadOnlyField

Type: **CSOM Boolean**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.ReadOnlyField**, as specified in section [3.2.5.37.1.1.13](#).

Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed, and the <b>list</b> is an <b>external list</b> .

### 3.2.5.59.1.1.15 Required

Type: **CSOM Boolean**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.Required**, as specified in section [3.2.5.37.1.1.14](#).

Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is set to "true", and the <b>list</b> is an <b>external list</b> .

### 3.2.5.59.1.1.16 SchemaXml

Type: **CSOM String**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.SchemaXml**, as specified in section [3.2.5.37.1.1.15](#).

It MUST be NULL, empty, or an **XML fragment** that conforms to the **FieldDefinition** type, as specified in [\[MS-WSSFO2\]](#) section 2.2.8.3.3 or [\[MS-WSSFO3\]](#) section 2.2.7.3.3.

Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed to a value that is not NULL or empty, and the <b>list</b> is an <b>external list</b> .

### 3.2.5.59.1.1.17 Scope

Type: **CSOM String**

Accessibility: Read Only

See **Microsoft.SharePoint.Client.Field.Scope**, as specified in section [3.2.5.37.1.1.16](#).

### 3.2.5.59.1.1.18 Sealed

Type: **CSOM Boolean**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.Sealed**, as specified in section [3.2.5.37.1.1.17](#).

### 3.2.5.59.1.1.19 Sortable

Type: **CSOM Boolean**

Accessibility: Read Only

See **Microsoft.SharePoint.Client.Field.Sortable**, as specified in section [3.2.5.37.1.1.18](#).

### 3.2.5.59.1.1.20 StaticName

Type: **CSOM String**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.StaticName**, as specified in section [3.2.5.37.1.1.19](#).

Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed, and the <b>list</b> is an <b>external list</b> .

### 3.2.5.59.1.1.21 Title

Type: **CSOM String**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.Title**, as specified in section [3.2.5.37.1.1.20](#).

### 3.2.5.59.1.1.22 TypeAsString

Type: **CSOM String**

**Accessibility:** Read/Write

See **Microsoft.SharePoint.Client.Field.TypeAsString**, as specified in section [3.2.5.37.1.1.21](#).

It MUST NOT be NULL. It MUST NOT be empty.

**Exceptions:**

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed, and the <b>list</b> is an <b>external list</b> .

### 3.2.5.59.1.1.23 TypeDisplayName

**Type:** CSOM String

**Accessibility:** Read Only

See **Microsoft.SharePoint.Client.Field.TypeDisplayName**, as specified in section [3.2.5.37.1.1.22](#).

It MUST NOT be NULL. It MUST NOT be empty.

### 3.2.5.59.1.1.24 TypeShortDescription

**Type:** CSOM String

**Accessibility:** Read Only

See **Microsoft.SharePoint.Client.Field.TypeShortDescription**, as specified in section [3.2.5.37.1.1.23](#).

It MUST NOT be NULL. It MUST NOT be empty.

### 3.2.5.59.1.1.25 ValidationFormula

**Type:** CSOM String

**Accessibility:** Read/Write

See **Microsoft.SharePoint.Client.Field.ValidationFormula**, as specified in section [3.2.5.37.1.1.24](#).

### 3.2.5.59.1.1.26 ValidationMessage

**Type:** CSOM String

**Accessibility:** Read/Write

See **Microsoft.SharePoint.Client.Field.ValidationMessage**, as specified in section [3.2.5.37.1.1.25](#).

Its length MUST be equal to or less than 1024.

### 3.2.5.59.1.1.27 JSLink

**Type:** CSOM String

**Accessibility:** Read/Write

Gets the name of an external ECMAScript ([\[ECMA-262-1999\]](#)) file containing any logic for this **field (2)**.

#### **3.2.5.59.1.1.28      EntityPropertyName**

**Type:** CSOM String

**Accessibility:** Read Only

Gets the name of the entity property of this **field (2)** in the **list item** entity that uses this field (2).

It MUST NOT be NULL. It MUST NOT be empty.

#### **3.2.5.59.1.1.29      Indexed**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Gets or sets a Boolean value that specifies whether the field is indexed.

#### **3.2.5.59.1.1.30      SchemaXmlWithResourceTokens**

**Type:** CSOM String

**Accessibility:** Read Only

Gets the unlocalized schema XML for this **field (2)**.

#### **3.2.5.59.1.1.31      AutoIndexed**

**Type:** CSOM Boolean

**Accessibility:** Read Only

Gets the Boolean value that specifies whether or not the field is auto-indexed. Specify a value of true if the field is auto-indexed; false if otherwise.

#### **3.2.5.59.1.1.32      ClientSideComponentId**

**Type:** CSOM GUID

**Accessibility:** Read/Write

The unique identifier of the client-side component defined with SharePoint Framework.

#### **3.2.5.59.1.1.33      ClientSideComponentProperties**

**Type:** CSOM String

**Accessibility:** Read/Write

This property is only used when a **ClientSideComponentId** is specified. It is optional. If non-empty, the string MUST contain a JSON object with custom initialization properties whose format and meaning are defined by the client-side component.

#### **3.2.5.59.1.1.34      CustomFormatter**

**Type:** CSOM String

**Accessibility:** Read/Write

A JSON string representing the custom rendering format of the field.

### **3.2.5.59.1.1.35 DefaultFormula**

**Type:** CSOM String

**Accessibility:** Read/Write

Gets or sets the default formula for a calculated field.

### **3.2.5.59.1.1.36 NoCrawl**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Gets or sets a Boolean value that specifies whether the field can be crawled by a search engine.

### **3.2.5.59.1.1.37 PinnedToFiltersPane**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Boolean value that indicates whether the field pins to filter pane.

### **3.2.5.59.1.1.38 ShowInFiltersPane**

**Type:** Microsoft.SharePoint.Client.ShowInFiltersPaneStatus

**Accessibility:** Read/Write

Indicates whether the field will be shown.

## **3.2.5.59.1.2 ObjectPath Properties**

### **3.2.5.59.1.2.1 DescriptionResource**

**Type:** Microsoft.SharePoint.Client.UserResource

**Accessibility:** Read Only

Gets the resource object corresponding to the **Description** property for a field.

### **3.2.5.59.1.2.2 TitleResource**

**Type:** Microsoft.SharePoint.Client.UserResource

**Accessibility:** Read Only

Gets the resource object corresponding to the **Title** property for a field.

## **3.2.5.59.2 Methods**

### **3.2.5.59.2.1 Scalar Methods**

#### **3.2.5.59.2.1.1 DeleteObject**

**Return Type:** None

Deletes the **field (2)** from the **list**, from the **site (2)**, or from the **content types** within the list.

**Parameters:** None

**Exceptions:**

Error Code	Error Type Name	Condition
-1	System.InvalidOperationException	<b>CanBeDeleted</b> is "false".

### **3.2.5.59.2.1.2 SetShowInDisplayForm**

**Return Type:** None

Sets this field to show or hide in the display form.

**Parameters:**

*value:* A Boolean value that indicates whether this field is shown in the display form.

Type: **CSOM Boolean**

### **3.2.5.59.2.1.3 SetShowInEditForm**

**Return Type:** None

Sets this field to show or hide in the edit form.

**Parameters:**

*value:* A Boolean value that indicates whether this field is shown in the edit form.

Type: **CSOM Boolean**

### **3.2.5.59.2.1.4 SetShowInNewForm**

**Return Type:** None

Sets this field to show or hide in the new form.

**Parameters:**

*value:* A Boolean value that indicates whether this field is shown in the new form.

Type: **CSOM Boolean**

### **3.2.5.59.2.1.5 Update**

**Return Type:** None

Commits changed properties of the **field (2)**.

**Parameters:** None

**Exceptions:**



Error Code	Error Type Name	Condition
- 2130246331	Microsoft.SharePoint.SPException	Type of the field (2) is changed for an <b>indexed field</b> . The field type of indexed fields cannot be changed.
- 2130246238	Microsoft.SharePoint.SPException	Field (2) is set to not be an indexed field, and <b>EnforceUniqueValues</b> is "true".
- 2130246236	Microsoft.SharePoint.SPException	Type of the field (2) is being changed and <b>EnforceUniqueValues</b> of the field (2) is "true".

### 3.2.5.59.2.1.6 UpdateAndPushChanges

**Return Type:** None

Commits changed properties of the **field (2)** and propagates changes to all **lists** that use the field (2).

**Parameters:**

*pushChangesToLists*: Specifies whether to propagate changes to all lists that use the field (2).

Type: **CSOM Boolean**

**Exceptions:**

Error Code	Error Type Name	Condition
- 2130246331	Microsoft.SharePoint.SPException	Type of the field (2) is changed for an <b>indexed field</b> . The field type of indexed fields cannot be changed.
- 2130246238	Microsoft.SharePoint.SPException	Field (2) is set to not be an indexed field, and <b>EnforceUniqueValues</b> is "true".
- 2130246236	Microsoft.SharePoint.SPException	Type of the field (2) is being changed and <b>EnforceUniqueValues</b> of the field (2) is "true".

### 3.2.5.59.2.1.7 ValidateSetValue

**Return Type:** None

Validates and sets the value of the **field (2)** for the **list item** based on an implementation-specific transformation of the value. [<30>](#)

**Parameters:**

*item*: Specifies the list item to be updated with the new value.

Type: Microsoft.SharePoint.Client.ListItem

It MUST NOT be NULL.

*value*: Specifies the new value for the field (2).

Type: **CSOM String**

### 3.2.5.59.2.2 ObjectPath Methods

None.

### 3.2.5.60 Microsoft.SharePoint.Client.FieldUrlValue

**TypeId:** {FA8B44AF-7B43-43F2-904A-BD319497011E}

**ShortName:** SP.FieldUrlValue

Specifies the hyperlink and the description values for **FieldURL**.

#### 3.2.5.60.1 Properties

##### 3.2.5.60.1.1 Scalar Properties

###### 3.2.5.60.1.1.1 Description

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies the description for the **URI**.

Its length MUST be equal to or less than 255.

###### 3.2.5.60.1.1.2 Url

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies the **URI**.

Its length MUST be equal to or less than 255. It MUST be one of the following: NULL, empty, an **absolute URL**, or a **server-relative URL**.

##### 3.2.5.60.1.2 ObjectPath Properties

None.

### 3.2.5.61 Microsoft.SharePoint.Client.FieldUser

**TypeId:** {EBD2FB89-E8A2-46C4-B317-9B2347121765}

**ShortName:** SP.FieldUser

Specifies a **field (2)** that contains a user. To set properties, call the **Update** method (section [3.2.5.61.2.1.5](#)).

The NoCrawl and SchemaXmlWithResourceTokens properties are not included in the **default scalar property set** for this type.

#### 3.2.5.61.1 Properties

##### 3.2.5.61.1.1 Scalar Properties

###### 3.2.5.61.1.1.1 AllowDisplay

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Specifies whether to display the name of the user in a **survey list**.

### 3.2.5.61.1.1.2 AllowMultipleValues

**Type:** CSOM Boolean

**Accessibility:** Read/Write

See **Microsoft.SharePoint.Client.FieldLookup.AllowMultipleValues**, as specified in section [3.2.5.49.1.1.1](#).

### 3.2.5.61.1.1.3 CanBeDeleted

**Type:** CSOM Boolean

**Accessibility:** Read Only

See **Microsoft.SharePoint.Client.Field.CanBeDeleted**, as specified in section [3.2.5.37.1.1.1](#).

### 3.2.5.61.1.1.4 DefaultValue

**Type:** CSOM String

**Accessibility:** Read/Write

See **Microsoft.SharePoint.Client.Field.DefaultValue**, as specified in section [3.2.5.37.1.1.2](#).

**Exceptions:**

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed, and the <b>list</b> is an <b>external list</b> .

### 3.2.5.61.1.1.5 Description

**Type:** CSOM String

**Accessibility:** Read/Write

See **Microsoft.SharePoint.Client.Field.Description**, as specified in section [3.2.5.37.1.1.3](#).

### 3.2.5.61.1.1.6 Direction

**Type:** CSOM String

**Accessibility:** Read/Write

See **Microsoft.SharePoint.Client.Field.Direction**, as specified in section [3.2.5.37.1.1.4](#).

**Exceptions:**

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed to a value other than "none", and the <b>list</b> is an <b>external list</b> .

### 3.2.5.61.1.1.7 EnforceUniqueValues

Type: CSOM Boolean

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.EnforceUniqueValues**, as specified in section [3.2.5.37.1.1.5](#)

#### Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Adding <b>unique column constraints</b> to the <b>field (2)</b> where the <b>list</b> is an <b>external list</b> .

### 3.2.5.61.1.1.8 FieldTypeKind

Type: Microsoft.SharePoint.Client.FieldType

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.FieldTypeKind**, as specified in section [3.2.5.37.1.1.6](#).

#### Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed, and the <b>list</b> is an <b>external list</b> .

### 3.2.5.61.1.1.9 Filterable

Type: CSOM Boolean

Accessibility: Read Only

See **Microsoft.SharePoint.Client.Field.Filterable**, as specified in section [3.2.5.37.1.1.7](#).

### 3.2.5.61.1.1.10 FromBaseType

Type: CSOM Boolean

Accessibility: Read Only

Gets a **Boolean** value that indicates whether the **field (2)** derives from a **base field type**.

### 3.2.5.61.1.1.11 Group

Type: CSOM String

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.Group**, as specified in section [3.2.5.37.1.1.9](#).

It MUST NOT be NULL. It MUST NOT be empty. Its length MUST be equal to or less than 128.

**Exceptions:**

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed, and the <b>list</b> is an <b>external list</b> .

**3.2.5.61.1.1.12 Hidden**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

See **Microsoft.SharePoint.Client.Field.Hidden**, as specified in section [3.2.5.37.1.1.10](#).

**3.2.5.61.1.1.13 Id**

**Type:** CSOM GUID

**Accessibility:** Read Only

See **Microsoft.SharePoint.Client.Field.Id**, as specified in section [3.2.5.37.1.1.11](#).

**3.2.5.61.1.1.14 InternalName**

**Type:** CSOM String

**Accessibility:** Read Only

See **Microsoft.SharePoint.Client.Field.InternalName**, as specified in section [3.2.5.37.1.1.12](#).

It MUST NOT be NULL. It MUST NOT be empty.

**3.2.5.61.1.1.15 IsRelationship**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

See **Microsoft.SharePoint.Client.FieldLookup.IsRelationship**, as specified in section [3.2.5.49.1.1.14](#).

**Exceptions:**

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is read, and the <b>list</b> is an <b>external list</b> .

**3.2.5.61.1.1.16 LookupField**

**Type:** CSOM String

**Accessibility:** Read/Write

See **Microsoft.SharePoint.Client.FieldLookup.LookupField**, as specified in section [3.2.5.49.1.1.15](#).

**Exceptions:**

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is read, and the <b>list</b> is an <b>external list</b> .

**3.2.5.61.1.1.17 LookupList**

Type: **CSOM String**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.FieldLookup.LookupList**, as specified in section [3.2.5.49.1.1.16](#).

**Exceptions:**

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is read, and the <b>list</b> is an <b>external list</b> .

**3.2.5.61.1.1.18 LookupWebId**

Type: **CSOM GUID**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.FieldLookup.LookupWebId**, as specified in section [3.2.5.49.1.1.17](#).

**Exceptions:**

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is read, and the <b>list</b> is an <b>external list</b> .

**3.2.5.61.1.1.19 Presence**

Type: **CSOM Boolean**

Accessibility: Read/Write

Specifies whether **presence** is enabled on the **field (2)**.

**3.2.5.61.1.1.20 PrimaryFieldId**

Type: **CSOM String**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.FieldLookup.PrimaryFieldId**, as specified in section [3.2.5.49.1.1.18](#).

**Exceptions:**

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	When the <b>list</b> that this <b>field (2)</b> belongs to is an <b>external list</b> .

**3.2.5.61.1.1.21 ReadOnlyField**

Type: **CSOM Boolean**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.ReadOnlyField**, as specified in section [3.2.5.37.1.1.13](#).

**Exceptions:**

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed, and the <b>list</b> is an <b>external list</b> .

**3.2.5.61.1.1.22 RelationshipDeleteBehavior**

Type: Microsoft.SharePoint.Client.RelationshipDeleteBehaviorType

Accessibility: Read/Write

Returns a **Microsoft.SharePoint.Client.FieldLookup.RelationshipDeleteBehavior** (section [3.2.5.49.1.1.20](#)) that represents the delete behavior of the lookup field.

**Exceptions:**

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is read, and the <b>list</b> is an <b>external list</b> .

**3.2.5.61.1.1.23 Required**

Type: **CSOM Boolean**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.Required**, as specified in section [3.2.5.37.1.1.14](#).

**Exceptions:**

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is set to "true", and the <b>list</b> is an <b>external list</b> .

### 3.2.5.61.1.1.24 SchemaXml

Type: **CSOM String**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.SchemaXml**, as specified in section [3.2.5.37.1.1.15](#).

It MUST be NULL, empty, or an **XML fragment** that conforms to the **FieldDefinition** type, as specified in [\[MS-WSSFO2\]](#) section 2.2.8.3.3 or [\[MS-WSSFO3\]](#) section 2.2.7.3.3.

#### Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed to a value that is not NULL or an empty value, and the <b>list</b> is an <b>external list</b> .

### 3.2.5.61.1.1.25 Scope

Type: **CSOM String**

Accessibility: Read Only

See **Microsoft.SharePoint.Client.Field.Scope**, as specified in section [3.2.5.37.1.1.16](#).

### 3.2.5.61.1.1.26 Sealed

Type: **CSOM Boolean**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.Sealed**, as specified in section [3.2.5.37.1.1.17](#).

### 3.2.5.61.1.1.27 SelectionGroup

Type: **CSOM Int32**

Accessibility: Read/Write

Specifies the identifier of the **group** whose **members** can be selected as values of the **field (2)**.

### 3.2.5.61.1.1.28 SelectionMode

Type: Microsoft.SharePoint.Client.FieldUserSelectionMode

Accessibility: Read/Write

Specifies whether users and **groups** or only users can be selected.

### 3.2.5.61.1.1.29 Sortable

Type: **CSOM Boolean**

Accessibility: Read Only

See **Microsoft.SharePoint.Client.Field.Sortable**, as specified in section [3.2.5.37.1.1.18](#).



### 3.2.5.61.1.1.30 StaticName

Type: **CSOM String**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.StaticName**, as specified in section [3.2.5.37.1.1.19](#).

Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed, and the <b>list</b> is an <b>external list</b> .

### 3.2.5.61.1.1.31 Title

Type: **CSOM String**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.Title**, as specified in section [3.2.5.37.1.1.20](#).

### 3.2.5.61.1.1.32 TypeAsString

Type: **CSOM String**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.TypeAsString**, as specified in section [3.2.5.37.1.1.21](#).

It MUST NOT be NULL. It MUST NOT be empty.

Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed, and the <b>list</b> is an <b>external list</b> .

### 3.2.5.61.1.1.33 TypeDisplayName

Type: **CSOM String**

Accessibility: Read Only

See **Microsoft.SharePoint.Client.Field.TypeDisplayName**, as specified in section [3.2.5.37.1.1.22](#).

It MUST NOT be NULL. It MUST NOT be empty.

### 3.2.5.61.1.1.34 TypeShortDescription

Type: **CSOM String**

Accessibility: Read Only

See **Microsoft.SharePoint.Client.Field.TypeShortDescription**, as specified in section [3.2.5.37.1.1.23](#).

It MUST NOT be NULL. It MUST NOT be empty.

### **3.2.5.61.1.1.35 ValidationFormula**

**Type:** CSOM String

**Accessibility:** Read/Write

See **Microsoft.SharePoint.Client.Field.ValidationFormula**, as specified in section [3.2.5.37.1.1.24](#).

### **3.2.5.61.1.1.36 ValidationMessage**

**Type:** CSOM String

**Accessibility:** Read/Write

See **Microsoft.SharePoint.Client.Field.ValidationMessage**, as specified in section [3.2.5.37.1.1.25](#).

Its length MUST be equal to or less than 1024.

### **3.2.5.61.1.1.37 Indexed**

**Type:** CSOM Boolean

**Accessibility:** Read Only

A bit that specifies whether the **field (2)** is an **indexed field**.

### **3.2.5.61.1.1.38 JSLink**

**Type:** CSOM String

**Accessibility:** Read/Write

Gets the name of an external ECMAScript ([\[ECMA-262-1999\]](#)) file containing any logic for this **field (2)**.

### **3.2.5.61.1.1.39 EntityPropertyName**

**Type:** CSOM String

**Accessibility:** Read Only

Gets the name of the entity property of this **field (2)** in the **list item** entity that uses this field (2).

It MUST NOT be NULL. It MUST NOT be empty.

### **3.2.5.61.1.1.40 SchemaXmlWithResourceTokens**

**Type:** CSOM String

**Accessibility:** Read Only

Gets the unlocalized schema XML for this **field (2)**.

### **3.2.5.61.1.1.41 AutoIndexed**

**Type:** CSOM Boolean

**Accessibility:** Read Only

Gets the Boolean value that specifies whether or not the field is auto-indexed. Specify a value of true if the field is auto-indexed; false if otherwise.

#### **3.2.5.61.1.1.42 ClientSideComponentId**

**Type:** CSOM GUID

**Accessibility:** Read/Write

The unique identifier of the client-side component defined with SharePoint Framework.

#### **3.2.5.61.1.1.43 ClientSideComponentProperties**

**Type:** CSOM String

**Accessibility:** Read/Write

This property is only used when a **ClientSideComponentId** is specified. It is optional. If non-empty, the string MUST contain a JSON object with custom initialization properties whose format and meaning are defined by the client-side component.

#### **3.2.5.61.1.1.44 CustomFormatter**

**Type:** CSOM String

**Accessibility:** Read/Write

A JSON string representing the custom rendering format of the field.

#### **3.2.5.61.1.1.45 DefaultFormula**

**Type:** CSOM String

**Accessibility:** Read/Write

Gets or sets the default formula for a calculated field.

#### **3.2.5.61.1.1.46 DependentLookupInternalNames**

**Type:** CSOM array of CSOM String

**Accessibility:** Read Only

Specifies the internal names of all the dependent lookups based on this primary lookup.

#### **3.2.5.61.1.1.47 IsDependentLookup**

**Type:** CSOM Boolean

**Accessibility:** Read Only

Check whether a lookup field is a dependent lookup field.

#### **3.2.5.61.1.1.48 NoCrawl**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Gets or sets a Boolean value that specifies whether the field can be crawled by a search engine.

### **3.2.5.61.1.1.49 PinnedToFiltersPane**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Boolean value that indicates whether the field pins to filter pane.

### **3.2.5.61.1.1.50 ShowInFiltersPane**

**Type:** Microsoft.SharePoint.Client.ShowInFiltersPaneStatus

**Accessibility:** Read/Write

Indicates whether the field will be shown.

### **3.2.5.61.1.1.51 UnlimitedLengthInDocumentLibrary**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Gets or sets a Boolean value that specifies whether to allow values with unlimited text in the lookup field.

## **3.2.5.61.1.2 ObjectPath Properties**

### **3.2.5.61.1.2.1 DescriptionResource**

**Type:** Microsoft.SharePoint.Client.UserResource

**Accessibility:** Read Only

Gets the resource object corresponding to the **Description** property for a field.

### **3.2.5.61.1.2.2 TitleResource**

**Type:** Microsoft.SharePoint.Client.UserResource

**Accessibility:** Read Only

Gets the resource object corresponding to the **Title** property for a field.

## **3.2.5.61.2 Methods**

### **3.2.5.61.2.1 Scalar Methods**

#### **3.2.5.61.2.1.1 DeleteObject**

**Return Type:** None

Deletes the **field (2)** from the **list**, from the **site (2)**, or from the **content types** within the list.

**Parameters:** None

**Exceptions:**

Error Code	Error Type Name	Condition
-1	System.InvalidOperationException	<b>CanBeDeleted</b> is "false".

### 3.2.5.61.2.1.2 SetShowInDisplayForm

**Return Type:** None

Sets this field to show or hide in the display form.

**Parameters:**

*value:* A Boolean value that indicates whether this field is shown in the display form.

Type: **CSOM Boolean**

### 3.2.5.61.2.1.3 SetShowInEditForm

**Return Type:** None

Sets this field to show or hide in the edit form.

**Parameters:**

*value:* A Boolean value that indicates whether this field is shown in the edit form.

Type: **CSOM Boolean**

### 3.2.5.61.2.1.4 SetShowInNewForm

**Return Type:** None

Sets this field to show or hide in the new form.

**Parameters:**

*value:* A Boolean value that indicates whether this field is shown in the new form.

Type: **CSOM Boolean**

### 3.2.5.61.2.1.5 Update

**Return Type:** None

Commits changed properties of the **field (2)**.

**Parameters:** None

**Exceptions:**

Error Code	Error Type Name	Condition
-2130246331	Microsoft.SharePoint.SPException	Type of the field (2) is changed for an <b>indexed field</b> . The field type of indexed fields cannot be changed.
-2130246238	Microsoft.SharePoint.SPException	Field (2) is set to not be an indexed field, and <b>EnforceUniqueValues</b> is "true".

Error Code	Error Type Name	Condition
- 2130246236	Microsoft.SharePoint.SPException	Type of the field (2) is being changed and <b>EnforceUniqueValues</b> of the field (2) is "true".

### 3.2.5.61.2.1.6 UpdateAndPushChanges

**Return Type:** None

Commits changed properties of the **field (2)** and propagates changes to all **lists** that use the field (2).

**Parameters:**

*pushChangesToLists*: Specifies whether to propagate changes to all lists that use the field (2).

Type: **CSOM Boolean**

**Exceptions:**

Error Code	Error Type Name	Condition
- 2130246331	Microsoft.SharePoint.SPException	Type of the field (2) is changed for an <b>indexed field</b> . The field type of indexed fields cannot be changed.
- 2130246238	Microsoft.SharePoint.SPException	Field (2) is set to not be an indexed field, and <b>EnforceUniqueValues</b> is "true".
- 2130246236	Microsoft.SharePoint.SPException	Type of the field (2) is being changed and <b>EnforceUniqueValues</b> of the field (2) is "true".

### 3.2.5.61.2.1.7 ValidateSetValue

**Return Type:** None

Validates and sets the value of the **field (2)** for the **list item** based on an implementation-specific transformation of the value. [<31>](#)

**Parameters:**

*item*: Specifies the list item to be updated with the new value.

Type: Microsoft.SharePoint.Client.ListItem

It MUST NOT be NULL.

*value*: Specifies the new value for the field (2).

Type: **CSOM String**

### 3.2.5.61.2.2 ObjectPath Methods

None.

### **3.2.5.62 Microsoft.SharePoint.Client.FieldUserSelectionMode**

**ShortName:** SP.FieldUserSelectionMode

**Flag:** false

Specifies the selection mode for field values from the column of user type.

#### **3.2.5.62.1 Field Values**

##### **3.2.5.62.1.1 PeopleOnly**

**Value:** 0

Specifies that only individual users can be selected.

##### **3.2.5.62.1.2 PeopleAndGroups**

**Value:** 1

Specifies that both individuals and groups can be selected.

### **3.2.5.63 Microsoft.SharePoint.Client.FieldUserValue**

**TypeId:** {C956AB54-16BD-4C18-89D2-996F57282A6F}

**ShortName:** SP.FieldUserValue

SP.FieldUserValue: field value class for SP.FieldUser (User field)

#### **3.2.5.63.1 Properties**

##### **3.2.5.63.1.1 Scalar Properties**

###### **3.2.5.63.1.1.1 Email**

**Type:** CSOM String

**Accessibility:** Read Only

Gets the Email of the user from the lookup string or SP.User object.

###### **3.2.5.63.1.1.2 LookupId**

**Type:** CSOM Int32

**Accessibility:** Read/Write

Gets or sets the identifier (ID) of the lookup field.

###### **3.2.5.63.1.1.3 LookupValue**

**Type:** CSOM String

**Accessibility:** Read Only

Gets the value of the user field as a string.

##### **3.2.5.63.1.2 ObjectPath Properties**

None.

### 3.2.5.64 Microsoft.SharePoint.Client.File

**TypeId:** {DF28BE1E-74B5-4B21-B73A-2BBAC0A23D8A}

**ShortName:** SP.File

Represents a file in a **site (2)** that can be a **Web Part Page**, an item in a **document library**, or a file in a folder.

The ListId, PageRenderType, ServerRelativePath, SiteId and WebId properties are not included in the **default scalar property set** for this type.

#### 3.2.5.64.1 Properties

##### 3.2.5.64.1.1 Scalar Properties

###### 3.2.5.64.1.1.1 CheckInComment

**Type:** CSOM String

**Accessibility:** Read Only

Specifies the comment used when a document is checked into a **document library**.

Its length MUST be equal to or less than 1023.

###### 3.2.5.64.1.1.2 CheckOutType

**Type:** Microsoft.SharePoint.Client.CheckOutType

**Accessibility:** Read Only

Specifies the type of **check out** on the **file**.

###### 3.2.5.64.1.1.3 CustomizedPageStatus

**Type:** Microsoft.SharePoint.Client.CustomizedPageStatus

**Accessibility:** Read Only

Specifies the customization status of the file.

###### 3.2.5.64.1.1.4 ETag

**Type:** CSOM String

**Accessibility:** Read Only

Specifies the **ETag** (see [\[RFC2616\]](#)) value.

#### Exceptions:

Error Code	Error Type Name	Condition
-2147024894	System.IO.FileNotFoundException	File cannot be found.



### 3.2.5.64.1.1.5 **Exists**

**Type:** CSOM Boolean

**Accessibility:** Read Only

Specifies whether the file exists.

### 3.2.5.64.1.1.6 **Level**

**Type:** Microsoft.SharePoint.Client.FileLevel

**Accessibility:** Read Only

Specifies the **publishing level** of the file.

#### **Exceptions:**

Error Code	Error Type Name	Condition
-2147024894	System.IO.FileNotFoundException	File cannot be found.

### 3.2.5.64.1.1.7 **MajorVersion**

**Type:** CSOM Int32

**Accessibility:** Read Only

Specifies the **major version** of the file.

#### **Exceptions:**

Error Code	Error Type Name	Condition
-2147024894	System.IO.FileNotFoundException	File cannot be found.

### 3.2.5.64.1.1.8 **MinorVersion**

**Type:** CSOM Int32

**Accessibility:** Read Only

Specifies the **minor version** of the file.

#### **Exceptions:**

Error Code	Error Type Name	Condition
-2147024894	System.IO.FileNotFoundException	File cannot be found.

### 3.2.5.64.1.1.9 **Name**

**Type:** CSOM String

**Accessibility:** Read Only

Specifies the file name including the extension.

It MUST NOT be NULL. Its length MUST be equal to or less than 260.

**Exceptions:**

Error Code	Error Type Name	Condition
-2147024894	System.IO.FileNotFoundException	File cannot be found.

### 3.2.5.64.1.1.10 ServerRelativeUrl

**Type:** CSOM String

**Accessibility:** Read Only

Specifies the **server-relative URL** of the file.

It MUST NOT be NULL. It MUST be a URL of server-relative form.

### 3.2.5.64.1.1.11 TimeCreated

**Type:** CSOM DateTime

**Accessibility:** Read Only

Specifies when the file was created.

**Exceptions:**

Error Code	Error Type Name	Condition
-2147024894	System.IO.FileNotFoundException	File cannot be found.

### 3.2.5.64.1.1.12 TimeLastModified

**Type:** CSOM DateTime

**Accessibility:** Read Only

Specifies when the file was last modified.

**Exceptions:**

Error Code	Error Type Name	Condition
-2147024894	System.IO.FileNotFoundException	File cannot be found.

### 3.2.5.64.1.1.13 Title

**Type:** CSOM String

**Accessibility:** Read Only

Specifies the **display name** of the file.

**Exceptions:**

Error Code	Error Type Name	Condition
-2147024894	System.IO.FileNotFoundException	File cannot be found.

### 3.2.5.64.1.1.14 UIVersion

**Type:** CSOM Int32

**Accessibility:** Read Only

Specifies the implementation-specific version identifier of the file.

**Exceptions:**

Error Code	Error Type Name	Condition
-2147024894	System.IO.FileNotFoundException	File cannot be found.

### 3.2.5.64.1.1.15 UIVersionLabel

**Type:** CSOM String

**Accessibility:** Read Only

Specifies the implementation-specific version identifier of the file.

It MUST NOT be NULL.

**Exceptions:**

Error Code	Error Type Name	Condition
-2147024894	System.IO.FileNotFoundException	File cannot be found.

### 3.2.5.64.1.1.16 Length

**Type:** CSOM Int64

**Accessibility:** Read Only

Specifies the size of the file in bytes, excluding the size of any **Web Parts** that are used in the file. [<32>](#)

**Exceptions:**

Error Code	Error Type Name	Condition
-2147024894	System.IO.FileNotFoundException	File cannot be found.
-2147024891	System.UnauthorizedAccessException	Lack of permissions to perform the operation.

### 3.2.5.64.1.1.17 ContentTag

Type: **CSOM String**

Accessibility: Read Only

Returns internal version of content, used to validate document equality for read purposes.

### 3.2.5.64.1.1.18 IrmEnabled

Type: **CSOM Boolean**

Accessibility: Read/Write

Specifies whether or not Information Rights Management (IRM) is enabled at the file level. A value of true indicates IRM is enabled; a value of false indicates IRM is disabled.

### 3.2.5.64.1.1.19 LinkingUrl

Type: **CSOM String**

Accessibility: Read Only

Specifies the URL that is suitable for durable linking to the file.

For file types that do not support durable linking, an empty string is returned.

It MUST NOT be NULL.

### 3.2.5.64.1.1.20 UniqueId

Type: **CSOM GUID**

Accessibility: Read/Write

Gets the GUID that uniquely identifies the file in the content database.

### 3.2.5.64.1.1.21 LinkingUri

Type: **CSOM String**

Accessibility: Read Only

Specifies the URL that is suitable for durable linking to the file.

It MUST NOT be NULL.

### 3.2.5.64.1.1.22 ListId

Type: **CSOM GUID**

Accessibility: Read Only

Gets the GUID that uniquely identifies the list/document library containing the file.

### 3.2.5.64.1.1.23 PageRenderType

**Type:** Microsoft.SharePoint.Client.ListPageRenderType

**Accessibility:** Read Only

Returns the render type of the current file. If the file will render in modern experience which is compelling, flexible and more performant, it'll return **ListPageRenderType.Modern**. If the file will render in classic experience, it'll return the reason for staying in classic, as specified by **ListPageRenderType** enumeration (section [3.2.5.413](#)).

### 3.2.5.64.1.1.24 ServerRelativePath

**Type:** Microsoft.SharePoint.Client.ResourcePath

**Accessibility:** Read Only

Specifies the relative path of the file based on the URL for the server.

### 3.2.5.64.1.1.25 SiteId

**Type:** CSOM GUID

**Accessibility:** Read Only

Gets the GUID that identifies the site collection containing the file.

### 3.2.5.64.1.1.26 WebId

**Type:** CSOM GUID

**Accessibility:** Read Only

Gets the GUID for the site containing the file.

## 3.2.5.64.1.2 ObjectPath Properties

### 3.2.5.64.1.2.1 Author

**Type:** Microsoft.SharePoint.Client.User

**Accessibility:** Read Only

Specifies the user who added the file.

**Exceptions:**

Error Code	Error Type Name	Condition
-2147024894	System.IO.FileNotFoundException	File cannot be found.

### 3.2.5.64.1.2.2 CheckedOutByUser

**Type:** Microsoft.SharePoint.Client.User

**Accessibility:** Read Only

Specifies the user who has checked out the **file**.

### **3.2.5.64.1.2.3 EffectiveInformationRightsManagementSettings**

**Type:** Microsoft.SharePoint.Client.EffectiveInformationRightsManagementSettings

**Accessibility:** Read Only

Returns the effective Information Rights Management (IRM) settings for the file.

A file can be IRM-protected based on the IRM settings for the file itself, based on the IRM settings for the list which contains the file, or based on a rule. From greatest to least, IRM settings take precedence in the following order: rule, list, then file.

### **3.2.5.64.1.2.4 InformationRightsManagementSettings**

**Type:** Microsoft.SharePoint.Client.InformationRightsManagementFileSettings

**Accessibility:** Read Only

Returns the Information Rights Management (IRM) settings for the file.

### **3.2.5.64.1.2.5 ListItemAllFields**

**Type:** Microsoft.SharePoint.Client.ListItem

**Accessibility:** Read Only

Specifies the **list item field (2)** values for the list item corresponding to the file.

### **3.2.5.64.1.2.6 LockedByUser**

**Type:** Microsoft.SharePoint.Client.User

**Accessibility:** Read Only

Specifies the user that owns the current lock on the file.

MUST return null if there is no lock.

#### **Exceptions:**

<b>Error Code</b>	<b>Error Type Name</b>	<b>Condition</b>
-2147024894	System.IO.FileNotFoundException	File cannot be found.

### **3.2.5.64.1.2.7 ModifiedBy**

**Type:** Microsoft.SharePoint.Client.User

**Accessibility:** Read Only

Specifies the user who last modified the file.

## Exceptions:

Error Code	Error Type Name	Condition
-2147024894	System.IO.FileNotFoundException	File cannot be found.

### 3.2.5.64.1.2.8 Properties

**Type:** Microsoft.SharePoint.Client.PropertyValues

**Accessibility:** Read Only

Gets a collection of all the properties for the file.

It MUST NOT be NULL.

### 3.2.5.64.1.2.9 VersionEvents

**Type:** Microsoft.SharePoint.Client.FileVersionEventCollection

**Accessibility:** Read Only

Gets the history of events on this version object.

### 3.2.5.64.1.2.10 Versions

**Type:** Microsoft.SharePoint.Client.FileVersionCollection

**Accessibility:** Read Only

Specifies a collection of file version **objects (1)** that represent the versions of the file.

It MUST NOT be NULL.

## 3.2.5.64.2 Methods

### 3.2.5.64.2.1 Scalar Methods

#### 3.2.5.64.2.1.1 CheckIn

**Return Type:** None

Checks the **file** in to a **document library** based on the check-in type.

**Parameters:**

*comment:* Specifies a comment for the check-in.

Type: **CSOM String**

Its length MUST be equal to or less than 1023.

*checkInType:* Specifies the type of check-in.

Type: Microsoft.SharePoint.Client.CheckinType

#### 3.2.5.64.2.1.2 CheckOut

**Return Type:** None

Checks out the **file** from a **document library**.

**Parameters:** None

**Exceptions:**

Error Code	Error Type Name	Condition
-2130575306	Microsoft.SharePoint.SPFileCheckOutException	File is already checked out.
-2147024891	System.UnauthorizedAccessException	Check-out arguments are not valid.

### 3.2.5.64.2.1.3 CopyTo

**Return Type:** None

Copies the file to the destination **URL**. The protocol server MUST overwrite an existing **file** of the same name if *bOverWrite* is "true".

**Parameters:**

*strNewUrl*: Specifies the destination URL.

Type: **CSOM String**

It MUST NOT be NULL. It MUST be a URL of relative or absolute form.

*bOverWrite*: Specifies whether a file with the same name is overwritten.

Type: **CSOM Boolean**

**Exceptions:**

Error Code	Error Type Name	Condition
-2147024729	Microsoft.SharePoint.SPFileLockException	File is not <b>locked</b> by the current user
-2147018894	Microsoft.SharePoint.SPFileLockException	A user other than the <b>current user</b> has a <b>shared lock</b> on the file
-2147018887	Microsoft.SharePoint.SPFileLockException	A user other than the current user has an <b>exclusive lock</b> on the file

### 3.2.5.64.2.1.4 DeleteObject

**Return Type:** None

Deletes the file.

**Parameters:** None

**Exceptions:**



Error Code	Error Type Name	Condition
-2147018894	Microsoft.SharePoint.SPFileLockException	Shared lock on the file.
-2147018887	Microsoft.SharePoint.SPFileLockException	<b>Exclusive lock</b> on the file.
-2147024894	System.IO.FileNotFoundException	File cannot be found.

### 3.2.5.64.2.1.5 MoveTo

**Return Type:** None

Moves the file to the specified destination URL.

**Parameters:**

*newUrl*: Specifies the destination URL.

Type: **CSOM String**

It MUST NOT be NULL. It MUST be a URL of relative or absolute form.

*flags*: Specifies the kind of move operation.

Type: Microsoft.SharePoint.Client.MoveOperations

MUST NOT have flags other than **MoveOperations.Overwrite** or **MoveOperations.AllowBrokenThickets** set.

**Exceptions:**

Error Code	Error Type Name	Condition
-2147024729	Microsoft.SharePoint.SPFileLockException	File is not locked by the current user.
-2147018894	Microsoft.SharePoint.SPFileLockException	A user other than the current user has a shared lock on the file.
-2147018887	Microsoft.SharePoint.SPFileLockException	A user other than the current user has an exclusive lock on the file.

### 3.2.5.64.2.1.6 Publish

**Return Type:** None

Submits the file for content approval with the specified comment.

**Parameters:**

*comment*: Specifies the comment.

Type: **CSOM String**

Its length MUST be equal to or less than 1023.

**Exceptions:**

Error Code	Error Type Name	Condition
-1	Microsoft.SharePoint.SPException	The user can only publish or unpublish documents in a minor version enabled <b>list</b> . The user cannot perform this action on a checked out document. The user can only unpublish a major version or approved document.
-2147024729	Microsoft.SharePoint.SPFileLockException	The file is not locked by the current user.
-2147018894	Microsoft.SharePoint.SPFileLockException	A user other than the current user has a shared lock on the file.
-2147018887	Microsoft.SharePoint.SPFileLockException	A user other than the current user has an exclusive lock on the file.

### 3.2.5.64.2.1.7 Recycle

**Return Type:** CSOM GUID

Moves the file to the **Recycle Bin** and returns the identifier of the new **Recycle Bin item**.

**Parameters:** None

**Exceptions:**

Error Code	Error Type Name	Condition
-2147018894	Microsoft.SharePoint.SPFileLockException	<b>Shared lock</b> on the file.
-2147018887	Microsoft.SharePoint.SPFileLockException	<b>Exclusive lock</b> on the file.
-2147024894	System.IO.FileNotFoundException	File cannot be found.

### 3.2.5.64.2.1.8 SaveBinary

**Return Type:** None

Saves the specified **file** into a **document library**.

**Parameters:**

*parameters:* An **object (1)** to facilitate updating the content of a file.

Type: Microsoft.SharePoint.Client.FileSaveBinaryInformation

It MUST NOT be NULL.

**Exceptions:**

Error Code	Error Type Name	Condition
-2147018894	Microsoft.SharePoint.SPFileLockException	<b>Shared lock</b> is on the file.

### 3.2.5.64.2.1.9 UndoCheckOut

**Return Type:** None

Reverts an existing checkout for the file.

**Parameters:** None

### 3.2.5.64.2.1.10 UnPublish

**Return Type:** None

Removes the file from content approval or unpublishes a **major version**.

**Parameters:**

*comment*: Specifies the comment for **UnPublish**.

Type: **CSOM String**

Its length MUST be equal to or less than 1023.

**Exceptions:**

Error Code	Error Type Name	Condition
- 2147024729	Microsoft.SharePoint.SPFileLockException	File is not locked by the current user.
- 2147018894	Microsoft.SharePoint.SPFileLockException	A user other than the current user has a shared lock on the file.
- 2147018887	Microsoft.SharePoint.SPFileLockException	A user other than the current user has an exclusive lock on the file.

### 3.2.5.64.2.1.11 OpenBinaryStream

**Return Type:** **CSOM Stream**

Opens the file as a **stream**.<33>

**Parameters:** None

### 3.2.5.64.2.1.12 SaveBinaryStream

**Return Type:** None

Saves the file in binary format.<34>

**Parameters:**

*file*: A stream containing the contents of the specified file.

Type: **CSOM Stream**

### 3.2.5.64.2.1.13 Approve

**Return Type:** None

Approves the **file** submitted for content approval with the specified comment.

**Parameters:**

*comment*: A string containing the comment.

Type: **CSOM String**

### **3.2.5.64.2.1.14 Deny**

**Return Type:** None

Denies the **file** submitted for content approval.

**Parameters:**

*comment*: A string containing a comment about the denial.

Type: **CSOM String**

### **3.2.5.64.2.1.15 GetContentVerFromTag**

This method is a **static CSOM method**.

**Return Type:** **CSOM Int32**

Reserved for internal use only. This method exposes the internal **ContentVersion** value inside of a **ContentTag**.

**Parameters:**

*contentTag*: Specifies the **ContentTag** from which the **ContentVersion** will be obtained.

Type: **CSOM String**

### **3.2.5.64.2.1.16 CancelUpload**

**Return Type:** None

Aborts the chunk upload session without saving the uploaded data. If **StartUpload** (section [3.2.5.64.2.1.22](#)) created the file, the file will be deleted.

**Parameters:**

*uploadId*: The upload session ID.

Type: **CSOM GUID**

### **3.2.5.64.2.1.17 ContinueUpload**

**Return Type:** **CSOM Int64**

Continues a chunk upload session with another fragment; the current file content is not changed.

**Parameters:**

*uploadId*: The upload session ID.

Type: **CSOM GUID**

*fileOffset*: The file offset where the fragment starts.

Type: CSOM Int64

*stream*: The stream containing the fragment.

Type: **CSOM Stream**

### **3.2.5.64.2.1.18 ExecuteCobaltRequest**

**Return Type:** **CSOM Stream**

Executes a Cobalt request against the file. Input can be serialized as either FssHttp ([\[MS-FSSHTTP\]](#)) or FssHttpB ([\[MS-FSSHTTPB\]](#)). The protocol being used is automatically detected.

**Parameters:**

*inputStream*: The input stream containing the FssHttp/FssHttpB Cobalt request.

Type: CSOM Stream

### **3.2.5.64.2.1.19 GetImagePreviewUrl**

**Return Type:** **CSOM String**

Returns the URL of the thumbnail with a size closest to the specified size; the actual resolution of the thumbnail might not be the same as the desired value.

**Parameters:**

*width*: The desired width of the resolution.

Type: **CSOM Int32**

*height*: The desired height of the resolution.

Type: CSOM Int32

*clientType*: The client type. This is used for logging purposes.

Type: CSOM String

### **3.2.5.64.2.1.20 GetPreAuthorizedAccessUrl**

**Return Type:** **CSOM String**

Returns a link for downloading the file without authentication.

**Parameters:**

*expirationHours*: The number of hours until the link expires.

Type: **CSOM Int32**

If the maximum expiration time defined in the web application is less than the specified expiration time, the maximum expiration time takes precedence.

### **3.2.5.64.2.1.21 GetWOPIFrameUrl**

**Return Type:** **CSOM String**

Returns the full URL to the SharePoint frame page that will initiate the specified WOPI frame action with the file's associated WOPI application. If there is no associated WOPI application or associated action, the return value is an empty string.

**Parameters:**

*action*: The full URL to the WOPI frame.

Type: Microsoft.SharePoint.Client.Utilities.SPWOPIFrameAction

### 3.2.5.64.2.1.22 StartUpload

**Return Type:** CSOM Int64

Returns the uploaded data's size (in bytes) after an upload chunk session is started and the first fragment is uploaded. The current file content is not changed. This method is idempotent when called with the same parameter values for *uploadId* and *stream*. Use the **ContinueUpload** method (section [3.2.5.64.2.1.17](#)) to initiate chunk upload sessions for further fragments.

**Parameters:**

*uploadId*: The upload session ID used for subsequent chunk upload sessions.

Type: CSOM GUID

*stream*: The stream containing the first fragment

Type: CSOM Stream

### 3.2.5.64.2.1.23 Update

**Return Type:** None

Updates the database with changes made to the file.

**Parameters:** None

### 3.2.5.64.2.1.24 CopyToUsingPath

**Return Type:** None

Copies the file to the destination path. Server MUST overwrite an existing file of the same name if *bOverwrite* is true.

**Parameters:**

*newPath*: Specifies the destination path.

Type: Microsoft.SharePoint.Client.ResourcePath

It MUST NOT be NULL.

*bOverWrite*: Specifies whether a file with the same name is overwritten.

Type: CSOM Boolean

**Exceptions:**

Error Code	Error Type Name	Condition
-2147024729	Microsoft.SharePoint.SPFileLockException	The file is not locked

Error Code	Error Type Name	Condition
-2147018894	Microsoft.SharePoint.SPFileLockException	There is a shared lock on the file
-2147018887	Microsoft.SharePoint.SPFileLockException	There is an exclusive lock on the file

### 3.2.5.64.2.1.25 **GetImagePreviewUri**

#### Return Type: **CSOM String**

Returns the uri where the thumbnail with the closest size to the desired can be found. The actual resolution of the thumbnail might not be the same as the desired values.

#### Parameters:

*width*: The desired width of the resolution.

Type: **CSOM Int32**

*height*: The desired height of the resolution.

Type: CSOM Int32

*clientType*: The client type. Used for logging.

Type: CSOM String

### 3.2.5.64.2.1.26 **MoveToUsingPath**

#### Return Type: None

Moves the file to the specified destination path.

#### Parameters:

*newPath*: Specifies the destination path.

Type: Microsoft.SharePoint.Client.ResourcePath

It MUST NOT be NULL.

*moveOperations*: Specifies the kind of move operation.

Type: Microsoft.SharePoint.Client.MoveOperations

MUST be MoveOperations.Overwrite OR MoveOperations.AllowBrokenThickets

#### Exceptions:

Error Code	Error Type Name	Condition
-2147024729	Microsoft.SharePoint.SPFileLockException	The file is not locked
-2147018894	Microsoft.SharePoint.SPFileLockException	There is a shared lock on the file
-2147018887	Microsoft.SharePoint.SPFileLockException	There is an exclusive lock on the file

### 3.2.5.64.2.1.27 OpenBinaryStreamWithOptions

**Return Type:** CSOM Stream

Opens the file as a stream.

**Parameters:**

*openOptions:* Options to use when opening the file.

Type: Microsoft.SharePoint.Client.SPOpenBinaryOptions

### 3.2.5.64.2.1.28 RecycleWithETag

**Return Type:** CSOM GUID

Moves the file to the recycle bin if the specified etag value matches with the current file eTag. MUST return the identifier of the new Recycle Bin item.

**Parameters:**

*etagMatch:* The **ETag** to verify before recycling the file.

Type: CSOM String

It MUST NOT be NULL. It MUST NOT be empty.

**Exceptions:**

Error Code	Error Type Name	Condition
-2147018894	Microsoft.SharePoint.SPFileLockException	There is a shared lock on the file
-2147018887	Microsoft.SharePoint.SPFileLockException	There is an exclusive lock on the file
-2147024894	System.IO.FileNotFoundException	File cannot be found.

### 3.2.5.64.2.1.29 UpdateVirusInfo

**Return Type:** None

Updates the virus info.

**Parameters:**

*virusStatus:* The virus infection status of the file.

Type: Microsoft.SharePoint.Client.SPVirusCheckStatus

*virusMessage:* The information about the virus infection.

Type: CSOM String

*etagToCheck:* The **ETag** against which the virus scan was performed.

Type: CSOM String

### 3.2.5.64.2.2 ObjectPath Methods



### 3.2.5.64.2.2.1 GetLimitedWebPartManager

**Return Type:** Microsoft.SharePoint.Client.WebParts.LimitedWebPartManager

Specifies the controls used to access, modify, or add **Web Parts** associated with this **Web Part Page** and view. A **reference** to the requested SP.WebParts.LimitedWebPartManager is returned.

**Parameters:**

*scope:* Specifies the **personalization scope** value that depicts how Web Parts are viewed on the Web Part Page.

Type: Microsoft.SharePoint.Client.WebParts.PersonalizationScope

**Exceptions:**

Error Code	Error Type Name	Condition
-1	Microsoft.SharePoint.SPException	<b>URL</b> does not have an extension of ".aspx".
-2147024894	System.IO.FileNotFoundException	New initialized instance of Web Part manager does not exist.

### 3.2.5.64.2.2.2 FinishUpload

**Return Type:** Microsoft.SharePoint.Client.File

Returns the current file after a chunk upload session uploads the last fragment.

**Parameters:**

*uploadId:* The upload session ID.

Type: **CSOM GUID**

*fileOffset:* The file offset where the last fragment starts.

Type: **CSOM Int64**

*stream:* The stream containing the fragment.

Type: **CSOM Stream**

### 3.2.5.64.2.2.3 GetUploadStatus

**Return Type:** Microsoft.SharePoint.Client.Utilities.UploadStatus

Gets the status of a chunk upload session.

**Parameters:**

*uploadId:* The upload session ID.

Type: **CSOM GUID**

### 3.2.5.65 Microsoft.SharePoint.Client.FileCollection

**TypeId:** {D367B17C-170B-4691-A1E3-8BCCF7686CE4}

**ShortName:** SP.FileCollection

A collection of file **objects (1)**.

### 3.2.5.65.1 Properties

#### 3.2.5.65.1.1 Scalar Properties

None.

#### 3.2.5.65.1.2 ObjectPath Properties

None.

### 3.2.5.65.2 Methods

#### 3.2.5.65.2.1 Scalar Methods

None.

#### 3.2.5.65.2.2 ObjectPath Methods

##### 3.2.5.65.2.2.1 Add

**Return Type:** Microsoft.SharePoint.Client.File

Adds a **file** to the collection based on provided file creation information. A **reference** to the SP.File that was added is returned.

**Parameters:**

*parameters:* File creation information

Type: Microsoft.SharePoint.Client.FileCreationInformation

It MUST NOT be NULL.

**Exceptions:**

Error Code	Error Type Name	Condition
- 2147024729	Microsoft.SharePoint.SPFileLockException	The file to be added or overwritten in the collection is not locked by the current user.
- 2147018894	Microsoft.SharePoint.SPFileLockException	There is a <b>shared lock</b> on the file to be added or overwritten in the collection by the other user.
- 2147018887	Microsoft.SharePoint.SPFileLockException	There is an <b>exclusive lock</b> on the file to be added or overwritten in the collection by the current user.

##### 3.2.5.65.2.2.2 AddStub

**Return Type:** Microsoft.SharePoint.Client.File

Returns the file after adding a new file stub which data will later be uploaded to.

**Parameters:**

*urlOfFile:* The **server-relative URL** for the **file**.

Type: **CSOM String**

### 3.2.5.65.2.2.3 AddStubUsingPath

**Return Type:** Microsoft.SharePoint.Client.File

Add a new file stub which the data will be uploaded later.

**Parameters:**

*pathOfFile:* The path for the file. It MUST NOT be NULL or empty.

Type: Microsoft.SharePoint.Client.ResourcePath

### 3.2.5.65.2.2.4 AddTemplateFile

**Return Type:** Microsoft.SharePoint.Client.File

Adds an **uncustomized** file to an existing **list** or **document library**. A **reference** to the SP.File that was added is returned.

**Parameters:**

*urlOfFile:* The **server-relative URL** of the file.

Type: **CSOM String**

It MUST NOT be NULL. It MUST NOT be empty.

*templateFileType:* Specifies the template **file** type used for file creation.

Type: Microsoft.SharePoint.Client.TemplateFileType

The *templateFileType* MUST be of standard or Wiki **site (2)** or **form** type.

### 3.2.5.65.2.2.5 AddUsingPath

**Return Type:** Microsoft.SharePoint.Client.File

Creates a file in the collection based on the specified path, a stream that contains a file, and optional settings for creating the file.

**Parameters:**

*path:* An **SP.ResourcePath** object (section [3.2.5.420](#)) that specifies the path for the file.

Type: Microsoft.SharePoint.Client.ResourcePath

It MUST NOT be NULL.

*parameters:* An **SP.FileCollectionAddParameters** object (section [3.2.5.398](#)) containing the various settings used for creating the file.

Type: Microsoft.SharePoint.Client.FileCollectionAddParameters

*contentStream:* A stream containing the content of the file.

Type: **CSOM Stream**

### 3.2.5.65.2.2.6 GetByPathOrAddStub

**Return Type:** Microsoft.SharePoint.Client.File

Get an **SP.File** object (section [3.2.5.64](#)) or add a new file stub to which the data will be uploaded later.

**Parameters:**

*pathOfFile:* An **SP.ResourcePath** (section [3.2.5.420](#)) that specifies the path for the file.

Type: Microsoft.SharePoint.Client.ResourcePath

### 3.2.5.65.2.2.7 GetByUrl

**Return Type:** Microsoft.SharePoint.Client.File

Get the **file** at the specified **URL**.

**Parameters:**

*url:* The **server-relative URL** for the file.

Type: **CSOM String**

### 3.2.5.65.2.2.8 GetByUrlOrAddStub

**Return Type:** Microsoft.SharePoint.Client.File

Returns the file or adds a new file stub which data will later be uploaded to.

**Parameters:**

*urlOfFile:* The **server-relative URL** for the **file**.

Type: **CSOM String**

## 3.2.5.66 Microsoft.SharePoint.Client.FileCreationInformation

**TypeId:** {F5C8173C-CAE6-4469-A7AF-3879CA3C617C}

**ShortName:** SP.FileCreationInformation

Represents a **file** to be added via **FileCollection.Add** as defined in section [3.2.5.65.2.2.1](#).

### 3.2.5.66.1 Properties

#### 3.2.5.66.1.1 Scalar Properties

##### 3.2.5.66.1.1.1 Content

Type: **CSOM binary**

**Accessibility:** Read/Write

Specifies the binary content of the **file** to be added.

##### 3.2.5.66.1.1.2 Overwrite

Type: **CSOM Boolean**

**Accessibility:** Read/Write

Specifies whether to overwrite an existing **file** with the same name and in the same location as the one being added.

### **3.2.5.66.1.1.3      Url**

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies the **URL** of the file to be added.

It MUST NOT be NULL. It MUST be a URL of relative or absolute form. Its length MUST be equal to or greater than 1.

### **3.2.5.66.1.1.4      ContentStream**

**Type:** CSOM Stream

**Accessibility:** Read/Write

The contents of the file as a **stream**.<35>

### **3.2.5.66.1.2    ObjectPath Properties**

None.

## **3.2.5.67      Microsoft.SharePoint.Client.FileLevel**

**ShortName:** SP.FileLevel

**Flag:** false

Specifies the type of version for a file.

### **3.2.5.67.1    Field Values**

#### **3.2.5.67.1.1    Published**

**Value:** 1

The current version of the file is published. Value=1.

#### **3.2.5.67.1.2    Draft**

**Value:** 2

The current version of the file is a draft. Value=2.

#### **3.2.5.67.1.3    Checkout**

**Value:** 255

The current version of the file is checked out to the current user. Value=255.

## **3.2.5.68      Microsoft.SharePoint.Client.FileSaveBinaryInformation**

**TypeId:** {C3DE0784-43E6-4F12-BD0C-F0D9A34EBF93}

**ShortName:** SP.FileSaveBinaryInformation

Contains information necessary for saving a **file**.

### **3.2.5.68.1 Properties**

#### **3.2.5.68.1.1 Scalar Properties**

##### **3.2.5.68.1.1.1 CheckRequiredFields**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Specifies whether required **fields (2)** in the **list** are validated when the **file** is saved.

If there are required fields (2) that have no value set, the save operation MUST fail.

##### **3.2.5.68.1.1.2 Content**

**Type:** CSOM binary

**Accessibility:** Read/Write

Specifies the content of the **file**.

The length MUST NOT be larger than 1,048,567 times the maximum file size for a **Web application**.

##### **3.2.5.68.1.1.3 ETag**

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies the **ETag** value, as specified in see [\[RFC2616\]](#).

If the **ETag** value is specified as not NULL, and no matching **ETag** can be found on the server the save operation MUST fail.

##### **3.2.5.68.1.1.4 ContentStream**

**Type:** CSOM Stream

**Accessibility:** Read/Write

The contents of the file as a **stream**.[<36>](#)

##### **3.2.5.68.1.1.5 FieldValues**

**Type:** CSOM dictionary

**Accessibility:** Read/Write

Updates the key value pairs representing properties of the file. The keys and values are implementation-specific.

#### **3.2.5.68.1.2 ObjectPath Properties**

None.

### 3.2.5.69 Microsoft.SharePoint.Client.FileSystemObjectType

**ShortName:** SP.FileSystemObjectType

**Flag:** false

Specifies the file system **object (1)** type.

#### 3.2.5.69.1 Field Values

##### 3.2.5.69.1.1 Invalid

**Value:** -1

It MUST NOT be used.

##### 3.2.5.69.1.2 File

**Value:** 0

Specifies the **object (1)** is a file.

##### 3.2.5.69.1.3 Folder

**Value:** 1

Specifies the **object (1)** is a folder.

##### 3.2.5.69.1.4 Web

**Value:** 2

Specifies the **object (1)** is a **site (2)**.

### 3.2.5.70 Microsoft.SharePoint.Client.FileVersion

**TypeId:** {96E4BC1B-E67F-4967-9327-36B79E20AEBC}

**ShortName:** SP.FileVersion

Represents a version of a **file object (1)**.

#### 3.2.5.70.1 Properties

##### 3.2.5.70.1.1 Scalar Properties

###### 3.2.5.70.1.1.1 CheckInComment

**Type:** CSOM String

**Accessibility:** Read Only

Specifies the check-in comment.

It MUST NOT be NULL. Its length MUST be equal to or less than 1023.

###### 3.2.5.70.1.1.2 Created

**Type:** CSOM DateTime

**Accessibility:** Read Only

Specifies the creation date and time for the file version.

### **3.2.5.70.1.1.3 ID**

**Type:** CSOM Int32

**Accessibility:** Read Only

Gets the internal identifier for the file version.

### **3.2.5.70.1.1.4 IsCurrentVersion**

**Type:** CSOM Boolean

**Accessibility:** Read Only

Specifies whether the **file version** is the **current version**.

### **3.2.5.70.1.1.5 Url**

**Type:** CSOM String

**Accessibility:** Read Only

Specifies the relative URL of the file version based on the **URL** for the **site (2)** or subsite.

It MUST NOT be empty. It MUST be a URL of relative form.

### **3.2.5.70.1.1.6 VersionLabel**

**Type:** CSOM String

**Accessibility:** Read Only

Specifies the implementation-specific identifier of the file.

It MUST NOT be NULL.

### **3.2.5.70.1.1.7 Size**

**Type:** CSOM Int32

**Accessibility:** Read Only

Gets the size of the file version in bytes.

Obsolete. Use **Length** (section [3.2.5.70.1.1.8](#)) instead.

This will throw an InvalidOperationException for versions larger than 2 gigabytes. Use Length instead.

### **3.2.5.70.1.1.8 Length**

**Type:** CSOM Int64

**Accessibility:** Read Only

Gets the length (in bytes) of the file version.



### 3.2.5.70.1.2 ObjectPath Properties

#### 3.2.5.70.1.2.1 CreatedBy

**Type:** Microsoft.SharePoint.Client.User

**Accessibility:** Read Only

Specifies the user that represents the person who created the file version.

### 3.2.5.70.2 Methods

#### 3.2.5.70.2.1 Scalar Methods

##### 3.2.5.70.2.1.1 DeleteObject

**Return Type:** None

Deletes the **file** version. <37>

**Parameters:** None

**Exceptions:**

Error Code	Error Type Name	Condition
- 2147024846	Microsoft.SharePoint.SPException	<b>Recycle Bin</b> is not enabled.
- 2147024891	System.UnauthorizedAccessException	The protocol client does not have permissions to update this file version.

##### 3.2.5.70.2.1.2 OpenBinaryStream

**Return Type:** **CSOM Stream**

Opens the **file** as a stream. Returns a System.IO.Stream object that contains the file version.

**Parameters:** None

#### 3.2.5.70.2.2 ObjectPath Methods

None.

### 3.2.5.71 Microsoft.SharePoint.Client.FileVersionCollection

**TypeId:** {3826E282-67A6-4861-88FB-474E8AAC897B}

**ShortName:** SP.FileVersionCollection

Represents a collection of **FileVersion objects (1)**.

#### 3.2.5.71.1 Properties

##### 3.2.5.71.1.1 Scalar Properties

None.

### 3.2.5.71.1.2 ObjectPath Properties

None.

### 3.2.5.71.2 Methods

#### 3.2.5.71.2.1 Scalar Methods

##### 3.2.5.71.2.1.1 DeleteAll

**Return Type:** None

Deletes all the file version **objects (1)** in the collection.

**Parameters:** None

**Exceptions:**

Error Code	Error Type Name	Condition
-2130575312	Microsoft.SharePoint.SPException	Specified file <b>URL</b> is invalid.

##### 3.2.5.71.2.1.2 DeleteByID

**Return Type:** None

Deletes the specified version of the file.

**Parameters:**

*vid*: Specifies the file version identifier to delete.

Type: **CSOM Int32**

The *vid* MUST NOT be zero.

**Exceptions:**

Error Code	Error Type Name	Condition
-2147024894	System.IO.FileNotFoundException	File with specified version identifier cannot be found.

##### 3.2.5.71.2.1.3 DeleteByLabel

**Return Type:** None

Deletes the file version **object (1)** with the specified version label.

**Parameters:**

*versionlabel*: Specifies the version label.

Type: **CSOM String**

It MUST NOT be NULL. It MUST NOT be empty. Version label MUST be the return value from the **VersionLabel** property of a Microsoft.Sharepoint.Client.FileVersion object (1).

**Exceptions:**

Error Code	Error Type Name	Condition
-2147024894	System.IO.FileNotFoundException	Specified version label is invalid.

### 3.2.5.71.2.1.4 RecycleByID

**Return Type:** None

Recycles the file version object with the specified version ID from the collection.

**Parameters:**

*vid*: Specifies the file version object to delete.

Type: **CSOM Int32**

Version Id cannot be zero.

**Exceptions:**

Error Code	Error Type Name	Condition
-2147024894	System.IO.FileNotFoundException	The specified version label is invalid.

### 3.2.5.71.2.1.5 RecycleByLabel

**Return Type:** None

Recycles the file version object with the specified version label.

**Parameters:**

*versionlabel*: Specifies the version label. The version label MUST be in the format n.n, for example, 3.1.

Type: **CSOM String**

It MUST NOT be NULL. It MUST NOT be empty. Version label MUST be the return value from VersionLabel property of a Microsoft.Sharepoint.Client.FileVersion object.

**Exceptions:**

Error Code	Error Type Name	Condition
-2147024894	System.IO.FileNotFoundException	The specified version label is invalid.

### 3.2.5.71.2.1.6 RestoreByLabel

**Return Type:** None

Creates a new file version from the file specified by the version label.

**Parameters:**

*versionlabel*: Specifies the version label.

Type: **CSOM String**

It MUST NOT be NULL. It MUST NOT be empty. Version label MUST be the return value from VersionLabel property of a **Microsoft.SharePoint.Client.FileVersion object (1)**.

### 3.2.5.71.2.2 ObjectPath Methods

#### 3.2.5.71.2.2.1 GetById

**Return Type:** Microsoft.SharePoint.Client.FileVersion

Returns the file version **object (1)** with the specified version label.<38>

**Parameters:**

*versionid*: Specifies the version label.

Type: **CSOM Int32**

### 3.2.5.72 Microsoft.SharePoint.Client.Folder

**TypeId:** {DBE8175A-505D-4EFF-BEC4-6C809709808B}

**ShortName:** SP.Folder

Represents a **list folder** on a **site (2)**.

Various folder properties in the **Web** class (section [3.2.5.143](#)) return any from a site or subsite. Use the **FolderCollection** (section [3.2.5.73](#)) that represents the collection of folders for a site or folder. Use an indexer to return a single folder from the collection.

The ContentTypeOrder, ServerRelativePath and UniqueContentTypeOrder properties are not included in the **default scalar property set** for this type.

#### 3.2.5.72.1 Properties

##### 3.2.5.72.1.1 Scalar Properties

###### 3.2.5.72.1.1.1 ContentTypeOrder

**Type:** **CSOM array** of Microsoft.SharePoint.Client.ContentTypeId

**Accessibility:** Read Only

Specifies the **content type order** for the **list folder**.

###### 3.2.5.72.1.1.2 Exists

**Type:** **CSOM Boolean**

**Accessibility:** Read Only

Gets a Boolean value that indicates whether the folder exists.

#### **3.2.5.72.1.1.3 IsWOPIEnabled**

**Type:** CSOM Boolean

**Accessibility:** Read Only

Indicates whether the folder is enabled for WOPI default action.

#### **3.2.5.72.1.1.4 ItemCount**

**Type:** CSOM Int32

**Accessibility:** Read Only

Specifies the count of items in the **list folder**.

#### **3.2.5.72.1.1.5 Name**

**Type:** CSOM String

**Accessibility:** Read Only

Specifies the **list folder** name.

It MUST NOT be NULL. Its length MUST be equal to or less than 256.

#### **3.2.5.72.1.1.6 ProgID**

**Type:** CSOM String

**Accessibility:** Read Only

Gets a string that identifies the application in which the folder was created.

#### **3.2.5.72.1.1.7 ServerRelativePath**

**Type:** Microsoft.SharePoint.Client.ResourcePath

**Accessibility:** Read Only

Returns the server-relative path of the folder.

#### **3.2.5.72.1.1.8 ServerRelativeUrl**

**Type:** CSOM String

**Accessibility:** Read Only

Specifies the **server-relative URL** of the **list folder**.

It MUST NOT be NULL. It MUST be a URL of server-relative form.

#### **3.2.5.72.1.1.9 TimeCreated**

**Type:** CSOM DateTime

**Accessibility:** Read Only

Gets when the folder was created in UTC.

### 3.2.5.72.1.1.10 TimeLastModified

**Type:** CSOM DateTime

**Accessibility:** Read Only

Gets the last time this folder or a direct child was modified in UTC.

### 3.2.5.72.1.1.11 UniqueContentTypeOrder

**Type:** CSOM array of Microsoft.SharePoint.Client.ContentTypeId

**Accessibility:** Read/Write

Specifies the **content type order** for the **list folder**.

It MUST return the same value as the **ContentTypeOrder**.

#### Exceptions:

Error Code	Error Type Name	Condition
-1	System.InvalidOperationException	Operation is not valid, because of the current state of the <b>object (1)</b> .

### 3.2.5.72.1.1.12 UniqueId

**Type:** CSOM GUID

**Accessibility:** Read Only

Gets the unique ID of the folder.

### 3.2.5.72.1.1.13 WelcomePage

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies the **server-relative URL** for the **list folder Welcome page**.

It MUST NOT be NULL.

## 3.2.5.72.1.2 ObjectPath Properties

### 3.2.5.72.1.2.1 Files

**Type:** Microsoft.SharePoint.Client.FileCollection

**Accessibility:** Read Only

Specifies the collection of files contained in the **list folder**.

It MUST NOT be NULL.

### 3.2.5.72.1.2.2 Folders

**Type:** Microsoft.SharePoint.Client.FolderCollection

**Accessibility:** Read Only

Specifies the collection of **list folders** contained within the list folder.

It MUST NOT be NULL.

### 3.2.5.72.1.2.3 ParentFolder

**Type:** Microsoft.SharePoint.Client.Folder

**Accessibility:** Read Only

Specifies the **list folder**.

### 3.2.5.72.1.2.4 Properties

**Type:** Microsoft.SharePoint.Client.PropertyValues

**Accessibility:** Read Only

Returns the properties for the **list folder**.[<39>](#)

It MUST NOT be NULL.

### 3.2.5.72.1.2.5 ListItemAllFields

**Type:** Microsoft.SharePoint.Client.ListItem

**Accessibility:** Read Only

Gets the **Microsoft.SharePoint.Client.ListItem** (section [3.2.5.87](#)) **object (1)** corresponding to the **list folder**, if the list folder belongs to a **document library**.[<40>](#)

### 3.2.5.72.1.2.6 StorageMetrics

**Type:** Microsoft.SharePoint.Client.StorageMetrics

**Accessibility:** Read Only

Specifies the storage-related metrics for **list folders** in the **site (2)**.

## 3.2.5.72.2 Methods

### 3.2.5.72.2.1 Scalar Methods

#### 3.2.5.72.2.1.1 AddSubFolder

**Return Type:** None

Create the subfolder inside the current folder, as specified by the leafName. The method doesn't support overwrite. If the leafName is taken, it'll fail.

**Parameters:**

*leafName*: The name of the subfolder.

Type: **CSOM String**

### **3.2.5.72.2.1.2 AddSubFolderUsingPath**

**Return Type:** None

Create the subfolder inside the current folder, as specified by the leafPath. The method doesn't support overwrite. If the leafPath is taken, it'll fail.

**Parameters:**

*leafPath:* The path of the subfolder.

Type: Microsoft.SharePoint.Client.ResourcePath

It MUST NOT be NULL.

### **3.2.5.72.2.1.3 DeleteObject**

**Return Type:** None

Deletes the **list folder**.

**Parameters:** None

### **3.2.5.72.2.1.4 MoveTo**

**Return Type:** None

Moves the folder and its contents to a new folder at the specified URL. This method applies only to the context of a single site.

**Parameters:**

*newUrl:* A string that specifies the URL for the new folder.

Type: **CSOM String**

An exception is thrown if a folder with the same name as specified in the parameter already exists.

### **3.2.5.72.2.1.5 MoveToUsingPath**

**Return Type:** None

Moves the folder and its contents to a new folder at the specified path.

**Parameters:**

*newPath:* Specifies the destination path.

Type: Microsoft.SharePoint.Client.ResourcePath

It MUST NOT be NULL.

### **3.2.5.72.2.1.6 Recycle**

**Return Type:** **CSOM GUID**

Moves the **list folder** to the **Recycle Bin** and returns the identifier of the new **Recycle Bin item**.

**Parameters:** None



### 3.2.5.72.2.1.7 Update

**Return Type:** None

Updates the **list folder** with changes that have been made to the list folder properties.

**Parameters:** None

### 3.2.5.72.2.2 ObjectPath Methods

#### 3.2.5.72.2.2.1 GetListItemChanges

**Return Type:** Microsoft.SharePoint.Client.ChangeCollection

Gets the collection of all changes from the change log that have occurred within the scope of the SharePoint folder based on the specified query.

**Parameters:**

*query:* Specifies the scope of the changes to retrieve from the change log.

Type: Microsoft.SharePoint.Client.ChangeQuery

It MUST NOT be NULL.

#### 3.2.5.72.2.2.2 GetChanges

**Return Type:** Microsoft.SharePoint.Client.ChangeCollection

Returns from the change log the collection of all changes that have occurred within the scope of the SharePoint folder based on the specified query.

**Parameters:**

*query:* An **SP.ChangeQuery** object (section [3.2.5.17](#)) that represents the query.

Type: Microsoft.SharePoint.Client.ChangeQuery

It MUST NOT be NULL.

### 3.2.5.73 Microsoft.SharePoint.Client.FolderCollection

**TypeId:** {B6B425AA-9E17-4205-A4AA-B82C2C3F884D}

**ShortName:** SP.FolderCollection

Represents a collection of **list folder objects (1)**.

#### 3.2.5.73.1 Properties

##### 3.2.5.73.1.1 Scalar Properties

None.

##### 3.2.5.73.1.2 ObjectPath Properties

None.

#### 3.2.5.73.2 Methods

### 3.2.5.73.2.1 Scalar Methods

None.

### 3.2.5.73.2.2 ObjectPath Methods

#### 3.2.5.73.2.2.1 Add

**Return Type:** Microsoft.SharePoint.Client.Folder

Adds the **list folder** to the collection of list folders and returns the added list folder.

**Parameters:**

*url*: Specifies the **URL** of the list folder.

Type: **CSOM String**

#### 3.2.5.73.2.2.2 AddUsingPath

**Return Type:** Microsoft.SharePoint.Client.Folder

Adds the folder located at the specified path to the collection.

**Parameters:**

*path*: An **SP.ResourcePath** object (section [3.2.5.420](#)) that specifies the path for the folder.

Type: Microsoft.SharePoint.Client.ResourcePath

It MUST NOT be NULL.

*parameters*: An **SP.FolderCollectionAddParameters** object (section [3.2.5.404](#)) containing the various settings used for creating the folder.

Type: Microsoft.SharePoint.Client.FolderCollectionAddParameters

#### 3.2.5.73.2.2.3 AddWithOverwrite

**Return Type:** Microsoft.SharePoint.Client.Folder

Adds the **list folder** to the collection of list folders and returns the added list folder. The server MUST overwrite an existing list folder if *overwrite* is "true".

**Parameters:**

*url*: Specifies the **URL** of the list folder.

Type: **CSOM String**

*overwrite*: Specifies whether a list folder is overwritten.

Type: **CSOM Boolean**

#### 3.2.5.73.2.2.4 GetByPath

**Return Type:** Microsoft.SharePoint.Client.Folder

Get folder at the specified path.

**Parameters:**

*path*: An **SP.ResourcePath** (section [3.2.5.420](#)) that specifies the path for the folder.

Type: Microsoft.SharePoint.Client.ResourcePath

It MUST NOT be NULL.

### 3.2.5.73.2.2.5 **GetByUrl**

**Return Type:** Microsoft.SharePoint.Client.Folder

Returns the **list folder** with the specified **URL**.[<41>](#)

#### **Parameters:**

*url*: Specifies the URL of the list folder. The URL MUST be an **absolute URL**, a **server-relative URL**, a **site-relative URL** relative to the **site (2)** containing the collection of list folders, or relative to the list folder that directly contains this collection of list folders.

Type: **CSOM String**

### 3.2.5.74 **Microsoft.SharePoint.Client.Form**

**TypeId:** {50AACA3C-FA54-47D2-B946-A2839EE956A9}

**ShortName:** SP.Form

Specified in [\[MS-WSSTS\]](#) section 2.1.2.15.4.

#### 3.2.5.74.1 **Properties**

##### 3.2.5.74.1.1 **Scalar Properties**

###### 3.2.5.74.1.1.1 **FormType**

**Type:** Microsoft.SharePoint.Client.PageType

**Accessibility:** Read Only

Specifies the **page type** of the **list form**.

###### 3.2.5.74.1.1.2 **Id**

**Type:** **CSOM GUID**

**Accessibility:** Read Only

Specifies the identifier of the **list form**.

It MUST NOT be an empty GUID.

###### 3.2.5.74.1.1.3 **ResourcePath**

**Type:** Microsoft.SharePoint.Client.ResourcePath

**Accessibility:** Read Only

Gets the Web site–relative Path of the form.

###### 3.2.5.74.1.1.4 **ServerRelativeUrl**

**Type:** CSOM String

**Accessibility:** Read Only

Specifies the **server-relative URL** of the **list form**.

It MUST NOT be empty. It MUST be a URL of server-relative form.

### 3.2.5.74.1.2 ObjectPath Properties

None.

### 3.2.5.74.2 Methods

#### 3.2.5.74.2.1 Scalar Methods

None.

#### 3.2.5.74.2.2 ObjectPath Methods

None.

### 3.2.5.75 Microsoft.SharePoint.Client.FormCollection

**TypeId:** {078611EA-CE4D-45C0-9B7A-D4B1B46CC327}

**ShortName:** SP.FormCollection

Specifies a collection of **list forms** for a **list**.

### 3.2.5.75.1 Properties

#### 3.2.5.75.1.1 Scalar Properties

None.

#### 3.2.5.75.1.2 ObjectPath Properties

None.

### 3.2.5.75.2 Methods

#### 3.2.5.75.2.1 Scalar Methods

None.

#### 3.2.5.75.2.2 ObjectPath Methods

##### 3.2.5.75.2.2.1 GetByPageType

**Return Type:** Microsoft.SharePoint.Client.Form

Returns the **list form** with the specified **page type**. If there is more than one list form with the specified page type, the protocol server MUST return one list form as determined by the protocol server. If there is no list form with the specified page type, the server MUST return NULL.

**Parameters:**

*formType*: Specifies the page type of the list form to return. It MUST be DISPLAYFORM, EDITFORM or NEWFORM.

Type: Microsoft.SharePoint.Client.PageType

### 3.2.5.75.2.2.2 GetById

**Return Type:** Microsoft.SharePoint.Client.Form

Returns the **list form** with the specified identifier.

**Parameters:**

*id*: Specifies the identifier of the list form.

Type: **CSOM GUID**

### 3.2.5.76 Microsoft.SharePoint.Client.Group

**TypeId:** {E54AD5F1-CE4E-453B-B7F7-AEA6556C9C40}

**ShortName:** SP.Group

Represents a collection of users.

The CanCurrentUserEditMembership, CanCurrentUserManageGroup and CanCurrentUserViewMembership properties are not included in the **default scalar property set** for this type.

#### 3.2.5.76.1 Properties

##### 3.2.5.76.1.1 Scalar Properties

###### 3.2.5.76.1.1.1 AllowMembersEditMembership

Type: **CSOM Boolean**

**Accessibility:** Read/Write

Specifies whether a **member** of the **group** can add and remove members from the group.

###### 3.2.5.76.1.1.2 AllowRequestToJoinLeave

Type: **CSOM Boolean**

**Accessibility:** Read/Write

Specifies whether to allow users to request to join or leave in the **group**.

###### 3.2.5.76.1.1.3 AutoAcceptRequestToJoinLeave

Type: **CSOM Boolean**

**Accessibility:** Read/Write

Specifies whether requests to join or leave the **group** are automatically accepted.

###### 3.2.5.76.1.1.4 CanCurrentUserEditMembership

**Type:** CSOM Boolean

**Accessibility:** Read Only

Specifies whether the **current user** can add and remove **members** from the **group**.

#### **3.2.5.76.1.1.5 CanCurrentUserManageGroup**

**Type:** CSOM Boolean

**Accessibility:** Read Only

Specifies whether the **current user** can change settings on the **group**.

#### **3.2.5.76.1.1.6 CanCurrentUserViewMembership**

**Type:** CSOM Boolean

**Accessibility:** Read Only

Specifies whether the **current user** can view the **membership** of the **group**.

#### **3.2.5.76.1.1.7 Description**

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies the description for the **group**.

#### **3.2.5.76.1.1.8 Id**

**Type:** CSOM Int32

**Accessibility:** Read Only

Specifies the identifier for the **group**.

#### **3.2.5.76.1.1.9 LoginName**

**Type:** CSOM String

**Accessibility:** Read Only

Specifies the name of the **group**. This is the same value as returned by the **Title** property.

Its length MUST be equal to or less than 251.

#### **3.2.5.76.1.1.10 OnlyAllowMembersViewMembership**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Specifies whether viewing the **membership** of the **group** is restricted to **members** of the group.

#### **3.2.5.76.1.1.11 OwnerTitle**

**Type:** CSOM String

**Accessibility:** Read Only

Specifies the name of the **owner** of the **group**.

### **3.2.5.76.1.1.12      PrincipalType**

**Type:** Microsoft.SharePoint.Client.Utilities.PrincipalType

**Accessibility:** Read Only

Specifies the type of **principal** represented by this **object (1)**.

### **3.2.5.76.1.1.13      RequestToJoinLeaveEmailSetting**

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies the **e-mail address** to which requests to join or leave the **group** are sent.

### **3.2.5.76.1.1.14      Title**

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies the name of a **group**.

It MUST NOT be NULL. Its length MUST be equal to or less than 255.

### **3.2.5.76.1.1.15      IsHiddenInUI**

**Type:** CSOM Boolean

**Accessibility:** Read Only

See **Microsoft.SharePoint.Client.Principal.IsHiddenInUI**, as specified in section [3.2.5.100.1.1.5.<42>](#)

## **3.2.5.76.1.2    ObjectPath Properties**

### **3.2.5.76.1.2.1      Owner**

**Type:** Microsoft.SharePoint.Client.Principal

**Accessibility:** Read/Write

Specifies the **owner** of the **group**.

### **3.2.5.76.1.2.2      Users**

**Type:** Microsoft.SharePoint.Client.UserCollection

**Accessibility:** Read Only

Specifies the collection of **members** for this **group**.

**Exceptions:**

Error Code	Error Type Name	Condition
-1	Microsoft.SharePoint.SPException	Cannot initialize group data.

### 3.2.5.76.2 Methods

#### 3.2.5.76.2.1 Scalar Methods

##### 3.2.5.76.2.1.1 Update

**Return Type:** None

Updates **group** properties after changes have been made.

**Parameters:** None

**Exceptions:**

Error Code	Error Type Name	Condition
-1	Microsoft.SharePoint.SPDistributionGroupException	Distribution group <b>member</b> resynchronization or properties update fails.

#### 3.2.5.76.2.2 ObjectPath Methods

None.

### 3.2.5.77 Microsoft.SharePoint.Client.GroupCollection

**TypeId:** {0B9F0E6C-2C15-425E-B0B2-961F78BF1ECF}

**ShortName:** SP.GroupCollection

Represents a collection of **group objects (1)**.

#### 3.2.5.77.1 Properties

##### 3.2.5.77.1.1 Scalar Properties

None.

##### 3.2.5.77.1.2 ObjectPath Properties

None.

#### 3.2.5.77.2 Methods

##### 3.2.5.77.2.1 Scalar Methods

##### 3.2.5.77.2.1.1 Remove

**Return Type:** None



Removes the specified **group** from the collection.

**Parameters:**

*group*: Specifies the group to be removed.

Type: Microsoft.SharePoint.Client.Group

It MUST NOT be NULL.

**Exceptions:**

Error Code	Error Type Name	Condition
-1	System.InvalidOperationException	Cannot remove users with unique <b>role assignment</b> permissions
-1	System.Security.SecurityException	Access denied when updating <b>farm</b> administrators group.

### 3.2.5.77.2.1.2 RemoveById

**Return Type:** None

Removes the cross-site group with the specified member identifier from the collection. <43>

**Parameters:**

*id*: Specifies the member identifier.

Type: **CSOM Int32**

### 3.2.5.77.2.1.3 RemoveByLoginName

**Return Type:** None

Removes the cross-site group with the specified name from the collection. <44>

**Parameters:**

*loginName*: A string that contains the name of the group.

Type: **CSOM String**

## 3.2.5.77.2.2 ObjectPath Methods

### 3.2.5.77.2.2.1 Add

**Return Type:** Microsoft.SharePoint.Client.Group

Adds a **group** to the collection. A **reference** to the SP.Group that was added is returned.

**Parameters:**

*parameters*: Specifies an **object (1)** to facilitate creation of a group.

Type: Microsoft.SharePoint.Client.GroupCreationInformation

It MUST NOT be NULL.

### 3.2.5.77.2.2.2 GetById

**Return Type:** Microsoft.SharePoint.Client.Group

Returns a **group** from the collection based on the identifier of the group.

**Parameters:**

*id*: Specifies the **member** identifier.

Type: **CSOM Int32**

### 3.2.5.77.2.2.3 GetByName

**Return Type:** Microsoft.SharePoint.Client.Group

Returns a **group** from the collection based on the name of the group. <45>

**Parameters:**

*name*: Specifies the group name.

Type: **CSOM String**

## 3.2.5.78 Microsoft.SharePoint.Client.GroupCreationInformation

**TypeId:** {9FD1540E-59E6-47FA-9A00-5173C9C35785}

**ShortName:** SP.GroupCreationInformation

An object used to facilitate creation of a cross-site group.

### 3.2.5.78.1 Properties

#### 3.2.5.78.1.1 Scalar Properties

##### 3.2.5.78.1.1.1 Description

**Type:** **CSOM String**

**Accessibility:** Read/Write

A string that contains the description of the cross-site group to be created.

Its length MUST be equal to or less than 512.

##### 3.2.5.78.1.1.2 Title

**Type:** **CSOM String**

**Accessibility:** Read/Write

A string that specifies the name of the cross-site group to be created.

It MUST NOT be NULL. Its length MUST be equal to or less than 255. It MUST NOT be empty.

It MUST conform to the following ABNF, as defined in [\[RFC5234\]](#): Title = 1\*1 (DIGIT/ALPHA/"-"/"\_" / "." / "~" / "&" / "%" / "!" / "(" / ")" / "{" / "}" )\*(DIGIT/ALPHA/SP/"-"/"\_" / "." / "~" / "&" / "%" / "!" / "(" / ")" / "{" / "}" )

### 3.2.5.78.1.2 ObjectPath Properties

None.

### 3.2.5.79 Microsoft.SharePoint.Client.List

**TypeId:** {D89F0B18-614E-4B4A-BAC0-FD6142B55448}

**ShortName:** SP.List

Specifies a **list** on a **site (2)**.

The AllowDeletion, BrowserFileHandling, DataSource, DefaultDisplayFormUrl, DefaultEditFormUrl, DefaultNewFormUrl, DefaultViewPath, DefaultViewUrl, EffectiveBasePermissions, EffectiveBasePermissionsForUI, EnableAssignToEmail, ExcludeFromOfflineClient, HasUniqueRoleAssignments, IsEnterpriseGalleryLibrary, IsSiteAssetsLibrary, IsSystemList, OnQuickLaunch, PageRenderType, ReadSecurity, SchemaXml, ValidationFormula, ValidationMessage and WriteSecurity properties are not included in the **default scalar property set** for this type.

#### 3.2.5.79.1 Properties

##### 3.2.5.79.1.1 Scalar Properties

###### 3.2.5.79.1.1.1 AllowContentTypes

**Type:** CSOM Boolean

**Accessibility:** Read Only

Specifies whether the **list** supports **content types**.

###### 3.2.5.79.1.1.2 BaseTemplate

**Type:** CSOM Int32

**Accessibility:** Read Only

Specifies the **list server template** of the **list**.

Its value MUST be equal to or greater than 0. Its value MUST be equal to or less than 2147483647.

###### 3.2.5.79.1.1.3 BaseType

**Type:** Microsoft.SharePoint.Client.BaseType

**Accessibility:** Read Only

Specifies the **base type** of the **list**.

It MUST be one of the following values: **GenericList**, **DocumentLibrary**, **DiscussionBoard**, **Survey**, or **Issue**.

###### 3.2.5.79.1.1.4 BrowserFileHandling

**Type:** Microsoft.SharePoint.Client.BrowserFileHandling

**Accessibility:** Read Only

Specifies the override at the **list** level for the **BrowserFileHandling** property of the **Web application**. If the **BrowserHandling** property of the Web application is **BrowserFileHandling.Strict**, then this setting MUST be ignored. If the **BrowserHandling** property of the Web application is **BrowserFileHandling.Permissive**, then this setting MUST be respected.

#### 3.2.5.79.1.1.5 ContentTypesEnabled

Type: **CSOM Boolean**

Accessibility: Read/Write

Specifies whether **content types** are enabled for the **list**.

#### 3.2.5.79.1.1.6 Created

Type: **CSOM DateTime**

Accessibility: Read Only

Specifies when the **list** was created.

#### 3.2.5.79.1.1.7 DataSource

Type: Microsoft.SharePoint.Client.ListDataSource

Accessibility: Read Only

Specifies the **data source** of an **external list**. If **HasExternalDataSource** is "false", the server MUST return NULL.

#### 3.2.5.79.1.1.8 DefaultContentApprovalWorkflowId

Type: **CSOM GUID**

Accessibility: Read/Write

Specifies the default **workflow identifier** for content approval on the **list**. It MUST be an **empty GUID** if there is no default content approval **workflow**.

#### 3.2.5.79.1.1.9 DefaultDisplayFormUrl

Type: **CSOM String**

Accessibility: Read/Write

Specifies the location of the default **display form** for the **list**.

It MUST NOT be NULL. It MUST NOT be empty. The client MUST set a **server-relative URL** and the server MUST return a **site-relative URL**.

#### 3.2.5.79.1.1.10 DefaultEditFormUrl

Type: **CSOM String**

Accessibility: Read/Write

Specifies the URL of the **edit form** to use for **list items** in the **list**.

It MUST NOT be NULL. It MUST NOT be empty. The client MUST set a **server-relative URL** and the server MUST return a **site-relative URL**.

### 3.2.5.79.1.1.11 DefaultNewFormUrl

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies the location of the default **new form** for the **list**.

It MUST NOT be NULL. It MUST NOT be empty. The client MUST set a **server-relative URL** and the server MUST return a **site-relative URL**.

### 3.2.5.79.1.1.12 DefaultViewUrl

**Type:** CSOM String

**Accessibility:** Read Only

Specifies the **server-relative URL** of the **default view** for the **list**.

It MUST NOT be NULL. It MUST NOT be empty. It MUST be a URL of server-relative form.

### 3.2.5.79.1.1.13 Description

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies the description of the **list**.

It MUST NOT be NULL.

### 3.2.5.79.1.1.14 Direction

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies the **reading order** of the **list** as specified in [\[MS-WSSFO2\]](#) section 2.2.8.2.9 or [\[MS-WSSFO3\]](#) section 2.2.7.2.9.

It MUST conform to the following ABNF, as defined in [\[RFC5234\]](#): Direction = "NONE" / "LTR" / "RTL".

### 3.2.5.79.1.1.15 DocumentTemplateUrl

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies the **server-relative URL** of the **document template (1)** for the **list**. It MUST be NULL if **BaseType** is not **DocumentLibrary**.

It MUST NOT be empty. It MUST be a URL of server-relative form.

### 3.2.5.79.1.1.16 DraftVersionVisibility

**Type:** Microsoft.SharePoint.Client.DraftVisibilityType

**Accessibility:** Read/Write

Specifies the minimum **permission** required to view **minor versions** and **drafts** within the **list**.

### 3.2.5.79.1.1.17 EffectiveBasePermissions

**Type:** Microsoft.SharePoint.Client.BasePermissions

**Accessibility:** Read Only

Specifies the effective **permissions** on the **list** that are assigned to the **current user**.

It MUST NOT be NULL.

### 3.2.5.79.1.1.18 EnableAttachments

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Specifies whether **list item attachments** are enabled for the **list**.

### 3.2.5.79.1.1.19 EnableFolderCreation

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Specifies whether new **list folders** can be added to the **list**.

### 3.2.5.79.1.1.20 EnableMinorVersions

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Specifies whether **minor versions** are enabled for the **list**.

### 3.2.5.79.1.1.21 EnableModeration

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Specifies whether content approval is enabled for the **list**.

#### Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is set to "true" and the list is an <b>external list</b> .

### 3.2.5.79.1.1.22 EnableVersioning

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Specifies whether **historical versions** of **list items** and **documents** can be created in the **list**.

#### Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is set to "true" and the list is an <b>external list</b> .

### 3.2.5.79.1.1.23 ForceCheckout

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Specifies whether **check out** is required when adding or editing **documents** in the **list**.

### 3.2.5.79.1.1.24 HasExternalDataSource

**Type:** CSOM Boolean

**Accessibility:** Read Only

Specifies whether the **list** is an **external list**.

### 3.2.5.79.1.1.25 HasUniqueRoleAssignments

**Type:** CSOM Boolean

**Accessibility:** Read Only

See **Microsoft.SharePoint.Client.SecurableObject.HasUniqueRoleAssignments** (section [3.2.5.118.1.1.1](#)).

### 3.2.5.79.1.1.26 Hidden

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Specifies whether the **list** is a **hidden** list. If the value is set to "true", the server MUST set the **OnQuickLaunch** property of the list to "false".

### 3.2.5.79.1.1.27 Id

**Type:** CSOM GUID

**Accessibility:** Read Only

Specifies the **list identifier**.

It MUST NOT be an empty GUID.

### 3.2.5.79.1.1.28 ImageUrl

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies the **URL** for the icon of the **list**.

It MUST NOT be NULL. Its length MUST be equal to or less than 255. It MUST be a **server-relative URL** or an **absolute URL**.

### 3.2.5.79.1.1.29 IsApplicationList

Type: **CSOM Boolean**

Accessibility: Read/Write

Specifies a flag that a client application can use to determine whether to display the **list**.

### 3.2.5.79.1.1.30 IsCatalog

Type: **CSOM Boolean**

Accessibility: Read Only

Specifies whether the **list** is a **gallery**.

### 3.2.5.79.1.1.31 IsSiteAssetsLibrary

Type: **CSOM Boolean**

Accessibility: Read Only

Specifies whether the **list** is designated as a default asset location for images or other files which the users upload to their wiki pages.

### 3.2.5.79.1.1.32 ItemCount

Type: **CSOM Int32**

Accessibility: Read Only

Specifies the number of **list items** in the **list**.

It MUST be greater than or equal to zero.

### 3.2.5.79.1.1.33 LastItemDeletedDate

Type: **CSOM DateTime**

Accessibility: Read Only

Specifies the last time a **list item** was deleted from the **list**. It MUST return **Created** if no list item has been deleted from the list yet.

### 3.2.5.79.1.1.34 LastItemModifiedDate

Type: **CSOM DateTime**

Accessibility: Read/Write

Specifies the last time a **list item, field (2)**, or property of the **list** was modified. It MUST return **Created** if the list has not been modified.

### 3.2.5.79.1.1.35 MultipleDataList

Type: **CSOM Boolean**

Accessibility: Read/Write



Specifies whether the **list** in a **Meeting Workspace site** contains data for multiple meeting instances within the **site (2)**. It MUST be "false" for a list that is not in a Meeting Workspace site.

### 3.2.5.79.1.1.36 NoCrawl

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Specifies that the **crawler** MUST NOT **crawl** the **list**.

**Exceptions:**

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is set to "true" and the list is an <b>external list</b> .

### 3.2.5.79.1.1.37 OnQuickLaunch

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Specifies whether the **list** appears on the **Quick Launch** of the **site (2)**. If the value is set to "true", the protocol server MUST set the **Hidden** property of the list to "false".

### 3.2.5.79.1.1.38 ParentWebUrl

**Type:** CSOM String

**Accessibility:** Read Only

Specifies the **server-relative URL** of the **site (2)** that contains the **list**.

It MUST be a URL of server-relative form.

### 3.2.5.79.1.1.39 SchemaXml

**Type:** CSOM String

**Accessibility:** Read Only

Specifies the **list schema** of the **list**.

It MUST NOT be NULL. It MUST NOT be empty. It MUST be an **XML document** that conforms to the **ListDefinition** type, as specified in [\[MS-WSSCAML\]](#) section 2.3.2.6.

### 3.2.5.79.1.1.40 ServerTemplateCanCreateFolders

**Type:** CSOM Boolean

**Accessibility:** Read Only

Specifies whether the **list template** the **list** is based on allows the creation of **folders**.

### 3.2.5.79.1.1.41 TemplateFeatureId

**Type:** CSOM GUID

**Accessibility:** Read Only

Specifies the **feature identifier** of the **feature** that contains the **list schema** for the **list**. It MUST be an **empty GUID** if the list schema for the list is not contained within a feature.

#### **3.2.5.79.1.1.42 Title**

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies the **display name** of the **list**.

It MUST NOT be NULL. Its length MUST be equal to or less than 255.

#### **3.2.5.79.1.1.43 ValidationFormula**

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies the **data validation criteria** for a **list item**.

It MUST NOT be NULL. Its length MUST be equal to or less than 1023.

#### **3.2.5.79.1.1.44 ValidationMessage**

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies the error message returned when **data validation** fails for a **list item**.

It MUST NOT be NULL. Its length MUST be equal to or less than 1024.

#### **3.2.5.79.1.1.45 EntityTypename**

**Type:** CSOM String

**Accessibility:** Read Only

Specifies the type name of the **list**.[<46>](#)

#### **3.2.5.79.1.1.46 ListItemEntityTypeFullName**

**Type:** CSOM String

**Accessibility:** Read Only

Specifies the full type name of the **list item**.[<47>](#)

#### **3.2.5.79.1.1.47 IrmEnabled**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Gets or sets a **Boolean** value that specifies whether **Information Rights Management (IRM)** is enabled for the **list**.[<48>](#)

**Exceptions:**

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	External list does not support setting the <b>IrmEnabled</b> property.

### 3.2.5.79.1.1.48 IrmExpire

Type: **CSOM Boolean**

Accessibility: Read/Write

Gets or sets a **Boolean** value that specifies whether **Information Rights Management (IRM)** expiration is enabled for the [list.<49>](#)

Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	External list does not support setting the <b>IrmExpire</b> property.

### 3.2.5.79.1.1.49 IrmReject

Type: **CSOM Boolean**

Accessibility: Read/Write

Gets or sets a **Boolean** value that specifies whether **Information Rights Management (IRM)** rejection is enabled for the [list.<50>](#)

Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	External list does not support setting the <b>IrmReject</b> property.

### 3.2.5.79.1.1.50 EffectiveBasePermissionsForUI

Type: Microsoft.SharePoint.Client.BasePermissions

Accessibility: Read Only

Specifies the effective base permissions for the current user as they SHOULD be displayed in user interface (UI).<51> If the list is not in read-only UI mode, the value of **EffectiveBasePermissionsForUI** MUST be the same as the value of **EffectiveBasePermissions** (section [3.2.5.79.1.1.17](#)). If the list is in read-only UI mode, the value of **EffectiveBasePermissionsForUI** MUST be a subset of the value of **EffectiveBasePermissions**.

It MUST NOT be NULL.

### 3.2.5.79.1.1.51 IsPrivate

Type: **CSOM Boolean**

Accessibility: Read Only

Specifies whether the **list** is a private list with restricted permissions. "True" if the list is a private list, otherwise "false".

### 3.2.5.79.1.1.52 **CrawlNonDefaultViews**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Specifies whether or not the crawler indexes the non-default views of the list.

Specify a value of true if the crawler indexes the list's non-default views; specify false if otherwise.

#### **Exceptions:**

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	External list does not support setting the "CrawlNonDefaultViews" property to "true".

### 3.2.5.79.1.1.53 **CurrentChangeToken**

**Type:** Microsoft.SharePoint.Client.ChangeToken

**Accessibility:** Read Only

Gets the current change token that is used in the change log for the list.

### 3.2.5.79.1.1.54 **FileSavePostProcessingEnabled**

**Type:** CSOM Boolean

**Accessibility:** Read Only

Specifies whether or not the files in the list can be processed in asynchronous manner

Specify a value of true if the list files can be processed asynchronously; specify false if otherwise.

### 3.2.5.79.1.1.55 **MajorVersionLimit**

**Type:** CSOM Int32

**Accessibility:** Read/Write

Gets or sets the maximum number of major versions allowed for an item in a document library that uses version control with major versions only.

### 3.2.5.79.1.1.56 **MajorWithMinorVersionsLimit**

**Type:** CSOM Int32

**Accessibility:** Read/Write

Gets or sets the maximum number of major versions that are allowed for an item in a document library that uses version control with both major and minor versions.

### 3.2.5.79.1.1.57 **ParserDisabled**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Specifies whether or not the document parser is enabled on the list.

Specify a value of true if the document parser is enabled on the list; specify false if otherwise.

### **3.2.5.79.1.1.58 AllowDeletion**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Gets or sets a Boolean value specifying whether the list can be deleted.

### **3.2.5.79.1.1.59 CustomActionElements**

**Type:** Microsoft.SharePoint.Client.CustomActionElementCollection

**Accessibility:** Read Only

Returns the **CustomAction** elements that are associated with the list, including Edit Control Block (ECB) menu custom actions and Ribbon Custom actions for the list.

### **3.2.5.79.1.1.60 DefaultItemOpenUseListSetting**

**Type:** CSOM Boolean

**Accessibility:** Read Only

This property returns whether to use the **List** setting or the server wide setting for **DefaultItemOpen** (**BrowserEnabledDocuments** setting) in the Web application. This property can only be set to false, thereby using the server-wide setting. To set it to use **List** setting, set the value for **DefaultItemOpen**.

### **3.2.5.79.1.1.61 DefaultViewPath**

**Type:** Microsoft.SharePoint.Client.ResourcePath

**Accessibility:** Read Only

Specifies the path of the default view for the list.

It MUST NOT be NULL. It MUST NOT be empty.

### **3.2.5.79.1.1.62 EnableAssignToEmail**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Gets or sets a Boolean value specifying whether e-mail notification is enabled for the list.

### **3.2.5.79.1.1.63 ExcludeFromOfflineClient**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

This doesn't block sync but acts as a recommendation to the client to not take this list offline. This gets returned as part of list properties in GetListSchema soap call.

### **3.2.5.79.1.1.64 ExemptFromBlockDownloadOfNonViewableFiles**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Property indicating whether the list is exempt from the policy to block download of non-server handled files. This SHOULD be set using the **SetExemptFromBlockDownloadOfNonViewableFiles** (section [3.2.5.79.2.1.25](#)) method.

### **3.2.5.79.1.1.65 ImagePath**

**Type:** Microsoft.SharePoint.Client.ResourcePath

**Accessibility:** Read/Write

The Path for the icon that represents the list.

It MUST NOT be NULL. Its length MUST be equal to or less than 255.

### **3.2.5.79.1.1.66 IsEnterpriseGalleryLibrary**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Gets a Boolean value that indicates whether the list is a gallery, such as for site templates, list templates, Web Parts, or Master Pages.

### **3.2.5.79.1.1.67 IsSystemList**

**Type:** CSOM Boolean

**Accessibility:** Read Only

Indicates whether the list is system list that does not contain end user data and created by system account. A value of "true" means yes.

### **3.2.5.79.1.1.68 LastItemUserModifiedDate**

**Type:** CSOM DateTime

**Accessibility:** Read/Write

Specifies when an item of the list was last modified by a non-system update. A non-system update is a change to a list item that is visible to end users. If no item has been created in the list, the list creation time is returned.

### **3.2.5.79.1.1.69 ListExperienceOptions**

**Type:** Microsoft.SharePoint.Client.ListExperience

**Accessibility:** Read/Write

Gets or sets the list to new experience, classic experience or default experience set by my administrator.

### 3.2.5.79.1.1.70 PageRenderType

**Type:** Microsoft.SharePoint.Client.ListPageRenderType

**Accessibility:** Read Only

Returns the render type of the current file. If the file will render in the modern experience it will return **ListPageRenderType.Modern**. If the file will render in the classic experience, it will return the reason for staying in classic, as specified by **ListPageRenderType** enumeration (section [3.2.5.413](#)).

### 3.2.5.79.1.1.71 ParentWebPath

**Type:** Microsoft.SharePoint.Client.ResourcePath

**Accessibility:** Read Only

Returns the path of the parent web for the list.

### 3.2.5.79.1.1.72 ReadSecurity

**Type:** CSOM Int32

**Accessibility:** Read/Write

Gets or sets the Read security setting for the list.

### 3.2.5.79.1.1.73 WriteSecurity

**Type:** CSOM Int32

**Accessibility:** Read/Write

Gets or sets the Write security setting for the list.

## 3.2.5.79.1.2 ObjectPath Properties

### 3.2.5.79.1.2.1 ContentTypes

**Type:** Microsoft.SharePoint.Client.ContentTypeCollection

**Accessibility:** Read Only

Specifies the collection of **content types** for the **list**.

It MUST NOT be NULL.

### 3.2.5.79.1.2.2 Fields

**Type:** Microsoft.SharePoint.Client.FieldCollection

**Accessibility:** Read Only

Specifies the collection of all **fields (2)** in the **list**.

It MUST NOT be NULL.

### 3.2.5.79.1.2.3 Forms

**Type:** Microsoft.SharePoint.Client.FormCollection

**Accessibility:** Read Only

Specifies the collection of all **list forms** in the **list**.

It MUST NOT be NULL.

#### **3.2.5.79.1.2.4 ParentWeb**

**Type:** Microsoft.SharePoint.Client.Web

**Accessibility:** Read Only

Specifies the **site (2)** that contains the **list**.

#### **3.2.5.79.1.2.5 RoleAssignments**

**Type:** Microsoft.SharePoint.Client.RoleAssignmentCollection

**Accessibility:** Read Only

See **Microsoft.SharePoint.Client.SecurableObject.RoleAssignments**, as specified in section [3.2.5.118.1.2.1](#).

#### **3.2.5.79.1.2.6 RootFolder**

**Type:** Microsoft.SharePoint.Client.Folder

**Accessibility:** Read Only

Specifies the **root folder** for the **list**.

It MUST NOT be NULL.

#### **3.2.5.79.1.2.7 UserCustomActions**

**Type:** Microsoft.SharePoint.Client.UserCustomActionCollection

**Accessibility:** Read Only

Specifies the collection of all **user custom actions** for the **list**.

It MUST NOT be NULL.

#### **3.2.5.79.1.2.8 Views**

**Type:** Microsoft.SharePoint.Client.ViewCollection

**Accessibility:** Read Only

Specifies the collection of all **public views** on the **list** and **personal views** of the **current user** on the list.

It MUST NOT be NULL.

#### **3.2.5.79.1.2.9 WorkflowAssociations**

**Type:** Microsoft.SharePoint.Client.Workflow.WorkflowAssociationCollection

**Accessibility:** Read Only

Specifies the collection of all **workflow associations** for the **list**.



It MUST NOT be NULL.

### 3.2.5.79.1.2.10 FirstUniqueAncestorSecurableObject

**Type:** Microsoft.SharePoint.Client.SecurableObject

**Accessibility:** Read Only

See **Microsoft.SharePoint.Client.SecurableObject.FirstUniqueAncestorSecurableObject**, as specified in section [3.2.5.118.1.2.2.<52>](#)

### 3.2.5.79.1.2.11 Items

**Type:** Microsoft.SharePoint.Client.ListItemEntityCollection

**Accessibility:** Read Only

Specifies the collection of **list items** for the **list**.[<53>](#)

### 3.2.5.79.1.2.12 InformationRightsManagementSettings

**Type:** Microsoft.SharePoint.Client.InformationRightsManagementSettings

**Accessibility:** Read Only

Specifies settings for **document library Information Rights Management (IRM)**.[<54>](#)

**Exceptions:**

Error Code	Error Type Name	Condition
-2146232832	System.NotSupportedException	<b>Picture library</b> does not support IRM settings.

### 3.2.5.79.1.2.13 EventReceivers

**Type:** Microsoft.SharePoint.Client.EventReceiverDefinitionCollection

**Accessibility:** Read Only

Gets the collection of **event receivers** that have been registered for the **list**.[<55>](#)

### 3.2.5.79.1.2.14 DefaultView

**Type:** Microsoft.SharePoint.Client.View

**Accessibility:** Read Only

Gets the default view for a **list**.

### 3.2.5.79.1.2.15 CreatablesInfo

**Type:** Microsoft.SharePoint.Client.CreatablesInfo

**Accessibility:** Read Only

Returns an object that describes what this **list** can create, and a collection of links to visit in order to create those things. If it can't create certain things, it contains an error message describing why.

The consumer MUST append the encoded **URL** of the current page to the links returned here. (This page the link goes to needs it as a query parameter to function correctly.) The consumer SHOULD also consider appending `&IsDlg=1` to the link, to remove the UI from the linked page, if desired.

### **3.2.5.79.1.2.16 DescriptionResource**

**Type:** Microsoft.SharePoint.Client.UserResource

**Accessibility:** Read Only

Represents the description of this list.

### **3.2.5.79.1.2.17 TitleResource**

**Type:** Microsoft.SharePoint.Client.UserResource

**Accessibility:** Read Only

Represents the title of this list.

### **3.2.5.79.1.2.18 Activities**

**Type:** Microsoft.SharePoint.Activities.SPActivityEntitySet

**Accessibility:** Read Only

Returns from the Activities Table the collection of all activities.

### **3.2.5.79.1.2.19 Subscriptions**

**Type:** Microsoft.SharePoint.Webhooks.SubscriptionCollection

**Accessibility:** Read Only

Returns the subscription collection for this list.

## **3.2.5.79.2 Methods**

### **3.2.5.79.2.1 Scalar Methods**

#### **3.2.5.79.2.1.1 BreakRoleInheritance**

**Return Type:** None

Updates the **list** to stop inheriting **role assignments** from the **site (2)** that contains the list.

**Parameters:**

*copyRoleAssignments*: Specifies whether to perform a one-time copy of the role assignments from the site (2) that contains the list to the list. If "false" the list MUST be given one role assignment containing the **current user**.

Type: **CSOM Boolean**

*clearSubscopes*: If the **securable object** is a site (2), and the *clearSubscopes* parameter is "true", the role assignments for all child securable objects in the current site (2) and in the sites (2) which inherit role assignments from the current site (2) MUST be cleared and those securable objects will inherit role assignments from the current site (2) after this call. If the securable object is a site (2), and the *clearSubscopes* parameter is "false", the role assignments for all child securable objects that

do not inherit role assignments from their parent **object (1)** MUST remain unchanged. If the securable object is not a site (2), and the *clearSubscopes* parameter is "true", the role assignments for all child securable objects MUST be cleared and those securable objects will inherit role assignments from the current securable object after this call. If the securable object is not a site (2), and the *clearSubscopes* parameter is "false", the role assignments for all child securable objects that do not inherit role assignments from their parent object (1) MUST remain unchanged.

Type: CSOM Boolean

### 3.2.5.79.2.1.2 DeleteObject

**Return Type:** None

Deletes the **list**.

**Parameters:** None

**Exceptions:**

Error Code	Error Type Name	Condition
- 2147016498	Microsoft.SharePoint.SPException	List cannot be deleted because it is being used as a <b>data source</b> .
- 2130575299	Microsoft.SharePoint.SPException	List cannot be deleted, because there MUST be one instance of this list type in a web.
- 2130575157	Microsoft.SharePoint.SPException	List cannot be deleted, because one or more related lists have a <b>relationship behavior constraint</b> that prevents the operation.

### 3.2.5.79.2.1.3 Recycle

**Return Type:** **CSOM GUID**

Moves the **list** to the **Recycle Bin** and returns the identifier of the new **Recycle Bin item**.

**Parameters:** None

**Exceptions:**

Error Code	Error Type Name	Condition
- 2147016498	Microsoft.SharePoint.SPException	List cannot be deleted because it is being used as a <b>data source</b> .
- 2130575299	Microsoft.SharePoint.SPException	List cannot be deleted because there MUST be one instance of this list type in a web.
- 2130575157	Microsoft.SharePoint.SPException	List cannot be deleted because one or more related lists have a <b>relationship behavior constraint</b> that prevents the operation.

### 3.2.5.79.2.1.4 ResetRoleInheritance

**Return Type:** None

Updates the **list** to inherit **role assignments** from the **site (2)** that contains the list.

**Parameters:** None

### 3.2.5.79.2.1.5 Update

**Return Type:** None

Commits changed properties of the **list**.

**Parameters:** None

**Exceptions:**

Error Code	Error Type Name	Condition
- 2130575342	Microsoft.SharePoint.SPException	Another list with the title already exists in the <b>site (2)</b> .
- 2130575305	Microsoft.SharePoint.SPException	List was modified on the server in a way that prevents changes from being committed, as determined by the protocol server.
- 2130575273	Microsoft.SharePoint.SPException	The <b>data validation criteria</b> refers to a column that does not exist.

### 3.2.5.79.2.1.6 RenderListData

**Return Type:** **CSOM String**

Returns the data for the specified query view. <56> The result is implementation-specific, used for providing data to a user interface.

**Parameters:**

*viewXml*: Specifies the **query** as **XML** that conforms to the **ViewDefinition** type as specified in [MS-WSSCAML] section 2.3.2.17.

Type: CSOM String

It MUST NOT be NULL.

### 3.2.5.79.2.1.7 GetListItemChangesSinceToken

**Return Type:** **CSOM Stream**

Returns the changes made to the **list** since the date and time specified in the change token defined by the *query* input parameter. <57>

**Parameters:**

*query*: Specifies the query values to get the changes made to the list. See section 3.2.5.183.

Type: Microsoft.SharePoint.Client.ChangeLogItemQuery

### 3.2.5.79.2.1.8 RenderListFormData

**Return Type:** **CSOM String**

Returns a string containing **field (2)** values and field (2) schema attributes for a **list item**.[<58>](#) The result is implementation-specific, used for providing data to a user interface.

**Parameters:**

*itemId*: Specifies the **list item identifier** for a list item in the **list**.

Type: **CSOM Int32**

It MUST NOT be NULL.

*formId*: Specifies a unique identifier in the client.

Type: CSOM String

It MUST NOT be NULL.

*mode*: Specifies the **page type** of the **list form**.

Type: CSOM Int32

It MUST NOT be NULL.

### **3.2.5.79.2.1.9 SaveAsNewView**

**Return Type: CSOM String**

Overwrites a **view** if it already exists, creates a new view if it does not; and then extracts the implementation-specific filter and sort information from the **URL** and builds and updates the view's **XML**.[<59>](#) Returns the URL of the view.

**Parameters:**

*oldName*: The name of the view the user is currently on.

Type: CSOM String

*newName*: The new name given by the user.

Type: CSOM String

*privateView*: Set to "true" to make the view private; otherwise, "false".

Type: **CSOM Boolean**

*uri*: URL that contains all the implementation-specific filter and sort information for the view.

Type: CSOM String

### **3.2.5.79.2.1.10 GetUserEffectivePermissions**

**Return Type: Microsoft.SharePoint.Client.BasePermissions**

Returns the user permissions for this **list**.

**Parameters:**

*userName*: Specifies the user login name.

Type: **CSOM String**

It MUST NOT be NULL.

### 3.2.5.79.2.1.11 ReserveListItemId

**Return Type:** CSOM Int32

Reserves the returned **list item** identifier for the idempotent creation of a list item.

**Parameters:** None

### 3.2.5.79.2.1.12 RenderListDataAsStream

**Return Type:** CSOM Stream

Returns the data for the specified query view.

**Parameters:**

*parameters:* The parameters to be used to return data.

Type: Microsoft.SharePoint.Client.RenderListDataParameters

It MUST NOT be NULL.

*overrideParameters:* The parameters that are used to override and extend the *parameters*.

Type: Microsoft.SharePoint.Client.RenderListDataOverrideParameters

### 3.2.5.79.2.1.13 CreateDocumentAndGetEditLink

**Return Type:** CSOM String

Creates a document at the path and of the type specified within the current list. Returns an edit link to the file.

**Parameters:**

*fileName:* Specifies the name of the document.

Type: CSOM String

If null or empty, the document will be given an automatically-created name.

*folderPath:* Specifies the path within the current list to create the document in.

Type: CSOM String

*documentTemplateType:* A number representing the type of document to create.

Type: CSOM Int32

Valid values are: 1 = Word, 2 = Excel, 3 = PowerPoint.

*templateUrl:* Specifies the **URL** of the **document template (2)** to base the new document on.

Type: CSOM String

MUST be a **site-relative URL** or **server-relative URL** or **full URL** that refers to a file stored within the **site (2)** that contains the current **list**.

### 3.2.5.79.2.1.14 GetSpecialFolderUrl

**Return Type:** CSOM String

Gets the relative URL of the Save to OneDrive folder.

**Parameters:**

*type*: The Save-to-OneDrive type.

Type: Microsoft.SharePoint.Client.SpecialFolderType

*bForceCreate*: Specify true if the folder doesn't exist and SHOULD be created.

Type: **CSOM Boolean**

*existingFolderGuid*: The GUID of the created folders that exist, if any.

Type: **CSOM GUID**

### **3.2.5.79.2.1.15      GetWebDavUrl**

**Return Type: CSOM String**

Gets the trusted URL for opening the folder in Explorer view.

**Parameters:**

*sourceUrl*: The URL of the current folder the user is in.

Type: CSOM String

### **3.2.5.79.2.1.16      RenderListContextMenuData**

**Return Type: CSOM Stream**

Returns the data for the specific list context menu item request.

**Parameters:**

*parameters*: The parameters to return the data.

Type: Microsoft.SharePoint.Client.RenderListContextMenuDataParameters

### **3.2.5.79.2.1.17      RenderListFilterData**

**Return Type: CSOM Stream**

Returns the data for the specific field filter item request.

**Parameters:**

*parameters*: The parameters to return the data.

Type: Microsoft.SharePoint.Client.RenderListFilterDataParameters

### **3.2.5.79.2.1.18      AddValidateUpdateItem**

**Return Type: CSOM array** of Microsoft.SharePoint.Client.ListItemFormUpdateValue

Adds an item to an existing list and validate the list item update values. If all fields validated successfully, commit all changes. If there's any exception in any of the fields, the item will not be committed.

**Parameters:**

*listItemCreateInfo*: Contains the information that determines how the item will be created.

Type: Microsoft.SharePoint.Client.ListItemCreationInformation

*formValues*: A collection of field internal names and values for the given field. If the collection is empty, no update will take place.

Type: CSOM array of Microsoft.SharePoint.Client.ListItemFormUpdateValue

It MUST NOT be NULL.

*bNewDocumentUpdate*: Indicates whether the list item is a document being updated after upload. A value of "true" means yes.

Type: **CSOM Boolean**

*checkInComment*: The comment of the check in if any. It's only applicable when the item is checked out.

Type: **CSOM String**

### **3.2.5.79.2.1.19 AddValidateUpdateItemUsingPath**

**Return Type:** **CSOM array** of Microsoft.SharePoint.Client.ListItemFormUpdateValue

Adds an item to an existing list and validate the list item update values. If all fields validated successfully, commit all changes. If there's any exception in any of the fields, the item will not be committed.

#### **Parameters:**

*listItemCreateInfo*: Specifies the creation information that determines how the item will be created.

Type: Microsoft.SharePoint.Client.ListItemCreationInformationUsingPath

*formValues*: A collection of field internal names and values for the given field. If the collection is empty, no update will take place.

Type: CSOM array of Microsoft.SharePoint.Client.ListItemFormUpdateValue

It MUST NOT be NULL.

*bNewDocumentUpdate*: Indicates whether the list item is a document being updated after upload. A value of "true" means yes.

Type: **CSOM Boolean**

*checkInComment*: Checkin comment (if any). It's only applicable when the item is checked out.

Type: **CSOM String**

### **3.2.5.79.2.1.20 BulkValidateUpdateListItems**

**Return Type:** **CSOM array** of Microsoft.SharePoint.Client.ListItemFormUpdateValue

Validate and update multiple list items.

#### **Parameters:**

*itemIds*: A collection of item Ids that need to be updated with the same formValues.

Type: CSOM array of **CSOM Int32**



It MUST NOT be NULL.

*formValues*: A collection of field internal names and values for the given field. If the collection is empty, no update will take place.

Type: CSOM array of Microsoft.SharePoint.Client.ListItemFormUpdateValue

It MUST NOT be NULL.

*bNewDocumentUpdate*: Indicates whether the list item is a document being updated after upload. A value of "true" means yes.

Type: **CSOM Boolean**

*checkInComment*: The comment of check in if any. It's only applicable when the item is checked out.

Type: **CSOM String**

*folderPath*: Decoded path of the folder where the items belong to. If not provided, the server will try to find items to update under root folder.

Type: CSOM String

### **3.2.5.79.2.1.21 CreateDocumentWithDefaultName**

**Return Type: CSOM String**

Creates a empty document with default filename with the given extension at the path given by folderPath. Returns the name of the newly created document.

#### **Parameters:**

*folderPath*: The path within the current list at which to create the document.

Type: CSOM String

*extension*: The file extension without dot prefix.

Type: CSOM String

### **3.2.5.79.2.1.22 GetListDataAsStream**

This method is a **static CSOM method**.

**Return Type: CSOM Stream**

Returns list data from the specified list url and for the specified query parameters.

#### **Parameters:**

*listFullUrl*: The **absolute URL** of the list.

Type: **CSOM String**

*parameters*: The parameters to be used.

Type: Microsoft.SharePoint.Client.RenderListDataParameters

It MUST NOT be NULL.

*overrideParameters*: Additional parameters to be used.

Type: Microsoft.SharePoint.Client.RenderListDataOverrideParameters

### 3.2.5.79.2.1.23 **RenderExtendedListFormData**

**Return Type:** CSOM String

Fetch listform data for the specified item.

**Parameters:**

*itemId*: The ID of the item.

Type: **CSOM Int32**

It MUST NOT be NULL.

*formId*: The ID of the form.

Type: CSOM String

It MUST NOT be NULL.

*mode*: The mode of form control. It MUST be one of the following values: 1 for "Display" mode, 2 for "Edit" mode or 3 for "New" mode.

Type: CSOM Int32

It MUST NOT be NULL.

*options*: Additional options controlling what type of item information and schema are returned.

Type: Microsoft.SharePoint.Client.RenderListFormDataOptions

*cutoffVersion*: The maximum version of the item to fetch.

Type: CSOM Int32

### 3.2.5.79.2.1.24 **SaveAsTemplate**

**Return Type:** None

Saves the list as a template in the list template gallery and includes the option of saving with or without the data that is contained in the current list.

**Parameters:**

*strFileName*: A string that contains the file name for the list template with an .stp extension.

Type: **CSOM String**

*strName*: A string that contains the title for the list template.

Type: CSOM String

*strDescription*: A string that contains the description for the list template.

Type: CSOM String

*bSaveData*: true to save the data of the original list along with the list template; otherwise, false.

Type: **CSOM Boolean**

### 3.2.5.79.2.1.25 SetExemptFromBlockDownloadOfNonViewableFiles

**Return Type:** None

Method to set the ExemptFromBlockDownloadOfNonViewableFiles property. Ensures that only a tenant administrator can set the exemption.

**Parameters:**

*value:* The value to set.

Type: **CSOM Boolean**

### 3.2.5.79.2.2 ObjectPath Methods

#### 3.2.5.79.2.2.1 AddItem

**Return Type:** Microsoft.SharePoint.Client.ListItem

Creates a new **list item** in the **list** and return a **reference** to the added SP.ListItem.

**Parameters:**

*parameters:* Specifies the properties of the new list item.

Type: Microsoft.SharePoint.Client.ListItemCreationInformation

#### 3.2.5.79.2.2.2 GetChanges

**Return Type:** Microsoft.SharePoint.Client.ChangeCollection

Specifies the collection of changes from the **change log** that have occurred within the **list**, based on the specified **query**.

**Parameters:**

*query:* Specifies the query.

Type: Microsoft.SharePoint.Client.ChangeQuery

It MUST NOT be NULL.

#### 3.2.5.79.2.2.3 GetItemById

**Return Type:** Microsoft.SharePoint.Client.ListItem

Specifies the **list item** with the specified **list item identifier**.

**Parameters:**

*id:* Specifies the list item identifier.

Type: **CSOM Int32**

#### 3.2.5.79.2.2.4 GetItemByStringId

**Return Type:** Microsoft.SharePoint.Client.ListItem

Returns the **list item** with either the specified **list item identifier** or the specified identifier for an instance of an **external content type**.

**Parameters:**

*sId*: Specifies the list item identifier, or if the **list** is an **external list**, specifies the identifier for an instance of an external content type as specified in [\[MS-ECTPWPS\]](#) section 3.1.4.1.2.1.

Type: **CSOM String**

It MUST NOT be NULL. It MUST NOT be empty.

**Exceptions:**

Error Code	Error Type Name	Condition
-2130575338	Microsoft.SharePoint.SPException	List item does not exist, and the list is an external list.
-1	System.FormatException	<b>sId</b> is a list item identifier with invalid format, and the list is not an external list.

**3.2.5.79.2.2.5 GetItems**

**Return Type:** Microsoft.SharePoint.Client.ListItemCollection

Returns a collection of **list items** from the **list** based on the specified **query**.

**Parameters:**

*query*: Specifies a query.

Type: Microsoft.SharePoint.Client.CamlQuery

It MUST NOT be NULL.

**3.2.5.79.2.2.6 GetRelatedFields**

**Return Type:** Microsoft.SharePoint.Client.RelatedFieldCollection

Returns a collection of **lookup fields** that use this **list** as a **data source** and that have **FieldLookup.IsRelationship** set to "true".

**Parameters:** None

**3.2.5.79.2.2.7 GetView**

**Return Type:** Microsoft.SharePoint.Client.View

Returns the **list view** with the specified **view identifier**. If an **empty GUID** is specified it MUST return the **default view** of the **list**.

**Parameters:**

*viewGuid*: Specifies the view identifier.

Type: **CSOM GUID**

**3.2.5.79.2.2.8 GetRelatedFieldsExtendedData**

**Return Type:** Microsoft.SharePoint.Client.RelatedFieldExtendedDataCollection

Returns a collection of **objects (1)** that store properties of **relationship lookup fields** of this [list.<60>](#)

**Parameters:** None

### **3.2.5.79.2.2.9 CreateDocument**

**Return Type:** Microsoft.SharePoint.Client.ListItem

Creates a new document in the specified folder and that is based on the provided template type.

**Parameters:**

*fileName:* The name of the document.

Type: **CSOM String**

If null or empty, a name will be automatically provided.

*targetFolder:* The folder to create the document within.

Type: Microsoft.SharePoint.Client.Folder

*templateType:* The template type the new document is created with.

Type: Microsoft.SharePoint.Client.DocumentTemplateType

### **3.2.5.79.2.2.10 CreateDocumentFromTemplate**

**Return Type:** Microsoft.SharePoint.Client.ListItem

Creates a new document in the specified folder and that is based on the template at the provided URL.

**Parameters:**

*fileName:* The name of the document.

Type: **CSOM String**

If null or empty, a name will be automatically provided.

*targetFolder:* The folder to create the document within.

Type: Microsoft.SharePoint.Client.Folder

*templateUrl:* The URL of the template to create the document with.

Type: CSOM String

### **3.2.5.79.2.2.11 CreateDocumentFromTemplateBytes**

**Return Type:** Microsoft.SharePoint.Client.ListItem

Creates a new document in the specified folder and that is based on the provided template bytes.

**Parameters:**

*fileName:* The name of the document.

Type: **CSOM String**

If null or empty, a name will be automatically provided.

*targetFolder*: The folder to create the document within.

Type: Microsoft.SharePoint.Client.Folder

*templateBytes*: The template bytes to create the document from.

Type: **CSOM binary**

The template bytes to create the document from.

*extension*: The extension of the document.

Type: CSOM String

In the case that a filename is not provided, the extension can be used to automatically generate a filename.

### **3.2.5.79.2.2.12 CreateDocumentFromTemplateStream**

**Return Type:** Microsoft.SharePoint.Client.ListItem

Creates a new document in the specified folder and based on the provided template stream.

**Parameters:**

*fileName*: The name of the document.

Type: **CSOM String**

If null or empty, a name will be automatically provided.

*targetFolder*: The folder to create the document within.

Type: Microsoft.SharePoint.Client.Folder

*extension*: The extension of the document.

Type: CSOM String

In the case that a filename is not provided, the extension can be used to automatically generate a filename.

*templateStream*: The template stream to create the document from.

Type: **CSOM Stream**

### **3.2.5.79.2.2.13 AddItemUsingPath**

**Return Type:** Microsoft.SharePoint.Client.ListItem

Adds a ListItem to an existing List.

**Parameters:**

*parameters*: The object that contains the information determining how the list item will be created.

Type: Microsoft.SharePoint.Client.ListItemCreationInformationUsingPath

### **3.2.5.79.2.2.14 CreateDocumentFromTemplateUsingPath**

**Return Type:** Microsoft.SharePoint.Client.ListItem

Creates a new document in the target folder based on the template Path provided.

**Parameters:**

*filePath*: The path of the document to create.

Type: Microsoft.SharePoint.Client.ResourcePath

*targetFolder*: The target folder to create the document. It MUST NOT be null.

Type: Microsoft.SharePoint.Client.Folder

*templatePath*: The path of the template. It MUST NOT be null.

Type: Microsoft.SharePoint.Client.ResourcePath

### **3.2.5.79.2.2.15      GetBloomFilter**

**Return Type:** Microsoft.SharePoint.Client.ListBloomFilter

Generates a Bloom filter (probabilistic structure for checking the existence of list items) for the current list

**Parameters:**

*startItemId*: The ID of the list item to start the search at.

Type: **CSOM Int32**

### **3.2.5.79.2.2.16      GetBloomFilterWithCustomFields**

**Return Type:** Microsoft.SharePoint.Client.ListBloomFilter

Generates a Bloom filter (probabilistic structure for checking the existence of list items) for the current list with fields provided to read.

**Parameters:**

*listItemStartingID*: The ID of the list item to start the search at.

Type: **CSOM Int32**

*internalFieldNames*: A list of internal fields to read from.

Type: **CSOM array** of **CSOM String**

### **3.2.5.79.2.2.17      GetCheckedOutFiles**

**Return Type:** Microsoft.SharePoint.Client.CheckedOutFileCollection

Returns a collection of checked-out files as specified in section [3.2.5.381](#).

**Parameters:** None

### **3.2.5.79.2.2.18      getFileExtendedActivities**

**Return Type:** Microsoft.SharePoint.Activities.SPActivityEntitySet

Gets all activities that have happened for the user for the document after the user's linger time.

**Parameters:**

*docIds*: List of identifiers of documents. Maximum number allowed is 50.

Type: **CSOM array** of **CSOM GUID**

*badgeOnly*: True if user wants only the badge.

Type: **CSOM Boolean**

### **3.2.5.79.2.2.19      GetItemByUniqueId**

**Return Type:** Microsoft.SharePoint.Client.ListItem

Returns the list item with the specified ID.

**Parameters:**

*uniqueId*: The unique ID that is associated with the **list item**.

Type: **CSOM GUID**

### **3.2.5.80      Microsoft.SharePoint.Client.ListCollection**

**TypeId:** {1E78B736-61F0-441C-A785-10FC25387C8D}

**ShortName:** SP.ListCollection

Specifies a collection of **lists**.

#### **3.2.5.80.1      Properties**

##### **3.2.5.80.1.1      Scalar Properties**

None.

##### **3.2.5.80.1.2      ObjectPath Properties**

None.

#### **3.2.5.80.2      Methods**

##### **3.2.5.80.2.1      Scalar Methods**

None.

##### **3.2.5.80.2.2      ObjectPath Methods**

###### **3.2.5.80.2.2.1      Add**

**Return Type:** Microsoft.SharePoint.Client.List

Creates a new **list** and adds it to the collection.

**Parameters:**

*parameters*: Specifies the properties of the new list.

Type: Microsoft.SharePoint.Client.ListCreationInformation

It MUST NOT be NULL.



## Exceptions:

Error Code	Error Type Name	Condition
-1	Microsoft.BusinessData.MetadataModel.MetadataObjectNotFoundFoundException	<b>Entity</b> specified in <b>ListCreationInformation.DataSourceProperties</b> or the specified <b>SpecificFinder</b> does not exist on the server.
-2130575342	Microsoft.SharePoint.SPException	Another list with the title already exists in the <b>site (2)</b> .
-2130575237	Microsoft.SharePoint.SPException	<b>List server template</b> is not valid.

### 3.2.5.80.2.2.2 EnsureClientRenderedSitePagesLibrary

**Return Type:** Microsoft.SharePoint.Client.List

Returns a list that is designated as a default location for site pages.

**Parameters:** None

### 3.2.5.80.2.2.3 EnsureEventsList

**Return Type:** Microsoft.SharePoint.Client.List

Returns a list that is designated as a default location for events.

**Parameters:** None

### 3.2.5.80.2.2.4 EnsureSiteAssetsLibrary

**Return Type:** Microsoft.SharePoint.Client.List

Returns a **list** that is designated as a default asset location for images or other files that the users upload to their wiki pages.

**Parameters:** None

### 3.2.5.80.2.2.5 EnsureSitePagesLibrary

**Return Type:** Microsoft.SharePoint.Client.List

Returns a **list** that is designated as a default location for wiki pages.

**Parameters:** None

### 3.2.5.80.2.2.6 GetById

**Return Type:** Microsoft.SharePoint.Client.List

Returns the **list** with the specified **list identifier**.

**Parameters:**

*id*: Specifies the list identifier.

Type: **CSOM GUID**

### **3.2.5.80.2.2.7 GetByTitle**

**Return Type:** Microsoft.SharePoint.Client.List

Returns the **list** with the specified **display name**.

**Parameters:**

*title*: Specifies the display name.

Type: **CSOM String**

It MUST NOT be NULL. It MUST NOT be empty. Its length MUST be equal to or less than 255.

### **3.2.5.81 Microsoft.SharePoint.Client.ListCreationInformation**

**TypeId:** {E247B7FC-095E-4EA4-A4C9-C5D373723D8C}

**ShortName:** SP.ListCreationInformation

Specifies the properties of the new **list**.

#### **3.2.5.81.1 Properties**

##### **3.2.5.81.1.1 Scalar Properties**

###### **3.2.5.81.1.1.1 CustomSchemaXml**

Type: **CSOM String**

**Accessibility:** Read/Write

Specifies the **list schema** of the new **list**.

It MUST be an **XML fragment** that conforms to List Schema as specified in [\[MS-WSSCAML\]](#) section 2.3.

###### **3.2.5.81.1.1.2 DataSourceProperties**

Type: **CSOM dictionary**

**Accessibility:** Read/Write

Specifies the properties of the **data source** of the new **list**. If the value is not NULL, **QuickLaunchOption** MUST be set to Off.

If it is not NULL, it MUST contain the following keys: "LobSystemInstance", "EntityNamespace", "Entity", and "SpecificFinder". The value of the "Entity" and "SpecificFinder" keys MUST be non-NULL and correct as determined by the protocol server.

###### **3.2.5.81.1.1.3 Description**

Type: **CSOM String**

**Accessibility:** Read/Write

Specifies the description of the new **list**.

#### **3.2.5.81.1.1.4 DocumentTemplateType**

**Type:** CSOM Int32

**Accessibility:** Read/Write

Specifies the identifier of the **document template (1)** for the new **list**.

#### **3.2.5.81.1.1.5 QuickLaunchOption**

**Type:** Microsoft.SharePoint.Client.QuickLaunchOptions

**Accessibility:** Read/Write

Specifies whether the new **list** is displayed on the **Quick Launch** of the **site (2)**.

#### **3.2.5.81.1.1.6 TemplateFeatureId**

**Type:** CSOM GUID

**Accessibility:** Read/Write

Specifies the **feature identifier** of the **feature** that contains the **list schema** for the new **list**. It MUST be **empty GUID** if the list schema for the new list is not contained within a feature.

#### **3.2.5.81.1.1.7 TemplateType**

**Type:** CSOM Int32

**Accessibility:** Read/Write

Specifies the **list server template** of the new **list**.

#### **3.2.5.81.1.1.8 Title**

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies the **display name** of the new **list**.

It MUST NOT be NULL. Its length MUST be equal to or less than 255.

#### **3.2.5.81.1.1.9 Url**

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies the **site-relative URL** of the location for the new **list**.

It MUST be a site-relative URL.

### **3.2.5.81.1.2 ObjectPath Properties**

#### **3.2.5.81.1.2.1 ListTemplate**

**Type:** Microsoft.SharePoint.Client.ListTemplate

**Accessibility:** Read/Write

Specifies the list template to be used to create a new list.

### **3.2.5.82 Microsoft.SharePoint.Client.ListDataSource**

**TypeId:** {06BFE4A5-1516-4B55-A6D7-ECBE3FF7A3C8}

**ShortName:** SP.ListDataSource

Stores the parameters required for a **list** to communicate with its external data source.

#### **3.2.5.82.1 Properties**

##### **3.2.5.82.1.1 Scalar Properties**

###### **3.2.5.82.1.1.1 Properties**

**Type:** **CSOM dictionary**

**Accessibility:** Read Only

Specifies the properties about the external data source.

It MUST NOT be NULL. It MUST have LobSystemInstance, EntityNamespace, Entity and SpecificFinder properties and their values.

###### **3.2.5.82.1.2 ObjectPath Properties**

None.

### **3.2.5.83 Microsoft.SharePoint.Client.ListDataValidationExceptionValue**

**TypeId:** {356FE248-721A-4ADF-AF96-20822BC5476E}

**ShortName:** SP.ListDataValidationExceptionValue

Specifies failure information for a failed **field (2)** or **list item data validation**.

#### **3.2.5.83.1 Properties**

##### **3.2.5.83.1.1 Scalar Properties**

###### **3.2.5.83.1.1.1 FieldFailures**

**Type:** **CSOM array** of Microsoft.SharePoint.Client.ListDataValidationFailure

**Accessibility:** Read Only

Specifies the collection of all failures that occurred during **field (2) data validation**.

###### **3.2.5.83.1.1.2 ItemFailure**

**Type:** Microsoft.SharePoint.Client.ListDataValidationFailure

**Accessibility:** Read Only

Specifies a failure that occurred during **list item data validation**.

### 3.2.5.83.1.2 ObjectPath Properties

None.

### 3.2.5.84 Microsoft.SharePoint.Client.ListDataValidationFailure

**TypeId:** {6E0BC783-53A2-4506-827F-135040524794}

**ShortName:** SP.ListDataValidationFailure

This class describes a specific validation failure during a list item insert or update.

#### 3.2.5.84.1 Properties

##### 3.2.5.84.1.1 Scalar Properties

###### 3.2.5.84.1.1.1 DisplayName

**Type:** CSOM String

**Accessibility:** Read Only

This property contains the list's title when the ValidationType property is SPValidationType.UserFormulaItem; otherwise, it contains the field display name.

###### 3.2.5.84.1.1.2 Message

**Type:** CSOM String

**Accessibility:** Read Only

If the Reason property is SPReason.DataFailure, then this property contains the validation message provided by the formula author when the ValidationType property is SPValidationType.UserFormulaItem or SPValidationType.UserFormulaField. For other SPValidationTypes, a static message is provided. If the Reason property is SPReason.FormulaError, then this property contains a static message indicating that the formula evaluated to an error (such as #REF!, #DIV/0!, #NAME!, etc.).

###### 3.2.5.84.1.1.3 Name

**Type:** CSOM String

**Accessibility:** Read Only

This property contains the list ID when the ValidationType property is SPValidationType.UserFormulaItem; otherwise, it contains the internal field name.

###### 3.2.5.84.1.1.4 Reason

**Type:** Microsoft.SharePoint.Client.ListDataValidationFailureReason

**Accessibility:** Read Only

This property describes the reason for the failure.

###### 3.2.5.84.1.1.5 ValidationType

**Type:** Microsoft.SharePoint.Client.ListDataValidationType

**Accessibility:** Read Only

This property describes the type of validation that triggered this failure.

### 3.2.5.84.1.2 ObjectPath Properties

None.

### 3.2.5.85 Microsoft.SharePoint.Client.ListDataValidationFailureReason

**ShortName:** SP.ListDataValidationFailureReason

**Flag:** false

This enum describes the type of error that triggered the validation failure for a particular validation type. Descriptions Data - The formula evaluated to false (or a value considered equivalent to false such as zero for a numeric result), or non-formula-based validation (such as required field validation) failed. Error - Evaluation of a formula resulted in an error (such as #NAME!). This SHOULD be kept in-sync with the enum ListDataFailureReason in sts\tp\tsapi\listdatavalidation.h.

#### 3.2.5.85.1 Field Values

##### 3.2.5.85.1.1 DataFailure

**Value:** 0

The data validation formula evaluates to false or to a value equivalent to false.

##### 3.2.5.85.1.2 FormulaError

**Value:** 1

The data validation formula contains an error.

### 3.2.5.86 Microsoft.SharePoint.Client.ListDataValidationType

**ShortName:** SP.ListDataValidationType

**Flag:** false

This enum describes the type of validation that triggered the failure. This SHOULD be kept in-sync with the enum ListDataValidationType in sts\tp\tsapi\listdatavalidation.h.

#### 3.2.5.86.1 Field Values

##### 3.2.5.86.1.1 UserFormulaField

**Value:** 0

This is a field validation formula created by a list author.

##### 3.2.5.86.1.2 UserFormulaItem

**Value:** 1

This is an item validation formula created by a list author.

##### 3.2.5.86.1.3 RequiredField

**Value:** 2

No value was provided for a required field.

#### 3.2.5.86.1.4 ChoiceField

**Value:** 3

The value was not one of the available choices for the field.

#### 3.2.5.86.1.5 MinMaxField

**Value:** 4

The value violated the field's **MinimumValue** (section [3.2.5.53.1.1.14](#)) or **MaximumValue** (section [3.2.5.53.1.1.13](#)) constraints.

#### 3.2.5.86.1.6 TextField

**Value:** 5

The value violated the field's **MaxLength** constraint (section [3.2.5.57.1.1.13](#)).

### 3.2.5.87 Microsoft.SharePoint.Client.ListItem

**TypeId:** {53CC48C0-1777-47B7-99CA-729390F06602}

**ShortName:** SP.ListItem

Specifies a **list item**.

Contains **CSOM expando fields**, which correspond to the **fields (2)** defined in the **parent list**. The CSOM expando field name is the name of the field (2) defined in the **list** and the CSOM expando field value is the field (2) value in the list item. The following table specifies the mapping between **field types** and values.

Field type	Mapping to a value
<b>Integer</b>	When its value is undefined it MUST be NULL, otherwise it MUST be a <b>CSOM Int32</b> .
<b>Text</b>	When its value is undefined it MUST be NULL, otherwise it MUST be a <b>CSOM String</b> .
<b>Note</b>	When its value is undefined it MUST be NULL, otherwise it MUST be a <b>CSOM String</b> .
<b>DateTime</b>	When its value is undefined it MUST be NULL, otherwise it MUST be a <b>CSOM DateTime</b> .
<b>Counter</b>	It MUST be a <b>CSOM Int32</b> .
<b>Choice</b>	When its value is undefined it MUST be NULL, otherwise it MUST be a <b>CSOM String</b> .
<b>Lookup</b>	When its value is undefined it MUST be NULL, otherwise it MUST be a <b>CSOM Object</b> of type <b>FieldLookupValue</b> , as specified in section <a href="#">3.2.5.50</a> .
<b>Boolean</b>	When its value is undefined it MUST be NULL, otherwise it MUST be a <b>CSOM Boolean</b> .
<b>Number</b>	When its value is undefined it MUST be NULL, otherwise it MUST be a <b>CSOM Double</b> .
<b>Currency</b>	When its value is undefined it MUST be NULL, otherwise it MUST be a <b>CSOM</b>

Field type	Mapping to a value
	<b>Double.</b>
<b>URL</b>	When its value is undefined it MUST be NULL, otherwise it MUST be a CSOM Object of type <b>FieldUriValue</b> , as specified in section <a href="#">3.2.5.60</a> .
<b>Computed</b>	N/A
<b>Threading</b>	When its value is undefined it MUST be NULL, otherwise it MUST be a <b>CSOM String</b> .
<b>Guid</b>	When its value is undefined it MUST be NULL, otherwise it MUST be a <b>CSOM GUID</b> .
<b>MultiChoice</b>	When its value is undefined it MUST be NULL, otherwise it MUST be a <b>CSOM Array</b> .
<b>GridChoice</b>	When its value is undefined it MUST be NULL, otherwise it MUST be a <b>CSOM Array</b> .
<b>Calculated</b>	N/A
<b>File</b>	When its value is undefined it MUST be NULL, otherwise it MUST be a <b>CSOM String</b> .
<b>Attachments</b>	When its value is undefined it MUST be NULL, otherwise it MUST be a <b>CSOM Boolean</b> .
<b>User</b>	When its value is undefined it MUST be NULL, otherwise it MUST be a CSOM Object of type <b>FieldUserValue</b> , as specified in section <a href="#">3.2.5.63</a> .
<b>Recurrence</b>	When its value is undefined it MUST be NULL, otherwise it MUST be a <b>CSOM Boolean</b> .
<b>CrossProjectLink</b>	When its value is undefined it MUST be NULL, otherwise it MUST be a <b>CSOM Boolean</b> .
<b>ModStat</b>	When its value is undefined it MUST be NULL, otherwise it MUST be a <b>CSOM Int32</b> .
<b>Error</b>	N/A
<b>ContentTypeId</b>	When its value is undefined it MUST be NULL, otherwise it MUST be CSOM Object of type <b>ContentTypeId</b> , as specified in section <a href="#">3.2.5.30</a> .
<b>PageSeparator</b>	N/A
<b>ThreadIndex</b>	When its value is undefined it MUST be NULL, otherwise it MUST be a <b>CSOM String</b> .
<b>WorkflowStatus</b>	When its value is undefined it MUST be NULL, otherwise it MUST be a <b>CSOM Int32</b> .
<b>AllDayEvent</b>	When its value is undefined it MUST be NULL, otherwise it MUST be a <b>CSOM Boolean</b> .
<b>WorkflowEventType</b>	When its value is undefined it MUST be NULL, otherwise it MUST be a <b>CSOM Int32</b> .
<b>Facilities</b>	When its value is undefined it MUST be NULL, otherwise it MUST be a <b>CSOM Array</b> .
<b>FreeBusy</b>	When its value is undefined it MUST be NULL, otherwise it MUST be a <b>CSOM String</b> .
<b>Overbook</b>	When its value is undefined it MUST be NULL, otherwise it MUST be a <b>CSOM String</b> .
<b>Confidential</b>	When its value is undefined it MUST be NULL, otherwise it MUST be a <b>CSOM Boolean</b> .
<b>WhatsNew</b>	When its value is undefined it MUST be NULL, otherwise it MUST be a <b>CSOM Boolean</b> .
<b>DueDate</b>	When its value is undefined it MUST be NULL, otherwise it MUST be a <b>CSOM DateTime</b> .



Field type	Mapping to a value
<b>AllowEditing</b>	When its value is undefined it MUST be NULL, otherwise it MUST be a <b>CSOM Boolean</b> .
<b>SendTo</b>	When its value is undefined it MUST be NULL, otherwise it MUST be a <b>CSOM Array</b> .
<b>Confirmations</b>	When its value is undefined it MUST be NULL, otherwise it MUST be a <b>CSOM String</b> .
<b>CallTo</b>	When its value is undefined it MUST be NULL, otherwise it MUST be a <b>CSOM Array</b> .
<b>CallTime</b>	When its value is undefined it MUST be NULL, otherwise it MUST be a <b>CSOM DateTime</b> .
<b>Whereabout</b>	When its value is undefined it MUST be NULL, otherwise it MUST be a <b>CSOM String</b> .
<b>From</b>	When its value is undefined it MUST be NULL, otherwise it MUST be a <b>CSOM DateTime</b> .
<b>Until</b>	When its value is undefined it MUST be NULL, otherwise it MUST be a <b>CSOM DateTime</b> .
<b>ContactInfo</b>	When its value is undefined it MUST be NULL, otherwise it MUST be a <b>CSOM String</b> .

The Client\_Title, CommentsDisabled, CommentsDisabledScope, DisplayName, EffectiveBasePermissions, EffectiveBasePermissionsForUI, HasUniqueRoleAssignments and IconOverlay properties are not included in the **default scalar property set** for this type.

### 3.2.5.87.1 Properties

#### 3.2.5.87.1.1 Scalar Properties

##### 3.2.5.87.1.1.1 DisplayName

**Type:** CSOM String

**Accessibility:** Read Only

Specifies the **display name** of the **list item**.

It MUST NOT be NULL. It MUST NOT be empty.

##### 3.2.5.87.1.1.2 EffectiveBasePermissions

**Type:** Microsoft.SharePoint.Client.BasePermissions

**Accessibility:** Read Only

Specifies the **permissions** on the **list item** that are assigned to the **current user**.

It MUST NOT be NULL.

##### 3.2.5.87.1.1.3 FileSystemObjectType

**Type:** Microsoft.SharePoint.Client.FileSystemObjectType

**Accessibility:** Read Only

Specifies whether the **list item** is a **file** or a **list folder**.

It MUST be one of the following values: File or Folder.

#### **3.2.5.87.1.1.4 HasUniqueRoleAssignments**

**Type:** CSOM Boolean

**Accessibility:** Read Only

Specifies whether the **role assignments** are uniquely defined for the **list item**. If the value is "false", role assignments are inherited from the **parent list**.

#### **3.2.5.87.1.1.5 Id**

**Type:** CSOM Int32

**Accessibility:** Read Only

Specifies the **list item identifier**. It MUST be 0 for a **list item** in an **external list**. It MUST be -1 for list items that have not yet been added to a **list**.

#### **3.2.5.87.1.1.6 EffectiveBasePermissionsForUI**

**Type:** Microsoft.SharePoint.Client.BasePermissions

**Accessibility:** Read Only

Specifies the effective base permissions for the current user, as they SHOULD be displayed in the user interface (UI).<61> If the list is not in read-only UI mode, the value of **EffectiveBasePermissionsForUI** MUST be the same as the value of **EffectiveBasePermissions** (section 3.2.5.87.1.1.2). If the list is in read-only UI mode, the value of **EffectiveBasePermissionsForUI** MUST be a subset of the value of **EffectiveBasePermissions**.

It MUST NOT be NULL.

#### **3.2.5.87.1.1.7 Client\_Title**

**Type:** CSOM String

**Accessibility:** Read Only

Gets the title of the item.

#### **3.2.5.87.1.1.8 CommentsDisabled**

**Type:** CSOM Boolean

**Accessibility:** Read Only

Indicates whether comments for this item are disabled or not.

#### **3.2.5.87.1.1.9 CommentsDisabledScope**

**Type:** Microsoft.SharePoint.Comments.CommentsDisabledScope

**Accessibility:** Read Only

Indicates at what scope comments are disabled.

#### **3.2.5.87.1.1.10 IconOverlay**

**Type:** CSOM String

**Accessibility:** Read/Write

This is an overlay icon for the item. If the parent list of the item does not already have the IconOverlay field and The user setting the property does not have rights to add the field to the list then the property will not be set for the item.

### 3.2.5.87.1.1.11 ServerRedirectedEmbedUri

**Type:** CSOM String

**Accessibility:** Read Only

Returns the path for previewing a document in the browser, often in an interactive way, if that feature exists.

### 3.2.5.87.1.1.12 ServerRedirectedEmbedUrl

**Type:** CSOM String

**Accessibility:** Read Only

Returns the URL for previewing a document in the browser, often in an interactive way, if that feature exists. This is currently used in the hovering panel of search results and document library.

## 3.2.5.87.1.2 ObjectPath Properties

### 3.2.5.87.1.2.1 ContentType

**Type:** Microsoft.SharePoint.Client.ContentType

**Accessibility:** Read Only

Specifies the **content type** of the **list item**. It MUST be NULL if the list item has no content type.

### 3.2.5.87.1.2.2 FieldValuesAsHtml

**Type:** Microsoft.SharePoint.Client.FieldStringValue

**Accessibility:** Read Only

Specifies the values for the **list item** as **Hypertext Markup Language (HTML)**.

It MUST NOT be NULL.

### 3.2.5.87.1.2.3 FieldValuesAsText

**Type:** Microsoft.SharePoint.Client.FieldStringValue

**Accessibility:** Read Only

Specifies the values for the **list item** as text.

It MUST NOT be NULL.

### 3.2.5.87.1.2.4 FieldValuesForEdit

**Type:** Microsoft.SharePoint.Client.FieldStringValue

**Accessibility:** Read Only

Specifies the formatted values to be displayed in an **edit form**.

It MUST NOT be NULL.

### **3.2.5.87.1.2.5 File**

**Type:** Microsoft.SharePoint.Client.File

**Accessibility:** Read Only

Specifies the **file** associated with the **list item**. It MUST be NULL if the **parent list** is not a **document library** or **FileSystemObjectType** is **Folder**.

### **3.2.5.87.1.2.6 ParentList**

**Type:** Microsoft.SharePoint.Client.List

**Accessibility:** Read Only

Specifies the **parent list** that contains the **list item**.

It MUST NOT be NULL.

### **3.2.5.87.1.2.7 RoleAssignments**

**Type:** Microsoft.SharePoint.Client.RoleAssignmentCollection

**Accessibility:** Read Only

Specifies the **role assignments** for the **list item**.

### **3.2.5.87.1.2.8 AttachmentFiles**

**Type:** Microsoft.SharePoint.Client.AttachmentCollection

**Accessibility:** Read Only

Specifies the collection of attachments that are associated with the **list item**.[<62>](#)

### **3.2.5.87.1.2.9 FirstUniqueAncestorSecurableObject**

**Type:** Microsoft.SharePoint.Client.SecurableObject

**Accessibility:** Read Only

See **Microsoft.SharePoint.Client.SecurableObject.FirstUniqueAncestorSecurableObject**, as specified in section [3.2.5.118.1.2.2.<63>](#)

### **3.2.5.87.1.2.10 Folder**

**Type:** Microsoft.SharePoint.Client.Folder

**Accessibility:** Read Only

Gets a **Microsoft.SharePoint.Client.Folder** (section [3.2.5.72](#)) object that is associated with the **list item**.[<64>](#)

Returns **null** if the list item is not a **folder**.

### 3.2.5.87.1.2.11 GetDlpPolicyTip

**Type:** Microsoft.SharePoint.Client.DlpPolicyTip

**Accessibility:** Read Only

Gets the Data Loss Protection policy tip notification for this item.

### 3.2.5.87.1.2.12 Activities

**Type:** Microsoft.SharePoint.Activities.SPActivityEntitySet

**Accessibility:** Read Only

Returns from the Activities Table the collection of all activities.

### 3.2.5.87.1.2.13 Properties

**Type:** Microsoft.SharePoint.Client.PropertyValues

**Accessibility:** Read Only

Gets a collection of all the properties for the list item.

It MUST NOT be NULL.

### 3.2.5.87.1.2.14 Versions

**Type:** Microsoft.SharePoint.Client.ListItemVersionCollection

**Accessibility:** Read Only

Gets the collection of item version objects that represent the versions of the item.

It MUST NOT be NULL.

## 3.2.5.87.2 Methods

### 3.2.5.87.2.1 Scalar Methods

#### 3.2.5.87.2.1.1 BreakRoleInheritance

**Return Type:** None

Updates the **list item** to stop inheriting **role assignments** from the **parent list** or the parent **folder**.

**Parameters:**

*copyRoleAssignments*: Specifies whether to perform a one-time copy of the role assignments from the parent list or the parent folder to the list item. If "false", the list item MUST be given one role assignment containing the **current user**.

Type: **CSOM Boolean**

*clearSubscopes*: Specifies whether the role assignments for all child list items MUST be cleared.

Type: CSOM Boolean

#### 3.2.5.87.2.1.2 DeleteObject

**Return Type:** None

Deletes the **list item**.

**Parameters:** None

**Exceptions:**

Error Code	Error Type Name	Condition
-1	System.InvalidOperationException	<b>List</b> does not support this operation or the list item does not exist in the <b>external list</b> .

### 3.2.5.87.2.1.3 ParseAndSetFieldValue

**Return Type:** None

Sets the value of the **field (2)** for the **list item** based on an implementation-specific transformation of the value.

**Parameters:**

*fieldName*: Specifies the **field internal name**.

Type: **CSOM String**

*value*: Specifies the new value for the field (2).

Type: CSOM String

**Exceptions:**

Error Code	Error Type Name	Condition
-2130575155	Microsoft.SharePoint.SPFieldValueException	Field (2) is required and <b>value</b> is NULL or empty, the field (2) does not support setting values, or the value cannot be converted to the type of the field (2).

### 3.2.5.87.2.1.4 Recycle

**Return Type:** **CSOM GUID**

Moves the **list item** to the **Recycle Bin** and returns the identifier of the new **Recycle Bin item**.

**Parameters:** None

**Exceptions:**

Error Code	Error Type Name	Condition
-2130575338	Microsoft.SharePoint.SPException	List item does not exist.
-1	System.NotSupportedException	Method called on an <b>external list</b> .

### 3.2.5.87.2.1.5 ResetRoleInheritance

**Return Type:** None

Updates the **list item** to inherit **role assignments** from the **parent list** or the parent **folder**.

**Parameters:** None

### 3.2.5.87.2.1.6 SetFieldValue

**Return Type:** None

Sets the value of the **field (2)** for the **list item**.

**Parameters:**

*fieldName*: Specifies the **field internal name**.

Type: **CSOM String**

*value*: Specifies the new value for the field (2).

Type: **CSOM Object**

**Exceptions:**

Error Code	Error Type Name	Condition
-2130575155	Microsoft.SharePoint.SPFieldValueException	Field (2) is required and <b>value</b> is NULL or empty, the field (2) does not support setting values, or the value cannot be converted to the type of the field (2).

### 3.2.5.87.2.1.7 Update

**Return Type:** None

Commits changed properties of the **list item**.

**Parameters:** None

**Exceptions:**

Error Code	Error Type Name	Condition
-2130575305	Microsoft.SharePoint.SPException	List item was modified on the server in a way that prevents changes from being committed, as determined by the protocol server.
-1	System.InvalidOperationException	<b>List</b> does not support this operation.

### 3.2.5.87.2.1.8 GetWOPIFrameUrl

**Return Type:** **CSOM String**

Validates that the action is available for this **list item**. If the action is available, sets the string to a **URI** for operating on the list item with the provided action. If the action is not available, sets the string to String.Empty.

**Parameters:**

*action*: Indicates which user action is indicated in the returned WOPIFrameUrl.

Type: Microsoft.SharePoint.Client.Utilities.SPWOPIFrameAction

### 3.2.5.87.2.1.9 ValidateUpdateListItem

**Return Type:** **CSOM array** of Microsoft.SharePoint.Client.ListItemFormUpdateValue

Validates and sets the values of the specified collection of **fields (2)** for the **list item** and, if successfully validated, commits all changes. Returns the modified list of values with updated exception information.

**Parameters:**

*formValues*: Specifies a collection of **field internal names** and values for the given field (2).

Type: CSOM array of Microsoft.SharePoint.Client.ListItemFormUpdateValue

If the collection is empty, no update will take place.

It MUST NOT be NULL.

*bNewDocumentUpdate*: Specifies whether the list item is a document being updated after upload.

Type: **CSOM Boolean**

*checkInComment*: Check-in comment, if any. This parameter is only applicable when the list item is checked out.

Type: **CSOM String**

**Exceptions:**

Error Code	Error Type Name	Condition
-2147024809	System.ArgumentException	A field (2) with the specified internal name does not exist.

### 3.2.5.87.2.1.10 GetUserEffectivePermissions

**Return Type:** Microsoft.SharePoint.Client.BasePermissions

Returns the user permissions for this **list item**.

**Parameters:**

*userName*: Specifies the user login name.

Type: **CSOM String**

It MUST NOT be NULL.

### 3.2.5.87.2.1.11 OverridePolicyTip



**Return Type:** Microsoft.SharePoint.Client.PolicyTipUserActionResult

Overrides the policy tip on this **list item**.

**Parameters:**

*userAction:* The user action to take.

Type: Microsoft.SharePoint.Client.PolicyTipUserAction

*justification:* The reason why the override is being done.

Type: **CSOM String**

### 3.2.5.87.2.1.12 SetCommentsDisabled

**Return Type:** None

Sets the value of **CommentsDisabled** (section [3.2.5.87.1.1.8](#)) for the item.

**Parameters:**

*value:* The new value.

Type: **CSOM Boolean**

### 3.2.5.87.2.1.13 SystemUpdate

**Return Type:** None

Updates the database with changes made to the list item.

**Parameters:** None

**Exceptions:**

Error Code	Error Type Name	Condition
-2130575305	Microsoft.SharePoint.SPException	Save Conflict. Your changes conflict with those made concurrently by another user. If you want your changes to be applied, click Back in your Web browser, refresh the page, and resubmit your changes.
-1	System.InvalidOperationException	Operation is not supported.

### 3.2.5.87.2.1.14 UpdateOverwriteVersion

**Return Type:** None

Updates the item without creating another version of the item.

**Parameters:** None

## 3.2.5.87.2.2 ObjectPath Methods

### 3.2.5.87.2.2.1 GetChanges

**Return Type:** Microsoft.SharePoint.Client.ChangeCollection

Returns from the change log the collection of all of the changes that have occurred within the scope of the SharePoint list item, based on the specified query.

**Parameters:**

*query*: The query parameters used to get the collection of changes from the change log.

Type: Microsoft.SharePoint.Client.ChangeQuery

It MUST NOT be NULL.

### **3.2.5.88 Microsoft.SharePoint.Client.ListItemCollection**

**TypeId:** {1722DF25-A4D3-44BB-A1C6-04DBB90E9D91}

**ShortName:** SP.ListItemCollection

Specifies a collection of **list items**.

#### **3.2.5.88.1 Properties**

##### **3.2.5.88.1.1 Scalar Properties**

###### **3.2.5.88.1.1.1 ListItemCollectionPosition**

**Type:** Microsoft.SharePoint.Client.ListItemCollectionPosition

**Accessibility:** Read Only

Specifies the information required to get the next page of data for a **list view**.

##### **3.2.5.88.1.2 ObjectPath Properties**

None.

#### **3.2.5.88.2 Methods**

##### **3.2.5.88.2.1 Scalar Methods**

None.

##### **3.2.5.88.2.2 ObjectPath Methods**

###### **3.2.5.88.2.2.1 GetById**

**Return Type:** Microsoft.SharePoint.Client.ListItem

Returns the **list item** with the specified **list item identifier**.

**Parameters:**

*id*: The list item identifier.

Type: **CSOM Int32**

###### **3.2.5.88.2.2.2 GetByStringId**

**Return Type:** Microsoft.SharePoint.Client.ListItem

Returns the **list item** with either the specified **list item identifier** or the specified identifier for an instance of an **external content type**.

**Parameters:**

*sId*: Specifies the list item identifier, or if the **list** is an **external list**, specifies the identifier for an instance of an external content type as specified in [\[MS-ECTPWPS\]](#) section 3.1.4.1.2.1.

Type: **CSOM String**

**Exceptions:**

Error Code	Error Type Name	Condition
-2130575338	Microsoft.SharePoint.SPException	List item does not exist, and the list is an external list.
-1	System.FormatException	<b>sId</b> is a list item identifier with invalid format, and the list is NOT an external list.
-1	System.OverflowException	The list does NOT have an external data source and the specified ID is an integer requiring more than 32 bits to represent.

### 3.2.5.89 Microsoft.SharePoint.Client.ListItemCollectionPosition

**TypeId:** {922354EB-C56A-4D88-AD59-67496854EFE1}

**ShortName:** SP.ListItemCollectionPosition

Specifies the information required to get the next page of data for a **list view**.

#### 3.2.5.89.1 Properties

##### 3.2.5.89.1.1 Scalar Properties

###### 3.2.5.89.1.1.1 PagingInfo

Type: **CSOM String**

**Accessibility:** Read/Write

Specifies information, as name-value pairs, required to get the next page of data for a **list view**. If a name appears more than once, one value **MUST** be used.

It **MUST** conform to the following ABNF as defined in [\[RFC5234\]](#):

PagingInfo = 0\*1(NameValuePair 0\*601("&" NameValuePair))

NameValuePair = Name "=" Value

Value = 1\*(Alphanum / Mark / Escaped)

Name = 1\*(Alphanum / Mark)

Escaped = "%" HEXDIG HEXDIG

Mark = "-" / "\_" / "." / "!" / "~" / "\*" / "" / "(" / ")"

Alphanum = DIGIT / ALPHA

### 3.2.5.89.1.2 ObjectPath Properties

None.

### 3.2.5.90 Microsoft.SharePoint.Client.ListItemCreationInformation

**TypeId:** {54CDBEE5-0897-44AC-829F-411557FA11BE}

**ShortName:** SP.ListItemCreationInformation

Specifies the properties of the new **list item**.

#### 3.2.5.90.1 Properties

##### 3.2.5.90.1.1 Scalar Properties

###### 3.2.5.90.1.1.1 FolderUrl

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies the **folder** for the new **list item**.

It MUST be NULL, empty, a **server-relative URL**, or an **absolute URL**. If the value is a server-relative URL or an absolute URL, it MUST be under the **root folder** of the **list**.

###### 3.2.5.90.1.1.2 LeafName

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies the name of the new **list item**. It MUST be the name of the **file** if the **parent list** of the list item is a **document library**.

Its length MUST be equal to or less than 128. It MUST NOT contain the following characters: \x00-\x1F, \x22, \x23, \x25, \x26, \x2A, \x3A, \x3C, x3E, \x3F, \x5C and \x7B-\x9F.

###### 3.2.5.90.1.1.3 UnderlyingObjectType

**Type:** Microsoft.SharePoint.Client.FileSystemObjectType

**Accessibility:** Read/Write

Specifies whether the new **list item** is a **file** or a **folder**.

It MUST be one of the following values: **File** or **Folder**.

### 3.2.5.90.1.2 ObjectPath Properties

None.

### 3.2.5.91 Microsoft.SharePoint.Client.ListTemplate

**TypeId:** {D772ECD1-DAA3-4CB1-9EA1-FEEA1E383FB2}

**ShortName:** SP.ListTemplate

Represents a list definition or a list template, which defines the fields and views for a list. List definitions are contained in files within \\Program Files\Common Files\Microsoft Shared\Web Server Extensions\12\TEMPLATE\FEATURES, but list templates are created through the user interface or through the object model when a list is saved as a template.

Use the `Web.ListTemplates` property (section [3.2.5.143.1.2.13](#)) to return a `ListTemplateCollection` (section [3.2.5.92](#)) for a site collection. Use an indexer to return a single list definition or list template from the collection.

### **3.2.5.91.1 Properties**

#### **3.2.5.91.1.1 Scalar Properties**

##### **3.2.5.91.1.1.1 AllowsFolderCreation**

**Type:** CSOM Boolean

**Accessibility:** Read Only

Gets a Boolean value indicating whether folders can be created within lists created through the list definition or template.

##### **3.2.5.91.1.1.2 BaseType**

**Type:** Microsoft.SharePoint.Client.BaseType

**Accessibility:** Read Only

Gets the base type for the list definition or list template.

##### **3.2.5.91.1.1.3 Description**

**Type:** CSOM String

**Accessibility:** Read Only

Gets the description of the list definition or list template that is displayed in the user interface.

##### **3.2.5.91.1.1.4 FeatureId**

**Type:** CSOM GUID

**Accessibility:** Read Only

Gets the ID of the Feature containing the list definition.

##### **3.2.5.91.1.1.5 Hidden**

**Type:** CSOM Boolean

**Accessibility:** Read Only

Gets a Boolean value that specifies whether the list definition or list template is hidden from Web site users and does not appear as an option on the Create page.

##### **3.2.5.91.1.1.6 ImageUrl**

**Type:** CSOM String

**Accessibility:** Read Only

Gets the relative path, based on the server, for the image used to represent the list definition or list template.

It MUST NOT be NULL. Its length MUST be equal to or less than 255. It MUST be a server-relative URL or an absolute URL.

#### **3.2.5.91.1.1.7 InternalName**

**Type:** CSOM String

**Accessibility:** Read Only

Gets the internal name used for the list definition or list template.

It MUST NOT be NULL.

#### **3.2.5.91.1.1.8 IsCustomTemplate**

**Type:** CSOM Boolean

**Accessibility:** Read Only

Gets a Boolean value that indicates whether the SP.ListTemplate object represents a list template, in other words, a template contained within an .stp file (custom template file).

#### **3.2.5.91.1.1.9 ListTemplateTypeKind**

**Type:** CSOM Int32

**Accessibility:** Read Only

Gets the type of the list definition or list template.

#### **3.2.5.91.1.1.10 Name**

**Type:** CSOM String

**Accessibility:** Read Only

Gets the display name for the list definition or list template.

It MUST NOT be NULL.

#### **3.2.5.91.1.1.11 OnQuickLaunch**

**Type:** CSOM Boolean

**Accessibility:** Read Only

Gets a Boolean value that specifies whether any list created with the list definition or list template is displayed on the Quick Launch bar.

#### **3.2.5.91.1.1.12 Unique**

**Type:** CSOM Boolean

**Accessibility:** Read Only

Gets a Boolean value that indicates whether only one instance of the list type can be created through the template, and that the template cannot be used to create a list through the object model or user interface.

### 3.2.5.91.1.2 ObjectPath Properties

None.

### 3.2.5.91.2 Methods

#### 3.2.5.91.2.1 Scalar Methods

##### 3.2.5.91.2.1.1 GetGlobalSchemaXml

**Return Type:** CSOM Stream

Retrieves the global schema.xml file.

**Parameters:** None

#### 3.2.5.91.2.2 ObjectPath Methods

None.

### 3.2.5.92 Microsoft.SharePoint.Client.ListTemplateCollection

**TypeId:** {23748D10-16A1-4946-A38B-98FDEC0E0EC8}

**ShortName:** SP.ListTemplateCollection

Specifies a collection of **list templates** (section [3.2.5.91](#)).

#### 3.2.5.92.1 Properties

##### 3.2.5.92.1.1 Scalar Properties

None.

##### 3.2.5.92.1.2 ObjectPath Properties

None.

#### 3.2.5.92.2 Methods

##### 3.2.5.92.2.1 Scalar Methods

None.

##### 3.2.5.92.2.2 ObjectPath Methods

###### 3.2.5.92.2.2.1 GetByName

**Return Type:** Microsoft.SharePoint.Client.ListTemplate

Returns the **list template** with the specified name. [<65>](#)

**Parameters:**

*name*: The specified name.

Type: **CSOM String**

**3.2.5.93 Microsoft.SharePoint.Client.ListTemplateType**

**ShortName:** SP.ListTemplateType

**Flag:** false

Specifies the type of a **list template**. A set of predefined values are specified in [\[MS-WSSTS\]](#) section 2.7.

**3.2.5.93.1 Field Values****3.2.5.93.1.1 NoListTemplate**

**Value:** 0

Specifies no template applies.

**3.2.5.93.1.2 GenericList**

**Value:** 100

Specifies a basic **list**.

**3.2.5.93.1.3 DocumentLibrary**

**Value:** 101

Specifies a **Document library**.

**3.2.5.93.1.4 Survey**

**Value:** 102

Specifies a survey **list**.

**3.2.5.93.1.5 Links**

**Value:** 103

Specifies a **links list**.

**3.2.5.93.1.6 Announcements**

**Value:** 104

Specifies an announcements **list**.

**3.2.5.93.1.7 Contacts**

**Value:** 105

Specifies a contacts **list**.



### **3.2.5.93.1.8 Events**

**Value:** 106

Specifies a calendar **list**.

### **3.2.5.93.1.9 Tasks**

**Value:** 107

Specifies a **task list**.

### **3.2.5.93.1.10DiscussionBoard**

**Value:** 108

Specifies a **discussion board**.

### **3.2.5.93.1.11PictureLibrary**

**Value:** 109

Specifies a **picture library**.

### **3.2.5.93.1.12DataSources**

**Value:** 110

Specifies a **list** of **data sources** for a **site (2)**.

### **3.2.5.93.1.13WebTemplateCatalog**

**Value:** 111

Specifies a **site template gallery**.

### **3.2.5.93.1.14UserInformation**

**Value:** 112

Specifies a **user information list**.

### **3.2.5.93.1.15WebPartCatalog**

**Value:** 113

Specifies a **Web Part gallery**.

### **3.2.5.93.1.16ListTemplateCatalog**

**Value:** 114

Specifies a **list template gallery**.

### **3.2.5.93.1.17XMLForm**

**Value:** 115

Specifies an **XML form library**.

### **3.2.5.93.1.18MasterPageCatalog**

**Value:** 116

Specifies a **master page gallery**.

### **3.2.5.93.1.19NoCodeWorkflows**

**Value:** 117

Specifies a **declarative workflow** library.

### **3.2.5.93.1.20WorkflowProcess**

**Value:** 118

Specifies a **form custom action workflow** library.

### **3.2.5.93.1.21WebPageLibrary**

**Value:** 119

Specifies a Wiki Page library.

### **3.2.5.93.1.22CustomGrid**

**Value:** 120

Specifies a **custom list** in **datasheet view**.

### **3.2.5.93.1.23SolutionCatalog**

**Value:** 121

Specifies a **site solution gallery**.

### **3.2.5.93.1.24NoCodePublic**

**Value:** 122

Specifies a **site collection** scoped **declarative workflow** library.

### **3.2.5.93.1.25ThemeCatalog**

**Value:** 123

Specifies a **theme gallery**.

### **3.2.5.93.1.26DataConnectionLibrary**

**Value:** 130

Specifies a **data connection library**.

### **3.2.5.93.1.27WorkflowHistory**

**Value:** 140

Specifies a **workflow history list**.

### **3.2.5.93.1.28GanttTasks**

**Value:** 150

Specifies a project **tasks list**.

### **3.2.5.93.1.29Meetings**

**Value:** 200

Specifies a meeting series **list** in a **Meeting Workspace site**.

### **3.2.5.93.1.30Agenda**

**Value:** 201

Specifies an agenda **list** in a **Meeting Workspace site**.

### **3.2.5.93.1.31MeetingUser**

**Value:** 202

Specifies an attendees **list** in a **Meeting Workspace site**.

### **3.2.5.93.1.32Decision**

**Value:** 204

Specifies a decisions **list** in a **Meeting Workspace site**.

### **3.2.5.93.1.33MeetingObjective**

**Value:** 207

Specifies an objectives **list** in a **Meeting Workspace site**.

### **3.2.5.93.1.34TextBox**

**Value:** 210

Specifies a text box **list** in a **Meeting Workspace site**.

### **3.2.5.93.1.35ThingsToBring**

**Value:** 211

Specifies a "things to bring" **list** in a **Meeting Workspace site**.

### **3.2.5.93.1.36HomePageLibrary**

**Value:** 212

Specifies a pages library in a **Meeting Workspace site**.

### **3.2.5.93.1.37Posts**

**Value:** 301

Specifies a posts **list** in a **blog**.

### **3.2.5.93.1.38Comments**

**Value:** 302

Specifies a comments **list** in a **blog**.

### **3.2.5.93.1.39Categories**

**Value:** 303

Specifies a categories **list** in a **blog**.

### **3.2.5.93.1.40Facility**

**Value:** 402

Specifies a **list** to document shared assets in a group worksite.

### **3.2.5.93.1.41Whereabouts**

**Value:** 403

Specifies a **list** to track employee locations in a group worksite.

### **3.2.5.93.1.42CallTrack**

**Value:** 404

Specifies a **list** to track incoming phone call information in a group worksite.

### **3.2.5.93.1.43Circulation**

**Value:** 405

Specifies a **list** to track the circulation of documents in a group worksite.

### **3.2.5.93.1.44Timecard**

**Value:** 420

Specifies a **list** to manage work hours in a group worksite.

### **3.2.5.93.1.45Holidays**

**Value:** 421

Specifies a **list** that can be used to add holidays to a calendar.

### **3.2.5.93.1.46IMEDic**

**Value:** 499

Specifies an **IME** dictionary list.

### **3.2.5.93.1.47ExternalList**

**Value:** 600

Specifies an **external list**.

### **3.2.5.93.1.48IssueTracking**

**Value:** 1100

Specifies an issue tracking **list**.

### **3.2.5.93.1.49AdminTasks**

**Value:** 1200

Specifies an Administrator **tasks list**.

### **3.2.5.93.1.50HealthRules**

**Value:** 1220

Specifies a Health Rules **list**.

### **3.2.5.93.1.51HealthReports**

**Value:** 1221

Specifies a Health Reports library.

### **3.2.5.93.1.52InvalidType**

**Value:** -1

Not used.

### **3.2.5.93.1.53AccessRequest**

**Value:** 160

Specifies a type of list that contains access requests. Access requests can be made for a site or for a list or for a list item. It also contains external user invitations. [<66>](#)

### **3.2.5.93.1.54DesignCatalog**

**Value:** 124

Specifies a type of list that contains designs. [<67>](#) Each design item defines a customized look for the site and contains references to the master page, theme, background image, and font for the look.

### **3.2.5.93.1.55MaintenanceLogs**

**Value:** 175

Specifies a maintenance log. [<68>](#)

### **3.2.5.93.1.56AppDataCatalog**

**Value:** 125

Specifies an **web application** data catalog.

### **3.2.5.93.1.57TasksWithTimelineAndHierarchy**

**Value:** 171

Specifies a tasks list with hierarchy and a timeline.

### **3.2.5.93.1.58MySiteDocumentLibrary**

**Value:** 700

Specifies a My Site Document library, the default document library on a user's My Site. [<69>](#)

### **3.2.5.93.1.59DeveloperSiteDraftApps**

**Value:** 1230

Stores a list of **apps (1)** deployed in a Developer Site. [<70>](#)

### **3.2.5.93.1.60HelpLibrary**

**Value:** 151

Specifies a help library.

### **3.2.5.93.1.61AccessApp**

**Value:** 3100

The list is an access app entry point.

### **3.2.5.93.1.62SharingLinks**

**Value:** 3300

The list is a list of sharing links.

### **3.2.5.93.1.63AppFilesCatalog**

**Value:** 126

Specifies an App Files catalog.

### **3.2.5.93.1.64PromotedLinks**

**Value:** 170

PromotedLinks List (shown in classic homepage).

### **3.2.5.93.1.65RecipesTable**

**Value:** 3410

Recipes Library.

### **3.2.5.93.1.66FormulasTable**

**Value:** 3411

Formulas Table.

### **3.2.5.93.1.67ItemReferenceCollection**

**Value:** 3500

Collection List of Item Reference.

### **3.2.5.93.1.68ItemReferenceReference**

**Value:** 3501

Reference List of Item Reference.

### **3.2.5.93.1.69ItemReferenceReferenceCollection**

**Value:** 3502

Reference Collection List of Item Reference.

### **3.2.5.93.1.70CertificateFileLists**

**Value:** 1222

Certificate file list.

## **3.2.5.94 Microsoft.SharePoint.Client.MoveOperations**

**ShortName:** SP.MoveOperations

**Flag:** true

Specifies criteria for how to move files.

### **3.2.5.94.1 Field Values**

#### **3.2.5.94.1.1 None**

**Value:** 0

Specifies no move operation is specified.

#### **3.2.5.94.1.2 Overwrite**

**Value:** 1

Specifies a **file** with the same name is to be overwritten if it exists.

#### **3.2.5.94.1.3 AllowBrokenThickets**

**Value:** 8

Specifies the move operation is to be finished even if **thicket supporting files** are separated from the **file**.

#### **3.2.5.94.1.4 BypassApprovePermission**

**Value:** 64

Specifies approval **permissions** are not required if there are no **published versions** of the **file**.

## **3.2.5.95 Microsoft.SharePoint.Client.Navigation**

**TypeId:** {D6AA87A7-71B3-4BBE-BCA7-00AB1BD7D37F}

**ShortName:** SP.Navigation

Represents navigation operations at the **site collection** level.

### 3.2.5.95.1 Properties

#### 3.2.5.95.1.1 Scalar Properties

##### 3.2.5.95.1.1.1 UseShared

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Specifies whether the **site (2)** inherits navigation. When this value is set, the change with the new value MUST be sent by the protocol client in the next request to the protocol server.

#### 3.2.5.95.1.2 ObjectPath Properties

##### 3.2.5.95.1.2.1 QuickLaunch

**Type:** Microsoft.SharePoint.Client.NavigationNodeCollection

**Accessibility:** Read Only

The collection of **navigation nodes** that correspond to links in the **Quick Launch** area of the **site (2)**. MUST be NULL if the Quick Launch is unavailable.

##### 3.2.5.95.1.2.2 TopNavigationBar

**Type:** Microsoft.SharePoint.Client.NavigationNodeCollection

**Accessibility:** Read Only

The collection of **navigation nodes** that correspond to links in the **link bar** of the **site (2)**. MUST be NULL if the top navigation bar is defined in a different site (2) or if the top navigation bar node collection has been deleted.

### 3.2.5.95.2 Methods

#### 3.2.5.95.2.1 Scalar Methods

None.

#### 3.2.5.95.2.2 ObjectPath Methods

##### 3.2.5.95.2.2.1 GetNodeById

**Return Type:** Microsoft.SharePoint.Client.NavigationNode

Gets the **navigation node** (**SP.NavigationNode**, section [3.2.5.96](#)) by using an integer identifier. [<71>](#)

**Parameters:**

*id*: Specifies the identifier of the navigation node.

Type: CSOM Int32



## 3.2.5.96 Microsoft.SharePoint.Client.NavigationNode

**TypeId:** {CD5D6053-7FFD-41AC-BF36-7B856320A122}

**ShortName:** SP.NavigationNode

Represents the **URL** to a specific **navigation node** and provides access to properties and methods for manipulating the ordering of the navigation node in a navigation node collection.

### 3.2.5.96.1 Properties

#### 3.2.5.96.1.1 Scalar Properties

##### 3.2.5.96.1.1.1 Id

**Type:** **CSOM Int32**

**Accessibility:** Read Only

Specifies the identifier for the **navigation node**.

##### 3.2.5.96.1.1.2 Title

**Type:** **CSOM String**

**Accessibility:** Read/Write

Specifies the **anchor text** for the **navigation node** link.

It MUST NOT be NULL. Its length MUST be equal to or less than 256.

##### 3.2.5.96.1.1.3 Url

**Type:** **CSOM String**

**Accessibility:** Read/Write

Specifies the **URL** stored with the **navigation node**.

MUST NOT be a URL of relative form if the URL corresponds to a page that is outside of the **site collection**.

It MUST be a URL of relative or absolute form.

##### 3.2.5.96.1.1.4 IsExternal

**Type:** **CSOM Boolean**

**Accessibility:** Read Only

Gets a **Boolean** value that specifies whether the navigation node URL corresponds to a page outside the **site collection**.[<72>](#)

##### 3.2.5.96.1.1.5 IsVisible

**Type:** **CSOM Boolean**

**Accessibility:** Read/Write

Gets or sets a **Boolean** value that specifies whether the **navigation node** is visible. <73>

### **3.2.5.96.1.1.6 IsDocLib**

**Type:** CSOM Boolean

**Accessibility:** Read Only

Gets a Boolean value that specifies whether the navigation node points to a **document library**.

### **3.2.5.96.1.1.7 ListTemplateType**

**Type:** Microsoft.SharePoint.Client.ListTemplateType

**Accessibility:** Read Only

An SP.ListTemplateType object that returns the **list template** type of the **list**.

## **3.2.5.96.1.2 ObjectPath Properties**

### **3.2.5.96.1.2.1 Children**

**Type:** Microsoft.SharePoint.Client.NavigationNodeCollection

**Accessibility:** Read Only

The collection of child nodes of the **navigation node**.

It MUST NOT be NULL.

## **3.2.5.96.2 Methods**

### **3.2.5.96.2.1 Scalar Methods**

#### **3.2.5.96.2.1.1 DeleteObject**

**Return Type:** None

Deletes the **navigation node**.

**Parameters:** None

#### **3.2.5.96.2.1.2 Update**

**Return Type:** None

Updates property changes that have been made to the **navigation node**.

**Parameters:** None

### **3.2.5.96.2.2 ObjectPath Methods**

None.

## **3.2.5.97 Microsoft.SharePoint.Client.NavigationNodeCollection**

**TypeId:** {2D818ED7-8FEF-4A1C-BCEB-A9404DFA482F}

**ShortName:** SP.NavigationNodeCollection

A collection of **navigation nodes**.

### **3.2.5.97.1 Properties**

#### **3.2.5.97.1.1 Scalar Properties**

None.

#### **3.2.5.97.1.2 ObjectPath Properties**

None.

### **3.2.5.97.2 Methods**

#### **3.2.5.97.2.1 Scalar Methods**

##### **3.2.5.97.2.1.1 MoveAfter**

**Return Type:** None

Moves a **navigation node** after a specified navigation node in the navigation node collection. [<74>](#)

**Parameters:**

*nodeId*: Identifier of the navigation node that is moved.

Type: **CSOM Int32**

*previousNodeId*: Identifier of the navigation node after which the node identified by *nodeId* moves to.

Type: CSOM Int32

#### **3.2.5.97.2.2 ObjectPath Methods**

##### **3.2.5.97.2.2.1 Add**

**Return Type:** Microsoft.SharePoint.Client.NavigationNode

Creates a **navigation node object (1)** and adds it to the collection.

**Parameters:**

*parameters*: Describes the node to be created.

Type: Microsoft.SharePoint.Client.NavigationNodeCreationInformation

It MUST NOT be NULL.

##### **3.2.5.97.2.2.2 GetById**

**Return Type:** Microsoft.SharePoint.Client.NavigationNode

Returns the **navigation node** with the specified identifier. [<75>](#) It MUST return NULL if no navigation node corresponds to the specified identifier.

**Parameters:**

*id*: Specifies the identifier of the navigation node.

Type: **CSOM Int32**

### 3.2.5.97.2.2.3 **GetByIndex**

**Return Type:** Microsoft.SharePoint.Client.NavigationNode

Returns the **navigation node** at the specified index. <76>

**Parameters:**

*index:* The index of the navigation node to be returned.

Type: **CSOM Int32**

### 3.2.5.98 **Microsoft.SharePoint.Client.NavigationNodeCreationInformation**

**TypeId:** {7AAAA605-79A9-4FDA-AE1E-DB952E5083E0}

**ShortName:** SP.NavigationNodeCreationInformation

Describes a new navigation node to be created.

#### 3.2.5.98.1 **Properties**

##### 3.2.5.98.1.1 **Scalar Properties**

###### 3.2.5.98.1.1.1 **AsLastNode**

Type: **CSOM Boolean**

**Accessibility:** Read/Write

Gets or sets a Boolean value that specifies whether the navigation node will be created as the last node in the navigation node collection. Has no effect if **PreviousNode** is not null.

###### 3.2.5.98.1.1.2 **IsExternal**

Type: **CSOM Boolean**

**Accessibility:** Read/Write

Gets a Boolean value that specifies whether the navigation node URL can correspond to a page outside the site collection.

###### 3.2.5.98.1.1.3 **Title**

Type: **CSOM String**

**Accessibility:** Read/Write

Gets or sets the string to be used as the anchor text for the node navigation link.

Its length MUST be equal to or less than 256.

###### 3.2.5.98.1.1.4 **Url**

Type: **CSOM String**

**Accessibility:** Read/Write

Gets or sets the URL to be stored with the navigation node.

### 3.2.5.98.1.2 ObjectPath Properties

#### 3.2.5.98.1.2.1 PreviousNode

**Type:** Microsoft.SharePoint.Client.NavigationNode

**Accessibility:** Read/Write

Gets or sets a navigation node after which the new navigation node will appear in the navigation node collection.

### 3.2.5.99 Microsoft.SharePoint.Client.PageType

**ShortName:** SP.PageType

**Flag:** false

As specified in [\[MS-WSSFO3\]](#) section 2.2.1.2.14.

#### 3.2.5.99.1 Field Values

##### 3.2.5.99.1.1 Invalid

**Value:** -1

Specifies a page that does not correspond to a **list view** or a **list form**.

##### 3.2.5.99.1.2 DefaultView

**Value:** 0

Specifies a page that is the **default view** for a **list**.

##### 3.2.5.99.1.3 NormalView

**Value:** 1

Specifies a page that is a **list view** and is not the **default view** for a **list**.

##### 3.2.5.99.1.4 DialogView

**Value:** 2

Specifies a page that can be displayed within a dialog box on a client computer.

##### 3.2.5.99.1.5 View

**Value:** 3

Specifies a page that is a **list view**.

##### 3.2.5.99.1.6 DisplayForm

**Value:** 4

Specifies a **list form** for displaying a **list item**.

### 3.2.5.99.1.7 DisplayFormDialog

**Value:** 5

Specifies a **list form** for displaying a **list item** within a dialog box on a client computer.

### 3.2.5.99.1.8 EditForm

**Value:** 6

Specifies a **list form** for editing a **list item**.

### 3.2.5.99.1.9 EditFormDialog

**Value:** 7

Specifies a **list form** for editing a **list item** that can be displayed within a dialog box on a client computer.

### 3.2.5.99.1.10NewForm

**Value:** 8

Specifies a **list form** for creating a new **list item**.

### 3.2.5.99.1.11NewFormDialog

**Value:** 9

Specifies a **list form** for creating a new **list item** that can be displayed within a dialog box on a client computer.

### 3.2.5.99.1.12SolutionForm

**Value:** 10

Specifies a **list form** that is represented by a **form template (.xsn) file** and is used for displaying or editing a **list item**.

### 3.2.5.99.1.13PAGE\_MAXITEMS

**Value:** 11

Represents the total number of valid page types.

## 3.2.5.100 Microsoft.SharePoint.Client.Principal

**TypeId:** {8A76E712-17A1-4A40-B2DF-CCA7C060D78F}

**ShortName:** SP.Principal

Specifies a base type that represents a user or **group** that can be assigned permissions to control security.

### 3.2.5.100.1 Properties

#### 3.2.5.100.1.1 Scalar Properties

### 3.2.5.100.1.1.1 Id

Type: **CSOM Int32**

Accessibility: Read Only

Specifies the **member** identifier for the user or **group**.

Its value MUST be equal to or greater than 1. Its value MUST be equal to or less than 2147483647.

### 3.2.5.100.1.1.2 LoginName

Type: **CSOM String**

Accessibility: Read Only

If this **object (1)** represents a user, **LoginName** specifies the **login name** of the user. For a **group**, it specifies the name of the group.

### 3.2.5.100.1.1.3 PrincipalType

Type: Microsoft.SharePoint.Client.Utilities.PrincipalType

Accessibility: Read Only

Specifies the type of **principal** represented by this **object (1)**.

### 3.2.5.100.1.1.4 Title

Type: **CSOM String**

Accessibility: Read/Write

Specifies the name of the **principal**.

It MUST NOT be NULL. Its length MUST be equal to or less than 255.

### 3.2.5.100.1.1.5 IsHiddenInUI

Type: **CSOM Boolean**

Accessibility: Read Only

Specifies whether the **principal** is hidden in the user interface (UI).<??>

## 3.2.5.100.1.2 ObjectPath Properties

None.

## 3.2.5.100.2 Methods

### 3.2.5.100.2.1 Scalar Methods

None.

### 3.2.5.100.2.2 ObjectPath Methods

None.

### 3.2.5.101 Microsoft.SharePoint.Client.PropertyValues

**TypeId:** {3973524D-2D5A-4683-AA39-38A2ACC6E63C}

**ShortName:** SP.PropertyValues

Contains the collection of name/value pairs of all the **CSOM expando fields**.

#### 3.2.5.101.1 Properties

##### 3.2.5.101.1.1 Scalar Properties

None.

##### 3.2.5.101.1.2 ObjectPath Properties

None.

#### 3.2.5.101.2 Methods

##### 3.2.5.101.2.1 Scalar Methods

###### 3.2.5.101.2.1.1 SetFieldValue

**Return Type:** None

Sets the value of the corresponding field to the value of the specified object.

**Parameters:**

*fieldName:* A string that contains the field name.

Type: **CSOM String**

*value:* An object whose value is to be used to set this field.

Type: **CSOM Object**

##### 3.2.5.101.2.2 ObjectPath Methods

None.

### 3.2.5.102 Microsoft.SharePoint.Client.QuickLaunchOptions

**ShortName:** SP.QuickLaunchOptions

**Flag:** false

Specifies whether the list will be displayed on the Quick Launch Bar or not.

#### 3.2.5.102.1 Field Values

##### 3.2.5.102.1.1 Off

**Value:** 0

Indicates that the list will not be displayed on the Quick Launch Bar.



### 3.2.5.102.1.2On

**Value:** 1

Indicates that the list will be displayed on the Quick Launch Bar.

### 3.2.5.102.1.3DefaultValue

**Value:** 2

Indicates that the decision of the list being displayed on the Quick Launch Bar will be based on the list template's OnQuickLaunch property.

## 3.2.5.103 Microsoft.SharePoint.Client.RecycleBinItem

**TypeId:** {5EBF462E-9E9A-440C-992B-ABBB3916563D}

**ShortName:** SP.RecycleBinItem

Represents a **Recycle Bin item** in the **Recycle Bin** of a **site (2)** or a **site collection**.

### 3.2.5.103.1 Properties

#### 3.2.5.103.1.1 Scalar Properties

##### 3.2.5.103.1.1.1 AuthorEmail

**Type:** CSOM String

**Accessibility:** Read Only

Gets the **email address** of the **user (1)** who originally created the **Recycle Bin item**.

##### 3.2.5.103.1.1.2 AuthorName

**Type:** CSOM String

**Accessibility:** Read Only

Gets the **user display name** of the **user (1)** who originally created the **Recycle Bin item**.

It MUST NOT be NULL.

##### 3.2.5.103.1.1.3 DeletedByEmail

**Type:** CSOM String

**Accessibility:** Read Only

Gets the **email address** of the **user (1)** who deleted the **Recycle Bin item**.

##### 3.2.5.103.1.1.4 DeletedByName

**Type:** CSOM String

**Accessibility:** Read Only

Gets the **user display name** of the **user (1)** who deleted the **Recycle Bin item**.

It MUST NOT be NULL.

#### **3.2.5.103.1.1.5 DeletedDate**

**Type:** CSOM DateTime

**Accessibility:** Read Only

Specifies when the **Recycle Bin item** was moved to the **Recycle Bin**.

#### **3.2.5.103.1.1.6 DeletedDateLocalFormatted**

**Type:** CSOM String

**Accessibility:** Read Only

Specifies when, in the default **time zone** for the current **site (2)**, the **Recycle Bin item** was moved to the **Recycle Bin**.

#### **3.2.5.103.1.1.7 DirName**

**Type:** CSOM String

**Accessibility:** Read Only

Specifies the **site-relative URL** of the **list** or **folder** that originally contained the **Recycle Bin item**.

It MUST NOT be NULL. It MUST be a URL of relative form. Its length MUST be equal to or less than 256.

#### **3.2.5.103.1.1.8 DirNamePath**

**Type:** Microsoft.SharePoint.Client.ResourcePath

**Accessibility:** Read Only

Returns the site relative path of the list or folder that originally contained the Recycle Bin item.

It MUST NOT be NULL.

#### **3.2.5.103.1.1.9 Id**

**Type:** CSOM GUID

**Accessibility:** Read Only

Specifies the identifier of the **Recycle Bin item**.

It MUST NOT be an empty GUID.

#### **3.2.5.103.1.1.10 ItemState**

**Type:** Microsoft.SharePoint.Client.RecycleBinItemState

**Accessibility:** Read Only

Specifies the **Recycle Bin** stage of the **Recycle Bin item**.

It MUST NOT be None.

### 3.2.5.103.1.1.11 ItemType

**Type:** Microsoft.SharePoint.Client.RecycleBinItemType

**Accessibility:** Read Only

Specifies the type of the **Recycle Bin item**.

It MUST NOT be None.

### 3.2.5.103.1.1.12 LeafName

**Type:** CSOM String

**Accessibility:** Read Only

Specifies the **leaf name** of the **Recycle Bin item**.

It MUST NOT be NULL. Its length MUST be equal to or less than 260. It MUST NOT contain the following characters: \x00-\x1F, \x22, \x23, \x25, \x26, \x2A, \x3A, \x3C, x3E, \x3F, \x5C and \x7B-\x9F.

### 3.2.5.103.1.1.13 LeafNamePath

**Type:** Microsoft.SharePoint.Client.ResourcePath

**Accessibility:** Read Only

Returns the leaf name path of the **Recycle Bin item**.

It MUST NOT be NULL. It MUST NOT contain the following characters: ([\"#%\*\":<>?\\|\x7F]).

### 3.2.5.103.1.1.14 Size

**Type:** CSOM Int64

**Accessibility:** Read Only

Specifies the size of the **Recycle Bin item** in bytes.

Its value MUST be equal to or greater than 0.

### 3.2.5.103.1.1.15 Title

**Type:** CSOM String

**Accessibility:** Read Only

Specifies the title of the **Recycle Bin item**.

It MUST NOT be NULL. Its length MUST be equal to or less than 255.

## 3.2.5.103.1.2 ObjectPath Properties

### 3.2.5.103.1.2.1 Author

**Type:** Microsoft.SharePoint.Client.User

**Accessibility:** Read Only

Specifies the user who created the **Recycle Bin item**.

### 3.2.5.103.1.2.2 DeletedBy

**Type:** Microsoft.SharePoint.Client.User

**Accessibility:** Read Only

Specifies the user who deleted the **Recycle Bin item**.

## 3.2.5.103.2 Methods

### 3.2.5.103.2.1 Scalar Methods

#### 3.2.5.103.2.1.1 DeleteObject

**Return Type:** None

Permanently deletes the **Recycle Bin item**.

**Parameters:** None

#### 3.2.5.103.2.1.2 MoveToSecondStage

**Return Type:** None

Moves the **Recycle Bin item** from the **first-stage Recycle Bin** to the **second-stage Recycle Bin** if the **SecondStageRecycleBinQuota** property on the current **web application** is not 0. Otherwise, deletes the item.

**Parameters:** None

#### 3.2.5.103.2.1.3 Restore

**Return Type:** None

Restores the **Recycle Bin item** to its original location.

**Parameters:** None

#### Exceptions:

Error Code	Error Type Name	Condition
- 2147024816	Microsoft.SharePoint.SPException	Another <b>file</b> or <b>folder</b> with the same name already exists in the original location.
- 2147024713	Microsoft.SharePoint.SPException	Another <b>list</b> with the same name already exists in the original location.
- 2130575168	Microsoft.SharePoint.SPException	Recycle Bin item contains duplicate <b>field (2)</b> values for a field (2) where <b>Field.EnforceUniqueValues</b> is "true".

### 3.2.5.103.2.2 ObjectPath Methods

None.

### 3.2.5.104 Microsoft.SharePoint.Client.RecycleBinItemCollection

**TypeId:** {9BFB60CF-1ACA-484C-A845-5F2D4EF20865}

**ShortName:** SP.RecycleBinItemCollection

Specifies a collection of **Recycle Bin items**.

#### 3.2.5.104.1 Properties

##### 3.2.5.104.1.1 Scalar Properties

None.

##### 3.2.5.104.1.2 ObjectPath Properties

None.

#### 3.2.5.104.2 Methods

##### 3.2.5.104.2.1 Scalar Methods

###### 3.2.5.104.2.1.1 DeleteAll

**Return Type:** None

Permanently deletes all **Recycle Bin items**.

**Parameters:** None

###### 3.2.5.104.2.1.2 DeleteAllSecondStageItems

**Return Type:** None

Permanently deletes all **Recycle Bin items** in the **second-stage Recycle Bin**.

**Parameters:** None

###### 3.2.5.104.2.1.3 MoveAllToSecondStage

**Return Type:** None

Moves all **Recycle Bin items** from the **first-stage Recycle Bin** to the **second-stage Recycle Bin** if the **SecondStageRecycleBinQuota** property of the current **web application** is not 0. Otherwise, permanently deletes all Recycle Bin items.

**Parameters:** None

###### 3.2.5.104.2.1.4 RestoreAll

**Return Type:** None

Restores all **Recycle Bin items** to their original locations.

**Parameters:** None

**Exceptions:**

Error Code	Error Type Name	Condition
- 2147024816	Microsoft.SharePoint.SPException	Another <b>file</b> or <b>folder</b> with the same name already exists in the original location.
- 2147024713	Microsoft.SharePoint.SPException	Another <b>list</b> with the same name already exists in the original location.
- 2130575168	Microsoft.SharePoint.SPException	Recycle Bin item contains duplicate <b>field (2)</b> values for a field (2) where <b>Field.EnforceUniqueValues</b> is "true".

### 3.2.5.104.2.2 ObjectPath Methods

#### 3.2.5.104.2.2.1 GetById

**Return Type:** Microsoft.SharePoint.Client.RecycleBinItem

Returns the **Recycle Bin item** with the specified identifier from the collection.

**Parameters:**

*id*: Specifies the identifier of the Recycle Bin item.

Type: **CSOM GUID**

#### 3.2.5.105 Microsoft.SharePoint.Client.RecycleBinItemState

**ShortName:** SP.RecycleBinItemState

**Flag:** false

Specifies the Recycle Bin stage of the Recycle Bin item.

##### 3.2.5.105.1 Field Values

###### 3.2.5.105.1.1 None

**Value:** 0

The item state is not specified.

###### 3.2.5.105.1.2 FirstStageRecycleBin

**Value:** 1

Specifies that the item is in the end-user Recycle Bin.

###### 3.2.5.105.1.3 SecondStageRecycleBin

**Value:** 2

Specifies that the item is in the second stage of the site-collection Recycle Bin.

#### 3.2.5.106 Microsoft.SharePoint.Client.RecycleBinItemType

**ShortName:** SP.RecycleBinItemType

**Flag:** false

Specifies the type of the **Recycle Bin item**.

### **3.2.5.106.1 Field Values**

#### **3.2.5.106.1.1 None**

**Value:** 0

The type of the **Recycle Bin item** is not specified.

#### **3.2.5.106.1.2 File**

**Value:** 1

Specifies that the **Recycle Bin item** is a **file**.

#### **3.2.5.106.1.3 FileVersion**

**Value:** 2

Specifies that the **Recycle Bin item** is a **historical version** of a **file**.

#### **3.2.5.106.1.4 ListItem**

**Value:** 3

Specifies that the **Recycle Bin item** is a **list item**.

#### **3.2.5.106.1.5 List**

**Value:** 4

Specifies that the **Recycle Bin item** is a **list**.

#### **3.2.5.106.1.6 Folder**

**Value:** 5

Specifies that the **Recycle Bin item** is a **folder**.

#### **3.2.5.106.1.7 FolderWithLists**

**Value:** 6

Specifies that the **Recycle Bin item** is a **folder** that contains a **list**.

#### **3.2.5.106.1.8 Attachment**

**Value:** 7

Specifies that the **Recycle Bin item** is an **attachment**.

#### **3.2.5.106.1.9 ListItemVersion**

**Value:** 8

Specifies that the **Recycle Bin item** is a **historical version** of a **list item**.

### 3.2.5.106.1.10 CascadeParent

**Value:** 9

Specifies that the **Recycle Bin item** is a **list item** that is the parent of one or more related list items.

### 3.2.5.106.1.11 Web

**Value:** 10

Specifies that the **Recycle Bin item** is a **site (2)**.<78>

### 3.2.5.106.1.12 App

**Value:** 11

Specifies that the **Recycle Bin item** is a **SharePoint Add-in**.

### 3.2.5.107 Microsoft.SharePoint.Client.RelatedField

**TypeId:** {A91DEB1A-2F24-4AC5-A1A6-3B1E530C307F}

**ShortName:** SP.RelatedField

Represents a Lookup Field that points to a given list on a **Web site**.

#### 3.2.5.107.1 Properties

##### 3.2.5.107.1.1 Scalar Properties

###### 3.2.5.107.1.1.1 FieldId

**Type:** **CSOM GUID**

**Accessibility:** Read Only

Specifies the field id of the corresponding Lookup Field.

###### 3.2.5.107.1.1.2 ListId

**Type:** **CSOM GUID**

**Accessibility:** Read Only

Specifies the ID of the List containing the corresponding Lookup Field.

###### 3.2.5.107.1.1.3 RelationshipDeleteBehavior

**Type:** Microsoft.SharePoint.Client.RelationshipDeleteBehaviorType

**Accessibility:** Read Only

Specifies the delete behavior of the corresponding Lookup Field.

###### 3.2.5.107.1.1.4 WebId

**Type:** **CSOM GUID**

**Accessibility:** Read Only



Specifies the ID of the Web containing the corresponding Lookup Field.

### **3.2.5.107.1.2ObjectPath Properties**

#### **3.2.5.107.1.2.1 LookupList**

**Type:** Microsoft.SharePoint.Client.List

**Accessibility:** Read Only

Specifies the List that the corresponding Lookup Field looks up to.

It MUST NOT be NULL.

### **3.2.5.107.2 Methods**

#### **3.2.5.107.2.1Scalar Methods**

None.

#### **3.2.5.107.2.2ObjectPath Methods**

None.

### **3.2.5.108 Microsoft.SharePoint.Client.RelatedFieldCollection**

**TypeId:** {4703193F-E3ED-445B-8612-7C6218E0EB5A}

**ShortName:** SP.RelatedFieldCollection

Represents a collection of Lookup Fields that point to given lists.

#### **3.2.5.108.1 Properties**

##### **3.2.5.108.1.1Scalar Properties**

None.

##### **3.2.5.108.1.2ObjectPath Properties**

None.

#### **3.2.5.108.2 Methods**

##### **3.2.5.108.2.1Scalar Methods**

None.

##### **3.2.5.108.2.2ObjectPath Methods**

###### **3.2.5.108.2.2.1 GetByFieldId**

**Return Type:** Microsoft.SharePoint.Client.RelatedField

Returns an **SP.RelatedField** (section [3.2.5.107](#)) specified by the identifier of the **SP.RelatedField**.

**Parameters:**

*fieldId*: Specifies the identifier of the **SP.RelatedField**.

Type: **CSOM GUID**

### **3.2.5.109 Microsoft.SharePoint.Client.RelationshipDeleteBehaviorType**

**ShortName:** SP.RelationshipDeleteBehaviorType

**Flag:** false

Defines the type of behavior that happens when you delete a parent item of two related lists.

#### **3.2.5.109.1 Field Values**

##### **3.2.5.109.1.1 None**

**Value:** 0

Nothing happens when you delete a parent item, and we leave the child item pointing to the parent as an orphan.

##### **3.2.5.109.1.2 Cascade**

**Value:** 1

A cascade delete happens when you delete a parent item, deleting all related child items of the related list.

##### **3.2.5.109.1.3 Restrict**

**Value:** 2

A parent item having any child items in the related list cannot be deleted.

### **3.2.5.110 Microsoft.SharePoint.Client.RequestContext**

**TypeId:** {3747ADCD-A3C3-41B9-BFAB-4A64DD2F1E0A}

**ShortName:** SP.RequestContext

Provides basic WSS context information: site, web, list, and list item.

Use this class to return context information about such objects as the current Web application, site collection, site, list, or list item.

#### **3.2.5.110.1 Properties**

##### **3.2.5.110.1.1 Scalar Properties**

None.

##### **3.2.5.110.1.2 ObjectPath Properties**

###### **3.2.5.110.1.2.1 Current**

**Type:** Microsoft.SharePoint.Client.RequestContext

**Accessibility:** Read Only

Returns the SP.RequestContext for the current HttpContext.

### **3.2.5.110.1.2.2 List**

**Type:** Microsoft.SharePoint.Client.List

**Accessibility:** Read Only

Returns the list that is associated with the Windows SharePoint Services context.

### **3.2.5.110.1.2.3 Site**

**Type:** Microsoft.SharePoint.Client.Site

**Accessibility:** Read Only

Returns the SP.Site object

It MUST NOT be NULL.

### **3.2.5.110.1.2.4 Web**

**Type:** Microsoft.SharePoint.Client.Web

**Accessibility:** Read Only

Gets the Web site that is associated with the Windows SharePoint Services context.

It MUST NOT be NULL.

## **3.2.5.110.2 Methods**

### **3.2.5.110.2.1 Scalar Methods**

None.

### **3.2.5.110.2.2 ObjectPath Methods**

#### **3.2.5.110.2.2.1 GetRemoteContext**

**Return Type:** Microsoft.SharePoint.Client.RequestContext

Returns the SP.RequestContext for the mounted folder. Returns null if this is not an attempt to render or act upon a mounted folder.

**Parameters:** None

## **3.2.5.111 Microsoft.SharePoint.Client.RoleAssignment**

**TypeId:** {07DA03BE-4D19-48F3-9C5F-7C67B134A93B}

**ShortName:** SP.RoleAssignment

Specifies the **role assignments** for a user or **group** on a **securable object**.

### **3.2.5.111.1 Properties**

#### **3.2.5.111.1.1 Scalar Properties**

### 3.2.5.111.1.1.1 PrincipalId

**Type:** CSOM Int32

**Accessibility:** Read Only

Specifies the identifier of the user or **group** corresponding to the **role assignment**.<79>

### 3.2.5.111.1.2 ObjectPath Properties

#### 3.2.5.111.1.2.1 Member

**Type:** Microsoft.SharePoint.Client.Principal

**Accessibility:** Read Only

Specifies the user or **group** corresponding to the **role assignment**.

It MUST NOT be NULL. The identifier of the user or group MUST be greater than zero.

#### 3.2.5.111.1.2.2 RoleDefinitionBindings

**Type:** Microsoft.SharePoint.Client.RoleDefinitionBindingCollection

**Accessibility:** Read Only

Specifies a collection of **role definitions** for this **role assignment**.

It MUST NOT be NULL.

### 3.2.5.111.2 Methods

#### 3.2.5.111.2.1 Scalar Methods

##### 3.2.5.111.2.1.1 DeleteObject

**Return Type:** None

Removes the **role assignment object (1)** from the parent role assignment collection.

**Parameters:** None

##### 3.2.5.111.2.1.2 ImportRoleDefinitionBindings

**Return Type:** None

Imports the specified **role definition** bindings into the collection of role definitions for the **role assignment**.

**Parameters:**

*roleDefinitionBindings:* Specifies the role definition bindings to be imported.

Type: Microsoft.SharePoint.Client.RoleDefinitionBindingCollection

##### 3.2.5.111.2.1.3 Update

**Return Type:** None

Updates the **role assignment object (1)** with changes that have been made to its properties.

**Parameters:** None

### 3.2.5.111.2.2 ObjectPath Methods

None.

### 3.2.5.112 Microsoft.SharePoint.Client.RoleAssignmentCollection

**TypeId:** {2690207A-E174-4D49-B2CA-CFF663225DC1}

**ShortName:** SP.RoleAssignmentCollection

The **object (1)** represents a collection of **role assignments** for each **securable object**.

#### 3.2.5.112.1 Properties

##### 3.2.5.112.1.1 Scalar Properties

None.

##### 3.2.5.112.1.2 ObjectPath Properties

###### 3.2.5.112.1.2.1 Groups

**Type:** Microsoft.SharePoint.Client.GroupCollection

**Accessibility:** Read Only

A collection of **groups** that is associated with this **role assignment** collection. [<80>](#)

#### 3.2.5.112.2 Methods

##### 3.2.5.112.2.1 Scalar Methods

###### 3.2.5.112.2.1.1 AddRoleAssignment

**Return Type:** None

Adds a **role assignment** to the role assignment collection. [<81>](#)

**Parameters:**

*principalId*: Specifies the user or **group** of the role assignment.

Type: **CSOM Int32**

*roleDefId*: Specifies the **role definition** of the role assignment.

Type: CSOM Int32

###### 3.2.5.112.2.1.2 RemoveRoleAssignment

**Return Type:** None

Removes the **role assignment** with the specified user or **group** from the collection. [<82>](#)

**Parameters:**

*principalId*: Specifies the user or group of the role assignment.

Type: **CSOM Int32**

*roleDefId*: Specifies the identifier of the **role definition** of the role assignment.

Type: CSOM Int32

### 3.2.5.112.2.2 ObjectPath Methods

#### 3.2.5.112.2.2.1 Add

**Return Type:** Microsoft.SharePoint.Client.RoleAssignment

Adds a **role assignment** to the role assignment collection.

**Parameters:**

*principal*: An **object (1)** that represents the user or **group** of the role assignment.

Type: Microsoft.SharePoint.Client.Principal

It MUST NOT be NULL.

*roleBindings*: An object (1) that represents the collection of the **role definitions** to be associated with the role assignment that is added.

Type: Microsoft.SharePoint.Client.RoleDefinitionBindingCollection

It MUST NOT be NULL. It MUST have at least one child in the collection.

#### 3.2.5.112.2.2.2 GetByPrincipal

**Return Type:** Microsoft.SharePoint.Client.RoleAssignment

Retrieves the **role assignment object (1)** based on the specified user or **group**.

**Parameters:**

*principalToFind*: An object (1) that represents the user or group.

Type: Microsoft.SharePoint.Client.Principal

It MUST NOT be NULL.

#### 3.2.5.112.2.2.3 GetByPrincipalId

**Return Type:** Microsoft.SharePoint.Client.RoleAssignment

Retrieves the **role assignment object (1)** based on the **Id** property of the specified user or **group**.

**Parameters:**

*principalId*: An identifier of the object (1) that represents the user or group.

Type: **CSOM Int32**

### 3.2.5.113 Microsoft.SharePoint.Client.RoleDefinition

**TypeId:** {AA7ECB4A-9C7E-4AD9-BD20-58A2775E5AD7}

**ShortName:** SP.RoleDefinition

Defines a single **role definition**, including a name, description, management properties, and a set of **rights**.

### 3.2.5.113.1 Properties

#### 3.2.5.113.1.1 Scalar Properties

##### 3.2.5.113.1.1.1 BasePermissions

**Type:** Microsoft.SharePoint.Client.BasePermissions

**Accessibility:** Read/Write

Specifies the base permissions for the **role definition**.

When assigning values to the property, use bitwise **AND**, **OR**, and **XOR** operators with values from the **BasePermissions** uint.

It MUST NOT be NULL.

**Exceptions:**

Error Code	Error Type Name	Condition
-1	System.InvalidOperationException	<b>Site (2)</b> inherits permission levels from a <b>parent site</b> , and permission levels cannot be customized.

##### 3.2.5.113.1.1.2 Description

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies the description of the **role definition**.

Its length MUST be equal to or less than 512.

**Exceptions:**

Error Code	Error Type Name	Condition
-1	System.InvalidOperationException	<b>Site (2)</b> inherits permission levels from a <b>parent site</b> , and permission levels cannot be customized.

##### 3.2.5.113.1.1.3 Hidden

**Type:** CSOM Boolean

**Accessibility:** Read Only

Specifies whether the **role definition** is displayed.

##### 3.2.5.113.1.1.4 Id

**Type:** CSOM Int32

**Accessibility:** Read Only

Specifies the identifier of the **role definition**.

Its value MUST be equal to or greater than 1073741824.

### 3.2.5.113.1.1.5 Name

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies the **role definition** name.

It MUST NOT be NULL. It MUST NOT be empty. Its length MUST be equal to or less than 255. MUST not contain any of the following characters: `\/[]:|<>+=;,?*'"@`

**Exceptions:**

Error Code	Error Type Name	Condition
-1	System.InvalidOperationException	Role definition is inherited from a <b>parent site</b> .

### 3.2.5.113.1.1.6 Order

**Type:** CSOM Int32

**Accessibility:** Read/Write

Specifies the order position of the **object (1)** in the **site collection** Permission Levels page.

**Exceptions:**

Error Code	Error Type Name	Condition
-1	System.InvalidOperationException	The user cannot customize permission levels in a <b>site (2)</b> with inherited permission levels.

### 3.2.5.113.1.1.7 RoleTypeKind

**Type:** Microsoft.SharePoint.Client.RoleType

**Accessibility:** Read Only

Specifies the type of the **role definition**.

Its value MUST be equal to or greater than 0. Its value MUST be equal to or less than 5.

### 3.2.5.113.1.2ObjectPath Properties

None.

### 3.2.5.113.2 Methods



### 3.2.5.113.2.1 Scalar Methods

#### 3.2.5.113.2.1.1 DeleteObject

**Return Type:** None

Deletes the **role definition object (1)**.

**Parameters:** None

**Exceptions:**

Error Code	Error Type Name	Condition
-1	Microsoft.SharePoint.SPException	Role definition type is either Guest or Administrator.

#### 3.2.5.113.2.1.2 Update

**Return Type:** None

Updates the **role definition** with changes that have been made to its properties.

**Parameters:** None

**Exceptions:**

Error Code	Error Type Name	Condition
-1	System.InvalidOperationException	Role definition is inherited from a <b>parent site</b> .

### 3.2.5.113.2.2 ObjectPath Methods

None.

#### 3.2.5.114 Microsoft.SharePoint.Client.RoleDefinitionBindingCollection

**TypeId:** {07BF1941-6953-4761-B114-58374B4AAF57}

**ShortName:** SP.RoleDefinitionBindingCollection

Specifies the **role definitions** that are bound to a **role assignment object (1)**.

#### 3.2.5.114.1 Properties

##### 3.2.5.114.1.1 Scalar Properties

None.

##### 3.2.5.114.1.2 ObjectPath Properties

None.

#### 3.2.5.114.2 Methods

### 3.2.5.114.2.1 Scalar Methods

#### 3.2.5.114.2.1.1 Add

**Return Type:** None

Adds the specified **role definition** to the binding collection.

**Parameters:**

*roleDefinition*: Specifies the role definition to be added.

Type: Microsoft.SharePoint.Client.RoleDefinition

It MUST NOT be NULL.

#### 3.2.5.114.2.1.2 Remove

**Return Type:** None

Removes the specified **role definition** from the binding collection.

**Parameters:**

*roleDefinition*: Specifies the role definition to be removed.

Type: Microsoft.SharePoint.Client.RoleDefinition

It MUST NOT be NULL.

#### 3.2.5.114.2.1.3 RemoveAll

**Return Type:** None

Removes all **role definitions** from the binding collection.

**Parameters:** None

### 3.2.5.114.2.2 ObjectPath Methods

#### 3.2.5.114.2.2.1 GetById

**Return Type:** Microsoft.SharePoint.Client.RoleDefinition

Returns an **SP.RoleDefinition** (section [3.2.5.113](#)) specified by the identifier of that **SP.RoleDefinition**.<83>

**Parameters:**

*id*: Specifies the identifier of the SP.RoleDefinition.

Type: **CSOM Int32**

**Exceptions:**

Error Code	Error Type Name	Condition
- 2147024809	System.ArgumentException	The <b>role definition</b> that the <b>SP.RoleDefinition</b> represents does not exist in the collection at the given scope.

### 3.2.5.114.2.2.2 CSOM Constructor

Create an object for holding a collection of **role definitions** binding information. [<84>](#)

**Parameters:** None

### 3.2.5.115 Microsoft.SharePoint.Client.RoleDefinitionCollection

**TypeId:** {964B9AB0-D026-4487-99D1-E06450963CC9}

**ShortName:** SP.RoleDefinitionCollection

Represents the collection of **role definitions** that are available within the **site (2)**.

#### 3.2.5.115.1 Properties

##### 3.2.5.115.1.1 Scalar Properties

None.

##### 3.2.5.115.1.2 ObjectPath Properties

None.

#### 3.2.5.115.2 Methods

##### 3.2.5.115.2.1 Scalar Methods

###### 3.2.5.115.2.1.1 RecreateMissingDefaultRoleDefinitions

**Return Type:** None

Recreates missing default role definitions. Requires that Microsoft.SharePoint.SPWeb has unique role definitions.

**Parameters:** None

##### 3.2.5.115.2.2 ObjectPath Methods

###### 3.2.5.115.2.2.1 Add

**Return Type:** Microsoft.SharePoint.Client.RoleDefinition

Adds a new **role definition** to the collection, based on the passed parameter.

**Parameters:**

*parameters:* An **object (1)** that represents the role definition to be added.

Type: Microsoft.SharePoint.Client.RoleDefinitionCreationInformation

It MUST NOT be NULL.

**Exceptions:**

Error Code	Error Type Name	Condition
- 2130575259	Microsoft.SharePoint.SPException	There are more than 1000 role definitions added to the same <b>site (2)</b>

### 3.2.5.115.2.2.2 GetById

**Return Type:** Microsoft.SharePoint.Client.RoleDefinition

Retrieves the **role definition** with the specified **Id** property from the collection.

**Parameters:**

*id*: Specifies the unique identifier of the role definition searched. The value of *id* does not correspond to the index of the role definition within the collection, but refers to the value of the **Id** property of the role definition.

Type: **CSOM Int32**

### 3.2.5.115.2.2.3 GetByName

**Return Type:** Microsoft.SharePoint.Client.RoleDefinition

Returns the **role definition** matching the *name* provided.

**Parameters:**

*name*: Specifies name of role definition.

Type: **CSOM String**

It MUST NOT be NULL. It MUST NOT be empty. Its length MUST be equal to or less than 255. Trimmed name MUST NOT be empty.

### 3.2.5.115.2.2.4 GetByType

**Return Type:** Microsoft.SharePoint.Client.RoleDefinition

Returns **role definition** of the specified type from the collection.

**Parameters:**

*roleType*: Specifies the role type. Role type MUST NOT be None.

Type: Microsoft.SharePoint.Client.RoleType

## 3.2.5.116 Microsoft.SharePoint.Client.RoleDefinitionCreationInformation

**TypeId:** {59EDDF82-1018-4677-8067-69E16EFD3495}

**ShortName:** SP.RoleDefinitionCreationInformation

The parameters to create a role definition.

### 3.2.5.116.1 Properties

#### 3.2.5.116.1.1 Scalar Properties

### 3.2.5.116.1.1.1 BasePermissions

**Type:** Microsoft.SharePoint.Client.BasePermissions

**Accessibility:** Read/Write

Specifies the permissions for the role.

It MUST NOT be NULL.

### 3.2.5.116.1.1.2 Description

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies a description of the role definition.

Its length MUST be equal to or less than 512.

### 3.2.5.116.1.1.3 Name

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies the name of the role definition.

It MUST NOT be NULL. It MUST NOT be empty. Its length MUST be equal to or less than 255.

It MUST NOT contain any of the following characters: [ ] \ : | < > + = ; , ? \* ' @

### 3.2.5.116.1.1.4 Order

**Type:** CSOM Int32

**Accessibility:** Read/Write

Specifies the order in which roles MUST be displayed in the WFE.

### 3.2.5.116.1.2 ObjectPath Properties

None.

## 3.2.5.117 Microsoft.SharePoint.Client.RoleType

**ShortName:** SP.RoleType

**Flag:** false

Specifies the types of **role definitions** that are available for users and **groups**.

### 3.2.5.117.1 Field Values

#### 3.2.5.117.1.1 None

**Value:** 0

The **role definition** has no rights on the **site (2)**.

### 3.2.5.117.1.2 Guest

**Value:** 1

The **role definition** has limited right to view pages and specific page elements. This role is used to give users access to a particular page, **list**, or item in a list, without granting rights to view the entire **site (2)**. Users cannot be added explicitly to the guest role; users who are given access to lists or **document libraries** by using permissions for a specific list are added automatically to the guest role. The guest role cannot be customized or deleted.

### 3.2.5.117.1.3 Reader

**Value:** 2

The **role definition** has a right to view items, personalize **Web Parts**, use **alerts**, and create a **top-level site**. A reader can only read a **site (2)**; the reader cannot add content. When a reader creates a site (2), the reader becomes the site (2) owner and a **member** of the administrator role for the new site (2). This does not affect the user's role membership for any other site (2). Rights included are *CreateSSCSite*, *ViewListItems*, and *ViewPages*.

### 3.2.5.117.1.4 Contributor

**Value:** 3

The **role definition** has reader rights, and a right to add items, edit items, delete items, manage **list** permissions, manage personal views, personalize **Web Part Pages**, and browse directories. Includes all rights in the reader role, and *AddDelPrivateWebParts*, *AddListItems*, *BrowseDirectories*, *CreatePersonalGroups*, *DeleteListItems*, *EditListItems*, *ManagePersonalViews*, and *UpdatePersonalWebParts* roles. Contributors cannot create new lists or **document libraries**, but they can add content to existing lists and document libraries.

### 3.2.5.117.1.5 Web Designer

**Value:** 4

The **role definition** has contributor rights and a right to cancel check out, delete items, manage **lists**, add and customize pages, define and apply themes and borders, and link style sheets. Includes all rights in the contributor role, and *AddAndCustomizePages*, *ApplyStyleSheets*, *ApplyThemeAndBorder*, *CancelCheckout*, and *ManageLists* roles. Web designers can modify the structure of the **site (2)** and create new lists or **document libraries**.

### 3.2.5.117.1.6 Administrator

**Value:** 5

The **role definition** includes all rights from other roles, and a right to manage roles and view usage analysis data. It also includes all rights in the *WebDesigner* role, and *ManageListPermissions*, *ManageRoles*, *ManageSubwebs*, and *ViewUsageData* roles. The Administrator role cannot be customized or deleted. **Members** of the Administrator role have access to, or can grant themselves access to, any item in the **site (2)**.

### 3.2.5.117.1.7 Editor

**Value:** 6

This **role definition** has contributor rights and the right to create, manage and delete lists. Includes all rights in the contributor role and "ManageLists". Editors can create new **lists** and **document libraries**.

### 3.2.5.117.1.8 Reviewer

**Value:** 7

The **role definition** has reader rights, plus rights to Review items. Includes all rights in the Reader role, plus the following: ReviewListItems. Reviewers cannot create new **lists** and **document libraries**, but they can add **comments** to existing **list items** or **documents**.

### 3.2.5.117.1.9 RestrictedReader

**Value:** 8

The **role definition** is a special reader role definition with restricted rights, it has a right to view the content of the file but cannot download the file directly. Includes all rights in the Guest role, plus the following: ViewPages, ViewListItems and ViewItemsRequiresOpen.

### 3.2.5.117.1.10 System

**Value:** 255

For SharePoint internal use only. System roles can not be deleted, nor modified.

## 3.2.5.118 Microsoft.SharePoint.Client.SecurableObject

**TypeId:** {1B1BF348-994E-44FD-823F-0748F5AD94C8}

**ShortName:** SP.SecurableObject

An **object (1)** that can be assigned security permissions.

The HasUniqueRoleAssignments property is not included in the **default scalar property set** for this type.

### 3.2.5.118.1 Properties

#### 3.2.5.118.1.1 Scalar Properties

##### 3.2.5.118.1.1.1 HasUniqueRoleAssignments

**Type:** CSOM Boolean

**Accessibility:** Read Only

Specifies whether the **role assignments** are uniquely defined for this **securable object** or inherited from a parent securable object. If the value is "false", role assignments are inherited from a parent securable object.

#### 3.2.5.118.1.2 ObjectPath Properties

##### 3.2.5.118.1.2.1 RoleAssignments

**Type:** Microsoft.SharePoint.Client.RoleAssignmentCollection

**Accessibility:** Read Only

The **role assignments** for the **securable object**.

##### 3.2.5.118.1.2.2 FirstUniqueAncestorSecurableObject

**Type:** Microsoft.SharePoint.Client.SecurableObject

**Accessibility:** Read Only

Specifies the object where **role assignments** for this object are defined. <85>

### 3.2.5.118.2 Methods

#### 3.2.5.118.2.1 Scalar Methods

##### 3.2.5.118.2.1.1 BreakRoleInheritance

**Return Type:** None

Creates unique **role assignments** for the **securable object**. If the securable object already has unique role assignments, the protocol server MUST NOT alter any role assignments.

**Parameters:**

*copyRoleAssignments*: Specifies whether to copy the role assignments from the parent securable object.

Type: **CSOM Boolean**

If the value is "false", the collection of role assignments MUST contain only 1 role assignment containing the **current user** after the operation.

*clearSubscopes*: If the securable object is a **site (2)**, and the *clearSubscopes* parameter is "true", the role assignments for all child securable objects in the current site (2) and in the sites (2) that inherit role assignments from the current site (2) MUST be cleared and those securable objects inherit role assignments from the current site (2) after this call. If the securable object is a site (2), and the *clearSubscopes* parameter is "false", the role assignments for all child securable objects that do not inherit role assignments from their parent **object (1)** MUST remain unchanged. If the securable object is not a site (2), and the *clearSubscopes* parameter is "true", the role assignments for all child securable objects MUST be cleared and those securable objects inherit role assignments from the current securable object after this call. If the securable object is not a site (2), and the *clearSubscopes* parameter is "false", the role assignments for all child securable objects that do not inherit role assignments from their parent object (1) MUST remain unchanged.

Type: CSOM Boolean

**Exceptions:**

Error Code	Error Type Name	Condition
-1	System.InvalidOperationException	There are uncommitted changes for the current site (2)

##### 3.2.5.118.2.1.2 ResetRoleInheritance

**Return Type:** None

Resets the role inheritance for the **securable object** and inherits **role assignments** from the parent securable object.

**Parameters:** None

**Exceptions:**



Error Code	Error Type Name	Condition
-1	System.InvalidOperationException	There are uncommitted changes for the <b>site (2)</b> .

### 3.2.5.118.2.2 ObjectPath Methods

None.

### 3.2.5.119 Microsoft.SharePoint.Client.Site

**TypeId:** {E1BB82E8-0D1E-4E52-B90C-684802AB4EF6}

**ShortName:** SP.Site

Represents a collection of **sites (2)** in a **Web application**, including a **top-level site** and all of its **subsites**.

The CanUpgrade, CommentsOnSitePagesDisabled, ServerRelativePath, ShowPeoplePickerSuggestionsForGuestUsers, StatusBarLink, StatusBarText, ThicketSupportDisabled, UpgradeInfo and Usage properties are not included in the **default scalar property set** for this type.

#### 3.2.5.119.1 Properties

##### 3.2.5.119.1.1 Scalar Properties

###### 3.2.5.119.1.1.1 AllowDesigner

**Type:** **CSOM Boolean**

**Accessibility:** Read/Write

Specifies whether a **designer** can be used on this **site collection**. See **Microsoft.SharePoint.Client.Web.AllowDesignerForCurrentUser**, which is the scalar property used to determine the behavior for the **current user**. The default, if not disabled on the **Web application**, is "true".

###### 3.2.5.119.1.1.2 AllowMasterPageEditing

**Type:** **CSOM Boolean**

**Accessibility:** Read/Write

Specifies whether master page editing is allowed on this **site collection**. See **Microsoft.SharePoint.Client.Web.AllowMasterPageEditingForCurrentUser**, which is the scalar property used to determine the behavior for the **current user**. The default, if not disabled on the **Web application**, is "false".

###### 3.2.5.119.1.1.3 AllowRevertFromTemplate

**Type:** **CSOM Boolean**

**Accessibility:** Read/Write

Specifies whether this **site collection** can be reverted to its base template. See **Microsoft.SharePoint.Client.Web.AllowRevertFromTemplateForCurrentUser**, which is the

scalar property used to determine the behavior for the **current user**. The default, if not disabled on the **Web application**, is "false".

#### **3.2.5.119.1.1.4 Id**

**Type:** CSOM GUID

**Accessibility:** Read Only

Specifies the **GUID** that identifies the **site collection**.

#### **3.2.5.119.1.1.5 MaxItemsPerThrottledOperation**

**Type:** CSOM UInt32

**Accessibility:** Read Only

Specifies the maximum number of **list items** allowed to be returned for each retrieve request before throttling occurs. If throttling occurs, list items MUST NOT be returned.

#### **3.2.5.119.1.1.6 ServerRelativeUrl**

**Type:** CSOM String

**Accessibility:** Read Only

Specifies the **server-relative URL** of the **top-level site** in the **site collection**.

This property MUST begin with a forward slash ("/").

#### **3.2.5.119.1.1.7 ShowUrlStructure**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Specifies whether the **URL** structure of this **site collection** is viewable. See **Microsoft.SharePoint.Client.Web.ShowURLStructureForCurrentUser**, which is the scalar property used to determine the behavior for the **current user**. The default, if not disabled on the **Web application**, is "false".

#### **3.2.5.119.1.1.8 UIVersionConfigurationEnabled**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Specifies whether the **visual upgrade** UI for this **site collection** is displayed.

#### **3.2.5.119.1.1.9 Url**

**Type:** CSOM String

**Accessibility:** Read Only

Specifies the full **URL** of the **site (2)**, including **host name**, port number and path.

This property MUST NOT end with a forward slash ("/").

#### **3.2.5.119.1.1.10 Usage**

**Type:** Microsoft.SharePoint.Client.UsageInfo

**Accessibility:** Read Only

Specifies usage information about the **site (2)**, including bandwidth, storage, and the number of visits to the **site collection**.

### **3.2.5.119.1.1.11 CompatibilityLevel**

**Type:** CSOM Int32

**Accessibility:** Read Only

Specifies the compatibility level of the **site collection** for the purpose of major version level compatibility checks. [.<86>](#)

### **3.2.5.119.1.1.12 LockIssue**

**Type:** CSOM String

**Accessibility:** Read Only

Specifies the comment that is used when a **site collection** is locked. [.<87>](#)

### **3.2.5.119.1.1.13 ReadOnly**

**Type:** CSOM Boolean

**Accessibility:** Read Only

Specifies whether the **site collection** is read-only and is unavailable for write access. [.<88>](#)

### **3.2.5.119.1.1.14 CanUpgrade**

**Type:** CSOM Boolean

**Accessibility:** Read Only

Specifies whether this **site collection** is in an implementation-specific valid state for site collection upgrade, "true" if it is; otherwise, "false". [.<89>](#)

### **3.2.5.119.1.1.15 AllowSelfServiceUpgrade**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Specifies whether a version-to-version **site collection** upgrade is allowed on this site collection. [.<90>](#) "true" if it is; otherwise, "false".

### **3.2.5.119.1.1.16 AllowSelfServiceUpgradeEvaluation**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Specifies whether **upgrade evaluation site collection** is allowed to be created for this **site collection**. [.<91>](#) "true" if it is; otherwise, "false".

### **3.2.5.119.1.1.17 PrimaryUri**

**Type:** CSOM String

**Accessibility:** Read Only

Specifies the primary **URI** of this **site collection**, including the host name, port number, and path.

### 3.2.5.119.1.1.18 UpgradeReminderDate

**Type:** CSOM DateTime

**Accessibility:** Read Only

Specifies a date, after which **site collection administrators** will be reminded to upgrade the **site collection**.

### 3.2.5.119.1.1.19 UpgradeInfo

**Type:** Microsoft.SharePoint.Client.UpgradeInfo

**Accessibility:** Read Only

Specifies the upgrade information of this **site collection**.

### 3.2.5.119.1.1.20 Upgrading

**Type:** CSOM Boolean

**Accessibility:** Read Only

Specifies whether the **site collection** is currently being upgraded.

### 3.2.5.119.1.1.21 ShareByLinkEnabled

**Type:** CSOM Boolean

**Accessibility:** Read Only

Specifies whether the user will be able to share links to the documents that can be accessed without signing in.

### 3.2.5.119.1.1.22 AllowCreateDeclarativeWorkflow

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Specifies whether a **designer** can be used to create **declarative workflows** on this **site collection**. See **Microsoft.SharePoint.Client.Web.AllowCreateDeclarativeWorkflowForCurrentUser** (section [3.2.5.143.1.1.31](#)), which is the scalar property used to determine the behavior for the **current user**. The default, if not disabled on the **Web application**, is "true".

### 3.2.5.119.1.1.23 AllowSaveDeclarativeWorkflowAsTemplate

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Specifies whether a **designer** can be used to save **declarative workflows** as a template on this **site collection**. See

**Microsoft.SharePoint.Client.Web.AllowSaveDeclarativeWorkflowAsTemplateForCurrentUser**

(section [3.2.5.143.1.1.32](#)), which is the scalar property used to determine the behavior for the **current user**. The default, if not disabled on the **Web application**, is "true".

#### **3.2.5.119.1.1.24 AllowSavePublishDeclarativeWorkflow**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Specifies whether a **designer** can be used to save or publish **declarative workflows** on this **site collection**. See

**Microsoft.SharePoint.Client.Web.AllowSavePublishDeclarativeWorkflowForCurrentUser** (section [3.2.5.143.1.1.33](#)), which is the scalar property used to determine the behavior for the **current user**. The default, if not disabled on the **Web application**, is "true".

#### **3.2.5.119.1.1.25 RequiredDesignerVersion**

**Type:** CSOM String

**Accessibility:** Read Only

Specifies the required minimum version of the **designer** that can be used on this **site collection**. The default, if not disabled on the **Web application**, is "15.0.0.0".

#### **3.2.5.119.1.1.26 AuditLogTrimmingRetention**

**Type:** CSOM Int32

**Accessibility:** Read/Write

Gets or sets the number of days of audit log data to retain. If unset and audit trimming is enabled, the retention defaults to one schedule window of the administrator-configured schedule for trimming.

#### **3.2.5.119.1.1.27 CurrentChangeToken**

**Type:** Microsoft.SharePoint.Client.ChangeToken

**Accessibility:** Read Only

Gets the current change token that is used in the change log for the site collection.

#### **3.2.5.119.1.1.28 ExternalSharingTipsEnabled**

**Type:** CSOM Boolean

**Accessibility:** Read Only

Gets a **Boolean** value that specifies whether users will be greeted with a notification bar telling them that the site can be shared with external users. The value is true if the notification bar is enabled; otherwise, it is false.

#### **3.2.5.119.1.1.29 NeedsB2BUpgrade**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Specifies whether the site needs a Build-to-Build upgrade.

### **3.2.5.119.1.1.30   SandboxedCodeActivationCapability**

**Type:** Microsoft.SharePoint.Client.SandboxedCodeActivationCapabilities

**Accessibility:** Read/Write

Gets or sets the sandboxed code capability for the site collection. The default is set to Check.

### **3.2.5.119.1.1.31   ShareByEmailEnabled**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

When true, users will be able to grant permissions to guests for resources within the site collection.

### **3.2.5.119.1.1.32   TrimAuditLog**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

When this flag is set for the site, the audit events are trimmed periodically.

### **3.2.5.119.1.1.33   UpgradeScheduled**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Specifies whether the upgrade has been scheduled. It can only be set to false by a farm administrator. To set it to true, set the **UpgradeScheduledDate** (section [3.2.5.119.1.1.34](#)) to a future time.

### **3.2.5.119.1.1.34   UpgradeScheduledDate**

**Type:** CSOM DateTime

**Accessibility:** Read/Write

Specifies the upgrade scheduled date in **UTC (Coordinated Universal Time)**. Only the Date part is used. If **UpgradeScheduled** (section [3.2.5.119.1.1.33](#)) is false, returns **SqlDateTime.MinValue**.

### **3.2.5.119.1.1.35   DisableCompanyWideSharingLinks**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Specifies whether company-wide sharing links are disabled on all child sites. True means company-wide sharing links are disabled throughout the site collection, regardless of the settings on the root or child sites. False means each site can individually decide whether to turn on or off company-wide sharing links.

### **3.2.5.119.1.1.36   Classification**

**Type:** CSOM String

**Accessibility:** Read/Write

Gets or sets the classification of this site.

### **3.2.5.119.1.1.37    CommentsOnSitePagesDisabled**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Indicates whether comments on site pages are disabled or not.

### **3.2.5.119.1.1.38    ResourcePath**

**Type:** Microsoft.SharePoint.Client.ResourcePath

**Accessibility:** Read Only

The full Path of the site, including hostname and portnumber. Example: "http://HostName:80" for standalone case It does not end with "/".

### **3.2.5.119.1.1.39    ServerRelativePath**

**Type:** Microsoft.SharePoint.Client.ResourcePath

**Accessibility:** Read Only

Gets the server-relative path of the root Web site in the site collection.

### **3.2.5.119.1.1.40    ShowPeoplePickerSuggestionsForGuestUsers**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Represents the option to search for existing guest users via the people picker.

### **3.2.5.119.1.1.41    StatusBarLink**

**Type:** CSOM String

**Accessibility:** Read/Write

Gets or sets the status bar message link target for this site.

### **3.2.5.119.1.1.42    StatusBarText**

**Type:** CSOM String

**Accessibility:** Read/Write

Gets or sets the status bar message text for this site.

### **3.2.5.119.1.1.43    ThicketSupportDisabled**

**Type:** CSOM Boolean

**Accessibility:** Read Only

Gets a Boolean value to see if support for html thicket files is enabled or disabled.

## **3.2.5.119.1.2ObjectPath Properties**

### **3.2.5.119.1.2.1    Features**

**Type:** Microsoft.SharePoint.Client.FeatureCollection

**Accessibility:** Read Only

Specifies the collection of the **site collection** features for the site collection that contains the **site (2)**.

### **3.2.5.119.1.2.2 RecycleBin**

**Type:** Microsoft.SharePoint.Client.RecycleBinItemCollection

**Accessibility:** Read Only

Specifies the collection of **Recycle Bin items** for the **site collection**.

### **3.2.5.119.1.2.3 RootWeb**

**Type:** Microsoft.SharePoint.Client.Web

**Accessibility:** Read Only

Specifies the **top-level site** of the **site collection**.

### **3.2.5.119.1.2.4 UserCustomActions**

**Type:** Microsoft.SharePoint.Client.UserCustomActionCollection

**Accessibility:** Read Only

Specifies the collection of **user custom actions** for the **site collection**.

### **3.2.5.119.1.2.5 Owner**

**Type:** Microsoft.SharePoint.Client.User

**Accessibility:** Read/Write

Specifies the owner of the **site collection**.<92>

### **3.2.5.119.1.2.6 EventReceivers**

**Type:** Microsoft.SharePoint.Client.EventReceiverDefinitionCollection

**Accessibility:** Read Only

Specifies the collection of **event receivers** of this **site (2)**.<93>

### **3.2.5.119.1.2.7 Audit**

**Type:** Microsoft.SharePoint.Client.Audit

**Accessibility:** Read Only

Gets an audit store that is attached to the site collection.

### **3.2.5.119.1.2.8 SecondaryContact**

**Type:** Microsoft.SharePoint.Client.User

**Accessibility:** Read/Write



Gets or sets the secondary contact that is used for the site collection. The user that is specified by the **SecondaryContact** property SHOULD NOT be identical to the user that is specified by the **Owner** (section [3.2.5.119.1.2.5](#)) property.

## 3.2.5.119.2 Methods

### 3.2.5.119.2.1 Scalar Methods

#### 3.2.5.119.2.1.1 CreateMigrationJob

**Return Type:** CSOM GUID

Creates a new migration import job and queues it up for later processing by a separate timer job. The job will consume a well formed (pre-defined format) import package that is located in the Azure Blob Storage Containers specified in this method. The SLA for migration job processing is controlled through pre-configured queue and work-load throttling settings, and there is no guaranteed SLA or return time for a submitted job.

Once processed, the job results are placed into log files at the *azureContainerManifestUri* location if that was set to be writable in the SAS token specified in the URI. The same output log is also placed at the "\_catalogs/MaintenanceLogs" location of the target site collection as a text file. The logs will only be copied to the destination locations once the job has finished and is removed from the queue. The output of the log files SHOULD be examined and verified to determine if further work is required post-import.

The unique identifier for the migration job is returned if the job is successfully queued, or if unsuccessful, a null value will be returned. The migration job unique identifier can be used to query the migration job status while it is in the queue or being processed by using the **GetMigrationJobStatus** (section [3.2.5.119.2.1.6](#)) method.

#### Parameters:

*gWebId*: The unique identifier for the targeted destination web for the package import. Addition information and identifiers for the import are specified within the import package itself.

Type: CSOM GUID

*azureContainerSourceUri*: A valid URL including SAS token for accessing the Azure Blob Storage Container that contains the binary files of type block.

Type: CSOM String

*azureContainerManifestUri*: A valid URL including SAS token for accessing the Azure Blob Storage Container that contains the manifest. If write access is granted in the SAS token in this URI, then it will also be used for the log output. This can be the same URL as *azureContainerSourceUri*.

Type: CSOM String

*azureQueueReportUri*: A valid URL including SAS token for accessing the user-provided Azure Queue. If not null, and proper access is granted in the SAS token in this URI, it will be used for a real-time status update.

Type: CSOM String

#### 3.2.5.119.2.1.2 CreatePreviewSPSite

**Return Type:** None

Schedules the creation of an evaluation copy of the **site collection** for the purposes of evaluating an upgrade of the site collection to a newer version. [<94>](#)

**Parameters:**

*upgrade*: If "true", the evaluation site collection MUST be upgraded when it is created. If "false", the evaluation site collection MUST NOT be upgraded when it is created.

Type: **CSOM Boolean**

*sendemail*: If "true", a notification email MUST be sent to the requestor and the site collection administrators at the completion of the creation of the evaluation site collection. If "false", such notification MUST NOT be sent.

Type: CSOM Boolean

**3.2.5.119.2.1.3 DeleteMigrationJob****Return Type: CSOM Boolean**

Deletes the given migration job from the queue. Returns true if the migration job is found in the queue and successfully deleted. If the job is not found, false is returned.

**Parameters:**

*id*: The unique identifier of the migration job returned from the **CreateMigrationJob** (section [3.2.5.119.2.1.1](#)) method.

Type: **CSOM GUID**

**3.2.5.119.2.1.4 Exists**

This method is a **static CSOM method**.

**Return Type: CSOM Boolean**

Determines if a site with the specified url exists.

**Parameters:**

*url*: The absolute url of a site.

Type: **CSOM String**

**3.2.5.119.2.1.5 ExtendUpgradeReminderDate****Return Type: None**

Extend the upgrade reminder date for this **site collection**, so that **site collection administrators** will not be reminded to run a site collection upgrade before the new date. [<95>](#)

**Parameters:** None

**3.2.5.119.2.1.6 GetMigrationJobStatus****Return Type: Microsoft.SharePoint.Client.MigrationJobState**

Queries the queue status for the specified migration job. It is an optional check after calling the **CreateMigrationJob** (section [3.2.5.119.2.1.1](#)) method. Once the migration job has completed, it will no longer show up in the queue and the log output SHOULD be checked for detailed status.

The migration job status is returned if the job is found in the queue. If unsuccessful, a value of None (0) is returned.

**Parameters:**

*id*: The unique identifier of the migration job returned from the **CreateMigrationJob** (section 3.2.5.119.2.1.1) method.

Type: **CSOM GUID**

### 3.2.5.119.2.1.7 GetWebPath

**Return Type:** Microsoft.SharePoint.Client.ResourcePath

Gets the absolute URL of the web specified by the SiteId and WebId.

**Parameters:**

*siteId*: The ID of the site collection.

Type: **CSOM GUID**

*webId*: The ID of the web.

Type: CSOM GUID

### 3.2.5.119.2.1.8 Invalidate

**Return Type:** None

Invalidates cached upgrade information about the **site collection** so that this information will be recomputed the next time it is needed. [<96>](#)

**Parameters:** None

### 3.2.5.119.2.1.9 NeedsUpgradeByType

**Return Type:** **CSOM Boolean**

Returns "true" if this site collection requires **site collection** upgrade of the specified type; otherwise, "false". [<97>](#)

**Parameters:**

*versionUpgrade*: If "true", version-to-version site collection upgrade is requested; otherwise "false" for build-to-build site collection upgrade.

Type: CSOM Boolean

*recursive*: If "true", child upgradable objects will be inspected; otherwise "false".

Type: CSOM Boolean

### 3.2.5.119.2.1.10 RunUpgradeSiteSession

**Return Type:** None

Either runs a **site collection** upgrade, or schedules it to be run in the future, depending on available system resources and the value of the *queueOnly* parameter. [<98>](#)

The user executing this method MUST be a **farm** administrator or a **site collection administrator**.

**Parameters:**

*versionUpgrade*: If "true", specifies that a version-to-version upgrade will be performed. If "false", specifies that a build-to-build upgrade will be performed.

Type: **CSOM Boolean**

*queueOnly*: If "true", specifies that the upgrade will not be run immediately; it will be queued for a later run.

Type: CSOM Boolean

*sendEmail*: If "true", a notification email will be sent to the requestor and the site collection administrators at the completion of the site collection upgrade. If "false", such notification will not be sent.

Type: CSOM Boolean

### **3.2.5.119.2.1.11 UpdateClientObjectModelUseRemoteAPIsPermissionSetting**

**Return Type:** None

Sets whether the client-side object model (CSOM) requests that are made in the context of any **site (2)** inside the **site collection** require *UseRemoteAPIs* permission.

**Parameters:**

*requireUseRemoteAPIs*: Specifies whether the client-side object model (CSOM) requests that are made in the context of any site (2) inside the site collection require *UseRemoteAPIs* permission.

Type: **CSOM Boolean**

## **3.2.5.119.2.2 ObjectPath Methods**

### **3.2.5.119.2.2.1 GetCatalog**

**Return Type:** Microsoft.SharePoint.Client.List

Specifies the **list template gallery**, **site template gallery**, **Web Part gallery**, **master page gallery**, or other galleries from the **site collection**, including custom galleries that are defined by users.

This method requires **permissions** to the **top-level site** of the site collection, which is where the galleries are located.

**Parameters:**

*typeCatalog*: Specifies the type of list template for the gallery.

Type: **CSOM Int32**

### **3.2.5.119.2.2.2 GetChanges**

**Return Type:** Microsoft.SharePoint.Client.ChangeCollection

Specifies the collection of the **site collection** changes from the **change log** that have occurred within the scope of the site collection, based on the specified **query**.

**Parameters:**

*query*: Specifies the query to be used to build the collection of site collection changes to be returned.

Type: Microsoft.SharePoint.Client.ChangeQuery

### 3.2.5.119.2.2.3 GetCustomListTemplates

**Return Type:** Microsoft.SharePoint.Client.ListTemplateCollection

Specifies the collection of custom **list templates** for a given **site (2)**.

**Parameters:**

*web*: Specifies the site (2) that contains the custom list templates to be returned.

Type: Microsoft.SharePoint.Client.Web

### 3.2.5.119.2.2.4 OpenWeb

**Return Type:** Microsoft.SharePoint.Client.Web

Opens a new **site (2)** by using the specified **URL**.

**Parameters:**

*strUrl*: Specifies the **server-relative URL** or **site-relative URL** of the site (2) to open. If **strUrl** is empty, the **top-level site** MUST be opened.

Type: **CSOM String**

It MUST NOT be NULL.

### 3.2.5.119.2.2.5 OpenWebById

**Return Type:** Microsoft.SharePoint.Client.Web

Returns the **site (2)** with the specified GUID.

**Parameters:**

*gWebId*: A GUID that specifies which site (2) to return.

Type: **CSOM GUID**

### 3.2.5.119.2.2.6 GetWebTemplates

**Return Type:** Microsoft.SharePoint.Client.WebTemplateCollection

Returns the collection of **site definitions** that are available for creating **Web sites** within the **site collection**.<99>

**Parameters:**

*LCID*: A 32-bit unsigned integer that specifies the language of the site definitions that are returned from the site collection.

Type: **CSOM UInt32**

*overrideCompatLevel*: Specifies the compatibility level of the **site (2)** to return from the site collection. If this value is 0, the compatibility level of the site (2) is used.

Type: **CSOM Int32**

### 3.2.5.119.2.2.7 RunHealthCheck

**Return Type:** Microsoft.SharePoint.Client.SiteHealth.SiteHealthSummary

Runs a health check as follows.<100> (The health rules referenced below perform an implementation-dependent check on the health of a site collection.)

- If *ruleId* is not an empty GUID, runs the specified **site collection** health rule and returns a summary of the results. If *ruleId* is an empty GUID, runs all of the site collection health rules and returns a summary of the results.
- If *bRepair* is "true", runs the specified rules in repair mode. In this case, and if a given rule is repairable, an attempt will be made to repair issues found by the rule, and the results from that attempted repairs are returned. If *bRepair* is "false", an attempt to repair issues found is not made.
- If *bRunAlways* is "true", rules are run by this method, and the results are returned. If "false", cached results from a recent previous run can be returned instead.

**Parameters:**

*ruleId*: Specifies the rule or rules to be run. If the value is an empty GUID, all rules are run, otherwise only the specified rule is run.

Type: **CSOM GUID**

*bRepair*: Specifies whether repairable rules are to be run in repair mode.

Type: **CSOM Boolean**

*bRunAlways*: Specifies whether the rules will be run as a result of this call or cached results from a previous run can be returned.

Type: CSOM Boolean

### **3.2.5.119.2.2.8 GetMigrationStatus**

**Return Type:** Microsoft.SharePoint.Client.SPMigrationJobStatusCollection

Queries the queue status for all migration jobs. It is an optional check after calling the **CreateMigrationJob** (section [3.2.5.119.2.1.1](#)) method. Once the migration job has completed, it will no longer show up in the queue and the log output SHOULD be checked for detailed status. The migration job status is returned if the job is found in the queue. If unsuccessful, a value of None (0) is returned.

**Parameters:** None

### **3.2.5.119.2.2.9 GetRecycleBinItems**

**Return Type:** Microsoft.SharePoint.Client.RecycleBinItemCollection

Returns a collection of **Recycle Bin items** within this **site collection**.

**Parameters:**

*pagingInfo*: A string describing paging information for the next page of Recycle Bin items.

Type: **CSOM String**

MUST be formatted as a **URL-encoded** form body as described in [\[HTML\]](#) section 17.13.4 - Form content types. MUST contain the following **key value pairs (KVP)**.

Key name	Description of value	Type of value
id	The <b>item identifier</b> of the Recycle Bin item to display first on the next page of Recycle Bin items.	<b>CSOM GUID</b>
title	The title of the Recycle Bin item to display first on the next page of Recycle Bin items.	CSOM String
searchValue	The value to search for in the <b>column</b> specified by the <i>orderBy</i> parameter.	CSOM String

*rowLimit*: The maximum number of Recycle Bin items to retrieve.

Type: **CSOM Int32**

*isAscending*: Specifies whether the Recycle Bin items are sorted in ascending order by the column specified in the *orderBy* parameter. A value of true indicates ascending order, and a value of false indicates descending order.

Type: **CSOM Boolean**

*orderBy*: The column to sort results by.

Type: Microsoft.SharePoint.Client.RecycleBinOrderBy

*itemState*: Specifies whether to retrieve items from the **first-stage Recycle Bin** or the **second-stage Recycle Bin**.

Type: Microsoft.SharePoint.Client.RecycleBinItemState

### 3.2.5.119.2.2.10 OpenWebUsingPath

**Return Type:** Microsoft.SharePoint.Client.Web

Opens a new SP.Web using the exact path of the web.

#### Parameters:

*path*: The **SP.ResourcePath** (section [3.2.5.420](#)) that contains the server relative or web relative path of the **SP.Web** (section [3.2.5.143](#)) to open.

Type: Microsoft.SharePoint.Client.ResourcePath

It MUST NOT be NULL.

### 3.2.5.120 Microsoft.SharePoint.Client.SubwebQuery

**TypeId:** {E3A4D63C-876B-4E24-A972-7664437146FE}

**ShortName:** SP.SubwebQuery

Defines a query to specify which child **Web sites** to return from a Web site.

#### 3.2.5.120.1 Properties

##### 3.2.5.120.1.1 Scalar Properties

### **3.2.5.120.1.1.1 ConfigurationFilter**

**Type:** CSOM Int32

**Accessibility:** Read/Write

An integer that identifies the site template used to provision this site. The value defaults to -1, which means no configuration filter is used for the query. The value MUST NOT be less than -1.

### **3.2.5.120.1.1.2 WebTemplateFilter**

**Type:** CSOM Int32

**Accessibility:** Read/Write

An integer that identifies the template used in the site definition to define the base structure of this site. The value defaults to -1, which means no web template filter is used for the query. The value MUST NOT be less than -1.

### **3.2.5.120.1.2ObjectPath Properties**

None.

### **3.2.5.121 Microsoft.SharePoint.Client.TemplateFileType**

**ShortName:** SP.TemplateFileType

**Flag:** false

Specifies the type of ghosted file template to use

#### **3.2.5.121.1 Field Values**

##### **3.2.5.121.1.1StandardPage**

**Value:** 0

A standard page uses the default view template. Value is 0.

##### **3.2.5.121.1.2WikiPage**

**Value:** 1

A Wiki page uses the default Wiki template. Value is 1.

##### **3.2.5.121.1.3FormPage**

**Value:** 2

A form page uses the default form template. Value is 2.

##### **3.2.5.121.1.4Invalid**

**Value:** -1

An invalid template file type. MUST NOT be used by any page.

##### **3.2.5.121.1.5ClientSidePage**



**Value:** 3

A client side page uses the default client side page template.

### **3.2.5.122 Microsoft.SharePoint.Client.UrlFieldFormatType**

**ShortName:** SP.UrlFieldFormatType

**Flag:** false

Specifies the display format used for URL fields.

#### **3.2.5.122.1 Field Values**

##### **3.2.5.122.1.1 Hyperlink**

**Value:** 0

Represents a usual anchor tag.

##### **3.2.5.122.1.2 Image**

**Value:** 1

Represents an image that serves as a hyperlink.

### **3.2.5.123 Microsoft.SharePoint.Client.UsageInfo**

**TypeId:** {7EC28504-35F9-4FCF-A09F-401024417292}

**ShortName:** SP.UsageInfo

Provides fields that are used to access information about **site collection** usage.

#### **3.2.5.123.1 Properties**

##### **3.2.5.123.1.1 Scalar Properties**

###### **3.2.5.123.1.1.1 Bandwidth**

**Type:** **CSOM Int64**

**Accessibility:** Read Only

Specifies the cumulative bandwidth, in bytes, used by the **site collection** during an implementation-specific period.

Its value MUST be equal to or greater than 0.

###### **3.2.5.123.1.1.2 DiscussionStorage**

**Type:** **CSOM Int64**

**Accessibility:** Read Only

Specifies the total amount of disk space, in bytes, currently being used to store **Web discussion comments** in the **site collection**.

Its value MUST be equal to or greater than 0.

### 3.2.5.123.1.1.3 Hits

**Type:** CSOM Int64

**Accessibility:** Read Only

Specifies the cumulative number of requests for pages in the **site collection** during an implementation-specific period.

Its value MUST be equal to or greater than 0.

### 3.2.5.123.1.1.4 Storage

**Type:** CSOM Int64

**Accessibility:** Read Only

Specifies the total amount of disk space, in bytes, currently being used by the **site collection**.

Its value MUST be equal to or greater than 0.

### 3.2.5.123.1.1.5 StoragePercentageUsed

**Type:** CSOM Double

**Accessibility:** Read Only

Specifies the ratio of the amount of disk space currently being used by the **site collection** to the maximum disk space specified in the **site collection quota**.

The server MUST return 0 if no maximum available storage is specified in the site collection quota

Its value MUST be equal to or greater than 0. Its value MUST be equal to or less than 1.

### 3.2.5.123.1.1.6 Visits

**Type:** CSOM Int64

**Accessibility:** Read Only

Specifies the cumulative number of requests for pages in the **site collection**, with no **HTTP referer**, or a HTTP referer outside of the current site collection during an implementation-specific period.

Its value MUST be equal to or greater than 0.

## 3.2.5.123.1.2 ObjectPath Properties

None.

### 3.2.5.124 Microsoft.SharePoint.Client.User

**TypeId:** {AE70D2A4-EC46-4ED9-9B1E-9D0245754463}

**ShortName:** SP.User

Specifies a user.

#### 3.2.5.124.1 Properties

### 3.2.5.124.1.1 Scalar Properties

#### 3.2.5.124.1.1.1 Email

Type: **CSOM String**

Accessibility: Read/Write

Specifies the **e-mail address** of the user.

It MUST NOT be NULL. Its length MUST be equal to or less than 255.

#### Exceptions:

Error Code	Error Type Name	Condition
-1	Microsoft.SharePoint.SPException	The property is read when either the user <b>object (1)</b> was not successfully initialized or the user could not be found.
-1	Microsoft.SharePoint.SPException	The property is set when either the user object (1) was not successfully initialized or the user could not be found.

#### 3.2.5.124.1.1.2 Id

Type: **CSOM Int32**

Accessibility: Read Only

Specifies the **member** identifier of the user. See **Microsoft.SharePoint.Client.Principal.Id**, as specified in section [3.2.5.100.1.1.1](#).

#### Exceptions:

Error Code	Error Type Name	Condition
-1	Microsoft.SharePoint.SPException	The user <b>object (1)</b> was not successfully initialized or the user could not be found.

#### 3.2.5.124.1.1.3 LoginName

Type: **CSOM String**

Accessibility: Read Only

Specifies the **login name** of the user.

Its length MUST be equal to or less than 251.

#### Exceptions:

Error Code	Error Type Name	Condition
-1	Microsoft.SharePoint.SPException	The user <b>object (1)</b> was not successfully initialized or the user

Error Code	Error Type Name	Condition
		could not be found.

#### 3.2.5.124.1.1.4 PrincipalType

**Type:** Microsoft.SharePoint.Client.Utilities.PrincipalType

**Accessibility:** Read Only

Specifies the type of **principal** represented by this **object (1)**.

If the user is a domain **group**, this MUST be **PrincipalType.SecurityGroup**. Otherwise it MUST be **PrincipalType.User**.

#### 3.2.5.124.1.1.5 Title

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies the **display name** of the user.

It MUST NOT be empty. Its length MUST be equal to or less than 255.

#### Exceptions:

Error Code	Error Type Name	Condition
-1	Microsoft.SharePoint.SPException	The property is read when either the user <b>object (1)</b> was not successfully initialized or the user could not be found.
-1	Microsoft.SharePoint.SPException	The property is set when either the user object (1) was not successfully initialized or the user could not be found.

#### 3.2.5.124.1.1.6 IsSiteAdmin

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Specifies whether the user is the **site collection** administrator for this site collection. [<101>](#)

#### 3.2.5.124.1.1.7 IsHiddenInUI

**Type:** CSOM Boolean

**Accessibility:** Read Only

See **Microsoft.SharePoint.Client.Principal.IsHiddenInUI**, as specified in section [3.2.5.100.1.1.5.<102>](#)

#### 3.2.5.124.1.1.8 UserId

**Type:** Microsoft.SharePoint.Client.UserIdInfo

**Accessibility:** Read Only

Gets identity provider's unique identifier information about the user.

The property returns null if identity provider's unique identifier cannot be constructed.

### **3.2.5.124.1.1.9 IsShareByEmailGuestUser**

**Type:** CSOM Boolean

**Accessibility:** Read Only

Gets a value indicating whether this User is a share by email guest user.

If this instance is a share by email guest user, it's true; otherwise, false.

### **3.2.5.124.1.1.10 IsEmailAuthenticationGuestUser**

**Type:** CSOM Boolean

**Accessibility:** Read Only

Indicates whether the User is a share by email guest user using time of access authentication.

If this instance is an email authentication guest user, this value MUST be true, otherwise it MUST be false.

## **3.2.5.124.1.2 ObjectPath Properties**

### **3.2.5.124.1.2.1 Groups**

**Type:** Microsoft.SharePoint.Client.GroupCollection

**Accessibility:** Read Only

Gets the **groups** that this **User** (section [3.2.5.124](#)) is a member of.<103>

### **3.2.5.124.1.2.2 Alerts**

**Type:** Microsoft.SharePoint.Client.AlertCollection

**Accessibility:** Read Only

Gets site alerts for this user.

## **3.2.5.124.2 Methods**

### **3.2.5.124.2.1 Scalar Methods**

#### **3.2.5.124.2.1.1 Update**

**Return Type:** None

Updates the user with changes that have been made to the user properties.

**Parameters:** None

### 3.2.5.124.2.2 ObjectPath Methods

None.

### 3.2.5.125 Microsoft.SharePoint.Client.UserCollection

**TypeId:** {E090781E-8899-4672-9B3D-A78F49FAD19D}

**ShortName:** SP.UserCollection

Represents a collection of user **objects (1)**.

#### 3.2.5.125.1 Properties

##### 3.2.5.125.1.1 Scalar Properties

None.

##### 3.2.5.125.1.2 ObjectPath Properties

None.

#### 3.2.5.125.2 Methods

##### 3.2.5.125.2.1 Scalar Methods

###### 3.2.5.125.2.1.1 Remove

**Return Type:** None

Removes the user specified by the parameter from the collection.

**Parameters:**

*user:* A user to remove from the collection

Type: Microsoft.SharePoint.Client.User

It MUST NOT be NULL.

###### 3.2.5.125.2.1.2 RemoveById

**Return Type:** None

Removes the user with the specified member identifier from the collection. [<104>](#)

**Parameters:**

*id:* Specifies the member identifier.

Type: **CSOM Int32**

###### 3.2.5.125.2.1.3 RemoveByLoginName

**Return Type:** None

Removes the user with the specified user name from the collection. [<105>](#)

**Parameters:**

*loginName*: A string that contains the user name.

Type: **CSOM String**

### 3.2.5.125.2.2 ObjectPath Methods

#### 3.2.5.125.2.2.1 Add

**Return Type:** Microsoft.SharePoint.Client.User

Adds the user specified by the user creation information parameter to the collection.

**Parameters:**

*parameters*: An **object (1)** containing information about the user to be added.

Type: Microsoft.SharePoint.Client.UserCreationInformation

It MUST NOT be NULL.

**Exceptions:**

Error Code	Error Type Name	Condition
-1	Microsoft.SharePoint.SPException	The collection is read-only.
-1	System.Security.SecurityException	The collection is the <b>farm administrators group</b> and the specified user is not a computer administrator.

#### 3.2.5.125.2.2.2 AddUser

**Return Type:** Microsoft.SharePoint.Client.User

Adds the user specified by the user parameter to the collection and returns a **reference** to the added SP.User.

**Parameters:**

*user*: A user to add.

Type: Microsoft.SharePoint.Client.User

**Exceptions:**

Error Code	Error Type Name	Condition
-1	Microsoft.SharePoint.SPException	The collection is read-only.
-1	System.Security.SecurityException	The collection is the <b>farm administrators group</b> and the specified user is not a computer administrator.

#### 3.2.5.125.2.2.3 GetByEmail

**Return Type:** Microsoft.SharePoint.Client.User

Returns the user with the specified e-mail address.

**Parameters:**

*emailAddress*: A string that contains the e-mail address of the user.

Type: **CSOM String**

It MUST NOT be NULL. It MUST NOT be empty. Its length MUST be equal to or less than 255.

### **3.2.5.125.2.2.4 GetById**

**Return Type:** Microsoft.SharePoint.Client.User

Returns the user with the specified **member** identifier.

**Parameters:**

*id*: Specifies the member identifier.

Type: **CSOM Int32**

### **3.2.5.125.2.2.5 GetByLoginName**

**Return Type:** Microsoft.SharePoint.Client.User

Returns the user with the specified login name.

**Parameters:**

*loginName*: A string that contains the **login name** of the user.

Type: **CSOM String**

It MUST NOT be NULL. It MUST NOT be empty. Its length MUST be equal to or less than 251.

## **3.2.5.126 Microsoft.SharePoint.Client.UserCreationInformation**

**TypeId:** {6ECD8AF6-BED3-4A74-BE76-1EC981B350E1}

**ShortName:** SP.UserCreationInformation

Parameters to invite a user.

### **3.2.5.126.1 Properties**

#### **3.2.5.126.1.1 Scalar Properties**

##### **3.2.5.126.1.1.1 Email**

Type: **CSOM String**

**Accessibility:** Read/Write

Specifies the e-mail address for the user to be created.

Its length MUST be equal to or less than 255.

##### **3.2.5.126.1.1.2 LoginName**



**Type:** CSOM String

**Accessibility:** Read/Write

Specifies the login name for the user to be created.

It MUST NOT be NULL. It MUST NOT be empty. Its length MUST be equal to or less than 251.

### 3.2.5.126.1.1.3 Title

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies the display name for the user to be created.

Its length MUST be equal to or less than 255.

### 3.2.5.126.1.2 ObjectPath Properties

None.

### 3.2.5.127 Microsoft.SharePoint.Client.UserCustomAction

**TypeId:** {232F8709-5DFD-44CF-A35B-7D8538C9336E}

**ShortName:** SP.UserCustomAction

Specifies a **custom action**.

#### 3.2.5.127.1 Properties

##### 3.2.5.127.1.1 Scalar Properties

###### 3.2.5.127.1.1.1 ClientSideComponentId

**Type:** CSOM GUID

**Accessibility:** Read/Write

The unique identifier of the client-side component associated with this custom action.

###### 3.2.5.127.1.1.2 ClientSideComponentProperties

**Type:** CSOM String

**Accessibility:** Read/Write

This property is only used when a **ClientSideComponentId** is specified. It is optional. If non-empty, the string MUST contain a JSON object with custom initialization properties whose format and meaning are defined by the client-side component.

###### 3.2.5.127.1.1.3 CommandUIExtension

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies an implementation-specific **XML fragment** that determines user interface properties of the **custom action**.

It MUST be an XML fragment.

#### **3.2.5.127.1.1.4 Description**

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies the description for the **custom action**.

#### **3.2.5.127.1.1.5 Group**

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies an implementation-specific value that determines the position of the **custom action** on the page.

#### **3.2.5.127.1.1.6 Id**

**Type:** CSOM GUID

**Accessibility:** Read Only

Specifies the identifier of the **custom action**.

#### **3.2.5.127.1.1.7 ImageUrl**

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies the **URL** for the icon of the **custom action**.

It MUST be NULL, a **server-relative URL**, or an **absolute URL**.

#### **3.2.5.127.1.1.8 Location**

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies an implementation-specific value that determines which pages display the **custom action**.

#### **3.2.5.127.1.1.9 Name**

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies the name of the **custom action**.

#### **3.2.5.127.1.1.10 RegistrationId**

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies the identifier of the **object (1)** associated with the **custom action**. It MUST be a **list identifier** or **list template** if **RegistrationType** is **Microsoft.SharePoint.Client.UserCustomActionRegistrationType.List**. It MUST be a **content type identifier** if **RegistrationType** is **Microsoft.SharePoint.Client.UserCustomActionRegistrationType.ContentType**. It MUST be a **ProgID** if **RegistrationType** is **Microsoft.SharePoint.Client.UserCustomActionRegistrationType.ProgId**. It MUST be a **file extension** if **RegistrationType** is **Microsoft.SharePoint.Client.UserCustomActionRegistrationType.FileType**.

### 3.2.5.127.1.1.11 RegistrationType

**Type:** Microsoft.SharePoint.Client.UserCustomActionRegistrationType

**Accessibility:** Read/Write

Specifies the type of **object (1)** associated with the **custom action**. It MUST be a **list** if the **RegistrationId** is a **list identifier** or **list template**. It MUST be **ContentType** if the **RegistrationId** is a **content type identifier**. It MUST be **ProgID** if the **RegistrationId** is a **ProgID**. It MUST be **FileType** if the **RegistrationId** is a **file extension**.

### 3.2.5.127.1.1.12 Rights

**Type:** Microsoft.SharePoint.Client.BasePermissions

**Accessibility:** Read/Write

Specifies the **permissions** needed for the **custom action**.

It MUST NOT be NULL.

### 3.2.5.127.1.1.13 Scope

**Type:** Microsoft.SharePoint.Client.UserCustomActionScope

**Accessibility:** Read Only

Specifies the scope of the **custom action**.

### 3.2.5.127.1.1.14 ScriptBlock

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies the [\[ECMA-262-1999\]](#) script to be executed when the **custom action** is performed. It MUST be NULL if *Location* is not "ScriptLink".

### 3.2.5.127.1.1.15 ScriptSrc

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies the **URI** of a **file** that contains the [\[ECMA-262-1999\]](#) script to execute on the page. It MUST be NULL if *Location* is not "ScriptLink".

It MUST be NULL, or a **server-relative URL**.

### 3.2.5.127.1.1.16 Sequence

**Type:** CSOM Int32

**Accessibility:** Read/Write

Specifies an implementation-specific value that determines the order of the **custom action** that appears on the page.

Its value MUST be equal to or greater than 0. Its value MUST be equal to or less than 65536.

### 3.2.5.127.1.1.17 Title

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies the **display name** for the **custom action**.

### 3.2.5.127.1.1.18 Url

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies the **URI** to navigate to when the **custom action** is called.

It MUST be NULL or a URI. If it is a URL, it MUST be a **server-relative URL**.

### 3.2.5.127.1.1.19 VersionOfUserCustomAction

**Type:** CSOM String

**Accessibility:** Read Only

Specifies an implementation-specific version identifier.

It MUST NOT be NULL.

## 3.2.5.127.1.2 ObjectPath Properties

### 3.2.5.127.1.2.1 DescriptionResource

**Type:** Microsoft.SharePoint.Client.UserResource

**Accessibility:** Read Only

Gets the **SP.UserResource** object that corresponds to the Description for this object.

### 3.2.5.127.1.2.2 TitleResource

**Type:** Microsoft.SharePoint.Client.UserResource

**Accessibility:** Read Only

Returns the **UserResource** object that corresponds to the Title for this object.

## 3.2.5.127.2 Methods

### 3.2.5.127.2.1 Scalar Methods

#### 3.2.5.127.2.1.1 DeleteObject

**Return Type:** None

Deletes the **custom action**.

**Parameters:** None

**Exceptions:**

Error Code	Error Type Name	Condition
- 2130575305	Microsoft.SharePoint.SPException	Custom action was modified on the server in a way that prevents changes from being committed, as determined by the protocol server.

#### 3.2.5.127.2.1.2 Update

**Return Type:** None

Commits changed properties of **custom action**.

**Parameters:** None

**Exceptions:**

Error Code	Error Type Name	Condition
- 2130575305	Microsoft.SharePoint.SPException	Custom action was modified on the server in a way that prevents changes from being committed, as determined by the protocol server.

### 3.2.5.127.2.2 ObjectPath Methods

None.

#### 3.2.5.128 Microsoft.SharePoint.Client.UserCustomActionCollection

**TypeId:** {70D1CB2D-D304-4D96-9B54-74B3F400FA28}

**ShortName:** SP.UserCustomActionCollection

Specifies a collection of **custom actions**.

#### 3.2.5.128.1 Properties

##### 3.2.5.128.1.1 Scalar Properties

None.

##### 3.2.5.128.1.2 ObjectPath Properties

None.

### 3.2.5.128.2 Methods

#### 3.2.5.128.2.1 Scalar Methods

##### 3.2.5.128.2.1.1 Clear

**Return Type:** None

Deletes all **custom actions** in the collection.

**Parameters:** None

**Exceptions:**

Error Code	Error Type Name	Condition
- 2130575305	Microsoft.SharePoint.SPException	Custom action was modified on the server in a way that prevents changes from being committed, as determined by the protocol server.

#### 3.2.5.128.2.2 ObjectPath Methods

##### 3.2.5.128.2.2.1 Add

**Return Type:** Microsoft.SharePoint.Client.UserCustomAction

Adds a **custom action** to the collection.

**Parameters:** None

##### 3.2.5.128.2.2.2 GetById

**Return Type:** Microsoft.SharePoint.Client.UserCustomAction

Returns the **custom action** with the specified identifier. It MUST return NULL if no custom action corresponds to the specified identifier.

**Parameters:**

*id*: Specifies the identifier of the custom action.

Type: **CSOM GUID**

### 3.2.5.129 Microsoft.SharePoint.Client.UserCustomActionRegistrationType

**ShortName:** SP.UserCustomActionRegistrationType

**Flag:** false

Specifies the type of **object (1)** associated with the **custom action**.

#### 3.2.5.129.1 Field Values

##### 3.2.5.129.1.1 None

**Value:** 0

Specifies that the **object (1)** association is not specified.

### **3.2.5.129.1.2List**

**Value:** 1

Specifies that the **custom action** is associated with a **list**.

### **3.2.5.129.1.3ContentType**

**Value:** 2

Specifies that the **custom action** is associated with a **content type**.

### **3.2.5.129.1.4ProgId**

**Value:** 3

Specifies that the **custom action** is associated with a **ProgID**.

### **3.2.5.129.1.5FileType**

**Value:** 4

Specifies that the **custom action** is associated with a **file extension**.

## **3.2.5.130 Microsoft.SharePoint.Client.UserCustomActionScope**

**ShortName:** SP.UserCustomActionScope

**Flag:** false

Specifies the scope of the **custom action**.

### **3.2.5.130.1 Field Values**

#### **3.2.5.130.1.1Unknown**

**Value:** 0

Specifies that the scope of the **custom action** is not specified.

#### **3.2.5.130.1.2Site**

**Value:** 2

Specifies that the scope of the **custom action** is limited to a **site collection**.

#### **3.2.5.130.1.3Web**

**Value:** 3

Specifies that the scope of the **custom action** is limited to a **site (2)**.

#### **3.2.5.130.1.4List**

**Value:** 4

Specifies that the scope of the **custom action** is limited to a **list**.

### **3.2.5.131 Microsoft.SharePoint.Client.Utilities.DateTimeFormat**

**ShortName:** SP.Utilities.DateTimeFormat

**Flag:** false

Specifies the date and time format.

#### **3.2.5.131.1 Field Values**

##### **3.2.5.131.1.1 DateTime**

**Value:** 0

Specifies that both date and time are included.

##### **3.2.5.131.1.2 DateOnly**

**Value:** 1

Specifies that only the date is included.

##### **3.2.5.131.1.3 TimeOnly**

**Value:** 2

Specifies that only time is included.

##### **3.2.5.131.1.4 ISO8601**

**Value:** 3

Specifies that the format is [\[ISO-8601\]](#) time format YYYY-MM-DDTHH:MM:SSZ.

##### **3.2.5.131.1.5 MonthDayOnly**

**Value:** 4

Specifies that only the month and day are included.

##### **3.2.5.131.1.6 MonthYearOnly**

**Value:** 5

Specifies that only the month and year are included.

##### **3.2.5.131.1.7 LongDate**

**Value:** 6

Specifies that the date is in long format including the day of week, day, month and year. [<106>](#)

##### **3.2.5.131.1.8 UnknownFormat**

**Value:** 7



Specifies that the date parsing code SHOULD ignore the format mask when attempting to parse the given date. <107>

### **3.2.5.132 Microsoft.SharePoint.Client.Utilities.IconSize**

**ShortName:** SP.Utilities.IconSize

**Flag:** false

Enumeration used to specify the icon size requested for the **MapToIcon** method in the Microsoft.SharePoint.SPWeb class.

#### **3.2.5.132.1 Field Values**

##### **3.2.5.132.1.1 Size16**

**Value:** 0

Specifies an icon size of 16 x 16 pixels.

##### **3.2.5.132.1.2 Size32**

**Value:** 1

Specifies an icon size of 32 x 32 pixels.

##### **3.2.5.132.1.3 Size256**

**Value:** 2

Specifies an icon size of 256 x 256 pixels.

### **3.2.5.133 Microsoft.SharePoint.Client.Utilities.PrincipalInfo**

**TypeId:** {C88E4D2E-768D-4065-9DA4-D2880E08733E}

**ShortName:** SP.Utilities.PrincipalInfo

Provides access to information about a **principal**.

#### **3.2.5.133.1 Properties**

##### **3.2.5.133.1.1 Scalar Properties**

###### **3.2.5.133.1.1.1 Department**

**Type:** CSOM String

**Accessibility:** Read Only

Specifies the department name of the **principal**.

###### **3.2.5.133.1.1.2 DisplayName**

**Type:** CSOM String

**Accessibility:** Read Only

Specifies the **display name** of the **principal**.

### **3.2.5.133.1.1.3      Email**

**Type:** CSOM String

**Accessibility:** Read Only

Specifies the **e-mail address** of the **principal**.

### **3.2.5.133.1.1.4      JobTitle**

**Type:** CSOM String

**Accessibility:** Read Only

Specifies the job title of the **principal**.

### **3.2.5.133.1.1.5      LoginName**

**Type:** CSOM String

**Accessibility:** Read Only

Specifies the **login name** of the **principal**.

### **3.2.5.133.1.1.6      Mobile**

**Type:** CSOM String

**Accessibility:** Read Only

Specifies the number of a **mobile device** of the **principal**.

### **3.2.5.133.1.1.7      PrincipalId**

**Type:** CSOM Int32

**Accessibility:** Read Only

Specifies an identifier for the **principal**. It MUST be -1 if the principal does not belong to the current **site (2)**.

### **3.2.5.133.1.1.8      PrincipalType**

**Type:** Microsoft.SharePoint.Client.Utilities.PrincipalType

**Accessibility:** Read Only

Specifies the type of **principal**.

It MUST NOT be a combination of more than one **member** of the **PrincipalType** enumeration. It MUST NOT be PrincipalType.All.

### **3.2.5.133.1.1.9      SIPAddress**

**Type:** CSOM String

**Accessibility:** Read Only

Specifies the **Session Initiation Protocol (SIP)** address of the **principal**.

### **3.2.5.133.1.2ObjectPath Properties**

None.

### **3.2.5.134 Microsoft.SharePoint.Client.Utilities.PrincipalSource**

**ShortName:** SP.Utilities.PrincipalSource

**Flag:** true

Specifies the source of a principal.

#### **3.2.5.134.1 Field Values**

##### **3.2.5.134.1.1None**

**Value:** 0

Do not specify a principal source.

##### **3.2.5.134.1.2UserInfoList**

**Value:** 1

Use the user information list as the source.

##### **3.2.5.134.1.3Windows**

**Value:** 2

Use Windows as the source.

##### **3.2.5.134.1.4MembershipProvider**

**Value:** 4

Use the current membership provider as the source.

##### **3.2.5.134.1.5RoleProvider**

**Value:** 8

Use the current role provider as the source

##### **3.2.5.134.1.6All**

**Value:** 15

Use all principal sources.

### **3.2.5.135 Microsoft.SharePoint.Client.Utilities.PrincipalType**

**ShortName:** SP.Utilities.PrincipalType

**Flag:** true

Specifies the type of a principal.

### **3.2.5.135.1 Field Values**

#### **3.2.5.135.1.1 None**

**Value:** 0

Do not specify a principal type.

#### **3.2.5.135.1.2 User**

**Value:** 1

A user principal type.

#### **3.2.5.135.1.3 DistributionList**

**Value:** 2

A distribution list principal type.

#### **3.2.5.135.1.4 SecurityGroup**

**Value:** 4

A security group principal type.

#### **3.2.5.135.1.5 SharePointGroup**

**Value:** 8

A SharePoint group principal type.

#### **3.2.5.135.1.6 All**

**Value:** 15

All principal types.

### **3.2.5.136 Microsoft.SharePoint.Client.Utilities.Utility**

**TypeId:** {16F43E7E-BF35-475D-B677-9DC61E549339}

**ShortName:** SP.Utilities.Utility

Provides tools for converting date and time formats, for obtaining information from user names, for modifying access to **sites (2)**, and for various other **tasks** in managing deployment. All methods in SP.Utilities.Utility are static.

#### **3.2.5.136.1 Properties**

##### **3.2.5.136.1.1 Scalar Properties**

None.

##### **3.2.5.136.1.2 ObjectPath Properties**

None.

## 3.2.5.136.2 Methods

### 3.2.5.136.2.1 Scalar Methods

#### 3.2.5.136.2.1.1 CreateEmailBodyForInvitation

This method is a **static CSOM method**.

**Return Type:** CSOM String

Creates the contents of the e-mail message used to invite users to a **document** or resource in a **site (2)**.

**Parameters:**

*pageAddress*: Specifies part of the **display name** for the document or resource.

Type: CSOM String

#### 3.2.5.136.2.1.2 FormatDateTime

This method is a **static CSOM method**.

**Return Type:** CSOM String

Returns a string representation of a **DateTime** value based on the **regional settings** of the **site (2)** and **current user**.

**Parameters:**

*web*: Specifies the site (2) to be used when formatting the value.

Type: Microsoft.SharePoint.Client.Web

*datetime*: Specifies the value to be formatted.

Type: **CSOM DateTime**

*format*: Specifies the date and time format of the result.

Type: Microsoft.SharePoint.Client.Utilities.DateTimeFormat

#### 3.2.5.136.2.1.3 GetCurrentUserEmailAddresses

This method is a **static CSOM method**.

**Return Type:** CSOM String

Returns the email addresses of the current user. If more than one email address exists for the current user, returns a list of email addresses separated by semicolons.

**Parameters:** None

#### 3.2.5.136.2.1.4 ResolvePrincipal

This method is a **static CSOM method**.

**Return Type:** Microsoft.SharePoint.Client.Utilities.PrincipalInfo

Returns information about a **principal** that matches the specified search criteria. If no matches are found, the protocol server MUST return NULL.

**Parameters:**

*web:* Specifies the **site (2)** to be used when searching for a principal.

Type: Microsoft.SharePoint.Client.Web

It MUST NOT be NULL.

*input:* Specifies the value to be used when searching for a principal.

Type: **CSOM String**

If this is not the **display name, e-mail address, or login name** of a principal, the server MUST return NULL.

Its length MUST be equal to or less than 255.

*scopes:* Specifies the type to be used when searching for a principal.

Type: Microsoft.SharePoint.Client.Utilities.PrincipalType

*sources:* Specifies the source to be used when searching for a principal.

Type: Microsoft.SharePoint.Client.Utilities.PrincipalSource

*usersContainer:* Specifies the collection of users to be used when searching for a principal.

Type: Microsoft.SharePoint.Client.UserCollection

*inputIsEmailOnly:* Specifies whether only the e-mail address is used when searching for a principal.

Type: **CSOM Boolean**

**Exceptions:**

Error Code	Error Type Name	Condition
-2147024891	System.UnauthorizedAccessException	The <b>current user</b> has insufficient permissions.

**3.2.5.136.2.1.5 SearchPrincipals**

This method is a **static CSOM method**.

**Return Type:** **CSOM array** of Microsoft.SharePoint.Client.Utilities.PrincipalInfo

Returns the collection of **principals** that partially or uniquely match the specified search criteria.

**Parameters:**

*web:* Specifies the **site (2)** to be used when searching for a principal.

Type: Microsoft.SharePoint.Client.Web

It MUST NOT be NULL.

*input*: Specifies the value to be used when searching for a principal.

Type: **CSOM String**

If this is not the **display name**, **e-mail address**, or **login name** of a principal, the server MUST return an empty collection.

It MUST NOT be NULL. Its length MUST be equal to or less than 255.

*scopes*: Specifies the type to be used when searching for a principal.

Type: Microsoft.SharePoint.Client.Utilities.PrincipalType

*sources*: Specifies the source to be used when searching for a principal.

Type: Microsoft.SharePoint.Client.Utilities.PrincipalSource

*usersContainer*: Specifies the collection of users to be used when searching for a principal.

Type: Microsoft.SharePoint.Client.UserCollection

*maxCount*: Specifies the maximum number of principals to be returned in the **list**.

Type: **CSOM Int32**

If the value is equal to or less than 0, the server MUST return an empty collection.

### **3.2.5.136.2.1.6      GetPeoplePickerURL**

This method is a **static CSOM method**.

**Return Type:** **CSOM String**

Returns a **server-relative URL** to a Web page used to search for **principals**.<108>

#### **Parameters:**

*web*: Specifies the **site (2)** to be used when searching for principals.

Type: Microsoft.SharePoint.Client.Web

It MUST NOT be NULL.

*fieldUser*: Specifies the **field (2)** to be used to set query parameters when searching for principals

Type: Microsoft.SharePoint.Client.FieldUser

It MUST NOT be NULL.

### **3.2.5.136.2.1.7      ResolvePrincipalInCurrentContext**

This method is a **static CSOM method**.

**Return Type:** Microsoft.SharePoint.Client.Utilities.PrincipalInfo

Returns information about a **principal** that matches the specified search criteria in the context of the current **Web site**.<109>

#### **Parameters:**

*input*: Specifies the value to be used when searching for a principal.

Type: **CSOM String**

If this is not the **display name**, **e-mail address**, or **login name** of a principal, the server MUST return NULL.

Its length MUST be equal to or less than 255.

*scopes*: Specifies the type to be used when searching for a principal.

Type: Microsoft.SharePoint.Client.Utilities.PrincipalType

*sources*: Specifies the source to be used when searching for a principal.

Type: Microsoft.SharePoint.Client.Utilities.PrincipalSource

*inputIsEmailOnly*: Specifies whether only the e-mail address is used when searching for a principal.

Type: **CSOM Boolean**

*addToUserInfoList*: Specifies whether to add the principal to the **user information list**.

Type: CSOM Boolean

*matchUserInfoList*: Specifies whether to return the principal found in the user information list.

Type: CSOM Boolean

**Exceptions:**

Error Code	Error Type Name	Condition
-2147024891	System.UnauthorizedAccessException	The <b>current user</b> has insufficient permissions.

**3.2.5.136.2.1.8 MarkDiscussionAsFeatured**

This method is a **static CSOM method**.

**Return Type:** None

Marks the specified **discussion items** as featured discussion items. <110>

**Exceptions:**

Error Code	Error Type Name	Condition
-2147467261	System.ArgumentNullException	The value passed for any of the required arguments is NULL.
-2147024891	System.UnauthorizedAccessException	The <b>current user</b> has insufficient permissions to mark the discussion items as featured discussion items.
-1	Microsoft.SharePoint.SPException	The security validation of the page failed.
-1	Microsoft.SharePoint.SPException	Any of the discussion items specified by the parameter <i>topicIDs</i> is invalid.



**Parameters:**

*listID*: Identifies the **discussion board** which contains the discussion items to be marked as featured discussion items.

Type: **CSOM String**

*topicIDs*: Identifies the discussion items to be marked as featured discussion items.

Type: CSOM String

The string MUST be formed by concatenating the identifiers for the discussion items using the comma character ",".

**3.2.5.136.2.1.9 UnmarkDiscussionAsFeatured**

This method is a **static CSOM method**.

**Return Type:** None

Unmarks the specified **discussion items** as featured discussion items. <111>

**Exceptions:**

Error Code	Error Type Name	Condition
-2147467261	System.ArgumentNullException	The value passed for any of the required arguments is NULL.
-2147024891	System.UnauthorizedAccessException	The <b>current user</b> has insufficient permissions to unmark the discussion items as featured discussion items.
-1	Microsoft.SharePoint.SPException	The security validation of the page failed.
-1	Microsoft.SharePoint.SPException	Any of the discussion items specified by the parameter <i>topicIDs</i> is invalid.

**Parameters:**

*listID*: Identifies the **discussion board** which contains the discussion items to be unmarked as featured discussion items.

Type: **CSOM String**

*topicIDs*: Identifies the discussion items to be marked as featured discussion items.

Type: CSOM String

The string MUST be formed by concatenating the identifiers for the discussion items using the comma character ",".

**3.2.5.136.2.1.10 SendEmail**

This method is a **static CSOM method**.

**Return Type:** None

Sends the e-mail message to the specified address. <112>

**Parameters:**

*properties*: The set of properties that define the email to send.

Type: Microsoft.SharePoint.Client.Utilities.EmailProperties

### 3.2.5.136.2.1.11 LogCustomAppError

This method is a **static CSOM method**.

**Return Type:** Microsoft.SharePoint.Client.Utilities.LogAppErrorResult

Logs an error from a **SharePoint Add-in**.[<113>](#) The return value indicates the success or failure of this operation.

These errors are of interest to administrators who monitor such **apps (2)**.

#### Parameters:

*error*: Error string to log.

Type: **CSOM String**

It MUST NOT be NULL. It MUST NOT be empty.

#### Exceptions:

Error Code	Error Type Name	Condition
- 2147024809	System.ArgumentException	The <i>error</i> parameter is NULL or empty.
- 2147024891	System.UnauthorizedAccessException	The <b>Web site</b> in the current request context does not represent a site for the SharePoint Add-in which matches the SharePoint Add-in identity in the current request.

### 3.2.5.136.2.1.12 GetAppLicenseInformation

This method is a **static CSOM method**.

**Return Type:** Microsoft.SharePoint.Client.AppLicenseCollection

Gets the collection of the **marketplace licenses** entitling the user to use the specified **SharePoint Add-in** within the **site subscription** including the current **site (2)**.[<114>](#)

The **Web site** in the current request context MUST represent a site (2) for the SharePoint Add-in that is identified by the *productId* parameter or the identity in the current request MUST match the identity of the SharePoint Add-in that is identified by the *productId* parameter.

#### Parameters:

*productId*: **App product identifier** of the specified SharePoint Add-in.

Type: **CSOM GUID**

### 3.2.5.136.2.1.13 IsUserLicensedForEntityInContext

This method is a **static CSOM method**.

**Return Type:** **CSOM Boolean**

Specifies whether the currently logged-in user has the appropriate license to access the specified entity. <115>

If "true", the user has the proper license to access the specified entity; otherwise, "false".

**Parameters:**

*licensableEntity*: The name of the entity to check the user's license for. The format of the string is an implementation detail of the protocol server.

Type: **CSOM String**

### 3.2.5.136.2.1.14 GetAppLicenseDeploymentId

This method is a **static CSOM method**.

**Return Type: CSOM GUID**

Returns the **marketplace deployment identifier** associated with **site subscription** of the **site (2)**. If there is no marketplace deployment identifier associated with the site subscription of the site (2), it randomly generates one and associates it with the site subscription of the site (2). <116> This method MUST be called by a **site collection administrator** of the **site collection** including the current site (2).

**Parameters:** None

### 3.2.5.136.2.1.15 ImportAppLicense

This method is a **static CSOM method**.

**Return Type:** None

Imports the given **marketplace license**, along with the associated **SharePoint Add-in** information, to the **site subscription** associated with the **site (2)**. <117> This method MUST be called by a **site collection administrator** of the **site collection** including the current site (2).

**Parameters:**

*licenseTokenToImport*: The **marketplace license token** associated with the marketplace license.

Type: **CSOM String**

If the marketplace license is a test license, this token could be missing the **marketplace deployment identifier**. Otherwise, the token MUST have a marketplace deployment identifier matching the marketplace deployment identifier associated with the site subscription of the site (2). If the marketplace license is not a test license, then this token MUST be verified by the marketplace for authenticity for the method to import the marketplace license.

This MUST NOT be NULL. This MUST NOT be empty string.

*contentMarket*: The **marketplace content market** of the marketplace license to be imported.

Type: CSOM String

It MUST NOT be NULL. It MUST NOT be empty string. The format of the string MUST be as described in [\[RFC4646\]](#) section 2.1.

*billingMarket*: The **marketplace billing market** of the marketplace license to be imported.

Type: CSOM String

It MUST NOT be NULL. It MUST NOT be empty string. The string MUST take one of the values defined in [\[ISO-3166\]](#).

*appName*: The title of the SharePoint Add-in.

Type: CSOM String

It MUST NOT be NULL. It MUST NOT be empty string.

*iconUrl*: The location of the icon image of the SharePoint Add-in.

Type: CSOM String

If it is not NULL, it MUST be a URL of absolute form.

*providerName*: The name of the publisher of the SharePoint Add-in.

Type: CSOM String

It MUST NOT be NULL. It MUST NOT be empty string.

*appSubtype*: The subtype of the SharePoint Add-in.

Type: **CSOM Int32**

### **3.2.5.136.2.1.16 SearchPrincipalsUsingContextWeb**

This method is a **static CSOM method**.

**Return Type:** **CSOM array** of Microsoft.SharePoint.Client.Utilities.PrincipalInfo

Returns the collection of **principals** that partially or uniquely matches the specified search criteria in the context of the current **Web site**.[<118>](#)

#### **Parameters:**

*input*: Specifies the value to be used when searching for a principal.

Type: **CSOM String**

If this is not the **display name**, **e-mail address**, or **login name** of a principal, the server MUST return an empty collection.

It MUST NOT be NULL. Its length MUST be equal to or less than 255.

*scopes*: Specifies the type to be used when searching for a principal.

Type: Microsoft.SharePoint.Client.Utilities.PrincipalType

*sources*: Specifies the source to be used when searching for a principal.

Type: Microsoft.SharePoint.Client.Utilities.PrincipalSource

*groupName*: Specifies the name of a **site collection group** in the **site collection** that contains the current Web site. The collection of users in this site collection group is used when searching for a principal.

Type: CSOM String

*maxCount*: Specifies the maximum number of principals to be returned.

Type: **CSOM Int32**

If the value is equal to or less than 0, the server MUST return an empty collection.

### 3.2.5.136.2.1.17 GetLocalizedString

This method is a **static CSOM method**.

#### Return Type: CSOM String

Retrieves the value for a named resource string from the resource file for a specified language. If a value cannot be found in the requested language, the value for the invariant language is returned. If a resource file for the invariant language does not exist or the specified resource name does not exist, the source string is returned without localization.

#### Parameters:

*source*: Specifies the resource in the form `$Resources:key`, where `key` is the name half of a name/value pair in a resource file.

Type: CSOM String

*defaultResourceFile*: Specifies the base file name of the language resource file containing a localized string value. For example, if there are a series of resource files named `myresources.en-us.resx`, `myresources.es-es.resx`, `myresources.de-de.resx`, and so on, the value to pass in this parameter is `myresources`.

Type: CSOM String

*language*: Specifies the LCID of the target language. The value MUST be a valid **language code identifier (LCID)**.

Type: **CSOM Int32**

### 3.2.5.136.2.1.18 GetLowerCaseString

This method is a **static CSOM method**.

#### Return Type: CSOM String

Gets the lower case value of a CSOM String using the supplied locale.

#### Parameters:

*sourceValue*: Value to convert to lower case.

Type: CSOM String

*lcid*: Locale ID to be used when converting to lower case.

Type: **CSOM Int32**

### 3.2.5.136.2.1.19 LogCustomRemoteAppError

This method is a **static CSOM method**.

**Return Type:** Microsoft.SharePoint.Client.Utilities.LogAppErrorResult

Logs an error from a **SharePoint Add-in**.<119> The return value indicates the success or failure of this operation.

These errors are of interest to administrators who monitor such **apps (2)**.

**Parameters:**

*productId*: The **app product identifier** of the **application**.

Type: **CSOM GUID**

It MUST NOT be an empty GUID.

*error*: Error string to log.

Type: **CSOM String**

It MUST NOT be NULL. It MUST NOT be empty.

**Exceptions:**

Error Code	Error Type Name	Condition
- 2147024809	System.ArgumentException	Thrown when the <i>error</i> parameter is null or empty or the <i>productId</i> parameter is empty.
- 2147024891	System.UnauthorizedAccessException	Thrown if there is no valid SharePoint Add-in context.

**3.2.5.136.2.1.20 ExpandGroupsToPrincipals**

This method is a **static CSOM method**.

**Return Type:** **CSOM array** of Microsoft.SharePoint.Client.Utilities.PrincipalInfo

Expands **groups** to a collection of **principals**.

**Parameters:**

*inputs*: A collection of groups to be expanded.

Type: CSOM array of **CSOM String**

*maxCount*: Specifies the maximum number of principals to be returned.

Type: **CSOM Int32**

**3.2.5.136.2.1.21 GetUserPermissionLevels**

This method is a **static CSOM method**.

**Return Type:** **CSOM array** of **CSOM String**

Retrieves a collection of permission levels of the current user on the web.

**Parameters:** None

**3.2.5.136.2.1.22 IsEmailServerSet**

This method is a **static CSOM method**.

**Return Type:** **CSOM Boolean**

Returns a Boolean value that specifies whether an e-mail server has been set for the site.

**Parameters:**

*web*: A Microsoft.SharePoint.SPWeb object that represents the site.

Type: Microsoft.SharePoint.Client.Web

### 3.2.5.136.2.2 ObjectPath Methods

#### 3.2.5.136.2.2.1 CreateNewDiscussion

This method is a **static CSOM method**.

**Return Type:** Microsoft.SharePoint.Client.ListItem

Creates a new top-level **discussion item** for a **discussion board** and returns the corresponding **list item**.

**Parameters:**

*list*: Specifies the discussion board that contains the new discussion item.

Type: Microsoft.SharePoint.Client.List

*title*: Specifies the value of the **Title field (2)** of the new discussion item.

Type: **CSOM String**

#### 3.2.5.136.2.2.2 CreateNewDiscussionReply

This method is a **static CSOM method**.

**Return Type:** Microsoft.SharePoint.Client.ListItem

Creates a new **discussion item** representing a reply to an existing discussion item in a **discussion board** and returns the corresponding **list item** as specified by **ListItem** (section [3.2.5.87](#)).

**Parameters:**

*parent*: Specifies the parent discussion item of the new discussion item.

Type: Microsoft.SharePoint.Client.ListItem

#### 3.2.5.136.2.2.3 CreateNewDiscussionItem

This method is a **static CSOM method**.

**Return Type:** Microsoft.SharePoint.Client.ListItem

Takes a **ListItem** (section [3.2.5.87](#)) that is created in a **discussion board** and sets **fields (2)** and other internal states in such a way that when the **Update** method is called on the **list item**, a **discussion item** that properly contains replies is created. [<120>](#)

**Parameters:**

*listId*: The list item identifier.

Type: **CSOM GUID**

*title*: The value to put in the **Title** field (2) of the item. This value is also used for the name of the created **folder**.

Type: **CSOM String**

### 3.2.5.136.2.2.4 CreateWikiPageInContextWeb

This method is a **static CSOM method**.

**Return Type:** Microsoft.SharePoint.Client.File

Creates a wiki page. [<121>](#)

**Parameters:**

*parameters:* The information used to create the wiki page.

Type: Microsoft.SharePoint.Client.Utilities.WikiPageCreationInformation

It MUST NOT be NULL.

### 3.2.5.136.2.2.5 LocalizeWebPartGallery

This method is a **static CSOM method**.

**Return Type:** **CSOM array** of Microsoft.SharePoint.Client.ListItem

Localizes **fields (2)** in a **Web Part gallery** for the specified collection of **list items**.

**Parameters:**

*items:* A collection of list items for a Web Part gallery.

Type: Microsoft.SharePoint.Client.ListItemCollection

It MUST NOT be NULL.

### 3.2.5.137 Microsoft.SharePoint.Client.View

**TypeId:** {2399F45D-1784-4965-9A5F-A3415790A0D0}

**ShortName:** SP.View

Specifies a **list view**.

The PageRenderType property is not included in the **default scalar property set** for this type.

#### 3.2.5.137.1 Properties

##### 3.2.5.137.1.1 Scalar Properties

###### 3.2.5.137.1.1.1 Aggregations

Type: **CSOM String**

**Accessibility:** Read/Write

Specifies **fields (2)** and functions that define totals shown in a **list view**.

It MUST be NULL or an **XML fragment** that conforms to the following **XML schema**:

```
<xs:sequence><xs:element name="FieldRef" type="FieldRefDefinitionAggregation" minOccurs="0" maxOccurs="unbounded" /></xs:sequence>
```



where **FieldRefDefinitionAggregation** is specified in [\[MS-WSSCAML\]](#) section 2.3.2.2.

#### **3.2.5.137.1.1.2 AggregationsStatus**

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies whether totals are shown in the **list view**.

It MUST be NULL If *Aggregations* is NULL; otherwise it MUST be "On" or "Off".

#### **3.2.5.137.1.1.3 BaseViewId**

**Type:** CSOM String

**Accessibility:** Read Only

Specifies the **base view identifier** of the **list view**.

It MUST be an integer encoded as a string. Its value MUST be equal to or greater than 0. Its value MUST be equal to or less than 255.

#### **3.2.5.137.1.1.4 ContentTypeId**

**Type:** Microsoft.SharePoint.Client.ContentTypeId

**Accessibility:** Read/Write

Specifies the identifier of the **content type** with which the **view** is associated.

#### **3.2.5.137.1.1.5 DefaultView**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Specifies whether the **list view** is the **default list view**.

#### **3.2.5.137.1.1.6 DefaultViewForContentType**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Specifies whether the **list view** is the **default list view** for the **content type** specified by *ContentTypeId*.

#### **3.2.5.137.1.1.7 EditorModified**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Specifies whether the **list view** was modified in an editor.

#### **3.2.5.137.1.1.8 Formats**

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies the column and row formatting for the **list view**.

It MUST be NULL or an **XML fragment** that conforms to **ViewFormatDefinitions** as specified in [\[MS-WSSCAML\]](#) section 2.3.2.21.

### **3.2.5.137.1.1.9 Hidden**

**Type:** **CSOM Boolean**

**Accessibility:** Read/Write

Specifies whether the **list view** is **hidden**.

### **3.2.5.137.1.1.10 HtmlSchemaXml**

**Type:** **CSOM String**

**Accessibility:** Read Only

Specifies the **XML document** that represents the **list view**.

It MUST NOT be NULL. It MUST be exactly one **XML fragment** conforming to **ViewDefinitions** as specified in [\[MS-WSSCAML\]](#) section 2.3.2.16.

### **3.2.5.137.1.1.11 Id**

**Type:** **CSOM GUID**

**Accessibility:** Read Only

Specifies the **view identifier** of the **list view**.

It MUST NOT be an empty GUID.

### **3.2.5.137.1.1.12 ImageUrl**

**Type:** **CSOM String**

**Accessibility:** Read Only

Specifies the **URL** of the image for the **list view**.

It MUST be a **server-relative URL** or an **absolute URL**.

### **3.2.5.137.1.1.13 IncludeRootFolder**

**Type:** **CSOM Boolean**

**Accessibility:** Read/Write

Specifies whether the current **folder** is displayed in the **list view**.

### **3.2.5.137.1.1.14 Method**

**Type:** **CSOM String**

**Accessibility:** Read/Write

Specifies the view method for the **list view**.

It MUST be NULL or an **XML document** where the **root element** is a valid Method **XML fragment** as specified in [\[MS-WSSCAP\]](#) section 2.2.5.2.

#### **3.2.5.137.1.1.15 MobileDefaultView**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Specifies whether the **list view** is the **default mobile list view**.

#### **3.2.5.137.1.1.16 MobileView**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Specifies whether the **list view** is a **mobile list view**.

#### **3.2.5.137.1.1.17 ModerationType**

**Type:** CSOM String

**Accessibility:** Read Only

Specifies the content approval type for the **list view**.

It MUST be one of the following: NULL, "", "Moderator", "Contributor", or "HideUnapproved".

#### **3.2.5.137.1.1.18 OrderedView**

**Type:** CSOM Boolean

**Accessibility:** Read Only

Specifies whether **list items** can be reordered in the **list view**.

#### **3.2.5.137.1.1.19 Paged**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Specifies whether the **list view** is a **paged view**.

#### **3.2.5.137.1.1.20 PersonalView**

**Type:** CSOM Boolean

**Accessibility:** Read Only

Specifies whether the **list view** is a **personal view**. If the value is "false", the **list** view is a **public view**.

#### **3.2.5.137.1.1.21 ReadOnlyView**

**Type:** CSOM Boolean

**Accessibility:** Read Only

Specifies whether the **list view** is read-only.

#### **3.2.5.137.1.1.22 RequiresClientIntegration**

**Type:** CSOM Boolean

**Accessibility:** Read Only

Specifies whether the **list view** requires client integration **rights**.

#### **3.2.5.137.1.1.23 RowLimit**

**Type:** CSOM UInt32

**Accessibility:** Read/Write

Specifies the maximum number of **list items** to display in a visual page of the **list view**.

Its value MUST be equal to or less than 2147483647.

#### **3.2.5.137.1.1.24 Scope**

**Type:** Microsoft.SharePoint.Client.ViewScope

**Accessibility:** Read/Write

Specifies the scope for the **list view**.

#### **3.2.5.137.1.1.25 ServerRelativeUrl**

**Type:** CSOM String

**Accessibility:** Read Only

Specifies the **server-relative URL** of the **list view page**.

It MUST NOT be NULL. It MUST NOT be empty. It MUST be a URL of server-relative form.

#### **3.2.5.137.1.1.26 StyleId**

**Type:** CSOM String

**Accessibility:** Read Only

Specifies the identifier of the **view style** for the **list view**.

It MUST be NULL or conform to **VisualStyleReference** as specified in [\[MS-WSSCAML\]](#) section 2.3.2.20.

#### **3.2.5.137.1.1.27 Threaded**

**Type:** CSOM Boolean

**Accessibility:** Read Only

Specifies whether the **list view** is a threaded view.

#### **3.2.5.137.1.1.28 Title**

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies the **display name** of the **list view**.

It MUST NOT be NULL. Its length MUST be equal to or less than 255.

### 3.2.5.137.1.1.29 **Toolbar**

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies the **toolbar** for the **list view**.

It MUST be NULL or conform to the following **XML schema**:

```
<xs:complexType><xs:sequence><xs:any minOccurs="0" maxOccurs="unbounded"
namespace="##any" processContents="skip"/></xs:sequence><xs:anyAttribute
processContents="skip"/></xs:complexType>
```

### 3.2.5.137.1.1.30 **ToolbarTemplateName**

**Type:** CSOM String

**Accessibility:** Read Only

Specifies the name of the template for the **toolbar** that is used in the **list view**, specified in [\[MS-WSSCAML\]](#) section 2.3.2.17.2.

### 3.2.5.137.1.1.31 **ViewData**

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies a **reference** to the **field (2)** that is used to render the Calendar View or Gantt view. If the view is a Calendar View or Gantt View, this section MUST be specified. For other view types, it MUST be ignored.

It MUST be NULL or an **XML fragment** that conforms to the following **XML schema**:

```
<xs:sequence><xs:element name="FieldRef" type="FieldRefDefinitionViewData"
minOccurs="3" maxOccurs="5"/></xs:sequence>
```

where **FieldRefDefinitionViewData** is specified in [\[MS-WSSCAML\]](#) section 2.3.2.18.

### 3.2.5.137.1.1.32 **ViewJoins**

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies the joins that are used in the **list view**.

It MUST be NULL or an XML fragment that conforms to **ListJoinsDefinition** as specified in [\[MS-WSSCAML\]](#) section 2.2.2.21.

### 3.2.5.137.1.1.33 **ViewProjectedFields**

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies the **dependent lookup field** to be used by the **list view**.

It MUST be NULL or an **XML fragment** that conforms to **ProjectedFieldsDefinition** as specified in [\[MS-WSSCAML\]](#) section 2.2.2.19.

### **3.2.5.137.1.1.34 ViewQuery**

**Type:** **CSOM String**

**Accessibility:** Read/Write

Specifies the **query** that is used by the **list view**.

It MUST be NULL or a valid **XML fragment** that conforms to **CamlQueryRoot** as specified in [\[MS-WSSCAML\]](#) section 2.2.2.1.

### **3.2.5.137.1.1.35 ViewType**

**Type:** **CSOM String**

**Accessibility:** Read Only

Specifies the type of the **list view**.

It MUST be one of the following: "HTML", "GRID", "CALENDAR", "RECURRENCE", "CHART", or "GANTT".

### **3.2.5.137.1.1.36 ListViewXml**

**Type:** **CSOM String**

**Accessibility:** Read/Write

Specifies the **View** (section [3.2.5.137](#)) **XML** that conforms to the **ViewDefinition** type as defined in [\[MS-WSSCAML\]](#) section 2.3.2.17. <122>

### **3.2.5.137.1.1.37 JSLink**

**Type:** **CSOM String**

**Accessibility:** Read/Write

Gets the name of an external ECMAScript ([\[ECMA-262-1999\]](#)) file containing any logic for this **list view**.

### **3.2.5.137.1.1.38 ColumnWidth**

**Type:** **CSOM String**

**Accessibility:** Read/Write

Specifies the width of columns.

### **3.2.5.137.1.1.39 CustomFormatter**

**Type:** **CSOM String**

**Accessibility:** Read/Write

Specifies the Custom Formatter used for the view.

#### **3.2.5.137.1.1.40 PageRenderType**

**Type:** Microsoft.SharePoint.Client.ListPageRenderType

**Accessibility:** Read Only

Specifies the render type of the current file.

#### **3.2.5.137.1.1.41 ServerRelativePath**

**Type:** Microsoft.SharePoint.Client.ResourcePath

**Accessibility:** Read Only

Specifies the server relative path of the list view page.

It MUST NOT be NULL.

#### **3.2.5.137.1.1.42 TabularView**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Specifies whether to include bulk selection checkboxes in a list view.

#### **3.2.5.137.1.1.43 VisualizationInfo**

**Type:** Microsoft.SharePoint.Client.Visualization

**Accessibility:** Read/Write

Specifies how the view is layed out.

### **3.2.5.137.1.2 ObjectPath Properties**

#### **3.2.5.137.1.2.1 ViewFields**

**Type:** Microsoft.SharePoint.Client.ViewFieldCollection

**Accessibility:** Read Only

Specifies the collection of **fields (2)** in the **list view**.

It MUST NOT be NULL.

### **3.2.5.137.2 Methods**

#### **3.2.5.137.2.1 Scalar Methods**

##### **3.2.5.137.2.1.1 DeleteObject**

**Return Type:** None

Deletes the **list view**.

**Parameters:** None

**Exceptions:**

Error Code	Error Type Name	Condition
-2130575320	Microsoft.SharePoint.SPException	List view does not exist.

**3.2.5.137.2.1.2 RenderAsHtml****Return Type:** CSOM StringReturns the **list view** as **HTML**. It MUST be HTML.**Parameters:** None**3.2.5.137.2.1.3 SetViewXml****Return Type:** None

Sets the view schema.

**Parameters:***viewXml*: The view XML to set.

Type: CSOM String

If this parameter is not XML-compliant, an exception is thrown, and the settings do not take effect.

**3.2.5.137.2.1.4 Update****Return Type:** NoneCommits changed properties of the **list view**.**Parameters:** None**Exceptions:**

Error Code	Error Type Name	Condition
-1	System.InvalidOperationException	List view does not exist.

**3.2.5.137.2.2 ObjectPath Methods****3.2.5.137.2.2.1 AddToSpotlight****Return Type:** Microsoft.SharePoint.Client.Utilities.SpotlightResultAdds the item indicated by **itemId** to the spotlight of the folder indicated by **folderPath** for this view, after the item indicated by **afterItemId**. If the item to be added is already in the spotlight, it will be removed and added again. If **afterItemId** is negative or not in the spotlight, the item is added to the front of the spotlight.**Parameters:**



*itemId*: The id of the item to add.

Type: **CSOM Int32**

*folderPath*: The web-relative path of the folder to add the item to.

Type: **CSOM String**

*afterItemId*: The item added to the spotlight will be added after this item.

Type: CSOM Int32

### **3.2.5.137.2.2.2 RemoveFromSpotlight**

**Return Type:** Microsoft.SharePoint.Client.Utilities.SpotlightResult

Removes the item indicated by **itemId** from the spotlight of the folder indicated by **folderPath** for this view.

#### **Parameters:**

*itemId*: The id of the item to remove.

Type: **CSOM Int32**

*folderPath*: The web-relative path of the folder to remove the item from.

Type: **CSOM String**

### **3.2.5.138 Microsoft.SharePoint.Client.ViewCollection**

**TypeId:** {03C5D7A9-9541-4482-9919-CA0CCCF565A0}

**ShortName:** SP.ViewCollection

Specifies a collection of **list views**.

#### **3.2.5.138.1 Properties**

##### **3.2.5.138.1.1 Scalar Properties**

None.

##### **3.2.5.138.1.2 ObjectPath Properties**

None.

#### **3.2.5.138.2 Methods**

##### **3.2.5.138.2.1 Scalar Methods**

None.

##### **3.2.5.138.2.2 ObjectPath Methods**

###### **3.2.5.138.2.2.1 Add**

**Return Type:** Microsoft.SharePoint.Client.View

Adds a new **list view** to the collection.

**Parameters:**

*parameters*: Specifies the new list view.

Type: Microsoft.SharePoint.Client.ViewCreationInformation

It MUST NOT be NULL.

**Exceptions:**

Error Code	Error Type Name	Condition
-1	System.InvalidOperationException	Type of the new list view is not allowed for the <b>list</b> .

**3.2.5.138.2.2.2 GetById**

**Return Type:** Microsoft.SharePoint.Client.View

Returns the view with the specified **view identifier**.

**Parameters:**

*guidId*: The view identifier of the view to return.

Type: **CSOM GUID**

**3.2.5.138.2.2.3 GetByTitle**

**Return Type:** Microsoft.SharePoint.Client.View

Returns the **list view** with the specified title. If there is more than one list view with the specified title, the server MUST return one list view as determined by the server.

**Parameters:**

*strTitle*: The title of the view to return.

Type: **CSOM String**

It MUST NOT be NULL.

**3.2.5.139 Microsoft.SharePoint.Client.ViewCreationInformation**

**TypeId:** {A3547807-7266-42F3-B055-AFA6E840E458}

**ShortName:** SP.ViewCreationInformation

Specifies the properties used to create a new **list view**.

**3.2.5.139.1 Properties**

**3.2.5.139.1.1 Scalar Properties**

**3.2.5.139.1.1.1 baseViewId**

**Type:** CSOM Int32

**Accessibility:** Read/Write

Specifies the baseviewID of the view.

### 3.2.5.139.1.1.2 Paged

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Specifies whether the new **list view** is a **paged view**.

### 3.2.5.139.1.1.3 PersonalView

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Specifies whether the new **list view** is a **personal view**. If the value is "false", the new list view is a **public view**.

### 3.2.5.139.1.1.4 Query

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies the **query** for the new **list view**.

It MUST be NULL or a valid **XML fragment** that conforms to **CamlQueryRoot** as specified in [\[MS-WSSCAML\]](#) section 2.2.2.1.

### 3.2.5.139.1.1.5 RowLimit

**Type:** CSOM UInt32

**Accessibility:** Read/Write

Specifies the maximum number of **list items** that the new **list view** displays on a visual page of the list view.

Its value MUST be equal to or less than 2147483647.

### 3.2.5.139.1.1.6 SetAsDefaultView

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Specifies whether the new **list view** is the **default list view**.

### 3.2.5.139.1.1.7 Title

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies the **display name** of the new **list view**.

Its length MUST be equal to or less than 255.

### 3.2.5.139.1.1.8 ViewFields

**Type:** CSOM array of CSOM String

**Accessibility:** Read/Write

Specifies the collection of **field internal names** for the **list fields (2)** in the new **list view**.

### 3.2.5.139.1.1.9 ViewTypeKind

**Type:** Microsoft.SharePoint.Client.ViewType

**Accessibility:** Read/Write

Specifies the type of the new **list view**.

### 3.2.5.139.1.2 ObjectPath Properties

None.

## 3.2.5.140 Microsoft.SharePoint.Client.ViewFieldCollection

**TypeId:** {AF975F76-8A94-4E6D-8325-BD1E20B7C301}

**ShortName:** SP.ViewFieldCollection

Specifies the collection of **fields (2)** in a **list view**.

### 3.2.5.140.1 Properties

#### 3.2.5.140.1.1 Scalar Properties

##### 3.2.5.140.1.1.1 SchemaXml

**Type:** CSOM String

**Accessibility:** Read Only

Specifies the **XML schema** that represents the collection.

It MUST NOT be NULL. It MUST be an **XML fragment** that conforms to the following XML schema:

```
<xs:sequence><xs:element name="FieldRef" type="FieldRefDefinitionView" minOccurs="0"
maxOccurs="unbounded" /></xs:sequence>
```

**FieldRefDefinitionView** is specified in [\[MS-WSSCAML\]](#) section 2.3.2.19.

#### 3.2.5.140.1.2 ObjectPath Properties

None.

### 3.2.5.140.2 Methods

#### 3.2.5.140.2.1 Scalar Methods

##### 3.2.5.140.2.1.1 Add

**Return Type:** None

Adds the **field (2)** with the specified **field internal name** or **display name** to the collection.

**Parameters:**

*strField*: Specifies the field internal name or the display name.

Type: **CSOM String**

It MUST NOT be NULL.

### 3.2.5.140.2.1.2 MoveFieldTo

**Return Type:** None

Moves the **field (2)** with the specified **field internal name** to the specified position in the collection.

**Parameters:**

*field*: Specifies the field internal name.

Type: **CSOM String**

It MUST NOT be NULL.

*index*: Specifies the position for the field (2). The first position is 0.

Type: **CSOM Int32**

Its value MUST be equal to or greater than 0.

**Exceptions:**

Error Code	Error Type Name	Condition
-2146232832	Microsoft.SharePoint.SPException	Field (2) does not exist in the collection.

### 3.2.5.140.2.1.3 Remove

**Return Type:** None

Removes the **field (2)** with the specified **field internal name** from the collection.

**Parameters:**

*strField*: Specifies the field internal name.

Type: **CSOM String**

It MUST NOT be NULL.

### 3.2.5.140.2.1.4 RemoveAll

**Return Type:** None

Removes all the **fields (2)** from the collection.

**Parameters:** None

### 3.2.5.140.2.1.5 AddViewField

**Return Type:** None

Adds the **field (2)** with the specified **field internal name** or display name to the collection. [<123>](#)

**Parameters:**

*strField*: Specifies the field internal name or display name.

Type: **CSOM String**

It MUST NOT be NULL.

### 3.2.5.140.2.1.6 MoveViewFieldTo

**Return Type:** None

Moves the **field (2)** with the specified **field internal name** to the specified position in the collection. [<124>](#)

**Parameters:**

*field*: Specifies the field internal name.

Type: **CSOM String**

It MUST NOT be NULL.

*index*: Specifies the new position for the field (2). The first position is 0.

Type: **CSOM Int32**

Its value MUST be equal to or greater than 0.

### 3.2.5.140.2.1.7 RemoveAllViewFields

**Return Type:** None

Removes all the **fields (2)** from the collection. [<125>](#)

**Parameters:** None

### 3.2.5.140.2.1.8 RemoveViewField

**Return Type:** None

Removes the **field (2)** with the specified **field internal name** or display name from the collection. [<126>](#)

**Parameters:**

*strField*: Specifies the field internal name or display name.

Type: **CSOM String**

It MUST NOT be NULL.

**Exceptions:**

Error Code	Error Type Name	Condition
-2146232832	Microsoft.SharePoint.SPException	Field (2) does not exist in the collection.

### 3.2.5.140.2.2ObjectPath Methods

None.

### 3.2.5.141 Microsoft.SharePoint.Client.ViewScope

**ShortName:** SP.ViewScope

**Flag:** false

Specifies the scope for returning **list items** and **list folders** in a **list view**.

#### 3.2.5.141.1 Field Values

##### 3.2.5.141.1.1DefaultValue

**Value:** 0

Specifies that all **list items** and all **list folders** in the current list folder are returned in the **list view**.

##### 3.2.5.141.1.2Recursive

**Value:** 1

Specifies that all **list items** in the **list** are returned in the **list view**.

##### 3.2.5.141.1.3RecursiveAll

**Value:** 2

Specifies that all **list items** and all **list folders** in the **list** are returned in the **list view**.

##### 3.2.5.141.1.4FilesOnly

**Value:** 3

Specifies that all **list items** in the current **list folder** are returned in the **list view**.

### 3.2.5.142 Microsoft.SharePoint.Client.ViewType

**ShortName:** SP.ViewType

**Flag:** false

Specifies the type of the **list view**.

#### 3.2.5.142.1 Field Values

##### 3.2.5.142.1.1None

**Value:** 0

The type of the **list view** is not specified.

### 3.2.5.142.1.2Html

**Value:** 1

Specifies an **HTML list view** type.

### 3.2.5.142.1.3Grid

**Value:** 2048

Specifies a **datasheet list view** type.

### 3.2.5.142.1.4Calendar

**Value:** 524288

Specifies a calendar **list view** type.

### 3.2.5.142.1.5Recurrence

**Value:** 8193

Specifies a **list view** type that displays recurring events.

### 3.2.5.142.1.6Chart

**Value:** 131072

Specifies a chart **list view** type.

### 3.2.5.142.1.7Gantt

**Value:** 67108864

Specifies a Gantt chart **list view** type.

## 3.2.5.143 Microsoft.SharePoint.Client.Web

**TypeId:** {A489ADD2-5D3A-4DE8-9445-49259462DCEB}

**ShortName:** SP.Web

Specifies a **site (2)**.

The AllowAutomaticASPXPageIndexing, AllowCreateDeclarativeWorkflowForCurrentUser, AllowDesignerForCurrentUser, AllowMasterPageEditingForCurrentUser, AllowRevertFromTemplateForCurrentUser, AllowSaveDeclarativeWorkflowAsTemplateForCurrentUser, AllowSavePublishDeclarativeWorkflowForCurrentUser, CommentsOnSitePagesDisabled, ContainsConfidentialInfo, DesignerDownloadUrlForCurrentUser, EffectiveBasePermissions, ExcludeFromOfflineClient, HasUniqueRoleAssignments, MembersCanShare, NotificationsInOneDriveForBusinessEnabled, NotificationsInSharePointEnabled, PreviewFeaturesEnabled, RequestAccessEmail, SaveSiteAsTemplateEnabled, ServerRelativePath, ShowUrlStructureForCurrentUser, SiteLogoDescription, SupportedUILanguageIds, ThemeData, ThemedCssFolderUrl and ThirdPartyMdmEnabled properties are not included in the **default scalar property set** for this type.

### 3.2.5.143.1 Properties



### 3.2.5.143.1.1 Scalar Properties

#### 3.2.5.143.1.1.1 AllowDesignerForCurrentUser

Type: **CSOM Boolean**

Accessibility: Read Only

Specifies whether the **current user** is allowed to use a designer application to customize this **site (2)**.

#### 3.2.5.143.1.1.2 AllowMasterPageEditingForCurrentUser

Type: **CSOM Boolean**

Accessibility: Read Only

Specifies whether the **current user** is allowed to edit the **master page**.

#### 3.2.5.143.1.1.3 AllowRevertFromTemplateForCurrentUser

Type: **CSOM Boolean**

Accessibility: Read Only

Specifies whether the **current user** is allowed to revert the **site (2)** to a default **site template**.

#### 3.2.5.143.1.1.4 AllowRssFeeds

Type: **CSOM Boolean**

Accessibility: Read Only

Specifies whether the **site (2)** allows RSS feeds.

#### 3.2.5.143.1.1.5 Created

Type: **CSOM DateTime**

Accessibility: Read Only

Specifies when the **site (2)** was created.

It MUST NOT be NULL.

#### 3.2.5.143.1.1.6 Description

Type: **CSOM String**

Accessibility: Read/Write

Specifies the description for the **site (2)**.

#### 3.2.5.143.1.1.7 EffectiveBasePermissions

**Type:** Microsoft.SharePoint.Client.BasePermissions

**Accessibility:** Read Only

Specifies the effective **permissions** that are assigned to the **current user**.

It MUST NOT be NULL.

### **3.2.5.143.1.1.8 HasUniqueRoleAssignments**

**Type:** CSOM Boolean

**Accessibility:** Read Only

See Microsoft.SharePoint.Client.SecurableObject.HasUniqueRoleAssignments (section 3.2.5.100.1.1.1).

### **3.2.5.143.1.1.9 Id**

**Type:** CSOM GUID

**Accessibility:** Read Only

Specifies the **site identifier** for the **site (2)**.

### **3.2.5.143.1.1.10 Language**

**Type:** CSOM UInt32

**Accessibility:** Read Only

Specifies the **language code identifier (LCID)** for the language that is used on the **site (2)**.

### **3.2.5.143.1.1.11 LastItemModifiedDate**

**Type:** CSOM DateTime

**Accessibility:** Read Only

Specifies when an **item** was last modified in the **site (2)**.

### **3.2.5.143.1.1.12 QuickLaunchEnabled**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Specifies whether the **Quick Launch** area is enabled on the **site (2)**.

### **3.2.5.143.1.1.13 RecycleBinEnabled**

**Type:** CSOM Boolean

**Accessibility:** Read Only

Specifies whether the **Recycle Bin** is enabled.

#### **3.2.5.143.1.1.14 ServerRelativeUrl**

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies the **server-relative URL** of the **site (2)**.

It MUST NOT be NULL. It MUST NOT contain any of the reserved **Uniform Resource Locators (URLs)**. Reserved URLs are implementation-specific and not defined by this protocol. It MUST NOT contain the following illegal characters:

[!#\$%&' +: <>?\\{|}~]|(//)|(\\.\\.)|(/\_)|(/wpresources\$)|(/wpresources/)

#### **3.2.5.143.1.1.15 ShowUrlStructureForCurrentUser**

**Type:** CSOM Boolean

**Accessibility:** Read Only

Specifies whether the **current user** is able to view the file system structure of this **site (2)**.

#### **3.2.5.143.1.1.16 SyndicationEnabled**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Specifies whether the [\[RSS2.0\]](#) feeds are enabled on the **site (2)**.

#### **3.2.5.143.1.1.17 Title**

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies the title for the **site (2)**.

Its length MUST be equal to or less than 255.

#### **3.2.5.143.1.1.18 TreeViewEnabled**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Specifies whether the tree view is enabled on the **site (2)**.

#### **3.2.5.143.1.1.19 UIVersion**

**Type:** CSOM Int32

**Accessibility:** Read/Write

Specifies which version of the user interface (UI) the **site (2)** is using. This value MUST be a defined **SPValidUIVersion** value, as specified in the following table.

SPValidUIVersion	Description
3	Specifies that the site (2) is using the SharePoint 2007 user interface (UI).
4	Specifies that the site (2) is using the SharePoint 2010 user interface (UI).

### 3.2.5.143.1.1.20 UIVersionConfigurationEnabled

Type: **CSOM Boolean**

Accessibility: Read/Write

Specifies whether the settings UI for **visual upgrade** is shown or hidden.

### 3.2.5.143.1.1.21 EnableMinimalDownload

Type: **CSOM Boolean**

Accessibility: Read/Write

Specifies whether the site will use the minimal download strategy by default. [<127>](#)

The minimal download strategy will use a single .aspx file (start.aspx) for your pages, with the actual **URL** encoded in the text following the hash mark ('#'). When navigating from page to page, only the changes between two compatible pages will be downloaded. Fewer bytes will be downloaded and the page will appear more quickly.

### 3.2.5.143.1.1.22 Url

Type: **CSOM String**

Accessibility: Read Only

Specifies the **URL** of the **site (2)**. [<128>](#)

### 3.2.5.143.1.1.23 CustomMasterUrl

Type: **CSOM String**

Accessibility: Read/Write

Specifies the **URL** for a custom **master page** to apply to the **Web site**. [<129>](#)

### 3.2.5.143.1.1.24 MasterUrl

Type: **CSOM String**

Accessibility: Read/Write

Specifies the **URL** for a **master page** to apply to the **Web site**. [<130>](#)

### 3.2.5.143.1.1.25 AppInstanceId

Type: **CSOM GUID**

Accessibility: Read Only

Specifies the identifier of the **app instance** that this **site (2)** represents. If this site (2) does not represent an app instance, then this MUST specify an empty GUID.

### 3.2.5.143.1.1.26 DocumentLibraryCalloutOfficeWebAppPreviewersDisabled

Type: **CSOM Boolean**

Accessibility: Read Only

Specifies whether the **Office Add-in** previews are disabled for the context menus in a **document library**.

### 3.2.5.143.1.1.27 Configuration

Type: **CSOM Int16**

Accessibility: Read Only

Specifies the identifier (ID) of the **site definition** that was used to create the **site (2)**. If the site (2) was created with a custom **site template** this specifies the identifier (ID) of the site definition from which the custom site template is derived.

### 3.2.5.143.1.1.28 WebTemplate

Type: **CSOM String**

Accessibility: Read Only

Specifies the name of the **site definition** that was used to create the **site (2)**. If the site (2) was created with a custom **site template** this specifies the name of the site definition from which the custom site template is derived.

### 3.2.5.143.1.1.29 SaveSiteAsTemplateEnabled

Type: **CSOM Boolean**

Accessibility: Read/Write

Specifies if the **site (2)** can be saved as a **site template**.

A **feature** that creates content which is not compatible for a site template can set this value to false to stop users of this site (2) from generating an invalid site template.

A feature ought to never set this value to true when it is deactivated or at any other time since another feature might have created content that is not compatible in a site template.

Setting this value to false, if it was true, will result in a site template that is not supported.

### 3.2.5.143.1.1.30 SupportedUILanguageIds

Type: **CSOM array** of **CSOM Int32**

Accessibility: Read Only

Specifies the **language code identifiers (LCIDs)** of the languages that are enabled for the **site (2)**.

### 3.2.5.143.1.1.31 AllowCreateDeclarativeWorkflowForCurrentUser

Type: **CSOM Boolean**

Accessibility: Read Only

Specifies whether the **current user** is allowed to create declarative workflows. The value, if not disabled on the **Web application**, is the same as the scalar property of **Microsoft.SharePoint.Client.Site.AllowCreateDeclarativeWorkflow**.

### 3.2.5.143.1.1.32 AllowSaveDeclarativeWorkflowAsTemplateForCurrentUser

Type: **CSOM Boolean**

Accessibility: Read Only

Specifies whether the **current user** is allowed to save declarative workflows as a template. The value, if not disabled on the **Web application**, is the same as the scalar property of **Microsoft.SharePoint.Client.Site.AllowSaveDeclarativeWorkflowAsTemplate**.

### 3.2.5.143.1.1.33 AllowSavePublishDeclarativeWorkflowForCurrentUser

Type: **CSOM Boolean**

Accessibility: Read Only

Specifies whether the **current user** is allowed to save or publish declarative workflows. The value, if not disabled on the **Web application**, is the same as the scalar property of **Microsoft.SharePoint.Client.Site.AllowSavePublishDeclarativeWorkflow**.

### 3.2.5.143.1.1.34 DesignerDownloadUrlForCurrentUser

Type: **CSOM String**

Accessibility: Read Only

Specifies the URL where the **current user** can download a **designer**.

### 3.2.5.143.1.1.35 MembersCanShare

Type: **CSOM Boolean**

Accessibility: Read/Write

Specifies whether to enable site members to invite external users.

### 3.2.5.143.1.1.36 SiteLogoUrl

Type: **CSOM String**

Accessibility: Read/Write

Specifies the server-relative URL of the Web site logo.

### 3.2.5.143.1.1.37 AlternateCssUrl

Type: **CSOM String**

Accessibility: Read/Write

Gets or sets the URL for an alternate cascading style sheet (CSS) to use in the website.

A string that contains the URL for an alternate CSS file.

### **3.2.5.143.1.1.38 ContainsConfidentialInfo**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Gets a Boolean value that specifies whether the site contains highly confidential information.

If the tenant settings don't allow tagging sites as confidential, this property will return false.

### **3.2.5.143.1.1.39 CurrentChangeToken**

**Type:** Microsoft.SharePoint.Client.ChangeToken

**Accessibility:** Read Only

Gets the current change token that is implemented in a query against the change log through the **GetChanges** method.

An SP.ChangeToken object that represents the change token.

### **3.2.5.143.1.1.40 IsMultilingual**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Gets or sets whether Multilingual UI is turned on for this web or not.

### **3.2.5.143.1.1.41 OverwriteTranslationsOnChange**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Gets or sets whether changing the UserResource value in the UICulture of the web overwrites the values for AdditionalUICultures or not.

### **3.2.5.143.1.1.42 ThemeData**

**Type:** CSOM String

**Accessibility:** Read Only

A string of **JSON** representing a theme.

### **3.2.5.143.1.1.43 ThirdPartyMdmEnabled**

**Type:** CSOM Boolean

**Accessibility:** Read Only

Gets the value that indicates whether or not the tenant that uses third-party Mobile Device Management (MDM) have block access to the public OneDrive app, and direct users to their company version of the app.

#### **3.2.5.143.1.1.44 RequestAccessEmail**

**Type:** CSOM String

**Accessibility:** Read/Write

Gets or sets the e-mail address to which requests for access are sent.

#### **3.2.5.143.1.1.45 AllowAutomaticASPXPageIndexing**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Gets or sets a Boolean value that specifies whether the .aspx page within the Web site is indexed by the search engine.

#### **3.2.5.143.1.1.46 CommentsOnSitePagesDisabled**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Indicates whether comments on site pages are disabled or not.

#### **3.2.5.143.1.1.47 DesignPackageId**

**Type:** CSOM GUID

**Accessibility:** Read/Write

Gets or sets the ID of the Design Package used in this SP.Web.

A value of Guid.Empty will mean that the default Design Package will be used for this SP.Web. The default is determined by the SP.WebTemplate of this SP.Web.

#### **3.2.5.143.1.1.48 ExcludeFromOfflineClient**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Indicates whether the data from the website is to be downloaded to the client during offline synchronization. A value of "true" means yes.

#### **3.2.5.143.1.1.49 LastItemUserModifiedDate**

**Type:** CSOM DateTime

**Accessibility:** Read Only

Gets the date and time that an item was last modified in the site by a non-system update. A non-system update is a change to a list item that is visible to end users.

#### **3.2.5.143.1.1.50 NoCrawl**

**Type:** CSOM Boolean

**Accessibility:** Read/Write



Gets or sets a Boolean value that specifies whether searching is enabled for the Web site.

#### **3.2.5.143.1.1.51 NotificationsInOneDriveForBusinessEnabled**

**Type:** CSOM Boolean

**Accessibility:** Read Only

Returns if true if the tenant allowed to send push notifications in ODB.

#### **3.2.5.143.1.1.52 NotificationsInSharePointEnabled**

**Type:** CSOM Boolean

**Accessibility:** Read Only

Returns if true if the tenant allowed to send push notifications in SharePoint.

#### **3.2.5.143.1.1.53 PreviewFeaturesEnabled**

**Type:** CSOM Boolean

**Accessibility:** Read Only

Indicates whether the tenant administrator has chosen to disable the Preview Features.

Defaults to True: Preview Features are enabled.

#### **3.2.5.143.1.1.54 ResourcePath**

**Type:** Microsoft.SharePoint.Client.ResourcePath

**Accessibility:** Read Only

The full path pointing to the web. It can be "http://www.office.net:8080/foo/bar" or "http://www.office.net/foo/bar" It will not be "http://www.office.net:8080/site/web/dir1/dir2/a.aspx"

#### **3.2.5.143.1.1.55 ServerRelativePath**

**Type:** Microsoft.SharePoint.Client.ResourcePath

**Accessibility:** Read Only

Gets the server-relative path of the web site.

#### **3.2.5.143.1.1.56 SiteLogoDescription**

**Type:** CSOM String

**Accessibility:** Read/Write

Gets or sets the description of the Web site logo.

#### **3.2.5.143.1.1.57 ThemedCssFolderUrl**

**Type:** CSOM String

**Accessibility:** Read/Write

Returns the URL of the folder containing the themed CSS for the web, null if no theme is applied.

### 3.2.5.143.1.1.58 WelcomePage

**Type:** CSOM String

**Accessibility:** Read Only

Specifies the **URL** of the **Welcome page** for the **site (2)**.

### 3.2.5.143.1.2 ObjectPath Properties

#### 3.2.5.143.1.2.1 AllProperties

**Type:** Microsoft.SharePoint.Client.PropertyValues

**Accessibility:** Read Only

Specifies the collection of name/value pairs of all the **CSOM expando fields** for the **site (2)**.

It MUST NOT be NULL.

#### 3.2.5.143.1.2.2 AssociatedMemberGroup

**Type:** Microsoft.SharePoint.Client.Group

**Accessibility:** Read/Write

Specifies the default **site (2) group** that was created with contribute permissions at the time the site (2) was created.

#### 3.2.5.143.1.2.3 AssociatedOwnerGroup

**Type:** Microsoft.SharePoint.Client.Group

**Accessibility:** Read/Write

Specifies the default **site (2) group** that was created with full control permissions at the time the site (2) was created.

#### 3.2.5.143.1.2.4 AssociatedVisitorGroup

**Type:** Microsoft.SharePoint.Client.Group

**Accessibility:** Read/Write

Specifies the default **site (2) group** that was created with read permissions at the time the site (2) was created.

#### 3.2.5.143.1.2.5 AvailableContentTypes

**Type:** Microsoft.SharePoint.Client.ContentTypeCollection

**Accessibility:** Read Only

Specifies the collection of all **site content types** that apply to the current scope, including those of the current **site (2)**, as well as any **parent sites**.

It MUST NOT be NULL.

#### **3.2.5.143.1.2.6 AvailableFields**

**Type:** Microsoft.SharePoint.Client.FieldCollection

**Accessibility:** Read Only

Specifies the collection of all **fields (2)** available for the current scope, including those of the current **site (2)**, as well as any **parent sites**.

It MUST NOT be NULL.

#### **3.2.5.143.1.2.7 ContentTypes**

**Type:** Microsoft.SharePoint.Client.ContentTypeCollection

**Accessibility:** Read Only

Specifies the collection of **content types** for the **site (2)**.

It MUST NOT be NULL.

#### **3.2.5.143.1.2.8 CurrentUser**

**Type:** Microsoft.SharePoint.Client.User

**Accessibility:** Read Only

Specifies the **current user** of the **site (2)**.

It MUST NOT be NULL.

#### **3.2.5.143.1.2.9 Features**

**Type:** Microsoft.SharePoint.Client.FeatureCollection

**Accessibility:** Read Only

Specifies the collection of **features** that are currently activated in the **site (2)**.

It MUST NOT be NULL.

#### **3.2.5.143.1.2.10 Fields**

**Type:** Microsoft.SharePoint.Client.FieldCollection

**Accessibility:** Read Only

Specifies the collection of all the **fields (2)** in the **site (2)**.

It MUST NOT be NULL.

#### **3.2.5.143.1.2.11 Folders**

**Type:** Microsoft.SharePoint.Client.FolderCollection

**Accessibility:** Read Only

Specifies the collection of all first-level folders in the **site (2)**.

It MUST NOT be NULL.

#### **3.2.5.143.1.2.12 Lists**

**Type:** Microsoft.SharePoint.Client.ListCollection

**Accessibility:** Read Only

Specifies the collection of **lists** that are contained in the **site (2)** available to the **current user** based on the current user's **permissions**.

#### **3.2.5.143.1.2.13 ListTemplates**

**Type:** Microsoft.SharePoint.Client.ListTemplateCollection

**Accessibility:** Read Only

Specifies the collection of **list templates** available for creating **lists** on the **site (2)**.

#### **3.2.5.143.1.2.14 Navigation**

**Type:** Microsoft.SharePoint.Client.Navigation

**Accessibility:** Read Only

Specifies the navigation structure on the **site (2)**, including the **Quick Launch** area and the **link bar**.

#### **3.2.5.143.1.2.15 RoleAssignments**

**Type:** Microsoft.SharePoint.Client.RoleAssignmentCollection

**Accessibility:** Read Only

See Microsoft.SharePoint.Client.SecurableObject.RoleAssignments (section 3.2.5.100.1.2.1).

#### **3.2.5.143.1.2.16 RoleDefinitions**

**Type:** Microsoft.SharePoint.Client.RoleDefinitionCollection

**Accessibility:** Read Only

Specifies the collection of **role definitions** for the **site (2)**.

### **3.2.5.143.1.2.17 RootFolder**

**Type:** Microsoft.SharePoint.Client.Folder

**Accessibility:** Read Only

Specifies the **root folder** for the **site (2)**.

### **3.2.5.143.1.2.18 SiteGroups**

**Type:** Microsoft.SharePoint.Client.GroupCollection

**Accessibility:** Read Only

Specifies the collection of the **site collection groups** for the **site collection** that contains the **site (2)**.

### **3.2.5.143.1.2.19 SiteUserInfoList**

**Type:** Microsoft.SharePoint.Client.List

**Accessibility:** Read Only

Specifies the **user information list** for the **site collection** that contains the **site (2)**.

### **3.2.5.143.1.2.20 UserCustomActions**

**Type:** Microsoft.SharePoint.Client.UserCustomActionCollection

**Accessibility:** Read Only

Specifies the collection of **user custom actions** for the **site (2)**.

### **3.2.5.143.1.2.21 Webs**

**Type:** Microsoft.SharePoint.Client.WebCollection

**Accessibility:** Read Only

Specifies the collection of all child **sites (2)** for the site (2).

### **3.2.5.143.1.2.22 WorkflowAssociations**

**Type:** Microsoft.SharePoint.Client.Workflow.WorkflowAssociationCollection

**Accessibility:** Read Only

Specifies the collection of all **workflow associations** for the **site (2)**.

### **3.2.5.143.1.2.23 WorkflowTemplates**

**Type:** Microsoft.SharePoint.Client.Workflow.WorkflowTemplateCollection

**Accessibility:** Read Only

Specifies the collection of **workflow templates** associated with the **site (2)**.

### **3.2.5.143.1.2.24 FirstUniqueAncestorSecurableObject**

**Type:** Microsoft.SharePoint.Client.SecurableObject

**Accessibility:** Read Only

See **Microsoft.SharePoint.Client.SecurableObject.FirstUniqueAncestorSecurableObject**, as specified in section [3.2.5.118.1.2.2.<131>](#)

### **3.2.5.143.1.2.25 RecycleBin**

**Type:** Microsoft.SharePoint.Client.RecycleBinItemCollection

**Accessibility:** Read Only

Specifies the collection of **Recycle Bin items** of the **Recycle Bin** of the **site (2)**.<132>

### **3.2.5.143.1.2.26 WebInfos**

**Type:** Microsoft.SharePoint.Client.WebInformationCollection

**Accessibility:** Read Only

Specifies the collection of all child **sites (2)** for the site (2).<133>

### **3.2.5.143.1.2.27 ThemeInfo**

**Type:** Microsoft.SharePoint.Client.ThemeInfo

**Accessibility:** Read Only

Specifies the site **theme** associated with the **site (2)**.<134>

### **3.2.5.143.1.2.28 EventReceivers**

**Type:** Microsoft.SharePoint.Client.EventReceiverDefinitionCollection

**Accessibility:** Read Only

Specifies the collection of **event receiver** definitions that are currently available on the **Web site**.<135>

### **3.2.5.143.1.2.29 SiteUsers**

**Type:** Microsoft.SharePoint.Client.UserCollection

**Accessibility:** Read Only

Specifies the collection of users in the **site collection** that contains the **site (2)**.<136>

### **3.2.5.143.1.2.30 RegionalSettings**

**Type:** Microsoft.SharePoint.Client.RegionalSettings

**Accessibility:** Read Only

Specifies the locale settings of the **site (2)**.<137>

### **3.2.5.143.1.2.31 PushNotificationSubscribers**

**Type:** Microsoft.SharePoint.Client.PushNotificationSubscriberCollection

**Accessibility:** Read Only

Specifies the collection of push notification subscribers for the **site (2)**.<138>

It MUST NOT be NULL.

#### **3.2.5.143.1.2.32 ParentWeb**

**Type:** Microsoft.SharePoint.Client.WebInformation

**Accessibility:** Read Only

Specifies the **parent site** of the **site (2)**.<139>

#### **3.2.5.143.1.2.33 AppTiles**

**Type:** Microsoft.SharePoint.Client.AppTileCollection

**Accessibility:** Read Only

Gets the collection of all app tiles that are contained in this website. An SP.AppTileCollection that represents the information about the app tiles.

This contains an aggregation of four data sources:

1. DocLibs and Lists, directly from the web.
2. Tenant-provided apps that apply to this web.
3. Apps instantiated by the user in this web.
4. Features activated in this web, which behave like apps.

#### **3.2.5.143.1.2.34 DataLeakagePreventionStatusInfo**

**Type:** Microsoft.SharePoint.Client.SPDataLeakagePreventionStatusInfo

**Accessibility:** Read Only

Gets a collection of DLP status indicators including:

- Whether or not external sharing tips are enabled on the parent site collection.
- The learn more link URL for the external sharing tips.
- Whether or not the site contains highly confidential information.
- The learn more link URL for site confidentiality.

#### **3.2.5.143.1.2.35 DescriptionResource**

**Type:** Microsoft.SharePoint.Client.UserResource

**Accessibility:** Read Only

A SP.UserResource object that represents the description of this web.

#### **3.2.5.143.1.2.36 TitleResource**

**Type:** Microsoft.SharePoint.Client.UserResource

**Accessibility:** Read Only

A SP.UserResource object that represents the title of this web.

### **3.2.5.143.1.2.37 Alerts**

**Type:** Microsoft.SharePoint.Client.AlertCollection

**Accessibility:** Read Only

Gets the collection of alerts for the site or subsite.

### **3.2.5.143.1.2.38 Author**

**Type:** Microsoft.SharePoint.Client.User

**Accessibility:** Read Only

Gets a user object that represents the user who created the Web site.

### **3.2.5.143.1.2.39 BingMapsInformation**

**Type:** Microsoft.SharePoint.Client.SP BingMapsInformation

**Accessibility:** Read Only

Retrieves the Bing maps related configurations, for example, Bing maps key.

See the section [3.2.5.461](#) for the more details.

### **3.2.5.143.1.2.40 ClientWebParts**

**Type:** Microsoft.SharePoint.Client.ClientWebPartCollection

**Accessibility:** Read Only

Gets a collection of the ClientWebParts installed in this SP.Web. It can be used to get metadata of the ClientWebParts or render them. It is a read-only collection as ClientWebParts need to be installed in an app package.

### **3.2.5.143.1.2.41 SiteCollectionAppCatalog**

**Type:**

Microsoft.SharePoint.Marketplace.CorporateCuratedGallery.SiteCollectionCorporateCatalogAccessor

**Accessibility:** Read Only

Returns the site collection app catalog for the given web if it exists.

### **3.2.5.143.1.2.42 TenantAppCatalog**

**Type:** Microsoft.SharePoint.Marketplace.CorporateCuratedGallery.TenantCorporateCatalogAccessor

**Accessibility:** Read Only

Returns the tenant app catalog for the given tenant if it exists.

## **3.2.5.143.2 Methods**

### **3.2.5.143.2.1 Scalar Methods**



### 3.2.5.143.2.1.1 ApplyWebTemplate

**Return Type:** None

Applies the specified **site definition** or **site template** to the **site (2)** that has no template applied to it.

**Parameters:**

*webTemplate:* A string that contains the name of the site definition or the file name of the site template.

Type: **CSOM String**

### 3.2.5.143.2.1.2 BreakRoleInheritance

**Return Type:** None

See Microsoft.SharePoint.Client.SecurableObject.BreakRoleInheritance (section [3.2.5.118.2.1.1](#)).

**Parameters:**

*copyRoleAssignments:* Specifies whether to copy the **role assignments** from the **parent site**. If the value is "false", the collection of role assignments MUST contain only 1 role assignment containing the **current user**.

Type: **CSOM Boolean**

*clearSubscopes:* Specifies whether the role assignments for all **sites (2)** that inherit from this site (2) MUST be cleared. If the value is "true", all child sites (2) with the same security scope MUST also be cleared.

Type: CSOM Boolean

**Exceptions:**

Error Code	Error Type Name	Condition
-1	System.InvalidOperationException	There are uncommitted changes on the site (2).

### 3.2.5.143.2.1.3 DeleteObject

**Return Type:** None

Deletes this **site (2)**.

**Parameters:** None

### 3.2.5.143.2.1.4 DoesUserHavePermissions

**Return Type:** **CSOM Boolean**

Returns whether the **current user** has the given set of **permissions**.

**Parameters:**

*permissionMask:* Specifies the set of permissions to verify.

Type: Microsoft.SharePoint.Client.BasePermissions

It MUST NOT be NULL.

### 3.2.5.143.2.1.5 GetWebUrlFromPageUrl

This method is a **static CSOM method**.

**Return Type: CSOM String**

Returns the **URL** of the **root folder** for the **site (2)** containing the specified URL. This is a static method.

**Parameters:**

*pageFullUrl*: Specifies the URL from which to return the site (2) URL.

Type: CSOM String

It MUST be a URL of absolute form. It MUST start with "http://" or "https://"

**Exceptions:**

Error Code	Error Type Name	Condition
-2147024894	System.IO.FileNotFoundException	A site (2) cannot be found at the given URL.

### 3.2.5.143.2.1.6 MapToIcon

**Return Type: CSOM String**

Returns the name of the image file for the **icon** that is used to represent the specified **file**.

**Parameters:**

*fileName*: Specifies the name of the file that is used to determine the image file name.

Type: CSOM String

If a NULL or empty string is passed into this parameter, the protocol server MUST return an empty string.

*progId*: Specifies the **ProgID** of the application that was used to create the file.

Type: CSOM String

If the value of this parameter is NULL or an empty string, the protocol server MUST return the name of the image file based on the specified *fileName*. The server selects the image file based on the *fileName* in an implementation-specific manner.

*size*: Specifies the icon size.

Type: Microsoft.SharePoint.Client.Utilities.IconSize

### 3.2.5.143.2.1.7 ResetRoleInheritance

**Return Type: None**

See Microsoft.SharePoint.Client.SecurableObject.ResetRoleInheritance as specified in section [3.2.5.118.2.1.2](#).

**Parameters:** None

**Exceptions:**

Error Code	Error Type Name	Condition
-1	System.InvalidOperationException	There are uncommitted changes on the <b>site (2)</b> .

### 3.2.5.143.2.1.8 Update

**Return Type:** None

Commits changes made to properties of this **site (2)**.

**Parameters:** None

### 3.2.5.143.2.1.9 ProcessExternalNotification

**Return Type:** CSOM String

Processes notifications from external system. [<140>](#) Returns status of processing. Possible values are "Success" or "SubscriptionNotRequired". Result "Success" indicates successful processing. Result "SubscriptionNotRequired" indicates that the subscription is no longer required and external system can safely delete the subscription.

**Parameters:**

*stream*: Notification message from the external system.

Type: **CSOM Stream**

**Exceptions:**

Error Code	Error Type Name	Condition
-2147024891	System.UnauthorizedAccessException	Access is denied. User does not have permission to send notifications.

### 3.2.5.143.2.1.10 GetContextWebInformation

This method is a **static CSOM method**.

**Return Type:** Microsoft.SharePoint.Client.ContextWebInformation

Returns an **object (1)** that specifies metadata about the **site (2)**. [<141>](#)

**Parameters:** None

### 3.2.5.143.2.1.11 ExecuteRemoteLOB

**Return Type:** CSOM Stream

This method is used to enable message exchange between a server hosted on the internet and a server hosted on the inside of an intranet, where the protocol server acts as a relay. <142> The protocol server relays the call to the intranet server specified in the message header. The protocol does not prescribe how to handle other message headers, if any. The protocol does not prescribe any format for inputStream. The protocol does not prescribe if the inputStream is modified before sending to the server inside the intranet or how the return value from the intranet server is handled.

**Parameters:**

*inputStream*: This parameter specifies inputStream. The protocol does not prescribe any format for inputStream.

Type: CSOM Stream

**3.2.5.143.2.1.12 DoesPushNotificationSubscriberExist**

**Return Type: CSOM Boolean**

Specifies whether the push notification subscriber exists for the current user with the given device **app instance** identifier. <143>

**Parameters:**

*deviceAppInstanceId*: Device application instance identifier.

Type: **CSOM GUID**

**Exceptions:**

Error Code	Error Type Name	Condition
-2147467261	System.ArgumentNullException	<b>Null</b> value passed for any of the required arguments.
-2147024891	System.UnauthorizedAccessException	Caller does not have permissions for the <b>site (2)</b> .

**3.2.5.143.2.1.13 UnregisterPushNotificationSubscriber**

**Return Type:** None

Unregisters the push notification subscriber from the **site (2)**. <144>

**Parameters:**

*deviceAppInstanceId*: Device **app instance** identifier.

Type: **CSOM GUID**

**Exceptions:**

Error Code	Error Type Name	Condition
-2147467261	System.ArgumentNullException	<b>Null</b> value passed for any of the required arguments.
-2147024891	System.UnauthorizedAccessException	Caller does not have permissions for the site (2).

**3.2.5.143.2.1.14 ApplyTheme**

**Return Type:** None

Applies the **theme** specified by the contents of each of the **files** specified in the arguments to the **site (2)**.

**Parameters:**

*colorPaletteUrl*: The **server-relative URL** of the **color scheme** to apply to the site (2).

Type: **CSOM String**

It MUST NOT be NULL. It MUST NOT be empty. It MUST be a URL of server-relative form.

*fontSchemeUrl*: The server-relative URL of the **font scheme** to apply to the site (2) or NULL to preserve default **fonts**.

Type: CSOM String

It MUST be a URL of server-relative form.

*backgroundImageUrl*: The server-relative URL of the image to apply as the background image on the site (2) or NULL to use no background image.

Type: CSOM String

It MUST be a URL of server-relative form.

*shareGenerated*: true to store themed files at the **top-level site**, false to store them in the current site (2).

Type: **CSOM Boolean**

### **3.2.5.143.2.1.15 GetUserEffectivePermissions**

**Return Type:** Microsoft.SharePoint.Client.BasePermissions

Returns the user permissions for this **site (2)**.

**Parameters:**

*userName*: Specifies the user login name.

Type: **CSOM String**

It MUST NOT be NULL.

### **3.2.5.143.2.1.16 AddSupportedUILanguage**

**Return Type:** None

Adds a supported UI language by its language identifier.

**Parameters:**

*lcid*: Specifies the language identifier to be added.

Type: **CSOM Int32**

### **3.2.5.143.2.1.17 CreateAnonymousLink**

This method is a **static CSOM method**.

### Return Type: CSOM String

Creates and returns an anonymous link that can be used to access a document without needing to authenticate.

#### Parameters:

*url*: The URL of the site, with the path of the object in SharePoint that is represented as query string parameters, forSharing set to 1 if sharing, and mbypass set to 1 to bypass any mobile logic.

Type: CSOM String

For example:

```
http://contoso.com/?forSharing=1&mbypass=1&List=%7BCF908473%2D72D4%2D449D%2D8A53%2D4BD01EC54B84%7D&obj={CF908473-72D4-449D-8A53-4BD01EC54B84},1,DOCUMENT
```

*isEditLink*: If true, the link will allow the guest user edit privileges on the item.

Type: CSOM Boolean

### 3.2.5.143.2.1.18 CreateAnonymousLinkWithExpiration

This method is a **static CSOM method**.

### Return Type: CSOM String

Creates and returns an anonymous link that can be used to access a document without needing to authenticate.

#### Parameters:

*url*: The URL of the site, with the path of the object in SharePoint that is represented as query string parameters, forSharing set to 1 if sharing, and mbypass set to 1 to bypass any mobile logic.

Type: CSOM String

For example:

```
http://contoso.com/?forSharing=1&mbypass=1&List=%7BCF908473%2D72D4%2D449D%2D8A53%2D4BD01EC54B84%7D&obj={CF908473-72D4-449D-8A53-4BD01EC54B84},1,DOCUMENT
```

*isEditLink*: If true, the link will allow the guest user edit privileges on the item.

Type: CSOM Boolean

*expirationString*: A date/time string for which the format conforms to the ISO 8601:2004(E) complete representation for calendar date and time of day, and which represents the time and date of expiry for the anonymous link. Both the minutes and hour value MUST be specified for the difference between the local and UTC time. Midnight is represented as 00:00:00.

Type: CSOM String

For example:

YYYYMMDDThhmmssZ

YYYYMMDDThhmmss±hhmm

YYYYMMDDThhmmss±hh:mm

YYYY-MM-DDThh:mm:ssZ

YYYY-MM-DDThh:mm:ss±hh:mm

YYYY-MM-DDThh:mm:ss±hhmm

A null value indicates no expiry.

### 3.2.5.143.2.1.19 CreateOrganizationSharingLink

This method is a **static CSOM method**.

#### Return Type: CSOM String

Creates and returns an organization-internal link that can be used to access a document and gain permissions to it.

#### Parameters:

*url*: The URL of the site, with the path of the object in SharePoint that is represented as query string parameters, forSharing set to 1 if sharing, and mbypass set to 1 to bypass any mobile logic.

Type: CSOM String

For example:

```
http://contoso.com/?forSharing=1&mbypass=1&List=%7BCF908473%2D72D4%2D449D%2D8A53%2D4BD01EC54B84%7D&obj={CF908473-72D4-449D-8A53-4BD01EC54B84},1,DOCUMENT
```

*isEditLink*: If true, the link will allow the logged in user to edit privileges on the item.

Type: **CSOM Boolean**

### 3.2.5.143.2.1.20 DeleteAllAnonymousLinksForObject

This method is a **static CSOM method**.

#### Return Type: None

Removes all existing anonymous links for an object.

#### Parameters:

*url*: The URL of the object being shared, with the path of the object in SharePoint that is represented as query string parameters.

Type: **CSOM String**

For example:

```
http://contoso.com/?obj={CF908473-72D4-449D-8A53-4BD01EC54B84},1,DOCUMENT&List=%7BCF908473%2D72D4%2D449D%2D8A53%2D4BD01EC54B84%7D
```

### 3.2.5.143.2.1.21 DeleteAnonymousLinkForObject

This method is a **static CSOM method**.

#### Return Type: None

Removes an existing anonymous link for an object. [<145>](#)

#### Parameters:

*url*: The URL of the object being shared, with the path of the object in SharePoint that is represented as query string parameters.

Type: **CSOM String**

For example:

```
http://contoso.com/?obj={CF908473-72D4-449D-8A53-4BD01EC54B84},1,DOCUMENT&List=%7BCF908473%2D72D4%2D449D%2D8A53%2D4BD01EC54B84%7D
```

*isEditLink*: If true, the edit link for the object will be removed. If false, the view only link for the object will be removed.

Type: **CSOM Boolean**

*removeAssociatedSharingLinkGroup*: Indicates whether to remove the **groups** that contain the users who have been given access to the shared object via the sharing link<sup>1</sup>.

Type: CSOM Boolean

### 3.2.5.143.2.1.22 DestroyOrganizationSharingLink

This method is a **static CSOM method**.

**Return Type:** None

Removes an existing organization link for an object. [<146>](#)

**Parameters:**

*url*: The URL of the object being shared, with the path of the object in SharePoint that is represented as query string parameters.

Type: **CSOM String**

For example:

```
http://contoso.com/?obj={CF908473-72D4-449D-8A53-4BD01EC54B84},1,DOCUMENT&List=%7BCF908473%2D72D4%2D449D%2D8A53%2D4BD01EC54B84%7D
```

*isEditLink*: If true, the edit link for the object will be removed. If false, the view-only link for the object will be removed.

Type: **CSOM Boolean**

*removeAssociatedSharingLinkGroup*: Indicates whether to remove the **groups** that contain the users who have been given access to the shared object via the sharing link<sup>1</sup>.

Type: CSOM Boolean

### 3.2.5.143.2.1.23 GetContextWebThemeData

This method is a **static CSOM method**.

**Return Type:** **CSOM String**

Get ThemeData for the context web.

**Parameters:** None



### 3.2.5.143.2.1.24 GetDocumentLibraries

This method is a **static CSOM method**.

**Return Type:** **CSOM array** of Microsoft.SharePoint.Client.DocumentLibraryInformation

Returns the document libraries of a SharePoint site, specifically a list of objects that represents document library information. Document libraries that are private—picture library, catalog library, asset library, application list, form template or libraries—for whom the user does not have permission to view the items are not included.

#### Parameters:

*webFullUrl*: The URL of the web.

Type: **CSOM String**

It MUST be a URL of absolute form. It MUST start with "http://" or "https://"

#### Exceptions:

Error Code	Error Type Name	Condition
-2147024894	System.IO.FileNotFoundException	Web cannot be found in the given URL

### 3.2.5.143.2.1.25 IncrementSiteClientTag

**Return Type:** None

Increments the client cache control number for this **site collection**.

**Parameters:** None

### 3.2.5.143.2.1.26 RemoveSupportedUILanguage

**Return Type:** None

Removes a supported UI language by its language identifier.

#### Parameters:

*lcid*: Specifies the language identifier to be removed.

Type: **CSOM Int32**

### 3.2.5.143.2.1.27 GetClientSideWebParts

**Return Type:** **CSOM array** of Microsoft.SharePoint.ClientSideComponent.SPClientSideComponentQueryResult

It MUST return an array of 3<sup>rd</sup> party webpart components installed on this **site (2)**.

#### Parameters:

*includeErrors*: If true, webparts with errors MUST be included in the results of the request. If false, webparts with errors MUST be excluded in the results of the request.

Type: **CSOM Boolean**

### 3.2.5.143.2.1.28 CreateDefaultAssociatedGroups

**Return Type:** None

Creates the default Owners, Members and Visitors SPGroups on the web.

**Parameters:**

*userLogin:* The user logon name of the group owner.

Type: **CSOM String**

*userLogin2:* The secondary contact for the group.

Type: CSOM String

*groupNameSeed:* The name seed to use when creating of the full names of the default groups. For example, if the name seed is Contoso then the default groups will be created with the names: Contoso Owners, Contoso Members and Contoso Visitors. If the value of this parameter is null then the web title is used instead.

Type: CSOM String

### 3.2.5.143.2.1.29 DefaultDocumentLibraryUrl

This method is a **static CSOM method**.

**Return Type:** Microsoft.SharePoint.Client.DocumentLibraryInformation

Returns the default document library **URL**.

**Parameters:**

*webUrl:* URL of the web.

Type: **CSOM String**

### 3.2.5.143.2.1.30 GetClientSideComponents

**Return Type:** **CSOM array** of

Microsoft.SharePoint.ClientSideComponent.SPClientSideComponentQueryResult

Returns the client side components for the requested components. Client components include data necessary to render Client Side Web Parts and Client Side Applications.

**Parameters:**

*components:* Array of requested components, defined by id and version.

Type: CSOM array of Microsoft.SharePoint.ClientSideComponent.SPClientSideComponentIdentifier

### 3.2.5.143.2.1.31 GetClientSideComponentsById

**Return Type:** **CSOM array** of

Microsoft.SharePoint.ClientSideComponent.SPClientSideComponentQueryResult

Returns the client side components for the requested component identifiers. Client components include data necessary to render Client Side Web Parts and Client Side Applications.

**Parameters:**

*componentIds*: Array of requested component identifiers.

Type: CSOM array of **CSOM GUID**

### 3.2.5.143.2.1.32 **GetDocumentAndMediaLibraries**

This method is a **static CSOM method**.

**Return Type:** **CSOM array** of Microsoft.SharePoint.Client.DocumentLibraryInformation

Returns the document libraries of a SharePoint site, including picture, asset, and site assets libraries. Document libraries that are private, catalog library, application list, form template, or libraries that user does not have permission to view items are not included.

#### **Parameters:**

*webFullUrl*: **URL** of the web.

Type: **CSOM String**

It MUST be a URL of absolute form. It MUST start with "http://" or "https://"

*includePageLibraries*: Indicates whether to include page libraries. A value of "true" means yes.

Type: **CSOM Boolean**

#### **Exceptions:**

Error Code	Error Type Name	Condition
-2147024894	System.IO.FileNotFoundException	Web cannot be found in the given URL

### 3.2.5.143.2.1.33 **GetOnePageContextAsStream**

**Return Type:** **CSOM Stream**

Gets context information used to transition to a new page in the browser without making a full-page load.

**Parameters:** None

### 3.2.5.143.2.1.34 **GetRegionalDateTimeSchema**

**Return Type:** **CSOM String**

Get DateTime Schema based on regional settings

**Parameters:** None

### 3.2.5.143.2.1.35 **GetSharingLinkData**

**Return Type:** Microsoft.SharePoint.Client.SharingLinkData

This method determines basic information about the supplied link URL, including limited data about the object the link URL refers to and any additional sharing link data if the link URL is a **tokenized sharing link**

**Parameters:**

*linkUrl*: A URL that is either a tokenized sharing link or a **canonical URL** for a **document**

Type: **CSOM String**

It MUST NOT be NULL.

### **3.2.5.143.2.1.36    GetSharingLinkKind**

This method is a **static CSOM method**.

**Return Type:** Microsoft.SharePoint.Client.SharingLinkKind

This method determines the kind of **tokenized sharing link** represented by the supplied file URL.

#### **Parameters:**

*fileUrl*: A URL that is a tokenized sharing link for a **document**

Type: **CSOM String**

It MUST NOT be NULL.

### **3.2.5.143.2.1.37    ParseDateTime**

**Return Type:** **CSOM String**

Returns parsed DateTime value.

#### **Parameters:**

*value*: The input is the string of a datetime that's in web's local time and in web's calendar. For example, the input "09/08/1430" when web's calendar was set to Hijri, the actual datetime is 07/31/2009 in Gregorian calendar.

Type: CSOM String

*displayFormat*: Int value representing SP.DateTimeFieldFormatType

Type: **CSOM Int32**

*calendarType*: Int value representing SP.CalendarType

Type: CSOM Int32

### **3.2.5.143.2.1.38    RemoveStorageEntity**

**Return Type:** None

This will remove the storage entity identified by the given key

#### **Parameters:**

*key*: Id of the storage entity to be removed.

Type: **CSOM String**

### **3.2.5.143.2.1.39    SetStorageEntity**

**Return Type:** None

This will set the storage entity identified by the given key

**Parameters:**

*key*: Id of the storage entity to be set.

Type: **CSOM String**

*value*: Value of the storage entity to be set.

Type: CSOM String

*description*: Description of the storage entity to be set.

Type: CSOM String

*comments*: Comments of the storage entity to be set.

Type: CSOM String

### 3.2.5.143.2.2 ObjectPath Methods

#### 3.2.5.143.2.2.1 EnsureUser

**Return Type:** Microsoft.SharePoint.Client.User

If the specified login name belongs to a valid user of the **site (2)**, returns the User **object (1)** corresponding to that user.

If the specified login name belongs to a valid user outside of the site, adds the user to the site (2) and returns the User object (1) corresponding to that user.

**Parameters:**

*logonName*: Specifies a string that contains the login name.

Type: **CSOM String**

#### 3.2.5.143.2.2.2 GetAvailableWebTemplates

**Return Type:** Microsoft.SharePoint.Client.WebTemplateCollection

Returns a collection of **site templates** available for the **site (2)**.

**Parameters:**

*lcid*: Specifies the **LCID** of the site templates to be retrieved.

Type: **CSOM UInt32**

If the specified LCID is not a valid LCID as specified in [\[MS-LCID\]](#), the server MUST return an empty collection.

*doIncludeCrossLanguage*: Specifies whether to include language-neutral site templates.

Type: **CSOM Boolean**

#### 3.2.5.143.2.2.3 GetCatalog

**Return Type:** Microsoft.SharePoint.Client.List

Returns the **list template gallery**, **site template** gallery, or **Web Part** gallery for the **site (2)**.

**Parameters:**

*typeCatalog*: Specifies the type for the gallery

Type: **CSOM Int32**

The server MUST return NULL if there is no gallery with the specified type or *typeCatalog* is not a valid **ListTemplateType** enumeration value as specified in [\[MS-WSSTS\]](#) section 2.7.

### 3.2.5.143.2.2.4 GetChanges

**Return Type:** Microsoft.SharePoint.Client.ChangeCollection

Returns the collection of all changes from the **change log** that have occurred within the scope of the **site (2)**, based on the specified **query**.

**Parameters:**

*query*: Specifies which changes to return.

Type: Microsoft.SharePoint.Client.ChangeQuery

It MUST NOT be NULL.

### 3.2.5.143.2.2.5 GetFileByServerRelativeUrl

**Return Type:** Microsoft.SharePoint.Client.File

Returns the **file** located at the specified **server-relative URL**.

**Parameters:**

*serverRelativeUrl*: Specifies the server-relative URL for the file.

Type: **CSOM String**

It MUST NOT be NULL. It MUST NOT be empty.

### 3.2.5.143.2.2.6 GetFolderByServerRelativeUrl

**Return Type:** Microsoft.SharePoint.Client.Folder

Returns the **folder** that is located at the specified **URL**. The user MUST have **permission** to browse directories of the **site (2)** specified by the given URL.

**Parameters:**

*serverRelativeUrl*: Specifies the **server-relative URL** for the folder.

Type: **CSOM String**

It MUST NOT be NULL.

**Exceptions:**

Error Code	Error Type Name	Condition
-2147024894	System.IO.FileNotFoundException	<i>serverRelativeUrl</i> doesn't correspond to a folder

### 3.2.5.143.2.2.7 GetSubwebsForCurrentUser

**Return Type:** Microsoft.SharePoint.Client.WebCollection

Returns the collection of **child sites (2)** of the current site (2) based on the specified **query**.

**Parameters:**

*query*: Specifies which child sites (2) to return.

Type: Microsoft.SharePoint.Client.SubwebQuery

If the query is not valid as described in section [3.2.5.120](#), the server MUST return an empty collection.

### 3.2.5.143.2.2.8 GetEntity

**Return Type:** Microsoft.BusinessData.MetadataModel.Entity

Specifies the **external content type** with the specified namespace and name in the context of the current **site (2)**.[<147>](#) This method is used as the entry point to create, read, update and delete (CRUD) operations against an **Entity** (section [3.2.5.176](#)).

**Parameters:**

*namespace*: The namespace of the external content type

Type: **CSOM String**

*name*: The name of the external content type

Type: CSOM String

**Exceptions:**

Error Code	Error Type Name	Condition
-1	Microsoft.BusinessData.MetadataModel.MetadataObjectNotFoundException	Entity with the given parameters cannot be found
-2147467261	System.ArgumentNullException	At least one of the parameters is null

### 3.2.5.143.2.2.9 GetUserById

**Return Type:** Microsoft.SharePoint.Client.User

Returns the user corresponding to the specified member identifier for the current **site (2)**.[<148>](#)

**Parameters:**

*userId*: Specifies the member identifier.

Type: **CSOM Int32**

**Exceptions:**

Error Code	Error Type Name	Condition
-2146232832	Microsoft.SharePoint.SPException	User cannot be found.
-2147024891	System.UnauthorizedAccessException	Access is denied.

### 3.2.5.143.2.2.10 GetCustomListTemplates

**Return Type:** Microsoft.SharePoint.Client.ListTemplateCollection

Returns the collection of custom **list templates** for a given **site (2)**.<149>

**Parameters:** None

### 3.2.5.143.2.2.11 GetSubwebsFilteredForCurrentUser

**Return Type:** Microsoft.SharePoint.Client.WebInformationCollection

Returns a collection of objects that contain metadata about **subsites** of the current **site (2)** in which the **current user** is a member.<150>

**Parameters:**

*nWebTemplateFilter*: Specifies the **site definition**.

Type: **CSOM Int32**

*nConfigurationFilter*: A 16-bit integer that specifies the identifier of a configuration.

Type: **CSOM Int16**

### 3.2.5.143.2.2.12 GetAppBdcCatalog

**Return Type:** Microsoft.BusinessData.MetadataModel.AppBdcCatalog

Returns the **Business Data Connectivity (BDC) MetadataCatalog** for an **application** that gives access to the **external content types** defined in the BDC metadata model packaged by the application.<151> This method SHOULD be called on the **Web** (section 3.2.5.143) object that represents the site for the application and it returns the BDC MetadataCatalog deployed on the site.

**Parameters:** None

### 3.2.5.143.2.2.13 GetAppBdcCatalogForAppInstance

**Return Type:** Microsoft.BusinessData.MetadataModel.AppBdcCatalog

Returns the **Business Data Connectivity (BDC) MetadataCatalog** for an **application** that gives access to the **external content types** defined in the BDC metadata model packaged by the application.<152> This method SHOULD be called on the **Web** (section 3.2.5.143) object where the application is installed and it returns the BDC MetadataCatalog deployed on the site for the application.

**Parameters:**



*appInstanceId*: The identifier of the **app instance**.

Type: **CSOM GUID**

It MUST NOT be an empty GUID.

**Exceptions:**

Error Code	Error Type Name	Condition
-1	System.InvalidOperationException	Application with given identifier is not installed on the web or the application does not have a <b>Web application</b> .

### 3.2.5.143.2.2.14    **GetAppInstanceById**

**Return Type:** Microsoft.SharePoint.Client.AppInstance

Returns an **application** instance installed on this **site (2)**.<153>

**Parameters:**

*appInstanceId*: Application instance identifier.

Type: **CSOM GUID**

### 3.2.5.143.2.2.15    **LoadAndInstallApp**

**Return Type:** Microsoft.SharePoint.Client.AppInstance

Uploads and installs an **app package** to this **site (2)**.<154> This site (2) MUST be enabled for remote development. This method returns a reference to the app instance.

**Parameters:**

*appPackageStream*: The stream of the app package.

Type: **CSOM Stream**

### 3.2.5.143.2.2.16    **GetPushNotificationSubscriber**

**Return Type:** Microsoft.SharePoint.Client.PushNotificationSubscriber

Specifies the push notification subscriber over the site for the specified device **app instance** identifier.<155>

**Parameters:**

*deviceAppInstanceId*: Device application instance identifier.

Type: **CSOM GUID**

**Exceptions:**

Error Code	Error Type Name	Condition
-2147467261	System.ArgumentNullException	<b>Null</b> value passed for any of the required arguments.

Error Code	Error Type Name	Condition
-2147024891	System.UnauthorizedAccessException	Caller does not have permissions for the <b>site (2)</b> .

### 3.2.5.143.2.2.17 GetPushNotificationSubscribersByArgs

**Return Type:** Microsoft.SharePoint.Client.PushNotificationSubscriberCollection

Queries for the push notification subscribers for the **site (2)** with the specified set of custom arguments. [<156>](#)

The passed value is compared against the subscribers' custom arguments in the store and exact matches are returned as a collection. **Null** or empty custom arguments return subscribers without any filtering. If no match is found, an empty collection is returned.

**Parameters:**

*customArgs*: Custom arguments.

Type: **CSOM String**

**Exceptions:**

Error Code	Error Type Name	Condition
-2147024891	System.UnauthorizedAccessException	Caller does not have permissions for the site (2).

### 3.2.5.143.2.2.18 GetPushNotificationSubscribersByUser

**Return Type:** Microsoft.SharePoint.Client.PushNotificationSubscriberCollection

Queries for the push notification subscribers for the **site (2)** for the specified user. [<157>](#)

**Parameters:**

*userName*: Login name of the user.

Type: **CSOM String**

It MUST NOT be NULL. It MUST NOT be empty.

**Exceptions:**

Error Code	Error Type Name	Condition
-2147467261	System.ArgumentNullException	<b>Null</b> value passed for any of the required arguments.
-2147024891	System.UnauthorizedAccessException	Caller does not have permissions for the site (2).

### 3.2.5.143.2.2.19 RegisterPushNotificationSubscriber

**Return Type:** Microsoft.SharePoint.Client.PushNotificationSubscriber

Registers the push notification subscriber for the **site (2)**.<158> If the registration already exists, the service token is updated with the new value.

**Parameters:**

*deviceAppInstanceId*: Device **app instance** identifier.

Type: **CSOM GUID**

*serviceToken*: Token provided by the notification service to the device to receive notifications.

Type: **CSOM String**

It MUST NOT be NULL. It MUST NOT be empty.

**Exceptions:**

Error Code	Error Type Name	Condition
-2147467261	System.ArgumentNullException	<b>Null</b> value passed for any of the required arguments.
-2147024891	System.UnauthorizedAccessException	Caller does not have permissions for the site (2).

### 3.2.5.143.2.2.20 **GetAppInstancesByProductId**

**Return Type:** **CSOM array** of Microsoft.SharePoint.Client.AppInstance

Returns a collection of **app instances** installed on the **site (2)** for the specified **application** with the provided **app product identifier**.

**Parameters:**

*productId*: The app product identifier of the specified application.

Type: **CSOM GUID**

### 3.2.5.143.2.2.21 **LoadAndInstallAppInSpecifiedLocale**

**Return Type:** Microsoft.SharePoint.Client.AppInstance

Uploads and installs an **app package** on the **site (2)** in a specified **locale**.<159> The site (2) MUST be enabled for remote development. The specified locale MUST be supported by the app package. This method returns a reference to an **app instance**.

**Parameters:**

*appPackageStream*: The stream of app package.

Type: **CSOM Stream**

*installationLocaleLCID*: Specifies the locale in which the app package is to be installed.

Type: **CSOM Int32**

### 3.2.5.143.2.2.22 **LoadApp**

**Return Type:** Microsoft.SharePoint.Client.AppInstance

Uploads an **app package** and creates an **app instance** on a **site (2)**. The site (2) MUST be enabled for remote development. The app instance is initialized with a specified **locale** in which it will be installed later. The specified locale MUST be supported by the app package. This method returns a reference to an app instance.

**Parameters:**

*appPackageStream*: The stream of app package.

Type: **CSOM Stream**

*installationLocaleLCID*: Specifies the locale in which the app package is to be installed later.

Type: **CSOM Int32**

### **3.2.5.143.2.2.23 DefaultDocumentLibrary**

**Return Type:** Microsoft.SharePoint.Client.List

Retrieves the default **document library**.

**Parameters:** None

### **3.2.5.143.2.2.24 ForwardObjectLink**

This method is a **static CSOM method**.

**Return Type:** Microsoft.SharePoint.Client.SharingResult

Shares an object in SharePoint, such as a list item or a site with no Acl changes, by sending the link. This is used when the user has no permission to share and cannot send access request. The user can use this method to send the link of the object to site members who already have permission to view the object.

Returns a SharingResult object that contains completion script and page for redirection if desired.

**Parameters:**

*url*: The URL of the website with the path of an object in SharePoint query string parameters.

Type: **CSOM String**

*peoplePickerInput*: A string of JSON that represents users in the people picker format. Entries in the people picker MUST be existing site members who have view-permission to the object.

Type: CSOM String

*emailSubject*: The e-mail subject.

Type: CSOM String

*emailBody*: The e-mail body.

Type: CSOM String

### **3.2.5.143.2.2.25 GetFileByGuestUrl**

**Return Type:** Microsoft.SharePoint.Client.File

Returns the file object from the guest access URL.

**Parameters:**

*guestUrl*: The guest access URL to get the file with.

Type: **CSOM String**

The query string parameters specify the file object identity.

To call this API using the REST endpoint, it is recommended to use a call of the form:

```
http://server/_api/web/GetFileByGuestUrl(@v)?@v='http%3A%2F%2Fserver%2F_layouts%2F15%2Fguestaccess%2Easpx%3fguestaccesstoken%3d<redacted>%26docid=18cd85dfb7a3847218a2ea37e1215a9b4'
```

where @v is both single quoted and run through the `UrlKeyValueEncode` method.

It MUST NOT be NULL.

**3.2.5.143.2.2.26 GetFileById**

**Return Type:** Microsoft.SharePoint.Client.File

Returns the file object with the specified GUID.

**Parameters:**

*uniqueId*: A GUID that identifies the file object.

Type: **CSOM GUID**

It MUST NOT be NULL.

**3.2.5.143.2.2.27 GetFileByLinkingUrl**

**Return Type:** Microsoft.SharePoint.Client.File

Returns the file object from the linking URL.

**Parameters:**

*linkingUrl*: The linking URL to return the file object for. A linking URL can be obtained from `LinkingUrl`.

Type: **CSOM String**

A linking URL might not point to the canonical URL specified in the input string due to a rename operation having occurred. The query string is what actually specifies the file object identity.

To call this API from the client object model, it is recommended to use a call of the form:

```
http://server/_api/web/GetFileByLinkingUrl(@v)?@v='%2FShared%20Documents%2fdoc.docx%3fd%3dw0aca4baf33bd48e0bcfd06f54682ff7a'
```

where @v is both single quoted and run through the `UrlKeyValueEncode` method.

It MUST NOT be NULL.

**3.2.5.143.2.2.28 GetFolderById**

**Return Type:** Microsoft.SharePoint.Client.Folder

Returns the folder object with the specified GUID.

**Parameters:**

*uniqueId*: A GUID that identifies the folder.

Type: **CSOM GUID**

It MUST NOT be NULL.

**3.2.5.143.2.2.29 GetList**

**Return Type:** Microsoft.SharePoint.Client.List

Returns the list that is associated with the specified site-relative URL.

**Parameters:**

*strUrl*: A string that contains the site-relative URL for a list, for example, /Lists/Announcements.

Type: **CSOM String**

**3.2.5.143.2.2.30 GetObjectSharingSettings**

This method is a **static CSOM method**.

**Return Type:** Microsoft.SharePoint.Client.ObjectSharingSettings

Given a path to an object in SharePoint, this will generate a sharing settings object which contains necessary information for rendering sharing information.

**Parameters:**

*objectUrl*: A URL with one of two possible formats.

Type: **CSOM String**

The two possible URL formats are:

1) The URL of the site, with the path of the object in SharePoint represented as query string parameters, forSharing set to 1 if sharing, and mbypass set to 1 to bypass any mobile logic e.g.  
<http://contoso.com/?forSharing=1&mbypass=1&List=%7BCF908473%2D72D4%2D449D%2D8A53%2D4BD01EC54B84%7D&obj={CF908473-72D4-449D-8A53-4BD01EC54B84},1,DOCUMENT>

2) The URL of the SharePoint object (web, list, item) intended for sharing e.g.  
<http://contoso.com/Documents/SampleFile.docx>

*groupId*: The id value of the permissions group if adding to a group, 0 otherwise.

Type: **CSOM Int32**

*useSimplifiedRoles*: A Boolean value indicating whether to use the SharePoint simplified roles (Edit, View) or not.

Type: **CSOM Boolean**

**3.2.5.143.2.2.31 ShareObject**

This method is a **static CSOM method**.

**Return Type:** Microsoft.SharePoint.Client.SharingResult

This method shares an object in SharePoint such as a list item or site. It returns a `SharingResult` object which contains the completion script and a page to redirect to if desired.

**Parameters:**

*url*: The URL of the website with the path of an object in SharePoint query string parameters.

Type: **CSOM String**

*peoplePickerInput*: A string of JSON representing users in people picker format.

Type: CSOM String

*roleValue*: The sharing role value for the type of permission to grant on the object.

Type: CSOM String

*groupId*: The ID of the group to be added. Zero if not adding to a permissions group.

Type: **CSOM Int32**

*propagateAcl*: A flag to determine if permissions SHOULD be pushed to items with unique permissions.

Type: **CSOM Boolean**

*sendEmail*: A flag to determine if an email notification SHOULD be sent (if email is configured).

Type: CSOM Boolean

*includeAnonymousLinkInEmail*: If an email is being sent, this determines if an anonymous link SHOULD be added to the message.

Type: CSOM Boolean

*emailSubject*: The email subject.

Type: CSOM String

*emailBody*: The email body.

Type: CSOM String

*useSimplifiedRoles*: A Boolean value indicating whether to use the SharePoint simplified roles (Edit, View) or not.

Type: CSOM Boolean

### **3.2.5.143.2.2.32 UnshareObject**

This method is a **static CSOM method**.

**Return Type:** `Microsoft.SharePoint.Client.SharingResult`

Removes Sharing permissions on an object.

**Parameters:**

*url*: A `SharingResult` object which contains status codes pertaining to the completion of the operation.

Type: **CSOM String**

### **3.2.5.143.2.2.33 GetRecycleBinItems**

**Return Type:** Microsoft.SharePoint.Client.RecycleBinItemCollection

Returns a collection of **Recycle Bin items** within this **site (2)**.

**Parameters:**

*pagingInfo*: A string describing paging information for the next page of Recycle Bin items.

Type: **CSOM String**

MUST be formatted as a **URL-encoded** form body as described in [\[HTML\]](#) section 17.13.4 - Form content types. MUST contain the following **key value pairs (KVP)**:

Key name	Description of value	Type of value
id	The <b>item identifier</b> of the Recycle Bin item to display first on the next page of Recycle Bin items.	<b>CSOM GUID</b>
title	The title of the Recycle Bin item to display first on the next page of Recycle Bin items.	CSOM String
searchValue	The value to search for in the <b>column</b> specified by the <i>orderBy</i> parameter.	CSOM String

*rowLimit*: The maximum number of Recycle Bin items to retrieve.

Type: **CSOM Int32**

*isAscending*: Specifies whether the Recycle Bin items are sorted in ascending order by the column specified in the *orderBy* parameter. A value of true indicates ascending order, and a value of false indicates descending order.

Type: **CSOM Boolean**

*orderBy*: The column to sort results by.

Type: Microsoft.SharePoint.Client.RecycleBinOrderBy

*itemState*: Specifies whether to retrieve items from the **first-stage Recycle Bin** or the **second-stage Recycle Bin**.

Type: Microsoft.SharePoint.Client.RecycleBinItemState

### 3.2.5.143.2.2.34 **GetFileByGuestUrlEnsureAccess**

**Return Type:** Microsoft.SharePoint.Client.File

Returns the file object from the **tokenized sharing link** URL.

**Parameters:**

*guestUrl*: The tokenized sharing link URL for the file.

Type: **CSOM String**

It MUST NOT be NULL.



*ensureAccess*: Indicates if the request to the tokenized sharing link grants perpetual access to the calling user.

Type: **CSOM Boolean**

If it is set to true then the user who is requesting the file will be granted perpetual permissions through the tokenized sharing link.

### **3.2.5.143.2.2.35 GetFileByGuestUrlExtended**

**Return Type:** Microsoft.SharePoint.Client.File

Returns the file object from the **tokenized sharing link** URL.

**Parameters:**

*guestUrl*: The tokenized sharing link URL for the file.

Type: **CSOM String**

It MUST NOT be NULL.

*requestSettings*: Extended parameters to the request.

Type: Microsoft.SharePoint.Client.Sharing.SharingLinkAccessRequest

See Microsoft.SharePoint.Client.Sharing.SharingLinkAccessRequest as specified in section [3.2.5.452](#)

### **3.2.5.143.2.2.36 GetFileByServerRelativePath**

**Return Type:** Microsoft.SharePoint.Client.File

Returns the file object located at the specified path.

**Parameters:**

*serverRelativePath*: Contains the server-relative path of the file.

Type: Microsoft.SharePoint.Client.ResourcePath

It MUST NOT be NULL.

### **3.2.5.143.2.2.37 GetFileByUrl**

**Return Type:** Microsoft.SharePoint.Client.File

Returns the file object from the given **URL**.

**Parameters:**

*fileUrl*: The URL used to get the file object.

Type: **CSOM String**

It MUST NOT be NULL.

### **3.2.5.143.2.2.38 GetFileByWOPIFrameUrl**

**Return Type:** Microsoft.SharePoint.Client.File

Returns the file object from the WOPI frame **URL**.

**Parameters:**

*wopiFrameUrl*: The WOPI frame URL used to get the file object.

Type: **CSOM String**

It MUST NOT be NULL.

**3.2.5.143.2.2.39 GetFolderByGuestUrl**

**Return Type:** Microsoft.SharePoint.Client.Folder

Returns the folder object from the **tokenized sharing link** URL.

**Parameters:**

*guestUrl*: The tokenized sharing link URL for the folder.

Type: **CSOM String**

It MUST NOT be NULL.

*ensureAccess*: Indicates if the request to the tokenized sharing link grants perpetual access to the calling user.

Type: **CSOM Boolean**

If it is set to true then the user who is requesting the folder will be granted perpetual permissions through the tokenized sharing link.

**3.2.5.143.2.2.40 GetFolderByGuestUrlExtended**

**Return Type:** Microsoft.SharePoint.Client.Folder

Returns the folder object from the **tokenized sharing link** URL.

**Parameters:**

*guestUrl*: The tokenized sharing link URL for the folder.

Type: **CSOM String**

It MUST NOT be NULL.

*requestSettings*: Extended parameters to the request.

Type: Microsoft.SharePoint.Client.Sharing.SharingLinkAccessRequest

See Microsoft.SharePoint.Client.Sharing.SharingLinkAccessRequest as specified in section [3.2.5.452](#)

**3.2.5.143.2.2.41 GetFolderByServerRelativePath**

**Return Type:** Microsoft.SharePoint.Client.Folder

Return the folder object that is located at the specified path.

**Parameters:**

*serverRelativePath*: Contains the **server-relative URL** for the folder.

Type: Microsoft.SharePoint.Client.ResourcePath

It MUST NOT be NULL.

**Exceptions:**

Error Code	Error Type Name	Condition
-2147024894	System.IO.FileNotFoundException	serverRelativePath doesn't correspond to a folder

**3.2.5.143.2.2.42 GetListItem**

**Return Type:** Microsoft.SharePoint.Client.ListItem

Returns the list item that is associated with the specified server-relative URL.

**Parameters:**

*strUrl*: A string that contains the server-relative URL, for example, "/sites/MySite/Shared Documents/MyDocument.docx".

Type: **CSOM String**

**3.2.5.143.2.2.43 GetListItemByResourceId**

**Return Type:** Microsoft.SharePoint.Client.ListItem

Returns the list item that is associated with the specified SkySync ResourceId.

**Parameters:**

*resourceId*: Contains the SkySync Resource Id.

Type: **CSOM String**

**3.2.5.143.2.2.44 GetListItemUsingPath**

**Return Type:** Microsoft.SharePoint.Client.ListItem

Returns the list item that is associated with the specified server-relative path.

**Parameters:**

*path*: Contains the site-relative path for the list item, for example, /sites/MySite/Shared Documents/MyDocument.docx.

Type: Microsoft.SharePoint.Client.ResourcePath

It MUST NOT be NULL.

**3.2.5.143.2.2.45 GetListUsingPath**

**Return Type:** Microsoft.SharePoint.Client.List

Returns the list that is associated with the specified server-relative path.

**Parameters:**

*path*: Contains the site-relative path for a list, for example, /Lists/Announcements.

Type: Microsoft.SharePoint.Client.ResourcePath

It MUST NOT be NULL.

#### **3.2.5.143.2.2.46    GetNewsList**

**Return Type:** Microsoft.SharePoint.Client.List

Returns the News List on this web, if it exists. If the list does not exist, the list will be created and then returned if allowCreate is set to true. The News List is a hidden SP.List in which News Posts are stored.

**Parameters:**

*allowCreate:* Indicates whether to create the list if it does not exist on this web. "true" means yes.

Type: **CSOM Boolean**

#### **3.2.5.143.2.2.47    GetRecycleBinItemsByQueryInfo**

**Return Type:** Microsoft.SharePoint.Client.RecycleBinItemCollection

Returns a collection of recycle bin items of the web.

**Parameters:**

*queryInfo:* Recycle bin query information for next page or previous page.

Type: Microsoft.SharePoint.Client.RecycleBinQueryInformation

It MUST NOT be NULL.

#### **3.2.5.143.2.2.48    GetStorageEntity**

**Return Type:** Microsoft.SharePoint.ClientSideComponent.StorageEntity

This will return the storage entity identified by the given key

**Parameters:**

*key:* ID of storage entity to be returned.

Type: **CSOM String**

#### **3.2.5.143.2.2.49    GetViewFromPath**

**Return Type:** Microsoft.SharePoint.Client.View

Returns a view of a list within the site based on the specified path.

**Parameters:**

*listPath:* Contains either an **absolute path** or a site-relative path of a view.

Type: Microsoft.SharePoint.Client.ResourcePath

#### **3.2.5.143.2.2.50    GetViewFromUrl**

**Return Type:** Microsoft.SharePoint.Client.View

Returns a view of a list within the site based on the specified **URL**.

**Parameters:**

*listUrl*: Contains either an **absolute URL** or a **site-relative URL** of a view.

Type: **CSOM String**

### 3.2.5.144 Microsoft.SharePoint.Client.WebCollection

**TypeId**: {C197D59E-D070-43BF-AD5E-10D6152E38A6}

**ShortName**: SP.WebCollection

Specifies a collection of **sites (2)**.

#### 3.2.5.144.1 Properties

##### 3.2.5.144.1.1 Scalar Properties

None.

##### 3.2.5.144.1.2 ObjectPath Properties

None.

#### 3.2.5.144.2 Methods

##### 3.2.5.144.2.1 Scalar Methods

None.

##### 3.2.5.144.2.2 ObjectPath Methods

###### 3.2.5.144.2.2.1 Add

**Return Type**: Microsoft.SharePoint.Client.Web

Creates a new **site (2)** and adds it to this collection of sites (2).

**Parameters:**

*parameters*: Specifies the properties of the new site (2).

Type: Microsoft.SharePoint.Client.WebCreationInformation

It MUST NOT be NULL.

**Exceptions:**

Error Code	Error Type Name	Condition
-2147024713	Microsoft.SharePoint.SPException	The URL specified in <i>parameters</i> is already in use.

### 3.2.5.145 Microsoft.SharePoint.Client.WebCreationInformation

**TypeId**: {8F9E9FBE-189E-492F-884F-98F9EF9CC4D6}

**ShortName**: SP.WebCreationInformation

Specifies the properties of a **site (2)** that is to be created.

### **3.2.5.145.1 Properties**

#### **3.2.5.145.1.1 Scalar Properties**

##### **3.2.5.145.1.1.1 Description**

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies the description of the new **site (2)**.

##### **3.2.5.145.1.1.2 Language**

**Type:** CSOM Int32

**Accessibility:** Read/Write

Specifies the **LCID** specifying the language of the new **site (2)**.

It MUST be a valid LCID, as specified in [\[MS-LCID\]](#).

##### **3.2.5.145.1.1.3 Title**

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies the title of the new **site (2)**.

Its length MUST be equal to or less than 255.

##### **3.2.5.145.1.1.4 Url**

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies the **leaf name** of the new **site (2)**.

It MUST NOT be NULL. Its length MUST be equal to or less than 128. It MUST NOT begin with or end with "/", ".". It MUST NOT contain consecutive "/" or ".". It MUST NOT contain /wpresources. It MUST NOT contain any of the following characters: "~", "'", "#", "%", "&", "\*", ":", "<", ">", "?", "\", "{", "|", "}", "\x7f".

##### **3.2.5.145.1.1.5 UseSamePermissionsAsParentSite**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Specifies whether the new **site (2)** inherits permissions from its **parent site**.

##### **3.2.5.145.1.1.6 WebTemplate**

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies the name of the **site template** to be used for creating the new **site (2)**

It MUST refer to an existing site template.

### 3.2.5.145.1.2 ObjectPath Properties

None.

## 3.2.5.146 Microsoft.SharePoint.Client.WebParts.LimitedWebPartManager

**TypeId:** {AC641ADE-62DF-49C9-AF8E-ABDA6278E920}

**ShortName:** SP.WebParts.LimitedWebPartManager

Provides operations to access and modify the existing **Web Parts** on a **Web Part Page**, and add new ones to the Web Part Page.

### 3.2.5.146.1 Properties

#### 3.2.5.146.1.1 Scalar Properties

##### 3.2.5.146.1.1.1 HasPersonalizedParts

**Type:** CSOM Boolean

**Accessibility:** Read Only

Specifies whether the **Web Part Page** contains one or more **personalized Web Parts**.

Its value MUST be "true" if both the **personalization scope** of the Web Part Page is "User" and the Web Part Page contains one or more personalized Web Parts; otherwise, it MUST be "false".

##### 3.2.5.146.1.1.2 Scope

**Type:** Microsoft.SharePoint.Client.WebParts.PersonalizationScope

**Accessibility:** Read Only

Specifies the current **personalization scope** of the **Web Part Page**.

Its value MUST be "User" if personalized data is loaded for the **Web Parts** on the Web Part Page, or "Shared" if common data for all users is loaded.

### 3.2.5.146.1.2 ObjectPath Properties

#### 3.2.5.146.1.2.1 WebParts

**Type:** Microsoft.SharePoint.Client.WebParts.WebPartDefinitionCollection

**Accessibility:** Read Only

A collection of the **Web Parts** on the **Web Part Page** available to the **current user** based on the current user's permissions.

### 3.2.5.146.2 Methods

### 3.2.5.146.2.1 Scalar Methods

#### 3.2.5.146.2.1.1 ExportWebPart

**Return Type:** CSOM String

Exports the specified Web Part, given its ID.

**Parameters:**

*webPartId*: The ID of the Web Part to export.

Type: CSOM GUID

It MUST NOT be an empty GUID.

### 3.2.5.146.2.2 ObjectPath Methods

#### 3.2.5.146.2.2.1 AddWebPart

**Return Type:** Microsoft.SharePoint.Client.WebParts.WebPartDefinition

Adds a **Web Part** to the **Web Part Page** and returns a **reference** to the SP.WebParts.WebPartDefinition of the newly added Web Part.

When **Scope** is *User*, the **current user** MUST have **permissions** to add and delete **personalized Web Parts**. When **Scope** is *Shared*, the current user MUST have permissions to customize pages.

**Parameters:**

*webPart*: The Web Part to add to the Web Part Page.

Type: Microsoft.SharePoint.Client.WebParts.WebPart

Use **ImportWebPart** to import a Web Part, and then use **AddWebPart** to add it to the Web Part Page.

It MUST NOT be NULL.

*zoneId*: The name of the **Web Part zone** to which to add the Web Part.

Type: CSOM String

It MUST NOT be NULL. It MUST NOT be empty. Its length MUST be equal to or less than 64.

*zoneIndex*: A **Web Part zone index** that specifies the position at which the Web Part is to be inserted within the Web Part zone.

Type: CSOM Int32

The new Web Part MUST be inserted directly before the existing Web Part with the lowest Web Part zone index greater than or equal to **zoneIndex**. If **zoneIndex** is greater than the index of all Web Parts in the zone or there are no Web Parts in the Web Part zone, then the new Web Part MUST be inserted at the end of the Web Part zone.

Its value MUST be equal to or greater than 0.

#### 3.2.5.146.2.2.2 ImportWebPart

**Return Type:** Microsoft.SharePoint.Client.WebParts.WebPartDefinition



Imports a **Web Part** from a string in the .dwp format as specified in [MS-WPPS] section 2.2.4.2, or the .webpart format as specified in [MS-WPPS] section 2.2.3.1. After importing, the Web Part is not added to a **Web Part Page**. To add a Web Part to a Web Part Page, use **AddWebPart**, supplying the **object (1)** returned by this method. A **reference** to the added SP.WebParts.WebPartDefinition is returned.

When **Scope** is **User**, the **current user** MUST have **permissions** to add and delete **personalized Web Parts**. When **Scope** is **Shared**, the current user MUST have permissions to customize pages.

**Parameters:**

*webPartXml*: The Web Part markup to import.

Type: **CSOM String**

It MUST NOT be NULL. It MUST NOT be empty. It MUST be valid XML in the .dwp or .webpart format.

**Exceptions:**

Error Code	Error Type Name	Condition
-1	Microsoft.SharePoint.WebPartPages.WebPartPageUserException	The provided Web Part markup is not in the .dwp or .webpart format.

**3.2.5.147 Microsoft.SharePoint.Client.WebParts.PersonalizationScope**

**ShortName:** SP.WebParts.PersonalizationScope

**Flag:** false

Specifies the **personalization scope** for the **LimitedWebPartManager object (1)**.

**3.2.5.147.1 Field Values**

**3.2.5.147.1.1 User**

**Value:** 0

**Personalization data** that is user-specific, as well as personalization data that applies to all users, is loaded for all **Web Parts** on a **Web Part Page** that support personalization data. Only personalization data that is user-specific is saved on the Web Part Page. When referring to the scope associated with a Web Parts control property, **User** scope indicates that the property can only load and store data applicable to all users when running on a page in **Shared** scope. However, when the property's control is running on a page in **User** scope, the property's per-user and all-user data will be loaded and merged. In this case, though, only per-user data will be saved when a page is running in **User** scope.

**3.2.5.147.1.2 Shared**

**Value:** 1

**Personalization data** that applies to all users is loaded for all **Web Parts** on a **Web Part Page** and is available to be saved on the Web Part Page. When referring to the scope associated with a Web Parts control property, **Shared** scope indicates that the property normally only allows loading or saving of data associated with all users.

### 3.2.5.148 Microsoft.SharePoint.Client.WebParts.WebPart

**TypeId:** {612A6BD9-6C99-43C9-813A-8D7E19702118}

**ShortName:** SP.WebParts.WebPart

Represents a **Web Part** on a **Web Part Page**.

#### 3.2.5.148.1 Properties

##### 3.2.5.148.1.1 Scalar Properties

###### 3.2.5.148.1.1.1 ExportMode

**Type:** Microsoft.SharePoint.Client.WebParts.WebPartExportMode

**Accessibility:** Read/Write

Gets or sets the export mode of a Web Part.

###### 3.2.5.148.1.1.2 Hidden

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Specifies whether a **Web Part** is displayed on a **Web Part Page**.

If "true", the Web Part MUST be hidden. Web Parts that are hidden MUST NOT be displayed on the page to the end user, but SHOULD still participate normally in the rendering of the page. The default value is "false".

###### 3.2.5.148.1.1.3 IsClosed

**Type:** CSOM Boolean

**Accessibility:** Read Only

Specifies whether a **Web Part** is currently closed on a **Web Part Page**.

If "true", the Web Part is closed. Web Parts that are closed MUST NOT be displayed on the page, and MUST NOT participate normally in the rendering of the page. The default value is "false".

To open or close a Web Part, see **WebPartDefinition.OpenWebPart**, as specified in section [3.2.5.149.2.1.4](#), and **WebPartDefinition.CloseWebPart**, as specified in section [3.2.5.149.2.1.1](#).

###### 3.2.5.148.1.1.4 Subtitle

**Type:** CSOM String

**Accessibility:** Read Only

Specifies a string that is concatenated with the **Title** property value to form a complete title for a **Web Part**.

The default value is an empty string ("").

###### 3.2.5.148.1.1.5 Title

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies the title of a **Web Part**.

If this property is set to NULL, the title of the Web Part MUST instead be reset to its default value if one is specified in the Web Part's definition.

### **3.2.5.148.1.1.6      TitleUrl**

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies a **URL** to the supplemental information about a **Web Part**.

If this property is set to NULL, the title URL of the Web Part MUST instead be reset to its default value if one is specified in the Web Part's definition.

The value of this property SHOULD be a valid URL, but the protocol server MAY accept other strings without validating them.

### **3.2.5.148.1.1.7      ZoneIndex**

**Type:** CSOM Int32

**Accessibility:** Read Only

Specifies the index position of a **Web Part** within the **Web Part zone**.

The value is the numerical order of a Web Part within the Web Part zone. The first Web Part in a Web Part zone MUST have an index value of zero.

## **3.2.5.148.1.2 ObjectPath Properties**

### **3.2.5.148.1.2.1      Properties**

**Type:** Microsoft.SharePoint.Client.PropertyValues

**Accessibility:** Read Only

Gets customizable properties for the **Web Part** as specified by **Microsoft.SharePoint.Client.PropertyValues** (section [3.2.5.101](#)), <160>

## **3.2.5.148.2      Methods**

### **3.2.5.148.2.1 Scalar Methods**

None.

### **3.2.5.148.2.2 ObjectPath Methods**

None.

## **3.2.5.149      Microsoft.SharePoint.Client.WebParts.WebPartDefinition**

**TypeId:** {44BF1024-6127-432A-8E3D-FB317FB4541E}

**ShortName:** SP.WebParts.WebPartDefinition

Represents a **Web Part** on a **Web Part Page**. Provides operations for moving, deleting, and changing the state of the Web Part.

The ZoneId property is not included in the **default scalar property set** for this type.

### 3.2.5.149.1 Properties

#### 3.2.5.149.1.1 Scalar Properties

##### 3.2.5.149.1.1.1 Id

**Type:** CSOM GUID

**Accessibility:** Read Only

Specifies the **Web Part identifier** of the **Web Part**.

This value MUST be unique for each Web Part.

##### 3.2.5.149.1.1.2 ZoneId

**Type:** CSOM String

**Accessibility:** Read Only

Gets the identifier of the WebPart Zone.

#### 3.2.5.149.1.2 ObjectPath Properties

##### 3.2.5.149.1.2.1 WebPart

**Type:** Microsoft.SharePoint.Client.WebParts.WebPart

**Accessibility:** Read Only

The **WebPart object (1)**, as specified in section [3.2.5.148](#), associated with this **WebPartDefinition**. The **WebPart** object (1) contains additional properties relating to the **Web Part** represented by this **WebPartDefinition** object (1).

Each **WebPartDefinition** object (1) MUST have exactly one **WebPart** object (1) associated with it. There can be multiple **WebPartDefinition** objects (1) with the same value for their **WebPart** property.

### 3.2.5.149.2 Methods

#### 3.2.5.149.2.1 Scalar Methods

##### 3.2.5.149.2.1.1 CloseWebPart

**Return Type:** None

Closes the **Web Part**. If the Web Part is already closed, this method does nothing.

If the **current user** does not have **permissions** to modify the Web Part, the server MUST ignore the call to this method.

**Parameters:** None

##### 3.2.5.149.2.1.2 DeleteWebPart

**Return Type:** None

Deletes the **Web Part** from the page.

When **Scope** is **User**, the **current user** MUST have **permissions** to add and delete **personalized Web Parts**. When **Scope** is **Shared**, the current user MUST have permissions to customize pages.

**Parameters:** None

**Exceptions:**

Error Code	Error Type Name	Condition
-1	Microsoft.SharePoint.WebPartPages.WebPartPageUserException	The current user has insufficient permissions.

### 3.2.5.149.2.1.3 MoveWebPartTo

**Return Type:** None

Moves the **Web Part** to a different location on a **Web Part Page**.

If the **current user** does not have **permissions** to modify the Web Part, the server MUST ignore the call to this method.

**Parameters:**

*zoneID*: The name of the **Web Part zone** to which to move the Web Part.

Type: **CSOM String**

It MUST NOT be NULL. It MUST NOT be empty. Its length MUST be equal to or less than 64.

*zoneIndex*: A **Web Part zone index** that specifies the position at which the Web Part is to be moved within the destination Web Part zone.

Type: **CSOM Int32**

The *zoneIndex* parameter for this method follows the same behavior as the *zoneIndex* parameter for **LimitedWebPartManager.AddWebPart**, as specified in section [3.2.5.146.2.2.1](#).

Its value MUST be equal to or greater than 0.

### 3.2.5.149.2.1.4 OpenWebPart

**Return Type:** None

Opens the **Web Part**. If the Web Part is already open, this method does nothing.

If the **current user** does not have **permissions** to modify the Web Part, the protocol server MUST ignore the call to this method.

**Parameters:** None

### 3.2.5.149.2.1.5 SaveWebPartChanges

**Return Type:** None

Saves changes to the **Web Part** made by using other properties and methods on the `WebPartDefinition` **object (1)**.

If the **current user** does not have **permissions** to modify the Web Part, the protocol server MUST ignore the call to this method.

**Parameters:** None

### 3.2.5.149.2.2 ObjectPath Methods

None.

## 3.2.5.150 Microsoft.SharePoint.Client.WebParts.WebPartDefinitionCollection

**TypeId:** {01C986B2-57A6-49FB-B8F1-DF159F5B2349}

**ShortName:** SP.WebParts.WebPartDefinitionCollection

Implements a collection of **Web Part** definition **objects (1)**.

### 3.2.5.150.1 Properties

#### 3.2.5.150.1.1 Scalar Properties

None.

#### 3.2.5.150.1.2 ObjectPath Properties

None.

### 3.2.5.150.2 Methods

#### 3.2.5.150.2.1 Scalar Methods

None.

#### 3.2.5.150.2.2 ObjectPath Methods

##### 3.2.5.150.2.2.1 GetById

**Return Type:** Microsoft.SharePoint.Client.WebParts.WebPartDefinition

Returns the **Web Part** definition **object (1)** in the collection with a **Web Part identifier** equal to the `id` parameter.

**Parameters:**

`id`: The Web Part identifier of the Web Part definition to retrieve.

Type: **CSOM GUID**

All **WebPartDefinition** objects (1) MUST have a unique value for their **Id** property.

##### 3.2.5.150.2.2.2 GetByControlId

**Return Type:** Microsoft.SharePoint.Client.WebParts.WebPartDefinition

Returns the **WebPartDefinition object (1)** in the collection with a **Hypertext Markup Language (HTML) ID** attribute equal to the *controlId* parameter. <161>

**Parameters:**

*controlId*: The HTML **ID** attribute of the **WebPartDefinition**.

Type: **CSOM String**

All **WebPartDefinition** objects (1) in the collection MUST have a unique value for their HTML **ID** attribute.

**Exceptions:**

Error Code	Error Type Name	Condition
-2146233086	System.ArgumentOutOfRangeException	There is no <b>WebPartDefinition</b> object (1) in the collection with a <b>ControlId</b> property equal to the <i>controlId</i> parameter.

### 3.2.5.151 Microsoft.SharePoint.Client.WebTemplate

**TypeId**: {2BE10268-4BE1-4B5A-850D-D06B137A9C40}

**ShortName**: SP.WebTemplate

Specifies a **site definition** or a **site template** that is used to instantiate a **site (2)**.

#### 3.2.5.151.1 Properties

##### 3.2.5.151.1.1 Scalar Properties

###### 3.2.5.151.1.1.1 Description

Type: **CSOM String**

**Accessibility**: Read Only

Specifies the description for the **site definition configuration** or **site template**.

###### 3.2.5.151.1.1.2 DisplayCategory

Type: **CSOM String**

**Accessibility**: Read Only

Specifies the **display name** for the category that this **site definition configuration** or **site template** is a part of.

###### 3.2.5.151.1.1.3 Id

Type: **CSOM Int32**

**Accessibility**: Read Only

Specifies the unique identifier for the **site definition configuration** or the **site template**.

#### **3.2.5.151.1.1.4      imageUrl**

**Type:** CSOM String

**Accessibility:** Read Only

Specifies the **URL** for the image that is associated with the **site definition configuration** or **site template**.

#### **3.2.5.151.1.1.5      IsHidden**

**Type:** CSOM Boolean

**Accessibility:** Read Only

Specifies whether the **site definition configuration** is displayed in the user interface for creating new **sites (2)**.

#### **3.2.5.151.1.1.6      IsRootWebOnly**

**Type:** CSOM Boolean

**Accessibility:** Read Only

Specifies whether the **site definition configuration** or **site template** can only be applied to the **top-level site** in the **site collection**.

#### **3.2.5.151.1.1.7      IsSubWebOnly**

**Type:** CSOM Boolean

**Accessibility:** Read Only

Specifies whether the **site definition configuration** or **site template** can only be applied to **subsites** created within the **site collection**.

#### **3.2.5.151.1.1.8      Lcid**

**Type:** CSOM UInt32

**Accessibility:** Read Only

Specifies the **LCID** for the **site definition configuration** or **site template**.

#### **3.2.5.151.1.1.9      Name**

**Type:** CSOM String

**Accessibility:** Read Only

Specifies the name for the **site definition configuration** or **site template**.

#### **3.2.5.151.1.1.10      Title**

**Type:** CSOM String

**Accessibility:** Read Only

Specifies the **display name** for the **site definition configuration** or **site template**.



### 3.2.5.151.1.2 ObjectPath Properties

None.

### 3.2.5.151.2 Methods

#### 3.2.5.151.2.1 Scalar Methods

None.

#### 3.2.5.151.2.2 ObjectPath Methods

None.

## 3.2.5.152 Microsoft.SharePoint.Client.WebTemplateCollection

**TypeId:** {15C2ECDA-D49E-4FDA-97C8-C538A203DFB5}

**ShortName:** SP.WebTemplateCollection

Specifies a collection of **site templates**.

### 3.2.5.152.1 Properties

#### 3.2.5.152.1.1 Scalar Properties

None.

#### 3.2.5.152.1.2 ObjectPath Properties

None.

### 3.2.5.152.2 Methods

#### 3.2.5.152.2.1 Scalar Methods

None.

#### 3.2.5.152.2.2 ObjectPath Methods

##### 3.2.5.152.2.2.1 GetByName

**Return Type:** Microsoft.SharePoint.Client.WebTemplate

Returns the **SP.WebTemplate** (section [3.2.5.151](#)) specified by its name. [<162>](#)

**Parameters:**

*name:* The name of the **SP.WebTemplate** that is returned.

Type: **CSOM String**

It MUST NOT be NULL. It MUST NOT be empty.

**Exceptions:**

Error Code	Error Type Name	Condition
-2147024809	System.ArgumentException	The <b>SP.WebTemplate</b> specified by <i>name</i> does not exist.

### 3.2.5.153 Microsoft.SharePoint.Client.Workflow.WorkflowAssociation

**TypeId:** {5B590642-3966-4F67-B937-C1DB8528A1D3}

**ShortName:** SP.Workflow.WorkflowAssociation

Represents the association of a **workflow template** with a specific **list** or **content type**

#### 3.2.5.153.1 Properties

##### 3.2.5.153.1.1 Scalar Properties

###### 3.2.5.153.1.1.1 AllowManual

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Specifies whether **workflow instances** based on this **workflow association** can be started manually. If the **AllowManual** property of the **BaseTemplate** is set to "false", setting this property results in no change to its value.

###### 3.2.5.153.1.1.2 AssociationData

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies the **workflow association** data for **workflow instances** created from this workflow association.

###### 3.2.5.153.1.1.3 AutoStartChange

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Specifies whether **workflow instances** are to be created from this **workflow association** and started automatically when a **list item** is changed. If the **AutoStartChange** property of the **BaseTemplate** for the workflow association is set to "false", setting this property results in no change to its value.

###### 3.2.5.153.1.1.4 AutoStartCreate

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Specifies whether **workflow instances** are to be created from this **workflow association** and started automatically when a **list item** is created. If the **AutoStartCreate** property of the **BaseTemplate** for the workflow association is set to "false", setting this property results in no change to its value.

### 3.2.5.153.1.1.5 BaseId

Type: **CSOM GUID**

Accessibility: Read Only

Specifies the identifier of the **workflow template** on which this **workflow association** is based.

### 3.2.5.153.1.1.6 Created

Type: **CSOM DateTime**

Accessibility: Read Only

Specifies the date and time at which this **workflow association** was created.

### 3.2.5.153.1.1.7 Description

Type: **CSOM String**

Accessibility: Read/Write

Specifies the description for this **workflow association**.

### 3.2.5.153.1.1.8 Enabled

Type: **CSOM Boolean**

Accessibility: Read/Write

Specifies whether new **workflow instances** is allowed for this **workflow association**.

#### Exceptions:

Error Code	Error Type Name	Condition
-1	System.InvalidOperationException	Value is "true" and this workflow association is based on a non-declarative <b>workflow template</b> that has been deactivated.

### 3.2.5.153.1.1.9 HistoryListTitle

Type: **CSOM String**

Accessibility: Read/Write

Specifies the title of the **list** to which to log **workflow history events (2)** for this **workflow association**.

It MUST NOT be NULL. It MUST NOT be empty. Its length MUST be equal to or less than 255.

### 3.2.5.153.1.1.10 Id

Type: **CSOM GUID**

Accessibility: Read Only

Specifies the identifier of the **workflow association**. Every workflow association MUST return its own **GUID** for this property.

#### **3.2.5.153.1.1.11 InstantiationUrl**

**Type:** CSOM String

**Accessibility:** Read Only

Specifies the **URL** of the **workflow initiation form** for this **workflow association**.

#### **3.2.5.153.1.1.12 InternalName**

**Type:** CSOM String

**Accessibility:** Read Only

Specifies the internal name of this **workflow association**, as determined by the **WorkflowAssociation** implementation.

#### **3.2.5.153.1.1.13 IsDeclarative**

**Type:** CSOM Boolean

**Accessibility:** Read Only

Specifies whether the **workflow association** represents a **declarative workflow**.

#### **3.2.5.153.1.1.14 ListId**

**Type:** CSOM GUID

**Accessibility:** Read Only

Specifies the identifier of the **list** on which this **workflow association** resides.

#### **3.2.5.153.1.1.15 Modified**

**Type:** CSOM DateTime

**Accessibility:** Read Only

Specifies the date and time at which this **workflow association** was last modified.

#### **3.2.5.153.1.1.16 Name**

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies the name of this **workflow association**.

#### **3.2.5.153.1.1.17 TaskListTitle**

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies the title of the **list** within which **workflow tasks** are to be created for this **workflow association**.

It MUST NOT be NULL. It MUST NOT be empty. Its length MUST be equal to or less than 255.

### 3.2.5.153.1.1.18 WebId

**Type:** CSOM GUID

**Accessibility:** Read Only

Specifies the identifier of the **site (2)** on which the **workflow association** resides.

### 3.2.5.153.1.2 ObjectPath Properties

None.

## 3.2.5.153.2 Methods

### 3.2.5.153.2.1 Scalar Methods

#### 3.2.5.153.2.1.1 DeleteObject

**Return Type:** None

Removes this **workflow association** from its parent **WorkflowAssociations** collection.

**Parameters:** None

#### 3.2.5.153.2.1.2 Update

**Return Type:** None

Informs this **workflow associations** parent **WorkflowAssociations** collection that changes have been made to this workflow association.

**Parameters:** None

**Exceptions:**

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	This workflow association is on an <b>external list</b> .

### 3.2.5.153.2.2 ObjectPath Methods

None.

## 3.2.5.154 Microsoft.SharePoint.Client.Workflow.WorkflowAssociationCollection

**TypeId:** {4E1196EA-CE71-4AA9-B3C0-3F8DA05DEEC9}

**ShortName:** SP.Workflow.WorkflowAssociationCollection

Implements a collection of **workflow association objects (1)**. Provides operations for listing existing workflow associations and adding new ones.

### 3.2.5.154.1 Properties

### 3.2.5.154.1.1 Scalar Properties

None.

### 3.2.5.154.1.2 ObjectPath Properties

None.

## 3.2.5.154.2 Methods

### 3.2.5.154.2.1 Scalar Methods

None.

### 3.2.5.154.2.2 ObjectPath Methods

#### 3.2.5.154.2.2.1 Add

**Return Type:** Microsoft.SharePoint.Client.Workflow.WorkflowAssociation

Creates a new **workflow association** based on properties specified in the **parameters object (1)**, and adds the object (1) representing that workflow association to the collection.

**Parameters:**

*parameters:* An object (1) that specifies the parameters used to create the workflow association.

Type: Microsoft.SharePoint.Client.Workflow.WorkflowAssociationCreationInformation

It MUST NOT be NULL.

#### 3.2.5.154.2.2.2 GetById

**Return Type:** Microsoft.SharePoint.Client.Workflow.WorkflowAssociation

Returns the **workflow association** in the collection with an identifier equal to the *associationId* parameter, or NULL if no such **object (1)** exists in the collection or *associationId* is an empty **GUID**.

**Parameters:**

*associationId:* The GUID of the workflow association object (1) to retrieve.

Type: **CSOM GUID**

Each workflow association MUST have a unique GUID.

#### 3.2.5.154.2.2.3 GetByName

**Return Type:** Microsoft.SharePoint.Client.Workflow.WorkflowAssociation

Returns the **workflow association** in the collection with a **Name** property equal to the *name* parameter, or NULL if no such **object (1)** exists in the collection.

**Parameters:**

*name:* The name of the workflow association to retrieve.

Type: **CSOM String**

All workflow association objects (1) in the collection MUST have unique values for their **Name** property.

### **3.2.5.155 Microsoft.SharePoint.Client.Workflow.WorkflowAssociationCreationInformation**

**TypeId:** {3C812F4F-8465-41CB-B298-BD33B2604A51}

**ShortName:** SP.Workflow.WorkflowAssociationCreationInformation

Specifies properties for a new **workflow association**.

#### **3.2.5.155.1 Properties**

##### **3.2.5.155.1.1 Scalar Properties**

###### **3.2.5.155.1.1.1 ContentTypeAssociationHistoryListName**

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies the name of the **workflow history list** to be used by a **site content type workflow association**.

Its value MUST NOT be NULL and MUST NOT be empty if the **workflow** are to be created with a site content type **workflow template** and the value of **HistoryList** is NULL. Its value MUST be ignored for any other type of workflow template.

###### **3.2.5.155.1.1.2 ContentTypeAssociationTaskListName**

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies the name of the **workflow task list** to be used by a **site content type workflow association**.

Its value MUST NOT be NULL and MUST NOT be empty if the **workflow** are to be created with a site content type **workflow template** and the value of **TaskList** is NULL. Its value MUST be ignored for any other type of workflow template.

###### **3.2.5.155.1.1.3 Name**

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies the name to be given to the **workflow association**.

Its value MUST NOT be NULL. Its value MUST NOT be empty. Its value MUST NOT be equal to the name of an existing workflow association that is associated with the same **object (1)** as the new workflow association.

##### **3.2.5.155.1.2 ObjectPath Properties**

###### **3.2.5.155.1.2.1 HistoryList**

**Type:** Microsoft.SharePoint.Client.List

**Accessibility:** Read/Write

Specifies the **workflow history list** to be used by the **workflow association**.

Its value MUST NOT be NULL, unless the **workflow** are to be based on a **site content type workflow template** and the value of **Content.Type.Association.History.ListName** is not NULL and NOT empty.

### 3.2.5.155.1.2.2 TaskList

**Type:** Microsoft.SharePoint.Client.List

**Accessibility:** Read/Write

Specifies the **workflow task list** to be used by the **workflow association**.

Its value MUST NOT be NULL, unless the **workflow** is to be based on a **site content type workflow template** and the value of **ContentType.Association.Task.List.Name** is not NULL or empty.

### 3.2.5.155.1.2.3 Template

**Type:** Microsoft.SharePoint.Client.Workflow.WorkflowTemplate

**Accessibility:** Read/Write

Specifies the **workflow template** to be used in the **workflow association**.

Its value MUST NOT be NULL.

## 3.2.5.156 Microsoft.SharePoint.Client.Workflow.WorkflowTemplate

**TypeId:** {36DE6DBB-60D6-4131-B47F-E895798E1E93}

**ShortName:** SP.Workflow.WorkflowTemplate

Represents a **workflow template** currently deployed on the **site (2)**.

### 3.2.5.156.1 Properties

#### 3.2.5.156.1.1 Scalar Properties

##### 3.2.5.156.1.1.1 AllowManual

**Type:** CSOM Boolean

**Accessibility:** Read Only

Specifies whether **workflow associations** based on this **workflow template** can be configured to allow **workflow instances** to be started manually.

##### 3.2.5.156.1.1.2 AssociationUrl

**Type:** CSOM String

**Accessibility:** Read Only



The **site-relative URL** of the **workflow association form** to use with the **workflow template**. If the workflow template has no workflow association form, the **URL** MUST return an empty string ("").

It MUST be a URL of relative form.

#### **3.2.5.156.1.1.3 AutoStartChange**

**Type: CSOM Boolean**

**Accessibility:** Read Only

Specifies whether **workflow associations** based on this **workflow template** can be configured to start **workflow instances** automatically when an item is changed.

#### **3.2.5.156.1.1.4 AutoStartCreate**

**Type: CSOM Boolean**

**Accessibility:** Read Only

Specifies whether **workflow associations** based on this **workflow template** can be configured to start **workflow instances** automatically when an item is created.

#### **3.2.5.156.1.1.5 Description**

**Type: CSOM String**

**Accessibility:** Read Only

The description for the **workflow template**.

Its length MUST be equal to or less than 255.

#### **3.2.5.156.1.1.6 Id**

**Type: CSOM GUID**

**Accessibility:** Read Only

The **workflow template** identifier. Every template MUST have its own unique **GUID**.

#### **3.2.5.156.1.1.7 IsDeclarative**

**Type: CSOM Boolean**

**Accessibility:** Read Only

Specifies whether the **workflow template** represents a **declarative workflow**.

#### **3.2.5.156.1.1.8 Name**

**Type: CSOM String**

**Accessibility:** Read Only

The name of the **workflow template**. This name is displayed in the user interface when creating new **workflow associations** of this template.

It MUST NOT be NULL. It MUST NOT be empty. Its length MUST be equal to or less than 255.

### 3.2.5.156.1.1.9 PermissionsManual

**Type:** Microsoft.SharePoint.Client.BasePermissions

**Accessibility:** Read Only

The **permission level** required for a user to manually start **workflow instances** based on the **workflow template**.

### 3.2.5.156.1.2ObjectPath Properties

None.

### 3.2.5.156.2 Methods

#### 3.2.5.156.2.1Scalar Methods

None.

#### 3.2.5.156.2.2ObjectPath Methods

None.

### 3.2.5.157 Microsoft.SharePoint.Client.Workflow.WorkflowTemplateCollection

**TypeId:** {F64CC3D2-888A-43CC-B579-EF32F83338A4}

**ShortName:** SP.Workflow.WorkflowTemplateCollection

The collection of **workflow templates** deployed on a **site (2)**.

#### 3.2.5.157.1 Properties

##### 3.2.5.157.1.1Scalar Properties

None.

##### 3.2.5.157.1.2ObjectPath Properties

None.

#### 3.2.5.157.2 Methods

##### 3.2.5.157.2.1Scalar Methods

None.

##### 3.2.5.157.2.2ObjectPath Methods

###### 3.2.5.157.2.2.1 GetById

**Return Type:** Microsoft.SharePoint.Client.Workflow.WorkflowTemplate

Returns a **workflow template** based on the workflow template identifier.

It MUST return the **WorkflowTemplate object (1)** in the collection with an Id property equal to the *templateId* parameter, or null if no such workflow template exists in the collection.

**Parameters:**

*templateId*: The identifier of the **WorkflowTemplate** to retrieve.

Type: **CSOM GUID**

### 3.2.5.157.2.2.2 GetByName

**Return Type:** Microsoft.SharePoint.Client.Workflow.WorkflowTemplate

Returns the **workflow template** matching the *name* provided.

It MUST return the **WorkflowTemplate object (1)** with **Name** property equal to the *name* parameter, or null if no such **WorkflowTemplate** exists in the collection. All **WorkflowTemplate** objects (1) in the collection MUST have a unique value for their **Name** property.

**Parameters:**

*name*: The name of the workflow template to retrieve.

Type: **CSOM String**

It MUST NOT be NULL.

### 3.2.5.158 Microsoft.BusinessData.MetadataModel.Collections.EntityFieldCollection

**TypeId:** {53746712-30F8-4626-8BC5-B1A421452652}

**ShortName:** SP.BusinessData.Collections.EntityFieldCollection

Represents a read only collection of **Fields (2)**.<163>

#### 3.2.5.158.1 Properties

##### 3.2.5.158.1.1 Scalar Properties

None.

##### 3.2.5.158.1.2 ObjectPath Properties

None.

#### 3.2.5.158.2 Methods

##### 3.2.5.158.2.1 Scalar Methods

None.

##### 3.2.5.158.2.2 ObjectPath Methods

None.

### 3.2.5.159 Microsoft.BusinessData.MetadataModel.Collections.EntityIdentifierCollection

**TypeId:** {0BF0D5B7-DF64-4520-A1E1-76BC7517EE24}

**ShortName:** SP.BusinessData.Collections.EntityIdentifierCollection

Represents a read only collection of identifiers. <164>

### **3.2.5.159.1 Properties**

#### **3.2.5.159.1.1 Scalar Properties**

None.

#### **3.2.5.159.1.2 ObjectPath Properties**

None.

### **3.2.5.159.2 Methods**

#### **3.2.5.159.2.1 Scalar Methods**

None.

#### **3.2.5.159.2.2 ObjectPath Methods**

None.

### **3.2.5.160 Microsoft.BusinessData.MetadataModel.Collections.LobSystemInstanceCollection**

**TypeId:** {3688D19C-D248-48CD-A46E-5F6719073953}

**ShortName:** SP.BusinessData.Collections.LobSystemInstanceCollection

Represents a read only collection of **LobSystemInstances**. <165>

### **3.2.5.160.1 Properties**

#### **3.2.5.160.1.1 Scalar Properties**

None.

#### **3.2.5.160.1.2 ObjectPath Properties**

None.

### **3.2.5.160.2 Methods**

#### **3.2.5.160.2.1 Scalar Methods**

None.

#### **3.2.5.160.2.2 ObjectPath Methods**

None.

### **3.2.5.161 Microsoft.BusinessData.MetadataModel.Collections.TypeDescriptorCollection**

**TypeId:** {E33CCA95-E780-4A9E-8704-FEE069A29E02}

**ShortName:** SP.BusinessData.Collections.TypeDescriptorCollection

Represents a read only collection of type descriptors. [<166>](#)

### 3.2.5.161.1 Properties

#### 3.2.5.161.1.1 Scalar Properties

None.

#### 3.2.5.161.1.2 ObjectPath Properties

None.

### 3.2.5.161.2 Methods

#### 3.2.5.161.2.1 Scalar Methods

None.

#### 3.2.5.161.2.2 ObjectPath Methods

None.

### 3.2.5.162 Microsoft.BusinessData.MetadataModel.EntityField

**TypeId:** {2EA29BD5-5A5E-407C-A956-BA7BABC6DCC7}

**ShortName:** SP.BusinessData.EntityField

Represents a data element in a **view**. [<167>](#)

### 3.2.5.162.1 Properties

#### 3.2.5.162.1.1 Scalar Properties

##### 3.2.5.162.1.1.1 ContainsLocalizedDisplayName

**Type:** CSOM Boolean

**Accessibility:** Read Only

Specifies whether the **EntityField** (section [3.2.5.162](#)) contains a localized display name.

##### 3.2.5.162.1.1.2 DefaultDisplayName

**Type:** CSOM String

**Accessibility:** Read Only

Specifies the default display name of the **EntityField** (section [3.2.5.162](#)).

##### 3.2.5.162.1.1.3 LocalizedDisplayName

**Type:** CSOM String

**Accessibility:** Read Only

Specifies the localized display name of the **EntityField** (section [3.2.5.162](#)).

#### **3.2.5.162.1.1.4 Name**

**Type:** CSOM String

**Accessibility:** Read Only

Retrieves the name of the **EntityField** (section [3.2.5.162](#)).

It MUST NOT be NULL. It MUST NOT be empty.

#### **3.2.5.162.1.2ObjectPath Properties**

None.

#### **3.2.5.162.2 Methods**

##### **3.2.5.162.2.1Scalar Methods**

None.

##### **3.2.5.162.2.2ObjectPath Methods**

None.

### **3.2.5.163 Microsoft.BusinessData.MetadataModel.EntityView**

**TypeId:** {971264EB-8186-4B1D-9FB0-F3F9D2BDFB66}

**ShortName:** SP.BusinessData.EntityView

An **EntityView** represents a collection of **fields (2)**.[<168>](#)

#### **3.2.5.163.1 Properties**

##### **3.2.5.163.1.1Scalar Properties**

###### **3.2.5.163.1.1.1 Name**

**Type:** CSOM String

**Accessibility:** Read Only

Specifies the name of the **EntityView** (section [3.2.5.163](#)).

###### **3.2.5.163.1.1.2 RelatedSpecificFinderName**

**Type:** CSOM String

**Accessibility:** Read Only

Specifies name of the **SpecificFinder** method instance of this **EntityView** (section [3.2.5.163](#)).

If the **view** contains a set of **fields (2)** that are not completely addressed by any of the **Finders** in the **external content type**, then this property MUST return null.

##### **3.2.5.163.1.2ObjectPath Properties**

### 3.2.5.163.1.2.1 Fields

**Type:** Microsoft.BusinessData.MetadataModel.Collections.EntityFieldCollection

**Accessibility:** Read Only

Specifies the collection of **fields (2)** in the **view**.

### 3.2.5.163.2 Methods

#### 3.2.5.163.2.1 Scalar Methods

##### 3.2.5.163.2.1.1 GetType

**Return Type:** CSOM String

Specifies the type descriptor for input field.

**Parameters:**

*fieldDotNotation*: The input field.

Type: CSOM String

**Exceptions:**

Error Code	Error Type Name	Condition
-2147467261	System.ArgumentNullException	<i>fieldDotNotation</i> is <b>null</b> .
-1	System.InvalidOperationException	Type descriptor with the given field does not exist.

##### 3.2.5.163.2.1.2 GetXmlSchema

**Return Type:** CSOM String

Gets the **XML schema** of the **view**.

The schema returned from this method can be used to generate a user interface form to display or edit the data that corresponds to this view.

The XML namespace specified by the XML schema is implementation-specific. The XML schema MUST specify the root element that corresponds to the View. The name of the root element MUST be equal to the name of the View. The root element MUST contain exactly one **XML element** for each of the **field (2)** in the View. The XML element is declared based on the TypeDescriptors that correspond to field (2).

**Parameters:** None

#### 3.2.5.163.2.2 ObjectPath Methods

##### 3.2.5.163.2.2.1 GetDefaultValues

**Return Type:** Microsoft.BusinessData.Runtime.EntityFieldValueDictionary

Gets a **EntityFieldValueDictionary** (section [3.2.5.164](#)) that contains the default values for this **view**.

**Parameters:** None

### 3.2.5.163.2.2.2 GetTypeDescriptor

**Return Type:** Microsoft.BusinessData.MetadataModel.TypeDescriptor

Gets the **TypeDescriptor** (section [3.2.5.180](#)) object that corresponds to the given field name.

**Parameters:**

*fieldDotNotation:* The given field name.

Type: **CSOM String**

**Exceptions:**

Error Code	Error Type Name	Condition
-2147467261	System.ArgumentNullException	<i>fieldDotNotation</i> is <b>null</b> .
-1	System.InvalidOperationException	Type descriptor with the given field name does not exist.

### 3.2.5.164 Microsoft.BusinessData.Runtime.EntityFieldValueDictionary

**TypeId:** {5BC2B16A-0BEE-449A-9EF0-8A504CA2AD22}

**ShortName:** SP.BusinessData.Runtime.EntityFieldValueDictionary

Specifies the **field (2)** value dictionary for data exchange. [<169>](#) The field is specified using dot notation, which is a representation of the data elements similar to accessing data elements in C#. Each data element is accessed by providing their parent data element and the name of the data element if the containing data element is a structure, or the index of the data element, if the containing element is a collection.

#### 3.2.5.164.1 Properties

##### 3.2.5.164.1.1 Scalar Properties

None.

##### 3.2.5.164.1.2 ObjectPath Properties

None.

#### 3.2.5.164.2 Methods

##### 3.2.5.164.2.1 Scalar Methods

###### 3.2.5.164.2.1.1 CreateCollectionInstance

**Return Type:** None

Creates and initializes a new instance of the collection specified by the field name.

**Parameters:**



*fieldDotNotation*: The path to the collection.

Type: **CSOM String**

It MUST NOT be NULL. It MUST NOT be empty.

*size*: The size of the collection.

Type: **CSOM Int32**

Its value MUST be equal to or greater than 0.

**Exceptions:**

Error Code	Error Type Name	Condition
-2147467261	System.ArgumentNullException	<i>fieldDotNotation</i> is <b>null</b> or empty.
-1	System.InvalidOperationException	Type descriptor with the given field name does not exist.

### 3.2.5.164.2.1.2 CreateInstance

**Return Type:** None

Creates and initializes a new instance of the object specified by the given field name.

**Parameters:**

*fieldInstanceDotNotation*: The path to the instance of the object to create.

Type: **CSOM String**

It MUST NOT be NULL. It MUST NOT be empty.

*fieldDotNotation*: The path to the object.

Type: CSOM String

It MUST NOT be NULL. It MUST NOT be empty.

**Exceptions:**

Error Code	Error Type Name	Condition
-2147467261	System.ArgumentNullException	At least one of the given field name is <b>null</b> or empty.
-1	System.InvalidOperationException	Type descriptor with the given field name does not exist.

### 3.2.5.164.2.1.3 FromXml

**Return Type:** None

Sets the value in the **field (2)** value dictionary (section [3.2.5.164](#)) from the given **XML**.

**Parameters:**

*xml*: A string containing the XML data.

Type: **CSOM String**

An example of the XML format is specified in section [3.2.5.164.2.1.6](#).

It MUST NOT be empty.

It MUST NOT be NULL.

**Exceptions:**

Error Code	Error Type Name	Condition
-2147467261	System.ArgumentNullException	Input XML is <b>null</b> or empty.

### 3.2.5.164.2.1.4 GetCollectionSize

**Return Type:** **CSOM Int32**

Returns the size of the collection specified by the field name.

**Parameters:**

*fieldDotNotation*: The path to the collection.

Type: **CSOM String**

It MUST NOT be NULL. It MUST NOT be empty.

**Exceptions:**

Error Code	Error Type Name	Condition
-2147467261	System.ArgumentNullException	<i>fieldDotNotation</i> is <b>null</b> or empty.
-1	System.InvalidOperationException	Type descriptor with the given dot notation doesn't exist.

### 3.2.5.164.2.1.5 SetFieldValue

**Return Type:** None

Sets a value in the **field (2)** value dictionary.

**Parameters:**

*fieldDotNotation*: The input field name.

Type: **CSOM String**

*value*: Value to be set.

Type: **CSOM Object**

**Exceptions:**

Error Code	Error Type Name	Condition
-2147467261	System.ArgumentNullException	<i>fieldDotNotation</i> is <b>null</b> or empty.
-1	System.InvalidOperationException	Type descriptor with the given field name does not exist.

### 3.2.5.164.2.1.6 ToXml

**Return Type:** CSOM String

Returns the value in the **field (2)** value dictionary in **XML**.

The XML output is implementation-specific. One such example of the XML output having four values in the EntityFieldValueDictionary is the following:

```
<GenericEntityGenericInvoker
xmlns="http://tempuri.org/XMLSchema.xsd/Microsoft.Lobi.WCFModel">
<DoubleValue>555</DoubleValue>
<FloatValue>5</FloatValue>
<IntValue>55</IntValue>
<ShortValue>105</ShortValue>
</GenericEntityGenericInvoker>
```

**Parameters:** None

### 3.2.5.164.2.2 ObjectPath Methods

None.

### 3.2.5.165 Microsoft.BusinessData.Runtime.EntityIdentity

**TypeId:** {36C08DBD-02E6-493E-99F5-DF3F18342F85}

**ShortName:** SP.BusinessData.Runtime.EntityIdentity

Specifies a metadata for **Entity** identity. [<170>](#)

#### 3.2.5.165.1 Properties

##### 3.2.5.165.1.1 Scalar Properties

##### 3.2.5.165.1.1.1 IdentifierCount

**Type:** CSOM Int32

**Accessibility:** Read Only

Specifies the count of the identifiers.

##### 3.2.5.165.1.2 ObjectPath Properties

None.

#### 3.2.5.165.2 Methods

### 3.2.5.165.2.1 Scalar Methods

None.

### 3.2.5.165.2.2 ObjectPath Methods

#### 3.2.5.165.2.2.1 CSOM Constructor

Initializes a new instance from one or more identifier values. These identifiers uniquely identify an entity instance.

For example, a Customer entity can have Customer First Name and Customer Last Name as identifiers.

#### Parameters:

*identifierValues*: identifier values.

Type: **CSOM array** of **CSOM Object**

### 3.2.5.166 Microsoft.BusinessData.Runtime.EntityInstance

**TypeId**: {C75B5D2D-1E0C-41E2-89D1-A3B6016AC9CE}

**ShortName**: SP.BusinessData.Runtime.EntityInstance

Represents instances of business objects and data associated with the object. [<171>](#) For example, customer and order information in a **back-end database server** business application.

#### 3.2.5.166.1 Properties

##### 3.2.5.166.1.1 Scalar Properties

None.

##### 3.2.5.166.1.2 ObjectPath Properties

None.

#### 3.2.5.166.2 Methods

##### 3.2.5.166.2.1 Scalar Methods

###### 3.2.5.166.2.1.1 CreateCollectionInstance

**Return Type**: None

Creates and initializes a new instance of the collection specified by the given field name.

#### Parameters:

*fieldDotNotation*: The path to the collection.

Type: **CSOM String**

*size*: The size of the collection.

Type: **CSOM Int32**

**Exceptions:**

Error Code	Error Type Name	Condition
-2147467261	System.ArgumentNullException	<i>fieldDotNotation</i> is <b>null</b> or empty.
-1	System.InvalidOperationException	Type descriptor with the given field name does not exist.

**3.2.5.166.2.1.2 CreateInstance****Return Type:** None

Creates and initializes a new instance of the object referred by the given field name.

**Parameters:***fieldInstanceDotNotation*: The path to the instance of the object to create.Type: **CSOM String***fieldDotNotation*: The path to the object.

Type: CSOM String

**Exceptions:**

Error Code	Error Type Name	Condition
-2147467261	System.ArgumentNullException	At least one of the given field names is <b>null</b> or empty.
-1	System.InvalidOperationException	Type descriptor with the given field name does not exist.

**3.2.5.166.2.1.3 DeleteObject****Return Type:** NoneDeletes this **EntityInstance** (section [3.2.5.166](#)).**Parameters:** None**Exceptions:**

Error Code	Error Type Name	Condition
-1	Microsoft.BusinessData.Infrastructure.AccessDeniedException	User does not have permission to delete the external item.
-1	Microsoft.BusinessData.Runtime.ObjectNotFoundException	The item to delete does not exist anymore.

**3.2.5.166.2.1.4 FromXml****Return Type:** None

Specifies the value in **EntityInstance** dictionary from given **XML**.

**Parameters:**

*xml*: A string containing the XML value.

Type: **CSOM String**

An example of the XML format is specified in section [3.2.5.164.2.1.6](#).

**Exceptions:**

Error Code	Error Type Name	Condition
-2147467261	System.ArgumentNullException	Input XML is <b>null</b> or empty.

### 3.2.5.166.2.1.5 SetFieldValue

**Return Type:** None

Method to set value.

**Parameters:**

*fieldDotNotation*: The input **field (2)** name.

Type: **CSOM String**

*value*: Value to be set.

Type: **CSOM Object**

**Exceptions:**

Error Code	Error Type Name	Condition
-2147467261	System.ArgumentNullException	<i>fieldDotNotation</i> is <b>null</b> or empty.
-1	System.InvalidOperationException	Type descriptor with the given field name does not exist.

### 3.2.5.166.2.1.6 ToXml

**Return Type:** **CSOM String**

Returns methods and properties defined in **EntityInstance** (section [3.2.5.166](#)) in **XML** format.

An example of XML output format is specified in section [3.2.5.164.2.1.6](#)

**Parameters:** None

### 3.2.5.166.2.1.7 Update

**Return Type:** None

Invokes the update method for this **EntityInstance** (section [3.2.5.166](#)).

**Parameters:** None

## Exceptions:

Error Code	Error Type Name	Condition
-1	Microsoft.BusinessData.Infrastructure.AccessDeniedException	User does not have permission to update the external item.
-1	Microsoft.BusinessData.Runtime.ObjectNotFoundException	The item to update does not exist anymore.

## 3.2.5.166.2 ObjectPath Methods

### 3.2.5.166.2.2.1 GetIdentity

**Return Type:** Microsoft.BusinessData.Runtime.EntityIdentity

Returns the identity of this **EntityInstance** (section [3.2.5.166](#)).

**Parameters:** None

### 3.2.5.167 Microsoft.SharePoint.Client.AlternateUrl

**TypeId:** {19E49AB8-90D1-44E1-B186-FACE114707F5}

**ShortName:** SP.AlternateUrl

Encapsulates a **URL** and the zone with which it is associated. [<172>](#)

#### 3.2.5.167.1 Properties

##### 3.2.5.167.1.1 Scalar Properties

###### 3.2.5.167.1.1.1 Uri

**Type:** CSOM String

**Accessibility:** Read Only

Identical to the incoming **URL**, but in **URI** form.

###### 3.2.5.167.1.1.2 UrlZone

**Type:** Microsoft.SharePoint.Client.UrlZone

**Accessibility:** Read Only

Specifies the zone associated with this **URL**.

##### 3.2.5.167.1.2 ObjectPath Properties

None.

#### 3.2.5.167.2 Methods

##### 3.2.5.167.2.1 Scalar Methods

None.

### **3.2.5.167.2.2ObjectPath Methods**

None.

### **3.2.5.168 Microsoft.SharePoint.Client.Analytics.EventTypeId**

**ShortName:** SP.Analytics.EventTypeId

**Flag:** false

Specifies the type of an analytics event. [<173>](#)

#### **3.2.5.168.1 Field Values**

##### **3.2.5.168.1.1View**

**Value:** 1

Specifies an event associated with viewing an **item**.

##### **3.2.5.168.1.2First**

**Value:** 1

Reserved. This value will be removed in a future iteration of the protocol.

##### **3.2.5.168.1.3RecommendationView**

**Value:** 2

Specifies the event associated with displaying an **item** recommendation.

##### **3.2.5.168.1.4RecommendationClick**

**Value:** 3

Specifies the event associated with following an **item** recommendation.

##### **3.2.5.168.1.5Last**

**Value:** 3

Reserved. This value will be removed in a future iteration of the protocol.

##### **3.2.5.168.1.6None**

**Value:** 0

Specifies an event type that is not valid.

### **3.2.5.169 Microsoft.SharePoint.Client.Attachment**

**TypeId:** {ABD102DE-1731-4BE2-AE7E-3515371CC5C7}

**ShortName:** SP.Attachment



Specifies a **list item attachment**.[<174>](#)

### **3.2.5.169.1 Properties**

#### **3.2.5.169.1.1 Scalar Properties**

##### **3.2.5.169.1.1.1 ServerRelativeUrl**

**Type:** CSOM String

**Accessibility:** Read Only

Specifies the **server-relative URL** of a **list item attachment**.

##### **3.2.5.169.1.1.2 FileName**

**Type:** CSOM String

**Accessibility:** Read Only

Specifies the file name of the **list item attachment**.

##### **3.2.5.169.1.1.3 FileNameAsPath**

**Type:** Microsoft.SharePoint.Client.ResourcePath

**Accessibility:** Read Only

The file name of the attachment as a SP.ResourcePath.

##### **3.2.5.169.1.1.4 ServerRelativePath**

**Type:** Microsoft.SharePoint.Client.ResourcePath

**Accessibility:** Read Only

The server-relative-path of the attachment.

#### **3.2.5.169.1.2 ObjectPath Properties**

None.

### **3.2.5.169.2 Methods**

#### **3.2.5.169.2.1 Scalar Methods**

##### **3.2.5.169.2.1.1 DeleteObject**

**Return Type:** None

Deletes this **list item attachment**.

**Parameters:** None

##### **3.2.5.169.2.1.2 RecycleObject**

**Return Type:** None

Move this attachment to site recycle bin.

**Parameters:** None

### 3.2.5.169.2.2ObjectPath Methods

None.

### 3.2.5.170 Microsoft.SharePoint.Client.AttachmentCollection

**TypeId:** {F4E86471-7DAB-4B47-B061-50A40E27140E}

**ShortName:** SP.AttachmentCollection

Specifies a collection of **list item attachments**.<175>

#### 3.2.5.170.1 Properties

##### 3.2.5.170.1.1Scalar Properties

None.

##### 3.2.5.170.1.2ObjectPath Properties

None.

#### 3.2.5.170.2 Methods

##### 3.2.5.170.2.1Scalar Methods

None.

##### 3.2.5.170.2.2ObjectPath Methods

###### 3.2.5.170.2.2.1 Add

**Return Type:** Microsoft.SharePoint.Client.Attachment

Adds the **attachment** represented by the file name and stream in the specified parameter to the list item.

**Parameters:**

*parameters:* The creation information which contains file name and content stream.

Type: Microsoft.SharePoint.Client.AttachmentCreationInformation

It MUST NOT be NULL.

**Exceptions:**

Error Code	Error Type Name	Condition
- 2147024809	System.ArgumentException	The <b>ContentStream</b> property of <i>parameters</i> is NULL, or the <b>FileName</b> property of <i>parameters</i> is NULL or empty.
- 2147467261	System.ArgumentNullException	<i>parameters</i> is NULL.

### 3.2.5.170.2.2.2 AddUsingPath

**Return Type:** Microsoft.SharePoint.Client.Attachment

Adds the attachment represented by the file name and stream in the specified parameter to the list item.

**Parameters:**

*filename:* A **ResourcePath** object (section [3.2.5.420](#)) that specifies the path for the attachment file.

Type: Microsoft.SharePoint.Client.ResourcePath

It MUST NOT be NULL.

*contentStream:* Stream containing the content of the attachment.

Type: **CSOM Stream**

It MUST NOT be NULL.

**Exceptions:**

Error Code	Error Type Name	Condition
-2147467261	System.ArgumentNullException	filename MUST NOT be null.
-2147467261	System.ArgumentNullException	contentStream MUST NOT be null.

### 3.2.5.170.2.2.3 GetByFileName

**Return Type:** Microsoft.SharePoint.Client.Attachment

Returns the **list item attachment** with the specified file name.

**Parameters:**

*fileName:* The specified file name.

Type: **CSOM String**

### 3.2.5.170.2.2.4 GetByFileNameAsPath

**Return Type:** Microsoft.SharePoint.Client.Attachment

Get the attachment file.

**Parameters:**

*fileName:* The file name.

Type: Microsoft.SharePoint.Client.ResourcePath

## 3.2.5.171 Microsoft.SharePoint.Client.AttachmentCreationInformation

**TypeId:** {EDF6309C-8142-4133-921E-4D6AEC35550D}

**ShortName:** SP.AttachmentCreationInformation

Specifies a **list item attachment**.<176>

### 3.2.5.171.1 Properties

#### 3.2.5.171.1.1 Scalar Properties

##### 3.2.5.171.1.1.1 ContentStream

**Type:** CSOM Stream

**Accessibility:** Read/Write

The contents of the file as a **stream**.

##### 3.2.5.171.1.1.2 FileName

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies the file name of the **list item attachment**.

#### 3.2.5.171.1.2 ObjectPath Properties

None.

### 3.2.5.172 Microsoft.SharePoint.Client.ServerSettings

**TypeId:** {ADFA7B3E-A27C-4288-9B6C-A8EA51BF082D}

**ShortName:** SP.ServerSettings

Provides methods for obtaining protocol server properties that correspond to different **Web application** zones.<177>

### 3.2.5.172.1 Properties

#### 3.2.5.172.1.1 Scalar Properties

None.

#### 3.2.5.172.1.2 ObjectPath Properties

None.

### 3.2.5.172.2 Methods

#### 3.2.5.172.2.1 Scalar Methods

##### 3.2.5.172.2.1.1 GetBlockedFileExtensions

This method is a **static CSOM method**.

**Return Type:** CSOM array of CSOM String

Returns the blocked file extensions for the current **site (2)**.

**Parameters:** None

### 3.2.5.172.2.1.2 GetGlobalInstalledLanguages

This method is a **static CSOM method**.

**Return Type:** **CSOM array** of Microsoft.SharePoint.Client.Language

Returns the installed server languages for the current **site (2)**.

**Parameters:**

*compatibilityLevel*: Specifies the major version to request installed server languages for.

Type: **CSOM Int32**

### 3.2.5.172.2.1.3 IsSharePointOnline

This method is a **static CSOM method**.

**Return Type:** **CSOM Boolean**

If true the service is a SharePoint Online service; false if otherwise.

**Parameters:** None

## 3.2.5.172.2.2 ObjectPath Methods

### 3.2.5.172.2.2.1 GetAlternateUrls

This method is a **static CSOM method**.

**Return Type:** **CSOM array** of Microsoft.SharePoint.Client.AlternateUrl

Returns all **URLs** of the current **site (2)** along with the corresponding zone information.

**Parameters:** None

## 3.2.5.173 Microsoft.SharePoint.Client.WebProxy

**TypeId:** {656A77C4-1634-415C-BF85-C6C0CB286E0E}

**ShortName:** SP.WebProxy

Specifies an infrastructure for the protocol server to make outbound **Hypertext Transfer Protocol (HTTP)** requests based on parameters specified by the client. [<178>](#)

### 3.2.5.173.1 Properties

#### 3.2.5.173.1.1 Scalar Properties

None.

#### 3.2.5.173.1.2 ObjectPath Properties

None.

### 3.2.5.173.2 Methods

#### 3.2.5.173.2.1 Scalar Methods

### 3.2.5.173.2.1.1 Invoke

This method is a **static CSOM method**.

**Return Type:** Microsoft.SharePoint.Client.WebResponseInfo

Specifies that the protocol server SHOULD make an outbound **Hypertext Transfer Protocol (HTTP)** request using the specified parameters.

#### Parameters:

*requestInfo*: A **WebRequestInfo** (section [3.2.5.174](#)) object that contains the **URL**, headers and body of the request.

Type: Microsoft.SharePoint.Client.WebRequestInfo

### 3.2.5.173.2.2 ObjectPath Methods

None.

## 3.2.5.174 Microsoft.SharePoint.Client.WebRequestInfo

**TypeId:** {71AA825D-BC12-422D-A177-D2E63FE68CD9}

**ShortName:** SP.WebRequestInfo

Specifies metadata about a **Hypertext Transfer Protocol (HTTP)** request. [<179>](#)

### 3.2.5.174.1 Properties

#### 3.2.5.174.1.1 Scalar Properties

##### 3.2.5.174.1.1.1 Body

**Type:** **CSOM String**

**Accessibility:** Read/Write

The content of the request, as described in [\[RFC2616\]](#) section 4.3.

##### 3.2.5.174.1.1.2 Headers

**Type:** **CSOM dictionary**

**Accessibility:** Read/Write

The headers of the request, as described in [\[RFC2616\]](#) section 4.2.

##### 3.2.5.174.1.1.3 Method

**Type:** **CSOM String**

**Accessibility:** Read/Write

The **HTTP method** of the request, as described in [\[RFC2616\]](#) section 5.1.1.

It MUST NOT be empty.

##### 3.2.5.174.1.1.4 Url

**Type:** CSOM String

**Accessibility:** Read/Write

The target **URL** of the request.

It MUST be a URL of absolute form. Its length MUST be equal to or less than 255.

### 3.2.5.174.1.2 ObjectPath Properties

None.

## 3.2.5.175 Microsoft.SharePoint.Client.WebResponseInfo

**TypeId:** {73B6054A-AA40-41E4-A34F-5A6F898E6D4F}

**ShortName:** SP.WebResponseInfo

Specifies metadata about a **Hypertext Transfer Protocol (HTTP)** response. <180>

### 3.2.5.175.1 Properties

#### 3.2.5.175.1.1 Scalar Properties

##### 3.2.5.175.1.1.1 Body

**Type:** CSOM String

**Accessibility:** Read/Write

The content of the response, as described in [\[RFC2616\]](#) section 4.3.

##### 3.2.5.175.1.1.2 Headers

**Type:** CSOM dictionary

**Accessibility:** Read/Write

The headers of the response, as described in [\[RFC2616\]](#) section 4.2.

##### 3.2.5.175.1.1.3 StatusCode

**Type:** CSOM Int32

**Accessibility:** Read/Write

The **Status-Code** of the response, as described in [\[RFC2616\]](#) section 10.

### 3.2.5.175.1.2 ObjectPath Properties

None.

## 3.2.5.176 Microsoft.BusinessData.MetadataModel.Entity

**TypeId:** {493FB354-E4A4-4577-B7F4-64BB868C128E}

**ShortName:** SP.BusinessData.Entity

Specifies an **external content type** in a **line-of-business (LOB) system** application. <181>

## 3.2.5.176.1 Properties

### 3.2.5.176.1.1 Scalar Properties

#### 3.2.5.176.1.1.1 EstimatedInstanceCount

Type: **CSOM Int64**

Accessibility: Read Only

Specifies the number of expected external **items** associated with this external content type.

Its value MUST be equal to or greater than 0.

#### 3.2.5.176.1.1.2 Name

Type: **CSOM String**

Accessibility: Read Only

Specifies the name of the metadata object.

It MUST NOT be NULL. It MUST NOT be empty.

#### 3.2.5.176.1.1.3 Namespace

Type: **CSOM String**

Accessibility: Read Only

Specifies the namespace of the given **Entity** (section [3.2.5.176](#)).

It MUST NOT be NULL. It MUST NOT be empty.

### 3.2.5.176.1.2 ObjectPath Properties

None.

## 3.2.5.176.2 Methods

### 3.2.5.176.2.1 Scalar Methods

#### 3.2.5.176.2.1.1 GetIdentifierCount

Return Type: **CSOM Int32**

Specifies the number of identifiers in an **external content type**.

Parameters: None

#### 3.2.5.176.2.1.2 Unsubscribe

Return Type: None

Calls to the external system indicating that the event notification is no longer required for this entity and event type.

Parameters:



*subscription*: The subscription registration information returned as part of the **Subscriber** stereotype call on the external content type.

Type: Microsoft.BusinessData.Runtime.Subscription

It MUST NOT be NULL.

*onBehalfOfUser*: The name or identifier of the user for whom the unsubscribe operation is performed.

Type: **CSOM String**

*unsubscribeName*: The name of the **EventUnsubscriber** method instance.

Type: CSOM String

It MUST NOT be NULL. It MUST NOT be empty.

*lobSystemInstance*: The external system instance.

Type: Microsoft.BusinessData.MetadataModel.LobSystemInstance

It MUST NOT be NULL.

#### Exceptions:

Error Code	Error Type Name	Condition
-1	Microsoft.BusinessData.Infrastructure.AccessDeniedException	User does not have permissions to unsubscribe.
-2147467261	System.ArgumentNullException	At least one of the parameters is null.
-2147024891	System.UnauthorizedAccessException	User does not have permissions to unsubscribe.

### 3.2.5.176.2.2 ObjectPath Methods

#### 3.2.5.176.2.2.1 Create

**Return Type:** Microsoft.BusinessData.Runtime.EntityIdentity

Creates an external item.

Use this method to create external items in the external system by specifying the values required for creation. The values do not necessarily correspond to fields of an external item.

The method returns the **EntityIdentity** (section [3.2.5.165](#)) that corresponds to the external item that was created.

The **EntityFieldValueDictionary** (section [3.2.5.164](#)) instance provided as an input to this method is created from a **View** that corresponds to a **MethodInstance** of type **Creator**.

#### Parameters:

*fieldValues*: The parameters of the **Create** method.

Type: Microsoft.BusinessData.Runtime.EntityFieldValueDictionary

It MUST NOT be NULL.

*lobSystemInstance*: The **line-of-business (LOB) system** instance.

Type: Microsoft.BusinessData.MetadataModel.LobSystemInstance

It MUST NOT be NULL.

**Exceptions:**

Error Code	Error Type Name	Condition
-1	Microsoft.BusinessData.Infrastructure.AccessDeniedException	User does not have permissions to create an external item.
-1	Microsoft.BusinessData.MetadataModel.InvalidMetadataObjectException	Creator MethodInstances cannot return collections.
-1	System.InvalidOperationException	The <b>Create</b> method does not have a return value. A proper <b>EntityIdentity</b> object MUST be supplied for the <b>Create</b> function.

**3.2.5.176.2.2.2 FindSpecific**

**Return Type:** Microsoft.BusinessData.Runtime.EntityInstance

Retrieves the external item corresponding to the identity by calling the given **SpecificFinder** method.

**Parameters:**

*identity*: The given identity.

Type: Microsoft.BusinessData.Runtime.EntityIdentity

It MUST NOT be NULL.

*specificFinderName*: SpecificFinder method name.

Type: **CSOM String**

It MUST NOT be NULL. It MUST NOT be empty.

*lobSystemInstance*: The **line-of-business (LOB) system** instance.

Type: Microsoft.BusinessData.MetadataModel.LobSystemInstance

It MUST NOT be NULL.

**Exceptions:**

Error Code	Error Type Name	Condition
-1	Microsoft.BusinessData.Infrastructure.AccessDeniedException	User does not have permissions to read an external item.
-1	Microsoft.BusinessData.MetadataModel.MetadataObjectNotFoundException	There is no SpecificFinder

Error Code	Error Type Name	Condition
		method available with the given name.
-1	Microsoft.BusinessData.Runtime.ObjectNotFoundException	An external item with the given identity does not exist.

### 3.2.5.176.2.2.3 FindSpecificByBdcId

**Return Type:** Microsoft.BusinessData.Runtime.EntityInstance

Retrieves the external item corresponding to the **Business Data Connectivity (BDC)** identity by calling the given **SpecificFinder** method.

**Parameters:**

*bdcIdentity*: Unique identity string for external item

Type: **CSOM String**

BdcIdentity is a unique identity string generated by **Business Connectivity Services (BCS)** from the entity identifiers to uniquely identify an external item.

It MUST NOT be NULL. It MUST NOT be empty.

*specificFinderName*: Name of the SpecificFinder method.

Type: CSOM String

It MUST NOT be NULL. It MUST NOT be empty.

*lobSystemInstance*: The **line-of-business (LOB) system** instance

Type: Microsoft.BusinessData.MetadataModel.LobSystemInstance

It MUST NOT be NULL.

**Exceptions:**

Error Code	Error Type Name	Condition
-1	Microsoft.BusinessData.Infrastructure.AccessDeniedException	User does not have permissions to read an external item.
-1	Microsoft.BusinessData.MetadataModel.MetadataObjectNotFoundException	There is no SpecificFinder available with the given name.
-1	Microsoft.BusinessData.Runtime.ObjectNotFoundException	An external item with the given id does not exist.

### 3.2.5.176.2.2.4 FindSpecificDefault

**Return Type:** Microsoft.BusinessData.Runtime.EntityInstance

Retrieves the external item corresponding to the identity by calling the default **SpecificFinder** method.

**Parameters:**

*identity:* The given **EntityIdentity** (section [3.2.5.165](#)).

Type: Microsoft.BusinessData.Runtime.EntityIdentity

It MUST NOT be NULL.

*lobSystemInstance:* The **line-of-business (LOB) system** instance.

Type: Microsoft.BusinessData.MetadataModel.LobSystemInstance

It MUST NOT be NULL.

**Exceptions:**

Error Code	Error Type Name	Condition
-1	Microsoft.BusinessData.Infrastructure.AccessDeniedException	User does not have permissions to read an external item.
-1	Microsoft.BusinessData.Runtime.ObjectNotFoundException	An external item with the given identity does not exist.

### 3.2.5.176.2.2.5 FindSpecificDefaultByBdcId

**Return Type:** Microsoft.BusinessData.Runtime.EntityInstance

Retrieves the external item corresponding to the **Business Data Connectivity (BDC)** identity by calling the default **SpecificFinder** method.

**Parameters:**

*bdcIdentity:* The given Business Data Connectivity (BDC) identity.

Type: **CSOM String**

It MUST NOT be NULL. It MUST NOT be empty.

*lobSystemInstance:* The external system instance.

Type: Microsoft.BusinessData.MetadataModel.LobSystemInstance

It MUST NOT be NULL.

**Exceptions:**

Error Code	Error Type Name	Condition
-1	Microsoft.BusinessData.Infrastructure.AccessDeniedException	User does not have permissions to read an external item.

Error Code	Error Type Name	Condition
-1	Microsoft.BusinessData.Runtime.ObjectNotFoundException	An external item with the given identifier does not exist.

### 3.2.5.176.2.2.6 GetCreatorView

**Return Type:** Microsoft.BusinessData.MetadataModel.EntityView

Gets the **View** for the given **Creator** method instance.

**Parameters:**

*methodName*: **MethodInstance** name

Type: **CSOM String**

It MUST NOT be NULL. It MUST NOT be empty.

**Exceptions:**

Error Code	Error Type Name	Condition
-1	Microsoft.BusinessData.MetadataModel.MetadataObjectNotFoundException	View with the given MethodInstance name cannot be found.

### 3.2.5.176.2.2.7 GetDefaultSpecificFinderView

**Return Type:** Microsoft.BusinessData.MetadataModel.EntityView

Gets the **View** for the default **SpecificFinder** method.

**Parameters:** None

**Exceptions:**

Error Code	Error Type Name	Condition
-1	Microsoft.BusinessData.MetadataModel.MetadataObjectNotFoundException	Default SpecificFinder cannot be found.

### 3.2.5.176.2.2.8 GetIdentifiers

**Return Type:** Microsoft.BusinessData.MetadataModel.Collections.EntityIdentifierCollection

Specifies the identifier parameters of an **external content type**.

Returns a read only collection of identifiers.

**Parameters:** None

### 3.2.5.176.2.2.9 GetLobSystem

**Return Type:** Microsoft.BusinessData.MetadataModel.LobSystem

Specifies **line-of-business (LOB) system** for an **external content type**.

**Parameters:** None

### 3.2.5.176.2.2.10 GetSpecificFinderView

**Return Type:** Microsoft.BusinessData.MetadataModel.EntityView

Specifies the **View** for the given **SpecificFinder** method.

**Parameters:**

*specificFinderName:* The name of the SpecificFinder.

Type: **CSOM String**

It MUST NOT be NULL. It MUST NOT be empty.

**Exceptions:**

Error Code	Error Type Name	Condition
-1	Microsoft.BusinessData.MetadataModel.MetadataObjectNotFoundException	View with the given method name cannot be found.

### 3.2.5.176.2.2.11 GetUpdaterView

**Return Type:** Microsoft.BusinessData.MetadataModel.EntityView

Specifies the **View** for the given **Updater** method.

**Parameters:**

*updaterName:* Updater name.

Type: **CSOM String**

It MUST NOT be NULL. It MUST NOT be empty.

**Exceptions:**

Error Code	Error Type Name	Condition
-1	Microsoft.BusinessData.MetadataModel.MetadataObjectNotFoundException	View with the given method name cannot be found.

### 3.2.5.176.2.2.12 FindAssociated

**Return Type:** Microsoft.BusinessData.MetadataModel.Collections.EntityInstanceCollection

Specifies the external items that are associated with a source external item using an association that is filtered by specified criteria.

**Parameters:**

*entityInstance*: Source **Business Data Connectivity (BDC)** external item.

Type: Microsoft.BusinessData.Runtime.EntityInstance

It MUST NOT be NULL.

*associationName*: The association name to use.

Type: **CSOM String**

It MUST NOT be NULL. It MUST NOT be empty.

*filterList*: The filters to apply.

Type: Microsoft.BusinessData.MetadataModel.Collections.FilterCollection

It MUST NOT be NULL.

*lobSystemInstance*: The **line-of-business (LOB) system** instance.

Type: Microsoft.BusinessData.MetadataModel.LobSystemInstance

It MUST NOT be NULL.

**Exceptions:**

Error Code	Error Type Name	Condition
-1	Microsoft.BusinessData.Infrastructure.AccessDeniedException	User does not have permissions to read an external item.
-1	Microsoft.BusinessData.MetadataModel.MetadataObjectNotFoundException	There is no association available with the given name.
-1	Microsoft.BusinessData.Runtime.ObjectNotFoundException	An external item with the given identifier does not exist.

**3.2.5.176.2.2.13 FindFiltered**

**Return Type:** Microsoft.BusinessData.MetadataModel.Collections.EntityInstanceCollection

Calls the given SpecificFinder method with the specified filters to retrieve a collection of items from the external **Business Data Connectivity (BDC)** system.

A protocol client SHOULD use a set of filters to narrow and constrain the set of items returned. Set filters using **FilterCollection** (section [3.2.5.199](#)) to filter the data returned by the external system.

**Parameters:**

*filterList*: The filters to apply.

Type: Microsoft.BusinessData.MetadataModel.Collections.FilterCollection

It MUST NOT be NULL.

*nameOfFinder*: The name of the **SpecificFinder**.

Type: **CSOM String**

It MUST NOT be NULL. It MUST NOT be empty.

*lobSystemInstance*: The **line-of-business (LOB) system** instance

Type: Microsoft.BusinessData.MetadataModel.LobSystemInstance

It MUST NOT be NULL.

**Exceptions:**

Error Code	Error Type Name	Condition
-1	Microsoft.BusinessData.Infrastructure.AccessDeniedException	User does not have permissions to read an external item.
-1	Microsoft.BusinessData.MetadataModel.MetadataObjectNotFoundException	There is no finder available with the given name.
-1	Microsoft.BusinessData.Runtime.ObjectNotFoundException	An external item with the given identifier does not exist.

**3.2.5.176.2.2.14 GetAssociationView**

**Return Type:** Microsoft.BusinessData.MetadataModel.EntityView

Specifies the **View** of the association.

**Parameters:**

*associationName*: The name of the association.

Type: **CSOM String**

It MUST NOT be NULL. It MUST NOT be empty.

**Exceptions:**

Error Code	Error Type Name	Condition
-1	Microsoft.BusinessData.MetadataModel.MetadataObjectNotFoundException	There is no association available with the given name.

**3.2.5.176.2.2.15 GetFilters**



**Return Type:** Microsoft.BusinessData.MetadataModel.Collections.FilterCollection

Specifies the list of filters defined for a given **MethodInstance** name.

**Parameters:**

*methodInstanceName:* MethodInstance name.

Type: **CSOM String**

It MUST NOT be NULL. It MUST NOT be empty.

**Exceptions:**

Error Code	Error Type Name	Condition
-1	Microsoft.BusinessData.MetadataModel.MetadataObjectNotFoundException	MethodInstance with the given name cannot be found.

**3.2.5.176.2.2.16 Execute**

**Return Type:** Microsoft.BusinessData.MetadataModel.MethodExecutionResult

Runs the given method instance against an external **line-of-business (LOB) system** instance with the given parameters.

**Parameters:**

*methodInstanceName:* The **MethodInstance** name.

Type: **CSOM String**

It MUST NOT be NULL. It MUST NOT be empty.

*lobSystemInstance:* The line-of-business (LOB) system instance.

Type: Microsoft.BusinessData.MetadataModel.LobSystemInstance

It MUST NOT be NULL.

*inputParams:* The arguments to pass to the external system. The *inputParams* array MUST have as many elements as there are parameters in the **Business Data Connectivity (BDC)** model for that method.

Type: **CSOM array of CSOM Object**

**Exceptions:**

Error Code	Error Type Name	Condition
-1	Microsoft.BusinessData.Infrastructure.AccessDeniedException	User does not have permissions to read an external item.
-1	Microsoft.BusinessData.MetadataModel.MetadataObjectNotFoundException	There is no MethodInstance available with the

Error Code	Error Type Name	Condition
		given name.
-1	Microsoft.BusinessData.Runtime.ObjectNotFoundException	An external item with the given input does not exist.
-2147024809	System.ArgumentException	Set of parameters provided do not exactly match what is defined by the metadata or execution result produces a collection as per the Business Data Connectivity (BDC) model but not enumerable.

### 3.2.5.176.2.2.17 GetFinderView

**Return Type:** Microsoft.BusinessData.MetadataModel.EntityView

Specifies the **View** for the given finder method.

**Parameters:**

*methodInstanceName*: finder **MethodInstance** name.

Type: **CSOM String**

It MUST NOT be NULL. It MUST NOT be empty.

**Exceptions:**

Error Code	Error Type Name	Condition
-1	Microsoft.BusinessData.MetadataModel.MetadataObjectNotFoundException	View with the given method name cannot be found.

### 3.2.5.176.2.2.18 Subscribe

**Return Type:** Microsoft.BusinessData.Runtime.Subscription

Subscribes the given notification endpoint with the external system to receive notifications.

**Parameters:**

*eventType*: The event type to subscribe.

Type: Microsoft.BusinessData.Runtime.EntityEventType

*notificationCallback*: The details related to the endpoint that will receive notifications in response to this subscription request.

Type: Microsoft.BusinessData.Runtime.NotificationCallback

It MUST NOT be NULL.

*onBehalfOfUser*: The name or id of the user for whom subscription is made.

Type: **CSOM String**

*subscriberName*: The name of **Subscriber** method instance.

Type: CSOM String

It MUST NOT be NULL. It MUST NOT be empty.

*lobSystemInstance*: The external **line-of-business (LOB) system** instance.

Type: Microsoft.BusinessData.MetadataModel.LobSystemInstance

It MUST NOT be NULL.

#### Exceptions:

Error Code	Error Type Name	Condition
-1	Microsoft.BusinessData.Infrastructure.AccessDeniedException	User does not have permissions to create a subscription.
-2147467261	System.ArgumentNullException	At least one of the parameters is null
-2147024891	System.UnauthorizedAccessException	User does not have permissions to create a subscription.

### 3.2.5.177 Microsoft.BusinessData.MetadataModel.EntityIdentifier

**TypeId**: {86B6671B-E6E1-4F99-AA9D-D7A3FFBD6C16}

**ShortName**: SP.BusinessData.EntityIdentifier

Defines the properties of an **external content type** identifier. <182>

#### 3.2.5.177.1 Properties

##### 3.2.5.177.1.1 Scalar Properties

###### 3.2.5.177.1.1.1 IdentifierType

Type: **CSOM String**

**Accessibility**: Read Only

Specifies the type of this **EntityIdentifier** (section [3.2.5.177](#)) as a string value.

###### 3.2.5.177.1.1.2 Name

Type: **CSOM String**

**Accessibility**: Read Only

Specifies the name of the **EntityIdentifier** (section [3.2.5.177](#)).

### 3.2.5.177.1.2 ObjectPath Properties

None.

### 3.2.5.177.2 Methods

#### 3.2.5.177.2.1 Scalar Methods

##### 3.2.5.177.2.1.1 ContainsLocalizedDisplayName

**Return Type:** CSOM Boolean

Specifies whether this **EntityIdentifier** (section [3.2.5.177](#)) contains a localized display name.

**Parameters:** None

##### 3.2.5.177.2.1.2 GetDefaultDisplayName

**Return Type:** CSOM String

Specifies the default display name of this **EntityIdentifier** (section [3.2.5.177](#)).

**Parameters:** None

##### 3.2.5.177.2.1.3 GetLocalizedDisplayName

**Return Type:** CSOM String

Specifies the localized display name of this **EntityIdentifier** (section [3.2.5.177](#)).

**Parameters:** None

#### Exceptions:

Error Code	Error Type Name	Condition
-1	Microsoft.BusinessData.MetadataModel.InvalidMetadataObjectException	Localized display name for current locale does not exist.

### 3.2.5.177.2.2 ObjectPath Methods

None.

### 3.2.5.178 Microsoft.BusinessData.MetadataModel.LobSystem

**TypeId:** {84EFF1C0-D351-441F-A57F-F73A0785CCEC}

**ShortName:** SP.BusinessData.LobSystem

Represents an external **line-of-business (LOB) system**.[<183>](#)

#### 3.2.5.178.1 Properties

### 3.2.5.178.1.1 Scalar Properties

#### 3.2.5.178.1.1.1 Name

Type: **CSOM String**

Accessibility: Read Only

Specifies the name of the external **LobSystem** (section [3.2.5.178](#)).

### 3.2.5.178.1.2 ObjectPath Properties

None.

### 3.2.5.178.2 Methods

#### 3.2.5.178.2.1 Scalar Methods

None.

#### 3.2.5.178.2.2 ObjectPath Methods

##### 3.2.5.178.2.2.1 GetLobSystemInstances

**Return Type:** Microsoft.BusinessData.MetadataModel.Collections.LobSystemInstanceCollection

Specifies the instances of this external **LobSystem** (section [3.2.5.178](#)).

**Parameters:** None

### 3.2.5.179 Microsoft.BusinessData.MetadataModel.LobSystemInstance

**TypeId:** {A59E617A-FED3-4C3F-8B2C-BB11EDBF7827}

**ShortName:** SP.BusinessData.LobSystemInstance

Specifies an instance of an external **line-of-business (LOB) system**.[<184>](#)

### 3.2.5.179.1 Properties

#### 3.2.5.179.1.1 Scalar Properties

##### 3.2.5.179.1.1.1 Name

Type: **CSOM String**

Accessibility: Read Only

Specifies the name of the external **line-of-business (LOB) system** instance.

### 3.2.5.179.1.2 ObjectPath Properties

None.

### 3.2.5.179.2 Methods

#### 3.2.5.179.2.1 Scalar Methods

None.

### 3.2.5.179.2.2 ObjectPath Methods

None.

### 3.2.5.180 Microsoft.BusinessData.MetadataModel.TypeDescriptor

**TypeId:** {D981A4B4-5FBD-4C46-9101-5C5E67D4AB3B}

**ShortName:** SP.BusinessData.TypeDescriptor

Describes a data structure in an external system. [<185>](#) It represents the data type for a method parameter in the **Business Data Connectivity (BDC) MetadataCatalog**.

#### 3.2.5.180.1 Properties

##### 3.2.5.180.1.1 Scalar Properties

###### 3.2.5.180.1.1.1 ContainsReadOnly

**Type:** CSOM Boolean

**Accessibility:** Read Only

Specifies whether this **TypeDescriptor** or one of its child items represent a read-only data structure.

###### 3.2.5.180.1.1.2 IsCollection

**Type:** CSOM Boolean

**Accessibility:** Read Only

Specifies whether the described type represents a collection data structure.

###### 3.2.5.180.1.1.3 IsReadOnly

**Type:** CSOM Boolean

**Accessibility:** Read Only

Specifies whether this **TypeDescriptor** represents a read-only data structure.

###### 3.2.5.180.1.1.4 Name

**Type:** CSOM String

**Accessibility:** Read Only

Specifies the name of this **TypeDescriptor** metadata object.

###### 3.2.5.180.1.1.5 TypeName

**Type:** CSOM String

**Accessibility:** Read Only

Specifies the name of the data type represented by this **TypeDescriptor**.

### 3.2.5.180.1.2 ObjectPath Properties

None.

### 3.2.5.180.2 Methods

#### 3.2.5.180.2.1 Scalar Methods

##### 3.2.5.180.2.1.1 ContainsLocalizedDisplayName

**Return Type:** CSOM Boolean

Specifies whether this **TypeDescriptor** contains a localized display name.

**Parameters:** None

##### 3.2.5.180.2.1.2 GetDefaultDisplayName

**Return Type:** CSOM String

Specifies the default display name of this **TypeDescriptor**.

**Parameters:** None

##### 3.2.5.180.2.1.3 GetLocalizedDisplayName

**Return Type:** CSOM String

Specifies the localized display name of this **TypeDescriptor**.

**Parameters:** None

#### Exceptions:

Error Code	Error Type Name	Condition
-1	Microsoft.BusinessData.MetadataModel.InvalidMetadataObjectException	Localized display name for the current locale does not exist.

##### 3.2.5.180.2.1.4 IsLeaf

**Return Type:** CSOM Boolean

Specifies whether this **TypeDescriptor** contains any child TypeDescriptors.

**Parameters:** None

##### 3.2.5.180.2.1.5 IsRoot

**Return Type:** CSOM Boolean

Specifies whether this **TypeDescriptor** represents the root of a data structure.

**Parameters:** None

### 3.2.5.180.2.2 ObjectPath Methods

#### 3.2.5.180.2.2.1 GetChildTypeDescriptors

**Return Type:** Microsoft.BusinessData.MetadataModel.Collections.TypeDescriptorCollection

Specifies the **TypeDescriptors** that correspond to the fields of the represented structure.

**Parameters:** None

#### 3.2.5.180.2.2.2 GetParentTypeDescriptor

**Return Type:** Microsoft.BusinessData.MetadataModel.TypeDescriptor

Returns the **TypeDescriptor** that contains this TypeDescriptor.

**Parameters:** None

#### Exceptions:

Error Code	Error Type Name	Condition
-1	Microsoft.BusinessData.MetadataModel.MetadataObjectNotFoundException	This TypeDescriptor represents the root of a data structure.

### 3.2.5.181 Microsoft.SharePoint.Client.AppCatalog

**TypeId:** {79CDEE9F-257E-423B-9E94-E6404659F7EA}

**ShortName:** SP.AppCatalog

Provides methods for retrieving installed **app instances**. [<186>](#) All methods in SP.AppCatalog are static.

#### 3.2.5.181.1 Properties

##### 3.2.5.181.1.1 Scalar Properties

None.

##### 3.2.5.181.1.2 ObjectPath Properties

None.

#### 3.2.5.181.2 Methods

##### 3.2.5.181.2.1 Scalar Methods

###### 3.2.5.181.2.1.1 IsAppSideloadEnabled

This method is a **static CSOM method**.

**Return Type:** **CSOM Boolean**



Returns "true" if side loading of **app instances** is enabled on the current **site (2)**, otherwise returns "false". Side loading allows an app instance to be installed directly from a programming environment, without the need to go through a published catalog.

**Parameters:** None

### **3.2.5.181.2.1.2      GetAppPermissionDescriptions**

This method is a **static CSOM method**.

**Return Type:** **CSOM array** of **CSOM String**

Gets the permissions requested by the SharePoint app. Returns null for a side-loaded app.

**Parameters:**

*web*: The web where the app is installed.

Type: Microsoft.SharePoint.Client.Web

*appInstance*: The appInstance for the app.

Type: Microsoft.SharePoint.Client.AppInstance

### **3.2.5.181.2.2 ObjectPath Methods**

#### **3.2.5.181.2.2.1      GetAppDetails**

This method is a **static CSOM method**.

**Return Type:** Microsoft.SharePoint.Packaging.AppDetails

Gets the AppDetails for the SP.App that has a host web of web and an appinstanceId of appinstance. If the SP.App has no details such as in the side-loaded case, then null is returned.

**Parameters:**

*web*: The host web where the application is installed.

Type: Microsoft.SharePoint.Client.Web

*appInstance*: The appInstance of the application.

Type: Microsoft.SharePoint.Client.AppInstance

#### **3.2.5.181.2.2.2      GetAppInstance**

This method is a **static CSOM method**.

**Return Type:** Microsoft.SharePoint.Client.AppInstance

Get an App Instance by the Id returned by the Install operation. If the App instance has any localizable properties (like Title), they will be localized based on the Current thread's CurrentUICulture.

**Parameters:**

*web*: The web that the App Instance is installed to.

Type: Microsoft.SharePoint.Client.Web

*appInstanceId*: The Id of the App Instance.

Type: **CSOM GUID**

### **3.2.5.181.2.2.3      GetAppInstances**

This method is a **static CSOM method**.

**Return Type:** **CSOM array** of Microsoft.SharePoint.Client.AppInstance

Gets the **app instances** installed in a given **site (2)**.

#### **Parameters:**

*web*: The target site (2).

Type: Microsoft.SharePoint.Client.Web

It MUST NOT be NULL.

### **3.2.5.181.2.2.4      GetDeveloperSiteAppInstancesByIds**

This method is a **static CSOM method**.

**Return Type:** **CSOM array** of Microsoft.SharePoint.Client.AppInstance

Gets the details of the **app instances** on the specified **site collection** for the specified app instance identifiers.

#### **Parameters:**

*site*: The site collection for which the app instance details will be returned.

Type: Microsoft.SharePoint.Client.Site

It MUST NOT be NULL.

It MUST be a Developer Site.

*appInstanceIds*: An array of app instance identifiers for which app instance details have to be retrieved.

Type: CSOM array of **CSOM GUID**

It MUST NOT be NULL. It MUST have at most 100 elements.

### **3.2.5.182      Microsoft.SharePoint.Client.AppInstance**

**TypeId:** {211A55DF-058B-4917-AC93-2B5E08B1A9FD}

**ShortName:** SP.AppInstance

Specifies an **app instance**.<187>

#### **3.2.5.182.1      Properties**

##### **3.2.5.182.1.1 Scalar Properties**

###### **3.2.5.182.1.1.1      Id**

**Type:** CSOM GUID

**Accessibility:** Read Only

Specifies the identifier of the **app instance**.

### 3.2.5.182.1.1.2 AppWebFullUrl

**Type:** CSOM String

**Accessibility:** Read Only

The absolute **URL** of the **site (2)** created during the installation of this **app instance**.

### 3.2.5.182.1.1.3 InError

**Type:** CSOM Boolean

**Accessibility:** Read Only

Specifies whether the **app instance** is in an error state. An error state means that a job to has to be retried or aborted for the instance to continue its current lifecycle operation.

### 3.2.5.182.1.1.4 RemoteAppUrl

**Type:** CSOM String

**Accessibility:** Read Only

Specifies the base **URL** of the remote system deployed during the installation of this **app instance**.

### 3.2.5.182.1.1.5 SiteId

**Type:** CSOM GUID

**Accessibility:** Read Only

Specifies the identifier of the **site collection** that contains the **site (2)** where this **app instance** is installed.

### 3.2.5.182.1.1.6 Status

**Type:** Microsoft.SharePoint.Client.AppInstanceStatus

**Accessibility:** Read Only

The status of the **app instance** as defined in section [3.2.5.238](#).

### 3.2.5.182.1.1.7 Title

**Type:** CSOM String

**Accessibility:** Read Only

Specifies the title of the **app instance**. The title can change with use, and SHOULD NOT be used as an identifier. Use **Id** (section [3.2.5.182.1.1.1](#)) instead.

### 3.2.5.182.1.1.8 WebId

**Type:** CSOM GUID

**Accessibility:** Read Only

Specifies the identifier of the **site (2)** where this **app instance** is installed.

### **3.2.5.182.1.1.9 StartPage**

**Type:** CSOM String

**Accessibility:** Read Only

The start page **URL** of the **app instance**.

### **3.2.5.182.1.1.10 AppPrincipalId**

**Type:** CSOM String

**Accessibility:** Read Only

Specifies the identifier of the **app principal**.

### **3.2.5.182.1.1.11 SettingsPageUrl**

**Type:** CSOM String

**Accessibility:** Read Only

Specifies the **URL** to configure the settings of this **app instance**.

### **3.2.5.182.1.1.12 ImageFallbackUrl**

**Type:** CSOM String

**Accessibility:** Read Only

Gets the **URL** of the fallback image.

### **3.2.5.182.1.1.13 ImageUrl**

**Type:** CSOM String

**Accessibility:** Read Only

The **URL** of the **image** relative to the layouts folder of the site where the app is installed.

### **3.2.5.182.1.1.14 PackageFingerprint**

**Type:** CSOM binary

**Accessibility:** Read Only

Gets the package fingerprint.

### **3.2.5.182.1.1.15 ProductId**

**Type:** CSOM GUID

**Accessibility:** Read Only

Gets the **App instance**'s Product Id.

### 3.2.5.182.1.2 ObjectPath Properties

None.

### 3.2.5.182.2 Methods

#### 3.2.5.182.2.1 Scalar Methods

##### 3.2.5.182.2.1.1 Uninstall

**Return Type:** CSOM GUID

Uninstalls the **app instance**.

**Parameters:** None

##### 3.2.5.182.2.1.2 CancelAllJobs

**Return Type:** CSOM Boolean

Cancels all executing lifecycle jobs for this **app instance**. If there is at least one job to cancel, this operation returns true.

**Parameters:** None

##### 3.2.5.182.2.1.3 RetryAllJobs

**Return Type:** None

Restarts all existing lifecycle jobs for this **app instance**.

**Parameters:** None

##### 3.2.5.182.2.1.4 Upgrade

**Return Type:** None

Uploads a new version of the **app package** to the **site (2)** that contains this **app instance** and upgrades this app instance to that version. The site (2) MUST be enabled for remote development.

**Parameters:**

*appPackageStream*: Stream of the app package.

Type: CSOM Stream

##### 3.2.5.182.2.1.5 Install

**Return Type:** CSOM GUID

Installs the **app instance**.

**Parameters:** None

##### 3.2.5.182.2.1.6 RetrieveAppDatabaseConnectionString

This method is a **static CSOM method**.

**Return Type:** CSOM String

Returns the database connection string if the **app instance** has an auto-deployed database, otherwise returns NULL.

**Parameters:** None

### **3.2.5.182.2.1.7      GetAppDatabaseConnectionString**

**Return Type:** **CSOM String**

The Connection string for the app database.

**Parameters:** None

### **3.2.5.182.2.1.8      Recycle**

**Return Type:** **CSOM GUID**

Creates a job that sends the **app instance** to the recycle bin, where it will stay until restored by <see cref="SPAppInstance.Restore" />, or uninstalled at the end of the retention period.

Returns the job Id of the recycle job.

**Parameters:** None

### **3.2.5.182.2.1.9      Restore**

**Return Type:** **CSOM GUID**

Creates a job that restores the **app instance** from the recycle bin to the Installed state.

Returns the job Id of the restore job.

**Parameters:** None

## **3.2.5.182.2.2 ObjectPath Methods**

### **3.2.5.182.2.2.1      GetPreviousAppVersion**

**Return Type:** Microsoft.SharePoint.Client.App

If the **app instance** was upgraded, it MUST return the version of the **app package** (as specified in section [3.2.5.237](#)) before upgrade. Else it MUST return NULL.

**Parameters:** None

### **3.2.5.182.2.2.2      GetErrorDetails**

**Return Type:** **CSOM array** of Microsoft.SharePoint.Client.AppInstanceErrorDetails

Returns the latest lifecycle error details for this **app instance** as specified in section [3.2.5.256](#).

**Parameters:** None

### **3.2.5.182.2.2.3      GetAppIcon**

This method is a **static CSOM method**.

**Return Type:** Microsoft.SharePoint.Packaging.AppIconInfo

Gets the icon information for the app. Returns the icon information for the app.

**Parameters:**

*hostWeb*: The app host web.

Type: Microsoft.SharePoint.Client.Web

*appinstanceId*: The **app instance** identifier.

Type: **CSOM GUID**

*packageFingerprint*: The **app package** fingerprint.

Type: **CSOM binary**

**3.2.5.183 Microsoft.SharePoint.Client.ChangeLogItemQuery**

**TypeId**: {820ED5A1-95F7-493B-88FA-266E9DB920AF}

**ShortName**: SP.ChangeLogItemQuery

Specifies an object that is used as the input parameter of **GetListItemChangesSinceToken** (section [3.2.5.79.2.1.7](#)) method. [<188>](#)

**3.2.5.183.1 Properties****3.2.5.183.1.1 Scalar Properties****3.2.5.183.1.1.1 ChangeToken**

Type: **CSOM String**

**Accessibility**: Read/Write

Specifies a string that contains the **change token** for the request.

**3.2.5.183.1.1.2 Contains**

Type: **CSOM String**

**Accessibility**: Read/Write

Specifies a string representation of the **XML element** that defines custom filtering for the query. See [\[MS-LISTSWS\]](#) section 2.2.4.3.

**3.2.5.183.1.1.3 Query**

Type: **CSOM String**

**Accessibility**: Read/Write

Specifies which records from the **list** are to be returned and the order in which they will be returned. See section 2.2 in [\[MS-WSSCAML\]](#).

**3.2.5.183.1.1.4 QueryOptions**

Type: **CSOM String**

**Accessibility**: Read/Write

Specifies various options for modifying the **Query** (section [3.2.5.183.1.1.3](#)). See [\[MS-LISTSWS\]](#) section 2.2.4.4.

### **3.2.5.183.1.1.5 ViewName**

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies the **GUID** for the **view**.

### **3.2.5.183.1.1.6 RowLimit**

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies a limit for the number of items in the **query** that are returned per page.

### **3.2.5.183.1.1.7 ViewFields**

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies the names of the **fields (2)** to be included in the **query** result.

### **3.2.5.183.1.2 ObjectPath Properties**

None.

### **3.2.5.184 Microsoft.SharePoint.Client.FieldCreationInformation**

**TypeId:** {46C21C03-8E93-4E5A-BF90-228366397C9A}

**ShortName:** SP.FieldCreationInformation

Specifies the metadata of a **field (2)** that is specified in [\[MS-WSSTS\]](#) section 2.1.2.9.<189>

#### **3.2.5.184.1 Properties**

##### **3.2.5.184.1.1 Scalar Properties**

###### **3.2.5.184.1.1.1 Choices**

**Type:** CSOM array of CSOM String

**Accessibility:** Read/Write

Specifies values that are available for selection in the **field (2)**.

###### **3.2.5.184.1.1.2 FieldTypeKind**

**Type:** CSOM Int32

**Accessibility:** Read/Write

Specifies the type of the **field (2)**.



### 3.2.5.184.1.1.3 IsCompactName

**Type:** CSOM Boolean

**Accessibility:** Read/Write

This value is "true" to compact the **field (2)** name to eight characters; otherwise, "false".

### 3.2.5.184.1.1.4 LookupFieldName

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies the name of the **field (2)** in the other data source when creating a **lookup field**.

### 3.2.5.184.1.1.5 LookupListId

**Type:** CSOM GUID

**Accessibility:** Read/Write

A CSOM GUID that specifies the target list for the lookup **field (2)**.

### 3.2.5.184.1.1.6 LookupWebId

**Type:** CSOM GUID

**Accessibility:** Read/Write

Specifies the identifier of the **site (2)** that contains the **list** that is the source for the **field (2)** value.

### 3.2.5.184.1.1.7 Required

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Specifies whether the **field (2)** requires a value. If the field (2) requires a value, this value MUST be set to "true". Otherwise, it MUST be set to "false".

### 3.2.5.184.1.1.8 Title

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies the **display name** of the **field (2)**.

It MUST NOT be NULL.

## 3.2.5.184.1.2 ObjectPath Properties

None.

## 3.2.5.185 Microsoft.SharePoint.Client.FieldGeolocation

**TypeId:** {D5A367F2-3B74-4984-AB50-9A700883C90B}

**ShortName:** SP.FieldGeolocation

Specifies a **field (2)** that contains geographical location values. <190>

The NoCrawl and SchemaXmlWithResourceTokens properties are not included in the **default scalar property set** for this type.

### 3.2.5.185.1 Properties

#### 3.2.5.185.1.1 Scalar Properties

##### 3.2.5.185.1.1.1 CanBeDeleted

Type: **CSOM Boolean**

Accessibility: Read Only

See **Microsoft.SharePoint.Client.Field.CanBeDeleted**, as specified in section [3.2.5.37.1.1.1](#).

##### 3.2.5.185.1.1.2 DefaultValue

Type: **CSOM String**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.DefaultValue**, as specified in section [3.2.5.37.1.1.2](#).

Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed, and the <b>list</b> is an <b>external list</b> .

##### 3.2.5.185.1.1.3 Description

Type: **CSOM String**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.Description**, as specified in section [3.2.5.37.1.1.3](#).

##### 3.2.5.185.1.1.4 Direction

Type: **CSOM String**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.Direction**, as specified in section [3.2.5.37.1.1.4](#).

Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed to a value other than "none," and the <b>list</b> is an <b>external list</b> .

### 3.2.5.185.1.1.5 EnforceUniqueValues

Type: **CSOM Boolean**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.EnforceUniqueValues**, as specified in section [3.2.5.37.1.1.5](#).

#### Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	The <b>list</b> has an external data source and is trying to set <b>unique column constraints</b> to "true".

### 3.2.5.185.1.1.6 FieldTypeKind

Type: Microsoft.SharePoint.Client.FieldType

Accessibility: Read/Write

Specifies the type of the **field (2)**.

See **Microsoft.SharePoint.Client.Field.FieldTypeKind**, as specified in section [3.2.5.37.1.1.6](#).

#### Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Adding <b>unique column constraints</b> to the field (2) where the <b>list</b> is an <b>external list</b> and <b>FieldTypeKind</b> is modified.

### 3.2.5.185.1.1.7 Filterable

Type: **CSOM Boolean**

Accessibility: Read Only

See **Microsoft.SharePoint.Client.Field.Filterable**, as specified in section [3.2.5.37.1.1.7](#).

### 3.2.5.185.1.1.8 FromBaseType

Type: **CSOM Boolean**

Accessibility: Read Only

Specifies whether the **field (2)** derives from a base field type.

### 3.2.5.185.1.1.9 Group

Type: **CSOM String**

**Accessibility:** Read/Write

See **Microsoft.SharePoint.Client.Field.Group**, as specified in section [3.2.5.37.1.1.9](#).

It MUST NOT be NULL. It MUST NOT be empty. Its length MUST be equal to or less than 128.

**Exceptions:**

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed, and the <b>list</b> is an external list.

### 3.2.5.185.1.1.10 Hidden

**Type:** CSOM Boolean

**Accessibility:** Read/Write

See **Microsoft.SharePoint.Client.Field.Hidden**, as specified in section [3.2.5.37.1.1.10](#).

### 3.2.5.185.1.1.11 Id

**Type:** CSOM GUID

**Accessibility:** Read Only

See **Microsoft.SharePoint.Client.Field.Id**, as specified in section [3.2.5.37.1.1.11](#).

### 3.2.5.185.1.1.12 InternalName

**Type:** CSOM String

**Accessibility:** Read Only

See **Microsoft.SharePoint.Client.Field.InternalName**, as specified in section [3.2.5.37.1.1.12](#).

It MUST NOT be NULL. It MUST NOT be empty.

### 3.2.5.185.1.1.13 ReadOnlyField

**Type:** CSOM Boolean

**Accessibility:** Read/Write

See **Microsoft.SharePoint.Client.Field.ReadOnlyField**, as specified in section [3.2.5.37.1.1.13](#).

**Exceptions:**

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed, and the <b>list</b> is an external list.

### 3.2.5.185.1.1.14 Required

**Type:** CSOM Boolean

**Accessibility:** Read/Write

See **Microsoft.SharePoint.Client.Field.Required**, as specified in section [3.2.5.37.1.1.14](#).

**Exceptions:**

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	This <b>field (2)</b> belongs to a <b>list</b> that has an external data source and <b>Required</b> is set to "true".

### 3.2.5.185.1.1.15 SchemaXml

**Type:** CSOM String

**Accessibility:** Read/Write

See **Microsoft.SharePoint.Client.Field.SchemaXml**, as specified in section [3.2.5.37.1.1.15](#).

It MUST be NULL, empty, or an **XML fragment** that conforms to the **FieldDefinition** type as defined in [\[MS-WSSFO2\]](#) section 2.2.8.3.3 or [\[MS-WSSFO3\]](#) section 2.2.7.3.3.

**Exceptions:**

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed to a non-NULL or non-empty value, and the <b>list</b> is an <b>external list</b> .

### 3.2.5.185.1.1.16 Scope

**Type:** CSOM String

**Accessibility:** Read Only

See **Microsoft.SharePoint.Client.Field.Scope**, as specified in section [3.2.5.37.1.1.16](#).

### 3.2.5.185.1.1.17 Sealed

**Type:** CSOM Boolean

**Accessibility:** Read/Write

See **Microsoft.SharePoint.Client.Field.Sealed**, as specified in section [3.2.5.37.1.1.17](#).

### 3.2.5.185.1.1.18 Sortable

**Type:** CSOM Boolean

**Accessibility:** Read Only

See **Microsoft.SharePoint.Client.Field.Sortable**, as specified in section [3.2.5.37.1.1.18](#).

### 3.2.5.185.1.1.19 StaticName

Type: **CSOM String**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.StaticName**, as specified in section [3.2.5.37.1.1.19](#).

Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed, and the <b>list</b> is an <b>external list</b> .

### 3.2.5.185.1.1.20 Title

Type: **CSOM String**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.Title**, as specified in section [3.2.5.37.1.1.20](#).

### 3.2.5.185.1.1.21 TypeAsString

Type: **CSOM String**

Accessibility: Read/Write

See **Microsoft.SharePoint.Client.Field.TypeAsString**, as specified in section [3.2.5.37.1.1.21](#).

It MUST NOT be NULL. It MUST NOT be empty.

Exceptions:

Error Code	Error Type Name	Condition
-1	System.NotSupportedException	Value is changed, and the <b>list</b> is an <b>external list</b> .

### 3.2.5.185.1.1.22 TypeDisplayName

Type: **CSOM String**

Accessibility: Read Only

See **Microsoft.SharePoint.Client.Field.TypeDisplayName**, as specified in section [3.2.5.37.1.1.22](#).

It MUST NOT be NULL. It MUST NOT be empty.

### 3.2.5.185.1.1.23 TypeShortDescription

Type: **CSOM String**

Accessibility: Read Only

See **Microsoft.SharePoint.Client.Field.TypeShortDescription**, as specified in section [3.2.5.37.1.1.23](#).

It MUST NOT be NULL. It MUST NOT be empty.

### **3.2.5.185.1.1.24 ValidationFormula**

**Type:** CSOM String

**Accessibility:** Read/Write

See **Microsoft.SharePoint.Client.Field.ValidationFormula**, as specified in section [3.2.5.37.1.1.24](#).

### **3.2.5.185.1.1.25 ValidationMessage**

**Type:** CSOM String

**Accessibility:** Read/Write

See **Microsoft.SharePoint.Client.Field.ValidationMessage**, as specified in section [3.2.5.37.1.1.25](#).

Its length MUST be equal to or less than 1024.

### **3.2.5.185.1.1.26 JSLink**

**Type:** CSOM String

**Accessibility:** Read/Write

Gets the name of an external ECMAScript ([\[ECMA-262-1999\]](#)) file containing any client-rendering logic for fields of this type

### **3.2.5.185.1.1.27 EntityPropertyName**

**Type:** CSOM String

**Accessibility:** Read Only

Gets the name of the entity property of this **field (2)** in the **list item** entity that uses this field (2).

It MUST NOT be NULL. It MUST NOT be empty.

### **3.2.5.185.1.1.28 Indexed**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Gets or sets a Boolean value that specifies whether the field is indexed.

### **3.2.5.185.1.1.29 SchemaXmlWithResourceTokens**

**Type:** CSOM String

**Accessibility:** Read Only

Gets the unlocalized schema XML for this **field (2)**.

### **3.2.5.185.1.1.30 AutoIndexed**

**Type:** CSOM Boolean

**Accessibility:** Read Only

Gets a Boolean value that specifies whether the field is auto-indexed. True to specify that the field is auto-indexed; otherwise, false.

#### **3.2.5.185.1.1.31 ClientSideComponentId**

**Type:** CSOM GUID

**Accessibility:** Read/Write

The unique identifier of the client-side component defined with SharePoint Framework.

#### **3.2.5.185.1.1.32 ClientSideComponentProperties**

**Type:** CSOM String

**Accessibility:** Read/Write

This property is only used when a **ClientSideComponentId** is specified. It is optional. If non-empty, the string MUST contain a JSON object with custom initialization properties whose format and meaning are defined by the client-side component.

#### **3.2.5.185.1.1.33 CustomFormatter**

**Type:** CSOM String

**Accessibility:** Read/Write

A JSON string representing the custom rendering format of the field.

#### **3.2.5.185.1.1.34 DefaultFormula**

**Type:** CSOM String

**Accessibility:** Read/Write

Gets or sets the default formula for a calculated field.

#### **3.2.5.185.1.1.35 NoCrawl**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Gets or sets a Boolean value that specifies whether the field can be crawled by a search engine.

#### **3.2.5.185.1.1.36 PinnedToFiltersPane**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Boolean value that indicates whether the field pins to filter pane.

#### **3.2.5.185.1.1.37 ShowInFiltersPane**

**Type:** Microsoft.SharePoint.Client.ShowInFiltersPaneStatus

**Accessibility:** Read/Write

Indicates whether the field will be shown.



### 3.2.5.185.1.2 ObjectPath Properties

#### 3.2.5.185.1.2.1 DescriptionResource

**Type:** Microsoft.SharePoint.Client.UserResource

**Accessibility:** Read Only

Gets the resource object corresponding to the Description property for a field.

#### 3.2.5.185.1.2.2 TitleResource

**Type:** Microsoft.SharePoint.Client.UserResource

**Accessibility:** Read Only

Gets the resource object corresponding to the Title property for a field.

### 3.2.5.185.2 Methods

#### 3.2.5.185.2.1 Scalar Methods

##### 3.2.5.185.2.1.1 DeleteObject

**Return Type:** None

Deletes the **field (2)** from the **list**, from the **site (2)**, or from the **content types** within the list.

**Parameters:** None

**Exceptions:**

Error Code	Error Type Name	Condition
-1	System.InvalidOperationException	<b>CanBeDeleted</b> is "false".

##### 3.2.5.185.2.1.2 setShowInDisplayForm

**Return Type:** None

Sets this field to show or hide in the display form.

**Parameters:**

*value:* A Boolean value that indicates whether this field is shown in the display form.

Type: **CSOM Boolean**

##### 3.2.5.185.2.1.3 setShowInEditForm

**Return Type:** None

Sets this field to show or hide in the edit form.

**Parameters:**

*value:* A Boolean value that indicates whether this field is shown in the edit form.

Type: **CSOM Boolean**

### 3.2.5.185.2.1.4 SetShowInNewForm

**Return Type:** None

Sets this field to show or hide in the new form.

**Parameters:**

*value*: A Boolean value that indicates whether this field is shown in the new form.

Type: **CSOM Boolean**

### 3.2.5.185.2.1.5 Update

**Return Type:** None

Commits changed properties of the **field (2)**.

**Parameters:** None

**Exceptions:**

Error Code	Error Type Name	Condition
- 2130246331	Microsoft.SharePoint.SPException	Type of the field (2) is changed for an <b>indexed field</b> . The field type of indexed fields cannot be changed.
- 2130246238	Microsoft.SharePoint.SPException	Field (2) is set to not be an indexed field, and <b>EnforceUniqueValues</b> is "true".
- 2130246236	Microsoft.SharePoint.SPException	Type of the field (2) is being changed and <b>EnforceUniqueValues</b> of the field (2) is "true".

### 3.2.5.185.2.1.6 UpdateAndPushChanges

**Return Type:** None

Commits changed properties of the **field (2)** and propagates changes to all **lists** that use the field (2).

**Parameters:**

*pushChangesToLists*: Specifies whether to propagate changes to all lists that use the field (2).

Type: **CSOM Boolean**

**Exceptions:**

Error Code	Error Type Name	Condition
- 2130246331	Microsoft.SharePoint.SPException	Type of the field (2) is changed for an <b>indexed field</b> . The field type of indexed fields cannot be changed.
- 2130246238	Microsoft.SharePoint.SPException	Field (2) is set to not be an indexed field, and <b>EnforceUniqueValues</b> is "true".
-	Microsoft.SharePoint.SPException	Type of the field (2) is being changed and

Error Code	Error Type Name	Condition
2130246236		<b>EnforceUniqueValues</b> of the field (2) is "true".

### 3.2.5.185.2.1.7 ValidateSetValue

**Return Type:** None

Validates and sets the value of the **field (2)** for the **list item** based on an implementation-specific transformation of the value.

**Parameters:**

*item*: Specifies the list item to be updated with the new value.

Type: Microsoft.SharePoint.Client.ListItem

It MUST NOT be NULL.

*value*: Specifies the new value for the field (2).

Type: **CSOM String**

### 3.2.5.185.2.2 ObjectPath Methods

None.

### 3.2.5.186 Microsoft.SharePoint.Client.FieldGeolocationValue

**TypeId:** {97650AFF-7E7B-44BE-AC6E-D559F7F897A2}

**ShortName:** SP.FieldGeolocationValue

Specifies altitude, latitude, longitude and measure values for **FieldGeolocation** (section [3.2.5.185](#)).<191>

#### 3.2.5.186.1 Properties

##### 3.2.5.186.1.1 Scalar Properties

###### 3.2.5.186.1.1.1 Altitude

**Type:** **CSOM Double**

**Accessibility:** Read/Write

Specifies the altitude value for **FieldGeolocation** (section [3.2.5.185](#)). The semantics of the altitude value are user-defined. This value will not be used in any out of the box calculations.

###### 3.2.5.186.1.1.2 Latitude

**Type:** **CSOM Double**

**Accessibility:** Read/Write

Specifies the latitude value for **FieldGeolocation** (section [3.2.5.185](#)).

### 3.2.5.186.1.1.3 Longitude

Type: **CSOM Double**

Accessibility: Read/Write

Specifies the longitude value for **FieldGeolocation** (section [3.2.5.185](#)).

### 3.2.5.186.1.1.4 Measure

Type: **CSOM Double**

Accessibility: Read/Write

Specifies the measure value for **FieldGeolocation** (section [3.2.5.185](#)). The semantics of the measure value are user-defined. This value will not be used in any out-of-the-box calculations.

### 3.2.5.186.1.2 ObjectPath Properties

None.

## 3.2.5.187 Microsoft.SharePoint.Client.Sharing.DocumentSharingManager

TypeId: {10C23C0E-CEAD-4F15-9DEB-A0F1D7507495}

ShortName: SP.Sharing.DocumentSharingManager

Specifies **document** sharing related methods. [<192>](#)

### 3.2.5.187.1 Properties

#### 3.2.5.187.1.1 Scalar Properties

None.

#### 3.2.5.187.1.2 ObjectPath Properties

None.

### 3.2.5.187.2 Methods

#### 3.2.5.187.2.1 Scalar Methods

##### 3.2.5.187.2.1.1 UpdateDocumentSharingInfo

This method is a **static CSOM method**.

**Return Type:** **CSOM array** of Microsoft.SharePoint.Client.Sharing.UserSharingResult

This method allows a caller with the 'ManagePermission' permission to update sharing information about a **document** to enable document sharing with a set of users. It returns an array of **UserSharingResult** (section [3.2.5.190](#)) elements where each element contains the sharing status for each user.

#### Parameters:

*resourceAddress*: A **URL** that points to a **securable object**, which can be a document, **folder** or the **root folder** of a **document library**.

Type: **CSOM String**

*userRoleAssignments*: An array of recipients and assigned roles on the securable object pointed to by the *resourceAddress* parameter.

Type: CSOM array of Microsoft.SharePoint.Client.Sharing.UserRoleAssignment

*validateExistingPermissions*: A Boolean flag indicating how to honor a requested permission for a user. If this value is "true", the protocol server will not grant the requested permission if a user already has sufficient permissions, and if this value is "false", the protocol server will grant the requested permission whether or not a user already has the same or more permissions. This parameter is applicable only when the parameter *additiveMode* is set to true.

Type: **CSOM Boolean**

*additiveMode*: A Boolean flag indicating whether the permission setting uses the additive or strict mode. If this value is "true", the permission setting uses the additive mode, which means that the specified permission will be added to the user's current list of permissions if it is not there already, and if this value is "false", the permission setting uses the strict mode, which means that the specified permission will replace the user's current permissions.

Type: CSOM Boolean

*sendServerManagedNotification*: A **Boolean** flag to indicate whether or not to generate an email notification to each recipient in the "userRoleAssignments" array after the document update is completed successfully. If this value is "true", the protocol server will send an email notification if an email server is configured, and if the value is "false", no email notification will be sent.

Type: CSOM Boolean

*customMessage*: A custom message to be included in the email notification.

Type: CSOM String

*includeAnonymousLinksInNotification*: A Boolean flag that indicates whether or not to include anonymous access links in the email notification to each recipient in the *userRoleAssignments* array after the document update is completed successfully. If the value is "true", the protocol server will include an anonymous access link in the email notification, and if the value is "false", no link will be included.

Type: CSOM Boolean

*propagateAcl*: A flag to determine if permissions SHOULD be pushed to items with unique permission.

Type: CSOM Boolean

### **3.2.5.187.2.1.2 IsDocumentSharingEnabled**

This method is a **static CSOM method**.

**Return Type: CSOM Boolean**

Specifies whether a **document** sharing is enabled on a **document library**.

**Parameters:**

*list*: The document library in which to check if document sharing is enabled.

Type: Microsoft.SharePoint.Client.List

### **3.2.5.187.2.1.3 CanMemberShare**

This method is a **static CSOM method**.

**Return Type:** CSOM Boolean

Specifies whether the **list** can do member sharing.

**Parameters:**

*list*: The list to check member sharing.

Type: Microsoft.SharePoint.Client.List

### 3.2.5.187.2.1.4 RemoveItemsFromSharedWithMeView

This method is a **static CSOM method**.

**Return Type:** CSOM array of

Microsoft.SharePoint.Client.Sharing.SharedWithMeViewItemRemovalResult

Removes an item so that it no longer shows in the current user's 'Shared With Me' view. However, this does not remove the user's actual permissions to the item. Up to 200 items can be provided in a single call. Returns a list of results indicating whether the items were successfully removed. The length of this array will match the length of the *itemUrls* array that was provided.

**Parameters:**

*itemUrls*: A list of absolute URLs of the items to be removed from the view. These items might belong to any site or site collection in the tenant.

Type: CSOM array of **CSOM String**

### 3.2.5.187.2.2 ObjectPath Methods

#### 3.2.5.187.2.2.1 GetRoleDefinition

This method is a **static CSOM method**.

**Return Type:** Microsoft.SharePoint.Client.RoleDefinition

This method returns a role definition in the current web that is associated with a given **Role** (section [3.2.5.188](#)) value.

**Parameters:**

*role*: A **Role** value for which to obtain the associated role definition object.

Type: Microsoft.SharePoint.Client.Sharing.Role

### 3.2.5.188 Microsoft.SharePoint.Client.Sharing.Role

**ShortName:** SP.Sharing.Role

**Flag:** false

Specifies a set of abstract roles that a user can be assigned to share a **securable object** in a **document library**.[<193>](#)

#### 3.2.5.188.1 Field Values

##### 3.2.5.188.1.1 None

**Value:** 0

The user does not have a permission to share a **securable object**.

### **3.2.5.188.1.2View**

**Value:** 1

The user can only read a **securable object**.

### **3.2.5.188.1.3Edit**

**Value:** 2

The user can edit or read a **securable object**, but cannot delete it.

### **3.2.5.188.1.4Owner**

**Value:** 3

The user is an owner of a **securable object** and can manage permissions, and edit, read or delete the object.

### **3.2.5.188.1.5LimitedView**

**Value:** 4

The user can only read a **securable object**. This role is specifically used in **tokenized sharing links**.

### **3.2.5.188.1.6LimitedEdit**

**Value:** 5

The user can edit or read a **securable object** but cannot delete it. This role is specifically used in **tokenized sharing links**.

### **3.2.5.188.1.7Review**

**Value:** 6

The user can read a **securable object**, plus comment in/on it.

### **3.2.5.188.1.8RestrictedView**

**Value:** 7

The user can view a **securable object** only in web viewer, cannot download it.

## **3.2.5.189 Microsoft.SharePoint.Client.Sharing.UserRoleAssignment**

**TypeId:** {74485063-E2B5-424B-950C-4B62E816E31F}

**ShortName:** SP.Sharing.UserRoleAssignment

Specifies a user and a **role** that is associated with the user. [<194>](#)

### **3.2.5.189.1 Properties**

### 3.2.5.189.1.1 Scalar Properties

#### 3.2.5.189.1.1.1 Role

**Type:** Microsoft.SharePoint.Client.Sharing.Role

**Accessibility:** Read/Write

Specifies a **Role** (section [3.2.5.188](#)) that is assigned to a user.

#### 3.2.5.189.1.1.2 UserId

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies the identifier of a user, which can be in the format of an email address or a login identifier.

### 3.2.5.189.1.2 ObjectPath Properties

None.

### 3.2.5.190 Microsoft.SharePoint.Client.Sharing.UserSharingResult

**TypeId:** {782142B7-1BB8-495F-8A60-9940982DE38E}

**ShortName:** SP.Sharing.UserSharingResult

Specifies a sharing result for an individual user that method **UpdateDocumentSharingInfo** (section [3.2.5.187.2.1.1](#)) returns. <195>

#### 3.2.5.190.1 Properties

##### 3.2.5.190.1.1 Scalar Properties

###### 3.2.5.190.1.1.1 AllowedRoles

**Type:** CSOM array of Microsoft.SharePoint.Client.Sharing.Role

**Accessibility:** Read Only

Specifies a set of **roles** that can be assigned to the user.

###### 3.2.5.190.1.1.2 CurrentRole

**Type:** Microsoft.SharePoint.Client.Sharing.Role

**Accessibility:** Read Only

Specifies the **role** that the user is currently assigned to.

###### 3.2.5.190.1.1.3 IsUserKnown

**Type:** CSOM Boolean

**Accessibility:** Read Only

Specifies whether the user is known to the server. If "true", the user is known to the server; if "false", user is unknown.



#### **3.2.5.190.1.1.4 Status**

**Type:** CSOM Boolean

**Accessibility:** Read Only

Specifies whether the sharing update for the user was completed successfully. If "true", the sharing update completed successfully for the user; if "false", the sharing update failed for the user.

#### **3.2.5.190.1.1.5 User**

**Type:** CSOM String

**Accessibility:** Read Only

Specifies the identifier of a user.

#### **3.2.5.190.1.1.6 Message**

**Type:** CSOM String

**Accessibility:** Read Only

Specifies a message string that explains the reason when the **Status** (section [3.2.5.190.1.1.4](#)) property is "false".

#### **3.2.5.190.1.1.7 DisplayName**

**Type:** CSOM String

**Accessibility:** Read Only

Gets the display name of the user.

#### **3.2.5.190.1.1.8 Email**

**Type:** CSOM String

**Accessibility:** Read Only

Gets the user email.

#### **3.2.5.190.1.1.9 InvitationLink**

**Type:** CSOM String

**Accessibility:** Read Only

Gets the invitation link.

#### **3.2.5.190.1.2ObjectPath Properties**

None.

#### **3.2.5.191 Microsoft.SharePoint.Client.WebInfoCreationInformation**

**TypeId:** {5143CF01-79B3-425C-96B2-6E8B34A45D03}

**ShortName:** SP.WebInfoCreationInformation

Specifies metadata about **site (2)** creation. <196>

### **3.2.5.191.1 Properties**

#### **3.2.5.191.1.1 Scalar Properties**

##### **3.2.5.191.1.1.1 Description**

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies the description for the **site (2)**.

##### **3.2.5.191.1.1.2 Language**

**Type:** CSOM UInt32

**Accessibility:** Read/Write

Specifies the **language code identifier (LCID)** for the language that is used on the **site (2)**.

##### **3.2.5.191.1.1.3 Title**

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies the title for the **site (2)**.

It MUST NOT be NULL. Its length MUST be equal to or less than 255.

##### **3.2.5.191.1.1.4 Url**

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies the **URL** of the **site (2)**.

It MUST NOT be NULL.

##### **3.2.5.191.1.1.5 UseUniquePermissions**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Specifies whether the **site (2)** inherits permissions from its parent.

##### **3.2.5.191.1.1.6 WebTemplate**

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies the name of the **site template** that is used to create the **site (2)**.

#### **3.2.5.191.1.2 ObjectPath Properties**

None.

### **3.2.5.192 Microsoft.SharePoint.Client.WebInformation**

**TypeId:** {F847686B-8E42-401C-88E4-B5ED4261A788}

**ShortName:** SP.WebInformation

Specifies metadata about a **site (2)**.<197>

#### **3.2.5.192.1 Properties**

##### **3.2.5.192.1.1 Scalar Properties**

###### **3.2.5.192.1.1.1 Created**

**Type:** CSOM DateTime

**Accessibility:** Read Only

Specifies when the **site (2)** was created.

###### **3.2.5.192.1.1.2 Description**

**Type:** CSOM String

**Accessibility:** Read Only

Specifies the description for the **site (2)**.

###### **3.2.5.192.1.1.3 Id**

**Type:** CSOM GUID

**Accessibility:** Read Only

Specifies the **site identifier** for the **site (2)**.

###### **3.2.5.192.1.1.4 Language**

**Type:** CSOM UInt32

**Accessibility:** Read Only

Specifies the **language code identifier (LCID)** for the language that is used on the **site (2)**.

###### **3.2.5.192.1.1.5 LastItemModifiedDate**

**Type:** CSOM DateTime

**Accessibility:** Read Only

Specifies when an **item** was last modified in the **site (2)**.

###### **3.2.5.192.1.1.6 Title**

**Type:** CSOM String

**Accessibility:** Read Only

Specifies the title for the **site (2)**.

Its length MUST be equal to or less than 255.

#### **3.2.5.192.1.1.7 WebTemplateId**

**Type:** CSOM Int32

**Accessibility:** Read Only

Specifies the identifier of the **site template** that was used to create the **site (2)**.

#### **3.2.5.192.1.1.8 ServerRelativeUrl**

**Type:** CSOM String

**Accessibility:** Read Only

Specifies the **server-relative URL** of the **site (2)**.

#### **3.2.5.192.1.1.9 Configuration**

**Type:** CSOM Int16

**Accessibility:** Read Only

Specifies the identifier (ID) of the **site definition configuration** that was used to create the **site (2)**.

#### **3.2.5.192.1.1.10 WebTemplate**

**Type:** CSOM String

**Accessibility:** Read Only

Specifies the name of the **site template** that was used to create the **site (2)**.

#### **3.2.5.192.1.1.11 LastItemUserModifiedDate**

**Type:** CSOM DateTime

**Accessibility:** Read Only

Gets the date and time that an item was last modified in the site by a non-system update. A non-system update is a change to a list item that is visible to end users.

### **3.2.5.192.1.2 ObjectPath Properties**

None.

### **3.2.5.192.2 Methods**

#### **3.2.5.192.2.1 Scalar Methods**

None.

#### **3.2.5.192.2.2 ObjectPath Methods**

None.

### 3.2.5.193 Microsoft.SharePoint.Client.WebInformationCollection

**TypeId:** {FDDC4EE9-DC2E-444E-9D02-664C255DA6F1}

**ShortName:** SP.WebInformationCollection

Specifies a collection of objects containing metadata about a **site (2)**.<198>

#### 3.2.5.193.1 Properties

##### 3.2.5.193.1.1 Scalar Properties

None.

##### 3.2.5.193.1.2 ObjectPath Properties

None.

#### 3.2.5.193.2 Methods

##### 3.2.5.193.2.1 Scalar Methods

None.

##### 3.2.5.193.2.2 ObjectPath Methods

###### 3.2.5.193.2.2.1 Add

**Return Type:** Microsoft.SharePoint.Client.WebInformation

Creates a new **site (2)** and adds it to this collection of sites (2).

**Parameters:**

*parameters:* The properties for the new site (2).

Type: Microsoft.SharePoint.Client.WebInfoCreationInformation

It MUST NOT be NULL.

###### 3.2.5.193.2.2.2 GetById

**Return Type:** Microsoft.SharePoint.Client.WebInformation

Returns an **SP.WebInformation** (section [3.2.5.192](#)) object that contains metadata about a **site (2)** specified by the identifier of the site (2).

**Parameters:**

*id:* Specifies the identifier of site (2).

Type: **CSOM GUID**

It MUST NOT be NULL. It MUST NOT be an empty GUID.

**Exceptions:**

Error Code	Error Type Name	Condition
- 2147024809	System.ArgumentException	The SP.WebInformation specified by <i>id</i> does not exist.
- 2147024891	System.UnauthorizedAccessException	The user does not have permissions to retrieve the SP.WebInformation.

### 3.2.5.194 Microsoft.SharePoint.Client.XmlSchemaFieldCreationInformation

**TypeId:** {27B11DE3-188C-43B6-A3AC-E7123E134DB7}

**ShortName:** SP.XmlSchemaFieldCreationInformation

Specifies metadata about a **field (2)**. [<199>](#)

#### 3.2.5.194.1 Properties

##### 3.2.5.194.1.1 Scalar Properties

###### 3.2.5.194.1.1.1 Options

**Type:** Microsoft.SharePoint.Client.AddFieldOptions

**Accessibility:** Read/Write

Specifies the control settings that are used while adding a **field (2)**.

###### 3.2.5.194.1.1.2 SchemaXml

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies the schema that defines the **field (2)**.

It MUST be NULL, empty, or an **XML fragment** that conforms to the **FieldDefinition** type as defined in [\[MS-WSSFO2\]](#) section 2.2.8.3.3 or [\[MS-WSSFO3\]](#) section 2.2.7.3.3.

###### 3.2.5.194.1.2 ObjectPath Properties

None.

### 3.2.5.195 Microsoft.SharePoint.Client.ListItemEntityCollection

**TypeId:** {FF83E272-F05F-4215-93E2-2C6DF20EC8C7}

**ShortName:** SP.ListItemEntityCollection

List item entity set.

#### 3.2.5.195.1 Properties

##### 3.2.5.195.1.1 Scalar Properties

None.

### 3.2.5.195.1.2ObjectPath Properties

None.

### 3.2.5.195.2 Methods

#### 3.2.5.195.2.1Scalar Methods

None.

#### 3.2.5.195.2.2ObjectPath Methods

##### 3.2.5.195.2.2.1 GetById

**Return Type:** Microsoft.SharePoint.Client.ListItem

Get list item by id.

**Parameters:**

*itemId*: Specifies the identifier of the **list item**.

Type: **CSOM Int32**

### 3.2.5.196 Microsoft.SharePoint.Client.ThemeInfo

**TypeId:** {1E0A65DD-0C5F-4D2C-AB41-A74312709124}

**ShortName:** SP.ThemeInfo

Specifies a **theme** for a **site (2)**.<200>

#### 3.2.5.196.1 Properties

##### 3.2.5.196.1.1Scalar Properties

###### 3.2.5.196.1.1.1 AccessibleDescription

Type: **CSOM String**

**Accessibility:** Read Only

Specifies the accessible description for this **theme**.

###### 3.2.5.196.1.1.2 ThemeBackgroundImageUri

Type: **CSOM String**

**Accessibility:** Read Only

Specifies the **URI** of the background image for this **theme**.

#### 3.2.5.196.1.2ObjectPath Properties

None.

### 3.2.5.196.2 Methods

### 3.2.5.196.2.1 Scalar Methods

#### 3.2.5.196.2.1.1 GetThemeFontByName

**Return Type:** CSOM String

Returns the name of the **theme** font for the specified font slot name and **language code identifier (LCID)**. MUST return **null** if the font slot does not exist.

**Parameters:**

*name:* Name of the font slot.

Type: CSOM String

*lcid:* The language code identifier (LCID) for the required language.

Type: **CSOM UInt32**

#### 3.2.5.196.2.1.2 GetThemeShadeByName

**Return Type:** CSOM String

Returns the **HTML** color code for the given theme color token.

**Parameters:**

*name:* The color token specifying a particular color slot in the theme.

Type: CSOM String

### 3.2.5.196.2.2 ObjectPath Methods

None.

## 3.2.5.197 Microsoft.SharePoint.Client.InformationRightsManagementSettings

**TypeId:** {DC0556DE-B544-4702-B2DC-9886AC31B25F}

**ShortName:** SP.InformationRightsManagementSettings

A collection of **Information Rights Management (IRM)** settings for a [list.<201>](#)

### 3.2.5.197.1 Properties

#### 3.2.5.197.1.1 Scalar Properties

##### 3.2.5.197.1.1.1 AllowPrint

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Specifies whether a user can print the downloaded **document**.

##### 3.2.5.197.1.1.2 AllowScript

**Type:** CSOM Boolean



**Accessibility:** Read/Write

Specifies whether a user can run scripts on the downloaded **document**.

### **3.2.5.197.1.1.3 AllowWriteCopy**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Specifies whether a user can write in a copy of the downloaded **document**.

### **3.2.5.197.1.1.4 DocumentAccessExpireDays**

**Type:** CSOM Int32

**Accessibility:** Read/Write

Specifies the number of days after which the downloaded **document** will expire.

### **3.2.5.197.1.1.5 DocumentLibraryProtectionExpireDate**

**Type:** CSOM DateTime

**Accessibility:** Read/Write

Specifies the date on which the **Information Rights Management (IRM)** protection of this **document library** will stop.

### **3.2.5.197.1.1.6 EnableDocumentAccessExpire**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Specifies whether the downloaded **document** will expire.

### **3.2.5.197.1.1.7 EnableGroupProtection**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Specifies whether the permission of the downloaded **document** is applicable to a **group**.

### **3.2.5.197.1.1.8 EnableLicenseCacheExpire**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Specifies whether a user MUST verify his or her credentials after certain intervals.

### **3.2.5.197.1.1.9 GroupName**

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies the **group** name (email address) that the permission is also applicable to.

### **3.2.5.197.1.1.10 LicenseCacheExpireDays**

**Type:** CSOM Int32

**Accessibility:** Read/Write

Specifies the number of days that the **Information Rights Management (IRM)** license can be cached by the application to open the downloaded document. When these elapse, the application will connect to the **IRM** server to validate the license.

### **3.2.5.197.1.1.11 PolicyDescription**

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies the permission **policy** description.

### **3.2.5.197.1.1.12 PolicyTitle**

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies the permission **policy** title.

### **3.2.5.197.1.1.13 EnableDocumentBrowserPublishingView**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Specifies whether publishing view is enabled in the **Office Add-in**. The default value is false.

### **3.2.5.197.1.1.14 DisableDocumentBrowserView**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Specifies whether to block the **Office Add-in** from showing this document. The default value is false.

### **3.2.5.197.1.1.15 TemplateId**

**Type:** CSOM String

**Accessibility:** Read/Write

Gets or sets the ID of the RMS template that will be applied to the file or library.

## **3.2.5.197.1.2ObjectPath Properties**

None.

## **3.2.5.197.2 Methods**

### **3.2.5.197.2.1 Scalar Methods**

#### **3.2.5.197.2.1.1 Reset**

**Return Type:** None

Resets all the properties to default value.

**Parameters:** None

### **3.2.5.197.2.1.2 Update**

**Return Type:** None

Updates the **document library** with changes that are made to the settings.

**Parameters:** None

### **3.2.5.197.2.2ObjectPath Methods**

None.

## **3.2.5.198 Microsoft.BusinessData.MetadataModel.Collections.EntityInstanceCollection**

**TypeId:** {973B9891-3BEF-4117-9E6F-90BDD6746D03}

**ShortName:** SP.BusinessData.Collections.EntityInstanceCollection

Specifies a read only collection of **EntityInstances**.<202>

### **3.2.5.198.1 Properties**

#### **3.2.5.198.1.1Scalar Properties**

None.

#### **3.2.5.198.1.2ObjectPath Properties**

None.

### **3.2.5.198.2 Methods**

#### **3.2.5.198.2.1Scalar Methods**

None.

#### **3.2.5.198.2.2ObjectPath Methods**

None.

## **3.2.5.199 Microsoft.BusinessData.MetadataModel.Collections.FilterCollection**

**TypeId:** {508617EA-E4BD-4EC7-817C-B8335C6384A2}

**ShortName:** SP.BusinessData.Collections.FilterCollection

Specifies a read only collection of filters.<203>

### **3.2.5.199.1 Properties**

### 3.2.5.199.1.1 Scalar Properties

None.

### 3.2.5.199.1.2 ObjectPath Properties

None.

## 3.2.5.199.2 Methods

### 3.2.5.199.2.1 Scalar Methods

#### 3.2.5.199.2.1.1 SetFilterValue

**Return Type:** None

Sets a value for a filter in the **FilterCollection** (section [3.2.5.199](#)).

**Parameters:**

*inputFilterName*: Filter name to which the value is set.

Type: **CSOM String**

It MUST NOT be NULL. It MUST NOT be empty.

*valueIndex*: The index in the filter value array for the value.

Type: **CSOM Int32**

Its value MUST be equal to or greater than 0.

*value*: New value for the filter.

Type: **CSOM Object**

**Exceptions:**

Error Code	Error Type Name	Condition
-1	Microsoft.BusinessData.Infrastructure.AccessDeniedException	User does not have permissions to modify the filter value.
-1	Microsoft.BusinessData.Runtime.ObjectNotFoundException	A filter item with the given name does not exist.
-2147467261	System.ArgumentNullException	The <i>inputFilterName</i> is <b>null</b> or empty.
-2146233086	System.ArgumentOutOfRangeException	The value at index in the filter is not accessible for modification. This problem occurs when the index is out of range.
-1	System.InvalidOperationException	Requested filter cannot be modified. Filter modification operation attempted on a non-modifiable filter.

### 3.2.5.199.2.2 ObjectPath Methods

None.

### 3.2.5.200 Microsoft.SharePoint.Client.ContextWebInformation

**TypeId:** {DF0C42FE-FC26-4D81-A32E-A40090D1ACB7}

**ShortName:** SP.ContextWebInformation

Specifies metadata about a [site \(2\)](#).<204>

#### 3.2.5.200.1 Properties

##### 3.2.5.200.1.1 Scalar Properties

###### 3.2.5.200.1.1.1 FormDigestTimeoutSeconds

**Type:** CSOM Int32

**Accessibility:** Read Only

Specifies the amount of time in seconds before security validation expires.

###### 3.2.5.200.1.1.2 FormDigestValue

**Type:** CSOM String

**Accessibility:** Read Only

Specifies a valid [form digest](#) for the [site \(2\)](#).

###### 3.2.5.200.1.1.3 LibraryVersion

**Type:** CSOM String

**Accessibility:** Read Only

Specifies the library version.

###### 3.2.5.200.1.1.4 SiteFullUrl

**Type:** CSOM String

**Accessibility:** Read Only

Specifies the URL of the [site collection](#) that contains the [site \(2\)](#).

###### 3.2.5.200.1.1.5 SupportedSchemaVersions

**Type:** CSOM array of CSOM String

**Accessibility:** Read Only

Specifies the supported client-side object model (CSOM) request [schema version](#).

###### 3.2.5.200.1.1.6 WebFullUrl

**Type:** CSOM String

**Accessibility:** Read Only

Specifies the URL of the **site (2)**.

### 3.2.5.200.1.2 ObjectPath Properties

None.

### 3.2.5.201 Microsoft.SharePoint.Client.EventReceiverDefinition

**TypeId:** {A8D3515C-1135-4FFF-95A6-4E5E5FFF4ADC}

**ShortName:** SP.EventReceiverDefinition

Abstract base class that defines general properties of an **event receiver**.<205>

#### 3.2.5.201.1 Properties

##### 3.2.5.201.1.1 Scalar Properties

###### 3.2.5.201.1.1.1 EventType

**Type:** Microsoft.SharePoint.Client.EventReceiverType

**Accessibility:** Read Only

Specifies the type of event for the **event receiver** (section [3.2.5.205](#)).

###### 3.2.5.201.1.1.2 ReceiverAssembly

**Type:** CSOM String

**Accessibility:** Read Only

Specifies the **strong name** of the assembly that is used for the **event receiver**.

###### 3.2.5.201.1.1.3 ReceiverClass

**Type:** CSOM String

**Accessibility:** Read Only

Specifies a string that represents the class that is used for receiving events.

###### 3.2.5.201.1.1.4 ReceiverName

**Type:** CSOM String

**Accessibility:** Read Only

Specifies the name of the **event receiver**.

###### 3.2.5.201.1.1.5 ReceiverUrl

**Type:** CSOM String

**Accessibility:** Read Only

Specifies the **URL** of a web service that is used as an **event receiver**.

### **3.2.5.201.1.1.6 SequenceNumber**

**Type:** CSOM Int32

**Accessibility:** Read Only

Specifies an integer that represents the relative sequence of the event.

### **3.2.5.201.1.1.7 Synchronization**

**Type:** Microsoft.SharePoint.Client.EventReceiverSynchronization

**Accessibility:** Read Only

Specifies the synchronization of actions of this **event receiver** (section [3.2.5.204](#)).

### **3.2.5.201.1.1.8 ReceiverId**

**Type:** CSOM GUID

**Accessibility:** Read Only

Specifies the identifier of the **event receiver** definition.

### **3.2.5.201.1.2 ObjectPath Properties**

None.

## **3.2.5.201.2 Methods**

### **3.2.5.201.2.1 Scalar Methods**

#### **3.2.5.201.2.1.1 DeleteObject**

**Return Type:** None

Deletes an **event receiver** definition.

**Parameters:** None

#### **3.2.5.201.2.1.2 Update**

**Return Type:** None

Updates the data associated with the **event receiver** registration.

**Parameters:** None

### **3.2.5.201.2.2 ObjectPath Methods**

None.

## **3.2.5.202 Microsoft.SharePoint.Client.EventReceiverDefinitionCollection**

**TypeId:** {8AEF5B03-F05E-46E9-9537-6C3AAD574B7A}

**ShortName:** SP.EventReceiverDefinitionCollection

Represents a collection of SP.EventReceiverDefinition objects that are used to enumerate the list of registered event receivers for Windows SharePoint Services objects that can have events.

### 3.2.5.202.1 Properties

#### 3.2.5.202.1.1 Scalar Properties

None.

#### 3.2.5.202.1.2 ObjectPath Properties

None.

### 3.2.5.202.2 Methods

#### 3.2.5.202.2.1 Scalar Methods

None.

#### 3.2.5.202.2.2 ObjectPath Methods

##### 3.2.5.202.2.2.1 Add

**Return Type:** Microsoft.SharePoint.Client.EventReceiverDefinition

Creates an event receiver definition in the collection that is based on the specified event receiver creation information.

**Parameters:**

*eventReceiverCreationInformation:* The event receiver creation information from which to create the event receiver definition in the collection.

Type: Microsoft.SharePoint.Client.EventReceiverDefinitionCreationInformation

##### 3.2.5.202.2.2.2 GetById

**Return Type:** Microsoft.SharePoint.Client.EventReceiverDefinition

Returns the event receiver with the specified identifier.

**Parameters:**

*eventReceiverId:* The identifier of the event receiver.

Type: **CSOM GUID**

### 3.2.5.203 Microsoft.SharePoint.Client.EventReceiverDefinitionCreationInformation

**TypeId:** {2C15382F-B6E4-41F6-8616-4CBE0080A5DE}

**ShortName:** SP.EventReceiverDefinitionCreationInformation

Specifies **event receiver** creation information. [<206>](#)

### 3.2.5.203.1 Properties

#### 3.2.5.203.1.1 Scalar Properties



### **3.2.5.203.1.1.1 EventType**

**Type:** Microsoft.SharePoint.Client.EventReceiverType

**Accessibility:** Read/Write

Specifies the type of event as specified by **EventReceiverType** (section [3.2.5.205](#)).

### **3.2.5.203.1.1.2 ReceiverAssembly**

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies the **strong name** of the assembly that is used for receiving events.

### **3.2.5.203.1.1.3 ReceiverClass**

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies a string that represents the class that is used for receiving events.

### **3.2.5.203.1.1.4 ReceiverName**

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies the name of the **event receiver**.

### **3.2.5.203.1.1.5 ReceiverUrl**

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies the **URL** of a web service that is used for receiving events.

### **3.2.5.203.1.1.6 SequenceNumber**

**Type:** CSOM Int32

**Accessibility:** Read/Write

Specifies an integer that represents the relative sequence of the event.

### **3.2.5.203.1.1.7 Synchronization**

**Type:** Microsoft.SharePoint.Client.EventReceiverSynchronization

**Accessibility:** Read/Write

Specifies the execution synchronization of the **event receiver**.

### **3.2.5.203.1.2 ObjectPath Properties**

None.

### 3.2.5.204 Microsoft.SharePoint.Client.EventReceiverSynchronization

**ShortName:** SP.EventReceiverSynchronization

**Flag:** false

Specifies the synchronization state value for the specified **event receiver**.<207>

#### 3.2.5.204.1 Field Values

##### 3.2.5.204.1.1 DefaultSynchronization

**Value:** 0

Specifies to run the **event receiver** synchronously, as specified in section [3.2.5.204.1.2](#), if it is a Before event. Specifies to run the event receiver asynchronously, as specified in section [3.2.5.204.1.3](#), if it is an After event.

##### 3.2.5.204.1.2 Synchronous

**Value:** 1

Specifies that the **event receiver** is to run synchronously, or immediately.

##### 3.2.5.204.1.3 Asynchronous

**Value:** 2

Specifies that the **event receiver** is to run asynchronously, or under a timer service.

### 3.2.5.205 Microsoft.SharePoint.Client.EventReceiverType

**ShortName:** SP.EventReceiverType

**Flag:** false

Specifies the type of event that is handled by the **event receiver**.<208>

#### 3.2.5.205.1 Field Values

##### 3.2.5.205.1.1 InvalidReceiver

**Value:** -1

Indicates that an invalid **event receiver** type has been specified.

##### 3.2.5.205.1.2 ItemAdding

**Value:** 1

Specifies an **event** that occurs before an **item** is added.

##### 3.2.5.205.1.3 ItemUpdating

**Value:** 2

Specifies an **event** that occurs before an **item** is updated.

### **3.2.5.205.1.4ItemDeleting**

**Value:** 3

Specifies an **event** that occurs before an **item** is deleted.

### **3.2.5.205.1.5ItemCheckingIn**

**Value:** 4

Specifies an **event** that occurs before an **item** is checked in.

### **3.2.5.205.1.6ItemCheckingOut**

**Value:** 5

Specifies an **event** that occurs before an **item** is checked out.

### **3.2.5.205.1.7ItemUncheckingOut**

**Value:** 6

Specifies an **event** that occurs before a checkout of an **item** is reversed.

### **3.2.5.205.1.8ItemAttachmentAdding**

**Value:** 7

Specifies an **event** that occurs before an **attachment** is added to the **item**.

### **3.2.5.205.1.9ItemAttachmentDeleting**

**Value:** 8

Specifies an **event** that occurs before an **attachment** is removed from the **item**.

### **3.2.5.205.1.10 ItemFileMoving**

**Value:** 9

Specifies an **event** that occurs before a **file** is moved.

### **3.2.5.205.1.11 ItemVersionDeleting**

**Value:** 11

Specifies an **event** that occurs before an **item** version is deleted.

### **3.2.5.205.1.12 FieldAdding**

**Value:** 101

Specifies an **event** that occurs before a **field (2)** is added to a **list**.

### **3.2.5.205.1.13 FieldUpdating**

**Value:** 102

Specifies an **event** that occurs before a **field (2)** is updated.

### **3.2.5.205.1.14**      **FieldDeleting**

**Value:** 103

Specifies an **event** that occurs before a **field (2)** is deleted from a **list**.

### **3.2.5.205.1.15**      **ListAdding**

**Value:** 104

Specifies an **event** that occurs before a **list** is created.

### **3.2.5.205.1.16**      **ListDeleting**

**Value:** 105

Specifies an **event** that occurs before a **list** is deleted.

### **3.2.5.205.1.17**      **SiteDeleting**

**Value:** 201

Specifies an **event** that occurs before a **site collection** is deleted.

### **3.2.5.205.1.18**      **WebDeleting**

**Value:** 202

Specifies an **event** that occurs before a **site (2)** is deleted.

### **3.2.5.205.1.19**      **WebMoving**

**Value:** 203

Specifies an **event** that occurs before a **site (2) URL** is changed.

### **3.2.5.205.1.20**      **WebAdding**

**Value:** 204

Specifies an **event** that occurs before a new **site (2)** is created.

### **3.2.5.205.1.21**      **GroupAdding**

**Value:** 301

Specifies an **event** that occurs before a **security group** is added.

### **3.2.5.205.1.22**      **GroupUpdating**

**Value:** 302

Specifies an **event** that occurs before a **security group** is updated.

### **3.2.5.205.1.23**      **GroupDeleting**

**Value:** 303

Specifies an **event** that occurs before a **security group** is deleted.

### **3.2.5.205.1.24 GroupUserAdding**

**Value:** 304

Specifies an **event** that occurs before a user is added to a **security group**.

### **3.2.5.205.1.25 GroupUserDeleting**

**Value:** 305

Specifies an **event** that occurs before a user is deleted from a **security group**.

### **3.2.5.205.1.26 RoleDefinitionAdding**

**Value:** 306

Specifies an **event** that occurs before a **role definition** is added.

### **3.2.5.205.1.27 RoleDefinitionUpdating**

**Value:** 307

Specifies an **event** that occurs before a **role definition** is updated.

### **3.2.5.205.1.28 RoleDefinitionDeleting**

**Value:** 308

Specifies an **event** that occurs before a **role definition** is deleted.

### **3.2.5.205.1.29 RoleAssignmentAdding**

**Value:** 309

Specifies an **event** that occurs before a **role assignment** is added.

### **3.2.5.205.1.30 RoleAssignmentDeleting**

**Value:** 310

Specifies an **event** that occurs before a **role assignment** is deleted.

### **3.2.5.205.1.31 InheritanceBreaking**

**Value:** 311

Specifies an **event** that occurs before an inheritance is broken.

### **3.2.5.205.1.32 WorkflowStarting**

**Value:** 501

Specifies an **event** that occurs before a **workflow** starts running.

### **3.2.5.205.1.33 ItemAdded**

**Value:** 10001

Specifies an **event** that occurs after an **item** has been added.

### **3.2.5.205.1.34      ItemUpdated**

**Value:** 10002

Specifies an **event** that occurs after an **item** has been updated.

### **3.2.5.205.1.35      ItemDeleted**

**Value:** 10003

Specifies an **event** that occurs after an **item** has been deleted.

### **3.2.5.205.1.36      ItemCheckedIn**

**Value:** 10004

Specifies an **event** that occurs after an **item** has been checked in.

### **3.2.5.205.1.37      ItemCheckedOut**

**Value:** 10005

Specifies an **event** that occurs after an **item** has been checked out.

### **3.2.5.205.1.38      ItemUncheckedOut**

**Value:** 10006

Specifies an **event** that occurs after a check-out for an **item** has been reversed.

### **3.2.5.205.1.39      ItemAttachmentAdded**

**Value:** 10007

Specifies an **event** that occurs after an **attachment** has been added to an **item**.

### **3.2.5.205.1.40      ItemAttachmentDeleted**

**Value:** 10008

Specifies an **event** that occurs after an **attachment** has been removed from an **item**.

### **3.2.5.205.1.41      ItemFileMoved**

**Value:** 10009

Specifies an **event** that occurs after a **file** has been moved.

### **3.2.5.205.1.42      ItemFileConverted**

**Value:** 10010

Specifies an **event** that occurs after a **file** has been transformed from one type to another.

### **3.2.5.205.1.43      ItemVersionDeleted**

**Value:** 10011

Specifies an **event** that occurs after a version of an **item** of a **file** is deleted.

**3.2.5.205.1.44      FieldAdded**

**Value:** 10101

Specifies an **event** that occurs after a **field (2)** has been added.

**3.2.5.205.1.45      FieldUpdated**

**Value:** 10102

Specifies an **event** that occurs after a **field (2)** has been updated.

**3.2.5.205.1.46      FieldDeleted**

**Value:** 10103

Specifies an **event** that occurs after a **field (2)** has been deleted.

**3.2.5.205.1.47      ListAdded**

**Value:** 10104

Specifies an **event** that occurs after a **list** has been created.

**3.2.5.205.1.48      ListDeleted**

**Value:** 10105

Specifies an **event** that occurs after a **list** has been deleted.

**3.2.5.205.1.49      SiteDeleted**

**Value:** 10201

Specifies an **event** that occurs after a **site collection** has been deleted.

**3.2.5.205.1.50      WebDeleted**

**Value:** 10202

Specifies an **event** that occurs after a **site (2)** has been deleted.

**3.2.5.205.1.51      WebMoved**

**Value:** 10203

Specifies an **event** that occurs after a **site (2) URL** has been changed.

**3.2.5.205.1.52      WebProvisioned**

**Value:** 10204

Specifies an **event** that occurs after a new **site (2)** has been created, but before that new site (2) is provisioned.

**3.2.5.205.1.53      GroupAdded**

**Value:** 10301

Specifies an **event** that occurs after a **security group** has been added.

**3.2.5.205.1.54      GroupUpdated**

**Value:** 10302

Specifies an **event** that occurs after a **security group** has been updated.

**3.2.5.205.1.55      GroupDeleted**

**Value:** 10303

Specifies an **event** that occurs after a **security group** has been deleted.

**3.2.5.205.1.56      GroupUserAdded**

**Value:** 10304

Specifies an **event** that occurs after a user is added to a **security group**.

**3.2.5.205.1.57      GroupUserDeleted**

**Value:** 10305

Specifies an **event** that occurs after a user is deleted from a **security group**.

**3.2.5.205.1.58      RoleDefinitionAdded**

**Value:** 10306

Specifies an **event** that occurs after a **role definition** is added.

**3.2.5.205.1.59      RoleDefinitionUpdated**

**Value:** 10307

Specifies an **event** that occurs after a **role definition** is updated.

**3.2.5.205.1.60      RoleDefinitionDeleted**

**Value:** 10308

Specifies an **event** that occurs after a **role definition** is deleted.

**3.2.5.205.1.61      RoleAssignmentAdded**

**Value:** 10309

Specifies an **event** that occurs after a **role assignment** is added.

**3.2.5.205.1.62      RoleAssignmentDeleted**

**Value:** 10310

Specifies an **event** that occurs after a **role assignment** is deleted.

**3.2.5.205.1.63      InheritanceBroken**

**Value:** 10311



Specifies an **event** that occurs after an inheritance has been broken.

**3.2.5.205.1.64 WorkflowStarted**

**Value:** 10501

Specifies an **event** that occurs after a **workflow** has started running.

**3.2.5.205.1.65 WorkflowPostponed**

**Value:** 10502

Specifies an **event** that occurs after a **workflow** has been postponed.

**3.2.5.205.1.66 WorkflowCompleted**

**Value:** 10503

Specifies an **event** that occurs after a **workflow** has completed running.

**3.2.5.205.1.67 EntityInstanceAdded**

**Value:** 10601

Specifies an **event** that occurs after an **EntityInstance** has been added.

**3.2.5.205.1.68 EntityInstanceUpdated**

**Value:** 10602

Specifies an **event** that occurs after an **EntityInstance** has been updated.

**3.2.5.205.1.69 EntityInstanceDeleted**

**Value:** 10603

Specifies an **event** that occurs after an **EntityInstance** has been deleted.

**3.2.5.205.1.70 AppInstalled**

**Value:** 10701

Specifies an **event** that occurs after an **application** has been installed.

**3.2.5.205.1.71 AppUpgraded**

**Value:** 10702

Specifies an **event** that occurs after an **application** has been upgraded.

**3.2.5.205.1.72 AppUninstalling**

**Value:** 10703

Specifies an **event** that occurs after an **application** has been uninstalled.

**3.2.5.205.1.73 EmailReceived**

**Value:** 20000

Specifies an **event** that occurs after a **list** received an e-mail message.

#### **3.2.5.205.1.74 ContextEvent**

**Value:** 32766

Specifies an **event** that occurs after a **list** received a context event.

#### **3.2.5.205.1.75 InheritanceResetting**

**Value:** 312

Specifies an **event** that occurs before the role inheritance is restored.

#### **3.2.5.205.1.76 InheritanceReset**

**Value:** 10312

Specifies an **event** that occurs after the role inheritance is restored.

#### **3.2.5.205.1.77 WebRestored**

**Value:** 10205

Specifies an **event** that occurs after a site was restored from the recycle bin.

### **3.2.5.206 Microsoft.SharePoint.Client.RelatedItem**

**TypeId:** {627C69F5-12E8-46BC-9052-BD5E46E155D3}

**ShortName:** SP.RelatedItem

Specifies the data object representation of all the information needed to display related items in a **field (2)** control. [<209>](#)

#### **3.2.5.206.1 Properties**

##### **3.2.5.206.1.1 Scalar Properties**

###### **3.2.5.206.1.1.1 IconUrl**

**Type:** **CSOM String**

**Accessibility:** Read/Write

The **URL** of the icon for the **list item**.

###### **3.2.5.206.1.1.2 ItemId**

**Type:** **CSOM Int32**

**Accessibility:** Read/Write

The **list item identifier** of the **list item**.

###### **3.2.5.206.1.1.3 ListId**

**Type:** **CSOM String**

**Accessibility:** Read/Write

The **list identifier** of the **parent list** of the **list item**.

If **ListId** is NULL then the parent list of the target list item is the same as the parent list of the source list item.

#### **3.2.5.206.1.1.4 Title**

**Type:** CSOM String

**Accessibility:** Read/Write

This property is first mapped to the **Title** property of underlying **list item** if the **Title** property is not **null**. If that fails, it is mapped it to the **Title** or **Filename** property of **ListItem.File** (section [3.2.5.87.1.2.5](#)) object if present. Finally the mapping defaults to a static title string.

#### **3.2.5.206.1.1.5 Url**

**Type:** CSOM String

**Accessibility:** Read/Write

Maps to the default display form **URL** for the underlying **list item** or file URL if **ListItem.File** (section [3.2.5.87.1.2.5](#)) object is present.

#### **3.2.5.206.1.1.6 WebId**

**Type:** CSOM String

**Accessibility:** Read/Write

The **site identifier** for the **site (2)** which contains the **parent list** of the **list item**.

If **WebId** is NULL then the site (2) that contains the target list item is the same as the site (2) that contains the source list item.

### **3.2.5.206.1.2ObjectPath Properties**

None.

### **3.2.5.207 Microsoft.SharePoint.Client.RelatedItemManager**

**TypeId:** {23AF17DB-2585-4D17-82A7-AA9E3FBA099D}

**ShortName:** SP.RelatedItemManager

Specifies a static class that provides methods to add, delete and enumerate related items to a particular **ListItem** (section [3.2.5.87](#)).<210>

#### **3.2.5.207.1 Properties**

##### **3.2.5.207.1.1Scalar Properties**

None.

##### **3.2.5.207.1.2ObjectPath Properties**

None.

## 3.2.5.207.2 Methods

### 3.2.5.207.2.1 Scalar Methods

#### 3.2.5.207.2.1.1 AddSingleLink

This method is a **static CSOM method**.

**Return Type:** None

Adds a unidirectional link from one **list item** to another.

**Parameters:**

*SourceListName:* Specifies the title or **list identifier** for the **parent list** of the source list item.

Type: **CSOM String**

*SourceItemID:* Specifies the **list item identifier** of the source list item.

Type: **CSOM Int32**

*SourceWebUrl:* Specifies the **URL** or **site identifier** for the **site (2)** which contains the parent list of the source list item.

Type: CSOM String

If SourceWebUrl is Null the Current Web will be used.

*TargetListName:* Specifies the title or list identifier for the parent list of the target list item.

Type: CSOM String

*TargetItemID:* Specifies the list item identifier of the target list item.

Type: CSOM Int32

*TargetWebUrl:* Specifies the URL or site identifier for the site (2) which contains the parent list of the target list item.

Type: CSOM String

*TryAddReverseLink:* Specifies whether an attempt will be made to create a link from the target list item to the source list item in addition to the link from the source item to the target item.

Type: **CSOM Boolean**

No error will be raised if adding the reverse link fails.

#### 3.2.5.207.2.1.2 DeleteSingleLink

This method is a **static CSOM method**.

**Return Type:** None

Deletes a unidirectional link between source and target **list items**.

**Parameters:**

*SourceListName:* Specifies the title or **list identifier** for the **parent list** of the source list item.

Type: **CSOM String**

*SourceItemID*: Specifies the **list item identifier** of the source list item.

Type: **CSOM Int32**

*SourceWebUrl*: Specifies the **URL** or **site identifier** for the **site (2)** which contains the parent list of the source list item.

Type: CSOM String

*TargetListName*: Specifies the title or list identifier for the parent list of the target list item.

Type: CSOM String

*TargetItemID*: Specifies the list item identifier of the target list item.

Type: CSOM Int32

*TargetWebUrl*: Specifies the URL or site identifier for the site (2) which contains the parent list of the target list item.

Type: CSOM String

*TryDeleteReverseLink*: Specifies whether an attempt will be made to delete a link from the target list item to the source list item in addition to deleting the link from the source item to the target item.

Type: **CSOM Boolean**

No error will be raised if deleting the reverse link fails.

### **3.2.5.207.2.1.3      GetPageOneRelatedItems**

This method is a **static CSOM method**.

**Return Type:** **CSOM array** of Microsoft.SharePoint.Client.RelatedItem

Returns a list of items related to the source **list item**. The maximum count of related items is four.

#### **Parameters:**

*SourceListName*: Specifies the **Title** property for the **ParentList** (section [3.2.5.87.1.2.6](#)) property of the source list item.

Type: **CSOM String**

*SourceItemID*: Specifies the **Id** (section [3.2.5.87.1.1.5](#)) property of the source list item.

Type: **CSOM Int32**

### **3.2.5.207.2.1.4      GetRelatedItems**

This method is a **static CSOM method**.

**Return Type:** **CSOM array** of Microsoft.SharePoint.Client.RelatedItem

Returns a list of items related to the source **list item**. The maximum count of related items is nine.

#### **Parameters:**

*SourceListName*: Specifies the **Title** property for the **ParentList** (section [3.2.5.87.1.2.6](#)) property of the source list item.

Type: **CSOM String**

*SourceItemID*: Specifies the **Id** (section [3.2.5.87.1.1.5](#)) property of the source list item.

Type: **CSOM Int32**

### **3.2.5.207.2.1.5 AddSingleLinkFromUrl**

This method is a **static CSOM method**.

**Return Type:** None

Adds a unidirectional link from one **list item** to another using a URL for the source list item.

**Parameters:**

*SourceItemUrl*: Specifies a URL for the source list item.

Type: **CSOM String**

*TargetListName*: Specifies the title or **list identifier** for the **parent list** of the target list item.

Type: CSOM String

*TargetItemID*: Specifies the **list item identifier** of the target list item.

Type: **CSOM Int32**

*TryAddReverseLink*: Specifies whether an attempt will be made to create a link from the target list item to the source list item in addition to the link from the source item to the target item.

Type: **CSOM Boolean**

No error will be raised if adding the reverse link fails.

### **3.2.5.207.2.1.6 AddSingleLinkToUrl**

This method is a **static CSOM method**.

**Return Type:** None

Adds a unidirectional link from one **list item** to another using a URL for the target list item.

**Parameters:**

*SourceListName*: Specifies the title or **list identifier** for the **parent list** of the source list item.

Type: **CSOM String**

*SourceItemID*: Specifies the **list item identifier** of the source list item.

Type: **CSOM Int32**

*TargetItemUrl*: Specifies a URL pointing to the target item.

Type: CSOM String

*TryAddReverseLink*: Specifies whether an attempt will be made to create a link from the target list item to the source list item in addition to the link from the source item to the target item.

Type: **CSOM Boolean**

No error will be raised if adding the reverse link fails.

### 3.2.5.207.2.2ObjectPath Methods

None.

### 3.2.5.208 Microsoft.SharePoint.Client.UpgradeType

**ShortName:** SP.UpgradeType

**Flag:** false

Specifies the type of **site collection** upgrade to conduct on a site collection. [<211>](#)

#### 3.2.5.208.1 Field Values

##### 3.2.5.208.1.1BuildUpgrade

**Value:** 0

Specifies build-to-build (**minor version**) **site collection** upgrade.

##### 3.2.5.208.1.2VersionUpgrade

**Value:** 1

Specifies version-to-version (**major version**) **site collection** upgrade.

### 3.2.5.209 Microsoft.SharePoint.Client.Utilities.WikiPageCreationInformation

**TypeId:** {9E154AAB-8847-4CF9-8BFA-EB8C1EC47926}

**ShortName:** SP.Utilities.WikiPageCreationInformation

Specifies wiki page creation information. [<212>](#)

#### 3.2.5.209.1 Properties

##### 3.2.5.209.1.1Scalar Properties

###### 3.2.5.209.1.1.1 ServerRelativeUrl

**Type:** **CSOM String**

**Accessibility:** Read/Write

The **server-relative URL** of the wiki page to be created.

It MUST NOT be empty. It MUST be a URL of server-relative form.

###### 3.2.5.209.1.1.2 WikiHtmlContent

**Type:** **CSOM String**

**Accessibility:** Read/Write

The **HTML** content of the wiki page.

##### 3.2.5.209.1.2ObjectPath Properties

None.

### 3.2.5.210 Microsoft.BusinessData.MetadataModel.AppBdcCatalog

**TypeId:** {8D36B2B8-5B9A-49A8-892B-5E9539FAF4E8}

**ShortName:** SP.BusinessData.AppBdcCatalog

Represents the **Business Data Connectivity (BDC) MetadataCatalog** for an **application** that contains **external content types** provisioned by the application. <213>

#### 3.2.5.210.1 Properties

##### 3.2.5.210.1.1 Scalar Properties

None.

##### 3.2.5.210.1.2 ObjectPath Properties

None.

#### 3.2.5.210.2 Methods

##### 3.2.5.210.2.1 Scalar Methods

###### 3.2.5.210.2.1.1 GetConnectionId

**Return Type:** CSOM String

Gets the identifier for the external connection being used by the given external system instance.

**Parameters:**

*lobSystemName:* The name of the external **line-of-business (LOB) system** under which the external system instance is defined.

Type: CSOM String

It MUST NOT be NULL. It MUST NOT be empty.

*lobSystemInstanceName:* The name of the external line-of-business (LOB) system instance.

Type: CSOM String

It MUST NOT be NULL. It MUST NOT be empty.

**Exceptions:**

Error Code	Error Type Name	Condition
- 2147024809	System.ArgumentException	Either the line-of-business (LOB) system or line-of-business (LOB) system instance does not exist in the <b>Business Data Connectivity (BDC) MetadataCatalog</b> file.
- 2147467261	System.ArgumentNullException	At least one of the parameters is <b>null</b> .
- 2147024894	System.IO.FileNotFoundException	BDC MetadataCatalog file not found.



### 3.2.5.210.2.1.2 GetLobSystemInstanceProperty

**Return Type:** CSOM String

Gets the value of the specified property for the given external system instance.

**Parameters:**

*lobSystemName:* The name of the external **line-of-business (LOB) system** under which the external system instance is defined.

Type: CSOM String

It MUST NOT be NULL. It MUST NOT be empty.

*lobSystemInstanceName:* The name of the external line-of-business (LOB) system instance.

Type: CSOM String

It MUST NOT be NULL. It MUST NOT be empty.

*propertyName:* The name of the property whose value is retrieved.

Type: CSOM String

It MUST NOT be NULL. It MUST NOT be empty. The allowed properties whose value can be read are **WcfEndpointAddress**, **ODataServiceUrl**, **RdbConnection Data Source** and **ODataConnectionSettingsId**. These properties are described in [\[MS-BDCMFFS\]](#) section 2.1.3.24.

**Exceptions:**

Error Code	Error Type Name	Condition
- 2147024809	System.ArgumentException	Either the line-of-business (LOB) system or line-of-business (LOB) system instance does not exist in the <b>Business Data Connectivity (BDC) MetadataCatalog</b> file.
- 2147467261	System.ArgumentNullException	At least one of the parameters is <b>null</b> .
-1	System.InvalidOperationException	Tried to read a property that is not in the list of properties whose value can be read.
- 2147024894	System.IO.FileNotFoundException	BDC MetadataCatalog file not found.

### 3.2.5.210.2.1.3 GetLobSystemProperty

**Return Type:** CSOM String

Gets the value of the specified property for the given external system.

**Parameters:**

*lobSystemName:* The name of the external **line-of-business (LOB) system**.

Type: CSOM String

It MUST NOT be NULL. It MUST NOT be empty.

*propertyName*: The name of the property whose value is retrieved.

Type: CSOM String

It MUST NOT be NULL. It MUST NOT be empty. The allowed properties whose value can be read are **WcfMexDocumentUrl**, **DataServiceMetadataUrl** and **RdbConnection Data Source**. **WcfMexDocumentUrl** and **DataServiceMetadataUrl** properties are described in [\[MS-BDCMFFS\]](#) section 2.1.3.23.

**Exceptions:**

Error Code	Error Type Name	Condition
-2147024809	System.ArgumentException	Line-of-business (LOB) system does not exist in the <b>Business Data Connectivity (BDC) MetadataCatalog</b> file.
-2147467261	System.ArgumentNullException	At least one of the parameters is <b>null</b> .
-1	System.InvalidOperationException	Tried to read a property that is not in the list of properties whose value can be read.
-2147024894	System.IO.FileNotFoundException	Business Data Connectivity (BDC) MetadataCatalog file not found.

**3.2.5.210.2.1.4 GetPermissibleConnections**

**Return Type:** CSOM array of CSOM String

Gets the list of external connections that the **application** has permissions to use.

**Parameters:** None

**Exceptions:**

Error Code	Error Type Name	Condition
-1	Microsoft.SharePoint.SPException	The list of external connections that the application has permissions to could not be retrieved.

**3.2.5.210.2.1.5 SetConnectionId**

**Return Type:** None

Sets the identifier for the external connection that will be used by the given external system instance.

**Parameters:**

*lobSystemName*: The name of the external **line-of-business (LOB) system** under which the external system instance is defined.

Type: CSOM String

It MUST NOT be NULL. It MUST NOT be empty.

*lobSystemInstanceName*: The name of the external line-of-business (LOB) system instance.

Type: CSOM String

It MUST NOT be NULL. It MUST NOT be empty.

*connectionId*: Identifier for the external connection.

Type: CSOM String

It MUST NOT be NULL. It MUST NOT be empty.

#### Exceptions:

Error Code	Error Type Name	Condition
-1	Microsoft.SharePoint.SPException	The list of external connections could not be retrieved.
-2147024809	System.ArgumentException	Either the line-of-business (LOB) system or line-of-business (LOB) system instance does not exist in the <b>Business Data Connectivity (BDC) MetadataCatalog</b> file.
-2147467261	System.ArgumentNullException	At least one of the parameters is <b>null</b> .
-2147024894	System.IO.FileNotFoundException	BDC MetadataCatalog file not found.

### 3.2.5.210.2.1.6 SetLobSystemInstanceProperty

**Return Type:** None

Sets the value of the specified property for the given external system instance.

#### Parameters:

*lobSystemName*: The name of the external **line-of-business (LOB) system** under which the external system instance is defined.

Type: **CSOM String**

It MUST NOT be NULL. It MUST NOT be empty.

*lobSystemInstanceName*: The name of the external line-of-business (LOB) system instance.

Type: CSOM String

It MUST NOT be NULL. It MUST NOT be empty.

*propertyName*: The name of the property whose value needs to be set.

Type: CSOM String

It MUST NOT be NULL. It MUST NOT be empty. The allowed properties whose value can be set are **WcfEndpointAddress**, **ODataServiceUrl**, **RdbConnection Data Source** and **ODataConnectionSettingsId**.

*propertyValue*: New value for the property.

Type: CSOM String

**Exceptions:**

Error Code	Error Type Name	Condition
- 2147024809	System.ArgumentException	Either the line-of-business (LOB) system or line-of-business (LOB) system instance does not exist in the <b>Business Data Connectivity (BDC) MetadataCatalog</b> file.
- 2147467261	System.ArgumentNullException	At least one of the parameters is <b>null</b> .
-1	System.InvalidOperationException	Tried to set a property that is not in the list of properties whose value can be set.
- 2147024894	System.IO.FileNotFoundException	BDC MetadataCatalog file not found.

**3.2.5.210.2.1.7 SetLobSystemProperty**

**Return Type:** None

Sets the value of the specified property for the given external system.

**Parameters:**

*lobSystemName:* The name of the external **line-of-business (LOB) system**.

Type: **CSOM String**

It MUST NOT be NULL. It MUST NOT be empty.

*propertyName:* The name of the property whose value needs to be set.

Type: CSOM String

It MUST NOT be NULL. It MUST NOT be empty. The allowed properties whose value can be set are **WcfMexDocumentUrl**, **ODataServiceMetadataUrl** and **RdbConnection Data Source**.

*propertyValue:* New value for the property.

Type: CSOM String

**Exceptions:**

Error Code	Error Type Name	Condition
- 2147024809	System.ArgumentException	LOB system does not exist in the <b>Business Data Connectivity (BDC) MetadataCatalog</b> file.
- 2147467261	System.ArgumentNullException	At least one of the parameters is <b>null</b> .
-1	System.InvalidOperationException	Tried to set a property which is not in the list of properties whose value can be set.
- 2147024894	System.IO.FileNotFoundException	Business Data Connectivity (BDC) MetadataCatalog file not found.

### 3.2.5.210.2.2 ObjectPath Methods

#### 3.2.5.210.2.2.1 GetEntity

**Return Type:** Microsoft.BusinessData.MetadataModel.Entity

Gets the **external content type** with the given name and namespace.

**Parameters:**

*namespace:* The namespace of the external content type. Namespaces are case sensitive.

Type: **CSOM String**

It MUST NOT be NULL. It MUST NOT be empty.

*name:* The name of the external content type. Names are case sensitive.

Type: CSOM String

It MUST NOT be NULL. It MUST NOT be empty.

**Exceptions:**

Error Code	Error Type Name	Condition
-1	Microsoft.BusinessData.MetadataModel.MetadataObjectNotFoundException	Entity with the given parameters cannot be found.
-2147467261	System.ArgumentNullException	At least one of the parameters is <b>null</b> .
-2147024894	System.IO.FileNotFoundException	<b>Business Data Connectivity (BDC) MetadataCatalog</b> file not found.

#### 3.2.5.211 Microsoft.SharePoint.Client.SiteHealth.SiteHealthSummary

**TypeId:** {9B6A775C-EE99-4DF4-B251-3E004216D5B0}

**ShortName:** SP.SiteHealth.SiteHealthSummary

Specifies a summary of the results of running a set of **site collection** health rules. [<214>](#)

##### 3.2.5.211.1 Properties

###### 3.2.5.211.1.1 Scalar Properties

###### 3.2.5.211.1.1.1 FailedErrorCount

Type: **CSOM Int32**

**Accessibility:** Read Only

Specifies the number of **site collection** health rules that failed with an error.

#### **3.2.5.211.1.1.2 FailedWarningCount**

**Type:** CSOM Int32

**Accessibility:** Read Only

Specifies the number of **site collection** health rules that failed with a warning.

#### **3.2.5.211.1.1.3 PassedCount**

**Type:** CSOM Int32

**Accessibility:** Read Only

Specifies the number of **site collection** health rules that passed.

#### **3.2.5.211.1.1.4 Results**

**Type:** CSOM array of Microsoft.SharePoint.Client.SiteHealth.SiteHealthResult

**Accessibility:** Read Only

Specifies a list of **site collection** health rule results, one for each site collection health rule that was run.

#### **3.2.5.211.1.2ObjectPath Properties**

None.

#### **3.2.5.211.2 Methods**

##### **3.2.5.211.2.1Scalar Methods**

None.

##### **3.2.5.211.2.2ObjectPath Methods**

None.

#### **3.2.5.212 Microsoft.SharePoint.Client.Utilities.EmailProperties**

**TypeId:** {FAB1608D-FDFB-4C8C-BB0A-9B9CC3618A15}

**ShortName:** SP.Utilities.EmailProperties

Specifies the definition of the email to send which includes both the message fields and body. [<215>](#)

##### **3.2.5.212.1 Properties**

###### **3.2.5.212.1.1Scalar Properties**

###### **3.2.5.212.1.1.1 AdditionalHeaders**

**Type:** CSOM dictionary

**Accessibility:** Read/Write

Specifies the email headers collection that corresponds to any additional fields of the message.

#### **3.2.5.212.1.1.2 BCC**

**Type:** CSOM array of CSOM String

**Accessibility:** Read/Write

Specifies the **blind carbon copy (bcc) recipients** of the email.

#### **3.2.5.212.1.1.3 Body**

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies the **message body** to send.

#### **3.2.5.212.1.1.4 CC**

**Type:** CSOM array of CSOM String

**Accessibility:** Read/Write

Specifies the **carbon copy (cc) recipients** of the email.

#### **3.2.5.212.1.1.5 From**

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies the From field of the email.

#### **3.2.5.212.1.1.6 Subject**

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies the Subject field of the e-mail.

#### **3.2.5.212.1.1.7 To**

**Type:** CSOM array of CSOM String

**Accessibility:** Read/Write

Specifies the To field of the email.

#### **3.2.5.212.1.2ObjectPath Properties**

None.

#### **3.2.5.213 Microsoft.BusinessData.MetadataModel.Filter**

**TypeId:** {EA36AF83-3D6A-4AE3-9EB1-4ED8E85EB176}

**ShortName:** SP.BusinessData.Filter

Specifies filters that are used to filter the data returned by the external **line-of-business (LOB) system**.<216>

Filters are the mechanism to pass parameters to the external LOB system methods.

### **3.2.5.213.1 Properties**

#### **3.2.5.213.1.1 Scalar Properties**

##### **3.2.5.213.1.1.1 DefaultDisplayName**

**Type:** CSOM String

**Accessibility:** Read Only

Specifies the default display name of the filter.

##### **3.2.5.213.1.1.2 FilterField**

**Type:** CSOM String

**Accessibility:** Read Only

Specifies the **field (3)** in the **View** that is affected by the result of this filter, described by dot notation path, which is a representation of the data elements similar to accessing data elements in C#. Each data element is accessed by providing their parent data element and the name of the data element if the containing data element is a structure, or the index of the data element, if the containing element is a collection.

##### **3.2.5.213.1.1.3 FilterType**

**Type:** CSOM String

**Accessibility:** Read Only

Specifies the type of the filter.

Valid Filter Types are "Comparison", "LastId", "Limit", "PageNumber", "Password", "SsoTicket", "Timestamp", "UserContext", "Username", "UserProfile", "Wildcard", "Input", "Output", "InputOutput", "Batching", "BatchingTermination", "UserCulture", "ActivityId" and "Sorting".

It MUST NOT be NULL. It MUST NOT be empty.

##### **3.2.5.213.1.1.4 LocalizedDisplayName**

**Type:** CSOM String

**Accessibility:** Read Only

Specifies the localized display name of the **field (3)** if available.

##### **3.2.5.213.1.1.5 Name**

**Type:** CSOM String

**Accessibility:** Read Only

Specifies the name of the filter.

It MUST NOT be NULL. It MUST NOT be empty.



### 3.2.5.213.1.1.6 ValueCount

Type: **CSOM Int32**

Accessibility: Read Only

Specifies the number of values for this filter.

Its value MUST be equal to or greater than 0.

### 3.2.5.213.1.2ObjectPath Properties

None.

### 3.2.5.213.2 Methods

#### 3.2.5.213.2.1Scalar Methods

None.

#### 3.2.5.213.2.2ObjectPath Methods

None.

## 3.2.5.214 Microsoft.BusinessData.MetadataModel.MethodExecutionResult

TypeId: {EA36AF83-3D6A-4AE3-9EB1-4ED8E85EB179}

ShortName: SP.BusinessData.MethodExecutionResult

Represents generic invoker method result. [<217>](#)

### 3.2.5.214.1 Properties

#### 3.2.5.214.1.1Scalar Properties

None.

#### 3.2.5.214.1.2ObjectPath Properties

##### 3.2.5.214.1.2.1 ReturnParameterCollection

Type: Microsoft.BusinessData.MetadataModel.ReturnParameterCollection

Accessibility: Read Only

Specifies the **ReturnParameterCollection** (section [3.2.5.215](#)) for the **MethodExecutionResult** (section [3.2.5.214](#)).

### 3.2.5.214.2 Methods

#### 3.2.5.214.2.1Scalar Methods

None.

#### 3.2.5.214.2.2ObjectPath Methods

None.

### 3.2.5.215 Microsoft.BusinessData.MetadataModel.ReturnParameterCollection

**TypeId:** {48264C2B-6775-458B-88DE-0C2A11938A03}

**ShortName:** SP.BusinessData.ReturnParameterCollection

Represents a read only collection of **EntityFieldValueDictionary** (section [3.2.5.164](#)) objects. [<218>](#)

#### 3.2.5.215.1 Properties

##### 3.2.5.215.1.1 Scalar Properties

None.

##### 3.2.5.215.1.2 ObjectPath Properties

None.

#### 3.2.5.215.2 Methods

##### 3.2.5.215.2.1 Scalar Methods

None.

##### 3.2.5.215.2.2 ObjectPath Methods

None.

### 3.2.5.216 Microsoft.SharePoint.Client.SiteHealth.SiteHealthResult

**TypeId:** {3BA0823B-9B49-433B-A8A6-65A5139F06EC}

**ShortName:** SP.SiteHealth.SiteHealthResult

Specifies the result of running a **site collection** health rule. [<219>](#)

#### 3.2.5.216.1 Properties

##### 3.2.5.216.1.1 Scalar Properties

###### 3.2.5.216.1.1.1 Status

**Type:** Microsoft.SharePoint.Client.SiteHealth.SiteHealthStatusType

**Accessibility:** Read/Write

Specifies the success or failure mode returned by a **site collection** health rule.

###### 3.2.5.216.1.1.2 TimeStamp

**Type:** **CSOM DateTime**

**Accessibility:** Read/Write

Specifies the date and time when the **site collection** health rule was run.

###### 3.2.5.216.1.1.3 MessageAsText

**Type:** CSOM String

**Accessibility:** Read Only

Specifies a summary of the results of running a **site collection** health rule.

#### 3.2.5.216.1.1.4 RuleHelpLink

**Type:** CSOM String

**Accessibility:** Read Only

Specifies a **hyperlink** to help information about the **site collection** health rule.

#### 3.2.5.216.1.1.5 RuleId

**Type:** CSOM GUID

**Accessibility:** Read Only

Specifies the unique identifier of the **site collection** health rule.

#### 3.2.5.216.1.1.6 RuleIsRepairable

**Type:** CSOM Boolean

**Accessibility:** Read Only

Specifies whether the **site collection** health rule is capable of attempting a repair of the issues found by the rule.

#### 3.2.5.216.1.1.7 RuleName

**Type:** CSOM String

**Accessibility:** Read Only

Specifies the name of the **site collection** health rule.

### 3.2.5.216.1.2 ObjectPath Properties

None.

### 3.2.5.217 Microsoft.SharePoint.ApplicationPages.ClientPickerQuery.ClientPeoplePickerQueryParameters

**TypeId:** {AC9358C6-E9B1-4514-BF6E-106ACBFB19CE}

**ShortName:** SP.UI.ApplicationPages.ClientPeoplePickerQueryParameters

Specifies the properties of a **principal** query. [<220>](#)

#### 3.2.5.217.1 Properties

##### 3.2.5.217.1.1 Scalar Properties

##### 3.2.5.217.1.1.1 AllowEmailAddresses

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Specifies whether the **principal** query can return a resolved principal matching an unverified **e-mail address** when unable to resolve to a known principal.

### **3.2.5.217.1.1.2 AllowMultipleEntities**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Specifies whether the **principal** query allows multiple values.

### **3.2.5.217.1.1.3 AllUrlZones**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Specifies whether the **principal** query will search all locations in the topology of the **farm**.

### **3.2.5.217.1.1.4 EnabledClaimProviders**

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies the **claims providers** to be used in the **principal** query.

### **3.2.5.217.1.1.5 MaximumEntitySuggestions**

**Type:** CSOM Int32

**Accessibility:** Read/Write

Specifies the maximum number of **principals** to be returned by the principal query.

### **3.2.5.217.1.1.6 PrincipalSource**

**Type:** Microsoft.SharePoint.Client.Utilities.PrincipalSource

**Accessibility:** Read/Write

Specifies the source to be used in the **principal** query.

### **3.2.5.217.1.1.7 PrincipalType**

**Type:** Microsoft.SharePoint.Client.Utilities.PrincipalType

**Accessibility:** Read/Write

Specifies the type to be used in the **principal** query.

### **3.2.5.217.1.1.8 QueryString**

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies the value to be used in the **principal** query.

### **3.2.5.217.1.1.9 Required**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Specifies whether the **principal** query is required to return a result.

### **3.2.5.217.1.1.10 SharePointGroupID**

**Type:** CSOM Int32

**Accessibility:** Read/Write

Specifies a **group** containing allowed **principals** to be used in the principal query.

### **3.2.5.217.1.1.11 UrlZone**

**Type:** Microsoft.SharePoint.Client.UrlZone

**Accessibility:** Read/Write

Specifies a location in the topology of the **farm** for the **principal** query.

### **3.2.5.217.1.1.12 UrlZoneSpecified**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Specifies whether any locations in the topology of the **farm** have been specified for the **principal** query.

### **3.2.5.217.1.1.13 WebApplicationID**

**Type:** CSOM GUID

**Accessibility:** Read/Write

Specifies the identifier of the **Web application** to be used in the **principal** query.

### **3.2.5.217.1.1.14 ForceClaims**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Specifies whether the **principal** query SHOULD be handled by **claims providers**.

### **3.2.5.217.1.1.15 AllowOnlyEmailAddresses**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Specifies whether to allow the picker to resolve only email addresses as valid entities.

This property is only used when **AllowEmailAddresses** (section [3.2.5.217.1.1.1](#)) is set to True. Otherwise it is ignored.

### 3.2.5.217.1.1.16 QuerySettings

**Type:** Microsoft.SharePoint.ApplicationPages.ClientPickerQuery.PeoplePickerQuerySettings

**Accessibility:** Read/Write

Specifies the settings to be used in the **principal** query.

### 3.2.5.217.1.2 ObjectPath Properties

#### 3.2.5.217.1.2.1 Web

**Type:** Microsoft.SharePoint.Client.Web

**Accessibility:** Read/Write

Specifies the **site (2)** to be used in the **principal** query.

### 3.2.5.218 Microsoft.SharePoint.Client.DateTimeFieldFriendlyFormatType

**ShortName:** SP.DateTimeFieldFriendlyFormatType

**Flag:** false

Specifies a friendly format to use in displaying date and time **fields (2)**.<221>

#### 3.2.5.218.1 Field Values

##### 3.2.5.218.1.1 Unspecified

**Value:** 0

Undefined. The default rendering will be used.

##### 3.2.5.218.1.2 Disabled

**Value:** 1

The standard absolute representation will be used (for example, "2011-01-15 3:00 PM").

##### 3.2.5.218.1.3 Relative

**Value:** 2

The standard friendly relative representation will be used (for example, "today at 3:00 PM").

### 3.2.5.219 Microsoft.SharePoint.Client.RegionalSettings

**TypeId:** {84C424A9-A1D6-46BA-8398-C46257ECD25B}

**ShortName:** SP.RegionalSettings

Specifies the locale settings of a **site (2)**.<222>

#### 3.2.5.219.1 Properties

##### 3.2.5.219.1.1 Scalar Properties

### 3.2.5.219.1.1.1 AdjustHijriDays

Type: CSOM Int16

Accessibility: Read/Write

Specifies the number of days to extend or reduce the current month in Hijri calendars on the **site (2)**.

### 3.2.5.219.1.1.2 AlternateCalendarType

Type: CSOM Int16

Accessibility: Read/Write

Gets an alternate calendar type that is used on the **site (2)**.

The possible values are described in the table below.

Value	Description
0	No alternate calendar
1	Gregorian
3	Japanese Emperor Era
5	Korean Tangun Era
6	Hijri
7	Buddhist
8	Hebrew Lunar
9	Gregorian Middle East French Calendar
10	Gregorian Arabic Calendar
11	Gregorian Transliterated English Calendar
12	Gregorian Transliterated French Calendar
16	Saka Era
Other	Gregorian

### 3.2.5.219.1.1.3 AM

Type: CSOM String

Accessibility: Read Only

Specifies the string that is used to represent time before midday on the **site (2)**.

### 3.2.5.219.1.1.4 CalendarType

Type: CSOM Int16

Accessibility: Read/Write

Specifies the calendar type that SHOULD be used when processing date values on the **site (2)**. This value MUST be a **CalendarType** as specified in [\[MS-WSSFO2\]](#) section 2.2.3.3 or [\[MS-WSSFO3\]](#) section 2.2.1.2.3.

### 3.2.5.219.1.1.5 Collation

**Type:** CSOM Int16

**Accessibility:** Read/Write

Specifies the **collation** order of the **site (2)**, which indicates an additional sorting order that SHOULD be processed by any **back-end database server** associated with the site (2). The collation method is an implementation-specific capability of the front-end Web server and back-end database server.

### 3.2.5.219.1.1.6 CollationLCID

**Type:** CSOM UInt32

**Accessibility:** Read Only

Gets the **language code identifier (LCID)** for the **collation** rules that are used on the **site (2)**.

### 3.2.5.219.1.1.7 DateFormat

**Type:** CSOM UInt32

**Accessibility:** Read Only

Specifies the date format that is used on the server.

The possible values are specified in the following table.

Value	Description
0	Month-Day-Year.
1	Day-Month-Year.
2	Year-Month-Day.

### 3.2.5.219.1.1.8 DateSeparator

**Type:** CSOM String

**Accessibility:** Read Only

Gets the separator that is used for dates on the server.

### 3.2.5.219.1.1.9 DecimalSeparator

**Type:** CSOM String

**Accessibility:** Read Only

Gets the separator that is used for decimals on the server.

### 3.2.5.219.1.1.10 DigitGrouping



**Type:** CSOM String

**Accessibility:** Read Only

Gets the separator that is used in grouping digits.

### 3.2.5.219.1.1.11 FirstDayOfWeek

**Type:** CSOM UInt32

**Accessibility:** Read/Write

Specifies the first day of the week used in calendars on the server.

The possible values are specified in the following table.

Value	Description
0	Sunday
1	Monday
2	Tuesday
3	Wednesday
4	Thursday
5	Friday
6	Saturday

### 3.2.5.219.1.1.12 FirstWeekOfYear

**Type:** CSOM Int16

**Accessibility:** Read/Write

Specifies the first week of the year used in calendars on the server.

Specifies which week of a year is considered the first week.

The possible values are specified in the following table.

Value	Description
0	The first week is the week that January 1 falls in.
1	The first week is the first week that has four or more days in the new year.
2	The first week is the first full week of the year.

### 3.2.5.219.1.1.13 IsEastAsia

**Type:** CSOM Boolean

**Accessibility:** Read Only

Returns "true" if the web locale is an East Asia locale; "false" otherwise.

### 3.2.5.219.1.1.14 IsRightToLeft

**Type:** CSOM Boolean

**Accessibility:** Read Only

Specifies whether the **site (2)** uses a right-to-left language. If it uses a right-to-left language, this value MUST be "true". Otherwise, this value MUST be "false".

### 3.2.5.219.1.1.15 IsUIRightToLeft

**Type:** CSOM Boolean

**Accessibility:** Read Only

Specifies whether the UI of the **site (2)** uses a right-to-left language. If it uses a right-to-left language, this value MUST be "true". Otherwise, this value MUST be "false".

### 3.2.5.219.1.1.16 LocaleId

**Type:** CSOM UInt32

**Accessibility:** Read/Write

Specifies the **language code identifier (LCID)** in use on the server.

### 3.2.5.219.1.1.17 NegativeSign

**Type:** CSOM String

**Accessibility:** Read Only

Specifies the symbol that is used to represent a negative sign on the **site (2)**.

### 3.2.5.219.1.1.18 NegNumberMode

**Type:** CSOM UInt32

**Accessibility:** Read Only

Specifies the negative number mode that is used for displaying negative numbers in calculated fields based on the locale of the server.

The possible values are specified in the following table.

Value	Description	Example
0	Parentheses contain the number.	(1.1)
1	Placed before the number.	-1.1
2	Placed before the number with an extra space.	- 1.1
3	Placed after the number.	1.1-
4	Placed after the number with extra space.	1.1 -

### 3.2.5.219.1.1.19 PM

Type: CSOM String

Accessibility: Read Only

Specifies the string that is used to represent time after noon on the **site (2)**.

### 3.2.5.219.1.1.20 PositiveSign

Type: CSOM String

Accessibility: Read Only

Specifies the symbol that is used to represent a positive number on the **site (2)**.

### 3.2.5.219.1.1.21 ShowWeeks

Type: CSOM Boolean

Accessibility: Read/Write

Specifies whether to display the week number in day or week views of a calendar.

### 3.2.5.219.1.1.22 ThousandSeparator

Type: CSOM String

Accessibility: Read Only

Specifies the symbol that is used to separate thousands for numbers on the **site (2)**. For example, if the symbol is "," the number 123456789 would appear as "123,456,789".

### 3.2.5.219.1.1.23 Time24

Type: CSOM Boolean

Accessibility: Read/Write

Specifies whether the **site (2)** uses a 24-hour time format in representing the hours of the day. If it does, this value MUST be "true"; otherwise, this value MUST be "false".

### 3.2.5.219.1.1.24 TimeMarkerPosition

Type: CSOM UInt32

Accessibility: Read Only

Specifies an unsigned 32-bit integer that indicates the position of A.M. and P.M. in relation to the time string.

The possible values are specified in the following table.

Value	Description	Example
0	A.M. or P.M. appears after the time string.	12:27 AM
1	A.M. or P.M. appears before the time string.	PM 12:27

### 3.2.5.219.1.1.25 TimeSeparator

Type: **CSOM String**

Accessibility: Read Only

Gets the time separator symbol that is used on the server. For example, if the separator is ":", the time will appear as "12:08 AM".

### 3.2.5.219.1.1.26 WorkDayEndHour

Type: **CSOM Int16**

Accessibility: Read/Write

Specifies the default hour at which the work day ends on the calendar that is in use on the **site (2)**.

The possible values are specified in the following table.

Value	Description
0	12:00 AM
60	1:00 AM
120	2:00 AM
180	3:00 AM
240	4:00 AM
300	5:00 AM
360	6:00 AM
320	7:00 AM
480	8:00 AM
540	9:00 AM
600	10:00 AM
660	11:00 AM
720	12:00 PM
780	1:00 PM
840	2:00 PM
900	3:00 PM
960	4:00 PM
1020	5:00 PM
1080	6:00 PM
1140	7:00 PM

Value	Description
1200	8:00 PM
1260	9:00 PM
1320	10:00 PM
1380	11:00 PM

### 3.2.5.219.1.1.27 WorkDays

Type: **CSOM Int16**

Accessibility: Read/Write

Specifies a number that represents the work days of **site (2)** calendars.

Specifies a value that represents the work days in the site (2). This value is converted to its binary value, and it is read from left to right starting on Sunday and ending on Saturday. The days that have 1 are the work days in the site (2).

The following table shows some example values.

Value	Description	Work Days
127	1111111	All
0	0000000	None
64	1000000	Sunday
32	0100000	Monday
16	0010000	Tuesday
8	0001000	Wednesday
4	0000100	Thursday
2	0000010	Friday
1	0000001	Saturday
62	0111110	Monday to Friday

### 3.2.5.219.1.1.28 WorkDayStartHour

Type: **CSOM Int16**

Accessibility: Read/Write

Specifies the default hour at which the work day starts on the calendar that is in use on the **site (2)**.

The possible values are specified in the following table.

Value	Description
0	12:00 AM
60	1:00 AM
120	2:00 AM
180	3:00 AM
240	4:00 AM
300	5:00 AM
360	6:00 AM
320	7:00 AM
480	8:00 AM
540	9:00 AM
600	10:00 AM
660	11:00 AM
720	12:00 PM
780	1:00 PM
840	2:00 PM
900	3:00 PM
960	4:00 PM
1020	5:00 PM
1080	6:00 PM
1140	7:00 PM
1200	8:00 PM
1260	9:00 PM
1320	10:00 PM
1380	11:00 PM

### 3.2.5.219.1.1.29 ListSeparator

Type: **CSOM String**

Accessibility: Read Only

Specifies the separator that is used for lists on the server. For example, if the separator is ",", items in a list will appear as "1,2,3,4".

### 3.2.5.219.1.2ObjectPath Properties

### 3.2.5.219.1.2.1 TimeZone

**Type:** Microsoft.SharePoint.Client.TimeZone

**Accessibility:** Read/Write

Specifies the **time zone** of the **site (2)**.

### 3.2.5.219.1.2.2 TimeZones

**Type:** Microsoft.SharePoint.Client.TimeZoneCollection

**Accessibility:** Read Only

Specifies the collection of **time zones** used on the **site (2)**.

## 3.2.5.219.2 Methods

### 3.2.5.219.2.1 Scalar Methods

#### 3.2.5.219.2.1.1 Update

**Return Type:** None

Saves updates that have been done to this object.

**Parameters:** None

### 3.2.5.219.2.2 ObjectPath Methods

None.

## 3.2.5.220 Microsoft.SharePoint.Client.TimeZone

**TypeId:** {5519D02C-CE37-4B91-B61D-A1CEFE0FC85E}

**ShortName:** SP.TimeZone

Specifies the **time zone** of a **site (2)**.<223>

### 3.2.5.220.1 Properties

#### 3.2.5.220.1.1 Scalar Properties

##### 3.2.5.220.1.1.1 Description

**Type:** **CSOM String**

**Accessibility:** Read Only

Specifies the display name of the **time zone**.

##### 3.2.5.220.1.1.2 Id

**Type:** **CSOM Int32**

**Accessibility:** Read Only

Specifies the identifier of the **time zone**.

### 3.2.5.220.1.1.3 Information

**Type:** Microsoft.SharePoint.Client.TimeZoneInformation

**Accessibility:** Read Only

Specifies additional information about the **time zone**.

### 3.2.5.220.1.2 ObjectPath Properties

None.

## 3.2.5.220.2 Methods

### 3.2.5.220.2.1 Scalar Methods

#### 3.2.5.220.2.1.1 LocalTimeToUTC

**Return Type:** CSOM DateTime

Converts the specified date and time from the time zone to **Coordinated Universal Time (UTC)**.

**Parameters:**

*date:* Specifies the value to convert.

Type: CSOM DateTime

#### 3.2.5.220.2.1.2 UTCToLocalTime

**Return Type:** CSOM DateTime

Converts the specified date and time from **Coordinated Universal Time (UTC)** to the **time zone**.

**Parameters:**

*date:* Specifies the value to convert

Type: CSOM DateTime

### 3.2.5.220.2.2 ObjectPath Methods

None.

## 3.2.5.221 Microsoft.SharePoint.Client.TimeZoneCollection

**TypeId:** {117CBF47-7E74-4165-B26B-C24180AB2095}

**ShortName:** SP.TimeZoneCollection

Represents a collection of SP.TimeZone objects.

### 3.2.5.221.1 Properties

#### 3.2.5.221.1.1 Scalar Properties

None.

#### 3.2.5.221.1.2 ObjectPath Properties



None.

### 3.2.5.221.2 Methods

#### 3.2.5.221.2.1 Scalar Methods

None.

#### 3.2.5.221.2.2 ObjectPath Methods

##### 3.2.5.221.2.2.1 GetById

**Return Type:** Microsoft.SharePoint.Client.TimeZone

Retrieves a time zone from the collection using the specified identifier.

**Parameters:**

*id*: The identifier associated with the time zone.

Type: **CSOM Int32**

### 3.2.5.222 Microsoft.SharePoint.Client.TimeZoneInformation

**TypeId:** {09E18222-7E4D-488B-811D-6EF43F31D17F}

**ShortName:** SP.TimeZoneInformation

Specifies metadata about a **time zone**.<224>

#### 3.2.5.222.1 Properties

##### 3.2.5.222.1.1 Scalar Properties

###### 3.2.5.222.1.1.1 Bias

Type: **CSOM Int32**

**Accessibility:** Read Only

Specifies the number of minutes that the **time zone** differs from **Coordinated Universal Time (UTC)**. A positive value indicates that the time zone is behind UTC.

###### 3.2.5.222.1.1.2 DaylightBias

Type: **CSOM Int32**

**Accessibility:** Read Only

Specifies the number of minutes added to the **Bias** (section [3.2.5.222.1.1.1](#)) during Daylight Savings Time.

###### 3.2.5.222.1.1.3 StandardBias

Type: **CSOM Int32**

**Accessibility:** Read Only

Specifies the number of minutes added to the **Bias** (section [3.2.5.222.1.1.1](#)) outside of Daylight Savings Time.

### 3.2.5.222.1.2 ObjectPath Properties

None.

### 3.2.5.223 Microsoft.SharePoint.ApplicationPages.ClientPickerQuery.ClientPeoplePickerWebServiceInterface

**TypeId:** {DE2DB963-8BAB-4FB4-8A58-611AEBC5254B}

**ShortName:** SP.UI.ApplicationPages.ClientPeoplePickerWebServiceInterface

Specifies an interface that can be used to query **principals**.

#### 3.2.5.223.1 Properties

##### 3.2.5.223.1.1 Scalar Properties

None.

##### 3.2.5.223.1.2 ObjectPath Properties

None.

#### 3.2.5.223.2 Methods

##### 3.2.5.223.2.1 Scalar Methods

###### 3.2.5.223.2.1.1 ClientPeoplePickerResolveUser

This method is a **static CSOM method**.

**Return Type:** **CSOM String**

Resolves the **principals** to a string of JSON representing users in people picker format.

**Parameters:**

*queryParams:* Specifies the properties of a principal query.

Type: Microsoft.SharePoint.ApplicationPages.ClientPickerQuery.ClientPeoplePickerQueryParameters

###### 3.2.5.223.2.1.2 ClientPeoplePickerSearchUser

This method is a **static CSOM method**.

**Return Type:** **CSOM String**

Returns for a string of JSON representing users in people picker format of the specified **principals**.

**Parameters:**

*queryParams:* Specifies the properties of a principal query.

Type: Microsoft.SharePoint.ApplicationPages.ClientPickerQuery.ClientPeoplePickerQueryParameters

### 3.2.5.223.2.2 ObjectPath Methods

#### 3.2.5.223.2.2.1 GetPickerEntityInformation

This method is a **static CSOM method**.

**Return Type:** Microsoft.SharePoint.ApplicationPages.ClientPickerQuery.PickerEntityInformation

Gets information of the specified **principal**.

**Parameters:**

*entityInformationRequest:* Specifies the principal for which information is being requested.

Type: Microsoft.SharePoint.ApplicationPages.ClientPickerQuery.PickerEntityInformationRequest

#### 3.2.5.224 Microsoft.SharePoint.ApplicationPages.PickerQuery.PeoplePickerWebServiceInterface

**TypeId:** {8A000BC7-5D42-4C47-AF0B-3DD25B28D26F}

**ShortName:** SP.UI.ApplicationPages.PeoplePickerWebServiceInterface

Specifies an interface that can be used to query **principals**.<225>

#### 3.2.5.224.1 Properties

##### 3.2.5.224.1.1 Scalar Properties

None.

##### 3.2.5.224.1.2 ObjectPath Properties

None.

#### 3.2.5.224.2 Methods

##### 3.2.5.224.2.1 Scalar Methods

#### 3.2.5.224.2.1.1 GetSearchResults

This method is a **static CSOM method**.

**Return Type:** CSOM String

Specifies a **JSON** formatted CSOM String of **principals** found in the search.

**Parameters:**

*searchPattern:* Specifies a pattern used to search for principals. The value is implementation-specific.

Type: CSOM String

*providerID:* The identifier of a **claims provider**.

Type: CSOM String

*hierarchyNodeID:* The identifier of a node in the hierarchy. The search **MUST** be conducted under this node.

Type: CSOM String

*entityTypes*: The type of principals to search for.

Type: CSOM String

This value MUST be a comma-separated list of principals.

### **3.2.5.224.2.1.2 GetSearchResultsByHierarchy**

This method is a **static CSOM method**.

**Return Type: CSOM String**

Specifies a **JSON** formatted CSOM String of **principals** found in the search grouped by hierarchy.

**Parameters:**

*providerID*: The identifier of a **claims provider**.

Type: CSOM String

*hierarchyNodeID*: The identifier of a node in the hierarchy. The search MUST be conducted under this node.

Type: CSOM String

*entityTypes*: The type of principals to search for.

Type: CSOM String

This value MUST be a comma-separated list of principals.

*contextUrl*: The URL to use as context when searching for principals.

Type: CSOM String

### **3.2.5.224.2.2 ObjectPath Methods**

None.

### **3.2.5.225 Microsoft.SharePoint.Client.RelatedFieldExtendedData**

**TypeId**: {45FBCB1B-F734-4A96-86FE-836835C605F0}

**ShortName**: SP.RelatedFieldExtendedData

Specifies properties of a **relationship lookup field**.[<226>](#)

#### **3.2.5.225.1 Properties**

##### **3.2.5.225.1.1 Scalar Properties**

###### **3.2.5.225.1.1.1 FieldId**

**Type: CSOM GUID**

**Accessibility**: Read Only

Specifies the **field (2)** identifier of the **relationship lookup field**.

### 3.2.5.225.1.1.2 ListId

Type: **CSOM GUID**

Accessibility: Read Only

Specifies the **list** identifier of the **relationship lookup field**.

### 3.2.5.225.1.1.3 ListImageUrl

Type: **CSOM String**

Accessibility: Read Only

Specifies the **URL** for the icon of the target **list**.

It MUST NOT be NULL. Its length MUST be equal to or less than 255. It MUST be a **server-relative URL** or an **absolute URL**.

### 3.2.5.225.1.1.4 ResolvedListTitle

Type: **CSOM String**

Accessibility: Read Only

Specifies the resolved titles of the **relationship lookup field** and the target **list**.

### 3.2.5.225.1.1.5 ToolTipDescription

Type: **CSOM String**

Accessibility: Read Only

Specifies the description of the **relationship lookup field** and the target **list** to be displayed on the **ToolTip**.

### 3.2.5.225.1.1.6 WebId

Type: **CSOM GUID**

Accessibility: Read Only

Specifies the identifier of the **site (2)** containing the target **list** for the **relationship lookup field**.

## 3.2.5.225.1.2 ObjectPath Properties

None.

## 3.2.5.225.2 Methods

### 3.2.5.225.2.1 Scalar Methods

None.

### 3.2.5.225.2.2 ObjectPath Methods

None.

### 3.2.5.226 Microsoft.SharePoint.Client.RelatedFieldExtendedDataCollection

**TypeId:** {32ED187C-003C-413F-9799-1A2822ADE931}

**ShortName:** SP.RelatedFieldExtendedDataCollection

Specifies a collection of **objects (1)** that store properties of **relationship lookup fields**.<227>

#### 3.2.5.226.1 Properties

##### 3.2.5.226.1.1 Scalar Properties

None.

##### 3.2.5.226.1.2 ObjectPath Properties

None.

#### 3.2.5.226.2 Methods

##### 3.2.5.226.2.1 Scalar Methods

None.

##### 3.2.5.226.2.2 ObjectPath Methods

None.

### 3.2.5.227 Microsoft.SharePoint.Client.ObjectSharingInformation

**TypeId:** {E7DAE9F6-8CA5-4286-92C8-61941D774C44}

**ShortName:** SP.ObjectSharingInformation

Provides information about the sharing state of a **securable object**.<228>

#### 3.2.5.227.1 Properties

##### 3.2.5.227.1.1 Scalar Properties

###### 3.2.5.227.1.1.1 IsSharedWithCurrentUser

**Type:** CSOM Boolean

**Accessibility:** Read Only

Specifies whether the **securable object** is shared with the user making the current request.

###### 3.2.5.227.1.1.2 IsSharedWithGuest

**Type:** CSOM Boolean

**Accessibility:** Read Only

Specifies whether the **securable object** can be accessed by an anonymous user.

###### 3.2.5.227.1.1.3 IsSharedWithMany

**Type:** CSOM Boolean

**Accessibility:** Read Only

Specifies whether the **securable object** is shared with at least 30 users or with at least one **security group**.

#### **3.2.5.227.1.1.4 IsSharedWithSecurityGroup**

**Type:** CSOM Boolean

**Accessibility:** Read Only

Specifies whether the **securable object** is shared with at least one **security group**.

#### **3.2.5.227.1.1.5 AnonymousEditLink**

**Type:** CSOM String

**Accessibility:** Read Only

Provides the **URL** that allows an anonymous user to edit the **securable object**.

If such a URL is not available, this property will provide an empty string.

#### **3.2.5.227.1.1.6 AnonymousViewLink**

**Type:** CSOM String

**Accessibility:** Read Only

Provides the **URL** that allows an anonymous user to view the **securable object**.

If such a URL is not available, this property will provide an empty string.

#### **3.2.5.227.1.1.7 CanManagePermissions**

**Type:** CSOM Boolean

**Accessibility:** Read Only

Specifies whether the current user is allowed to change the **permissions** of the **securable object**.

#### **3.2.5.227.1.1.8 HasPendingAccessRequests**

**Type:** CSOM Boolean

**Accessibility:** Read Only

Provides information about whether there are any pending access requests for the **securable object**.

This information is only provided if the current user has sufficient **permissions** to view any pending access requests. If the current user does not have such permissions, this property will return false.

#### **3.2.5.227.1.1.9 PendingAccessRequestsLink**

**Type:** CSOM String

**Accessibility:** Read Only

Provides a **URL** to a location that describes any access requests present in the **site (2)**.

This information is only provided if the current user has sufficient **permissions** to view any pending access requests. If the current user does not have such permissions, this property will return an empty string.

#### **3.2.5.227.1.1.10 HasPermissionLevels**

**Type:** CSOM Boolean

**Accessibility:** Read Only

Indicates whether the object sharing information contains **permissions** information in addition to the identities of the users who have access to the **securable object**.

#### **3.2.5.227.1.1.11 CanBeShared**

**Type:** CSOM Boolean

**Accessibility:** Read Only

Indicates whether the current **securable object** can be shared.

#### **3.2.5.227.1.1.12 CanBeUnshared**

**Type:** CSOM Boolean

**Accessibility:** Read Only

Indicates whether the current **securable object** can be unshared.

#### **3.2.5.227.1.1.13 SharingLinks**

**Type:** CSOM array of Microsoft.SharePoint.Client.SharingLinkInfo

**Accessibility:** Read Only

Indicates the collection of all available sharing links for the **securable object**.

#### **3.2.5.227.1.1.14 IsFolder**

**Type:** CSOM Boolean

**Accessibility:** Read Only

Indicates whether the current selection is a folder.

#### **3.2.5.227.1.1.15 TotalFileCount**

**Type:** CSOM UInt64

**Accessibility:** Read Only

Indicates the number of files under the directory if the current selection is a directory (**IsFolder** is true).

### **3.2.5.227.1.2 ObjectPath Properties**

#### **3.2.5.227.1.2.1 SharedWithUsersCollection**

**Type:** Microsoft.SharePoint.Client.ObjectSharingInformationUserCollection



**Accessibility:** Read Only

A collection of shared with users.

### 3.2.5.227.2 Methods

#### 3.2.5.227.2.1 Scalar Methods

##### 3.2.5.227.2.1.1 CanCurrentUserShare

This method is a **static CSOM method**.

**Return Type:** Microsoft.SharePoint.Client.UserSharingCapabilities

Indicates whether the current user can share the document identified by docId.

**Parameters:**

*docId*: Identifies the document that will be analyzed from a sharing perspective.

Type: **CSOM String**

##### 3.2.5.227.2.1.2 CanCurrentUserShareRemote

This method is a **static CSOM method**.

**Return Type:** Microsoft.SharePoint.Client.UserSharingCapabilities

Indicates whether the current user can share the document identified by docId, from a remote context.

**Parameters:**

*docId*: Identifies the document that will be analyzed from a sharing perspective.

Type: **CSOM String**

#### 3.2.5.227.2.2 ObjectPath Methods

##### 3.2.5.227.2.2.1 GetObjectSharingInformation

This method is a **static CSOM method**.

**Return Type:** Microsoft.SharePoint.Client.ObjectSharingInformation

Retrieves information about the sharing state for a given **securable object**.

**Parameters:**

*securableObject*: Specifies the securable object for which to obtain sharing information.

Type: Microsoft.SharePoint.Client.SecurableObject

*excludeCurrentUser*: Specifies whether the returned sharing state information will exclude information about the user making the request.

Type: **CSOM Boolean**

*excludeSiteAdmin*: Specifies whether the returned sharing state information will exclude information about users who are **site collection administrators** of the **site collection** which contains the securable object.

Type: CSOM Boolean

*excludeSecurityGroups*: Specifies whether the returned sharing state information will exclude information about **security groups** which have **permissions** to the securable object.

Type: CSOM Boolean

*retrieveAnonymousLinks*: Specifies whether the returned sharing state information will contain information about a URL that allows an anonymous user to access the securable object.

Type: CSOM Boolean

*retrieveUserInfoDetails*: Specifies whether the returned sharing state information will contain basic or detailed information about the users with permissions to the securable object.

Type: CSOM Boolean

This parameter is ignored if detailed information is not available.

*checkForAccessRequests*: Specifies whether the returned sharing state information will contain a URL to a location which describes any access requests present in the **site (2)**, if such a URL is available.

Type: CSOM Boolean

*retrievePermissionLevels*: Specifies whether the returned sharing state information will contain permission information for each returned user.

Type: CSOM Boolean

This parameter is ignored if permission information is not available.

### **3.2.5.227.2.2.2      GetListItemSharingInformation**

This method is a **static CSOM method**.

**Return Type:** Microsoft.SharePoint.Client.ObjectSharingInformation

Retrieves information about the sharing state for a given **list**.

#### **Parameters:**

*listID*: The **list identifier** for the list which contains the **list item** for which the sharing state is requested.

Type: **CSOM GUID**

*itemID*: The **list item identifier** for the list item for which the sharing state is requested.

Type: **CSOM Int32**

*excludeCurrentUser*: Specifies whether the returned sharing state information will exclude information about the user making the request.

Type: **CSOM Boolean**

*excludeSiteAdmin*: Specifies whether the returned sharing state information will exclude information about users who are **site collection administrators** of the **site collection** which contains the list.

Type: CSOM Boolean

*excludeSecurityGroups*: Specifies whether the returned sharing state information will exclude information about **security groups** which have **permissions** to the list item.

Type: CSOM Boolean

*retrieveAnonymousLinks*: Specifies whether the returned sharing state information will contain information about a URL that allows an anonymous user to access the list item.

Type: CSOM Boolean

*retrieveUserInfoDetails*: Specifies whether the returned sharing state information will contain basic or detailed information about the users with permissions to the list item.

Type: CSOM Boolean

*checkForAccessRequests*: Specifies whether the returned sharing state information will contain a URL to a location which describes any access requests present in the **site (2)**, if such a URL is available.

Type: CSOM Boolean

### **3.2.5.227.2.2.3      GetSharedWithUsers**

**Return Type:** **CSOM array** of Microsoft.SharePoint.Client.ObjectSharingInformationUser

Returns an array that contains the users with whom a **securable object** is shared.

**Parameters:** None

### **3.2.5.227.2.2.4      GetWebSharingInformation**

This method is a **static CSOM method**.

**Return Type:** Microsoft.SharePoint.Client.ObjectSharingInformation

Retrieves information about the sharing state for the current **site (2)**. The current site (2) is the site (2) in the context of which this method is invoked.

**Parameters:**

*excludeCurrentUser*: Specifies whether the returned sharing state information will exclude information about the user making the request.

Type: **CSOM Boolean**

*excludeSiteAdmin*: Specifies whether the returned sharing state information will exclude information about users who are **site collection administrators** of the **site collection** which contains the current site (2).

Type: CSOM Boolean

*excludeSecurityGroups*: Specifies whether the returned sharing state information will exclude information about **security groups** which have **permissions** to the current site (2).

Type: CSOM Boolean

*retrieveAnonymousLinks*: This parameter is ignored by the method.

Type: CSOM Boolean

*retrieveUserInfoDetails*: Specifies whether the returned sharing state information will contain basic or detailed information about the users with permissions to the current site (2).

Type: CSOM Boolean

*checkForAccessRequests*: Specifies whether the returned sharing state information will contain a URL to a location which describes any access requests present in the current site (2), if such a URL is available.

Type: CSOM Boolean

### 3.2.5.227.2.2.5      **GetObjectSharingInformation2**

This method is a **static CSOM method**.

**Return Type:** Microsoft.SharePoint.Client.ObjectSharingInformation

Retrieves information about the sharing state for a given **securable object**.

#### **Parameters:**

*securableObject*: Specifies the securable object for which to obtain sharing information.

Type: Microsoft.SharePoint.Client.SecurableObject

*excludeCurrentUser*: Specifies whether the returned sharing state information will exclude information about the user making the request.

Type: **CSOM Boolean**

*excludeSiteAdmin*: Specifies whether the returned sharing state information will exclude information about users who are **site collection administrators** of the **site collection** which contains the securable object.

Type: CSOM Boolean

*excludeSecurityGroups*: Specifies whether the returned sharing state information will exclude information about **security groups** which have **permissions** to the securable object.

Type: CSOM Boolean

*retrieveAnonymousLinks*: Specifies whether the returned sharing state information will contain information about a URL that allows an anonymous user to access the securable object.

Type: CSOM Boolean

*retrieveUserInfoDetails*: Specifies whether the returned sharing state information will contain basic or detailed information about the users with permissions to the securable object.

Type: CSOM Boolean

*checkForAccessRequests*: Specifies whether the returned sharing state information will contain a URL to a location which describes any access requests present in the **site (2)**, if such a URL is available.

Type: CSOM Boolean

*retrievePermissionLevels*: Specifies whether the returned sharing state information will contain permission information for each returned user.

Type: CSOM Boolean

*forceRetrievePermissionLevels*: Specifies whether to retrieve sharing information with permission levels.

Type: CSOM Boolean

### **3.2.5.227.2.2.6      GetObjectSharingInformationByUrl**

This method is a **static CSOM method**.

**Return Type:** Microsoft.SharePoint.Client.ObjectSharingInformation

Retrieves information about the sharing state for a given object URL.

#### **Parameters:**

*objectUrl*: Specifies the URL of the securable object for which to obtain sharing information.

Type: **CSOM String**

*excludeCurrentUser*: Specifies whether the returned sharing state information will exclude information about the user making the request.

Type: **CSOM Boolean**

*excludeSiteAdmin*: Specifies whether the returned sharing state information will exclude information about users who are **site collection administrators** of the **site collection** which contains the **securable object**.

Type: CSOM Boolean

*excludeSecurityGroups*: Specifies whether the returned sharing state information will exclude information about **security groups** which have **permissions** to the securable object.

Type: CSOM Boolean

*retrieveAnonymousLinks*: Specifies whether the returned sharing state information will contain information about a URL that allows an anonymous user to access the securable object.

Type: CSOM Boolean

*retrieveUserInfoDetails*: Specifies whether the returned sharing state information will contain basic or detailed information about the users with permissions to the securable object.

Type: CSOM Boolean

*checkForAccessRequests*: Specifies whether the returned sharing state information will contain a URL to a location which describes any access requests present in the **site (2)**, if such a URL is available.

Type: CSOM Boolean

*retrievePermissionLevels*: Specifies whether the returned sharing state information will contain permission information for each returned user.

Type: CSOM Boolean

### **3.2.5.228      Microsoft.SharePoint.Client.PushNotificationSubscriber**

**TypeId:** {1489ADD2-5D3A-4DE8-9445-49259462DCEB}

**ShortName:** SP.PushNotificationSubscriber

Specifies a push notification subscriber. <229>

### 3.2.5.228.1 Properties

#### 3.2.5.228.1.1 Scalar Properties

##### 3.2.5.228.1.1.1 CustomArgs

Type: **CSOM String**

Accessibility: Read/Write

Specifies a custom arguments string that represents the state of the notifications subscription. This string can be used by the application logic to differentiate between its notification subscribers for different kinds of notifications.

##### 3.2.5.228.1.1.2 DeviceAppInstanceId

Type: **CSOM GUID**

Accessibility: Read Only

Specifies a device **app instance** identifier.

##### 3.2.5.228.1.1.3 LastModifiedTimeStamp

Type: **CSOM DateTime**

Accessibility: Read Only

Specifies the time and date when the subscriber was last updated.

##### 3.2.5.228.1.1.4 RegistrationTimeStamp

Type: **CSOM DateTime**

Accessibility: Read Only

Specifies the time and date when the subscriber registered for push notifications.

##### 3.2.5.228.1.1.5 ServiceToken

Type: **CSOM String**

Accessibility: Read/Write

Specifies the delivery channel **URI** for push notifications.

It MUST NOT be NULL. It MUST NOT be empty.

##### 3.2.5.228.1.1.6 SubscriberType

Type: **CSOM String**

Accessibility: Read/Write

Specifies the type of the subscriber.

#### 3.2.5.228.1.2 ObjectPath Properties

### 3.2.5.228.1.2.1 User

**Type:** Microsoft.SharePoint.Client.User

**Accessibility:** Read Only

Specifies the user for the push notification subscriber.

### 3.2.5.228.2 Methods

#### 3.2.5.228.2.1 Scalar Methods

##### 3.2.5.228.2.1.1 Update

**Return Type:** None

Updates the push notification subscriber in the store with the changes made to the instance.

**Parameters:** None

#### 3.2.5.228.2.2 ObjectPath Methods

None.

### 3.2.5.229 Microsoft.SharePoint.Client.PushNotificationSubscriberCollection

**TypeId:** {99676B16-B4C9-429A-B3D9-DE883C42C4D5}

**ShortName:** SP.PushNotificationSubscriberCollection

Specifies a collection of push notification subscribers. [<230>](#)

#### 3.2.5.229.1 Properties

##### 3.2.5.229.1.1 Scalar Properties

None.

##### 3.2.5.229.1.2 ObjectPath Properties

None.

#### 3.2.5.229.2 Methods

##### 3.2.5.229.2.1 Scalar Methods

None.

##### 3.2.5.229.2.2 ObjectPath Methods

###### 3.2.5.229.2.2.1 GetByStoreId

**Return Type:** Microsoft.SharePoint.Client.PushNotificationSubscriber

Returns the push notification subscriber from the specified store identifier.

**Parameters:**

*id*: Store identifier for the notification subscriber.

Type: **CSOM String**

### **3.2.5.230 Microsoft.BusinessData.Runtime.EntityEventType**

**ShortName:** SP.BusinessData.Runtime.EntityEventType

**Flag:** false

The enumeration of event types to be used in the **Subscriber** stereotype.

#### **3.2.5.230.1 Field Values**

##### **3.2.5.230.1.1 None**

**Value:** 0

This value denotes an invalid event type. This value **MUST NOT** be used in the **Subscriber** stereotype.

##### **3.2.5.230.1.2 ItemAdded**

**Value:** 1

An item has been added.

##### **3.2.5.230.1.3 ItemUpdated**

**Value:** 2

An item has been updated.

##### **3.2.5.230.1.4 ItemDeleted**

**Value:** 3

An item has been deleted.

### **3.2.5.231 Microsoft.BusinessData.Runtime.NotificationCallback**

**TypeId:** {87D0A4EE-8341-4848-8078-5135A1357A9D}

**ShortName:** SP.BusinessData.Runtime.NotificationCallback

Specifies the properties of the endpoint to which notifications from the external system is delivered.

#### **3.2.5.231.1 Properties**

##### **3.2.5.231.1.1 Scalar Properties**

###### **3.2.5.231.1.1.1 NotificationContext**

Type: **CSOM String**

**Accessibility:** Read/Write

The custom information that will be sent to the notification endpoint when notification arrives.



### 3.2.5.231.1.1.2 NotificationEndpoint

Type: **CSOM String**

Accessibility: Read Only

The **URI** of the endpoint at which notifications will be received.

### 3.2.5.231.1.1.3 NotificationForwarderType

Type: **CSOM String**

Accessibility: Read/Write

The type of the intermediate forwarder site on the protocol server that forwards the notifications to the **notification endpoint**.

If no value is set, by default, the value is set to "CurrentContext". The allowed valid values for this parameter are "CurrentContext", "DeliveryAddressRelative" and "GlobalStore".

- If value "CurrentContext" is provided, then the site in the current context of the CSOM request will be used as the intermediate forwarder site.
- If value "GlobalStore" is provided, then the site information saved at the administration catalog will be used as the intermediate forwarder site. The property with name "EntityNotificationWeb" contains a value with site information in the format "<site\_collection\_id>,<site\_id>".
- If the value "DeliveryAddressRelative" is provided, then the site information found in the notification endpoint will be used as the intermediate forwarder site.

### 3.2.5.231.1.2 ObjectPath Properties

None.

### 3.2.5.231.2 Methods

#### 3.2.5.231.2.1 Scalar Methods

None.

#### 3.2.5.231.2.2 ObjectPath Methods

##### 3.2.5.231.2.2.1 CSOM Constructor

Creates an instance of type **NotificationCallback** (section [3.2.5.231](#)).

**Parameters:**

*notificationEndpoint*: The **URI** of the endpoint at which notifications will be received.

Type: **CSOM String**

### 3.2.5.232 Microsoft.BusinessData.Runtime.Subscription

**TypeId**: {69AA7DD9-23A0-4E20-9464-0749FC0E6406}

**ShortName**: SP.BusinessData.Runtime.Subscription

The **subscription** registration information token returned in response to the Subscriber stereotype call. This object is used as an input in the EventUnsubscriber stereotype call.

### 3.2.5.232.1 Properties

#### 3.2.5.232.1.1 Scalar Properties

##### 3.2.5.232.1.1.1 Hash

Type: **CSOM String**

Accessibility: Read Only

The digest header set by **Business Connectivity Services (BCS)** to identify the **Subscription** during Unsubscribe.

##### 3.2.5.232.1.1.2 ID

Type: **CSOM dictionary**

Accessibility: Read Only

The map of **subscription** identifier names and their values returned by the external system during the Subscriber stereotype call.

#### 3.2.5.232.1.2 ObjectPath Properties

None.

### 3.2.5.232.2 Methods

#### 3.2.5.232.2.1 Scalar Methods

None.

#### 3.2.5.232.2.2 ObjectPath Methods

##### 3.2.5.232.2.2.1 CSOM Constructor

Creates an instance of type Subscription (section [3.2.5.232](#)).

**Parameters:**

*id*: The map of subscription identifier names and their values returned by the external system during the Subscriber stereotype call.

Type: **CSOM dictionary**

*hash*: The digest header set by **Business Connectivity Services (BCS)** to identify the **Subscription** during Unsubscribe.

Type: **CSOM String**

### 3.2.5.233 Microsoft.SharePoint.Administration.SPAnalyticsUsageService

**TypeId**: {D75AAFC0-CBE3-4930-9637-BB32DD276C8F}

**ShortName**: Microsoft.SharePoint.Administration.SPAnalyticsUsageService

Represents the entry point for the Event REST service exposed through CSOM. <231>

### 3.2.5.233.1 Properties

#### 3.2.5.233.1.1 Scalar Properties

None.

#### 3.2.5.233.1.2 ObjectPath Properties

None.

### 3.2.5.233.2 Methods

#### 3.2.5.233.2.1 Scalar Methods

##### 3.2.5.233.2.1.1 logevent

**Return Type:** None

Used to log events.

**Parameters:**

*usageEntry*: the **UsageEntry** (section [3.2.5.234](#)) object representing the event.

Type: Microsoft.SharePoint.Administration.UsageEntry

The **UsageEntry** object is validated. **usageEntry.ItemId** (section [3.2.5.234.1.1.2](#)) is a required property. **usageEntry.EventTypeId** (section [3.2.5.234.1.1.1](#)) is required and MUST be a valid event type. If **usageEntry.Site** (section [3.2.5.234.1.1.4](#)) equals **Guid.Empty**, the current site is used.

#### 3.2.5.233.2.2 ObjectPath Methods

##### 3.2.5.233.2.2.1 CSOM Constructor

Creates an instance of type **SPAnalyticsUsageService** (section [3.2.5.233](#))

**Parameters:** None

### 3.2.5.234 Microsoft.SharePoint.Administration.UsageEntry

**TypeId:** {6DFA6EB7-93AF-4625-95EA-508B84BE1751}

**ShortName:** Microsoft.SharePoint.Administration.UsageEntry

Represents an event, logged through the **logevent** method (section [3.2.5.233.2.1.1](#)). <232>

### 3.2.5.234.1 Properties

#### 3.2.5.234.1.1 Scalar Properties

##### 3.2.5.234.1.1.1 EventTypeId

**Type:** CSOM Int32

**Accessibility:** Read/Write

MUST be one of the values described in section [3.2.5.168](#).

### **3.2.5.234.1.1.2 ItemId**

**Type:** CSOM String

**Accessibility:** Read/Write

The identifier of the item to which the event applies.

### **3.2.5.234.1.1.3 ScopeId**

**Type:** CSOM GUID

**Accessibility:** Read/Write

A scope identifier to which the event applies.

### **3.2.5.234.1.1.4 Site**

**Type:** CSOM GUID

**Accessibility:** Read/Write

The identifier of the site to which the event applies.

### **3.2.5.234.1.1.5 User**

**Type:** CSOM String

**Accessibility:** Read/Write

The identifier of the user which the event relates to.

### **3.2.5.234.1.2ObjectPath Properties**

None.

## **3.2.5.235 Microsoft.BusinessData.Infrastructure.EntityInstanceIdEncoder**

**TypeId:** {7B23E667-073D-42E2-B519-2FF52345735A}

**ShortName:** Microsoft.SharePoint.BusinessData.Infrastructure.EntityInstanceIdEncoder

Encodes and decodes **EntityInstance** identifiers.

### **3.2.5.235.1 Properties**

#### **3.2.5.235.1.1Scalar Properties**

None.

#### **3.2.5.235.1.2ObjectPath Properties**

None.

### **3.2.5.235.2 Methods**

### 3.2.5.235.2.1 Scalar Methods

#### 3.2.5.235.2.1.1 EncodeEntityInstanceId

This method is a **static CSOM method**.

**Return Type:** **CSOM String**

Encodes the external item sub-identifiers and returns the encoded external item identifier.

**Parameters:**

*subIdentifiers*: An array of external item sub-identifiers.

Type: **CSOM array** of **CSOM Object**

This method is not available in ECMAScript ([\[ECMA-262-1999\]](#)).

**Exceptions:**

Error Code	Error Type Name	Condition
-2147467261	System.ArgumentNullException	At least one of the parameters is null.
-2146233086	System.ArgumentOutOfRangeException	Need less than 26 subIdentifiers.

### 3.2.5.235.2.2 ObjectPath Methods

None.

#### 3.2.5.236 Microsoft.BusinessData.Infrastructure.ExternalSubscriptionStore

**TypeId:** {B5D4DFA9-E948-4068-A32B-012EEA5A1A61}

**ShortName:** SP.BusinessData.Infrastructure.ExternalSubscriptionStore

Defines a SharePoint list which contains a collection of **subscriptions**. This collection is referred to in this section as the "external subscription store".

#### 3.2.5.236.1 Properties

##### 3.2.5.236.1.1 Scalar Properties

None.

##### 3.2.5.236.1.2 ObjectPath Properties

None.

#### 3.2.5.236.2 Methods

##### 3.2.5.236.2.1 Scalar Methods

##### 3.2.5.236.2.1.1 IndexStore

**Return Type:** None

Indexes the external subscription store.

**Parameters:** None

**Exceptions:**

Error Code	Error Type Name	Condition
-1	Microsoft.BusinessData.Infrastructure.BdcException	External Subscription Feature is not enabled or external subscriptions list is not found.
-2147024891	System.UnauthorizedAccessException	User does not have permissions to index the external subscription store.

### 3.2.5.236.2.2 ObjectPath Methods

#### 3.2.5.236.2.2.1 CSOM Constructor

Creates an instance of type **ExternalSubscriptionStore** (section [3.2.5.236](#)).

**Parameters:**

*web*: The **site (2)** containing the external subscription store.

Type: Microsoft.SharePoint.Client.Web

It MUST NOT be NULL.

#### 3.2.5.237 Microsoft.SharePoint.Client.App

**TypeId**: {7B3E0C67-45C1-423C-AF60-240BD774ADC0}

**ShortName**: SP.App

Specifies an **app package**.

#### 3.2.5.237.1 Properties

##### 3.2.5.237.1.1 Scalar Properties

###### 3.2.5.237.1.1.1 AssetId

Type: **CSOM String**

**Accessibility**: Read Only

If the **app package** is from the marketplace, the value MUST be a unique identifier for the app package in the marketplace. Otherwise it MUST be NULL.

###### 3.2.5.237.1.1.2 ContentMarket

Type: **CSOM String**

**Accessibility**: Read Only

If the **app package** is from the marketplace, the value MUST be the **marketplace content market** of the **SharePoint Add-in**. Otherwise it MUST be NULL.

### **3.2.5.237.1.1.3 VersionString**

**Type:** CSOM String

**Accessibility:** Read Only

Specifies the version of the **app package**.

It MUST NOT be NULL. It MUST NOT be empty string.

### **3.2.5.237.1.2ObjectPath Properties**

None.

### **3.2.5.237.2 Methods**

#### **3.2.5.237.2.1Scalar Methods**

None.

#### **3.2.5.237.2.2ObjectPath Methods**

None.

### **3.2.5.238 Microsoft.SharePoint.Client.AppInstanceStatus**

**ShortName:** SP.AppInstanceStatus

**Flag:** false

Specifies the lifecycle status of this **app instance**.

#### **3.2.5.238.1 Field Values**

##### **3.2.5.238.1.1InvalidStatus**

**Value:** 0

This value indicates an internal product error. An app instance SHOULD NOT have this value.

##### **3.2.5.238.1.2Installing**

**Value:** 1

This value indicates that the **app instance** is in the process of installing.

##### **3.2.5.238.1.3Canceling**

**Value:** 7

This value indicates that the **app instance** was installing, but was cancelled, and is now uninstalling.

##### **3.2.5.238.1.4Uninstalling**

**Value:** 4

This value indicates that the **app instance** is uninstalling.

### **3.2.5.238.1.5 Installed**

**Value:** 5

This value indicates that the **app instance** is installed.

### **3.2.5.238.1.6 Upgrading**

**Value:** 8

This value indicates that the **app instance** is upgrading.

### **3.2.5.238.1.7 Initialized**

**Value:** 9

This value indicates that the **app instance** has been created, but not yet installed.

### **3.2.5.238.1.8 UpgradeCanceling**

**Value:** 10

This value indicates that the **app instance** was upgrading, but has cancelled.

### **3.2.5.238.1.9 Disabling**

**Value:** 11

This value indicates that the **app instance** is disabling.

### **3.2.5.238.1.10 Disabled**

**Value:** 12

This value indicates that the **app instance** is disabled.

### **3.2.5.238.1.11 SecretRolling**

**Value:** 13

This value indicates that the **app instance** is rolling the secret associated with its **app principal**.

### **3.2.5.238.1.12 Recycling**

**Value:** 14

This value indicates that the **App instance** is moving to the **recycle** bin.

### **3.2.5.238.1.13 Recycled**

**Value:** 15

This value indicates that the **App instance** is in the **recycle** bin.

### **3.2.5.238.1.14 Restoring**

**Value:** 16



This value indicates that the **App instance** is moving from the **recycled** bin back to Installed.

### **3.2.5.238.1.15 RestoreCanceling**

**Value:** 17

This value indicates that the **App instance** was restoring from the **recycle** bin, but has cancelled.

### **3.2.5.239 Microsoft.SharePoint.Client.AppLicense**

**TypeId:** {D3425BF9-FE82-4957-AFDA-5FBD21DABB85}

**ShortName:** SP.AppLicense

Specifies a **marketplace license**.[<233>](#)

#### **3.2.5.239.1 Properties**

##### **3.2.5.239.1.1 Scalar Properties**

###### **3.2.5.239.1.1.1 RawXMLLicenseToken**

**Type:** **CSOM String**

**Accessibility:** Read Only

The implementation-specific **XML** that specifies the **marketplace license token**.

##### **3.2.5.239.1.2 ObjectPath Properties**

None.

### **3.2.5.240 Microsoft.SharePoint.Client.AppLicenseCollection**

**TypeId:** {47BEB529-4C4B-41BA-B717-28D18FBDF258}

**ShortName:** SP.AppLicenseCollection

Specifies a collection of **marketplace licenses**.[<234>](#)

#### **3.2.5.240.1 Properties**

##### **3.2.5.240.1.1 Scalar Properties**

None.

##### **3.2.5.240.1.2 ObjectPath Properties**

None.

### **3.2.5.241 Microsoft.SharePoint.Client.AppLicenseType**

**ShortName:** SP.AppLicenseType

**Flag:** false

Enumeration of the possible types of **marketplace licenses** that can enable trial periods for or perpetual usage of a **SharePoint Add-in**, and can also limit the number of people who are able to use the SharePoint Add-in.

### 3.2.5.241.1 Field Values

#### 3.2.5.241.1.1 PerpetualMultiUser

**Value:** 0

Specifies a non-trial **marketplace license** with a limit on the number of people who can use the **SharePoint Add-in**.

#### 3.2.5.241.1.2 PerpetualAllUsers

**Value:** 1

Specifies a non-trial **marketplace license** without a limit on the number of people who can use the **SharePoint Add-in**.

#### 3.2.5.241.1.3 TrialMultiUser

**Value:** 2

Specifies a trial **marketplace license** with a limit on the number of people who can use the **SharePoint Add-in**.

#### 3.2.5.241.1.4 TrialAllUsers

**Value:** 3

Specifies a trial **marketplace license** without a limit on the number of people who can use the **SharePoint Add-in**.

### 3.2.5.242 Microsoft.SharePoint.Client.Language

**TypeId:** {EAE9F1B5-1AE9-417B-9A8B-04A1B4C05A4B}

**ShortName:** SP.Language

Represents a natural language.

#### 3.2.5.242.1 Properties

##### 3.2.5.242.1.1 Scalar Properties

###### 3.2.5.242.1.1.1 DisplayName

**Type:** **CSOM String**

**Accessibility:** Read Only

Specifies the name of the language as displayed in the user interface.

###### 3.2.5.242.1.1.2 LanguageTag

**Type:** **CSOM String**

**Accessibility:** Read Only

Specifies the corresponding **culture name** for the language.

### **3.2.5.242.1.1.3 Lcid**

**Type:** **CSOM Int32**

**Accessibility:** Read Only

Specifies the **language code identifier (LCID)** for the language.

### **3.2.5.242.1.2 ObjectPath Properties**

None.

### **3.2.5.243 Microsoft.SharePoint.Client.ListItemFormUpdateValue**

**TypeId:** {03745A5A-2400-440E-92D6-DAD4AFEE30A6}

**ShortName:** SP.ListItemFormUpdateValue

Specifies the properties of a **list item field (2)** and its value.

#### **3.2.5.243.1 Properties**

##### **3.2.5.243.1.1 Scalar Properties**

###### **3.2.5.243.1.1.1 ErrorMessage**

**Type:** **CSOM String**

**Accessibility:** Read/Write

Specifies the error message result after validating the value for the **field (2)**.

###### **3.2.5.243.1.1.2 FieldName**

**Type:** **CSOM String**

**Accessibility:** Read/Write

Specifies the **field internal name** for a **field (2)**.

###### **3.2.5.243.1.1.3 FieldValue**

**Type:** **CSOM String**

**Accessibility:** Read/Write

Specifies a value for a **field (2)**.

###### **3.2.5.243.1.1.4 HasException**

**Type:** **CSOM Boolean**

**Accessibility:** Read/Write

Specifies whether there was an error result after validating the value for the **field (2)**.

### 3.2.5.243.1.1.5 **ItemId**

**Type:** CSOM Int32

**Accessibility:** Read/Write

Specifies the identifier for the **field (2)**.

### 3.2.5.243.1.2 **ObjectPath Properties**

None.

## 3.2.5.244 **Microsoft.SharePoint.Client.MenuNode**

**TypeId:** {B85A901B-328E-4378-922F-4F9AE35B36E1}

**ShortName:** SP.MenuNode

Represents a navigation node in the navigation hierarchy. A navigation hierarchy is a tree structure of navigation nodes.

### 3.2.5.244.1 **Properties**

#### 3.2.5.244.1.1 **Scalar Properties**

##### 3.2.5.244.1.1.1 **CustomProperties**

**Type:** CSOM dictionary

**Accessibility:** Read/Write

Contains key value pairs, where both the key and value MUST be of type **CSOM String**.

The keys SHOULD be prefixed with "Nav\_", "\_Nav\_" or "\_Sys\_Facet\_".

##### 3.2.5.244.1.1.2 **FriendlyUrlSegment**

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies the **URL** of the navigation node relative to the URL of the parent navigation node.

##### 3.2.5.244.1.1.3 **IsDeleted**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

A client MUST use this property set to TRUE to indicate that this node MUST be deleted by the server. When set to TRUE the server MUST delete the node including all the child nodes when present. When set to FALSE the server SHOULD NOT delete this node.

##### 3.2.5.244.1.1.4 **IsHidden**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Specifies whether the node will be hidden in the navigation menu. During editing, all nodes temporarily become visible so that they can be edited.

#### **3.2.5.244.1.1.5 Key**

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies the identifier for the navigation node in the menu tree. If the navigation node does not exist on the protocol server, this value MUST be an empty string.

It MUST NOT be NULL.

#### **3.2.5.244.1.1.6 Nodes**

**Type:** CSOM array of Microsoft.SharePoint.Client.MenuNode

**Accessibility:** Read/Write

Specifies an array of child nodes.

#### **3.2.5.244.1.1.7 NodeType**

**Type:** Microsoft.SharePoint.Client.MenuNodeType

**Accessibility:** Read/Write

Specifies the type of the navigation node.

#### **3.2.5.244.1.1.8 SimpleUrl**

**Type:** CSOM String

**Accessibility:** Read/Write

If the **NodeType** (section [3.2.5.244.1.1.7](#)) property is set to "SimpleLink", this property represents the **URL** of the navigation node. The URL can be relative or absolute. If the value is a relative URL, it can begin with URL tokens "~site" and "~sitecollection". These tokens indicate that the URL is either relative to the **site (2)** or to the **site collection** respectively. If the **NodeType** (section [3.2.5.244.1.1.7](#)) property is not set to "SimpleLink", the value MUST be an empty string.

#### **3.2.5.244.1.1.9 Title**

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies the title of the navigation node. The value is in the preferred language of the user, if available, or is in the default language of the **site (2)** as a fallback.

#### **3.2.5.244.1.2 ObjectPath Properties**

None.

### **3.2.5.245 Microsoft.SharePoint.Client.MenuNodeType**

**ShortName:** SP.MenuNodeType

**Flag:** false

Represents the different types of menu nodes.

### 3.2.5.245.1 Field Values

#### 3.2.5.245.1.1 SimpleLink

**Value:** 0

Standard navigation menu node. If the URL is blank, then the node acts as a menu caption with no hyperlink.

#### 3.2.5.245.1.2 FriendlyUrl

**Value:** 1

Special **taxonomy navigation** menu node that defines a user friendly **URL**.

### 3.2.5.246 Microsoft.SharePoint.Client.MenuState

**TypeId:** {B85A901B-328E-4378-922F-4F9AE35B36E0}

**ShortName:** SP.MenuState

A menu tree which can be shown in the **Quick Launch** of a **site (2)**.

#### 3.2.5.246.1 Properties

##### 3.2.5.246.1.1 Scalar Properties

###### 3.2.5.246.1.1.1 FriendlyUrlPrefix

**Type:** **CSOM String**

**Accessibility:** Read/Write

Specifies the **site collection** relative **URL** for the root node of the menu tree.

###### 3.2.5.246.1.1.2 Nodes

**Type:** **CSOM array** of Microsoft.SharePoint.Client.MenuNode

**Accessibility:** Read/Write

The child nodes of the root node of the menu tree.

###### 3.2.5.246.1.1.3 SimpleUrl

**Type:** **CSOM String**

**Accessibility:** Read/Write

If the **NodeType** property (section [3.2.5.244.1.1.7](#)) of the menu tree root node is set to "SimpleLink", this property represents the **URL** of the root node. The URL can be relative or absolute. If the value is a relative URL, it can begin with URL tokens "~site" and "~sitecollection". These tokens indicate that the URL is either relative to the **site (2)** or to the **site collection** respectively. If the **NodeType** property (section [3.2.5.244.1.1.7](#)) of the menu tree root node is not set to "SimpleLink", this value MUST be NULL.

#### **3.2.5.246.1.1.4 SPSitePrefix**

**Type:** CSOM String

**Accessibility:** Read/Write

Defines the text that SHOULD be substituted for "~sitecollection/" in relative links (such as "~sitecollection/Pages/MyPage.aspx").

#### **3.2.5.246.1.1.5 SPWebPrefix**

**Type:** CSOM String

**Accessibility:** Read/Write

Defines the text that SHOULD be substituted for "~site/" in relative links (such as "~site/Pages/MyPage.aspx").

#### **3.2.5.246.1.1.6 StartingNodeKey**

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies the identifier for the root node in the menu tree.

#### **3.2.5.246.1.1.7 StartingNodeTitle**

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies the title of the root node in the menu tree.

#### **3.2.5.246.1.1.8 Version**

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies an implementation-specific value that the protocol server uses to detect external changes.

### **3.2.5.246.1.2 ObjectPath Properties**

None.

### **3.2.5.247 Microsoft.SharePoint.Client.ObjectSharingInformationUser**

**TypeId:** {F7B7FE66-58A7-4843-882D-99AF0D97992B}

**ShortName:** SP.ObjectSharingInformationUser

Contains information about a **principal** with whom a **securable object** is shared. It can be a user or a **group**.

#### **3.2.5.247.1 Properties**

##### **3.2.5.247.1.1 Scalar Properties**

### **3.2.5.247.1.1.1 Department**

**Type:** CSOM String

**Accessibility:** Read Only

Specifies the department for the user.

It MUST be NULL or empty if the **principal** is a **group**.

### **3.2.5.247.1.1.2 Email**

**Type:** CSOM String

**Accessibility:** Read Only

Specifies the email address for the user.

It MUST be NULL or empty if the **principal** is a **group**.

### **3.2.5.247.1.1.3 Id**

**Type:** CSOM Int32

**Accessibility:** Read Only

Specifies the identifier of the **principal**.

### **3.2.5.247.1.1.4 JobTitle**

**Type:** CSOM String

**Accessibility:** Read Only

Specifies the job title of the user.

It MUST be NULL or empty if the **principal** is a **group**.

### **3.2.5.247.1.1.5 Name**

**Type:** CSOM String

**Accessibility:** Read Only

Specifies the name of the **principal**.

It MUST NOT be NULL. It MUST NOT be empty.

### **3.2.5.247.1.1.6 Picture**

**Type:** CSOM String

**Accessibility:** Read Only

Specifies the picture **URL** of the user.

It MUST be NULL or empty if the **principal** is a **group**.

### **3.2.5.247.1.1.7 SipAddress**

**Type:** CSOM String



**Accessibility:** Read Only

Specifies the SIP address of the user.

It MUST be NULL or empty if the **principal** is a **group**.

### **3.2.5.247.1.1.8 CustomRoleNames**

**Type:** CSOM String

**Accessibility:** Read Only

Specifies the custom **role** names that the user has for a **document**.

It MUST be NULL or empty for a **securable object** that is not a document.

### **3.2.5.247.1.1.9 HasEditPermission**

**Type:** CSOM Boolean

**Accessibility:** Read Only

Indicates whether the **principal** has Edit permission for a **document**.

It MUST be false for a **securable object** that is not a document.

### **3.2.5.247.1.1.10 HasViewPermission**

**Type:** CSOM Boolean

**Accessibility:** Read Only

Indicates whether the **principal** has View permission for a **document**.

It MUST be false for a **securable object** that is not a document.

### **3.2.5.247.1.1.11 IsSiteAdmin**

**Type:** CSOM Boolean

**Accessibility:** Read Only

Indicates whether user is a **site collection** administrator.

It MUST be false if the **principal** is a **group**.

### **3.2.5.247.1.1.12 LoginName**

**Type:** CSOM String

**Accessibility:** Read Only

Specifies the login name for the **principal**.

It MUST NOT be NULL. It MUST NOT be empty.

### **3.2.5.247.1.1.13 IsDomainGroup**

**Type:** CSOM Boolean

**Accessibility:** Read Only

Specifies whether the user is a DomainGroup.

#### **3.2.5.247.1.1.14 IsMemberOfGroup**

**Type:** CSOM Boolean

**Accessibility:** Read Only

Specifies whether the user is a member of SP.Group.

#### **3.2.5.247.1.1.15 HasReviewPermission**

**Type:** CSOM Boolean

**Accessibility:** Read Only

Indicates whether the **principal** has Review permission for a **document**.

#### **3.2.5.247.1.1.16 IsExternalUser**

**Type:** CSOM Boolean

**Accessibility:** Read Only

Boolean indicating whether the user is external or not.

### **3.2.5.247.1.2 ObjectPath Properties**

#### **3.2.5.247.1.2.1 User**

**Type:** Microsoft.SharePoint.Client.User

**Accessibility:** Read Only

Specifies the user with whom a **securable object** is shared.

#### **3.2.5.247.1.2.2 Principal**

**Type:** Microsoft.SharePoint.Client.Principal

**Accessibility:** Read Only

The **principal** with whom a **securable object** is shared. It is either a user or a **group**.

It MUST NOT be NULL.

### **3.2.5.247.2 Methods**

#### **3.2.5.247.2.1 Scalar Methods**

None.

#### **3.2.5.247.2.2 ObjectPath Methods**

None.

### **3.2.5.248 Microsoft.SharePoint.Client.OpenWebOptions**

**ShortName:** SP.OpenWebOptions

**Flag:** true

The **OpenWebOptions** type specifies if additional navigation information is to be returned with the **site (2)**.

### 3.2.5.248.1 Field Values

#### 3.2.5.248.1.1 None

**Value:** 0

This value specifies that no additional navigation information is to be returned with the **site (2)**.

#### 3.2.5.248.1.2 InitNavigationCache

**Value:** 1

This value specifies that the navigation information is to be returned with the **site (2)**.

### 3.2.5.249 Microsoft.SharePoint.Client.RequestVariable

**TypeId:** {5806D374-4904-49E9-A73F-3265EE2E06C6}

**ShortName:** SP.RequestVariable

Specifies a variable that can be used while processing requests between protocol server and protocol client.

#### 3.2.5.249.1 Properties

##### 3.2.5.249.1.1 Scalar Properties

###### 3.2.5.249.1.1.1 Value

**Type:** CSOM String

**Accessibility:** Read Only

The value of this request variable.

##### 3.2.5.249.1.2 ObjectPath Properties

None.

#### 3.2.5.249.2 Methods

##### 3.2.5.249.2.1 Scalar Methods

###### 3.2.5.249.2.1.1 Append

**Return Type:** None

Appends a value to the value of this request variable.

**Parameters:**

*value:* The value to be appended to the current value of this request variable.

Type: **CSOM String**

### **3.2.5.249.2.1.2 Set**

**Return Type:** None

Sets the value of this request variable.

**Parameters:**

*value:* The value to be set for this request variable.

Type: **CSOM String**

## **3.2.5.249.2.2ObjectPath Methods**

### **3.2.5.249.2.2.1 CSOM Constructor**

Instantiates an instance of type **RequestVariable** (section [3.2.5.249](#)).

**Parameters:** None

## **3.2.5.250 Microsoft.SharePoint.Client.SiteUrl**

**TypeId:** {D7DA1187-8020-42EC-97F4-823AC965AC75}

**ShortName:** SP.SiteUrl

Represents a **URL** for a **site collection**.

### **3.2.5.250.1 Properties**

#### **3.2.5.250.1.1Scalar Properties**

None.

#### **3.2.5.250.1.2ObjectPath Properties**

None.

### **3.2.5.250.2 Methods**

#### **3.2.5.250.2.1Scalar Methods**

None.

#### **3.2.5.250.2.2ObjectPath Methods**

None.

## **3.2.5.251 Microsoft.SharePoint.Client.UserIdInfo**

**TypeId:** {C5C3AE1A-63B6-4F25-A887-54B0B20A28E2}

**ShortName:** SP.UserIdInfo

Contains an identity provider's unique identifier information.

### 3.2.5.251.1 Properties

#### 3.2.5.251.1.1 Scalar Properties

##### 3.2.5.251.1.1.1 NameId

Type: **CSOM String**

Accessibility: Read Only

Specifies the identity provider's unique identifier.

##### 3.2.5.251.1.1.2 NameIdIssuer

Type: **CSOM String**

Accessibility: Read Only

Specifies the identity provider's display name as registered in a **farm**.

#### 3.2.5.251.1.2 ObjectPath Properties

None.

### 3.2.5.252 Microsoft.SharePoint.Client.Utilities.SPWOPIFrameAction

ShortName: SP.Utilities.SPWOPIFrameAction

Flag: false

Specifies distinct operations that are available for the **list item**.

#### 3.2.5.252.1 Field Values

##### 3.2.5.252.1.1 View

Value: 0

Requests a browser-based viewing experience.

##### 3.2.5.252.1.2 Edit

Value: 1

Requests a browser-based editing experience.

##### 3.2.5.252.1.3 MobileView

Value: 2

Requests a mobile browser-based viewing experience.

##### 3.2.5.252.1.4 InteractivePreview

Value: 3

Requests a browser-based previewing experience, suitable for use in an iFrame.

### 3.2.5.252.1.5Syndicate

**Value:** 4

Opens the item in syndicate mode.

### 3.2.5.252.1.6LegacyWebService

**Value:** 5

Opens the item in legacy web service mode.

## 3.2.5.253 Microsoft.SharePoint.Navigation.REST.NavigationServiceRest

**TypeId:** {8FE28B7A-6EBF-4F28-B564-5F0729301FAC}

**ShortName:** Microsoft.SharePoint.Navigation.REST.NavigationServiceRest

The entry point for REST-based navigation service operations.

### 3.2.5.253.1 Properties

#### 3.2.5.253.1.1Scalar Properties

None.

#### 3.2.5.253.1.2ObjectPath Properties

None.

### 3.2.5.253.2 Methods

#### 3.2.5.253.2.1Scalar Methods

##### 3.2.5.253.2.1.1 GetPublishingNavigationProviderType

**Return Type:** Microsoft.SharePoint.Navigation.REST.PublishingNavigationProviderType

Gets a publishing navigation provider type when publishing feature is turned on for the **site (2)**. If navigation provider is not found on the site MUST return **InvalidSiteMapProvider** type.

**Parameters:**

*mapProviderName:* Name identifying the navigation provider

Type: **CSOM String**

The server will use "SPNavigationProvider" as provider name if mapProviderName is not specified.

It MUST NOT be NULL.

##### 3.2.5.253.2.1.2 MenuNodeKey

**Return Type:** **CSOM String**

Returns the unique key for a node within the menu tree. If a key cannot be found, an exception is returned.

**Parameters:**

*currentUrl*: A URL relative to the **site collection** identifying the node within the menu tree.

Type: CSOM String

*mapProviderName*: The name identifying a provider to use for the look up. <235>

Type: CSOM String

### 3.2.5.253.2.1.3 MenuState

**Return Type:** Microsoft.SharePoint.Client.MenuState

Returns the menu tree rooted at the specified root node for a given provider.

**Parameters:**

*menuNodeKey*: A unique key identifying the node that will be used as root node in the returned result.

Type: **CSOM String**

*mapProviderName*: The name identifying the provider to use. <236>

Type: CSOM String

*depth*: The number of levels to include in the returned site map. If no value is specified, a depth of 10 is used.

Type: **CSOM Int32**

*customProperties*: A comma separated list of custom properties to request. The character "\" is used to escape commas, allowing comma to be part of the property names.

Type: CSOM String

## 3.2.5.253.2.2 ObjectPath Methods

### 3.2.5.253.2.2.1 CSOM Constructor

Instantiates an instance of type **NavigationServiceRest** (section [3.2.5.253](#)).

**Parameters:** None

### 3.2.5.254 Microsoft.SharePoint.Client.UpgradeInfo

**TypeId:** {A012E5FA-A28F-4232-9561-C4033F61C889}

**ShortName:** SP.UpgradeInfo

A class containing **site collection** upgrade information.

#### 3.2.5.254.1 Properties

##### 3.2.5.254.1.1 Scalar Properties

###### 3.2.5.254.1.1.1 ErrorFile

Type: **CSOM String**

**Accessibility:** Read Only

Specifies the location of the file that contains upgrade errors.

#### **3.2.5.254.1.1.2 Errors**

**Type:** CSOM Int32

**Accessibility:** Read Only

Specifies the number of errors encountered during the **site collection** upgrade.

#### **3.2.5.254.1.1.3 LastUpdated**

**Type:** CSOM DateTime

**Accessibility:** Read Only

Specifies the **DateTime** of the latest upgrade progress update.

#### **3.2.5.254.1.1.4 LogFile**

**Type:** CSOM String

**Accessibility:** Read Only

Specifies the location of the file that contains upgrade log.

#### **3.2.5.254.1.1.5 RequestDate**

**Type:** CSOM DateTime

**Accessibility:** Read Only

Specifies the **DateTime** when the **site collection** upgrade was requested.

#### **3.2.5.254.1.1.6 RetryCount**

**Type:** CSOM Int32

**Accessibility:** Read Only

Specifies how many times the **site collection** upgrade was attempted.

#### **3.2.5.254.1.1.7 StartTime**

**Type:** CSOM DateTime

**Accessibility:** Read Only

Specifies the **DateTime** when the **site collection** upgrade was started.

#### **3.2.5.254.1.1.8 Status**

**Type:** Microsoft.SharePoint.Client.UpgradeStatus

**Accessibility:** Read Only

Specifies the current **site collection** upgrade status.

#### **3.2.5.254.1.1.9 UpgradeType**



**Type:** Microsoft.SharePoint.Client.UpgradeType

**Accessibility:** Read Only

Specifies the type of the **site collection** upgrade type. The type can be either a build-to-build upgrade, or a version-to-version upgrade.

### 3.2.5.254.1.1.10 Warnings

**Type:** CSOM Int32

**Accessibility:** Read Only

Specifies the number of warnings encountered during the **site collection** upgrade.

### 3.2.5.254.1.2 ObjectPath Properties

None.

## 3.2.5.255 Microsoft.SharePoint.Client.UpgradeStatus

**ShortName:** SP.UpgradeStatus

**Flag:** false

Specifies the status of the **site collection** upgrade.

### 3.2.5.255.1 Field Values

#### 3.2.5.255.1.1 None

**Value:** 0

Upgrade has not started.

#### 3.2.5.255.1.2 InProgress

**Value:** 1

Upgrade is in progress.

#### 3.2.5.255.1.3 Failed

**Value:** 2

Upgrade has failed.

#### 3.2.5.255.1.4 Completed

**Value:** 3

Upgrade has completed successfully.

## 3.2.5.256 Microsoft.SharePoint.Client.AppInstanceErrorDetails

**TypeId:** {E1EE83CD-B0A5-4F57-A10C-5BCC11EB1C69}

**ShortName:** SP.AppInstanceErrorDetails

Specifies details about the error encountered during a lifecycle operation of an **app instance**.

### **3.2.5.256.1 Properties**

#### **3.2.5.256.1.1 Scalar Properties**

##### **3.2.5.256.1.1.1 CorrelationId**

**Type:** CSOM GUID

**Accessibility:** Read/Write

Specifies the unique identifier of the lifecycle operation associated with the error.

##### **3.2.5.256.1.1.2 ErrorDetail**

**Type:** CSOM String

**Accessibility:** Read Only

Specifies the detailed error message.

##### **3.2.5.256.1.1.3 ErrorType**

**Type:** Microsoft.SharePoint.Client.AppInstanceErrorType

**Accessibility:** Read/Write

Specifies the type of error as specified in section [3.2.5.258](#).

##### **3.2.5.256.1.1.4 ErrorTypeName**

**Type:** CSOM String

**Accessibility:** Read Only

Specifies the name for the error type.

##### **3.2.5.256.1.1.5 ExceptionMessage**

**Type:** CSOM String

**Accessibility:** Read Only

Specifies the exception message that caused the error.

##### **3.2.5.256.1.1.6 Source**

**Type:** Microsoft.SharePoint.Client.AppInstanceErrorSource

**Accessibility:** Read/Write

Specifies the source of the error as specified in section [3.2.5.257](#).

##### **3.2.5.256.1.1.7 SourceName**

**Type:** CSOM String

**Accessibility:** Read Only

Specifies the name for the source of error.

### **3.2.5.256.1.2ObjectPath Properties**

None.

### **3.2.5.256.2 Methods**

#### **3.2.5.256.2.1Scalar Methods**

None.

#### **3.2.5.256.2.2ObjectPath Methods**

None.

### **3.2.5.257 Microsoft.SharePoint.Client.AppInstanceErrorSource**

**ShortName:** SP.AppInstanceErrorSource

**Flag:** false

Specifies the source of error for the **app instance** lifecycle operation.

#### **3.2.5.257.1 Field Values**

##### **3.2.5.257.1.1Common**

**Value:** 0

The error originated from none of the well-defined sources.

##### **3.2.5.257.1.2AppWeb**

**Value:** 1

The error originated from an **app instance** lifecycle operation on the **app(2) site (2)**.

##### **3.2.5.257.1.3ParentWeb**

**Value:** 2

The error originated from an **app instance** lifecycle operation on the **site (2)** that contains the app instance.

##### **3.2.5.257.1.4RemoteWebSite**

**Value:** 3

The error originated from an **app instance** lifecycle remote system operation outside of SharePoint.

##### **3.2.5.257.1.5Database**

**Value:** 4

The error originated from an **app instance** lifecycle database operation.

##### **3.2.5.257.1.6OfficeExtension**

**Value:** 5

The error originated from an **app instance** lifecycle operation associated with **Office Add-in**.

### **3.2.5.257.1.7 EventCallouts**

**Value:** 6

The error originated from an **app instance** lifecycle operation on a remote event receiver.

### **3.2.5.257.1.8 Finalization**

**Value:** 7

The error originated from the final step of an **app instance** lifecycle operation.

## **3.2.5.258 Microsoft.SharePoint.Client.AppInstanceErrorType**

**ShortName:** SP.AppInstanceErrorType

**Flag:** false

Specifies the type of error that occurred during lifecycle operation for an **app instance**.

### **3.2.5.258.1 Field Values**

#### **3.2.5.258.1.1 Transient**

**Value:** 0

A transient or intermittent error occurred during lifecycle operation.

#### **3.2.5.258.1.2 Configuration**

**Value:** 1

An error related to configuration occurred during lifecycle operation.

#### **3.2.5.258.1.3 App**

**Value:** 2

An error related to a bad **app package** occurred during lifecycle operation.

## **3.2.5.259 Microsoft.SharePoint.Client.CompatibilityRange**

**TypeId:** {3A64E199-FBE8-4277-960B-9067471CF64B}

**ShortName:** SP.CompatibilityRange

Specifies a range of compatibility levels.

### **3.2.5.259.1 Properties**

#### **3.2.5.259.1.1 Scalar Properties**

None.

### 3.2.5.259.1.2 ObjectPath Properties

None.

### 3.2.5.259.2 Methods

#### 3.2.5.259.2.1 Scalar Methods

None.

#### 3.2.5.259.2.2 ObjectPath Methods

None.

### 3.2.5.260 Microsoft.SharePoint.Client.AccessRequests

**TypeId:** {E7DAE9F6-8AA5-4B86-92C8-61941D774C44}

**ShortName:** SP.AccessRequests

Provides functionality to operate on access requests and external user invitations.

#### 3.2.5.260.1 Properties

##### 3.2.5.260.1.1 Scalar Properties

None.

##### 3.2.5.260.1.2 ObjectPath Properties

None.

#### 3.2.5.260.2 Methods

##### 3.2.5.260.2.1 Scalar Methods

###### 3.2.5.260.2.1.1 ChangeRequestStatus

This method is a **static CSOM method**.

**Return Type:** None

This method changes the status of an access request. The user executing this method **MUST** be in the associated site owners group.

**Parameters:**

*itemId*: The identifier of the access request.

Type: **CSOM Int32**

This **MUST** be a non-negative integer id of a valid item in the list.

*newStatus*: The new status for the request.

Type: CSOM Int32

This **MUST** be an integer in the range 0 through 5.

*convStr*: A message to include with this update.

Type: **CSOM String**

*permType*: The new permission type for this request.

Type: CSOM String

The values MUST be one of "Role Definition" or "SharePoint Group".

*permissionLevel*: The new permission level for this request.

Type: CSOM Int32

Based on what the *permType* is, the value MUST be a valid **ID** property (section [3.2.5.76.1.1.8](#)) of an existing site group or a valid **ID** property (section [3.2.5.113.1.1.4](#)) pointing to a role definition.

### **3.2.5.260.2.1.2 ChangeRequestStatusBulk**

This method is a **static CSOM method**.

**Return Type:** None

Changes the status of a list of access requests. The user executing this method MUST be in the associated site owners group.

#### **Parameters:**

*requestIds*: The list of identifiers of the access requests.

Type: **CSOM array** of **CSOM Int32**

This array MUST contain at least one valid non negative integer. It MUST NOT be NULL. It MUST NOT be an empty array.

*newStatus*: The new status for the access requests.

Type: CSOM Int32

It MUST be an integer in the range 0 through 5. The status code MUST be one of the following:

<b>Status code</b>	<b>Status description</b>
<b>0</b>	The access request or invitation is pending.
<b>1</b>	The access request has been approved.
<b>2</b>	The invitation has been accepted.
<b>3</b>	The access request has been denied.
<b>4</b>	The invitation has expired.
<b>5</b>	The invitation has been revoked.

### **3.2.5.260.2.1.3 QuickActionChangeRequestStatus**

This method is a **static CSOM method**.

**Return Type:** Microsoft.SharePoint.QuickActionMessageCard.MessageCard

Change an access request status through actionable message card

**Parameters:**

*web*: The current **site (2)** that is the target of the request.

Type: Microsoft.SharePoint.Client.Web

*refreshStatus*: An object that contains signature to verify, unique Id of the access request, and the target status.

Type: Microsoft.SharePoint.QuickActionMessageCard.SPAccessRequestRefreshStatus

### 3.2.5.260.2.1.4 UpdateConversation

This method is a **static CSOM method**.

**Return Type:** None

Updates a conversation in a request.

**Parameters:**

*itemId*: The identifier of the conversation.

Type: **CSOM Int32**

*convStr*: A message to include with this update.

Type: **CSOM String**

*web*: The **site (2)** containing the conversation.

Type: Microsoft.SharePoint.Client.Web

### 3.2.5.260.2.2 ObjectPath Methods

None.

### 3.2.5.261 Microsoft.SharePoint.Client.AppContextSite

**TypeId:** {5530F782-6A0D-41EC-BFD9-2CB628FE1557}

**ShortName:** SP.AppContextSite

Specifies the request context information for a **site collection** when a **SharePoint Add-in** accesses that site collection.

#### 3.2.5.261.1 Properties

##### 3.2.5.261.1.1 Scalar Properties

None.

##### 3.2.5.261.1.2 ObjectPath Properties

###### 3.2.5.261.1.2.1 Site

**Type:** Microsoft.SharePoint.Client.Site

**Accessibility:** Read Only

Specifies the **site collection** that is the target of the request from a **SharePoint Add-in**.

It MUST NOT be NULL.

### **3.2.5.261.1.2.2 Web**

**Type:** Microsoft.SharePoint.Client.Web

**Accessibility:** Read Only

Specifies the **site (2)** that is the target of the request from a **SharePoint Add-in**.

It MUST NOT be NULL.

## **3.2.5.261.2 Methods**

### **3.2.5.261.2.1 Scalar Methods**

None.

### **3.2.5.261.2.2 ObjectPath Methods**

#### **3.2.5.261.2.2.1 CSOM Constructor**

Instantiates an instance of type **AppContextSite** (section [3.2.5.261](#)).

**Parameters:**

*siteUrl*: The **absolute URL** for the **site collection**.

Type: **CSOM String**

## **3.2.5.262 Microsoft.SharePoint.Client.Analytics.AnalyticsUsageEntry**

**TypeId:** {47228DF5-E073-47CA-97A8-A0537B77A1DF}

**ShortName:** SP.Analytics.AnalyticsUsageEntry

Specifies an analytics usage entry to log user or system events. [<237>](#)

### **3.2.5.262.1 Properties**

#### **3.2.5.262.1.1 Scalar Properties**

None.

#### **3.2.5.262.1.2 ObjectPath Properties**

None.

### **3.2.5.262.2 Methods**

#### **3.2.5.262.2.1 Scalar Methods**



### 3.2.5.262.2.1.1 LogAnalyticsAppEvent

This method is a **static CSOM method**.

**Return Type:** None

Creates and logs an analytics event into the analytics pipeline.

**Parameters:**

*appEventTypeId*: The event type identifier of the analytics event to be created.

Type: **CSOM GUID**

*itemId*: The identifier of the item for which the event is being logged.

Type: **CSOM String**

MUST be less than or equal to 260 characters.

### 3.2.5.262.2.1.2 LogAnalyticsAppEvent2

This method is a **static CSOM method**.

**Return Type:** None

Creates and logs an analytics event into the analytics pipeline with additional parameters.

**Parameters:**

*appEventTypeId*: The event type identifier of the analytics event to be created.

Type: **CSOM GUID**

*itemId*: The identifier of the item for which the event is being logged.

Type: **CSOM String**

MUST be less than or equal to 260 characters.

*rollupScopeId*: The identifier of a rollup scope. Events for different items with the same rollup scope can be aggregated together at that rollup scope in addition to being counted just at the item scope.

Type: CSOM GUID

*siteId*: The identifier of the item's site.

Type: CSOM GUID

*userId*: The identifier of the user generating the event.

Type: CSOM String

MUST be less than or equal to 260 characters.

### 3.2.5.262.2.1.3 LogAnalyticsEvent

This method is a **static CSOM method**.

**Return Type:** None

Creates and logs an analytics event into the analytics pipeline.

**Parameters:**

*eventTypeid*: The event type identifier of the analytics event to create.

Type: **CSOM Int32**

MUST be one of the values specified by Microsoft.SharePoint.Client.Analytics.EventTypeId.

*itemid*: The identifier of the item for which the event is being logged.

Type: **CSOM String**

MUST be less than or equal to 260 characters.

**3.2.5.262.2.1.4 LogAnalyticsEvent2**

This method is a **static CSOM method**.

**Return Type:** None

Creates and logs an analytics event into the analytics pipeline with additional parameters.

**Parameters:**

*eventTypeid*: The event type identifier of the analytics event to create

Type: **CSOM Int32**

MUST be one of the values specified by Microsoft.SharePoint.Client.Analytics.EventTypeId.

*itemid*: The identifier of the item for which the event is being logged.

Type: **CSOM String**

MUST be less than or equal to 260 characters.

*rollupScopeId*: The identifier of a rollup scope. Events for different items with the same rollup scope can be aggregated together at that rollup scope in addition to being counted just at the item scope.

Type: **CSOM GUID**

*siteId*: The identifier of the item's site.

Type: CSOM GUID

*userId*: The identifier of the user generating the event.

Type: CSOM String

MUST be less than or equal to 260 characters.

**3.2.5.262.2.2ObjectPath Methods**

None.

**3.2.5.263 Microsoft.SharePoint.Client.UrlZone**

**ShortName:** SP.UrlZone

**Flag:** false

Represents a location in the topology of the **farm**.

### **3.2.5.263.1 Field Values**

#### **3.2.5.263.1.1 DefaultZone**

**Value:** 0

Specifies the default zone used for requests unless another zone is specified.

#### **3.2.5.263.1.2 Intranet**

**Value:** 1

Specifies an intranet zone.

#### **3.2.5.263.1.3 Internet**

**Value:** 2

Specifies an internet zone.

#### **3.2.5.263.1.4 Custom**

**Value:** 3

Specifies a custom zone.

#### **3.2.5.263.1.5 Extranet**

**Value:** 4

Specifies an extranet zone.

### **3.2.5.264 Microsoft.SharePoint.Client.WebParts.TileData**

**TypeId:** {9786D53B-4147-4E57-9D94-1D9F335D42B3}

**ShortName:** SP.WebParts.TileData

Represents a Tile that describes a graphical link the user can click.

#### **3.2.5.264.1 Properties**

##### **3.2.5.264.1.1 Scalar Properties**

###### **3.2.5.264.1.1.1 BackgroundCollageImageLocations**

**Type:** CSOM array of CSOM String

**Accessibility:** Read/Write

Specifies the location of the images used to render the tile background, if it is a tile with a split background.

###### **3.2.5.264.1.1.2 BackgroundImageLocation**

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies the **URL** of the Tile background image.

#### **3.2.5.264.1.1.3 BackgroundImageRendersAsIcon**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Specifies whether the background image renders as an icon, positioned just above the overlay.

#### **3.2.5.264.1.1.4 BodyText**

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies the text written in the body of the tile.

#### **3.2.5.264.1.1.5 Description**

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies the text that describes a Tile.

#### **3.2.5.264.1.1.6 HoverDisabled**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Specifies whether the tile's hover behavior SHOULD be disabled.

#### **3.2.5.264.1.1.7 ID**

**Type:** CSOM Int32

**Accessibility:** Read/Write

Species a unique number that represents the Tile in a list of Tiles.

#### **3.2.5.264.1.1.8 IsWide**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Specifies whether the tile is a wide tile.

#### **3.2.5.264.1.1.9 LinkLocation**

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies the **URL** location of the navigation that happens on Tile click.

#### **3.2.5.264.1.1.10 TileOrder**

**Type:** CSOM Int32

**Accessibility:** Read/Write

Specifies a number that indicates the ordering of the Tile in a list of Tiles.

#### **3.2.5.264.1.1.11 Title**

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies the title of the Tile.

#### **3.2.5.264.1.1.12 TransparentOverlay**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Specifies whether the tile's title overlay SHOULD be completely transparent.

#### **3.2.5.264.1.2ObjectPath Properties**

None.

### **3.2.5.265 Microsoft.SharePoint.Client.AppPrincipal**

**TypeId:** {A19A4C61-D4C0-4100-9D47-A04BE33AF6F1}

**ShortName:** SP.AppPrincipal

Represents a single **app principal**.

#### **3.2.5.265.1 Properties**

##### **3.2.5.265.1.1 Scalar Properties**

###### **3.2.5.265.1.1.1 DisplayName**

**Type:** CSOM String

**Accessibility:** Read Only

The display name of the **app principal**.

###### **3.2.5.265.1.1.2 EndpointAuthorities**

**Type:** CSOM array of CSOM String

**Accessibility:** Read Only

The endpoints of the app.

The value is a list of hostname[:port].

###### **3.2.5.265.1.1.3 NameIdentifier**

**Type:** CSOM String

**Accessibility:** Read Only

The name identifier of the **app principal**.

#### **3.2.5.265.1.1.4 RedirectAddresses**

**Type:** CSOM array of CSOM String

**Accessibility:** Read Only

The redirect URI associated with the app.

The authorization server sends the end user back to the redirect URI once the access is granted or denied.

#### **3.2.5.265.1.2 ObjectPath Properties**

None.

#### **3.2.5.265.2 Methods**

##### **3.2.5.265.2.1 Scalar Methods**

None.

##### **3.2.5.265.2.2 ObjectPath Methods**

None.

#### **3.2.5.266 Microsoft.SharePoint.Client.AppPrincipalConfiguration**

**TypeId:** {358F59EE-7E98-4CC0-9F40-A160CCF3879F}

**ShortName:** SP.AppPrincipalConfiguration

Represents the configuration associated with an app principal.

#### **3.2.5.266.1 Properties**

##### **3.2.5.266.1.1 Scalar Properties**

###### **3.2.5.266.1.1.1 ApplicationEndpointAuthorities**

**Type:** CSOM array of CSOM String

**Accessibility:** Read/Write

The list of endpoint authorities exposed by the principal.

###### **3.2.5.266.1.1.2 ApplicationPrincipalNames**

**Type:** CSOM array of CSOM String

**Accessibility:** Read/Write

The list of principal names.

###### **3.2.5.266.1.1.3 NameIdentifier**

Type: **CSOM String**

**Accessibility:** Read/Write

The name of the principal.

#### **3.2.5.266.1.1.4 RedirectAddresses**

Type: **CSOM array** of **CSOM String**

**Accessibility:** Read/Write

The list of redirect addresses of the principal.

#### **3.2.5.266.1.2ObjectPath Properties**

None.

### **3.2.5.267 Microsoft.SharePoint.Client.AppPrincipalCredential**

**TypeId:** {9C0B9F8A-D87B-431D-BC10-D0F0B4AFC79C}

**ShortName:** SP.AppPrincipalCredential

Represents a credential belonging to an **app principal**.

#### **3.2.5.267.1 Properties**

##### **3.2.5.267.1.1Scalar Properties**

None.

##### **3.2.5.267.1.2ObjectPath Properties**

None.

#### **3.2.5.267.2 Methods**

##### **3.2.5.267.2.1Scalar Methods**

None.

##### **3.2.5.267.2.2ObjectPath Methods**

###### **3.2.5.267.2.2.1 CreateFromKeyGroup**

This method is a **static CSOM method**.

**Return Type:** Microsoft.SharePoint.Client.AppPrincipalCredential

Create an instance of **SP.AppPrincipalCredential** that wraps a key group identifier.

**Parameters:**

*keyGroupIdentifier:* The key group identifier.

Type: **CSOM GUID**

### 3.2.5.267.2.2.2 CreateFromSymmetricKey

This method is a **static CSOM method**.

**Return Type:** Microsoft.SharePoint.Client.AppPrincipalCredential

Create an instance of **SP.AppPrincipalCredential** that wraps a symmetric key.

#### Parameters:

*symmetricKey*: The symmetric key of the **app principal** credential.

Type: **CSOM String**

*notBefore*: The earliest time when the key is valid.

Type: **CSOM DateTime**

*notAfter*: The time when the key expires.

Type: CSOM DateTime

### 3.2.5.268 Microsoft.SharePoint.Client.AppPrincipalCredentialReference

**TypeId:** {AAF308B2-EBDD-4A5B-BE65-01BB0EC8C5BE}

**ShortName:** SP.AppPrincipalCredentialReference

Represents a reference to a credential for an **app principal**.

#### 3.2.5.268.1 Properties

##### 3.2.5.268.1.1 Scalar Properties

###### 3.2.5.268.1.1.1 Id

**Type:** **CSOM GUID**

**Accessibility:** Read/Write

The unique identifier of the **app principal** credential.

###### 3.2.5.268.1.1.2 NameIdentifier

**Type:** **CSOM String**

**Accessibility:** Read/Write

The name of the **app principal** credential.

###### 3.2.5.268.1.1.3 NotAfter

**Type:** **CSOM DateTime**

**Accessibility:** Read/Write

The earliest time when the **app principal** credential is valid.

###### 3.2.5.268.1.1.4 NotBefore



**Type:** CSOM DateTime

**Accessibility:** Read/Write

The time when the **app principal** credential expires.

### 3.2.5.268.1.2 ObjectPath Properties

None.

## 3.2.5.269 Microsoft.SharePoint.Client.AppPrincipalIdentityProvider

**TypeId:** {3CC457AE-D404-4747-8B95-C6F86BFD1842}

**ShortName:** SP.AppPrincipalIdentityProvider

Represents an identity provider for **app principals**.

### 3.2.5.269.1 Properties

#### 3.2.5.269.1.1 Scalar Properties

None.

#### 3.2.5.269.1.2 ObjectPath Properties

##### 3.2.5.269.1.2.1 External

**Type:** Microsoft.SharePoint.Client.AppPrincipalIdentityProvider

**Accessibility:** Read Only

The external **app principal** identity provider.

### 3.2.5.269.2 Methods

#### 3.2.5.269.2.1 Scalar Methods

None.

#### 3.2.5.269.2.2 ObjectPath Methods

None.

## 3.2.5.270 Microsoft.SharePoint.Client.AppPrincipalManager

**TypeId:** {1DAEE121-93EA-40E6-AAD2-15252287F09A}

**ShortName:** SP.AppPrincipalManager

Represents a top level object used to manage **app principals**.

### 3.2.5.270.1 Properties

#### 3.2.5.270.1.1 Scalar Properties

None.

### 3.2.5.270.1.2 ObjectPath Properties

None.

### 3.2.5.270.2 Methods

#### 3.2.5.270.2.1 Scalar Methods

##### 3.2.5.270.2.1.1 AddAppPrincipalCredential

**Return Type:** None

Add a new credential for an existing **app principal**.

**Parameters:**

*appPrincipal*: The app principal.

Type: Microsoft.SharePoint.Client.AppPrincipal

*credential*: The credential to add.

Type: Microsoft.SharePoint.Client.AppPrincipalCredential

##### 3.2.5.270.2.1.2 DeleteAppPrincipal

**Return Type:** None

Delete an app principal.

**Parameters:**

*appPrincipal*: The **app principal** to delete.

Type: Microsoft.SharePoint.Client.AppPrincipal

##### 3.2.5.270.2.1.3 DeleteAppPrincipalCredential

**Return Type:** None

Delete an existing credential for an app principal.

**Parameters:**

*credentialReference*: A reference to the credential to be deleted

Type: Microsoft.SharePoint.Client.AppPrincipalCredentialReference

##### 3.2.5.270.2.1.4 GetAppPrincipalConfiguration

**Return Type:** Microsoft.SharePoint.Client.AppPrincipalConfiguration

Get the configuration associated with the specified **app principal**.

**Parameters:**

*appPrincipal*: The app principal

Type: Microsoft.SharePoint.Client.AppPrincipal

### 3.2.5.270.2.1.5      **GetAppPrincipalCredentials**

**Return Type:** **CSOM array** of Microsoft.SharePoint.Client.AppPrincipalCredentialReference

Get a reference to each credential associated with an **app principal**.

**Parameters:**

*appPrincipal:* The app principal

Type: Microsoft.SharePoint.Client.AppPrincipal

### 3.2.5.270.2.1.6      **SetAppPrincipalConfiguration**

**Return Type:** None

Set the configuration associated with the specified app principal.

**Parameters:**

*appPrincipalConfiguration:* The configuration to be associated with the **app principal**.

Type: Microsoft.SharePoint.Client.AppPrincipalConfiguration

## 3.2.5.270.2.2 ObjectPath Methods

### 3.2.5.270.2.2.1      **CreateAppPrincipal**

**Return Type:** Microsoft.SharePoint.Client.AppPrincipal

Create an app principal.

**Parameters:**

*parameters:* The collection of input parameters used to create a new **app principal**.

Type: Microsoft.SharePoint.Client.ExternalAppPrincipalCreationParameters

### 3.2.5.270.2.2.2      **GetManager**

This method is a **static CSOM method**.

**Return Type:** Microsoft.SharePoint.Client.AppPrincipalManager

Create a new instance of AppPrincipalManager.

**Parameters:**

*web:* The context object required to manage app principals.

Type: Microsoft.SharePoint.Client.Web

### 3.2.5.270.2.2.3      **LookupAppPrincipal**

**Return Type:** Microsoft.SharePoint.Client.AppPrincipal

Looks up an **app principal**.

**Parameters:**

*identityProvider:* The identity provider of the app principal.

Type: Microsoft.SharePoint.Client.AppPrincipalIdentityProvider

*appPrincipalName*: The app principal name

Type: Microsoft.SharePoint.Client.AppPrincipalName

### **3.2.5.271 Microsoft.SharePoint.Client.AppPrincipalName**

**TypeId:** {2F631229-B71E-4DDF-83D6-96D290D0FC57}

**ShortName:** SP.AppPrincipalName

Represents the name of an **app principal**.

#### **3.2.5.271.1 Properties**

##### **3.2.5.271.1.1 Scalar Properties**

None.

##### **3.2.5.271.1.2 ObjectPath Properties**

None.

#### **3.2.5.271.2 Methods**

##### **3.2.5.271.2.1 Scalar Methods**

None.

##### **3.2.5.271.2.2 ObjectPath Methods**

###### **3.2.5.271.2.2.1 CreateFromAppPrincipalIdentifier**

This method is a **static CSOM method**.

**Return Type:** Microsoft.SharePoint.Client.AppPrincipalName

Creates an instance from the specified **app principal** identifier.

**Parameters:**

*appPrincipalIdentifier*: The app principal identifier of the desired app principal.

Type: **CSOM String**

###### **3.2.5.271.2.2.2 CreateFromNameIdentifier**

This method is a **static CSOM method**.

**Return Type:** Microsoft.SharePoint.Client.AppPrincipalName

Creates an instance from the specified name identifier.

**Parameters:**

*nameIdentifier*: The name identifier of the desired **app principal**.

Type: **CSOM String**

### 3.2.5.272 Microsoft.SharePoint.Client.ExternalAppPrincipalCreationParameters

**TypeId:** {5D3A2EAE-4870-414E-B9AE-8F1904B28408}

**ShortName:** SP.ExternalAppPrincipalCreationParameters

Represents the parameters used to create a new external **app principal**.

#### 3.2.5.272.1 Properties

##### 3.2.5.272.1.1 Scalar Properties

###### 3.2.5.272.1.1.1 AppIdentifier

**Type:** CSOM String

**Accessibility:** Read/Write

The unique identifier of the **app principal**.

###### 3.2.5.272.1.1.2 ApplicationEndpointAuthorities

**Type:** CSOM array of CSOM String

**Accessibility:** Read/Write

The list of hostname[:port] strings that expose app endpoints.

###### 3.2.5.272.1.1.3 DisplayName

**Type:** CSOM String

**Accessibility:** Read/Write

The display name of the **app principal**.

###### 3.2.5.272.1.1.4 RedirectAddresses

**Type:** CSOM array of CSOM String

**Accessibility:** Read/Write

The list of redirect addresses for the **app principal**.

###### 3.2.5.272.1.1.5 TrustedForDelegation

**Type:** CSOM Boolean

**Accessibility:** Read/Write

This value is true if and only if the **app principal** is trusted for delegation.

##### 3.2.5.272.1.2 ObjectPath Properties

###### 3.2.5.272.1.2.1 Credential

**Type:** Microsoft.SharePoint.Client.AppPrincipalCredential

**Accessibility:** Read/Write

The credential to associate with the new **app principal**.

### **3.2.5.273 Microsoft.SharePoint.Client.SiteHealth.SiteHealthStatusType**

**ShortName:** SP.SiteHealth.SiteHealthStatusType

**Flag:** false

Specifies the success or failure mode of a site collection health rule. [<238>](#)

#### **3.2.5.273.1 Field Values**

##### **3.2.5.273.1.1 Passed**

**Value:** 0

Specifies that the site collection health rule passed. Site collection upgrade is not blocked by this site collection health rule.

##### **3.2.5.273.1.2 FailedWarning**

**Value:** 1

Specifies that the site collection health rule failed with a warning. Site collection upgrade is not blocked by this site collection health rule.

##### **3.2.5.273.1.3 FailedError**

**Value:** 2

Specifies that the site collection health rule failed with an error. Site collection upgrade is blocked by this site collection health rule.

### **3.2.5.274 Microsoft.SharePoint.Client.Utilities.LogAppErrorResult**

**ShortName:** SP.Utilities.LogAppErrorResult

**Flag:** false

Specifies the success or failure result of logging a custom error by a **SharePoint Add-in**. [<239>](#)

#### **3.2.5.274.1 Field Values**

##### **3.2.5.274.1.1 Success**

**Value:** 0

Specifies that the error logging succeeded.

##### **3.2.5.274.1.2 ErrorsThrottled**

**Value:** -1

Specifies that the current error was not logged successfully because there are too many errors reported.

##### **3.2.5.274.1.3 AccessDenied**

**Value:** -2

Specifies that the current error was not logged successfully because an authorization error occurred.

### **3.2.5.275 Microsoft.SharePoint.Client.RenderListDataParameters**

**TypeId:** {AE2D69B3-12FA-4ECB-BA76-BBA24D51E83D}

**ShortName:** SP.RenderListDataParameters

Specifies the parameters to be used to render list data as a **JSON** string.

#### **3.2.5.275.1 Properties**

##### **3.2.5.275.1.1 Scalar Properties**

###### **3.2.5.275.1.1.1 AddRequiredFields**

**Type:** **CSOM Boolean**

**Accessibility:** Read/Write

This parameter indicates if we return required fields.

###### **3.2.5.275.1.1.2 AllowMultipleValueFilterForTaxonomyFields**

**Type:** **CSOM Boolean**

**Accessibility:** Read/Write

This parameter indicates whether multi value filtering is allowed for taxonomy fields.

###### **3.2.5.275.1.1.3 DatesInUtc**

**Type:** **CSOM Boolean**

**Accessibility:** Read/Write

Specifies if the DateTime field is returned in UTC or local time.

###### **3.2.5.275.1.1.4 ExpandGroups**

**Type:** **CSOM Boolean**

**Accessibility:** Read/Write

Specifies whether to expand the grouping or not.

###### **3.2.5.275.1.1.5 FirstGroupOnly**

**Type:** **CSOM Boolean**

**Accessibility:** Read/Write

Specifies whether to only return first group (regardless of view schema) or not.

###### **3.2.5.275.1.1.6 FolderServerRelativeUrl**

**Type:** **CSOM String**

**Accessibility:** Read/Write

Specifies the **server-relative URL** of a **list folder** from which to return items.

### **3.2.5.275.1.1.7 ImageFieldsToTryRewriteToCdnUrls**

**Type:** **CSOM String**

**Accessibility:** Read/Write

This parameter indicates which fields to try and ReWrite to CDN Urls. The format of this parameter SHOULD be a comma separated list of field names.

### **3.2.5.275.1.1.8 OverrideViewXml**

**Type:** **CSOM String**

**Accessibility:** Read/Write

Specified the override XML to be combined with the View CAML.

### **3.2.5.275.1.1.9 Paging**

**Type:** **CSOM String**

**Accessibility:** Read/Write

Specifies the paging information.

### **3.2.5.275.1.1.10 RenderOptions**

**Type:** Microsoft.SharePoint.Client.RenderListDataOptions

**Accessibility:** Read/Write

Specifies the type of output to return.

### **3.2.5.275.1.1.11 ReplaceGroup**

**Type:** **CSOM Boolean**

**Accessibility:** Read/Write

Specifies whether to replace the grouping or not to deal with GroupBy throttling.

### **3.2.5.275.1.1.12 ViewXml**

**Type:** **CSOM String**

**Accessibility:** Read/Write

Specifies the **CAML** view **XML**.

### **3.2.5.275.1.2ObjectPath Properties**

None.



### 3.2.5.276 Microsoft.SharePoint.Client.TenantAppUtility\_manual

**TypeId:** {A7E15A67-957E-459b-8903-E1E42FA52AB1}

**ShortName:** SP.TenantAppUtility

#### 3.2.5.276.1 Properties

##### 3.2.5.276.1.1 Scalar Properties

None.

##### 3.2.5.276.1.2 ObjectPath Properties

None

#### 3.2.5.276.2 Methods

##### 3.2.5.276.2.1 Scalar Methods

None

##### 3.2.5.276.2.2 ObjectPath Methods

###### 3.2.5.276.2.2.1 GetTenantAppInformationCollection

This method is a **static CSOM method**.

**Return Type:** List<Microsoft.SharePoint.Client.TenantAppInformation>

Get a list of tenant app information.

**Parameters:**

*web*: The site where to get the tenant apps.

Type: Microsoft.SharePoint.Client.Web

*lcid*: The locale supported by the tenant apps.

Type: int

### 3.2.5.277 Microsoft.SharePoint.Client.TenantAppInformation\_manual

**TypeId:** {52E6BC7D-825F-45B5-9F39-7A11723319DF}

**ShortName:** SP.TenantAppAppInformation

#### 3.2.5.277.1 Properties

##### 3.2.5.277.1.1 Scalar Properties

###### 3.2.5.277.1.1.1 Id

Type: **CSOM String**

**Accessibility:** Read Only

The Id of an app.

### **3.2.5.277.1.1.2      CreationTime**

**Type:** CSOM DateTime

**Accessibility:** Read Only

The creation time of an app.

### **3.2.5.277.1.1.3      LaunchUrl**

**Type:** CSOM String

**Accessibility:** Read Only

The launch URL of an app.

### **3.2.5.277.1.1.4      RemoteAppUrl**

**Type:** CSOM String

**Accessibility:** Read Only

The URL of the remote host of an app.

### **3.2.5.277.1.1.5      AppPrincipalId**

**Type:** CSOM String

**Accessibility:** Read Only

The OAuth Id of an app.

### **3.2.5.277.1.1.6      Status**

**Type:** Microsoft.SharePoint.Client.AppInstanceStatus

**Accessibility:** Read Only

The status of the **app instance** as defined in section [3.2.5.238](#).

### **3.2.5.277.1.1.7      Title**

**Type:** CSOM String

**Accessibility:** Read Only

The title of an app.

### **3.2.5.277.1.1.8      ProductId**

**Type:** CSOM GUID

**Accessibility:** Read Only

The product Id of an app.

### **3.2.5.277.1.1.9      IconAbsoluteUrl**

**Type:** CSOM String

**Accessibility:** Read Only

The absolute URL of an app's icon.

### **3.2.5.277.1.1.10 IconFallbackAbsoluteUrl**

**Type:** CSOM String

**Accessibility:** Read Only

The absolute fallback URL of an app's icon.

### **3.2.5.277.1.1.11 AppWebFullUrl**

**Type:** CSOM String

**Accessibility:** Read Only

The full URL of an app's web.

### **3.2.5.277.1.1.12 PackageFingerprint**

**Type:** CSOM Stream

**Accessibility:** Read Only

The fingerprint of an app's package.

## **3.2.5.277.1.2ObjectPath Properties**

None.

## **3.2.5.277.2 Methods**

### **3.2.5.277.2.1Scalar Methods**

None.

### **3.2.5.277.2.2ObjectPath Methods**

None.

## **3.2.5.278 Microsoft.SharePoint.Client.AppTile**

**TypeId:** {C84B5B09-0AB8-43F0-8A01-6A7A2EC4C7B9}

**ShortName:** SP.AppTile

Represents information about an app tile.

### **3.2.5.278.1 Properties**

#### **3.2.5.278.1.1Scalar Properties**

##### **3.2.5.278.1.1.1 AppId**

**Type:** CSOM GUID

**Accessibility:** Read Only

The Id of the app.

### 3.2.5.278.1.1.2 AppPrincipalId

**Type:** CSOM String

**Accessibility:** Read Only

The application principal identifier associated with this app. Defaults to empty string.

### 3.2.5.278.1.1.3 AppSource

**Type:** Microsoft.SharePoint.Administration.AppSource

**Accessibility:** Read Only

The source of the app.

### 3.2.5.278.1.1.4 AppStatus

**Type:** Microsoft.SharePoint.Client.AppStatus

**Accessibility:** Read Only

Status of the app. Defaults to Installed.

### 3.2.5.278.1.1.5 AppType

**Type:** Microsoft.SharePoint.Client.AppType

**Accessibility:** Read Only

The type of the app represented by this app tile.

### 3.2.5.278.1.1.6 AssetId

**Type:** CSOM String

**Accessibility:** Read Only

An Id representing the underlying asset type and version, for example document library. This value is used by **GetAppProperties** (section [3.2.5.377.2.1.1](#)).

### 3.2.5.278.1.1.7 BaseTemplate

**Type:** Microsoft.SharePoint.Client.ListTemplateType

**Accessibility:** Read Only

If the is DocLib or List, this will be the base template of the app, otherwise invalid.

### 3.2.5.278.1.1.8 ChildCount

**Type:** CSOM Int32

**Accessibility:** Read Only

The number of children contained in the app represented by this app tile, if applicable.

### **3.2.5.278.1.1.9 ContentMarket**

**Type:** CSOM String

**Accessibility:** Read Only

The market from which the app was installed. Defaults to empty string.

### **3.2.5.278.1.1.10 CustomSettingsUrl**

**Type:** CSOM String

**Accessibility:** Read Only

An app provided url for a custom settings page. Defaults to empty string.

### **3.2.5.278.1.1.11 Description**

**Type:** CSOM String

**Accessibility:** Read Only

An optional description of the app. Defaults to empty string.

### **3.2.5.278.1.1.12 IsCorporateCatalogSite**

**Type:** CSOM Boolean

**Accessibility:** Read Only

Shows if current site is corporate catalog. Defaults to false.

### **3.2.5.278.1.1.13 LastModified**

**Type:** CSOM String

**Accessibility:** Read Only

The date/time when the app this app tile represented was last changed, if applicable.

### **3.2.5.278.1.1.14 LastModifiedDate**

**Type:** CSOM DateTime

**Accessibility:** Read Only

The date/time when the app represented by this app tile was last changed, if applicable. Defaults to DateTime.MinValue.

### **3.2.5.278.1.1.15 ProductId**

**Type:** CSOM GUID

**Accessibility:** Read Only

The Id of the product associated with the app.

### **3.2.5.278.1.1.16 Target**

**Type:** CSOM String

**Accessibility:** Read Only

The server address of the app this app tile represents.

### **3.2.5.278.1.1.17 Thumbnail**

**Type:** CSOM String

**Accessibility:** Read Only

The server address of the thumbnail for the app tile.

### **3.2.5.278.1.1.18 Title**

**Type:** CSOM String

**Accessibility:** Read Only

The server address of the app this app tile represents.

### **3.2.5.278.1.1.19 Version**

**Type:** CSOM String

**Accessibility:** Read Only

The version of the app. Defaults to empty string.

### **3.2.5.278.1.2ObjectPath Properties**

None.

### **3.2.5.278.2 Methods**

#### **3.2.5.278.2.1Scalar Methods**

None.

#### **3.2.5.278.2.2ObjectPath Methods**

None.

### **3.2.5.279 Microsoft.SharePoint.Client.AppTileCollection**

**TypeId:** {8DD21099-80DB-4719-B12A-555456F8930C}

**ShortName:** SP.AppTileCollection

Represents a collection of app tiles.

#### **3.2.5.279.1 Properties**

##### **3.2.5.279.1.1Scalar Properties**

None.

### **3.2.5.279.1.2ObjectPath Properties**

None.

### **3.2.5.279.2 Methods**

#### **3.2.5.279.2.1Scalar Methods**

None.

#### **3.2.5.279.2.2ObjectPath Methods**

None.

### **3.2.5.280 Microsoft.SharePoint.Client.AppType**

**ShortName:** SP.AppType

**Flag:** false

The type of app tile.

#### **3.2.5.280.1 Field Values**

##### **3.2.5.280.1.1Doclib**

**Value:** 0

Represents information about a document library.

##### **3.2.5.280.1.2List**

**Value:** 1

Represents information about a list.

##### **3.2.5.280.1.3Tenant**

**Value:** 2

Represents information about a tenant-managed app.

##### **3.2.5.280.1.4Instance**

**Value:** 3

Represents information about a web administrator-managed app.

##### **3.2.5.280.1.5Feature**

**Value:** 4

Represents information about a feature that behaves like an app.

##### **3.2.5.280.1.6CommonList**

**Value:** 5

Represents information about a list with a common base template, other than DocLib or GenericList.

### **3.2.5.281 Microsoft.SharePoint.Client.Audit**

**TypeId:** {1307502C-2A94-4C1E-8BA6-30DA4B0391F1}

**ShortName:** SP.Audit

Enables auditing of how site collections, sites, lists, folders, and list items are accessed, changed, and used.

#### **3.2.5.281.1 Properties**

##### **3.2.5.281.1.1 Scalar Properties**

###### **3.2.5.281.1.1.1 AuditFlags**

**Type:** Microsoft.SharePoint.Client.AuditMaskType

**Accessibility:** Read/Write

Gets or sets a value indicating what kinds of events and actions are audited specifically for this object.

##### **3.2.5.281.1.2 ObjectPath Properties**

None.

#### **3.2.5.281.2 Methods**

##### **3.2.5.281.2.1 Scalar Methods**

###### **3.2.5.281.2.1.1 Update**

**Return Type:** None

Updates the SharePoint database with changes to the Microsoft.SharePoint.SPAudit.AuditFlags property.

**Parameters:** None

##### **3.2.5.281.2.2 ObjectPath Methods**

None.

### **3.2.5.282 Microsoft.SharePoint.Client.AuditMaskType**

**ShortName:** SP.AuditMaskType

**Flag:** false

Specifies what kind of actions and events are being audited for a particular site collection, site, list, folder, or list item object.

#### **3.2.5.282.1 Field Values**

##### **3.2.5.282.1.1 None**



**Value:** 0

No events or actions.

### **3.2.5.282.1.2CheckOut**

**Value:** 1

Check out of the object.

### **3.2.5.282.1.3CheckIn**

**Value:** 2

Check in of the object.

### **3.2.5.282.1.4View**

**Value:** 4

Viewing of the object by a user.

### **3.2.5.282.1.5ObjectDelete**

**Value:** 8

Deletion of the object.

### **3.2.5.282.1.6Update**

**Value:** 16

Update of the object.

### **3.2.5.282.1.7ProfileChange**

**Value:** 32

Change of a profile.

### **3.2.5.282.1.8ChildDelete**

**Value:** 64

Deletion of one of the object's child objects.

### **3.2.5.282.1.9SchemaChange**

**Value:** 128

Change of the object's schema.

### **3.2.5.282.1.10 SecurityChange**

**Value:** 256

Change in a security configuration for the object.

### **3.2.5.282.1.11 Undelete**

**Value:** 512

Reversal of the deletion of the object.

### **3.2.5.282.1.12 Workflow**

**Value:** 1024

Use of the object in a workflow task.

### **3.2.5.282.1.13 Copy**

**Value:** 2048

Copying the object.

### **3.2.5.282.1.14 Move**

**Value:** 4096

Move of the object.

### **3.2.5.282.1.15 Search**

**Value:** 8192

Search of the object.

### **3.2.5.282.1.16 All**

**Value:** -1

All types of events and actions.

## **3.2.5.283 Microsoft.SharePoint.Client.CreatableItemInfo**

**TypeId:** {E9797D9D-2304-4C12-BC6B-4A4E9D7A0EA6}

**ShortName:** SP.CreatableItemInfo

Information on a creatable item: what the item is and where to go to create it. Alternatively, the information provided here can be used to call **CreateDocument** (section [3.2.5.79.2.2.9](#)) or **CreateDocumentAndGetEditLink** (section [3.2.5.79.2.1.13](#)).

### **3.2.5.283.1 Properties**

#### **3.2.5.283.1.1 Scalar Properties**

##### **3.2.5.283.1.1.1 DocumentTemplate**

**Type:** **CSOM Int32**

**Accessibility:** Read Only

The enumeration value of this item's type, corresponding to **DocumentTemplateType** (section [3.2.5.288](#)).

##### **3.2.5.283.1.1.2 FileExtension**

**Type:** CSOM String

**Accessibility:** Read Only

The file extension of the item to be created.

### 3.2.5.283.1.1.3 ItemType

**Type:** CSOM String

**Accessibility:** Read Only

The name of the item's type (e.g. Word or PowerPoint).

### 3.2.5.283.1.2ObjectPath Properties

None.

## 3.2.5.284 Microsoft.SharePoint.Client.CreatableItemInfoCollection

**TypeId:** {9B16C27E-29B9-46DB-ACB0-9E36D3AB244A}

**ShortName:** SP.CreatableItemInfoCollection

Represents a collection of **CreatableItemInfo** (section [3.2.5.283](#)) objects.

### 3.2.5.284.1 Properties

#### 3.2.5.284.1.1Scalar Properties

None.

#### 3.2.5.284.1.2ObjectPath Properties

None.

## 3.2.5.285 Microsoft.SharePoint.Client.CreatablesInfo

**TypeId:** {9EC9B742-583B-4A15-B1E8-23C8E0D7B6DF}

**ShortName:** SP.CreatablesInfo

Returns an object that describes what this **list** can create, and a collection of links to visit in order to create those things. If it can't create certain things, it contains an error message describing why.

The consumer MUST append the encoded **URL** of the current page to the links returned here. (This page the link goes to needs it as a query parameter to function correctly.) The consumer SHOULD also consider appending &IsDlg=1 to the link, to remove the UI from the linked page, if desired.

### 3.2.5.285.1 Properties

#### 3.2.5.285.1.1Scalar Properties

##### 3.2.5.285.1.1.1 CanCreateFolders

**Type:** CSOM Boolean

**Accessibility:** Read Only

Indicates if the user is able to create folders in the current list. The user MUST have the appropriate permissions and the list MUST allow folder creation.

### **3.2.5.285.1.1.2 CanCreateItems**

**Type:** CSOM Boolean

**Accessibility:** Read Only

Indicates whether this list can create items (such as documents (Word/Excel/PowerPoint)) using Microsoft Office Online.

### **3.2.5.285.1.1.3 CanUploadFiles**

**Type:** CSOM Boolean

**Accessibility:** Read Only

Indicates whether the user is able to upload files to this list.

### **3.2.5.285.1.1.4 CreatablesCollection**

**Type:** Microsoft.SharePoint.Client.CreatableItemInfoCollection

**Accessibility:** Read Only

Represents a collection of **CreatableItemInfo** (section [3.2.5.283](#)) objects describing what can be created, one **CreatableItemInfo** for each creatable type.

### **3.2.5.285.1.2ObjectPath Properties**

None.

## **3.2.5.285.2 Methods**

### **3.2.5.285.2.1Scalar Methods**

None.

### **3.2.5.285.2.2ObjectPath Methods**

None.

## **3.2.5.286 Microsoft.SharePoint.Client.DlpPolicyTip**

**TypeId:** {4FC085D6-53CB-4668-BC9B-AE1E54209812}

**ShortName:** SP.DlpPolicyTip

Provides information about the Data Loss Protection policy on an item so it can be shown to the user.

### **3.2.5.286.1 Properties**

#### **3.2.5.286.1.1Scalar Properties**

##### **3.2.5.286.1.1.1 AppliedActionsText**

**Type:** CSOM String

**Accessibility:** Read Only

Specifies the text which states what restrictive actions have been applied to this item.

### **3.2.5.286.1.1.2 ComplianceUrl**

**Type:** CSOM String

**Accessibility:** Read Only

Specifies the **URL** that provides additional help on the policy tip dialog.

### **3.2.5.286.1.1.3 GeneralText**

**Type:** CSOM String

**Accessibility:** Read Only

General text that appears on the top of the policy tip dialog.

### **3.2.5.286.1.1.4 LastProcessedTime**

**Type:** CSOM DateTime

**Accessibility:** Read Only

The last time this item was processed for policy matches.

### **3.2.5.286.1.1.5 MatchedConditionDescriptions**

**Type:** CSOM array of CSOM String

**Accessibility:** Read Only

An array that contains a description of each policy condition that has been matched.

### **3.2.5.286.1.1.6 OverrideOptions**

**Type:** Microsoft.SharePoint.Client.RuleOverrideOptions

**Accessibility:** Read Only

The allowable options that someone can take to override policy matches.

### **3.2.5.286.1.1.7 TwoLetterISOLanguageName**

**Type:** CSOM String

**Accessibility:** Read Only

The two-letter language code of the generated policy tip detail.

## **3.2.5.286.1.2 ObjectPath Properties**

None.

## **3.2.5.286.2 Methods**

### **3.2.5.286.2.1 Scalar Methods**

None.

### 3.2.5.286.2.2ObjectPath Methods

None.

### 3.2.5.287 Microsoft.SharePoint.Client.DocumentLibraryInformation

**TypeId:** {FB3DDD20-725D-4C42-8C72-34C5EFC2A0B4}

**ShortName:** SP.DocumentLibraryInformation

Specifies the information for a **document library** on a **site (2)**.

#### 3.2.5.287.1 Properties

##### 3.2.5.287.1.1Scalar Properties

###### 3.2.5.287.1.1.1 AbsoluteUrl

**Type:** CSOM String

**Accessibility:** Read Only

Absolute Url of the document library.

###### 3.2.5.287.1.1.2 Modified

**Type:** CSOM DateTime

**Accessibility:** Read Only

Identifies the modified date of the **document library**.

###### 3.2.5.287.1.1.3 ModifiedFriendlyDisplay

**Type:** CSOM String

**Accessibility:** Read Only

Identifies a friendly display for the modified date of the **document library**.

###### 3.2.5.287.1.1.4 ServerRelativeUrl

**Type:** CSOM String

**Accessibility:** Read Only

Identifies the **server-relative URL** of the **document library**.

###### 3.2.5.287.1.1.5 Title

**Type:** CSOM String

**Accessibility:** Read Only

Identifies the title of the **document library**.

##### 3.2.5.287.1.2ObjectPath Properties

None.

### **3.2.5.288 Microsoft.SharePoint.Client.DocumentTemplateType**

**ShortName:** SP.DocumentTemplateType

**Flag:** false

Specifies the type for the **document template (1)** for the new **list**.

#### **3.2.5.288.1 Field Values**

##### **3.2.5.288.1.1 Invalid**

**Value:** 0

Invalid **document template (1)**.

##### **3.2.5.288.1.2 Word**

**Value:** 1

Word template.

##### **3.2.5.288.1.3 Excel**

**Value:** 2

Excel template.

##### **3.2.5.288.1.4 PowerPoint**

**Value:** 3

PowerPoint template.

##### **3.2.5.288.1.5 OneNote**

**Value:** 4

OneNote template.

##### **3.2.5.288.1.6 ExcelForm**

**Value:** 5

Excel-based form template.

##### **3.2.5.288.1.7 Max**

**Value:** 9

Maximum value to indicate a **document template (1)**.

##### **3.2.5.288.1.8 Visio**

**Value:** 8

Visio template.

### 3.2.5.289 Microsoft.SharePoint.Client.EffectiveInformationRightsManagementSettings

**TypeId:** {7763BD9A-B98E-491D-82A8-252CBF76C64E}

**ShortName:** SP.EffectiveInformationRightsManagementSettings

A collection of effective **IRM** settings on the file.

#### 3.2.5.289.1 Properties

##### 3.2.5.289.1.1 Scalar Properties

###### 3.2.5.289.1.1.1 AllowPrint

**Type:** CSOM Boolean

**Accessibility:** Read Only

Specifies whether a user can print the downloaded **document**.

###### 3.2.5.289.1.1.2 AllowScript

**Type:** CSOM Boolean

**Accessibility:** Read Only

Specifies whether a user can run a script on the downloaded **document**.

###### 3.2.5.289.1.1.3 AllowWriteCopy

**Type:** CSOM Boolean

**Accessibility:** Read Only

Specifies whether a user can write on a copy of the downloaded **document**.

###### 3.2.5.289.1.1.4 DisableDocumentBrowserView

**Type:** CSOM Boolean

**Accessibility:** Read Only

Specifies whether to block the **Office Add-in** from showing this **document**.

###### 3.2.5.289.1.1.5 DocumentAccessExpireDays

**Type:** CSOM Int32

**Accessibility:** Read Only

Specifies the number of days after which the downloaded **document** will expire.

###### 3.2.5.289.1.1.6 DocumentLibraryProtectionExpireDate

**Type:** CSOM DateTime

**Accessibility:** Read Only



Specifies the date on which the **Information Rights Management (IRM)** protection of this **document library** will stop.

#### **3.2.5.289.1.1.7 EnableDocumentAccessExpire**

**Type:** CSOM Boolean

**Accessibility:** Read Only

Specifies whether the downloaded **document** will expire.

#### **3.2.5.289.1.1.8 EnableDocumentBrowserPublishingView**

**Type:** CSOM Boolean

**Accessibility:** Read Only

Specifies whether publishing view is enabled in the **Office Add-in**.

#### **3.2.5.289.1.1.9 EnableGroupProtection**

**Type:** CSOM Boolean

**Accessibility:** Read Only

Specifies whether the permission of the downloaded **document** is applicable to a **group**.

#### **3.2.5.289.1.1.10 EnableLicenseCacheExpire**

**Type:** CSOM Boolean

**Accessibility:** Read Only

Specifies whether a user MUST verify his or her credentials after certain intervals.

#### **3.2.5.289.1.1.11 GroupName**

**Type:** CSOM String

**Accessibility:** Read Only

Specifies the **group** name (email address) that the permission is also applicable to.

#### **3.2.5.289.1.1.12 IrmEnabled**

**Type:** CSOM Boolean

**Accessibility:** Read Only

Specifies whether the **Information Rights Management (IRM)** is enabled.

#### **3.2.5.289.1.1.13 LicenseCacheExpireDays**

**Type:** CSOM Int32

**Accessibility:** Read Only

Specifies the number of days that the **Information Rights Management (IRM)** license can be cached by the application to open the downloaded document. When these elapse, the application will connect to the **IRM** server to validate the license.

### **3.2.5.289.1.1.14 PolicyDescription**

**Type:** CSOM String

**Accessibility:** Read Only

Specifies the permission **policy** description.

### **3.2.5.289.1.1.15 PolicyTitle**

**Type:** CSOM String

**Accessibility:** Read Only

Specifies the permission **policy** title.

### **3.2.5.289.1.1.16 SettingSource**

**Type:** Microsoft.SharePoint.Client.SPEffectiveInformationRightsManagementSettingsSource

**Accessibility:** Read Only

Specifies the source of the effective settings.

### **3.2.5.289.1.1.17 TemplateId**

**Type:** CSOM String

**Accessibility:** Read Only

Gets the template ID of the RMS template that will be applied to the file/library.

## **3.2.5.289.1.2 ObjectPath Properties**

None.

## **3.2.5.289.2 Methods**

### **3.2.5.289.2.1 Scalar Methods**

None.

### **3.2.5.289.2.2 ObjectPath Methods**

None.

## **3.2.5.290 Microsoft.SharePoint.Client.FolderEntityData**

**TypeId:** {0FFBD1DB-E28A-42AA-A6BA-CCF4F2626A6B}

**ShortName:** SP.FolderEntityData

Specifies the entity data for a **list folder**.

### **3.2.5.290.1 Properties**

#### **3.2.5.290.1.1 Scalar Properties**

### **3.2.5.290.1.1.1 Overwrite**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Specifies whether the **list folder** is overwritten.

It MUST NOT be NULL.

### **3.2.5.290.1.1.2 ServerRelativeUrl**

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies the **server-relative URL** of the **list folder**.

It MUST NOT be NULL.

### **3.2.5.290.1.2 ObjectPath Properties**

None.

## **3.2.5.291 Microsoft.SharePoint.Client.InformationRightsManagementFileSettings**

**TypeId:** {F920FBE4-9C61-4E05-BB11-702126533CB4}

**ShortName:** SP.InformationRightsManagementFileSettings

Represents the **Information Rights Management (IRM)** settings of a file.

### **3.2.5.291.1 Properties**

#### **3.2.5.291.1.1 Scalar Properties**

##### **3.2.5.291.1.1.1 AllowPrint**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Gets or sets a value indicating whether or not the user can print the downloaded document.

True if print is allowed; otherwise, it is false. The default value is false.

##### **3.2.5.291.1.1.2 AllowScript**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Gets or sets a value indicating whether or not the user can run a script on the downloaded document.

True if the script is allowed to run; otherwise, it is false. The default value is false.

##### **3.2.5.291.1.1.3 AllowWriteCopy**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Gets or sets a value indicating whether or not the user can write on a copy of the downloaded document.

True if write on a copy is allowed; otherwise, it is false. The default value is false.

#### **3.2.5.291.1.1.4      DisableDocumentBrowserView**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Gets or sets a value indicating whether or not to block Web Application Companion applications (WACs) from showing this document.

True if the WAC is blocked; otherwise, it is false. The default value is false.

#### **3.2.5.291.1.1.5      DocumentAccessExpireDays**

**Type:** CSOM Int32

**Accessibility:** Read/Write

Gets or sets the number of days after which the downloaded document will expire.

Specifies the document access expire days between 1 and 365 if **IRM** and document access expire are both enabled; otherwise, it returns the default value.

#### **3.2.5.291.1.1.6      EnableDocumentAccessExpire**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Gets or sets a value indicating whether or not the downloaded document will expire.

True if the downloaded document will expire; otherwise, it is false. The default value is false.

#### **3.2.5.291.1.1.7      EnableDocumentBrowserPublishingView**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Gets or sets a value indicating whether or not to enable Web Application Companion applications (WACs) to publishing view.

True if the WAC publishing view is enabled; otherwise, it is false. The default value is false.

#### **3.2.5.291.1.1.8      EnableGroupProtection**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Gets or sets a value indicating whether or not the permission of the downloaded document is applicable to a group.

True if the group protection is enabled; otherwise, it is false. The default value is false.

### **3.2.5.291.1.1.9 EnableLicenseCacheExpire**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Gets or sets a value indicating whether or not users verify their credentials after some intervals. True if the license cache expire is enabled; otherwise, it is false. The default value is false.

### **3.2.5.291.1.1.10 GroupName**

**Type:** CSOM String

**Accessibility:** Read/Write

Gets or sets the group name (email address) that the permission is also applicable to.

### **3.2.5.291.1.1.11 IrmEnabled**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Indicates whether the Information Rights Management is enabled or not.

### **3.2.5.291.1.1.12 LicenseCacheExpireDays**

**Type:** CSOM Int32

**Accessibility:** Read/Write

Gets or sets the number of days that the application that opens the document caches the IRM license. When these elapse, the application will connect to the IRM server to validate the license.

### **3.2.5.291.1.1.13 PolicyDescription**

**Type:** CSOM String

**Accessibility:** Read/Write

Gets or sets the permission policy description.

### **3.2.5.291.1.1.14 PolicyTitle**

**Type:** CSOM String

**Accessibility:** Read/Write

Gets or sets the permission policy title.

### **3.2.5.291.1.1.15 TemplateId**

**Type:** CSOM String

**Accessibility:** Read/Write

Gets or sets the ID of the RMS template that will be applied to the file or library.

### **3.2.5.291.1.2ObjectPath Properties**

None.

### **3.2.5.291.2 Methods**

#### **3.2.5.291.2.1 Scalar Methods**

##### **3.2.5.291.2.1.1 Reset**

**Return Type:** None

Resets all properties to the default value.

**Parameters:** None

##### **3.2.5.291.2.1.2 Update**

**Return Type:** None

Updates the document library with the changes made to the settings.

**Parameters:** None

#### **3.2.5.291.2.2 ObjectPath Methods**

None.

### **3.2.5.292 Microsoft.SharePoint.Client.IngestionTaskKey**

**TypeId:** {3314041B-E208-4492-A0E9-A275FA3F6204}

**ShortName:** SP.IngestionTaskKey

Specifies key data for accessing an Azure Blob storage account and a status publishing account.

#### **3.2.5.292.1 Properties**

##### **3.2.5.292.1.1 Scalar Properties**

###### **3.2.5.292.1.1.1 IngestionTableAccountKey**

**Type:** CSOM String

**Accessibility:** Read/Write

Gets or sets the ingestion table account key.

###### **3.2.5.292.1.1.2 IngestionTableAccountName**

**Type:** CSOM String

**Accessibility:** Read/Write

Gets or sets the ingestion table account name.

###### **3.2.5.292.1.1.3 JobId**

**Type:** CSOM String

**Accessibility:** Read/Write

Gets or sets the job Id.

### **3.2.5.292.1.1.4 TaskId**

**Type:** CSOM String

**Accessibility:** Read/Write

Gets or sets the task Id.

### **3.2.5.292.1.1.5 TenantName**

**Type:** CSOM String

**Accessibility:** Read/Write

Gets or sets the tenant name.

### **3.2.5.292.1.2ObjectPath Properties**

None.

## **3.2.5.293 Microsoft.SharePoint.Client.MigrationJobState**

**ShortName:** SP.MigrationJobState

**Flag:** false

Enumeration containing possible migration job status values. It is used as a return type for the **GetMigrationJobStatus** (section [3.2.5.119.2.1.6](#)) method. Note that there is currently no way to query the job status if it has already succeeded or failed and been removed from the queue, in which case a value of None (0) is returned, so the easiest way to determine the results of the migration job in that case is to look at the log output.

### **3.2.5.293.1 Field Values**

#### **3.2.5.293.1.1None**

**Value:** 0

The migration job is no longer in the queue.

#### **3.2.5.293.1.2Queued**

**Value:** 2

The migration job is in the queue.

#### **3.2.5.293.1.3Processing**

**Value:** 4

The migration job is being processed.

### 3.2.5.294 Microsoft.SharePoint.Client.MountedFolderInfo

**TypeId:** {5F2BBB09-0544-46D4-B398-33BD3962D5BF}

**ShortName:** SP.MountedFolderInfo

Provides read-only properties that describe a mounted folder.

#### 3.2.5.294.1 Properties

##### 3.2.5.294.1.1 Scalar Properties

###### 3.2.5.294.1.1.1 FolderUrl

**Type:** CSOM String

**Accessibility:** Read Only

Gets the URL of the mounted folder.

###### 3.2.5.294.1.1.2 HasEditPermission

**Type:** CSOM Boolean

**Accessibility:** Read Only

Specifies whether the current user has edit permission to the mounted folder.

###### 3.2.5.294.1.1.3 ItemId

**Type:** CSOM Int32

**Accessibility:** Read Only

Gets the identifier of the mounted folder.

###### 3.2.5.294.1.1.4 ListTemplateType

**Type:** Microsoft.SharePoint.Client.ListTemplateType

**Accessibility:** Read Only

Gets the template type of the list that contains the mounted folder.

###### 3.2.5.294.1.1.5 ListViewUrl

**Type:** CSOM String

**Accessibility:** Read Only

Gets the view URL of the list that contains the mounted folder.

###### 3.2.5.294.1.1.6 WebUrl

**Type:** CSOM String

**Accessibility:** Read Only

Gets the URL of the web that the mounted folder is in.



### 3.2.5.294.1.2 ObjectPath Properties

None.

### 3.2.5.294.2 Methods

#### 3.2.5.294.2.1 Scalar Methods

None.

#### 3.2.5.294.2.2 ObjectPath Methods

None.

### 3.2.5.295 Microsoft.SharePoint.Client.MountPoint

**TypeId:** {0489CFAD-CCD4-422D-9014-BE0F150E4389}

**ShortName:** SP.MountPoint

Provides client-callable methods for **mount point** operations.

#### 3.2.5.295.1 Properties

##### 3.2.5.295.1.1 Scalar Properties

None.

##### 3.2.5.295.1.2 ObjectPath Properties

None.

#### 3.2.5.295.2 Methods

##### 3.2.5.295.2.1 Scalar Methods

###### 3.2.5.295.2.1.1 CreateMountPoint

This method is a **static CSOM method**.

**Return Type:** None

Creates a new **mount point**.

**Parameters:**

*folder:* The folder that will contain the new mount point.

Type: Microsoft.SharePoint.Client.Folder

If the *folder* parameter is null, the mount point will be created in the current user's Microsoft OneDrive root folder. Currently, only folders can be **mounted**.

*name:* The display name of the new mount point.

Type: **CSOM String**

*targetSiteId:* The site collection identifier of the item to be mounted.

Type: **CSOM GUID**

*targetWebId*: The web identifier of the item to be mounted.

Type: CSOM GUID

*targetUniqueId*: The unique identifier of the item to be mounted.

Type: CSOM GUID

### **3.2.5.295.2.1.2 GetMountedFolderUrls**

This method is a **static CSOM method**.

**Return Type:** **CSOM array** of **CSOM String**

Gets an enumerable collection of **mounted** folder URLs of the **mount points** in a list.

**Parameters:**

*list*: List that contains the mount points.

Type: Microsoft.SharePoint.Client.List

### **3.2.5.295.2.2 ObjectPath Methods**

#### **3.2.5.295.2.2.1 GetMountedFolderInfo**

This method is a **static CSOM method**.

**Return Type:** Microsoft.SharePoint.Client.MountedFolderInfo

Gets information about a **mounted folder**.

**Parameters:**

*targetSiteId*: The site collection identifier of the folder to be **mounted**.

Type: **CSOM GUID**

*targetWebId*: The web identifier of the folder to be mounted.

Type: CSOM GUID

*targetUniqueId*: The unique identifier of the folder to be mounted.

Type: CSOM GUID

### **3.2.5.296 Microsoft.SharePoint.Client.MountPointInfo**

**TypeId:** {30BC42FC-5AEB-4221-9BF1-6181619B9AA0}

**ShortName:** SP.MountPointInfo

Provides read-only properties that describe a **mount point**.

#### **3.2.5.296.1 Properties**

##### **3.2.5.296.1.1 Scalar Properties**

### 3.2.5.296.1.1.1 Name

Type: **CSOM String**

Accessibility: Read Only

Gets the name of the **mount point**.

### 3.2.5.296.1.1.2 RedirectUrl

Type: **CSOM String**

Accessibility: Read Only

Gets the URL that will redirect to the target **mounted folder**.

### 3.2.5.296.1.2ObjectPath Properties

None.

### 3.2.5.296.2 Methods

#### 3.2.5.296.2.1Scalar Methods

None.

#### 3.2.5.296.2.2ObjectPath Methods

None.

### 3.2.5.297 Microsoft.SharePoint.Client.MoveCopyUtil

**TypeId:** {C668C5CA-BBDD-435F-8008-502F3180CF20}

**ShortName:** SP.MoveCopyUtil

A container class for static move/copy methods.

#### 3.2.5.297.1 Properties

##### 3.2.5.297.1.1Scalar Properties

None.

##### 3.2.5.297.1.2ObjectPath Properties

None.

#### 3.2.5.297.2 Methods

##### 3.2.5.297.2.1Scalar Methods

###### 3.2.5.297.2.1.1 CopyFile

This method is a **static CSOM method**.

**Return Type:** None

Copies a file from the source location to the destination location.

**Parameters:**

*srcUrl*: A full URL that specifies the source file.

Type: **CSOM String**

It MUST NOT be NULL. It MUST be a URL of absolute form.

*destUrl*: A full URL that specifies the destination file.

Type: CSOM String

It MUST NOT be NULL. It MUST be a URL of absolute form.

*overwrite*: Overwrites the destination file when it exists.

Type: **CSOM Boolean**

*options*: Contains options used to modify the behavior.

Type: Microsoft.SharePoint.Client.MoveCopyOptions

**Exceptions:**

Error Code	Error Type Name	Condition
-1	Microsoft.SharePoint.SPFileCheckOutException	The srcFile cannot be checked out.
-1	Microsoft.SharePoint.SPFileLockException	The srcFile cannot be locked.
- 2147467261	System.ArgumentNullException	1) srcUrl MUST NOT be null or empty.2) destUrl MUST NOT be null or empty.
- 2146233086	System.ArgumentOutOfRangeException	The srcUrl is not contained in a site.
-1	System.InvalidOperationException	srcUrl and destUrl MUST NOT be the same.
- 2147024894	System.IO.FileNotFoundException	The file at the srcUrl MUST exist.
-1	System.IO.IOException	The file at the destUrl MUST NOT exist.

**3.2.5.297.2.1.2 CopyFileByPath**

This method is a **static CSOM method**.

**Return Type:** None

Copies a file from the source location to the destination location

**Parameters:**

*srcPath*: A full URL that specifies the source file.

Type: Microsoft.SharePoint.Client.ResourcePath

It MUST NOT be NULL.

*destPath*: A full URL that specifies the destination file.

Type: Microsoft.SharePoint.Client.ResourcePath

It MUST NOT be NULL.

*overwrite*: Overwrites the destination file when it exists.

Type: **CSOM Boolean**

*options*: Contains options used to modify the behavior.

Type: Microsoft.SharePoint.Client.MoveCopyOptions

**Exceptions:**

Error Code	Error Type Name	Condition
-1	Microsoft.SharePoint.SPFileCheckOutException	The srcFile can not be checked out.
-1	Microsoft.SharePoint.SPFileLockException	The srcFile can not be locked.
- 2147467261	System.ArgumentNullException	1) srcPath MUST NOT be null or empty.2) destPath MUST NOT be null or empty.
- 2146233086	System.ArgumentOutOfRangeException	The srcPath is not contained in a site.
-1	System.InvalidOperationException	srcUrl and destPath MUST NOT be the same.
- 2147024894	System.IO.FileNotFoundException	The file at the srcPath MUST exist.
-1	System.IO.IOException	The file at the destPath MUST NOT exist.

**3.2.5.297.2.1.3 CopyFolder**

This method is a **static CSOM method**.

**Return Type:** None

Copies a folder from a source URL to a destination URL.

**Parameters:**

*srcUrl*: A full URL that represents the source folder.

Type: **CSOM String**

It MUST NOT be NULL. It MUST be a URL of absolute form.

*destUrl*: A full URL that represents the destination folder.

Type: CSOM String

It MUST NOT be NULL. It MUST be a URL of absolute form.

*options*: Contains options used to modify the behavior.

Type: Microsoft.SharePoint.Client.MoveCopyOptions

## Exceptions:

Error Code	Error Type Name	Condition
-1	Microsoft.SharePoint.SPFileCheckOutException	The srcFile cannot be checked out.
-1	Microsoft.SharePoint.SPFileLockException	The srcFile cannot be locked.
- 2147467261	System.ArgumentNullException	1) srcUrl MUST NOT be null or empty.2) destUrl MUST NOT be null or empty.
- 2146233086	System.ArgumentOutOfRangeException	The srcUrl is not contained in a site.
-1	System.InvalidOperationException	srcUrl and destUrl MUST NOT be the same.
- 2147024894	System.IO.FileNotFoundException	The file at the srcUrl MUST exist.
-1	System.IO.IOException	The file at the destUrl MUST NOT exist.

### 3.2.5.297.2.1.4 CopyFolderByPath

This method is a **static CSOM method**.

**Return Type:** None

Copies a folder from a source URL to a destination URL.

#### Parameters:

*srcPath*: A full URL path that represents the source folder.

Type: Microsoft.SharePoint.Client.ResourcePath

It MUST NOT be NULL.

*destPath*: A full URL path that represents the destination folder.

Type: Microsoft.SharePoint.Client.ResourcePath

It MUST NOT be NULL.

*options*: Contains options used to modify the behavior.

Type: Microsoft.SharePoint.Client.MoveCopyOptions

#### Exceptions:

Error Code	Error Type Name	Condition
-1	Microsoft.SharePoint.SPFileCheckOutException	The srcFile can not be checked out.
-1	Microsoft.SharePoint.SPFileLockException	The srcFile can not be locked.
- 2147467261	System.ArgumentNullException	1) srcPath MUST NOT be null or empty.2) destPath MUST NOT be null or empty.
- 2146233086	System.ArgumentOutOfRangeException	The srcPath is not contained in a site.

Error Code	Error Type Name	Condition
-1	System.InvalidOperationException	srcUrl and destPath MUST NOT be the same.
-2147024894	System.IO.FileNotFoundException	The file at the srcPath MUST exist.
-1	System.IO.IOException	The file at the destPath MUST NOT exist.

### 3.2.5.297.2.1.5 MoveFile

This method is a **static CSOM method**.

**Return Type:** None

Moves a file from the source location to the destination location.

#### Parameters:

*srcUrl*: A full URL that specifies the source file.

Type: **CSOM String**

It MUST NOT be NULL. It MUST be a URL of absolute form.

*destUrl*: A full URL that specifies the destination file.

Type: CSOM String

It MUST NOT be NULL. It MUST be a URL of absolute form.

*overwrite*: Overwrites the destination file when it exists.

Type: **CSOM Boolean**

*options*: Contains options used to modify the behavior.

Type: Microsoft.SharePoint.Client.MoveCopyOptions

#### Exceptions:

Error Code	Error Type Name	Condition
-1	Microsoft.SharePoint.SPFileCheckOutException	The srcFile cannot be checked out.
-1	Microsoft.SharePoint.SPFileLockException	The srcFile cannot be locked.
-2147467261	System.ArgumentNullException	1) srcUrl MUST NOT be null or empty.2) destUrl MUST NOT be null or empty.
-2146233086	System.ArgumentOutOfRangeException	The srcUrl is not contained in a site.
-1	System.InvalidOperationException	srcUrl and destUrl MUST NOT be the same.
-2147024894	System.IO.FileNotFoundException	The file at the srcUrl MUST exist.
-1	System.IO.IOException	The file at the destUrl MUST NOT exist.

### 3.2.5.297.2.1.6 MoveFileByPath

This method is a **static CSOM method**.

**Return Type:** None

Moves a file from the source location to the destination location.

**Parameters:**

*srcPath*: A full URL path that specifies the source file.

Type: Microsoft.SharePoint.Client.ResourcePath

It MUST NOT be NULL.

*destPath*: A full URL path that specifies the destination file.

Type: Microsoft.SharePoint.Client.ResourcePath

It MUST NOT be NULL.

*overwrite*: A Boolean value that specify whether to overwrite the destination file when it exists.

Type: **CSOM Boolean**

*options*: Contains options used to modify the behavior.

Type: Microsoft.SharePoint.Client.MoveCopyOptions

**Exceptions:**

Error Code	Error Type Name	Condition
-1	Microsoft.SharePoint.SPFileCheckOutException	The srcFile can not be checked out.
-1	Microsoft.SharePoint.SPFileLockException	The srcFile can not be locked.
- 2147467261	System.ArgumentNullException	1) srcPath MUST NOT be null or empty.2) destPath MUST NOT be null or empty.
- 2146233086	System.ArgumentOutOfRangeException	The srcPath is not contained in a site.
-1	System.InvalidOperationException	srcUrl and destPath MUST NOT be the same.
- 2147024894	System.IO.FileNotFoundException	The file at the srcPath MUST exist.
-1	System.IO.IOException	The file at the destPath MUST NOT exist.

### 3.2.5.297.2.1.7 MoveFolder

This method is a **static CSOM method**.

**Return Type:** None

Moves a folder from a source URL to a destination URL.



**Parameters:**

*srcUrl*: A full URL that represents the source folder.

Type: **CSOM String**

It MUST NOT be NULL. It MUST be a URL of absolute form.

*destUrl*: A full URL that represents the destination folder.

Type: CSOM String

It MUST NOT be NULL. It MUST be a URL of absolute form.

*options*: Contains options used to modify the behavior.

Type: Microsoft.SharePoint.Client.MoveCopyOptions

**Exceptions:**

Error Code	Error Type Name	Condition
-1	Microsoft.SharePoint.SPFileCheckOutException	The srcFile cannot be checked out.
-1	Microsoft.SharePoint.SPFileLockException	The srcFile cannot be locked.
- 2147467261	System.ArgumentNullException	1) srcUrl MUST NOT be null or empty.2) destUrl MUST NOT be null or empty.
- 2146233086	System.ArgumentOutOfRangeException	The srcUrl is not contained in a site.
-1	System.InvalidOperationException	srcUrl and destUrl MUST NOT be the same.
- 2147024894	System.IO.FileNotFoundException	The file at the srcUrl MUST exist.
-1	System.IO.IOException	The file at the destUrl MUST NOT exist.

**3.2.5.297.2.1.8 MoveFolderByPath**

This method is a **static CSOM method**.

**Return Type:** None

Moves a folder from a source URL to a destination URL.

**Parameters:**

*srcPath*: A full URL path that represents the source folder.

Type: Microsoft.SharePoint.Client.ResourcePath

It MUST NOT be NULL.

*destPath*: A full URL path that represents the destination folder.

Type: Microsoft.SharePoint.Client.ResourcePath

It MUST NOT be NULL.

*options*: Contains options used to modify the behavior.

Type: Microsoft.SharePoint.Client.MoveCopyOptions

**Exceptions:**

Error Code	Error Type Name	Condition
-1	Microsoft.SharePoint.SPFileCheckOutException	The srcFile can not be checked out.
-1	Microsoft.SharePoint.SPFileLockException	The srcFile can not be locked.
- 2147467261	System.ArgumentNullException	1) srcPath MUST NOT be null or empty.2) destPath MUST NOT be null or empty.
- 2146233086	System.ArgumentOutOfRangeException	The srcPath is not contained in a site.
-1	System.InvalidOperationException	srcUrl and destPath MUST NOT be the same.
- 2147024894	System.IO.FileNotFoundException	The file at the srcPath MUST exist.
-1	System.IO.IOException	The file at the destPath MUST NOT exist.

**3.2.5.297.2.2ObjectPath Methods**

None.

**3.2.5.298 Microsoft.SharePoint.Client.OAuth.NativeClient**

**TypeId:** {5B5B3A87-6976-4485-96A7-55A324AF6CE0}

**ShortName:** SP.OAuth.NativeClient

Gets endpoints for native client authentication relative to current request.

**3.2.5.298.1 Properties**

**3.2.5.298.1.1Scalar Properties**

None.

**3.2.5.298.1.2ObjectPath Properties**

None.

**3.2.5.298.2 Methods**

**3.2.5.298.2.1Scalar Methods**

**3.2.5.298.2.1.1 Authenticate**

**Return Type:** None

Authentication module to handle MicrosoftOnlineCredentials.

**Parameters:** None

### 3.2.5.298.2.2 ObjectPath Methods

#### 3.2.5.298.2.2.1 CSOM Constructor

Creates an instance of type **NativeClient** (section [3.2.5.298](#)).

**Parameters:** None

### 3.2.5.299 Microsoft.SharePoint.Client.ObjectSharingInformationUserCollection

**TypeId:** {1ECA4555-5715-4122-9C3D-0AB651518BC1}

**ShortName:** SP.ObjectSharingInformationUserCollection

This class contains a collection of shared with users.

#### 3.2.5.299.1 Properties

##### 3.2.5.299.1.1 Scalar Properties

None.

##### 3.2.5.299.1.2 ObjectPath Properties

None.

#### 3.2.5.299.2 Methods

##### 3.2.5.299.2.1 Scalar Methods

None.

##### 3.2.5.299.2.2 ObjectPath Methods

None.

### 3.2.5.300 Microsoft.SharePoint.Client.ObjectSharingSettings

**TypeId:** {9CA08AFE-29FA-4FAF-86AF-5BCB06E41969}

**ShortName:** SP.ObjectSharingSettings

This class contains the information necessary to read and change the sharing status of a SharePoint object. It also contains a reference to SharePoint specific settings denoted by "SharePointSettings".

#### 3.2.5.300.1 Properties

##### 3.2.5.300.1.1 Scalar Properties

##### 3.2.5.300.1.1.1 AccessRequestMode

**Type:** CSOM Boolean

**Accessibility:** Read Only

**Boolean** indicating whether the sharing context operates under the access request mode.

#### **3.2.5.300.1.1.2 BlockPeoplePickerAndSharing**

**Type:** CSOM Boolean

**Accessibility:** Read Only

Boolean indicating whether the current user can use the People Picker to do any sharing.

#### **3.2.5.300.1.1.3 CanCurrentUserManageOrganizationReadOnlyLink**

**Type:** CSOM Boolean

**Accessibility:** Read Only

**Boolean** indicating whether the current user can create or disable an organization View link.

#### **3.2.5.300.1.1.4 CanCurrentUserManageOrganizationReadWriteLink**

**Type:** CSOM Boolean

**Accessibility:** Read Only

**Boolean** indicating whether the current user can create or disable an organization Edit link.

#### **3.2.5.300.1.1.5 CanCurrentUserManageReadOnlyLink**

**Type:** CSOM Boolean

**Accessibility:** Read Only

**Boolean** indicating whether the current user can create or disable an anonymous View link.

#### **3.2.5.300.1.1.6 CanCurrentUserManageReadWriteLink**

**Type:** CSOM Boolean

**Accessibility:** Read Only

**Boolean** indicating whether the current user can create or disable an anonymous Edit link.

#### **3.2.5.300.1.1.7 CanCurrentUserRetrieveOrganizationReadOnlyLink**

**Type:** CSOM Boolean

**Accessibility:** Read Only

**Boolean** indicating whether the current user can retrieve an organization View link, if one has already been created.

If one has not been created, the user cannot create one

#### **3.2.5.300.1.1.8 CanCurrentUserRetrieveOrganizationReadWriteLink**

**Type:** CSOM Boolean

**Accessibility:** Read Only

**Boolean** indicating whether the current user can retrieve an organization Edit link, if one has already been created.

If one has not been created, the user cannot create one.

### **3.2.5.300.1.1.9 CanCurrentUserRetrieveReadOnlyLink**

**Type: CSOM Boolean**

**Accessibility:** Read Only

**Boolean** indicating whether the current user can retrieve an anonymous View link, if one has already been created.

If one has not been created, the user cannot create one.

### **3.2.5.300.1.1.10 CanCurrentUserRetrieveReadWriteLink**

**Type: CSOM Boolean**

**Accessibility:** Read Only

**Boolean** indicating whether the current user can retrieve an anonymous Edit link, if one has already been created.

If one has not been created, the user cannot create one.

### **3.2.5.300.1.1.11 CanCurrentUserShareExternally**

**Type: CSOM Boolean**

**Accessibility:** Read Only

**Boolean** indicating whether the current user can share outside the tenancy, by inviting external users.

### **3.2.5.300.1.1.12 CanCurrentUserShareInternally**

**Type: CSOM Boolean**

**Accessibility:** Read Only

**Boolean** indicating whether the current user can only share within the tenancy

### **3.2.5.300.1.1.13 CanSendEmail**

**Type: CSOM Boolean**

**Accessibility:** Read Only

**Boolean** indicating whether email invitations can be sent.

### **3.2.5.300.1.1.14 CanSendLink**

**Type: CSOM Boolean**

**Accessibility:** Read Only

**Boolean** indicating whether the current user can make use of Share-By-Link.

### 3.2.5.300.1.1.15 CanShareFolder

**Type:** CSOM Boolean

**Accessibility:** Read Only

Boolean indicating whether the folder object can be shared.

### 3.2.5.300.1.1.16 DefaultShareLinkPermission

**Type:** Microsoft.SharePoint.Client.Sharing.Role

**Accessibility:** Read Only

Default **tokenized sharing link** permission returned as Role.

### 3.2.5.300.1.1.17 DefaultShareLinkType

**Type:** Microsoft.SharePoint.Client.SharingLinkKind

**Accessibility:** Read Only

Default **tokenized sharing link** type returned as SharingLinkKind.

### 3.2.5.300.1.1.18 GroupsList

**Type:** CSOM dictionary

**Accessibility:** Read Only

A **dictionary** object that lists the display name and the id of the SharePoint groups.

### 3.2.5.300.1.1.19 HasEditRole

**Type:** CSOM Boolean

**Accessibility:** Read Only

Boolean that indicates whether or not the site has the standard "**Editor**" role.

### 3.2.5.300.1.1.20 HasReadRole

**Type:** CSOM Boolean

**Accessibility:** Read Only

Boolean that indicates whether or not the site has the standard "Reader" role.

### 3.2.5.300.1.1.21 InheritingWebLink

**Type:** CSOM String

**Accessibility:** Read Only

The **URL** of the site from which the shared object inherits **permissions**.

### 3.2.5.300.1.1.22 IsGuestUser

**Type:** CSOM Boolean

**Accessibility:** Read Only

Boolean that indicates whether or not the current user is a guest user.

### **3.2.5.300.1.1.23 IsPictureLibrary**

**Type:** CSOM Boolean

**Accessibility:** Read Only

Boolean that indicates whether or not the object to share is a **picture library**.

### **3.2.5.300.1.1.24 IsUserSiteAdmin**

**Type:** CSOM Boolean

**Accessibility:** Read Only

Boolean that indicates whether or not the current user is a **site collection administrator**.

### **3.2.5.300.1.1.25 ItemId**

**Type:** CSOM String

**Accessibility:** Read Only

The list item ID (if applicable).

### **3.2.5.300.1.1.26 ItemName**

**Type:** CSOM String

**Accessibility:** Read Only

The object title.

### **3.2.5.300.1.1.27 ItemUrl**

**Type:** CSOM String

**Accessibility:** Read Only

The server relative object **URL**.

### **3.2.5.300.1.1.28 ListId**

**Type:** CSOM GUID

**Accessibility:** Read Only

The unique ID of the **parent list** (if applicable).

### **3.2.5.300.1.1.29 PermissionsOnlyMode**

**Type:** CSOM Boolean

**Accessibility:** Read Only

Boolean that indicates whether or not the sharing context operates under the **permissions** only mode (that is, adding to a group or hiding the groups drop-down in the SharePoint UI).

### **3.2.5.300.1.1.30 RequiredAnonymousLinkExpirationInDays**

**Type:** CSOM Int32

**Accessibility:** Read Only

A value that indicates number of days an anonymous **tokenized sharing link** can be valid before it expires.

### **3.2.5.300.1.1.31 Roles**

**Type:** CSOM dictionary

**Accessibility:** Read Only

A dictionary object that lists the display name and the id of the SharePoint regular roles.

### **3.2.5.300.1.1.32 ShareByEmailEnabled**

**Type:** CSOM Boolean

**Accessibility:** Read Only

Boolean flag denoting if guest users are enabled for the **site collection**.

### **3.2.5.300.1.1.33 ShowExternalSharingWarning**

**Type:** CSOM Boolean

**Accessibility:** Read Only

Boolean that indicates whether or not the client logic SHOULD warn the user that they are about to share with external email addresses.

### **3.2.5.300.1.1.34 SimplifiedRoles**

**Type:** CSOM dictionary

**Accessibility:** Read Only

A **dictionary** object that lists the display name and the id of the SharePoint simplified roles (edit, view).

### **3.2.5.300.1.1.35 SupportsAclPropagation**

**Type:** CSOM Boolean

**Accessibility:** Read Only

Boolean that indicates whether or not the object to share supports **ACL** propagation.

### **3.2.5.300.1.1.36 WebUrl**

**Type:** CSOM String

**Accessibility:** Read Only

The **URL** pointing to the containing SP.Web object.

## **3.2.5.300.1.2ObjectPath Properties**



### **3.2.5.300.1.2.1 ObjectSharingInformation**

**Type:** Microsoft.SharePoint.Client.ObjectSharingInformation

**Accessibility:** Read Only

Contains information about the sharing state of a shareable object.

### **3.2.5.300.1.2.2 SharePointSettings**

**Type:** Microsoft.SharePoint.Client.SharePointSharingSettings

**Accessibility:** Read Only

An object that contains the SharePoint UI specific sharing settings.

### **3.2.5.300.1.2.3 SharingPermissions**

**Type:** Microsoft.SharePoint.Client.SharingPermissionInformationCollection

**Accessibility:** Read Only

A list of SharingPermissionInformation objects that can be used to share.

## **3.2.5.300.2 Methods**

### **3.2.5.300.2.1 Scalar Methods**

None.

### **3.2.5.300.2.2 ObjectPath Methods**

None.

## **3.2.5.301 Microsoft.SharePoint.Client.PickerSettings**

**TypeId:** {8D31357D-328A-45CC-A5AB-B15C9C83EB71}

**ShortName:** SP.PickerSettings

This class contains configuration settings for the client people picker control hosted by the SharePoint sharing UI.

### **3.2.5.301.1 Properties**

#### **3.2.5.301.1.1 Scalar Properties**

##### **3.2.5.301.1.1.1 AllowEmailAddresses**

**Type:** CSOM Boolean

**Accessibility:** Read Only

Boolean value indicating whether the picker control will allow the resolution of arbitrary email addresses.

##### **3.2.5.301.1.1.2 AllowOnlyEmailAddresses**

**Type:** CSOM Boolean

**Accessibility:** Read Only

Boolean value indicating whether the picker control will only allow the resolution of email addresses.

This property is used only when **AllowEmailAddresses** (section [3.2.5.301.1.1.1](#)) is set to True. Otherwise, it is ignored.

### **3.2.5.301.1.1.3 PrincipalAccountType**

**Type:** CSOM String

**Accessibility:** Read Only

The account types that the picker control can query.

### **3.2.5.301.1.1.4 PrincipalSource**

**Type:** Microsoft.SharePoint.Client.Utilities.PrincipalSource

**Accessibility:** Read Only

An enumeration object that specifies the principal source for the people picker control.

### **3.2.5.301.1.1.5 QuerySettings**

**Type:** Microsoft.SharePoint.ApplicationPages.ClientPickerQuery.PeoplePickerQuerySettings

**Accessibility:** Read Only

The query settings to be used by the picker control.

### **3.2.5.301.1.1.6 VisibleSuggestions**

**Type:** CSOM Int32

**Accessibility:** Read Only

Number indicating the number of visible suggestions in the picker dropdown for possible entities.

### **3.2.5.301.1.2 ObjectPath Properties**

None.

### **3.2.5.301.2 Methods**

#### **3.2.5.301.2.1 Scalar Methods**

None.

#### **3.2.5.301.2.2 ObjectPath Methods**

None.

### **3.2.5.302 Microsoft.SharePoint.Client.PolicyTipUserAction**

**ShortName:** SP.PolicyTipUserAction

**Flag:** false

Specifies the user action to take in response to a **policy tip**.

### **3.2.5.302.1 Field Values**

#### **3.2.5.302.1.1 Override**

**Value:** 0

Override the applied action.

#### **3.2.5.302.1.2 ReportFalsePositive**

**Value:** 1

Report false positive.

### **3.2.5.303 Microsoft.SharePoint.Client.PolicyTipUserActionResult**

**ShortName:** SP.PolicyTipUserActionResult

**Flag:** false

The result from reporting or overriding a **policy tip**.

### **3.2.5.303.1 Field Values**

#### **3.2.5.303.1.1 None**

**Value:** 0

No action was taken on the item. This happens if the item doesn't actually have a matching policy rule.

#### **3.2.5.303.1.2 FalsePositiveReported**

**Value:** 1

A false positive was reported for this item.

#### **3.2.5.303.1.3 Overridden**

**Value:** 2

The matching policy rule was overridden.

#### **3.2.5.303.1.4 FalsePositiveReportedAndOverridden**

**Value:** 3

A false positive was reported for this item, which resulted in the matching policy rule to be overridden.

### **3.2.5.304 Microsoft.SharePoint.Client.RemoteWeb**

**TypeId:** {E31F488B-8615-4434-87A8-381B3AF1EE3B}

**ShortName:** SP.RemoteWeb

Specifies a remote web that might be on a different domain.

### 3.2.5.304.1 Properties

#### 3.2.5.304.1.1 Scalar Properties

##### 3.2.5.304.1.1.1 CanSendEmail

**Type:** CSOM Boolean

**Accessibility:** Read Only

Indicates whether an e-mail server has been set for the **site (2)** this web is in.

##### 3.2.5.304.1.1.2 ShareByEmailEnabled

**Type:** CSOM Boolean

**Accessibility:** Read Only

Indicates whether users will be able to grant permissions to guests for resources within the web's parent **site collection**.

##### 3.2.5.304.1.1.3 ShareByLinkEnabled

**Type:** CSOM Boolean

**Accessibility:** Read Only

Indicates whether users will be able to share links to **documents** that can be accessed without logging in.

#### 3.2.5.304.1.2 ObjectPath Properties

##### 3.2.5.304.1.2.1 Web

**Type:** Microsoft.SharePoint.Client.Web

**Accessibility:** Read Only

Gets the SP.Web.

### 3.2.5.304.2 Methods

#### 3.2.5.304.2.1 Scalar Methods

None.

#### 3.2.5.304.2.2 ObjectPath Methods

##### 3.2.5.304.2.2.1 CSOM Constructor

Creates an instance of type **RemoteWeb** (section [3.2.5.304](#)).

**Parameters:**

*requestUrl*: A string that contains the URL for the web.

Type: **CSOM String**

### 3.2.5.304.2.2.2 **GetFileByServerRelativePath**

**Return Type:** Microsoft.SharePoint.Client.File

Returns the file object located at the specified path.

**Parameters:**

*serverRelativeFilePath:* Contains the server-relative path of the file.

Type: Microsoft.SharePoint.Client.ResourcePath

### 3.2.5.304.2.2.3 **GetFileByServerRelativeUrl**

**Return Type:** Microsoft.SharePoint.Client.File

Returns the file object located at the specified URL.

**Parameters:**

*serverRelativeFileUrl:* A string that contains the URL for the file.

Type: **CSOM String**

### 3.2.5.304.2.2.4 **GetFileByUrl**

**Return Type:** Microsoft.SharePoint.Client.File

Returns the file object from the **URL** returned by SPFile.GetWOPIFrameUrl(), SPFile.ShareByLink() or SPFile.LinkingUrl. Caller does not need to know the type of the URL provided.

**Parameters:**

*fileUrl:* A string that contains the URL for the file.

Type: **CSOM String**

### 3.2.5.304.2.2.5 **GetFolderByServerRelativeUrl**

**Return Type:** Microsoft.SharePoint.Client.Folder

Returns the folder object that is located at the specified URL.

**Parameters:**

*serverRelativeUrl:* A string that contains the URL for the folder.

Type: **CSOM String**

It MUST NOT be NULL.

**Exceptions:**

Error Code	Error Type Name	Condition
-2147024894	System.IO.FileNotFoundException	<i>serverRelativeUrl</i> doesn't correspond to a folder.

### 3.2.5.304.2.2.6 GetGroupById

**Return Type:** Microsoft.SharePoint.Client.Group

Returns the SharePoint group indicated by the specified Id.

**Parameters:**

*groupId*: The identifier of the SharePoint group to be retrieved.

Type: **CSOM Int32**

**Exceptions:**

Error Code	Error Type Name	Condition
- 2146233086	System.ArgumentOutOfRangeException	The specified <i>groupId</i> value does not match a valid SharePoint Group object.

### 3.2.5.304.2.2.7 GetListById

**Return Type:** Microsoft.SharePoint.Client.List

Returns the list indicated by the specified Id.

**Parameters:**

*listGuid*: The Id of the list to be retrieved.

Type: **CSOM GUID**

### 3.2.5.304.2.2.8 GetListByServerRelativeUrl

**Return Type:** Microsoft.SharePoint.Client.List

Returns the list that is associated with the specified server-relative URL.

**Parameters:**

*serverRelativeUrl*: A string that contains the site-relative URL for a list.

Type: **CSOM String**

### 3.2.5.305 Microsoft.SharePoint.Client.RenderListContextMenuDataParameters

**TypeId:** {775A72C4-6D8F-457F-AD76-D2779CA29921}

**ShortName:** SP.RenderListContextMenuDataParameters

Specifies the parameters that are used for a list menu item.

#### 3.2.5.305.1 Properties

##### 3.2.5.305.1.1 Scalar Properties

##### 3.2.5.305.1.1.1 CascDelWarnMessage

**Type:** CSOM String

**Accessibility:** Read/Write

The message that SHOULD be displayed if there is a cascade deletion warning.

### **3.2.5.305.1.1.2 CustomAction**

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies a **user custom action**.

### **3.2.5.305.1.1.3 Field**

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies a special field that SHOULD be included.

### **3.2.5.305.1.1.4 ID**

**Type:** CSOM String

**Accessibility:** Read/Write

The id of the list item whose menu information is being sought.

### **3.2.5.305.1.1.5 InplaceFullListSearch**

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies whether there is a full list search. "true" if there is a full list search; "false" otherwise.

### **3.2.5.305.1.1.6 InplaceSearchQuery**

**Type:** CSOM String

**Accessibility:** Read/Write

Search term for a full list search.

### **3.2.5.305.1.1.7 IsCSR**

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies whether this view is a client side rendered view.

### **3.2.5.305.1.1.8 IsXslView**

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies whether this view is an Xsl view.

### **3.2.5.305.1.1.9      ItemId**

**Type:** CSOM String

**Accessibility:** Read/Write

The list item id of the item whose menu information is being sought.

### **3.2.5.305.1.1.10     ListViewPageUrl**

**Type:** CSOM String

**Accessibility:** Read/Write

The URL of the view that is being displayed.

### **3.2.5.305.1.1.11     OverrideScope**

**Type:** CSOM String

**Accessibility:** Read/Write

Used to override a scope on the rendered view: SPView.Scope.

### **3.2.5.305.1.1.12     RootFolder**

**Type:** CSOM String

**Accessibility:** Read/Write

The folder that the view is displaying.

### **3.2.5.305.1.1.13     View**

**Type:** CSOM String

**Accessibility:** Read/Write

The view identifier Guid of the current view.

### **3.2.5.305.1.1.14     ViewCount**

**Type:** CSOM String

**Accessibility:** Read/Write

When multiple views are on a page, this identifies one of them.

## **3.2.5.305.1.2ObjectPath Properties**

None.

## **3.2.5.306      Microsoft.SharePoint.Client.RenderListDataOptions**

**ShortName:** SP.RenderListDataOptions

**Flag:** true



The type of data to return when rendering a list view as **JSON**.

### **3.2.5.306.1 Field Values**

#### **3.2.5.306.1.1 None**

**Value:** 0

Default render type.

#### **3.2.5.306.1.2 ContextInfo**

**Value:** 1

Returns the list data context information.

#### **3.2.5.306.1.3 ListData**

**Value:** 2

Returns the list data.

#### **3.2.5.306.1.4 ListSchema**

**Value:** 4

Returns the list schema.

#### **3.2.5.306.1.5 MenuView**

**Value:** 8

Returns the menu view of the list.

#### **3.2.5.306.1.6 ListContentType**

**Value:** 16

Returns the **list content type**.

#### **3.2.5.306.1.7 FileSystemItemId**

**Value:** 32

The returned list will have a FileSystemItemId field on each item if possible.

#### **3.2.5.306.1.8 ClientFormSchema**

**Value:** 64

Returns the client form schema to add and edit items.

#### **3.2.5.306.1.9 QuickLaunch**

**Value:** 128

Returns QuickLaunch navigation nodes.

#### **3.2.5.306.1.10 Spotlight**

**Value:** 256

Returns Spotlight rendering information

### **3.2.5.306.1.11 Visualization**

**Value:** 512

Returns Visualization rendering information.

### **3.2.5.306.1.12 ViewMetadata**

**Value:** 1024

Returns view XML and other information about the current view.

### **3.2.5.306.1.13 DisableAutoHyperlink**

**Value:** 2048

Prevents AutoHyperlink from being run on text fields in this query.

### **3.2.5.306.1.14 EnableMediaTAUrls**

**Value:** 4096

Enables urls pointing to Media TA service, such as .thumbnailUrl, .videoManifestUrl, .pdfConversionUrls.

### **3.2.5.306.1.15 ParentInfo**

**Value:** 8192

Return Parent folder information.

### **3.2.5.306.1.16 PageContextInfo**

**Value:** 16384

Return Page context info for the current list being rendered.

### **3.2.5.306.1.17 ClientSideComponentManifest**

**Value:** 32768

Return client-side component manifest information associated with the list.

## **3.2.5.307 Microsoft.SharePoint.Client.RenderListDataOverrideParameters**

**TypeId:** {AD0885E6-0F16-4694-9397-058C65376FB7}

**ShortName:** SP.RenderListDataOverrideParameters

The parameters that are used to override and extend the regular SP.RenderListDataParameters.

### **3.2.5.307.1 Properties**

#### **3.2.5.307.1.1 Scalar Properties**

### **3.2.5.307.1.1.1 CascDelWarnMessage**

**Type:** CSOM String

**Accessibility:** Read/Write

The message that SHOULD be displayed if there is a cascade deletion warning.

### **3.2.5.307.1.1.2 CustomAction**

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies a **user custom action**.

### **3.2.5.307.1.1.3 DrillDown**

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies that some groups in a grouped view are expanded. Used with **GroupString** (section [3.2.5.307.1.1.84](#)).

### **3.2.5.307.1.1.4 Field**

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies a special **field (2)** that SHOULD be included.

### **3.2.5.307.1.1.5 FieldInternalName**

**Type:** CSOM String

**Accessibility:** Read/Write

Used to identify a field when a list has an external data source. Also used when filtering on a custom field.

### **3.2.5.307.1.1.6 Filter**

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies whether the requested view has a filter applied.

### **3.2.5.307.1.1.7 FilterData**

**Type:** CSOM String

**Accessibility:** Read/Write

Data specified by a particular filter.

### **3.2.5.307.1.1.8 FilterData1**

**Type:** CSOM String

**Accessibility:** Read/Write

Data specified by a particular filter.

#### **3.2.5.307.1.1.9 FilterData10**

**Type:** CSOM String

**Accessibility:** Read/Write

Data specified by a particular filter.

#### **3.2.5.307.1.1.10 FilterData2**

**Type:** CSOM String

**Accessibility:** Read/Write

Data specified by a particular filter.

#### **3.2.5.307.1.1.11 FilterData3**

**Type:** CSOM String

**Accessibility:** Read/Write

Data specified by a particular filter.

#### **3.2.5.307.1.1.12 FilterData4**

**Type:** CSOM String

**Accessibility:** Read/Write

Data specified by a particular filter.

#### **3.2.5.307.1.1.13 FilterData5**

**Type:** CSOM String

**Accessibility:** Read/Write

Data specified by a particular filter.

#### **3.2.5.307.1.1.14 FilterData6**

**Type:** CSOM String

**Accessibility:** Read/Write

Data specified by a particular filter.

#### **3.2.5.307.1.1.15 FilterData7**

**Type:** CSOM String

**Accessibility:** Read/Write

Data specified by a particular filter.

#### **3.2.5.307.1.1.16 FilterData8**

**Type:** CSOM String

**Accessibility:** Read/Write

Data specified by a particular filter.

#### **3.2.5.307.1.1.17 FilterData9**

**Type:** CSOM String

**Accessibility:** Read/Write

Data specified by a particular filter.

#### **3.2.5.307.1.1.18 FilterField**

**Type:** CSOM String

**Accessibility:** Read/Write

A filter field name for a specific filter that is applied to the view.

#### **3.2.5.307.1.1.19 FilterField1**

**Type:** CSOM String

**Accessibility:** Read/Write

A filter field name for a specific filter that is applied to the view.

#### **3.2.5.307.1.1.20 FilterField10**

**Type:** CSOM String

**Accessibility:** Read/Write

A filter field name for a specific filter that is applied to the view.

#### **3.2.5.307.1.1.21 FilterField2**

**Type:** CSOM String

**Accessibility:** Read/Write

A filter field name for a specific filter that is applied to the view.

#### **3.2.5.307.1.1.22 FilterField3**

**Type:** CSOM String

**Accessibility:** Read/Write

A filter field name for a specific filter that is applied to the view.

#### **3.2.5.307.1.1.23 FilterField4**

**Type:** CSOM String

**Accessibility:** Read/Write

A filter field name for a specific filter that is applied to the view.

#### **3.2.5.307.1.1.24 FilterField5**

**Type:** CSOM String

**Accessibility:** Read/Write

A filter field name for a specific filter that is applied to the view.

#### **3.2.5.307.1.1.25 FilterField6**

**Type:** CSOM String

**Accessibility:** Read/Write

A filter field name for a specific filter that is applied to the view.

#### **3.2.5.307.1.1.26 FilterField7**

**Type:** CSOM String

**Accessibility:** Read/Write

A filter field name for a specific filter that is applied to the view.

#### **3.2.5.307.1.1.27 FilterField8**

**Type:** CSOM String

**Accessibility:** Read/Write

A filter field name for a specific filter that is applied to the view.

#### **3.2.5.307.1.1.28 FilterField9**

**Type:** CSOM String

**Accessibility:** Read/Write

A filter field name for a specific filter that is applied to the view.

#### **3.2.5.307.1.1.29 FilterFields**

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies multiple fields that are being filtered on for a multiplier filter.

#### **3.2.5.307.1.1.30 FilterFields1**

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies multiple fields that are being filtered on for a multiplier filter.

#### **3.2.5.307.1.1.31 FilterFields10**

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies multiple fields that are being filtered on for a multiplier filter.

#### **3.2.5.307.1.1.32 FilterFields2**

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies multiple fields that are being filtered on for a multiplier filter.

#### **3.2.5.307.1.1.33 FilterFields3**

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies multiple fields that are being filtered on for a multiplier filter.

#### **3.2.5.307.1.1.34 FilterFields4**

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies multiple fields that are being filtered on for a multiplier filter.

#### **3.2.5.307.1.1.35 FilterFields5**

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies multiple fields that are being filtered on for a multiplier filter.

#### **3.2.5.307.1.1.36 FilterFields6**

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies multiple fields that are being filtered on for a multiplier filter.

#### **3.2.5.307.1.1.37 FilterFields7**

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies multiple fields that are being filtered on for a multiplier filter.

#### **3.2.5.307.1.1.38 FilterFields8**

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies multiple fields that are being filtered on for a multiplier filter.

#### **3.2.5.307.1.1.39 FilterFields9**

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies multiple fields that are being filtered on for a multiplier filter.

#### **3.2.5.307.1.1.40 FilterLookupId**

**Type:** CSOM String

**Accessibility:** Read/Write

Used when filtering on a lookup field. This is the item id in the foreign list that has a value that is being filtered on.

#### **3.2.5.307.1.1.41 FilterLookupId1**

**Type:** CSOM String

**Accessibility:** Read/Write

Used when filtering on a lookup field. This is the item id in the foreign list that has a value that is being filtered on.

#### **3.2.5.307.1.1.42 FilterLookupId10**

**Type:** CSOM String

**Accessibility:** Read/Write

Used when filtering on a lookup field. This is the item id in the foreign list that has a value that is being filtered on.

#### **3.2.5.307.1.1.43 FilterLookupId2**

**Type:** CSOM String

**Accessibility:** Read/Write

Used when filtering on a lookup field. This is the item id in the foreign list that has a value that is being filtered on.

#### **3.2.5.307.1.1.44 FilterLookupId3**

**Type:** CSOM String

**Accessibility:** Read/Write

Used when filtering on a lookup field. This is the item id in the foreign list that has a value that is being filtered on.

#### **3.2.5.307.1.1.45 FilterLookupId4**



**Type:** CSOM String

**Accessibility:** Read/Write

Used when filtering on a lookup field. This is the item id in the foreign list that has a value that is being filtered on.

#### **3.2.5.307.1.1.46 FilterLookupId5**

**Type:** CSOM String

**Accessibility:** Read/Write

Used when filtering on a lookup field. This is the item id in the foreign list that has a value that is being filtered on.

#### **3.2.5.307.1.1.47 FilterLookupId6**

**Type:** CSOM String

**Accessibility:** Read/Write

Used when filtering on a lookup field. This is the item id in the foreign list that has a value that is being filtered on.

#### **3.2.5.307.1.1.48 FilterLookupId7**

**Type:** CSOM String

**Accessibility:** Read/Write

Used when filtering on a lookup field. This is the item id in the foreign list that has a value that is being filtered on.

#### **3.2.5.307.1.1.49 FilterLookupId8**

**Type:** CSOM String

**Accessibility:** Read/Write

Used when filtering on a lookup field. This is the item id in the foreign list that has a value that is being filtered on.

#### **3.2.5.307.1.1.50 FilterLookupId9**

**Type:** CSOM String

**Accessibility:** Read/Write

Used when filtering on a lookup field. This is the item id in the foreign list that has a value that is being filtered on.

#### **3.2.5.307.1.1.51 FilterOp**

**Type:** CSOM String

**Accessibility:** Read/Write

Filter operator. Used when filtering with other operators than Eq (Geq, Leq etc.).

### **3.2.5.307.1.1.52 FilterOp1**

**Type:** CSOM String

**Accessibility:** Read/Write

Filter operator. Used when filtering with other operators than Eq (Geq, Leq etc.).

### **3.2.5.307.1.1.53 FilterOp10**

**Type:** CSOM String

**Accessibility:** Read/Write

Filter operator. Used when filtering with other operators than Eq (Geq, Leq etc.).

### **3.2.5.307.1.1.54 FilterOp2**

**Type:** CSOM String

**Accessibility:** Read/Write

Filter operator. Used when filtering with other operators than Eq (Geq, Leq etc.).

### **3.2.5.307.1.1.55 FilterOp3**

**Type:** CSOM String

**Accessibility:** Read/Write

Filter operator. Used when filtering with other operators than Eq (Geq, Leq etc.).

### **3.2.5.307.1.1.56 FilterOp4**

**Type:** CSOM String

**Accessibility:** Read/Write

Filter operator. Used when filtering with other operators than Eq (Geq, Leq etc.).

### **3.2.5.307.1.1.57 FilterOp5**

**Type:** CSOM String

**Accessibility:** Read/Write

Filter operator. Used when filtering with other operators than Eq (Geq, Leq etc.).

### **3.2.5.307.1.1.58 FilterOp6**

**Type:** CSOM String

**Accessibility:** Read/Write

Filter operator. Used when filtering with other operators than Eq (Geq, Leq etc.).

### **3.2.5.307.1.1.59 FilterOp7**

**Type:** CSOM String

**Accessibility:** Read/Write

Filter operator. Used when filtering with other operators than Eq (Geq, Leq etc.).

### **3.2.5.307.1.1.60 FilterOp8**

**Type:** CSOM String

**Accessibility:** Read/Write

Filter operator. Used when filtering with other operators than Eq (Geq, Leq etc.).

### **3.2.5.307.1.1.61 FilterOp9**

**Type:** CSOM String

**Accessibility:** Read/Write

Filter operator. Used when filtering with other operators than Eq (Geq, Leq etc.).

### **3.2.5.307.1.1.62 FilterValue**

**Type:** CSOM String

**Accessibility:** Read/Write

The filter value associated with a particular filter. For example, FilterField3 goes with FilterValue3 and so forth.

### **3.2.5.307.1.1.63 FilterValue1**

**Type:** CSOM String

**Accessibility:** Read/Write

The filter value associated with a particular filter. For example, FilterField3 goes with FilterValue3 and so forth.

### **3.2.5.307.1.1.64 FilterValue10**

**Type:** CSOM String

**Accessibility:** Read/Write

The filter value associated with a particular filter. For example, FilterField3 goes with FilterValue3 and so forth.

### **3.2.5.307.1.1.65 FilterValue2**

**Type:** CSOM String

**Accessibility:** Read/Write

The filter value associated with a particular filter. For example, FilterField3 goes with FilterValue3 and so forth.

### **3.2.5.307.1.1.66 FilterValue3**

**Type:** CSOM String

**Accessibility:** Read/Write

The filter value associated with a particular filter. For example, FilterField3 goes with FilterValue3 and so forth.

#### **3.2.5.307.1.1.67 FilterValue4**

**Type:** CSOM String

**Accessibility:** Read/Write

The filter value associated with a particular filter. For example, FilterField3 goes with FilterValue3 and so forth.

#### **3.2.5.307.1.1.68 FilterValue5**

**Type:** CSOM String

**Accessibility:** Read/Write

The filter value associated with a particular filter. For example, FilterField3 goes with FilterValue3 and so forth.

#### **3.2.5.307.1.1.69 FilterValue6**

**Type:** CSOM String

**Accessibility:** Read/Write

The filter value associated with a particular filter. For example, FilterField3 goes with FilterValue3 and so forth.

#### **3.2.5.307.1.1.70 FilterValue7**

**Type:** CSOM String

**Accessibility:** Read/Write

The filter value associated with a particular filter. For example, FilterField3 goes with FilterValue3 and so forth.

#### **3.2.5.307.1.1.71 FilterValue8**

**Type:** CSOM String

**Accessibility:** Read/Write

The filter value associated with a particular filter. For example, FilterField3 goes with FilterValue3 and so forth.

#### **3.2.5.307.1.1.72 FilterValue9**

**Type:** CSOM String

**Accessibility:** Read/Write

The filter value associated with a particular filter. For example, FilterField3 goes with FilterValue3 and so forth.

#### **3.2.5.307.1.1.73 FilterValues**

**Type:** CSOM String

**Accessibility:** Read/Write

Used with **FilterFields** (section [3.2.5.307.1.1.29](#)) for multiplier filter.

#### **3.2.5.307.1.1.74 FilterValues1**

**Type:** CSOM String

**Accessibility:** Read/Write

Used with **FilterFields1** (section [3.2.5.307.1.1.30](#)) for multiplier filter.

#### **3.2.5.307.1.1.75 FilterValues10**

**Type:** CSOM String

**Accessibility:** Read/Write

Used with **FilterFields10** (section [3.2.5.307.1.1.31](#)) for multiplier filter.

#### **3.2.5.307.1.1.76 FilterValues2**

**Type:** CSOM String

**Accessibility:** Read/Write

Used with **FilterFields2** (section [3.2.5.307.1.1.32](#)) for multiplier filter.

#### **3.2.5.307.1.1.77 FilterValues3**

**Type:** CSOM String

**Accessibility:** Read/Write

Used with **FilterFields3** (section [3.2.5.307.1.1.33](#)) for multiplier filter.

#### **3.2.5.307.1.1.78 FilterValues4**

**Type:** CSOM String

**Accessibility:** Read/Write

Used with **FilterFields4** (section [3.2.5.307.1.1.34](#)) for multiplier filter.

#### **3.2.5.307.1.1.79 FilterValues5**

**Type:** CSOM String

**Accessibility:** Read/Write

Used with **FilterFields5** (section [3.2.5.307.1.1.35](#)) for multiplier filter.

#### **3.2.5.307.1.1.80 FilterValues6**

**Type:** CSOM String

**Accessibility:** Read/Write

Used with **FilterFields6** (section [3.2.5.307.1.1.36](#)) for multiplier filter.

#### **3.2.5.307.1.1.81 FilterValues7**

**Type:** CSOM String

**Accessibility:** Read/Write

Used with **FilterFields7** (section [3.2.5.307.1.1.37](#)) for multiplier filter.

#### **3.2.5.307.1.1.82 FilterValues8**

**Type:** CSOM String

**Accessibility:** Read/Write

Used with **FilterFields8** (section [3.2.5.307.1.1.38](#)) for multiplier filter.

#### **3.2.5.307.1.1.83 FilterValues9**

**Type:** CSOM String

**Accessibility:** Read/Write

Used with **FilterFields9** (section [3.2.5.307.1.1.39](#)) for multiplier filter.

#### **3.2.5.307.1.1.84 GroupString**

**Type:** CSOM String

**Accessibility:** Read/Write

Group identifier used for drill-down feature.

#### **3.2.5.307.1.1.85 HasOverrideSelectCommand**

**Type:** CSOM String

**Accessibility:** Read/Write

Used to ensure that certain fields are present for proper functioning of the ListView control.

#### **3.2.5.307.1.1.86 ID**

**Type:** CSOM String

**Accessibility:** Read/Write

The item id of the item whose information is being sought.

#### **3.2.5.307.1.1.87 InplaceFullListSearch**

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies whether there is a full list search. "true" if there is a full list search; "false" otherwise.

#### **3.2.5.307.1.1.88 InplaceSearchQuery**

**Type:** CSOM String

**Accessibility:** Read/Write

Search term for a full list search.

### **3.2.5.307.1.1.89 IsCSR**

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies whether this view is a client side rendered view.

### **3.2.5.307.1.1.90 IsGroupRender**

**Type:** CSOM String

**Accessibility:** Read/Write

Used to set the IsGroupRender property of the SP.View.

### **3.2.5.307.1.1.91 IsXslView**

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies whether this view is an xslt list view.

### **3.2.5.307.1.1.92 ListViewPageUrl**

**Type:** CSOM String

**Accessibility:** Read/Write

The URL of the view that is being displayed.

### **3.2.5.307.1.1.93 OverrideScope**

**Type:** CSOM String

**Accessibility:** Read/Write

Used to override a scope on the rendered view: SPView.Scope.

### **3.2.5.307.1.1.94 OverrideSelectCommand**

**Type:** CSOM String

**Accessibility:** Read/Write

Used to make sure that certain fields are present in the query regardless of whether they are explicitly included in the view.

### **3.2.5.307.1.1.95 PageFirstRow**

**Type:** CSOM String

**Accessibility:** Read/Write

Paging information about the first row that is requested. Used for paging list views.

### **3.2.5.307.1.1.96 PageLastRow**

**Type:** CSOM String

**Accessibility:** Read/Write

Paging information about the last row that is requested. Used for paging list views.

### **3.2.5.307.1.1.97 RootFolder**

**Type:** CSOM String

**Accessibility:** Read/Write

The folder that the view is displaying.

### **3.2.5.307.1.1.98 SortDir**

**Type:** CSOM String

**Accessibility:** Read/Write

The sort direction of an ad hoc sort that is being applied to the view.

### **3.2.5.307.1.1.99 SortDir1**

**Type:** CSOM String

**Accessibility:** Read/Write

The sort direction of an ad hoc sort that is being applied to the view.

### **3.2.5.307.1.1.100 SortDir10**

**Type:** CSOM String

**Accessibility:** Read/Write

The sort direction of an ad hoc sort that is being applied to the view.

### **3.2.5.307.1.1.101 SortDir2**

**Type:** CSOM String

**Accessibility:** Read/Write

The sort direction of an ad hoc sort that is being applied to the view.

### **3.2.5.307.1.1.102 SortDir3**

**Type:** CSOM String

**Accessibility:** Read/Write

The sort direction of an ad hoc sort that is being applied to the view.

### **3.2.5.307.1.1.103 SortDir4**



**Type:** CSOM String

**Accessibility:** Read/Write

The sort direction of an ad hoc sort that is being applied to the view.

#### **3.2.5.307.1.1.104 SortDir5**

**Type:** CSOM String

**Accessibility:** Read/Write

The sort direction of an ad hoc sort that is being applied to the view.

#### **3.2.5.307.1.1.105 SortDir6**

**Type:** CSOM String

**Accessibility:** Read/Write

The sort direction of an ad hoc sort that is being applied to the view.

#### **3.2.5.307.1.1.106 SortDir7**

**Type:** CSOM String

**Accessibility:** Read/Write

The sort direction of an ad hoc sort that is being applied to the view.

#### **3.2.5.307.1.1.107 SortDir8**

**Type:** CSOM String

**Accessibility:** Read/Write

The sort direction of an ad hoc sort that is being applied to the view.

#### **3.2.5.307.1.1.108 SortDir9**

**Type:** CSOM String

**Accessibility:** Read/Write

The sort direction of an ad hoc sort that is being applied to the view.

#### **3.2.5.307.1.1.109 SortField**

**Type:** CSOM String

**Accessibility:** Read/Write

A field that the view SHOULD be sorted on.

#### **3.2.5.307.1.1.110 SortField1**

**Type:** CSOM String

**Accessibility:** Read/Write

A field that the view SHOULD be sorted on.

**3.2.5.307.1.1.111 SortField10**

**Type:** CSOM String

**Accessibility:** Read/Write

A field that the view SHOULD be sorted on.

**3.2.5.307.1.1.112 SortField2**

**Type:** CSOM String

**Accessibility:** Read/Write

A field that the view SHOULD be sorted on.

**3.2.5.307.1.1.113 SortField3**

**Type:** CSOM String

**Accessibility:** Read/Write

A field that the view SHOULD be sorted on.

**3.2.5.307.1.1.114 SortField4**

**Type:** CSOM String

**Accessibility:** Read/Write

A field that the view SHOULD be sorted on.

**3.2.5.307.1.1.115 SortField5**

**Type:** CSOM String

**Accessibility:** Read/Write

A field that the view SHOULD be sorted on.

**3.2.5.307.1.1.116 SortField6**

**Type:** CSOM String

**Accessibility:** Read/Write

A field that the view SHOULD be sorted on.

**3.2.5.307.1.1.117 SortField7**

**Type:** CSOM String

**Accessibility:** Read/Write

A field that the view SHOULD be sorted on.

**3.2.5.307.1.1.118 SortField8**

**Type:** CSOM String

**Accessibility:** Read/Write

A field that the view SHOULD be sorted on.

#### **3.2.5.307.1.1.119 SortField9**

**Type:** CSOM String

**Accessibility:** Read/Write

A field that the view SHOULD be sorted on.

#### **3.2.5.307.1.1.120 SortFields**

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies the name of the first Field to sort by.

#### **3.2.5.307.1.1.121 SortFieldValues**

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies the name of the first Field to sort by.

#### **3.2.5.307.1.1.122 View**

**Type:** CSOM String

**Accessibility:** Read/Write

The view identifier Guid of the current view.

#### **3.2.5.307.1.1.123 ViewCount**

**Type:** CSOM String

**Accessibility:** Read/Write

When multiple list views are on a page, this identifies one of them.

#### **3.2.5.307.1.1.124 ViewId**

**Type:** CSOM String

**Accessibility:** Read/Write

Specifies the base view that will be used to render the list. Ad hoc parameters will be applied on top of this view. If both ViewXml and BaseViewId are given, then the ViewXml will be used and the ad hoc parameters will be ignored.

#### **3.2.5.307.1.1.125 ViewPath**

**Type:** CSOM String

**Accessibility:** Read/Write

Specify the path of the view that will be used to render the list. If ViewId is given then the ViewId will be used and this parameters will be ignored.

### **3.2.5.307.1.1.126 WebPartId**

**Type:** CSOM String

**Accessibility:** Read/Write

The id of the list view web part that is showing this view.

### **3.2.5.307.1.2ObjectPath Properties**

None.

### **3.2.5.308 Microsoft.SharePoint.Client.RenderListFilterDataParameters**

**TypeId:** {5932E072-C4E0-4809-B1C9-88077C4DF471}

**ShortName:** SP.RenderListFilterDataParameters

Specifies the parameters that are used to retrieve filter data.

#### **3.2.5.308.1 Properties**

##### **3.2.5.308.1.1 Scalar Properties**

###### **3.2.5.308.1.1.1 ExcludeFieldFilteringHtml**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

This parameter indicates whether field specific list filter html is excluded from rendering.

###### **3.2.5.308.1.1.2 FieldInternalName**

**Type:** CSOM String

**Accessibility:** Read/Write

The field internal name whose filter data is returned.

###### **3.2.5.308.1.1.3 OverrideScope**

**Type:** CSOM String

**Accessibility:** Read/Write

The overrideScope for which the field filter data is returned. The string values come from SPView.ConvertStringToViewScope.

###### **3.2.5.308.1.1.4 ProcessQStringToCAML**

**Type:** CSOM String

**Accessibility:** Read/Write

The processQueryString for which the field filter data is returned.

### **3.2.5.308.1.1.5 ViewId**

**Type:** CSOM String

**Accessibility:** Read/Write

The View ID (GUID) for the view from which to retrieve filter data.

### **3.2.5.308.1.2ObjectPath Properties**

None.

## **3.2.5.309 Microsoft.SharePoint.Client.RequestUserContext**

**TypeId:** {56E4C4BC-9C90-400C-8EFD-940E74794E3A}

**ShortName:** SP.RequestUserContext

The class that represents the user context for the present request. Typically found under /\_api/me

### **3.2.5.309.1 Properties**

#### **3.2.5.309.1.1Scalar Properties**

None.

#### **3.2.5.309.1.2ObjectPath Properties**

##### **3.2.5.309.1.2.1 Current**

**Type:** Microsoft.SharePoint.Client.RequestUserContext

**Accessibility:** Read Only

Gets the SP.RequestUserContext for the current request.

##### **3.2.5.309.1.2.2 User**

**Type:** Microsoft.SharePoint.Client.User

**Accessibility:** Read Only

The SP.User object for the current request.

### **3.2.5.309.2 Methods**

#### **3.2.5.309.2.1Scalar Methods**

None.

#### **3.2.5.309.2.2ObjectPath Methods**

None.

### **3.2.5.310 Microsoft.SharePoint.Client.RuleOverrideOptions**

**ShortName:** SP.RuleOverrideOptions

**Flag:** false

The allowable options that someone can take to override a policy match.

#### **3.2.5.310.1 Field Values**

##### **3.2.5.310.1.1None**

**Value:** 0

No override is allowed.

##### **3.2.5.310.1.2Allow**

**Value:** 1

Override is allowed without requiring justification.

##### **3.2.5.310.1.3AllowWithJustification**

**Value:** 2

Override is allowed as long as justification is provided.

### **3.2.5.311 Microsoft.SharePoint.Client.SandboxedCodeActivationCapabilities**

**ShortName:** SP.SandboxedCodeActivationCapabilities

**Flag:** false

The sandboxed code capabilities for the site collection.

Note that the `SandboxedCodeActivationCapabilities` enum in `ms.online.sp.powershell Get/Set-SPOSite` cmdlet defines the first enum value as 'Unknown'. This is because the `SandboxedCodeActivationCapabilities` in that code base needs an unknown value, indicating that the default use of `Get-SPOSite` does not return site properties. So you have to show the value in this case as unknown (that is the current model for that code base). If you add the `-Detailed` switch to `Get-SPOSite`, it will get the site properties.

#### **3.2.5.311.1 Field Values**

##### **3.2.5.311.1.1Check**

**Value:** 1

The sandboxed code capability for the site collection is chosen based on the presence of existing solutions with sandboxed code. If the site collection contains one or more activated solutions with sandboxed code, the capability will be Enabled, otherwise Disabled. This is the default sandboxed code capability for site collections.

##### **3.2.5.311.1.2Disabled**

**Value:** 2

The site collection will block activation and upgrade of solutions with sandboxed code.

### 3.2.5.311.1.3 Enabled

**Value:** 3

The site collection will allow activation and upgrade of solutions with sandboxed code.

### 3.2.5.312 Microsoft.SharePoint.Client.SharePointSharingSettings

**TypeId:** {07DBEBDF-94BC-4A22-843A-323551F64FAB}

**ShortName:** SP.SharePointSharingSettings

This class contains the SharePoint UI-specific sharing settings.

#### 3.2.5.312.1 Properties

##### 3.2.5.312.1.1 Scalar Properties

###### 3.2.5.312.1.1.1 AddToGroupModeName

**Type:** CSOM String

**Accessibility:** Read Only

The group name when adding users to a single group (AddToGroup mode).

###### 3.2.5.312.1.1.2 GroupNameLines

**Type:** CSOM array of CSOM String

**Accessibility:** Read Only

A collection of each group's name in the site.

###### 3.2.5.312.1.1.3 GroupRoleDefinitionNamesLines

**Type:** CSOM array of CSOM String

**Accessibility:** Read Only

A collection of HTML definitions for each group's role in the site.

Format: <span title="ToolTip\_Text">Group's role name</span>

###### 3.2.5.312.1.1.4 IsMobileView

**Type:** CSOM Boolean

**Accessibility:** Read Only

Boolean that indicates whether or not the sharing dialog SHOULD render as a mobile view.

###### 3.2.5.312.1.1.5 PanelGivePermissionsVisible

**Type:** CSOM Boolean

**Accessibility:** Read Only

Boolean that indicates whether or not the "Give permissions" section (label and group/role drop-down) is visible.

#### **3.2.5.312.1.1.6 PanelShowHideMoreOptionsVisible**

**Type:** CSOM Boolean

**Accessibility:** Read Only

Boolean that indicates whether or not the Show/Hide more options link is visible.

#### **3.2.5.312.1.1.7 PanelSimplifiedRoleSelectorVisible**

**Type:** CSOM Boolean

**Accessibility:** Read Only

Boolean that indicates whether or not the simplified role (edit, view) drop-down is visible.

#### **3.2.5.312.1.1.8 RequiredScriptFileLinks**

**Type:** CSOM array of CSOM String

**Accessibility:** Read Only

Provides file dependencies as a list of URLs, for the sharing feature.

#### **3.2.5.312.1.1.9 RoleDefinitionNameLines**

**Type:** CSOM array of CSOM String

**Accessibility:** Read Only

A collection of HTML definitions for each basic role in the site.

#### **3.2.5.312.1.1.10 SelectedGroup**

**Type:** CSOM String

**Accessibility:** Read Only

The reference to the currently selected group.

#### **3.2.5.312.1.1.11 SharedWithEnabled**

**Type:** CSOM Boolean

**Accessibility:** Read Only

Specifies whether the tabbed **Shared With** pane is enabled.

#### **3.2.5.312.1.1.12 SharingCssLink**

**Type:** CSOM String

**Accessibility:** Read Only

CSS file link URL for the sharing feature.

#### **3.2.5.312.1.1.13 TabbedDialogEnabled**



**Type:** CSOM Boolean

**Accessibility:** Read Only

Specifies whether the sharing dialog supports tabbing.

#### **3.2.5.312.1.1.14 TabToShow**

**Type:** CSOM Int32

**Accessibility:** Read Only

An integer corresponding to the tab that is requested.

#### **3.2.5.312.1.1.15 txtEmailSubjectText**

**Type:** CSOM String

**Accessibility:** Read Only

A value that is used to fill in the sharing email subject line.

#### **3.2.5.312.1.1.16 UserDisplayUrl**

**Type:** CSOM String

**Accessibility:** Read Only

Base URL of the page used to display information about a particular user.

### **3.2.5.312.1.2ObjectPath Properties**

#### **3.2.5.312.1.2.1 PickerProperties**

**Type:** Microsoft.SharePoint.Client.PickerSettings

**Accessibility:** Read Only

An object containing the necessary information to initialize a client people picker control used to search for and resolve desired users and groups.

### **3.2.5.312.2 Methods**

#### **3.2.5.312.2.1Scalar Methods**

None.

#### **3.2.5.312.2.2ObjectPath Methods**

None.

### **3.2.5.313 Microsoft.SharePoint.Client.Sharing.WebSharingManager**

**TypeId:** {A187F049-F067-42CD-977B-79E85EA2A9FA}

**ShortName:** SP.Sharing.WebSharingManager

Specifies a placeholder for all web sharing methods.

### 3.2.5.313.1 Properties

#### 3.2.5.313.1.1 Scalar Properties

None.

#### 3.2.5.313.1.2 ObjectPath Properties

None.

### 3.2.5.313.2 Methods

#### 3.2.5.313.2.1 Scalar Methods

##### 3.2.5.313.2.1.1 CanMemberShare

This method is a **static CSOM method**.

**Return Type:** **CSOM Boolean**

Indicates whether the input site can do member sharing.

**Parameters:**

*web*: The **site (2)** to check member sharing.

Type: Microsoft.SharePoint.Client.Web

##### 3.2.5.313.2.1.2 UpdateWebSharingInformation

This method is a **static CSOM method**.

**Return Type:** **CSOM array** of Microsoft.SharePoint.Client.Sharing.UserSharingResult

This method allows a user to update a site's sharing information.

**Parameters:**

*web*: The **site (2)** to update the sharing information.

Type: Microsoft.SharePoint.Client.Web

*userRoleAssignments*: A list of recipients and their new assigned roles on the **securable object**.

Type: CSOM array of Microsoft.SharePoint.Client.Sharing.UserRoleAssignment

*sendServerManagedNotification*: A Boolean to tell the server to generate an email notification if an email server is configured on the server.

Type: **CSOM Boolean**

*customMessage*: A custom message to be included in the email notification.

Type: **CSOM String**

*additivePermission*: A Boolean indicating whether the permission setting uses the additive or strict mode.

Type: CSOM Boolean

*allowExternalSharing*: A Boolean to indicate whether to support external sharing.

Type: CSOM Boolean

### 3.2.5.313.2 ObjectPath Methods

None.

### 3.2.5.314 Microsoft.SharePoint.Client.SharingLinkInfo

**TypeId:** {43647532-53C0-489A-A800-B51F5A3804A2}

**ShortName:** SP.SharingLinkInfo

Specifies the information about the **tokenized sharing link**.

#### 3.2.5.314.1 Properties

##### 3.2.5.314.1.1 Scalar Properties

###### 3.2.5.314.1.1.1 AllowsAnonymousAccess

**Type:** CSOM Boolean

**Accessibility:** Read Only

Indicates whether the **tokenized sharing link** allows anonymous access.

###### 3.2.5.314.1.1.2 Created

**Type:** CSOM String

**Accessibility:** Read Only

The UTC date/time string with complete representation for calendar date and time of day which represents the time and date of creation of the **tokenized sharing link**. Format returned from get operation is "YYYY-MM-DDThh:mm:ss.fffZ" (e.g. "2016-09-22T12:20:10.125Z"), with a null value indicating no recorded creation date. The date/time string format for set operations conforms to the ISO 8601:2004(E) complete representation for calendar date and time of day. Both the minutes and hour value MUST be specified for the difference between the local and UTC time. Midnight is represented as 00:00:00. For example: YYYYMMDDThhmmssZ YYYYMMDDThhmmss±hhmm YYYYMMDDThhmmss±hh:mm YYYYMMDDThhmmssfffZ YYYY-MM-DDThh:mm:ssZ YYYY-MM-DDThh:mm:ss±hh:mm YYYY-MM-DDThh:mm:ss±hhmm YYYY-MM-DDThh:mm:ss.fffZ.

###### 3.2.5.314.1.1.3 CreatedBy

**Type:** Microsoft.SharePoint.Client.Sharing.Principal

**Accessibility:** Read Only

Indicates the principal who created the **tokenized sharing link**, or null if the created by value is not recorded.

###### 3.2.5.314.1.1.4 Expiration

**Type:** CSOM String

**Accessibility:** Read Only

The UTC date/time string with complete representation for calendar date and time of day which represents the time and date of expiry for the **tokenized sharing link** (i.e. is not accessible anymore). Format returned from get operation is "YYYY-MM-DDThh:mm:ss.fffZ" (e.g. "2016-09-22T12:20:10.125Z"), with a null value indicating no expiry. The date/time string format for set operations conforms to the ISO 8601:2004(E) complete representation for calendar date and time of day. Both the minutes and hour value MUST be specified for the difference between the local and UTC time. Midnight is represented as 00:00:00. For example: YYYYMMDDThhmmssZ  
YYYYMMDDThhmmss±hhmm YYYYMMDDThhmmss±hh:mm YYYYMMDDThhmmssfffZ YYYY-MM-DDThh:mm:ssZ YYYY-MM-DDThh:mm:ss±hh:mm YYYY-MM-DDThh:mm:ss±hhmm YYYY-MM-DDThh:mm:ss.fffZ A null value indicates no expiry.

This value is only applicable to tokenized sharing links that are **anonymous access links**.

### **3.2.5.314.1.1.5 HasExternalGuestInvitees**

**Type:** CSOM Boolean

**Accessibility:** Read Only

Indicates whether the **tokenized sharing link** has any External Guest Invitees (external users explicitly invited by email address).

### **3.2.5.314.1.1.6 Invitations**

**Type:** CSOM array of Microsoft.SharePoint.Client.Sharing.LinkInvitation

**Accessibility:** Read Only

This value contains the current membership list for principals that have been Invited to the **tokenized sharing link**.

### **3.2.5.314.1.1.7 IsActive**

**Type:** CSOM Boolean

**Accessibility:** Read Only

Indicates whether the **tokenized sharing link** is active.

### **3.2.5.314.1.1.8 IsEditLink**

**Type:** CSOM Boolean

**Accessibility:** Read Only

Indicates whether the **tokenized sharing link** provides edit access.

### **3.2.5.314.1.1.9 IsFormsLink**

**Type:** CSOM Boolean

**Accessibility:** Read Only

Indicates whether the **tokenized sharing link** is a forms link.

### **3.2.5.314.1.1.10 IsReviewLink**

**Type:** CSOM Boolean

**Accessibility:** Read Only

Indicates whether the **tokenized sharing link** provides review access.

#### **3.2.5.314.1.1.11 IsUnhealthy**

**Type:** CSOM Boolean

**Accessibility:** Read Only

Indicates the **tokenized sharing link** is in unhealthy state and might not work.

#### **3.2.5.314.1.1.12 LastModified**

**Type:** CSOM String

**Accessibility:** Read Only

The UTC date/time string with complete representation for calendar date and time of day which represents the time and date of the last update of the settings for the **tokenized sharing link**. Format returned from get operation is "YYYY-MM-DDThh:mm:ss.fffZ" (e.g. "2016-09-22T12:20:10.125Z"), with a null value indicating no recorded modification date. The date/time string format for set operations conforms to the ISO 8601:2004(E) complete representation for calendar date and time of day. Both the minutes and hour value MUST be specified for the difference between the local and UTC time. Midnight is represented as 00:00:00. For example: YYYYMMDDThhmmssZ YYYYMMDDThhmmss±hhmm YYYYMMDDThhmmss±hh:mm YYYYMMDDThhmmssfffZ YYYY-MM-DDThh:mm:ssZ YYYY-MM-DDThh:mm:ss±hh:mm YYYY-MM-DDThh:mm:ss±hhmm YYYY-MM-DDThh:mm:ss.fffZ.

#### **3.2.5.314.1.1.13 LastModifiedBy**

**Type:** Microsoft.SharePoint.Client.Sharing.Principal

**Accessibility:** Read Only

Indicates the principal who last modified the **tokenized sharing link**. This value MUST be null if the last modified by value is not recorded.

#### **3.2.5.314.1.1.14 LinkKind**

**Type:** Microsoft.SharePoint.Client.SharingLinkKind

**Accessibility:** Read Only

Specifies the kind of **tokenized sharing link**.

#### **3.2.5.314.1.1.15 RequiresPassword**

**Type:** CSOM Boolean

**Accessibility:** Read Only

Indicates whether the **tokenized sharing link** is password protected.

#### **3.2.5.314.1.1.16 RestrictedShareMembership**

**Type:** CSOM Boolean

**Accessibility:** Read Only

Indicates whether the **tokenized sharing link** allows access only to the Invitees.

### 3.2.5.314.1.1.17 ShareId

Type: **CSOM GUID**

Accessibility: Read Only

The unique share identifier of a **tokenized sharing link**.

### 3.2.5.314.1.1.18 Url

Type: **CSOM String**

Accessibility: Read Only

Specifies the **URL** of the **tokenized sharing link**

### 3.2.5.314.1.2ObjectPath Properties

None.

## 3.2.5.315 Microsoft.SharePoint.Client.SharingLinkKind

ShortName: SP.SharingLinkKind

Flag: false

Specifies the kind of **tokenized sharing link**

### 3.2.5.315.1 Field Values

#### 3.2.5.315.1.1Uninitialized

Value: 0

Indicates the kind is indeterminate or that the value has not been initialized

#### 3.2.5.315.1.2Direct

Value: 1

Indicates a direct link or **canonical URL** to an object

#### 3.2.5.315.1.3OrganizationView

Value: 2

Indicates an **organization access link** with view permissions to an object

#### 3.2.5.315.1.4OrganizationEdit

Value: 3

Indicates an **organization access link** with edit permissions to an object

#### 3.2.5.315.1.5AnonymousView

Value: 4

Indicates an **anonymous access link** with view permissions to an object

### **3.2.5.315.1.6 AnonymousEdit**

**Value:** 5

Indicates an **anonymous access link** with edit permissions to an object

### **3.2.5.315.1.7 Flexible**

**Value:** 6

Indicates a **tokenized sharing link** where properties can change without affecting link URL

## **3.2.5.316 Microsoft.SharePoint.Client.SharingOperationStatusCode**

**ShortName:** SP.SharingOperationStatusCode

**Flag:** false

Contains values representing the overall result of a sharing operation.

### **3.2.5.316.1 Field Values**

#### **3.2.5.316.1.1 CompletedSuccessfully**

**Value:** 0

Indicates the share operation completed without errors.

#### **3.2.5.316.1.2 AccessRequestsQueued**

**Value:** 1

Indicates the share operation completed and generated requests for access.

#### **3.2.5.316.1.3 NoResolvedUsers**

**Value:** -1

Indicates the share operation failed as there were no resolved users.

#### **3.2.5.316.1.4 AccessDenied**

**Value:** -2

Indicates the share operation failed due to insufficient permissions.

#### **3.2.5.316.1.5 CrossSiteRequestNotSupported**

**Value:** -3

Indicates the share operation failed when attempting a cross-site share, which is not supported.

#### **3.2.5.316.1.6 UnknowError**

**Value:** -4

Indicates the sharing operation failed due to an unknown error.

#### **3.2.5.316.1.7 EmailBodyTooLong**

**Value:** -5

The email body text is too long.

### **3.2.5.316.1.8ListUniqueScopesExceeded**

**Value:** -6

The maximum number of unique **security scopes** in the **list** has been exceeded.

### **3.2.5.316.1.9CapabilityDisabled**

**Value:** -7

The share operation failed because a sharing capability is disabled in the **site (1)**.

### **3.2.5.316.1.10 ObjectNotSupported**

**Value:** -8

The specified object for the share operation is not supported.

### **3.2.5.316.1.11 NestedGroupsNotSupported**

**Value:** -9

A SharePoint group cannot contain another SharePoint group.

### **3.2.5.316.1.12 QuotaExceeded**

**Value:** -10

A SharePoint Quota limit exceeded. (eg. group, site, file storage, etc).

### **3.2.5.316.1.13 InvalidValue**

**Value:** -11

A SharePoint invalid value.

### **3.2.5.316.1.14 UserDoesNotExist**

**Value:** -12

User does not exist.

### **3.2.5.316.1.15 TooManyChildItemsWithUniqueScopes**

**Value:** -13

The share operation failed because the target object has too many child **list items** with unique **security scopes**.

### **3.2.5.317 Microsoft.SharePoint.Client.SharingPermissionInformation**

**TypeId:** {1A97A9B7-5F9F-4DA3-9402-48324BCB9D9F}

**ShortName:** SP.SharingPermissionInformation



Contains information about a sharing permission entity such as group or role.

### **3.2.5.317.1 Properties**

#### **3.2.5.317.1.1 Scalar Properties**

##### **3.2.5.317.1.1.1 IsDefaultPermission**

**Type:** CSOM Boolean

**Accessibility:** Read Only

Identifies whether or not the permission entity is a default SP.Group or role (meaning it is recommended for granting permissions).

A value of true specifies the current permission is a default SP.Group for granting permissions to a site (site owner, member, or visitor SP.Group) or a default role for granting permission to a file or other non-site object (edit or view). A value of false specifies otherwise.

For SPSites & SPWebs, there can be three default permission entities: owners, members, or visitors SPGroups. For granting permissions to a file or other non-site object, there can be two default permission entities: a role for view permissions (StandardViewerRoleDefinitionID) and a role for edit permissions (StandardEditorRoleDefinitionID).

##### **3.2.5.317.1.1.2 PermissionDescription**

**Type:** CSOM String

**Accessibility:** Read Only

Gets the permission's associated group or role name including its descriptions (optional).

##### **3.2.5.317.1.1.3 PermissionId**

**Type:** CSOM String

**Accessibility:** Read Only

Gets the ID of this permission in the following formats: group:x, role: xxxxxx.

##### **3.2.5.317.1.1.4 PermissionKind**

**Type:** Microsoft.SharePoint.Client.SharingPermissionKind

**Accessibility:** Read Only

Gets the kind of sharing permission such as group, role, etc.

##### **3.2.5.317.1.1.5 PermissionName**

**Type:** CSOM String

**Accessibility:** Read Only

Gets the name of the permission.

##### **3.2.5.317.1.1.6 PermissionRoleType**

**Type:** Microsoft.SharePoint.Client.RoleType

**Accessibility:** Read Only

Returns the RoleType that indicates the permission role represented by the sharing permission entry.

### **3.2.5.317.1.2ObjectPath Properties**

None.

### **3.2.5.317.2 Methods**

#### **3.2.5.317.2.1Scalar Methods**

None.

#### **3.2.5.317.2.2ObjectPath Methods**

None.

### **3.2.5.318 Microsoft.SharePoint.Client.SharingPermissionInformationCollection**

**TypeId:** {7EE2A862-17C8-46B8-8F66-0373EE06AFBF}

**ShortName:** SP.SharingPermissionInformationCollection

Contains a collection of **SharingPermissionInformation** (section [3.2.5.317](#)) objects.

#### **3.2.5.318.1 Properties**

##### **3.2.5.318.1.1Scalar Properties**

None.

##### **3.2.5.318.1.2ObjectPath Properties**

None.

#### **3.2.5.318.2 Methods**

##### **3.2.5.318.2.1Scalar Methods**

None.

##### **3.2.5.318.2.2ObjectPath Methods**

None.

### **3.2.5.319 Microsoft.SharePoint.Client.SharingPermissionKind**

**ShortName:** SP.SharingPermissionKind

**Flag:** false

Describes the kind of **SharingPermissionInformation** (section [3.2.5.317](#)) a particular permission option is when it is used for granting permission.

#### **3.2.5.319.1 Field Values**

### 3.2.5.319.1.1 Group

**Value:** 0

This kind of permission option is a SharePoint group, which users are added to in order to grant permissions.

### 3.2.5.319.1.2 Role

**Value:** 1

This kind of permission option grants permissions by assigning a particular role directly to the user.

## 3.2.5.320 Microsoft.SharePoint.Client.SharingResult

**TypeId:** {AEB0DDA7-3371-4E99-8063-9AFF83BB44E6}

**ShortName:** SP.SharingResult

Contains properties generated as a result of sharing.

### 3.2.5.320.1 Properties

#### 3.2.5.320.1.1 Scalar Properties

##### 3.2.5.320.1.1.1 ErrorMessage

**Type:** CSOM String

**Accessibility:** Read Only

Gets an error message about the failure if sharing was unsuccessful.

##### 3.2.5.320.1.1.2 IconUrl

**Type:** CSOM String

**Accessibility:** Read Only

Gets a URL to an icon that represents the **securable object**, if one exists.

##### 3.2.5.320.1.1.3 InvitedUsers

**Type:** CSOM array of Microsoft.SharePoint.Client.SPInvitationCreationResult

**Accessibility:** Read Only

Gets a list of **SPInvitationCreationResult** (section [3.2.5.325](#)) objects representing the external users being invited to have access.

##### 3.2.5.320.1.1.4 Name

**Type:** CSOM String

**Accessibility:** Read Only

Gets the name of the **securable object** being shared.

##### 3.2.5.320.1.1.5 PermissionsPageRelativeUri

**Type:** CSOM String

**Accessibility:** Read Only

Gets the relative URL of the page that shows permissions.

### 3.2.5.320.1.1.6      **StatusCode**

**Type:** Microsoft.SharePoint.Client.SharingOperationStatusCode

**Accessibility:** Read Only

Gets the enumeration value which summarizes the result of the sharing operation.

### 3.2.5.320.1.1.7      **UniquelyPermissionedUsers**

**Type:** CSOM array of Microsoft.SharePoint.Client.Sharing.UserSharingResult

**Accessibility:** Read Only

Gets the list of **UserSharingResult** (section [3.2.5.190](#)) objects obtained when attempting to share a **securable object** with unique permissions.

### 3.2.5.320.1.1.8      **Url**

**Type:** CSOM String

**Accessibility:** Read Only

Gets the URL of the **securable object** being shared.

### 3.2.5.320.1.1.9      **UsersAddedToGroup**

**Type:** CSOM array of Microsoft.SharePoint.Client.Sharing.UserSharingResult

**Accessibility:** Read Only

Gets the list of users being added to the SharePoint permissions group.

## 3.2.5.320.1.2 ObjectPath Properties

### 3.2.5.320.1.2.1      **GroupsSharedWith**

**Type:** Microsoft.SharePoint.Client.GroupCollection

**Accessibility:** Read Only

Gets the groups which were granted permissions.

### 3.2.5.320.1.2.2      **GroupUsersAddedTo**

**Type:** Microsoft.SharePoint.Client.Group

**Accessibility:** Read Only

Gets the SharePoint group that users, if any, were added to.

### 3.2.5.320.1.2.3      **UsersWithAccessRequests**

**Type:** Microsoft.SharePoint.Client.SharingUserCollection

**Accessibility:** Read Only

Gets the collection of users which have new pending access requests as a result of sharing.

### **3.2.5.320.2 Methods**

#### **3.2.5.320.2.1 Scalar Methods**

None.

#### **3.2.5.320.2.2 ObjectPath Methods**

None.

### **3.2.5.321 Microsoft.SharePoint.Client.SharingUserCollection**

**TypeId:** {EADF1A24-3786-44DD-8C4F-1B16E787F4AD}

**ShortName:** SP.SharingUserCollection

Specifies a collection of sharing users.

#### **3.2.5.321.1 Properties**

##### **3.2.5.321.1.1 Scalar Properties**

None.

##### **3.2.5.321.1.2 ObjectPath Properties**

None.

#### **3.2.5.321.2 Methods**

##### **3.2.5.321.2.1 Scalar Methods**

None.

##### **3.2.5.321.2.2 ObjectPath Methods**

None.

### **3.2.5.322 Microsoft.SharePoint.Client.SPDataLeakagePreventionStatusInfo**

**TypeId:** {3D7F9E23-8100-41F1-96A8-D272093463F8}

**ShortName:** SP.SPDataLeakagePreventionStatusInfo

Contains all the Data Leakage Prevention status information to render the appropriate sharing warnings to the user on page load.

#### **3.2.5.322.1 Properties**

##### **3.2.5.322.1.1 Scalar Properties**

###### **3.2.5.322.1.1.1 ContainsConfidentialInfo**

**Type:** CSOM Boolean

**Accessibility:** Read Only

Returns the **ContainsConfidentialInfo** property (section [3.2.5.143.1.1.38](#)) of the **SP.Web**.

### **3.2.5.322.1.1.2 ContainsConfidentialInfoLearnMoreUrl**

**Type:** CSOM String

**Accessibility:** Read Only

Returns the Learn More link **URL** associated with the **ContainsConfidentialInfo** property (section [3.2.5.143.1.1.38](#)).

### **3.2.5.322.1.1.3 ExternalSharingTipsEnabled**

**Type:** CSOM Boolean

**Accessibility:** Read Only

Returns the **ExternalSharingTipsEnabled** property (section [3.2.5.119.1.1.28](#)) of the **SP.Site**.

### **3.2.5.322.1.1.4 ExternalSharingTipsLearnMoreUrl**

**Type:** CSOM String

**Accessibility:** Read Only

Returns the Learn More link URL associated with the **ExternalSharingTipsEnabled** property (section [3.2.5.119.1.1.28](#)).

## **3.2.5.322.1.2ObjectPath Properties**

None.

## **3.2.5.322.2 Methods**

### **3.2.5.322.2.1Scalar Methods**

None.

### **3.2.5.322.2.2ObjectPath Methods**

None.

## **3.2.5.323 Microsoft.SharePoint.Client.SpecialFolderType**

**ShortName:** SP.SpecialFolderType

**Flag:** false

Scenarios that are supported by the "Save to OneDrive" API.

### **3.2.5.323.1 Field Values**

#### **3.2.5.323.1.1Attachment**

**Value:** 0

The email attachment can be saved to OneDrive.

### **3.2.5.323.1.2Photos**

**Value:** 1

Photos can be saved to OneDrive.

### **3.2.5.323.1.3CameraRoll**

**Value:** 2

The camera roll can be saved to OneDrive.

### **3.2.5.323.1.4Music**

**Value:** 3

Music can be saved to OneDrive.

### **3.2.5.323.1.5Apps**

**Value:** 4

Apps can be saved to OneDrive.

### **3.2.5.323.1.6AppRoot**

**Value:** 5

The AppRoot can be saved to OneDrive.

### **3.2.5.323.1.7Desktop**

**Value:** 6

The Desktop folder can be saved to OneDrive.

### **3.2.5.323.1.8Documents**

**Value:** 7

The Documents folder can be saved to OneDrive.

### **3.2.5.323.1.9ScreenShots**

**Value:** 8

The Screenshots folder can be saved to OneDrive.

### **3.2.5.323.1.10 Templates**

**Value:** 9

The Templates folder can be saved to OneDrive.

### **3.2.5.324 Microsoft.SharePoint.Client.SPEffectiveInformationRightsManagementSettingsSource**

**ShortName:** SP.SPEffectiveInformationRightsManagementSettingsSource

**Flag:** false

Specifies the different effective **IRM** settings source for the file.

#### **3.2.5.324.1 Field Values**

##### **3.2.5.324.1.1 None**

**Value:** 0

No **IRM** settings.

##### **3.2.5.324.1.2 File**

**Value:** 1

The **IRM** settings are applied from the file.

##### **3.2.5.324.1.3 List**

**Value:** 2

The **IRM** settings are applied from the list containing the file.

##### **3.2.5.324.1.4 Rule**

**Value:** 3

The **IRM** settings are applied from a Data Loss Prevention rule.

### **3.2.5.325 Microsoft.SharePoint.Client.SPInvitationCreationResult**

**TypeId:** {56593357-67A4-41F7-B6D8-CCE2D1013AFE}

**ShortName:** SP.SPInvitationCreationResult

Specifies a result of adding an invitation.

#### **3.2.5.325.1 Properties**

##### **3.2.5.325.1.1 Scalar Properties**

###### **3.2.5.325.1.1.1 Email**

**Type:** **CSOM String**

**Accessibility:** Read Only

Specifies an email address of the invitation.

###### **3.2.5.325.1.1.2 InvitationLink**

**Type:** **CSOM String**



**Accessibility:** Read Only

Specifies an invitation link which was generated during invitation creation.

### **3.2.5.325.1.1.3 Succeeded**

**Type:** CSOM Boolean

**Accessibility:** Read Only

Specifies whether adding the invitation is successful.

### **3.2.5.325.1.2ObjectPath Properties**

None.

### **3.2.5.326 Microsoft.SharePoint.Client.SPMigrationJobStatus**

**TypeId:** {6F5420D8-0B1C-4212-9770-AD7A2E67B3C7}

**ShortName:** SP.SPMigrationJobStatus

Specifies the status of the migration job.

#### **3.2.5.326.1 Properties**

##### **3.2.5.326.1.1Scalar Properties**

###### **3.2.5.326.1.1.1 JobId**

**Type:** CSOM GUID

**Accessibility:** Read/Write

Gets or sets the ID of the migration job.

###### **3.2.5.326.1.1.2 JobState**

**Type:** Microsoft.SharePoint.Client.MigrationJobState

**Accessibility:** Read/Write

Gets or sets the status of the migration job.

##### **3.2.5.326.1.2ObjectPath Properties**

None.

#### **3.2.5.326.2 Methods**

##### **3.2.5.326.2.1Scalar Methods**

None.

##### **3.2.5.326.2.2ObjectPath Methods**

None.

### **3.2.5.327 Microsoft.SharePoint.Client.SPMigrationJobStatusCollection**

**TypeId:** {B584E7EA-7FC7-4DD7-AAA6-45A098E356A6}

**ShortName:** SP.SPMigrationJobStatusCollection

Specifies a status collection of the migration job.

#### **3.2.5.327.1 Properties**

##### **3.2.5.327.1.1 Scalar Properties**

None.

##### **3.2.5.327.1.2 ObjectPath Properties**

None.

#### **3.2.5.327.2 Methods**

##### **3.2.5.327.2.1 Scalar Methods**

None.

##### **3.2.5.327.2.2 ObjectPath Methods**

None.

### **3.2.5.328 Microsoft.SharePoint.Client.StorageMetrics**

**TypeId:** {33C58B88-4AF3-4EF1-A310-6BA3EF255058}

**ShortName:** SP.StorageMetrics

Represents storage-related metrics.

#### **3.2.5.328.1 Properties**

##### **3.2.5.328.1.1 Scalar Properties**

###### **3.2.5.328.1.1.1 LastModified**

**Type:** CSOM DateTime

**Accessibility:** Read Only

Last modified date for all the items under the corresponding folder.

###### **3.2.5.328.1.1.2 TotalFileCount**

**Type:** CSOM Int64

**Accessibility:** Read Only

Aggregate number of files within the corresponding folder and its sub-folders. Excludes versions, list item attachments, and non-customized documents.

###### **3.2.5.328.1.1.3 TotalFileStreamSize**

**Type:** CSOM Int64

**Accessibility:** Read Only

Aggregate stream size in bytes for all files under the corresponding folder and its sub-folders. Excludes version, metadata, list item attachment, and non-customized document sizes.

### 3.2.5.328.1.1.4 TotalSize

**Type:** CSOM Int64

**Accessibility:** Read Only

Aggregate of total sizes in bytes for all items under the corresponding folder and its sub-folders. Total size for a file/folder includes stream, version, and metadata sizes.

### 3.2.5.328.1.2 ObjectPath Properties

None.

### 3.2.5.328.2 Methods

#### 3.2.5.328.2.1 Scalar Methods

None.

#### 3.2.5.328.2.2 ObjectPath Methods

None.

### 3.2.5.329 Microsoft.SharePoint.Client.TenantAppInformation

**TypeId:** {52E6BC7D-825F-45B5-9F39-7A11723319DF}

**ShortName:** SP.TenantAppInformation

Specifies the information for the tenant-scoped app.

#### 3.2.5.329.1 Properties

##### 3.2.5.329.1.1 Scalar Properties

###### 3.2.5.329.1.1.1 AppPrincipalId

**Type:** CSOM String

**Accessibility:** Read Only

Specifies the **OAuth** Id for the tenant-scoped app.

###### 3.2.5.329.1.1.2 AppWebFullUrl

**Type:** CSOM String

**Accessibility:** Read Only

Specifies the web full **URL** for the tenant-scoped app.

### **3.2.5.329.1.1.3      CreationTime**

**Type:** CSOM DateTime

**Accessibility:** Read Only

Specifies the creation time for the tenant-scoped app.

### **3.2.5.329.1.1.4      IconAbsoluteUrl**

**Type:** CSOM String

**Accessibility:** Read Only

Specifies the absolute icon **URL** for the tenant-scoped app.

### **3.2.5.329.1.1.5      IconFallbackAbsoluteUrl**

**Type:** CSOM String

**Accessibility:** Read Only

Specifies the fallback icon **URL** for the tenant-scoped app.

### **3.2.5.329.1.1.6      Id**

**Type:** CSOM GUID

**Accessibility:** Read Only

Specifies the identifier for the tenant-scoped app.

### **3.2.5.329.1.1.7      LaunchUrl**

**Type:** CSOM String

**Accessibility:** Read Only

Specifies the launch **URL** for the tenant-scoped app.

### **3.2.5.329.1.1.8      PackageFingerprint**

**Type:** CSOM binary

**Accessibility:** Read Only

Specifies the package fingerprint for the tenant-scoped app.

### **3.2.5.329.1.1.9      ProductId**

**Type:** CSOM GUID

**Accessibility:** Read Only

Specifies the product ID for the tenant-scoped app.

### **3.2.5.329.1.1.10    RemoteAppUrl**

**Type:** CSOM String

**Accessibility:** Read Only

Specifies the remote host URL for the tenant-scoped app.

### **3.2.5.329.1.1.11 Status**

**Type:** Microsoft.SharePoint.Client.AppInstanceStatus

**Accessibility:** Read Only

Specifies the status for the tenant-scoped app.

### **3.2.5.329.1.1.12 Title**

**Type:** CSOM String

**Accessibility:** Read Only

Specifies the title for the tenant-scoped app.

### **3.2.5.329.1.2 ObjectPath Properties**

None.

## **3.2.5.330 Microsoft.SharePoint.Client.TenantAppInstance**

**TypeId:** {729F09B7-A266-4D40-8689-0A1490156244}

**ShortName:** SP.TenantAppInstance

Represents an instance of a tenant-scoped app for a given host web.

### **3.2.5.330.1 Properties**

#### **3.2.5.330.1.1 Scalar Properties**

##### **3.2.5.330.1.1.1 Id**

**Type:** CSOM GUID

**Accessibility:** Read Only

Specifies the unique identifier of this instance.

##### **3.2.5.330.1.1.2 SiteId**

**Type:** CSOM GUID

**Accessibility:** Read Only

Specifies the identifier of the **site collection** that contains the **site (2)** where this instance is installed.

##### **3.2.5.330.1.1.3 WebId**

**Type:** CSOM GUID

**Accessibility:** Read Only

Specifies the identifier of the **site (2)** where this instance is installed.

### **3.2.5.330.1.2ObjectPath Properties**

None.

### **3.2.5.330.2 Methods**

#### **3.2.5.330.2.1Scalar Methods**

None.

#### **3.2.5.330.2.2ObjectPath Methods**

None.

### **3.2.5.331 Microsoft.SharePoint.Client.TenantAppUtility**

**TypeId:** {A7E15A67-957E-459B-8903-E1E42FA52AB1}

**ShortName:** SP.TenantAppUtility

Specifies the tenant app related utility.

#### **3.2.5.331.1 Properties**

##### **3.2.5.331.1.1Scalar Properties**

None.

##### **3.2.5.331.1.2ObjectPath Properties**

None.

#### **3.2.5.331.2 Methods**

##### **3.2.5.331.2.1Scalar Methods**

###### **3.2.5.331.2.1.1 GetAppPermissionDescriptions**

This method is a **static CSOM method**.

**Return Type:** **CSOM array** of **CSOM String**

Gets the app permissions for the tenant-scoped app.

**Parameters:**

*web*: The web in which the tenant-scoped app is deployed.

Type: Microsoft.SharePoint.Client.Web

*tenantAppInstance*: The instance for the tenant app.

Type: Microsoft.SharePoint.Client.TenantAppInstance

###### **3.2.5.331.2.1.2 GetTenantAppInformationCollection**

This method is a **static CSOM method**.

**Return Type:** CSOM array of Microsoft.SharePoint.Client.TenantAppInformation

Gets information of tenant-scoped apps of a site.

**Parameters:**

*web*: The web in which the tenant-scoped app is deployed.

Type: Microsoft.SharePoint.Client.Web

*lcid*: The locale that is supported by the tenant apps.

Type: **CSOM Int32**

### 3.2.5.331.2.2 ObjectPath Methods

#### 3.2.5.331.2.2.1 GetAppDetails

This method is a **static CSOM method**.

**Return Type:** Microsoft.SharePoint.Packaging.AppDetails

Gets the app details for the tenant-scoped app.

**Parameters:**

*web*: The web in which the tenant-scoped app is deployed.

Type: Microsoft.SharePoint.Client.Web

*tenantAppInstance*: The instance for the tenant app.

Type: Microsoft.SharePoint.Client.TenantAppInstance

#### 3.2.5.331.2.2.2 GetAppIcon

This method is a **static CSOM method**.

**Return Type:** Microsoft.SharePoint.Packaging.AppIconInfo

Gets the icon information for the tenant scoped app.

**Parameters:**

*web*: The web in which the tenant-scoped app is deployed.

Type: Microsoft.SharePoint.Client.Web

*appInstanceId*: The app instance identifier.

Type: **CSOM GUID**

*packageFingerprint*: The app package fingerprint.

Type: **CSOM binary**

#### 3.2.5.331.2.2.3 GetTenantAppInstance

This method is a **static CSOM method**.

**Return Type:** Microsoft.SharePoint.Client.TenantAppInstance

Gets the instance for the tenant-scoped app.

**Parameters:**

*web*: The web in which the tenant-scoped app is deployed.

Type: Microsoft.SharePoint.Client.Web

*appInstance*: The app instance identifier.

Type: **CSOM GUID**

### **3.2.5.332 Microsoft.SharePoint.Client.TenantSettings**

**TypeId:** {E9A11C41-0667-4C14-A4A5-E0D6CF67F6FA}

**ShortName:** SP.TenantSettings

Specifies the tenant properties.

#### **3.2.5.332.1 Properties**

##### **3.2.5.332.1.1 Scalar Properties**

###### **3.2.5.332.1.1.1 CorporateCatalogUrl**

Type: **CSOM String**

**Accessibility:** Read Only

Specifies the **URL** of the corporate catalog **site collection**.

##### **3.2.5.332.1.2 ObjectPath Properties**

###### **3.2.5.332.1.2.1 Current**

Type: Microsoft.SharePoint.Client.TenantSettings

**Accessibility:** Read Only

Specifies the current instance for the **SP.TenantSettings**.

#### **3.2.5.332.2 Methods**

##### **3.2.5.332.2.1 Scalar Methods**

None.

##### **3.2.5.332.2.2 ObjectPath Methods**

None.

### **3.2.5.333 Microsoft.SharePoint.Client.UserResource**

**TypeId:** {2B2AFFEB-3CCD-4996-9864-211C960E647C}



**ShortName:** SP.UserResource

An object representing user-defined localizable resources.

### 3.2.5.333.1 Properties

#### 3.2.5.333.1.1 Scalar Properties

None.

#### 3.2.5.333.1.2 ObjectPath Properties

None.

### 3.2.5.333.2 Methods

#### 3.2.5.333.2.1 Scalar Methods

##### 3.2.5.333.2.1.1 GetValueForUICulture

**Return Type:** CSOM String

Returns the value of the resource for the requested culture. This falls back to the value specified for the web's UI culture.

**Parameters:**

*cultureName*: The culture for which value is requested.

Type: CSOM String

It MUST NOT be NULL. It MUST NOT be empty.

**Exceptions:**

Error Code	Error Type Name	Condition
- 2147024809	System.Globalization.CultureNotFoundException	<i>cultureName</i> doesn't correspond to a valid culture.

##### 3.2.5.333.2.1.2 SetValueForUICulture

**Return Type:** None

Sets the value of the resource for the requested culture. This method throws an exception if the culture is not enabled for the web.

**Parameters:**

*cultureName*: The culture for which the value is specified.

Type: CSOM String

It MUST NOT be NULL. It MUST NOT be empty.

*value*: The value of the resource in the requested culture.

Type: CSOM String

**Exceptions:**

Error Code	Error Type Name	Condition
- 2147024809	System.Globalization.CultureNotFoundException	<i>cultureName</i> doesn't correspond to a valid culture.

### 3.2.5.333.2.2ObjectPath Methods

None.

### 3.2.5.334 Microsoft.SharePoint.Client.UserResourceScope

**ShortName:** SP.UserResourceScope

**Flag:** false

The possible scopes for the SP.UserResource object.

#### 3.2.5.334.1 Field Values

##### 3.2.5.334.1.1Web

**Value:** 0

Resources scoped to the SP.Web.

##### 3.2.5.334.1.2List

**Value:** 1

Resources scoped to the SP.List.

### 3.2.5.335 Microsoft.SharePoint.Client.UserResourceType

**ShortName:** SP.UserResourceType

**Flag:** false

The possible types for SP.UserResource strings. This can be either single-line, or multiline.

#### 3.2.5.335.1 Field Values

##### 3.2.5.335.1.1SingleLine

**Value:** 0

Strings that have a width of less than 256 bytes.

##### 3.2.5.335.1.2MultiLine

**Value:** 1

Strings with a width of more than 256 bytes.

### **3.2.5.336 Microsoft.SharePoint.Client.UserSharingCapabilities**

**ShortName:** SP.UserSharingCapabilities

**Flag:** true

Describes the types of sharing actions that a user can perform on a document.

#### **3.2.5.336.1 Field Values**

##### **3.2.5.336.1.1 None**

**Value:** 0

The user cannot share.

##### **3.2.5.336.1.2 CanShareInternally**

**Value:** 1

The user can only share within the tenancy.

##### **3.2.5.336.1.3 CanShareExternally**

**Value:** 2

The user can share outside the tenancy by inviting external users.

##### **3.2.5.336.1.4 CanUseReadOnlyLink**

**Value:** 4

The user can retrieve an **anonymous access link** that provides read access, if one has already been created. If one has not been created, the user cannot create one.

##### **3.2.5.336.1.5 CanManageReadOnlyLink**

**Value:** 8

The user can retrieve an **anonymous access link** that provides read access, if one has already been created. If one has not been created, the user can create one.

##### **3.2.5.336.1.6 CanUseReadWriteLink**

**Value:** 16

The user can retrieve an **anonymous access link** that provides edit access, if one has already been created. If one has not been created, the user cannot create one.

##### **3.2.5.336.1.7 CanManageReadWriteLink**

**Value:** 32

The user can retrieve an **anonymous access link** that provides edit access, if one has already been created. If one has not been created, the user can create one.

##### **3.2.5.336.1.8 CanUseOrganizationReadOnlyLink**

**Value:** 64

The user can retrieve an **organization access link** that provides read access, if one has already been created. If one has not been created, the user cannot create one.

### **3.2.5.336.1.9 CanManageOrganizationReadOnlyLink**

**Value:** 128

The user can retrieve an **organization access link** that provides read access, if one has already been created. If one has not been created, the user can create one.

### **3.2.5.336.1.10 CanUseOrganizationReadWriteLink**

**Value:** 256

The user can retrieve an **organization access link** that provides edit access, if one has already been created. If one has not been created, the user cannot create one.

### **3.2.5.336.1.11 CanManageOrganizationReadWriteLink**

**Value:** 512

The user can retrieve an **organization access link** that provides edit access, if one has already been created. If one has not been created, the user can create one.

### **3.2.5.336.1.12 CanUsePeopleSharingReadOnlyLink**

**Value:** 1024

User can retrieve a **tokenized sharing link** that provides read access to a specified membership set, if one has already been created. If one has not been created, the user cannot create one.

### **3.2.5.336.1.13 CanManagePeopleSharingReadOnlyLink**

**Value:** 2048

User can retrieve a **tokenized sharing link** that provides read access to a specified membership set, if one has already been created. If one has not been created, the user can create one.

### **3.2.5.336.1.14 CanUsePeopleSharingReadWriteLink**

**Value:** 4096

User can retrieve a **tokenized sharing link** that provides edit access to a specified membership set, if one has already been created. If one has not been created, the user cannot create one.

### **3.2.5.336.1.15 CanManagePeopleSharingReadWriteLink**

**Value:** 8192

User can retrieve a **tokenized sharing link** that provides edit access to a specified membership set, if one has already been created. If one has not been created, the user can create one.

## **3.2.5.337 Microsoft.SharePoint.Client.Utilities.WopiProperties**

**TypeId:** {690C6ECD-195F-4ED8-B282-04DFDA883845}

**ShortName:** SP.Utilities.WopiProperties

Do not use. For internal use only.

## 3.2.5.337.1 Properties

### 3.2.5.337.1.1 Scalar Properties

#### 3.2.5.337.1.1.1 AccessToken

Type: **CSOM String**

Accessibility: Read Only

Do not use. For internal use only.

#### 3.2.5.337.1.1.2 AccessTokenTtl

Type: **CSOM Int64**

Accessibility: Read Only

Do not use. For internal use only.

#### 3.2.5.337.1.1.3 AppIconUrl

Type: **CSOM String**

Accessibility: Read Only

Do not use. For internal use only.

#### 3.2.5.337.1.1.4 ErrorMessageToDisplay

Type: **CSOM String**

Accessibility: Read Only

Do not use. For internal use only.

#### 3.2.5.337.1.1.5 RedirectUrl

Type: **CSOM String**

Accessibility: Read Only

Do not use. For internal use only.

#### 3.2.5.337.1.1.6 WebApplicationUrl

Type: **CSOM String**

Accessibility: Read Only

Do not use. For internal use only.

### 3.2.5.337.1.2 ObjectPath Properties

None.

## 3.2.5.337.2 Methods

### 3.2.5.337.2.1 Scalar Methods

None.

### 3.2.5.337.2.2ObjectPath Methods

None.

### 3.2.5.338 Microsoft.SharePoint.Packaging.AppDetails

**TypeId:** {393DBB05-A6C5-4159-83A7-DD70055AD640}

**ShortName:** Microsoft.SharePoint.Packaging.AppDetails

Specifies the detail properties for a **SharePoint Add-in**.

#### 3.2.5.338.1 Properties

##### 3.2.5.338.1.1Scalar Properties

###### 3.2.5.338.1.1.1 EulaUrl

**Type:** CSOM String

**Accessibility:** Read Only

Specifies the **URL** to get the **End User License Agreement (EULA)** information for the **SharePoint Add-in**.

###### 3.2.5.338.1.1.2 PrivacyUrl

**Type:** CSOM String

**Accessibility:** Read Only

Specifies the **URL** of the privacy statement for the **SharePoint Add-in**.

###### 3.2.5.338.1.1.3 Publisher

**Type:** CSOM String

**Accessibility:** Read Only

Specifies the publisher name for the **SharePoint Add-in**.

###### 3.2.5.338.1.1.4 ShortDescription

**Type:** CSOM String

**Accessibility:** Read Only

Specifies a short description for the **SharePoint Add-in**.

###### 3.2.5.338.1.1.5 SupportUrl

**Type:** CSOM String

**Accessibility:** Read Only

Specifies the **URL** of the support page for the **SharePoint Add-in**.

### **3.2.5.338.1.2ObjectPath Properties**

None.

### **3.2.5.338.2 Methods**

#### **3.2.5.338.2.1Scalar Methods**

None.

#### **3.2.5.338.2.2ObjectPath Methods**

None.

### **3.2.5.339 Microsoft.SharePoint.Packaging.AppIconInfo**

**TypeId:** {A6A203A3-6F7D-4430-B8EB-830D1FDE4AE8}

**ShortName:** Microsoft.SharePoint.Packaging.AppIconInfo

Specifies the icon information for a **SharePoint Add-in**.

### **3.2.5.339.1 Properties**

#### **3.2.5.339.1.1Scalar Properties**

##### **3.2.5.339.1.1.1 Content**

**Type:** **CSOM binary**

**Accessibility:** Read Only

Specifies the byte array of the icon.

##### **3.2.5.339.1.1.2 MimeType**

**Type:** **CSOM String**

**Accessibility:** Read Only

Specifies the **MIME type** of the icon content.

#### **3.2.5.339.1.2ObjectPath Properties**

None.

### **3.2.5.339.2 Methods**

#### **3.2.5.339.2.1Scalar Methods**

None.

#### **3.2.5.339.2.2ObjectPath Methods**

None.

### 3.2.5.340 Microsoft.SharePoint.WebControls.ModuleLink

**TypeId:** {6585CBBB-FB91-45E7-B687-08D8CD8FF94C}

**ShortName:** Microsoft.SharePoint.WebControls.ModuleLink

Takes a set of Asynchronous module definition (AMD) modules described in a resource manifest file, and generates the AMD loader configuration needed to link modules to the page.

#### 3.2.5.340.1 Properties

##### 3.2.5.340.1.1 Scalar Properties

None.

##### 3.2.5.340.1.2 ObjectPath Properties

None.

#### 3.2.5.340.2 Methods

##### 3.2.5.340.2.1 Scalar Methods

None.

##### 3.2.5.340.2.2 ObjectPath Methods

###### 3.2.5.340.2.2.1 GetResourceManifestInformation

This method is a **static CSOM method**.

**Return Type:** Microsoft.SharePoint.WebControls.ResourceManifestInformation

Gets the information for a resource manifest file.

**Parameters:**

*web*: The **site (2)** for retrieving the resource manifest file.

Type: Microsoft.SharePoint.Client.Web

*manifestName*: Specifies the resource manifest name.

Type: **CSOM String**

### 3.2.5.341 Microsoft.SharePoint.WebControls.ResourceManifestInformation

**TypeId:** {4FAA3FED-379C-4F9F-B0C7-FE0451DDAB7E}

**ShortName:** Microsoft.SharePoint.WebControls.ResourceManifestInformation

Represents the information for a resource manifest file.

#### 3.2.5.341.1 Properties

##### 3.2.5.341.1.1 Scalar Properties

###### 3.2.5.341.1.1.1 RequireJsScriptBlock



**Type:** CSOM String

**Accessibility:** Read Only

Literal script for client to configure the Asynchronous module definition (AMD) loader.

### **3.2.5.341.1.1.2 ScenarioMapping**

**Type:** CSOM dictionary

**Accessibility:** Read Only

Maps scenario name to comma-delimited list of Asynchronous module definition (AMD) module IDs.

### **3.2.5.341.1.2ObjectPath Properties**

None.

### **3.2.5.341.2 Methods**

#### **3.2.5.341.2.1Scalar Methods**

None.

#### **3.2.5.341.2.2ObjectPath Methods**

None.

### **3.2.5.342 Microsoft.SharePoint.Client.RecycleBinOrderBy**

**ShortName:** SP.RecycleBinOrderBy

**Flag:** false

Specifies the column for which to order a Recycle Bin query.

#### **3.2.5.342.1 Field Values**

##### **3.2.5.342.1.1Min**

**Value:** 0

Order by minimum size.

##### **3.2.5.342.1.2DefaultOrderBy**

**Value:** 0

Use default order.

##### **3.2.5.342.1.3Title**

**Value:** 0

Name column.

##### **3.2.5.342.1.4DirName**

**Value:** 1

Original Location column.

### **3.2.5.342.1.5 Author**

**Value:** 2

Created By column.

### **3.2.5.342.1.6 DeletedDate**

**Value:** 3

Order by the Deleted column, which specifies the date that the **Recycle Bin item** was deleted.

### **3.2.5.342.1.7 Size**

**Value:** 4

Size column.

### **3.2.5.342.1.8 DeletedBy**

**Value:** 5

Deleted By column.

### **3.2.5.342.1.9 None**

**Value:** 6

Ordering is not enforced. Can be used only for SPRecycleBinItemCollectionPosition.FirstPage.

### **3.2.5.342.1.10 Max**

**Value:** 6

Order by maximum size.

## **3.2.5.343 Microsoft.SharePoint.Client.Sharing.RemoveItemsFromSharedWithMeViewErrorCode**

**ShortName:** SP.Sharing.RemoveItemsFromSharedWithMeViewErrorCode

**Flag:** false

An error code representing what went wrong during the removal of an item from the 'Shared With Me' view.

### **3.2.5.343.1 Field Values**

#### **3.2.5.343.1.1 Success**

**Value:** 0

Operation was successful without any errors.

### 3.2.5.343.1.2InvalidListItem

**Value:** -1

Item URL was empty or null or couldn't find the list item specified by the URL.

### 3.2.5.343.1.3InvalidItemSharing

**Value:** -2

List item does not contain valid sharing information or item is not shared with current user.

### 3.2.5.343.1.4UnableToRemoveItem

**Value:** -3

Operation failed due to an unknown error.

## 3.2.5.344 Microsoft.SharePoint.Client.Sharing.SharedWithMeViewItemRemovalResult

**TypeId:** {418572C1-2347-4190-90BD-30A19A251C11}

**ShortName:** SP.Sharing.SharedWithMeViewItemRemovalResult

An object that contains the result of calling the API to remove an item from a user's 'Shared With Me' view.

### 3.2.5.344.1 Properties

#### 3.2.5.344.1.1Scalar Properties

##### 3.2.5.344.1.1.1 ErrorCode

**Type:** Microsoft.SharePoint.Client.Sharing.RemoveItemsFromSharedWithMeViewErrorCode

**Accessibility:** Read Only

Error code if the operation was not successful.

##### 3.2.5.344.1.1.2 ErrorMessage

**Type:** CSOM String

**Accessibility:** Read Only

Description of the error that happened if the operation was not successful.

##### 3.2.5.344.1.1.3 Success

**Type:** CSOM Boolean

**Accessibility:** Read Only

Indicates whether the overall operation succeeded.

#### 3.2.5.344.1.2ObjectPath Properties

None.

### 3.2.5.345 Microsoft.SharePoint.ClientSideComponent.SPClientSideComponentQueryResult

**TypeId:** {AAB91EFE-8E87-4B0F-8DCB-51F556F9AC01}

**ShortName:** Microsoft.SharePoint.ClientSideComponent.SPClientSideComponentQueryResult

This object contains information about the requested component and the status of the query that was used to retrieve the component.

#### 3.2.5.345.1 Properties

##### 3.2.5.345.1.1 Scalar Properties

###### 3.2.5.345.1.1.1 ComponentType

**Type:** Microsoft.SharePoint.ClientSideComponent.SPClientSideComponentType

**Accessibility:** Read/Write

Specifies the type of component. See section [3.2.5.347](#) for more information.

###### 3.2.5.345.1.1.2 Id

**Type:** CSOM String

**Accessibility:** Read/Write

The unique identifier of a component. It MUST be a valid GUID string.

###### 3.2.5.345.1.1.3 Manifest

**Type:** CSOM String

**Accessibility:** Read/Write

The manifest of a component.

###### 3.2.5.345.1.1.4 ManifestType

**Type:** Microsoft.SharePoint.ClientSideComponent.SPClientSideManifestType

**Accessibility:** Read/Write

Specifies the type of the manifest. The manifest type MUST be Unknown or Component.

###### 3.2.5.345.1.1.5 Name

**Type:** CSOM String

**Accessibility:** Read/Write

The name of the component.

###### 3.2.5.345.1.1.6 Status

**Type:** Microsoft.SharePoint.ClientSideComponent.SPClientSideQueryStatus

**Accessibility:** Read/Write

Specifies the result of the query used to retrieve components.

### **3.2.5.345.1.2ObjectPath Properties**

None.

### **3.2.5.346 Microsoft.SharePoint.ClientSideComponent.SPClientSideComponentType**

**ShortName:** Microsoft.SharePoint.ClientSideComponent.SPClientSideComponentType

**Flag:** false

Describes the requested component's type.

#### **3.2.5.346.1 Field Values**

##### **3.2.5.346.1.1Unknown**

**Value:** 0

Specifies an unknown component type.

##### **3.2.5.346.1.2WebPart**

**Value:** 1

Specifies a client-side web part.

##### **3.2.5.346.1.3Application**

**Value:** 2

Specifies the application responsible for hosting webparts.

##### **3.2.5.346.1.4Library**

**Value:** 3

Specifies a library of reusable JavaScript code and resources.

##### **3.2.5.346.1.5Extension**

**Value:** 4

Specifies a client-side extension, which is a plug-in component that customizes or augments the functionality of a client-side application.

### **3.2.5.347 Microsoft.SharePoint.ClientSideComponent.SPClientSideManifestType**

**ShortName:** Microsoft.SharePoint.ClientSideComponent.SPClientSideManifestType

**Flag:** false

Specifies the manifest type.

#### **3.2.5.347.1 Field Values**

##### **3.2.5.347.1.1Unknown**

**Value:** 0

Specifies an unknown manifest type.

### **3.2.5.347.1.2Component**

**Value:** 1

Specifies a component type manifest.

### **3.2.5.347.1.3Container**

**Value:** 2

Specifies a container type manifest.

## **3.2.5.348 Microsoft.SharePoint.ClientSideComponent.SPClientSideQueryStatus**

**ShortName:** Microsoft.SharePoint.ClientSideComponent.SPClientSideQueryStatus

**Flag:** false

Specifies the status of a query to retrieve SPClientSideComponentQueryResult (section [3.2.5.345](#)).

### **3.2.5.348.1 Field Values**

#### **3.2.5.348.1.1Success**

**Value:** 0

The component was found with no errors.

#### **3.2.5.348.1.2ErrorNotFound**

**Value:** 1

The component was not found.

#### **3.2.5.348.1.3ErrorDisabled**

**Value:** 2

The component was found but disabled.

#### **3.2.5.348.1.4ErrorInvalidManifest**

**Value:** 3

The component was found but had an invalid manifest.

#### **3.2.5.348.1.5ErrorCustomScriptDisabled**

**Value:** 4

The component was not retrieved because custom scripts are disabled on the **Site (2)** .

#### **3.2.5.348.1.6ErrorFeatureNotEnabled**

**Value:** 5

The component was not retrieved because an associated **feature** is not enabled on the **Site (2)**.

### **3.2.5.349 Microsoft.SharePoint.Activities.ActivityCapabilities**

**TypeId:** {9B700F82-8575-4600-9A6C-EBDB2F7F2759}

**ShortName:** Microsoft.SharePoint.Activities.ActivityCapabilities

Microsoft.SharePoint.Activities.ActivityCapabilities is not applicable. [.<240>](#)

#### **3.2.5.349.1 Properties**

##### **3.2.5.349.1.1 Scalar Properties**

None.

##### **3.2.5.349.1.2 ObjectPath Properties**

None.

### **3.2.5.350 Microsoft.SharePoint.Activities.ActivityClientIdentity**

**TypeId:** {4B113A1C-620E-491A-8DFB-882B22516AC1}

**ShortName:** Microsoft.SharePoint.Activities.ActivityClientIdentity

Microsoft.SharePoint.Activities.ActivityClientIdentity is not applicable. [.<241>](#)

#### **3.2.5.350.1 Properties**

##### **3.2.5.350.1.1 Scalar Properties**

None.

##### **3.2.5.350.1.2 ObjectPath Properties**

None.

### **3.2.5.351 Microsoft.SharePoint.Activities.ActivityClientRequest**

**TypeId:** {65927107-94A9-49B6-AD5C-ED3661B580EB}

**ShortName:** Microsoft.SharePoint.Activities.ActivityClientRequest

Microsoft.SharePoint.Activities.ActivityClientRequest is not applicable. [.<242>](#)

#### **3.2.5.351.1 Properties**

##### **3.2.5.351.1.1 Scalar Properties**

None.

##### **3.2.5.351.1.2 ObjectPath Properties**

None.

### 3.2.5.352 Microsoft.SharePoint.Activities.ActivityClientResponse

**TypeId:** {3356F279-C9C6-430D-AF57-8126E82B8BC5}

**ShortName:** Microsoft.SharePoint.Activities.ActivityClientResponse

Microsoft.SharePoint.Activities.ActivityClientResponse is not applicable. [<243>](#)

#### 3.2.5.352.1 Properties

##### 3.2.5.352.1.1 Scalar Properties

None.

##### 3.2.5.352.1.2 ObjectPath Properties

None.

### 3.2.5.353 Microsoft.SharePoint.Activities.CommentFacet

**TypeId:** {35CC064A-D3D3-4E79-BF4E-6EC85437AE70}

**ShortName:** Microsoft.SharePoint.Activities.CommentFacet

Microsoft.SharePoint.Activities.CommentFacet is not applicable. [<244>](#)

#### 3.2.5.353.1 Properties

##### 3.2.5.353.1.1 Scalar Properties

###### 3.2.5.353.1.1.1 commentText

**Type:** CSOM String

**Accessibility:** Read/Write

Gets or sets the comment text.

###### 3.2.5.353.1.1.2 parentAuthor

**Type:** Microsoft.SharePoint.Activities.ActivityClientIdentity

**Accessibility:** Read/Write

Gets or sets the parent author.

##### 3.2.5.353.1.2 ObjectPath Properties

None.

### 3.2.5.354 Microsoft.SharePoint.Activities.MentionFacet

**TypeId:** {D4B454B0-FA53-4C71-A34B-E349EDA5ED1D}

**ShortName:** Microsoft.SharePoint.Activities.MentionFacet

A class representing an "at mention" (sometimes referred to as @mention) facet [<245>](#)



### 3.2.5.354.1 Properties

#### 3.2.5.354.1.1 Scalar Properties

None.

#### 3.2.5.354.1.2 ObjectPath Properties

None.

### 3.2.5.355 Microsoft.SharePoint.Activities.RevisionInfo

**TypeId:** {93DC3A83-4670-4222-89BB-219F0280D1B9}

**ShortName:** Microsoft.SharePoint.Activities.RevisionInfo

A class representing information about a revision. [<246>](#)

#### 3.2.5.355.1 Properties

##### 3.2.5.355.1.1 Scalar Properties

None.

##### 3.2.5.355.1.2 ObjectPath Properties

None.

### 3.2.5.356 Microsoft.SharePoint.Activities.RevisionSetFacet

**TypeId:** {A0E5DE75-4D0A-40EC-A5B3-A150696207D9}

**ShortName:** Microsoft.SharePoint.Activities.RevisionSetFacet

A class representing RevisionSet facet. [<247>](#)

#### 3.2.5.356.1 Properties

##### 3.2.5.356.1.1 Scalar Properties

None.

##### 3.2.5.356.1.2 ObjectPath Properties

None.

### 3.2.5.357 Microsoft.SharePoint.Activities.SPActivityEntitySet

**TypeId:** {073124B3-2993-4C09-9289-D3ADEFB93B87}

**ShortName:** Microsoft.SharePoint.Activities.SPActivityEntitySet

Microsoft.SharePoint.Activities.SPActivityEntitySet is not applicable. [<248>](#)

#### 3.2.5.357.1 Properties

### 3.2.5.357.1.1 Scalar Properties

None.

### 3.2.5.357.1.2 ObjectPath Properties

None.

## 3.2.5.357.2 Methods

### 3.2.5.357.2.1 Scalar Methods

None.

### 3.2.5.357.2.2 ObjectPath Methods

None.

## 3.2.5.358 Microsoft.SharePoint.Activities.SPActivityResponseStatus

**ShortName:** Microsoft.SharePoint.Activities.SPActivityResponseStatus

**Flag:** false

Microsoft.SharePoint.Activities.SPActivityResponseStatus enumeration is not applicable. [<249>](#)

### 3.2.5.358.1 Field Values

None.

## 3.2.5.359 Microsoft.SharePoint.Administration.AppSource

**ShortName:** Microsoft.SharePoint.Administration.AppSource

**Flag:** false

The source of the App package.

### 3.2.5.359.1 Field Values

#### 3.2.5.359.1.1 InvalidSource

**Value:** 0

This value indicates an internal product error, and SHOULD NOT occur in usage.

#### 3.2.5.359.1.2 Marketplace

**Value:** 1

Indicates that the App was installed off the Marketplace.

#### 3.2.5.359.1.3 CorporateCatalog

**Value:** 2

Indicates that the App came from the corporate gallery.

### 3.2.5.359.1.4 DeveloperSite

**Value:** 3

Indicates that the App came from the Developer Site.

### 3.2.5.359.1.5 ObjectModel

**Value:** 4

Indicates that the App was loaded via OM.

### 3.2.5.359.1.6 RemoteObjectModel

**Value:** 5

Indicates that the App was uploaded via CSOM.

### 3.2.5.359.1.7 SiteCollectionCorporateCatalog

**Value:** 6

Indicates that the App came from a site collection corporate gallery.

## 3.2.5.360 Microsoft.SharePoint.ApplicationPages.ClientPickerQuery.PeoplePickerQuerySettings

**TypeId:** {836910B9-5DD8-4CDB-9863-4E7154DE92D2}

**ShortName:** SP.UI.ApplicationPages.PeoplePickerQuerySettings

Represents additional settings for the **principal** query.

### 3.2.5.360.1 Properties

#### 3.2.5.360.1.1 Scalar Properties

##### 3.2.5.360.1.1.1 ExcludeAllUsersOnTenantClaim

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Specifies whether the all users on tenant claim provider is excluded or not from the **principal** query.

##### 3.2.5.360.1.1.2 IsSharing

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Specifies if the **principal** query is for sharing scenario or not.

#### 3.2.5.360.1.2 ObjectPath Properties

None.

### 3.2.5.361 Microsoft.SharePoint.ApplicationPages.ClientPickerQuery.PickerEntityInformation

**TypeId:** {2285517C-0162-4825-B2DD-87469EAE3085}

**ShortName:** SP.UI.ApplicationPages.PickerEntityInformation

Represents additional information about the **principal**.

#### 3.2.5.361.1 Properties

##### 3.2.5.361.1.1 Scalar Properties

###### 3.2.5.361.1.1.1 Entity

**Type:** Microsoft.SharePoint.ApplicationPages.ClientPickerQuery.PickerEntityInformationRequest

**Accessibility:** Read Only

The **principal** for which information is being requested.

###### 3.2.5.361.1.1.2 TotalMemberCount

**Type:** CSOM Int32

**Accessibility:** Read Only

The count of members in a group. Valid when the **principal** is a SharePoint group or a **security group**.

##### 3.2.5.361.1.2 ObjectPath Properties

None.

#### 3.2.5.361.2 Methods

##### 3.2.5.361.2.1 Scalar Methods

None.

##### 3.2.5.361.2.2 ObjectPath Methods

None.

### 3.2.5.362 Microsoft.SharePoint.ApplicationPages.ClientPickerQuery.PickerEntityInformationRequest

**TypeId:** {892C6B6A-8E53-4E91-8957-67846F7545E8}

**ShortName:** SP.UI.ApplicationPages.PickerEntityInformationRequest

Represents a request for **GetPickerEntityInformation** (section [3.2.5.223.2.2.1](#))

#### 3.2.5.362.1 Properties

##### 3.2.5.362.1.1 Scalar Properties

### 3.2.5.362.1.1.1 EmailAddress

**Type:** CSOM String

**Accessibility:** Read/Write

Gets or sets the email address of the **principal**.

### 3.2.5.362.1.1.2 GroupId

**Type:** CSOM Int32

**Accessibility:** Read/Write

Gets or sets the SharePoint group Id.

### 3.2.5.362.1.1.3 Key

**Type:** CSOM String

**Accessibility:** Read/Write

Gets or sets the identifier of the **principal**.

### 3.2.5.362.1.1.4 PrincipalType

**Type:** Microsoft.SharePoint.Client.Utilities.PrincipalType

**Accessibility:** Read/Write

Gets or sets the type of the **principal**.

## 3.2.5.362.1.2 ObjectPath Properties

None.

## 3.2.5.363 Microsoft.SharePoint.Client.Alert

**TypeId:** {004DAA6C-ACC5-48FC-877A-2604A2CB3358}

**ShortName:** SP.Alert

Represents an alert, which generates periodic e-mail notifications sent to a user about the list, list item, document, or document library to which the alert applies. SP.Alert provides information about the alert, such as which alert template is used, the alert frequency, and the UserID of the user who created the alert.

The AlertTime, ItemID, ListID and ListUrl properties are not included in the **default scalar property set** for this type.

### 3.2.5.363.1 Properties

#### 3.2.5.363.1.1 Scalar Properties

##### 3.2.5.363.1.1.1 AlertFrequency

**Type:** Microsoft.SharePoint.Client.AlertFrequency

**Accessibility:** Read/Write

Gets or sets the time interval for sending the alert.

#### **3.2.5.363.1.1.2      AlertTemplateName**

**Type:** CSOM String

**Accessibility:** Read Only

Gets the string representing the alert template name.

#### **3.2.5.363.1.1.3      AlertTime**

**Type:** CSOM DateTime

**Accessibility:** Read/Write

Gets or sets the date and time for sending the alert.

#### **3.2.5.363.1.1.4      AlertType**

**Type:** Microsoft.SharePoint.Client.AlertType

**Accessibility:** Read Only

Gets the type of object to which the alert applies, which can be a list or document library, a list item or document, or a custom object.

#### **3.2.5.363.1.1.5      AlwaysNotify**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Gets or sets a Boolean value that causes daily and weekly alerts to trigger, even if there is no matching event.

#### **3.2.5.363.1.1.6      DeliveryChannels**

**Type:** Microsoft.SharePoint.Client.AlertDeliveryChannel

**Accessibility:** Read/Write

The DeliveryChannels of the alert, could be any combination of Email, Sms.

#### **3.2.5.363.1.1.7      EventType**

**Type:** Microsoft.SharePoint.Client.AlertEventType

**Accessibility:** Read/Write

Gets or sets the type of event to which the alert applies.

#### **3.2.5.363.1.1.8      Filter**

**Type:** CSOM String

**Accessibility:** Read/Write

Gets or sets the syntax query in Collaborative Application Markup Language (CAML) for a filter to apply to the alert.

### **3.2.5.363.1.1.9 ID**

**Type:** CSOM GUID

**Accessibility:** Read Only

Gets the GUID that identifies the alert.

### **3.2.5.363.1.1.10 ItemID**

**Type:** CSOM Int32

**Accessibility:** Read Only

Gets the integer that identifies the list item or document to which an alert applies in the parent collection of list items.

### **3.2.5.363.1.1.11 ListID**

**Type:** CSOM GUID

**Accessibility:** Read Only

Gets the GUID of the list or document library to which the alert applies.

### **3.2.5.363.1.1.12 ListUrl**

**Type:** CSOM String

**Accessibility:** Read Only

Gets the site-relative URL of the list to which the alert applies.

### **3.2.5.363.1.1.13 Properties**

**Type:** CSOM dictionary

**Accessibility:** Read Only

Properties is of type SPPropertyBag which inherits from StringDictionary. This new property is meant to allow access to the property bag via CSOM.

### **3.2.5.363.1.1.14 Status**

**Type:** Microsoft.SharePoint.Client.AlertStatus

**Accessibility:** Read/Write

Gets or sets the status of the alert.

### **3.2.5.363.1.1.15 Title**

**Type:** CSOM String

**Accessibility:** Read/Write

Gets or sets the title of the alert as displayed in the user interface.

### **3.2.5.363.1.1.16 UserId**

**Type:** CSOM Int32

**Accessibility:** Read Only

Gets the ID of the user who created the alert.

### 3.2.5.363.1.2 ObjectPath Properties

#### 3.2.5.363.1.2.1 AllProperties

**Type:** Microsoft.SharePoint.Client.PropertyValues

**Accessibility:** Read Only

Gets a collection of all the properties for the alert.

#### 3.2.5.363.1.2.2 Item

**Type:** Microsoft.SharePoint.Client.ListItem

**Accessibility:** Read Only

Gets the list item or document to which the alert applies.

#### 3.2.5.363.1.2.3 List

**Type:** Microsoft.SharePoint.Client.List

**Accessibility:** Read Only

Gets the list or document library to which the alert applies.

#### 3.2.5.363.1.2.4 User

**Type:** Microsoft.SharePoint.Client.User

**Accessibility:** Read Only

Gets a user object representing the user who created the alert.

### 3.2.5.363.2 Methods

#### 3.2.5.363.2.1 Scalar Methods

##### 3.2.5.363.2.1.1 UpdateAlert

**Return Type:** None

Commits the changes to the the alert properties in the database.

**Parameters:** None

#### 3.2.5.363.2.2 ObjectPath Methods

None.

### 3.2.5.364 Microsoft.SharePoint.Client.AlertCollection

**TypeId:** {86531F9B-B741-453D-96FC-5F05F038000A}



**ShortName:** SP.AlertCollection

Represents a collection of SP.Alert objects. The SP.AlertCollection is available as a property of either SP.Web or SP.User.

### 3.2.5.364.1 Properties

#### 3.2.5.364.1.1 Scalar Properties

None.

#### 3.2.5.364.1.2 ObjectPath Properties

None.

### 3.2.5.364.2 Methods

#### 3.2.5.364.2.1 Scalar Methods

##### 3.2.5.364.2.1.1 Add

**Return Type:** CSOM GUID

Add an SP.Alert to SP.AlertCollection based on the given alertCreationInformation

**Parameters:**

*alertCreationInformation:* Contains the properties used to create a new SP.Alert.

Type: Microsoft.SharePoint.Client.AlertCreationInformation

It MUST NOT be NULL.

##### 3.2.5.364.2.1.2 Contains

**Return Type:** CSOM Boolean

Returns true if the given alert exists in the alert collection. False otherwise.

**Parameters:**

*idAlert:* The Id of the alert to search.

Type: CSOM GUID

##### 3.2.5.364.2.1.3 DeleteAlert

**Return Type:** None

Deletes the given alert.

**Parameters:**

*idAlert:* The Id of the alert to delete.

Type: CSOM GUID

##### 3.2.5.364.2.1.4 DeleteAlertAtIndex

**Return Type:** None

Deletes the alert based on the given index.

**Parameters:**

*index:* A 32-bit integer that is greater than or equal to 0 and less than the count of the alert in the collection. Specifies the index of the alert in the collection.

Type: **CSOM Int32**

### 3.2.5.364.2.2 ObjectPath Methods

#### 3.2.5.364.2.2.1 GetById

**Return Type:** Microsoft.SharePoint.Client.Alert

Gets an alert based on the Id.

**Parameters:**

*idAlert:* The Id of the alert to get.

Type: **CSOM GUID**

### 3.2.5.365 Microsoft.SharePoint.Client.AlertCreationInformation

**TypeId:** {F0C12E8E-54F5-4E31-B015-F4F824EEA024}

**ShortName:** SP.AlertCreationInformation

An object that contain the properties used to create a new SP.Alert

#### 3.2.5.365.1 Properties

##### 3.2.5.365.1.1 Scalar Properties

###### 3.2.5.365.1.1.1 AlertFrequency

**Type:** Microsoft.SharePoint.Client.AlertFrequency

**Accessibility:** Read/Write

Gets or sets the time interval for sending the alert.

###### 3.2.5.365.1.1.2 AlertTemplateName

**Type:** **CSOM String**

**Accessibility:** Read/Write

Gets or sets the name of the alert template.

###### 3.2.5.365.1.1.3 AlertTime

**Type:** **CSOM DateTime**

**Accessibility:** Read/Write

Gets or sets the time the alert triggers.

#### **3.2.5.365.1.1.4     AlertType**

**Type:** Microsoft.SharePoint.Client.AlertType

**Accessibility:** Read/Write

Gets or sets the alert type.

#### **3.2.5.365.1.1.5     AlwaysNotify**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Gets or sets whether to notify.

#### **3.2.5.365.1.1.6     DeliveryChannels**

**Type:** Microsoft.SharePoint.Client.AlertDeliveryChannel

**Accessibility:** Read/Write

Gets or sets the delivery channel.

#### **3.2.5.365.1.1.7     EventType**

**Type:** Microsoft.SharePoint.Client.AlertEventType

**Accessibility:** Read/Write

Gets or sets the event type to alert on.

#### **3.2.5.365.1.1.8     EventTypeBitmask**

**Type:** CSOM Int32

**Accessibility:** Read/Write

Gets or sets the event type bit mask.

#### **3.2.5.365.1.1.9     Filter**

**Type:** CSOM String

**Accessibility:** Read/Write

Gets or sets the syntax query in Collaborative Application Markup Language (CAML) for a filter to apply to the alert.

#### **3.2.5.365.1.1.10    Properties**

**Type:** CSOM dictionary

**Accessibility:** Read/Write

Gets or sets additional alert properties.

#### **3.2.5.365.1.1.11    Status**

**Type:** Microsoft.SharePoint.Client.AlertStatus

**Accessibility:** Read/Write

Gets or sets the alert status.

### **3.2.5.365.1.1.12 Title**

**Type:** CSOM String

**Accessibility:** Read/Write

Gets or sets the alert title.

## **3.2.5.365.1.2ObjectPath Properties**

### **3.2.5.365.1.2.1 Item**

**Type:** Microsoft.SharePoint.Client.ListItem

**Accessibility:** Read/Write

Gets or sets the path of the object to alert on.

### **3.2.5.365.1.2.2 List**

**Type:** Microsoft.SharePoint.Client.List

**Accessibility:** Read/Write

Gets or sets the Sharepoint list the alert is in.

### **3.2.5.365.1.2.3 User**

**Type:** Microsoft.SharePoint.Client.User

**Accessibility:** Read/Write

Gets or sets the user that owns the alert.

It MUST NOT be NULL.

## **3.2.5.366 Microsoft.SharePoint.Client.AlertDeliveryChannel**

**ShortName:** SP.AlertDeliveryChannel

**Flag:** false

Gets or sets the delivery channel.

### **3.2.5.366.1 Field Values**

#### **3.2.5.366.1.1Email**

**Value:** 1

Send the alert via email.

#### **3.2.5.366.1.2Sms**

**Value:** 2

Send the alert via Sms text.

### **3.2.5.367 Microsoft.SharePoint.Client.AlertEventType**

**ShortName:** SP.AlertEventType

**Flag:** false

Specifies the type of event for a list, list item, document, or document library to which an alert responds.

#### **3.2.5.367.1 Field Values**

##### **3.2.5.367.1.1AddObject**

**Value:** 1

Additions to the list or list item.

##### **3.2.5.367.1.2ModifyObject**

**Value:** 2

All changes made in a list or list item.

##### **3.2.5.367.1.3DeleteObject**

**Value:** 4

Deletion of a list or list item.

##### **3.2.5.367.1.4Discussion**

**Value:** 4080

Changes in Web discussions.

##### **3.2.5.367.1.5All**

**Value:** -1

All events pertaining to the list or list item.

### **3.2.5.368 Microsoft.SharePoint.Client.AlertFrequency**

**ShortName:** SP.AlertFrequency

**Flag:** false

The SP.AlertFrequency enumeration specifies the time interval for sending an alert about changes to a specific list, list item, document library, or document.

#### **3.2.5.368.1 Field Values**

##### **3.2.5.368.1.1Immediate**

**Value:** 0

Send immediately when the list or list item changes.

### **3.2.5.368.1.2Daily**

**Value:** 1

Send daily.

### **3.2.5.368.1.3Weekly**

**Value:** 2

Send weekly.

## **3.2.5.369 Microsoft.SharePoint.Client.AlertStatus**

**ShortName:** SP.AlertStatus

**Flag:** false

Specifies the status of an alert.

### **3.2.5.369.1 Field Values**

#### **3.2.5.369.1.1On**

**Value:** 0

The alert is implemented.

#### **3.2.5.369.1.2Off**

**Value:** 1

The alert is not implemented.

#### **3.2.5.369.1.3Error**

**Value:** 2

The alert is not functional.

## **3.2.5.370 Microsoft.SharePoint.Client.AlertType**

**ShortName:** SP.AlertType

**Flag:** false

Specifies the type of item that an alert applies to.

### **3.2.5.370.1 Field Values**

#### **3.2.5.370.1.1List**

**Value:** 0

Applies to a list.

### **3.2.5.370.1.2Item**

**Value:** 1

Applies to a list item.

### **3.2.5.370.1.3Custom**

**Value:** 2

Applies to a custom object.

## **3.2.5.371 Microsoft.SharePoint.Client.AnonymousLinkType**

**ShortName:** SP.AnonymousLinkType

**Flag:** false

Indicates whether an anonymous link (also known as share-by-link) is included in an invitation, and if so, what permissions are granted via that link. The anonymous link will be created once the invitation is created.

### **3.2.5.371.1 Field Values**

#### **3.2.5.371.1.1None**

**Value:** 0

No anonymous link is included.

#### **3.2.5.371.1.2View**

**Value:** 1

A view only anonymous link is included.

#### **3.2.5.371.1.3Edit**

**Value:** 2

A view/edit anonymous link is included.

## **3.2.5.372 Microsoft.SharePoint.Client.APIHubConnector**

**TypeId:** {95A3C720-F6C5-4979-80AD-42EE585CE0D0}

**ShortName:** SP.APIHubConnector

Contains operations used in SharePoint connector serving Flow, PowerApps and LogicApps services.

### **3.2.5.372.1 Properties**

#### **3.2.5.372.1.1Scalar Properties**

None.

### 3.2.5.372.1.2 ObjectPath Properties

None.

### 3.2.5.372.2 Methods

#### 3.2.5.372.2.1 Scalar Methods

None.

#### 3.2.5.372.2.2 ObjectPath Methods

##### 3.2.5.372.2.2.1 CreateListItem

This method is a **static CSOM method**.

**Return Type:** Microsoft.SharePoint.Client.ConnectorResult

Creates a list item in the list.

**Parameters:**

*listName:* List title or ID

Type: **CSOM String**

*itemData:* JSON representation of the new item.

Type: CSOM String

##### 3.2.5.372.2.2.2 DeleteListItem

This method is a **static CSOM method**.

**Return Type:** Microsoft.SharePoint.Client.ConnectorResult

Deletes an item in the list.

**Parameters:**

*listName:* List title or ID

Type: **CSOM String**

*itemId:* List item ID.

Type: CSOM String

##### 3.2.5.372.2.2.3 GetDeletedListItems

This method is a **static CSOM method**.

**Return Type:** Microsoft.SharePoint.Client.ConnectorResult

Returns deleted items in the list.

**Parameters:**

*listName:* List title or ID.

Type: **CSOM String**



*folderPath*: Optional path of the folder to limit the scope of operation.

Type: Microsoft.SharePoint.Client.ResourcePath

*referrer*: URL of the original request to the connector.

Type: CSOM String

*callback*: URL for webhook subscription.

Type: CSOM String

#### **3.2.5.372.2.2.4 GetEntities**

This method is a **static CSOM method**.

**Return Type:** Microsoft.SharePoint.Client.ConnectorResult

Returns a list of fields of certain type in the list.

##### **Parameters:**

*listName*: List title or ID

Type: **CSOM String**

*entityType*: Type of fields to return.

Type: CSOM String

#### **3.2.5.372.2.2.5 GetEntityValues**

This method is a **static CSOM method**.

**Return Type:** Microsoft.SharePoint.Client.ConnectorResult

Returns a list of reference choices for a reference-based field.

##### **Parameters:**

*listName*: List title or ID.

Type: **CSOM String**

*fieldId*: ID of the reference-based field.

Type: CSOM String

*queryOptions*: Query options to be applied to reference choices.

Type: CSOM String

Only supports \$search option

#### **3.2.5.372.2.2.6 GetListItem**

This method is a **static CSOM method**.

**Return Type:** Microsoft.SharePoint.Client.ConnectorResult

Returns item data for the list item.

**Parameters:**

*listName*: List title or ID.

Type: **CSOM String**

*itemId*: List item ID

Type: CSOM String

**3.2.5.372.2.2.7 GetListItems**

This method is a **static CSOM method**.

**Return Type:** Microsoft.SharePoint.Client.ConnectorResult

Returns a list of items in the list.

**Parameters:**

*listName*: List title or ID.

Type: **CSOM String**

*queryOptions*: Query options to be applied to list items query.

Type: CSOM String

**3.2.5.372.2.2.8 GetNewListItems**

This method is a **static CSOM method**.

**Return Type:** Microsoft.SharePoint.Client.ConnectorResult

Returns created items in the list.

**Parameters:**

*listName*: List title or ID.

Type: **CSOM String**

*folderPath*: Optional path of the folder to limit the scope of operation.

Type: Microsoft.SharePoint.Client.ResourcePath

*referrer*: URL of the original request to the connector.

Type: CSOM String

*callback*: URL for webhook subscription.

Type: CSOM String

**3.2.5.372.2.2.9 GetTableMetadata**

This method is a **static CSOM method**.

**Return Type:** Microsoft.SharePoint.Client.ConnectorResult

Returns list schema.

**Parameters:**

*listName*: List title or ID

Type: **CSOM String**

**3.2.5.372.2.2.10 GetTables**

This method is a **static CSOM method**.

**Return Type:** Microsoft.SharePoint.Client.ConnectorResult

Returns supported lists.

**Parameters:** None

**3.2.5.372.2.2.11 GetUpdatedListItems**

This method is a **static CSOM method**.

**Return Type:** Microsoft.SharePoint.Client.ConnectorResult

Returns created or modified items in the list.

**Parameters:**

*listName*: List title or ID.

Type: **CSOM String**

*folderPath*: Optional path of the folder to limit the scope of operation.

Type: Microsoft.SharePoint.Client.ResourcePath

*referrer*: URL of the original request to the connector

Type: CSOM String

*callback*: URL for webhook subscription.

Type: CSOM String

**3.2.5.372.2.2.12 ResolveEntityValue**

This method is a **static CSOM method**.

**Return Type:** Microsoft.SharePoint.Client.ConnectorResult

Returns a single reference choice for a reference-based field.

**Parameters:**

*listName*: List title or ID.

Type: **CSOM String**

*fieldId*: ID of the reference-based field.

Type: CSOM String

*queryOptions*: Query options to be applied to reference choices.

Type: CSOM String

Only supports \$search option

### 3.2.5.372.2.2.13 SetApprovalStatus

This method is a **static CSOM method**.

**Return Type:** Microsoft.SharePoint.Client.ConnectorResult

Sets the moderation status on a list item.

#### Parameters:

*listName*: This is the title or ID of the list which contains the item whose moderation status is being set.

Type: **CSOM String**

*itemId*: This is the ID of the list item whose moderation status is being set.

Type: CSOM String

*action*: This is the action (Approve, Reject or Submit) that can be taken on the list item.

Type: CSOM String

*comments*: These are the comments that can be optionally set while submitting an item for approval, approving, or rejecting an item.

Type: CSOM String

*etag*: ETag of the file attached to the list item which is the unique tag that is passed in while approving the item to ensure that the latest version is being approved or rejected.

Type: CSOM String

### 3.2.5.372.2.2.14 UpdateListItem

This method is a **static CSOM method**.

**Return Type:** Microsoft.SharePoint.Client.ConnectorResult

Updates list item data.

#### Parameters:

*listName*: List title or ID.

Type: **CSOM String**

*itemId*: List item ID.

Type: CSOM String

*itemData*: JSON representation of the updated item.

Type: CSOM String

### **3.2.5.373 Microsoft.SharePoint.Client.AppProperties**

**TypeId:** {45493869-65A1-4B1E-A159-C7B32EB57794}

**ShortName:** SP.AppProperties

Contains properties relevant to a given app.

#### **3.2.5.373.1 Properties**

##### **3.2.5.373.1.1 Scalar Properties**

###### **3.2.5.373.1.1.1 AppSettingsEnabled**

**Type:** CSOM Boolean

**Accessibility:** Read Only

Returns true if a settings link is enabled.

###### **3.2.5.373.1.1.2 Description**

**Type:** CSOM String

**Accessibility:** Read Only

A description of the app.

###### **3.2.5.373.1.1.3 EulaUrl**

**Type:** CSOM String

**Accessibility:** Read Only

A path to the EULA for the app.

###### **3.2.5.373.1.1.4 IsAnonymous**

**Type:** CSOM Boolean

**Accessibility:** Read Only

True if the user is not authenticated.

###### **3.2.5.373.1.1.5 IsDisabled**

**Type:** CSOM Boolean

**Accessibility:** Read Only

True if the app is disabled.

###### **3.2.5.373.1.1.6 ManagedDeploymentEnabled**

**Type:** CSOM Boolean

**Accessibility:** Read Only

True is the app deployment is managed.

### **3.2.5.373.1.1.7      ManagePermissionsEnabled**

**Type:** CSOM Boolean

**Accessibility:** Read Only

True if user can manage the app permissions.

### **3.2.5.373.1.1.8      ManageSeatsEnabled**

**Type:** CSOM Boolean

**Accessibility:** Read Only

True if the user is able to manage the license seats.

### **3.2.5.373.1.1.9      MonitoringEnabled**

**Type:** CSOM Boolean

**Accessibility:** Read Only

True is app analytics data is available.

### **3.2.5.373.1.1.10     Publisher**

**Type:** CSOM String

**Accessibility:** Read Only

The publisher of the app.

### **3.2.5.373.1.1.11     RemoveEnabled**

**Type:** CSOM Boolean

**Accessibility:** Read Only

Whether the user can remove the app.

### **3.2.5.373.1.1.12     SideLoadEnabled**

**Type:** CSOM Boolean

**Accessibility:** Read Only

True if app can be sideloaded.

### **3.2.5.373.1.1.13     SupportUrl**

**Type:** CSOM String

**Accessibility:** Read Only

A custom url, if available, to access app settings.

### **3.2.5.373.1.1.14     ViewInMarketPlaceEnabled**

**Type:** CSOM Boolean

**Accessibility:** Read Only

True if the app is viewable in the app marketplace.

### **3.2.5.373.1.2ObjectPath Properties**

None.

### **3.2.5.374 Microsoft.SharePoint.Client.AppSiteContext**

**TypeId:** {5D861CDF-2818-4912-AFD3-82CAA1032837}

**ShortName:** SP.AppSiteContext

An app site context

#### **3.2.5.374.1 Properties**

##### **3.2.5.374.1.1Scalar Properties**

###### **3.2.5.374.1.1.1 SiteUrl**

**Type:** CSOM String

**Accessibility:** Read Only

The URL of the site.

##### **3.2.5.374.1.2ObjectPath Properties**

None.

### **3.2.5.375 Microsoft.SharePoint.Client.AppSiteContextUtility**

**TypeId:** {D6CBDC41-0A1E-4711-BB3B-69D81746A39B}

**ShortName:** SP.AppSiteContextUtility

A utility class to retrieve App site context objects.

#### **3.2.5.375.1 Properties**

##### **3.2.5.375.1.1Scalar Properties**

None.

##### **3.2.5.375.1.2ObjectPath Properties**

None.

#### **3.2.5.375.2 Methods**

##### **3.2.5.375.2.1Scalar Methods**

###### **3.2.5.375.2.1.1 GetAppSiteContextCollection**

This method is a **static CSOM method**.

**Return Type:** **CSOM array** of Microsoft.SharePoint.Client.AppSiteContext

Retrieves the sites that an app has been launched on. The request **MUST** be made by an app with a valid user identity.

**Parameters:** None

### **3.2.5.375.2 ObjectPath Methods**

None.

### **3.2.5.376 Microsoft.SharePoint.Client.AppStatus**

**ShortName:** SP.AppStatus

**Flag:** false

The status of app. An app can only be executed if its status is Installed, any other status is either transient or might allow for additional operations, such as enabling a disabled app, or restoring a recycled app.

#### **3.2.5.376.1 Field Values**

##### **3.2.5.376.1.1 InvalidStatus**

**Value:** 0

This value indicates an internal product error, and SHOULD NOT occur in usage.

##### **3.2.5.376.1.2 Installing**

**Value:** 1

This value indicates that the App instance is in the process of installing.

##### **3.2.5.376.1.3 Canceling**

**Value:** 2

This value indicates that the App instance was installing, but was canceled, and is now uninstalling.

##### **3.2.5.376.1.4 Uninstalling**

**Value:** 3

This value indicates that the App instance is uninstalling.

##### **3.2.5.376.1.5 Installed**

**Value:** 4

This value indicates that the App instance is installed.

##### **3.2.5.376.1.6 Upgrading**

**Value:** 5

This value indicates that the App instance is upgrading.



### **3.2.5.376.1.7 Initialized**

**Value:** 6

This value indicates that the App instance has been created, but not yet installed.

### **3.2.5.376.1.8 UpgradeCanceling**

**Value:** 7

This value indicates that the App instance was upgrading, but has canceled.

### **3.2.5.376.1.9 Disabling**

**Value:** 8

This value indicates that the App instance is disabling.

### **3.2.5.376.1.10 Disabled**

**Value:** 9

This value indicates that the App instance is disabled.

### **3.2.5.376.1.11 SecretRolling**

**Value:** 10

This value indicates that the App instance is rolling the secret associated with its principal.

### **3.2.5.376.1.12 Recycling**

**Value:** 11

This value indicates the App instance is moving to the recycle bin.

### **3.2.5.376.1.13 Recycled**

**Value:** 12

This value indicates the App instance is in the recycle bin.

### **3.2.5.376.1.14 Restoring**

**Value:** 13

This value indicates the App instance is moving from the recycle bin back to Installed.

### **3.2.5.376.1.15 RestoreCanceling**

**Value:** 14

This value indicates the App instance was restoring from the recycle bin, but has canceled.

### **3.2.5.377 Microsoft.SharePoint.Client.AppTileProperties**

**TypeId:** {9E132B04-191D-415F-9EEE-87BECC7CC9A0}

**ShortName:** SP.AppTileProperties

A utility class that retrieves the properties of an app.

### **3.2.5.377.1 Properties**

#### **3.2.5.377.1.1 Scalar Properties**

None.

#### **3.2.5.377.1.2 ObjectPath Properties**

None.

### **3.2.5.377.2 Methods**

#### **3.2.5.377.2.1 Scalar Methods**

##### **3.2.5.377.2.1.1 GetAppProperties**

This method is a **static CSOM method**.

**Return Type:** Microsoft.SharePoint.Client.AppProperties

Retrieves the properties of a given app.

**Parameters:**

*appId*: The Id of the app.

Type: **CSOM GUID**

*appType*: The type of the app.

Type: Microsoft.SharePoint.Client.AppType

*productId*: The Id of the product associated with the app.

Type: CSOM GUID

*appSource*: The source of the app.

Type: Microsoft.SharePoint.Administration.AppSource

*assetId*: An Id representing the underlying asset type and version, for example document library.

Type: **CSOM String**

*contentMarket*: The market from which the app was installed.

Type: CSOM String

*isTenantApp*: True if this is an app provisioned through the tenant.

Type: **CSOM Boolean**

#### **3.2.5.377.2.2 ObjectPath Methods**

None.

### 3.2.5.378 Microsoft.SharePoint.Client.AppViewCreationInfo

**TypeId:** {52A8011D-98C5-466F-9CDE-2E5EF9CC811B}

**ShortName:** SP.AppViewCreationInfo

Microsoft.SharePoint.Client.AppViewCreationInfo is not applicable. [<250>](#)

#### 3.2.5.378.1 Properties

##### 3.2.5.378.1.1 Scalar Properties

None.

##### 3.2.5.378.1.2 ObjectPath Properties

None.

### 3.2.5.379 Microsoft.SharePoint.Client.CheckedOutFile

**TypeId:** {F1AB6895-066D-4B51-86BC-AFDDA92E5A8C}

**ShortName:** SP.CheckedOutFile

Represents a checked-out file in a document library or workspace.

#### 3.2.5.379.1 Properties

##### 3.2.5.379.1.1 Scalar Properties

###### 3.2.5.379.1.1.1 CheckedOutById

**Type:** CSOM Int32

**Accessibility:** Read Only

Returns the user ID of the account used to check out the file.

###### 3.2.5.379.1.1.2 ServerRelativePath

**Type:** Microsoft.SharePoint.Client.ResourcePath

**Accessibility:** Read Only

The server relative path of the checked out file.

##### 3.2.5.379.1.2 ObjectPath Properties

###### 3.2.5.379.1.2.1 CheckedOutBy

**Type:** Microsoft.SharePoint.Client.User

**Accessibility:** Read Only

Returns the user name of the account used to check out the file.

#### 3.2.5.379.2 Methods

### 3.2.5.379.2.1 Scalar Methods

#### 3.2.5.379.2.1.1 TakeOverCheckOut

**Return Type:** None

Instructs the site that another user account is taking over control of a currently checked-out file.

**Parameters:** None

### 3.2.5.379.2.2 ObjectPath Methods

None.

### 3.2.5.380 Microsoft.SharePoint.Client.CheckedOutFileCollection

**TypeId:** {41F73D00-1C59-49A6-A3ED-DD0982F80D24}

**ShortName:** SP.CheckedOutFileCollection

Represents a collection of checked-out files as specified in section [3.2.5.379](#).

#### 3.2.5.380.1 Properties

##### 3.2.5.380.1.1 Scalar Properties

None.

##### 3.2.5.380.1.2 ObjectPath Properties

None.

#### 3.2.5.380.2 Methods

##### 3.2.5.380.2.1 Scalar Methods

None.

##### 3.2.5.380.2.2 ObjectPath Methods

###### 3.2.5.380.2.2.1 GetByPath

**Return Type:** Microsoft.SharePoint.Client.CheckedOutFile

Get a collection of checked-out files at the specified path.

**Parameters:**

*path*: An **SP.ResourcePath** (section [3.2.5.420](#)) that specifies the path.

Type: Microsoft.SharePoint.Client.ResourcePath

It MUST NOT be NULL.

### 3.2.5.381 Microsoft.SharePoint.Client.ClientWebPart

**TypeId:** {4FED2270-C9A3-4E64-BB3B-011C54A3784C}

**ShortName:** SP.ClientWebPart

Representation of a ClientWebPart. It provides with ClientWebPart metadata and methods to render it.

### 3.2.5.381.1 Properties

#### 3.2.5.381.1.1 Scalar Properties

##### 3.2.5.381.1.1.1 Id

**Type:** CSOM GUID

**Accessibility:** Read Only

Id of the ClientWebPart. This id is generated by ClientWebPartComponentIdGenerator, based on the productId, the featureId and the name of the ClientWebPart, as ClientWebParts don't have an explicit id defined.

##### 3.2.5.381.1.1.2 Name

**Type:** CSOM String

**Accessibility:** Read Only

Name of the ClientWebPart.

#### 3.2.5.381.1.2 ObjectPath Properties

None.

### 3.2.5.381.2 Methods

#### 3.2.5.381.2.1 Scalar Methods

##### 3.2.5.381.2.1.1 Render

**Return Type:** CSOM String

Renders the ClientWebPart. Returns HTML that can be inserted in a page.

**Parameters:**

*properties:* Properties for the ClientWebPart, including edit mode.

Type: CSOM dictionary

Additional properties aside from the properties defined on the web part are: InstanceId, Width, Height, Autofit and Edit mode.

InstanceId is the instance Id of the web part on the page. It is passed as property "instanceId" and will set to ID property of the ClientWebPart instance.

Width is the width in pixels. It is passed as property "width" and can have an integer value.

Height is the height in pixels. It is passed as property "height" and can have an integer value.

Autofit will override the width to 100%. It is passed as property "autofit" and can have a value of "true" or "false".

Edit mode tells the ClientWebPart to render in edit mode. It is passed as property "editMode" and can have a value of "0" or "1".

### **3.2.5.381.2.2ObjectPath Methods**

None.

### **3.2.5.382 Microsoft.SharePoint.Client.ClientWebPartCollection**

**TypeId:** {CFE00E6E-6A55-4EB2-9094-735202954D29}

**ShortName:** SP.ClientWebPartCollection

Collection of ClientWebPart representations. It includes all ClientWebParts installed in the SP.Web.

#### **3.2.5.382.1 Properties**

##### **3.2.5.382.1.1Scalar Properties**

None.

##### **3.2.5.382.1.2ObjectPath Properties**

None.

#### **3.2.5.382.2 Methods**

##### **3.2.5.382.2.1Scalar Methods**

None.

##### **3.2.5.382.2.2ObjectPath Methods**

###### **3.2.5.382.2.2.1 GetById**

**Return Type:** Microsoft.SharePoint.Client.ClientWebPart

Returns the ClientWebPart representation with the set id.

**Parameters:**

*id:* The ID of the client web part to retrieve.

Type: **CSOM GUID**

### **3.2.5.383 Microsoft.SharePoint.Client.ConnectorResult**

**TypeId:** {D6CA3680-8029-441C-B872-75DF2C2BC0A2}

**ShortName:** SP.ConnectorResult

Used to return data from Connector operations in a specific format

#### **3.2.5.383.1 Properties**

##### **3.2.5.383.1.1Scalar Properties**

### **3.2.5.383.1.1.1 ContextData**

**Type:** CSOM String

**Accessibility:** Read Only

Additional data to be returned.

### **3.2.5.383.1.1.2 Value**

**Type:** CSOM String

**Accessibility:** Read Only

Contains result of the operation.

### **3.2.5.383.1.2ObjectPath Properties**

None.

### **3.2.5.383.2 Methods**

#### **3.2.5.383.2.1Scalar Methods**

None.

#### **3.2.5.383.2.2ObjectPath Methods**

None.

### **3.2.5.384 Microsoft.SharePoint.Client.CopyJobProgress**

**TypeId:** {BC64B0DB-1450-44BE-9ADD-F15B09E8CFCA}

**ShortName:** SP.CopyJobProgress

Microsoft.SharePoint.Client.CopyJobProgress is not applicable. [<251>](#)

#### **3.2.5.384.1 Properties**

##### **3.2.5.384.1.1Scalar Properties**

None.

##### **3.2.5.384.1.2ObjectPath Properties**

None.

### **3.2.5.385 Microsoft.SharePoint.Client.CopyMigrationInfo**

**TypeId:** {6B7EF931-D5BF-4213-BFB1-509278A9CABF}

**ShortName:** SP.CopyMigrationInfo

Microsoft.SharePoint.Client.CopyMigrationInfo is not applicable. [<252>](#)

#### **3.2.5.385.1 Properties**

### 3.2.5.385.1.1 Scalar Properties

None.

### 3.2.5.385.1.2 ObjectPath Properties

None.

### 3.2.5.386 Microsoft.SharePoint.Client.CopyMigrationOptions

**TypeId:** {E9C85D2D-0451-4B77-AE22-76365A2E9F0C}

**ShortName:** SP.CopyMigrationOptions

Microsoft.SharePoint.Client.CopyMigrationsOptions is not applicable. [<253>](#)

#### 3.2.5.386.1 Properties

##### 3.2.5.386.1.1 Scalar Properties

None.

##### 3.2.5.386.1.2 ObjectPath Properties

None.

### 3.2.5.387 Microsoft.SharePoint.Client.CurrencyInformation

**TypeId:** {80FFC784-B438-41FB-A239-3CA1382C80DF}

**ShortName:** SP.CurrencyInformation

Information about a currency necessary for currency identification and display in the UI.

#### 3.2.5.387.1 Properties

##### 3.2.5.387.1.1 Scalar Properties

###### 3.2.5.387.1.1.1 DisplayString

**Type:** CSOM String

**Accessibility:** Read Only

The Display String (ex: \$123,456.00 (United States)) for a specific currency which contains a sample formatted value (the currency and the number formatting from the web's locale) and the name of the country/region for the currency.

###### 3.2.5.387.1.1.2 LCID

**Type:** CSOM String

**Accessibility:** Read Only

The LCID (locale identifier) for a specific currency.

##### 3.2.5.387.1.2 ObjectPath Properties



None.

### **3.2.5.388 Microsoft.SharePoint.Client.CurrencyInformationCollection**

**TypeId:** {C00C915F-131D-45FF-9FFB-8DF65751B89F}

**ShortName:** SP.CurrencyInformationCollection

List of supported currencies: contains **CurrencyInformation** objects.

#### **3.2.5.388.1 Properties**

##### **3.2.5.388.1.1 Scalar Properties**

None.

##### **3.2.5.388.1.2 ObjectPath Properties**

None.

### **3.2.5.389 Microsoft.SharePoint.Client.CurrencyList**

**TypeId:** {B952F329-C588-4EAC-B193-7B598875C88E}

**ShortName:** SP.CurrencyList

List of supported currencies.

#### **3.2.5.389.1 Properties**

##### **3.2.5.389.1.1 Scalar Properties**

None.

##### **3.2.5.389.1.2 ObjectPath Properties**

None.

#### **3.2.5.389.2 Methods**

##### **3.2.5.389.2.1 Scalar Methods**

###### **3.2.5.389.2.1.1 GetList**

This method is a **static CSOM method**.

**Return Type:** Microsoft.SharePoint.Client.CurrencyInformationCollection

Generates a list of all the currencies allowed in SharePoint currency columns. The list contains **CurrencyInformation** objects with display strings and LCIDs for each currency.

**Parameters:** None

##### **3.2.5.389.2.2 ObjectPath Methods**

None.

### 3.2.5.390 Microsoft.SharePoint.Client.CustomActionElement

**TypeId:** {7295EB25-E721-42B6-AAC9-CBB6C39AFC54}

**ShortName:** SP.CustomActionElement

A class specifies a **custom action** element.

#### 3.2.5.390.1 Properties

##### 3.2.5.390.1.1 Scalar Properties

###### 3.2.5.390.1.1.1 ClientSideComponentId

**Type:** CSOM GUID

**Accessibility:** Read Only

The unique identifier of the client-side component associated with the custom action.

###### 3.2.5.390.1.1.2 ClientSideComponentProperties

**Type:** CSOM String

**Accessibility:** Read Only

This property is only used when a **ClientSideComponentId** is specified. It is optional. If non-empty, the string MUST contain a JSON object with custom initialization properties whose format and meaning are defined by the client-side component.

###### 3.2.5.390.1.1.3 CommandUIExtension

**Type:** CSOM String

**Accessibility:** Read Only

Gets the action's command ui definition that is used to store the ribbon xml.

###### 3.2.5.390.1.1.4 EnabledScript

**Type:** CSOM String

**Accessibility:** Read Only

The client side script to enabled or disable the custom action.

###### 3.2.5.390.1.1.5 ImageUrl

**Type:** CSOM String

**Accessibility:** Read Only

Returns the URL for a thumbnail image associated with the custom action.

###### 3.2.5.390.1.1.6 Location

**Type:** CSOM String

**Accessibility:** Read Only

Specifies where the Custom Action will be placed in the UI.

### **3.2.5.390.1.1.7 RegistrationId**

**Type:** CSOM String

**Accessibility:** Read Only

Registration ID of the custom action. It can be file extension for ECB menu custom action, or contenttype id for content type custom action.

### **3.2.5.390.1.1.8 RegistrationType**

**Type:** Microsoft.SharePoint.Client.UserCustomActionRegistrationType

**Accessibility:** Read Only

Registration type of the custom Action. Its values are defined in SP.UserCustomActionRegistrationType enum.

### **3.2.5.390.1.1.9 RequireSiteAdministrator**

**Type:** CSOM Boolean

**Accessibility:** Read Only

Returns true if the custom action requires site collection admin privilege to run.

### **3.2.5.390.1.1.10 Rights**

**Type:** Microsoft.SharePoint.Client.BasePermissions

**Accessibility:** Read Only

Returns the EffectiveBasePermissions object.

It MUST NOT be NULL.

### **3.2.5.390.1.1.11 Title**

**Type:** CSOM String

**Accessibility:** Read Only

Title of the custom Action.

### **3.2.5.390.1.1.12 UrlAction**

**Type:** CSOM String

**Accessibility:** Read Only

Url Action of the custom Action. It could contain embedded JavaScript for the custom action.

### **3.2.5.390.1.2ObjectPath Properties**

None.

### **3.2.5.391 Microsoft.SharePoint.Client.CustomActionElementCollection**

**TypeId:** {8085C8A0-AC08-44C8-AC9F-8A35540B34D1}

**ShortName:** SP.CustomActionElementCollection

This is the class that represents a collection of **CustomActionElement**.

#### **3.2.5.391.1 Properties**

##### **3.2.5.391.1.1 Scalar Properties**

None.

##### **3.2.5.391.1.2 ObjectPath Properties**

None.

### **3.2.5.392 Microsoft.SharePoint.Client.CustomerKeyInfo**

**TypeId:** {CDC51C4D-1C56-41E9-8E38-D75217A70B85}

**ShortName:** SP.CustomerKeyInfo

Microsoft.SharePoint.Client.CustomerKeyInfo is not applicable. [.<254>](#)

#### **3.2.5.392.1 Properties**

##### **3.2.5.392.1.1 Scalar Properties**

None.

##### **3.2.5.392.1.2 ObjectPath Properties**

None.

### **3.2.5.393 Microsoft.SharePoint.Client.CustomerKeyStatus**

**ShortName:** SP.CustomerKeyStatus

**Flag:** false

Microsoft.SharePoint.Client.CustomerKeyStatus is not applicable. [.<255>](#)

#### **3.2.5.393.1 Field Values**

None.

### **3.2.5.394 Microsoft.SharePoint.Client.CustomerKeyStatusInfo**

**TypeId:** {EE8F1D43-6049-424C-BCED-6145B6415C2B}

**ShortName:** SP.CustomerKeyStatusInfo

Microsoft.SharePoint.Client.CustomerKeyStatusInfo is not applicable. [.<256>](#)

#### **3.2.5.394.1 Properties**

### 3.2.5.394.1.1 Scalar Properties

None.

### 3.2.5.394.1.2 ObjectPath Properties

None.

### 3.2.5.395 Microsoft.SharePoint.Client.CustomerKeyVaultInfo

**TypeId:** {19D15BC5-C167-4D4F-A469-A9D7DE4BDCC1}

**ShortName:** SP.CustomerKeyVaultInfo

Microsoft.SharePoint.ClientCustomerKeyVaultInfo is not applicable. <257>

#### 3.2.5.395.1 Properties

##### 3.2.5.395.1.1 Scalar Properties

None.

##### 3.2.5.395.1.2 ObjectPath Properties

None.

### 3.2.5.396 Microsoft.SharePoint.Client.CustomerKeyVaultKeyType

**ShortName:** SP.CustomerKeyVaultKeyType

**Flag:** false

Microsoft.SharePoint.Client.CustomerKeyVaultKeyType is not applicable. <258>

#### 3.2.5.396.1 Field Values

None.

### 3.2.5.397 Microsoft.SharePoint.Client.EncryptionOption

**TypeId:** {85614AD4-7A40-49E0-B272-6D1807DBFCC6}

**ShortName:** SP.EncryptionOption

Migration options. <259>

#### 3.2.5.397.1 Properties

##### 3.2.5.397.1.1 Scalar Properties

None.

##### 3.2.5.397.1.2 ObjectPath Properties

None.

### **3.2.5.398 Microsoft.SharePoint.Client.FileCollectionAddParameters**

**TypeId:** {19ECCEE3-91D5-4335-9AFC-CD7FE47E5493}

**ShortName:** SP.FileCollectionAddParameters

This indicates an object encapsulating various options to use while saving a file.

#### **3.2.5.398.1 Properties**

##### **3.2.5.398.1.1 Scalar Properties**

###### **3.2.5.398.1.1.1 Overwrite**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Specifies whether to overwrite an existing file of the same name as the one being created.

##### **3.2.5.398.1.2 ObjectPath Properties**

None.

### **3.2.5.399 Microsoft.SharePoint.Client.FileVersionEvent**

**TypeId:** {478A36FE-CD3D-4F97-99DA-D373D2C2E6E4}

**ShortName:** SP.FileVersionEvent

Represents an event object happened on a Microsoft.SharePoint.SPFile.

#### **3.2.5.399.1 Properties**

##### **3.2.5.399.1.1 Scalar Properties**

###### **3.2.5.399.1.1.1 Editor**

**Type:** CSOM String

**Accessibility:** Read Only

Returns the name of the user who initiated the event.

###### **3.2.5.399.1.1.2 EditorEmail**

**Type:** CSOM String

**Accessibility:** Read Only

Returns the email corresponding to the user who initiated the event.

###### **3.2.5.399.1.1.3 EventType**

**Type:** Microsoft.SharePoint.Client.FileVersionEventType

**Accessibility:** Read Only

Returns the type of the event.

### **3.2.5.399.1.1.4 SharedByUser**

**Type:** Microsoft.SharePoint.Client.SharedWithUser

**Accessibility:** Read Only

Returns the shared by user Information in sharing action for change log.

### **3.2.5.399.1.1.5 SharedWithUsers**

**Type:** Microsoft.SharePoint.Client.SharedWithUserCollection

**Accessibility:** Read Only

Returns the array of users that have been shared in sharing action for the change log.

### **3.2.5.399.1.1.6 Time**

**Type:** CSOM DateTime

**Accessibility:** Read Only

Returns the **UTC (Coordinated Universal Time)** time of this event.

### **3.2.5.399.1.2ObjectPath Properties**

None.

### **3.2.5.399.2 Methods**

#### **3.2.5.399.2.1Scalar Methods**

None.

#### **3.2.5.399.2.2ObjectPath Methods**

None.

### **3.2.5.400 Microsoft.SharePoint.Client.FileVersionEventCollection**

**TypeId:** {098C4937-812C-449A-9D93-F4BB34E22323}

**ShortName:** SP.FileVersionEventCollection

Collection of event objects of a SPFile.

#### **3.2.5.400.1 Properties**

##### **3.2.5.400.1.1Scalar Properties**

None.

##### **3.2.5.400.1.2ObjectPath Properties**

None.

##### **3.2.5.400.2 Methods**

### 3.2.5.400.2.1 Scalar Methods

None.

### 3.2.5.400.2.2 ObjectPath Methods

None.

## 3.2.5.401 Microsoft.SharePoint.Client.FileVersionEventType

**ShortName:** SP.FileVersionEventType

**Flag:** false

Type of version events.

### 3.2.5.401.1 Field Values

#### 3.2.5.401.1.1 Share

**Value:** 1

A share event.

#### 3.2.5.401.1.2 Rename

**Value:** 2

A rename event.

#### 3.2.5.401.1.3 Restore

**Value:** 3

A restore event.

#### 3.2.5.401.1.4 MaxServerType

**Value:** 28671

Maximum allowed server event type.

#### 3.2.5.401.1.5 FromClient

**Value:** 28672

An event initiated from client.

## 3.2.5.402 Microsoft.SharePoint.Client.FlowSynchronizationResult

**TypeId:** {D9F77691-3136-41E7-8AAC-0BFC7736D842}

**ShortName:** SP.FlowSynchronizationResult

The result of the synchronization operation. [.<260>](#)

### 3.2.5.402.1 Properties



### 3.2.5.402.1.1 Scalar Properties

None.

### 3.2.5.402.1.2 ObjectPath Properties

None.

### 3.2.5.402.2 Methods

#### 3.2.5.402.2.1 Scalar Methods

None.

#### 3.2.5.402.2.2 ObjectPath Methods

None.

### 3.2.5.403 Microsoft.SharePoint.Client.FlowSynchronizationStatus

**ShortName:** SP.FlowSynchronizationStatus

**Flag:** false

The status of the synchronization operation [<261>](#)

#### 3.2.5.403.1 Field Values

None.

### 3.2.5.404 Microsoft.SharePoint.Client.FolderCollectionAddParameters

**TypeId:** {80315927-DC9D-47D8-A95D-B776A33373BE}

**ShortName:** SP.FolderCollectionAddParameters

Specifies the settings used for creating a folder.

#### 3.2.5.404.1 Properties

##### 3.2.5.404.1.1 Scalar Properties

###### 3.2.5.404.1.1.1 Overwrite

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Specifies whether to overwrite an existing folder of the same name as the one being created.

##### 3.2.5.404.1.2 ObjectPath Properties

None.

### 3.2.5.405 Microsoft.SharePoint.Client.FormRenderMode

**ShortName:** SP.FormRenderMode

**Flag:** false

The mode in which a form will render.

### **3.2.5.405.1 Field Values**

#### **3.2.5.405.1.1 Classic**

**Value:** 1

Classic User Experience. This is the default if none of the other modes match.

#### **3.2.5.405.1.2 Modern**

**Value:** 2

Modern User Experience.

#### **3.2.5.405.1.3 Customized**

**Value:** 4

Uses customized form rendering like InfoPath.

### **3.2.5.406 Microsoft.SharePoint.Client.Hashtag**

**TypeId:** {CDD68411-BC1E-46F6-ACC6-9FB857454976}

**ShortName:** SP.Hashtag

Microsoft.SharePoint.Client.Hashtag is not applicable. [<262>](#)

#### **3.2.5.406.1 Properties**

##### **3.2.5.406.1.1 Scalar Properties**

None.

##### **3.2.5.406.1.2 ObjectPath Properties**

None.

### **3.2.5.407 Microsoft.SharePoint.Client.LanguageCollection**

**TypeId:** {A3BACB34-297F-4EB5-A478-9F0820B247AC}

**ShortName:** SP.LanguageCollection

Represents a collection of SPLanguage objects. [<263>](#)

#### **3.2.5.407.1 Properties**

##### **3.2.5.407.1.1 Scalar Properties**

None.

##### **3.2.5.407.1.2 ObjectPath Properties**

None.

### **3.2.5.407.2 Methods**

#### **3.2.5.407.2.1 Scalar Methods**

None.

#### **3.2.5.407.2.2 ObjectPath Methods**

None.

### **3.2.5.408 Microsoft.SharePoint.Client.ListBloomFilter**

**TypeId:** {987C1FDF-B1CE-4E29-893F-16727D0D154C}

**ShortName:** SP.ListBloomFilter

Specifies a Bloom filter (probabilistic structure for checking the existence of list items).

#### **3.2.5.408.1 Properties**

##### **3.2.5.408.1.1 Scalar Properties**

###### **3.2.5.408.1.1.1 BloomFilterSize**

**Type:** CSOM Int32

**Accessibility:** Read Only

The length of the Bloom Filter

###### **3.2.5.408.1.1.2 FalsePositiveRate**

**Type:** CSOM Double

**Accessibility:** Read Only

The false positive rate for the Bloom Filter.

###### **3.2.5.408.1.1.3 HashedValueSet**

**Type:** CSOM array of CSOM String

**Accessibility:** Read Only

Specifies the set of the hash of the items in the bloom array.

###### **3.2.5.408.1.1.4 IndexMap**

**Type:** CSOM array of CSOM Int32

**Accessibility:** Read Only

Specifies a list of bloom indexes for item.

###### **3.2.5.408.1.1.5 ItemProcessedCount**

**Type:** CSOM Int32

**Accessibility:** Read Only

Specifies the count of the processed items.

### **3.2.5.408.1.1.6 K**

**Type:** CSOM Int32

**Accessibility:** Read Only

The number of has hash functions we would want to have with infinite compute.

### **3.2.5.408.1.1.7 LastListItemIdProcessed**

**Type:** CSOM Int32

**Accessibility:** Read Only

Specifies the item id of the last processed item.

### **3.2.5.408.1.1.8 MaxItemCount**

**Type:** CSOM Int32

**Accessibility:** Read Only

The number of list items added to the Bloom filter

### **3.2.5.408.1.2ObjectPath Properties**

None.

## **3.2.5.408.2 Methods**

### **3.2.5.408.2.1Scalar Methods**

None.

### **3.2.5.408.2.2ObjectPath Methods**

None.

## **3.2.5.409 Microsoft.SharePoint.Client.ListExperience**

**ShortName:** SP.ListExperience

**Flag:** false

List Experience Setting enum for List experience which includes auto, new experience, and classic experience. If either the new experience or the classic experience is selected, the list will be display accordingly. Auto means the Default experience set by administrator.

### **3.2.5.409.1 Field Values**

#### **3.2.5.409.1.1Auto**

**Value:** 0

The list experience is not specified, and will be selected automatically.

### **3.2.5.409.1.2NewExperience**

**Value:** 1

The new list experience.

### **3.2.5.409.1.3ClassicExperience**

**Value:** 2

The classic experience.

## **3.2.5.410 Microsoft.SharePoint.Client.ListItemCreationInformationUsingPath**

**TypeId:** {B3776C4E-509D-4BED-983F-CDDC43118E30}

**ShortName:** SP.ListItemCreationInformationUsingPath

Specifies the properties of the new list item.

### **3.2.5.410.1 Properties**

#### **3.2.5.410.1.1 Scalar Properties**

##### **3.2.5.410.1.1.1 FolderPath**

**Type:** Microsoft.SharePoint.Client.ResourcePath

**Accessibility:** Read/Write

Specifies the path of the folder of the new list item.

The value MUST be either null or the decoded url value an empty string or a server-relative URL or an absolute URL. If the value is not null or the decoded url value not being empty string, the decoded url value MUST point to a location within the list.

##### **3.2.5.410.1.1.2 LeafName**

**Type:** Microsoft.SharePoint.Client.ResourcePath

**Accessibility:** Read/Write

Specifies the name of the list item that will be created. In the case of a document library, the name is equal to the filename of the list item.

It MUST NOT contain the following characters: \x00-\x1FF, \x22, \x23, \x25, \x26, \x2A, \x3A, \x3C, \x3E, \x3F, \x5C and \x7B-\x9F. The maximum length of the decoded URL of the file is 400, which includes the length of the file name.

##### **3.2.5.410.1.1.3 UnderlyingObjectType**

**Type:** Microsoft.SharePoint.Client.FileSystemObjectType

**Accessibility:** Read/Write

Specifies the file system object type for the item that will be created.

It MUST be either FileSystemObjectType.File or FileSystemObjectType.Folder.

### **3.2.5.410.1.2ObjectPath Properties**

None.

### **3.2.5.411 Microsoft.SharePoint.Client.ListItemVersion**

**TypeId:** {79840421-ED80-46F7-A6A5-00EE62576E15}

**ShortName:** SP.ListItemVersion

Represents a version of a list item. [<264>](#)

#### **3.2.5.411.1 Properties**

##### **3.2.5.411.1.1 Scalar Properties**

###### **3.2.5.411.1.1.1 Created**

**Type:** CSOM DateTime

**Accessibility:** Read Only

Gets the creation date and time for the item version.

###### **3.2.5.411.1.1.2 IsCurrentVersion**

**Type:** CSOM Boolean

**Accessibility:** Read Only

Specifies whether the list item version is the current version.

###### **3.2.5.411.1.1.3 VersionId**

**Type:** CSOM Int32

**Accessibility:** Read Only

Gets the ID of the version.

###### **3.2.5.411.1.1.4 VersionLabel**

**Type:** CSOM String

**Accessibility:** Read Only

Gets the version number of the item version.

##### **3.2.5.411.1.2ObjectPath Properties**

###### **3.2.5.411.1.2.1 CreatedBy**

**Type:** Microsoft.SharePoint.Client.User

**Accessibility:** Read Only

Specifies the SharePoint user that represents the creator of the file version.

### 3.2.5.411.1.2.2 Fields

**Type:** Microsoft.SharePoint.Client.FieldCollection

**Accessibility:** Read Only

Gets the collection of fields that are used in the list that contains the item version.

### 3.2.5.411.1.2.3 FileVersion

**Type:** Microsoft.SharePoint.Client.FileVersion

**Accessibility:** Read Only

Gets the **FileVersion** object associated with the **ListItemVersion**.

## 3.2.5.411.2 Methods

### 3.2.5.411.2.1 Scalar Methods

#### 3.2.5.411.2.1.1 DeleteObject

**Return Type:** None

Deletes the list item version.

**Parameters:** None

**Exceptions:**

Error Code	Error Type Name	Condition
- 2147024846	Microsoft.SharePoint.SPException	Recycle bin is disabled.
- 2147024891	System.UnauthorizedAccessException	User does not have permissions to update this file version.

### 3.2.5.411.2.2 ObjectPath Methods

None.

## 3.2.5.412 Microsoft.SharePoint.Client.ListItemVersionCollection

**TypeId:** {00F9666D-F344-4C6D-A5D7-B2A2E73CD799}

**ShortName:** SP.ListItemVersionCollection

Represents a collection of SP.ListItemVersion objects.

### 3.2.5.412.1 Properties

#### 3.2.5.412.1.1 Scalar Properties

None.

### **3.2.5.412.1.2ObjectPath Properties**

None.

### **3.2.5.412.2 Methods**

#### **3.2.5.412.2.1Scalar Methods**

None.

#### **3.2.5.412.2.2ObjectPath Methods**

##### **3.2.5.412.2.2.1 GetById**

**Return Type:** Microsoft.SharePoint.Client.ListItemVersion

Returns a version from the collection based on the specified version ID.

**Parameters:**

*versionId*: A 32-bit integer that specifies the ID of the version to return.

Type: **CSOM Int32**

### **3.2.5.413 Microsoft.SharePoint.Client.ListPageRenderType**

**ShortName:** SP.ListPageRenderType

**Flag:** false

Reasons why the page is rendered in classic experience, or Modern if the page is in modern experience.

#### **3.2.5.413.1 Field Values**

##### **3.2.5.413.1.1Undefined**

**Value:** 0

There's not enough information to know the render mode,

##### **3.2.5.413.1.2MultipleWebPart**

**Value:** 1

More than one **Web Part** on the default view page.

##### **3.2.5.413.1.3JSLinkCustomization**

**Value:** 2

The page is using JavaScript file to customize the list rendering.

##### **3.2.5.413.1.4XsllinkCustomization**

**Value:** 3



The page is using **XSL** file to customize the list rendering.

### **3.2.5.413.1.5NoSPList**

**Value:** 4

The view is not supported by the page.

### **3.2.5.413.1.6HasBusinessDataField**

**Value:** 5

The page has business data field.

### **3.2.5.413.1.7HasTaskOutcomeField**

**Value:** 6

The page has field which type is **OutcomeChoice** (section [3.2.5.58.1.34](#)).

### **3.2.5.413.1.8HasPublishingfield**

**Value:** 7

The page has publishing field.

### **3.2.5.413.1.9HasGeolocationField**

**Value:** 8

The page has field that contains Geographical location values.

### **3.2.5.413.1.10 HasCustomActionWithCode**

**Value:** 9

The page has **custom action**.

### **3.2.5.413.1.11 HasMetadataNavFeature**

**Value:** 10

Metadata navigation feature is on in the page.

### **3.2.5.413.1.12 SpecialViewType**

**Value:** 11

The page has a special view like Gantt chart or Calendar.

### **3.2.5.413.1.13 ListTypeNoSupportForModernMode**

**Value:** 12

The modern experience could not be rendered.

### **3.2.5.413.1.14 AnonymousUser**

**Value:** 13

The user is anonymous.

**3.2.5.413.1.15 ListSettingOff**

**Value:** 14

Modern list rendering has been disabled at the list level.

**3.2.5.413.1.16 SiteSettingOff**

**Value:** 15

Modern list rendering has been disabled at the site level.

**3.2.5.413.1.17 WebSettingOff**

**Value:** 16

Modern list rendering has been disabled at the web level.

**3.2.5.413.1.18 TenantSettingOff**

**Value:** 17

Modern list rendering has been disabled at the tenant level.

**3.2.5.413.1.19 CustomizedForm**

**Value:** 18

The page only has one field or in a dialog mode or is not client rendered form.

**3.2.5.413.1.20 DocLibNewForm**

**Value:** 19

The page is a form to create a **document library**.

**3.2.5.413.1.21 UnsupportedFieldTypeInForm**

**Value:** 20

Unsupported file type in the **list**.

**3.2.5.413.1.22 InvalidFieldTypeInForm**

**Value:** 21

Invalid file type in the **list**.

**3.2.5.413.1.23 InvalidControlModeInForm**

**Value:** 22

Invalid control mode in the **list**.

**3.2.5.413.1.24 CustomizedPage**

**Value:** 23

The page is customized.

### **3.2.5.413.1.25 ListTemplateNotSupported**

**Value:** 24

Unsupported **list template**.

### **3.2.5.413.1.26 WikiPage**

**Value:** 25

The page is a Wiki page.

### **3.2.5.413.1.27 DropOffLibrary**

**Value:** 26

The container is a Drop Off library, which is automatically created when you activate the Content Organizer feature, serves as the default location.

### **3.2.5.413.1.28 IsUnghosted**

**Value:** 27

The **list** is a Pages library or unghosted Asset library.

### **3.2.5.413.1.29 Modern**

**Value:** 100

Page render in modern experience.

## **3.2.5.414 Microsoft.SharePoint.Client.MigrationNameConflictBehavior**

**ShortName:** SP.MigrationNameConflictBehavior

**Flag:** false

Microsoft.SharePoint.Client.MigrationNameConflictBehavior is not applicable. [<265>](#)

### **3.2.5.414.1 Field Values**

None.

## **3.2.5.415 Microsoft.SharePoint.Client.MoveCopyOptions**

**TypeId:** {B3FF81B8-6CEC-4AD3-AE27-9D5CFF515D8E}

**ShortName:** SP.MoveCopyOptions

Microsoft.SharePoint.Client.MoveCopyOptions is not applicable. [<266>](#)

### **3.2.5.415.1 Properties**

#### **3.2.5.415.1.1 Scalar Properties**

None.

### 3.2.5.415.1.2 ObjectPath Properties

None.

### 3.2.5.416 Microsoft.SharePoint.Client.ProvisionedMigrationContainersInfo

**TypeId:** {F562770D-C45C-4080-9B5D-CDDEC7D1FC15}

**ShortName:** SP.ProvisionedMigrationContainersInfo

Microsoft.SharePoint.Client.ProvisionedMigrationContainersInfo is not applicable. <267>

#### 3.2.5.416.1 Properties

##### 3.2.5.416.1.1 Scalar Properties

None.

##### 3.2.5.416.1.2 ObjectPath Properties

None.

### 3.2.5.417 Microsoft.SharePoint.Client.ProvisionedMigrationQueueInfo

**TypeId:** {1D940081-60CB-44CB-8415-334EF96369CA}

**ShortName:** SP.ProvisionedMigrationQueueInfo

Microsoft.SharePoint.Client.ProvisionedMigrationQueueInfo is not applicable. <268>

#### 3.2.5.417.1 Properties

##### 3.2.5.417.1.1 Scalar Properties

None.

##### 3.2.5.417.1.2 ObjectPath Properties

None.

### 3.2.5.418 Microsoft.SharePoint.Client.RecycleBinQueryInformation

**TypeId:** {D525B376-6849-48DB-B9D3-7A58F1B00BDF}

**ShortName:** SP.RecycleBinQueryInformation

Represents information for the recycle bin query.

#### 3.2.5.418.1 Properties

##### 3.2.5.418.1.1 Scalar Properties

###### 3.2.5.418.1.1.1 IsAscending

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Gets or sets a Boolean value that specifies whether to sort in ascending order.

### **3.2.5.418.1.1.2 ItemState**

**Type:** Microsoft.SharePoint.Client.RecycleBinItemState

**Accessibility:** Read/Write

Gets or sets the Recycle Bin state of items to return in the query.

### **3.2.5.418.1.1.3 OrderBy**

**Type:** Microsoft.SharePoint.Client.RecycleBinOrderBy

**Accessibility:** Read/Write

Gets or sets the column by which to order the Recycle Bin query.

### **3.2.5.418.1.1.4 PagingInfo**

**Type:** CSOM String

**Accessibility:** Read/Write

Gets or sets a string used to get the next set of rows in the page.

### **3.2.5.418.1.1.5 RowLimit**

**Type:** CSOM Int32

**Accessibility:** Read/Write

Gets or sets a limit for the number of items returned in the query per page.

### **3.2.5.418.1.1.6 ShowOnlyMyItems**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Gets or sets a Boolean value that specifies whether to get items deleted by other users.

## **3.2.5.418.1.2ObjectPath Properties**

None.

## **3.2.5.419 Microsoft.SharePoint.Client.RenderListFormDataOptions**

**ShortName:** SP.RenderListFormDataOptions

**Flag:** true

The type of data to return when retrieving listform data for a specified item as JSON.

### **3.2.5.419.1 Field Values**

#### **3.2.5.419.1.1None**

**Value:** 0

No options specified.

### **3.2.5.419.1.2 ExcludeListSchema**

**Value:** 1

The returned form data will contain only list data and not any list schema information.

### **3.2.5.419.1.3 IncludeAttachments**

**Value:** 2

The returned form data will have an attachments field if possible.

### **3.2.5.419.1.4 IncludeListViewData**

**Value:** 4

The returned form data will contain ListView Data.

### **3.2.5.419.1.5 IncludeAppendOnlyData**

**Value:** 8

The returned form data will contain AppendOnly Data.

## **3.2.5.420 Microsoft.SharePoint.Client.ResourcePath**

**TypeId:** {A265A356-274B-4E6C-B0EF-BBC22BD0969A}

**ShortName:** SP.ResourcePath

Represents the full (absolute) or parts (relative) path of a site collection, web, file, folder or other artifacts in the database.

### **3.2.5.420.1 Properties**

#### **3.2.5.420.1.1 Scalar Properties**

##### **3.2.5.420.1.1.1 DecodedUrl**

**Type:** CSOM String

**Accessibility:** Read Only

Gets the path in the decoded form.

#### **3.2.5.420.1.2 ObjectPath Properties**

None.

## **3.2.5.421 Microsoft.SharePoint.Client.ScriptSafeDomain**

**TypeId:** {87136B0D-6FC3-40F8-9348-1A2D332363C1}

**ShortName:** SP.ScriptSafeDomain

Microsoft.SharePoint.Client.ScriptSafeDomain is not applicable. [<269>](#)

### 3.2.5.421.1 Properties

#### 3.2.5.421.1.1 Scalar Properties

None.

#### 3.2.5.421.1.2 ObjectPath Properties

None.

### 3.2.5.421.2 Methods

#### 3.2.5.421.2.1 Scalar Methods

None.

#### 3.2.5.421.2.2 ObjectPath Methods

None.

### 3.2.5.422 Microsoft.SharePoint.Client.ScriptSafeDomainEntityData

**TypeId:** {5D93B2FA-ED48-47EB-84CE-4B6C2E10F38C}

**ShortName:** SP.ScriptSafeDomainEntityData

Microsoft.SharePoint.Client.ScriptSafeDomainEntityData is not applicable. [<270>](#)

#### 3.2.5.422.1 Properties

##### 3.2.5.422.1.1 Scalar Properties

None.

##### 3.2.5.422.1.2 ObjectPath Properties

None.

### 3.2.5.423 Microsoft.SharePoint.Client.ScriptSafeExternalEmbedding

**ShortName:** SP.ScriptSafeExternalEmbedding

**Flag:** false

Microsoft.SharePoint.ClientScriptSafeExternalEmbedding. [<271>](#)

#### 3.2.5.423.1 Field Values

None.

### 3.2.5.424 Microsoft.SharePoint.Client.SharedWithUser

**TypeId:** {01D693D9-72C2-4531-9FB9-105C88B6706B}

**ShortName:** SP.SharedWithUser

Represents a **principal** with whom a **list item** is shared.

### 3.2.5.424.1 Properties

#### 3.2.5.424.1.1 Scalar Properties

##### 3.2.5.424.1.1.1 Email

Type: **CSOM String**

Accessibility: Read Only

Gets the email of the **principal**.

##### 3.2.5.424.1.1.2 Name

Type: **CSOM String**

Accessibility: Read Only

Gets the name of the **principal**.

#### 3.2.5.424.1.2 ObjectPath Properties

None.

### 3.2.5.425 Microsoft.SharePoint.Client.SharedWithUserCollection

**TypeId:** {C60FA59C-1DE9-4B4F-A6ED-2B4B625FF300}

**ShortName:** SP.SharedWithUserCollection

Represents a collection of shared with users.

#### 3.2.5.425.1 Properties

##### 3.2.5.425.1.1 Scalar Properties

None.

##### 3.2.5.425.1.2 ObjectPath Properties

None.

### 3.2.5.426 Microsoft.SharePoint.Client.Sharing.AccessRequestSettings

**TypeId:** {CBA89C6C-1469-4AC8-A582-6E199FBCF925}

**ShortName:** SP.Sharing.AccessRequestSettings

This class returns the access request settings. It's an optional property that can be retrieved in `Microsoft.SharePoint.Client.Sharing.SecurableObjectExtensions.GetSharingInformation()` call on a **list item**.

#### 3.2.5.426.1 Properties

##### 3.2.5.426.1.1 Scalar Properties

##### 3.2.5.426.1.1.1 hasPendingAccessRequests



**Type:** CSOM Boolean

**Accessibility:** Read/Write

Boolean indicating whether there are pending access requests for the **list item**.

### 3.2.5.426.1.1.2 pendingAccessRequestsLink

**Type:** CSOM String

**Accessibility:** Read/Write

The **full URL** to the access requests page for the **list item**, or an empty string if the link is not available.

### 3.2.5.426.1.1.3 requiresAccessApproval

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Boolean indicating whether the current user's access on the **list item** requires approval from admin for sharing to others.

## 3.2.5.426.1.2 ObjectPath Properties

None.

## 3.2.5.427 Microsoft.SharePoint.Client.Sharing.DirectSharingAbilities

**TypeId:** {75FDF241-5BBC-4C55-975A-D4BCD063D8BE}

**ShortName:** SP.Sharing.DirectSharingAbilities

Represents the set of capabilities for direct sharing for the current user.

### 3.2.5.427.1 Properties

#### 3.2.5.427.1.1 Scalar Properties

##### 3.2.5.427.1.1.1 canAddExternalPrincipal

**Type:** Microsoft.SharePoint.Client.Sharing.SharingAbilityStatus

**Accessibility:** Read Only

Indicates whether the current user can share to new external users.

##### 3.2.5.427.1.1.2 canAddInternalPrincipal

**Type:** Microsoft.SharePoint.Client.Sharing.SharingAbilityStatus

**Accessibility:** Read Only

Indicates whether the current user can share to internal users.

##### 3.2.5.427.1.1.3 canRequestGrantAccess

**Type:** Microsoft.SharePoint.Client.Sharing.SharingAbilityStatus

**Accessibility:** Read Only

Indicates whether the current user can initiate a request for someone with higher permissions to grant access.

### 3.2.5.427.1.2 ObjectPath Properties

None.

### 3.2.5.428 Microsoft.SharePoint.Client.Sharing.DomainRestrictionSettings

**TypeId:** {DC0D8514-F3B7-48CD-8E21-3FF6A489B052}

**ShortName:** SP.Sharing.DomainRestrictionSettings

Represents the settings of the restricted **domain names** sharing.

#### 3.2.5.428.1 Properties

##### 3.2.5.428.1.1 Scalar Properties

###### 3.2.5.428.1.1.1 domainRestrictionMode

**Type:** Microsoft.SharePoint.Client.Sharing.SharingDomainRestrictionMode

**Accessibility:** Read/Write

Indicates whether the current restricted **domain names** for sending sharing invitation at the organization level is the domain allow list or deny list.

###### 3.2.5.428.1.1.2 domainRestrictionModeAtSite

**Type:** Microsoft.SharePoint.Client.Sharing.SharingDomainRestrictionMode

**Accessibility:** Read/Write

Indicates whether the current restricted **domain names** for sending sharing invitation at the site collection level is the domain allow list or deny list.

###### 3.2.5.428.1.1.3 restrictedDomains

**Type:** CSOM String

**Accessibility:** Read/Write

Comma separated list of allowed or denied **domain names** for sending sharing invitation at the organization level.

###### 3.2.5.428.1.1.4 restrictedDomainsAtSite

**Type:** CSOM String

**Accessibility:** Read/Write

Comma separated list of allowed or denied **domain names** for sending sharing invitation at the site collection level.

### 3.2.5.428.1.2 ObjectPath Properties

None.

### **3.2.5.429 Microsoft.SharePoint.Client.Sharing.EmailData**

**TypeId:** {C4704EBB-5C92-4716-A5E2-06CD122B9162}

**ShortName:** SP.Sharing.EmailData

Represents email data to be used to initiate sending notification e-mail when sharing using a **tokenized sharing link**.

#### **3.2.5.429.1 Properties**

##### **3.2.5.429.1.1 Scalar Properties**

###### **3.2.5.429.1.1.1 body**

**Type:** **CSOM String**

**Accessibility:** Read/Write

The value to use as the custom message body for a notification e-mail when sharing using a **tokenized sharing link**.

If this value is null, the default message body MUST be used.

###### **3.2.5.429.1.1.2 subject**

**Type:** **CSOM String**

**Accessibility:** Read/Write

The value to use as the custom subject line for a notification e-mail when sharing using a **tokenized sharing link**.

If this value is null, the default subject line MUST be used.

##### **3.2.5.429.1.2 ObjectPath Properties**

None.

### **3.2.5.430 Microsoft.SharePoint.Client.Sharing.EntityPermission**

**TypeId:** {6C146C91-E313-46EC-ADA6-BC22C368327E}

**ShortName:** SP.Sharing.EntityPermission

Represents a response for  
Microsoft.SharePoint.Client.Sharing.SecurableObjectExtensions.CheckPermissions

#### **3.2.5.430.1 Properties**

##### **3.2.5.430.1.1 Scalar Properties**

###### **3.2.5.430.1.1.1 hasAccess**

**Type:** **CSOM Boolean**

**Accessibility:** Read Only

Boolean indicating whether the Entity has Access to the **list item**.

### **3.2.5.430.1.1.2 inputEntity**

**Type:** CSOM String

**Accessibility:** Read Only

The Input Entity string provided to the call.

### **3.2.5.430.1.1.3 resolvedEntity**

**Type:** CSOM String

**Accessibility:** Read Only

The Resolved Entity after resolving using PeoplePicker API.

### **3.2.5.430.1.1.4 role**

**Type:** Microsoft.SharePoint.Client.Sharing.Role

**Accessibility:** Read Only

Role of the Entity on **list item**.

## **3.2.5.430.1.2 ObjectPath Properties**

None.

## **3.2.5.431 Microsoft.SharePoint.Client.Sharing.LinkInfo**

**TypeId:** {9631A3F1-DDC4-4C20-9D47-39549CE37FF7}

**ShortName:** SP.Sharing.LinkInfo

This class provides metadata for the **tokenized sharing link** including settings details, inheritance status, and an optional array of members.

### **3.2.5.431.1 Properties**

#### **3.2.5.431.1.1 Scalar Properties**

##### **3.2.5.431.1.1.1 isInherited**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Boolean that indicates if the **tokenized sharing link** is present due to inherited permissions from a parent object.

##### **3.2.5.431.1.1.2 linkDetails**

**Type:** Microsoft.SharePoint.Client.SharingLinkInfo

**Accessibility:** Read/Write

The SharingLinkInfo object for the **tokenized sharing link** with encoded Url.

### **3.2.5.431.1.1.3 linkMembers**

**Type:** CSOM array of Microsoft.SharePoint.Client.Sharing.Principal

**Accessibility:** Read/Write

List of principals present on the **tokenized sharing link**.

The number of principals returned in this array MUST not exceed 30, and any excess principals on the tokenized sharing link MUST NOT be included.

### **3.2.5.431.1.2ObjectPath Properties**

None.

## **3.2.5.432 Microsoft.SharePoint.Client.Sharing.LinkInvitation**

**TypeId:** {166665BE-3D9B-4765-A29C-8A197FADF01A}

**ShortName:** SP.Sharing.LinkInvitation

This class is used to identify the specific invitees for a **tokenized sharing link**, along with who invited them and when.

### **3.2.5.432.1 Properties**

#### **3.2.5.432.1.1 Scalar Properties**

##### **3.2.5.432.1.1.1 invitedBy**

**Type:** Microsoft.SharePoint.Client.Sharing.Principal

**Accessibility:** Read/Write

Indicates the principal who invited the invitee to the **tokenized sharing link**.

##### **3.2.5.432.1.1.2 invitedOn**

**Type:** CSOM String

**Accessibility:** Read/Write

String representation of nullable DateTime value indicating when the invitee was invited to the **tokenized sharing link**.

##### **3.2.5.432.1.1.3 invitee**

**Type:** Microsoft.SharePoint.Client.Sharing.Principal

**Accessibility:** Read/Write

Indicates a principal who is invited to the **tokenized sharing link**.

### **3.2.5.432.1.2ObjectPath Properties**

None.

### 3.2.5.433 Microsoft.SharePoint.Client.Sharing.OversharedWebInfo

**TypeId:** {0FC442DF-FFC5-4657-B790-694093B9BF73}

**ShortName:** SP.Sharing.OversharedWebInfo

This class provides details of users who have access to the default **document library**. It also indicates whether there are any unique **role assignments** for the default document library.

#### 3.2.5.433.1 Properties

##### 3.2.5.433.1.1 Scalar Properties

###### 3.2.5.433.1.1.1 hasUniqueRoleAssignmentsForList

**Type:** **CSOM Boolean**

**Accessibility:** Read/Write

Boolean value that specifies whether default **document library** list has unique **role assignments**.

###### 3.2.5.433.1.1.2 principals

**Type:** **CSOM array** of Microsoft.SharePoint.Client.Sharing.Principal

**Accessibility:** Read/Write

Users/groups who have access to the default **document library** of another user.

##### 3.2.5.433.1.2 ObjectPath Properties

None.

### 3.2.5.434 Microsoft.SharePoint.Client.Sharing.PermissionCollection

**TypeId:** {77B744E6-3826-444B-AD34-59B8905A44BE}

**ShortName:** SP.Sharing.PermissionCollection

This class is returned when Microsoft.SharePoint.Client.Sharing.SecurableObjectExtensions.GetSharingInformation is called with the optional expand on permissionsInformation property. It contains a collection of LinkInfo and PrincipalInfo objects of users/groups that have access to the **list item** and also the site administrators who have implicit access.

#### 3.2.5.434.1 Properties

##### 3.2.5.434.1.1 Scalar Properties

###### 3.2.5.434.1.1.1 links

**Type:** **CSOM array** of Microsoft.SharePoint.Client.Sharing.LinkInfo

**Accessibility:** Read/Write

The List of **tokenized sharing links** with their LinkInfo objects.

###### 3.2.5.434.1.1.2 principals

**Type:** **CSOM array** of Microsoft.SharePoint.Client.Sharing.PrincipalInfo

**Accessibility:** Read/Write

The List of Principals with their roles on this **list item**.

### **3.2.5.434.1.1.3 siteAdmins**

**Type:** **CSOM array** of Microsoft.SharePoint.Client.Sharing.PrincipalInfo

**Accessibility:** Read/Write

The List of Principals who are Site Admins. This property is returned only if the caller is an Auditor.

### **3.2.5.434.1.2ObjectPath Properties**

None.

## **3.2.5.435 Microsoft.SharePoint.Client.Sharing.PersonalWeb**

**TypeId:** {DF04740C-846C-466E-A30F-E3128F45F8C0}

**ShortName:** SP.Sharing.PersonalWeb

Microsoft.SharePoint.Client.Sharing.PersonalWeb namespace represents methods that apply to a **Web site** for individual users. Methods act on the users default **document library**.

### **3.2.5.435.1 Properties**

#### **3.2.5.435.1.1Scalar Properties**

None.

#### **3.2.5.435.1.2ObjectPath Properties**

None.

### **3.2.5.435.2 Methods**

#### **3.2.5.435.2.1Scalar Methods**

##### **3.2.5.435.2.1.1 FixPermissionInheritance**

This method is a **static CSOM method**.

**Return Type:** None

This method fixes the permission inheritance for the default document library of the personal web when breakRoleInheritance didn't happen correctly during the default document library creation.

**Parameters:** None

##### **3.2.5.435.2.1.2 GetOversharedWebInfo**

This method is a **static CSOM method**.

**Return Type:** Microsoft.SharePoint.Client.Sharing.OversharedWebInfo

This method gets users/groups who have access to default document library of current personal web.

**Parameters:** None

### 3.2.5.435.2.1.3 RemovePermissionForUsers

This method is a **static CSOM method**.

**Return Type:** **CSOM array** of Microsoft.SharePoint.Client.Sharing.UserSharingResult

This method removes the given users who have access to the default **document library** of current personal web.

**Parameters:**

*users:* The users who have access to entire default document library.

Type: CSOM array of Microsoft.SharePoint.Client.Sharing.Principal

### 3.2.5.435.2.2 ObjectPath Methods

None.

### 3.2.5.436 Microsoft.SharePoint.Client.Sharing.Principal

**TypeId:** {FEE7EF67-6F88-4770-AFFE-145366518A1B}

**ShortName:** SP.Sharing.Principal

Microsoft.SharePoint.Client.Sharing.Principal class is a representation of an identity (user/group).

#### 3.2.5.436.1 Properties

##### 3.2.5.436.1.1 Scalar Properties

###### 3.2.5.436.1.1.1 email

**Type:** **CSOM String**

**Accessibility:** Read/Write

Email address of the Principal.

###### 3.2.5.436.1.1.2 id

**Type:** **CSOM Int32**

**Accessibility:** Read/Write

Id of the Principal in SharePoint's UserInfo List.

###### 3.2.5.436.1.1.3 isActive

**Type:** **CSOM Boolean**

**Accessibility:** Read/Write

Boolean value representing if the Principal is Active.



#### **3.2.5.436.1.1.4 isExternal**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Boolean value representing if the Principal is an external user.

#### **3.2.5.436.1.1.5 jobTitle**

**Type:** CSOM String

**Accessibility:** Read/Write

The Job Title of the Principal.

#### **3.2.5.436.1.1.6 loginName**

**Type:** CSOM String

**Accessibility:** Read/Write

LoginName of the Principal.

#### **3.2.5.436.1.1.7 name**

**Type:** CSOM String

**Accessibility:** Read/Write

Name of the Principal.

#### **3.2.5.436.1.1.8 principalType**

**Type:** Microsoft.SharePoint.Client.Utilities.PrincipalType

**Accessibility:** Read/Write

PrincipalType of the Principal.

#### **3.2.5.436.1.1.9 userId**

**Type:** Microsoft.SharePoint.Client.UserIdInfo

**Accessibility:** Read Only

Identity information of the Principal.

#### **3.2.5.436.1.2ObjectPath Properties**

None.

#### **3.2.5.437 Microsoft.SharePoint.Client.Sharing.PrincipalInfo**

**TypeId:** {91D5E7A9-FD99-4B7B-9F7F-ADCA1BF31F05}

**ShortName:** SP.Sharing.PrincipalInfo

SP.Sharing.PrincipalInfo class represents Principal and its Role on the **list item**.

### 3.2.5.437.1 Properties

#### 3.2.5.437.1.1 Scalar Properties

##### 3.2.5.437.1.1.1 principal

**Type:** Microsoft.SharePoint.Client.Sharing.Principal

**Accessibility:** Read/Write

The Principal who has permission on the **list item**.

##### 3.2.5.437.1.1.2 role

**Type:** Microsoft.SharePoint.Client.Sharing.Role

**Accessibility:** Read/Write

The role that the Principal has on the **list item**.

#### 3.2.5.437.1.2 ObjectPath Properties

None.

### 3.2.5.438 Microsoft.SharePoint.Client.Sharing.Recipient

**TypeId:** {077C1FD2-6569-452B-862E-405EE70AC93F}

**ShortName:** SP.Sharing.Recipient

This class represents an Entity for which Permission check is requested for a given **list item**.

#### 3.2.5.438.1 Properties

##### 3.2.5.438.1.1 Scalar Properties

###### 3.2.5.438.1.1.1 alias

**Type:** CSOM String

**Accessibility:** Read/Write

The alias of the recipient.

###### 3.2.5.438.1.1.2 email

**Type:** CSOM String

**Accessibility:** Read/Write

The email address of the recipient.

###### 3.2.5.438.1.1.3 objectId

**Type:** CSOM String

**Accessibility:** Read/Write

The objectId of the recipient.

### 3.2.5.438.1.2 ObjectPath Properties

None.

### 3.2.5.439 Microsoft.SharePoint.Client.Sharing.SecurableObjectExtensions

**TypeId:** {7479EB87-DFD9-4F5F-94B6-DFB5B4296150}

**ShortName:** SP.Sharing.SecurableObjectExtensions

Contains extension methods of **securable object**.

#### 3.2.5.439.1 Properties

##### 3.2.5.439.1.1 Scalar Properties

None.

##### 3.2.5.439.1.2 ObjectPath Properties

None.

#### 3.2.5.439.2 Methods

##### 3.2.5.439.2.1 Scalar Methods

###### 3.2.5.439.2.1.1 CheckPermissions

This method is a **static CSOM method**.

**Return Type:** **CSOM array** of Microsoft.SharePoint.Client.Sharing.EntityPermission

This method can be used to check the permission on a **list item** that a give array of recipients have on it. It returns an array of EntityPermission's.

**Parameters:**

*listItem*: List item on which the check permission needs to be performed.

Type: Microsoft.SharePoint.Client.ListItem

*recipients*: Array of recipients for whom the permissions needs to be checked.

Type: CSOM array of Microsoft.SharePoint.Client.Sharing.Recipient

###### 3.2.5.439.2.1.2 DeleteLinkByKind

This method is a **static CSOM method**.

**Return Type:** None

Removes the specified **tokenized sharing link** of the **list item**

**Parameters:**

*item*: The list item MUST refer to a **document** within a **document library**.

Type: Microsoft.SharePoint.Client.ListItem

*linkKind*: The kind of tokenized sharing link that is intended to be removed.

Type: Microsoft.SharePoint.Client.SharingLinkKind

This MUST be set to one of the following values:

- **OrganizationView** (section [3.2.5.315.1.3](#))
- **OrganizationEdit** (section [3.2.5.315.1.4](#))
- **AnonymousView** (section [3.2.5.315.1.5](#))
- **AnonymousEdit** (section [3.2.5.315.1.6](#))

### 3.2.5.439.2.1.3 ShareLink

This method is a **static CSOM method**.

**Return Type:** Microsoft.SharePoint.Client.Sharing.ShareLinkResponse

Creates a **tokenized sharing link** for a **list item** based on the specified parameters and optionally sends an email to the people that are listed in the specified parameters.

**Parameters:**

*listItem*: The list item intended to be shared.

Type: Microsoft.SharePoint.Client.ListItem

The list item MUST refer to a **document** within a **document library**.

*request*: The request options for sharing a tokenized sharing link for the list item.

Type: Microsoft.SharePoint.Client.Sharing.ShareLinkRequest

### 3.2.5.439.2.1.4 UnshareLink

This method is a **static CSOM method**.

**Return Type:** None

Removes the specified **tokenized sharing link** of the **list item**.

**Parameters:**

*item*: The shared list item that represents a **document** within a **document library**.

Type: Microsoft.SharePoint.Client.ListItem

*linkKind*: The kind of tokenized sharing link that is intended to be removed.

Type: Microsoft.SharePoint.Client.SharingLinkKind

If the shareId parameter is populated with is null or an **empty GUID**, this MUST be set to one of the following values:

- **OrganizationView** (section [3.2.5.315.1.3](#))
- **OrganizationEdit** (section [3.2.5.315.1.4](#))
- **AnonymousView** (section [3.2.5.315.1.5](#))

- **AnonymousEdit** (section [3.2.5.315.1.6](#))

If the `shareId` parameter is not populated with is null or an empty GUID, this MAY also be set to:

- **Flexible** (section [3.2.5.315.1.7](#))

*shareId*: This optional value specifies the **globally unique identifier (GUID)** of the tokenized sharing link that is intended to be removed.

Type: **CSOM GUID**

If this value is null or an empty GUID then only the `linkKind` parameter value MUST be used to look up the existing tokenized sharing link. If this value is specified, the `linkKind` parameter value MUST match the configured kind for the tokenized sharing link represented by this identifier and this identifier MUST be used to look up the existing tokenized sharing link.

### 3.2.5.439.2.1.5 UpdateDocumentSharingInfo

This method is a **static CSOM method**.

**Return Type:** **CSOM array** of `Microsoft.SharePoint.Client.Sharing.UserSharingResult`

This method allows a caller with the 'ManagePermission' permission to update sharing information about a document to enable document sharing with a set of users. It returns an array of **UserSharingResult** (section [3.2.5.190](#)) elements where each element contains the sharing status for each user.

#### Parameters:

*item*: The **list item** intended to be shared.

Type: `Microsoft.SharePoint.Client.ListItem`

*userRoleAssignments*: An array of recipients with the assigned role on the **securable object**.

Type: CSOM array of `Microsoft.SharePoint.Client.Sharing.UserRoleAssignment`

*validateExistingPermissions*: A Boolean flag indicating how to honor a requested permission for a user. If this value is "true", the protocol server will not grant the requested permission if a user already has enough permissions, and if this value is "false", the protocol server will grant the requested permission whether or not a user already has the same or more permissions. This parameter is applicable only when the parameter `additiveMode` is set to true.

Type: **CSOM Boolean**

*additiveMode*: A Boolean flag indicating whether the permission setting uses the additive or strict mode. If this value is "true", the permission setting uses the additive mode, which means that the specified permission will be added to the user's current list of permissions if it is not there already, and if this value is "false", the permission setting uses the strict mode, which means that the specified permission will replace the user's current permissions.

Type: CSOM Boolean

*sendServerManagedNotification*: A Boolean flag to indicate whether to generate an email notification to each recipient in the "userRoleAssignments" array after the document update is completed successfully. If this value is "true", the protocol server will send an email notification if an email server is configured, and if the value is "false", no email notification will be sent.

Type: CSOM Boolean

*customMessage*: A custom message to be included in the email notification.

Type: **CSOM String**

*includeAnonymousLinksInNotification*: A Boolean flag that indicates whether to include anonymous access links in the email notification to each recipient in the `userRoleAssignments` array after the document update is completed successfully. If the value is "true", the protocol server will include an anonymous access link in the email notification, and if the value is "false", no link will be included.

Type: CSOM Boolean

*propagateAcl*: A flag to determine if permissions SHOULD be pushed to items with unique permission.

Type: CSOM Boolean

### 3.2.5.439.2.2 ObjectPath Methods

#### 3.2.5.439.2.2.1 ForwardObjectLink

This method is a **static CSOM method**.

**Return Type:** Microsoft.SharePoint.Client.SharingResult

Shares an object in SharePoint, such as a **list item** or a site with no **ACL** changes, by sending the link. This is used when the user has no permission to share and cannot send access request. The user can use this method to send the link of the object to site members who already have permission to view the object.

**Parameters:**

*item*: The list item intended to be shared.

Type: Microsoft.SharePoint.Client.ListItem

*peoplePickerInput*: A string of JSON serialized data representing a list of **principals** in people picker format. Entries in the people picker MUST be existing site members who have view-permission to the object.

Type: **CSOM String**

*emailSubject*: The e-mail subject.

Type: CSOM String

*emailBody*: The e-mail body.

Type: CSOM String

#### 3.2.5.439.2.2.2 GetObjectSharingSettings

This method is a **static CSOM method**.

**Return Type:** Microsoft.SharePoint.Client.ObjectSharingSettings

Gets the sharing settings of a **list item**.

**Parameters:**

*item*: List item for which we want the sharing settings.

Type: Microsoft.SharePoint.Client.ListItem

*useSimplifiedRoles*: Boolean value input to use simplified roles.

Type: **CSOM Boolean**

### 3.2.5.439.2.2.3 GetSharingInformation

This method is a **static CSOM method**.

**Return Type:** Microsoft.SharePoint.Client.Sharing.SharingInformation

Gets the sharing information for a **list item**.

#### Parameters:

*listItem*: The intended list item for which Sharing Information needs to be returned.

Type: Microsoft.SharePoint.Client.ListItem

*request*: The **SharingInformationRequest** object.

Type: Microsoft.SharePoint.Client.Sharing.SharingInformationRequest

### 3.2.5.439.2.2.4 ShareObject

This method is a **static CSOM method**.

**Return Type:** Microsoft.SharePoint.Client.SharingResult

This method shares a **list item**. It returns a **SharingResult** object which contains the completion script and a page to redirect to if desired.

#### Parameters:

*item*: The list item intended to be shared.

Type: Microsoft.SharePoint.Client.ListItem

*peoplePickerInput*: A string of JSON serialized data representing a list of **principals** in people picker format.

Type: **CSOM String**

*roleValue*: The sharing role value for the type of permission to grant on the object.

Type: CSOM String

*groupId*: The ID of the group to be added. Zero if not adding to a permissions group.

Type: **CSOM Int32**

*propagateAcl*: A flag to determine if permissions SHOULD be pushed to items with unique permissions.

Type: **CSOM Boolean**

*sendEmail*: A flag to determine if an email notification SHOULD be sent (if email is configured).

Type: CSOM Boolean

*includeAnonymousLinkInEmail*: If an email is being sent, this determines if an anonymous link SHOULD be added to the message.

Type: CSOM Boolean

*emailSubject*: The email subject.

Type: CSOM String

*emailBody*: The email body.

Type: CSOM String

*useSimplifiedRoles*: A Boolean value indicating whether to use the SharePoint simplified roles (Edit, View) or not.

Type: CSOM Boolean

### **3.2.5.439.2.2.5 UnshareObject**

This method is a **static CSOM method**.

**Return Type:** Microsoft.SharePoint.Client.SharingResult

Removes Sharing permissions on an object

#### **Parameters:**

*item*: The **list item** intended to be unshared.

Type: Microsoft.SharePoint.Client.ListItem

### **3.2.5.440 Microsoft.SharePoint.Client.Sharing.SharedDocInfoSet**

**TypeId:** {3AED49F2-5B02-4F61-AFC7-CFB212CA8FCF}

**ShortName:** SP.Sharing.SharedDocInfoSet

Microsoft.SharePoint.Client.SharingSharedDocInfoSet is not applicable. [<272>](#)

#### **3.2.5.440.1 Properties**

##### **3.2.5.440.1.1 Scalar Properties**

None.

##### **3.2.5.440.1.2 ObjectPath Properties**

None.

#### **3.2.5.440.2 Methods**

##### **3.2.5.440.2.1 Scalar Methods**

None.

##### **3.2.5.440.2.2 ObjectPath Methods**

None.

### **3.2.5.441 Microsoft.SharePoint.Client.Sharing.SharedObjectType**

**ShortName:** SP.Sharing.SharedObjectType

**Flag:** false



Identifies the type of object that is shared

### **3.2.5.441.1 Field Values**

#### **3.2.5.441.1.1 Unknown**

**Value:** 0

The object type is unable to be determined.

#### **3.2.5.441.1.2 File**

**Value:** 1

The object is a **file** stored in a **list**.

#### **3.2.5.441.1.3 Folder**

**Value:** 2

The object is a **list folder**.

#### **3.2.5.441.1.4 Item**

**Value:** 3

The object is a **list item**.

#### **3.2.5.441.1.5 List**

**Value:** 4

The object is a **list**.

#### **3.2.5.441.1.6 Web**

**Value:** 5

The object is a **Web site**.

#### **3.2.5.441.1.7 Max**

**Value:** 6

Unused

### **3.2.5.442 Microsoft.SharePoint.Client.Sharing.ShareLinkRequest**

**TypeId:** {3FE76F3E-CABD-4AA2-8091-D0345E2EAC74}

**ShortName:** SP.Sharing.ShareLinkRequest

Represents a request for the retrieval or creation of a **tokenized sharing link**.

#### **3.2.5.442.1 Properties**

##### **3.2.5.442.1.1 Scalar Properties**

### 3.2.5.442.1.1.1 createLink

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Indicates whether the operation attempts to create the **tokenized sharing link** based on the requested settings if it does not currently exist.

If set to true, the operation will attempt to retrieve an existing tokenized sharing link that matches the requested settings and failing that will attempt to create a new tokenized sharing link based on the requested settings. If false, the operation will attempt to retrieve an existing tokenized sharing link that matches the requested settings and failing that will terminate the operation.

### 3.2.5.442.1.1.2 emailData

**Type:** Microsoft.SharePoint.Client.Sharing.EmailData

**Accessibility:** Read/Write

This contains optional data that defines some of the content in the email message sent to the list of identities in the **peoplePickerInput** field (section [3.2.5.442.1.1.5](#)). If populated, an email message will be sent to the email addresses of each of the identities once the **tokenized sharing link** is retrieved or created.

If email is intended to be sent but no optional message values are to be set, this value MUST be populated but MUST have no values set within this object.

If email is intended to not be sent, this value is null then no email will be sent.

### 3.2.5.442.1.1.3 expiration

**Type:** CSOM String

**Accessibility:** Read/Write

A date/time string for which the format conforms to the ISO 8601:2004(E) complete representation for calendar date and time of day and which represents the time and date of expiry for the **tokenized sharing link**. Both the minutes and hour value MUST be specified for the difference between the local and UTC time. Midnight is represented as 00:00:00. For example: YYYYMMDDThhmmssZ YYYYMMDDThhmmss±hhmm YYYYMMDDThhmmss±hh:mm YYYYMMDDThhmmssfffZ YYYY-MM-DDThh:mm:ssZ YYYY-MM-DDThh:mm:ss±hh:mm YYYY-MM-DDThh:mm:ss±hhmm YYYY-MM-DDThh:mm:ss.fffZ A null value indicates no expiry.

This value is only applicable to tokenized sharing links that are **anonymous access links**.

This value MAY be set however it is considered obsolete. This value is superseded by an equivalent expiration value (section [3.2.5.444.1.1.2](#)) of the settings object stored in the settings field (section [3.2.5.442.1.1.6](#)).

### 3.2.5.442.1.1.4 linkKind

**Type:** Microsoft.SharePoint.Client.SharingLinkKind

**Accessibility:** Read/Write

The kind of the **tokenized sharing link** to be created/updated or retrieved.

This value MAY be set however it is considered obsolete. This value is superseded by an equivalent linkKind value (section [3.2.5.444.1.1.4](#)) of the settings object stored in the settings field (section [3.2.5.442.1.1.6](#)).

### 3.2.5.442.1.1.5 peoplePickerInput

**Type:** CSOM String

**Accessibility:** Read/Write

A string of **JSON** serialized data representing users in people picker format. This value specifies a list of identities that will be pre-granted access through the **tokenized sharing link** and optionally sent an e-mail notification.

If this value is null or empty, no identities will be will be pre-granted access through the tokenized sharing link and no notification email will be sent.

### 3.2.5.442.1.1.6 settings

**Type:** Microsoft.SharePoint.Client.Sharing.ShareLinkSettings

**Accessibility:** Read/Write

The settings for the **tokenized sharing link** to be created/updated.

This value MUST NOT be set to Uninitialized (section [3.2.5.315.1.1](#)) nor Direct (section [3.2.5.315.1.2](#)).

### 3.2.5.442.1.2ObjectPath Properties

None.

## 3.2.5.443 Microsoft.SharePoint.Client.Sharing.ShareLinkResponse

**TypeId:** {E8A89A08-8B8B-4216-8E8A-BA21911CCD85}

**ShortName:** SP.Sharing.ShareLinkResponse

Represents a response for a request for the retrieval or creation/update of a **tokenized sharing link**.

### 3.2.5.443.1 Properties

#### 3.2.5.443.1.1Scalar Properties

##### 3.2.5.443.1.1.1 sharingLinkInfo

**Type:** Microsoft.SharePoint.Client.SharingLinkInfo

**Accessibility:** Read Only

A data structure that represents the settings and information about the **tokenized sharing link**. This MUST be populated if the sharing operation is returning a tokenized sharing link.

### 3.2.5.443.1.2ObjectPath Properties

None.

### 3.2.5.444 Microsoft.SharePoint.Client.Sharing.ShareLinkSettings

**TypeId:** {298F5C7C-DCD6-40EA-B0BF-86EE4E92AA26}

**ShortName:** SP.Sharing.ShareLinkSettings

Represents the settings the retrieval or creation/update of a **tokenized sharing link**

#### 3.2.5.444.1 Properties

##### 3.2.5.444.1.1 Scalar Properties

###### 3.2.5.444.1.1.1 allowAnonymousAccess

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Indicates if the **tokenized sharing link** supports anonymous access. This value is optional and defaults to false for **Flexible** links (section [3.2.5.315.1.7](#)) and is ignored for other link kinds.

###### 3.2.5.444.1.1.2 expiration

**Type:** CSOM String

**Accessibility:** Read/Write

A date/time string for which the format conforms to the ISO 8601:2004(E) complete representation for calendar date and time of day and which represents the time and date of expiry for the **tokenized sharing link**. Both the minutes and hour value MUST be specified for the difference between the local and UTC time. Midnight is represented as 00:00:00. For example: YYYYMMDDThhmmssZ  
YYYYMMDDThhmmss±hhmm YYYYMMDDThhmmss±hh:mm YYYYMMDDThhmmssfffZ YYYY-MM-DDThh:mm:ssZ YYYY-MM-DDThh:mm:ss±hh:mm YYYY-MM-DDThh:mm:ss±hhmm YYYY-MM-DDThh:mm:ss.fffZ A null value indicates no expiry.

This value is only applicable to tokenized sharing links that are **anonymous access links**

###### 3.2.5.444.1.1.3 inviteesToRemove

**Type:** CSOM array of Microsoft.SharePoint.Client.Sharing.Principal

**Accessibility:** Read/Write

Optional set of invitee principals to remove from an existing sharing link. This applies only to update operations on existing **tokenized sharing links** that have invitees.

###### 3.2.5.444.1.1.4 linkKind

**Type:** Microsoft.SharePoint.Client.SharingLinkKind

**Accessibility:** Read/Write

The kind of the **tokenized sharing link** to be created/updated or retrieved.

This value MUST NOT be set to **Uninitialized** (section [3.2.5.315.1.1](#)) nor **Direct** (section [3.2.5.315.1.2](#))

###### 3.2.5.444.1.1.5 password

**Type:** CSOM String

**Accessibility:** Read/Write

Optional password value to apply to the **tokenized sharing link**, if it can support password protection.

If this value is null or empty when the **updatePassword** parameter is set, any existing password on the tokenized sharing link MUST be cleared. Any other value will be applied to the tokenized sharing link as a password setting.

### 3.2.5.444.1.1.6 restrictShareMembership

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Indicates if the **tokenized sharing link** restricts share access, allowing only those explicitly invited in advance to use the link.

This value MUST NOT be true when the **allowAnonymousAccess** parameter is true or when the linkKind is any other value than **Flexible** (section [3.2.5.315.1.7](#)).

### 3.2.5.444.1.1.7 role

**Type:** Microsoft.SharePoint.Client.Sharing.Role

**Accessibility:** Read/Write

The role to be used for the **tokenized sharing link**. This is required for **Flexible** links (section [3.2.5.315.1.7](#)) and ignored for all other kinds.

### 3.2.5.444.1.1.8 shareId

**Type:** CSOM GUID

**Accessibility:** Read/Write

The optional unique identifier of an existing section **tokenized sharing link** to be retrieved and updated if necessary.

### 3.2.5.444.1.1.9 updatePassword

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Indicates whether to update (set or clear) the password value for the specified **tokenized sharing link**. This value is applicable only if the tokenized sharing link can support password protection.

If set to true, the password value MUST be applied to the new or existing tokenized sharing link if the link can support password protection. If set to false the password value in this request MUST be ignored.

### 3.2.5.444.1.2 ObjectPath Properties

None.

### 3.2.5.445 Microsoft.SharePoint.Client.Sharing.SharingAbilities

**TypeId:** {BAE25567-A77A-4B28-B922-A0B70D1D2211}

**ShortName:** SP.Sharing.SharingAbilities

Represents the matrix of possible sharing abilities for direct sharing and **tokenized sharing links** along with the state of each capability for the current user.

#### 3.2.5.445.1 Properties

##### 3.2.5.445.1.1 Scalar Properties

###### 3.2.5.445.1.1.1 anonymousLinkAbilities

**Type:** Microsoft.SharePoint.Client.Sharing.SharingLinkAbilities

**Accessibility:** Read Only

Indicates abilities for **anonymous access links**.

###### 3.2.5.445.1.1.2 directSharingAbilities

**Type:** Microsoft.SharePoint.Client.Sharing.DirectSharingAbilities

**Accessibility:** Read Only

Indicates abilities for direct sharing of a **document** using the **canonical URL**.

###### 3.2.5.445.1.1.3 organizationLinkAbilities

**Type:** Microsoft.SharePoint.Client.Sharing.SharingLinkAbilities

**Accessibility:** Read Only

Indicates abilities for **organization access links**.

###### 3.2.5.445.1.1.4 peopleSharingLinkAbilities

**Type:** Microsoft.SharePoint.Client.Sharing.SharingLinkAbilities

**Accessibility:** Read Only

Indicates abilities for **tokenized sharing links** that are configured to support only a predefined restricted membership set.

##### 3.2.5.445.1.2 ObjectPath Properties

None.

### 3.2.5.446 Microsoft.SharePoint.Client.Sharing.SharingAbilityStatus

**TypeId:** {A07D70B0-03A8-4AAE-89F0-C07C460C1F67}

**ShortName:** SP.Sharing.SharingAbilityStatus

Represents the status for a specific sharing capability for the current user.

#### 3.2.5.446.1 Properties

### 3.2.5.446.1.1 Scalar Properties

#### 3.2.5.446.1.1.1 disabledReason

**Type:** Microsoft.SharePoint.Client.Sharing.SharingCapabilityDisabledReason

**Accessibility:** Read Only

Indicates the reason why the capability is disabled if the capability is disabled for any reason.

This value MUST be **None** (section [3.2.5.447.1.2](#)) if the capability is not disabled.

This value MUST be **Unavailable** (section [3.2.5.447.1.1](#)) if this capability is not applicable.

This value MUST be one of the other **SharingCapabilityDisabledReasons** (section [3.2.5.447](#)) if the capability is disabled for any reason.

#### 3.2.5.446.1.1.2 enabled

**Type:** CSOM Boolean

**Accessibility:** Read Only

Indicates whether capability is enabled.

This value MUST be true if this capability is enabled and MUST be false if it is not.

### 3.2.5.446.1.2 ObjectPath Properties

None.

### 3.2.5.447 Microsoft.SharePoint.Client.Sharing.SharingCapabilityDisabledReason

**ShortName:** SP.Sharing.SharingCapabilityDisabledReason

**Flag:** false

The reason why a sharing capability is disabled.

#### 3.2.5.447.1 Field Values

##### 3.2.5.447.1.1 Unavailable

**Value:** -1

Unavailable/not implemented.

##### 3.2.5.447.1.2 None

**Value:** 0

Not disabled.

##### 3.2.5.447.1.3 Disabled

**Value:** 1

Sharing is Disabled.

### **3.2.5.447.1.4NotShareableByLink**

**Value:** 2

Could not be cast to a shareable by link object.

### **3.2.5.447.1.5ParentListIsPrivate**

**Value:** 3

Cannot create **tokenized sharing link** when parent list is private.

### **3.2.5.447.1.6ParentListIsCatalogDocLib**

**Value:** 4

Cannot create **tokenized sharing link** when parent list is catalog document library.

### **3.2.5.447.1.7NotSupportedByWOPI**

**Value:** 5

Cannot create **tokenized sharing link** when container object not supported by WOPI.

### **3.2.5.447.1.8IRMIEnabled**

**Value:** 6

Cannot create a **tokenized sharing link** when **IRM** is enabled.

### **3.2.5.447.1.9DocumentIsProtectedByDLP**

**Value:** 7

Document is blocked from sharing externally due to document lifecycle policy features.

### **3.2.5.447.1.10 ForceCheckoutEditLink**

**Value:** 8

**Anonymous access link** that supports read access are not allowed in a force checkout scenario.

### **3.2.5.447.1.11 AnonymousEditLinkNotAllowedByTenant**

**Value:** 9

**Anonymous access link** that supports edit access is not allowed by tenant anonymous link settings.

### **3.2.5.447.1.12 NonClaimsWebapp**

**Value:** 10

Cannot share **anonymous access links** on non-claims authentication enabled **web application**.

### **3.2.5.447.1.13 AccessDeniedToAnonGuest**

**Value:** 11



User is currently authenticated as an anonymous guest and is attempting to get or create a **tokenized sharing link** so does not have permissions to do so.

#### **3.2.5.447.1.14 BlockedByWhoCanShareSettings**

**Value:** 12

User is not allowed to share to external users due to tenant settings for who can share.

#### **3.2.5.447.1.15 BlockedByExternalShareSettings**

**Value:** 13

User is not allowed to share to external users due to tenant external sharing settings.

#### **3.2.5.447.1.16 AccessDeniedNotEnoughPermissions**

**Value:** 14

User does not have permissions to share.

#### **3.2.5.447.1.17 AccessDeniedToExternalUser**

**Value:** 15

User currently is authenticated as a ShareByEmailGuest and is attempting to get or create a **tokenized sharing link** so does not have permissions to do so.

#### **3.2.5.448 Microsoft.SharePoint.Client.Sharing.SharingDomainRestrictionMode**

**ShortName:** SP.Sharing.SharingDomainRestrictionMode

**Flag:** false

Check if tenant is now honoring allow list or deny list, or just disabled this setting.

##### **3.2.5.448.1 Field Values**

###### **3.2.5.448.1.1None**

**Value:** 0

Tenant has not configured or disabled either allowed or blocked domain list.

###### **3.2.5.448.1.2AllowList**

**Value:** 1

Tenant has configured an active allowed domain list.

###### **3.2.5.448.1.3BlockList**

**Value:** 2

Tenant has configured an active blocked domain list.

### 3.2.5.449 Microsoft.SharePoint.Client.Sharing.SharingInformation

**TypeId:** {A683DDD7-7930-4DCC-88FE-DC326C5E514E}

**ShortName:** SP.Sharing.SharingInformation

Represents a response for  
Microsoft.SharePoint.Client.Sharing.SecurableObjectExtensions.GetSharingInformation.

The accessRequestSettings, domainRestrictionSettings and permissionsInformation properties are not included in the **default scalar property set** for this type.

#### 3.2.5.449.1 Properties

##### 3.2.5.449.1.1 Scalar Properties

###### 3.2.5.449.1.1.1 accessRequestSettings

**Type:** Microsoft.SharePoint.Client.Sharing.AccessRequestSettings

**Accessibility:** Read Only

**AccessRequestSettings** is an optional property set to retrieve details for pending access requests if present.

###### 3.2.5.449.1.1.2 anonymousLinkExpirationRestrictionDays

**Type:** CSOM Int32

**Accessibility:** Read/Write

Tenant's anonymous link expiration restriction in days.

###### 3.2.5.449.1.1.3 blockPeoplePickerAndSharing

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Boolean indicating whether the current user can use the People Picker to do any sharing.

###### 3.2.5.449.1.1.4 canAddExternalPrincipal

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Boolean indicating if the current user can perform External Sharing.

###### 3.2.5.449.1.1.5 canAddInternalPrincipal

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Boolean indicating if the current user can perform Internal Sharing with users in the same tenancy.

###### 3.2.5.449.1.1.6 canRequestAccessForGrantAccess

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Boolean indicating is access request ON/OFF for Sharing.

### **3.2.5.449.1.1.7      canSendEmail**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Boolean indicating of the current user has rights to Send Email.

### **3.2.5.449.1.1.8      canUseSimplifiedRoles**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Boolean indicating if can use simplified roles is present in the Roles enum.

### **3.2.5.449.1.1.9      currentRole**

**Type:** Microsoft.SharePoint.Client.Sharing.Role

**Accessibility:** Read/Write

The current user's **Role** on the **list item**.

### **3.2.5.449.1.1.10     defaultLinkKind**

**Type:** Microsoft.SharePoint.Client.SharingLinkKind

**Accessibility:** Read/Write

The default **SharingLinkKind**.

### **3.2.5.449.1.1.11     defaultShareLinkPermission**

**Type:** Microsoft.SharePoint.Client.Sharing.Role

**Accessibility:** Read/Write

The Default **tokenized sharing link** permission returned as a Role.

### **3.2.5.449.1.1.12     directUrl**

**Type:** CSOM String

**Accessibility:** Read/Write

The **full URL** for the **list item** (Encoded).

### **3.2.5.449.1.1.13     domainRestrictionSettings**

**Type:** Microsoft.SharePoint.Client.Sharing.DomainRestrictionSettings

**Accessibility:** Read Only

Whether **DomainRestrictionSettings** is used to limit the external Users set by Admin.

### 3.2.5.449.1.1.14 hasUniquePermissions

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Boolean indicating if the current **list item** has unique permissions.

### 3.2.5.449.1.1.15 microserviceShareUiUrl

**Type:** CSOM String

**Accessibility:** Read/Write

Microservice Share UI Url for the Securable Object (Encoded).

### 3.2.5.449.1.1.16 permissionsInformation

**Type:** Microsoft.SharePoint.Client.Sharing.PermissionCollection

**Accessibility:** Read Only

The **PermissionCollection** that are on the **list item**. It contains a collection of **PrincipalInfo** and **LinkInfo**.

### 3.2.5.449.1.1.17 sharedObjectType

**Type:** Microsoft.SharePoint.Client.Sharing.SharedObjectType

**Accessibility:** Read/Write

The type of **list item** (SPSharedObjectType).

### 3.2.5.449.1.1.18 shareUiUrl

**Type:** CSOM String

**Accessibility:** Read/Write

The **full URL** where the Share control for the **list item** is hosted. (Encoded).

### 3.2.5.449.1.1.19 sharingAbilities

**Type:** Microsoft.SharePoint.Client.Sharing.SharingAbilities

**Accessibility:** Read/Write

Matrix of possible sharing abilities per sharing type and the state of each capability for the current user on the **list item**.

### 3.2.5.449.1.1.20 sharingStatus

**Type:** Microsoft.SharePoint.Client.Sharing.SharingStatus

**Accessibility:** Read/Write

**SharingStatus** of the current **list item**. It refers to whether its shared or private in personal default **document library**.

### 3.2.5.449.1.1.21 showExternalSharingWarning

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Boolean indicating whether the client logic warns the user that they are about to share with external email addresses.

### 3.2.5.449.1.1.22 **webUrl**

**Type:** CSOM String

**Accessibility:** Read/Write

Parent Web **full URL** for the **list item** (Encoded).

## 3.2.5.449.1.2 **ObjectPath Properties**

### 3.2.5.449.1.2.1 **pickerSettings**

**Type:** Microsoft.SharePoint.Client.PickerSettings

**Accessibility:** Read Only

PickerSettings used by the PeoplePicker Control.

## 3.2.5.449.2 **Methods**

### 3.2.5.449.2.1 **Scalar Methods**

None.

### 3.2.5.449.2.2 **ObjectPath Methods**

None.

## 3.2.5.450 **Microsoft.SharePoint.Client.Sharing.SharingInformationRequest**

**TypeId:** {F66716BA-8B69-477C-8509-BAF98B4F60DE}

**ShortName:** SP.Sharing.SharingInformationRequest

Represents the optional Request Object for Microsoft.SharePoint.Client.Sharing.SecurableObjectExtensions.GetSharingInformation.

### 3.2.5.450.1 **Properties**

#### 3.2.5.450.1.1 **Scalar Properties**

##### 3.2.5.450.1.1.1 **clientSupportedFeatures**

**Type:** CSOM String

**Accessibility:** Read/Write

Supported Features (For future use by Office Client).

##### 3.2.5.450.1.1.2 **maxPrincipalsToReturn**

**Type:** CSOM Int32

**Accessibility:** Read/Write

Maximum number of principals to return.

### 3.2.5.450.1.2 ObjectPath Properties

None.

### 3.2.5.451 Microsoft.SharePoint.Client.Sharing.SharingLinkAbilities

**TypeId:** {C6DA9A62-B159-43B8-8C38-144F3E70D14F}

**ShortName:** SP.Sharing.SharingLinkAbilities

Represents the set of capabilities for specific configurations of **tokenized sharing link** for the current user and whether they are enabled or not.

#### 3.2.5.451.1 Properties

##### 3.2.5.451.1.1 Scalar Properties

###### 3.2.5.451.1.1.1 canGetEditLink

**Type:** Microsoft.SharePoint.Client.Sharing.SharingAbilityStatus

**Accessibility:** Read Only

Indicates whether the current user can get an existing **tokenized sharing link** that provides edit access.

###### 3.2.5.451.1.1.2 canGetReadLink

**Type:** Microsoft.SharePoint.Client.Sharing.SharingAbilityStatus

**Accessibility:** Read Only

Indicates whether the current user can get an existing **tokenized sharing link** that provides read access.

###### 3.2.5.451.1.1.3 canHaveExternalUsers

**Type:** Microsoft.SharePoint.Client.Sharing.SharingAbilityStatus

**Accessibility:** Read Only

Indicates whether the **tokenized sharing link** supports external users.

###### 3.2.5.451.1.1.4 canManageEditLink

**Type:** Microsoft.SharePoint.Client.Sharing.SharingAbilityStatus

**Accessibility:** Read Only

Indicates whether current user can create/manage a **tokenized sharing link** that provides edit access.

###### 3.2.5.451.1.1.5 canManageReadLink

**Type:** Microsoft.SharePoint.Client.Sharing.SharingAbilityStatus

**Accessibility:** Read Only

Indicates whether the current user can create/manage a **tokenized sharing link** that provides read access.

### 3.2.5.451.1.1.6 linkExpiration

**Type:** Microsoft.SharePoint.Client.Sharing.SharingLinkExpirationAbilityStatus

**Accessibility:** Read Only

Indicates whether the **tokenized sharing link** supports expiration.

### 3.2.5.451.1.1.7 passwordProtected

**Type:** Microsoft.SharePoint.Client.Sharing.SharingLinkPasswordAbilityStatus

**Accessibility:** Read Only

Indicates whether the **tokenized sharing link** supports password protection.

### 3.2.5.451.1.2 ObjectPath Properties

None.

## 3.2.5.452 Microsoft.SharePoint.Client.Sharing.SharingLinkAccessRequest

**TypeId:** {52F77AAE-0FED-4F77-B13D-1C039129F39D}

**ShortName:** SP.Sharing.SharingLinkAccessRequest

Represents extended values to include in a request for access to an object exposed through a **tokenized sharing link**.

### 3.2.5.452.1 Properties

#### 3.2.5.452.1.1 Scalar Properties

##### 3.2.5.452.1.1.1 ensureAccess

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Indicates if the request to the **tokenized sharing link** grants perpetual access to the calling user.

##### 3.2.5.452.1.1.2 password

**Type:** CSOM String

**Accessibility:** Read/Write

This value contains the password to be supplied to a **tokenized sharing link** for validation. This value is only needed if the link requires a password before granting access and the calling user does not currently have perpetual access through the tokenized sharing link.

This value MUST be set to the correct password for the tokenized sharing link for the access granting operation to succeed. If the tokenized sharing link does not require a password or the calling user already has perpetual access through the tokenized sharing link, this value will be ignored.

### 3.2.5.452.1.2ObjectPath Properties

None.

### 3.2.5.453 Microsoft.SharePoint.Client.Sharing.SharingLinkExpirationAbilityStatus

**TypeId:** {1F935920-81AE-4BCC-9B37-6AAEA648F3FD}

**ShortName:** SP.Sharing.SharingLinkExpirationAbilityStatus

Represents expiration capabilities status for **tokenized sharing links** for the current user.

#### 3.2.5.453.1 Properties

##### 3.2.5.453.1.1Scalar Properties

###### 3.2.5.453.1.1.1 defaultExpirationInDays

**Type:** CSOM Int32

**Accessibility:** Read Only

Indicates the default expiration value.

###### 3.2.5.453.1.1.2 disabledReason

**Type:** Microsoft.SharePoint.Client.Sharing.SharingCapabilityDisabledReason

**Accessibility:** Read Only

Indicates the reason why this ability is disabled.

This value MUST be None (section [3.2.5.447.1.2](#)) if the ability is not disabled.

This value MUST be Unavailable (section [3.2.5.447.1.1](#)) if this capability is not applicable.

This value MUST be one of the other SharingCapabilityDisabledReasons (section [3.2.5.447](#)) if the capability is disabled for any reason.

###### 3.2.5.453.1.1.3 enabled

**Type:** CSOM Boolean

**Accessibility:** Read Only

Indicates whether this ability is enabled.

This value MUST be true if this ability is enabled and MUST be false if it is not.

### 3.2.5.453.1.2ObjectPath Properties

None.



### 3.2.5.454 Microsoft.SharePoint.Client.Sharing.SharingLinkPasswordAbilityStatus

**TypeId:** {5FA2CA32-318D-44A4-9811-6E0CA65351B9}

**ShortName:** SP.Sharing.SharingLinkPasswordAbilityStatus

Represents password capabilities status for **tokenized sharing links** for the current user.

#### 3.2.5.454.1 Properties

##### 3.2.5.454.1.1 Scalar Properties

###### 3.2.5.454.1.1.1 disabledReason

**Type:** Microsoft.SharePoint.Client.Sharing.SharingCapabilityDisabledReason

**Accessibility:** Read Only

Indicates reason why ability is disabled.

This value MUST be None (section [3.2.5.447.1.2](#)) if the ability is not disabled.

This value MUST be Unavailable (section [3.2.5.447.1.1](#)) if this capability is not applicable.

This value MUST be one of the other SharingCapabilityDisabledReasons (section [3.2.5.447](#)) if the capability is disabled for any reason.

###### 3.2.5.454.1.1.2 enabled

**Type:** CSOM Boolean

**Accessibility:** Read Only

Indicates whether this ability is enabled.

This value MUST be true if this ability is enabled and MUST be false if it is not.

##### 3.2.5.454.1.2 ObjectPath Properties

None.

### 3.2.5.455 Microsoft.SharePoint.Client.Sharing.SharingStatus

**ShortName:** SP.Sharing.SharingStatus

**Flag:** false

Contains the values of 3 allowed Sharing Status of a **list item**. The values are applicable to the list items present in the users personal document library.

#### 3.2.5.455.1 Field Values

##### 3.2.5.455.1.1 Unavailable

**Value:** -1

Unavailable or not implemented.

##### 3.2.5.455.1.2 Private

**Value:** 1

Not Shared.

### **3.2.5.455.1.3 Shared**

**Value:** 2

Shared.

## **3.2.5.456 Microsoft.SharePoint.Client.Sharing.UserDirectoryInfo**

**TypeId:** {7FF155A1-B124-4E27-A0BE-F96AAF7AB861}

**ShortName:** SP.Sharing.UserDirectoryInfo

User information from directory service.

### **3.2.5.456.1 Properties**

#### **3.2.5.456.1.1 Scalar Properties**

##### **3.2.5.456.1.1.1 Name**

**Type:** CSOM String

**Accessibility:** Read/Write

Name of the directory user.

##### **3.2.5.456.1.1.2 NetId**

**Type:** CSOM String

**Accessibility:** Read/Write

User NetId property in directory.

##### **3.2.5.456.1.1.3 PrimaryEmail**

**Type:** CSOM String

**Accessibility:** Read/Write

User primary email of the directory user. E.g. user@domain.com.

##### **3.2.5.456.1.1.4 PrincipalName**

**Type:** CSOM String

**Accessibility:** Read/Write

Principal name of the directory user. E.g. user@domain.com.

#### **3.2.5.456.1.2 ObjectPath Properties**

None.

### 3.2.5.457 Microsoft.SharePoint.Client.SharingLinkData

**TypeId:** {28A0779D-8BC1-4F12-8D19-23FD631BEA10}

**ShortName:** SP.SharingLinkData

This class stores basic overview information about the link URL, including limited data about the object the link URL refers to and any additional sharing link data if the link URL is a **tokenized sharing link**.

#### 3.2.5.457.1 Properties

##### 3.2.5.457.1.1 Scalar Properties

###### 3.2.5.457.1.1.1 Expiration

**Type:** CSOM String

**Accessibility:** Read/Write

The UTC date/time string with complete representation for calendar date and time of day which represents the time and date of expiry for the **tokenized sharing link** (i.e. is not accessible anymore). Format returned from get operation is "YYYY-MM-DDThh:mm:ss.fffZ" (e.g. "2016-09-22T12:20:10.125Z"), with a null value indicating no expiry. The date/time string format for set operations conforms to the ISO 8601:2004(E) complete representation for calendar date and time of day. Both the minutes and hour value MUST be specified for the difference between the local and UTC time. Midnight is represented as 00:00:00. For example: YYYYMMDDThhmmssZ YYYYMMDDThhmmss±hhmm YYYYMMDDThhmmss±hh:mm YYYYMMDDThhmmssfffZ YYYY-MM-DDThh:mm:ssZ YYYY-MM-DDThh:mm:ss±hh:mm YYYY-MM-DDThh:mm:ss±hhmm YYYY-MM-DDThh:mm:ss.fffZ A null value indicates no expiry.

If the link URL is a tokenized sharing link that supports expiration and has an expiration value set, this MUST indicate when the tokenized sharing link is set to expire and stop providing access through the link, it MUST be null otherwise.

###### 3.2.5.457.1.1.2 HasExternalGuestInvitees

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Boolean indicating whether the link URL is a **tokenized sharing link** that has any external guest invitees (external users explicitly invited by email address).

This value MUST be true only if the link URL is a tokenized sharing link which is configured to support specific external guest invitees, otherwise this MUST be false.

###### 3.2.5.457.1.1.3 IsAnonymous

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Boolean indicating if the link is anonymously accessible.

This value MUST be true if the link URL is an **anonymous access link**, otherwise this MUST be false.

###### 3.2.5.457.1.1.4 IsFormsLink

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Indicates if the link URL is a **tokenized sharing link** that supports forms sharing. This is limited to only tokenized sharing links generated with the Excel Survey feature.

This value MUST be true only if the link URL is a tokenized sharing link which is configured to support forms sharing, otherwise this MUST be false.

### **3.2.5.457.1.1.5 IsOriginatedFromSharingFlow**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Indicates whether the link URL is generated from sharing dialog.

This value MUST be true only if the link URL contains a value that indicates it originated from the sharing dialog, otherwise this MUST be false.

### **3.2.5.457.1.1.6 IsReviewLink**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Indicates if the link URL is a **tokenized sharing link** that supports review operations.

This value MUST be true only if the link URL is a tokenized sharing link which is configured to support access with the review role, otherwise this MUST be false.

### **3.2.5.457.1.1.7 IsSharingLink**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Indicates if the link URL is a **tokenized sharing link**.

This value MUST be true only if the link URL is a tokenized sharing link, otherwise this MUST be false.

### **3.2.5.457.1.1.8 IsWritable**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Indicates if the link URL is a **tokenized sharing link** that supports write/edit operations.

This value MUST be true only if the link URL is a tokenized sharing link which is configured to support access with the edit role, otherwise this MUST be false.

### **3.2.5.457.1.1.9 LinkKind**

**Type:** Microsoft.SharePoint.Client.SharingLinkKind

**Accessibility:** Read/Write

The kind of link that the link URL refers to.

### **3.2.5.457.1.1.10 ObjectType**

**Type:** Microsoft.SharePoint.Client.Sharing.SharedObjectType

**Accessibility:** Read/Write

The type of object the link URL refers to.

#### **3.2.5.457.1.1.11 ObjectUniqueId**

**Type:** CSOM GUID

**Accessibility:** Read/Write

The unique identifier of the object the link URL refers to.

#### **3.2.5.457.1.1.12 RequiresPassword**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Indicates if the link URL is a **tokenized sharing link** that requires a password before users can gain access.

This value MUST be true only if the link URL is a tokenized sharing link which is configured to support access only with a password, otherwise this MUST be false.

#### **3.2.5.457.1.1.13 RestrictedShareMembership**

**Type:** CSOM Boolean

**Accessibility:** Read/Write

Indicates whether the link URL allows access only to a specified membership set.

This MUST be true if the link URL is a **tokenized sharing link** that is configured to support restricted share membership, or if the link URL is the **canonical URL** for a document as access is enforced by membership in an **access control list (ACL)**, otherwise it MUST be false.

#### **3.2.5.457.1.1.14 ShareId**

**Type:** CSOM GUID

**Accessibility:** Read/Write

The identifier of the object that stores the settings of a **tokenized sharing link** specified by the link URL.

This value MUST be an **empty GUID** if the link URL is not a tokenized sharing link and MUST be set to the identity of the object that stores the settings if the link URL is a tokenized sharing link.

### **3.2.5.457.1.2 ObjectPath Properties**

None.

### **3.2.5.458 Microsoft.SharePoint.Client.SharingState**

**ShortName:** SP.SharingState

**Flag:** false

Contains the values of the 3 allowed states for Sharing properties.

### **3.2.5.458.1 Field Values**

#### **3.2.5.458.1.1 Unspecified**

**Value:** 0

State 1: Unspecified. Implies that the Tenant Admin is choosing to let Site and Web Owners specify the behavior for Sharing Property State

#### **3.2.5.458.1.2 On**

**Value:** 1

State 2: On. Implies that Tenant Admin is forcing Sharing Property State to behave as if they are set to True

#### **3.2.5.458.1.3 Off**

**Value:** 2

State 3: Off. Implies that Tenant Admin is forcing Sharing Property State to behave as if they are set to False

### **3.2.5.459 Microsoft.SharePoint.Client.SharingUtility**

**TypeId:** {92EE6C48-9E9C-456A-801F-63E68A88C184}

**ShortName:** SP.SharingUtility

Provides sharing related utility methods.

#### **3.2.5.459.1 Properties**

##### **3.2.5.459.1.1 Scalar Properties**

None.

##### **3.2.5.459.1.2 ObjectPath Properties**

None.

#### **3.2.5.459.2 Methods**

##### **3.2.5.459.2.1 Scalar Methods**

###### **3.2.5.459.2.1.1 GetUserDirectoryInfoByEmail**

This method is a **static CSOM method**.

**Return Type:** Microsoft.SharePoint.Client.Sharing.UserDirectoryInfo

Get user information by the user's email address in directory.

**Parameters:**

*email:* The email address of a user.

Type: **CSOM String**

### **3.2.5.459.2.1.2 ValidateSameUserEmails**

This method is a **static CSOM method**.

**Return Type:** **CSOM Boolean**

Validate the primary email/principal name and other email are of the same user.

**Parameters:**

*primaryEmail*: User's primary email address

Type: **CSOM String**

*otherEmail*: Another email address.

Type: CSOM String

*principalName*: User's principal name.

Type: CSOM String

### **3.2.5.459.2.2 ObjectPath Methods**

None.

### **3.2.5.460 Microsoft.SharePoint.Client.ShowInFiltersPaneStatus**

**ShortName:** SP.ShowInFiltersPaneStatus

**Flag:** false

Represents status to determine whether the filters pane will show the field.

#### **3.2.5.460.1 Field Values**

##### **3.2.5.460.1.1 Auto**

**Value:** 0

Field will be auto determined to show/hide in filters pane based on the list data.

##### **3.2.5.460.1.2 Pinned**

**Value:** 1

Field will pin in Filters pane.

##### **3.2.5.460.1.3 Removed**

**Value:** 2

Field will never show in filters pane.

### **3.2.5.461 Microsoft.SharePoint.Client.SP BingMapsInformation**

**TypeId:** {9C6E38AD-BBFE-472E-A5CB-7F9DD9F60EE3}

**ShortName:** SP.SP BingMapsInformation

Represents the Bing maps key and related configurations. These configurations are set by administrator with PowerShell Cmdlets.

### 3.2.5.461.1 Properties

#### 3.2.5.461.1.1 Scalar Properties

##### 3.2.5.461.1.1.1 IsBlockedInCurrentRegion

**Type:** CSOM Boolean

**Accessibility:** Read/Write

A flag indicates if the current region is blocked to use Bing maps by administrator.

This configuration is set by Set-SPBingMapsBlock Cmdlet. The value is same as retrieved from Get-SPBingMapsBlock Cmdlet.

##### 3.2.5.461.1.1.2 Key

**Type:** CSOM String

**Accessibility:** Read/Write

The Bing maps key configured by administrator.

This configuration is set by Set-SPBingMapsKey Cmdlet. The value is same as retrieved from Get-SPBingMapsKey Cmdlet.

#### 3.2.5.461.1.2 ObjectPath Properties

None.

### 3.2.5.461.2 Methods

#### 3.2.5.461.2.1 Scalar Methods

None.

#### 3.2.5.461.2.2 ObjectPath Methods

None.

### 3.2.5.462 Microsoft.SharePoint.Client.SPChangeActivityType

**ShortName:** SP.SPChangeActivityType

**Flag:** false

Activity types.

#### 3.2.5.462.1 Field Values

##### 3.2.5.462.1.1 NoActivity

**Value:** 0



No activity.

### **3.2.5.462.1.2Hashtag**

**Value:** 1

Hashtag activity.

### **3.2.5.462.1.3Spotlight**

**Value:** 2

Spotlight activity.

### **3.2.5.462.1.4Comment**

**Value:** 3

**Comment** activity.

## **3.2.5.463 Microsoft.SharePoint.Client.SPOpenBinaryOptions**

**ShortName:** SP.SPOpenBinaryOptions

**Flag:** true

Provides values to pass when opening a binary stream file when using the **OpenBinary** or **OpenBinaryStream** methods.

### **3.2.5.463.1 Field Values**

#### **3.2.5.463.1.1None**

**Value:** 0

Provides no options on opening the binary file stream.

#### **3.2.5.463.1.2Unprotected**

**Value:** 2

Disables information rights management for this operation.

#### **3.2.5.463.1.3SkipVirusScan**

**Value:** 4

Enables opening a binary stream file without running a virus scan when using the **OpenBinary** or **OpenBinaryStream** methods.

#### **3.2.5.463.1.4MinimizeProcessing**

**Value:** 1

Does not write back changes to the stream lazily made by the parser (e.x. link fixup).

### 3.2.5.464 Microsoft.SharePoint.Client.SPScriptSafeDomainsCollection

**TypeId:** {C971BEDB-702E-47AE-9A24-41137291A744}

**ShortName:** SP.SPScriptSafeDomainsCollection

Microsoft.SharePoint.Client.SPScriptSafeDomainsCollection is not applicable. <273>

#### 3.2.5.464.1 Properties

##### 3.2.5.464.1.1 Scalar Properties

None.

##### 3.2.5.464.1.2 ObjectPath Properties

None.

#### 3.2.5.464.2 Methods

##### 3.2.5.464.2.1 Scalar Methods

None.

##### 3.2.5.464.2.2 ObjectPath Methods

###### 3.2.5.464.2.2.1 GetByDomainName

**Return Type:** Microsoft.SharePoint.Client.ScriptSafeDomain

Get ScriptSafeDomain object by domain name.

**Parameters:**

*domainName:* Specifies the domain name.

Type: **CSOM String**

It MUST NOT be empty.

### 3.2.5.465 Microsoft.SharePoint.Client.SPVariantThemeType

**ShortName:** SP.SPVariantThemeType

**Flag:** false

Microsoft.SharePoint.Client.SPVariantThemeType is not applicable. <274>

#### 3.2.5.465.1 Field Values

None.

### 3.2.5.466 Microsoft.SharePoint.Client.SPVirusCheckStatus

**ShortName:** SP.SPVirusCheckStatus

**Flag:** false

Specifies the virus infection status of the file.

### **3.2.5.466.1 Field Values**

#### **3.2.5.466.1.1 Clean**

**Value:** 0

The file is clean.

#### **3.2.5.466.1.2 Infected**

**Value:** 1

The file is infected.

#### **3.2.5.466.1.3 InfectedCleanable**

**Value:** 2

The file is infected and cleanable.

#### **3.2.5.466.1.4 Cleaned**

**Value:** 3

The file is cleaned.

#### **3.2.5.466.1.5 CleanFailed**

**Value:** 4

Failed on cleaning the file.

#### **3.2.5.466.1.6 Deleted**

**Value:** 5

The file is deleted.

#### **3.2.5.466.1.7 Timeout**

**Value:** 6

Error for virus scanning.

### **3.2.5.467 Microsoft.SharePoint.Client.TeamChannelManager**

**TypeId:** {9C3B73DF-2147-4E44-AFF6-DAF69B75EF2B}

**ShortName:** SP.TeamChannelManager

This class is a placeholder for all TeamChannel related methods.

#### **3.2.5.467.1 Properties**

##### **3.2.5.467.1.1 Scalar Properties**

None.

### 3.2.5.467.1.2 ObjectPath Properties

None.

### 3.2.5.467.2 Methods

#### 3.2.5.467.2.1 Scalar Methods

##### 3.2.5.467.2.1.1 DemoteTeamChannelById

This method is a **static CSOM method**.

**Return Type:** CSOM Boolean

Disconnects a folder from a team channel. Removes the team channel ProgId and leave the team channel Url alone.

**Parameters:**

*folderId*: Specifies the ID of the folder.

Type: **CSOM GUID**

It MUST NOT be NULL.

##### 3.2.5.467.2.1.2 DemoteTeamChannelByPath

This method is a **static CSOM method**.

**Return Type:** CSOM Boolean

Disconnect a folder from a team channel. take away the team channel ProgId and leave the team channel Url alone.

**Parameters:**

*folderPath*: Specifies the server relative path for the folder.

Type: Microsoft.SharePoint.Client.ResourcePath

It MUST NOT be NULL.

##### 3.2.5.467.2.1.3 PromoteToTeamChannelById

This method is a **static CSOM method**.

**Return Type:** CSOM Boolean

Promote a folder to a team channel. Give it the team channel ProgId and set the team channel Url

**Parameters:**

*folderId*: Specifies the **GUID** of the folder.

Type: **CSOM GUID**

It MUST NOT be NULL.

*teamChannelUrl*: Specifies the team channel **URL**.

Type: **CSOM String**

*channelName*: Specifies the name of the channel. If empty, the existing folder name will be kept as is.

Type: CSOM String

### **3.2.5.467.2.1.4 PromoteToTeamChannelByPath**

This method is a **static CSOM method**.

**Return Type:** **CSOM Boolean**

Promote a folder to a team channel. Give it the team channel ProgId and set the team channel Url

**Parameters:**

*folderPath*: Specifies the server relative path for the folder.

Type: Microsoft.SharePoint.Client.ResourcePath

It MUST NOT be NULL.

*teamChannelUrl*: Specifies the team channel **URL**.

Type: **CSOM String**

*channelName*: Specifies the name of the channel. If empty, the existing folder name will be kept as is.

Type: CSOM String

### **3.2.5.467.2.2 ObjectPath Methods**

#### **3.2.5.467.2.2.1 AddTeamChannel**

This method is a **static CSOM method**.

**Return Type:** Microsoft.SharePoint.Client.Folder

Create Team Channel based folder with specific prodID.

**Parameters:**

*parentFolderPath*: Server relative path of the folder.

Type: Microsoft.SharePoint.Client.ResourcePath

It MUST NOT be NULL.

*newFolderPath*: New folder name.

Type: Microsoft.SharePoint.Client.ResourcePath

It MUST NOT be NULL.

*teamChannelUrl*: Team channel URL to be stored in the folder metadata.

Type: **CSOM String**

### **3.2.5.468 Microsoft.SharePoint.Client.Utilities.FileHandlerWopiProperties**

**TypeId:** {D5F6D0C5-4056-4951-B565-F3E558D37289}

**ShortName:** SP.Utilities.FileHandlerWopiProperties

Microsoft.SharePoint.Client.Utilities.FileHandlerWopiProperties is not applicable. [.<275>](#)

### **3.2.5.468.1 Properties**

#### **3.2.5.468.1.1 Scalar Properties**

None.

#### **3.2.5.468.1.2 ObjectPath Properties**

None.

### **3.2.5.468.2 Methods**

#### **3.2.5.468.2.1 Scalar Methods**

None.

#### **3.2.5.468.2.2 ObjectPath Methods**

None.

### **3.2.5.469 Microsoft.SharePoint.Client.Utilities.JsonTheme**

**TypeId:** {CAA8F0B6-1852-4D37-9FE7-565664BD32AB}

**ShortName:** SP.Utilities.JsonTheme

Microsoft.SharePoint.Client.Utilities.JsonTheme is not applicable. [.<276>](#)

### **3.2.5.469.1 Properties**

#### **3.2.5.469.1.1 Scalar Properties**

None.

#### **3.2.5.469.1.2 ObjectPath Properties**

None.

### **3.2.5.470 Microsoft.SharePoint.Client.Utilities.NewsItem**

**TypeId:** {E56C7408-C249-40F9-8209-E58C234C8403}

**ShortName:** SP.Utilities.NewsItem

Represents an item in the News List.

### **3.2.5.470.1 Properties**

#### **3.2.5.470.1.1 Scalar Properties**

##### **3.2.5.470.1.1.1 backupPictureUri**

**Type:** CSOM String

**Accessibility:** Read/Write

The url of the picture to use for this News Item if the primary picture breaks.

### **3.2.5.470.1.1.2 caption**

**Type:** CSOM String

**Accessibility:** Read/Write

The caption for the News Item.

### **3.2.5.470.1.1.3 fileExtension**

**Type:** CSOM String

**Accessibility:** Read/Write

File extension (indicating the type of file) if the resource is a file.

### **3.2.5.470.1.1.4 itemId**

**Type:** CSOM Int32

**Accessibility:** Read/Write

The id of the list item storing this news post.

### **3.2.5.470.1.1.5 newsType**

**Type:** Microsoft.SharePoint.Client.Utilities.NewsType

**Accessibility:** Read/Write

Indicates the type of object the resource is.

### **3.2.5.470.1.1.6 pictureAltText**

**Type:** CSOM String

**Accessibility:** Read/Write

Alt text to use on the image of the picture for the News Item.

### **3.2.5.470.1.1.7 pictureUrl**

**Type:** CSOM String

**Accessibility:** Read/Write

The url of the picture for the News Item.

### **3.2.5.470.1.1.8 progId**

**Type:** CSOM String

**Accessibility:** Read/Write

The program identifier for the resource, if the resource is a file or a folder. Used to determine which program to use when the resource is opened.

### **3.2.5.470.1.1.9 properties**

**Type:** CSOM String

**Accessibility:** Read/Write

A JSON blob of properties for the News Item.

### **3.2.5.470.1.1.10 siteId**

**Type:** CSOM GUID

**Accessibility:** Read/Write

The site ID of the SP.Site the resource is in. If the resource is not a recognized type, or is not in a site, this will be the empty Guid.

### **3.2.5.470.1.1.11 title**

**Type:** CSOM String

**Accessibility:** Read/Write

The title of the resource. If the resource does not have a title, or is not a recognized type this will be the empty string.

### **3.2.5.470.1.1.12 uniqueId**

**Type:** CSOM GUID

**Accessibility:** Read/Write

The unique ID of the resource. If the resource does not have a unique ID or is not a recognized type, this will be the empty Guid.

### **3.2.5.470.1.1.13 url**

**Type:** CSOM String

**Accessibility:** Read/Write

The URL of the resource.

### **3.2.5.470.1.1.14 webId**

**Type:** CSOM GUID

**Accessibility:** Read/Write

The web ID of the SP.Web the resource is in. If the resource is not a recognized type, or is not in a web, this will be the empty Guid.

### **3.2.5.470.1.2ObjectPath Properties**

None.

### **3.2.5.471 Microsoft.SharePoint.Client.Utilities.NewsItemFlags**

**ShortName:** SP.Utilities.NewsItemFlags



**Flag:** true

Additional flags that can apply to an item.

### **3.2.5.471.1 Field Values**

#### **3.2.5.471.1.1 None**

**Value:** 0

Indicates that none of the flags apply to this item.

#### **3.2.5.471.1.2 DefaultItem**

**Value:** 1

Indicates that this item is a default item, created by SharePoint.

### **3.2.5.472 Microsoft.SharePoint.Client.Utilities.NewsItemMetaData**

**TypeId:** {97FD8A65-2B4D-4D93-A8BF-F2E9952AB5A0}

**ShortName:** SP.Utilities.NewsItemMetaData

Contains metadata about the resource at a given url. The url might or might not be in SharePoint.

#### **3.2.5.472.1 Properties**

##### **3.2.5.472.1.1 Scalar Properties**

###### **3.2.5.472.1.1.1 fileExtension**

**Type:** CSOM String

**Accessibility:** Read/Write

File extension (indicating the type of file) if the resource is a file.

###### **3.2.5.472.1.1.2 newsType**

**Type:** Microsoft.SharePoint.Client.Utilities.NewsType

**Accessibility:** Read/Write

Indicates the type of object the resource is.

###### **3.2.5.472.1.1.3 progId**

**Type:** CSOM String

**Accessibility:** Read/Write

The program identifier for the resource, if the resource is a file or a folder. Used to determine which program to use when the resource is opened.

###### **3.2.5.472.1.1.4 siteId**

**Type:** CSOM GUID

**Accessibility:** Read/Write

The site ID of the SP.Site the resource is in. If the resource is not a recognized type, or is not in a site, this will be the empty Guid.

### **3.2.5.472.1.1.5 title**

**Type:** CSOM String

**Accessibility:** Read/Write

The title of the resource. If the resource does not have a title, or is not a recognized type this will be the empty string.

### **3.2.5.472.1.1.6 uniqueId**

**Type:** CSOM GUID

**Accessibility:** Read/Write

The unique ID of the resource. If the resource does not have a unique ID or is not a recognized type, this will be the empty Guid.

### **3.2.5.472.1.1.7 url**

**Type:** CSOM String

**Accessibility:** Read/Write

The URL of the resource.

### **3.2.5.472.1.1.8 webId**

**Type:** CSOM GUID

**Accessibility:** Read/Write

The web ID of the SP.Web the resource is in. If the resource is not a recognized type, or is not in a web, this will be the empty Guid.

## **3.2.5.472.1.2ObjectPath Properties**

None.

## **3.2.5.473 Microsoft.SharePoint.Client.Utilities.NewsType**

**ShortName:** SP.Utilities.NewsType

**Flag:** false

Indicates the type of resource an SPNewsItemMetadata item represents.

### **3.2.5.473.1 Field Values**

#### **3.2.5.473.1.1File**

**Value:** 0

Indicates that the resource is a file in SharePoint.

### **3.2.5.473.1.2Folder**

**Value:** 1

Indicates that the resource is a folder in SharePoint.

### **3.2.5.473.1.3Link**

**Value:** 2

Indicates that the resource is an arbitrary URL, which might or might not be in SharePoint. This is the default case.

### **3.2.5.473.1.4ListItem**

**Value:** 3

Indicates that the resource is a List Item in SharePoint.

### **3.2.5.473.1.5List**

**Value:** 4

Indicates that the resource is a List in SharePoint.

### **3.2.5.473.1.6DocumentLibrary**

**Value:** 5

Indicates that the resource is a Document Library in SharePoint.

## **3.2.5.474 Microsoft.SharePoint.Client.Utilities.NewsUtility**

**TypeId:** {E7C27B43-EBF7-40F1-A1C8-AC694C10A0EA}

**ShortName:** SP.Utilities.NewsUtility

Provides tools for dealing with the QuickLinks feature. The reason this class is called SPNewsUtility is that at the time this file was written, the QuickLinks feature was called the "News" feature.

### **3.2.5.474.1 Properties**

#### **3.2.5.474.1.1Scalar Properties**

None.

#### **3.2.5.474.1.2ObjectPath Properties**

None.

### **3.2.5.474.2 Methods**

#### **3.2.5.474.2.1Scalar Methods**

##### **3.2.5.474.2.1.1 CreateOrUpdateNewsItem**

This method is a **static CSOM method**.

**Return Type: CSOM Int32**

Creates a new item in the News List or updates an existing one.

**Parameters:**

*itemData*: Information about the item to be created or updated.

Type: Microsoft.SharePoint.Client.Utilities.NewsItem

*afterItemId*: The item will be created or moved after the indicated item if this value is positive.

Type: CSOM Int32

**3.2.5.474.2.1.2 DeleteNewsItem**

This method is a **static CSOM method**.

**Return Type:** None

Deletes the item indicated by itemId.

**Parameters:**

*itemId*: Indicates the item to delete.

Type: **CSOM Int32**

**3.2.5.474.2.1.3 GetMetadataForUrl**

This method is a **static CSOM method**.

**Return Type:** Microsoft.SharePoint.Client.Utilities.NewsItemMetaData

Retrieves the metadata about the indicated resource needed in order to add it to the News List.

**Parameters:**

*url*: Indicates the resource to retrieve metadata about.

Type: **CSOM String**

*useContextWeb*: If true, searches for the URL in the current context web. This is faster but will fail if the url is not located in the current context web.

Type: **CSOM Boolean**

**3.2.5.474.2.2 ObjectPath Methods**

None.

**3.2.5.475 Microsoft.SharePoint.Client.Utilities.ShortcutLink**

**TypeId:** {3703EE23-B792-4E69-B1ED-56826521AFEA}

**ShortName:** SP.Utilities.ShortcutLink

Class for handling shortcut links.

**3.2.5.475.1 Properties**

### 3.2.5.475.1.1 Scalar Properties

None.

### 3.2.5.475.1.2 ObjectPath Properties

None.

## 3.2.5.475.2 Methods

### 3.2.5.475.2.1 Scalar Methods

None.

### 3.2.5.475.2.2 ObjectPath Methods

#### 3.2.5.475.2.2.1 GetShortcutLink

This method is a **static CSOM method**.

**Return Type:** Microsoft.SharePoint.Client.Utilities.ShortcutTargetInfo

Processes a shortcut file to extract its target and save that value in the shortcut file's property bag.

If applicable, also saves the target's site id, web id, and file unique id to the property bag.

If the shortcut file does not contain a valid target URL, this method returns the path to the shortcut file.

**Parameters:**

*shortcutPath*: The absolute URL of the shortcut file to process.

Type: **CSOM String**

### 3.2.5.476 Microsoft.SharePoint.Client.Utilities.ShortcutTargetInfo

**TypeId:** {7D40E829-711F-4672-9A7C-4098782BFA58}

**ShortName:** SP.Utilities.ShortcutTargetInfo

The entity data object for shortcut link target information.

Some of the properties only apply to shortcut targets that are in SharePoint.

#### 3.2.5.476.1 Properties

##### 3.2.5.476.1.1 Scalar Properties

###### 3.2.5.476.1.1.1 siteId

Type: **CSOM GUID**

**Accessibility:** Read/Write

The ID of the <see cref="SPSite"/> containing the shortcut target, if applicable.

###### 3.2.5.476.1.1.2 uniqueId

**Type:** CSOM GUID

**Accessibility:** Read/Write

The UniqueId of the <see cref="SPFile"/> corresponding to the shortcut target, if applicable.

### 3.2.5.476.1.1.3 url

**Type:** CSOM String

**Accessibility:** Read/Write

The target URL of the shortcut.

### 3.2.5.476.1.1.4 webId

**Type:** CSOM GUID

**Accessibility:** Read/Write

The ID of the <see cref="SPWeb"/> containing the shortcut target, if applicable.

## 3.2.5.476.1.2 ObjectPath Properties

None.

## 3.2.5.476.2 Methods

### 3.2.5.476.2.1 Scalar Methods

None.

### 3.2.5.476.2.2 ObjectPath Methods

None.

## 3.2.5.477 Microsoft.SharePoint.Client.Utilities.SpotlightResult

**TypeId:** {49DC00D0-6338-4C4D-8827-2D82A867CD44}

**ShortName:** SP.Utilities.SpotlightResult

Contains the result of a spotlight operation, such as AddToSpotlight or RemoveFromSpotlight, and also contains the updated set of items in the spotlight.

### 3.2.5.477.1 Properties

#### 3.2.5.477.1.1 Scalar Properties

##### 3.2.5.477.1.1.1 Order

**Type:** CSOM array of CSOM Int32

**Accessibility:** Read/Write

An ordered IEnumerable of list item ids which indicates the resulting order of spotlight items after a spotlight operation, such as AddToSpotlight or RemoveFromSpotlight.

### **3.2.5.477.1.1.2      ResultCode**

**Type:** Microsoft.SharePoint.Client.Utilities.SpotlightResultCode

**Accessibility:** Read/Write

Indicates success or the failure reason of a spotlight operation, such as AddToSpotlight or RemoveFromSpotlight.

### **3.2.5.477.1.2ObjectPath Properties**

None.

### **3.2.5.477.2    Methods**

#### **3.2.5.477.2.1Scalar Methods**

None.

#### **3.2.5.477.2.2ObjectPath Methods**

None.

### **3.2.5.478      Microsoft.SharePoint.Client.Utilities.SpotlightResultCode**

**ShortName:** SP.Utilities.SpotlightResultCode

**Flag:** false

Indicates success or the failure reason of a spotlight operation, such as AddToSpotlight or RemoveFromSpotlight.

#### **3.2.5.478.1    Field Values**

##### **3.2.5.478.1.1Success**

**Value:** 0

The operation succeeded.

##### **3.2.5.478.1.2FolderDoesNotExist**

**Value:** 1

The operation failed because the indicated folder does not exist.

##### **3.2.5.478.1.3ItemDoesNotExist**

**Value:** 2

The operation failed because the indicated item does not exist.

##### **3.2.5.478.1.4TooManyItems**

**Value:** 3

The operation failed because the number of items the current folder's spotlight exceeded the maximum.

### 3.2.5.478.1.5ItemNotInSpotlight

**Value:** 4

The operation failed because the indicated item was not in spotlight.

### 3.2.5.478.1.6InvalidArgument

**Value:** 5

The operation failed because an invalid argument was passed in.

### 3.2.5.478.1.7ServerError

**Value:** 6

The operation failed due to an error on the server.

## 3.2.5.479 Microsoft.SharePoint.Client.Utilities.SPSocialSwitch

**TypeId:** {AA7F12FA-FFE8-4607-A085-09A563D77EEB}

**ShortName:** SP.Utilities.SPSocialSwitch

Provides methods to determine whether certain social features are enabled or disabled.

### 3.2.5.479.1 Properties

#### 3.2.5.479.1.1Scalar Properties

None.

#### 3.2.5.479.1.2ObjectPath Properties

None.

### 3.2.5.479.2 Methods

#### 3.2.5.479.2.1Scalar Methods

##### 3.2.5.479.2.1.1 IsFollowingFeatureEnabled

This method is a **static CSOM method**.

**Return Type:** **CSOM Boolean**

Returns true if the SPSocial follow feature is enabled, taking into account the current context as appropriate. Specifically, if there is a SP.Web within the SP.RequestContext, this method will take into account whether the FollowingContent feature is activated within the SP.Web as well. Regardless of whether there is an SP.Web within the context, it will take into account if SPSocial is enabled at the tenant level.

**Parameters:** None

#### 3.2.5.479.2.2ObjectPath Methods

None.



### 3.2.5.480 Microsoft.SharePoint.Client.Utilities.ThemingOptions

**TypeId:** {22177C35-3B3B-4E8F-BE80-97B53BE0B0B5}

**ShortName:** SP.Utilities.ThemingOptions

Microsoft.SharePoint.Client.Utilities.ThemingOptions is not applicable. [<277>](#)

#### 3.2.5.480.1 Properties

##### 3.2.5.480.1.1 Scalar Properties

None.

##### 3.2.5.480.1.2 ObjectPath Properties

None.

### 3.2.5.481 Microsoft.SharePoint.Client.Utilities.UploadStatus

**TypeId:** {B67BB458-2B47-4E3C-8A50-F7AE33A1D7D3}

**ShortName:** SP.Utilities.UploadStatus

The status of a chunk session upload.

#### 3.2.5.481.1 Properties

##### 3.2.5.481.1.1 Scalar Properties

###### 3.2.5.481.1.1.1 ExpectedContentRange

**Type:** CSOM String

**Accessibility:** Read Only

The string representation of the byte offset of the stream uploaded in chunk upload session that the next **ContinueUpload** ([3.2.5.64.2.1.17](#)) call uses to continue chunk upload.

###### 3.2.5.481.1.1.2 ExpirationDateTime

**Type:** CSOM DateTime

**Accessibility:** Read/Write

The earliest time at which the chunk upload session will be automatically expired and then deleted.

###### 3.2.5.481.1.1.3 UploadId

**Type:** CSOM GUID

**Accessibility:** Read/Write

Unique Id of the chunk session upload.

##### 3.2.5.481.1.2 ObjectPath Properties

None.

## 3.2.5.481.2 Methods

### 3.2.5.481.2.1 Scalar Methods

None.

### 3.2.5.481.2.2 ObjectPath Methods

None.

## 3.2.5.482 Microsoft.SharePoint.Client.Utilities.WebAppExtUrlPair

**TypeId:** {65AB7214-194D-4DED-B1C9-0A2E01E30C81}

**ShortName:** SP.Utilities.WebAppExtUrlPair

Extension/Prog Id and its Web application url Pair.

### 3.2.5.482.1 Properties

#### 3.2.5.482.1.1 Scalar Properties

##### 3.2.5.482.1.1.1 Ext

**Type:** CSOM String

**Accessibility:** Read/Write

Document extension.

##### 3.2.5.482.1.1.2 WacUrl

**Type:** CSOM String

**Accessibility:** Read/Write

WebApplication url for this file extentsion.

#### 3.2.5.482.1.2 ObjectPath Properties

None.

## 3.2.5.483 Microsoft.SharePoint.Client.Utilities.WebAppUrlsByAction

**TypeId:** {073E22D2-B763-4F8E-B3B0-8DC1E425AC62}

**ShortName:** SP.Utilities.WebAppUrlsByAction

Microsoft.SharePoint.Client.Utilities.WebAppUrlsByAction is not applicable. <278>

### 3.2.5.483.1 Properties

#### 3.2.5.483.1.1 Scalar Properties

None.

#### 3.2.5.483.1.2 ObjectPath Properties

None.

### **3.2.5.484 Microsoft.SharePoint.Client.Utilities.WopiWebAppProperties**

**TypeId:** {E6E88CA4-B529-4E87-9199-AEAA3F9D0CF9}

**ShortName:** SP.Utilities.WopiWebAppProperties

Microsoft.SharePoint.Client.Utilities.WopiWebAppProperties is not applicable. [<279>](#)

#### **3.2.5.484.1 Properties**

##### **3.2.5.484.1.1 Scalar Properties**

None.

##### **3.2.5.484.1.2 ObjectPath Properties**

None.

### **3.2.5.485 Microsoft.SharePoint.Client.Visualization**

**TypeId:** {E19FE976-FCF7-4E2B-A738-AE521F941767}

**ShortName:** SP.Visualization

Microsoft.SharePoint.Client.Visualization is not applicable. [<280>](#)

#### **3.2.5.485.1 Properties**

##### **3.2.5.485.1.1 Scalar Properties**

None.

##### **3.2.5.485.1.2 ObjectPath Properties**

None.

### **3.2.5.486 Microsoft.SharePoint.Client.VisualizationAppInfo**

**TypeId:** {47684720-7A91-4DB0-828A-50F42E8678BB}

**ShortName:** SP.VisualizationAppInfo

Microsoft.SharePoint.Client.VisualizationAppInfo is not applicable. [<281>](#)

#### **3.2.5.486.1 Properties**

##### **3.2.5.486.1.1 Scalar Properties**

None.

##### **3.2.5.486.1.2 ObjectPath Properties**

None.

### **3.2.5.487 Microsoft.SharePoint.Client.VisualizationAppMappedViewCollection**

**TypeId:** {97C60F7B-3061-47C1-A65D-444D8EAD845D}

**ShortName:** SP.VisualizationAppMappedViewCollection

Microsoft.SharePoint.Client.VisualizationAppMappedViewCollection is not applicable. [<282>](#)

#### **3.2.5.487.1 Properties**

##### **3.2.5.487.1.1 Scalar Properties**

None.

##### **3.2.5.487.1.2 ObjectPath Properties**

None.

#### **3.2.5.487.2 Methods**

##### **3.2.5.487.2.1 Scalar Methods**

None.

##### **3.2.5.487.2.2 ObjectPath Methods**

None.

### **3.2.5.488 Microsoft.SharePoint.Client.VisualizationAppSynchronizationResult**

**TypeId:** {CE91BEFA-B1C4-459E-BAC5-18CEB35E037C}

**ShortName:** SP.VisualizationAppSynchronizationResult

Microsoft.SharePoint.Client.VisualizationAppSynchronizationResult is not applicable. [<283>](#)

#### **3.2.5.488.1 Properties**

##### **3.2.5.488.1.1 Scalar Properties**

None.

##### **3.2.5.488.1.2 ObjectPath Properties**

None.

#### **3.2.5.488.2 Methods**

##### **3.2.5.488.2.1 Scalar Methods**

None.

##### **3.2.5.488.2.2 ObjectPath Methods**

None.

### **3.2.5.489 Microsoft.SharePoint.Client.VisualizationAppSynchronizationStatus**

**ShortName:** SP.VisualizationAppSynchronizationStatus

**Flag:** false

Microsoft.SharePoint.Client.VisualizationAppSynchronizationStatus is not applicable. <284>

#### **3.2.5.489.1 Field Values**

None.

### **3.2.5.490 Microsoft.SharePoint.Client.VisualizationAppTarget**

**ShortName:** SP.VisualizationAppTarget

**Flag:** false

Microsoft.SharePoint.Client.VisualizationAppTarget is not applicable. <285>

#### **3.2.5.490.1 Field Values**

None.

### **3.2.5.491 Microsoft.SharePoint.Client.VisualizationField**

**TypeId:** {4F32C806-2DDE-4142-9E2B-2E2E082FB9CF}

**ShortName:** SP.VisualizationField

Contains CSS properties relating to how an individual field is layed out relative to it's container.

#### **3.2.5.491.1 Properties**

##### **3.2.5.491.1.1 Scalar Properties**

###### **3.2.5.491.1.1.1 InternalName**

**Type:** CSOM String

**Accessibility:** Read/Write

A Property which will specify which set of sub-elements to apply this set of CSS properties on.

###### **3.2.5.491.1.1.2 Style**

**Type:** CSOM String

**Accessibility:** Read/Write

CSS properties in serialized JSON format.

###### **3.2.5.491.1.2 ObjectPath Properties**

None.

### **3.2.5.492 Microsoft.SharePoint.Client.VisualizationStyleSet**

**TypeId:** {AB366D26-BE89-4814-B6E6-D9E45AFF97BF}

**ShortName:** SP.VisualizationStyleSet

Microsoft.SharePoint.Client.VisualizationStyleSet is not applicable. [<286>](#)

#### **3.2.5.492.1 Properties**

##### **3.2.5.492.1.1 Scalar Properties**

None.

##### **3.2.5.492.1.2 ObjectPath Properties**

None.

### **3.2.5.493 Microsoft.SharePoint.Client.VisualizationType**

**ShortName:** SP.VisualizationType

**Flag:** false

Information about the type of visualization that this SP.View represents.

#### **3.2.5.493.1 Field Values**

##### **3.2.5.493.1.1 Standard**

**Value:** 0

This view uses the out-of-the-box visualization controls.

##### **3.2.5.493.1.2 Custom**

**Value:** 1

This view uses various VisualizationStyleSets to define custom controls that show the data.

### **3.2.5.494 Microsoft.SharePoint.Client.WebParts.WebPartExportMode**

**ShortName:** SP.WebParts.WebPartExportMode

**Flag:** false

Specifies whether all, some, or none of a WebPart control's properties can be exported.

#### **3.2.5.494.1 Field Values**

##### **3.2.5.494.1.1 None**

**Value:** 0

None of a Web Parts control's properties can be exported.

##### **3.2.5.494.1.2 All**

**Value:** 1

All of a Web Parts control's properties can be exported.

### 3.2.5.494.1.3 NonSensitiveData

**Value:** 2

Only properties of a Web Parts control that have been defined as non-sensitive can be exported.

### 3.2.5.495 **Microsoft.SharePoint.ClientSideComponent.SPClientSideComponentIdentifier**

**TypeId:** {B8E5DEF1-DE2D-403C-AF1B-0F5B87233AA3}

**ShortName:** Microsoft.SharePoint.ClientSideComponent.SPClientSideComponentIdentifier

This identifier uniquely identifies a component.

#### 3.2.5.495.1 **Properties**

##### 3.2.5.495.1.1 **Scalar Properties**

###### 3.2.5.495.1.1.1 **id**

**Type:** CSOM String

**Accessibility:** Read/Write

The ID of the component.

###### 3.2.5.495.1.1.2 **version**

**Type:** CSOM String

**Accessibility:** Read/Write

The version of the component.

##### 3.2.5.495.1.2 **ObjectPath Properties**

None.

### 3.2.5.496 **Microsoft.SharePoint.ClientSideComponent.SPExtensionType**

**ShortName:** Microsoft.SharePoint.ClientSideComponent.SPExtensionType

**Flag:** false

Sub-types of an extension component.

#### 3.2.5.496.1 **Field Values**

##### 3.2.5.496.1.1 **Unknown**

**Value:** 0

Unknown extension type

### 3.2.5.496.1.2FieldCustomizer

**Value:** 1

A client-side extension that customizes the appearance and/or behavior of a SharePoint field, e.g. when it is displayed in a SharePoint list view.

### 3.2.5.496.1.3ApplicationCustomizer

**Value:** 2

A client-side extension that can perform general operations as part of the overall browser page lifecycle.

### 3.2.5.496.1.4ListViewCommandSet

**Value:** 3

A client-side extension that defines a set of custom commands that can be shown in a menu, tool bar, or other UI surface for the SharePoint list view.

## 3.2.5.497 Microsoft.SharePoint.ClientSideComponent.StorageEntity

**TypeId:** {499CB725-3086-42F9-86D1-71594212A6CA}

**ShortName:** Microsoft.SharePoint.ClientSideComponent.StorageEntity

Storage entities which are available across app catalog scopes.

### 3.2.5.497.1 Properties

#### 3.2.5.497.1.1Scalar Properties

##### 3.2.5.497.1.1.1 Comment

**Type:** CSOM String

**Accessibility:** Read Only

Comment on the storage entity

##### 3.2.5.497.1.1.2 Description

**Type:** CSOM String

**Accessibility:** Read Only

Description of the storage entity.

##### 3.2.5.497.1.1.3 Value

**Type:** CSOM String

**Accessibility:** Read Only

The value inside the storage entity.

### 3.2.5.497.1.2ObjectPath Properties



None.

### **3.2.5.497.2 Methods**

#### **3.2.5.497.2.1 Scalar Methods**

None.

#### **3.2.5.497.2.2 ObjectPath Methods**

None.

### **3.2.5.498 Microsoft.SharePoint.Comments.CommentsDisabledScope**

**ShortName:** Microsoft.SharePoint.Comments.CommentsDisabledScope

**Flag:** false

Microsoft.SharePoint.Comments.CommentsDisabledScope is not applicable. [.<287>](#)

#### **3.2.5.498.1 Field Values**

None.

### **3.2.5.499 Microsoft.SharePoint.Internal.ActivityLogger**

**TypeId:** {D3E87991-ED24-4DB6-8F5C-1C37EC905250}

**ShortName:** Microsoft.SharePoint.Internal.ActivityLogger

Microsoft.SharePoint.Internal.ActivityLogger is not applicable. [.<288>](#)

#### **3.2.5.499.1 Properties**

##### **3.2.5.499.1.1 Scalar Properties**

None.

##### **3.2.5.499.1.2 ObjectPath Properties**

None.

#### **3.2.5.499.2 Methods**

##### **3.2.5.499.2.1 Scalar Methods**

None.

##### **3.2.5.499.2.2 ObjectPath Methods**

None.

### **3.2.5.500 Microsoft.SharePoint.Internal.ClientSideComponent.ComponentContextInfo**

**TypeId:** {944D52E1-7032-4583-BB3A-A8198528856C}

**ShortName:** Microsoft.SharePoint.Internal.ClientSideComponent.ComponentContextInfo

This class functions as a wrapper of the ContextInfo object. Reserved for internal use only.

### 3.2.5.500.1 Properties

#### 3.2.5.500.1.1 Scalar Properties

##### 3.2.5.500.1.1.1 SerializedData

**Type:** CSOM String

**Accessibility:** Read Only

This property returns the serialized version of the **ContextInfo** object. The output string is internal and subject to change. Please avoid taking a direct dependency on shape of the string.

#### 3.2.5.500.1.2 ObjectPath Properties

None.

### 3.2.5.500.2 Methods

#### 3.2.5.500.2.1 Scalar Methods

None.

#### 3.2.5.500.2.2 ObjectPath Methods

##### 3.2.5.500.2.2.1 CSOM Constructor

Reserved for internal use only.

**Parameters:** None

### 3.2.5.501 Microsoft.SharePoint.Likes.likedByInformation

**TypeId:** {D0A2024E-2CD7-4B35-815C-2E4E6C9A11D2}

**ShortName:** Microsoft.SharePoint.Likes.likedByInformation

Represents the information about the set of users who liked the **list item**.

### 3.2.5.501.1 Properties

#### 3.2.5.501.1.1 Scalar Properties

##### 3.2.5.501.1.1.1 isLikedByUser

**Type:** CSOM Boolean

**Accessibility:** Read/Write

MUST be TRUE if the **current user** has liked the list item.

##### 3.2.5.501.1.1.2 likeCount

**Type:** CSOM Int64

**Accessibility:** Read/Write

Number of users that have liked the item.

### **3.2.5.501.1.2ObjectPath Properties**

#### **3.2.5.501.1.2.1 likedBy**

**Type:** Microsoft.SharePoint.Likes.LikeEntitySet

**Accessibility:** Read/Write

List of like entries corresponding to individual likes. MUST NOT contain more than one entry for the same user in the set.

### **3.2.5.501.2 Methods**

#### **3.2.5.501.2.1Scalar Methods**

None.

#### **3.2.5.501.2.2ObjectPath Methods**

None.

### **3.2.5.502 Microsoft.SharePoint.Likes.LikeEntitySet**

**TypeId:** {F6A8FB59-0ACD-44E3-AA48-FFAEA55D1CB6}

**ShortName:** Microsoft.SharePoint.Likes.LikeEntitySet

Collection of like entries for a list item. MUST NOT contain more than one entry for the same user in the set.

#### **3.2.5.502.1 Properties**

##### **3.2.5.502.1.1Scalar Properties**

None.

##### **3.2.5.502.1.2ObjectPath Properties**

None.

#### **3.2.5.502.2 Methods**

##### **3.2.5.502.2.1Scalar Methods**

None.

##### **3.2.5.502.2.2ObjectPath Methods**

None.

### 3.2.5.503 Microsoft.SharePoint.Likes.LikesAPI

**TypeId:** {C9CADCF1-90F6-4391-8977-FF2FDAB3B67B}

**ShortName:** Microsoft.SharePoint.Likes.LikesAPI

This class implements top level methods that allow the client to manipulate likes on list items.

#### 3.2.5.503.1 Properties

##### 3.2.5.503.1.1 Scalar Properties

None.

##### 3.2.5.503.1.2 ObjectPath Properties

None.

#### 3.2.5.503.2 Methods

##### 3.2.5.503.2.1 Scalar Methods

###### 3.2.5.503.2.1.1 Like

This method is a **static CSOM method**.

**Return Type:** None

Likes the SP.ListItem for the **current user**

**Parameters:**

*item*: list item to like

Type: Microsoft.SharePoint.Client.ListItem

MUST fail for the user who already liked the item.

###### 3.2.5.503.2.1.2 Unlike

This method is a **static CSOM method**.

**Return Type:** None

Unlikes the SP.ListItem for the **current user**.

**Parameters:**

*item*: list item to unlike

Type: Microsoft.SharePoint.Client.ListItem

MUST fail if the user hasn't liked the item before.

##### 3.2.5.503.2.2 ObjectPath Methods

###### 3.2.5.503.2.2.1 likedBy

This method is a **static CSOM method**.

**Return Type:** Microsoft.SharePoint.Likes.LikeEntitySet

Retrieve the set of likes for the specified list item.

**Parameters:**

*item*: list item for which to retrieve likes.

Type: Microsoft.SharePoint.Client.ListItem

The set MUST contain 0 entries for list items that don't have any likes and MUST contain at most one entry per user.

**3.2.5.504 Microsoft.SharePoint.Likes.userEntity**

**TypeId:** {EC921C23-33E4-426C-B4DA-7CC45C854116}

**ShortName:** Microsoft.SharePoint.Likes.userEntity

Represents a single like within a likedBy set of the list item.

**3.2.5.504.1 Properties**

**3.2.5.504.1.1 Scalar Properties**

**3.2.5.504.1.1.1 creationDate**

Type: **CSOM DateTime**

**Accessibility:** Read Only

The **Datetime** of the like.

**3.2.5.504.1.1.2 email**

Type: **CSOM String**

**Accessibility:** Read Only

The email of the user who liked the item.

**3.2.5.504.1.1.3 id**

Type: **CSOM Int32**

**Accessibility:** Read Only

The associated user's internal ID. MUST be unique for each user within a **sites (2)**.

**3.2.5.504.1.1.4 loginName**

Type: **CSOM String**

**Accessibility:** Read Only

The associated user's loginName.

**3.2.5.504.1.1.5 name**

**Type:** CSOM String

**Accessibility:** Read Only

The associated user's name.

### 3.2.5.504.1.2 ObjectPath Properties

None.

### 3.2.5.504.2 Methods

#### 3.2.5.504.2.1 Scalar Methods

None.

#### 3.2.5.504.2.2 ObjectPath Methods

None.

### 3.2.5.505 Microsoft.SharePoint.Marketplace.CorporateCuratedGallery.CorporateCatalogAppMetadata

**TypeId:** {EF80960B-B867-4A71-B55E-FB0179608E09}

**ShortName:**

Microsoft.SharePoint.Marketplace.CorporateCuratedGallery.CorporateCatalogAppMetadata

App metadata for apps stored in the corporate catalog.

### 3.2.5.505.1 Properties

#### 3.2.5.505.1.1 Scalar Properties

##### 3.2.5.505.1.1.1 AppCatalogVersion

**Type:** CSOM String

**Accessibility:** Read Only

The version of the app stored in the corporate catalog.

##### 3.2.5.505.1.1.2 CanUpgrade

**Type:** CSOM Boolean

**Accessibility:** Read Only

Whether an existing instance of an app can be upgraded.

##### 3.2.5.505.1.1.3 CurrentVersionDeployed

**Type:** CSOM Boolean

**Accessibility:** Read Only

Whether the current version of the app is deployed.

### **3.2.5.505.1.1.4 Deployed**

**Type:** CSOM Boolean

**Accessibility:** Read Only

Whether the app is deployed.

### **3.2.5.505.1.1.5 ID**

**Type:** CSOM String

**Accessibility:** Read Only

The identifier of the app.

### **3.2.5.505.1.1.6 InstalledVersion**

**Type:** CSOM String

**Accessibility:** Read Only

The version of the app that is installed.

### **3.2.5.505.1.1.7 IsClientSideSolution**

**Type:** CSOM Boolean

**Accessibility:** Read Only

Whether the app is a client-side solution.

### **3.2.5.505.1.1.8 Title**

**Type:** CSOM String

**Accessibility:** Read Only

The title of the app.

## **3.2.5.505.1.2 ObjectPath Properties**

None.

## **3.2.5.505.2 Methods**

### **3.2.5.505.2.1 Scalar Methods**

#### **3.2.5.505.2.1.1 Deploy**

**Return Type:** None

This method deploys an app on the app catalog. It MUST be called in the context of the tenant app catalog web or it will fail.

**Parameters:**

*skipFeatureDeployment:* Specifies whether the app can be centrally deployed across the tenant.

Type: CSOM Boolean

### **3.2.5.505.2.1.2 Install**

**Return Type:** None

This method allows an app which is already deployed to be installed on a web.

**Parameters:** None

### **3.2.5.505.2.1.3 Remove**

**Return Type:** None

This method removes an app from the tenant app catalog.

**Parameters:** None

### **3.2.5.505.2.1.4 Retract**

**Return Type:** None

This method retracts a deployed app on the app catalog. It MUST be called in the context of the tenant app catalog web or it will fail.

**Parameters:** None

### **3.2.5.505.2.1.5 Uninstall**

**Return Type:** None

This method uninstalls an app from a web.

**Parameters:** None

### **3.2.5.505.2.1.6 Upgrade**

**Return Type:** None

This method upgrades an app on a web.

**Parameters:** None

## **3.2.5.505.2.2 ObjectPath Methods**

None.

## **3.2.5.506 Microsoft.SharePoint.Marketplace.CorporateCuratedGallery.CorporateCatalogAppMetadataCollection**

**TypeId:** {4E676688-CEDD-481A-ACF6-78BDA4B08211}

**ShortName:**

Microsoft.SharePoint.Marketplace.CorporateCuratedGallery.CorporateCatalogAppMetadataCollection

Collection of app metadata.

### **3.2.5.506.1 Properties**

#### **3.2.5.506.1.1 Scalar Properties**



None.

### **3.2.5.506.1.2ObjectPath Properties**

None.

### **3.2.5.506.2 Methods**

#### **3.2.5.506.2.1Scalar Methods**

None.

#### **3.2.5.506.2.2ObjectPath Methods**

##### **3.2.5.506.2.2.1 GetById**

**Return Type:**

Microsoft.SharePoint.Marketplace.CorporateCuratedGallery.CorporateCatalogAppMetadata

Get app metadata by id.

**Parameters:**

*id*: The identifier of the app to retrieve.

Type: **CSOM String**

### **3.2.5.507 Microsoft.SharePoint.Marketplace.CorporateCuratedGallery.SiteCollectionAppCatalogAllowedCollection**

**TypeId:** {E6A14F02-4A7B-4BD2-B869-23A0A63283DB}

**ShortName:**

Microsoft.SharePoint.Marketplace.CorporateCuratedGallery.SiteCollectionAppCatalogAllowedCollection

Accessor for site collection app catalog allowed list.

### **3.2.5.507.1 Properties**

#### **3.2.5.507.1.1Scalar Properties**

None.

#### **3.2.5.507.1.2ObjectPath Properties**

None.

### **3.2.5.507.2 Methods**

#### **3.2.5.507.2.1Scalar Methods**

##### **3.2.5.507.2.1.1 Remove**

**Return Type:** None

Remove an allowed site collection app catalog from the allowed list.

**Parameters:**

*absolutePath*: The absolute URL of the site collection to remove from the allow list.

Type: **CSOM String**

**3.2.5.507.2.1.2 RemoveById**

**Return Type:** None

Remove an allowed site collection app catalog from the allowed list.

**Parameters:**

*siteId*: The ID of the site collection to remove from the allow list.

Type: **CSOM GUID**

**3.2.5.507.2.2 ObjectPath Methods**

**3.2.5.507.2.2.1 Add**

**Return Type:**

Microsoft.SharePoint.Marketplace.CorporateCuratedGallery.SiteCollectionAppCatalogAllowedItem

Add a site that is enabled for site collection app catalogs.

**Parameters:**

*absolutePath*: The absolute URL of the site collection to add to the allow list.

Type: **CSOM String**

**3.2.5.507.2.2.2 GetByAbsoluteUrl**

**Return Type:**

Microsoft.SharePoint.Marketplace.CorporateCuratedGallery.SiteCollectionAppCatalogAllowedItem

Gets an allow list item based on the URL it was created by. [<289>](#)

**Parameters:**

*absolutePath*: The absolute URL of the site collection to look up in the allow list.

Type: CSOM String

**3.2.5.508 Microsoft.SharePoint.Marketplace.CorporateCuratedGallery.SiteCollectionAppCatalogAllowedItem**

**TypeId:** {9FF9BEE6-14BF-490A-ADB3-6897E9BD592E}

**ShortName:**

Microsoft.SharePoint.Marketplace.CorporateCuratedGallery.SiteCollectionAppCatalogAllowedItem

An entry in the site collection app catalog allow list.

**3.2.5.508.1 Properties**

**3.2.5.508.1.1 Scalar Properties**

### **3.2.5.508.1.1.1 AbsoluteUrl**

**Type:** CSOM String

**Accessibility:** Read Only

The absolute URL of a site collection in the allow list.

### **3.2.5.508.1.1.2 SiteID**

**Type:** CSOM GUID

**Accessibility:** Read Only

The ID of a site collection in the allow list.

### **3.2.5.508.1.2ObjectPath Properties**

None.

### **3.2.5.508.2 Methods**

#### **3.2.5.508.2.1Scalar Methods**

None.

#### **3.2.5.508.2.2ObjectPath Methods**

None.

### **3.2.5.509 Microsoft.SharePoint.Marketplace.CorporateCuratedGallery.SiteCollectionCorporateCatalogAccessor**

**TypeId:** {D7C291F0-684B-4295-B64F-7610F5E4086A}

**ShortName:**

Microsoft.SharePoint.Marketplace.CorporateCuratedGallery.SiteCollectionCorporateCatalogAccessor

Accessor for the site collection corporate catalog.

### **3.2.5.509.1 Properties**

#### **3.2.5.509.1.1Scalar Properties**

None.

#### **3.2.5.509.1.2ObjectPath Properties**

##### **3.2.5.509.1.2.1 AvailableApps**

**Type:**

Microsoft.SharePoint.Marketplace.CorporateCuratedGallery.CorporateCatalogAppMetadataCollection

**Accessibility:** Read Only

Returns the apps available in this corporate catalog.

### **3.2.5.509.2 Methods**

### 3.2.5.509.2.1 Scalar Methods

None.

### 3.2.5.509.2.2 ObjectPath Methods

#### 3.2.5.509.2.2.1 Add

**Return Type:** Microsoft.SharePoint.Client.File

Adds a file to the corporate catalog.

**Parameters:**

*parameters:* File creation information

Type: Microsoft.SharePoint.Client.FileCreationInformation

It MUST NOT be NULL.

### 3.2.5.510 Microsoft.SharePoint.Marketplace.CorporateCuratedGallery.TenantCorporateCatalogAccessor

**TypeId:** {97E1FA65-794C-4FE8-8D64-8C91D18CACAB}

**ShortName:**

Microsoft.SharePoint.Marketplace.CorporateCuratedGallery.TenantCorporateCatalogAccessor

Accessor for the tenant corporate catalog.

#### 3.2.5.510.1 Properties

##### 3.2.5.510.1.1 Scalar Properties

None.

##### 3.2.5.510.1.2 ObjectPath Properties

###### 3.2.5.510.1.2.1 AvailableApps

**Type:**

Microsoft.SharePoint.Marketplace.CorporateCuratedGallery.CorporateCatalogAppMetadataCollection

**Accessibility:** Read Only

Returns the apps available in this corporate catalog.

###### 3.2.5.510.1.2.2 SiteCollectionAppCatalogsSites

**Type:**

Microsoft.SharePoint.Marketplace.CorporateCuratedGallery.SiteCollectionAppCatalogAllowedCollection

**Accessibility:** Read Only

Returns an accessor to the allow list of site collections allowed to have site collection corporate catalogs.

#### 3.2.5.510.2 Methods

### 3.2.5.510.2.1 Scalar Methods

None.

### 3.2.5.510.2.2 ObjectPath Methods

#### 3.2.5.510.2.2.1 Add

**Return Type:** Microsoft.SharePoint.Client.File

Adds a file to the corporate catalog.

**Parameters:**

*parameters:* File creation information.

Type: Microsoft.SharePoint.Client.FileCreationInformation

It MUST NOT be NULL.

### 3.2.5.511 Microsoft.SharePoint.Navigation.REST.PublishingNavigationProviderType

**ShortName:** Microsoft.SharePoint.Navigation.REST.PublishingNavigationProviderType

**Flag:** false

Enumeration of navigation provider types. Exact differences in provide behaviors are implementation details of the protocol server.

#### 3.2.5.511.1 Field Values

##### 3.2.5.511.1.1 InvalidSiteMapProvider

**Value:** 0

Invalid provider type. MUST NOT be set on the server.

##### 3.2.5.511.1.2 PortalSiteMapProvider

**Value:** 1

Portal site map provider.

##### 3.2.5.511.1.3 TaxonomySiteMapProvider

**Value:** 2

Taxonomy site map provider.

### 3.2.5.512 Microsoft.SharePoint.QuickActionMessageCard.HeroImage

**TypeId:** {EDB2B3C0-1B2F-4F67-B2A8-C350007E4712}

**ShortName:** Microsoft.SharePoint.QuickActionMessageCard.HeroImage

Microsoft.SharePoint.QuickActionMessageCard.HeroImage is not applicable. [<290>](#)

#### 3.2.5.512.1 Properties

### 3.2.5.512.1.1 Scalar Properties

None.

### 3.2.5.512.1.2 ObjectPath Properties

None.

### 3.2.5.513 Microsoft.SharePoint.QuickActionMessageCard.MessageCard

**TypeId:** {2E1E19AD-03EC-4F62-9603-73ECBB94EB59}

**ShortName:** Microsoft.SharePoint.QuickActionMessageCard.MessageCard

Microsoft.SharePoint.QuickActionMessageCard.MessageCard is not applicable. [<291>](#)

#### 3.2.5.513.1 Properties

##### 3.2.5.513.1.1 Scalar Properties

None.

##### 3.2.5.513.1.2 ObjectPath Properties

None.

### 3.2.5.514 Microsoft.SharePoint.QuickActionMessageCard.MessageCardAction

**TypeId:** {7EE91CD1-E281-48CA-B5A7-06D7036FAC3F}

**ShortName:** Microsoft.SharePoint.QuickActionMessageCard.MessageCardAction

Microsoft.SharePoint.QuickActionMessageCard.MessageCardAction is not applicable. [<292>](#)

#### 3.2.5.514.1 Properties

##### 3.2.5.514.1.1 Scalar Properties

None.

##### 3.2.5.514.1.2 ObjectPath Properties

None.

### 3.2.5.515 Microsoft.SharePoint.QuickActionMessageCard.Section

**TypeId:** {B895E075-2C50-40B6-91C1-48B18EF130DD}

**ShortName:** Microsoft.SharePoint.QuickActionMessageCard.Section

Microsoft.SharePoint.QuickActionMessageCard.Section is not applicable. [<293>](#)

#### 3.2.5.515.1 Properties

##### 3.2.5.515.1.1 Scalar Properties

None.

### 3.2.5.515.1.2 ObjectPath Properties

None.

### 3.2.5.516 Microsoft.SharePoint.QuickActionMessageCard.SPAccessRequestRefresh Status

**TypeId:** {19014F53-8B85-45AE-B7C9-8ECA4CDDD274}

**ShortName:** Microsoft.SharePoint.QuickActionMessageCard.SPAccessRequestRefreshStatus

Specifies a class that contains signature to verify, unique Id of the access request, and the target status.

#### 3.2.5.516.1 Properties

##### 3.2.5.516.1.1 Scalar Properties

None.

##### 3.2.5.516.1.2 ObjectPath Properties

None.

### 3.2.5.517 Microsoft.SharePoint.Webhooks.Subscription

**TypeId:** {7A71A510-B052-4C9D-ADCD-07220EBB8069}

**ShortName:** Microsoft.SharePoint.Webhooks.Subscription

A subscription for receiving notifications at a specified endpoint.

#### 3.2.5.517.1 Properties

##### 3.2.5.517.1.1 Scalar Properties

###### 3.2.5.517.1.1.1 clientState

**Type:** CSOM String

**Accessibility:** Read/Write

Client-defined state that will be passed in each subscription callout.

###### 3.2.5.517.1.1.2 expirationDateTime

**Type:** CSOM DateTime

**Accessibility:** Read/Write

Expiration time of the subscription. The maximum expiration time allowed is 180 days in the future.

###### 3.2.5.517.1.1.3 id

**Type:** CSOM GUID

**Accessibility:** Read Only

Id of current subscription.

It MUST NOT be NULL. It MUST NOT be an empty GUID.

#### **3.2.5.517.1.1.4 notificationUrl**

**Type:** CSOM String

**Accessibility:** Read/Write

Endpoint that will be called when an event occurs.

It MUST NOT be NULL. It MUST NOT be empty.

#### **3.2.5.517.1.1.5 resource**

**Type:** CSOM String

**Accessibility:** Read/Write

The resource path to watch.

It MUST NOT be NULL. It MUST NOT be empty.

#### **3.2.5.517.1.1.6 resourceData**

**Type:** CSOM String

**Accessibility:** Read/Write

This property is unused.

It MUST NOT be NULL. It MUST NOT be empty.

### **3.2.5.517.1.2 ObjectPath Properties**

None.

## **3.2.5.517.2 Methods**

### **3.2.5.517.2.1 Scalar Methods**

#### **3.2.5.517.2.1.1 Delete**

**Return Type:** None

Delete the subscription.

**Parameters:** None

#### **3.2.5.517.2.1.2 Update**

**Return Type:** None

Update a subscription object.

**Parameters:**

*parameters:* An object containing the parameters to update on the subscription.



Type: Microsoft.SharePoint.Webhooks.SubscriptionInformation

### 3.2.5.517.2.2 ObjectPath Methods

None.

### 3.2.5.518 Microsoft.SharePoint.Webhooks.SubscriptionCollection

**TypeId:** {D4F40890-E1AC-46AF-B67E-589A45E40F96}

**ShortName:** Microsoft.SharePoint.Webhooks.SubscriptionCollection

Collection of subscriptions.

#### 3.2.5.518.1 Properties

##### 3.2.5.518.1.1 Scalar Properties

None.

##### 3.2.5.518.1.2 ObjectPath Properties

None.

#### 3.2.5.518.2 Methods

##### 3.2.5.518.2.1 Scalar Methods

###### 3.2.5.518.2.1.1 Remove

**Return Type:** None

Remove a subscription from the subscription collection.

**Parameters:**

*subscriptionId*: The id of the subscription to remove.

Type: **CSOM GUID**

##### 3.2.5.518.2.2 ObjectPath Methods

###### 3.2.5.518.2.2.1 Add

**Return Type:** Microsoft.SharePoint.Webhooks.Subscription

Add a subscription to the subscription collection.

**Parameters:**

*parameters*: An object containing the parameters for the Add operation.

Type: Microsoft.SharePoint.Webhooks.SubscriptionInformation

###### 3.2.5.518.2.2.2 GetById

**Return Type:** Microsoft.SharePoint.Webhooks.Subscription

Get subscription by subscription id.

**Parameters:**

*id*: The id of the subscription to get.

Type: **CSOM GUID**

### **3.2.5.519 Microsoft.SharePoint.Webhooks.SubscriptionInformation**

**TypeId**: {552733AF-BA95-4402-BFEC-DB7F4C32C1C4}

**ShortName**: Microsoft.SharePoint.Webhooks.SubscriptionInformation

Parameter class for webhook Update and Create REST operations.

#### **3.2.5.519.1 Properties**

##### **3.2.5.519.1.1 Scalar Properties**

###### **3.2.5.519.1.1.1 clientState**

Type: **CSOM String**

**Accessibility**: Read/Write

Client-defined state that will be passed in each subscription callout.

###### **3.2.5.519.1.1.2 expirationDateTime**

Type: **CSOM DateTime**

**Accessibility**: Read/Write

Expiration time of the subscription. The maximum expiration time allowed is 180 days in the future.

###### **3.2.5.519.1.1.3 notificationUrl**

Type: **CSOM String**

**Accessibility**: Read/Write

Endpoint that will be called when an event occurs.

It MUST NOT be empty. Its length MUST be equal to or less than 1024.

###### **3.2.5.519.1.1.4 resource**

Type: **CSOM String**

**Accessibility**: Read/Write

The resource path to watch.

It MUST NOT be empty.

###### **3.2.5.519.1.1.5 resourceData**

Type: **CSOM String**

**Accessibility:** Read/Write

This property is unused.

### **3.2.5.519.1.2ObjectPath Properties**

None.

### **3.2.6 Timer Events**

None.

### **3.2.7 Other Local Events**

None.

## 4 Protocol Examples

### 4.1 Get the Title of a Web

In this example, the title of a **site (2)** is retrieved by using the **Web object (1)** obtained from a **Context**. The operation is summarized in the following steps.

1. Get the context from the protocol server that corresponds to the **URL** where the service is called.
2. Get the associated **Web** object (1) from the context.
3. Request the properties for the associated **Web** object (1).

#### Request:

```
<Request AddExpandoFieldTypeSuffix="true" SchemaVersion="14.0.0.0"
LibraryVersion="14.0.4104.1000" ApplicationName=".NET Library"
xmlns="http://schemas.microsoft.com/sharepoint/clientquery/2009">
  <Actions>
    <ObjectPath Id="2" ObjectPathId="1" />
    <ObjectPath Id="4" ObjectPathId="3" />
    <Query Id="5" ObjectPathId="3">
      <Query SelectAllProperties="true">
        <Properties />
      </Query>
    </Query>
  </Actions>
  <ObjectPaths>
    <StaticProperty Id="1" TypeId="{3747adcd-a3c3-41b9-bfab-4a64dd2f1e0a}" Name="Current" />
    <Property Id="3" ParentId="1" Name="Web" />
  </ObjectPaths></Request>
```

#### Response:

```
[
  {
    "SchemaVersion": "14.0.0.0",
    "LibraryVersion": "14.0.4104.1000",
    "ErrorInfo": null
  }, 2, {
    "IsNull": false
  }, 4, {
    "IsNull": false
  }, 5, {
    "_ObjectType_": "SP.Web",
    "_ObjectIdentity_": "740c6a0b-85e2-48a0-a494-e0f1759d4aa7:web:eb66d01f-d638-41f8-81d7-1a58dd459268",
    "Description": "",
    "Created": "\\Date(2009,4,18,20,50,9,0)\\",
    "LastItemModifiedDate": "\\Date(2009,4,18,21,28,50,0)\\",
    "RecycleBinEnabled": true,
    "Title": "4104",
    "ServerRelativeUrl": "\\u002f",
    "Id": "\\Guid(eb66d01f-d638-41f8-81d7-1a58dd459268)\\",
    "SyndicationEnabled": true,
    "AllowRssFeeds": true,
    "QuickLaunchEnabled": true,
    "TreeViewEnabled": false,
    "Language": 1033,
    "UIVersion": 4,
    "UIVersionConfigurationEnabled": false,
    "AllowDesignerForCurrentUser": true,
    "AllowRevertFromTemplateForCurrentUser": false,
```

```

    "AllowMasterPageEditingForCurrentUser": false,
    "ShowUrlStructureForCurrentUser": false
  }
]

```

## 4.2 Update the Description of a List

In this example, the description of an existing List **object (1)** is updated by using the following steps.

1. Get the context from the protocol server that corresponds to the **URL** where the service is called.
2. Get the associated **Web** object (1) from the context.
3. Get the **List** object (1) from the **Web** object (1).
4. Update the description of the **List** object (1).

### Request:

```

<Request AddExpandoFieldTypeSuffix="true" SchemaVersion="14.0.0.0"
LibraryVersion="14.0.4104.1000" ApplicationName=".NET Library"
xmlns="http://schemas.microsoft.com/sharepoint/clientquery/2009">
  <Actions>
    <ObjectPath Id="2" ObjectPathId="1" />
    <ObjectPath Id="4" ObjectPathId="3" />
    <ObjectPath Id="6" ObjectPathId="5" />
    <ObjectPath Id="8" ObjectPathId="7" />
    <ObjectIdentityQuery Id="9" ObjectPathId="7" />
    <SetProperty Id="10" ObjectPathId="7" Name="Description">
      <Parameter Type="String">The new description</Parameter>
    </SetProperty>
    <Method Name="Update" Id="11" ObjectPathId="7" />
  </Actions>
  <ObjectPaths>
    <StaticProperty Id="1" TypeId="{3747adcd-a3c3-41b9-bfab-4a64dd2f1e0a}" Name="Current" />
    <Property Id="3" ParentId="1" Name="Web" />
    <Property Id="5" ParentId="3" Name="Lists" />
    <Method Id="7" ParentId="5" Name="GetByTitle">
      <Parameters>
        <Parameter Type="String">My List</Parameter>
      </Parameters>
    </Method>
  </ObjectPaths></Request>

```

### Response:

```

[
  {
    "SchemaVersion": "14.0.0.0", "LibraryVersion": "14.0.4104.1000", "ErrorInfo": null
  }, 2, {
    "IsNull": false
  }, 4, {
    "IsNull": false
  }, 6, {
    "IsNull": false
  }, 8, {
    "IsNull": false
  }, 9, {
    "_ObjectIdentity_": "740c6a0b-85e2-48a0-a494-e0f1759d4aa7:web:eb66d01f-d638-41f8-81d7-1a58dd459268:list:c3a072d4-45d2-4db0-a4ac-78fe0a12b5fc"
  }
]

```

]

### 4.3 Add a List to a ListCollection

In this example, a new **List object (1)** is added to an existing **ListCollection** object (1). The following steps provide an overview of adding a **List** to a **ListCollection** object (1).

1. Get the context from the server that corresponds to the **URL** where the service is called.
2. Get the **Web** object (1) from the context.
3. Get the **ListCollection** object (1) from the **Web** object (1).
4. Create new **List** object (1).
5. Add **List** to the **ListCollection** for the **Web**.

#### Request:

```
<Request AddExpandoFieldTypeSuffix="true" SchemaVersion="14.0.0.0"
LibraryVersion="14.0.4104.1000" ApplicationName=".NET Library"
xmlns="http://schemas.microsoft.com/sharepoint/clientquery/2009">
  <Actions>
    <ObjectPath Id="2" ObjectPathId="1" />
    <ObjectPath Id="4" ObjectPathId="3" />
    <ObjectPath Id="6" ObjectPathId="5" />
    <ObjectPath Id="8" ObjectPathId="7" />
    <ObjectIdentityQuery Id="9" ObjectPathId="7" />
  </Actions>
  <ObjectPaths>
    <StaticProperty Id="1" TypeId="{3747adcd-a3c3-41b9-bfab-4a64dd2f1e0a}" Name="Current" />
    <Property Id="3" ParentId="1" Name="Web" />
    <Property Id="5" ParentId="3" Name="Lists" />
    <Method Id="7" ParentId="5" Name="Add">
      <Parameters>
        <Parameter TypeId="{e247b7fc-095e-4ea4-a4c9-c5d373723d8c}">
          <Property Name="Title" Type="String">My New List</Property>
          <Property Name="Description" Type="Null" />
          <Property Name="Url" Type="Null" />
          <Property Name="TemplateFeatureId" Type="Guid">{00000000-0000-0000-0000-
000000000000}</Property>
          <Property Name="TemplateType" Type="Int32">101</Property>
          <Property Name="DocumentTemplateType" Type="Int32">0</Property>
          <Property Name="CustomSchemaXml" Type="Null" />
          <Property Name="QuickLaunchOption" Type="Enum">0</Property>
          <Property Name="DataSourceProperties" Type="Dictionary" />
        </Parameter>
      </Parameters>
    </Method>
  </ObjectPaths>
</Request>
```

#### Response:

```
[
  {
    "SchemaVersion":"14.0.0.0","LibraryVersion":"14.0.4104.1000","ErrorInfo":null
  },2,{
    "IsNull":false
  },4,{
    "IsNull":false
  }
```

```

    }, 6, {
      "IsNull": false
    }, 8, {
      "IsNull": false
    }, 9, {
      " ObjectIdentity " : "740c6a0b-85e2-48a0-a494-e0f1759d4aa7:web:eb66d01f-d638-41f8-81d7-1a58dd459268:list:6a969bdb-9373-436b-b46e-20ba0bd00274"
    }
  ]
}
]

```

## 4.4 Add a Lookup Field

In this example, a new **lookup field** is added to an existing **list** that points to another existing list. The following steps provide an overview of this operation.

1. Get the context from the protocol server that corresponds to the **URL** where the service is called.
2. Get the associated **Web object (1)** from the context.
3. Get the necessary list information from **Web** (Request 1).
4. Add a lookup field to "List 1" that points to "List 2" (Request 2).

### Request 1:

```

<Request AddExpandoFieldTypeSuffix="true" SchemaVersion="14.0.0.0"
LibraryVersion="14.0.4104.1000" ApplicationName=".NET Library"
xmlns="http://schemas.microsoft.com/sharepoint/clientquery/2009">
  <Actions>
    <ObjectPath Id="2" ObjectPathId="1" />
    <ObjectPath Id="4" ObjectPathId="3" />
    <ObjectPath Id="6" ObjectPathId="5" />
    <ObjectPath Id="8" ObjectPathId="7" />
    <ObjectIdentityQuery Id="9" ObjectPathId="7" />
    <ObjectPath Id="11" ObjectPathId="10" />
    <ObjectIdentityQuery Id="12" ObjectPathId="10" />
    <Query Id="13" ObjectPathId="10">
      <Query SelectAllProperties="false">
        <Properties>
          <Property Name="Id" ScalarProperty="true" />
        </Properties>
      </Query>
    </Query>
  </Actions>
  <ObjectPaths>
    <StaticProperty Id="1" TypeId="{3747adcd-a3c3-41b9-bfab-4a64dd2f1e0a}" Name="Current" />
    <Property Id="3" ParentId="1" Name="Web" />
    <Property Id="5" ParentId="3" Name="Lists" />
    <Method Id="7" ParentId="5" Name="GetByTitle">
      <Parameters>
        <Parameter Type="String">List 1</Parameter>
      </Parameters>
    </Method>
    <Method Id="10" ParentId="5" Name="GetByTitle">
      <Parameters>
        <Parameter Type="String">List 2</Parameter>
      </Parameters>
    </Method>
  </ObjectPaths>
</Request>

```

### Response 1:

```
[
  {
    "SchemaVersion": "14.0.0.0", "LibraryVersion": "14.0.4104.1000", "ErrorInfo": null
  }, 2, {
    "IsNull": false
  }, 4, {
    "IsNull": false
  }, 6, {
    "IsNull": false
  }, 8, {
    "IsNull": false
  }, 9, {
    "_ObjectIdentity_": "740c6a0b-85e2-48a0-a494-e0f1759d4aa7:web:eb66d01f-d638-41f8-81d7-1a58dd459268:list:6c4bd5ac-b10c-46f0-9553-be32439987d7"
  }, 11, {
    "IsNull": false
  }, 12, {
    "_ObjectIdentity_": "740c6a0b-85e2-48a0-a494-e0f1759d4aa7:web:eb66d01f-d638-41f8-81d7-1a58dd459268:list:da4af6bf-43e6-463a-a95b-ece4183a7538"
  }, 13, {
    "_ObjectType_": "SP.List", "_ObjectIdentity_": "740c6a0b-85e2-48a0-a494-e0f1759d4aa7:web:eb66d01f-d638-41f8-81d7-1a58dd459268:list:da4af6bf-43e6-463a-a95b-ece4183a7538", " ObjectVersion " : "0", "Id": "\/Guid(da4af6bf-43e6-463a-a95b-ece4183a7538)\/"
  }
]
```

## Request 2:

```
<Request AddExpandoFieldTypeSuffix="true" SchemaVersion="14.0.0.0"
LibraryVersion="14.0.4104.1000" ApplicationName=".NET Library"
xmlns="http://schemas.microsoft.com/sharepoint/clientquery/2009">
  <Actions>
    <ObjectPath Id="18" ObjectPathId="17" />
    <ObjectPath Id="20" ObjectPathId="19" />
    <ObjectIdentityQuery Id="21" ObjectPathId="19" />
  </Actions>
  <ObjectPaths>
    <Property Id="17" ParentId="7" Name="Fields" />
    <Method Id="19" ParentId="17" Name="AddFieldAsXml">
      <Parameters>
        <Parameter Type="String">&lt;Field Type="Lookup" List="da4af6bf-43e6-463a-a95b-ece4183a7538" ShowField="Title" DisplayName="Lookup Field" Description="Lookup field created using CSOM." Required="FALSE" Indexed="FALSE" /></Parameter>
        <Parameter Type="Boolean">true</Parameter>
        <Parameter Type="Enum">0</Parameter>
      </Parameters>
    </Method>
    <Identity Id="7" Name="740c6a0b-85e2-48a0-a494-e0f1759d4aa7:web:eb66d01f-d638-41f8-81d7-1a58dd459268:list:6c4bd5ac-b10c-46f0-9553-be32439987d7" />
  </ObjectPaths></Request>
```

## Response 2:

```
[
  {
    "SchemaVersion": "14.0.0.0", "LibraryVersion": "14.0.4104.1000", "ErrorInfo": null
  }, 18, {
    "IsNull": false
  }, 20, {
    "IsNull": false
  }, 21, {
    "_ObjectIdentity_": "740c6a0b-85e2-48a0-a494-e0f1759d4aa7:web:eb66d01f-d638-41f8-81d7-1a58dd459268:list:6c4bd5ac-b10c-46f0-9553-be32439987d7:field:c84fe21c-7666-4129-85f8-1a317da06017"
  }
]
```



]

#### 4.5 Attempt to Delete a Site With an Account That Does Not Have Permissions for the Operation

The protocol client attempts to delete a **site (2) object (1)** on the protocol server. However, the current user does not have permissions to perform this operation, so deleting a site (2) causes an error. The protocol server returns a **CSOM error**. The following steps provide an overview of this operation.

1. Get the context to a **Site** object (1).
2. Get the **Web** object (1) from the **Site** object (1).
3. Execute **delete** operation on the **Web** object (1).

##### Request:

```
<Request AddExpandoFieldTypeSuffix="true" SchemaVersion="14.0.0.0"
LibraryVersion="14.0.4104.1000" ApplicationName=".NET Library"
xmlns="http://schemas.microsoft.com/sharepoint/clientquery/2009">
  <Actions>
    <ObjectPath Id="2" ObjectPathId="1" />
    <ObjectPath Id="4" ObjectPathId="3" />
    <Method Name="DeleteObject" Id="5" ObjectPathId="3" />
  </Actions>
  <ObjectPaths>
    <StaticProperty Id="1" TypeId="{3747adcd-a3c3-41b9-bfab-4a64dd2f1e0a}" Name="Current" />
    <Property Id="3" ParentId="1" Name="Web" />
  </ObjectPaths></Request>
```

##### Response:

```
[
  {
    "SchemaVersion": "14.0.0.0",
    "LibraryVersion": "14.0.4111.1000",
    "ErrorInfo":
      {
        "ErrorMessage": "Access is denied.",
        "ErrorValue": null
        "ErrorCode": -2147024891,
        "ErrorTypeName": "System.UnauthorizedAccessException"
      }
  }
]
```

## **5 Security**

### **5.1 Security Considerations for Implementers**

None.

### **5.2 Index of Security Parameters**

None.

## 6 Appendix A: Product Behavior

The information in this specification is applicable to the following Microsoft products or supplemental software. References to product versions include updates to those products.

- Microsoft SharePoint Foundation 2010
- Microsoft SharePoint Foundation 2013
- Microsoft SharePoint Server 2016
- Microsoft SharePoint Server 2019
- Microsoft SharePoint Server Subscription Edition

Exceptions, if any, are noted in this section. If an update version, service pack or Knowledge Base (KB) number appears with a product name, the behavior changed in that update. The new behavior also applies to subsequent updates unless otherwise specified. If a product edition appears with the product version, behavior is different in that product edition.

Unless otherwise specified, any statement of optional behavior in this specification that is prescribed using the terms "SHOULD" or "SHOULD NOT" implies product behavior in accordance with the SHOULD or SHOULD NOT prescription. Unless otherwise specified, the term "MAY" implies that the product does not follow the prescription.

[<1> Section 3.2.1.2](#): This relationship is available only in SharePoint Foundation 2013.

[<2> Section 3.2.5.3.1.5](#): The **DiscussionBoard** base type is deprecated. SharePoint Foundation 2010 uses the **GenericList** base type for **discussion boards**.

[<3> Section 3.2.5.5.1.16](#): This field value is available only in SharePoint Foundation 2013.

[<4> Section 3.2.5.27.1.1.17](#): This property is available only in SharePoint Foundation 2013.

[<5> Section 3.2.5.27.1.1.18](#): This property is available only in SharePoint Foundation 2013.

[<6> Section 3.2.5.27.1.1.19](#): This property is available only in SharePoint Foundation 2013.

[<7> Section 3.2.5.35.2.2.1](#): SharePoint Foundation 2010 will throw System.ArgumentException (-2147024809 "featdefScope") for FeatureDefinitionScope.Farm.

[<8> Section 3.2.5.37.2.1.7](#): This method is available only in SharePoint Foundation 2013.

[<9> Section 3.2.5.38.2.1.7](#): This method is available only in SharePoint Foundation 2013.

[<10> Section 3.2.5.40.2.1.7](#): This method is available only in SharePoint Foundation 2013.

[<11> Section 3.2.5.41.2.2.7](#): This method is available only in SharePoint Foundation 2013.

[<12> Section 3.2.5.41.2.2.8](#): This method is available only in SharePoint Foundation 2013.

[<13> Section 3.2.5.41.2.2.9](#): This method is available only in SharePoint Foundation 2013.

[<14> Section 3.2.5.42.2.1.7](#): This method is available only in SharePoint Foundation 2013.

[<15> Section 3.2.5.43.2.1.7](#): This method is available only in SharePoint Foundation 2013.

[<16> Section 3.2.5.44.1.1.28](#): This property is available only in SharePoint Foundation 2013.

[<17> Section 3.2.5.44.2.1.7](#): This method is available only in SharePoint Foundation 2013.

[<18> Section 3.2.5.45.2.1.7](#): This method is available only in SharePoint Foundation 2013.

[<19> Section 3.2.5.46.1.1.5](#): This property is available only in SharePoint Foundation 2013.

[<20> Section 3.2.5.47.2.2.2](#): This method is available only in SharePoint Foundation 2013.

[<21> Section 3.2.5.49.1.1.33](#): This property is available only in SharePoint Foundation 2013.

[<22> Section 3.2.5.49.2.1.7](#): This method is available only in SharePoint Foundation 2013.

[<23> Section 3.2.5.51.2.1.7](#): This method is available only in SharePoint Foundation 2013.

[<24> Section 3.2.5.52.2.1.7](#): This method is available only in SharePoint Foundation 2013.

[<25> Section 3.2.5.53.2.1.7](#): This method is available only in SharePoint Foundation 2013.

[<26> Section 3.2.5.54.2.1.7](#): This method is available only in SharePoint Foundation 2013.

[<27> Section 3.2.5.57.2.1.7](#): This method is available only in SharePoint Foundation 2013.

[<28> Section 3.2.5.58.1.33](#): This field value is available only in SharePoint Foundation 2013.

[<29> Section 3.2.5.58.1.34](#): This field value is available only in SharePoint Foundation 2013.

[<30> Section 3.2.5.59.2.1.7](#): This method is available only in SharePoint Foundation 2013.

[<31> Section 3.2.5.61.2.1.7](#): This method is available only in SharePoint Foundation 2013.

[<32> Section 3.2.5.64.1.1.16](#): This property is available only in SharePoint Foundation 2013.

[<33> Section 3.2.5.64.2.1.11](#): This method is available only in SharePoint Foundation 2013.

[<34> Section 3.2.5.64.2.1.12](#): This method is available only in SharePoint Foundation 2013.

[<35> Section 3.2.5.66.1.1.4](#): This property is available only in SharePoint Foundation 2013.

[<36> Section 3.2.5.68.1.1.4](#): This property is available only in SharePoint Foundation 2013.

[<37> Section 3.2.5.70.2.1.1](#): This method is available only in SharePoint Foundation 2013.

[<38> Section 3.2.5.71.2.2.1](#): This method is available only in SharePoint Foundation 2013.

[<39> Section 3.2.5.72.1.2.4](#): This method is available only in SharePoint Foundation 2013.

[<40> Section 3.2.5.72.1.2.5](#): This property is available only in SharePoint Foundation 2013.

[<41> Section 3.2.5.73.2.2.5](#): This method is available only in SharePoint Foundation 2013.

[<42> Section 3.2.5.76.1.1.15](#): This property is available only in SharePoint Foundation 2013.

[<43> Section 3.2.5.77.2.1.2](#): This method is available only in SharePoint Foundation 2013.

[<44> Section 3.2.5.77.2.1.3](#): This method is available only in SharePoint Foundation 2013.

[<45> Section 3.2.5.77.2.2.3](#): This method is available only in SharePoint Foundation 2013.

[<46> Section 3.2.5.79.1.1.45](#): This property is available only in SharePoint Foundation 2013.

[<47> Section 3.2.5.79.1.1.46](#): This property is available only in SharePoint Foundation 2013.

[<48> Section 3.2.5.79.1.1.47](#): This property is available only in SharePoint Foundation 2013.

[<49> Section 3.2.5.79.1.1.48](#): This property is available only in SharePoint Foundation 2013.

<50> [Section 3.2.5.79.1.1.49](#): This property is available only in SharePoint Foundation 2013.

<51> [Section 3.2.5.79.1.1.50](#): This property is available only in SharePoint Foundation 2013.

<52> [Section 3.2.5.79.1.2.10](#): This property is available only in SharePoint Foundation 2013.

<53> [Section 3.2.5.79.1.2.11](#): This property is available only in SharePoint Foundation 2013.

<54> [Section 3.2.5.79.1.2.12](#): This property is available only in SharePoint Foundation 2013.

<55> [Section 3.2.5.79.1.2.13](#): This property is available only in SharePoint Foundation 2013.

<56> [Section 3.2.5.79.2.1.6](#): This method is available only in SharePoint Foundation 2013.

<57> [Section 3.2.5.79.2.1.7](#): This method is available only in SharePoint Foundation 2013.

<58> [Section 3.2.5.79.2.1.8](#): This method is available only in SharePoint Foundation 2013.

<59> [Section 3.2.5.79.2.1.9](#): This method is available only in SharePoint Foundation 2013.

<60> [Section 3.2.5.79.2.2.8](#): This method is available only in SharePoint Foundation 2013.

<61> [Section 3.2.5.87.1.1.6](#): This property is available only in SharePoint Foundation 2013.

<62> [Section 3.2.5.87.1.2.8](#): This property is available only in SharePoint Foundation 2013.

<63> [Section 3.2.5.87.1.2.9](#): This property is available only in SharePoint Foundation 2013.

<64> [Section 3.2.5.87.1.2.10](#): This property is available only in SharePoint Foundation 2013.

<65> [Section 3.2.5.92.2.2.1](#): This method is available only in SharePoint Foundation 2013.

<66> [Section 3.2.5.93.1.53](#): This field value is available only in SharePoint Foundation 2013.

<67> [Section 3.2.5.93.1.54](#): This field value is available only in SharePoint Foundation 2013.

<68> [Section 3.2.5.93.1.55](#): This field value is available only in SharePoint Foundation 2013.

<69> [Section 3.2.5.93.1.58](#): This field value is available only in SharePoint Foundation 2013.

<70> [Section 3.2.5.93.1.59](#): This field value is available only in SharePoint Foundation 2013.

<71> [Section 3.2.5.95.2.2.1](#): This method is available only in SharePoint Foundation 2013.

<72> [Section 3.2.5.96.1.1.4](#): This property is available only in SharePoint Foundation 2013.

<73> [Section 3.2.5.96.1.1.5](#): This property is available only in SharePoint Foundation 2013.

<74> [Section 3.2.5.97.2.1.1](#): This method is available only in SharePoint Foundation 2013.

<75> [Section 3.2.5.97.2.2.2](#): This method is available only in SharePoint Foundation 2013.

<76> [Section 3.2.5.97.2.2.3](#): This method is available only in SharePoint Foundation 2013.

<77> [Section 3.2.5.100.1.1.5](#): This property is available only in SharePoint Foundation 2013.

<78> [Section 3.2.5.106.1.11](#): This field value is available only in SharePoint Foundation 2013.

<79> [Section 3.2.5.111.1.1.1](#): This property is available only in SharePoint Foundation 2013.

<80> [Section 3.2.5.112.1.2.1](#): This property is available only in SharePoint Foundation 2013.

<81> [Section 3.2.5.112.2.1.1](#): This method is available only in SharePoint Foundation 2013.

<82> [Section 3.2.5.112.2.1.2](#): This method is available only in SharePoint Foundation 2013.

<83> [Section 3.2.5.114.2.2.1](#): This method is available only in SharePoint Foundation 2013.

<84> [Section 3.2.5.114.2.2.2](#): This method is available only in SharePoint Foundation 2013.

<85> [Section 3.2.5.118.1.2.2](#): This property is available only in SharePoint Foundation 2013.

<86> [Section 3.2.5.119.1.1.11](#): This property is available only in SharePoint Foundation 2013.

<87> [Section 3.2.5.119.1.1.12](#): This property is available only in SharePoint Foundation 2013.

<88> [Section 3.2.5.119.1.1.13](#): This property is available only in SharePoint Foundation 2013.

<89> [Section 3.2.5.119.1.1.14](#): This property is available only in SharePoint Foundation 2013.

<90> [Section 3.2.5.119.1.1.15](#): This property is available only in SharePoint Foundation 2013.

<91> [Section 3.2.5.119.1.1.16](#): This property is available only in SharePoint Foundation 2013.

<92> [Section 3.2.5.119.1.2.5](#): This property is available only in SharePoint Foundation 2013.

<93> [Section 3.2.5.119.1.2.6](#): This property is available only in SharePoint Foundation 2013.

<94> [Section 3.2.5.119.2.1.2](#): This method is available only in SharePoint Foundation 2013.

<95> [Section 3.2.5.119.2.1.5](#): This method is available only in SharePoint Foundation 2013.

<96> [Section 3.2.5.119.2.1.8](#): This method is available only in SharePoint Foundation 2013.

<97> [Section 3.2.5.119.2.1.9](#): This method is available only in SharePoint Foundation 2013.

<98> [Section 3.2.5.119.2.1.10](#): This method is available only in SharePoint Foundation 2013.

<99> [Section 3.2.5.119.2.2.6](#): This method is available only in SharePoint Foundation 2013.

<100> [Section 3.2.5.119.2.2.7](#): This method is available only in SharePoint Foundation 2013.

<101> [Section 3.2.5.124.1.1.6](#): This property is available only in SharePoint Foundation 2013.

<102> [Section 3.2.5.124.1.1.7](#): This property is available only in SharePoint Foundation 2013.

<103> [Section 3.2.5.124.1.2.1](#): This property is available only in SharePoint Foundation 2013.

<104> [Section 3.2.5.125.2.1.2](#): This method is available only in SharePoint Foundation 2013.

<105> [Section 3.2.5.125.2.1.3](#): This method is available only in SharePoint Foundation 2013.

<106> [Section 3.2.5.131.1.7](#): This field value is available only in SharePoint Foundation 2013.

<107> [Section 3.2.5.131.1.8](#): This field value is available only in SharePoint Foundation 2013.

<108> [Section 3.2.5.136.2.1.6](#): This method is available only in SharePoint Foundation 2013.

<109> [Section 3.2.5.136.2.1.7](#): This method is available only in SharePoint Foundation 2013.

<110> [Section 3.2.5.136.2.1.8](#): This method is available only in SharePoint Foundation 2013.

<111> [Section 3.2.5.136.2.1.9](#): This method is available only in SharePoint Foundation 2013.

<112> [Section 3.2.5.136.2.1.10](#): This method is available only in SharePoint Foundation 2013.

<113> [Section 3.2.5.136.2.1.11](#): This method is available only in SharePoint Foundation 2013.

[<114> Section 3.2.5.136.2.1.12](#): This method is available only in SharePoint Foundation 2013.

[<115> Section 3.2.5.136.2.1.13](#): This method is available only in SharePoint Foundation 2013.

[<116> Section 3.2.5.136.2.1.14](#): This method is available only in SharePoint Foundation 2013.

[<117> Section 3.2.5.136.2.1.15](#): This method is available only in SharePoint Foundation 2013.

[<118> Section 3.2.5.136.2.1.16](#): This method is available only in SharePoint Foundation 2013.

[<119> Section 3.2.5.136.2.1.19](#): This method is available only in SharePoint Foundation 2013.

[<120> Section 3.2.5.136.2.2.3](#): This method is available only in SharePoint Foundation 2013.

[<121> Section 3.2.5.136.2.2.4](#): This method is available only in SharePoint Foundation 2013.

[<122> Section 3.2.5.137.1.1.36](#): This property is available only in SharePoint Foundation 2013.

[<123> Section 3.2.5.140.2.1.5](#): This method is available only in SharePoint Foundation 2013.

[<124> Section 3.2.5.140.2.1.6](#): This method is available only in SharePoint Foundation 2013.

[<125> Section 3.2.5.140.2.1.7](#): This method is available only in SharePoint Foundation 2013.

[<126> Section 3.2.5.140.2.1.8](#): This method is available only in SharePoint Foundation 2013.

[<127> Section 3.2.5.143.1.1.21](#): This property is available only in SharePoint Foundation 2013.

[<128> Section 3.2.5.143.1.1.22](#): This property is available only in SharePoint Foundation 2013.

[<129> Section 3.2.5.143.1.1.23](#): This property is available only in SharePoint Foundation 2013.

[<130> Section 3.2.5.143.1.1.24](#): This property is available only in SharePoint Foundation 2013.

[<131> Section 3.2.5.143.1.2.24](#): This property is available only in SharePoint Foundation 2013.

[<132> Section 3.2.5.143.1.2.25](#): This property is available only in SharePoint Foundation 2013.

[<133> Section 3.2.5.143.1.2.26](#): This property is available only in SharePoint Foundation 2013.

[<134> Section 3.2.5.143.1.2.27](#): This property is available only in SharePoint Foundation 2013.

[<135> Section 3.2.5.143.1.2.28](#): This property is available only in SharePoint Foundation 2013.

[<136> Section 3.2.5.143.1.2.29](#): This property is available only in SharePoint Foundation 2013.

[<137> Section 3.2.5.143.1.2.30](#): This property is available only in SharePoint Foundation 2013.

[<138> Section 3.2.5.143.1.2.31](#): This property is available only in SharePoint Foundation 2013.

[<139> Section 3.2.5.143.1.2.32](#): This property is available only in SharePoint Foundation 2013.

[<140> Section 3.2.5.143.2.1.9](#): This method is available only in SharePoint Foundation 2013.

[<141> Section 3.2.5.143.2.1.10](#): This method is available only in SharePoint Foundation 2013.

[<142> Section 3.2.5.143.2.1.11](#): This method is available only in SharePoint Foundation 2013.

[<143> Section 3.2.5.143.2.1.12](#): This method is available only in SharePoint Foundation 2013.

[<144> Section 3.2.5.143.2.1.13](#): This method is available only in SharePoint Foundation 2013.

[<145> Section 3.2.5.143.2.1.21](#): This method is not available in SharePoint Foundation 2010 and SharePoint Foundation 2013. An exception of "NotImplementedException" will be thrown when making this call for SharePoint Server 2016.

[<146> Section 3.2.5.143.2.1.22](#): This method is not available in SharePoint Foundation 2010 and SharePoint Foundation 2013. An exception of "NotImplementedException" will be thrown when making this call for SharePoint Server 2016.

[<147> Section 3.2.5.143.2.2.8](#): This method is available only in SharePoint Foundation 2013.

[<148> Section 3.2.5.143.2.2.9](#): This method is available only in SharePoint Foundation 2013.

[<149> Section 3.2.5.143.2.2.10](#): This method is available only in SharePoint Foundation 2013.

[<150> Section 3.2.5.143.2.2.11](#): This method is available only in SharePoint Foundation 2013.

[<151> Section 3.2.5.143.2.2.12](#): This method is available only in SharePoint Foundation 2013.

[<152> Section 3.2.5.143.2.2.13](#): This method is available only in SharePoint Foundation 2013.

[<153> Section 3.2.5.143.2.2.14](#): This method is available only in SharePoint Foundation 2013.

[<154> Section 3.2.5.143.2.2.15](#): This method is available only in SharePoint Foundation 2013.

[<155> Section 3.2.5.143.2.2.16](#): This method is available only in SharePoint Foundation 2013.

[<156> Section 3.2.5.143.2.2.17](#): This method is available only in SharePoint Foundation 2013.

[<157> Section 3.2.5.143.2.2.18](#): This method is available only in SharePoint Foundation 2013.

[<158> Section 3.2.5.143.2.2.19](#): This method is available only in SharePoint Foundation 2013.

[<159> Section 3.2.5.143.2.2.21](#): This method is available only in SharePoint Foundation 2013.

[<160> Section 3.2.5.148.1.2.1](#): This property is available only in SharePoint Foundation 2013.

[<161> Section 3.2.5.150.2.2.2](#): This method is available only in SharePoint Foundation 2013.

[<162> Section 3.2.5.152.2.2.1](#): This method is available only in SharePoint Foundation 2013.

[<163> Section 3.2.5.158](#): This object and its properties and methods are available only in SharePoint Foundation 2013.

[<164> Section 3.2.5.159](#): This object and its properties and methods are available only in SharePoint Foundation 2013.

[<165> Section 3.2.5.160](#): This object and its properties and methods are available only in SharePoint Foundation 2013.

[<166> Section 3.2.5.161](#): This object and its properties and methods are available only in SharePoint Foundation 2013.

[<167> Section 3.2.5.162](#): This object and its properties and methods are available only in SharePoint Foundation 2013.

[<168> Section 3.2.5.163](#): This object and its properties and methods are available only in SharePoint Foundation 2013.

[<169> Section 3.2.5.164](#): This object and its properties and methods are available only in SharePoint Foundation 2013.



[<170> Section 3.2.5.165](#): This object and its properties and methods are available only in SharePoint Foundation 2013.

[<171> Section 3.2.5.166](#): This object and its properties and methods are available only in SharePoint Foundation 2013.

[<172> Section 3.2.5.167](#): This object and its properties and methods are available only in SharePoint Foundation 2013.

[<173> Section 3.2.5.168](#): This object and its fields are available only in SharePoint Foundation 2013.

[<174> Section 3.2.5.169](#): This object and its properties and methods are available only in SharePoint Foundation 2013.

[<175> Section 3.2.5.170](#): This object and its properties and methods are available only in SharePoint Foundation 2013.

[<176> Section 3.2.5.171](#): This object and its properties and methods are available only in SharePoint Foundation 2013.

[<177> Section 3.2.5.172](#): This object and its properties and methods are available only in SharePoint Foundation 2013.

[<178> Section 3.2.5.173](#): This object and its properties and methods are available only in SharePoint Foundation 2013.

[<179> Section 3.2.5.174](#): This object and its properties are available only in SharePoint Foundation 2013.

[<180> Section 3.2.5.175](#): This object and its properties and methods are available only in SharePoint Foundation 2013.

[<181> Section 3.2.5.176](#): This object and its properties and methods are available only in SharePoint Foundation 2013.

[<182> Section 3.2.5.177](#): This object and its properties and methods are available only in SharePoint Foundation 2013.

[<183> Section 3.2.5.178](#): This object and its properties and methods are available only in SharePoint Foundation 2013.

[<184> Section 3.2.5.179](#): This object and its properties and methods are available only in SharePoint Foundation 2013.

[<185> Section 3.2.5.180](#): This object and its properties and methods are available only in SharePoint Foundation 2013.

[<186> Section 3.2.5.181](#): This object and its properties and methods are available only in SharePoint Foundation 2013.

[<187> Section 3.2.5.182](#): This object and its properties and methods are available only in SharePoint Foundation 2013.

[<188> Section 3.2.5.183](#): This object and its properties are available only in SharePoint Foundation 2013.

[<189> Section 3.2.5.184](#): This object and its properties and methods are available only in SharePoint Foundation 2013.

[<190> Section 3.2.5.185](#): This object and its properties and methods are available only in SharePoint Foundation 2013.

[<191> Section 3.2.5.186](#): This object and its properties are available only in SharePoint Foundation 2013.

[<192> Section 3.2.5.187](#): This object and its properties and methods are available only in SharePoint Foundation 2013.

[<193> Section 3.2.5.188](#): This object and its fields are available only in SharePoint Foundation 2013.

[<194> Section 3.2.5.189](#): This object and its properties and methods are available only in SharePoint Foundation 2013.

[<195> Section 3.2.5.190](#): This object and its properties are available only in SharePoint Foundation 2013.

[<196> Section 3.2.5.191](#): This object and its properties are available only in SharePoint Foundation 2013.

[<197> Section 3.2.5.192](#): This object and its properties are available only in SharePoint Foundation 2013.

[<198> Section 3.2.5.193](#): This object and its properties are available only in SharePoint Foundation 2013.

[<199> Section 3.2.5.194](#): This object and its properties and methods are available only in SharePoint Foundation 2013.

[<200> Section 3.2.5.196](#): This object and its properties and methods are available only in SharePoint Foundation 2013.

[<201> Section 3.2.5.197](#): This object and its properties and methods are available only in SharePoint Foundation 2013.

[<202> Section 3.2.5.198](#): This object and its properties and methods are available only in SharePoint Foundation 2013.

[<203> Section 3.2.5.199](#): This object and its properties and methods are available only in SharePoint Foundation 2013.

[<204> Section 3.2.5.200](#): This object and its properties and methods are available only in SharePoint Foundation 2013.

[<205> Section 3.2.5.201](#): This object and its properties are available only in SharePoint Foundation 2013.

[<206> Section 3.2.5.203](#): This object and its properties and methods are available only in SharePoint Foundation 2013.

[<207> Section 3.2.5.204](#): This object and its properties are available only in SharePoint Foundation 2013.

[<208> Section 3.2.5.205](#): This object and its fields are available only in SharePoint Foundation 2013.

[<209> Section 3.2.5.206](#): This object and its properties and methods are available only in SharePoint Foundation 2013.

[<210> Section 3.2.5.207](#): This object and its properties are available only in SharePoint Foundation 2013.

[<211> Section 3.2.5.208](#): This object and its properties are available only in SharePoint Foundation 2013.

[<212> Section 3.2.5.209](#): This object and its properties and methods are available only in SharePoint Foundation 2013.

[<213> Section 3.2.5.210](#): This object and its properties and methods are available only in SharePoint Foundation 2013.

[<214> Section 3.2.5.211](#): This object and its properties are available only in SharePoint Foundation 2013.

[<215> Section 3.2.5.212](#): This object and its properties and methods are available only in SharePoint Foundation 2013.

[<216> Section 3.2.5.213](#): This object and its properties and methods are available only in SharePoint Foundation 2013.

[<217> Section 3.2.5.214](#): This object and its properties are available only in SharePoint Foundation 2013.

[<218> Section 3.2.5.215](#): This object and its properties and methods are available only in SharePoint Foundation 2013.

[<219> Section 3.2.5.216](#): This object and its fields are available only in SharePoint Foundation 2013.

[<220> Section 3.2.5.217](#): This object and its properties and methods are available only in SharePoint Foundation 2013.

[<221> Section 3.2.5.218](#): This object and its fields are available only in SharePoint Foundation 2013.

[<222> Section 3.2.5.219](#): This object and its properties are available only in SharePoint Foundation 2013.

[<223> Section 3.2.5.220](#): This object and its properties and methods are available only in SharePoint Foundation 2013.

[<224> Section 3.2.5.222](#): This object and its properties and methods are available only in SharePoint Foundation 2013.

[<225> Section 3.2.5.224](#): This object and its properties and methods are available only in SharePoint Foundation 2013.

[<226> Section 3.2.5.225](#): This object and its properties and methods are available only in SharePoint Foundation 2013.

[<227> Section 3.2.5.226](#): This object and its properties and methods are available only in SharePoint Foundation 2013.

[<228> Section 3.2.5.227](#): This object and its properties are available only in SharePoint Foundation 2013.

[<229> Section 3.2.5.228](#): This object and its properties and methods are available only in SharePoint Foundation 2013.

[<230> Section 3.2.5.229](#): This object and its properties and methods are available only in SharePoint Foundation 2013.

[<231> Section 3.2.5.233](#): This object and its methods are available only in SharePoint Foundation 2013.

[<232> Section 3.2.5.234](#): This object and its fields are available only in SharePoint Foundation 2013.

[<233> Section 3.2.5.239](#): This object and its properties and methods are available only in SharePoint Foundation 2013.

[<234> Section 3.2.5.240](#): This object and its properties and methods are available only in SharePoint Foundation 2013.

[<235> Section 3.2.5.253.2.1.2](#): This parameter is available only in SharePoint Foundation 2013. The following providers are supported: SPNavigationProvider, AdministrationQuickLaunchProvider, SharedServicesQuickLaunchProvider, GlobalNavSiteMapProvider, CombinedNavSiteMapProvider, CurrentNavSiteMapProvider, CurrentNavSiteMapProviderNoEncode, GlobalNavigation, CurrentNavigation, MySitePersonalQuickLaunchProvider, MySiteHostTopNavigationProvider, GlobalNavigationSwitchableProvider, CurrentNavigationSwitchableProvider, GlobalNavigationTaxonomyProvider, CurrentNavigationTaxonomyProvider, MySiteMapProvider, MySiteLeftNavProvider, MySiteDocumentStaticProvider, MySiteSitesPageStaticProvider, MySiteSubNavProvider, EduTopNavProvider, MySiteHostQuickLaunchProvider.

[<236> Section 3.2.5.253.2.1.3](#): This parameter is available only in SharePoint Foundation 2013. The following providers are supported: SPNavigationProvider, AdministrationQuickLaunchProvider, SharedServicesQuickLaunchProvider, GlobalNavSiteMapProvider, CombinedNavSiteMapProvider, CurrentNavSiteMapProvider, CurrentNavSiteMapProviderNoEncode, GlobalNavigation, CurrentNavigation, MySitePersonalQuickLaunchProvider, MySiteHostTopNavigationProvider, GlobalNavigationSwitchableProvider, CurrentNavigationSwitchableProvider, GlobalNavigationTaxonomyProvider, CurrentNavigationTaxonomyProvider, MySiteMapProvider, MySiteLeftNavProvider, MySiteDocumentStaticProvider, MySiteSitesPageStaticProvider, MySiteSubNavProvider, EduTopNavProvider, MySiteHostQuickLaunchProvider.

[<237> Section 3.2.5.262](#): This object and its properties and methods are available only in SharePoint Foundation 2013.

[<238> Section 3.2.5.273](#): This object and its fields are available only in SharePoint Foundation 2013.

[<239> Section 3.2.5.274](#): This object and its fields are available only in SharePoint Foundation 2013.

[<240> Section 3.2.5.349](#): This is not supported in SharePoint Server.

[<241> Section 3.2.5.350](#): This is not supported in SharePoint Server.

[<242> Section 3.2.5.351](#): This is not supported in SharePoint Server.

[<243> Section 3.2.5.352](#): This is not supported in SharePoint Server.

[<244> Section 3.2.5.353](#): This is not supported in SharePoint Server.

[<245> Section 3.2.5.354](#): This is not supported in SharePoint Server.

[<246> Section 3.2.5.355](#): This is not supported in SharePoint Server.

[<247> Section 3.2.5.356](#): This is not supported in SharePoint Server.

[<248> Section 3.2.5.357](#): This is not supported in SharePoint Server.

[<249> Section 3.2.5.358](#): This is not supported in SharePoint Server.

[<250> Section 3.2.5.378](#): This is not supported in SharePoint Server.

[<251> Section 3.2.5.384](#): This is not supported in SharePoint Server.

[<252> Section 3.2.5.385](#): This is not supported in SharePoint Server.

[<253> Section 3.2.5.386](#): This is not supported in SharePoint Server.

[<254> Section 3.2.5.392](#): This is not supported in SharePoint Server.

[<255> Section 3.2.5.393](#): This is not supported in SharePoint Server.

[<256> Section 3.2.5.394](#): This is not supported in SharePoint Server.

[<257> Section 3.2.5.395](#): This is not supported in SharePoint Server.

[<258> Section 3.2.5.396](#): This is not supported in SharePoint Server.

[<259> Section 3.2.5.397](#): This is not supported in SharePoint Server.

[<260> Section 3.2.5.402](#): This is not supported in SharePoint Server.

[<261> Section 3.2.5.403](#): This is not supported in SharePoint Server.

[<262> Section 3.2.5.406](#): This is not supported in SharePoint Server.

[<263> Section 3.2.5.407](#): This is not supported in SharePoint Server.

[<264> Section 3.2.5.411](#): Microsoft.SharePoint.Client.ListItemVersion is not applicable to the on-premises version of Microsoft SharePoint Server.

[<265> Section 3.2.5.414](#): This is not supported in SharePoint Server.

[<266> Section 3.2.5.415](#): This is not supported in SharePoint Server.

[<267> Section 3.2.5.416](#): This is not supported in SharePoint Server.

[<268> Section 3.2.5.417](#): This is not supported in SharePoint Server.

[<269> Section 3.2.5.421](#): This is not supported in SharePoint Server.

[<270> Section 3.2.5.422](#): This is not supported in SharePoint Server.

[<271> Section 3.2.5.423](#): This is not supported in SharePoint Server.

[<272> Section 3.2.5.440](#): This is not supported in SharePoint Server.

[<273> Section 3.2.5.464](#): This is not supported in SharePoint Server.

[<274> Section 3.2.5.465](#): This is not supported in SharePoint Server.

[<275> Section 3.2.5.468](#): This is not supported in SharePoint Server.

[<276> Section 3.2.5.469](#): This is not supported in SharePoint Server.

[<277> Section 3.2.5.480](#): This is not supported in SharePoint Server.

[<278> Section 3.2.5.483](#): This is not supported in SharePoint Server.

[<279> Section 3.2.5.484](#): This is not supported in SharePoint Server.

[<280> Section 3.2.5.485](#): This is not supported in SharePoint Server.

[<281> Section 3.2.5.486](#): This is not supported in SharePoint Server.

[<282> Section 3.2.5.487](#): This is not supported in SharePoint Server.

[<283> Section 3.2.5.488](#): This is not supported in SharePoint Server.

[<284> Section 3.2.5.489](#): This is not supported in SharePoint Server.

[<285> Section 3.2.5.490](#): This is not supported in SharePoint Server.

[<286> Section 3.2.5.492](#): This is not supported in SharePoint Server.

[<287> Section 3.2.5.498](#): This is not supported in SharePoint Server.

[<288> Section 3.2.5.499](#): This is not supported in SharePoint Server.

[<289> Section 3.2.5.507.2.2.2](#): This method is only applicable to SharePoint Server 2019.

[<290> Section 3.2.5.512](#): This is not supported in SharePoint Server.

[<291> Section 3.2.5.513](#): This is not supported in SharePoint Server.

[<292> Section 3.2.5.514](#): This is not supported in SharePoint Server.

[<293> Section 3.2.5.515](#): This is not supported in SharePoint Server.

## 7 Change Tracking

This section identifies changes that were made to this document since the last release. Changes are classified as Major, Minor, or None.

The revision class **Major** means that the technical content in the document was significantly revised. Major changes affect protocol interoperability or implementation. Examples of major changes are:

- A document revision that incorporates changes to interoperability requirements.
- A document revision that captures changes to protocol functionality.

The revision class **Minor** means that the meaning of the technical content was clarified. Minor changes do not affect protocol interoperability or implementation. Examples of minor changes are updates to clarify ambiguity at the sentence, paragraph, or table level.

The revision class **None** means that no new technical changes were introduced. Minor editorial and formatting changes may have been made, but the relevant technical content is identical to the last released version.

The changes made to this document are listed in the following table. For more information, please contact [dochelp@microsoft.com](mailto:dochelp@microsoft.com).

Section	Description	Revision class
<a href="#">3.2.5</a> Message Processing Events and Sequencing Rules	Removed unused section Microsoft.SharePoint.Client.ListItemCompliance Info	Minor
<a href="#">3.2.5.37.2.1.4</a> SetShowInNewForm	Updated description for SetShowInNewForm method.	Minor
<a href="#">3.2.5.42.2.1.2</a> SetShowInDisplayForm	Updated the description for this method.	Minor
<a href="#">3.2.5.42.2.1.3</a> SetShowInEditForm	Updated the description for this method.	Minor
<a href="#">3.2.5.42.2.1.4</a> SetShowInNewForm	Updated the description for this method.	Minor
<a href="#">3.2.5.49.1.1.42</a> DependentLookupInternalNames	Added description for the DependentLookupInternalNames property.	Minor
<a href="#">3.2.5.61.1.1.46</a> DependentLookupInternalNames	Added description for the DependentLookupInternalNames property.	Minor
<a href="#">3.2.5.64.2.1.24</a> CopyToUsingPath	Added description for the parameters of the CopyToUsingPath method.	Minor
<a href="#">3.2.5.64.2.1.25</a> GetImagePreviewUri	Added description for the parameters of the GetImagePreviewUri method.	Minor
<a href="#">3.2.5.64.2.1.26</a> MoveToUsingPath	Added description for the parameters of MoveToUsingPath method.	Minor
<a href="#">3.2.5.64.2.1.27</a> OpenBinaryStreamWithOptions	Added description for the openOptions parameter.	Minor
<a href="#">3.2.5.64.2.1.28</a> RecycleWithETag	Added specification for RecycleWithETag.	Minor
<a href="#">3.2.5.64.2.1.29</a> UpdateVirusInfo	Added description for the UpdateVirusInfo method and its parameters.	Minor
<a href="#">3.2.5.65.2.2.3</a> AddStubUsingPath	Added description for the pathOfFile parameter.	Minor

Section	Description	Revision class
<a href="#">3.2.5.65.2.2.5</a> AddUsingPath	Added descriptions for the AddUsingPath method parameters.	Minor
<a href="#">3.2.5.65.2.2.6</a> GetByPathOrAddStub	Added description for the pathOfFile parameter.	Minor
<a href="#">3.2.5.72.2.1.5</a> MoveToUsingPath	Added description for the newPath parameter.	Minor
<a href="#">3.2.5.72.2.2.2</a> GetChanges	Added description for the query parameter.	Minor
<a href="#">3.2.5.73.2.2.2</a> AddUsingPath	Added description for the AddUsingPath method parameters.	Minor
<a href="#">3.2.5.73.2.2.4</a> GetByPath	Added description for the path parameter.	Minor
<a href="#">3.2.5.79.1.1.59</a> CustomActionElements	Added definition of ECB.	Minor
<a href="#">3.2.5.79.1.1.64</a> ExemptFromBlockDownloadOfNonViewableFiles	Added description for ExemptFromBlockDownloadOfNonViewableFiles property.	Minor
<a href="#">3.2.5.79.1.1.67</a> IsSystemList	Added description for the IsSystemList property.	Minor
<a href="#">3.2.5.79.1.1.70</a> PageRenderType	Added description for the PageRenderType property.	Minor
<a href="#">3.2.5.79.2.1.18</a> AddValidateUpdateItem	Added description for the AddValidateUpdateItem method and it's parameters.	Minor
<a href="#">3.2.5.79.2.1.19</a> AddValidateUpdateItemUsingPath	Added description for the AddValidateUpdateItemUsingPath method and it's parameters.	Minor
<a href="#">3.2.5.79.2.1.20</a> BulkValidateUpdateListItems	Added description for the BulkValidateUpdateListItems method and it's parameters.	Minor
<a href="#">3.2.5.79.2.1.21</a> CreateDocumentWithDefaultName	Added description for the CreateDocumentWithDefaultName method and it's parameters.	Minor
<a href="#">3.2.5.79.2.1.22</a> GetListDataAsStream	Added description for the GetListDataAsStream method and it's parameters.	Minor
<a href="#">3.2.5.79.2.1.23</a> RenderExtendedListFormData	Added description for the RenderExtendedListFormData method and it's parameters.	Minor
<a href="#">3.2.5.79.2.1.25</a> SetExemptFromBlockDownloadOfNonViewableFiles	Added description for the value parameter.	Minor
3.2.5.79.2.1.25 SetExemptFromBlockDownloadOfNonViewableFiles	Updated description for the SetExemptFromBlockDownloadOfNonViewableFiles method.	Minor
<a href="#">3.2.5.79.2.2.13</a> AddItemUsingPath	Added description of the parameters parameter.	Minor
<a href="#">3.2.5.79.2.2.14</a> CreateDocumentFromTemplateUsingPath	Added description for the CreateDocumentFromTemplateUsingPath	Minor



Section	Description	Revision class
	method and it's parameters.	
<a href="#">3.2.5.79.2.2.15</a> GetBloomFilter	Added description for parameter startItemId.	Minor
<a href="#">3.2.5.79.2.2.16</a> GetBloomFilterWithCustomFields	Added description for the GetBloomFilterWithCustomFields method and it's parameters.	Minor
<a href="#">3.2.5.79.2.2.17</a> GetCheckedOutFiles	Updated description of the GetCheckedOutFiles method.	Minor
<a href="#">3.2.5.79.2.2.18</a> getFileExtendedActivities	Added description for getFileExtendedActivities method.	Major
<a href="#">3.2.5.79.2.2.19</a> GetItemByUniqueId	Added description for uniqueId parameter.	Minor
<a href="#">3.2.5.87.2.1.12</a> SetCommentsDisabled	Added description for the SetCommentsDisabled method.	Minor
<a href="#">3.2.5.87.2.1.13</a> SystemUpdate	Added description for the SystemUpdate method.	Minor
<a href="#">3.2.5.93.1.70</a> CertificateFileLists	Added new Field Value for CertificateFileLists.	Minor
<a href="#">3.2.5.103.1.1.13</a> LeafNamePath	Updated description for LeafNamePath property.	Minor
<a href="#">3.2.5.119.2.2.10</a> OpenWebUsingPath	Added description for the path parameter.	Minor
<a href="#">3.2.5.123</a> Microsoft.SharePoint.Client.UsageInfo	Added description for UsageInfo.	Minor
<a href="#">3.2.5.137.1.1.40</a> PageRenderType	Added description for PageRenderType property.	Minor
<a href="#">3.2.5.137.1.1.42</a> TabularView	Added description for TabularView property.	Minor
<a href="#">3.2.5.137.2.1.3</a> SetViewXml	Added description for SetViewXml method.	Minor
<a href="#">3.2.5.137.2.2.1</a> AddToSpotlight	Added description for AddToSpotlight method.	Minor
<a href="#">3.2.5.137.2.2.2</a> RemoveFromSpotlight	Added description for RemoveFromSpotlight method.	Minor
<a href="#">3.2.5.145.1.1.4</a> Url	Updated description for Url property.	Minor
<a href="#">3.2.5.152.2.2.1</a> GetByName	Changed strKey to name.	Minor
<a href="#">3.2.5.170.2.2.2</a> AddUsingPath	Added description for the AddUsingPath parameters.	Minor
<a href="#">3.2.5.170.2.2.4</a> GetByFileNameAsPath	Added description for the fileName parameter.	Minor
<a href="#">3.2.5.185.2.1.2</a> SetShowInDisplayForm	Updated description for SetShowInDisplayForm method.	Minor
<a href="#">3.2.5.185.2.1.3</a> SetShowInEditForm	Updated description for SetShowInEditForm method.	Minor
<a href="#">3.2.5.243.1.1.5</a> ItemId	Added description for ItemId property.	Minor
<a href="#">3.2.5.288.1.8</a> Visio	Added description for Visio field.	Minor

Section	Description	Revision class
<a href="#">3.2.5.304.2.2.2</a> GetFileByServerRelativePath	Added description for the GetFileByServerRelativePath method and its parameter.	Minor
<a href="#">3.2.5.304.2.2.4</a> GetFileByUrl	Added description for the fileUrl parameter.	Minor
<a href="#">3.2.5.306.1.6</a> ListContentType	Added description for ListContentType field.	Minor
<a href="#">3.2.5.380.2.2.1</a> GetByPath	Added description for GetByPath method.	Minor
<a href="#">3.2.5.390</a> Microsoft.SharePoint.Client.CustomActionElement	Added description for the CustomActionElement object.	Minor
<a href="#">3.2.5.401.1.1</a> Share	Added description for value Share.	Minor
<a href="#">3.2.5.401.1.2</a> Rename	Added description for value Rename.	Minor
<a href="#">3.2.5.401.1.3</a> Restore	Added description for value Restore.	Minor
<a href="#">3.2.5.401.1.4</a> MaxServerType	Added description for value MaxServerType.	Minor
<a href="#">3.2.5.401.1.5</a> FromClient	Added description for value FromClient.	Minor
<a href="#">3.2.5.411</a> Microsoft.SharePoint.Client.ListItemVersion	Clarified applicability of Microsoft.SharePoint.Client.ListItemVersion.	Minor
<a href="#">3.2.5.412.2.2.1</a> GetById	Added description for the versionId parameter.	Minor
<a href="#">3.2.5.464.2.2.1</a> GetByDomainName	Added description for parameter domainName.	Minor
<a href="#">3.2.5.467.2.1.1</a> DemoteTeamChannelById	Added description for parameter folderId.	Minor
<a href="#">3.2.5.467.2.1.3</a> PromoteToTeamChannelById	Added description for parameter folderPath.	Minor
3.2.5.467.2.1.3 PromoteToTeamChannelById	Added description for parameters of PromoteToTeamChannelById.	Minor
<a href="#">3.2.5.467.2.1.4</a> PromoteToTeamChannelByPath	Added description for parameters of PromoteToTeamChannelByPath.	Minor
<a href="#">3.2.5.505.2.1.1</a> Deploy	Added description for skipFeatureDeployment parameter.	Minor
<a href="#">3.2.5.507.2.2.2</a> GetByAbsoluteUrl	Clarified applicability of GetByAbsoluteURL.	Minor
<a href="#">6</a> Appendix A: Product Behavior	Updated list of supported products.	Major

## 8 Index

### A

Abstract data model  
[server](#) 145  
[server – parent types](#) 145  
[server – REST List Items Support](#) 146  
[Add a list to a ListCollection example](#) 1077  
[Add a lookup field example](#) 1078  
[Applicability](#) 142  
[Attempt to delete a site with an account that does not have permissions for the operation example](#) 1080

### C

[Capability negotiation](#) 142  
[Change tracking](#) 1094  
Collections  
[EntityFieldCollection type](#) 642  
[Common Exceptions message](#) 144

### D

Data model - abstract  
[server](#) 145  
[DateTimeFormat type](#) 543

### E

Examples  
[add a list to a list collection](#) 1077  
[add a lookup field](#) 1078  
[attempt to delete a site with an account that does not have Permissions for the operation](#) 1080  
[get the title of a web](#) 1075  
[update the description of a list](#) 1076

### F

[Fields - vendor-extensible](#) 142

### G

[Get the title of a web example](#) 1075  
[Glossary](#) 122

### H

Higher-layer triggered events  
[server](#) 149

### I

[Implementer - security considerations](#) 1081  
[Index of security parameters](#) 1081  
[Informative references](#) 141  
Initialization  
[server](#) 149  
[Introduction](#) 122

### L

[LimitedWebPartManager type](#) 622

### M

Message processing  
[BasePermissions](#) 150  
[BaseType](#) 152  
[CalendarType](#) 154  
[CamlQuery](#) 155  
[ChangeAlert](#) 158  
[ChangeCollection](#) 159  
[ChangeContentType](#) 160  
[ChangeField](#) 162  
[ChangeFile](#) 163  
[ChangeFolder](#) 165  
[ChangeGroup](#) 167  
[ChangeItem](#) 168  
[ChangeList](#) 172  
[ChangeSite](#) 180  
[ChangeToken](#) 181  
[ChangeType \(section 3.2.5.20\)](#) 182, [section 3.2.5.241](#) 784)  
[ChangeUser](#) 185  
[ChangeView](#) 186  
[ChangeWeb](#) 188  
[Collections - EntityFieldCollection](#) 642  
[ContentType](#) 191  
[ContentTypeCollection](#) 196  
[FeatureCollection](#) 202  
[Field](#) 204  
[FieldCalculated](#) 214  
[FieldChoice](#) 225  
[FieldCollection](#) 235  
[FieldComputed](#) 240  
[FieldCurrency](#) 250  
[FieldDateTime \(section 3.2.5.44\)](#) 260, [section 3.2.5.185](#) 688)  
[FieldGuid](#) 270  
[FieldLink](#) 279  
[FieldLinkCollection](#) 281  
[FieldLookup](#) 283  
[FieldMultiChoice](#) 295  
[FieldMultiLineText](#) 305  
[FieldNumber](#) 315  
[FieldRatingScale](#) 326  
[FieldRatingScaleQuestionAnswer](#) 337  
[FieldStringValue](#) 337  
[FieldText](#) 338  
[FieldType](#) 347  
[FieldUrl](#) 351  
[FieldUser](#) 361  
[File](#) 375  
[FileCollection](#) 392  
[FileSaveBinaryInformation](#) 396  
[FileSystemObjectType](#) 398  
[FileVersion](#) 398  
[FileVersionCollection](#) 400  
[Folder](#) 403  
[FolderCollection](#) 408

[Form](#) 410  
[FormCollection](#) 411  
[GroupCollection](#) 415  
[List](#) 418  
[ListCollection](#) 447  
[ListCreationInformation](#) 449  
[ListItem](#) 454  
[ListItemCollectionPosition](#) 466  
[ListItemCreationInformation](#) ([section 3.2.5.90](#) 467, [section 3.2.5.217](#) 746, [section 3.2.5.223.2.1.1](#) 761, [section 3.2.5.223.2.1.2](#) 761)  
[ListTemplateType](#) 471  
[MoveOperations](#) 478  
[Navigation](#) 479  
[NavigationNode](#) 480  
[PageType](#) 484  
[RecycleBinItem](#) 488  
[RecycleBinItemCollection](#) 492  
[RecycleBinItemType](#) 493  
[RelatedFieldCollection](#) ([section 3.2.5.79.2.2.8](#) 443, [section 3.2.5.226](#) 765)  
[RoleDefinition](#) 501  
[RoleDefinitionCollection](#) 506  
[RoleType](#) 508  
[SecurableObject](#) 510  
[Site](#) 512  
[UsageInfo](#) 528  
[User](#) 529  
[UserCollection](#) 533  
[UserCustomAction](#) 536  
[UserCustomActionCollection](#) 540  
[UserCustomActionRegistrationType](#) 541  
[UserCustomActionScope](#) 542  
[Utilities - DateTimeFormat](#) 543  
[Utilities - Utility](#) 547  
[View](#) 559  
[ViewCollection](#) 568  
[ViewCreationInformation](#) 569  
[ViewFieldCollection](#) 571  
[ViewScope](#) 574  
[ViewType](#) 574  
[Web](#) ([section 3.2.5.143](#) 575, [section 3.2.5.192](#) 706, [section 3.2.5.193](#) 708, [section 3.2.5.194](#) 709)  
[WebParts - LimitedWebPartManager](#) 622  
[WebParts - PersonalizationScope](#) 624  
[WebParts - WebPart](#) 625  
[WebParts - WebPartDefinition](#) 626  
[WebParts - WebPartDefinitionCollection](#) 629  
[Workflow - WorkflowAssociationCreationInfo](#) 638  
 Messages  
   [Common Exceptions](#) 144  
   [transport](#) 144  
**N**  
[Normative references](#) 140  
**O**  
 Other local events  
   [server](#) 1074  
[Overview \(synopsis\)](#) 141  
**P**

[Parameters - security index](#) 1081  
[Parent types – abstract data model](#) 145  
[PersonalizationScope type](#) 624  
[Preconditions](#) 142  
[Prerequisites](#) 142  
[Product behavior](#) 1082  
**R**  
[References](#) 140  
   [informative](#) 141  
   [normative](#) 140  
[Relationship to other protocols](#) 141  
[REST List Items Support – abstract data model](#) 146  
**S**  
 Security  
   [implementer considerations](#) 1081  
   [parameter index](#) 1081  
 Sequencing rules  
   [BasePermissions](#) 150  
   [BaseType](#) 152  
   [CalendarType](#) 154  
   [CamlQuery](#) 155  
   [ChangeAlert](#) 158  
   [ChangeCollection](#) 159  
   [ChangeContentType](#) 160  
   [ChangeField](#) 162  
   [ChangeFile](#) 163  
   [ChangeFolder](#) 165  
   [ChangeGroup](#) 167  
   [ChangeItem](#) 168  
   [ChangeList](#) 172  
   [ChangeSite](#) 180  
   [ChangeToken](#) 181  
   [ChangeType](#) ([section 3.2.5.20](#) 182, [section 3.2.5.241](#) 784)  
   [ChangeUser](#) 185  
   [ChangeView](#) 186  
   [ChangeWeb](#) 188  
   [Collections - EntityFieldCollection](#) 642  
   [ContentType](#) 191  
   [ContentTypeCollection](#) 196  
   [FeatureCollection](#) 202  
   [Field](#) 204  
   [FieldCalculated](#) 214  
   [FieldChoice](#) 225  
   [FieldCollection](#) 235  
   [FieldComputed](#) 240  
   [FieldCurrency](#) 250  
   [FieldDateTime](#) ([section 3.2.5.44](#) 260, [section 3.2.5.185](#) 688)  
   [FieldGuid](#) 270  
   [FieldLink](#) 279  
   [FieldLinkCollection](#) 281  
   [FieldLookup](#) 283  
   [FieldMultiChoice](#) 295  
   [FieldMultiLineText](#) 305  
   [FieldNumber](#) 315  
   [FieldRatingScale](#) 326  
   [FieldRatingScaleQuestionAnswer](#) 337  
   [FieldStringValue](#) 337  
   [FieldText](#) 338

[FieldType](#) 347  
[FieldUrl](#) 351  
[FieldUser](#) 361  
[File](#) 375  
[FileCollection](#) 392  
[FileSaveBinaryInformation](#) 396  
[FileSystemObjectType](#) 398  
[FileVersion](#) 398  
[FileVersionCollection](#) 400  
[Folder](#) 403  
[FolderCollection](#) 408  
[Form](#) 410  
[FormCollection](#) 411  
[GroupCollection](#) 415  
[List](#) 418  
[ListCollection](#) 447  
[ListCreationInformation](#) 449  
[ListItem](#) 454  
[ListItemCollectionPosition](#) 466  
[ListItemCreationInformation](#) ([section 3.2.5.90](#) 467, [section 3.2.5.217](#) 746, [section 3.2.5.223.2.1.1](#) 761, [section 3.2.5.223.2.1.2](#) 761)  
[ListTemplateType](#) 471  
[MoveOperations](#) 478  
[Navigation](#) 479  
[NavigationNode](#) 480  
[PageType](#) 484  
[RecycleBinItem](#) 488  
[RecycleBinItemCollection](#) 492  
[RecycleBinItemType](#) 493  
[RelatedFieldCollection](#) ([section 3.2.5.79.2.2.8](#) 443, [section 3.2.5.226](#) 765)  
[RoleDefinition](#) 501  
[RoleDefinitionCollection](#) 506  
[RoleType](#) 508  
[SecurableObject](#) 510  
[Site](#) 512  
[UsageInfo](#) 528  
[User](#) 529  
[UserCollection](#) 533  
[UserCustomAction](#) 536  
[UserCustomActionCollection](#) 540  
[UserCustomActionRegistrationType](#) 541  
[UserCustomActionScope](#) 542  
[Utilities - DateTimeFormat](#) 543  
[Utilities - Utility](#) 547  
[View](#) 559  
[ViewCollection](#) 568  
[ViewCreationInformation](#) 569  
[ViewFieldCollection](#) 571  
[ViewScope](#) 574  
[ViewType](#) 574  
[Web](#) ([section 3.2.5.143](#) 575, [section 3.2.5.192](#) 706, [section 3.2.5.193](#) 708, [section 3.2.5.194](#) 709)  
[WebParts - LimitedWebPartManager](#) 622  
[WebParts - PersonalizationScope](#) 624  
[WebParts - WebPart](#) 625  
[WebParts - WebPartDefinition](#) 626  
[WebParts - WebPartDefinitionCollection](#) 629  
[Workflow - WorkflowAssociationCreationInfo](#) 638  
Server  
[abstract data model](#) 145  
[abstract data model – parent types](#) 145  
[abstract data model – REST List Items Support](#) 146  
[higher-layer triggered events](#) 149  
[initialization](#) 149  
[other local events](#) 1074  
[overview](#) 145  
[timer events](#) 1074  
[timers](#) 148  
[Standards assignments](#) 143  
**T**  
Timer events  
[server](#) 1074  
Timers  
[server](#) 148  
[Tracking changes](#) 1094  
[Transport](#) 144  
Triggered events - higher-layer  
[server](#) 149  
**U**  
[Update the description of a list example](#) 1076  
Utilities  
[DateTimeFormat type](#) 543  
[Utility type](#) 547  
[Utility type](#) 547  
**V**  
[Vendor-extensible fields](#) 142  
[Versioning](#) 142  
**W**  
[WebPart type](#) 625  
[WebPartDefinition type](#) 626  
[WebPartDefinitionCollection type](#) 629  
WebParts  
[LimitedWebPartManager type](#) 622  
[PersonalizationScope type](#) 624  
[WebPart type](#) 625  
[WebPartDefinition type](#) 626  
[WebPartDefinitionCollection type](#) 629  
Workflow  
[WorkflowAssociationCreationInfo type](#) 638  
[WorkflowAssociationCreationInfo type](#) 638  
[WorkflowTemplateCollection type](#) 642