

[MS-OE376]: Office Implementation Information for ECMA-376 Standards Support

Intellectual Property Rights Notice for Open Specifications Documentation

- **Technical Documentation.** Microsoft publishes Open Specifications documentation for protocols, file formats, languages, standards as well as overviews of the interaction among each of these technologies.
- **Copyrights.** This documentation is covered by Microsoft copyrights. Regardless of any other terms that are contained in the terms of use for the Microsoft website that hosts this documentation, you may make copies of it in order to develop implementations of the technologies described in the Open Specifications and may distribute portions of it in your implementations using these technologies or your documentation as necessary to properly document the implementation. You may also distribute in your implementation, with or without modification, any schema, IDL's, or code samples that are included in the documentation. This permission also applies to any documents that are referenced in the Open Specifications.
- **No Trade Secrets.** Microsoft does not claim any trade secret rights in this documentation.
- **Patents.** Microsoft has patents that may cover your implementations of the technologies described in the Open Specifications. Neither this notice nor Microsoft's delivery of the documentation grants any licenses under those or any other Microsoft patents. However, a given Open Specification may be covered by Microsoft [Open Specification Promise](#) or the [Community Promise](#). If you would prefer a written license, or if the technologies described in the Open Specifications are not covered by the Open Specifications Promise or Community Promise, as applicable, patent licenses are available by contacting iplg@microsoft.com.
- **Trademarks.** The names of companies and products contained in this documentation may be covered by trademarks or similar intellectual property rights. This notice does not grant any licenses under those rights. For a list of Microsoft trademarks, visit www.microsoft.com/trademarks.
- **Fictitious Names.** The example companies, organizations, products, domain names, email addresses, logos, people, places, and events depicted in this documentation are fictitious. No association with any real company, organization, product, domain name, email address, logo, person, place, or event is intended or should be inferred.

Reservation of Rights. All other rights are reserved, and this notice does not grant any rights other than specifically described above, whether by implication, estoppel, or otherwise.

Tools. The Open Specifications do not require the use of Microsoft programming tools or programming environments in order for you to develop an implementation. If you have access to Microsoft programming tools and environments you are free to take advantage of them. Certain Open Specifications are intended for use in conjunction with publicly available standard specifications and network programming art, and assumes that the reader either is familiar with the aforementioned material or has immediate access to it.

Revision Summary

| Date | Revision History | Revision Class | Comments |
|------------|------------------|----------------|--|
| 12/15/2009 | 1.0 | Major | Initial Availability |
| 02/19/2010 | 1.01 | Editorial | Revised and edited the technical content |
| 03/31/2010 | 1.02 | Major | Revised for template compliance |
| 04/30/2010 | 1.03 | Editorial | Revised and edited the technical content |
| 06/07/2010 | 1.04 | Editorial | Revised and edited the technical content |
| 06/29/2010 | 1.05 | Editorial | Changed language and formatting in the technical content. |
| 07/23/2010 | 1.05 | No change | No changes to the meaning, language, or formatting of the technical content. |
| 09/27/2010 | 1.05 | No change | No changes to the meaning, language, or formatting of the technical content. |
| 11/15/2010 | 1.06 | Editorial | Changed language and formatting in the technical content. |
| 12/17/2010 | 1.06 | No change | No changes to the meaning, language, or formatting of the technical content. |
| 03/18/2011 | 1.06 | No change | No changes to the meaning, language, or formatting of the technical content. |
| 06/10/2011 | 1.06 | No change | No changes to the meaning, language, or formatting of the technical content. |
| 01/20/2012 | 1.7 | Minor | Clarified the meaning of the technical content. |
| 04/11/2012 | 1.7 | No change | No changes to the meaning, language, or formatting of the technical content. |
| 07/16/2012 | 1.7 | No change | No changes to the meaning, language, or formatting of the technical content. |
| 10/08/2012 | 1.7 | No change | No changes to the meaning, language, or formatting of the technical content. |
| 02/11/2013 | 1.7 | No change | No changes to the meaning, language, or formatting of the technical content. |
| 07/30/2013 | 1.7 | No change | No changes to the meaning, language, or formatting of the technical content. |
| 11/18/2013 | 1.7 | No change | No changes to the meaning, language, or formatting of the technical content. |
| 02/10/2014 | 1.7 | No change | No changes to the meaning, language, or formatting of the technical content. |

Table of Contents

| | |
|---|-----------|
| 1 Introduction | 48 |
| 1.1 Glossary..... | 48 |
| 1.2 References..... | 48 |
| 1.2.1 Normative References..... | 49 |
| 1.2.2 Informative References..... | 50 |
| 1.3 Microsoft Implementations..... | 50 |
| 2 Conformance Statements | 51 |
| 2.1 Normative Variations..... | 51 |
| 2.1.1 Part 1 Section 2.5, Application Conformance..... | 51 |
| 2.1.2 Part 1 Section 8.5, PresentationML..... | 51 |
| 2.1.3 Part 1 Section 8.6.2, VML..... | 51 |
| 2.1.4 Part 1 Section 8.6.5, Math..... | 51 |
| 2.1.5 Part 1 Section 9, Packages..... | 51 |
| 2.1.6 Part 1 Section 11.1, Glossary of WordprocessingML-Specific Terms..... | 52 |
| 2.1.7 Part 1 Section 11.3, Part Summary..... | 52 |
| 2.1.8 Part 1 Section 11.3.10, Main Document Part..... | 52 |
| 2.1.9 Part 1 Section 12.3, Part Summary..... | 52 |
| 2.1.10 Part 1 Section 12.3.2, Chartsheet Part..... | 53 |
| 2.1.11 Part 1 Section 12.3.5, Custom Property Part..... | 53 |
| 2.1.12 Part 1 Section 12.3.6, Custom XML Mappings Part..... | 53 |
| 2.1.13 Part 1 Section 12.3.7, Dialogsheet Part..... | 54 |
| 2.1.14 Part 1 Section 12.3.19, Single Cell Table Definitions Part..... | 54 |
| 2.1.15 Part 1 Section 12.3.20, Styles Part..... | 54 |
| 2.1.16 Part 1 Section 12.3.23, Workbook Part..... | 54 |
| 2.1.17 Part 1 Section 12.3.24, Worksheet Part..... | 54 |
| 2.1.18 Part 1 Section 12.4, External Workbooks..... | 55 |
| 2.1.19 Part 1 Section 13.3, Part Summary..... | 55 |
| 2.1.20 Part 1 Section 13.3.3, Handout Master Part..... | 55 |
| 2.1.21 Part 1 Section 13.3.4, Notes Master Part..... | 56 |
| 2.1.22 Part 1 Section 13.3.5, Notes Slide Part..... | 57 |
| 2.1.23 Part 1 Section 13.3.6, Presentation Part..... | 58 |
| 2.1.24 Part 1 Section 13.3.7, Presentation Properties Part..... | 58 |
| 2.1.25 Part 1 Section 13.3.8, Slide Part..... | 58 |
| 2.1.26 Part 1 Section 13.3.9, Slide Layout Part..... | 59 |
| 2.1.27 Part 1 Section 13.3.10, Slide Master Part..... | 59 |
| 2.1.28 Part 1 Section 13.4, HTML Publish Location..... | 60 |
| 2.1.29 Part 1 Section 14.2.3, Diagram Colors Part..... | 60 |
| 2.1.30 Part 1 Section 15.2, Part Summary..... | 61 |
| 2.1.31 Part 1 Section 15.2.4, Custom XML Data Storage Part..... | 61 |
| 2.1.32 Part 1 Section 15.2.8, Embedded Control Persistence Part..... | 62 |
| 2.1.33 Part 1 Section 15.2.11.1, Core File Properties Part..... | 62 |
| 2.1.34 Part 1 Section 15.2.12, Font Part..... | 62 |
| 2.1.35 Part 1 Section 15.2.13, Image Part..... | 62 |
| 2.1.36 Part 1 Section 15.2.14, Printer Settings Part..... | 63 |
| 2.1.37 Part 1 Section 15.2.17, VML Drawing Part..... | 63 |
| 2.1.38 Part 2 Section 12.2.4.26, Relationships Transform Algorithm..... | 63 |
| 2.1.39 Part 4 Section 2.2.1, background (Document Background)..... | 63 |
| 2.1.40 Part 4 Section 2.2.2, body (Document Body)..... | 63 |
| 2.1.41 Part 4 Section 2.3.1.4, bar (Paragraph Border Between Facing Pages)..... | 63 |

| | | |
|--------|--|----|
| 2.1.42 | Part 4 Section 2.3.1.5, between (Paragraph Border Between Identical Paragraphs)..... | 64 |
| 2.1.43 | Part 4 Section 2.3.1.6, bidi (Right to Left Paragraph Layout)..... | 64 |
| 2.1.44 | Part 4 Section 2.3.1.7, bottom (Paragraph Border Between Identical Paragraphs)..... | 64 |
| 2.1.45 | Part 4 Section 2.3.1.8, cnfStyle (Paragraph Conditional Formatting) | 64 |
| 2.1.46 | Part 4 Section 2.3.1.10, divId (Associated HTML div ID) | 64 |
| 2.1.47 | Part 4 Section 2.3.1.11, framePr (Text Frame Properties)..... | 64 |
| 2.1.48 | Part 4 Section 2.3.1.13, jc (Paragraph Alignment) | 65 |
| 2.1.49 | Part 4 Section 2.3.1.14, keepLines (Keep All Lines On One Page) | 65 |
| 2.1.50 | Part 4 Section 2.3.1.16, kinsoku (Use East Asian Typography Rules for First and Last Character per Line)..... | 65 |
| 2.1.51 | Part 4 Section 2.3.1.17, left (Left Paragraph Border)..... | 66 |
| 2.1.52 | Part 4 Section 2.3.1.18, mirrorIndents (Use Left/Right Indents as Inside/Outside Indents) | 66 |
| 2.1.53 | Part 4 Section 2.3.1.19, numPr (Numbering Definition Instance Reference) | 66 |
| 2.1.54 | Part 4 Section 2.3.1.20, outlineLvl (Associated Outline Level) | 66 |
| 2.1.55 | Part 4 Section 2.3.1.21, overflowPunct (Allow Punctuation to Extent Past Text Extents)..... | 66 |
| 2.1.56 | Part 4 Section 2.3.1.22, p (Paragraph)..... | 67 |
| 2.1.57 | Part 4 Section 2.3.1.25, pPr (Previous Paragraph Properties) | 67 |
| 2.1.58 | Part 4 Section 2.3.1.27, pStyle (Referenced Paragraph Style) | 67 |
| 2.1.59 | Part 4 Section 2.3.1.28, right (Right Paragraph Border) | 67 |
| 2.1.60 | Part 4 Section 2.3.1.29, rPr (Run Properties for the Paragraph Mark)..... | 67 |
| 2.1.61 | Part 4 Section 2.3.1.30, rPr (Previous Run Properties for the Paragraph Mark) | 67 |
| 2.1.62 | Part 4 Section 2.3.1.31, shd (Paragraph Shading) | 68 |
| 2.1.63 | Part 4 Section 2.3.1.37, tab (Custom Tab Stop) | 68 |
| 2.1.64 | Part 4 Section 2.3.1.40, textboxTightWrap (Allow Surrounding Paragraphs to Tight Wrap to Text Box Contents)..... | 68 |
| 2.1.65 | Part 4 Section 2.3.1.41, textDirection (Paragraph Text Flow Direction)..... | 68 |
| 2.1.66 | Part 4 Section 2.3.1.42, top (Paragraph Border Above Identical Paragraphs) | 68 |
| 2.1.67 | Part 4 Section 2.3.1.43, topLinePunct (Compress Punctuation at Start of a Line) .. | 68 |
| 2.1.68 | Part 4 Section 2.3.1.44, widowControl (Allow First/Last Line to Display on a Separate Page) | 68 |
| 2.1.69 | Part 4 Section 2.3.1.45, wordWrap (Allow Line Breaking At Character Level)..... | 68 |
| 2.1.70 | Part 4 Section 2.3.2.1, b (Bold)..... | 69 |
| 2.1.71 | Part 4 Section 2.3.2.2, bCs (Complex Script Bold) | 69 |
| 2.1.72 | Part 4 Section 2.3.2.3, bdr (Text Border)..... | 69 |
| 2.1.73 | Part 4 Section 2.3.2.5, color (Run Content Color) | 69 |
| 2.1.74 | Part 4 Section 2.3.2.6, cs (Use Complex Script Formatting on Run) | 71 |
| 2.1.75 | Part 4 Section 2.3.2.8, eastAsianLayout (East Asian Typography Settings) | 71 |
| 2.1.76 | Part 4 Section 2.3.2.9, effect (Animated Text Effect)..... | 72 |
| 2.1.77 | Part 4 Section 2.3.2.11, emboss (Embossing) | 72 |
| 2.1.78 | Part 4 Section 2.3.2.12, fitText (Manual Run Width) | 72 |
| 2.1.79 | Part 4 Section 2.3.2.13, highlight (Text Highlighting) | 72 |
| 2.1.80 | Part 4 Section 2.3.2.14, i (Italics)..... | 72 |
| 2.1.81 | Part 4 Section 2.3.2.15, iCs (Complex Script Italics) | 73 |
| 2.1.82 | Part 4 Section 2.3.2.16, imprint (Imprinting) | 73 |
| 2.1.83 | Part 4 Section 2.3.2.17, kern (Font Kerning)..... | 73 |
| 2.1.84 | Part 4 Section 2.3.2.18, lang (Languages for Run Content)..... | 73 |
| 2.1.85 | Part 4 Section 2.3.2.19, noProof (Do Not Check Spelling or Grammar) | 73 |
| 2.1.86 | Part 4 Section 2.3.2.20, oMath (Office Open XML Math) | 73 |
| 2.1.87 | Part 4 Section 2.3.2.21, outline (Display Character Outline)..... | 74 |

| | | |
|---------|--|----|
| 2.1.88 | Part 4 Section 2.3.2.23, r (Text Run) | 74 |
| 2.1.89 | Part 4 Section 2.3.2.24, rFonts (Run Fonts) | 74 |
| 2.1.90 | Part 4 Section 2.3.2.25, rPr (Run Properties) | 78 |
| 2.1.91 | Part 4 Section 2.3.2.26, rPr (Previous Run Properties) | 78 |
| 2.1.92 | Part 4 Section 2.3.2.27, rStyle (Referenced Character Style) | 78 |
| 2.1.93 | Part 4 Section 2.3.2.28, rtl (Right To Left Text) | 78 |
| 2.1.94 | Part 4 Section 2.3.2.30, shd (Run Shading) | 79 |
| 2.1.95 | Part 4 Section 2.3.2.31, smallCaps (Small Caps) | 79 |
| 2.1.96 | Part 4 Section 2.3.2.33, spacing (Character Spacing Adjustment) | 79 |
| 2.1.97 | Part 4 Section 2.3.2.34, specVanish (Paragraph Mark Is Always Hidden) | 79 |
| 2.1.98 | Part 4 Section 2.3.2.36, sz (Font Size) | 79 |
| 2.1.99 | Part 4 Section 2.3.2.37, szCs (Complex Script Font Size) | 79 |
| 2.1.100 | Part 4 Section 2.3.2.38, u (Underline) | 79 |
| 2.1.101 | Part 4 Section 2.3.2.41, w (Expanded/Compressed Text) | 80 |
| 2.1.102 | Part 4 Section 2.3.2.42, webHidden (Web Hidden Text) | 80 |
| 2.1.103 | Part 4 Section 2.3.3.2, control (Floating Embedded Control) | 80 |
| 2.1.104 | Part 4 Section 2.3.3.3, control (Inline Embedded Control) | 80 |
| 2.1.105 | Part 4 Section 2.3.3.9, drawing (DrawingML Object) | 80 |
| 2.1.106 | Part 4 Section 2.3.3.12, hpsRaise (Distance Between Phonetic Guide Text and Phonetic Guide Base Text) | 81 |
| 2.1.107 | Part 4 Section 2.3.3.14, lid (Language ID for Phonetic Guide) | 81 |
| 2.1.108 | Part 4 Section 2.3.3.17, movie (Embedded Video) | 81 |
| 2.1.109 | Part 4 Section 2.3.3.19, object (Inline Embedded Object) | 81 |
| 2.1.110 | Part 4 Section 2.3.3.21, pict (VML Object) | 81 |
| 2.1.111 | Part 4 Section 2.3.3.23, rt (Phonetic Guide Text) | 81 |
| 2.1.112 | Part 4 Section 2.3.3.26, rubyBase (Phonetic Guide Base Text) | 81 |
| 2.1.113 | Part 4 Section 2.3.3.29, sym (Symbol Character) | 82 |
| 2.1.114 | Part 4 Section 2.4.1, bidiVisual (Visually Right to Left Table) | 82 |
| 2.1.115 | Part 4 Section 2.4.2, bottom (Table Cell Bottom Margin Exception) | 82 |
| 2.1.116 | Part 4 Section 2.4.3, bottom (Table Cell Bottom Border) | 82 |
| 2.1.117 | Part 4 Section 2.4.4, bottom (Table Bottom Border) | 83 |
| 2.1.118 | Part 4 Section 2.4.5, bottom (Table Cell Bottom Margin Default) | 83 |
| 2.1.119 | Part 4 Section 2.4.6, cantSplit (Table Row Cannot Break Across Pages) | 83 |
| 2.1.120 | Part 4 Section 2.4.7, cnfStyle (Table Cell Conditional Formatting) | 83 |
| 2.1.121 | Part 4 Section 2.4.8, cnfStyle (Table Row Conditional Formatting) | 83 |
| 2.1.122 | Part 4 Section 2.4.9, divId (Associated HTML div ID) | 83 |
| 2.1.123 | Part 4 Section 2.4.10, gridAfter (Grid Columns After Last Cell) | 83 |
| 2.1.124 | Part 4 Section 2.4.11, gridBefore (Grid Columns Before First Cell) | 84 |
| 2.1.125 | Part 4 Section 2.4.13, gridSpan (Grid Columns Spanned by Current Table Cell) | 84 |
| 2.1.126 | Part 4 Section 2.4.14, hidden (Hidden Table Row Marker) | 84 |
| 2.1.127 | Part 4 Section 2.4.15, hideMark (Ignore End Of Cell Marker In Row Height Calculation) | 84 |
| 2.1.128 | Part 4 Section 2.4.16, hMerge (Horizontally Merged Cell) | 84 |
| 2.1.129 | Part 4 Section 2.4.17, insideH (Table Inside Horizontal Edges Border) | 84 |
| 2.1.130 | Part 4 Section 2.4.18, insideH (Table Cell Inside Horizontal Edges Border) | 85 |
| 2.1.131 | Part 4 Section 2.4.19, insideV (Table Cell Inside Vertical Edges Border) | 85 |
| 2.1.132 | Part 4 Section 2.4.20, insideV (Table Inside Vertical Edges Border) | 85 |
| 2.1.133 | Part 4 Section 2.4.21, jc (Table Alignment Exception) | 85 |
| 2.1.134 | Part 4 Section 2.4.22, jc (Table Row Alignment) | 85 |
| 2.1.135 | Part 4 Section 2.4.23, jc (Table Alignment) | 85 |
| 2.1.136 | Part 4 Section 2.4.24, left (Table Cell Left Border) | 85 |
| 2.1.137 | Part 4 Section 2.4.25, left (Table Cell Left Margin Exception) | 86 |
| 2.1.138 | Part 4 Section 2.4.26, left (Table Cell Left Margin Default) | 86 |

| | | |
|---------|--|----|
| 2.1.139 | Part 4 Section 2.4.27, left (Table Left Border) | 86 |
| 2.1.140 | Part 4 Section 2.4.28, noWrap (Don't Wrap Cell Content) | 86 |
| 2.1.141 | Part 4 Section 2.4.29, right (Table Cell Right Margin Default) | 86 |
| 2.1.142 | Part 4 Section 2.4.30, right (Table Cell Right Border) | 87 |
| 2.1.143 | Part 4 Section 2.4.31, right (Table Cell Right Margin Exception) | 87 |
| 2.1.144 | Part 4 Section 2.4.32, right (Table Right Border) | 87 |
| 2.1.145 | Part 4 Section 2.4.33, shd (Table Cell Shading) | 87 |
| 2.1.146 | Part 4 Section 2.4.34, shd (Table Shading Exception) | 87 |
| 2.1.147 | Part 4 Section 2.4.35, shd (Table Shading) | 88 |
| 2.1.148 | Part 4 Section 2.4.36, tbl (Table) | 88 |
| 2.1.149 | Part 4 Section 2.4.37, tblBorders (Table Borders Exceptions) | 88 |
| 2.1.150 | Part 4 Section 2.4.38, tblBorders (Table Borders) | 88 |
| 2.1.151 | Part 4 Section 2.4.41, tblCellSpacing (Table Cell Spacing Exception) | 88 |
| 2.1.152 | Part 4 Section 2.4.42, tblCellSpacing (Table Row Cell Spacing) | 89 |
| 2.1.153 | Part 4 Section 2.4.43, tblCellSpacing (Table Cell Spacing Default) | 89 |
| 2.1.154 | Part 4 Section 2.4.46, tblHeader (Repeat Table Row on Every New Page) | 89 |
| 2.1.155 | Part 4 Section 2.4.47, tblInd (Table Indent from Leading Margin Exception) | 89 |
| 2.1.156 | Part 4 Section 2.4.48, tblInd (Table Indent from Leading Margin) | 90 |
| 2.1.157 | Part 4 Section 2.4.49, tblLayout (Table Layout) | 90 |
| 2.1.158 | Part 4 Section 2.4.50, tblLayout (Table Layout Exception) | 90 |
| 2.1.159 | Part 4 Section 2.4.51, tblLook (Table Style Conditional Formatting Settings) | 90 |
| 2.1.160 | Part 4 Section 2.4.52, tblLook (Table Style Conditional Formatting Settings Exception) | 91 |
| 2.1.161 | Part 4 Section 2.4.53, tblOverlap (Floating Table Allows Other Tables to Overlap) | 91 |
| 2.1.162 | Part 4 Section 2.4.54, tblpPr (Floating Table Positioning) | 91 |
| 2.1.163 | Part 4 Section 2.4.55, tblPr (Table Properties) | 92 |
| 2.1.164 | Part 4 Section 2.4.56, tblPr (Previous Table Properties) | 92 |
| 2.1.165 | Part 4 Section 2.4.59, tblStyle (Referenced Table Style) | 92 |
| 2.1.166 | Part 4 Section 2.4.60, tblW (Preferred Table Width Exception) | 92 |
| 2.1.167 | Part 4 Section 2.4.61, tblW (Preferred Table Width) | 93 |
| 2.1.168 | Part 4 Section 2.4.62, tc (Table Cell) | 93 |
| 2.1.169 | Part 4 Section 2.4.63, tcBorders (Table Cell Borders) | 93 |
| 2.1.170 | Part 4 Section 2.4.64, tcFitText (Fit Text Within Cell) | 96 |
| 2.1.171 | Part 4 Section 2.4.68, tcW (Preferred Table Cell Width) | 96 |
| 2.1.172 | Part 4 Section 2.4.69, textDirection (Table Cell Text Flow Direction) | 96 |
| 2.1.173 | Part 4 Section 2.4.70, tl2br (Table Cell Top Left to Bottom Right Diagonal Border) | 97 |
| 2.1.174 | Part 4 Section 2.4.71, top (Table Top Border) | 97 |
| 2.1.175 | Part 4 Section 2.4.72, top (Table Cell Top Margin Default) | 97 |
| 2.1.176 | Part 4 Section 2.4.73, top (Table Cell Top Margin Exception) | 97 |
| 2.1.177 | Part 4 Section 2.4.74, top (Table Cell Top Border) | 97 |
| 2.1.178 | Part 4 Section 2.4.75, tr (Table Row) | 97 |
| 2.1.179 | Part 4 Section 2.4.76, tr2bl (Table Cell Top Right to Bottom Left Diagonal Border) | 98 |
| 2.1.180 | Part 4 Section 2.4.77, trHeight (Table Row Height) | 98 |
| 2.1.181 | Part 4 Section 2.4.80, vAlign (Table Cell Vertical Alignment) | 98 |
| 2.1.182 | Part 4 Section 2.4.81, vMerge (Vertically Merged Cell) | 99 |
| 2.1.183 | Part 4 Section 2.4.82, wAfter (Preferred Width After Table Row) | 99 |
| 2.1.184 | Part 4 Section 2.4.83, wBefore (Preferred Width Before Table Row) | 99 |
| 2.1.185 | Part 4 Section 2.5.1.1, attr (Custom XML Attribute) | 99 |
| 2.1.186 | Part 4 Section 2.5.1.2, attr (Smart Tag Property) | 99 |
| 2.1.187 | Part 4 Section 2.5.1.3, customXml (Cell-Level Custom XML Element) | 99 |

| | | |
|---------|--|-----|
| 2.1.188 | Part 4 Section 2.5.1.4, customXml (Row-Level Custom XML Element) | 100 |
| 2.1.189 | Part 4 Section 2.5.1.5, customXml (Inline-Level Custom XML Element) | 100 |
| 2.1.190 | Part 4 Section 2.5.1.6, customXml (Block-Level Custom XML Element) | 100 |
| 2.1.191 | Part 4 Section 2.5.1.9, smartTag (Inline-Level Smart Tag) | 101 |
| 2.1.192 | Part 4 Section 2.5.2.6, dataBinding (XML Mapping) | 101 |
| 2.1.193 | Part 4 Section 2.5.2.7, date (Date Structured Document Tag) | 101 |
| 2.1.194 | Part 4 Section 2.5.2.9, docPart (Document Part Reference) | 101 |
| 2.1.195 | Part 4 Section 2.5.2.18, id (Unique ID) | 101 |
| 2.1.196 | Part 4 Section 2.5.2.19, lid (Date Picker Language ID) | 101 |
| 2.1.197 | Part 4 Section 2.5.2.24, placeholder (Structured Document Tag Placeholder Text) | 102 |
| 2.1.198 | Part 4 Section 2.5.2.26, rPr (Run Properties For Structured Document Tag Contents) | 102 |
| 2.1.199 | Part 4 Section 2.5.2.27, rPr (Structured Document Tag End Character Run Properties) | 102 |
| 2.1.200 | Part 4 Section 2.5.2.28, sdt (Cell-Level Structured Document Tag) | 102 |
| 2.1.201 | Part 4 Section 2.5.2.29, sdt (Inline-Level Structured Document Tag) | 103 |
| 2.1.202 | Part 4 Section 2.5.2.30, sdt (Block-Level Structured Document Tag) | 104 |
| 2.1.203 | Part 4 Section 2.5.2.31, sdt (Row-Level Structured Document Tag) | 105 |
| 2.1.204 | Part 4 Section 2.5.2.32, sdtContent (Block-Level Structured Document Tag Content) | 106 |
| 2.1.205 | Part 4 Section 2.5.2.33, sdtContent (Cell-Level Structured Document Tag Content) | 106 |
| 2.1.206 | Part 4 Section 2.5.2.34, sdtContent (Row-Level Structured Document Tag Content) | 106 |
| 2.1.207 | Part 4 Section 2.5.2.35, sdtContent (Inline-Level Structured Document Tag Content) | 106 |
| 2.1.208 | Part 4 Section 2.5.2.41, temporary (Remove Structured Document Tag When Contents Are Edited) | 106 |
| 2.1.209 | Part 4 Section 2.6.2, bottom (Bottom Border) | 106 |
| 2.1.210 | Part 4 Section 2.6.3, col (Single Column Definition) | 106 |
| 2.1.211 | Part 4 Section 2.6.4, cols (Column Definitions) | 107 |
| 2.1.212 | Part 4 Section 2.6.7, left (Left Border) | 107 |
| 2.1.213 | Part 4 Section 2.6.8, lnNumType (Line Numbering Settings) | 107 |
| 2.1.214 | Part 4 Section 2.6.9, paperSrc (Paper Source Information) | 107 |
| 2.1.215 | Part 4 Section 2.6.10, pgBorders (Page Borders) | 107 |
| 2.1.216 | Part 4 Section 2.6.11, pgMar (Page Margins) | 108 |
| 2.1.217 | Part 4 Section 2.6.12, pgNumType (Page Numbering Settings) | 108 |
| 2.1.218 | Part 4 Section 2.6.13, pgSz (Page Size) | 108 |
| 2.1.219 | Part 4 Section 2.6.14, printerSettings (Reference to Printer Settings Data) | 109 |
| 2.1.220 | Part 4 Section 2.6.15, right (Right Border) | 109 |
| 2.1.221 | Part 4 Section 2.6.17, sectPr (Previous Section Properties) | 109 |
| 2.1.222 | Part 4 Section 2.6.18, sectPr (Document Final Section Properties) | 109 |
| 2.1.223 | Part 4 Section 2.6.19, sectPr (Section Properties) | 109 |
| 2.1.224 | Part 4 Section 2.6.21, top (Top Border) | 110 |
| 2.1.225 | Part 4 Section 2.6.22, type (Section Type) | 110 |
| 2.1.226 | Part 4 Section 2.7, Styles | 110 |
| 2.1.227 | Part 4 Section 2.7.3.1, aliases (Alternate Style Names) | 110 |
| 2.1.228 | Part 4 Section 2.7.3.2, autoRedefine (Automatically Merge User Formatting Into Style Definition) | 110 |
| 2.1.229 | Part 4 Section 2.7.3.3, basedOn (Parent Style ID) | 111 |
| 2.1.230 | Part 4 Section 2.7.3.4, hidden (Hide Style From User Interface) | 111 |
| 2.1.231 | Part 4 Section 2.7.3.5, latentStyles (Latent Style Information) | 111 |

| | | |
|---------|---|-----|
| 2.1.232 | Part 4 Section 2.7.3.6, link (Linked Style Reference) | 111 |
| 2.1.233 | Part 4 Section 2.7.3.7, locked (Style Cannot Be Applied) | 112 |
| 2.1.234 | Part 4 Section 2.7.3.8, lsdException (Latent Style Exception) | 112 |
| 2.1.235 | Part 4 Section 2.7.3.9, name (Primary Style Name) | 112 |
| 2.1.236 | Part 4 Section 2.7.3.10, next (Style For Next Paragraph) | 121 |
| 2.1.237 | Part 4 Section 2.7.3.11, personal (E-Mail Message Text Style) | 121 |
| 2.1.238 | Part 4 Section 2.7.3.12, personalCompose (E-Mail Message Composition Style) | 122 |
| 2.1.239 | Part 4 Section 2.7.3.13, personalReply (E-Mail Message Reply Style) | 122 |
| 2.1.240 | Part 4 Section 2.7.3.14, qFormat (Primary Style) | 122 |
| 2.1.241 | Part 4 Section 2.7.3.16, semiHidden (Hide Style From Main User Interface) | 122 |
| 2.1.242 | Part 4 Section 2.7.3.17, style (Style Definition) | 122 |
| 2.1.243 | Part 4 Section 2.7.3.19, uiPriority (Optional User Interface Sorting Order) | 123 |
| 2.1.244 | Part 4 Section 2.7.3.20, unhideWhenUsed (Remove Semi-Hidden Property When Style Is Used) | 123 |
| 2.1.245 | Part 4 Section 2.7.4.2, pPr (Paragraph Properties) | 123 |
| 2.1.246 | Part 4 Section 2.7.4.4, rPr (Run Properties) | 123 |
| 2.1.247 | Part 4 Section 2.7.5, Table Styles | 123 |
| 2.1.248 | Part 4 Section 2.7.5.1, pPr (Table Style Conditional Formatting Paragraph Properties) | 124 |
| 2.1.249 | Part 4 Section 2.7.5.2, rPr (Table Style Conditional Formatting Run Properties) | 124 |
| 2.1.250 | Part 4 Section 2.7.5.3, tblPr (Table Style Conditional Formatting Table Properties) | 124 |
| 2.1.251 | Part 4 Section 2.7.5.4, tblPr (Style Table Properties) | 124 |
| 2.1.252 | Part 4 Section 2.7.5.5, tblStyleColBandSize (Number of Columns in Column Band) | 124 |
| 2.1.253 | Part 4 Section 2.7.5.6, tblStylePr (Style Conditional Table Formatting Properties) | 125 |
| 2.1.254 | Part 4 Section 2.7.5.7, tblStyleRowBandSize (Number of Rows in Row Band) | 125 |
| 2.1.255 | Part 4 Section 2.7.5.8, tcPr (Style Table Cell Properties) | 125 |
| 2.1.256 | Part 4 Section 2.7.5.9, tcPr (Table Style Conditional Formatting Table Cell Properties) | 126 |
| 2.1.257 | Part 4 Section 2.7.5.10, trPr (Table Style Conditional Formatting Table Row Properties) | 126 |
| 2.1.258 | Part 4 Section 2.7.5.11, trPr (Style Table Row Properties) | 126 |
| 2.1.259 | Part 4 Section 2.7.7, Paragraph Styles | 126 |
| 2.1.260 | Part 4 Section 2.7.7.2, pPr (Style Paragraph Properties) | 126 |
| 2.1.261 | Part 4 Section 2.7.8.1, rPr (Run Properties) | 127 |
| 2.1.262 | Part 4 Section 2.8, Fonts | 127 |
| 2.1.263 | Part 4 Section 2.8.2.1, altName (Alternate Names for Font) | 127 |
| 2.1.264 | Part 4 Section 2.8.2.2, charset (Character Set Supported By Font) | 128 |
| 2.1.265 | Part 4 Section 2.8.2.3, embedBold (Bold Style Font Style Embedding) | 128 |
| 2.1.266 | Part 4 Section 2.8.2.4, embedBoldItalic (Bold Italic Font Style Embedding) | 128 |
| 2.1.267 | Part 4 Section 2.8.2.5, embedItalic (Italic Font Style Embedding) | 128 |
| 2.1.268 | Part 4 Section 2.8.2.6, embedRegular (Regular Font Style Embedding) | 128 |
| 2.1.269 | Part 4 Section 2.8.2.8, embedTrueTypeFonts (Embed TrueType Fonts) | 129 |
| 2.1.270 | Part 4 Section 2.8.2.9, family (Font Family) | 129 |
| 2.1.271 | Part 4 Section 2.8.2.10, font (Properties for a Single Font) | 129 |
| 2.1.272 | Part 4 Section 2.8.2.12, notTrueType (Raster or Vector Font) | 129 |
| 2.1.273 | Part 4 Section 2.8.2.13, panose1 (Panose-1 Typeface Classification Number) | 129 |
| 2.1.274 | Part 4 Section 2.8.2.14, pitch (Font Pitch) | 130 |
| 2.1.275 | Part 4 Section 2.8.2.16, sig (Supported Unicode Subranges and Code Pages) | 130 |
| 2.1.276 | Part 4 Section 2.9.1, abstractNum (Abstract Numbering Definition) | 130 |

| | | |
|---------|--|-----|
| 2.1.277 | Part 4 Section 2.9.2, abstractNumId (Abstract Numbering Definition Reference)..... | 130 |
| 2.1.278 | Part 4 Section 2.9.3, ilvl (Numbering Level Reference) | 130 |
| 2.1.279 | Part 4 Section 2.9.4, isLgl (Display All Levels Using Arabic Numerals)..... | 130 |
| 2.1.280 | Part 4 Section 2.9.5, legacy (Legacy Numbering Level Properties) | 131 |
| 2.1.281 | Part 4 Section 2.9.6, lvl (Numbering Level Override Definition)..... | 131 |
| 2.1.282 | Part 4 Section 2.9.7, lvl (Numbering Level Definition)..... | 131 |
| 2.1.283 | Part 4 Section 2.9.8, lvlJc (Justification) | 131 |
| 2.1.284 | Part 4 Section 2.9.11, lvlRestart (Restart Numbering Level Symbol)..... | 131 |
| 2.1.285 | Part 4 Section 2.9.12, lvlText (Numbering Level Text) | 132 |
| 2.1.286 | Part 4 Section 2.9.14, name (Abstract Numbering Definition Name)..... | 132 |
| 2.1.287 | Part 4 Section 2.9.16, num (Numbering Definition Instance) | 132 |
| 2.1.288 | Part 4 Section 2.9.18, numFmt (Numbering Format) | 132 |
| 2.1.289 | Part 4 Section 2.9.19, numId (Numbering Definition Instance Reference) | 132 |
| 2.1.290 | Part 4 Section 2.9.22, numStyleLink (Numbering Style Reference)..... | 133 |
| 2.1.291 | Part 4 Section 2.9.23, pict (Picture Numbering Symbol Properties) | 133 |
| 2.1.292 | Part 4 Section 2.9.24, pPr (Numbering Level Associated Paragraph Properties)..... | 133 |
| 2.1.293 | Part 4 Section 2.9.25, pStyle (Paragraph Style's Associated Numbering Level) .. | 133 |
| 2.1.294 | Part 4 Section 2.9.26, rPr (Numbering Symbol Run Properties)..... | 133 |
| 2.1.295 | Part 4 Section 2.9.27, start (Starting Value) | 133 |
| 2.1.296 | Part 4 Section 2.9.29, styleLink (Numbering Style Definition) | 134 |
| 2.1.297 | Part 4 Section 2.10.1, evenAndOddHeaders (Different Even/Odd Page Headers and Footers) | 134 |
| 2.1.298 | Part 4 Section 2.10.2, footerReference (Footer Reference)..... | 134 |
| 2.1.299 | Part 4 Section 2.10.3, ftr (Footer)..... | 134 |
| 2.1.300 | Part 4 Section 2.10.4, hdr (Header) | 134 |
| 2.1.301 | Part 4 Section 2.10.5, headerReference (Header Reference) | 135 |
| 2.1.302 | Part 4 Section 2.10.6, titlePg (Different First Page Headers and Footers) | 135 |
| 2.1.303 | Part 4 Section 2.11.2, endnote (Endnote Content) | 135 |
| 2.1.304 | Part 4 Section 2.11.3, endnote (Special Endnote List) | 135 |
| 2.1.305 | Part 4 Section 2.11.7, endnoteReference (Endnote Reference) | 135 |
| 2.1.306 | Part 4 Section 2.11.9, footnote (Special Footnote List) | 136 |
| 2.1.307 | Part 4 Section 2.11.10, footnote (Footnote Content) | 136 |
| 2.1.308 | Part 4 Section 2.11.14, footnoteReference (Footnote Reference) | 136 |
| 2.1.309 | Part 4 Section 2.11.17, numFmt (Footnote Numbering Format) | 136 |
| 2.1.310 | Part 4 Section 2.11.18, numFmt (Endnote Numbering Format)..... | 136 |
| 2.1.311 | Part 4 Section 2.11.20, numStart (Footnote and Endnote Numbering Starting Value)..... | 137 |
| 2.1.312 | Part 4 Section 2.11.21, pos (Footnote Placement)..... | 137 |
| 2.1.313 | Part 4 Section 2.12.5, docPart (Glossary Document Entry)..... | 137 |
| 2.1.314 | Part 4 Section 2.12.6, docPartBody (Contents of Glossary Document Entry)..... | 137 |
| 2.1.315 | Part 4 Section 2.12.7, docPartPr (Glossary Document Entry Properties) | 137 |
| 2.1.316 | Part 4 Section 2.12.11, guid (Entry ID) | 137 |
| 2.1.317 | Part 4 Section 2.13.4.2, comment (Comment Content)..... | 138 |
| 2.1.318 | Part 4 Section 2.13.4.3, commentRangeEnd (Comment Anchor Range End) | 140 |
| 2.1.319 | Part 4 Section 2.13.4.4, commentRangeStart (Comment Anchor Range Start) .. | 140 |
| 2.1.320 | Part 4 Section 2.13.4.5, commentReference (Comment Content Reference Mark)..... | 140 |
| 2.1.321 | Part 4 Section 2.13.5.1, cellDel (Table Cell Deletion)..... | 141 |
| 2.1.322 | Part 4 Section 2.13.5.2, cellIns (Table Cell Insertion) | 141 |
| 2.1.323 | Part 4 Section 2.13.5.3, cellMerge (Vertically Merged/Split Table Cells) | 141 |
| 2.1.324 | Part 4 Section 2.13.5.4, customXmlDelRangeEnd (Custom XML Markup Deletion End)..... | 141 |

| | | |
|---------|---|-----|
| 2.1.325 | Part 4 Section 2.13.5.5, customXmlDelRangeStart (Custom XML Markup Deletion Start) | 141 |
| 2.1.326 | Part 4 Section 2.13.5.6, customXmlInsRangeEnd (Custom XML Markup Insertion End) | 141 |
| 2.1.327 | Part 4 Section 2.13.5.7, customXmlInsRangeStart (Custom XML Markup Insertion Start) | 142 |
| 2.1.328 | Part 4 Section 2.13.5.8, customXmlMoveFromRangeEnd (Custom XML Markup Move Source End) | 142 |
| 2.1.329 | Part 4 Section 2.13.5.9, customXmlMoveFromRangeStart (Custom XML Markup Move Source Start) | 142 |
| 2.1.330 | Part 4 Section 2.13.5.10, customXmlMoveToRangeEnd (Custom XML Markup Move Destination Location End) | 143 |
| 2.1.331 | Part 4 Section 2.13.5.11, customXmlMoveToRangeStart (Custom XML Markup Move Destination Location Start) | 143 |
| 2.1.332 | Part 4 Section 2.13.5.12, del (Deleted Run Content) | 144 |
| 2.1.333 | Part 4 Section 2.13.5.13, del (Deleted Paragraph) | 144 |
| 2.1.334 | Part 4 Section 2.13.5.14, del (Deleted Table Row) | 144 |
| 2.1.335 | Part 4 Section 2.13.5.15, del (Deleted Math Control Character) | 144 |
| 2.1.336 | Part 4 Section 2.13.5.16, ins (Inserted Table Row) | 144 |
| 2.1.337 | Part 4 Section 2.13.5.17, ins (Inserted Math Control Character) | 144 |
| 2.1.338 | Part 4 Section 2.13.5.18, ins (Inserted Paragraph) | 145 |
| 2.1.339 | Part 4 Section 2.13.5.19, ins (Inserted Numbering Properties) | 145 |
| 2.1.340 | Part 4 Section 2.13.5.20, ins (Inserted Run Content) | 145 |
| 2.1.341 | Part 4 Section 2.13.5.21, moveFrom (Move Source Run Content) | 145 |
| 2.1.342 | Part 4 Section 2.13.5.22, moveFrom (Move Source Paragraph) | 146 |
| 2.1.343 | Part 4 Section 2.13.5.23, moveFromRangeEnd (Move Source Location Container - End) | 146 |
| 2.1.344 | Part 4 Section 2.13.5.24, moveFromRangeStart (Move Source Location Container - Start) | 146 |
| 2.1.345 | Part 4 Section 2.13.5.25, moveTo (Move Destination Paragraph) | 146 |
| 2.1.346 | Part 4 Section 2.13.5.26, moveTo (Move Destination Run Content) | 146 |
| 2.1.347 | Part 4 Section 2.13.5.27, moveToRangeEnd (Move Destination Location Container - End) | 147 |
| 2.1.348 | Part 4 Section 2.13.5.28, moveToRangeStart (Move Destination Location Container - Start) | 147 |
| 2.1.349 | Part 4 Section 2.13.5.29, numberingChange (Previous Numbering Field Properties) | 147 |
| 2.1.350 | Part 4 Section 2.13.5.30, numberingChange (Previous Paragraph Numbering Properties) | 147 |
| 2.1.351 | Part 4 Section 2.13.5.31, pPrChange (Revision Information for Paragraph Properties) | 150 |
| 2.1.352 | Part 4 Section 2.13.5.32, rPrChange (Revision Information for Run Properties) | 150 |
| 2.1.353 | Part 4 Section 2.13.5.33, rPrChange (Revision Information for Run Properties on the Paragraph Mark) | 150 |
| 2.1.354 | Part 4 Section 2.13.5.34, sectPrChange (Revision Information for Section Properties) | 150 |
| 2.1.355 | Part 4 Section 2.13.5.35, tblGridChange (Revision Information for Table Grid Column Definitions) | 151 |
| 2.1.356 | Part 4 Section 2.13.5.36, tblPrChange (Revision Information for Table Properties) | 151 |
| 2.1.357 | Part 4 Section 2.13.5.37, tblPrExChange (Revision Information for Table-Level Property Exceptions) | 151 |

| | | |
|---------|--|-----|
| 2.1.358 | Part 4 Section 2.13.5.38, tcPrChange (Revision Information for Table Cell Properties) | 151 |
| 2.1.359 | Part 4 Section 2.13.5.39, trPrChange (Revision Information for Table Row Properties) | 151 |
| 2.1.360 | Part 4 Section 2.13.6, Bookmarks | 151 |
| 2.1.361 | Part 4 Section 2.13.6.1, bookmarkEnd (Bookmark End)..... | 151 |
| 2.1.362 | Part 4 Section 2.13.6.2, bookmarkStart (Bookmark Start) | 152 |
| 2.1.363 | Part 4 Section 2.13.7.1, permEnd (Range Permission End)..... | 152 |
| 2.1.364 | Part 4 Section 2.13.7.2, permStart (Range Permission Start) | 152 |
| 2.1.365 | Part 4 Section 2.13.8.1, proofErr (Proofing Error Anchor)..... | 153 |
| 2.1.366 | Part 4 Section 2.14, Mail Merge | 153 |
| 2.1.367 | Part 4 Section 2.14.2, activeRecord (Record Currently Displayed In Merged Document) | 153 |
| 2.1.368 | Part 4 Section 2.14.4, checkErrors (Mail Merge Error Reporting Setting) | 153 |
| 2.1.369 | Part 4 Section 2.14.5, colDelim (Column Delimiter for Data Source)..... | 153 |
| 2.1.370 | Part 4 Section 2.14.6, column (Index of Column Containing Unique Values for Record)..... | 153 |
| 2.1.371 | Part 4 Section 2.14.7, column (Index of Column Being Mapped) | 154 |
| 2.1.372 | Part 4 Section 2.14.9, dataSource (Data Source File Path) | 154 |
| 2.1.373 | Part 4 Section 2.14.12, doNotSuppressBlankLines (Remove Blank Lines from Merged Documents)..... | 154 |
| 2.1.374 | Part 4 Section 2.14.13, dynamicAddress (Use Country-Based Address Field Ordering) | 154 |
| 2.1.375 | Part 4 Section 2.14.14, fHdr (First Row of Data Source Contains Column Names) | 154 |
| 2.1.376 | Part 4 Section 2.14.15, fieldMapData (External Data Source to Merge Field Mapping)..... | 154 |
| 2.1.377 | Part 4 Section 2.14.16, headerSource (Header Definition File Path)..... | 156 |
| 2.1.378 | Part 4 Section 2.14.17, lid (Merge Field Name Language ID) | 156 |
| 2.1.379 | Part 4 Section 2.14.18, linkToQuery (Query Contains Link to External Query File)..... | 156 |
| 2.1.380 | Part 4 Section 2.14.20, mailMerge (Mail Merge Settings) | 156 |
| 2.1.381 | Part 4 Section 2.14.23, mappedName (Predefined Merge Field Name) | 156 |
| 2.1.382 | Part 4 Section 2.14.24, name (Data Source Name for Column)..... | 156 |
| 2.1.383 | Part 4 Section 2.14.25, odso (Office Data Source Object Settings) | 157 |
| 2.1.384 | Part 4 Section 2.14.26, query (Query For Data Source Records To Merge) | 157 |
| 2.1.385 | Part 4 Section 2.14.27, recipientData (Reference to Inclusion/Exclusion Data for Data Source) | 157 |
| 2.1.386 | Part 4 Section 2.14.30, src (ODSO Data Source File Path)..... | 157 |
| 2.1.387 | Part 4 Section 2.14.31, table (Data Source Table Name) | 157 |
| 2.1.388 | Part 4 Section 2.14.34, udl (UDL Connection String) | 157 |
| 2.1.389 | Part 4 Section 2.14.35, uniqueTag (Unique Value for Record)..... | 158 |
| 2.1.390 | Part 4 Section 2.15.1.1, activeWritingStyle (Grammar Checking Settings) | 159 |
| 2.1.391 | Part 4 Section 2.15.1.3, alwaysMergeEmptyNamespace (Do Not Mark Custom XML Elements With No Namespace As Invalid) | 159 |
| 2.1.392 | Part 4 Section 2.15.1.6, attachedTemplate (Attached Document Template) | 160 |
| 2.1.393 | Part 4 Section 2.15.1.7, autoCaption (Single Automatic Captioning Setting)..... | 160 |
| 2.1.394 | Part 4 Section 2.15.1.8, autoCaptions (Automatic Captioning Settings) | 160 |
| 2.1.395 | Part 4 Section 2.15.1.9, autoFormatOverride (Allow Automatic Formatting to Override Formatting Protection Settings)..... | 160 |
| 2.1.396 | Part 4 Section 2.15.1.11, bookFoldPrinting (Book Fold Printing)..... | 160 |
| 2.1.397 | Part 4 Section 2.15.1.12, bookFoldPrintingSheets (Number of Pages Per Booklet) | 161 |

| | | |
|---------|---|-----|
| 2.1.398 | Part 4 Section 2.15.1.13, bookFoldRevPrinting (Reverse Book Fold Printing) | 161 |
| 2.1.399 | Part 4 Section 2.15.1.16, caption (Single Caption Type Definition) | 162 |
| 2.1.400 | Part 4 Section 2.15.1.17, captions (Caption Settings) | 162 |
| 2.1.401 | Part 4 Section 2.15.1.19, clickAndTypeStyle (Paragraph Style Applied to Automatically Generated Paragraphs) | 162 |
| 2.1.402 | Part 4 Section 2.15.1.20, clrSchemeMapping (Theme Color Mappings) | 162 |
| 2.1.403 | Part 4 Section 2.15.1.21, consecutiveHyphenLimit (Maximum Number of Consecutively Hyphenated Lines) | 162 |
| 2.1.404 | Part 4 Section 2.15.1.22, decimalSymbol (Radix Point for Field Code Evaluation) | 163 |
| 2.1.405 | Part 4 Section 2.15.1.23, defaultTableStyle (Default Table Style for Newly Inserted Tables) | 163 |
| 2.1.406 | Part 4 Section 2.15.1.24, defaultTabStop (Distance Between Automatic Tab Stops) | 163 |
| 2.1.407 | Part 4 Section 2.15.1.26, displayHorizontalDrawingGridEvery (Distance between Vertical Gridlines) | 163 |
| 2.1.408 | Part 4 Section 2.15.1.27, displayVerticalDrawingGridEvery (Distance between Horizontal Gridlines) | 163 |
| 2.1.409 | Part 4 Section 2.15.1.28, documentProtection (Document Editing Restrictions) .. | 164 |
| 2.1.410 | Part 4 Section 2.15.1.30, docVar (Single Document Variable) | 167 |
| 2.1.411 | Part 4 Section 2.15.1.41, doNotUseMarginsForDrawingGridOrigin (Do Not Use Margins for Drawing Grid Origin) | 167 |
| 2.1.412 | Part 4 Section 2.15.1.43, drawingGridHorizontalOrigin (Drawing Grid Horizontal Origin Point) | 167 |
| 2.1.413 | Part 4 Section 2.15.1.45, drawingGridVerticalOrigin (Drawing Grid Vertical Origin Point) | 167 |
| 2.1.414 | Part 4 Section 2.15.1.50, hdrShapeDefaults (Default Properties for VML Objects in Header and Footer) | 167 |
| 2.1.415 | Part 4 Section 2.15.1.53, hyphenationZone (Hyphenation Zone) | 167 |
| 2.1.416 | Part 4 Section 2.15.1.56, listSeparator (List Separator for Field Code Evaluation) | 168 |
| 2.1.417 | Part 4 Section 2.15.1.58, noLineBreaksAfter (Custom Set of Characters Which Cannot End a Line) | 168 |
| 2.1.418 | Part 4 Section 2.15.1.59, noLineBreaksBefore (Custom Set Of Characters Which Cannot Begin A Line) | 168 |
| 2.1.419 | Part 4 Section 2.15.1.60, noPunctuationKerning (Never Kern Punctuation Characters) | 168 |
| 2.1.420 | Part 4 Section 2.15.1.62, printFractionalCharacterWidth (Print Fractional Character Widths) | 168 |
| 2.1.421 | Part 4 Section 2.15.1.63, printPostScriptOverText (Print PostScript Codes With Document Text) | 169 |
| 2.1.422 | Part 4 Section 2.15.1.66, readModeInkLockDown (Freeze Document Layout) ... | 169 |
| 2.1.423 | Part 4 Section 2.15.1.69, revisionView (Visibility of Annotation Types) | 169 |
| 2.1.424 | Part 4 Section 2.15.1.70, rsid (Single Session Revision Save ID) | 169 |
| 2.1.425 | Part 4 Section 2.15.1.74, saveInvalidXml (Allow Saving Document As XML File When Custom XML Markup Is Invalid) | 169 |
| 2.1.426 | Part 4 Section 2.15.1.76, saveThroughXslt (Custom XSL Transform To Use When Saving As XML File) | 169 |
| 2.1.427 | Part 4 Section 2.15.1.79, shapeDefaults (Default Properties for VML Objects in Main Document) | 170 |
| 2.1.428 | Part 4 Section 2.15.1.81, showXMLTags (Show Visual Indicators for Custom XML Markup Start/End Locations) | 170 |

| | | |
|---------|--|-----|
| 2.1.429 | Part 4 Section 2.15.1.82, smartTagType (Supplementary Smart Tag Information) | 170 |
| 2.1.430 | Part 4 Section 2.15.1.83, strictFirstAndLastChars (Use Strict Kinsoku Rules for Japanese Text)..... | 170 |
| 2.1.431 | Part 4 Section 2.15.1.86, stylePaneFormatFilter (Suggested Filtering for List of Document Styles)..... | 170 |
| 2.1.432 | Part 4 Section 2.15.1.87, stylePaneSortMethod (Suggested Sorting for List of Document Styles)..... | 171 |
| 2.1.433 | Part 4 Section 2.15.1.88, summaryLength (Percentage of Document to Use When Generating Summary)..... | 171 |
| 2.1.434 | Part 4 Section 2.15.1.89, themeFontLang (Theme Font Languages) | 171 |
| 2.1.435 | Part 4 Section 2.15.1.91, updateFields (Automatically Recalculate Fields on Open) | 171 |
| 2.1.436 | Part 4 Section 2.15.1.93, view (Document View Setting) | 172 |
| 2.1.437 | Part 4 Section 2.15.1.94, writeProtection (Write Protection) | 172 |
| 2.1.438 | Part 4 Section 2.15.1.95, zoom (Magnification Setting) | 173 |
| 2.1.439 | Part 4 Section 2.15.2.1, allowPNG (Allow PNG as Graphic Format) | 174 |
| 2.1.440 | Part 4 Section 2.15.2.2, blockQuote (Data for HTML blockquote Element) | 174 |
| 2.1.441 | Part 4 Section 2.15.2.3, bodyDiv (Data for HTML body Element)..... | 174 |
| 2.1.442 | Part 4 Section 2.15.2.4, bottom (Bottom Border for HTML div) | 174 |
| 2.1.443 | Part 4 Section 2.15.2.5, color (Frameset Splitter Color) | 174 |
| 2.1.444 | Part 4 Section 2.15.2.6, div (Information About Single HTML div Element)..... | 174 |
| 2.1.445 | Part 4 Section 2.15.2.10, doNotOrganizeInFolder (Do Not Place Supporting Files in Subdirectory) | 175 |
| 2.1.446 | Part 4 Section 2.15.2.14, encoding (Output Encoding When Saving as Web Page)..... | 175 |
| 2.1.447 | Part 4 Section 2.15.2.15, flatBorders (Frameset Splitter Border Style)..... | 175 |
| 2.1.448 | Part 4 Section 2.15.2.17, frameLayout (Frameset Layout) | 175 |
| 2.1.449 | Part 4 Section 2.15.2.18, frameset (Root Frameset Definition) | 175 |
| 2.1.450 | Part 4 Section 2.15.2.19, frameset (Nested Frameset Definition) | 175 |
| 2.1.451 | Part 4 Section 2.15.2.21, left (Left Border for HTML div)..... | 175 |
| 2.1.452 | Part 4 Section 2.15.2.22, linkedToFile (Maintain Link to Existing File) | 176 |
| 2.1.453 | Part 4 Section 2.15.2.29, name (Frame Name)..... | 176 |
| 2.1.454 | Part 4 Section 2.15.2.30, noBorder (Do Not Display Frameset Splitters) | 176 |
| 2.1.455 | Part 4 Section 2.15.2.31, noResizeAllowed (Frame Cannot Be Resized) | 176 |
| 2.1.456 | Part 4 Section 2.15.2.32, optimizeForBrowser (Disable Features Not Supported by Target Web Browser)..... | 176 |
| 2.1.457 | Part 4 Section 2.15.2.33, pixelsPerInch (Pixels per Inch for Graphics/Images) .. | 176 |
| 2.1.458 | Part 4 Section 2.15.2.35, right (Right Border for HTML div)..... | 177 |
| 2.1.459 | Part 4 Section 2.15.2.38, sourceFileName (Source File for Frame) | 177 |
| 2.1.460 | Part 4 Section 2.15.2.39, sz (Frame Size) | 177 |
| 2.1.461 | Part 4 Section 2.15.2.40, sz (Nested Frameset Size) | 177 |
| 2.1.462 | Part 4 Section 2.15.2.41, targetScreenSz (Target Screen Size for Web Page) | 177 |
| 2.1.463 | Part 4 Section 2.15.2.42, top (Top Border for HTML div)..... | 177 |
| 2.1.464 | Part 4 Section 2.15.3.4, applyBreakingRules (Use Legacy Ethiopic and Amharic Line Breaking Rules) | 178 |
| 2.1.465 | Part 4 Section 2.15.3.6, autoSpaceLikeWord95 (Emulate Word 95 Full-Width Character Spacing) | 178 |
| 2.1.466 | Part 4 Section 2.15.3.10, convMailMergeEsc (Treat Backslash Quotation Delimiter as a Single Quotation Mark) | 180 |
| 2.1.467 | Part 4 Section 2.15.3.12, doNotAutofitConstrainedTables (Do Not AutoFit Tables To Fit Next To Wrapped Objects) | 180 |

| | | |
|---------|--|-----|
| 2.1.468 | Part 4 Section 2.15.3.16, doNotLeaveBackslashAlone (Convert Backslash To Yen Sign When Entered)..... | 180 |
| 2.1.469 | Part 4 Section 2.15.3.19, doNotSuppressParagraphBorders (Do Not Suppress Paragraph Borders Next To Frames) | 180 |
| 2.1.470 | Part 4 Section 2.15.3.26, footnoteLayoutLikeWW8 (Emulate Word 6.x/95/97 Footnote Placement)..... | 181 |
| 2.1.471 | Part 4 Section 2.15.3.31, lineWrapLikeWord6 (Emulate Word 6.0 Line Wrapping for East Asian Text)..... | 183 |
| 2.1.472 | Part 4 Section 2.15.3.32, mwSmallCaps (Emulate Word 5.x for the Macintosh Small Caps Formatting)..... | 184 |
| 2.1.473 | Part 4 Section 2.15.3.41, shapeLayoutLikeWW8 (Emulate Word 97 Text Wrapping Around Floating Objects)..... | 185 |
| 2.1.474 | Part 4 Section 2.15.3.46, subFontBySize (Increase Priority Of Font Size During Font Substitution)..... | 187 |
| 2.1.475 | Part 4 Section 2.15.3.51, suppressTopSpacingWP (Emulate WordPerfect 5.x Line Spacing)..... | 187 |
| 2.1.476 | Part 4 Section 2.15.3.53, truncateFontHeightsLikeWP6 (Emulate WordPerfect 6.x Font Height Calculation)..... | 188 |
| 2.1.477 | Part 4 Section 2.15.3.54, uiCompat97To2003 (Disable Features Incompatible With Earlier Word Formats)..... | 189 |
| 2.1.478 | Part 4 Section 2.15.3.63, useWord2002TableStyleRules (Emulate Word 2002 Table Style Rules) | 189 |
| 2.1.479 | Part 4 Section 2.15.3.64, useWord97LineBreakRules (Emulate Word 97 East Asian Line Breaking)..... | 190 |
| 2.1.480 | Part 4 Section 2.15.3.65, wpJustification (Emulate WordPerfect 6.x Paragraph Justification) | 192 |
| 2.1.481 | Part 4 Section 2.15.3.66, wpSpaceWidth (Space width)..... | 193 |
| 2.1.482 | Part 4 Section 2.16.1, Syntax..... | 194 |
| 2.1.483 | Part 4 Section 2.16.3.3, Operators..... | 194 |
| 2.1.484 | Part 4 Section 2.16.4.1, Date and time formatting | 194 |
| 2.1.485 | Part 4 Section 2.16.4.3, General formatting | 206 |
| 2.1.486 | Part 4 Section 2.16.5.1, ADDRESSBLOCK | 206 |
| 2.1.487 | Part 4 Section 2.16.5.2, ADVANCE | 207 |
| 2.1.488 | Part 4 Section 2.16.5.4, AUTHOR..... | 208 |
| 2.1.489 | Part 4 Section 2.16.5.5, AUTONUM | 208 |
| 2.1.490 | Part 4 Section 2.16.5.6, AUTONUMLGL | 208 |
| 2.1.491 | Part 4 Section 2.16.5.7, AUTONUMOUT | 208 |
| 2.1.492 | Part 4 Section 2.16.5.10, BARCODE | 208 |
| 2.1.493 | Part 4 Section 2.16.5.11, BIBLIOGRAPHY | 208 |
| 2.1.494 | Part 4 Section 2.16.5.12, BIDIOUTLINE | 209 |
| 2.1.495 | Part 4 Section 2.16.5.13, CITATION | 209 |
| 2.1.496 | Part 4 Section 2.16.5.14, COMMENTS..... | 209 |
| 2.1.497 | Part 4 Section 2.16.5.16, CREATEDATE | 209 |
| 2.1.498 | Part 4 Section 2.16.5.17, DATABASE..... | 210 |
| 2.1.499 | Part 4 Section 2.16.5.18, DATE | 234 |
| 2.1.500 | Part 4 Section 2.16.5.19, DOCPROPERTY | 234 |
| 2.1.501 | Part 4 Section 2.16.5.22, EQ..... | 234 |
| 2.1.502 | Part 4 Section 2.16.5.23, FILENAME..... | 235 |
| 2.1.503 | Part 4 Section 2.16.5.24, FILESIZE | 235 |
| 2.1.504 | Part 4 Section 2.16.5.26, FORMCHECKBOX | 235 |
| 2.1.505 | Part 4 Section 2.16.5.27, FORMDROPDOWN..... | 235 |
| 2.1.506 | Part 4 Section 2.16.5.29, GOTOBUTTON | 235 |
| 2.1.507 | Part 4 Section 2.16.5.30, GREETINGLINE..... | 235 |

| | | |
|---------|---|-----|
| 2.1.508 | Part 4 Section 2.16.5.31, HYPERLINK | 237 |
| 2.1.509 | Part 4 Section 2.16.5.35, INDEX | 237 |
| 2.1.510 | Part 4 Section 2.16.5.37, KEYWORDS | 237 |
| 2.1.511 | Part 4 Section 2.16.5.38, LASTSAVEDBY | 237 |
| 2.1.512 | Part 4 Section 2.16.5.39, LINK | 237 |
| 2.1.513 | Part 4 Section 2.16.5.40, LISTNUM | 238 |
| 2.1.514 | Part 4 Section 2.16.5.41, MACROBUTTON | 238 |
| 2.1.515 | Part 4 Section 2.16.5.42, MERGEFIELD | 239 |
| 2.1.516 | Part 4 Section 2.16.5.47, NOTEREF | 239 |
| 2.1.517 | Part 4 Section 2.16.5.52, PAGEREF | 239 |
| 2.1.518 | Part 4 Section 2.16.5.53, PRINT | 239 |
| 2.1.519 | Part 4 Section 2.16.5.54, PRINTDATE | 240 |
| 2.1.520 | Part 4 Section 2.16.5.56, QUOTE | 240 |
| 2.1.521 | Part 4 Section 2.16.5.57, RD | 240 |
| 2.1.522 | Part 4 Section 2.16.5.58, REF | 240 |
| 2.1.523 | Part 4 Section 2.16.5.59, REVNUM | 241 |
| 2.1.524 | Part 4 Section 2.16.5.60, SAVEDATE | 241 |
| 2.1.525 | Part 4 Section 2.16.5.61, SECTION | 242 |
| 2.1.526 | Part 4 Section 2.16.5.62, SECTIONPAGES | 242 |
| 2.1.527 | Part 4 Section 2.16.5.63, SEQ | 242 |
| 2.1.528 | Part 4 Section 2.16.5.65, SKIPIF | 242 |
| 2.1.529 | Part 4 Section 2.16.5.66, STYLEREF | 242 |
| 2.1.530 | Part 4 Section 2.16.5.67, SUBJECT | 243 |
| 2.1.531 | Part 4 Section 2.16.5.68, SYMBOL | 243 |
| 2.1.532 | Part 4 Section 2.16.5.69, TA | 243 |
| 2.1.533 | Part 4 Section 2.16.5.71, TEMPLATE | 244 |
| 2.1.534 | Part 4 Section 2.16.5.72, TIME | 244 |
| 2.1.535 | Part 4 Section 2.16.5.73, TITLE | 244 |
| 2.1.536 | Part 4 Section 2.16.5.74, TOA | 244 |
| 2.1.537 | Part 4 Section 2.16.5.75, TOC | 244 |
| 2.1.538 | Part 4 Section 2.16.5.76, USERADDRESS | 244 |
| 2.1.539 | Part 4 Section 2.16.5.77, USERINITIALS | 244 |
| 2.1.540 | Part 4 Section 2.16.5.78, USERNAME | 245 |
| 2.1.541 | Part 4 Section 2.16.5.79, XE | 245 |
| 2.1.542 | Part 4 Section 2.16.9, ddList (Drop-Down List Form Field Properties) | 245 |
| 2.1.543 | Part 4 Section 2.16.10, default (Default Text Box Form Field String) | 245 |
| 2.1.544 | Part 4 Section 2.16.11, default (Default Drop-Down List Item Index) | 245 |
| 2.1.545 | Part 4 Section 2.16.12, default (Default Checkbox Form Field State) | 245 |
| 2.1.546 | Part 4 Section 2.16.17, ffData (Form Field Properties) | 245 |
| 2.1.547 | Part 4 Section 2.16.19, fldData (Custom Field Data) | 245 |
| 2.1.548 | Part 4 Section 2.16.20, fldData (Custom Field Data) | 246 |
| 2.1.549 | Part 4 Section 2.16.21, fldSimple (Simple Field) | 246 |
| 2.1.550 | Part 4 Section 2.16.22, format (Text Box Form Field Formatting) | 246 |
| 2.1.551 | Part 4 Section 2.16.24, hyperlink (Hyperlink) | 246 |
| 2.1.552 | Part 4 Section 2.16.26, listEntry (Drop-Down List Entry) | 246 |
| 2.1.553 | Part 4 Section 2.16.27, maxLength (Text Box Form Field Maximum Length) | 247 |
| 2.1.554 | Part 4 Section 2.16.31, sizeAuto (Automatically Size Form Field) | 247 |
| 2.1.555 | Part 4 Section 2.17.1.1, txbxContent (Rich Text Box Content Container) | 247 |
| 2.1.556 | Part 4 Section 2.17.2.1, subDoc (Anchor for Subdocument Location) | 247 |
| 2.1.557 | Part 4 Section 2.17.3.1, altChunk (Anchor for Imported External Content) | 247 |
| 2.1.558 | Part 4 Section 2.18.4, ST_Border (Border Styles) | 248 |
| 2.1.559 | Part 4 Section 2.18.5, ST_BrClear (Line Break Text Wrapping Restart Location) | 248 |
| 2.1.560 | Part 4 Section 2.18.8, ST_CaptionPos (Automatic Caption Positioning Values) | 248 |

| | | |
|---------|--|-----|
| 2.1.561 | Part 4 Section 2.18.10, ST_CharacterSpacing (Character-Level Whitespace Compression Settings) | 249 |
| 2.1.562 | Part 4 Section 2.18.16, ST_DecimalNumber (Decimal Number Value)..... | 249 |
| 2.1.563 | Part 4 Section 2.18.17, ST_DisplacedByCustomXml (Location of Custom XML Markup Displacing an Annotation) | 249 |
| 2.1.564 | Part 4 Section 2.18.18, ST_DocGrid (Document Grid Types) | 249 |
| 2.1.565 | Part 4 Section 2.18.19, ST_DocPartBehavior (Insertion Behavior Types)..... | 249 |
| 2.1.566 | Part 4 Section 2.18.28, ST_Em (Emphasis Mark Type) | 250 |
| 2.1.567 | Part 4 Section 2.18.29, ST_FFHelpTextVal (Help Text Value)..... | 250 |
| 2.1.568 | Part 4 Section 2.18.30, ST_FFName (Form Field Name Value) | 250 |
| 2.1.569 | Part 4 Section 2.18.31, ST_FFStatusTextVal (Status Text Value) | 250 |
| 2.1.570 | Part 4 Section 2.18.35, ST_FrameLayout (Frameset Layout Order) | 250 |
| 2.1.571 | Part 4 Section 2.18.38, ST_FtnPos (Footnote Positioning Location)..... | 251 |
| 2.1.572 | Part 4 Section 2.18.41, ST_HdrFtr (Header or Footer Type) | 251 |
| 2.1.573 | Part 4 Section 2.18.48, ST_HpsMeasure (Measurement in Half-Points) | 251 |
| 2.1.574 | Part 4 Section 2.18.50, ST_Jc (Horizontal Alignment Type) | 251 |
| 2.1.575 | Part 4 Section 2.18.51, ST_Lang (Language Reference)..... | 251 |
| 2.1.576 | Part 4 Section 2.18.52, ST_LangCode (Two Digit Hexadecimal Language Code)..... | 251 |
| 2.1.577 | Part 4 Section 2.18.59, ST_MailMergeDataType (Mail Merge Data Source Type Values) | 252 |
| 2.1.578 | Part 4 Section 2.18.64, ST_Merge (Merged Cell Type) | 252 |
| 2.1.579 | Part 4 Section 2.18.66, ST_NumberFormat (Numbering Format) | 252 |
| 2.1.580 | Part 4 Section 2.18.67, ST_OnOff (On/Off Value)..... | 252 |
| 2.1.581 | Part 4 Section 2.18.68, ST_PageBorderDisplay (Page Border Display Options)..... | 253 |
| 2.1.582 | Part 4 Section 2.18.75, ST_PointMeasure (Measurement in Points) | 253 |
| 2.1.583 | Part 4 Section 2.18.77, ST_ProofErr (Proofing Error Type) | 253 |
| 2.1.584 | Part 4 Section 2.18.82, ST_RubyAlign (Phonetic Guide Text Alignment)..... | 253 |
| 2.1.585 | Part 4 Section 2.18.85, ST_Shd (Shading Patterns) | 253 |
| 2.1.586 | Part 4 Section 2.18.87, ST_SignedHpsMeasure (Signed Measurement in Half-Points)..... | 253 |
| 2.1.587 | Part 4 Section 2.18.88, ST_SignedTwipsMeasure (Signed Measurement in Twentieths of a Point) | 253 |
| 2.1.588 | Part 4 Section 2.18.91, ST_TabJc (Custom Tab Stop Type) | 254 |
| 2.1.589 | Part 4 Section 2.18.100, ST_TextDirection (Text Flow Direction) | 254 |
| 2.1.590 | Part 4 Section 2.18.101, ST_TextEffect (Animated Text Effects) | 254 |
| 2.1.591 | Part 4 Section 2.18.102, ST_TextScale (Text Expansion/Compression Percentage) | 254 |
| 2.1.592 | Part 4 Section 2.18.106, ST_UcharHexNumber (Two Digit Hexadecimal Number Value)..... | 254 |
| 2.1.593 | Part 4 Section 2.18.108, ST_UnsignedDecimalNumber (Unsigned Decimal Number Value)..... | 254 |
| 2.1.594 | Part 4 Section 2.18.111, ST_VerticalJc (Vertical Alignment Type) | 255 |
| 2.1.595 | Part 4 Section 2.18.112, ST_View (Document View Values) | 255 |
| 2.1.596 | Part 4 Section 2.18.113, ST_Wrap (Text Wrapping around Text Frame Type) | 255 |
| 2.1.597 | Part 4 Section 3.2.1, bookViews (Workbook Views) | 255 |
| 2.1.598 | Part 4 Section 3.2.2, calcPr (Calculation Properties) | 255 |
| 2.1.599 | Part 4 Section 3.2.3, customWorkbookView (Custom Workbook View)..... | 256 |
| 2.1.600 | Part 4 Section 3.2.4, customWorkbookViews (Custom Workbook Views) | 258 |
| 2.1.601 | Part 4 Section 3.2.5, definedName (Defined Name)..... | 258 |
| 2.1.602 | Part 4 Section 3.2.6, definedNames (Defined Names)..... | 260 |
| 2.1.603 | Part 4 Section 3.2.7, ext (Extension)..... | 260 |
| 2.1.604 | Part 4 Section 3.2.9, externalReferences (External References) | 260 |
| 2.1.605 | Part 4 Section 3.2.11, fileRecoveryPr (File Recovery Properties) | 260 |

| | | |
|---------|---|-----|
| 2.1.606 | Part 4 Section 3.2.12, fileSharing (File Sharing) | 261 |
| 2.1.607 | Part 4 Section 3.2.13, fileVersion (File Version) | 263 |
| 2.1.608 | Part 4 Section 3.2.14, functionGroup (Function Group) | 264 |
| 2.1.609 | Part 4 Section 3.2.15, functionGroups (Function Groups) | 264 |
| 2.1.610 | Part 4 Section 3.2.16, oleSize (Embedded Object Size) | 264 |
| 2.1.611 | Part 4 Section 3.2.19, sheet (Sheet Information) | 264 |
| 2.1.612 | Part 4 Section 3.2.20, sheets (Sheets) | 265 |
| 2.1.613 | Part 4 Section 3.2.21, smartTagPr (Smart Tag Properties) | 265 |
| 2.1.614 | Part 4 Section 3.2.22, smartTagType (Smart Tag Type) | 265 |
| 2.1.615 | Part 4 Section 3.2.23, smartTagTypes (Smart Tag Types) | 265 |
| 2.1.616 | Part 4 Section 3.2.24, webPublishing (Web Publishing Properties) | 265 |
| 2.1.617 | Part 4 Section 3.2.25, webPublishObject (Web Publishing Object) | 266 |
| 2.1.618 | Part 4 Section 3.2.27, workbook (Workbook) | 266 |
| 2.1.619 | Part 4 Section 3.2.28, workbookPr (Workbook Properties) | 266 |
| 2.1.620 | Part 4 Section 3.2.29, workbookProtection (Workbook Protection) | 269 |
| 2.1.621 | Part 4 Section 3.2.30, workbookView (Workbook View) | 272 |
| 2.1.622 | Part 4 Section 3.3.1.2, brk (Break) | 273 |
| 2.1.623 | Part 4 Section 3.3.1.3, c (Cell) | 274 |
| 2.1.624 | Part 4 Section 3.3.1.4, cellSmartTag (Cell Smart Tag) | 274 |
| 2.1.625 | Part 4 Section 3.3.1.5, cellSmartTagPr (Smart Tag Properties) | 274 |
| 2.1.626 | Part 4 Section 3.3.1.6, cellSmartTags (Cell Smart Tags) | 275 |
| 2.1.627 | Part 4 Section 3.3.1.7, cellWatch (Cell Watch Item) | 275 |
| 2.1.628 | Part 4 Section 3.3.1.9, cfRule (Conditional Formatting Rule) | 275 |
| 2.1.629 | Part 4 Section 3.3.1.10, cfvo (Conditional Format Value Object) | 275 |
| 2.1.630 | Part 4 Section 3.3.1.12, col (Column Width & Formatting) | 275 |
| 2.1.631 | Part 4 Section 3.3.1.13, colBreaks (Vertical Page Breaks) | 276 |
| 2.1.632 | Part 4 Section 3.3.1.14, color (Color) | 276 |
| 2.1.633 | Part 4 Section 3.3.1.15, colorScale (Color Scale) | 277 |
| 2.1.634 | Part 4 Section 3.3.1.17, conditionalFormatting (Conditional Formatting) | 277 |
| 2.1.635 | Part 4 Section 3.3.1.18, control (Embedded Control) | 277 |
| 2.1.636 | Part 4 Section 3.3.1.19, controls (Embedded Controls) | 277 |
| 2.1.637 | Part 4 Section 3.3.1.20, customPr (Custom Property) | 277 |
| 2.1.638 | Part 4 Section 3.3.1.22, customSheetView (Custom Chart Sheet View) | 277 |
| 2.1.639 | Part 4 Section 3.3.1.23, customSheetView (Custom Sheet View) | 277 |
| 2.1.640 | Part 4 Section 3.3.1.24, customSheetViews (Custom Chart Sheet Views) | 278 |
| 2.1.641 | Part 4 Section 3.3.1.25, customSheetViews (Custom Sheet Views) | 278 |
| 2.1.642 | Part 4 Section 3.3.1.26, dataBar (Data Bar) | 278 |
| 2.1.643 | Part 4 Section 3.3.1.30, dataValidation (Data Validation) | 278 |
| 2.1.644 | Part 4 Section 3.3.1.31, dataValidations (Data Validations) | 279 |
| 2.1.645 | Part 4 Section 3.3.1.32, dialogsSheet (Dialog Sheet) | 279 |
| 2.1.646 | Part 4 Section 3.3.1.34, drawing (Drawing) | 279 |
| 2.1.647 | Part 4 Section 3.3.1.35, evenFooter (Even Page Footer) | 280 |
| 2.1.648 | Part 4 Section 3.3.1.36, evenHeader (Even Page Header) | 280 |
| 2.1.649 | Part 4 Section 3.3.1.37, f (Formula) | 282 |
| 2.1.650 | Part 4 Section 3.3.1.38, firstFooter (First Page Footer) | 284 |
| 2.1.651 | Part 4 Section 3.3.1.39, firstHeader (First Page Header) | 284 |
| 2.1.652 | Part 4 Section 3.3.1.40, formula (Formula) | 284 |
| 2.1.653 | Part 4 Section 3.3.1.41, formula1 (Formula 1) | 285 |
| 2.1.654 | Part 4 Section 3.3.1.42, formula2 (Formula 2) | 285 |
| 2.1.655 | Part 4 Section 3.3.1.44, hyperlink (Hyperlink) | 285 |
| 2.1.656 | Part 4 Section 3.3.1.47, ignoredError (Ignored Error) | 285 |
| 2.1.657 | Part 4 Section 3.3.1.48, ignoredErrors (Ignored Errors) | 285 |
| 2.1.658 | Part 4 Section 3.3.1.49, inputCells (Input Cells) | 285 |

| | | |
|---------|---|-----|
| 2.1.659 | Part 4 Section 3.3.1.50, is (Rich Text Inline) | 286 |
| 2.1.660 | Part 4 Section 3.3.1.54, mergeCells (Merge Cells) | 286 |
| 2.1.661 | Part 4 Section 3.3.1.55, oddFooter (Odd Page Footer) | 286 |
| 2.1.662 | Part 4 Section 3.3.1.56, oddHeader (Odd Header) | 286 |
| 2.1.663 | Part 4 Section 3.3.1.57, oleObject (Embedded Object) | 287 |
| 2.1.664 | Part 4 Section 3.3.1.58, oleObjects (Embedded Objects) | 287 |
| 2.1.665 | Part 4 Section 3.3.1.60, pageMargins (Page Margins) | 287 |
| 2.1.666 | Part 4 Section 3.3.1.61, pageSetup (Page Setup Settings) | 288 |
| 2.1.667 | Part 4 Section 3.3.1.62, pageSetup (Chart Sheet Page Setup) | 292 |
| 2.1.668 | Part 4 Section 3.3.1.64, pane (View Pane) | 297 |
| 2.1.669 | Part 4 Section 3.3.1.66, pivotArea (Pivot Area) | 297 |
| 2.1.670 | Part 4 Section 3.3.1.67, pivotSelection (PivotTable Selection) | 298 |
| 2.1.671 | Part 4 Section 3.3.1.69, protectedRange (Protected Range) | 299 |
| 2.1.672 | Part 4 Section 3.3.1.71, row (Row) | 301 |
| 2.1.673 | Part 4 Section 3.3.1.72, rowBreaks (Horizontal Page Breaks (Row)) | 302 |
| 2.1.674 | Part 4 Section 3.3.1.73, scenario (Scenario) | 302 |
| 2.1.675 | Part 4 Section 3.3.1.74, scenarios (Scenarios) | 302 |
| 2.1.676 | Part 4 Section 3.3.1.75, selection (Selection) | 302 |
| 2.1.677 | Part 4 Section 3.3.1.78, sheetFormatPr (Sheet Format Properties) | 303 |
| 2.1.678 | Part 4 Section 3.3.1.79, sheetPr (Sheet Properties) | 303 |
| 2.1.679 | Part 4 Section 3.3.1.80, sheetPr (Chart Sheet Properties) | 303 |
| 2.1.680 | Part 4 Section 3.3.1.81, sheetProtection (Sheet Protection Options) | 303 |
| 2.1.681 | Part 4 Section 3.3.1.82, sheetProtection (Chart Sheet Protection) | 305 |
| 2.1.682 | Part 4 Section 3.3.1.83, sheetView (Worksheet View) | 307 |
| 2.1.683 | Part 4 Section 3.3.1.84, sheetView (Chart Sheet View) | 307 |
| 2.1.684 | Part 4 Section 3.3.1.85, sheetViews (Sheet Views) | 307 |
| 2.1.685 | Part 4 Section 3.3.1.86, sheetViews (Chart Sheet Views) | 307 |
| 2.1.686 | Part 4 Section 3.3.1.88, sortCondition (Sort Condition) | 307 |
| 2.1.687 | Part 4 Section 3.3.1.90, tabColor (Sheet Tab Color) | 307 |
| 2.1.688 | Part 4 Section 3.3.1.93, v (Cell Value) | 308 |
| 2.1.689 | Part 4 Section 3.3.1.94, webPublishItem (Web Publishing Item) | 308 |
| 2.1.690 | Part 4 Section 3.3.1.96, worksheet (Worksheet) | 309 |
| 2.1.691 | Part 4 Section 3.3.2.1, colorFilter (Color Filter Criteria) | 309 |
| 2.1.692 | Part 4 Section 3.3.2.4, dateGroupItem (Date Grouping) | 309 |
| 2.1.693 | Part 4 Section 3.3.2.5, dynamicFilter (Dynamic Filter) | 310 |
| 2.1.694 | Part 4 Section 3.3.2.6, filter (Filter) | 310 |
| 2.1.695 | Part 4 Section 3.3.2.7, filterColumn (AutoFilter Column) | 310 |
| 2.1.696 | Part 4 Section 3.3.2.8, filters (Filter Criteria) | 310 |
| 2.1.697 | Part 4 Section 3.3.2.9, iconFilter (Icon Filter) | 310 |
| 2.1.698 | Part 4 Section 3.3.2.10, top10 (Top 10) | 310 |
| 2.1.699 | Part 4 Section 3.4.3, phoneticPr (Phonetic Properties) | 311 |
| 2.1.700 | Part 4 Section 3.4.5, rFont (Font) | 311 |
| 2.1.701 | Part 4 Section 3.4.6, rPh (Phonetic Run) | 311 |
| 2.1.702 | Part 4 Section 3.4.7, rPr (Run Properties) | 311 |
| 2.1.703 | Part 4 Section 3.4.8, si (String Item) | 311 |
| 2.1.704 | Part 4 Section 3.4.9, sst (Shared String Table) | 311 |
| 2.1.705 | Part 4 Section 3.4.11, sz (Font Size) | 312 |
| 2.1.706 | Part 4 Section 3.4.12, t (Text) | 312 |
| 2.1.707 | Part 4 Section 3.5.1.1, calculatedColumnFormula (Calculated Column Formula) | 312 |
| 2.1.708 | Part 4 Section 3.5.1.2, table (Table) | 312 |
| 2.1.709 | Part 4 Section 3.5.1.3, tableColumn (Table Column) | 313 |
| 2.1.710 | Part 4 Section 3.5.1.5, tableStyleInfo (Table Style) | 314 |
| 2.1.711 | Part 4 Section 3.5.1.6, totalsRowFormula (Totals Row Formula) | 315 |

| | | |
|---------|--|-----|
| 2.1.712 | Part 4 Section 3.5.1.7, xmlColumnPr (XML Column Properties) | 315 |
| 2.1.713 | Part 4 Section 3.5.2.1, singleXmlCell (Table Properties) | 315 |
| 2.1.714 | Part 4 Section 3.5.2.3, xmlCellPr (Cell Properties) | 315 |
| 2.1.715 | Part 4 Section 3.5.2.4, xmlPr (Column XML Properties) | 316 |
| 2.1.716 | Part 4 Section 3.6.1, c (Cell) | 316 |
| 2.1.717 | Part 4 Section 3.7.1, author (Author) | 317 |
| 2.1.718 | Part 4 Section 3.7.3, comment (Comment) | 317 |
| 2.1.719 | Part 4 Section 3.7.6, text (Comment Text) | 317 |
| 2.1.720 | Part 4 Section 3.8.1, alignment (Alignment) | 317 |
| 2.1.721 | Part 4 Section 3.8.3, bgColor (Background Color) | 318 |
| 2.1.722 | Part 4 Section 3.8.4, border (Border) | 318 |
| 2.1.723 | Part 4 Section 3.8.5, borders (Borders) | 318 |
| 2.1.724 | Part 4 Section 3.8.7, cellStyle (Cell Style) | 318 |
| 2.1.725 | Part 4 Section 3.8.8, cellStyles (Cell Styles) | 319 |
| 2.1.726 | Part 4 Section 3.8.9, cellStyleXfs (Formatting Records) | 319 |
| 2.1.727 | Part 4 Section 3.8.10, cellXfs (Cell Formats) | 319 |
| 2.1.728 | Part 4 Section 3.8.15, dxfs (Formats) | 320 |
| 2.1.729 | Part 4 Section 3.8.17, family (Font Family) | 320 |
| 2.1.730 | Part 4 Section 3.8.18, fgColor (Foreground Color) | 320 |
| 2.1.731 | Part 4 Section 3.8.20, fills (Fills) | 320 |
| 2.1.732 | Part 4 Section 3.8.21, font (Font) | 320 |
| 2.1.733 | Part 4 Section 3.8.22, fonts (Fonts) | 320 |
| 2.1.734 | Part 4 Section 3.8.23, gradientFill (Gradient) | 321 |
| 2.1.735 | Part 4 Section 3.8.26, indexedColors (Color Indexes) | 321 |
| 2.1.736 | Part 4 Section 3.8.28, mruColors (MRU Colors) | 321 |
| 2.1.737 | Part 4 Section 3.8.29, name (Font Name) | 321 |
| 2.1.738 | Part 4 Section 3.8.30, numFmt (Number Format) | 321 |
| 2.1.739 | Part 4 Section 3.8.31, numFmts (Number Formats) | 332 |
| 2.1.740 | Part 4 Section 3.8.33, protection (Protection Properties) | 333 |
| 2.1.741 | Part 4 Section 3.8.38, stop (Gradient Stop) | 333 |
| 2.1.742 | Part 4 Section 3.8.39, styleSheet (Style Sheet) | 333 |
| 2.1.743 | Part 4 Section 3.8.40, tableStyle (Table Style) | 333 |
| 2.1.744 | Part 4 Section 3.8.41, tableStyleElement (Table Style) | 333 |
| 2.1.745 | Part 4 Section 3.8.42, tableStyles (Table Styles) | 333 |
| 2.1.746 | Part 4 Section 3.8.45, xf (Format) | 334 |
| 2.1.747 | Part 4 Section 3.9.1, bk (Metadata Block) | 335 |
| 2.1.748 | Part 4 Section 3.9.3, cellMetadata (Cell Metadata) | 335 |
| 2.1.749 | Part 4 Section 3.9.4, futureMetadata (Future Metadata) | 335 |
| 2.1.750 | Part 4 Section 3.9.5, k (KPI MDX Metadata) | 336 |
| 2.1.751 | Part 4 Section 3.9.6, mdx (MDX Metadata Record) | 336 |
| 2.1.752 | Part 4 Section 3.9.7, mdxMetadata (MDX Metadata Information) | 336 |
| 2.1.753 | Part 4 Section 3.9.9, metadataStrings (Metadata String Store) | 336 |
| 2.1.754 | Part 4 Section 3.9.10, metadataType (Metadata Type Information) | 336 |
| 2.1.755 | Part 4 Section 3.9.11, metadataTypes (Metadata Types Collection) | 340 |
| 2.1.756 | Part 4 Section 3.9.12, ms (Set MDX Metadata) | 340 |
| 2.1.757 | Part 4 Section 3.9.13, n (Member Unique Name Index) | 340 |
| 2.1.758 | Part 4 Section 3.9.14, p (Member Property MDX Metadata) | 340 |
| 2.1.759 | Part 4 Section 3.9.15, rc (Metadata Record) | 341 |
| 2.1.760 | Part 4 Section 3.9.16, t (Tuple MDX Metadata) | 341 |
| 2.1.761 | Part 4 Section 3.9.17, valueMetadata (Value Metadata) | 348 |
| 2.1.762 | Part 4 Section 3.10.1.1, autoSortScope (AutoSort Scope) | 348 |
| 2.1.763 | Part 4 Section 3.10.1.2, b (Boolean) | 349 |
| 2.1.764 | Part 4 Section 3.10.1.3, cacheField (PivotCache Field) | 349 |

| | | |
|---------|---|-----|
| 2.1.765 | Part 4 Section 3.10.1.4, cacheFields (PivotCache Fields) | 350 |
| 2.1.766 | Part 4 Section 3.10.1.5, cacheHierarchies (PivotCache Hierarchies)..... | 351 |
| 2.1.767 | Part 4 Section 3.10.1.6, cacheHierarchy (PivotCache Hierarchy) | 351 |
| 2.1.768 | Part 4 Section 3.10.1.7, cacheSource (PivotCache Source Description) | 353 |
| 2.1.769 | Part 4 Section 3.10.1.8, calculatedItem (Calculated Item) | 354 |
| 2.1.770 | Part 4 Section 3.10.1.10, calculatedMember (Calculated Member) | 354 |
| 2.1.771 | Part 4 Section 3.10.1.12, chartFormat (PivotChart Format)..... | 355 |
| 2.1.772 | Part 4 Section 3.10.1.15, colHierarchiesUsage (Column OLAP Hierarchy References) | 355 |
| 2.1.773 | Part 4 Section 3.10.1.16, colHierarchyUsage (Column OLAP Hierarchies) | 355 |
| 2.1.774 | Part 4 Section 3.10.1.17, colItems (Column Items)..... | 355 |
| 2.1.775 | Part 4 Section 3.10.1.18, conditionalFormat (Conditional Formatting) | 355 |
| 2.1.776 | Part 4 Section 3.10.1.20, consolidation (Consolidation Source)..... | 356 |
| 2.1.777 | Part 4 Section 3.10.1.21, d (Date Time) | 356 |
| 2.1.778 | Part 4 Section 3.10.1.22, dataField (Data Field Item) | 357 |
| 2.1.779 | Part 4 Section 3.10.1.24, dimension (OLAP Dimension) | 357 |
| 2.1.780 | Part 4 Section 3.10.1.26, discretePr (Discrete Grouping Properties) | 358 |
| 2.1.781 | Part 4 Section 3.10.1.27, e (Error Value) | 358 |
| 2.1.782 | Part 4 Section 3.10.1.29, field (Field) | 360 |
| 2.1.783 | Part 4 Section 3.10.1.30, fieldGroup (Field Group Properties) | 360 |
| 2.1.784 | Part 4 Section 3.10.1.31, fieldsUsage (Fields Usage) | 360 |
| 2.1.785 | Part 4 Section 3.10.1.32, fieldUsage (PivotCache Field Id) | 361 |
| 2.1.786 | Part 4 Section 3.10.1.33, filter (PivotTable Advanced Filter) | 361 |
| 2.1.787 | Part 4 Section 3.10.1.35, format (PivotTable Format)..... | 361 |
| 2.1.788 | Part 4 Section 3.10.1.37, group (OLAP Group) | 361 |
| 2.1.789 | Part 4 Section 3.10.1.38, groupItems (OLAP Group Items) | 362 |
| 2.1.790 | Part 4 Section 3.10.1.39, groupLevel (OLAP Grouping Levels) | 362 |
| 2.1.791 | Part 4 Section 3.10.1.41, groupMember (OLAP Group Member) | 362 |
| 2.1.792 | Part 4 Section 3.10.1.44, i (Row Items)..... | 362 |
| 2.1.793 | Part 4 Section 3.10.1.45, item (PivotTable Field Item)..... | 363 |
| 2.1.794 | Part 4 Section 3.10.1.46, items (Field Items) | 365 |
| 2.1.795 | Part 4 Section 3.10.1.47, kpi (OLAP KPI) | 366 |
| 2.1.796 | Part 4 Section 3.10.1.49, location (PivotTable Location) | 367 |
| 2.1.797 | Part 4 Section 3.10.1.50, m (No Value) | 367 |
| 2.1.798 | Part 4 Section 3.10.1.51, map (OLAP Measure Group) | 369 |
| 2.1.799 | Part 4 Section 3.10.1.53, measureGroup (OLAP Measure Group) | 369 |
| 2.1.800 | Part 4 Section 3.10.1.55, member (Member) | 369 |
| 2.1.801 | Part 4 Section 3.10.1.56, members (Members)..... | 370 |
| 2.1.802 | Part 4 Section 3.10.1.57, mp (OLAP Member Property) | 370 |
| 2.1.803 | Part 4 Section 3.10.1.58, mpMap (Member Properties Map) | 371 |
| 2.1.804 | Part 4 Section 3.10.1.60, n (Numeric) | 372 |
| 2.1.805 | Part 4 Section 3.10.1.62, pageField (Page Field)..... | 373 |
| 2.1.806 | Part 4 Section 3.10.1.63, pageFields (Page Field Items) | 374 |
| 2.1.807 | Part 4 Section 3.10.1.64, pageItem (Page Item)..... | 374 |
| 2.1.808 | Part 4 Section 3.10.1.67, pivotCacheDefinition (PivotCache Definition) | 374 |
| 2.1.809 | Part 4 Section 3.10.1.68, pivotCacheRecords (PivotCache Records) | 376 |
| 2.1.810 | Part 4 Section 3.10.1.69, pivotField (PivotTable Field) | 376 |
| 2.1.811 | Part 4 Section 3.10.1.70, pivotFields (PivotTable Fields) | 384 |
| 2.1.812 | Part 4 Section 3.10.1.71, pivotHierarchies (PivotTable OLAP Hierarchies)..... | 384 |
| 2.1.813 | Part 4 Section 3.10.1.72, pivotHierarchy (OLAP Hierarchy) | 385 |
| 2.1.814 | Part 4 Section 3.10.1.73, pivotTableDefinition (PivotTable Definition) | 386 |
| 2.1.815 | Part 4 Section 3.10.1.74, pivotTableStyleInfo (PivotTable Style)..... | 393 |
| 2.1.816 | Part 4 Section 3.10.1.75, query (Query) | 394 |

| | | |
|---------|---|-----|
| 2.1.817 | Part 4 Section 3.10.1.77, r (PivotCache Record) | 394 |
| 2.1.818 | Part 4 Section 3.10.1.78, rangePr (Range Grouping Properties) | 394 |
| 2.1.819 | Part 4 Section 3.10.1.79, rangeSet (Range Set) | 396 |
| 2.1.820 | Part 4 Section 3.10.1.83, rowHierarchyUsage (Row OLAP Hierarchies) | 397 |
| 2.1.821 | Part 4 Section 3.10.1.85, s (Character Value)..... | 397 |
| 2.1.822 | Part 4 Section 3.10.1.86, serverFormat (Server Format) | 398 |
| 2.1.823 | Part 4 Section 3.10.1.88, set (OLAP Set) | 406 |
| 2.1.824 | Part 4 Section 3.10.1.90, sharedItems (Shared Items)..... | 406 |
| 2.1.825 | Part 4 Section 3.10.1.91, sortByTuple (Sort By Tuple)..... | 408 |
| 2.1.826 | Part 4 Section 3.10.1.92, tpl (Tuple) | 409 |
| 2.1.827 | Part 4 Section 3.10.1.95, worksheetSource (Worksheet PivotCache Source)..... | 409 |
| 2.1.828 | Part 4 Section 3.10.1.96, x (Member Property Index)..... | 409 |
| 2.1.829 | Part 4 Section 3.10.1.97, x (Shared Items Index)..... | 410 |
| 2.1.830 | Part 4 Section 3.10.2.1, reference (Reference) | 410 |
| 2.1.831 | Part 4 Section 3.11.1.1, header (Header) | 412 |
| 2.1.832 | Part 4 Section 3.11.1.2, headers (Revision Headers) | 412 |
| 2.1.833 | Part 4 Section 3.11.1.3, nc (New Cell Data) | 413 |
| 2.1.834 | Part 4 Section 3.11.1.5, oc (Old Cell Data)..... | 414 |
| 2.1.835 | Part 4 Section 3.11.1.7, oldFormula (Old Formula)..... | 414 |
| 2.1.836 | Part 4 Section 3.11.1.8, raf (Revision AutoFormat) | 414 |
| 2.1.837 | Part 4 Section 3.11.1.9, rcc (Revision Cell Change)..... | 414 |
| 2.1.838 | Part 4 Section 3.11.1.10, rcft (Revision Merge Conflict) | 414 |
| 2.1.839 | Part 4 Section 3.11.1.11, rcmt (Revision Cell Comment)..... | 415 |
| 2.1.840 | Part 4 Section 3.11.1.13, rdn (Revision Defined Name) | 415 |
| 2.1.841 | Part 4 Section 3.11.1.14, reviewed (Reviewed) | 416 |
| 2.1.842 | Part 4 Section 3.11.1.17, rfmt (Revision Format)..... | 416 |
| 2.1.843 | Part 4 Section 3.11.1.18, ris (Revision Insert Sheet) | 416 |
| 2.1.844 | Part 4 Section 3.11.1.19, rm (Revision Cell Move) | 417 |
| 2.1.845 | Part 4 Section 3.11.1.20, rqt (Revision Query Table)..... | 417 |
| 2.1.846 | Part 4 Section 3.11.1.21, rrc (Revision Row Column Insert Delete) | 417 |
| 2.1.847 | Part 4 Section 3.11.1.22, rsnm (Revision Sheet Name) | 417 |
| 2.1.848 | Part 4 Section 3.11.1.23, sheetId (Sheet Id) | 418 |
| 2.1.849 | Part 4 Section 3.11.1.24, sheetIdMap (Sheet Id Map) | 418 |
| 2.1.850 | Part 4 Section 3.11.1.25, undo (Undo) | 418 |
| 2.1.851 | Part 4 Section 3.11.2.2, users (User List) | 419 |
| 2.1.852 | Part 4 Section 3.12.1, deletedField (Deleted Field)..... | 419 |
| 2.1.853 | Part 4 Section 3.12.2, queryTable (Query Table) | 419 |
| 2.1.854 | Part 4 Section 3.12.4, queryTableField (QueryTable Field) | 419 |
| 2.1.855 | Part 4 Section 3.12.6, queryTableRefresh (QueryTable Refresh Information) | 420 |
| 2.1.856 | Part 4 Section 3.13.1, connection (Connection) | 420 |
| 2.1.857 | Part 4 Section 3.13.3, dbPr (Database Properties) | 422 |
| 2.1.858 | Part 4 Section 3.13.5, olapPr (OLAP Properties)..... | 422 |
| 2.1.859 | Part 4 Section 3.13.6, parameter (Parameter Properties)..... | 422 |
| 2.1.860 | Part 4 Section 3.13.8, s (Character Value) | 422 |
| 2.1.861 | Part 4 Section 3.13.10, textField (Text Import Field Settings)..... | 423 |
| 2.1.862 | Part 4 Section 3.13.11, textFields (Fields)..... | 423 |
| 2.1.863 | Part 4 Section 3.13.12, textPr (Text Import Settings)..... | 423 |
| 2.1.864 | Part 4 Section 3.13.13, webPr (Web Query Properties) | 424 |
| 2.1.865 | Part 4 Section 3.14.1, cell (External Cell Data) | 424 |
| 2.1.866 | Part 4 Section 3.14.2, ddeItem (DDE Item definition)..... | 424 |
| 2.1.867 | Part 4 Section 3.14.4, ddeLink (DDE Connection) | 425 |
| 2.1.868 | Part 4 Section 3.14.5, definedName (Defined Name)..... | 425 |
| 2.1.869 | Part 4 Section 3.14.8, externalLink (External Reference) | 425 |

| | | |
|---------|--|-----|
| 2.1.870 | Part 4 Section 3.14.9, oleItem (OLE Link Item) | 425 |
| 2.1.871 | Part 4 Section 3.14.11, oleLink (OLE Link) | 426 |
| 2.1.872 | Part 4 Section 3.14.12, row (Row) | 426 |
| 2.1.873 | Part 4 Section 3.14.13, sheetData (External Sheet Data Set) | 426 |
| 2.1.874 | Part 4 Section 3.14.15, sheetName (Sheet Name) | 426 |
| 2.1.875 | Part 4 Section 3.14.16, sheetNames (Supporting Workbook Sheet Names) | 426 |
| 2.1.876 | Part 4 Section 3.14.17, val (DDE Link Value) | 426 |
| 2.1.877 | Part 4 Section 3.14.18, value (Value) | 427 |
| 2.1.878 | Part 4 Section 3.14.19, values (DDE Name Values) | 427 |
| 2.1.879 | Part 4 Section 3.15.1, main (Main) | 427 |
| 2.1.880 | Part 4 Section 3.15.2, stp (Strings in Subtopic) | 427 |
| 2.1.881 | Part 4 Section 3.15.3, tp (Topic) | 427 |
| 2.1.882 | Part 4 Section 3.15.4, tr (References) | 428 |
| 2.1.883 | Part 4 Section 3.16.1, DataBinding (XML Mapping) | 428 |
| 2.1.884 | Part 4 Section 3.16.2, Map (XML Mapping Properties) | 428 |
| 2.1.885 | Part 4 Section 3.16.4, Schema (XML Schema) | 429 |
| 2.1.886 | Part 4 Section 3.17, Formulas | 429 |
| 2.1.887 | Part 4 Section 3.17.2, Syntax | 430 |
| 2.1.888 | Part 4 Section 3.17.2.1, Constants | 437 |
| 2.1.889 | Part 4 Section 3.17.2.2, Operators | 439 |
| 2.1.890 | Part 4 Section 3.17.2.3, Cell References | 439 |
| 2.1.891 | Part 4 Section 3.17.2.3.1, A1-Style Cell References | 440 |
| 2.1.892 | Part 4 Section 3.17.2.3.2, R1C1-Style Cell Reference | 441 |
| 2.1.893 | Part 4 Section 3.17.2.4, Functions | 442 |
| 2.1.894 | Part 4 Section 3.17.2.5, Names | 442 |
| 2.1.895 | Part 4 Section 3.17.2.6, Types and Values | 443 |
| 2.1.896 | Part 4 Section 3.17.3, Error values | 443 |
| 2.1.897 | Part 4 Section 3.17.4.1, Date Representation | 443 |
| 2.1.898 | Part 4 Section 3.17.5.2, Precision | 443 |
| 2.1.899 | Part 4 Section 3.17.5.4, Interpretation | 444 |
| 2.1.900 | Part 4 Section 3.17.6.3, Array Formulas | 444 |
| 2.1.901 | Part 4 Section 3.17.6.5, Name Representation | 444 |
| 2.1.902 | Part 4 Section 3.17.7.2, ACCRINT | 444 |
| 2.1.903 | Part 4 Section 3.17.7.3, ACCRINTM | 445 |
| 2.1.904 | Part 4 Section 3.17.7.4, ACOS | 446 |
| 2.1.905 | Part 4 Section 3.17.7.6, ADDRESS | 446 |
| 2.1.906 | Part 4 Section 3.17.7.7, AMORDEGRC | 446 |
| 2.1.907 | Part 4 Section 3.17.7.8, AMORLINC | 447 |
| 2.1.908 | Part 4 Section 3.17.7.10, AREAS | 447 |
| 2.1.909 | Part 4 Section 3.17.7.12, ASIN | 447 |
| 2.1.910 | Part 4 Section 3.17.7.13, ASINH | 447 |
| 2.1.911 | Part 4 Section 3.17.7.14, ATAN | 448 |
| 2.1.912 | Part 4 Section 3.17.7.15, ATAN2 | 448 |
| 2.1.913 | Part 4 Section 3.17.7.17, AVEDEV | 448 |
| 2.1.914 | Part 4 Section 3.17.7.19, AVERAGEA | 448 |
| 2.1.915 | Part 4 Section 3.17.7.20, AVERAGEIF | 448 |
| 2.1.916 | Part 4 Section 3.17.7.21, AVERAGEIFS | 449 |
| 2.1.917 | Part 4 Section 3.17.7.23, BESSELI | 449 |
| 2.1.918 | Part 4 Section 3.17.7.24, BESSELJ | 449 |
| 2.1.919 | Part 4 Section 3.17.7.25, BESSELK | 449 |
| 2.1.920 | Part 4 Section 3.17.7.26, BESSELY | 449 |
| 2.1.921 | Part 4 Section 3.17.7.28, BETAINV | 449 |
| 2.1.922 | Part 4 Section 3.17.7.29, BIN2DEC | 450 |

| | | |
|---------|---|-----|
| 2.1.923 | Part 4 Section 3.17.7.34, CELL | 450 |
| 2.1.924 | Part 4 Section 3.17.7.37, CHIINV | 455 |
| 2.1.925 | Part 4 Section 3.17.7.40, CLEAN | 455 |
| 2.1.926 | Part 4 Section 3.17.7.45, COMPLEX | 455 |
| 2.1.927 | Part 4 Section 3.17.7.47, CONFIDENCE | 455 |
| 2.1.928 | Part 4 Section 3.17.7.48, CONVERT | 455 |
| 2.1.929 | Part 4 Section 3.17.7.49, CORREL | 456 |
| 2.1.930 | Part 4 Section 3.17.7.50, COS | 456 |
| 2.1.931 | Part 4 Section 3.17.7.52, COUNT | 456 |
| 2.1.932 | Part 4 Section 3.17.7.53, COUNTA | 456 |
| 2.1.933 | Part 4 Section 3.17.7.56, COUNTIFS | 456 |
| 2.1.934 | Part 4 Section 3.17.7.57, COUPDAYBS | 456 |
| 2.1.935 | Part 4 Section 3.17.7.58, COUPDAYS | 457 |
| 2.1.936 | Part 4 Section 3.17.7.59, COUPDAYSNC | 458 |
| 2.1.937 | Part 4 Section 3.17.7.60, COUPNCD | 458 |
| 2.1.938 | Part 4 Section 3.17.7.61, COUPNUM | 459 |
| 2.1.939 | Part 4 Section 3.17.7.62, COUPPCD | 460 |
| 2.1.940 | Part 4 Section 3.17.7.64, CRITBINOM | 460 |
| 2.1.941 | Part 4 Section 3.17.7.65, CUBEKPIMEMBER | 460 |
| 2.1.942 | Part 4 Section 3.17.7.69, CUBESET | 461 |
| 2.1.943 | Part 4 Section 3.17.7.70, CUBESETCOUNT | 461 |
| 2.1.944 | Part 4 Section 3.17.7.72, CUMIPMT | 461 |
| 2.1.945 | Part 4 Section 3.17.7.73, CUMPRINC | 461 |
| 2.1.946 | Part 4 Section 3.17.7.74, DATE | 461 |
| 2.1.947 | Part 4 Section 3.17.7.76, DATEVALUE | 462 |
| 2.1.948 | Part 4 Section 3.17.7.77, DAVERAGE | 462 |
| 2.1.949 | Part 4 Section 3.17.7.78, DAY | 462 |
| 2.1.950 | Part 4 Section 3.17.7.79, DAYS360 | 462 |
| 2.1.951 | Part 4 Section 3.17.7.80, DB | 463 |
| 2.1.952 | Part 4 Section 3.17.7.81, DCOUNT | 463 |
| 2.1.953 | Part 4 Section 3.17.7.82, DCOUNTA | 463 |
| 2.1.954 | Part 4 Section 3.17.7.83, DDB | 463 |
| 2.1.955 | Part 4 Section 3.17.7.84, DEC2BIN | 463 |
| 2.1.956 | Part 4 Section 3.17.7.85, DEC2HEX | 463 |
| 2.1.957 | Part 4 Section 3.17.7.86, DEC2OCT | 463 |
| 2.1.958 | Part 4 Section 3.17.7.89, DEVSQ | 464 |
| 2.1.959 | Part 4 Section 3.17.7.90, DGET | 464 |
| 2.1.960 | Part 4 Section 3.17.7.91, DISC | 464 |
| 2.1.961 | Part 4 Section 3.17.7.92, DMAX | 465 |
| 2.1.962 | Part 4 Section 3.17.7.93, DMIN | 465 |
| 2.1.963 | Part 4 Section 3.17.7.94, DOLLAR | 465 |
| 2.1.964 | Part 4 Section 3.17.7.95, DOLLARDE | 465 |
| 2.1.965 | Part 4 Section 3.17.7.96, DOLLARFR | 465 |
| 2.1.966 | Part 4 Section 3.17.7.97, DPRODUCT | 466 |
| 2.1.967 | Part 4 Section 3.17.7.98, DSTDEV | 466 |
| 2.1.968 | Part 4 Section 3.17.7.99, DSTDEVP | 466 |
| 2.1.969 | Part 4 Section 3.17.7.100, DSUM | 466 |
| 2.1.970 | Part 4 Section 3.17.7.101, DURATION | 466 |
| 2.1.971 | Part 4 Section 3.17.7.102, DVAR | 467 |
| 2.1.972 | Part 4 Section 3.17.7.103, DVARP | 467 |
| 2.1.973 | Part 4 Section 3.17.7.104, EDATE | 467 |
| 2.1.974 | Part 4 Section 3.17.7.107, ERF | 467 |
| 2.1.975 | Part 4 Section 3.17.7.108, ERF | 467 |

| | | |
|----------|---|-----|
| 2.1.976 | Part 4 Section 3.17.7.109, ERROR.TYPE | 467 |
| 2.1.977 | Part 4 Section 3.17.7.118, FIND | 467 |
| 2.1.978 | Part 4 Section 3.17.7.119, FINDB | 468 |
| 2.1.979 | Part 4 Section 3.17.7.120, FINV | 468 |
| 2.1.980 | Part 4 Section 3.17.7.123, FIXED | 468 |
| 2.1.981 | Part 4 Section 3.17.7.124, FLOOR | 468 |
| 2.1.982 | Part 4 Section 3.17.7.125, FORECAST | 469 |
| 2.1.983 | Part 4 Section 3.17.7.128, FV | 469 |
| 2.1.984 | Part 4 Section 3.17.7.131, GAMMAINV | 469 |
| 2.1.985 | Part 4 Section 3.17.7.134, GEOMEAN | 469 |
| 2.1.986 | Part 4 Section 3.17.7.136, GETPIVOTDATA | 469 |
| 2.1.987 | Part 4 Section 3.17.7.138, HARMEAN | 469 |
| 2.1.988 | Part 4 Section 3.17.7.142, HLOOKUP | 470 |
| 2.1.989 | Part 4 Section 3.17.7.143, HOUR | 470 |
| 2.1.990 | Part 4 Section 3.17.7.146, IF | 470 |
| 2.1.991 | Part 4 Section 3.17.7.147, IFERROR | 470 |
| 2.1.992 | Part 4 Section 3.17.7.150, IMARGUMENT | 470 |
| 2.1.993 | Part 4 Section 3.17.7.153, IMDIV | 470 |
| 2.1.994 | Part 4 Section 3.17.7.155, IMLN | 470 |
| 2.1.995 | Part 4 Section 3.17.7.156, IMLOG10 | 471 |
| 2.1.996 | Part 4 Section 3.17.7.157, IMLOG2 | 471 |
| 2.1.997 | Part 4 Section 3.17.7.158, IMPOWER | 471 |
| 2.1.998 | Part 4 Section 3.17.7.161, IMSIN | 471 |
| 2.1.999 | Part 4 Section 3.17.7.162, IMSQRT | 471 |
| 2.1.1000 | Part 4 Section 3.17.7.165, INDEX | 471 |
| 2.1.1001 | Part 4 Section 3.17.7.166, INDIRECT | 472 |
| 2.1.1002 | Part 4 Section 3.17.7.167, INFO | 472 |
| 2.1.1003 | Part 4 Section 3.17.7.169, INTERCEPT | 472 |
| 2.1.1004 | Part 4 Section 3.17.7.170, INTRATE | 472 |
| 2.1.1005 | Part 4 Section 3.17.7.171, IPMT | 473 |
| 2.1.1006 | Part 4 Section 3.17.7.172, IRR | 474 |
| 2.1.1007 | Part 4 Section 3.17.7.182, ISPMT | 474 |
| 2.1.1008 | Part 4 Section 3.17.7.189, LEFT | 474 |
| 2.1.1009 | Part 4 Section 3.17.7.190, LEFTB | 474 |
| 2.1.1010 | Part 4 Section 3.17.7.191, LEN | 474 |
| 2.1.1011 | Part 4 Section 3.17.7.192, LENB | 475 |
| 2.1.1012 | Part 4 Section 3.17.7.193, LINEST | 475 |
| 2.1.1013 | Part 4 Section 3.17.7.195, LOG | 475 |
| 2.1.1014 | Part 4 Section 3.17.7.197, LOGEST | 476 |
| 2.1.1015 | Part 4 Section 3.17.7.198, LOGINV | 476 |
| 2.1.1016 | Part 4 Section 3.17.7.199, LOGNORMDIST | 476 |
| 2.1.1017 | Part 4 Section 3.17.7.202, MATCH | 476 |
| 2.1.1018 | Part 4 Section 3.17.7.206, MDURATION | 476 |
| 2.1.1019 | Part 4 Section 3.17.7.208, MID | 477 |
| 2.1.1020 | Part 4 Section 3.17.7.209, MIDB | 477 |
| 2.1.1021 | Part 4 Section 3.17.7.210, MIN | 478 |
| 2.1.1022 | Part 4 Section 3.17.7.211, MINA | 478 |
| 2.1.1023 | Part 4 Section 3.17.7.213, MINVERSE | 478 |
| 2.1.1024 | Part 4 Section 3.17.7.220, MULTINOMIAL | 479 |
| 2.1.1025 | Part 4 Section 3.17.7.221, N | 479 |
| 2.1.1026 | Part 4 Section 3.17.7.223, NEGBINOMDIST | 479 |
| 2.1.1027 | Part 4 Section 3.17.7.224, NETWORKDAYS | 479 |
| 2.1.1028 | Part 4 Section 3.17.7.227, NORMINV | 479 |

| | | |
|----------|--|-----|
| 2.1.1029 | Part 4 Section 3.17.7.228, NORMSDIST | 479 |
| 2.1.1030 | Part 4 Section 3.17.7.229, NORMSINV | 480 |
| 2.1.1031 | Part 4 Section 3.17.7.232, NPER | 480 |
| 2.1.1032 | Part 4 Section 3.17.7.233, NPV | 480 |
| 2.1.1033 | Part 4 Section 3.17.7.234, OCT2BIN | 480 |
| 2.1.1034 | Part 4 Section 3.17.7.235, OCT2DEC | 481 |
| 2.1.1035 | Part 4 Section 3.17.7.238, ODDFPRICE | 481 |
| 2.1.1036 | Part 4 Section 3.17.7.239, ODDFYIELD | 481 |
| 2.1.1037 | Part 4 Section 3.17.7.240, ODDLPRICE | 482 |
| 2.1.1038 | Part 4 Section 3.17.7.241, ODDLYIELD | 483 |
| 2.1.1039 | Part 4 Section 3.17.7.242, OFFSET | 484 |
| 2.1.1040 | Part 4 Section 3.17.7.244, PEARSON | 484 |
| 2.1.1041 | Part 4 Section 3.17.7.245, PERCENTILE | 484 |
| 2.1.1042 | Part 4 Section 3.17.7.246, PERCENTRANK | 484 |
| 2.1.1043 | Part 4 Section 3.17.7.250, PMT | 484 |
| 2.1.1044 | Part 4 Section 3.17.7.251, POISSON | 484 |
| 2.1.1045 | Part 4 Section 3.17.7.252, POWER | 485 |
| 2.1.1046 | Part 4 Section 3.17.7.253, PPMT | 485 |
| 2.1.1047 | Part 4 Section 3.17.7.254, PRICE | 485 |
| 2.1.1048 | Part 4 Section 3.17.7.255, PRICEDISC | 486 |
| 2.1.1049 | Part 4 Section 3.17.7.256, PRICEMAT | 486 |
| 2.1.1050 | Part 4 Section 3.17.7.257, PROB | 487 |
| 2.1.1051 | Part 4 Section 3.17.7.258, PRODUCT | 487 |
| 2.1.1052 | Part 4 Section 3.17.7.260, PV | 487 |
| 2.1.1053 | Part 4 Section 3.17.7.266, RANK | 487 |
| 2.1.1054 | Part 4 Section 3.17.7.267, RATE | 488 |
| 2.1.1055 | Part 4 Section 3.17.7.268, RECEIVED | 488 |
| 2.1.1056 | Part 4 Section 3.17.7.269, REPLACE | 488 |
| 2.1.1057 | Part 4 Section 3.17.7.270, REPLACEB | 489 |
| 2.1.1058 | Part 4 Section 3.17.7.272, RIGHT | 489 |
| 2.1.1059 | Part 4 Section 3.17.7.273, RIGHTB | 489 |
| 2.1.1060 | Part 4 Section 3.17.7.274, ROMAN | 490 |
| 2.1.1061 | Part 4 Section 3.17.7.275, ROUND | 490 |
| 2.1.1062 | Part 4 Section 3.17.7.279, ROWS | 490 |
| 2.1.1063 | Part 4 Section 3.17.7.280, RSQ | 490 |
| 2.1.1064 | Part 4 Section 3.17.7.281, RTD | 490 |
| 2.1.1065 | Part 4 Section 3.17.7.282, SEARCH | 491 |
| 2.1.1066 | Part 4 Section 3.17.7.283, SEARCHB | 491 |
| 2.1.1067 | Part 4 Section 3.17.7.285, SERIESSUM | 491 |
| 2.1.1068 | Part 4 Section 3.17.7.287, SIN | 491 |
| 2.1.1069 | Part 4 Section 3.17.7.291, SLOPE | 491 |
| 2.1.1070 | Part 4 Section 3.17.7.296, STDEV | 491 |
| 2.1.1071 | Part 4 Section 3.17.7.297, STDEVA | 492 |
| 2.1.1072 | Part 4 Section 3.17.7.298, STDEVP | 492 |
| 2.1.1073 | Part 4 Section 3.17.7.299, STDEVPA | 492 |
| 2.1.1074 | Part 4 Section 3.17.7.301, SUBSTITUTE | 492 |
| 2.1.1075 | Part 4 Section 3.17.7.303, SUM | 492 |
| 2.1.1076 | Part 4 Section 3.17.7.305, SUMIFS | 492 |
| 2.1.1077 | Part 4 Section 3.17.7.306, SUMPRODUCT | 493 |
| 2.1.1078 | Part 4 Section 3.17.7.307, SUMSQ | 493 |
| 2.1.1079 | Part 4 Section 3.17.7.313, TAN | 493 |
| 2.1.1080 | Part 4 Section 3.17.7.316, TBILLPRICE | 493 |
| 2.1.1081 | Part 4 Section 3.17.7.317, TBILLYIELD | 493 |

| | | |
|----------|--|-----|
| 2.1.1082 | Part 4 Section 3.17.7.320, TIME | 493 |
| 2.1.1083 | Part 4 Section 3.17.7.321, TIMEVALUE | 494 |
| 2.1.1084 | Part 4 Section 3.17.7.327, TRIMMEAN | 494 |
| 2.1.1085 | Part 4 Section 3.17.7.329, TRUNC..... | 494 |
| 2.1.1086 | Part 4 Section 3.17.7.330, TTEST | 494 |
| 2.1.1087 | Part 4 Section 3.17.7.331, TYPE | 494 |
| 2.1.1088 | Part 4 Section 3.17.7.333, USDOLLAR | 494 |
| 2.1.1089 | Part 4 Section 3.17.7.334, VALUE | 494 |
| 2.1.1090 | Part 4 Section 3.17.7.335, VAR..... | 494 |
| 2.1.1091 | Part 4 Section 3.17.7.336, VARA..... | 495 |
| 2.1.1092 | Part 4 Section 3.17.7.337, VARP | 495 |
| 2.1.1093 | Part 4 Section 3.17.7.338, VARPA | 495 |
| 2.1.1094 | Part 4 Section 3.17.7.339, VDB | 495 |
| 2.1.1095 | Part 4 Section 3.17.7.340, VLOOKUP | 496 |
| 2.1.1096 | Part 4 Section 3.17.7.343, WEIBULL..... | 496 |
| 2.1.1097 | Part 4 Section 3.17.7.344, WORKDAY..... | 496 |
| 2.1.1098 | Part 4 Section 3.17.7.345, XIRR | 496 |
| 2.1.1099 | Part 4 Section 3.17.7.346, XNPV..... | 496 |
| 2.1.1100 | Part 4 Section 3.17.7.348, YEARFRAC..... | 497 |
| 2.1.1101 | Part 4 Section 3.17.7.349, YIELD | 497 |
| 2.1.1102 | Part 4 Section 3.17.7.350, YIELDDISC..... | 498 |
| 2.1.1103 | Part 4 Section 3.17.7.351, YIELDMAT | 499 |
| 2.1.1104 | Part 4 Section 3.17.7.352, ZTEST | 500 |
| 2.1.1105 | Part 4 Section 3.18.2, ST_BorderId (Border Id) | 500 |
| 2.1.1106 | Part 4 Section 3.18.7, ST_CellFormulaType (Formula Type) | 500 |
| 2.1.1107 | Part 4 Section 3.18.8, ST_CellRef (Cell Reference) | 500 |
| 2.1.1108 | Part 4 Section 3.18.9, ST_CellSpan (Cell Span Type)..... | 501 |
| 2.1.1109 | Part 4 Section 3.18.17, ST_CredMethod (Credentials Method) | 501 |
| 2.1.1110 | Part 4 Section 3.18.26, ST_DxfId (Format Id) | 501 |
| 2.1.1111 | Part 4 Section 3.18.30, ST_FileType (File Type)..... | 502 |
| 2.1.1112 | Part 4 Section 3.18.31, ST_FillId (Fill Id) | 502 |
| 2.1.1113 | Part 4 Section 3.18.36, ST_Formula (Formula) | 502 |
| 2.1.1114 | Part 4 Section 3.18.44, ST_IconSetType (Icon Set Type) | 502 |
| 2.1.1115 | Part 4 Section 3.18.49, ST_NumFmtId (Number Format Id) | 502 |
| 2.1.1116 | Part 4 Section 3.18.59, ST_PhoneticType (Phonetic Type)..... | 502 |
| 2.1.1117 | Part 4 Section 3.18.61, ST_PivotFilterType (Pivot Filter Types) | 502 |
| 2.1.1118 | Part 4 Section 3.18.64, ST_Ref (Cell Range Reference)..... | 503 |
| 2.1.1119 | Part 4 Section 3.18.65, ST_RefA (Absolute Cell Reference) | 503 |
| 2.1.1120 | Part 4 Section 3.18.78, ST_Sqref (Reference Sequence) | 503 |
| 2.1.1121 | Part 4 Section 3.18.79, ST_TableStyleType (Table Style Type) | 503 |
| 2.1.1122 | Part 4 Section 3.18.83, ST_TotalsRowFunction (Totals Row Function Types).... | 504 |
| 2.1.1123 | Part 4 Section 3.18.88, ST_UpdateLinks (Update Links Behavior Types) | 504 |
| 2.1.1124 | Part 4 Section 3.18.91, ST_Visibility (Visibility Types)..... | 504 |
| 2.1.1125 | Part 4 Section 3.18.94, ST_WebSourceType (Web Source Type) | 505 |
| 2.1.1126 | Part 4 Section 3.18.96, ST_Xstring (Escaped String) | 505 |
| 2.1.1127 | Part 4 Section 4.2.1, custData (Customer Data)..... | 505 |
| 2.1.1128 | Part 4 Section 4.2.2, custShow (Custom Show) | 505 |
| 2.1.1129 | Part 4 Section 4.2.3, ext (Extension) | 505 |
| 2.1.1130 | Part 4 Section 4.2.8, sldRg (Slide Range)..... | 505 |
| 2.1.1131 | Part 4 Section 4.3.1.4, clrMru (Color MRU) | 506 |
| 2.1.1132 | Part 4 Section 4.3.1.5, custShow (Custom Show)..... | 506 |
| 2.1.1133 | Part 4 Section 4.3.1.9, embeddedFontLst (Embedded Font List)..... | 506 |
| 2.1.1134 | Part 4 Section 4.3.1.10, font (Embedded Font Name) | 506 |

| | | |
|----------|---|-----|
| 2.1.1135 | Part 4 Section 4.3.1.13, htmlPubPr (HTML Publishing Properties) | 506 |
| 2.1.1136 | Part 4 Section 4.3.1.15, kinsoku (Kinsoku Settings) | 507 |
| 2.1.1137 | Part 4 Section 4.3.1.17, modifyVerifier (Modification Verifier) | 507 |
| 2.1.1138 | Part 4 Section 4.3.1.20, notesSz (Notes Slide Size) | 510 |
| 2.1.1139 | Part 4 Section 4.3.1.22, photoAlbum (Photo Album Information) | 510 |
| 2.1.1140 | Part 4 Section 4.3.1.23, present (Presenter Slide Show Mode) | 511 |
| 2.1.1141 | Part 4 Section 4.3.1.24, presentation (Presentation) | 511 |
| 2.1.1142 | Part 4 Section 4.3.1.34, sldSz (Presentation Slide Size) | 511 |
| 2.1.1143 | Part 4 Section 4.3.1.35, smartTags (Smart Tags)..... | 512 |
| 2.1.1144 | Part 4 Section 4.3.2.3, gridSpacing (Grid Spacing) | 512 |
| 2.1.1145 | Part 4 Section 4.3.2.4, guide (A Guide)..... | 512 |
| 2.1.1146 | Part 4 Section 4.3.2.5, guideLst (List of Guides) | 512 |
| 2.1.1147 | Part 4 Section 4.3.2.6, normalViewPr (Normal View Properties) | 512 |
| 2.1.1148 | Part 4 Section 4.3.2.9, origin (View Origin) | 513 |
| 2.1.1149 | Part 4 Section 4.3.2.11, restoredLeft (Normal View Restored Left Properties) .. | 513 |
| 2.1.1150 | Part 4 Section 4.3.2.12, restoredTop (Normal View Restored Top Properties) .. | 513 |
| 2.1.1151 | Part 4 Section 4.3.2.13, scale (View Scale) | 513 |
| 2.1.1152 | Part 4 Section 4.4.1.1, bg (Slide Background) | 514 |
| 2.1.1153 | Part 4 Section 4.4.1.2, bgPr (Background Properties) | 514 |
| 2.1.1154 | Part 4 Section 4.4.1.4, blipFill (Picture Fill) | 514 |
| 2.1.1155 | Part 4 Section 4.4.1.15, cSld (Common Slide Data)..... | 514 |
| 2.1.1156 | Part 4 Section 4.4.1.20, grpSpPr (Group Shape Properties) | 514 |
| 2.1.1157 | Part 4 Section 4.4.1.24, notesMaster (Notes Master) | 514 |
| 2.1.1158 | Part 4 Section 4.4.1.25, notesStyle (Notes Text Style)..... | 514 |
| 2.1.1159 | Part 4 Section 4.4.1.30, nvPr (Non-Visual Properties)..... | 514 |
| 2.1.1160 | Part 4 Section 4.4.1.33, ph (Placeholder Shape) | 515 |
| 2.1.1161 | Part 4 Section 4.4.1.35, sld (Presentation Slide) | 515 |
| 2.1.1162 | Part 4 Section 4.4.1.41, spPr (Shape Properties)..... | 515 |
| 2.1.1163 | Part 4 Section 4.4.1.46, transition (Slide Transition for a Slide Layout) | 515 |
| 2.1.1164 | Part 4 Section 4.4.1.49, xfrm (2D Transform for Graphic Frame) | 516 |
| 2.1.1165 | Part 4 Section 4.4.2.1, control (Embedded Control)..... | 516 |
| 2.1.1166 | Part 4 Section 4.4.2.2, embed (Embedded Object or Control) | 516 |
| 2.1.1167 | Part 4 Section 4.4.2.3, link (Linked Object or Control) | 516 |
| 2.1.1168 | Part 4 Section 4.4.2.4, oleObj (Global Element for Embedded objects and Controls)..... | 516 |
| 2.1.1169 | Part 4 Section 4.4.3.1, tag (Programmable Extensibility Tag) | 517 |
| 2.1.1170 | Part 4 Section 4.5.1, cm (Comment) | 518 |
| 2.1.1171 | Part 4 Section 4.5.5, pos (Comment Position)..... | 518 |
| 2.1.1172 | Part 4 Section 4.6.1, anim (Animate) | 518 |
| 2.1.1173 | Part 4 Section 4.6.2, animClr (Animate Color Behavior) | 519 |
| 2.1.1174 | Part 4 Section 4.6.3, animEffect (Animate Effect)..... | 520 |
| 2.1.1175 | Part 4 Section 4.6.4, animMotion (Animate Motion) | 524 |
| 2.1.1176 | Part 4 Section 4.6.5, animRot (Animate Rotation) | 526 |
| 2.1.1177 | Part 4 Section 4.6.6, animScale (Animate Scale)..... | 527 |
| 2.1.1178 | Part 4 Section 4.6.7, attrName (Attribute Name) | 528 |
| 2.1.1179 | Part 4 Section 4.6.9, audio (Audio) | 528 |
| 2.1.1180 | Part 4 Section 4.6.12, bldDgm (Build Diagram)..... | 528 |
| 2.1.1181 | Part 4 Section 4.6.13, bldGraphic (Build Graphics) | 529 |
| 2.1.1182 | Part 4 Section 4.6.15, bldOleChart (Build Embedded Chart) | 529 |
| 2.1.1183 | Part 4 Section 4.6.16, bldP (Build Paragraph) | 529 |
| 2.1.1184 | Part 4 Section 4.6.17, bldSub (Build Sub Elements) | 530 |
| 2.1.1185 | Part 4 Section 4.6.20, by (By) | 530 |
| 2.1.1186 | Part 4 Section 4.6.22, cBhvr (Common Behavior) | 531 |

| | | |
|----------|--|-----|
| 2.1.1187 | Part 4 Section 4.6.23, charRg (Character Range) | 532 |
| 2.1.1188 | Part 4 Section 4.6.28, cmd (Command) | 532 |
| 2.1.1189 | Part 4 Section 4.6.29, cMediaNode (Common Media Node Properties)..... | 534 |
| 2.1.1190 | Part 4 Section 4.6.31, cond (Condition) | 534 |
| 2.1.1191 | Part 4 Section 4.6.33, cTn (Common Time Node Properties)..... | 535 |
| 2.1.1192 | Part 4 Section 4.6.34, cut (Cut Slide Transition) | 536 |
| 2.1.1193 | Part 4 Section 4.6.39, endSync (EndSync) | 536 |
| 2.1.1194 | Part 4 Section 4.6.40, excl (Exclusive)..... | 536 |
| 2.1.1195 | Part 4 Section 4.6.41, fade (Fade Slide Transition)..... | 537 |
| 2.1.1196 | Part 4 Section 4.6.43, from (From) | 537 |
| 2.1.1197 | Part 4 Section 4.6.44, from (From) | 537 |
| 2.1.1198 | Part 4 Section 4.6.45, graphicEl (Graphic Element) | 538 |
| 2.1.1199 | Part 4 Section 4.6.46, hsl (HSL)..... | 538 |
| 2.1.1200 | Part 4 Section 4.6.47, inkTgt (Ink Target)..... | 538 |
| 2.1.1201 | Part 4 Section 4.6.49, iterate (Iterate) | 538 |
| 2.1.1202 | Part 4 Section 4.6.51, nextCondLst (Next Conditions List)..... | 538 |
| 2.1.1203 | Part 4 Section 4.6.52, oleChartEl (Embedded Chart Element) | 538 |
| 2.1.1204 | Part 4 Section 4.6.55, prevCondLst (Previous Conditions List) | 538 |
| 2.1.1205 | Part 4 Section 4.6.56, pRg (Paragraph Text Range)..... | 539 |
| 2.1.1206 | Part 4 Section 4.6.57, progress (Progress) | 539 |
| 2.1.1207 | Part 4 Section 4.6.62, rCtr (Rotation Center)..... | 539 |
| 2.1.1208 | Part 4 Section 4.6.63, rgb (RGB) | 539 |
| 2.1.1209 | Part 4 Section 4.6.65, seq (Sequence Time Node)..... | 540 |
| 2.1.1210 | Part 4 Section 4.6.66, set (Set Time Node Behavior) | 540 |
| 2.1.1211 | Part 4 Section 4.6.67, sldTgt (Slide Target)..... | 540 |
| 2.1.1212 | Part 4 Section 4.6.72, spTgt (Shape Target)..... | 540 |
| 2.1.1213 | Part 4 Section 4.6.77, subSp (Subshape) | 540 |
| 2.1.1214 | Part 4 Section 4.6.78, subTnLst (Sub-TimeNodes List)..... | 541 |
| 2.1.1215 | Part 4 Section 4.6.79, tav (Time Animate Value)..... | 541 |
| 2.1.1216 | Part 4 Section 4.6.83, tmPct (Time Percentage)..... | 545 |
| 2.1.1217 | Part 4 Section 4.6.84, tmpl (Template Effects)..... | 545 |
| 2.1.1218 | Part 4 Section 4.6.85, tmplLst (Template effects)..... | 545 |
| 2.1.1219 | Part 4 Section 4.6.87, tnLst (Time Node List) | 545 |
| 2.1.1220 | Part 4 Section 4.6.88, to (To) | 546 |
| 2.1.1221 | Part 4 Section 4.6.89, to (To) | 546 |
| 2.1.1222 | Part 4 Section 4.6.90, to (To)..... | 550 |
| 2.1.1223 | Part 4 Section 4.6.93, video (Video) | 550 |
| 2.1.1224 | Part 4 Section 4.6.95, wheel (Wheel Slide Transition) | 550 |
| 2.1.1225 | Part 4 Section 4.8.11, ST_PhotoAlbumFrameShape (Photo Album Shape for Photo Mask)..... | 550 |
| 2.1.1226 | Part 4 Section 4.8.28, ST_TLAnimateEffectTransition (Time List Animate Effect Transition)..... | 552 |
| 2.1.1227 | Part 4 Section 4.8.29, ST_TLAnimateMotionBehaviorOrigin (Time List Animate Motion Behavior Origin)..... | 552 |
| 2.1.1228 | Part 4 Section 4.8.32, ST_TLBehaviorAdditiveType (Behavior Additive Type) ... | 552 |
| 2.1.1229 | Part 4 Section 4.8.34, ST_TLBehaviorTransformType (Behavior Transform Type)..... | 553 |
| 2.1.1230 | Part 4 Section 4.8.42, ST_TLTime (Time)..... | 553 |
| 2.1.1231 | Part 4 Section 4.8.43, ST_TLTimeAnimateValueTime (Animation Time)..... | 553 |
| 2.1.1232 | Part 4 Section 4.8.45, ST_TLTimeNodeFillType (Time Node Fill Type) | 553 |
| 2.1.1233 | Part 4 Section 4.8.47, ST_TLTimeNodeMasterRelation (Time Node Master Relation) | 554 |
| 2.1.1234 | Part 4 Section 4.8.49, ST_TLTimeNodeRestartType (Time Node Restart Type) . | 554 |

| | | |
|----------|---|-----|
| 2.1.1235 | Part 4 Section 4.8.50, ST_TLTimeNodeSyncType (Time Node Sync Type) | 554 |
| 2.1.1236 | Part 4 Section 4.8.52, ST_TLTriggerEvent (Trigger Event) | 554 |
| 2.1.1237 | Part 4 Section 4.8.59, ST_ViewType (List of View Types) | 555 |
| 2.1.1238 | Part 4 Section 4.8.61, ST_WebEncoding (Web Encoding) | 555 |
| 2.1.1239 | Part 4 Section 5.1.2.1.1, bldChart (Build Chart) | 557 |
| 2.1.1240 | Part 4 Section 5.1.2.1.2, bldDgm (Build Diagram) | 557 |
| 2.1.1241 | Part 4 Section 5.1.2.1.4, cNvCxnSpPr (Non-Visual Connector Shape Drawing Properties) | 557 |
| 2.1.1242 | Part 4 Section 5.1.2.1.5, cNvGraphicFramePr (Non-Visual Graphic Frame Drawing Properties) | 557 |
| 2.1.1243 | Part 4 Section 5.1.2.1.6, cNvGrpSpPr (Non-Visual Group Shape Drawing Properties) | 557 |
| 2.1.1244 | Part 4 Section 5.1.2.1.11, cxnSpLocks (Connection Shape Locks) | 557 |
| 2.1.1245 | Part 4 Section 5.1.2.1.12, dgm (Diagram to Animate) | 557 |
| 2.1.1246 | Part 4 Section 5.1.2.1.13, endCxn (Connection End) | 558 |
| 2.1.1247 | Part 4 Section 5.1.2.1.14, ext (Extension) | 558 |
| 2.1.1248 | Part 4 Section 5.1.2.1.17, graphicData (Graphic Object Data) | 558 |
| 2.1.1249 | Part 4 Section 5.1.2.1.19, graphicFrameLocks (Graphic Frame Locks) | 559 |
| 2.1.1250 | Part 4 Section 5.1.2.1.21, grpSpLocks (Group Shape Locks) | 559 |
| 2.1.1251 | Part 4 Section 5.1.2.1.22, grpSpPr (Visual Group Shape Properties) | 559 |
| 2.1.1252 | Part 4 Section 5.1.2.1.23, hlinkHover (Hyperlink for Hover) | 559 |
| 2.1.1253 | Part 4 Section 5.1.2.1.24, ln (Outline) | 559 |
| 2.1.1254 | Part 4 Section 5.1.2.1.31, picLocks (Picture Locks) | 559 |
| 2.1.1255 | Part 4 Section 5.1.2.1.34, spLocks (Shape Locks) | 560 |
| 2.1.1256 | Part 4 Section 5.1.2.1.35, spPr (Shape Properties) | 560 |
| 2.1.1257 | Part 4 Section 5.1.2.1.36, stCxn (Connection Start) | 560 |
| 2.1.1258 | Part 4 Section 5.1.2.1.37, style (Shape Style) | 560 |
| 2.1.1259 | Part 4 Section 5.1.2.2.1, alpha (Alpha) | 560 |
| 2.1.1260 | Part 4 Section 5.1.2.2.4, blue (Blue) | 561 |
| 2.1.1261 | Part 4 Section 5.1.2.2.5, blueMod (Blue Modification) | 561 |
| 2.1.1262 | Part 4 Section 5.1.2.2.6, blueOff (Blue Offset) | 561 |
| 2.1.1263 | Part 4 Section 5.1.2.2.10, green (Green) | 561 |
| 2.1.1264 | Part 4 Section 5.1.2.2.11, greenMod (Green Modification) | 561 |
| 2.1.1265 | Part 4 Section 5.1.2.2.12, greenOff (Green Offset) | 561 |
| 2.1.1266 | Part 4 Section 5.1.2.2.19, lum (Luminance) | 561 |
| 2.1.1267 | Part 4 Section 5.1.2.2.20, lumMod (Luminance Modulation) | 561 |
| 2.1.1268 | Part 4 Section 5.1.2.2.21, lumOff (Luminance Offset) | 561 |
| 2.1.1269 | Part 4 Section 5.1.2.2.22, prstClr (Preset Color) | 562 |
| 2.1.1270 | Part 4 Section 5.1.2.2.23, red (Red) | 562 |
| 2.1.1271 | Part 4 Section 5.1.2.2.24, redMod (Red Modulation) | 562 |
| 2.1.1272 | Part 4 Section 5.1.2.2.25, redOff (Red Offset) | 562 |
| 2.1.1273 | Part 4 Section 5.1.2.2.26, sat (Saturation) | 562 |
| 2.1.1274 | Part 4 Section 5.1.2.2.27, satMod (Saturation Modulation) | 562 |
| 2.1.1275 | Part 4 Section 5.1.2.2.28, satOff (Saturation Offset) | 562 |
| 2.1.1276 | Part 4 Section 5.1.2.2.31, shade (Shade) | 562 |
| 2.1.1277 | Part 4 Section 5.1.2.2.33, sysClr (System Color) | 563 |
| 2.1.1278 | Part 4 Section 5.1.2.2.34, tint (Tint) | 563 |
| 2.1.1279 | Part 4 Section 5.1.3.3, end (Audio End Time) | 563 |
| 2.1.1280 | Part 4 Section 5.1.3.5, st (Audio Start Time) | 563 |
| 2.1.1281 | Part 4 Section 5.1.4.1.1, accent1 (Accent 1) | 563 |
| 2.1.1282 | Part 4 Section 5.1.4.1.2, accent2 (Accent 2) | 563 |
| 2.1.1283 | Part 4 Section 5.1.4.1.3, accent3 (Accent 3) | 563 |
| 2.1.1284 | Part 4 Section 5.1.4.1.4, accent4 (Accent 4) | 563 |

| | | |
|----------|--|-----|
| 2.1.1285 | Part 4 Section 5.1.4.1.5, accent5 (Accent 5) | 563 |
| 2.1.1286 | Part 4 Section 5.1.4.1.6, accent6 (Accent 6) | 564 |
| 2.1.1287 | Part 4 Section 5.1.4.1.9, dk1 (Dark 1) | 564 |
| 2.1.1288 | Part 4 Section 5.1.4.1.10, dk2 (Dark 2) | 564 |
| 2.1.1289 | Part 4 Section 5.1.4.1.15, folHlink (Followed Hyperlink) | 564 |
| 2.1.1290 | Part 4 Section 5.1.4.1.17, fontRef (Font Reference) | 564 |
| 2.1.1291 | Part 4 Section 5.1.4.1.19, hlink (Hyperlink) | 564 |
| 2.1.1292 | Part 4 Section 5.1.4.1.22, lt1 (Light 1) | 564 |
| 2.1.1293 | Part 4 Section 5.1.4.1.23, lt2 (Light 2) | 564 |
| 2.1.1294 | Part 4 Section 5.1.4.2.2, band1V (Band 1 Vertical) | 564 |
| 2.1.1295 | Part 4 Section 5.1.4.2.4, band2V (Band 2 Vertical) | 565 |
| 2.1.1296 | Part 4 Section 5.1.4.2.9, fill (Fill) | 565 |
| 2.1.1297 | Part 4 Section 5.1.4.2.19, lnRef (Line Reference) | 565 |
| 2.1.1298 | Part 4 Section 5.1.4.2.26, tblStyle (Table Style) | 565 |
| 2.1.1299 | Part 4 Section 5.1.5.1.1, bodyPr (Body Properties) | 566 |
| 2.1.1300 | Part 4 Section 5.1.5.1.2, noAutofit (No AutoFit) | 566 |
| 2.1.1301 | Part 4 Section 5.1.5.1.3, normAutofit (Normal AutoFit) | 566 |
| 2.1.1302 | Part 4 Section 5.1.5.1.4, spAutoFit (Shape AutoFit) | 567 |
| 2.1.1303 | Part 4 Section 5.1.5.2.2, defPPr (Default Paragraph Style) | 567 |
| 2.1.1304 | Part 4 Section 5.1.5.2.3, endParaRPr (End Paragraph Run Properties) | 567 |
| 2.1.1305 | Part 4 Section 5.1.5.2.4, fld (Text Field) | 567 |
| 2.1.1306 | Part 4 Section 5.1.5.2.5, lnSp (Line Spacing) | 568 |
| 2.1.1307 | Part 4 Section 5.1.5.2.6, p (Text Paragraphs) | 568 |
| 2.1.1308 | Part 4 Section 5.1.5.2.7, pPr (Text Paragraph Properties) | 568 |
| 2.1.1309 | Part 4 Section 5.1.5.2.8, spcAft (Space After) | 569 |
| 2.1.1310 | Part 4 Section 5.1.5.2.9, spcBef (Space Before) | 569 |
| 2.1.1311 | Part 4 Section 5.1.5.3.1, cs (Complex Script Font) | 569 |
| 2.1.1312 | Part 4 Section 5.1.5.3.2, defRPr (Default Text Run Properties) | 569 |
| 2.1.1313 | Part 4 Section 5.1.5.3.3, ea (East Asian Font) | 569 |
| 2.1.1314 | Part 4 Section 5.1.5.3.5, hlinkClick (Click Hyperlink) | 569 |
| 2.1.1315 | Part 4 Section 5.1.5.3.6, hlinkMouseOver (Mouse-Over Hyperlink) | 570 |
| 2.1.1316 | Part 4 Section 5.1.5.3.7, latin (Latin Font) | 570 |
| 2.1.1317 | Part 4 Section 5.1.5.3.8, r (Text Run) | 572 |
| 2.1.1318 | Part 4 Section 5.1.5.3.9, rPr (Text Run Properties) | 573 |
| 2.1.1319 | Part 4 Section 5.1.5.3.10, sym (Symbol Font) | 574 |
| 2.1.1320 | Part 4 Section 5.1.5.3.13, uFillTx (Underline Fill Properties Follow Text) | 574 |
| 2.1.1321 | Part 4 Section 5.1.5.3.14, uLn (Underline Stroke) | 574 |
| 2.1.1322 | Part 4 Section 5.1.5.4.6, buFont (Specified) | 574 |
| 2.1.1323 | Part 4 Section 5.1.5.4.9, buSzPct (Bullet Size Percentage) | 574 |
| 2.1.1324 | Part 4 Section 5.1.5.4.10, buSzPts (Bullet Size Points) | 574 |
| 2.1.1325 | Part 4 Section 5.1.5.4.13, lvl1pPr (List Level 1 Text Style) | 574 |
| 2.1.1326 | Part 4 Section 5.1.5.4.14, lvl2pPr (List Level 2 Text Style) | 575 |
| 2.1.1327 | Part 4 Section 5.1.5.4.15, lvl3pPr (List Level 3 Text Style) | 575 |
| 2.1.1328 | Part 4 Section 5.1.5.4.16, lvl4pPr (List Level 4 Text Style) | 575 |
| 2.1.1329 | Part 4 Section 5.1.5.4.17, lvl5pPr (List Level 5 Text Style) | 575 |
| 2.1.1330 | Part 4 Section 5.1.5.4.18, lvl6pPr (List Level 6 Text Style) | 575 |
| 2.1.1331 | Part 4 Section 5.1.5.4.19, lvl7pPr (List Level 7 Text Style) | 576 |
| 2.1.1332 | Part 4 Section 5.1.5.4.20, lvl8pPr (List Level 8 Text Style) | 576 |
| 2.1.1333 | Part 4 Section 5.1.5.4.21, lvl9pPr (List Level 9 Text Style) | 576 |
| 2.1.1334 | Part 4 Section 5.1.6.1, cell3D (Cell 3-D) | 576 |
| 2.1.1335 | Part 4 Section 5.1.6.2, gridCol (Table Grid Column) | 576 |
| 2.1.1336 | Part 4 Section 5.1.6.3, lnB (Bottom Border Line Properties) | 576 |

| | | |
|----------|---|-----|
| 2.1.1337 | Part 4 Section 5.1.6.4, InBToTr (Bottom-Left to Top-Right Border Line Properties) | 576 |
| 2.1.1338 | Part 4 Section 5.1.6.5, InL (Left Border Line Properties)..... | 577 |
| 2.1.1339 | Part 4 Section 5.1.6.6, InR (Right Border Line Properties) | 577 |
| 2.1.1340 | Part 4 Section 5.1.6.7, InT (Top Border Line Properties)..... | 577 |
| 2.1.1341 | Part 4 Section 5.1.6.8, InTToBr (Top-Left to Bottom-Right Border Line Properties) | 577 |
| 2.1.1342 | Part 4 Section 5.1.6.10, tableStyleId (Table Style ID)..... | 577 |
| 2.1.1343 | Part 4 Section 5.1.6.11, tbl (Table) | 658 |
| 2.1.1344 | Part 4 Section 5.1.6.12, tblGrid (Table Grid)..... | 659 |
| 2.1.1345 | Part 4 Section 5.1.6.14, tc (Table Cell) | 659 |
| 2.1.1346 | Part 4 Section 5.1.6.16, tr (Table Row)..... | 660 |
| 2.1.1347 | Part 4 Section 5.1.7.1, anchor (Anchor Point) | 660 |
| 2.1.1348 | Part 4 Section 5.1.7.2, backdrop (Backdrop Plane)..... | 660 |
| 2.1.1349 | Part 4 Section 5.1.7.3, bevelB (Bottom Bevel) | 660 |
| 2.1.1350 | Part 4 Section 5.1.7.4, bevelT (Top Bevel) | 660 |
| 2.1.1351 | Part 4 Section 5.1.7.5, camera (Camera) | 661 |
| 2.1.1352 | Part 4 Section 5.1.7.6, contourClr (Contour Color) | 661 |
| 2.1.1353 | Part 4 Section 5.1.7.7, extrusionClr (Extrusion Color)..... | 661 |
| 2.1.1354 | Part 4 Section 5.1.7.8, flatTx (No text in 3D scene)..... | 661 |
| 2.1.1355 | Part 4 Section 5.1.7.9, lightRig (Light Rig) | 661 |
| 2.1.1356 | Part 4 Section 5.1.7.10, norm (Normal) | 661 |
| 2.1.1357 | Part 4 Section 5.1.7.12, sp3d (Apply 3D shape properties)..... | 662 |
| 2.1.1358 | Part 4 Section 5.1.7.13, up (Up Vector) | 662 |
| 2.1.1359 | Part 4 Section 5.1.9.1, chExt (Child Extents) | 662 |
| 2.1.1360 | Part 4 Section 5.1.9.2, chOff (Child Offset) | 662 |
| 2.1.1361 | Part 4 Section 5.1.9.3, ext (Extents) | 662 |
| 2.1.1362 | Part 4 Section 5.1.9.4, off (Offset) | 663 |
| 2.1.1363 | Part 4 Section 5.1.9.5, xfrm (2D Transform for Grouped Objects) | 663 |
| 2.1.1364 | Part 4 Section 5.1.9.6, xfrm (2D Transform for Individual Objects) | 663 |
| 2.1.1365 | Part 4 Section 5.1.10, Shape Fills, Effects, and Line Properties | 663 |
| 2.1.1366 | Part 4 Section 5.1.10.4, alphaInv (Alpha Inverse Effect) | 665 |
| 2.1.1367 | Part 4 Section 5.1.10.5, alphaMod (Alpha Modulate Effect)..... | 665 |
| 2.1.1368 | Part 4 Section 5.1.10.14, blipFill (Picture Fill) | 665 |
| 2.1.1369 | Part 4 Section 5.1.10.15, blur (Blur Effect)..... | 665 |
| 2.1.1370 | Part 4 Section 5.1.10.16, clrChange (Color Change Effect) | 666 |
| 2.1.1371 | Part 4 Section 5.1.10.20, cont (Effect Container) | 666 |
| 2.1.1372 | Part 4 Section 5.1.10.22, ds (Dash Stop) | 666 |
| 2.1.1373 | Part 4 Section 5.1.10.23, duotone (Duotone Effect)..... | 666 |
| 2.1.1374 | Part 4 Section 5.1.10.24, effect (Effect)..... | 666 |
| 2.1.1375 | Part 4 Section 5.1.10.25, effectDag (Effect Container)..... | 666 |
| 2.1.1376 | Part 4 Section 5.1.10.31, fillToRect (Fill To Rectangle)..... | 667 |
| 2.1.1377 | Part 4 Section 5.1.10.33, gradFill (Gradient Fill) | 667 |
| 2.1.1378 | Part 4 Section 5.1.10.35, grpFill (Group Fill)..... | 667 |
| 2.1.1379 | Part 4 Section 5.1.10.39, hsl (Hue Saturation Luminance Effect)..... | 667 |
| 2.1.1380 | Part 4 Section 5.1.10.40, innerShdw (Inner Shadow Effect) | 667 |
| 2.1.1381 | Part 4 Section 5.1.10.42, lum (Luminance Effect) | 667 |
| 2.1.1382 | Part 4 Section 5.1.10.43, miter (Miter Line Join) | 667 |
| 2.1.1383 | Part 4 Section 5.1.10.50, reflection (Reflection Effect) | 668 |
| 2.1.1384 | Part 4 Section 5.1.10.52, round (Round Line Join) | 668 |
| 2.1.1385 | Part 4 Section 5.1.10.53, softEdge (Soft Edge Effect) | 668 |
| 2.1.1386 | Part 4 Section 5.1.10.55, srcRect (Source Rectangle) | 668 |
| 2.1.1387 | Part 4 Section 5.1.10.59, tileRect (Tile Rectangle)..... | 668 |

| | | |
|----------|---|-----|
| 2.1.1388 | Part 4 Section 5.1.11.11, gd (Shape Guide) | 668 |
| 2.1.1389 | Part 4 Section 5.1.11.15, path (Shape Path) | 669 |
| 2.1.1390 | Part 4 Section 5.1.11.17, pos (Shape Position Coordinate) | 669 |
| 2.1.1391 | Part 4 Section 5.1.11.20, pt (Shape Path Point) | 669 |
| 2.1.1392 | Part 4 Section 5.1.12.12, ST_BlipCompression (Blip Compression Type) | 669 |
| 2.1.1393 | Part 4 Section 5.1.12.15, ST_CompoundLine (Compound Line Type) | 669 |
| 2.1.1394 | Part 4 Section 5.1.12.16, ST_Coordinate (Coordinate) | 669 |
| 2.1.1395 | Part 4 Section 5.1.12.29, ST_LightRigDirection (Light Rig Direction) | 669 |
| 2.1.1396 | Part 4 Section 5.1.12.30, ST_LightRigType (Light Rig Type) | 669 |
| 2.1.1397 | Part 4 Section 5.1.12.32, ST_LineEndLength (Line End Length) | 670 |
| 2.1.1398 | Part 4 Section 5.1.12.35, ST_LineWidth (Line Width) | 670 |
| 2.1.1399 | Part 4 Section 5.1.12.40, ST_PenAlignment (Alignment Type) | 670 |
| 2.1.1400 | Part 4 Section 5.1.12.42, ST_PositiveCoordinate (Positive Coordinate) | 670 |
| 2.1.1401 | Part 4 Section 5.1.12.48, ST_PresetColorVal (Preset Color Value) | 671 |
| 2.1.1402 | Part 4 Section 5.1.12.55, ST_ShapeID (Shape ID) | 671 |
| 2.1.1403 | Part 4 Section 5.1.12.60, ST_TextAnchoringType (Text Anchoring Types) | 672 |
| 2.1.1404 | Part 4 Section 5.1.12.64, ST_TextCapsType (Text Cap Types) | 672 |
| 2.1.1405 | Part 4 Section 5.1.12.72, ST_TextLanguageID (Language ID) | 672 |
| 2.1.1406 | Part 4 Section 5.1.12.74, ST_TextNonNegativePoint (Text Non-Negative Point) | 673 |
| 2.1.1407 | Part 4 Section 5.1.12.75, ST_TextPoint (Text Point) | 673 |
| 2.1.1408 | Part 4 Section 5.1.12.76, ST_TextShapeType (Preset Text Shape Types) | 673 |
| 2.1.1409 | Part 4 Section 5.1.12.77, ST_TextSpacingPercent (Text Spacing Percent) | 673 |
| 2.1.1410 | Part 4 Section 5.1.12.78, ST_TextSpacingPoint (Text Spacing Point) | 674 |
| 2.1.1411 | Part 4 Section 5.1.12.82, ST_TextUnderlineType (Text Underline Types) | 674 |
| 2.1.1412 | Part 4 Section 5.2.2.1, blipFill (Picture Fill) | 674 |
| 2.1.1413 | Part 4 Section 5.2.2.6, spPr (Shape Properties) | 674 |
| 2.1.1414 | Part 4 Section 5.5.2.3, anchor (Anchor for Floating DrawingML Object) | 674 |
| 2.1.1415 | Part 4 Section 5.5.2.6, effectExtent (Object Extents Including Effects) | 674 |
| 2.1.1416 | Part 4 Section 5.5.2.7, extent (Drawing Object Size) | 674 |
| 2.1.1417 | Part 4 Section 5.5.2.9, lineTo (Wrapping Polygon Line End Position) | 674 |
| 2.1.1418 | Part 4 Section 5.5.2.11, positionV (Vertical Positioning) | 674 |
| 2.1.1419 | Part 4 Section 5.5.2.13, simplePos (Simple Positioning Coordinates) | 675 |
| 2.1.1420 | Part 4 Section 5.5.2.14, start (Wrapping Polygon Start) | 675 |
| 2.1.1421 | Part 4 Section 5.6.2.2, blipFill (Picture Fill) | 675 |
| 2.1.1422 | Part 4 Section 5.6.2.8, cNvPr (Non-Visual Drawing Properties) | 675 |
| 2.1.1423 | Part 4 Section 5.6.2.9, cNvSpPr (Connection Non-Visual Shape Properties) | 675 |
| 2.1.1424 | Part 4 Section 5.6.2.10, col (Column) | 675 |
| 2.1.1425 | Part 4 Section 5.6.2.12, cxnSp (Connection Shape) | 675 |
| 2.1.1426 | Part 4 Section 5.6.2.13, ext (Shape Extent) | 675 |
| 2.1.1427 | Part 4 Section 5.6.2.14, from (Starting Anchor Point) | 675 |
| 2.1.1428 | Part 4 Section 5.6.2.15, graphicFrame (Graphic Frame) | 676 |
| 2.1.1429 | Part 4 Section 5.6.2.17, grpSpPr (Group Shape Properties) | 676 |
| 2.1.1430 | Part 4 Section 5.6.2.24, pic (Picture) | 676 |
| 2.1.1431 | Part 4 Section 5.6.2.25, pos (Position) | 676 |
| 2.1.1432 | Part 4 Section 5.6.2.26, row (Row) | 676 |
| 2.1.1433 | Part 4 Section 5.6.2.28, sp (Shape) | 676 |
| 2.1.1434 | Part 4 Section 5.6.2.29, spPr (Shape Properties) | 677 |
| 2.1.1435 | Part 4 Section 5.6.2.30, style (Shape Style) | 677 |
| 2.1.1436 | Part 4 Section 5.6.2.31, to (Ending Anchor Point) | 677 |
| 2.1.1437 | Part 4 Section 5.6.2.33, txBody (Shape Text Body) | 677 |
| 2.1.1438 | Part 4 Section 5.6.2.35, xfrm (2D Transform for Graphic Frames) | 678 |
| 2.1.1439 | Part 4 Section 5.7.2.1, applyToEnd (Apply to End) | 678 |

| | | |
|----------|--|-----|
| 2.1.1440 | Part 4 Section 5.7.2.2, applyToFront (Apply To Front) | 678 |
| 2.1.1441 | Part 4 Section 5.7.2.3, applyToSides (Apply To Sides) | 678 |
| 2.1.1442 | Part 4 Section 5.7.2.4, area3DChart (3D Area Charts) | 679 |
| 2.1.1443 | Part 4 Section 5.7.2.5, areaChart (Area Charts) | 679 |
| 2.1.1444 | Part 4 Section 5.7.2.6, auto (Automatic Category Axis) | 679 |
| 2.1.1445 | Part 4 Section 5.7.2.7, autoTitleDeleted (Auto Title Is Deleted) | 679 |
| 2.1.1446 | Part 4 Section 5.7.2.8, autoUpdate (Update Automatically) | 679 |
| 2.1.1447 | Part 4 Section 5.7.2.9, axId (Axis ID) | 680 |
| 2.1.1448 | Part 4 Section 5.7.2.10, axPos (Axis Position) | 680 |
| 2.1.1449 | Part 4 Section 5.7.2.11, backWall (Back Wall) | 680 |
| 2.1.1450 | Part 4 Section 5.7.2.12, backward (Backward) | 680 |
| 2.1.1451 | Part 4 Section 5.7.2.14, bandFmts (Band Formats) | 680 |
| 2.1.1452 | Part 4 Section 5.7.2.15, bar3DChart (3D Bar Charts) | 680 |
| 2.1.1453 | Part 4 Section 5.7.2.16, barChart (Bar Charts) | 681 |
| 2.1.1454 | Part 4 Section 5.7.2.17, barDir (Bar Direction) | 681 |
| 2.1.1455 | Part 4 Section 5.7.2.18, baseTimeUnit (Base Time Unit) | 681 |
| 2.1.1456 | Part 4 Section 5.7.2.19, bubble3D (3D Bubble) | 681 |
| 2.1.1457 | Part 4 Section 5.7.2.20, bubbleChart (Bubble Charts) | 682 |
| 2.1.1458 | Part 4 Section 5.7.2.23, builtInUnit (Built in Display Unit Value) | 682 |
| 2.1.1459 | Part 4 Section 5.7.2.24, cat (Category Axis Data) | 682 |
| 2.1.1460 | Part 4 Section 5.7.2.25, catAx (Category Axis Data) | 683 |
| 2.1.1461 | Part 4 Section 5.7.2.28, chartObject (Chart Object) | 683 |
| 2.1.1462 | Part 4 Section 5.7.2.31, crossAx (Crossing Axis ID) | 683 |
| 2.1.1463 | Part 4 Section 5.7.2.34, crossesAt (Crossing Value) | 683 |
| 2.1.1464 | Part 4 Section 5.7.2.36, custUnit (Custom Display Unit) | 684 |
| 2.1.1465 | Part 4 Section 5.7.2.37, data (Data Cannot Be Changed) | 684 |
| 2.1.1466 | Part 4 Section 5.7.2.38, date1904 (1904 Date System) | 684 |
| 2.1.1467 | Part 4 Section 5.7.2.39, dateAx (Date Axis) | 685 |
| 2.1.1468 | Part 4 Section 5.7.2.40, delete (Delete) | 685 |
| 2.1.1469 | Part 4 Section 5.7.2.41, depthPercent (Depth Percent) | 685 |
| 2.1.1470 | Part 4 Section 5.7.2.42, dispBlanksAs (Display Blanks As) | 685 |
| 2.1.1471 | Part 4 Section 5.7.2.43, dispEq (Display Equation) | 687 |
| 2.1.1472 | Part 4 Section 5.7.2.44, dispRSqr (Display R Squared Value) | 687 |
| 2.1.1473 | Part 4 Section 5.7.2.47, dLbl (Data Label) | 687 |
| 2.1.1474 | Part 4 Section 5.7.2.48, dLblPos (Data Label Position) | 688 |
| 2.1.1475 | Part 4 Section 5.7.2.49, dLbls (Data Labels) | 689 |
| 2.1.1476 | Part 4 Section 5.7.2.50, doughnutChart (Doughnut Charts) | 689 |
| 2.1.1477 | Part 4 Section 5.7.2.55, errBars (Error Bars) | 689 |
| 2.1.1478 | Part 4 Section 5.7.2.56, errBarType (Error Bar Type) | 689 |
| 2.1.1479 | Part 4 Section 5.7.2.57, errDir (Error Bar Direction) | 689 |
| 2.1.1480 | Part 4 Section 5.7.2.58, errValType (Error Bar Value Type) | 690 |
| 2.1.1481 | Part 4 Section 5.7.2.59, evenFooter (Even Footer) | 690 |
| 2.1.1482 | Part 4 Section 5.7.2.60, evenHeader (Even Header) | 690 |
| 2.1.1483 | Part 4 Section 5.7.2.61, explosion (Explosion) | 690 |
| 2.1.1484 | Part 4 Section 5.7.2.63, externalData (External Data Relationship) | 690 |
| 2.1.1485 | Part 4 Section 5.7.2.65, f (Formula) | 690 |
| 2.1.1486 | Part 4 Section 5.7.2.66, firstFooter (First Footer) | 691 |
| 2.1.1487 | Part 4 Section 5.7.2.67, firstHeader (First Header) | 691 |
| 2.1.1488 | Part 4 Section 5.7.2.69, floor (Floor) | 691 |
| 2.1.1489 | Part 4 Section 5.7.2.70, fmtId (Format ID) | 691 |
| 2.1.1490 | Part 4 Section 5.7.2.72, formatting (Formatting) | 691 |
| 2.1.1491 | Part 4 Section 5.7.2.73, forward (Forward) | 692 |
| 2.1.1492 | Part 4 Section 5.7.2.74, gapDepth (Gap Depth) | 692 |

| | | |
|----------|---|-----|
| 2.1.1493 | Part 4 Section 5.7.2.75, gapWidth (Gap Width) | 692 |
| 2.1.1494 | Part 4 Section 5.7.2.76, grouping (Grouping) | 692 |
| 2.1.1495 | Part 4 Section 5.7.2.77, grouping (Bar Grouping) | 692 |
| 2.1.1496 | Part 4 Section 5.7.2.78, h (Height) | 693 |
| 2.1.1497 | Part 4 Section 5.7.2.79, headerFooter (Header and Footer) | 693 |
| 2.1.1498 | Part 4 Section 5.7.2.81, hMode (Height Mode) | 693 |
| 2.1.1499 | Part 4 Section 5.7.2.82, holeSize (Hole Size) | 693 |
| 2.1.1500 | Part 4 Section 5.7.2.83, hPercent (Height Percent) | 694 |
| 2.1.1501 | Part 4 Section 5.7.2.84, idx (Index) | 694 |
| 2.1.1502 | Part 4 Section 5.7.2.85, intercept (Intercept) | 694 |
| 2.1.1503 | Part 4 Section 5.7.2.86, invertIfNegative (Invert if Negative) | 694 |
| 2.1.1504 | Part 4 Section 5.7.2.88, layout (Layout) | 694 |
| 2.1.1505 | Part 4 Section 5.7.2.89, layoutTarget (Layout Target) | 695 |
| 2.1.1506 | Part 4 Section 5.7.2.92, leaderLines (Leader Lines) | 695 |
| 2.1.1507 | Part 4 Section 5.7.2.96, legendPos (Legend Position) | 695 |
| 2.1.1508 | Part 4 Section 5.7.2.97, line3DChart (3D Line Charts) | 695 |
| 2.1.1509 | Part 4 Section 5.7.2.98, lineChart (Line Charts) | 695 |
| 2.1.1510 | Part 4 Section 5.7.2.100, lvl (Level) | 695 |
| 2.1.1511 | Part 4 Section 5.7.2.102, majorTickMark (Major Tick Mark) | 695 |
| 2.1.1512 | Part 4 Section 5.7.2.103, majorTimeUnit (Major Time Unit) | 696 |
| 2.1.1513 | Part 4 Section 5.7.2.104, majorUnit (Major Unit) | 696 |
| 2.1.1514 | Part 4 Section 5.7.2.105, manualLayout (Manual Layout) | 696 |
| 2.1.1515 | Part 4 Section 5.7.2.106, marker (Marker) | 696 |
| 2.1.1516 | Part 4 Section 5.7.2.107, marker (Show Marker) | 696 |
| 2.1.1517 | Part 4 Section 5.7.2.108, max (Maximum) | 696 |
| 2.1.1518 | Part 4 Section 5.7.2.109, min (Minimum) | 696 |
| 2.1.1519 | Part 4 Section 5.7.2.111, minorTickMark (Minor Tick Mark) | 697 |
| 2.1.1520 | Part 4 Section 5.7.2.112, minorTimeUnit (Minor Time Unit) | 697 |
| 2.1.1521 | Part 4 Section 5.7.2.113, minorUnit (Minor Unit) | 697 |
| 2.1.1522 | Part 4 Section 5.7.2.114, minus (Minus) | 697 |
| 2.1.1523 | Part 4 Section 5.7.2.115, multiLvlStrCache (Multi Level String Cache) | 697 |
| 2.1.1524 | Part 4 Section 5.7.2.116, multiLvlStrRef (Multi Level String Reference) | 697 |
| 2.1.1525 | Part 4 Section 5.7.2.118, name (Pivot Name) | 697 |
| 2.1.1526 | Part 4 Section 5.7.2.119, noEndCap (No End Cap) | 698 |
| 2.1.1527 | Part 4 Section 5.7.2.120, noMultiLvlLbl (No Multi-level Labels) | 698 |
| 2.1.1528 | Part 4 Section 5.7.2.122, numFmt (Number Format) | 698 |
| 2.1.1529 | Part 4 Section 5.7.2.125, oddFooter (Odd Footer) | 699 |
| 2.1.1530 | Part 4 Section 5.7.2.126, oddHeader (Odd Header) | 699 |
| 2.1.1531 | Part 4 Section 5.7.2.127, ofPieChart (Pie of Pie or Bar of Pie Charts) | 699 |
| 2.1.1532 | Part 4 Section 5.7.2.128, ofPieType (Pie of Pie or Bar of Pie Type) | 699 |
| 2.1.1533 | Part 4 Section 5.7.2.129, order (Order) | 699 |
| 2.1.1534 | Part 4 Section 5.7.2.130, order (Polynomial Trendline Order) | 699 |
| 2.1.1535 | Part 4 Section 5.7.2.131, orientation (Axis Orientation) | 700 |
| 2.1.1536 | Part 4 Section 5.7.2.132, overlap (Overlap) | 700 |
| 2.1.1537 | Part 4 Section 5.7.2.133, overlay (Overlay) | 700 |
| 2.1.1538 | Part 4 Section 5.7.2.134, pageMargins (Page Margins) | 700 |
| 2.1.1539 | Part 4 Section 5.7.2.135, pageSetup (Page Setup) | 701 |
| 2.1.1540 | Part 4 Section 5.7.2.136, period (Period) | 705 |
| 2.1.1541 | Part 4 Section 5.7.2.137, perspective (Perspective) | 706 |
| 2.1.1542 | Part 4 Section 5.7.2.139, pictureOptions (Picture Options) | 706 |
| 2.1.1543 | Part 4 Section 5.7.2.141, pie3DChart (3D Pie Charts) | 706 |
| 2.1.1544 | Part 4 Section 5.7.2.142, pieChart (Pie Charts) | 706 |
| 2.1.1545 | Part 4 Section 5.7.2.143, pivotFmt (Pivot Format) | 707 |

| | | |
|----------|---|-----|
| 2.1.1546 | Part 4 Section 5.7.2.144, pivotFmts (Pivot Formats)..... | 707 |
| 2.1.1547 | Part 4 Section 5.7.2.145, pivotSource (Pivot Source)..... | 707 |
| 2.1.1548 | Part 4 Section 5.7.2.146, plotArea (Plot Area) | 707 |
| 2.1.1549 | Part 4 Section 5.7.2.147, plotVisOnly (Plot Visible Only) | 707 |
| 2.1.1550 | Part 4 Section 5.7.2.148, plus (Plus) | 707 |
| 2.1.1551 | Part 4 Section 5.7.2.149, printSettings (Print Settings)..... | 708 |
| 2.1.1552 | Part 4 Section 5.7.2.150, protection (Protection) | 708 |
| 2.1.1553 | Part 4 Section 5.7.2.151, pt (Numeric Point) | 708 |
| 2.1.1554 | Part 4 Section 5.7.2.152, pt (String Point) | 708 |
| 2.1.1555 | Part 4 Section 5.7.2.153, ptCount (Point Count) | 708 |
| 2.1.1556 | Part 4 Section 5.7.2.154, radarChart (Radar Charts) | 709 |
| 2.1.1557 | Part 4 Section 5.7.2.155, radarStyle (Radar Style)..... | 709 |
| 2.1.1558 | Part 4 Section 5.7.2.156, rAngAx (Right Angle Axes)..... | 709 |
| 2.1.1559 | Part 4 Section 5.7.2.157, rich (Rich Text) | 709 |
| 2.1.1560 | Part 4 Section 5.7.2.158, rotX (X Rotation) | 709 |
| 2.1.1561 | Part 4 Section 5.7.2.159, rotY (Y Rotation)..... | 709 |
| 2.1.1562 | Part 4 Section 5.7.2.160, roundedCorners (Rounded Corners) | 709 |
| 2.1.1563 | Part 4 Section 5.7.2.162, scatterChart (Scatter Charts) | 710 |
| 2.1.1564 | Part 4 Section 5.7.2.163, scatterStyle (Scatter Style)..... | 710 |
| 2.1.1565 | Part 4 Section 5.7.2.164, secondPiePt (Second Pie Point)..... | 710 |
| 2.1.1566 | Part 4 Section 5.7.2.166, selection (Selection)..... | 710 |
| 2.1.1567 | Part 4 Section 5.7.2.167, separator (Separator) | 710 |
| 2.1.1568 | Part 4 Section 5.7.2.168, ser (Bubble Chart Series)..... | 710 |
| 2.1.1569 | Part 4 Section 5.7.2.169, ser (Line Chart Series) | 711 |
| 2.1.1570 | Part 4 Section 5.7.2.170, ser (Pie Chart Series)..... | 711 |
| 2.1.1571 | Part 4 Section 5.7.2.171, ser (Surface Chart Series) | 712 |
| 2.1.1572 | Part 4 Section 5.7.2.172, ser (Scatter Chart Series) | 712 |
| 2.1.1573 | Part 4 Section 5.7.2.173, ser (Radar Chart Series)..... | 712 |
| 2.1.1574 | Part 4 Section 5.7.2.174, ser (Area Chart Series)..... | 712 |
| 2.1.1575 | Part 4 Section 5.7.2.175, ser (Bar Chart Series) | 713 |
| 2.1.1576 | Part 4 Section 5.7.2.176, serAx (Series Axis) | 713 |
| 2.1.1577 | Part 4 Section 5.7.2.177, serLines (Series Lines) | 713 |
| 2.1.1578 | Part 4 Section 5.7.2.178, shape (Shape)..... | 714 |
| 2.1.1579 | Part 4 Section 5.7.2.179, showBubbleSize (Show Bubble Size) | 714 |
| 2.1.1580 | Part 4 Section 5.7.2.180, showCatName (Show Category Name) | 714 |
| 2.1.1581 | Part 4 Section 5.7.2.181, showDLblsOverMax (Show Data Labels over Maximum) | 714 |
| 2.1.1582 | Part 4 Section 5.7.2.182, showHorzBorder (Show Horizontal Border)..... | 714 |
| 2.1.1583 | Part 4 Section 5.7.2.183, showKeys (Show Legend Keys) | 715 |
| 2.1.1584 | Part 4 Section 5.7.2.184, showLeaderLines (Show Leader Lines)..... | 715 |
| 2.1.1585 | Part 4 Section 5.7.2.185, showLegendKey (Show Legend Key) | 715 |
| 2.1.1586 | Part 4 Section 5.7.2.186, showNegBubbles (Show Negative Bubbles) | 716 |
| 2.1.1587 | Part 4 Section 5.7.2.187, showOutline (Show Outline Border)..... | 716 |
| 2.1.1588 | Part 4 Section 5.7.2.188, showPercent (Show Percent) | 716 |
| 2.1.1589 | Part 4 Section 5.7.2.189, showSerName (Show Series Name) | 716 |
| 2.1.1590 | Part 4 Section 5.7.2.190, showVal (Show Value)..... | 716 |
| 2.1.1591 | Part 4 Section 5.7.2.191, showVertBorder (Show Vertical Border)..... | 717 |
| 2.1.1592 | Part 4 Section 5.7.2.192, sideWall (Side Wall) | 717 |
| 2.1.1593 | Part 4 Section 5.7.2.195, smooth (Smoothing) | 717 |
| 2.1.1594 | Part 4 Section 5.7.2.196, splitPos (Split Position) | 717 |
| 2.1.1595 | Part 4 Section 5.7.2.197, splitType (Split Type) | 717 |
| 2.1.1596 | Part 4 Section 5.7.2.198, spPr (Shape Properties)..... | 718 |
| 2.1.1597 | Part 4 Section 5.7.2.199, stockChart (Stock Charts)..... | 718 |

| | | |
|----------|--|-----|
| 2.1.1598 | Part 4 Section 5.7.2.203, style (Style) | 719 |
| 2.1.1599 | Part 4 Section 5.7.2.204, surface3DChart (3D Surface Charts) | 719 |
| 2.1.1600 | Part 4 Section 5.7.2.205, surfaceChart (Surface Charts) | 719 |
| 2.1.1601 | Part 4 Section 5.7.2.207, thickness (Thickness) | 719 |
| 2.1.1602 | Part 4 Section 5.7.2.209, tickLblSkip (Tick Label Skip) | 719 |
| 2.1.1603 | Part 4 Section 5.7.2.210, tickMarkSkip (Tick Mark Skip) | 720 |
| 2.1.1604 | Part 4 Section 5.7.2.211, title (Title) | 720 |
| 2.1.1605 | Part 4 Section 5.7.2.212, trendline (Trendlines) | 720 |
| 2.1.1606 | Part 4 Section 5.7.2.213, trendlineLbl (Trendline Label) | 720 |
| 2.1.1607 | Part 4 Section 5.7.2.214, trendlineType (Trendline Type) | 720 |
| 2.1.1608 | Part 4 Section 5.7.2.215, tx (Chart Text) | 720 |
| 2.1.1609 | Part 4 Section 5.7.2.216, tx (Series Text) | 721 |
| 2.1.1610 | Part 4 Section 5.7.2.217, txPr (Text Properties) | 721 |
| 2.1.1611 | Part 4 Section 5.7.2.220, userInterface (User Interface) | 721 |
| 2.1.1612 | Part 4 Section 5.7.2.224, v (Numeric Value) | 721 |
| 2.1.1613 | Part 4 Section 5.7.2.226, val (Error Bar Value) | 722 |
| 2.1.1614 | Part 4 Section 5.7.2.227, valAx (Value Axis) | 722 |
| 2.1.1615 | Part 4 Section 5.7.2.228, varyColors (Vary Colors by Point) | 722 |
| 2.1.1616 | Part 4 Section 5.7.2.229, view3D (View In 3D) | 723 |
| 2.1.1617 | Part 4 Section 5.7.2.230, w (Width) | 723 |
| 2.1.1618 | Part 4 Section 5.7.2.231, wireframe (Wireframe) | 723 |
| 2.1.1619 | Part 4 Section 5.7.2.232, wMode (Width Mode) | 723 |
| 2.1.1620 | Part 4 Section 5.7.2.233, x (Left) | 723 |
| 2.1.1621 | Part 4 Section 5.7.2.234, xMode (Left Mode) | 724 |
| 2.1.1622 | Part 4 Section 5.7.2.236, y (Top) | 724 |
| 2.1.1623 | Part 4 Section 5.7.2.237, yMode (Top Mode) | 724 |
| 2.1.1624 | Part 4 Section 5.7.3.1, ST_AxisUnit (Axis Unit) | 724 |
| 2.1.1625 | Part 4 Section 5.7.3.3, ST_BarDir (Bar Direction) | 725 |
| 2.1.1626 | Part 4 Section 5.7.3.4, ST_BarGrouping (Bar Grouping) | 725 |
| 2.1.1627 | Part 4 Section 5.7.3.6, ST_BuiltInUnit (Built-In Unit) | 725 |
| 2.1.1628 | Part 4 Section 5.7.3.8, ST_Crosses (Crosses) | 725 |
| 2.1.1629 | Part 4 Section 5.7.3.9, ST_DepthPercent (Depth Percent) | 725 |
| 2.1.1630 | Part 4 Section 5.7.3.14, ST_ErrValType (Error Value Type) | 725 |
| 2.1.1631 | Part 4 Section 5.7.3.17, ST_Grouping (Grouping) | 726 |
| 2.1.1632 | Part 4 Section 5.7.3.18, ST_HoleSize (Hole Size) | 726 |
| 2.1.1633 | Part 4 Section 5.7.3.20, ST_LayoutMode (Layout Mode) | 726 |
| 2.1.1634 | Part 4 Section 5.7.3.27, ST_MarkerStyle (Marker Style) | 726 |
| 2.1.1635 | Part 4 Section 5.7.3.30, ST_Orientation (Orientation) | 726 |
| 2.1.1636 | Part 4 Section 5.7.3.33, ST_Period (Period) | 727 |
| 2.1.1637 | Part 4 Section 5.7.3.34, ST_Perspective (Perspective) | 727 |
| 2.1.1638 | Part 4 Section 5.7.3.35, ST_PictureFormat (Picture Format) | 727 |
| 2.1.1639 | Part 4 Section 5.7.3.36, ST_PictureStackUnit (Picture Stack Unit) | 727 |
| 2.1.1640 | Part 4 Section 5.7.3.37, ST_RadarStyle (Radar Style) | 727 |
| 2.1.1641 | Part 4 Section 5.7.3.40, ST_ScatterStyle (Scatter Style) | 727 |
| 2.1.1642 | Part 4 Section 5.7.3.42, ST_Shape (Shape) | 728 |
| 2.1.1643 | Part 4 Section 5.7.3.44, ST_Skip (Skip) | 728 |
| 2.1.1644 | Part 4 Section 5.7.3.45, ST_SplitType (Split Type) | 728 |
| 2.1.1645 | Part 4 Section 5.7.3.46, ST_Style (Style) | 728 |
| 2.1.1646 | Part 4 Section 5.7.3.51, ST_TrendlineType (Trendline Type) | 730 |
| 2.1.1647 | Part 4 Section 5.7.3.52, ST_Xstring (String With Encoded Characters) | 730 |
| 2.1.1648 | Part 4 Section 5.8.2.1, absSizeAnchor (Absolute Anchor Shape Size) | 730 |
| 2.1.1649 | Part 4 Section 5.8.2.2, blipFill (Picture Fill) | 730 |
| 2.1.1650 | Part 4 Section 5.8.2.7, cNvPr (Non-Visual Drawing Properties) | 730 |

| | | |
|----------|--|-----|
| 2.1.1651 | Part 4 Section 5.8.2.9, cxnSp (Connection Shape) | 730 |
| 2.1.1652 | Part 4 Section 5.8.2.10, ext (Shape Extent) | 731 |
| 2.1.1653 | Part 4 Section 5.8.2.12, graphicFrame (Graphic Frame) | 731 |
| 2.1.1654 | Part 4 Section 5.8.2.14, grpSpPr (Group Shape Properties) | 731 |
| 2.1.1655 | Part 4 Section 5.8.2.20, pic (Picture) | 731 |
| 2.1.1656 | Part 4 Section 5.8.2.21, relSizeAnchor (Relative Anchor Shape Size) | 731 |
| 2.1.1657 | Part 4 Section 5.8.2.22, sp (Shape) | 732 |
| 2.1.1658 | Part 4 Section 5.8.2.23, spPr (Shape Properties) | 732 |
| 2.1.1659 | Part 4 Section 5.8.2.24, style (Shape Style) | 732 |
| 2.1.1660 | Part 4 Section 5.8.2.25, to (Ending Anchor Point) | 732 |
| 2.1.1661 | Part 4 Section 5.8.2.26, txBody (Shape Text Body) | 733 |
| 2.1.1662 | Part 4 Section 5.8.2.28, xfrm (Graphic Frame Transform) | 733 |
| 2.1.1663 | Part 4 Section 5.9.2.7, clrData (Color Transform Sample Data) | 733 |
| 2.1.1664 | Part 4 Section 5.9.2.13, extLst (Extension List) | 733 |
| 2.1.1665 | Part 4 Section 5.9.2.14, forEach (For Each) | 733 |
| 2.1.1666 | Part 4 Section 5.9.2.20, param (Parameter) | 734 |
| 2.1.1667 | Part 4 Section 5.9.2.26, sampData (Sample Data) | 734 |
| 2.1.1668 | Part 4 Section 5.9.2.27, shape (Shape) | 734 |
| 2.1.1669 | Part 4 Section 5.9.2.29, styleData (Style Data) | 734 |
| 2.1.1670 | Part 4 Section 5.9.3.2, cxn (Connection) | 734 |
| 2.1.1671 | Part 4 Section 5.9.3.4, prSet (Property Set) | 734 |
| 2.1.1672 | Part 4 Section 5.9.3.5, pt (Point) | 735 |
| 2.1.1673 | Part 4 Section 5.9.3.7, spPr (Shape Properties) | 735 |
| 2.1.1674 | Part 4 Section 5.9.3.8, t (Text Body) | 735 |
| 2.1.1675 | Part 4 Section 5.9.4.3, colorsDef (Color Transform Definitions) | 735 |
| 2.1.1676 | Part 4 Section 5.9.4.7, effectClrLst (Effect Color List) | 735 |
| 2.1.1677 | Part 4 Section 5.9.4.8, fillClrLst (Fill Color List) | 735 |
| 2.1.1678 | Part 4 Section 5.9.4.9, linClrLst (Line Color List) | 735 |
| 2.1.1679 | Part 4 Section 5.9.4.12, txEffectClrLst (Text Effect Color List) | 736 |
| 2.1.1680 | Part 4 Section 5.9.4.13, txFillClrLst (Text Fill Color List) | 736 |
| 2.1.1681 | Part 4 Section 5.9.4.14, txLinClrLst (Text Line Color List) | 736 |
| 2.1.1682 | Part 4 Section 5.9.5.6, sp3d (3-D Shape Properties) | 736 |
| 2.1.1683 | Part 4 Section 5.9.5.10, styleLbl (Style Label) | 736 |
| 2.1.1684 | Part 4 Section 5.9.7.3, ST_AnimOneStr (One by One Animation Value Definition) | 736 |
| 2.1.1685 | Part 4 Section 5.9.7.6, ST_AxisType (Axis Type) | 736 |
| 2.1.1686 | Part 4 Section 5.9.7.25, ST_ElementType (Element Type) | 736 |
| 2.1.1687 | Part 4 Section 5.9.7.48, ST_ParameterId (Parameter Identifier) | 737 |
| 2.1.1688 | Part 4 Section 5.9.7.55, ST_SecondaryChildAlignment (Secondary Child Alignment) | 741 |
| 2.1.1689 | Part 4 Section 5.9.7.56, ST_SecondaryLinearDirection (Secondary Linear Direction) | 742 |
| 2.1.1690 | Part 4 Section 6.1, VML | 742 |
| 2.1.1691 | Part 4 Section 6.1.2.1, arc (Arc Segment) | 742 |
| 2.1.1692 | Part 4 Section 6.1.2.2, background (Document Background) | 750 |
| 2.1.1693 | Part 4 Section 6.1.2.3, curve (Bezier Curve) | 751 |
| 2.1.1694 | Part 4 Section 6.1.2.4, f (Single Formula) | 751 |
| 2.1.1695 | Part 4 Section 6.1.2.5, fill (Shape Fill Properties) | 752 |
| 2.1.1696 | Part 4 Section 6.1.2.6, formulas (Set of Formulas) | 754 |
| 2.1.1697 | Part 4 Section 6.1.2.7, group (Shape Group) | 754 |
| 2.1.1698 | Part 4 Section 6.1.2.8, h (Shape Handle) | 754 |
| 2.1.1699 | Part 4 Section 6.1.2.9, handles (Set of Handles) | 754 |
| 2.1.1700 | Part 4 Section 6.1.2.10, image (Image File) | 755 |

| | | |
|----------|---|-----|
| 2.1.1701 | Part 4 Section 6.1.2.11, imagedata (Image Data) | 756 |
| 2.1.1702 | Part 4 Section 6.1.2.12, line (Line) | 757 |
| 2.1.1703 | Part 4 Section 6.1.2.13, oval (Oval) | 758 |
| 2.1.1704 | Part 4 Section 6.1.2.14, path (Shape Path) | 758 |
| 2.1.1705 | Part 4 Section 6.1.2.15, polyline (Multiple Path Line) | 761 |
| 2.1.1706 | Part 4 Section 6.1.2.16, rect (Rectangle) | 761 |
| 2.1.1707 | Part 4 Section 6.1.2.17, roundrect (Rounded Rectangle) | 761 |
| 2.1.1708 | Part 4 Section 6.1.2.18, shadow (Shadow Effect) | 762 |
| 2.1.1709 | Part 4 Section 6.1.2.19, shape (Shape Definition) | 763 |
| 2.1.1710 | Part 4 Section 6.1.2.20, shapetype (Shape Template) | 763 |
| 2.1.1711 | Part 4 Section 6.1.2.21, stroke (Line Stroke Settings) | 764 |
| 2.1.1712 | Part 4 Section 6.1.2.22, textbox (Text Box) | 765 |
| 2.1.1713 | Part 4 Section 6.1.2.23, textpath (Text Layout Path) | 767 |
| 2.1.1714 | Part 4 Section 6.1.3.1, ST_ColorType (Color Type) | 768 |
| 2.1.1715 | Part 4 Section 6.1.3.3, ST_Ext (VML Extension Handling Behaviors) | 771 |
| 2.1.1716 | Part 4 Section 6.1.3.4, ST_FillMethod (Gradient Fill Computation Type) | 772 |
| 2.1.1717 | Part 4 Section 6.1.3.5, ST_FillType (Shape Fill Type) | 772 |
| 2.1.1718 | Part 4 Section 6.1.3.7, ST_ShadowType (Shadow Type) | 772 |
| 2.1.1719 | Part 4 Section 6.2.2.1, bottom (Text Box Bottom Stroke) | 772 |
| 2.1.1720 | Part 4 Section 6.2.2.2, callout (Callout) | 774 |
| 2.1.1721 | Part 4 Section 6.2.2.3, clippath (Shape Clipping Path) | 776 |
| 2.1.1722 | Part 4 Section 6.2.2.4, colormenu (UI Default Colors) | 776 |
| 2.1.1723 | Part 4 Section 6.2.2.5, colormru (Most Recently Used Colors) | 777 |
| 2.1.1724 | Part 4 Section 6.2.2.6, column (Text Box Interior Stroke) | 777 |
| 2.1.1725 | Part 4 Section 6.2.2.7, complex (Complex) | 778 |
| 2.1.1726 | Part 4 Section 6.2.2.8, diagram (VML Diagram) | 778 |
| 2.1.1727 | Part 4 Section 6.2.2.10, extrusion (3D Extrusion) | 779 |
| 2.1.1728 | Part 4 Section 6.2.2.11, FieldCodes (WordprocessingML Field Switches) | 781 |
| 2.1.1729 | Part 4 Section 6.2.2.12, fill (Shape Fill Extended Properties) | 781 |
| 2.1.1730 | Part 4 Section 6.2.2.13, idmap (Shape ID Map) | 781 |
| 2.1.1731 | Part 4 Section 6.2.2.14, ink (Ink) | 782 |
| 2.1.1732 | Part 4 Section 6.2.2.15, left (Text Box Left Stroke) | 782 |
| 2.1.1733 | Part 4 Section 6.2.2.16, LinkType (Embedded Object Alternate Image Request) | 783 |
| 2.1.1734 | Part 4 Section 6.2.2.17, lock (Shape Protections) | 783 |
| 2.1.1735 | Part 4 Section 6.2.2.18, LockedField (Embedded Object Cannot Be Refreshed) | 783 |
| 2.1.1736 | Part 4 Section 6.2.2.19, OLEObject (Embedded OLE Object) | 784 |
| 2.1.1737 | Part 4 Section 6.2.2.20, proxy (Shape Reference) | 784 |
| 2.1.1738 | Part 4 Section 6.2.2.21, r (Rule) | 785 |
| 2.1.1739 | Part 4 Section 6.2.2.23, rel (Diagram Relationship) | 785 |
| 2.1.1740 | Part 4 Section 6.2.2.25, right (Text Box Right Stroke) | 785 |
| 2.1.1741 | Part 4 Section 6.2.2.27, shapedefaults (New Shape Defaults) | 786 |
| 2.1.1742 | Part 4 Section 6.2.2.28, shapelayout (Shape Layout Properties) | 787 |
| 2.1.1743 | Part 4 Section 6.2.2.29, signatureline (Digital Signature Line) | 787 |
| 2.1.1744 | Part 4 Section 6.2.2.30, skew (Skew Transform) | 787 |
| 2.1.1745 | Part 4 Section 6.2.2.31, top (Text Box Top Stroke) | 788 |
| 2.1.1746 | Part 4 Section 6.2.3.2, ST_BWMode (Black And White Modes) | 788 |
| 2.1.1747 | Part 4 Section 6.2.3.3, ST_CalloutDrop (Callout Drop Location) | 788 |
| 2.1.1748 | Part 4 Section 6.2.3.5, ST_ColorType (Color Type) | 789 |
| 2.1.1749 | Part 4 Section 6.2.3.11, ST_FillType (Shape Fill Type) | 792 |
| 2.1.1750 | Part 4 Section 6.3.2.2, borderbottom (Bottom Border) | 792 |
| 2.1.1751 | Part 4 Section 6.3.2.3, borderleft (Left Border) | 792 |
| 2.1.1752 | Part 4 Section 6.3.2.4, borderright (Right Border) | 792 |

| | | |
|----------|--|-----|
| 2.1.1753 | Part 4 Section 6.3.2.5, bordertop (Top Border) | 792 |
| 2.1.1754 | Part 4 Section 6.3.2.6, wrap (Text Wrapping) | 792 |
| 2.1.1755 | Part 4 Section 6.3.3.3, ST_HorizontalAnchor (Horizontal Anchor Type) | 792 |
| 2.1.1756 | Part 4 Section 6.3.3.4, ST_VerticalAnchor (Vertical Anchor Type) | 792 |
| 2.1.1757 | Part 4 Section 6.4.2.1, Accel (Primary Keyboard Accelerator) | 792 |
| 2.1.1758 | Part 4 Section 6.4.2.2, Accel2 (Secondary Keyboard Accelerator) | 792 |
| 2.1.1759 | Part 4 Section 6.4.2.3, Anchor (Anchor) | 793 |
| 2.1.1760 | Part 4 Section 6.4.2.4, AutoFill (AutoFill) | 793 |
| 2.1.1761 | Part 4 Section 6.4.2.5, AutoLine (AutoLine) | 793 |
| 2.1.1762 | Part 4 Section 6.4.2.7, AutoScale (Font AutoScale) | 793 |
| 2.1.1763 | Part 4 Section 6.4.2.8, Camera (Camera Tool) | 793 |
| 2.1.1764 | Part 4 Section 6.4.2.10, CF (Clipboard Format) | 794 |
| 2.1.1765 | Part 4 Section 6.4.2.12, ClientData (Attached Object Data) | 794 |
| 2.1.1766 | Part 4 Section 6.4.2.13, ColHidden (Comment's Column is Hidden) | 794 |
| 2.1.1767 | Part 4 Section 6.4.2.14, Colored (Dropdown Color Toggle) | 794 |
| 2.1.1768 | Part 4 Section 6.4.2.16, DDE (Dynamic Data Exchange) | 794 |
| 2.1.1769 | Part 4 Section 6.4.2.18, DefaultSize (Default Size Toggle) | 794 |
| 2.1.1770 | Part 4 Section 6.4.2.21, DropLines (Dropdown Maximum Lines) | 794 |
| 2.1.1771 | Part 4 Section 6.4.2.22, DropStyle (Dropdown Style) | 795 |
| 2.1.1772 | Part 4 Section 6.4.2.23, Dx (Scroll Bar Width) | 795 |
| 2.1.1773 | Part 4 Section 6.4.2.25, FmlaGroup (Linked Formula - Group Box) | 795 |
| 2.1.1774 | Part 4 Section 6.4.2.27, FmlaMacro (Reference to Custom Function) | 795 |
| 2.1.1775 | Part 4 Section 6.4.2.29, FmlaRange (List Items Source Range) | 795 |
| 2.1.1776 | Part 4 Section 6.4.2.30, FmlaTxbx (Text Formula) | 795 |
| 2.1.1777 | Part 4 Section 6.4.2.32, Horiz (Scroll Bar Orientation) | 795 |
| 2.1.1778 | Part 4 Section 6.4.2.33, Inc (Scroll Bar Increment) | 796 |
| 2.1.1779 | Part 4 Section 6.4.2.35, LCT (Callback Type) | 796 |
| 2.1.1780 | Part 4 Section 6.4.2.36, ListItem (Non-linked List Item) | 796 |
| 2.1.1781 | Part 4 Section 6.4.2.40, Max (Scroll Bar Maximum) | 796 |
| 2.1.1782 | Part 4 Section 6.4.2.41, Min (Scroll Bar Minimum) | 796 |
| 2.1.1783 | Part 4 Section 6.4.2.42, MoveWithCells (Move with Cells) | 796 |
| 2.1.1784 | Part 4 Section 6.4.2.45, NoThreeD (Disable 3D) | 796 |
| 2.1.1785 | Part 4 Section 6.4.2.47, Page (Scroll Bar Page Increment) | 796 |
| 2.1.1786 | Part 4 Section 6.4.2.49, RecalcAlways (Recalculation Toggle) | 797 |
| 2.1.1787 | Part 4 Section 6.4.2.51, RowHidden (Comment's Row is Hidden) | 797 |
| 2.1.1788 | Part 4 Section 6.4.2.59, SizeWithCells (Resize with Cells) | 797 |
| 2.1.1789 | Part 4 Section 6.4.2.61, TextVAlign (Vertical Text Alignment) | 797 |
| 2.1.1790 | Part 4 Section 6.4.2.62, UIObj (UI Object Toggle) | 797 |
| 2.1.1791 | Part 4 Section 6.4.2.63, Val (Scroll bar position) | 797 |
| 2.1.1792 | Part 4 Section 6.4.2.64, ValidIds (Valid ID) | 797 |
| 2.1.1793 | Part 4 Section 6.4.2.68, WidthMin (Minimum Width) | 797 |
| 2.1.1794 | Part 4 Section 6.4.3.3, ST_TrueFalseBlank (Boolean Value with Blank State) | 798 |
| 2.1.1795 | Part 4 Section 6.5.2.2, textdata (VML Diagram Text) | 798 |
| 2.1.1796 | Part 4 Section 7.1, Math | 798 |
| 2.1.1797 | Part 4 Section 7.1.2.1, acc (Accent) | 798 |
| 2.1.1798 | Part 4 Section 7.1.2.3, aln (Alignment) | 798 |
| 2.1.1799 | Part 4 Section 7.1.2.6, argSz (Argument Size) | 799 |
| 2.1.1800 | Part 4 Section 7.1.2.7, bar (Bar) | 799 |
| 2.1.1801 | Part 4 Section 7.1.2.8, barPr (Bar Properties) | 799 |
| 2.1.1802 | Part 4 Section 7.1.2.9, baseJc (Matrix Base Justification) | 799 |
| 2.1.1803 | Part 4 Section 7.1.2.11, borderBox (Border-Box Function) | 800 |
| 2.1.1804 | Part 4 Section 7.1.2.13, box (Box Function) | 800 |
| 2.1.1805 | Part 4 Section 7.1.2.15, brk (Break) | 800 |

| | | |
|----------|--|-----|
| 2.1.1806 | Part 4 Section 7.1.2.16, brkBin (Break on Binary Operators) | 800 |
| 2.1.1807 | Part 4 Section 7.1.2.17, brkBinSub (Break on Binary Subtraction) | 801 |
| 2.1.1808 | Part 4 Section 7.1.2.18, cGp (Matrix Column Gap) | 801 |
| 2.1.1809 | Part 4 Section 7.1.2.19, cGpRule (Matrix Column Gap Rule) | 801 |
| 2.1.1810 | Part 4 Section 7.1.2.20, chr (Accent Character) | 801 |
| 2.1.1811 | Part 4 Section 7.1.2.21, count (Matrix Column Count) | 801 |
| 2.1.1812 | Part 4 Section 7.1.2.22, cSp (Matrix Column Spacing) | 802 |
| 2.1.1813 | Part 4 Section 7.1.2.23, ctrlPr (Control Properties) | 803 |
| 2.1.1814 | Part 4 Section 7.1.2.24, d (Delimiter Function) | 803 |
| 2.1.1815 | Part 4 Section 7.1.2.25, defJc (Default Justification) | 803 |
| 2.1.1816 | Part 4 Section 7.1.2.26, deg (Degree) | 803 |
| 2.1.1817 | Part 4 Section 7.1.2.27, degHide (Hide Degree) | 803 |
| 2.1.1818 | Part 4 Section 7.1.2.28, den (Denominator) | 803 |
| 2.1.1819 | Part 4 Section 7.1.2.30, dispDef (Use Display Math Defaults) | 803 |
| 2.1.1820 | Part 4 Section 7.1.2.32, e (Base (Argument)) | 804 |
| 2.1.1821 | Part 4 Section 7.1.2.34, eqArr (Equation-Array Function) | 804 |
| 2.1.1822 | Part 4 Section 7.1.2.36, f (Fraction Function) | 805 |
| 2.1.1823 | Part 4 Section 7.1.2.37, fName (Function Name) | 805 |
| 2.1.1824 | Part 4 Section 7.1.2.39, func (Function Apply Function) | 805 |
| 2.1.1825 | Part 4 Section 7.1.2.41, groupChr (Group-Character Function) | 805 |
| 2.1.1826 | Part 4 Section 7.1.2.42, groupChrPr (Group-Character Properties) | 805 |
| 2.1.1827 | Part 4 Section 7.1.2.43, grow (n-ary Grow) | 805 |
| 2.1.1828 | Part 4 Section 7.1.2.48, interSp (Inter-Equation Spacing) | 806 |
| 2.1.1829 | Part 4 Section 7.1.2.49, intLim (Integral Limit Locations) | 806 |
| 2.1.1830 | Part 4 Section 7.1.2.50, intraSp (Intra-Equation Spacing) | 806 |
| 2.1.1831 | Part 4 Section 7.1.2.51, jc (Justification) | 806 |
| 2.1.1832 | Part 4 Section 7.1.2.52, lim (Limit (Lower)) | 806 |
| 2.1.1833 | Part 4 Section 7.1.2.53, limLoc (n-ary Limit Location) | 806 |
| 2.1.1834 | Part 4 Section 7.1.2.54, limLow (Lower-Limit Function) | 807 |
| 2.1.1835 | Part 4 Section 7.1.2.56, limUpp (Upper-Limit Function) | 807 |
| 2.1.1836 | Part 4 Section 7.1.2.58, lit (Literal) | 807 |
| 2.1.1837 | Part 4 Section 7.1.2.59, lMargin (Left Margin) | 807 |
| 2.1.1838 | Part 4 Section 7.1.2.60, m (Matrix Function) | 807 |
| 2.1.1839 | Part 4 Section 7.1.2.61, mathFont (Math Font) | 807 |
| 2.1.1840 | Part 4 Section 7.1.2.63, maxDist (Maximum Distribution) | 808 |
| 2.1.1841 | Part 4 Section 7.1.2.64, mc (Matrix Column) | 808 |
| 2.1.1842 | Part 4 Section 7.1.2.67, mcs (Matrix Columns) | 808 |
| 2.1.1843 | Part 4 Section 7.1.2.69, mr (Matrix Row) | 808 |
| 2.1.1844 | Part 4 Section 7.1.2.70, nary (n-ary Operator Function) | 808 |
| 2.1.1845 | Part 4 Section 7.1.2.71, naryLim (n-ary Limit Location) | 808 |
| 2.1.1846 | Part 4 Section 7.1.2.73, noBreak (No Break) | 808 |
| 2.1.1847 | Part 4 Section 7.1.2.75, num (Numerator) | 809 |
| 2.1.1848 | Part 4 Section 7.1.2.76, objDist (Object Distribution) | 809 |
| 2.1.1849 | Part 4 Section 7.1.2.77, oMath (Office Math) | 809 |
| 2.1.1850 | Part 4 Section 7.1.2.78, oMathPara (Math Paragraph) | 810 |
| 2.1.1851 | Part 4 Section 7.1.2.80, opEmu (Operator Emulator) | 811 |
| 2.1.1852 | Part 4 Section 7.1.2.81, phant (Phantom Function) | 811 |
| 2.1.1853 | Part 4 Section 7.1.2.84, pos (Position) | 812 |
| 2.1.1854 | Part 4 Section 7.1.2.85, postSp (Post-Equation Spacing) | 812 |
| 2.1.1855 | Part 4 Section 7.1.2.86, preSp (Pre-Equation Spacing) | 812 |
| 2.1.1856 | Part 4 Section 7.1.2.87, r (Run) | 812 |
| 2.1.1857 | Part 4 Section 7.1.2.88, rad (Radical Function) | 812 |
| 2.1.1858 | Part 4 Section 7.1.2.90, rMargin (Right Margin) | 812 |

| | | |
|----------|---|-----|
| 2.1.1859 | Part 4 Section 7.1.2.92, rSp (Row Spacing) | 813 |
| 2.1.1860 | Part 4 Section 7.1.2.93, rSpRule (Row Spacing Rule) | 813 |
| 2.1.1861 | Part 4 Section 7.1.2.94, scr (Script) | 813 |
| 2.1.1862 | Part 4 Section 7.1.2.97, shp (Shape (Delimiters)) | 813 |
| 2.1.1863 | Part 4 Section 7.1.2.98, smallFrac (Small Fraction) | 814 |
| 2.1.1864 | Part 4 Section 7.1.2.99, sPre (Pre-Sub-Superscript Function) | 814 |
| 2.1.1865 | Part 4 Section 7.1.2.101, sSub (Subscript Function) | 814 |
| 2.1.1866 | Part 4 Section 7.1.2.103, sSubSup (Sub-Superscript Function) | 814 |
| 2.1.1867 | Part 4 Section 7.1.2.105, sSup (Superscript Function) | 814 |
| 2.1.1868 | Part 4 Section 7.1.2.111, sty (style) | 814 |
| 2.1.1869 | Part 4 Section 7.1.2.112, sub (Subscript (Pre-Sub-Superscript)) | 815 |
| 2.1.1870 | Part 4 Section 7.1.2.113, subHide (Hide Subscript (n-ary)) | 815 |
| 2.1.1871 | Part 4 Section 7.1.2.114, sup (Superscript (Superscript function)) | 815 |
| 2.1.1872 | Part 4 Section 7.1.2.115, supHide (Hide Superscript (n-ary)) | 815 |
| 2.1.1873 | Part 4 Section 7.1.2.116, t (Text) | 815 |
| 2.1.1874 | Part 4 Section 7.1.2.117, transp (Transparent (Phantom)) | 815 |
| 2.1.1875 | Part 4 Section 7.1.3.1, ST_BreakBin (Break Binary Operators) | 816 |
| 2.1.1876 | Part 4 Section 7.1.3.7, ST_Jc (Justification) | 816 |
| 2.1.1877 | Part 4 Section 7.1.3.11, ST_Shp (Shape (Delimiters)) | 816 |
| 2.1.1878 | Part 4 Section 7.1.3.15, ST_TopBot (Top-Bottom) | 816 |
| 2.1.1879 | Part 4 Section 7.1.3.16, ST_TwipsMeasure (Twips measurement) | 816 |
| 2.1.1880 | Part 4 Section 7.1.3.17, ST_UnSignedInteger (Unsigned integer.) | 816 |
| 2.1.1881 | Part 4 Section 7.1.3.19, ST_YAlign (Vertical Alignment) | 816 |
| 2.1.1882 | Part 4 Section 7.2.2.2, AppVersion (Application Version) | 817 |
| 2.1.1883 | Part 4 Section 7.2.2.6, DigSig (Digital Signature) | 817 |
| 2.1.1884 | Part 4 Section 7.2.2.7, DocSecurity (Document Security) | 817 |
| 2.1.1885 | Part 4 Section 7.2.2.8, HeadingPairs (Heading Pairs) | 817 |
| 2.1.1886 | Part 4 Section 7.2.2.10, HLinks (Hyperlink List) | 818 |
| 2.1.1887 | Part 4 Section 7.2.2.26, TitlesOfParts (Part Titles) | 818 |
| 2.1.1888 | Part 4 Section 7.2.2.27, TotalTime (Total Edit Time Metadata Element) | 819 |
| 2.1.1889 | Part 4 Section 7.3.2.2, property (Custom File Property) | 819 |
| 2.1.1890 | Part 4 Section 7.4, Variant Types | 821 |
| 2.1.1891 | Part 4 Section 7.4.2.1, array (Array) | 822 |
| 2.1.1892 | Part 4 Section 7.4.2.5, cf (Clipboard Data) | 822 |
| 2.1.1893 | Part 4 Section 7.4.2.6, clsid (Class ID) | 822 |
| 2.1.1894 | Part 4 Section 7.4.2.7, cy (Currency) | 822 |
| 2.1.1895 | Part 4 Section 7.4.2.8, date (Date and Time) | 823 |
| 2.1.1896 | Part 4 Section 7.4.2.10, empty (Empty) | 823 |
| 2.1.1897 | Part 4 Section 7.4.2.12, filetime (File Time) | 823 |
| 2.1.1898 | Part 4 Section 7.4.2.20, null (Null) | 823 |
| 2.1.1899 | Part 4 Section 7.4.2.22, ostorage (Binary Storage Object) | 823 |
| 2.1.1900 | Part 4 Section 7.4.2.26, storage (Binary Storage) | 823 |
| 2.1.1901 | Part 4 Section 7.4.2.35, vstream (Binary Versioned Stream) | 823 |
| 2.1.1902 | Part 4 Section 7.4.3.4, ST_Error (Error Status Code Simple Type) | 823 |
| 2.1.1903 | Part 4 Section 7.4.3.5, ST_Format (Format Simple Type) | 824 |
| 2.1.1904 | Part 4 Section 7.6.2.5, Author (Contributors List) | 824 |
| 2.1.1905 | Part 4 Section 7.6.2.30, Guid (GUID) | 824 |
| 2.1.1906 | Part 4 Section 7.6.2.39, LCID (Locale ID) | 824 |
| 2.1.1907 | Part 4 Section 7.6.2.50, Person (Person) | 832 |
| 2.1.1908 | Part 4 Section 7.6.2.59, Source (Source) | 832 |
| 2.1.1909 | Part 4 Section 7.6.2.65, Tag (Tag) | 832 |
| 2.1.1910 | Part 4 Section 7.6.2.76, YearAccessed (Year Accessed) | 832 |
| 2.1.1911 | Part 4 Section 7.8.2.1, ST_RelationshipId (Explicit Relationship ID) | 832 |

| | | |
|----------|--|-----|
| 2.1.1912 | Part 4 Section 8.2.1, schema (Custom XML Schema Reference) | 833 |
| 2.1.1913 | Part 5 Section 9, Markup Compatibility Attributes and Elements | 833 |

| | | |
|--------------|--|------------|
| 3 | Appendix A: Additional Information | 834 |
| 3.1 | Word | 834 |
| 3.1.1 | Additional Parts | 834 |
| 3.1.1.1 | Word Attached Toolbars Part | 834 |
| 3.1.1.2 | Customizations Part | 834 |
| 3.1.1.3 | Mail Merge Recipient Data Part | 836 |
| 3.1.2 | Word Schema | 837 |
| 3.1.2.1 | Keyboard and Toolbar Customizations | 837 |
| 3.1.2.1.1 | Elements | 837 |
| 3.1.2.1.1.1 | acd (Allocated Command) | 837 |
| 3.1.2.1.1.2 | acd (Allocated Command Keyboard Customization Action) | 838 |
| 3.1.2.1.1.3 | acdEntry (Allocated Command Manifest Entry) | 839 |
| 3.1.2.1.1.4 | acdManifest (Allocated Command Manifest) | 840 |
| 3.1.2.1.1.5 | acds (Allocated Commands) | 840 |
| 3.1.2.1.1.6 | active (Record Is Included in Mail Merge) | 841 |
| 3.1.2.1.1.7 | fci (Fixed Command Keyboard Customization Action) | 842 |
| 3.1.2.1.1.8 | keymap (Key Map Entry) | 843 |
| 3.1.2.1.1.9 | keymaps (Key Map Customizations) | 845 |
| 3.1.2.1.1.10 | keymapsBad (Key Map Customizations for Mismatched Keyboards) | 846 |
| 3.1.2.1.1.11 | macro (Macro Keyboard Customization Action) | 847 |
| 3.1.2.1.1.12 | tcg (Keyboard and Toolbar Customizations) | 848 |
| 3.1.2.1.1.13 | toolbarData (Toolbar data) | 849 |
| 3.1.2.1.1.14 | toolbars (Legacy Toolbar Customizations) | 849 |
| 3.1.2.1.1.15 | wch (Character Insertion Keyboard Customization Action) | 850 |
| 3.1.2.1.1.16 | wll (WLL Macro Keyboard Customization Action) | 851 |
| 3.1.2.1.2 | Fixed Commands | 851 |
| 3.1.2.1.3 | Statements | 916 |
| 3.1.2.2 | Mail Merge | 931 |
| 3.1.2.2.1 | Elements | 932 |
| 3.1.2.2.1.1 | hash (Hash Code for Record) | 932 |
| 3.1.2.2.1.2 | recipientData (Data About Single Data Source Record) | 933 |
| 3.1.2.2.1.3 | recipients (Inclusion/Exclusion Data for Data Source) | 935 |
| 3.1.2.3 | Simple Types | 936 |
| 3.1.2.3.1 | ST_DecimalNumber (Decimal Number Value) | 936 |
| 3.1.2.3.2 | ST_LongHexNumber (Four Digit Hexadecimal Number Value) | 936 |
| 3.1.2.3.3 | ST_OnOff (On/Off Value) | 937 |
| 3.1.2.3.4 | ST_ShortHexNumber (Two Digit Hexadecimal Number Value) | 938 |
| 3.1.2.3.5 | ST_String (String) | 939 |
| 3.1.3 | Additional WordprocessingML Schema | 939 |
| 3.1.3.1 | Additional Elements | 939 |
| 3.1.3.1.1 | customXml (Ruby Inline-Level Custom XML Element) | 939 |
| 3.1.3.1.2 | fldSimple (Ruby Simple Field) | 943 |
| 3.1.3.1.3 | hyperlink (Ruby Hyperlink) | 948 |
| 3.1.3.1.4 | moveFrom (Move Source Math Control Character) | 954 |
| 3.1.3.1.5 | moveTo (Move Destination Math Control Character) | 955 |
| 3.1.3.1.6 | sdt (Ruby Inline-Level Structured Document Tag) | 957 |
| 3.1.3.1.7 | sdtContent (Ruby Inline-Level Structured Document Tag Content) | 959 |
| 3.1.3.2 | Additional Fields | 963 |
| 3.1.3.2.1 | DDE | 963 |
| 3.1.3.2.2 | DDEAUTO | 964 |

| | | |
|-------------|---|-----|
| 3.1.3.2.3 | GLOSSARY | 965 |
| 3.1.3.2.4 | IMPORT | 966 |
| 3.1.3.2.5 | INCLUDE | 966 |
| 3.1.3.2.6 | SHAPE | 967 |
| 3.1.3.3 | Simple Types | 967 |
| 3.1.3.3.1 | ST_CustomXmlURI (URI for Custom XML) | 968 |
| 3.1.3.3.2 | ST_DateTime (Standard Date and Time Storage Format) | 968 |
| 3.1.3.3.3 | ST_MarkupId (Annotation Identifier)..... | 968 |
| 3.1.3.3.4 | ST_NcName255 (Non-colonized Name)..... | 969 |
| 3.1.3.3.5 | ST_NonNegativeDecimalNumber (Non-Negative Decimal Number Value).... | 969 |
| 3.1.3.3.6 | ST_OnOff (On/Off Value) | 970 |
| 3.1.3.3.7 | ST_SignedDecimalNumberMax-2 (Decimal Number Value Max -2)..... | 971 |
| 3.1.3.3.8 | ST_String (String)..... | 971 |
| 3.1.3.3.9 | ST_String255 (String) | 972 |
| 3.1.3.3.10 | ST_String260 (String)..... | 972 |
| 3.1.4 | DrawingML Persistence Part | 973 |
| 3.1.4.1 | DrawingML Persistence Parts..... | 973 |
| 3.1.4.1.1 | Graphic Frame Doc..... | 973 |
| 3.1.4.1.2 | Downrev Storage | 974 |
| 3.1.4.2 | Additional DrawingML - Main Schema | 975 |
| 3.1.4.2.1 | Additional Elements | 975 |
| 3.1.4.2.1.1 | bounds (Bounds) | 975 |
| 3.1.4.2.1.2 | downRevStg (DownRev Storage) | 976 |
| 3.1.4.2.2 | Simple Types..... | 977 |
| 3.1.4.2.2.1 | ST_Coordinate (Coordinate)..... | 977 |
| 3.1.4.3 | Additional DrawingML - WordprocessingML Schema | 977 |
| 3.1.4.3.1 | Additional Elements | 977 |
| 3.1.4.3.1.1 | e2oholder (E2o Holder) | 978 |
| 3.1.4.3.1.2 | effectOffset (Effect Offset) | 978 |
| 3.2 | Excel..... | 979 |
| 3.2.1 | Additional Parts..... | 979 |
| 3.2.1.1 | Excel Attached Toolbars Part..... | 979 |
| 3.2.1.2 | Worksheet Sort Map Part | 980 |
| 3.2.2 | Microsoft Office Excel Sortmap..... | 980 |
| 3.2.2.1 | Sortmap Elements | 981 |
| 3.2.2.1.1 | col (Column) | 982 |
| 3.2.2.1.2 | colSortMap (Column Sort Map) | 983 |
| 3.2.2.1.3 | row (Row) | 984 |
| 3.2.2.1.4 | rowSortMap (Row Sort Map)..... | 984 |
| 3.2.2.1.5 | worksheetSortMap (Worksheet Sort Map)..... | 985 |
| 3.2.2.2 | Simple Types | 985 |
| 3.2.2.2.1 | ST_SortMapCount (Sort Map Count) | 985 |
| 3.2.3 | Additional SpreadsheetML Schema | 986 |
| 3.2.3.1 | Formulas | 986 |
| 3.2.3.1.1 | Structure References | 986 |
| 3.2.3.1.2 | Conditional Formatting Formulas..... | 988 |
| 3.2.3.1.3 | Data Validation Formulas | 989 |
| 3.2.3.1.4 | Name Formulas..... | 989 |
| 3.2.3.1.5 | External Name Formulas | 990 |
| 3.2.3.1.6 | Chart formulas..... | 990 |
| 3.2.3.1.7 | R1C1 formulas..... | 990 |
| 3.2.3.1.8 | Pivot Formulas..... | 991 |
| 3.2.3.1.8.1 | Calculated Field Formulas | 991 |

| | | |
|-------------|--|------|
| 3.2.3.1.8.2 | Calculated Item Formulas | 992 |
| 3.2.3.1.9 | OLE Link Formulas..... | 993 |
| 3.3 | PowerPoint..... | 993 |
| 3.3.1 | Additional Parts..... | 993 |
| 3.3.1.1 | Legacy Diagram Text part..... | 993 |
| 3.3.1.2 | Legacy Diagram Text Info part | 994 |
| 3.3.1.3 | SmartTags part | 994 |
| 3.4 | Shared | 995 |
| 3.4.1 | Additional Parts..... | 995 |
| 3.4.1.1 | Embedded Control Persistence Binary Data Part | 995 |
| 3.4.1.2 | Quick Access Toolbar Customizations Part..... | 996 |
| 3.4.1.3 | Ribbon Extensibility Part | 997 |
| 3.5 | Office Well Defined Custom XML Parts | 998 |
| 3.5.1 | Cover Page Properties..... | 999 |
| 3.5.1.1 | Cover Page Properties Schema | 999 |
| 3.5.1.1.1 | Elements..... | 999 |
| 3.5.1.1.1.1 | Abstract (Document Abstract) | 999 |
| 3.5.1.1.1.2 | CompanyAddress (Company Address) | 999 |
| 3.5.1.1.1.3 | CompanyEmail (Company Email Address)..... | 999 |
| 3.5.1.1.1.4 | CompanyFax (Company Fax Number) | 999 |
| 3.5.1.1.1.5 | CompanyPhone (Company Phone Number) | 1000 |
| 3.5.1.1.1.6 | CoverPageProperties (Cover Page Properties)..... | 1000 |
| 3.5.1.1.1.7 | PublishDate (Document Publish Date) | 1000 |
| 3.5.1.1.2 | Simple Types..... | 1001 |
| 3.5.1.1.2.1 | ST_PublishDate (Publish Date Value) | 1001 |
| 3.5.2 | Content Type Schemas | 1001 |
| 3.5.2.1 | Content Type Schemas Schema..... | 1002 |
| 3.5.2.1.1 | Elements..... | 1002 |
| 3.5.2.1.1.1 | contentTypeSchema (Schema for Content Type) | 1002 |
| 3.5.2.2 | Metadata Attributes | 1006 |
| 3.5.2.2.1 | Shared Attributes (Content Type Schemas) | 1006 |
| 3.5.2.2.2 | Simple Types..... | 1010 |
| 3.5.2.2.2.1 | ST_ContentTypeId (Content Type ID) | 1010 |
| 3.5.2.2.2.2 | ST_IntNonNegative (Non-Negative Integer) | 1010 |
| 3.5.2.2.2.3 | ST_TrueOnly (True Only)..... | 1011 |
| 3.5.2.2.2.4 | ST_UniqueIdentifierWithoutBraces (Unique Identifier without Braces)..... | 1011 |
| 3.5.3 | Custom Document Information Panel..... | 1012 |
| 3.5.3.1 | Custom Document Information Panel Schema | 1012 |
| 3.5.3.1.1 | Elements..... | 1012 |
| 3.5.3.1.1.1 | customPropertyEditor (Custom Property Editor) | 1012 |
| 3.5.3.1.1.2 | customPropertyEditors (Custom Property Editors List) | 1013 |
| 3.5.3.1.1.3 | defaultPropertyEditorNamespace (Default Namespace) | 1013 |
| 3.5.3.1.1.4 | showOnOpen (Show On Open) | 1013 |
| 3.5.3.1.1.5 | XMLNamespace (Namespace for Property Editor)..... | 1014 |
| 3.5.3.1.1.6 | XSNLocation (Location of XSN File) | 1014 |
| 3.5.4 | Custom XSN | 1014 |
| 3.5.4.1 | Custom XSN Schema | 1014 |
| 3.5.4.1.1 | Elements..... | 1014 |
| 3.5.4.1.1.1 | cached (Cached View)..... | 1014 |
| 3.5.4.1.1.2 | customXsn (Custom XSN)..... | 1014 |
| 3.5.4.1.1.3 | openByDefault (Open By Default) | 1015 |
| 3.5.4.1.1.4 | xsnLocation (XSN Location) | 1015 |
| 3.5.4.1.1.5 | xsnScope (Scope)..... | 1015 |

| | | |
|-------------|---|------|
| 3.5.5 | Long Properties | 1015 |
| 3.5.5.1 | Long Properties Schema | 1016 |
| 3.5.5.1.1 | Elements | 1016 |
| 3.5.5.1.1.1 | LongProp (Custom XML Server Property - Long Property) | 1016 |
| 3.5.5.1.1.2 | LongProperties (Custom XML Server Properties - Long Properties) | 1016 |
| 3.6 | Office ActiveX Supplemental Information | 1017 |
| 3.6.1 | Elements | 1017 |
| 3.6.1.1 | font (Standard COM Font Object) | 1017 |
| 3.6.1.2 | ocx (ActiveX Control Data) | 1018 |
| 3.6.1.3 | ocxPr (Object Property) | 1020 |
| 3.6.1.4 | picture (Standard COM Picture Object) | 1021 |
| 3.6.2 | Simple Types | 1022 |
| 3.6.2.1 | ST_Persistence (Control Persistence Attribute Contents) | 1022 |
| 3.6.2.2 | ST_String (String Type) | 1023 |
| 3.7 | Office Digital Signature | 1023 |
| 3.7.1 | Elements | 1023 |
| 3.7.1.1 | ApplicationVersion (Application Version) | 1023 |
| 3.7.1.2 | ColorDepth (Color Depth) | 1024 |
| 3.7.1.3 | DelegateSuggestedSigner (Delegate Suggested Signer) | 1024 |
| 3.7.1.4 | DelegateSuggestedSigner2 (Delegate Suggested Signer) | 1024 |
| 3.7.1.5 | DelegateSuggestedSignerEmail (Delegate Suggested Signer E-mail Address) | 1024 |
| 3.7.1.6 | HorizontalResolution (Horizontal Resolution) | 1025 |
| 3.7.1.7 | ManifestHashAlgorithm (Manifest Hash Algorithm) | 1025 |
| 3.7.1.8 | Monitors (Monitor Count) | 1025 |
| 3.7.1.9 | OfficeVersion (Office Version) | 1026 |
| 3.7.1.10 | SetupID (Setup ID) | 1026 |
| 3.7.1.11 | SignatureComments (Signature Comments) | 1026 |
| 3.7.1.12 | SignatureImage (Signature Image) | 1027 |
| 3.7.1.13 | SignatureInfoV1 (Office Digital Signature V1 Info) | 1027 |
| 3.7.1.14 | SignatureProviderDetails (Signature Provider Details) | 1028 |
| 3.7.1.15 | SignatureProviderId (Signature Provider ID) | 1028 |
| 3.7.1.16 | SignatureProviderUrl (Signature Provider URL) | 1029 |
| 3.7.1.17 | SignatureText (Signature Text) | 1029 |
| 3.7.1.18 | SignatureType (Signature Type) | 1029 |
| 3.7.1.19 | VerticalResolution (Vertical Resolution) | 1030 |
| 3.7.1.20 | WindowsVersion (Windows Version) | 1030 |
| 3.7.2 | Simple Types | 1031 |
| 3.7.2.1 | ST_PositiveInteger (Positive Integer) | 1031 |
| 3.7.2.2 | ST_SignatureComments (Signature Comments) | 1031 |
| 3.7.2.3 | ST_SignatureProviderUrl (Signature Provider URL) | 1031 |
| 3.7.2.4 | ST_SignatureText (Signature Text) | 1032 |
| 3.7.2.5 | ST_SignatureType (Signature Type) | 1032 |
| 3.7.2.6 | ST_UniqueIdentifierWithBraces (Unique Identifier with Braces) | 1033 |
| 3.7.2.7 | ST_Version (Version) | 1033 |
| 3.8 | Equation XML | 1034 |
| 3.8.1 | Introduction | 1034 |
| 3.8.2 | Basic Format | 1034 |
| 3.8.3 | Reading the equationXml attribute | 1035 |
| 3.8.3.1 | Word 2003 XML elements which can contain Office Open XML Math elements | 1036 |
| 3.8.3.2 | Containment of the oMathPara element | 1036 |
| 3.8.3.3 | Containment of Math runs and Math functions and objects | 1036 |
| 3.8.4 | Office Open XML Math elements which can contain Word 2003 XML elements | 1037 |
| 3.8.4.1 | Control Properties | 1037 |

| | | |
|----------|--|-------------|
| 3.8.4.2 | oMath and Math Arguments | 1037 |
| 3.8.4.3 | Math Run..... | 1038 |
| 3.8.5 | Limitations in Word | 1038 |
| 3.9 | Simple Types | 1038 |
| 3.9.1 | ST_Fraction (Fraction Type)..... | 1039 |
| 3.9.2 | ST_Macro (Custom Function Name Type) | 1039 |
| 3.9.3 | ST_ObjID (Object ID) | 1039 |
| 3.9.4 | ST_ObjIDRef (Object ID Reference)..... | 1040 |
| 3.9.5 | ST_ShapeType (Shape Type)..... | 1040 |
| 3.9.6 | ST_SpId (Shape ID Type) | 1046 |
| 4 | Change Tracking..... | 1047 |
| 5 | Index | 1048 |

1 Introduction

In creating an interoperable implementation, it may be helpful to understand specific implementation choices made by other products implementing the same standard. For example, portions of the standard may provide only general guidance, leaving specific implementation choices up to the application implementer; in some circumstances, it may be helpful for other implementers to understand those choices. In addition, products often vary from or extend standards either because of application deviations or to allow for use scenarios not originally envisioned by the specifications. Documentation of those variations and/or extensions may also be helpful to other implementers.

The implementer notes contained in this document provide information about how Office implements ECMA-376 Office Open XML File Formats [\[ECMA-376\]](#), including areas where additional detail may be of benefit to other implementers and areas where the product is known to vary from or extend the specification.

The ECMA-376 standard does not conform to RFC 2119 with respect to consistent usage of MUST, MUST NOT, SHOULD, SHOULD NOT, and MAY. Section 2 of ECMA-376 directs that the user of the word “shall” indicates required behavior. The standard also uses “should”, “must”, “might”, and “may” as normative verbs.

In evaluating Microsoft’s implementation of ECMA-376, the following definitions were applied:

| | |
|------------------------------------|---|
| MUST, SHALL | Indicates required behavior. All deviations from this required behavior are documented in implementer notes. |
| MUST NOT, SHALL NOT, MAY NOT | Indicates a prohibited behavior. All deviations from this prohibition are documented in implementer notes. |
| SHOULD | Indicates recommended, but not required, behavior. Deviations from the suggested behavior are documented in implementer notes on a case-by-case basis. |
| SHOULD NOT | Indicates that the behavior is not recommended, but is not prohibited. Deviations from the suggested behavior are documented in implementer notes on a case-by-case basis. |
| MIGHT, MAY, MIGHT NOT | Indicates truly optional behavior. Deviations from the optional behavior are not documented in implementer notes. Note: MIGHT was not taken as a prohibition for an implementer note. An implementer note is still written if it is necessary for interoperability. |

This is not an exhaustive list of the criteria used in creating implementer notes. For deviations from MUST, MUST NOT, and MAY NOT behaviors, an implementer note was always created. All other situations, as noted, were considered on a case-by-case basis.

1.1 Glossary

MAY, SHOULD, MUST, SHOULD NOT, MUST NOT: These terms (in all caps) are used as described in [\[RFC2119\]](#). All statements of optional behavior use either MAY, SHOULD, or SHOULD NOT.

1.2 References

References to Microsoft Open Specifications documentation do not include a publishing year because links are to the latest version of the documents, which are updated frequently. References to other documents include a publishing year when one is available.

1.2.1 Normative References

We conduct frequent surveys of the normative references to assure their continued availability. If you have any issue with finding a normative reference, please contact dochelp@microsoft.com. We will assist you in finding the relevant information.

[CSS-LEVEL2] Bos, B., Celik, T., Hickson, I., and Lie, H., "Cascading Style Sheets Level 2 Revision 1 (CSS2.1) Specification: W3C Candidate Recommendation", July 2007, <http://www.w3.org/TR/2007/CR-CSS21-20070719/>

[DEVMODE] Microsoft Corporation, "DEVMODE structure", [http://msdn.microsoft.com/en-us/library/dd183565\(VS.85\).aspx](http://msdn.microsoft.com/en-us/library/dd183565(VS.85).aspx)

[ECMA-376] ECMA International, "Office Open XML File Formats", 1st Edition, ECMA-376, December 2006, <http://www.ecma-international.org/publications/standards/Ecma-376.htm>

[Embed-Open-Type-Format] Nelson, P., "Embedded OpenType (EOT) File Format", W3C Member Submission, March 2008, <http://www.w3.org/Submission/2008/SUBM-EOT-20080305/>

[ISO/IEC-29500-1] International Organization for Standardization, "Information technology -- Document description and processing languages -- Office Open XML File Formats -- Part 1: Fundamentals and Markup Language Reference", ISO/IEC 29500-1:2008, http://www.iso.org/iso/iso_catalogue/catalogue_tc/catalogue_detail.htm?csnumber=51463

[ISO-8601] International Organization for Standardization, "Data Elements and Interchange Formats - Information Interchange - Representation of Dates and Times", ISO/IEC 8601:2004, December 2004, <http://www.iso.org/iso/en/CatalogueDetailPage.CatalogueDetail?CSNUMBER=40874&ICS1=1&ICS2=140&ICS3=30>

Note There is a charge to download the specification.

[MC-ISF] Microsoft Corporation, "Ink Serialized Format (ISF) Specification", 2007, [http://download.microsoft.com/download/0/B/E/0BE8BDD7-E5E8-422A-ABFD-4342ED7AD886/InkSerializedFormat\(ISF\)Specification.pdf](http://download.microsoft.com/download/0/B/E/0BE8BDD7-E5E8-422A-ABFD-4342ED7AD886/InkSerializedFormat(ISF)Specification.pdf)

[Micro-Type-Exp-Format] Martin, S., Ristow, A., Martin, S., Levantovsky, V., and Chapman, C., "MicroType Express (MTX) Font Format", W3C Member Submission, March 2008, <http://www.w3.org/Submission/2008/SUBM-MTX-20080305/>

[MS-CFB] Microsoft Corporation, "[Compound File Binary File Format](#)".

[MS-CUSTOMUI] Microsoft Corporation, "[Custom UI XML Markup Specification](#)".

[MS-DOC] Microsoft Corporation, "[Word Binary File Format \(.doc\) Structure Specification](#)".

[MS-EMF] Microsoft Corporation, "[Enhanced Metafile Format](#)".

[MS-EMFPLUS] Microsoft Corporation, "[Enhanced Metafile Format Plus Extensions](#)".

[MS-IPFF] Microsoft Corporation, "[InfoPath Form Template Format](#)".

[MS-LCID] Microsoft Corporation, "[Windows Language Code Identifier \(LCID\) Reference](#)".

[MS-LISTSWS] Microsoft Corporation, "[Lists Web Service Protocol](#)".

[MS-OFORMS] Microsoft Corporation, "[Office Forms Binary File Format\(s\)](#)".

[MS-OSHARED] Microsoft Corporation, "[Office Common Data Types and Objects Structures](#)".

[MS-PPT] Microsoft Corporation, "[PowerPoint Binary File Format \(.ppt\) Structure Specification](#)".

[MS-WMF] Microsoft Corporation, "[Windows Metafile Format](#)".

[MS-WSSCAML] Microsoft Corporation, "[Collaborative Application Markup Language \(CAML\) Structure](#)".

[MS-XLS] Microsoft Corporation, "[Excel Binary File Format \(.xls\) Structure](#)".

[RFC2119] Bradner, S., "Key words for use in RFCs to Indicate Requirement Levels", BCP 14, RFC 2119, March 1997, <http://www.rfc-editor.org/rfc/rfc2119.txt>

[Unicode-Plain-Text-Encoding-Math] Sargent, Murray, III, "Unicode Nearly Plain-Text Encoding of Mathematics", Unicode Technical Note #28, Version 2, August 2006, <http://www.unicode.org/notes/tn28/>

1.2.2 Informative References

None.

1.3 Microsoft Implementations

The implementer notes apply to the following Office products:

Microsoft® Office Excel® 2007

Microsoft® Office Excel® 2007 SP1

Microsoft® Office Excel® 2007 SP2

Microsoft® Office Excel® 2010

Microsoft® Office PowerPoint® 2007

Microsoft® Office PowerPoint® 2007 SP1

Microsoft® Office PowerPoint® 2007 SP2

Microsoft® Office PowerPoint® 2010

Microsoft® Office Word 2007

Microsoft® Office Word 2007 SP1

Microsoft® Office Word 2007 SP2

Microsoft® Office Word 2010

Where appropriate, specific references to these products have been made. Otherwise, these applications are collectively referred to as Office.

2 Conformance Statements

2.1 Normative Variations

This section contains implementation information about how Microsoft® Office Excel® 2007-2010, Microsoft® Office PowerPoint® 2007-2010, and Microsoft® Office Word 2007-2010 implement ECMA-376 Office Open XML File Formats [\[ECMA-376\]](#). The Office Implementation Information section follows the organization of ECMA-376 Office Open XML File Formats [\[ECMA-376\]](#).

2.1.1 Part 1 Section 2.5, Application Conformance

a. *The standard specifies that white space content in strings representing atomic data must be normalized as part of processing.*

Office will only accept XML in which atomic content of attributes and elements is represented with white space content already normalized.

b. *The standard allows INF, NaN, and -INF as legal representations for double and float XML Schema types.*

Office does not accept INF, NaN, and -INF as valid representations for double and float data.

2.1.2 Part 1 Section 8.5, PresentationML

a. *The standard states that all comment authors in a document are stored in one comment-authors part while each slide has its own part.*

Office interprets comments to mean comment authors in this context.

2.1.3 Part 1 Section 8.6.2, VML

a. *The standard specifies that shape definitions are typically specified using the shapeData element and the shape element.*

Office specifies shape definitions using only the shape element.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.4 Part 1 Section 8.6.5, Math

a. *The standard states that Math has a root element of math.*

Office uses Math with root elements oMath and oMathPara.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.5 Part 1 Section 9, Packages

a. *The standard does not define idOfficeObject digital signature.*

Office reserves the object ID of idOfficeObject ([§3.7, Office Digital Signature](#)) for its digital signature.

2.1.6 Part 1 Section 11.1, Glossary of WordprocessingML-Specific Terms

- a. *The standard defines a document setting as "A reusable element in a template."*

Office defines a document setting to be "A document-level property that affects the handling of a given document, and influences the appearance and behavior of the current document, as well as the stored document-level state."

2.1.7 Part 1 Section 11.3, Part Summary

- a. *The standard does not document a Customizations part for key mapping and toolbar customizations.*

Word defines a Customizations part ([§3.1.1.2, Customizations Part](#)) for key mapping and toolbar customizations.

- b. *The standard does not include documentation for the Attachedtoolbars part.*

Word defines an Attachedtoolbars part ([§3.1.1.1, Word Attached Toolbars Part](#)), which supports the storage of custom toolbars created by the user.

- c. *The standard does not document a Mail Merge Recipient Data part for storage of mail merge recipient data.*

Word defines a Mail Merge Recipient Data part ([§3.1.1.3, Mail Merge Recipient Data Part](#)) for storage of mail merge recipient data.

2.1.8 Part 1 Section 11.3.10, Main Document Part

- a. *The standard states that the content type for the Main Document part is: application/vnd.openxmlformats-officedocument.wordprocessingml.main+xml.*

Office uses the following content type for the Main Document part: application/vnd.openxmlformats-officedocument.wordprocessingml.document.main+xml.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.9 Part 1 Section 12.3, Part Summary

- a. *The standard does not include documentation for the Attachedtoolbars part.*

Office defines an Attachedtoolbars part ([§3.2.1.1, Excel Attached Toolbars Part](#)), which supports the storage of custom toolbars created by the user.

- b. *The standard lists the Comment part as a relationship target of the Chartsheet part and the Dialogsheet part.*

Office does not allow the Comment part as a valid relationship target of the Chartsheet part or the Dialogsheet part.

- c. *The standard states that the Custom Property part is a relationship target of the Workbook part.*

Office requires that the Custom Property part is a relationship target of the Worksheet part.

- d. *The standard states that the Single Cell Table Definitions part is a valid relationship target of the Dialogsheet part.*

Office does not allow the Single Cell Table Definitions part as a relationship target of the Dialogsheet part.

e. *The standard states that the Table Definition part is a valid relationship target of the Dialogsheet part.*

Office does not allow the Table Definition part as a relationship target of the Dialogsheet part.

f. *The standard specifies the Root Element of the Dialogsheet part as dialogSheet.*

Office requires the Root Element to be dialogsheet.

g. *The standard specifies the Root Element of the External Workbook References part as externalReference.*

Office requires the Root Element to be externalLink.

h. *The standard does not include documentation for the Worksheet Sort Map part.*

Office defines a Worksheet Sort Map part ([§3.2.2, Microsoft Office Excel Sortmap](#)) to reconcile different sort operations on the worksheet in a shared workbook.

i. *The standard does not list the Query Table part as a relationship target of the Table Definition part.*

Office allows the Query Table part as a valid relationship target of the Table Definition part.

2.1.10 Part 1 Section 12.3.2, Chartsheet Part

a. *The standard does not allow the Chartsheet part to have an explicit relationship with the VML Drawing part.*

Office allows the Chartsheet part to have an explicit relationship with the VML Drawing part.

b. *The standard does not allow the Chartsheet part to have an explicit relationship with the Images part.*

Office allows the Chartsheet part to have an explicit relationship with the Images part.

2.1.11 Part 1 Section 12.3.5, Custom Property Part

a. *The standard says that a package shall contain at most one Custom Property part, and that part shall be the target of an implicit relationship from the Workbook part.*

Office permits a package to contain zero or more Custom Property parts. Each such Custom Property part shall be the target of an explicit relationship from the Worksheet part.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.12 Part 1 Section 12.3.6, Custom XML Mappings Part

a. *The standard specifies the Root Element of the Custom XML Mapping part as mapInfo.*

Office requires the Root Element to be MapInfo.

2.1.13 Part 1 Section 12.3.7, Dialogsheet Part

a. *The standard states that a Dialogsheet part is permitted to have an explicit relationship with the Embedded Control Persistence part.*

Office does not allow a Dialogsheet part to have an explicit relationship to the Embedded Control Persistence part.

b. *The standard does not allow the Dialogsheet part to have an explicit relationship with the VML Drawing part.*

Office allows the Dialogsheet part to have an explicit relationship with the VML Drawing part.

2.1.14 Part 1 Section 12.3.19, Single Cell Table Definitions Part

a. *The standard specifies the Root Element of the Single Cell Table Definitions part as singleCells.*

Office requires the Root Element to be singleXmlCells.

2.1.15 Part 1 Section 12.3.20, Styles Part

a. *The standard specifies the Root Namespace for the Styles Part as <http://schemas.openxmlformats.org/spreadsheetml/2006/main>.*

Office requires the Root Namespace to be <http://schemas.openxmlformats.org/spreadsheetml/2006/main>.

2.1.16 Part 1 Section 12.3.23, Workbook Part

a. *The standard specifies the content type for the Workbook part as <application/vnd.openxmlformats-officedocument.spreadsheetml.sheet.main+xml>.*

Office requires the content type to be <application/vnd.openxmlformats-officedocument.spreadsheetml.sheet.main+xml>.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.17 Part 1 Section 12.3.24, Worksheet Part

a. *The standard does not allow the Worksheet part to have an implicit relationship with the Worksheet Sort Map part.*

Office allows the Worksheet part to have an implicit relationship with the Worksheet Sort Map part.

b. *The standard does not allow the Worksheet part to have an implicit relationship with the Query Table part.*

Office allows the Worksheet part to have an implicit relationship with the Query Table part.

c. *The standard does not allow the Worksheet part to have an explicit relationship with the Custom Property part.*

Office allows the Worksheet part to have an explicit relationship with the Custom Property part.

2.1.18 Part 1 Section 12.4, External Workbooks

a. *The standard does not specify the meaning of the <http://schemas.microsoft.com/office/2006/relationships/xlExternalLinkPath/xlStartup> relationship type.*

Excel uses the <http://schemas.microsoft.com/office/2006/relationships/xlExternalLinkPath/xlStartup> relationship type to specify a base path of an application-defined startup directory.

b. *The standard does not specify the meaning of the <http://schemas.microsoft.com/office/2006/relationships/xlExternalLinkPath/xlAlternateStartup> relationship type.*

Excel uses the <http://schemas.microsoft.com/office/2006/relationships/xlExternalLinkPath/xlAlternateStartup> relationship type to specify a base path of an application-defined alternate startup directory.

c. *The standard does not specify the meaning of the <http://schemas.microsoft.com/office/2006/relationships/xlExternalLinkPath/xlPathMissing> relationship type.*

Excel uses the <http://schemas.microsoft.com/office/2006/relationships/xlExternalLinkPath/xlPathMissing> relationship type to specify that a base path should not be inferred.

d. *The standard does not specify the meaning of the <http://schemas.microsoft.com/office/2006/relationships/xlExternalLinkPath/xlLibrary> relationship type.*

Excel uses the <http://schemas.microsoft.com/office/2006/relationships/xlExternalLinkPath/xlLibrary> relationship type to specify a base path of an application-defined library directory.

e. *The standard states that this part can only contain links to external workbooks.*

Excel also allows this part to contain OLE links and DDE links.

2.1.19 Part 1 Section 13.3, Part Summary

a. *The standard does not include documentation for the Legacy Diagram Text Info binary part.*

PowerPoint defines a Legacy Diagram Text Info binary part ([§3.3.1.1, Legacy Diagram Text part](#)) to store legacy diagram text information.

b. *The standard does not include documentation for the Legacy Diagram Text binary part.*

PowerPoint defines a Legacy Diagram Text binary part ([§3.3.1.1, Legacy Diagram Text part](#)) to store legacy diagram text.

c. *The standard does not include documentation for the SmartTags binary part.*

PowerPoint defines a SmartTags binary part ([§3.3.1.3, SmartTags part](#)) to store smart tag data.

2.1.20 Part 1 Section 13.3.3, Handout Master Part

a. *The standard states that a Handout Master part is permitted to have an explicit relationship with the Embedded Control Persistence part.*

Office does not allow a Handout Master part to have an explicit relationship to the Embedded Control Persistence part.

b. *The standard does not allow the Handout Master part to have an explicit relationship with the User Defined Tags part.*

Office allows the Handout Master part to have an explicit relationship with the User Defined Tags part.

c. *The standard states that a Handout Master part is permitted to have an implicit relationship with the Custom XML Data Storage part.*

Office only allows for an explicit relationship between these two parts.

d. *The standard states that a Handout Master part is permitted to have an implicit relationship with the Thumbnail part.*

Office does not allow a Handout Master part to have an implicit relationship to the Thumbnail part.

e. *The standard does not allow the Handout Master part to have an explicit relationship with the Slide part.*

Office allows the Handout Master part to have an explicit relationship with the Slide part.

f. *The standard permits the Handout Master part to have an explicit relationship with the VML Drawing part.*

Office only permits the Handout Master part to have an implicit relationship with the VML Drawing part.

g. *The standard permits the Handout Master part to have an implicit relationship with the Additional Characteristics part.*

Office only permits the Handout Master part to have an explicit relationship with the Additional Characteristics part.

h. *The standard states that the Handout Master part is permitted to have an implicit relationship to a Bibliography part.*

Office only allows the Handout Master part to have an explicit relationship with a Bibliography part.

2.1.21 Part 1 Section 13.3.4, Notes Master Part

a. *The standard states that a Notes Master part is permitted to have an explicit relationship with the Embedded Control Persistence part.*

Office does not allow a Notes Master part to have an explicit relationship to the Embedded Control Persistence part.

b. *The standard states that a Notes Master part is permitted to have an implicit relationship with the Thumbnail part.*

Office does not allow a Notes Master part to have an implicit relationship to the Thumbnail part.

c. *The standard does not allow the Notes Master part to have an explicit relationship with the User Defined Tags part.*

Office allows the Notes Master part to have an explicit relationship with the User Defined Tags part.

d. *The standard does not allow the Notes Master part to have an explicit relationship with the Slide part.*

Office allows the Notes Master part to have an explicit relationship with the Slide part.

e. *The standard permits the Notes Master part to have an explicit relationship with the VML Drawing part.*

Office only permits the Notes Master part to have an implicit relationship with the VML Drawing part.

f. *The standard permits the Notes Master part to have an implicit relationship with the Additional Characteristics part.*

Office only permits the Notes Master part to have an explicit relationship with the Additional Characteristics part.

g. *The standard states that the Notes Master part is permitted to have an implicit relationship to a Bibliography part.*

Office only allows the Notes Master part to have an explicit relationship with a Bibliography part.

2.1.22 Part 1 Section 13.3.5, Notes Slide Part

a. *The standard states that a Notes Slide part is permitted to have an explicit relationship with the Embedded Control Persistence part.*

Office does not allow a Notes Slide part to have an explicit relationship to the Embedded Control Persistence part.

b. *The standard does not allow the Notes Slide part to have an implicit relationship to a Slide part.*

Office allows the Notes Slide part to have an implicit relationship to a Slide part.

c. *The standard states that a Notes Slide part is permitted to have an implicit relationship with the Thumbnail part.*

Office does not allow a Notes Slide part to have an implicit relationship to the Thumbnail part.

d. *The standard does not allow the Notes Slide part to have an explicit relationship with the User Defined Tags part.*

Office allows the Notes Slide part to have an explicit relationship with the User Defined Tags part.

e. *The standard does not allow the Notes Slide part to have an explicit relationship with the Slide part.*

Office allows the Notes Slide part to have an explicit relationship with the Slide part.

f. *The standard permits the Notes Slide part to have an explicit relationship with the VML Drawing part.*

Office only permits the Notes Slide part to have an implicit relationship with the VML Drawing part.

g. *The standard permits the Notes Slide part to have an implicit relationship with the Additional Characteristics part.*

Office only permits the Notes Slide part to have an explicit relationship with the Additional Characteristics part.

h. *The standard states that the Notes Slide part is permitted to have an implicit relationship to a Bibliography part.*

Office only allows the Notes Slide part to have an explicit relationship with a Bibliography part.

2.1.23 Part 1 Section 13.3.6, Presentation Part

a. *The standard states that a Presentation part is permitted to have implicit relationships with the Comments part.*

Office only allows the Presentation part to have implicit relationships with the Comment Authors part.

b. *The standard states that a Presentation part is permitted to have explicit relationships with the Slide Layout part.*

Office does not allow a Presentation part to have explicit relationships with the Slide Layout part.

c. *The standard states that the Presentation part is permitted to have an implicit relationship to a Font part.*

Office only allows the Presentation part to have an explicit relationship with a Font part.

d. *The standard states that a Presentation part is permitted to have an implicit relationship to the Thumbnail part.*

Office does not allow a Presentation part to have an implicit relationship to the Thumbnail part.

e. *The standard states that the Presentation part is permitted to have an implicit relationship to a Custom XML Data Storage part.*

Office also allows for an explicit relationship between the Presentation part and a Custom XML Data Storage part.

f. *The standard states that a Presentation part is permitted to have an implicit relationship to the Additional Characteristics part.*

Office also allows there to be an explicit relationship between a Presentation part and the Additional Characteristics part.

g. *The standard states that a Presentation part is permitted to have an implicit relationship to a Bibliography part.*

Office also allows there to be an explicit relationship between a Presentation part and a Bibliography part.

2.1.24 Part 1 Section 13.3.7, Presentation Properties Part

a. *The standard states that a Presentation Properties part does not have any implicit or explicit relationships to other parts.*

Office allows a Presentation Properties part to have an explicit relationship to the HTML Publish part.

2.1.25 Part 1 Section 13.3.8, Slide Part

a. *The standard states that a Slide part is permitted to have an implicit relationship with the Thumbnail part.*

Office does not allow a Slide part to have an implicit relationship to the Thumbnail part.

b. *The standard does not allow the Slide part to have an explicit relationship with the Slide part.*

Office allows the Slide part to have an explicit relationship with the Slide part.

c. *The standard permits the Slide part to have an explicit relationship with the VML Drawing part.*

Office only permits the Slide part to have an implicit relationship with the VML Drawing part.

d. *The standard permits the Slide part to have an implicit relationship with the Additional Characteristics part.*

Office only permits the Slide part to have an explicit relationship with the Additional Characteristics part.

e. *The standard states that the Slide part is permitted to have an implicit relationship to a Bibliography part.*

Office only allows the Slide part to have an explicit relationship with a Bibliography part.

2.1.26 Part 1 Section 13.3.9, Slide Layout Part

a. *The standard states that a Slide Layout part is permitted to have an implicit relationship with the Thumbnail part.*

Office does not allow a Slide Layout part to have an implicit relationship to the Thumbnail part.

b. *The standard does not allow the Slide Layout part to have an explicit relationship with the User Defined Tags part.*

Office allows the Slide Layout part to have an explicit relationship with the User Defined Tags part.

c. *The standard does not allow the Slide Layout part to have an explicit relationship with the Slide part.*

Office allows the Slide Layout part to have an explicit relationship with the Slide part.

d. *The standard permits the Slide Layout part to have an explicit relationship with the VML Drawing part.*

Office only permits the Slide Layout part to have an implicit relationship with the VML Drawing part.

e. *The standard permits the Slide Layout part to have an implicit relationship with the Additional Characteristics part.*

Office only permits the Slide Layout part to have an explicit relationship with the Additional Characteristics part.

f. *The standard states that the Slide Layout part is permitted to have an implicit relationship to a Bibliography part.*

Office only allows the Slide Layout part to have an explicit relationship with a Bibliography part.

2.1.27 Part 1 Section 13.3.10, Slide Master Part

a. *The standard states that a Slide Master part is permitted to have an implicit relationship with the Slide Layout part.*

Office only allows a Slide Master part to have an explicit relationship with the Slide Layout part.

b. *The standard states that the Slide Master part is permitted to have an implicit relationship to a Slide Layout part.*

Office only allows the Slide Master part to have an explicit relationship with a Slide Layout part.

c. *The standard states that a Slide Master part is permitted to have an implicit relationship with the Thumbnail part.*

Office does not allow a Slide Master part to have an implicit relationship to the Thumbnail part.

d. *The standard does not allow the Slide Master part to have an explicit relationship with the User Defined Tags part.*

Office allows the Slide Master part to have an explicit relationship with the User Defined Tags part.

e. *The standard does not allow the Slide Master part to have an explicit relationship with the Slide part.*

Office allows the Slide Master part to have an explicit relationship with the Slide part.

f. *The standard permits the Slide Master part to have an explicit relationship with the VML Drawing part.*

Office only permits the Slide Master part to have an implicit relationship with the VML Drawing part.

g. *The standard permits the Slide Master part to have an implicit relationship with the Additional Characteristics part.*

Office only permits the Slide Master part to have an explicit relationship with the Additional Characteristics part.

h. *The standard states that the Slide Master part is permitted to have an implicit relationship to a Bibliography part.*

Office only allows the Slide Master part to have an explicit relationship with a Bibliography part.

2.1.28 Part 1 Section 13.4, HTML Publish Location

a. *The standard states that a package shall contain one HTML Publish Location relationship for each slide linked with an HTML publish location.*

Office does not use this relationship per slide.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.29 Part 1 Section 14.2.3, Diagram Colors Part

a. *The standard states that a Diagram Colors part is the target of an explicit relationship in a WordprocessingML Main Document, SpreadsheetML Drawings, or PresentationM Slide part.*

In Office, the Diagram Colors part can also be the target of an explicit relationship in a PresentationML Handout Master ("[\[ECMA-376\]](#) Part 1 §13.3.3; Handout Master Part"), Notes Master ("[\[ECMA-376\]](#) Part 1 §13.3.4; Notes Master Part"), Notes Slide ("[\[ECMA-376\]](#) Part 1 §13.3.5; Notes Slide Part"), Slide ("[\[ECMA-376\]](#) Part 1 §13.3.8; Slide Part"), Slide Layout ("[\[ECMA-376\]](#) Part 1 §13.3.9; Slide Layout Part"), or Slide Master ("[\[ECMA-376\]](#) Part 1 §13.3.10; Slide Master Part") part.

2.1.30 Part 1 Section 15.2, Part Summary

a. *The standard does not include documentation for the Embedded Control Persistence Binary Data part.*

Office defines an Embedded Control Persistence Binary Data part ([§3.4.1.1, Embedded Control Persistence Binary Data Part](#)), which contains information about persisted embedded controls in the package.

b. *The standard does not include documentation for the Quick Access Toolbar Customizations part.*

Office defines a Quick Access Toolbar Customizations part ([§3.4.1.2, Quick Access Toolbar Customizations Part](#)), which contains information about quick access toolbar customizations.

c. *The standard does not include documentation for the Ribbon Extensibility part.*

Office defines a Ribbon Extensibility part ([§3.4.1.3, Ribbon Extensibility Part](#)), which contains information about ribbon customizations.

2.1.31 Part 1 Section 15.2.4, Custom XML Data Storage Part

a. *The standard does not specify that Office reserves namespaces for storing document properties.*

Office reserves the following specific namespaces for storing document properties:

| Root Namespace | Reference |
|---|--|
| http://schemas.microsoft.com/office/2006/customDocumentInformationPanel | §3.5.3.1, Custom Document Information Panel Schema |
| http://schemas.microsoft.com/office/2006/metadata/customXsn | §3.5.4.1, Custom XSN Schema |
| http://schemas.microsoft.com/office/2006/metadata/contentType | §3.5.2.1, Content Type Schemas Schema |
| http://schemas.microsoft.com/office/2006/coverPageProps | §3.5.1.1, Cover Page Properties Schema |
| http://schemas.microsoft.com/office/2006/metadata/longProperties | §3.5.5.1, Long Properties Schema |
| office.server.policy | Collaborative Application Markup Language (CAML) Structure (IMS-WSSCAML Subclause 2.5.1.7). |

Furthermore, a Custom XML Data Storage part with root namespace of <http://schemas.microsoft.com/office/2006/metadata/properties> describes the properties of this document as defined by the `xsd:schema` children of Content Type Schemas ([§3.5.2.1, Content Type Schemas Schema](#)). The `xsd:schema` that bears the `ma:root` Root ([§3.5.2.2.1, Shared Attributes](#)) attribute describes the structure of the root element this Custom XML Data Storage part, with the other `xsd:schema` children collectively describing elements from other namespaces referenced.

2.1.32 Part 1 Section 15.2.8, Embedded Control Persistence Part

- a. *The standard does not state the content type used for ActiveX data stored in the Embedded Control Persistence part.*

When Office stores data for ActiveX controls in the Embedded Control Persistence part, the following content type is used: application/vnd.ms-office.activeX+xml.

2.1.33 Part 1 Section 15.2.11.1, Core File Properties Part

- a. *The standard specifies a source relationship for the Core File Properties part as follows: <http://schemas.openxmlformats.org/officedocument/2006/relationships/metadata/core-properties>.*

Office uses the following source relationship for the Core File Properties part:
<http://schemas.openxmlformats.org/package/2006/relationships/metadata/core-properties>.

2.1.34 Part 1 Section 15.2.12, Font Part

- a. *The standard states that fonts are stored in one of two formats: application/x-fontdata and application/x-font-ttf, which does not account for the obfuscation in WordprocessingML documents.*

Word stores obfuscated fonts using the following content type: application/vnd.openxmlformats-officedocument.obfuscatedFont. *application/vnd.openxmlformats-officedocument.obfuscatedFont* specifies that the font shall be stored in the TrueType or OpenType format and shall be obfuscated using the algorithm specified by Font Embedding ("ECMA-376 Part 4 §2.8.1; Font Embedding"). Only WordprocessingML is permitted to reference obfuscated fonts.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

- b. *The standard states that application/x-font-ttf specifies that the font shall be stored in the TrueType or OpenType format.*

PowerPoint does not use this content type. Word reads these fonts if the value of the fontKey attribute is equal to 00000000-0000-0000-0000-000000000000.

- c. *The standard states that application/x-fontdata specifies that the font shall be stored as a bitmapped font (each glyph is stored as a raster image).*

PowerPoint stores TrueType and OpenType fonts ([\[Embed-Open-Type-Format\]](#), [\[Micro-Type-Exp-Format\]](#)) in parts of this type. Word does not read or write this content type.

2.1.35 Part 1 Section 15.2.13, Image Part

- a. *The standard does not list a reference to the Enhanced Metafile Format Specification.*

Office also supports the image/emf image type [\[MS-EMF\]](#).

- b. *The standard does not list reference to the Enhanced Metafile Format Plus Extensions Specification.*

Office also supports the image/emf+ image type [\[MS-EMFPLUS\]](#).

- c. *The standard does not list a reference to the Windows Metafile Format Specification.*

Office also supports the image/wmf image type [\[MS-WMF\]](#).

2.1.36 Part 1 Section 15.2.14, Printer Settings Part

- a. *The standard provides the following reference to DEVMODE:*
http://msdn.microsoft.com/library/default.asp?url=/library/en-us/gdi/prntspol_8nle.asp.

Office uses DEVMODE [\[DEVMODE\]](#) as specified by: <http://msdn2.microsoft.com/en-us/library/ms535771.aspx>.

- b. *The standard does not specify the contents of the target attribute.*

Office writes the DEVMODE [\[DEVMODE\]](#) structure including printer driver specific data in machine byte order to the part specified in target attribute.

2.1.37 Part 1 Section 15.2.17, VML Drawing Part

- a. *The standard implies that the VML Drawing part is not an XML part but contains XML-style markup.*

In Office, the VML Drawing part closely resembles XML. An XML parser designed to read and write ECMA-376 VML markup can parse the contents of a VML Drawing part by consuming the XML root element and then handling the contained VML markup normally.

2.1.38 Part 2 Section 12.2.4.26, Relationships Transform Algorithm

- a. *The standard specifies that a Relationship element shall be used for signing if the Id value matches any SourceId value or if the Type value matches any SourceType value.*

Office will only use Relationship elements for signing if the Id value matches any SourceId value.

2.1.39 Part 4 Section 2.2.1, background (Document Background)

- a. *The standard states that any element from the VML namespace or the Office VML Drawing namespace is allowed as a child of the background element.*

Word only allows a single instance of the VML background element to be a child of the background element.

- b. *The standard does not state which setting is applied when both the themeShade and the themeTint attributes are present.*

Word applies the themeTint setting when both of these attributes are present.

2.1.40 Part 4 Section 2.2.2, body (Document Body)

For additional notes that apply to this portion of the standard, please see the notes for [oMath](#), [§7.1.2.77\(g\)](#); [oMathPara](#), [§7.1.2.78\(d\)](#).

2.1.41 Part 4 Section 2.3.1.4, bar (Paragraph Border Between Facing Pages)

For additional notes that apply to this portion of the standard, please see the notes for [bdr](#), [§2.3.2.3\(a\)](#); [left](#), [§2.15.2.21\(a\)](#).

- a. *The standard does not state a default value for the color attribute.*

Word uses a default value of auto for this attribute.

b. *The standard does not specify a default value for the sz attribute.*

Word uses a default value of 0 for this attribute.

c. *The standard does not specify a default value for the space attribute.*

Word uses a default value of 0 for this attribute.

2.1.42 Part 4 Section 2.3.1.5, between (Paragraph Border Between Identical Paragraphs)

For additional notes that apply to this portion of the standard, please see the notes for [bar](#), [§2.3.1.4\(a-c\)](#); [bdr](#), [§2.3.2.3\(a\)](#); [left](#), [§2.15.2.21\(a\)](#).

2.1.43 Part 4 Section 2.3.1.6, bidi (Right to Left Paragraph Layout)

a. *The standard says this element does not affect the layout of text within the contents of the paragraph.*

Word uses this element to specify the directionality of the line (HL1 in the Unicode Bidirectional algorithm), which affects the layout of text within the contents of the paragraph.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.44 Part 4 Section 2.3.1.7, bottom (Paragraph Border Between Identical Paragraphs)

For additional notes that apply to this portion of the standard, please see the notes for [bar](#), [§2.3.1.4\(a-c\)](#); [bdr](#), [§2.3.2.3\(a\)](#); [left](#), [§2.15.2.21\(a\)](#).

2.1.45 Part 4 Section 2.3.1.8, cnfStyle (Paragraph Conditional Formatting)

For additional notes that apply to this portion of the standard, please see the notes for [pPr](#), [§2.7.4.2\(a\)](#); [pPr](#), [§2.7.5.1\(a\)](#); [pPr](#), [§2.7.7.2\(a\)](#); [pPr](#), [§2.9.24\(a\)](#).

2.1.46 Part 4 Section 2.3.1.10, divId (Associated HTML div ID)

For additional notes that apply to this portion of the standard, please see the notes for [divId](#), [§2.4.9\(a\)](#); [pPr](#), [§2.7.4.2\(a\)](#); [pPr](#), [§2.7.5.1\(a\)](#); [pPr](#), [§2.7.7.2\(a\)](#); [pPr](#), [§2.9.24\(a\)](#).

a. *The standard states that the values of the val attribute are defined by the XML Schema integer datatype.*

Word does not allow a value of 0 on this attribute.

2.1.47 Part 4 Section 2.3.1.11, framePr (Text Frame Properties)

a. *The standard states that the lines attribute can be any 32-bit integer.*

Word restricts this attributes to values between 1 and 10.

b. *The standard states that the values of the h attribute are defined by the ST_TwipsMeasure simple type.*

Word restricts the value of this attribute to be at least 1 and at most 31680.

c. *The standard states that the hAnchor attribute is evaluated relative to paragraph direction (LTR versus RTL).*

Word always evaluates the hAnchor attribute relative to the left edge.

d. *The standard states that the h attribute is optional.*

Word requires this attribute to be present when the value of the hRule attribute is "atLeast" or "exact".

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

e. *The standard states that 0 is a valid value of the h attribute.*

Word treats a value of 0 on this attribute as a value of auto.

f. *The standard states that the default value of the hAnchor attribute is page.*

Word uses a default value of text for the hAnchor attribute.

g. *The standard states that the default value of the hRule attribute is auto.*

Word uses a default value of atLeast for this attribute when the value of the h attribute is not 0.

h. *The standard states that the default value for the vAnchor attribute is page.*

Word uses a default value of text for this attribute.

2.1.48 Part 4 Section 2.3.1.13, jc (Paragraph Alignment)

a. *The standard states that no alignment is applied to the paragraph when the paragraph alignment setting is never specified in the style hierarchy.*

Word applies a left alignment to the paragraph under this circumstance.

b. *The standard states that the possible values of the val attribute are always specified relative to the page, and do not change semantic from right-to-left and left-to-right documents.*

Word evaluates the value of this attribute based on the value of the bidi element: Left is the right side of a right-to-left paragraph, and right is the left side of a right-to-left paragraph.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.49 Part 4 Section 2.3.1.14, keepLines (Keep All Lines On One Page)

a. *The standard states that the property can be applied to paragraphs anywhere in a document.*

Word does not keep lines together when rendering paragraphs inside a table.

2.1.50 Part 4 Section 2.3.1.16, kinsoku (Use East Asian Typography Rules for First and Last Character per Line)

a. *The standard states that the East Asian typography and line-breaking rules only apply to Chinese PRC, Chinese Taiwan, and Japanese text in the paragraph.*

Word only applies these rules to Chinese (Simplified), Chinese (Traditional), Korean, and Japanese text in the paragraph.

2.1.62 Part 4 Section 2.3.1.31, shd (Paragraph Shading)

For additional notes that apply to this portion of the standard, please see the notes for [shd](#), [§2.4.33\(a,d\)](#).

2.1.63 Part 4 Section 2.3.1.37, tab (Custom Tab Stop)

a. *The standard states that the values of the pos attribute are defined by the XML Schema integer datatype.*

Word restricts the value of this attribute to be at least -31680 (-22") and at most 31680 (22").

2.1.64 Part 4 Section 2.3.1.40, textboxTightWrap (Allow Surrounding Paragraphs to Tight Wrap to Text Box Contents)

a. *The standard describes that the val attribute on the textboxTightWrap element takes one of five values: none, allLines, firstAndLastLine, firstLineOnly, and lastLineOnly.*

Word always resets the value of this attribute to allLines when opening a document.

2.1.65 Part 4 Section 2.3.1.41, textDirection (Paragraph Text Flow Direction)

a. *The standard states that this element specifies the direction of the text flow for this paragraph.*

Word uses this property only when the paragraph is contained within a frame.

2.1.66 Part 4 Section 2.3.1.42, top (Paragraph Border Above Identical Paragraphs)

For additional notes that apply to this portion of the standard, please see the notes for [bar](#), [§2.3.1.4\(a-c\)](#); [bdr](#), [§2.3.2.3\(a\)](#); [left](#), [§2.15.2.21\(a\)](#).

2.1.67 Part 4 Section 2.3.1.43, topLinePunct (Compress Punctuation at Start of a Line)

a. *The standard states that this element specifies whether punctuation shall be compressed when it appears as the first character in a line, but does not define which characters are affected.*

Word only applies this property to runs in one of the following languages: Chinese (Simplified), Chinese (Traditional), Korean, or Japanese.

2.1.68 Part 4 Section 2.3.1.44, widowControl (Allow First/Last Line to Display on a Separate Page)

a. *The standard states that this element is applied to all paragraphs.*

Word ignores this element when rendering paragraphs inside a table.

2.1.69 Part 4 Section 2.3.1.45, wordWrap (Allow Line Breaking At Character Level)

a. *The standard states that this element will cause Latin text to break on the character level.*

If Word determines the language in use is Korean, it will apply this property to Korean text only.

2.1.70 Part 4 Section 2.3.2.1, b (Bold)

a. *The standard states that this element applies bold to non-complex script characters, but does not specify how that determination is made.*

Word determines this state based on the state of the `cs` and `rtl` properties and applies bold to runs that do not use either of those properties.

2.1.71 Part 4 Section 2.3.2.2, bCs (Complex Script Bold)

a. *The standard states that this element applies bold to complex script characters, but does not specify how that determination is made.*

Word determines this state based on the state of the `cs` and `rtl` properties and applies bold to runs that use either of those properties.

2.1.72 Part 4 Section 2.3.2.3, bdr (Text Border)

For additional notes that apply to this portion of the standard, please see the notes for [bar](#), [§2.3.1.4\(a-c\)](#); [left](#), [§2.15.2.21\(a\)](#).

a. *The standard does not state which setting is applied when both the `themeShade` and the `themeTint` attributes are present.*

Word applies the `themeTint` setting when both of these attributes are present.

2.1.73 Part 4 Section 2.3.2.5, color (Run Content Color)

For additional notes that apply to this portion of the standard, please see the notes for [color](#), [§2.15.2.5\(a\)](#).

a. *The standard specifies an algorithm for `themeShade` calculations that is different from `themeShade` calculations in other subclauses.*

Given an RGB color defined as three hex values in RRGGBB format, the shade is applied as follows:

Convert the color to the HSL color format (values from 0 to 1).

Modify the luminance factor as follows:

$$L' = L * \text{Shade}_{\text{percentage}}$$

Convert the resultant HSL color to RGB.

If this attribute is specified in the **color** element (“[\[ECMA-376\]](#) Part 4 §2.15.2.5; `color` (Frameset Splitter Color)”) nested inside a **framesetSplitbar** (“[\[ECMA-376\]](#) Part 4 §2.15.2.20; `framesetSplitbar` (Frameset Splitter Properties)”) element, Word deviates from this behavior. Refer to the **themeColor** attribute description.

[Example: Consider a document with a background using the `accent2` theme color, whose RGB value (in RRGGBB hex format) is `C0504D`.

The equivalent HSL color value would be $(\frac{1}{360}, 0.48, 0.53)$.

Applying the shade formula with a shade percentage of 75% to the luminance, the result is:

$$L' = 0.53 * 0.75$$

$$= 0.39698$$

Taking the resulting HSL color value of $(\frac{1}{360}, 0.48, 0.39698)$ and converting back to RGB, the result is 943634.

This transformed value can be seen in the resulting run color WordprocessingML's **val** attribute:

```
<w:color w:val="943634" w:themeColor="accent2" w:themeShade="BF" />
```

end example]

b. *The standard does not state which setting is applied when both the themeShade and the themeTint attributes are present.*

Word applies the themeTint setting when both of these attributes are present.

c. *The standard describes an algorithm for themeTint calculations that is different from themeTint calculations in other subclasses.*

In Word, the themeTint attribute is calculated using the following algorithm:

Given an RGB color defined as three hex values in RRGGBB format, the shade is applied as follows:

Convert the color to the HSL color format (values from 0 to 1).

Modify the luminance factor as follows:

$$L' = L * Tint_{pct} + (1 - Tint_{pct})$$

Convert the resultant HSL color to RGB.

If this attribute is specified in the **color** element ("ECMA-376 Part 4 §2.15.2.5; color (Frameset Splitter Color)") nested inside a **framesetSplitbar** element ("ECMA-376 Part 4 §2.15.2.20; framesetSplitbar (Frameset Splitter Properties)"), Word will not use the specified theme color but rather will use an RGB color based on the **themeShade** and **themeTint** attributes. The intensity of the red, green, and blue components of this RGB color range from 0 to 255. The value of **themeTint** shall specify the intensity of the red component. If the **themeTint** attribute is omitted, the intensity of the red component shall default to 255. The value of **themeShade** shall specify the intensity of the green component. If the **themeShade** attribute is omitted, the intensity of the green component shall default to 255. The intensity of the blue component shall be 0.

[Example: Consider a document with a background using the *accent2* theme color, whose RGB value (in RRGGBB hex format) is 4F81BD.

The equivalent HSL color value would be $\left(\frac{213}{360}, 0.45, 0.53\right)$.

Applying the tint formula with a tint percentage of 60% to the luminance, the result is:

$$L' = 0.53 * 0.6 + (1 - .6)$$

$$= 0.71$$

Taking the resulting HSL color value of $\left(\frac{213}{360}, 0.45, 0.71\right)$ and converting back to RGB, the result is 95B3D7.

This transformed value can be seen in the resulting background's **color** attribute:

```
<w:top w:val="single" w:sz="4" w:space="24"
  w:color="95B3D7" w:themeColor="accent2"
  w:themeTint="99"/>
```

end example]

2.1.74 Part 4 Section 2.3.2.6, cs (Use Complex Script Formatting on Run)

For additional notes that apply to this portion of the standard, please see the notes for [rPr, §2.7.4.4\(a\)](#); [rPr, §2.7.5.2\(a\)](#); [rPr, §2.7.8.1\(a\)](#).

2.1.75 Part 4 Section 2.3.2.8, eastAsianLayout (East Asian Typography Settings)

a. *The standard states that horizontal in vertical text is performed with rotation for vertical at 90 degrees in one location and 270 in another.*

Word rotates text 90 degrees to the left.

b. *The standard states that the vertCompress attribute determines whether the rotated text shall be compressed at display time in order to ensure that it fits into the existing line height.*

Word ignores this attribute.

c. *The standard does not state how to resolve conflicts between this element and the fitText element.*

Word ignores this element if the fitText element is also present on the parent paragraph.

d. *The standard does not state how a conflict between the settings specified by the combine attribute and the vert attribute should be resolved.*

Word ignores the vert attribute when the combine attribute is set to true (or equivalent).

e. *The standard states that this element should work within a numbering level definition.*

Word does not support this element when used within the run properties of a numbering level definition.

f. *The standard states that this element specifies the East Asian typography settings which shall be applied to the contents of the run.*

Word ignores these settings when the run is contained inside an equation, and when the run's direction does not match the direction of the parent paragraph.

2.1.76 Part 4 Section 2.3.2.9, effect (Animated Text Effect)

a. *The standard states that the text effect is rendered around the text, but not all effects are border effects.*

Word renders the text effects defined in blinkBackground, shimmer, and sparkle animations behind the text, as they are not border animations.

2.1.77 Part 4 Section 2.3.2.11, emboss (Embossing)

a. *The standard states that this element shall not be present with either the imprint or outline elements.*

Word also prevents it from being present with the shadow element.

2.1.78 Part 4 Section 2.3.2.12, fitText (Manual Run Width)

a. *The standard states that the fitText element causes the contents of the run to be resized to fit the width specified by the val attribute.*

Word ignores this element inside Math, inside structured document tags, and for text that does not match the reading order of the parent paragraph.

b. *The standard states that if the id attribute is omitted, then this run has no ID and shall not be linked with any other run in the parent paragraph.*

Word assigns an id of 0 when the id attribute is omitted, and links it to other contiguous runs having an omitted id attribute (or an explicit id value of 0).

c. *The standard states that the val attribute can contain any 64-bit integer value.*

Word restricts this attribute to a value between 0 and 31680 (22").

d. *The standard does not state how a conflict between this setting and the spacing element and/or the eastAsianLayout element should be handled.*

Word uses this element when it is present, ignoring the spacing element and/or the eastAsianLayout element.

2.1.79 Part 4 Section 2.3.2.13, highlight (Text Highlighting)

For additional notes that apply to this portion of the standard, please see the notes for [rPr, §2.7.4.4\(a\)](#); [rPr, §2.7.5.2\(a\)](#); [rPr, §2.7.8.1\(a\)](#); [rPr, §2.9.26\(a\)](#).

2.1.80 Part 4 Section 2.3.2.14, i (Italics)

a. *The standard states that this element applies italics to non-complex script characters, but does not specify how that determination is made.*

Word determines this state based on the state of the cs and rtl properties and applies italics to runs that do not use either of those properties.

2.1.81 Part 4 Section 2.3.2.15, iCs (Complex Script Italics)

- a. *The standard states that this element applies italics to complex script characters, but does not specify how that determination is made.*

Word determines this state based on the state of the `cs` and `rtl` properties and applies italics to runs that use either of those properties.

2.1.82 Part 4 Section 2.3.2.16, imprint (Imprinting)

- a. *The standard states that this element shall not be present with either the `emboss` or `outline` elements.*

Word also prevents it from being present with the `shadow` element.

2.1.83 Part 4 Section 2.3.2.17, kern (Font Kerning)

- a. *The standard states that the values of the `val` attribute are defined by the XML Schema `unsignedLong` datatype.*

Word defines the values of this attribute with the XML Schema `unsignedInt` datatype, with a minimum value of 0 and a maximum value of 3277.

2.1.84 Part 4 Section 2.3.2.18, lang (Languages for Run Content)

- a. *The standard states that the `bidi` attribute applies font size to complex script characters, but does not specify how that determination is made.*

Word determines this state based on the state of the `cs` and `rtl` properties and applies the language to runs that use either of those properties.

2.1.85 Part 4 Section 2.3.2.19, noProof (Do Not Check Spelling or Grammar)

- a. *The standard states that this element causes spelling and grammar to be suppressed.*

Word does not check spelling, grammar, or hyphenate runs that contain this element.

2.1.86 Part 4 Section 2.3.2.20, oMath (Office Open XML Math)

For additional notes that apply to this portion of the standard, please see the notes for [rPr, §2.7.4.4\(a\)](#); [rPr, §2.7.5.2\(a\)](#); [rPr, §2.7.8.1\(a\)](#); [rPr, §2.9.26\(a\)](#).

- a. *The standard states that the `oMath` run property can be applied to any run.*

Word only supports the `oMath` element when applied to the `run` properties on the paragraph mark.

- b. *The standard states that the `oMath` element must come after the `rFonts` element when it is present.*

Word incorrectly writes the `oMath` element before the `rFonts` elements when present on a paragraph mark.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.87 Part 4 Section 2.3.2.21, outline (Display Character Outline)

- a. *The standard states that the outline element is mutually exclusive with emboss/engrave (imprint).*

Under limited conditions, Word will save these mutually exclusive properties into a document.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.88 Part 4 Section 2.3.2.23, r (Text Run)

For additional notes that apply to this portion of the standard, please see the notes for [oMathPara, §7.1.2.78\(a\)](#).

- a. *The standard states that runs can occur outside of paragraphs.*

Word does not open a file that contains this element outside of a paragraph. This paragraph element does not need to be the direct parent of the run, but the paragraph element must exist at some level around the run.

2.1.89 Part 4 Section 2.3.2.24, rFonts (Run Fonts)

- a. *The standard does not limit the length of the `ascii`, `hAnsi`, `cs`, and `eastAsia` attributes.*

Word restricts the value of these attributes to be less than 32 characters.

- b. *The standard states that the use of each of the run fonts shall be determined by the Unicode character values of the run content, but does not explain precisely how this is done.*

Word determines the use of each of these fonts from the Unicode character values in the following manner:

If the run has the **cs** element (“[\[ECMA-376\]](#) Part 4 §2.3.2.6; `cs` (Use Complex Script Formatting on Run)”) or the **rtl** element (“[\[ECMA-376\]](#) Part 4 §2.3.2.28; `rtl` (Right To Left Text)”), then the **cs** (or **csTheme** if defined) font is used, regardless of the Unicode character values of the run’s content.

If the **eastAsia** (or **eastAsiaTheme** if defined) attribute’s value is “Times New Roman” and the **ascii** (or **asciiTheme** if defined) and **hAnsi** (or **hAnsiTheme** if defined) attributes are equal, then the **ascii** (or **asciiTheme** if defined) font is used.

Otherwise, the following table is used. For all ranges not listed in the following table, the **hAnsi** (or **hAnsiTheme** if defined) font shall be used.

| Unicode Block | Range | Classification |
|--------------------|-------------|---|
| Basic Latin | 0000 – 007F | ascii (or asciiTheme if defined) |
| Latin-1 Supplement | 00A0 – 00FF | hAnsi (or hAnsiTheme if defined), with the following exceptions: If hint is <i>eastAsia</i> , the following characters use eastAsia (or eastAsiaTheme if defined): A1, A4, A7 – A8, AA, AD, AF, B0 – B4, B6 – BA, BC – BF, D7, F7 If hint is <i>eastAsia</i> and the language of the run is either Chinese Traditional or Chinese Simplified, the following characters use eastAsia (or eastAsiaTheme if defined): E0 – E1, E8 – EA, EC – |

| Unicode Block | Range | Classification |
|------------------------------------|-------------|---|
| | | ED, F2 – F3, F9 – FA, FC |
| Latin Extended-A | 0100 – 017F | hAnsi (or hAnsiTheme if defined), with the following exception: If hint is <i>eastAsia</i> , and the language of the run is either Chinese Traditional or Chinese Simplified, or the character set of the eastAsia (or eastAsiaTheme if defined) font is Chinese5 or GB2312 then eastAsia (or eastAsiaTheme if defined) font is used. |
| Latin Extended-B | 0180 – 024F | hAnsi (or hAnsiTheme if defined), with the following exception: If hint is <i>eastAsia</i> , and the language of the run is either Chinese Traditional or Chinese Simplified, or the character set of the eastAsia (or eastAsiaTheme if defined) font is Chinese5 or GB2312 then eastAsia (or eastAsiaTheme if defined) font is used. |
| IPA Extensions | 0250 – 02AF | hAnsi (or hAnsiTheme if defined), with the following exception: If hint is <i>eastAsia</i> , and the language of the run is either Chinese Traditional or Chinese Simplified, or the character set of the eastAsia (or eastAsiaTheme if defined) font is Chinese5 or GB2312 then eastAsia (or eastAsiaTheme if defined) font is used. |
| Spacing Modifier Letters | 02B0 – 02FF | If the hint is <i>eastAsia</i> then eastAsia (or eastAsiaTheme if defined) is used. |
| Combining Diacritical Marks | 0300 – 036F | If the hint is <i>eastAsia</i> then eastAsia (or eastAsiaTheme if defined) is used. |
| Greek | 0370 – 03CF | If the hint is <i>eastAsia</i> then eastAsia (or eastAsiaTheme if defined) is used. |
| Cyrillic | 0400 – 04FF | If the hint is <i>eastAsia</i> then eastAsia (or eastAsiaTheme if defined) is used. |
| Hebrew | 0590 – 05FF | ascii (or asciiTheme if defined) |
| Arabic | 0600 – 06FF | ascii (or asciiTheme if defined) |
| Syriac | 0700 – 074F | ascii (or asciiTheme if defined) |
| Arabic Supplement | 0750 – 077F | ascii (or asciiTheme if defined) |
| Thaana | 0780 – 07BF | ascii (or asciiTheme if defined) |
| Hangul Jamo | 1100 – 11FF | eastAsia (or eastAsiaTheme if defined) |
| Latin Extended Additional | 1E00 – 1EFF | hAnsi (or hAnsiTheme if defined), with the following exception: If the hint is <i>eastAsia</i> and the language of the run is Chinese Traditional or Chinese Simplified then eastAsia (or eastAsiaTheme if defined) is used. |
| General Punctuation | 2000 – 206F | If the hint is <i>eastAsia</i> then eastAsia (or eastAsiaTheme if defined) is used. |

| Unicode Block | Range | Classification |
|--|-------------|--|
| Superscripts and Subscripts | 2070 – 209F | If the hint is <i>eastAsia</i> then eastAsia (or eastAsiaTheme if defined) is used. |
| Currency Symbols | 20A0 – 20CF | If the hint is <i>eastAsia</i> then eastAsia (or eastAsiaTheme if defined) is used. |
| Combining Diacritical Marks for Symbols | 20D0 – 20FF | If the hint is <i>eastAsia</i> then eastAsia (or eastAsiaTheme if defined) is used. |
| Letter-like Symbols | 2100 – 214F | If the hint is <i>eastAsia</i> then eastAsia (or eastAsiaTheme if defined) is used. |
| Number Forms | 2150 – 218F | If the hint is <i>eastAsia</i> then eastAsia (or eastAsiaTheme if defined) is used. |
| Arrows | 2190 – 21FF | If the hint is <i>eastAsia</i> then eastAsia (or eastAsiaTheme if defined) is used. |
| Mathematical Operators | 2200 – 22FF | If the hint is <i>eastAsia</i> then eastAsia (or eastAsiaTheme if defined) is used. |
| Miscellaneous Technical | 2300 – 23FF | If the hint is <i>eastAsia</i> then eastAsia (or eastAsiaTheme if defined) is used. |
| Control Pictures | 2400 – 243F | If the hint is <i>eastAsia</i> then eastAsia (or eastAsiaTheme if defined) is used. |
| Optical Character Recognition | 2440 – 245F | If the hint is <i>eastAsia</i> then eastAsia (or eastAsiaTheme if defined) is used. |
| Enclosed Alphanumerics | 2460 – 24FF | If the hint is <i>eastAsia</i> then eastAsia (or eastAsiaTheme if defined) is used. |
| Box Drawing | 2500 – 257F | If the hint is <i>eastAsia</i> then eastAsia (or eastAsiaTheme if defined) is used. |
| Block Elements | 2580 – 259F | If the hint is <i>eastAsia</i> then eastAsia (or eastAsiaTheme if defined) is used. |
| Geometric Shapes | 25A0 – 25FF | If the hint is <i>eastAsia</i> then eastAsia (or eastAsiaTheme if defined) is used. |
| Miscellaneous Symbols | 2600 – 26FF | If the hint is <i>eastAsia</i> then eastAsia (or eastAsiaTheme if defined) is used. |
| Dingbats | 2700 – 27BF | If the hint is <i>eastAsia</i> then eastAsia (or eastAsiaTheme if defined) is used. |
| CJK Radicals Supplement | 2E80 – 2EFF | If the hint is <i>eastAsia</i> then eastAsia (or eastAsiaTheme if defined) is used. |
| Kangxi Radicals | 2F00 – 2FDF | eastAsia (or eastAsiaTheme if defined) |
| Ideographic Description Characters | 2FF0 – 2FFF | eastAsia (or eastAsiaTheme if defined) |

| Unicode Block | Range | Classification |
|---|-------------|--|
| CJK Symbols and Punctuation | 3000 – 303F | eastAsia (or eastAsiaTheme if defined) |
| Hiragana | 3040 – 309F | eastAsia (or eastAsiaTheme if defined) |
| Katakana | 30A0 – 30FF | eastAsia (or eastAsiaTheme if defined) |
| Bopomofo | 3100 – 312F | eastAsia (or eastAsiaTheme if defined) |
| Hangul Compatibility Jamo | 3130 – 318F | eastAsia (or eastAsiaTheme if defined) |
| Kanbun | 3190 – 319F | eastAsia (or eastAsiaTheme if defined) |
| Enclosed CJK Letters and Months | 3200 – 32FF | eastAsia (or eastAsiaTheme if defined) |
| CJK Compatibility | 3300 – 33FF | eastAsia (or eastAsiaTheme if defined) |
| CJK Unified Ideographs Extension A | 3400 – 4DBF | eastAsia (or eastAsiaTheme if defined) |
| CJK Unified Ideographs | 4E00 – 9FAF | eastAsia (or eastAsiaTheme if defined) |
| Yi Syllables | A000 – A48F | eastAsia (or eastAsiaTheme if defined) |
| Yi Radicals | A490 – A4CF | eastAsia (or eastAsiaTheme if defined) |
| Hangul Syllables | AC00 – D7AF | eastAsia (or eastAsiaTheme if defined) |
| High Surrogates | D800 – DB7F | eastAsia (or eastAsiaTheme if defined) |
| High Private Use Surrogates | DB80 – DBFF | eastAsia (or eastAsiaTheme if defined) |
| Low Surrogates | DC00 – DFFF | eastAsia (or eastAsiaTheme if defined) |
| Private Use Area | E000 – F8FF | If the hint is <i>eastAsia</i> then eastAsia (or eastAsiaTheme if defined) is used. |
| CJK Compatibility Ideographs | F900 – FAFF | eastAsia (or eastAsiaTheme if defined) |
| Alphabetic Presentation Forms | FB00 – FB4F | hAnsi (or hAnsiTheme if defined), with the following exceptions: If the hint is <i>eastAsia</i> then eastAsia (or eastAsiaTheme if defined) is used for characters in the range FB00 – FB1C. |

| Unicode Block | Range | Classification |
|--------------------------------------|-------------|--|
| | | For the range FB1D – FB4F, ascii (or asciiTheme if defined) is used. |
| Arabic Presentation Forms-A | FB50 – FDFD | ascii (or asciiTheme if defined) |
| CJK Compatibility Forms | FE30 – FE4F | eastAsia (or eastAsiaTheme if defined) |
| Small Form Variants | FE50 – FE6F | eastAsia (or eastAsiaTheme if defined) |
| Arabic Presentation Forms-B | FE70 – FEFE | ascii (or asciiTheme if defined) |
| Halfwidth and Fullwidth Forms | FF00 – FFEF | eastAsia (or eastAsiaTheme if defined) |

c. The standard states that the default fonts for the *ascii*, *hAnsi*, *cs*, and *eastAsia* attributes are application-defined.

Word uses a default font of Times New Roman for all of these attributes.

2.1.90 Part 4 Section 2.3.2.25, rPr (Run Properties)

For additional notes that apply to this portion of the standard, please see the notes for [oMath, §2.3.2.20\(a\)](#); [del, §2.13.5.15\(a\)](#); [ctrlPr, §7.1.2.23\(b\)](#).

2.1.91 Part 4 Section 2.3.2.26, rPr (Previous Run Properties)

For additional notes that apply to this portion of the standard, please see the notes for [oMath, §2.3.2.20\(a\)](#); [del, §2.13.5.15\(a\)](#).

2.1.92 Part 4 Section 2.3.2.27, rStyle (Referenced Character Style)

For additional notes that apply to this portion of the standard, please see the notes for [rPr, §2.7.4.4\(a\)](#); [rPr, §2.7.5.2\(a\)](#); [rPr, §2.7.8.1\(a\)](#); [numStyleLink, §2.9.22\(a\)](#); [rPr, §2.9.26\(a\)](#).

a. The standard states that this element specifies the style ID of the character style that shall be used to format the contents of this paragraph.

Word applies character styles to the parent run.

b. The standard does not limit the length of the value of the *val* attribute.

Word restricts the value of this attribute to be at most 253 characters.

2.1.93 Part 4 Section 2.3.2.28, rtl (Right To Left Text)

For additional notes that apply to this portion of the standard, please see the notes for [rPr, §2.7.4.4\(a\)](#); [rPr, §2.7.5.2\(a\)](#); [rPr, §2.7.8.1\(a\)](#).

a. The standard states that this element specifies that the alignment and reading order for the run shall be right to left.

Word uses this element to specify that the layout for the run shall be right to left.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.94 Part 4 Section 2.3.2.30, shd (Run Shading)

For additional notes that apply to this portion of the standard, please see the notes for [shd](#), [§2.4.33\(a,d\)](#).

2.1.95 Part 4 Section 2.3.2.31, smallCaps (Small Caps)

a. *The standard states that all small letter characters shall display as their capital letter equivalent in a font size two points smaller than the actual font size specified.*

Word displays small caps text in a font size slightly smaller than the original size, but not exactly 2 points smaller.

2.1.96 Part 4 Section 2.3.2.33, spacing (Character Spacing Adjustment)

a. *The standard does not state how a conflict between this element and the fitText element should be resolved, when their requirements conflict.*

Word ignores this element when the fitText element is also specified.

b. *The standard states that the values of the val attribute are defined by the XML Schema integer datatype.*

Word restricts the value of this attribute to be at least -31680 (-22") and at most 31680 (22").

2.1.97 Part 4 Section 2.3.2.34, specVanish (Paragraph Mark Is Always Hidden)

a. *The standard states that this element results in the text always being hidden.*

Word ignores this element unless the vanish element is also set.

2.1.98 Part 4 Section 2.3.2.36, sz (Font Size)

a. *The standard states that this element applies font size to non-complex script characters but does not specify how that determination is made.*

Word determines this state based on the state of the cs and rtl properties and applies font size to runs that do not use either of those properties.

2.1.99 Part 4 Section 2.3.2.37, szCs (Complex Script Font Size)

a. *The standard states that this element applies font size to complex script characters but does not specify how that determination is made.*

Word determines this state based on the state of the cs and rtl properties and applies font size to runs that use either of those properties.

2.1.100 Part 4 Section 2.3.2.38, u (Underline)

a. *The standard does not state a default value for the color attribute.*

If the color attribute is not specified, Word defaults to the value defined in the style hierarchy and then to a value of auto.

b. *The standard does not state which setting is applied when both the themeShade and the themeTint attributes are present.*

Word applies the themeTint setting when both of these attributes are present.

c. *The standard does not specify a default value for the val attribute.*

If the val attribute is not specified, Word defaults to the value defined in the style hierarchy and then to no underline.

2.1.101 Part 4 Section 2.3.2.41, w (Expanded/Compressed Text)

a. *The standard implies that the val attribute is optional.*

Word requires this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.102 Part 4 Section 2.3.2.42, webHidden (Web Hidden Text)

a. *The standard states that this setting shall cause content to be hidden from display at display time in a document when the document is being displayed in a web page view.*

Word ignores this setting when it is applied as part of a character style definition.

b. *The standard states that this element specifies whether the contents of this run shall be hidden from display at display time in a document when the document is being displayed in a web page view.*

If this element is present within the previous run properties for a run, Word will apply that setting to the current run properties when it is saved.

2.1.103 Part 4 Section 2.3.3.2, control (Floating Embedded Control)

For additional notes that apply to this portion of the standard, please see the notes for [pict.](#) [§2.9.23\(a\).](#)

a. *The standard allows strings of unbounded length for the value of the shapeid attribute.*

Word restricts the value of the shapeid attribute to at most 254 characters.

2.1.104 Part 4 Section 2.3.3.3, control (Inline Embedded Control)

For additional notes that apply to this portion of the standard, please see the notes for [control.](#) [§2.3.3.2\(a\).](#)

2.1.105 Part 4 Section 2.3.3.9, drawing (DrawingML Object)

a. *The standard states that there can be an unlimited number of inline drawing and anchor drawing properties inside the drawing element.*

Word expects a single child element to occur and will behave according to the last such element in the drawing element.

2.1.106 Part 4 Section 2.3.3.12, hpsRaise (Distance Between Phonetic Guide Text and Phonetic Guide Base Text)

- a. *The standard states that the values of the val attribute are defined by the XML Schema unsignedLong datatype.*

Word defines the values of this attribute with the XML Schema short datatype.

2.1.107 Part 4 Section 2.3.3.14, lid (Language ID for Phonetic Guide)

For additional notes that apply to this portion of the standard, please see the notes for [lid](#), [§2.14.17\(a\)](#).

2.1.108 Part 4 Section 2.3.3.17, movie (Embedded Video)

For additional notes that apply to this portion of the standard, please see the notes for [pict](#), [§2.9.23\(a\)](#); [attachedTemplate](#), [§2.15.1.6\(a\)](#).

- a. *The standard states that this element shall be used to store video information associated with an image.*

Word ignores this element when loading a WordprocessingML document; therefore, this element is lost on roundtrip.

2.1.109 Part 4 Section 2.3.3.19, object (Inline Embedded Object)

- a. *The standard states that any element from the VML namespace or the Office VML Drawing namespace is a valid child of the object element.*

Word only allows the arc, curve, group, image, line, OLEObject, oval, polyline, rect, roundrect, shape, and shapetype elements from these namespaces to be children of the object element.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.110 Part 4 Section 2.3.3.21, pict (VML Object)

- a. *The standard states that any element from the VML namespace or the Office VML Drawing namespace is allowed as a child element.*

Word only allows the following child elements: arc, curve, group, image, line, OLEObject, oval, polyline, rect, roundrect, shape, and shapetype.

2.1.111 Part 4 Section 2.3.3.23, rt (Phonetic Guide Text)

For additional notes that apply to this portion of the standard, please see the notes for [rubyBase](#), [§2.3.3.26\(a-d\)](#); [oMath](#), [§7.1.2.77\(d\)](#).

2.1.112 Part 4 Section 2.3.3.26, rubyBase (Phonetic Guide Base Text)

For additional notes that apply to this portion of the standard, please see the notes for [oMath](#), [§7.1.2.77\(d\)](#).

- a. *The standard makes no mention of a child customXml element.*

Word allows a child customXml element as defined in customXml (Ruby Cell-Level Custom XML Element) ([§3.1.3.1.1, customXml](#)).

b. *The standard makes no mention of a child fldSimple element.*

Word allows a child fldSimple element as defined in fldSimple (Ruby Simple Field) ([§3.1.3.1.2, fldSimple](#)).

c. *The standard makes no mention of a child hyperlink element.*

Word allows a child hyperlink element as defined in hyperlink (Ruby Hyperlink) ([§3.1.3.1.3, hyperlink](#)).

d. *The standard makes no mention of a child sdt element.*

Word allows a child sdt element as defined in sdt (Ruby Inline-Level Structured Document Tag) ([§3.1.3.1.6, sdt](#)).

2.1.113 Part 4 Section 2.3.3.29, sym (Symbol Character)

a. *The standard states that the font attribute can contain any string value.*

Word restricts the contents of the font attribute to a maximum length of 31 characters.

2.1.114 Part 4 Section 2.4.1, bidiVisual (Visually Right to Left Table)

For additional notes that apply to this portion of the standard, please see the notes for [tblPr, §2.7.5.3\(a\)](#); [tblPr, §2.7.5.4\(a\)](#).

a. *The standard states that the values 0 and false on the val attribute are equivalent to the value off.*

Word treats these values on this attribute as equivalent to the value on.

This note applies to the following products: 2007, 2007 SP1.

2.1.115 Part 4 Section 2.4.2, bottom (Table Cell Bottom Margin Exception)

For additional notes that apply to this portion of the standard, please see the notes for [top, §2.4.73\(a\)](#).

a. *The standard states that the type and w attributes are optional.*

Word requires these attributes.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

b. *The standard states that the values of the w attribute are defined by the XML Schema integer datatype.*

Word defines the values of this attribute with the XML Schema short datatype, with a minimum value of 0.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.116 Part 4 Section 2.4.3, bottom (Table Cell Bottom Border)

For additional notes that apply to this portion of the standard, please see the notes for [bar, §2.3.1.4\(a-c\)](#); [bdr, §2.3.2.3\(a\)](#); [left, §2.15.2.21\(a\)](#).

2.1.117 Part 4 Section 2.4.4, bottom (Table Bottom Border)

For additional notes that apply to this portion of the standard, please see the notes for [bar](#), [§2.3.1.4\(a-c\)](#); [bdr](#), [§2.3.2.3\(a\)](#); [left](#), [§2.15.2.21\(a\)](#).

2.1.118 Part 4 Section 2.4.5, bottom (Table Cell Bottom Margin Default)

For additional notes that apply to this portion of the standard, please see the notes for [bottom](#), [§2.4.2\(a, b\)](#); [top](#), [§2.4.73\(a\)](#).

2.1.119 Part 4 Section 2.4.6, cantSplit (Table Row Cannot Break Across Pages)

a. *The standard states that the values 0 and false on the val attribute are equivalent to the value off.*

Word treats these values on this attribute as equivalent to the value on.

This note applies to the following products: 2007, 2007 SP1.

b. *The standard states that the row shall start on a new page and flow onto multiple pages as necessary when the contents of the table row cannot fit on a single page.*

Word starts the row on a new page and cuts off overflowing contents as necessary under this circumstance.

2.1.120 Part 4 Section 2.4.7, cnfStyle (Table Cell Conditional Formatting)

For additional notes that apply to this portion of the standard, please see the notes for [tcPr](#), [§2.7.5.8\(a\)](#); [tcPr](#), [§2.7.5.9\(b\)](#).

2.1.121 Part 4 Section 2.4.8, cnfStyle (Table Row Conditional Formatting)

For additional notes that apply to this portion of the standard, please see the notes for [trPr](#), [§2.7.5.10\(b\)](#); [trPr](#), [§2.7.5.11\(a\)](#).

2.1.122 Part 4 Section 2.4.9, divId (Associated HTML div ID)

For additional notes that apply to this portion of the standard, please see the notes for [divId](#), [§2.3.1.10\(a\)](#); [trPr](#), [§2.7.5.10\(b\)](#); [trPr](#), [§2.7.5.11\(a\)](#).

a. *The standard states that the values of the val attribute are defined by the XML Schema integer datatype.*

Word does not allow a value of 0 on this attribute.

2.1.123 Part 4 Section 2.4.10, gridAfter (Grid Columns After Last Cell)

For additional notes that apply to this portion of the standard, please see the notes for [trPr](#), [§2.7.5.10\(b\)](#); [trPr](#), [§2.7.5.11\(a\)](#).

a. *The standard states that if this element conflicts with the document grid, then it is ignored.*

In Word, if this element conflicts with the table grid, then it is ignored.

b. *The standard states the values for the val attribute are defined by the ST_DecimalNumber simple type*

Word only ignores 0 or negative values for this element

2.1.124 Part 4 Section 2.4.11, gridBefore (Grid Columns Before First Cell)

For additional notes that apply to this portion of the standard, please see the notes for [trPr, §2.7.5.10\(b\)](#); [trPr, §2.7.5.11\(a\)](#).

a. The standard states that if the value of this element exceeds the number of grid columns, then the value shall be ignored.

Word requires that this value not exceed the total number of grid columns. If the value of this element exceeds the number of grid columns, then the behavior is unpredictable.

b. The possible values for the val attribute are defined by the ST_DecimalNumber simple type

The product only understand non-negative values for this element

2.1.125 Part 4 Section 2.4.13, gridSpan (Grid Columns Spanned by Current Table Cell)

For additional notes that apply to this portion of the standard, please see the notes for [tcPr, §2.7.5.8\(a\)](#); [tcPr, §2.7.5.9\(b\)](#).

a. The standard allows a gridSpan to have a value of 0.

Word treats a gridSpan of 0 the same as a grid span of 1.

2.1.126 Part 4 Section 2.4.14, hidden (Hidden Table Row Marker)

a. The standard allows the hidden element inside a table style definition.

Word ignores the hidden element inside a table style definition.

2.1.127 Part 4 Section 2.4.15, hideMark (Ignore End Of Cell Marker In Row Height Calculation)

For additional notes that apply to this portion of the standard, please see the notes for [tcPr, §2.7.5.8\(a\)](#); [tcPr, §2.7.5.9\(b\)](#).

a. The standard states that the values 0 and false on the val attribute are equivalent to the value off.

Word treats these values on this attribute as equivalent to the value on.

This note applies to the following products: 2007, 2007 SP1.

2.1.128 Part 4 Section 2.4.16, hMerge (Horizontally Merged Cell)

For additional notes that apply to this portion of the standard, please see the notes for [tcPr, §2.7.5.8\(a\)](#); [tcPr, §2.7.5.9\(b\)](#).

2.1.129 Part 4 Section 2.4.17, insideH (Table Inside Horizontal Edges Border)

For additional notes that apply to this portion of the standard, please see the notes for [bar, §2.3.1.4\(a-c\)](#); [bdr, §2.3.2.3\(a\)](#); [left, §2.15.2.21\(a\)](#).

2.1.130 Part 4 Section 2.4.18, insideH (Table Cell Inside Horizontal Edges Border)

For additional notes that apply to this portion of the standard, please see the notes for [bar](#), [§2.3.1.4\(a-c\)](#); [bdr](#), [§2.3.2.3\(a\)](#); [left](#), [§2.15.2.21\(a\)](#).

a. *The standard states that if the table has cell spacing then inside horizontal borders are displayed.*

In Word, when a table has cell spacing, the appearance of the insideH border is still subject to the conflict resolution algorithm defined by the tcBorders and tblBorders elements.

2.1.131 Part 4 Section 2.4.19, insideV (Table Cell Inside Vertical Edges Border)

For additional notes that apply to this portion of the standard, please see the notes for [bar](#), [§2.3.1.4\(a-c\)](#); [bdr](#), [§2.3.2.3\(a\)](#); [left](#), [§2.15.2.21\(a\)](#).

a. *The standard states that if the table has cell spacing then inside vertical borders are displayed.*

In Word, when a table has cell spacing the appearance of the insideV border is still subject to the conflict resolution algorithm defined by the tcBorders and tblBorders elements.

2.1.132 Part 4 Section 2.4.20, insideV (Table Inside Vertical Edges Border)

For additional notes that apply to this portion of the standard, please see the notes for [bar](#), [§2.3.1.4\(a-c\)](#); [bdr](#), [§2.3.2.3\(a\)](#); [left](#), [§2.15.2.21\(a\)](#).

2.1.133 Part 4 Section 2.4.21, jc (Table Alignment Exception)

For additional notes that apply to this portion of the standard, please see the notes for [jc](#), [§2.4.23\(a\)](#); [vlJc](#), [§2.9.8\(a\)](#).

2.1.134 Part 4 Section 2.4.22, jc (Table Row Alignment)

For additional notes that apply to this portion of the standard, please see the notes for [jc](#), [§2.4.23\(a\)](#); [vlJc](#), [§2.9.8\(a\)](#).

2.1.135 Part 4 Section 2.4.23, jc (Table Alignment)

a. *The standard states that the values of the val attribute are defined by the ST_Jc simple type.*

Word only allows the values left, center, and right.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

b. *The standard states that the table shall be left justified with zero indentation from the leading margin when no table alignment is specified in the style hierarchy.*

Word honors indentation under this circumstance.

2.1.136 Part 4 Section 2.4.24, left (Table Cell Left Border)

For additional notes that apply to this portion of the standard, please see the notes for [bar](#), [§2.3.1.4\(a-c\)](#); [bdr](#), [§2.3.2.3\(a\)](#); [left](#), [§2.15.2.21\(a\)](#).

2.1.137 Part 4 Section 2.4.25, left (Table Cell Left Margin Exception)

For additional notes that apply to this portion of the standard, please see the notes for [bottom, §2.4.2\(a, b\)](#); [top, §2.4.73\(a\)](#).

a. *The standard states that the table cell left margin exception overrides the table cell bottom margin.*

In Word, the table cell left margin exception overrides the table cell left margin.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.138 Part 4 Section 2.4.26, left (Table Cell Left Margin Default)

For additional notes that apply to this portion of the standard, please see the notes for [bottom, §2.4.2\(a, b\)](#).

a. *The standard states that the table cell left margin default may be overridden by the table cell bottom margin.*

In Word, the table cell left margin default may be overridden by the table cell left margin.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

b. *The standard states that any width value of type pct or auto for this element shall be ignored.*

Word uses a default value of 0 for the width when the value of the type attribute is pct or auto.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.139 Part 4 Section 2.4.27, left (Table Left Border)

For additional notes that apply to this portion of the standard, please see the notes for [bar, §2.3.1.4\(a-c\)](#); [bdr, §2.3.2.3\(a\)](#); [left, §2.15.2.21\(a\)](#).

2.1.140 Part 4 Section 2.4.28, noWrap (Don't Wrap Cell Content)

a. *The standard states that the values 0 and false on the val attribute are equivalent to the value off.*

Word treats these values on this attribute as equivalent to the value on.

This note applies to the following products: 2007, 2007 SP1.

2.1.141 Part 4 Section 2.4.29, right (Table Cell Right Margin Default)

For additional notes that apply to this portion of the standard, please see the notes for [bottom, §2.4.2\(a, b\)](#).

a. *The standard states that any width value of type pct or auto for this element shall be ignored.*

Word uses a default value of 0 for the width when the value of the type attribute is pct or auto.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.142 Part 4 Section 2.4.30, right (Table Cell Right Border)

For additional notes that apply to this portion of the standard, please see the notes for [bar](#), [§2.3.1.4\(a-c\)](#); [bdr](#), [§2.3.2.3\(a\)](#); [left](#), [§2.15.2.21\(a\)](#).

2.1.143 Part 4 Section 2.4.31, right (Table Cell Right Margin Exception)

For additional notes that apply to this portion of the standard, please see the notes for [bottom](#), [§2.4.2\(a, b\)](#); [top](#), [§2.4.73\(a\)](#).

a. *The standard states that the setting from this element shall override the table cell bottom margin definition specified by the right element contained within the table properties.*

Word uses the setting from this element to override the table cell right margin definition specified by the right element contained within the table properties.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.144 Part 4 Section 2.4.32, right (Table Right Border)

For additional notes that apply to this portion of the standard, please see the notes for [bar](#), [§2.3.1.4\(a-c\)](#); [bdr](#), [§2.3.2.3\(a\)](#); [left](#), [§2.15.2.21\(a\)](#).

2.1.145 Part 4 Section 2.4.33, shd (Table Cell Shading)

a. *The standard does not state which setting is applied when both the themeShade and the themeTint attributes are present.*

Word applies the themeTint setting when both of these attributes are present.

b. *The standard states that if the shd element is omitted, then the cell shading is determined by the table-level or table-level exception cell shading settings.*

In Word if the shd element is omitted, then the cell shading is determined by the table style.

c. *The standard specifies that the val attribute is both required and optional.*

Word treats the val attribute as required.

d. *The standard states that if the themeFill attribute is omitted, the color attribute is used.*

Because themeFill is the theme color equivalent of fill, if themeFill is omitted, Word uses the fill attribute in its place.

2.1.146 Part 4 Section 2.4.34, shd (Table Shading Exception)

For additional notes that apply to this portion of the standard, please see the notes for [shd](#), [§2.4.33\(a,d\)](#).

a. *The standard states that table shading is applied to cells in the table.*

Word applies table shading only to the cell spacing of the table.

b. *The standard specifies that the val attribute is both required and optional.*

Word treats the val attribute as required.

2.1.147 Part 4 Section 2.4.35, shd (Table Shading)

For additional notes that apply to this portion of the standard, please see the notes for [shd](#), [§2.4.33\(a,d\)](#).

- a. *The standard states that table shading is applied to cells in the table.*

Word applies table shading only to the cell spacing of the table.

- b. *The standard specifies that the val attribute is both required and optional.*

Word treats the val attribute as required.

2.1.148 Part 4 Section 2.4.36, tbl (Table)

For additional notes that apply to this portion of the standard, please see the notes for [oMath](#), [§7.1.2.77\(g\)](#); [oMathPara](#), [§7.1.2.78\(d\)](#).

2.1.149 Part 4 Section 2.4.37, tblBorders (Table Borders Exceptions)

- a. *The standard specifies a method for resolving border conflicts.*

In Word, when cell spacing is nonzero, **insideH** and **insideV** table-level exception borders may still conflict with cell borders. If there is a border conflict, it shall be resolved using the method describe in **tcBorders** (“[\[ECMA-376\]](#) Part 4 §2.4.63; tcBorders (Table Cell Borders)”).

- b. *The standard says that if cell spacing is nonzero, then there is no border conflict even though insideH and insideV table exception borders may conflict with cell borders.*

In Word, when cell spacing is nonzero, insideH and insideV table exception borders may still conflict with cell borders.

2.1.150 Part 4 Section 2.4.38, tblBorders (Table Borders)

- a. *The standard specifies a method for resolving border conflicts.*

In Word, when cell spacing is nonzero, **insideH** and **insideV** table-level exception borders may still conflict with cell borders. If there is a border conflict, it shall be resolved using the method describe in **tcBorders** (“[\[ECMA-376\]](#) Part 4 §2.4.63; tcBorders (Table Cell Borders)”).

- b. *The standard says that if cell spacing is nonzero, then there is no border conflict even though insideH and insideV table exception borders may conflict with cell borders.*

In Word, when cell spacing is nonzero, insideH and insideV table exception borders may still conflict with cell borders.

2.1.151 Part 4 Section 2.4.41, tblCellSpacing (Table Cell Spacing Exception)

For additional notes that apply to this portion of the standard, please see the notes for [bottom](#), [§2.4.2\(a, b\)](#).

- a. *The standard states that any width value of type pct or auto for this element shall be ignored.*

Word uses a default value of 0 for the width when the value of the type attribute is pct or auto.

2.1.152 Part 4 Section 2.4.42, tblCellSpacing (Table Row Cell Spacing)

For additional notes that apply to this portion of the standard, please see the notes for [bottom, §2.4.2\(a, b\)](#).

- a. *The standard states that any width value of type pct or auto for this element shall be ignored.*

Word uses a default value of 0 for the width when the value of the type attribute is pct or auto.

2.1.153 Part 4 Section 2.4.43, tblCellSpacing (Table Cell Spacing Default)

For additional notes that apply to this portion of the standard, please see the notes for [bottom, §2.4.2\(a, b\)](#).

- a. *The standard states that any width value of type pct or auto for this element shall be ignored.*

Word uses a default value of 0 for the width when the value of the type attribute is pct or auto.

2.1.154 Part 4 Section 2.4.46, tblHeader (Repeat Table Row on Every New Page)

- a. *The standard states that the values 0 and false on the val attribute are equivalent to the value on.*

Word treats these values on this attribute as equivalent to the value on.

This note applies to the following products: 2007, 2007 SP1.

- b. *The standard states that the table shall inherit the table cell spacing from the associated table style when this element is omitted.*

Word has the table inherit the value of the tblHeader element from the associated table style under this circumstance.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.155 Part 4 Section 2.4.47, tblInd (Table Indent from Leading Margin Exception)

- a. *The standard allows table indent exception to be set for any table row.*

Word applies table indent exception to the whole table if the property is specified for the first table row and ignores this property if it is set for other table rows.

- b. *The standard says tblInd is ignored if justification on the parent table row is not left.*

Word does not ignore tblInd if the justification is not left.

- c. *The standard states that the type and w attributes are optional.*

Word requires these attributes.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

- d. *The standard states that the values of the w attribute are defined by the XML Schema integer datatype.*

Word defines the values of this attribute with the XML Schema short datatype.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.156 Part 4 Section 2.4.48, tblInd (Table Indent from Leading Margin)

a. *The standard says tblInd is ignored if the justification is not left.*

Word does not ignore tblInd if the justification is not left.

b. *The standard states that the values of the w attribute are defined by the XML Schema integer datatype.*

Word defines the values of this attribute with the XML Schema short datatype.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

c. *The standard states that the type and w attributes are optional.*

Word requires these attributes.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.157 Part 4 Section 2.4.49, tblLayout (Table Layout)

For additional notes that apply to this portion of the standard, please see the notes for [tblPr, §2.7.5.3\(a\)](#); [tblPr, §2.7.5.4\(a\)](#).

2.1.158 Part 4 Section 2.4.50, tblLayout (Table Layout Exception)

a. *The standard states that the table layout exception can be used to set any table row's table layout to autofit or fixed.*

Word ignores this element if it is not in the first row of the table or if its value is autofit. If the value is not ignored, then it applies to the whole table.

b. *The standard states that if the tblLayout element is omitted, then the value defaults to autofit.*

In Word, if the tblLayout element is omitted, then the layout algorithm is determined by the default set of table properties on the parent table.

2.1.159 Part 4 Section 2.4.51, tblLook (Table Style Conditional Formatting Settings)

For additional notes that apply to this portion of the standard, please see the notes for [tblPr, §2.7.5.3\(a\)](#); [tblPr, §2.7.5.4\(a\)](#).

a. *The standard states that when the tblLook element is omitted, the bitmask of table style options on the current table shall be assumed to be 0x0000.*

In Word, when the tblLook element is omitted, the bitmask of table style options on the current table is assumed to be 0x04A0.

b. *The standard states there are six conditional formatting options that can be set in tblLook.*

In addition to the six listed conditional formatting options, Word supports the following additional options and combinations:

0x00A0 - Allow NE Cell conditional formatting. This and the following bitmasks are combinations of two bits. These bits allow an intersection of the appropriate row and column.

0x0120 - Allow NW Cell conditional formatting.

0x00C0 - Allow SE Cell conditional formatting.

0x0140 - Allow SW Cell conditional formatting.

2.1.160 Part 4 Section 2.4.52, tblLook (Table Style Conditional Formatting Settings Exception)

a. *The standard states there are six conditional formatting options that can be set in tblLook.*

In addition to the six listed conditional formatting options, Word supports the following additional options and combinations:

0x00A0 - Allow NE Cell conditional formatting. This and the following bitmasks are combinations of two bits. These bits allow an intersection of the appropriate row and column.

0x0120 - Allow NW Cell conditional formatting.

0x00C0 - Allow SE Cell conditional formatting.

0x0140 - Allow SW Cell conditional formatting.

2.1.161 Part 4 Section 2.4.53, tblOverlap (Floating Table Allows Other Tables to Overlap)

For additional notes that apply to this portion of the standard, please see the notes for [tblPr, §2.7.5.3\(a\)](#); [tblPr, §2.7.5.4\(a\)](#).

2.1.162 Part 4 Section 2.4.54, tblpPr (Floating Table Positioning)

For additional notes that apply to this portion of the standard, please see the notes for [tblPr, §2.7.5.3\(a\)](#); [tblPr, §2.7.5.4\(a\)](#).

a. *The standard says that horizontal floating table positioning flips which edge it is relative to in right to left paragraphs versus left to right paragraphs.*

In Word, horizontal floating table positioning is always relative to the left edge.

b. *The standard does not specify any conditions under which tblpPr is ignored.*

Word ignores the **tblpPr** element if all attributes are omitted. It also ignores this element if the table is contained in a textbox, footnote, endnote, or comment, or if all of the following conditions are met:

The **tblpX** attribute value is 0.

The **tblpY** attribute value is 0.

The **horzAnchor** attribute value is *text*.

The **vertAnchor** attribute value is not *text*.

c. *The standard states that the default values of vertAnchor and horzAnchor are page.*

In Word, the default value for vertAnchor is margin and the default value for horzAnchor is text.

d. *The standard allows any integer for leftFromText, rightFromText, topFromText, bottomFromText, tblpX, and tblpY.*

Word only allows integers between 0 and 32767 for leftFromText, rightFromText, topFromText, bottomFromText, tblpX, and tblpY.

e. *The standard does not specify that tblpX and tblpY should be changed before display.*

To avoid the condition where the tblpPr element is ignored, Word adds 1 twentieth of a point to the actual distance value when it saves a file and subtracts 1 twentieth of a point to the actual distance value when it opens a file. For example, if the value of attribute **tblpX** or **tblpY** is supposed be 0 twentieths of a point, then Word writes 1 instead, and if Word reads the value 1 for tblpX or tblpY it interprets that value as 0 instead.

2.1.163 Part 4 Section 2.4.55, tblPr (Table Properties)

a. *The standard states that the tblStyleColBandSize and tblStyleRowBandSize elements are valid children of the tblPr element.*

Word does not allow these elements to be children of the tblPr element.

2.1.164 Part 4 Section 2.4.56, tblPr (Previous Table Properties)

a. *The standard states that the tblStyleColBandSize and tblStyleRowBandSize elements are valid children of the tblPr element.*

Word does not allow these elements to be children the tblPr element.

2.1.165 Part 4 Section 2.4.59, tblStyle (Referenced Table Style)

For additional notes that apply to this portion of the standard, please see the notes for [tblPr, §2.7.5.3\(a\)](#); [tblPr, §2.7.5.4\(a\)](#); [numStyleLink, §2.9.22\(a\)](#).

a. *The standard does not limit the length of the value of the val attribute.*

Word restricts the value of this attribute to be at most 253 characters.

2.1.166 Part 4 Section 2.4.60, tblW (Preferred Table Width Exception)

For additional notes that apply to this portion of the standard, please see the notes for [bottom, §2.4.2\(a, b\)](#); [top, §2.4.73\(a\)](#).

a. *The standard specifies that this element specifies the preferred width for the parent table row.*

Word ignores this element if it is not present in the first row of the table. If it is in the first row, Word applies this preferred width to the entire table.

b. *The standard specifies that if w is 0, the preferred table width is 0.*

Word interprets the type attribute as auto if w is 0.

c. *The standard states that if the tblW element is omitted, then the cell width is auto.*

In Word, if the tblW element is omitted, then the table width is determined by the preferred table width element.

d. *The standard does not specify the behavior when the type attribute is nil.*

Word interprets the type attribute value as auto when the type attribute has a value of nil.

2.1.167 Part 4 Section 2.4.61, tblW (Preferred Table Width)

For additional notes that apply to this portion of the standard, please see the notes for [bottom, §2.4.2\(a, b\)](#); [top, §2.4.73\(a\)](#); [tblPr, §2.7.5.3\(a\)](#); [tblPr, §2.7.5.4\(a\)](#).

a. *The standard specifies that if w is 0, the preferred table width is 0.*

Word interprets the type attribute as auto if w is 0.

b. *The standard does not specify the behavior when the type attribute is nil.*

When the type attribute has a value of nil, Word interprets the type attribute value as auto.

2.1.168 Part 4 Section 2.4.62, tc (Table Cell)

For additional notes that apply to this portion of the standard, please see the notes for [oMath, §7.1.2.77\(g\)](#); [oMathPara, §7.1.2.78\(d\)](#).

2.1.169 Part 4 Section 2.4.63, tcBorders (Table Cell Borders)

For additional notes that apply to this portion of the standard, please see the notes for [tcPr, §2.7.5.8\(b\)](#).

a. *The standard specifies a method for resolving border conflicts.*

Word determines top, bottom, left, and right cell border for each cell as follows:

If the cell border is omitted, find the cell border from the table style ("[\[ECMA-376\]](#) Part 4 §2.7.5; Table Styles").

If the cell border is still not specified, find the appropriate border from the table-level border exceptions ("[\[ECMA-376\]](#) Part 4 §2.4.37; tblBorders").

If the cell border is still not specified, find the appropriate border from the table-level borders ("[\[ECMA-376\]](#) Part 4 §2.4.38; tblBorders").

If the cell spacing is nonzero as specified using the tblCellSpacing element ("[\[ECMA-376\]](#) Part 4 §2.4.41; tblCellSpacing", "[\[ECMA-376\]](#) Part 4 §2.4.42; tblCellSpacing", "[\[ECMA-376\]](#) Part 4 §2.4.43; tblCellSpacing"), then all cell borders and outer table borders display.

If the cell spacing is zero, then there may be a conflict between two adjacent borders. In Office, this conflict is resolved using the following procedure:

If either conflicting table cell border is *nil* or *none* (no border), then the opposing border shall be displayed.

Each border shall then be assigned a weight using the following formula, and the border which has a higher value using this calculation shall be displayed over the alternative border:

$$W_{\text{border}} = \text{border width} * \text{border number}$$

The border width shall be specified in measurements of eighths of a point. The border number shall be determined by the following list. The borders with *dotted* and *dashed* styles shall be assigned the weight 1 regardless of the border width and number.

| Border Number | |
|-------------------------------|-----------|
| single | 1 |
| thick | 2 |
| double | 3 |
| dotDash | 8 |
| dotDotDash | 9 |
| triple | 10 |
| thinThickSmallGap | 11 |
| thickThinSmallGap | 12 |
| thinThickThinSmallGap | 13 |
| thinThickMediumGap | 14 |
| thickThinMediumGap | 15 |
| thinThickThinMediumGap | 16 |
| thinThickLargeGap | 17 |
| thickThinLargeGap | 18 |
| thinThickThinLargeGap | 19 |
| wave | 20 |
| doubleWave | 21 |
| dashSmallGap | 22 |
| dashDotStroked | 23 |
| threeDEmboss | 24 |
| threeDEngrave | 25 |
| outset | 26 |
| inset | 27 |

If the borders have an equal weight, then the higher of the two on this precedence list shall be displayed:

single
thick
double
dotted
dashed
dotDash
dotDotDash
triple
thinThickSmallGap
thickThinSmallGap
thinThickThinSmallGap
thinThickMediumGap
thickThinMediumGap
thinThickThinMediumGap
thinThickLargeGap
thickThinLargeGap
thinThickThinLargeGap
wave
doubleWave
dashSmallGap
dashDotStroked
threeDEmboss
threeDEngrave
outset
inset

If the borders have an identical style, then each border color shall be assigned a brightness value as follows:

$$\text{Brightness} = R + B + 2 * G$$

The color with the smaller brightness value shall be displayed.

If the borders have an identical brightness value, then each border color shall be assigned a new brightness value as follows:

$$\text{Brightness} = B + 2 * G$$

The color with the smaller brightness value shall be displayed.

If the borders have an identical brightness value, then each border color shall be assigned a brightness value as follows:

$$\text{Brightness} = G$$

The color with the smaller brightness value shall be displayed.

If the borders have an identical brightness value, then they are functionally identical, and the first border in reading order should be displayed.

2.1.170 Part 4 Section 2.4.64, tcFitText (Fit Text Within Cell)

For additional notes that apply to this portion of the standard, please see the notes for [tcPr, §2.7.5.8\(a\)](#); [tcPr, §2.7.5.9\(b\)](#).

a. *The standard states that the values 0 and false on the val attribute are equivalent to the value off.*

Word treats these values on this attribute as equivalent to the value on.

This note applies to the following products: 2007, 2007 SP1.

b. *The standard defines no special behavior for a cell containing text with line breaks.*

In Word, the text in the first paragraph in the cell is fit, but subsequent paragraphs are not.

c. *The standard states that inter-character spacing shall be reduced to fit text.*

In Word, the horizontal size of non-space characters is also reduced to fit text.

2.1.171 Part 4 Section 2.4.68, tcW (Preferred Table Cell Width)

For additional notes that apply to this portion of the standard, please see the notes for [bottom, §2.4.2\(a, b\)](#); [top, §2.4.73\(a\)](#); [tcPr, §2.7.5.8\(a\)](#); [tcPr, §2.7.5.9\(b\)](#).

a. *The standard states that if the w attribute is 0, then preferred cell width is 0.*

In Word, if the w attribute is 0, then the type attribute is interpreted as auto.

b. *The standard does not specify the behavior when type is nil.*

Word interprets the type attribute value as auto when the type attribute has a value of nil.

2.1.172 Part 4 Section 2.4.69, textDirection (Table Cell Text Flow Direction)

For additional notes that apply to this portion of the standard, please see the notes for [tcPr, §2.7.5.8\(a\)](#); [tcPr, §2.7.5.9\(b\)](#).

a. *The standard states that if the textDirection element is omitted and is not specified in table style, then the table cell shall inherit text flow direction from the parent section.*

In Word, if the textDirection element is omitted and is not specified in table style, then the default text flow direction is lRtB.

2.1.173 Part 4 Section 2.4.70, t12br (Table Cell Top Left to Bottom Right Diagonal Border)

For additional notes that apply to this portion of the standard, please see the notes for [bar](#), [§2.3.1.4\(a-c\)](#); [bdr](#), [§2.3.2.3\(a\)](#); [left](#), [§2.15.2.21\(a\)](#).

- a. The standard places no restrictions on the border style used in the val attribute.

Word displays diagonal cell borders as a single solid line, except borders with dotted, dashed, dashSmallGap, dotDash, dotDotDash, and double border styles.

- b. The standard states that if this element is omitted then the table's border settings may be used.

In Word, if this element is omitted, then the table styles border is used.

2.1.174 Part 4 Section 2.4.71, top (Table Top Border)

For additional notes that apply to this portion of the standard, please see the notes for [bar](#), [§2.3.1.4\(a-c\)](#); [bdr](#), [§2.3.2.3\(a\)](#); [left](#), [§2.15.2.21\(a\)](#).

2.1.175 Part 4 Section 2.4.72, top (Table Cell Top Margin Default)

For additional notes that apply to this portion of the standard, please see the notes for [bottom](#), [§2.4.2\(a, b\)](#); [top](#), [§2.4.73\(a\)](#).

2.1.176 Part 4 Section 2.4.73, top (Table Cell Top Margin Exception)

For additional notes that apply to this portion of the standard, please see the notes for [bottom](#), [§2.4.2\(a, b\)](#).

- a. The standard states that the value of the type attribute shall be assumed to be dxa (twentieths of a point) when it is omitted.

Word ignores this element when this attribute is omitted.

2.1.177 Part 4 Section 2.4.74, top (Table Cell Top Border)

For additional notes that apply to this portion of the standard, please see the notes for [bar](#), [§2.3.1.4\(a-c\)](#); [bdr](#), [§2.3.2.3\(a\)](#); [left](#), [§2.15.2.21\(a\)](#).

2.1.178 Part 4 Section 2.4.75, tr (Table Row)

For additional notes that apply to this portion of the standard, please see the notes for [oMath](#), [§7.1.2.77\(g\)](#); [oMathPara](#), [§7.1.2.78\(d\)](#).

- a. The standard states that if a table cell does not contain at least one child, then the file is corrupt.

In Word, if a table row does not contain at least one child other than the row properties, then the file is corrupt.

2.1.179 Part 4 Section 2.4.76, tr2bl (Table Cell Top Right to Bottom Left Diagonal Border)

For additional notes that apply to this portion of the standard, please see the notes for [bar](#), [§2.3.1.4\(a-c\)](#); [bdr](#), [§2.3.2.3\(a\)](#); [left](#), [§2.15.2.21\(a\)](#).

- a. *The standard places no restrictions on the border style used in the val attribute.*

Word displays diagonal cell borders as a single solid line, except borders with dotted, dashed, dashSmallGap, dotDash, dotDotDash, and double border styles.

- b. *The standard states that if this element is omitted then the table's border settings may be used.*

In Word, if this element is omitted, then the table styles border is used.

2.1.180 Part 4 Section 2.4.77, trHeight (Table Row Height)

For additional notes that apply to this portion of the standard, please see the notes for [trPr](#), [§2.7.5.10\(b\)](#); [trPr](#), [§2.7.5.11\(a\)](#).

- a. *The standard states that if the hRule attribute is omitted, then its value is assumed to be auto.*

In Word, if the hRule attribute is omitted, then its value is assumed to be atLeast.

- b. *The standard implies that the val attribute is optional.*

Word requires this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

- c. *The standard states that if the hRule attribute is auto, then the val attribute is ignored.*

In Word, if the hRule attribute is auto, then the val attribute must be 0.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

- d. *The standard states that the values of the val attribute are defined by the XML Schema unsignedLong datatype.*

Word defines the values of this attribute with the XML Schema unsignedInt datatype, with a minimum value of 0 and a maximum value of 31680.

- e. *The standard allows the hRule attribute to be set to exact while the val attribute is set to 0.*

Word requires that if the hRule attribute is set to exact, then the val attribute must not be 0.

- f. *The standard states that if the hRule attribute is exact, the row height must be exactly as specified.*

In Word, if the hRule attribute is exact, Word sets the row height to the exact height plus the largest bottom cell padding of any cell in the row.

2.1.181 Part 4 Section 2.4.80, vAlign (Table Cell Vertical Alignment)

- a. *The standard states that the values of the val attribute are defined by the ST_VerticalJc simple type.*

Word only allows the values top, center, and bottom.

2.1.182 Part 4 Section 2.4.81, vMerge (Vertically Merged Cell)

For additional notes that apply to this portion of the standard, please see the notes for [tcPr, §2.7.5.8\(a\)](#); [tcPr, §2.7.5.9\(b\)](#).

2.1.183 Part 4 Section 2.4.82, wAfter (Preferred Width After Table Row)

For additional notes that apply to this portion of the standard, please see the notes for [bottom, §2.4.2\(a, b\)](#); [top, §2.4.73\(a\)](#); [trPr, §2.7.5.10\(b\)](#); [trPr, §2.7.5.11\(a\)](#).

2.1.184 Part 4 Section 2.4.83, wBefore (Preferred Width Before Table Row)

For additional notes that apply to this portion of the standard, please see the notes for [bottom, §2.4.2\(a, b\)](#); [top, §2.4.73\(a\)](#); [trPr, §2.7.5.10\(b\)](#); [trPr, §2.7.5.11\(a\)](#).

a. The standard states that the *wBefore* element specifies the width for the grid columns specified in *gridAfter*.

In Word, the *wBefore* element specifies the width for the grid columns specified in *gridBefore*.

2.1.185 Part 4 Section 2.5.1.1, attr (Custom XML Attribute)

a. The standard states that the values of the *name* attribute are defined by the *ST_String* simple type.

Word defines the values of this attribute with the XML Schema *NCName* datatype, restricting it to a maximum length of 255 characters.

b. The standard places no restrictions on the value of the *uri* attribute.

Word requires that the URI specified in this attribute also be declared by the *attachedSchema* element.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.186 Part 4 Section 2.5.1.2, attr (Smart Tag Property)

a. The standard does not place any restrictions on the value of the *uri* attribute.

Word requires the value of this attribute to be `urn:schemas-microsoft-com:office:office`.

2.1.187 Part 4 Section 2.5.1.3, customXml (Cell-Level Custom XML Element)

For additional notes that apply to this portion of the standard, please see the notes for [oMath, §7.1.2.77\(g\)](#); [oMathPara, §7.1.2.78\(d\)](#).

a. The standard states that the *element* attribute can contain any string value.

Word only allows values conforming to the XML specification; a string conforming to the definition of *xsd:NCName* with a length of at most 255 characters.

b. The standard states that the *uri* attribute can contain any string value.

Word requires that the namespace specified in the *uri* attribute be declared in an accompanying *attachedSchema* element.

2.1.188 Part 4 Section 2.5.1.4, customXml (Row-Level Custom XML Element)

For additional notes that apply to this portion of the standard, please see the notes for [oMath, §7.1.2.77\(g\)](#); [oMathPara, §7.1.2.78\(d\)](#).

- a. *The standard states that the uri attribute can contain any string value.*

Word will not load a file if the URI used in the uri attribute is not also contained within an attachedSchema element.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

- b. *The standard states that the element attribute can contain any string value.*

Word only allows values conforming to the XML specification; a string conforming to the definition of xsd:NCName with a length of at most 255 characters.

2.1.189 Part 4 Section 2.5.1.5, customXml (Inline-Level Custom XML Element)

For additional notes that apply to this portion of the standard, please see the notes for [oMath, §7.1.2.77\(d\)](#).

- a. *The standard allows ins, del, moveTo, and moveFrom to contain inline customXml.*

Word will fail to load a file if ins, del, moveTo, or moveFrom contains inline customXml.

- b. *The standard states a specific set of parent elements that can contain inline customXml elements.*

Word allows the following parent elements in addition to those already listed: deg, den, e, fName, lim, num, oMath, sub, and sup.

- c. *The standard allows any string for the uri attribute.*

Word will not open a file if the uri attribute is not declared in an accompanying attachedSchema element.

- d. *The standard states that the element attribute can contain any string value.*

Word only allows values conforming to the XML specification; a string conforming to the definition of xsd:NCName with a length of at most 255 characters.

2.1.190 Part 4 Section 2.5.1.6, customXml (Block-Level Custom XML Element)

For additional notes that apply to this portion of the standard, please see the notes for [oMath, §7.1.2.77\(g\)](#); [oMathPara, §7.1.2.78\(d\)](#).

- a. *The standard states that the element attribute can contain any string value.*

Word only allows values conforming to the XML specification: a string conforming to the definition of xsd:NCName with a length of at most 255 characters.

- b. *The standard allows any string for the uri attribute.*

Word will not open a file if the uri attribute is not declared in an accompanying attachedSchema element.

2.1.191 Part 4 Section 2.5.1.9, smartTag (Inline-Level Smart Tag)

For additional notes that apply to this portion of the standard, please see the notes for [oMath, §7.1.2.77\(d\)](#).

- a. *The standard states that the element attribute can contain any string value.*

Word only allows values for this attribute that conform to the xsd:NCName datatype.

- b. *The standard states that the values of the uri attribute are defined by the ST_String simple type.*

Word requires the value of the uri attribute to be declared in an accompanying attachedSchema element.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.192 Part 4 Section 2.5.2.6, dataBinding (XML Mapping)

- a. *The standard states that if the parent structured document tag is of type rich text or document part gallery, then this property shall be ignored.*

Word ignores the type of the content control and reverts it to plain text if this property is present.

2.1.193 Part 4 Section 2.5.2.7, date (Date Structured Document Tag)

- a. *The standard says a date structured document tag cannot contain more than one table cell and cannot contain a table cell.*

In Word, a date structured document tag cannot contain more than one table cell and cannot contain a table.

2.1.194 Part 4 Section 2.5.2.9, docPart (Document Part Reference)

- a. *The standard states that the application shall display the placeholder text of a document part if the parent structured document tag run contents are empty.*

Word does not display the placeholder text until the user clicks in and out of the structured document tag.

2.1.195 Part 4 Section 2.5.2.18, id (Unique ID)

- a. *The standard states that if multiple SDTs specify the same value for id, then the first SDT is maintained, and others get a new ID.*

Word discards each SDT completely (leaving its contents) except the last one.

2.1.196 Part 4 Section 2.5.2.19, lid (Date Picker Language ID)

For additional notes that apply to this portion of the standard, please see the notes for [lid, §2.14.17\(a\)](#).

2.1.197 Part 4 Section 2.5.2.24, placeholder (Structured Document Tag Placeholder Text)

- a. *The standard states that the placeholder text shall be displayed when the parent structured document tag's run is empty*

Application does not show content control nor the placeholder text

2.1.198 Part 4 Section 2.5.2.26, rPr (Run Properties For Structured Document Tag Contents)

For additional notes that apply to this portion of the standard, please see the notes for [oMath, §2.3.2.20\(a\)](#).

2.1.199 Part 4 Section 2.5.2.27, rPr (Structured Document Tag End Character Run Properties)

For additional notes that apply to this portion of the standard, please see the notes for [oMath, §2.3.2.20\(a\)](#).

2.1.200 Part 4 Section 2.5.2.28, sdt (Cell-Level Structured Document Tag)

- a. *The standard does not allow range elements as children of the sdt element.*

Word allows the following additional elements as children of the sdt element:

| Child Elements |
|---|
| bookmarkEnd (" [ECMA-376] Part 4 §2.13.6.1; bookmarkEnd (Bookmark End)") |
| bookmarkStart (" [ECMA-376] Part 4 §2.13.6.2; bookmarkStart (Bookmark Start)") |
| commentRangeEnd (" [ECMA-376] Part 4 §2.13.4.3; commentRangeEnd (Comment Anchor Range End)") |
| commentRangeStart (" [ECMA-376] Part 4 §2.13.4.4; commentRangeStart (Comment Anchor Range Start)") |
| customXmlDelRangeEnd (" [ECMA-376] Part 4 §2.13.5.4; customXmlDelRangeEnd (Custom XML Markup Deletion End)") |
| customXmlDelRangeStart (" [ECMA-376] Part 4 §2.13.5.5; customXmlDelRangeStart (Custom XML Markup Deletion Start)") |
| customXmlInsRangeEnd (" [ECMA-376] Part 4 §2.13.5.6; customXmlInsRangeEnd (Custom XML Markup Insertion End)") |
| customXmlInsRangeStart (" [ECMA-376] Part 4 §2.13.5.7; customXmlInsRangeStart (Custom XML Markup Insertion Start)") |
| customXmlMoveFromRangeEnd (" [ECMA-376] Part 4 §2.13.5.8; customXmlMoveFromRangeEnd (Custom XML Markup Move Source End)") |
| customXmlMoveFromRangeStart (" [ECMA-376] Part 4 §2.13.5.9; customXmlMoveFromRangeStart (Custom XML Markup Move Source Start)") |
| customXmlMoveToRangeEnd (" [ECMA-376] Part 4 §2.13.5.10; customXmlMoveToRangeEnd (Custom XML Markup Move Destination Location End)") |

| Child Elements |
|--|
| customXmlMoveToRangeStart ("ECMA-376 Part 4 §2.13.5.11; customXmlMoveToRangeStart (Custom XML Markup Move Destination Location Start)") |
| moveFromRangeEnd ("ECMA-376 Part 4 §2.13.5.23; moveFromRangeEnd (Move Source Location Container - End)") |
| moveFromRangeStart ("ECMA-376 Part 4 §2.13.5.24; moveFromRangeStart (Move Source Location Container - Start)") |
| moveToRangeEnd ("ECMA-376 Part 4 §2.13.5.27; moveToRangeEnd (Move Destination Location Container - End)") |
| moveToRangeStart ("ECMA-376 Part 4 §2.13.5.28; moveToRangeStart (Move Destination Location Container - Start)") |

2.1.201 Part 4 Section 2.5.2.29, sdt (Inline-Level Structured Document Tag)

For additional notes that apply to this portion of the standard, please see the notes for [oMath, §7.1.2.77\(d\)](#).

- a. The standard does not allow range elements as children of the sdt element.

Word allows the following additional elements as children of the sdt element:

| Child Elements |
|--|
| bookmarkEnd ("ECMA-376 Part 4 §2.13.6.1; bookmarkEnd (Bookmark End)") |
| bookmarkStart ("ECMA-376 Part 4 §2.13.6.2; bookmarkStart (Bookmark Start)") |
| commentRangeEnd ("ECMA-376 Part 4 §2.13.4.3; commentRangeEnd (Comment Anchor Range End)") |
| commentRangeStart ("ECMA-376 Part 4 §2.13.4.4; commentRangeStart (Comment Anchor Range Start)") |
| customXmlDelRangeEnd ("ECMA-376 Part 4 §2.13.5.4; customXmlDelRangeEnd (Custom XML Markup Deletion End)") |
| customXmlDelRangeStart ("ECMA-376 Part 4 §2.13.5.5; customXmlDelRangeStart (Custom XML Markup Deletion Start)") |
| customXmlInsRangeEnd ("ECMA-376 Part 4 §2.13.5.6; customXmlInsRangeEnd (Custom XML Markup Insertion End)") |
| customXmlInsRangeStart ("ECMA-376 Part 4 §2.13.5.7; customXmlInsRangeStart (Custom XML Markup Insertion Start)") |
| customXmlMoveFromRangeEnd ("ECMA-376 Part 4 §2.13.5.8; customXmlMoveFromRangeEnd (Custom XML Markup Move Source End)") |
| customXmlMoveFromRangeStart ("ECMA-376 Part 4 §2.13.5.9; customXmlMoveFromRangeStart (Custom XML Markup Move Source Start)") |
| customXmlMoveToRangeEnd ("ECMA-376 Part 4 §2.13.5.10; customXmlMoveToRangeEnd (Custom XML Markup Move Destination Location End)") |
| customXmlMoveToRangeStart ("ECMA-376 Part 4 §2.13.5.11; customXmlMoveToRangeStart (Custom XML Markup Move Destination Location Start)") |

| Child Elements |
|---|
| XML Markup Move Destination Location Start") |
| moveFromRangeEnd (" [ECMA-376] Part 4 §2.13.5.23; moveFromRangeEnd (Move Source Location Container - End)") |
| moveFromRangeStart (" [ECMA-376] Part 4 §2.13.5.24; moveFromRangeStart (Move Source Location Container - Start)") |
| moveToRangeEnd (" [ECMA-376] Part 4 §2.13.5.27; moveToRangeEnd (Move Destination Location Container - End)") |
| moveToRangeStart (" [ECMA-376] Part 4 §2.13.5.28; moveToRangeStart (Move Destination Location Container - Start)") |

2.1.202 Part 4 Section 2.5.2.30, sdt (Block-Level Structured Document Tag)

- a. *The standard does not allow range elements as children of the sdt element.*

Word allows the following additional elements as children of the sdt element:

| Child Elements |
|---|
| bookmarkEnd (" [ECMA-376] Part 4 §2.13.6.1; bookmarkEnd (Bookmark End)") |
| bookmarkStart (" [ECMA-376] Part 4 §2.13.6.2; bookmarkStart (Bookmark Start)") |
| commentRangeEnd (" [ECMA-376] Part 4 §2.13.4.3; commentRangeEnd (Comment Anchor Range End)") |
| commentRangeStart (" [ECMA-376] Part 4 §2.13.4.4; commentRangeStart (Comment Anchor Range Start)") |
| customXmlDelRangeEnd (" [ECMA-376] Part 4 §2.13.5.4; customXmlDelRangeEnd (Custom XML Markup Deletion End)") |
| customXmlDelRangeStart (" [ECMA-376] Part 4 §2.13.5.5; customXmlDelRangeStart (Custom XML Markup Deletion Start)") |
| customXmlInsRangeEnd (" [ECMA-376] Part 4 §2.13.5.6; customXmlInsRangeEnd (Custom XML Markup Insertion End)") |
| customXmlInsRangeStart (" [ECMA-376] Part 4 §2.13.5.7; customXmlInsRangeStart (Custom XML Markup Insertion Start)") |
| customXmlMoveFromRangeEnd (" [ECMA-376] Part 4 §2.13.5.8; customXmlMoveFromRangeEnd (Custom XML Markup Move Source End)") |
| customXmlMoveFromRangeStart (" [ECMA-376] Part 4 §2.13.5.9; customXmlMoveFromRangeStart (Custom XML Markup Move Source Start)") |
| customXmlMoveToRangeEnd (" [ECMA-376] Part 4 §2.13.5.10; customXmlMoveToRangeEnd (Custom XML Markup Move Destination Location End)") |
| customXmlMoveToRangeStart (" [ECMA-376] Part 4 §2.13.5.11; customXmlMoveToRangeStart (Custom XML Markup Move Destination Location Start)") |
| moveFromRangeEnd (" [ECMA-376] Part 4 §2.13.5.23; moveFromRangeEnd (Move Source Location Container - End)") |

| Child Elements |
|--|
| moveFromRangeStart ("ECMA-376 Part 4 §2.13.5.24; moveFromRangeStart (Move Source Location Container - Start)") |
| moveToRangeEnd ("ECMA-376 Part 4 §2.13.5.27; moveToRangeEnd (Move Destination Location Container - End)") |
| moveToRangeStart ("ECMA-376 Part 4 §2.13.5.28; moveToRangeStart (Move Destination Location Container - Start)") |

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.203 Part 4 Section 2.5.2.31, sdt (Row-Level Structured Document Tag)

a. The standard does not allow range elements as children of the sdt element.

Word allows the following additional elements as children of the sdt element:

| Child Elements |
|--|
| bookmarkEnd ("ECMA-376 Part 4 §2.13.6.1; bookmarkEnd (Bookmark End)") |
| bookmarkStart ("ECMA-376 Part 4 §2.13.6.2; bookmarkStart (Bookmark Start)") |
| commentRangeEnd ("ECMA-376 Part 4 §2.13.4.3; commentRangeEnd (Comment Anchor Range End)") |
| commentRangeStart ("ECMA-376 Part 4 §2.13.4.4; commentRangeStart (Comment Anchor Range Start)") |
| customXmlDelRangeEnd ("ECMA-376 Part 4 §2.13.5.4; customXmlDelRangeEnd (Custom XML Markup Deletion End)") |
| customXmlDelRangeStart ("ECMA-376 Part 4 §2.13.5.5; customXmlDelRangeStart (Custom XML Markup Deletion Start)") |
| customXmlInsRangeEnd ("ECMA-376 Part 4 §2.13.5.6; customXmlInsRangeEnd (Custom XML Markup Insertion End)") |
| customXmlInsRangeStart ("ECMA-376 Part 4 §2.13.5.7; customXmlInsRangeStart (Custom XML Markup Insertion Start)") |
| customXmlMoveFromRangeEnd ("ECMA-376 Part 4 §2.13.5.8; customXmlMoveFromRangeEnd (Custom XML Markup Move Source End)") |
| customXmlMoveFromRangeStart ("ECMA-376 Part 4 §2.13.5.9; customXmlMoveFromRangeStart (Custom XML Markup Move Source Start)") |
| customXmlMoveToRangeEnd ("ECMA-376 Part 4 §2.13.5.10; customXmlMoveToRangeEnd (Custom XML Markup Move Destination Location End)") |
| customXmlMoveToRangeStart ("ECMA-376 Part 4 §2.13.5.11; customXmlMoveToRangeStart (Custom XML Markup Move Destination Location Start)") |
| moveFromRangeEnd ("ECMA-376 Part 4 §2.13.5.23; moveFromRangeEnd (Move Source Location Container - End)") |
| moveFromRangeStart ("ECMA-376 Part 4 §2.13.5.24; moveFromRangeStart (Move Source Location Container - Start)") |

| Child Elements |
|--|
| moveToRangeEnd ("[ECMA-376] Part 4 §2.13.5.27; moveToRangeEnd (Move Destination Location Container - End)") |
| moveToRangeStart ("[ECMA-376] Part 4 §2.13.5.28; moveToRangeStart (Move Destination Location Container - Start)") |

2.1.204 Part 4 Section 2.5.2.32, sdtContent (Block-Level Structured Document Tag Content)

For additional notes that apply to this portion of the standard, please see the notes for [oMath, §7.1.2.77\(g\)](#); [oMathPara, §7.1.2.78\(d\)](#).

2.1.205 Part 4 Section 2.5.2.33, sdtContent (Cell-Level Structured Document Tag Content)

For additional notes that apply to this portion of the standard, please see the notes for [oMath, §7.1.2.77\(g\)](#); [oMathPara, §7.1.2.78\(d\)](#).

2.1.206 Part 4 Section 2.5.2.34, sdtContent (Row-Level Structured Document Tag Content)

For additional notes that apply to this portion of the standard, please see the notes for [oMath, §7.1.2.77\(g\)](#); [oMathPara, §7.1.2.78\(d\)](#).

2.1.207 Part 4 Section 2.5.2.35, sdtContent (Inline-Level Structured Document Tag Content)

For additional notes that apply to this portion of the standard, please see the notes for [oMath, §7.1.2.77\(d\)](#).

2.1.208 Part 4 Section 2.5.2.41, temporary (Remove Structured Document Tag When Contents Are Edited)

- a. *The standard states that temporary means the parent sdt should be removed when the contents are modified.*

Under limited circumstances involving inserting pictures, Word fails to remove the parent sdt when the contents are modified.

2.1.209 Part 4 Section 2.6.2, bottom (Bottom Border)

For additional notes that apply to this portion of the standard, please see the notes for [bar, §2.3.1.4\(a-c\)](#); [bdr, §2.3.2.3\(a\)](#); [left, §2.15.2.21\(a\)](#).

2.1.210 Part 4 Section 2.6.3, col (Single Column Definition)

- a. *The standard does not specify a default value for the space attribute.*

Word uses a default value of 0 for this attribute.

- b. *The standard states that the w attribute is always optional.*

Word requires that this attribute is present when the parent cols element has an equalWidth attribute value of false (or equivalent).

2.1.211 Part 4 Section 2.6.4, cols (Column Definitions)

a. *The standard states that the num attribute allows any integer value.*

Word restricts the value of the num attribute to a value between 1 and 45.

b. *The standard does not specify a default value for the equalWidth attribute.*

Word uses a default value of true for this attribute.

c. *The standard states that when the equalWidth attribute is false (or equivalent), the num attribute is ignored in favor of the number of child col elements.*

Word requires that the value of the num attribute matches the number of child col elements. If the num attribute is not specified, then Word assumes a value of 1.

2.1.212 Part 4 Section 2.6.7, left (Left Border)

For additional notes that apply to this portion of the standard, please see the notes for [bar](#), [§2.3.1.4\(a-c\)](#); [bdr](#), [§2.3.2.3\(a\)](#); [left](#), [§2.15.2.21\(a\)](#).

2.1.213 Part 4 Section 2.6.8, InNumType (Line Numbering Settings)

a. *The standard states that the values of the start attribute are defined by the ST_DecimalNumber simple type.*

Word restricts the value of this attribute to be at least 0 and at most 32767.

b. *The standard states that the start attribute specifies the starting value for (re)started line numbering.*

Word uses the start attribute as the number of line numbers that should be skipped when starting or restarting line numbering (for example, a value of 3 means to start numbering at 4).

c. *The standard states that the countBy attribute can be any integer value.*

Word restricts the contents of this attribute to a value between 1 and 100 inclusive.

2.1.214 Part 4 Section 2.6.9, paperSrc (Paper Source Information)

a. *The standard states that the first and other attributes can be any integer.*

Word restricts these values to the range of an unsigned short.

b. *The standard simply states that this element's attributes specify "...a printer-specific code that uniquely identifies a specific printer tray..."*

Word passes this value to the Windows DEVMODE printing API [\[DEVMODE\]](#) where the value may have a standard meaning to Windows or an installed printer.

2.1.215 Part 4 Section 2.6.10, pgBorders (Page Borders)

a. *The standard does not specify a default value for the zOrder attribute.*

Word uses a default value of front for this attribute.

- b. *The standard does not specify a default value for the offsetFrom attribute.*

Word uses a default value of text for this attribute.

2.1.216 Part 4 Section 2.6.11, pgMar (Page Margins)

- a. *The standard states that the values of the right, left, header, footer, and gutter attributes are defined by the XML Schema unsignedLong datatype.*

Word restricts the values of these attributes to be at most 31680 (22").

- b. *The standard states that all attributes on the pgMar element are required.*

Word does not require any attribute whose value is the same as the value in the current section properties.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

- c. *The standard states that the values of the top and bottom attributes are defined by the XML Schema integer datatype.*

Word restricts the values of these attributes to be at least -31680 (-22") and at most 31680 (22").

2.1.217 Part 4 Section 2.6.12, pgNumType (Page Numbering Settings)

- a. *The standard states that the chapStyle attribute can be any integer value.*

Word requires that this attribute is an unsigned byte.

- b. *The standard does not specify a default value for the chapSep attribute.*

Word uses a default value of hyphen for this attribute.

- c. *The standard does not state a default for the fmt attribute.*

Word uses a default value of decimal for this attribute.

- d. *The standard states that the start attribute can be any integer value.*

Word requires that the start attribute is an unsigned 32-bit integer.

2.1.218 Part 4 Section 2.6.13, pgSz (Page Size)

- a. *The standard states that the values of the code attribute are defined by the ST_DecimalNumber simple type.*

Word restricts the value of this attribute to be at least 0 and at most 118.

- b. *The standard states that the code attribute is a number sent directly to the printer for representing paper size.*

Word interprets this code attribute value as a value within the set of paper size identifier constants defined in the public Windows DEVMODE printing API [\[DEVMODE\]](#).

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

c. *The standard states that the h and w attributes can have any value in the range 0 to 4294967295, inclusive.*

Word requires that this value is between the width of the page margins (and any column widths, for the w attribute) and 31680 (22 inches).

2.1.219 Part 4 Section 2.6.14, printerSettings (Reference to Printer Settings Data)

For additional notes that apply to this portion of the standard, please see the notes for [attachedTemplate, §2.15.1.6\(a\)](#).

a. *The standard states that the printerSettings element references the Printer Settings part associated with this section.*

Word discards this element and the associated Printer Settings part.

2.1.220 Part 4 Section 2.6.15, right (Right Border)

For additional notes that apply to this portion of the standard, please see the notes for [bar, §2.3.1.4\(a-c\)](#); [bdr, §2.3.2.3\(a\)](#); [left, §2.15.2.21\(a\)](#).

2.1.221 Part 4 Section 2.6.17, sectPr (Previous Section Properties)

For additional notes that apply to this portion of the standard, please see the notes for [sectPr, §2.6.19\(a, b\)](#).

a. *The standard states that text flow direction can differ between previous section properties and current section properties.*

Word sets the text direction in the previous section properties to the text flow direction specified in the current section properties.

2.1.222 Part 4 Section 2.6.18, sectPr (Document Final Section Properties)

For additional notes that apply to this portion of the standard, please see the notes for [sectPr, §2.6.19\(a, b\)](#).

2.1.223 Part 4 Section 2.6.19, sectPr (Section Properties)

For additional notes that apply to this portion of the standard, please see the notes for [pPr, §2.7.4.2\(a\)](#); [pPr, §2.7.5.1\(a\)](#); [pPr, §2.7.7.2\(a\)](#); [pPr, §2.9.24\(a\)](#).

a. *The standard appears to have the same definition for rsidSect as it does for rsidRPr.*

Word uses rsidSect to denote the editing session when the section properties were last modified.

b. *The standard states that rsids are stored on the section properties, distinct from the paragraph in which they are located.*

Word ignores rsids in the sectPr and instead applies the corresponding rsids from the containing p (for the sectPr of any non-final section) or the last p in the document (for the final section).

c. *The standard states that a sectPr element can be contained within any pPr element.*

Word does not allow this element to be used on paragraphs within tables, headers, footers, comments, footnotes, endnotes, or text boxes.

2.1.224 Part 4 Section 2.6.21, top (Top Border)

For additional notes that apply to this portion of the standard, please see the notes for [bar](#), [§2.3.1.4\(a-c\)](#); [bdr](#), [§2.3.2.3\(a\)](#); [left](#), [§2.15.2.21\(a\)](#).

2.1.225 Part 4 Section 2.6.22, type (Section Type)

- a. *The standard implies that the val attribute is optional.*

Word requires this attribute.

2.1.226 Part 4 Section 2.7, Styles

- a. *The standard states that numbering styles are applied before paragraph styles in the style hierarchy.*

Word applies paragraph styles before numbering styles in the style hierarchy.

2.1.227 Part 4 Section 2.7.3.1, aliases (Alternate Style Names)

For additional notes that apply to this portion of the standard, please see the notes for [numStyleLink](#), [§2.9.22\(a\)](#).

- a. *The standard states that any series of alternate style names is valid.*

Word does not roundtrip multiple instances of an identical style name (including both duplication within this element and duplication with the primary style name).

- b. *The standard states that any number of consecutive comma characters can be used to delimit consecutive style names.*

Word discards all aliases after the presence of multiple consecutive comma characters.

- c. *The standard does not limit the length of the value of the val attribute.*

Word restricts the value of this attribute to be at most 253 characters, removing all aliases whose inclusion would exceed that length.

2.1.228 Part 4 Section 2.7.3.2, autoRedefine (Automatically Merge User Formatting Into Style Definition)

- a. *The standard states that the values 0 and false on the val attribute are equivalent to the value off.*

Word treats these values on this attribute as equivalent to the value on.

This note applies to the following products: 2007, 2007 SP1.

- b. *The standard states that this element can be specified for any type of style.*

Word only applies this element to paragraph styles.

2.1.229 Part 4 Section 2.7.3.3, basedOn (Parent Style ID)

For additional notes that apply to this portion of the standard, please see the notes for [numStyleLink, §2.9.22\(a\)](#).

- a. *The standard allows loops in the style based-on chain.*

Word requires that the style based-on chain does not have a circular reference.

- b. *The standard does not limit the length of the value of the val attribute.*

Word restricts the value of this attribute to be at most 253 characters.

2.1.230 Part 4 Section 2.7.3.4, hidden (Hide Style From User Interface)

- a. *The standard states that the values 0 and false on the val attribute are equivalent to the value off.*

Word treats these values on this attribute as equivalent to the value on.

This note applies to the following products: 2007, 2007 SP1.

2.1.231 Part 4 Section 2.7.3.5, latentStyles (Latent Style Information)

- a. *The standard allows any integer for defUIPriority.*

Word allows values between 0 and 99 inclusive for defUIPriority.

- b. *The standard says that count specifies how many built-in styles to apply latent style defaults to, but does not specify which ones.*

Word applies these latent style defaults to the built-in styles in order of their index within Word's built-in styles. The table listing the primary style names of the built-in styles ("[ECMA-376](#) Part 4 §2.7.3.9; name") provides the index for each built-in style.

- c. *The standard says the default value for defUIPriority is 99.*

In Word, the default value for defUIPriority is 0.

- d. *The standard does not specify default behavior when count is omitted.*

If count is omitted, then Word applies the latent style defaults to all known built-in styles.

2.1.232 Part 4 Section 2.7.3.6, link (Linked Style Reference)

For additional notes that apply to this portion of the standard, please see the notes for [numStyleLink, §2.9.22\(a\)](#).

- a. *The standard does not specify behavior when more than one style specifies the same styleId for a link.*

Word ignores all but the last link to a given style.

- b. *The standard does not specify behavior for a singly linked style pairing.*

If Word reads a singly-linked style pairing, it makes the linking bi-directional.

- c. *The standard does not limit the length of the value of the val attribute.*

Word restricts the value of this attribute to be at most 253 characters.

2.1.233 Part 4 Section 2.7.3.7, locked (Style Cannot Be Applied)

- a. *The standard states that the values 0 and false on the val attribute are equivalent to the value off.*

Word treats these values on this attribute as equivalent to the value on.

This note applies to the following products: 2007, 2007 SP1.

2.1.234 Part 4 Section 2.7.3.8, IsdException (Latent Style Exception)

- a. *The standard allows an unbounded integer for uiPriority.*

Word allows values between 0 and 99 for uiPriority.

2.1.235 Part 4 Section 2.7.3.9, name (Primary Style Name)

- a. *The standard does not place any restrictions on the value of the val attribute.*

Word does not allow commas in this attribute's value.

- b. *The standard does not limit the length of the value of the val attribute.*

Word restricts the combined length of the primary style name, all aliases, and alias separators (commas) to be at most 253 characters.

- c. *The standard does not specify to remove whitespace from the beginning or end of primary style name.*

Word removes whitespace from the beginning or end of primary style name.

- d. *The standard does not specify that certain primary style names must have certain style types.*

Word reserves a list of style names for use as built-in styles and requires that these names be used with the appropriate style type. If a built-in style name is used with the wrong style type or the style type is omitted, then Word enforces the correct built-in style name types by renaming the style or changing its type to match the built-in style type.

| Reserved name | Style type | Index within built-in styles |
|----------------------|-------------------|-------------------------------------|
| annotation reference | character | 39 |
| annotation subject | paragraph | 106 |
| annotation text | paragraph | 30 |
| Balloon Text | paragraph | 153 |
| Bibliography | paragraph | 265 |
| Block Text | paragraph | 84 |
| Body Text | paragraph | 66 |
| Body Text 2 | paragraph | 80 |

| Reserved name | Style type | Index within built-in styles |
|---------------------------|-------------------|-------------------------------------|
| Body Text 3 | paragraph | 81 |
| Body Text First Indent | paragraph | 77 |
| Body Text First Indent 2 | paragraph | 78 |
| Body Text Indent | paragraph | 67 |
| Body Text Indent 2 | paragraph | 82 |
| Body Text Indent 3 | paragraph | 83 |
| Book Title | character | 264 |
| caption | paragraph | 34 |
| Closing | paragraph | 63 |
| Colorful Grid | table | 171 |
| Colorful Grid Accent 1 | table | 189 |
| Colorful Grid Accent 2 | table | 203 |
| Colorful Grid Accent 3 | table | 217 |
| Colorful Grid Accent 4 | table | 231 |
| Colorful Grid Accent 5 | table | 245 |
| Colorful Grid Accent 6 | table | 259 |
| Colorful List | table | 170 |
| Colorful List Accent 1 | table | 188 |
| Colorful List Accent 2 | table | 202 |
| Colorful List Accent 3 | table | 216 |
| Colorful List Accent 4 | table | 230 |
| Colorful List Accent 5 | table | 244 |
| Colorful List Accent 6 | table | 258 |
| Colorful Shading | table | 169 |
| Colorful Shading Accent 1 | table | 187 |
| Colorful Shading Accent 2 | table | 201 |
| Colorful Shading Accent 3 | table | 215 |
| Colorful Shading Accent 4 | table | 229 |
| Colorful Shading Accent 5 | table | 243 |
| Colorful Shading Accent 6 | table | 257 |

| Reserved name | Style type | Index within built-in styles |
|------------------------|-------------------|-------------------------------------|
| Dark List | table | 168 |
| Dark List Accent 1 | table | 186 |
| Dark List Accent 2 | table | 200 |
| Dark List Accent 3 | table | 214 |
| Dark List Accent 4 | table | 228 |
| Dark List Accent 5 | table | 242 |
| Dark List Accent 6 | table | 256 |
| Date | paragraph | 76 |
| Default Paragraph Font | character | 65 |
| Document Map | paragraph | 89 |
| E-mail Signature | paragraph | 91 |
| Emphasis | character | 88 |
| endnote reference | character | 42 |
| endnote text | paragraph | 43 |
| envelope address | paragraph | 36 |
| envelope return | paragraph | 37 |
| FollowedHyperlink | character | 86 |
| footer | paragraph | 32 |
| footnote reference | character | 38 |
| footnote text | paragraph | 29 |
| header | paragraph | 31 |
| heading 1 | paragraph | 1 |
| heading 2 | paragraph | 2 |
| heading 3 | paragraph | 3 |
| heading 4 | paragraph | 4 |
| heading 5 | paragraph | 5 |
| heading 6 | paragraph | 6 |
| heading 7 | paragraph | 7 |
| heading 8 | paragraph | 8 |
| heading 9 | paragraph | 9 |

| Reserved name | Style type | Index within built-in styles |
|----------------------|-------------------|-------------------------------------|
| HTML Acronym | character | 95 |
| HTML Address | paragraph | 96 |
| HTML Bottom of Form | paragraph | 93 |
| HTML Cite | character | 97 |
| HTML Code | character | 98 |
| HTML Definition | character | 99 |
| HTML Keyboard | character | 100 |
| HTML Preformatted | paragraph | 101 |
| HTML Sample | character | 102 |
| HTML Top of Form | paragraph | 92 |
| HTML Typewriter | character | 103 |
| HTML Variable | character | 104 |
| Hyperlink | character | 85 |
| index 1 | paragraph | 10 |
| index 2 | paragraph | 11 |
| index 3 | paragraph | 12 |
| index 4 | paragraph | 13 |
| index 5 | paragraph | 14 |
| index 6 | paragraph | 15 |
| index 7 | paragraph | 16 |
| index 8 | paragraph | 17 |
| index 9 | paragraph | 18 |
| index heading | paragraph | 33 |
| Intense Emphasis | character | 261 |
| Intense Quote | paragraph | 181 |
| Intense Reference | character | 263 |
| Light Grid | table | 160 |
| Light Grid Accent 1 | table | 174 |
| Light Grid Accent 2 | table | 192 |
| Light Grid Accent 3 | table | 206 |

| Reserved name | Style type | Index within built-in styles |
|------------------------|-------------------|-------------------------------------|
| Light Grid Accent 4 | table | 220 |
| Light Grid Accent 5 | table | 234 |
| Light Grid Accent 6 | table | 248 |
| Light List | table | 159 |
| Light List Accent 1 | table | 173 |
| Light List Accent 2 | table | 191 |
| Light List Accent 3 | table | 205 |
| Light List Accent 4 | table | 219 |
| Light List Accent 5 | table | 233 |
| Light List Accent 6 | table | 247 |
| Light Shading | table | 158 |
| Light Shading Accent 1 | table | 172 |
| Light Shading Accent 2 | table | 190 |
| Light Shading Accent 3 | table | 204 |
| Light Shading Accent 4 | table | 218 |
| Light Shading Accent 5 | table | 232 |
| Light Shading Accent 6 | table | 246 |
| line number | character | 40 |
| List | paragraph | 47 |
| List 2 | paragraph | 50 |
| List 3 | paragraph | 51 |
| List 4 | paragraph | 52 |
| List 5 | paragraph | 53 |
| List Bullet | paragraph | 48 |
| List Bullet 2 | paragraph | 54 |
| List Bullet 3 | paragraph | 55 |
| List Bullet 4 | paragraph | 56 |
| List Bullet 5 | paragraph | 57 |
| List Continue | paragraph | 68 |
| List Continue 2 | paragraph | 69 |

| Reserved name | Style type | Index within built-in styles |
|------------------------|-------------------|-------------------------------------|
| List Continue 3 | paragraph | 70 |
| List Continue 4 | paragraph | 71 |
| List Continue 5 | paragraph | 72 |
| List Number | paragraph | 49 |
| List Number 2 | paragraph | 58 |
| List Number 3 | paragraph | 59 |
| List Number 4 | paragraph | 60 |
| List Number 5 | paragraph | 61 |
| List Paragraph | paragraph | 179 |
| macro | paragraph | 45 |
| Medium Grid 1 | table | 165 |
| Medium Grid 1 Accent 1 | table | 183 |
| Medium Grid 1 Accent 2 | table | 197 |
| Medium Grid 1 Accent 3 | table | 211 |
| Medium Grid 1 Accent 4 | table | 225 |
| Medium Grid 1 Accent 5 | table | 239 |
| Medium Grid 1 Accent 6 | table | 253 |
| Medium Grid 2 | table | 166 |
| Medium Grid 2 Accent 1 | table | 184 |
| Medium Grid 2 Accent 2 | table | 198 |
| Medium Grid 2 Accent 3 | table | 212 |
| Medium Grid 2 Accent 4 | table | 226 |
| Medium Grid 2 Accent 5 | table | 240 |
| Medium Grid 2 Accent 6 | table | 254 |
| Medium Grid 3 | table | 167 |
| Medium Grid 3 Accent 1 | table | 185 |
| Medium Grid 3 Accent 2 | table | 199 |
| Medium Grid 3 Accent 3 | table | 213 |
| Medium Grid 3 Accent 4 | table | 227 |
| Medium Grid 3 Accent 5 | table | 241 |

| Reserved name | Style type | Index within built-in styles |
|---------------------------|-------------------|-------------------------------------|
| Medium Grid 3 Accent 6 | table | 255 |
| Medium List 1 | table | 163 |
| Medium List 1 Accent 1 | table | 177 |
| Medium List 1 Accent 2 | table | 195 |
| Medium List 1 Accent 3 | table | 209 |
| Medium List 1 Accent 4 | table | 223 |
| Medium List 1 Accent 5 | table | 237 |
| Medium List 1 Accent 6 | table | 251 |
| Medium List 2 | table | 164 |
| Medium List 2 Accent 1 | table | 182 |
| Medium List 2 Accent 2 | table | 196 |
| Medium List 2 Accent 3 | table | 210 |
| Medium List 2 Accent 4 | table | 224 |
| Medium List 2 Accent 5 | table | 238 |
| Medium List 2 Accent 6 | table | 252 |
| Medium Shading 1 | table | 161 |
| Medium Shading 1 Accent 1 | table | 175 |
| Medium Shading 1 Accent 2 | table | 193 |
| Medium Shading 1 Accent 3 | table | 207 |
| Medium Shading 1 Accent 4 | table | 221 |
| Medium Shading 1 Accent 5 | table | 235 |
| Medium Shading 1 Accent 6 | table | 249 |
| Medium Shading 2 | table | 162 |
| Medium Shading 2 Accent 1 | table | 176 |
| Medium Shading 2 Accent 2 | table | 194 |
| Medium Shading 2 Accent 3 | table | 208 |
| Medium Shading 2 Accent 4 | table | 222 |
| Medium Shading 2 Accent 5 | table | 236 |
| Medium Shading 2 Accent 6 | table | 250 |
| Message Header | paragraph | 73 |

| Reserved name | Style type | Index within built-in styles |
|----------------------|-------------------|-------------------------------------|
| No List | numbering | 107 |
| No Spacing | paragraph | 157 |
| Normal | paragraph | 0 |
| Normal (Web) | paragraph | 94 |
| Normal Indent | paragraph | 28 |
| Normal Table | table | 105 |
| Note Heading | paragraph | 79 |
| Outline List 1 | numbering | 108 |
| Outline List 2 | numbering | 109 |
| Outline List 3 | numbering | 110 |
| page number | character | 41 |
| Placeholder Text | character | 156 |
| Plain Text | paragraph | 90 |
| Quote | paragraph | 180 |
| Revision | paragraph | 178 |
| Salutation | paragraph | 75 |
| Signature | paragraph | 64 |
| Strong | character | 87 |
| Subtitle | paragraph | 74 |
| Subtle Emphasis | character | 260 |
| Subtle Reference | character | 262 |
| Table 3D effects 1 | table | 142 |
| Table 3D effects 2 | table | 143 |
| Table 3D effects 3 | table | 144 |
| Table Classic 1 | table | 114 |
| Table Classic 2 | table | 115 |
| Table Classic 3 | table | 116 |
| Table Classic 4 | table | 117 |
| Table Colorful 1 | table | 118 |
| Table Colorful 2 | table | 119 |

| Reserved name | Style type | Index within built-in styles |
|----------------------|-------------------|-------------------------------------|
| Table Colorful 3 | table | 120 |
| Table Columns 1 | table | 121 |
| Table Columns 2 | table | 122 |
| Table Columns 3 | table | 123 |
| Table Columns 4 | table | 124 |
| Table Columns 5 | table | 125 |
| Table Contemporary | table | 145 |
| Table Elegant | table | 146 |
| Table Grid | table | 154 |
| Table Grid 1 | table | 126 |
| Table Grid 2 | table | 127 |
| Table Grid 3 | table | 128 |
| Table Grid 4 | table | 129 |
| Table Grid 5 | table | 130 |
| Table Grid 6 | table | 131 |
| Table Grid 7 | table | 132 |
| Table Grid 8 | table | 133 |
| Table List 1 | table | 134 |
| Table List 2 | table | 135 |
| Table List 3 | table | 136 |
| Table List 4 | table | 137 |
| Table List 5 | table | 138 |
| Table List 6 | table | 139 |
| Table List 7 | table | 140 |
| Table List 8 | table | 141 |
| table of authorities | paragraph | 44 |
| table of figures | paragraph | 35 |
| Table Professional | table | 147 |
| Table Simple 1 | table | 111 |
| Table Simple 2 | table | 112 |

| Reserved name | Style type | Index within built-in styles |
|----------------|------------|------------------------------|
| Table Simple 3 | table | 113 |
| Table Subtle 1 | table | 148 |
| Table Subtle 2 | table | 149 |
| Table Theme | table | 155 |
| Table Web 1 | table | 150 |
| Table Web 2 | table | 151 |
| Table Web 3 | table | 152 |
| Title | paragraph | 62 |
| toa heading | paragraph | 46 |
| toc 1 | paragraph | 19 |
| toc 2 | paragraph | 20 |
| toc 3 | paragraph | 21 |
| toc 4 | paragraph | 22 |
| toc 5 | paragraph | 23 |
| toc 6 | paragraph | 24 |
| toc 7 | paragraph | 25 |
| toc 8 | paragraph | 26 |
| toc 9 | paragraph | 27 |
| TOC Heading | paragraph | 266 |

2.1.236 Part 4 Section 2.7.3.10, next (Style For Next Paragraph)

For additional notes that apply to this portion of the standard, please see the notes for [numStyleLink](#), §2.9.22(a).

- a. *The standard does not limit the length of the value of the val attribute.*

Word restricts the value of this attribute to be at most 253 characters.

2.1.237 Part 4 Section 2.7.3.11, personal (E-Mail Message Text Style)

- a. *The standard states that the values 0 and false on the val attribute are equivalent to the value off.*

Word treats these values on this attribute as equivalent to the value on.

This note applies to the following products: 2007, 2007 SP1.

b. *The standard says personal is ignored if no style exists whose styleId matches the boolean val attribute.*

Word treats the val attribute of personal as a boolean setting.

2.1.238 Part 4 Section 2.7.3.12, personalCompose (E-Mail Message Composition Style)

a. *The standard states that the values 0 and false on the val attribute are equivalent to the value off.*

Word treats these values on this attribute as equivalent to the value on.

This note applies to the following products: 2007, 2007 SP1.

b. *The standard says personalCompose is ignored if no style exists whose styleId matches the boolean val attribute.*

Word treats the val attribute of personalCompose as a boolean setting.

2.1.239 Part 4 Section 2.7.3.13, personalReply (E-Mail Message Reply Style)

a. *The standard states that the values 0 and false on the val attribute are equivalent to the value off.*

Word treats these values on this attribute as equivalent to the value on.

This note applies to the following products: 2007, 2007 SP1.

b. *The standard says personalReply is ignored if no style exists whose styleId matches the boolean val attribute.*

Word treats the val attribute of personalReply as a boolean setting.

2.1.240 Part 4 Section 2.7.3.14, qFormat (Primary Style)

a. *The standard states that the values 0 and false on the val attribute are equivalent to the value off.*

Word treats these values on this attribute as equivalent to the value on.

This note applies to the following products: 2007, 2007 SP1.

2.1.241 Part 4 Section 2.7.3.16, semiHidden (Hide Style From Main User Interface)

a. *The standard states that the values 0 and false on the val attribute are equivalent to the value off.*

Word treats these values on this attribute as equivalent to the value on.

This note applies to the following products: 2007, 2007 SP1.

2.1.242 Part 4 Section 2.7.3.17, style (Style Definition)

a. *The standard says the length of the styleId attribute is unlimited.*

Word ignores the value of the styleId attribute if it exceeds 253 characters in length.

b. *The standard states that the number of styles is unbounded.*

Word does not open a document containing more than 4,079 styles.

2.1.243 Part 4 Section 2.7.3.19, uiPriority (Optional User Interface Sorting Order)

a. *The standard states that the values of the val attribute are defined by the XML Schema integer datatype.*

Word restricts the value of this attribute to be at least 0 and at most 99.

b. *The standard says the default behavior is to sort to the end of the list.*

In Word, the default behavior is to sort to the beginning of the list.

2.1.244 Part 4 Section 2.7.3.20, unhideWhenUsed (Remove Semi-Hidden Property When Style Is Used)

a. *The standard states that the values 0 and false on the val attribute are equivalent to the value off.*

Word treats these values on this attribute as equivalent to the value on.

This note applies to the following products: 2007, 2007 SP1.

2.1.245 Part 4 Section 2.7.4.2, pPr (Paragraph Properties)

a. *The standard states that the cnfStyle, divId, pPrChange, pStyle, rPr, and sectPr elements are valid children of the pPr element.*

Word does not allow these elements to be children of the pPr element.

2.1.246 Part 4 Section 2.7.4.4, rPr (Run Properties)

a. *The standard states that the cs, highlight, oMath, rPrChange, rStyle, and rtl elements are valid children of the rPr element.*

Word does not allow these elements to be children of the rPr element.

2.1.247 Part 4 Section 2.7.5, Table Styles

a. *The standard does not specify how the tblLook affects the corner cell conditional formatting.*

In Word, corner cell conditional formatting is applied only if both of the corresponding first or last row or column are enabled.

b. *The standard specifies that the resolved value of the toggle properties will toggle the previous level (True) or leave it unchanged (False) when present in a table style.*

Word resets the value of the toggle property to the value specified by the table style if a value is present; for example, a value of 1 resets the property's state to True instead of toggling it.

2.1.248 Part 4 Section 2.7.5.1, pPr (Table Style Conditional Formatting Paragraph Properties)

a. *The standard states that the `cnfStyle`, `divId`, `pStyle`, `rPr`, and `sectPr` elements are valid children of the `pPr` element.*

Word does not allow these elements to be children of the `pPr` element.

b. *The standard allows `framePr`, `suppressOverlap`, and `textDirection` as a child element of `pPr` in a table style.*

Word does not allow `framePr`, `suppressOverlap`, or `textDirection` as a child element of `pPr` in a table style, and may fail to open such a file.

2.1.249 Part 4 Section 2.7.5.2, rPr (Table Style Conditional Formatting Run Properties)

For additional notes that apply to this portion of the standard, please see the notes for [rPr](#), [§2.7.4.4\(a\)](#).

a. *The standard states that the `cs`, `highlight`, `oMath`, `rPrChange`, `rStyle`, and `rtl` elements are valid children of the `rPr` element.*

Word does not allow these elements to be children of the `rPr` element.

2.1.250 Part 4 Section 2.7.5.3, tblPr (Table Style Conditional Formatting Table Properties)

a. *The standard states that the `bidiVisual`, `tblLayout`, `tblLook`, `tblOverlap`, `tblpPr`, `tblStyle`, `tblStyleColBandSize`, `tblStyleRowBandSize`, and `tblW` elements are valid children of the `tblPr` element.*

Word does not allow these elements to be children of the `tblPr` element.

2.1.251 Part 4 Section 2.7.5.4, tblPr (Style Table Properties)

a. *The standard states that the `bidiVisual`, `tblLayout`, `tblLook`, `tblOverlap`, `tblpPr`, `tblStyle`, and `tblW` elements are valid children of the `tblPr` element.*

Word does not allow these elements to be children of the `tblPr` element.

2.1.252 Part 4 Section 2.7.5.5, tblStyleColBandSize (Number of Columns in Column Band)

For additional notes that apply to this portion of the standard, please see the notes for [tblPr](#), [§2.4.55\(a\)](#); [tblPr](#), [§2.4.56\(a\)](#); [tblPr](#), [§2.7.5.3\(a\)](#).

a. *The standard states that the values of the `val` attribute are defined by the XML Schema integer datatype.*

Word restricts the value of this attribute to be at least 0 and at most 3.

b. *The standard says the default for `tblStyleColBandSize` is 1.*

Word uses 0 as the default for `tblStyleColBadSize`.

c. *The standard does not specify the meaning if `tblStyleColBandSize` is set to 0.*

If `tblStyleColBandSize` is set to 0, Word does not apply any banded column conditional formatting.

2.1.253 Part 4 Section 2.7.5.6, `tblStylePr` (Style Conditional Table Formatting Properties)

a. *The standard specifies the precedence order in which conditional formatting should be applied.*

When specified, Office applies conditional formats in the following order (therefore subsequent formats override properties on previous formats):

Whole table

Banded rows, even row banding

Banded columns, even column banding

First column, last column

First row, last row

Top left, top right, bottom left, bottom right

2.1.254 Part 4 Section 2.7.5.7, `tblStyleRowBandSize` (Number of Rows in Row Band)

For additional notes that apply to this portion of the standard, please see the notes for [tblPr, §2.4.55\(a\)](#); [tblPr, §2.4.56\(a\)](#); [tblPr, §2.7.5.3\(a\)](#).

a. *The standard says the default for `tblStyleRowBandSize` is 1.*

Word uses 0 as the default for `tblStyleRowBandSize`.

b. *The standard does not specify the meaning if `tblStyleRowBandSize` is set to 0.*

If `tblStyleRowBandSize` is set to 0, Word does not apply any banded row conditional formatting.

c. *The standard states that the values of the `val` attribute are defined by the XML Schema integer datatype.*

Word restricts the value of this attribute to be at least 0 and at most 3.

2.1.255 Part 4 Section 2.7.5.8, `tcPr` (Style Table Cell Properties)

a. *The standard allows all table cell properties in table styles.*

Word does not allow `cellDel`, `cellIns`, `cellMerge`, `cnfStyle`, `gridSpan`, `hideMark`, `hMerge`, `tcFitText`, `tcPrChange`, `tcW`, `textDirection`, and `vMerge` in table styles.

b. *The standard allows `tcBorders` elements in a table style for table-wide cell properties.*

Word does not allow the `tcBorders` elements in a table style for table-wide cell properties.

2.1.256 Part 4 Section 2.7.5.9, tcPr (Table Style Conditional Formatting Table Cell Properties)

a. *The standard says the properties in this element apply to the table regions specified by the conditional formatting setting.*

In Word, the noWrap, tcMar, and vAlign elements in this element always apply to entire table rows, even if the parent tblStylePr specifies the formatting should be applied to columns or a particular cell.

b. *The standard states that the cellDel, cellIns, cellMerge, cnfStyle, gridSpan, hideMark, hMerge, tcFitText, tcPrChange, tcW, textDirection, and vMerge elements are valid children of the tcPr element.*

Word does not allow these elements to be children of the tcPr element.

2.1.257 Part 4 Section 2.7.5.10, trPr (Table Style Conditional Formatting Table Row Properties)

For additional notes that apply to this portion of the standard, please see the notes for [trPrChange, §2.13.5.39\(a\)](#).

a. *The standard allows hidden as a child of trPr in a table style.*

Word ignores hidden if it is a child of trPr in a table style.

b. *The standard states that the cnfStyle, del, divId, gridAfter, gridBefore, ins, trHeight, trPrChange, wAfter, and wBefore elements are valid children of the trPr element.*

Word does not allow these elements to be children of the trPr element.

2.1.258 Part 4 Section 2.7.5.11, trPr (Style Table Row Properties)

a. *The standard states that the cnfStyle, del, divId, gridAfter, gridBefore, ins, trHeight, trPrChange, wAfter, and wBefore elements are valid children of the trPr element.*

Word does not allow these elements to be children of the trPr element.

b. *The standard allows hidden as a child of trPr in a table style.*

Word ignores hidden as a child of trPr in a table style.

2.1.259 Part 4 Section 2.7.7, Paragraph Styles

a. *The standard specifies that the resolved value of the toggle properties will toggle the previous level (True) or leave it unchanged (False) when present in a paragraph style.*

Word resets the value of the toggle property to the value specified by the paragraph style if a value is present; for example, a value of 1 resets the property's state to True instead of toggling it.

2.1.260 Part 4 Section 2.7.7.2, pPr (Style Paragraph Properties)

a. *The standard states that the cnfStyle, divId, pStyle, rPr, and sectPr elements are valid children of the pPr element.*

Word does not allow these elements to be children of the pPr element.

b. *The standard allows framePr, suppressOverlap, and textDirection as child elements of pPr in a style.*

Word does not allow framePr, suppressOverlap, and textDirection as child elements in a style and may fail to load such a file.

2.1.261 Part 4 Section 2.7.8.1, rPr (Run Properties)

a. *The standard states that the cs, highlight, oMath, rStyle, and rtl elements are valid children of the rPr element.*

Word does not allow these elements to be children of the rPr element.

2.1.262 Part 4 Section 2.8, Fonts

a. *The standard states that when a font is unavailable, font substitution elements may not be modified.*

Word can modify the font substitution elements (altName, panose1, charset, family, notTrueType, pitch, sig) if a font with the same name has been loaded before in the same application session.

b. *The standard does not state that different forms of embedded font types must be from the same font.*

Word can only display one embedded font per font name. If **embedRegular** ("[\[ECMA-376\]](#) Part 4 §2.8.2.6; embedRegular (Regular Font Style Embedding)"), **embedBold** ("[\[ECMA-376\]](#) Part 4 §2.8.2.3; embedBold (Bold Style Font Style Embedding)"), **embedItalic** ("[\[ECMA-376\]](#) Part 4 §2.8.2.5; embedItalic (Italic Font Style Embedding)") or **embedBoldItalic** ("[\[ECMA-376\]](#) Part 4 §2.8.2.4; embedBoldItalic (Bold Italic Font Style Embedding)") specify different fonts, only one of these fonts will be used to display all variations. If multiple documents are loaded which specify different embedded fonts for a given font name, only one embedded font will be used to display all variations of such font across all documents. When Word saves a document; **embedRegular**, **embedBold**, **embedItalic** and **embedBoldItalic** will all be embedded forms of the same font.

2.1.263 Part 4 Section 2.8.2.1, altName (Alternate Names for Font)

a. *The standard describes the altName element as a set of alternative names given as comma-delimited list.*

Word does not split values on commas or anything else; instead, it treats the entire value as a single alternate font name.

b. *The standard does not limit the length of the value of the val attribute.*

Word restricts the value of this attribute to be at most 31 characters.

c. *The standard states that the value of the altName element does not change when resaving a document.*

Word removes the altName element for system fonts, keeps it for other fonts the first time they are loaded in the session, and reverts them to the previous value for subsequent times they are loaded in the session.

d. *The standard states that the value of the altName element does not change when resaving a document.*

When Word resolves an unknown font, it changes the value of the altName element to the font to which it was resolved, whether altName had a value before or not.

2.1.264 Part 4 Section 2.8.2.2, charset (Character Set Supported By Font)

- a. *The standard states that when a font is unavailable the charset element shall not be modified.*

Word can modify the charset element of an unavailable font if a font with the same name has been loaded before in the same Word instance.

2.1.265 Part 4 Section 2.8.2.3, embedBold (Bold Style Font Style Embedding)

For additional notes that apply to this portion of the standard, please see the notes for [embedRegular, §2.8.2.6\(a\)](#); [attachedTemplate, §2.15.1.6\(a\)](#).

- a. *The standard states that the subsetted attribute specifies that the embedded font targeted by the id attribute has been subsetted.*

Word ignores the subsetted attribute on load. Rather, it determines if a font is subsetted by examining the embedded font data.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

- b. *The standard states that if the subsetted attribute is omitted, then the embedded font target by the id attribute shall not be handled as though it is subsetted.*

Word does not write the subsetted attribute if saveSubsetFonts is off, even if the font really is subsetted.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.266 Part 4 Section 2.8.2.4, embedBoldItalic (Bold Italic Font Style Embedding)

For additional notes that apply to this portion of the standard, please see the notes for [embedBold, §2.8.2.3\(a, b\)](#); [embedRegular, §2.8.2.6\(a\)](#); [attachedTemplate, §2.15.1.6\(a\)](#).

2.1.267 Part 4 Section 2.8.2.5, embedItalic (Italic Font Style Embedding)

For additional notes that apply to this portion of the standard, please see the notes for [embedBold, §2.8.2.3\(a, b\)](#); [embedRegular, §2.8.2.6\(a\)](#); [attachedTemplate, §2.15.1.6\(a\)](#).

2.1.268 Part 4 Section 2.8.2.6, embedRegular (Regular Font Style Embedding)

For additional notes that apply to this portion of the standard, please see the notes for [embedBold, §2.8.2.3\(a, b\)](#); [attachedTemplate, §2.15.1.6\(a\)](#).

- a. *The standard implies that the fontKey attribute is optional.*

Word requires this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.269 Part 4 Section 2.8.2.8, embedTrueTypeFonts (Embed TrueType Fonts)

- a. *The standard states that the embedTrueTypeFonts element directs the application to embed used fonts.*

Word does not embed non-installed fonts after resolved through font substitution.

2.1.270 Part 4 Section 2.8.2.9, family (Font Family)

- a. *The standard states that when a font is unavailable the family element shall not be modified.*

Word can modify the family element of an unavailable font if a font with the same name has been loaded before in the same Word instance.

2.1.271 Part 4 Section 2.8.2.10, font (Properties for a Single Font)

- a. *The standard defines font name with an unbounded string length.*

Word limits font name length to between 1 and 31 characters.

- b. *The standard does not describe font names as case insensitive.*

In Word, font names are case insensitive.

- c. *The standard states that the name attribute specifies the name of the font.*

Word prepends the font name with an @ symbol to signify the font should be used for rendering vertical text.

2.1.272 Part 4 Section 2.8.2.12, notTrueType (Raster or Vector Font)

- a. *The standard states that the values 0 and false on the val attribute are equivalent to the value off.*

Word treats these values on this attribute as equivalent to the value on.

This note applies to the following products: 2007, 2007 SP1.

- b. *The standard states that when a font is unavailable the notTrueType element shall not be modified.*

Word can modify the notTrueType element of an unavailable font if a font with the same name has been loaded before in the same Word instance.

2.1.273 Part 4 Section 2.8.2.13, panose1 (Pansose-1 Typeface Classification Number)

- a. *The standard states that when a font is unavailable, the panose1 element shall not be modified.*

Word does not roundtrip the panose1 value for fonts not installed on the system.

- b. *The standard states that when a font is unavailable the panose1 element shall not be modified.*

Word can modify the panose1 element of an unavailable font if a font with the same name has been loaded before in the same Word instance.

2.1.274 Part 4 Section 2.8.2.14, pitch (Font Pitch)

- a. *The standard states that when a font is unavailable the pitch element shall not be modified.*

Word can modify the pitch element of an unavailable font if a font with the same name has been loaded before in the same Word instance.

2.1.275 Part 4 Section 2.8.2.16, sig (Supported Unicode Subranges and Code Pages)

- a. *The standard states that the sig element shall not be modified when the font is an unknown font.*

For unknown fonts, if the font cannot be resolved using the alternate font name or character set, Word might incorrectly reset bits to 0 in the usb0 attribute when bits in the csb0 attribute are set.

- b. *The standard states that if the sig element is omitted, then no supported code page or Unicode subrange information is available.*

Word writes the font signature with all bits set to 0 when the sig element is omitted.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

- c. *The standard states that when a font is unavailable the sig element shall not be modified.*

Word can modify the sig element of an unavailable font if a font with the same name has been loaded before in the same Word instance.

- d. *The standard defines Bit 8 in csb0 as Reserved for Alternate ANSI.*

In Word, Bit 8 in csb0 is defined as the Vietnamese code page.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.276 Part 4 Section 2.9.1, abstractNum (Abstract Numbering Definition)

- a. *The standard allows any integer for the attribute abstractNumId.*

Word will not load a file where abstractNumId is negative.

2.1.277 Part 4 Section 2.9.2, abstractNumId (Abstract Numbering Definition Reference)

- a. *The standard states that the values of the val attribute are defined by the XML integer datatype.*

Word restricts the value of this attribute to be at least 0.

2.1.278 Part 4 Section 2.9.3, ilvl (Numbering Level Reference)

- a. *The standard states that the values of the val attribute are defined by the XML Schema integer datatype.*

Word restricts the value of this attribute to be at least 0 and at most 255.

2.1.279 Part 4 Section 2.9.4, isLgl (Display All Levels Using Arabic Numerals)

- a. *The standard implies that only previous levels are affected by isLgl.*

Word isLgl affects all numbering levels, including the immediate level.

b. *The standard says the level text is displayed using the decimal number format regardless of the actual number format of that level in the list.*

In Word, if the actual numbering format of the level is none, then Word will display the level text using the none format regardless of isLgl.

2.1.280 Part 4 Section 2.9.5, legacy (Legacy Numbering Level Properties)

a. *The standard allows negative values for legacyIndent.*

Word will ignore the level definition if the value of legacyIndent is negative.

b. *The standard says the default value for the legacy attribute is on.*

In Word, the default value for the legacy attribute is off.

2.1.281 Part 4 Section 2.9.6, lvl (Numbering Level Override Definition)

For additional notes that apply to this portion of the standard, please see the notes for [lvl, §2.9.7\(a, b\)](#).

2.1.282 Part 4 Section 2.9.7, lvl (Numbering Level Definition)

a. *The standard allows any integer for lvl.*

Word will not load a file with lvl less than 0 or greater than 8.

b. *The standard states that tentative levels shall not be shown in user interface.*

Word displays tentative numbering levels in its Multilevel List drop-down list.

2.1.283 Part 4 Section 2.9.8, lvlJc (Justification)

For additional notes that apply to this portion of the standard, please see the notes for [jc, §2.3.1.13\(b\)](#).

a. *The standard allows many values for lvlJc beyond left, center and right.*

Word only supports values left, center, and right for lvlJc.

2.1.284 Part 4 Section 2.9.11, lvlRestart (Restart Numbering Level Symbol)

a. *The standard allows any integer for the value of lvlRestart.*

Word only allows values between 0 and 7 for lvlRestart.

b. *The standard allows lvlRestart as a child of lvl (Numbering Level Override Definition).*

Word ignores lvlRestart if it is a child of lvl (Numbering Level Override Definition).

c. *The standard states that a numbering level restarts when an instance of the specified numbering level is used.*

Word restarts a numbering level when an instance of the specified numbering level or any higher level is used.

d. *The standard states that if this element is omitted, the numbering level shall restart each time the previous numbering level is used.*

If this element is omitted, Word restarts the numbering level each time the previous numbering level or any higher level is used.

2.1.285 Part 4 Section 2.9.12, lvlText (Numbering Level Text)

a. *The standard does not bound the number of escaped sequences %[1-9] included in the val attribute.*

Word allows at most 9 escaped sequences %[1-9] in the val attribute.

b. *The standard allows any length string for the val attribute of lvlText.*

Word requires that the length of the val attribute be at most 31 characters after instances of the % syntax are converted to their final values.

c. *The standard states that if the val attribute contains a % followed by a number higher than the current level, then that number is ignored.*

If the val attribute contains a % followed by a number higher than the current level, then Word ignores the entire lvlText.

d. *The standard allows the val attribute to be omitted while the null attribute is not set to on.*

Word requires that the null attribute be set to on if the val attribute is omitted.

2.1.286 Part 4 Section 2.9.14, name (Abstract Numbering Definition Name)

For additional notes that apply to this portion of the standard, please see the notes for [numStyleLink, §2.9.22\(a\)](#).

a. *The standard does not limit the length of the value of the val attribute.*

Word restricts the value of this attribute to be at most 253 characters.

2.1.287 Part 4 Section 2.9.16, num (Numbering Definition Instance)

a. *The standard allows any integer for the numId.*

Word requires that the numId contain at most 32 characters.

2.1.288 Part 4 Section 2.9.18, numFmt (Numbering Format)

a. *The standard does not specify behavior when numFmt is bullet but lvlText is also set.*

If the numFmt is bullet, Word will use the literal text in lvlText, ignoring %x syntax in lvlText.

2.1.289 Part 4 Section 2.9.19, numId (Numbering Definition Instance Reference)

a. *The standard states that the values of the val attribute are defined by the XML Schema integer datatype.*

Word restricts the value of this attribute to be at least 0.

2.1.290 Part 4 Section 2.9.22, numStyleLink (Numbering Style Reference)

- a. *The standard does not limit the length of the value of the val attribute.*

Word restricts the value of this attribute to be at most 253 characters.

2.1.291 Part 4 Section 2.9.23, pict (Picture Numbering Symbol Properties)

- a. *The standard states that any element from the VML namespace or the Office VML Drawing namespace is a valid child of the pict element.*

Word only allows the group, image, line, oval, polyline, rect, roundrect, shape, and shapetype elements from these namespaces to be children of the pict element.

- b. *The standard states that the control and movie elements are valid children of the pict element.*

Word does not allow the control and movie elements to be children of the pict element.

2.1.292 Part 4 Section 2.9.24, pPr (Numbering Level Associated Paragraph Properties)

- a. *The standard states that the cnfStyle, divId, pPrChange, rPr, and sectPr elements are valid children of the pPr element.*

Word does not allow these elements to be children of the pPr element.

- b. *The standard lists all pPr child elements as valid in the context of a numbering definition instance.*

Word only allows jc, ind, and tabs as child elements.

2.1.293 Part 4 Section 2.9.25, pStyle (Paragraph Style's Associated Numbering Level)

For additional notes that apply to this portion of the standard, please see the notes for [numStyleLink, §2.9.22\(a\)](#).

- a. *The standard does not limit the length of the value of the val attribute.*

Word restricts the value of this attribute to be at most 253 characters.

2.1.294 Part 4 Section 2.9.26, rPr (Numbering Symbol Run Properties)

- a. *The standard states that the highlight, oMath, rPrChange, and rStyle elements are valid children of the rPr element.*

Word does not allow these elements to be children of the rPr element.

2.1.295 Part 4 Section 2.9.27, start (Starting Value)

- a. *The standard states that the values of the val attribute are defined by the XML Schema integer datatype.*

Word restricts the value of this attribute to be at least 0.

- b. *The standard allows start as a child of lvl (Numbering Level Override Definition).*

Word ignores start if it is a child of lvl (Numbering Level Override Definition).

2.1.296 Part 4 Section 2.9.29, styleLink (Numbering Style Definition)

For additional notes that apply to this portion of the standard, please see the notes for [numStyleLink, §2.9.22\(a\)](#).

- a. *The standard does not limit the length of the value of the val attribute.*

Word restricts the value of this attribute to be at most 253 characters.

2.1.297 Part 4 Section 2.10.1, evenAndOddHeaders (Different Even/Odd Page Headers and Footers)

- a. *The standard says the determination of even and odd pages is based on the ordinality of the pages.*

Word uses the starting value of page numbering for the parent section to determine if the first page is even or odd. This is specified with the start attribute on pgNumType element.

- b. *The standard says a missing header type shall use a new blank header.*

If a header is missing in a section beyond the first section, Word uses the header from the previous section.

2.1.298 Part 4 Section 2.10.2, footerReference (Footer Reference)

For additional notes that apply to this portion of the standard, please see the notes for [attachedTemplate, §2.15.1.6\(a\)](#).

- a. *The standard says the relationship type referenced by this element shall be <http://schemas.openxmlformats.org/officeDocument/2006/footer>.*

Word uses the relationship type <http://schemas.openxmlformats.org/officeDocument/2006/relationships/footer> as specified by part 1.

- b. *The standard says that when no footerReference for the odd page footer is specified, then the even page footer shall be inherited from the previous section.*

In Word, when no footerReference for the odd page footer is specified, then the odd page footer is inherited from the previous section.

2.1.299 Part 4 Section 2.10.3, ftr (Footer)

For additional notes that apply to this portion of the standard, please see the notes for [oMath, §7.1.2.77\(g\)](#); [oMathPara, §7.1.2.78\(d\)](#).

2.1.300 Part 4 Section 2.10.4, hdr (Header)

For additional notes that apply to this portion of the standard, please see the notes for [oMath, §7.1.2.77\(g\)](#); [oMathPara, §7.1.2.78\(d\)](#).

2.1.301 Part 4 Section 2.10.5, headerReference (Header Reference)

For additional notes that apply to this portion of the standard, please see the notes for [attachedTemplate, §2.15.1.6\(a\)](#).

- a. The standard says that the relationship type referenced by this element shall be <http://schemas.openxmlformats.org/officeDocument/2006/header>.

Word uses the relationship type

<http://schemas.openxmlformats.org/officeDocument/2006/relationships/header> as specified in part 1.

- b. The standard says that if no headerReference for the odd page header is specified, then the even page header shall be inherited from the previous section.

In Word, if no headerReference for the odd page header is specified, then the odd page header is inherited from the previous section.

2.1.302 Part 4 Section 2.10.6, titlePg (Different First Page Headers and Footers)

- a. The standard says that if titlePg is not specified, the first page shall use the odd page header/footer.

If the evenAndOddHeaders element is true, Word uses the odd/even state of the start attribute on the pgNumType element to determine whether to use the even or odd header on the first page.

- b. The standard says that if this element is specified and no first page header is specified using headerReference, a blank first page header is used.

In Word, for all sections other than the first section in the document, if this element is specified and no first page header is specified, then the first page header of the previous section is used.

2.1.303 Part 4 Section 2.11.2, endnote (Endnote Content)

For additional notes that apply to this portion of the standard, please see the notes for [footnote, §2.11.10\(a\)](#); [oMath, §7.1.2.77\(g\)](#); [oMathPara, §7.1.2.78\(d\)](#).

- a. The standard allows any integer for footnote or endnote ID.

Word only allows integers between -2147483648 and 32767.

2.1.304 Part 4 Section 2.11.3, endnote (Special Endnote List)

- a. The standard allows any integer for footnote or endnote ID.

Word only allows integers between -2147483648 and 32767.

- b. The standard says the footnote or endnote ID is used to match the ID in the footnoteRef or endnoteRef, although footnoteRef and endnoteRef do not contain an ID.

In Word, the footnote or endnote ID is used to match the ID in the footnoteReference or endnoteReference.

2.1.305 Part 4 Section 2.11.7, endnoteReference (Endnote Reference)

- a. The standard allows any integer for footnote or endnote ID.

Word only allows integers between -2147483648 and 32767.

b. *The standard allows endnote references in headers, footers, comments, and textboxes.*

Word does not allow endnote references in headers, footers, comments, or textboxes.

2.1.306 Part 4 Section 2.11.9, footnote (Special Footnote List)

For additional notes that apply to this portion of the standard, please see the notes for [endnote, §2.11.3\(a, b\)](#).

2.1.307 Part 4 Section 2.11.10, footnote (Footnote Content)

For additional notes that apply to this portion of the standard, please see the notes for [endnote, §2.11.2\(a\)](#); [oMath, §7.1.2.77\(g\)](#); [oMathPara, §7.1.2.78\(d\)](#).

a. *The standard states that the id attribute is used to match the contents of a footnote or endnote using the footnoteRef or endnoteRef element.*

Word uses this attribute to make this match using the footnoteReference/endnoteReference elements.

2.1.308 Part 4 Section 2.11.14, footnoteReference (Footnote Reference)

For additional notes that apply to this portion of the standard, please see the notes for [endnoteReference, §2.11.7\(a\)](#).

a. *The standard states that footnote references can appear in headers, footers, comments, and textboxes.*

Word does not allow footnote references in headers, footers, comments, or textboxes.

2.1.309 Part 4 Section 2.11.17, numFmt (Footnote Numbering Format)

a. *The standard says the footnote numFmt specifies the numbering format that shall be used for both footnotes and endnotes.*

In Word, the footnotes numFmt specifies the numbering format for footnotes and the endnote numFmt specifies the numbering format for endnotes.

b. *The standard allows the numFmt to be set to bullet numbering format.*

If numFmt is set to bullet numbering format, Word uses decimal numbering format instead.

2.1.310 Part 4 Section 2.11.18, numFmt (Endnote Numbering Format)

a. *The standard says the default value for endnote numbering format is decimal.*

In Word, the default value for endnote numbering format is lowerRoman.

b. *The standard allows the numFmt to be set to bullet numbering format.*

If numFmt is set to bullet numbering format, Word uses decimal numbering format instead.

c. *The standard says the endnote numFmt specifies the numbering format which shall be used for both footnotes and endnotes.*

In Word, the footnotes numFmt specifies the numbering format for footnotes and the endnote numFmt specifies the numbering format for endnotes.

2.1.311 Part 4 Section 2.11.20, numStart (Footnote and Endnote Numbering Starting Value)

a. *The standard states that the values of the val attribute are defined by the XML Schema integer datatype.*

Word defines the values of this attribute with the XML Schema unsignedShort datatype.

2.1.312 Part 4 Section 2.11.21, pos (Footnote Placement)

a. *The standard states that footnote placement operates at the document level and is ignored at the section level.*

Word determines footnote placement from the section level and ignores the setting at the document level.

2.1.313 Part 4 Section 2.12.5, docPart (Glossary Document Entry)

a. *The standard states that the minOccurs value for the docPartPr child element is 0.*

Word requires an occurrence of this element.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.314 Part 4 Section 2.12.6, docPartBody (Contents of Glossary Document Entry)

For additional notes that apply to this portion of the standard, please see the notes for [oMath, §7.1.2.77\(g\)](#); [oMathPara, §7.1.2.78\(d\)](#).

2.1.315 Part 4 Section 2.12.7, docPartPr (Glossary Document Entry Properties)

a. *The standard implies that the name child element is optional.*

Word requires an instance of the name child element.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

b. *The standard states that there can be multiple occurrences of any given child element.*

Word ignores all except the last occurrence of any given child element.

2.1.316 Part 4 Section 2.12.11, guid (Entry ID)

a. *The standard implies that the val attribute is optional.*

Word requires this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.317 Part 4 Section 2.13.4.2, comment (Comment Content)

For additional notes that apply to this portion of the standard, please see the notes for [cellDel, §2.13.5.1\(a\)](#); [ins, §2.13.5.20\(b\)](#); [oMath, §7.1.2.77\(g\)](#); [oMathPara, §7.1.2.78\(d\)](#).

- a. The standard does not limit the length of the value of the initials attribute.

Word restricts the value of this attribute to be at most nine characters.

- b. The standard allows revisions inside comments.

Word does not support having revisions in comments and the following revision elements should not appear in comment content:

| Revision Elements |
|---|
| cellDel (“ [ECMA-376] Part 4 §2.13.5.1; cellDel (Table Cell Deletion)”) |
| cellIns (“ [ECMA-376] Part 4 §2.13.5.2; cellIns (Table Cell Insertion)”) |
| cellMerge (“ [ECMA-376] Part 4 §2.13.5.3; cellMerge (Vertically Merged/Split Table Cells)”); |
| customXmlDelRangeEnd (“ [ECMA-376] Part 4 §2.13.5.4; customXmlDelRangeEnd (Custom XML Markup Deletion End)”) |
| customXmlDelRangeStart (“ [ECMA-376] Part 4 §2.13.5.5; customXmlDelRangeStart (Custom XML Markup Deletion Start)”) |
| customXmlInsRangeEnd (“ [ECMA-376] Part 4 §2.13.5.6; customXmlInsRangeEnd (Custom XML Markup Insertion End)”) |
| customXmlInsRangeStart (“ [ECMA-376] Part 4 §2.13.5.7; customXmlInsRangeStart (Custom XML Markup Insertion Start)”) |
| customXmlMoveFromRangeEnd (“ [ECMA-376] Part 4 §2.13.5.8; customXmlMoveFromRangeEnd (Custom XML Markup Move Source End)”) |
| customXmlMoveFromRangeStart (“ [ECMA-376] Part 4 §2.13.5.9; customXmlMoveFromRangeStart (Custom XML Markup Move Source Start)”) |
| customXmlMoveToRangeEnd (“ [ECMA-376] Part 4 §2.13.5.10; customXmlMoveToRangeEnd (Custom XML Markup Move Destination Location End)”) |
| customXmlMoveToRangeStart (“ [ECMA-376] Part 4 §2.13.5.11; customXmlMoveToRangeStart (Custom XML Markup Move Destination Location Start)”) |
| del (“ [ECMA-376] Part 4 §2.13.5.12; del (Deleted Run Content)”) |
| del (“ [ECMA-376] Part 4 §2.13.5.13; del (Deleted Paragraph)”) |
| del (“ [ECMA-376] Part 4 §2.13.5.14; del (Deleted Table Row)”) |
| del (“ [ECMA-376] Part 4 §2.13.5.15; del (Deleted Math Control Character)”) |
| delInstrText (“ [ECMA-376] Part 4 §2.16.13; delInstrText (Deleted Field Code)”) |
| delText (“ [ECMA-376] Part 4 §2.3.3.7; delText (Deleted Text)”); |
| ins (“ [ECMA-376] Part 4 §2.13.5.16; ins (Inserted Table Row)”) |

| Revision Elements |
|---|
| ins ("ECMA-376 Part 4 §2.13.5.17; ins (Inserted Math Control Character)"); |
| ins ("ECMA-376 Part 4 §2.13.5.18; ins (Inserted Paragraph)") |
| ins ("ECMA-376 Part 4 §2.13.5.19; ins (Inserted Numbering Properties)") |
| ins ("ECMA-376 Part 4 §2.13.5.20; ins (Inserted Run Content)") |
| moveFrom ("ECMA-376 Part 4 §2.13.5.21; moveFrom (Move Source Run Content)") |
| moveFrom ("ECMA-376 Part 4 §2.13.5.22; moveFrom (Move Source Paragraph)") |
| moveFromRangeEnd ("ECMA-376 Part 4 §2.13.5.23; moveFromRangeEnd (Move Source Location Container - End)") |
| moveFromRangeStart ("ECMA-376 Part 4 §2.13.5.24; moveFromRangeStart (Move Source Location Container - Start)") |
| moveTo ("ECMA-376 Part 4 §2.13.5.25; moveTo (Move Destination Paragraph)") |
| moveTo ("ECMA-376 Part 4 §2.13.5.26; moveTo (Move Destination Run Content)") |
| moveToRangeEnd ("ECMA-376 Part 4 §2.13.5.27; moveToRangeEnd (Move Destination Location Container - End)") |
| moveToRangeStart ("ECMA-376 Part 4 §2.13.5.28; moveToRangeStart (Move Destination Location Container - Start)") |
| numberingChange ("ECMA-376 Part 4 §2.13.5.29; numberingChange (Previous Numbering Field Properties)") |
| numberingChange ("ECMA-376 Part 4 §2.13.5.30; numberingChange (Previous Paragraph Numbering Properties)") |
| pPrChange ("ECMA-376 Part 4 §2.13.5.31; pPrChange (Revision Information for Paragraph Properties)") |
| rPrChange ("ECMA-376 Part 4 §2.13.5.32; rPrChange (Revision Information for Run Properties)") |
| rPrChange ("ECMA-376 Part 4 §2.13.5.33; rPrChange (Revision Information for Run Properties on the Paragraph Mark)") |
| sectPrChange ("ECMA-376 Part 4 §2.13.5.34; sectPrChange (Revision Information for Section Properties)") |
| tblGridChange ("ECMA-376 Part 4 §2.13.5.35; tblGridChange (Revision Information for Table Grid Column Definitions)") |
| tblPrChange ("ECMA-376 Part 4 §2.13.5.36; tblPrChange (Revision Information for Table Properties)") |
| tblPrExChange ("ECMA-376 Part 4 §2.13.5.37; tblPrExChange (Revision Information for Table-Level Property Exceptions)") |
| tcPrChange ("ECMA-376 Part 4 §2.13.5.38; tcPrChange (Revision Information for Table Cell Properties)") |
| trPrChange ("ECMA-376 Part 4 §2.13.5.39; trPrChange (Revision Information for Table Row Properties)") |

c. The standard does not limit the length of the value of the author attribute.

Word restricts the value of this attribute to be at most 255 characters.

2.1.318 Part 4 Section 2.13.4.3, commentRangeEnd (Comment Anchor Range End)

For additional notes that apply to this portion of the standard, please see the notes for [sdt, §2.5.2.28\(a\)](#); [sdt, §2.5.2.29\(a\)](#); [sdt, §2.5.2.30\(a\)](#); [sdt, §2.5.2.31\(a\)](#); [cellDel, §2.13.5.1\(a\)](#); [oMathPara, §7.1.2.78\(a\)](#).

a. *The standard says that if this element appears in a comment content story, then it may be ignored.*

If this element appears in a comment content story, then Word sometimes fails to load the document.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.319 Part 4 Section 2.13.4.4, commentRangeStart (Comment Anchor Range Start)

For additional notes that apply to this portion of the standard, please see the notes for [sdt, §2.5.2.28\(a\)](#); [sdt, §2.5.2.29\(a\)](#); [sdt, §2.5.2.30\(a\)](#); [sdt, §2.5.2.31\(a\)](#); [cellDel, §2.13.5.1\(a\)](#); [oMathPara, §7.1.2.78\(a\)](#).

a. *The standard says that commentRangeStart, if appearing in comment content, may be ignored.*

If commentRangeStart appears in comment content, Word may fail to load the file.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

b. *The standard allows a comment range to begin inside a math object and end outside that math object or vice versa.*

Word does not allow a comment range to begin inside a math object and end outside that math object or vice versa.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

c. *The standard allows an unbounded number of comment ranges.*

Word will not open a file with too many comment ranges (16380 if the uiCompat97to2003 element is present, intMax otherwise).

2.1.320 Part 4 Section 2.13.4.5, commentReference (Comment Content Reference Mark)

For additional notes that apply to this portion of the standard, please see the notes for [cellDel, §2.13.5.1\(a\)](#).

a. *The standard says that if commentReference appears in comment content it may be ignored.*

If commentReference appears in comment content, Word may fail to load the file.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

b. *The standard allows commentReference in headers, footers, textboxes, footnotes, and endnotes.*

Word does not allow this element in headers, footers, textboxes, footnotes, and endnotes.

2.1.321 Part 4 Section 2.13.5.1, cellDel (Table Cell Deletion)

For additional notes that apply to this portion of the standard, please see the notes for [tcPr, §2.7.5.8\(a\)](#); [tcPr, §2.7.5.9\(b\)](#); [comment, §2.13.4.2\(c\)](#); [ins, §2.13.5.20\(b\)](#).

a. The standard states that the values of the *id* attribute are defined by the XML Schema integer datatype.

Word does not allow a value of -1 on this attribute.

2.1.322 Part 4 Section 2.13.5.2, cellIns (Table Cell Insertion)

For additional notes that apply to this portion of the standard, please see the notes for [tcPr, §2.7.5.9\(b\)](#); [comment, §2.13.4.2\(c\)](#); [cellDel, §2.13.5.1\(a\)](#); [ins, §2.13.5.20\(b\)](#).

2.1.323 Part 4 Section 2.13.5.3, cellMerge (Vertically Merged/Split Table Cells)

For additional notes that apply to this portion of the standard, please see the notes for [tcPr, §2.7.5.8\(a\)](#); [tcPr, §2.7.5.9\(b\)](#); [comment, §2.13.4.2\(c\)](#); [cellDel, §2.13.5.1\(a\)](#); [ins, §2.13.5.20\(b\)](#).

2.1.324 Part 4 Section 2.13.5.4, customXmlDelRangeEnd (Custom XML Markup Deletion End)

For additional notes that apply to this portion of the standard, please see the notes for [sdt, §2.5.2.28\(a\)](#); [sdt, §2.5.2.29\(a\)](#); [sdt, §2.5.2.30\(a\)](#); [sdt, §2.5.2.31\(a\)](#); [comment, §2.13.4.2\(b\)](#); [cellDel, §2.13.5.1\(a\)](#); [oMathPara, §7.1.2.78\(a\)](#).

2.1.325 Part 4 Section 2.13.5.5, customXmlDelRangeStart (Custom XML Markup Deletion Start)

For additional notes that apply to this portion of the standard, please see the notes for [sdt, §2.5.2.28\(a\)](#); [sdt, §2.5.2.29\(a\)](#); [sdt, §2.5.2.30\(a\)](#); [sdt, §2.5.2.31\(a\)](#); [comment, §2.13.4.2\(b, c\)](#); [cellDel, §2.13.5.1\(a\)](#); [ins, §2.13.5.20\(b\)](#); [oMathPara, §7.1.2.78\(a\)](#).

a. The standard states that the *customXmlDelRangeStart* element applies deletion to *customXml* elements.

Word uses this element to apply deletion to *customXml* elements and structured document tag elements.

b. The standard states that the range specified by a pair of *customXmlDelRangeStart* and *customXmlDelRangeEnd* elements can overlap the range specified by another such pair of elements.

Word does not allow the range specified by a pair of *customXmlDelRangeStart* and *customXmlDelRangeEnd* elements to overlap the range specified by any other such pair of elements.

2.1.326 Part 4 Section 2.13.5.6, customXmlInsRangeEnd (Custom XML Markup Insertion End)

For additional notes that apply to this portion of the standard, please see the notes for [sdt, §2.5.2.28\(a\)](#); [sdt, §2.5.2.29\(a\)](#); [sdt, §2.5.2.30\(a\)](#); [sdt, §2.5.2.31\(a\)](#); [comment, §2.13.4.2\(b\)](#); [cellDel, §2.13.5.1\(a\)](#); [oMathPara, §7.1.2.78\(a\)](#).

2.1.327 Part 4 Section 2.13.5.7, customXmlInsRangeStart (Custom XML Markup Insertion Start)

For additional notes that apply to this portion of the standard, please see the notes for [sdt, §2.5.2.28\(a\)](#); [sdt, §2.5.2.29\(a\)](#); [sdt, §2.5.2.30\(a\)](#); [sdt, §2.5.2.31\(a\)](#); [comment, §2.13.4.2\(b, c\)](#); [cellDel, §2.13.5.1\(a\)](#); [ins, §2.13.5.20\(b\)](#); [oMathPara, §7.1.2.78\(a\)](#).

a. The standard applies semantics and restrictions of both `customXmlInsRangeStart` and `customXmlInsRangeEnd` to `customXmlInsRangeStart`.

Word only applies the semantics and restrictions of `customXmlInsRangeStart`.

b. The standard states that the `customXmlInsRangeStart` element applies insertion to `customXml` elements.

Word uses this element to apply insertion to `customXml` elements and structured document tag elements.

c. The standard states that the range specified by a pair of `customXmlInsRangeStart` and `customXmlInsRangeEnd` elements can overlap the range specified by another such pair of elements.

Word does not allow the range specified by a pair of `customXmlInsRangeStart` and `customXmlInsRangeEnd` elements to overlap the range specified by any other such pair of elements.

2.1.328 Part 4 Section 2.13.5.8, customXmlMoveFromRangeEnd (Custom XML Markup Move Source End)

For additional notes that apply to this portion of the standard, please see the notes for [sdt, §2.5.2.28\(a\)](#); [sdt, §2.5.2.29\(a\)](#); [sdt, §2.5.2.30\(a\)](#); [sdt, §2.5.2.31\(a\)](#); [comment, §2.13.4.2\(b, c\)](#); [cellDel, §2.13.5.1\(a\)](#); [oMathPara, §7.1.2.78\(a\)](#).

a. The standard says that multiple end elements with the same ID are ignored, but the subclause for `customXmlMoveFromRangeStart` specified that multiple end elements with the same id are matched in document order.

Word matches multiple end elements with the same ID in document order.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.329 Part 4 Section 2.13.5.9, customXmlMoveFromRangeStart (Custom XML Markup Move Source Start)

For additional notes that apply to this portion of the standard, please see the notes for [sdt, §2.5.2.28\(a\)](#); [sdt, §2.5.2.29\(a\)](#); [sdt, §2.5.2.30\(a\)](#); [sdt, §2.5.2.31\(a\)](#); [comment, §2.13.4.2\(b, c\)](#); [cellDel, §2.13.5.1\(a\)](#); [ins, §2.13.5.20\(b\)](#); [oMathPara, §7.1.2.78\(a\)](#).

a. The standard states that this element applies `moveFrom` to `customXml` elements.

Word uses this element to apply `moveFrom` to `customXml` elements and structured document tag elements.

b. The standard states that the range specified by a pair of `customXmlMoveFromRangeStart` and `customXmlMoveFromRangeEnd` elements can overlap the range specified by another such pair of elements.

Word does not allow the range specified by a pair of `customXmlMoveFromRangeStart` and `customXmlMoveFromRangeEnd` elements to overlap the range specified by any other such pair of elements.

c. *The standard allows customXML move tracking to begin inside, end inside, or contain an `oMathPara` element.*

Word has unpredictable results when customXML move tracking begins inside, ends inside, or contains an `oMathPara` element.

2.1.330 Part 4 Section 2.13.5.10, customXmlMoveToRangeEnd (Custom XML Markup Move Destination Location End)

For additional notes that apply to this portion of the standard, please see the notes for [sdt, §2.5.2.28\(a\)](#); [sdt, §2.5.2.29\(a\)](#); [sdt, §2.5.2.30\(a\)](#); [sdt, §2.5.2.31\(a\)](#); [comment, §2.13.4.2\(b\)](#); [cellDel, §2.13.5.1\(a\)](#); [oMathPara, §7.1.2.78\(a\)](#).

a. *The standard states that the `customXmlMoveToRangeEnd` element applies `moveTo` to `customXml` elements.*

Word uses this element to apply `moveTo` to `customXml` elements and structured document tag elements.

b. *The standard says that multiple end elements with the same ID are ignored, but the subclause for `customXmlMoveToRangeStart` specified that multiple end elements with the same ID are matched in document order.*

Word matches multiple end elements with the same ID in document order.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

c. *The standard says to ignore `customXmlMoveToRangeEnd` if it is not contained in a move source container.*

Word ignores `customXmlMoveToRangeEnd` if it is not contained in a move destination container.

2.1.331 Part 4 Section 2.13.5.11, customXmlMoveToRangeStart (Custom XML Markup Move Destination Location Start)

For additional notes that apply to this portion of the standard, please see the notes for [sdt, §2.5.2.28\(a\)](#); [sdt, §2.5.2.29\(a\)](#); [sdt, §2.5.2.30\(a\)](#); [sdt, §2.5.2.31\(a\)](#); [comment, §2.13.4.2\(b, c\)](#); [cellDel, §2.13.5.1\(a\)](#); [ins, §2.13.5.20\(b\)](#); [oMathPara, §7.1.2.78\(a\)](#).

a. *The standard states that the `customXmlMoveToRangeStart` element applies `moveTo` to `customXml` elements.*

Word uses this element to apply `moveTo` to `customXml` elements and structured document tag elements.

b. *The standard states that the range specified by a pair of `customXmlMoveToRangeStart` and `customXmlMoveToRangeEnd` elements can overlap the range specified by another such pair of elements.*

Word does not allow the range specified by a pair of `customXmlMoveToRangeStart` and `customXmlMoveToRangeEnd` elements to overlap the range specified by any other such pair of elements.

c. *The standard allows customXML move tracking to begin inside, end inside, or contain an oMathPara element.*

Word has unpredictable behavior when customXML move tracking begins inside, ends inside, or contains an oMathPara element.

d. *The standard says to ignore customXmlMoveToRangeStart if it is not contained in a move source container.*

Word ignores customXmlMoveToRangeStart if it is not contained in a move destination container.

2.1.332 Part 4 Section 2.13.5.12, del (Deleted Run Content)

For additional notes that apply to this portion of the standard, please see the notes for [customXml, §2.5.1.5\(a\)](#); [comment, §2.13.4.2\(b, c\)](#); [cellDel, §2.13.5.1\(a\)](#); [ins, §2.13.5.20\(b\)](#); [oMathPara, §7.1.2.78\(a\)](#).

a. *The standard allows nested deletions.*

Word does not support nested deletions.

2.1.333 Part 4 Section 2.13.5.13, del (Deleted Paragraph)

For additional notes that apply to this portion of the standard, please see the notes for [comment, §2.13.4.2\(c\)](#); [cellDel, §2.13.5.1\(a\)](#); [ins, §2.13.5.20\(b\)](#).

2.1.334 Part 4 Section 2.13.5.14, del (Deleted Table Row)

For additional notes that apply to this portion of the standard, please see the notes for [trPr, §2.7.5.10\(b\)](#); [trPr, §2.7.5.11\(a\)](#); [comment, §2.13.4.2\(c\)](#); [cellDel, §2.13.5.1\(a\)](#); [ins, §2.13.5.20\(b\)](#).

2.1.335 Part 4 Section 2.13.5.15, del (Deleted Math Control Character)

For additional notes that apply to this portion of the standard, please see the notes for [comment, §2.13.4.2\(c\)](#); [cellDel, §2.13.5.1\(a\)](#); [ins, §2.13.5.17\(a\)](#); [ins, §2.13.5.20\(b\)](#); [ctrlPr, §7.1.2.23\(b\)](#).

a. *The standard states that the rPr (Previous Run Properties) element is a valid child.*

Word allows the rPr (Run Properties) element, not the rPr (Previous Run Properties) element, to be a child.

b. *The standard states that the minOccurs value for the rPr child element is 1.*

Word does not require an occurrence of this element.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.336 Part 4 Section 2.13.5.16, ins (Inserted Table Row)

For additional notes that apply to this portion of the standard, please see the notes for [trPr, §2.7.5.10\(b\)](#); [trPr, §2.7.5.11\(a\)](#); [comment, §2.13.4.2\(c\)](#); [cellDel, §2.13.5.1\(a\)](#); [ins, §2.13.5.20\(b\)](#).

2.1.337 Part 4 Section 2.13.5.17, ins (Inserted Math Control Character)

For additional notes that apply to this portion of the standard, please see the notes for [comment, §2.13.4.2\(c\)](#); [cellDel, §2.13.5.1\(a\)](#); [del, §2.13.5.15\(a\)](#); [ins, §2.13.5.20\(b\)](#); [ctrlPr, §7.1.2.23\(b\)](#).

- a. *The standard does not state that the del element is a valid child.*

Word allows the del element to be a child when a math control character is part of both a tracked insertion and tracked deletion.

- b. *The standard states that the rPr (Previous Run Properties) element is a valid child.*

Word allows the rPr (Run Properties) element, not the rPr (Previous Run Properties) element, to be a child.

- c. *The standard states that the minOccurs value for the rPr child element is 1.*

Word does not require an occurrence of this element.

2.1.338 Part 4 Section 2.13.5.18, ins (Inserted Paragraph)

For additional notes that apply to this portion of the standard, please see the notes for [comment, §2.13.4.2\(c\)](#); [cellDel, §2.13.5.1\(a\)](#); [ins, §2.13.5.20\(b\)](#).

- a. *The standard states that this element specifies that a paragraph mark shall be treated as deleted (that is, the contents of this paragraph are no longer delimited by this paragraph mark, and are combined with the following paragraph).*

Word uses this element to specify that the paragraph mark shall be treated as inserted (that is, the contents of this paragraph used to be combined with the following paragraph but were moved into a new paragraph).

2.1.339 Part 4 Section 2.13.5.19, ins (Inserted Numbering Properties)

For additional notes that apply to this portion of the standard, please see the notes for [comment, §2.13.4.2\(c\)](#); [cellDel, §2.13.5.1\(a\)](#); [ins, §2.13.5.20\(b\)](#).

2.1.340 Part 4 Section 2.13.5.20, ins (Inserted Run Content)

For additional notes that apply to this portion of the standard, please see the notes for [customXml, §2.5.1.5\(a\)](#); [comment, §2.13.4.2\(b, c\)](#); [cellDel, §2.13.5.1\(a\)](#); [oMathPara, §7.1.2.78\(a\)](#).

- a. *The standard allows nested insertions.*

Word does not support nested insertions.

- b. *The standard states that the author attribute is required, but the prose defines its behaviour when omitted.*

Word behaves according to schema - the author attribute is required.

2.1.341 Part 4 Section 2.13.5.21, moveFrom (Move Source Run Content)

For additional notes that apply to this portion of the standard, please see the notes for [customXml, §2.5.1.5\(a\)](#); [comment, §2.13.4.2\(b, c\)](#); [cellDel, §2.13.5.1\(a\)](#); [ins, §2.13.5.20\(b\)](#); [oMathPara, §7.1.2.78\(a\)](#).

- a. *The standard allows moveFrom to be nested.*

Word does not support nesting moveFrom.

- b. *The standard allows tracked moves in math objects and functions.*

Word treats tracked moves (moveFrom, moveTo) in math objects and functions as insertions and deletions.

2.1.342 Part 4 Section 2.13.5.22, moveFrom (Move Source Paragraph)

For additional notes that apply to this portion of the standard, please see the notes for [comment, §2.13.4.2\(c\)](#); [cellDel, §2.13.5.1\(a\)](#); [ins, §2.13.5.20\(b\)](#).

- a. *The standard specifies semantics for this element.*

Word ignores this element.

2.1.343 Part 4 Section 2.13.5.23, moveFromRangeEnd (Move Source Location Container - End)

For additional notes that apply to this portion of the standard, please see the notes for [sdt, §2.5.2.28\(a\)](#); [sdt, §2.5.2.29\(a\)](#); [sdt, §2.5.2.30\(a\)](#); [sdt, §2.5.2.31\(a\)](#); [comment, §2.13.4.2\(b\)](#); [cellDel, §2.13.5.1\(a\)](#); [oMathPara, §7.1.2.78\(a\)](#).

2.1.344 Part 4 Section 2.13.5.24, moveFromRangeStart (Move Source Location Container - Start)

For additional notes that apply to this portion of the standard, please see the notes for [sdt, §2.5.2.28\(a\)](#); [sdt, §2.5.2.29\(a\)](#); [sdt, §2.5.2.30\(a\)](#); [sdt, §2.5.2.31\(a\)](#); [comment, §2.13.4.2\(b\)](#); [cellDel, §2.13.5.1\(a\)](#); [bookmarkStart, §2.13.6.2\(a-d\)](#); [oMathPara, §7.1.2.78\(a\)](#).

- a. *The standard allows an unbounded number of moveFrom/moveTo ranges.*

Word will not open a document with too many moveFrom/moveTo ranges. If the uiCompat97to2003 is set, the maximum is 32,751; otherwise the maximum is 2,147,483,647.

2.1.345 Part 4 Section 2.13.5.25, moveTo (Move Destination Paragraph)

For additional notes that apply to this portion of the standard, please see the notes for [comment, §2.13.4.2\(c\)](#); [cellDel, §2.13.5.1\(a\)](#); [ins, §2.13.5.20\(b\)](#).

- a. *The standard specifies semantics for this element.*

Word ignores this element.

2.1.346 Part 4 Section 2.13.5.26, moveTo (Move Destination Run Content)

For additional notes that apply to this portion of the standard, please see the notes for [customXml, §2.5.1.5\(a\)](#); [comment, §2.13.4.2\(b, c\)](#); [cellDel, §2.13.5.1\(a\)](#); [ins, §2.13.5.20\(b\)](#); [oMathPara, §7.1.2.78\(a\)](#).

- a. *The standard allows the moveTo element to be a descendant of another moveTo element.*

Word does not allow the moveTo element to be a descendant of another moveTo element.

2.1.347 Part 4 Section 2.13.5.27, moveToRangeEnd (Move Destination Location Container - End)

For additional notes that apply to this portion of the standard, please see the notes for [sdt, §2.5.2.28\(a\)](#); [sdt, §2.5.2.29\(a\)](#); [sdt, §2.5.2.30\(a\)](#); [sdt, §2.5.2.31\(a\)](#); [comment, §2.13.4.2\(b\)](#); [cellDel, §2.13.5.1\(a\)](#); [oMathPara, §7.1.2.78\(a\)](#).

2.1.348 Part 4 Section 2.13.5.28, moveToRangeStart (Move Destination Location Container - Start)

For additional notes that apply to this portion of the standard, please see the notes for [sdt, §2.5.2.28\(a\)](#); [sdt, §2.5.2.29\(a\)](#); [sdt, §2.5.2.30\(a\)](#); [sdt, §2.5.2.31\(a\)](#); [comment, §2.13.4.2\(b\)](#); [cellDel, §2.13.5.1\(a\)](#); [bookmarkStart, §2.13.6.2\(a-d\)](#); [oMathPara, §7.1.2.78\(a\)](#).

2.1.349 Part 4 Section 2.13.5.29, numberingChange (Previous Numbering Field Properties)

For additional notes that apply to this portion of the standard, please see the notes for [comment, §2.13.4.2\(c\)](#); [cellDel, §2.13.5.1\(a\)](#); [ins, §2.13.5.20\(b\)](#); [numberingChange, §2.13.5.30\(a\)](#).

- a. The standard allows any length string for the original attribute.

Word only allows strings of length 15 at most for the original attribute.

2.1.350 Part 4 Section 2.13.5.30, numberingChange (Previous Paragraph Numbering Properties)

For additional notes that apply to this portion of the standard, please see the notes for [comment, §2.13.4.2\(c\)](#); [cellDel, §2.13.5.1\(a\)](#); [ins, §2.13.5.20\(b\)](#).

- a. The standard states that the original attribute is optional.

Word requires this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

- b. The standard states that the numbering level in the original attribute starts with %.

In Word, the value of **original** is represented as separate numbering level definitions defined as follows:

```
<[numbering prefix]#[numbering level]:[nfc value]:[numbering format]:[separator]>[repeat if more than one level]
```

where:

numbering prefix – Optional text which should precede the number.

numbering level – The level for which the numbering definition is defined.

nfc value – The value of the numbering style at the specific numbering level.

numbering format – The nfc value of the numbering format, as referenced in the following table.

`separator` – The separator used to separate the numbering level definitions.

If the **numbering** prefix or `separator` includes a pair of consecutive % characters, then that pair of characters shall be treated as a single % character rather than the start of a new `numbering` level.

The total length of **original**, omitting all instances of `nfc value` and `numbering format` and all ':' characters used to separate the pieces of the number level definitions, shall be at most 31.

The numbering format values are mapped as follows:

| nfc Value | ST_NumberFormat enumeration equivalent |
|------------------|---|
| 0 | <i>decimal</i> |
| 1 | <i>upperRoman</i> |
| 2 | <i>lowerRoman</i> |
| 3 | <i>upperLetter</i> |
| 4 | <i>lowerLetter</i> |
| 5 | <i>ordinal</i> |
| 6 | <i>cardinalText</i> |
| 7 | <i>ordinalText</i> |
| 8 | <i>hex</i> |
| 9 | <i>chicago</i> |
| 10 | <i>ideographDigital</i> |
| 11 | <i>japaneseCounting</i> |
| 12 | <i>Aiueo</i> |
| 13 | <i>Iroha</i> |
| 14 | <i>decimalFullWidth</i> |
| 15 | <i>decimalHalfWidth</i> |
| 16 | <i>japaneseLegal</i> |
| 17 | <i>japaneseDigitalTenThousand</i> |
| 18 | <i>decimalEnclosedCircle</i> |
| 19 | <i>decimalFullWidth2</i> |
| 20 | <i>aiueoFullWidth</i> |
| 21 | <i>irohaFullWidth</i> |
| 22 | <i>decimalZero</i> |
| 23 | <i>bullet</i> |
| 24 | <i>ganada</i> |

| nfc Value | ST_NumberFormat enumeration equivalent |
|------------------|---|
| 25 | <i>chosung</i> |
| 26 | <i>decimalEnclosedFullstop</i> |
| 27 | <i>decimalEnclosedParen</i> |
| 28 | <i>decimalEnclosedCircleChinese</i> |
| 29 | <i>ideographEnclosedCircle</i> |
| 30 | <i>ideographTraditional</i> |
| 31 | <i>ideographZodiac</i> |
| 32 | <i>ideographZodiacTraditional</i> |
| 33 | <i>taiwaneseCounting</i> |
| 34 | <i>ideographLegalTraditional</i> |
| 35 | <i>taiwaneseCountingThousand</i> |
| 36 | <i>taiwaneseDigital</i> |
| 37 | <i>chineseCounting</i> |
| 38 | <i>chineseLegalSimplified</i> |
| 39 | <i>chineseCountingThousand</i> |
| 40 | Application-defined. May be ignored. |
| 41 | <i>koreanDigital</i> |
| 42 | <i>koreanCounting</i> |
| 43 | <i>koreanLegal</i> |
| 44 | <i>koreanDigital2</i> |
| 45 | <i>hebrew1</i> |
| 46 | <i>arabicAlpha</i> |
| 47 | <i>hebrew2</i> |
| 48 | <i>arabicAbjad</i> |
| 49 | <i>hindiVowels</i> |
| 50 | <i>hindiConsonants</i> |
| 51 | <i>hindiNumbers</i> |
| 52 | <i>hindiCounting</i> |
| 53 | <i>thaiLetters</i> |
| 54 | <i>thaiNumbers</i> |

| nfc Value | ST_NumberFormat enumeration equivalent |
|--------------|--|
| 55 | thaiCounting |
| 56 | vietnameseCounting |
| 57 | numberInDash |
| 58 | russianLower |
| 59 | russianUpper |
| 60 or higher | Application-defined. May be ignored. |

c. *The standard does not state how to interpret a pair of consecutive percent characters in the value of the original attribute.*

Word treats a pair of consecutive percent characters in this attribute as a single percent character.

d. *The standard does not restrict the length of the original attribute.*

Word requires that the total length of original, omitting all instances of nfc_value and numbering_format and all ':' characters used to separate the pieces of the number level definitions, shall be at most 31 characters.

2.1.351 Part 4 Section 2.13.5.31, pPrChange (Revision Information for Paragraph Properties)

For additional notes that apply to this portion of the standard, please see the notes for [pPr, §2.7.4.2\(a\)](#); [pPr, §2.9.24\(a\)](#); [comment, §2.13.4.2\(c\)](#); [cellDel, §2.13.5.1\(a\)](#); [ins, §2.13.5.20\(b\)](#).

2.1.352 Part 4 Section 2.13.5.32, rPrChange (Revision Information for Run Properties)

For additional notes that apply to this portion of the standard, please see the notes for [rPr, §2.7.4.4\(a\)](#); [rPr, §2.7.5.2\(a\)](#); [rPr, §2.9.26\(a\)](#); [comment, §2.13.4.2\(c\)](#); [cellDel, §2.13.5.1\(a\)](#); [ins, §2.13.5.20\(b\)](#).

2.1.353 Part 4 Section 2.13.5.33, rPrChange (Revision Information for Run Properties on the Paragraph Mark)

For additional notes that apply to this portion of the standard, please see the notes for [comment, §2.13.4.2\(c\)](#); [cellDel, §2.13.5.1\(a\)](#); [ins, §2.13.5.20\(b\)](#).

2.1.354 Part 4 Section 2.13.5.34, sectPrChange (Revision Information for Section Properties)

For additional notes that apply to this portion of the standard, please see the notes for [comment, §2.13.4.2\(c\)](#); [cellDel, §2.13.5.1\(a\)](#); [ins, §2.13.5.20\(b\)](#).

a. *The standard states that the previous section properties are expressed as a complete set of properties.*

Word interprets previous section properties as relative to the current set of properties.

2.1.355 Part 4 Section 2.13.5.35, tblGridChange (Revision Information for Table Grid Column Definitions)

For additional notes that apply to this portion of the standard, please see the notes for [cellDel, §2.13.5.1\(a\)](#).

2.1.356 Part 4 Section 2.13.5.36, tblPrChange (Revision Information for Table Properties)

For additional notes that apply to this portion of the standard, please see the notes for [comment, §2.13.4.2\(c\)](#); [cellDel, §2.13.5.1\(a\)](#); [ins, §2.13.5.20\(b\)](#).

2.1.357 Part 4 Section 2.13.5.37, tblPrExChange (Revision Information for Table-Level Property Exceptions)

For additional notes that apply to this portion of the standard, please see the notes for [comment, §2.13.4.2\(c\)](#); [cellDel, §2.13.5.1\(a\)](#); [ins, §2.13.5.20\(b\)](#).

2.1.358 Part 4 Section 2.13.5.38, tcPrChange (Revision Information for Table Cell Properties)

For additional notes that apply to this portion of the standard, please see the notes for [tcPr, §2.7.5.8\(a\)](#); [tcPr, §2.7.5.9\(b\)](#); [comment, §2.13.4.2\(c\)](#); [cellDel, §2.13.5.1\(a\)](#); [ins, §2.13.5.20\(b\)](#).

2.1.359 Part 4 Section 2.13.5.39, trPrChange (Revision Information for Table Row Properties)

For additional notes that apply to this portion of the standard, please see the notes for [trPr, §2.7.5.10\(b\)](#); [trPr, §2.7.5.11\(a\)](#); [comment, §2.13.4.2\(c\)](#); [cellDel, §2.13.5.1\(a\)](#); [ins, §2.13.5.20\(b\)](#).

- a. *The standard states that table styles can contain row property revisions.*

Word does not allow row property revisions in table styles.

2.1.360 Part 4 Section 2.13.6, Bookmarks

- a. *The standard allows a bookmark to begin inside a math object and end outside that object or vice versa.*

Word does not allow a bookmark to begin inside a math object and end outside that object or vice versa.

- b. *The standard does not specify a maximum number of bookmarks allowed in a document.*

Word fails to open the file if it has too many bookmarks (more than 16380 when the uiCompat97to2003 element is present, more than 2147483647 otherwise).

2.1.361 Part 4 Section 2.13.6.1, bookmarkEnd (Bookmark End)

For additional notes that apply to this portion of the standard, please see the notes for [sdt, §2.5.2.28\(a\)](#); [sdt, §2.5.2.29\(a\)](#); [sdt, §2.5.2.30\(a\)](#); [sdt, §2.5.2.31\(a\)](#); [cellDel, §2.13.5.1\(a\)](#); [oMathPara, §7.1.2.78\(a\)](#).

2.1.362 Part 4 Section 2.13.6.2, bookmarkStart (Bookmark Start)

For additional notes that apply to this portion of the standard, please see the notes for [sdt, §2.5.2.28\(a\)](#); [sdt, §2.5.2.29\(a\)](#); [sdt, §2.5.2.30\(a\)](#); [sdt, §2.5.2.31\(a\)](#); [cellDel, §2.13.5.1\(a\)](#); [oMathPara, §7.1.2.78\(a\)](#).

- a. *The standard allows any integer for the colFirst and colLast attributes.*

Word only allows non-negative 32-bit integers for the colFirst and colLast attributes.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

- b. *The standard says that if colFirst or colLast is greater than the number of columns in the table or colFirst is greater than colLast, then colFirst and colLast should be ignored.*

In Word, if colFirst is greater than colLast, then colFirst behaves as if it took on the value of colLast and if colLast is greater than the number of columns in the table, the bookmark includes no columns.

- c. *The standard allows any length string for the name attribute.*

Word only allows strings of length at most 40 for the name attribute.

- d. *The standard says that if multiple bookmarks have the same name, the first bookmark shall be maintained, and all subsequent bookmarks should be ignored.*

In Word, if multiple bookmarks have the same name, the last bookmark is maintained and all others are ignored.

2.1.363 Part 4 Section 2.13.7.1, permEnd (Range Permission End)

For additional notes that apply to this portion of the standard, please see the notes for [oMathPara, §7.1.2.78\(a\)](#).

- a. *The standard allows any string for the id attribute.*

Word only allows 32-bit integers for the id attribute.

- b. *The standard allows an unbounded number of range permissions.*

Word will not open a file with too many range permissions (32752 if the uiCompat97to2003 element is present, 2147483647 otherwise).

2.1.364 Part 4 Section 2.13.7.2, permStart (Range Permission Start)

For additional notes that apply to this portion of the standard, please see the notes for [permEnd, §2.13.7.1\(a\)](#).

- a. *The standard says that if colFirst or colLast is greater than the number of columns in table, both attributes should be ignored.*

Word does not ignore the attributes and instead behaves unpredictably.

- b. *The standard does not specify behavior when both the ed and edGrp attributes are present.*

In Word, if the ed attribute is present, the edGrp attribute will be ignored.

- c. *The standard allows range permissions inside math objects and spanning parts of math objects.*

If a range permission is inside a math object or includes only part of a math object, then Word exhibits unpredictable behavior and may move or duplicate the range permission.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.365 Part 4 Section 2.13.8.1, proofErr (Proofing Error Anchor)

For additional notes that apply to this portion of the standard, please see the notes for [oMathPara. §7.1.2.78\(a\)](#).

2.1.366 Part 4 Section 2.14, Mail Merge

a. *The standard says that the odso element in settings.xml contains information about whether to include or exclude records.*

In Word, information about whether to include or exclude records is stored in recipientData.xml.

b. *The standard says the odso element contains information about how to map data source columns to MERGEFIELD fields.*

In Word, the odso element contains information about how to map data source columns to a set of predefined mail merge fields.

2.1.367 Part 4 Section 2.14.2, activeRecord (Record Currently Displayed In Merged Document)

a. *The standard says that if the val attribute is greater than the number of records in the specified external data source, the val attribute is treated as if it were 1.*

If the val attribute greater than the number of records in the specified external data source, Word fails to open the file.

b. *The standard says that data is populated in merge fields based on mappings defined by the fieldMapData elements.*

In Word, merge fields directly reference data columns in the data source, not fieldMapData mappings.

2.1.368 Part 4 Section 2.14.4, checkErrors (Mail Merge Error Reporting Setting)

a. *The standard says that apps can define their own behaviors for values other than 1, 2, and 3.*

Word fails to roundtrip any value other than 1, 2, and 3.

2.1.369 Part 4 Section 2.14.5, colDelim (Column Delimiter for Data Source)

a. *The standard states that the values of the val attribute are defined by the XML Schema integer datatype.*

Word defines the values of this attribute with the XML Schema unsignedInt datatype.

2.1.370 Part 4 Section 2.14.6, column (Index of Column Containing Unique Values for Record)

a. *The standard states that the values of the val attribute are defined by the XML Schema integer datatype.*

Word defines the values of this attribute with the XML Schema unsignedInt datatype.

2.1.371 Part 4 Section 2.14.7, column (Index of Column Being Mapped)

a. *The standard states that the values of the val attribute are defined by the XML Schema integer datatype.*

Word defines the values of this attribute with the XML Schema unsignedInt datatype.

2.1.372 Part 4 Section 2.14.9, dataSource (Data Source File Path)

For additional notes that apply to this portion of the standard, please see the notes for [attachedTemplate, §2.15.1.6\(a\)](#).

2.1.373 Part 4 Section 2.14.12, doNotSuppressBlankLines (Remove Blank Lines from Merged Documents)

a. *The standard specifies that when this element is present, the merged documents which are generated from the mail merge shall not have any blank lines removed.*

If this element is present with a val attribute value of false, Word will stop trying to connect to the external data source.

2.1.374 Part 4 Section 2.14.13, dynamicAddress (Use Country-Based Address Field Ordering)

a. *The standard says the default value of dynamicAddress is on.*

In Word, the default value of dynamicAddress is off.

2.1.375 Part 4 Section 2.14.14, fHdr (First Row of Data Source Contains Column Names)

a. *The standard says this element specifies the first row of data in the specified external data source should be treated as a header row.*

Word ignores this element for all types of external data sources except Excel.

2.1.376 Part 4 Section 2.14.15, fieldMapData (External Data Source to Merge Field Mapping)

a. *The standard says the dynamicAddress element must appear in the fieldMapData after the lid element.*

Word sometimes writes the dynamicAddress element before the lid element.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

b. *The standard states that the fieldMapData element is used to map from mappedName to data source columns.*

Word uses 30 pre-defined mail merge fields as follows:

Unique

CourtesyTitle

FirstName
MiddleName
LastName
Suffix
Nickname
JobTitle
Company
Address1
Address2
City
State
PostalCode
CountryorRegion
BusinessPhone
BusinessFax
HomePhone
HomeFax
EmailAddress
WebPage
SpouseCourtesyTitle
SpouseFirstName
SpouseMiddleName
SpouseLastName
SpouseNickname
RubyFirstName
RubyLastName
Address3
Department

Word ignores the **mappedName** child element of a **fieldMapData** element and maps the mail merge fields according to the order of the fieldMapData elements inside the **odso** element. Specifically, the first **fieldMapData** element inside the **odso** element corresponds to the *Unique* field, second **fieldMapData** element corresponds to *CourtesyTitle* field, and so on.

c. *The standard says that this element maps MERGEFIELD fields to data source columns.*

In Word, this element maps predefined fields to data source columns.

2.1.377 Part 4 Section 2.14.16, headerSource (Header Definition File Path)

For additional notes that apply to this portion of the standard, please see the notes for [attachedTemplate, §2.15.1.6\(a\)](#).

a. *The standard specifies the headerSource element.*

Word fails to open WordprocessingML documents in which this element is present.

2.1.378 Part 4 Section 2.14.17, lid (Merge Field Name Language ID)

a. *The standard says the val attribute specifies either an ISO 639-1 letter code or 4 digit hexadecimal code for a specific language.*

Word does not understand 4 digit hexadecimal codes for languages when stored in this attribute.

2.1.379 Part 4 Section 2.14.18, linkToQuery (Query Contains Link to External Query File)

a. *The standard says this element specifies that the query string contains a reference to an external query file that contains the actual query data to be used against the specified external data source for the mail merge.*

Word saves this element irrespective of whether the query string actually contains a reference to an external query file or not, and subsequently ignores the element.

2.1.380 Part 4 Section 2.14.20, mailMerge (Mail Merge Settings)

a. *The standard states that the minOccurs value for the mainDocumentType child element is 1.*

Word does not require an occurrence of this element.

2.1.381 Part 4 Section 2.14.23, mappedName (Predefined Merge Field Name)

a. *The standard says that this element is used to map MERGEFIELD fields to data source columns.*

In Word, this element is used to map predefined mail merge fields to data source columns.

2.1.382 Part 4 Section 2.14.24, name (Data Source Name for Column)

a. *The standard says this element is used to look up a column name that is used to determine which column to map from the data source, but it also specifies the same meaning for the column element.*

In Word, the name element caches the value of the name of this column in the data source at the time when the connection was established, but the column element is used to determine which column to map from the data source.

b. *The standard says that if this element is omitted, no data source column name is provided for the current column.*

In Word, if this element is omitted, no data source column name is provided for the current column mapping.

2.1.383 Part 4 Section 2.14.25, odso (Office Data Source Object Settings)

- a. *The standard states that the maxOccurs value for the recipientData child element is unbounded.*

Word limits the occurrences of this element to 1.

- b. *The standard says that the odso element provides information about mapping to MERGEFIELD fields.*

In Word, the odso element provides information about mappings to built-in mail merge data fields, not MERGEFIELD fields.

2.1.384 Part 4 Section 2.14.26, query (Query For Data Source Records To Merge)

- a. *The standard does not restrict the SQL statements that may be used.*

Word does not allow SQL statements that attempt to modify the data source.

2.1.385 Part 4 Section 2.14.27, recipientData (Reference to Inclusion/Exclusion Data for Data Source)

For additional notes that apply to this portion of the standard, please see the notes for [attachedTemplate, §2.15.1.6\(a\)](#).

- a. *The standard requires relationships specified by this element to be of type <http://schemas.openxmlformats.org/officeDocument/2006/mailMergeRecipientData>.*

Word expects relationships specified by this element to be of type <http://schemas.openxmlformats.org/officeDocument/2006/relationships/recipientData>.

2.1.386 Part 4 Section 2.14.30, src (ODSO Data Source File Path)

For additional notes that apply to this portion of the standard, please see the notes for [attachedTemplate, §2.15.1.6\(a\)](#).

- a. *The standard specifies that this element is used only under certain conditions.*

Word does not use this element under any conditions.

2.1.387 Part 4 Section 2.14.31, table (Data Source Table Name)

- a. *The standard says that this element specifies which table in a data source is being used.*

Word uses this element only when the query element is omitted.

2.1.388 Part 4 Section 2.14.34, udl (UDL Connection String)

- a. *The standard specifies conditions under which the udl connection string is used.*

Word does not use the udl connection string.

2.1.389 Part 4 Section 2.14.35, uniqueTag (Unique Value for Record)

a. *The standard does not define the contents of this element.*

Word defines this element to contain a val attribute that is defined by the XML Schema base64Binary datatype.

b. *The standard says that this element is used to maintain a relationship between the records within an external data source and a given merged WordprocessingML document.*

Word uses this element to maintain a relationship between the records within an external data source and a given source WordprocessingML document.

c. *The standard does not state how this element should be populated when the column containing unique data for a record is empty.*

Word computes the unique tag, when empty, to be a base64-encoded value using the following algorithm:

Utility function 1:

```
#define nPrimeLast 4294967291
__int32 LHashMM( __int32 l, __int32 dl )
{
    l = 131 * l + dl;

    if (l >= nPrimeLast) {
        l -= nPrimeLast;
    }

    return l;
}
```

Utility function 2:

```
__int32 LGetHashWz(const WCHAR *wzText)
{
    int cch = lstrlen(wzText);
    __int32 lhash = 0L;

    for (int i = 0; i < cch; i++) {
        lhash = LHashMM(lhash, wzText[i]);
    }

    return lhash;
}
```

Utility function 3:

```
__int32 DwRowHash(thisRow)
{
    __int32 lwHash = 0L;
    for(int i = 0; i < TotalNumberOfColumnsInTheDataSource; i++) {
        Retrieve the value in the i-th column of thisRow as a Unicode String wzData;
        __int32 l = LGetHashWz(wzData);
        if(l) {
```

```

        lWHash = LHashMM(lWHash, 1);
    }
}
return lWHash;
}

```

Unique tag computation algorithm:

```

WCHAR wzUniqueTag[64] = {0};

*((__int32*) wzUniqueTag) = DwRowHash(the_row_containing_this_record);

return the wzUniqueTag as the uniqueTag;

```

2.1.390 Part 4 Section 2.15.1.1, activeWritingStyle (Grammar Checking Settings)

a. *The standard states that the lang attribute specifies the language of the engine used to perform the grammatical content checking.*

Word ignores the activeWritingStyle element if the lang attribute specifies an unknown locale.

b. *The standard states that the dllVersion attribute can be any integer value.*

Word restricts this attribute to a 32-bit unsigned integer when the nICheck attribute value is on, and a 16-bit unsigned integer when the nICheck attribute value is off.

c. *The standard states that the values of the vendorID attribute are defined by the XML Schema integer datatype.*

Word defines this attribute with the XML Schema int datatype, with a minimum value of 0.

d. *The standard does not state a default value for the nICheck attribute.*

Word uses off as the default value for the nICheck attribute.

e. *The standard states that if an application reads these settings and does not understand the value of appName, then its settings may be ignored and the application's default settings used instead.*

Word only understands an appName attribute value of MSWord.

2.1.391 Part 4 Section 2.15.1.3, alwaysMergeEmptyNamespace (Do Not Mark Custom XML Elements With No Namespace As Invalid)

a. *The standard states that if this element is not present, then the custom XML markup that has no associated namespace shall be treated as an error.*

Word uses a default value of true for the val attribute of this element when no schemas are attached to the document using the attachedSchema element and no custom XML markup with an associated namespace appears in the document.

b. *The standard states that if this element is not present, then the custom XML markup that has no associated namespace shall be moved into a special error namespace when the document is opened.*

Word does not move the custom XML markup into an error namespace if the alwaysMergeEmptyNamespace element is not present.

2.1.392 Part 4 Section 2.15.1.6, attachedTemplate (Attached Document Template)

- a. *The standard states that the id attribute specifies the relationship that shall have the type required by the parent element, yet a relationship type for the attachedTemplate element is not listed.*

Word requires

<http://schemas.openxmlformats.org/officeDocument/2006/relationships/attachedTemplate> as the relationship type for the attachedTemplate element, as specified in Office Open XML Fundamentals [ECMA-376].

- b. *The standard states that this element's val attribute shall contain the file path of the associated document template.*

Word does not support a val attribute for the attachedTemplate element. The file path for the associated document template is determined by evaluating the relationship ID on this element.

2.1.393 Part 4 Section 2.15.1.7, autoCaption (Single Automatic Captioning Setting)

- a. *The standard places no restrictions on the conditions under which this element is to be used.*

Word only reads this element when it is stored within the default document template.

- b. *The standard states that the name attribute specifies a unique identifier for types of objects to be automatically captioned.*

Word writes and expects wfwTables for Microsoft Word Tables, and the key name of the OLE object for OLE objects (the key name is stored in the Windows registry under HKEY_CLASSES_ROOT).

- c. *The standard states that the name attribute and the caption attribute can contain a string of unlimited length.*

Word limits these values to 255 characters.

2.1.394 Part 4 Section 2.15.1.8, autoCaptions (Automatic Captioning Settings)

- a. *The standard does not state that this element will be ignored under certain circumstances.*

Word ignores this element unless it is stored within its default document template.

2.1.395 Part 4 Section 2.15.1.9, autoFormatOverride (Allow Automatic Formatting to Override Formatting Protection Settings)

- a. *The standard states that the val attribute specifies that automatic formatting behavior shall be applied regardless of the formatting restrictions in place.*

Word ignores this element.

2.1.396 Part 4 Section 2.15.1.11, bookFoldPrinting (Book Fold Printing)

- a. *The standard says book fold printing divides the page in half vertically with two left margins emanating from the bisector of the page, and two right margins instantiated at the left and right side of the page.*

Word divides the page in half vertically with two right margins emanating from the bisector of the page, and two left margins instantiated at the left and right side of the page.

2.1.397 Part 4 Section 2.15.1.12, bookFoldPrintingSheets (Number of Pages Per Booklet)

a. *The standard states that if this element is omitted, then default behavior shall be to print the document on a single sheet.*

In Word, if this element is omitted, default behavior is to include all the pages of the document in a single booklet.

b. *The standard states that the values of the val attribute are defined by the XML Schema integer datatype.*

Word defines the values of this attribute with the XML Schema short datatype, with a minimum value of 0.


2.1.398 Part 4 Section 2.15.1.13, bookFoldRevPrinting (Reverse Book Fold Printing)

a. *The standard says this element divides the page in half vertically with two left margins emanating from the bisector of the page, and two right margins instantiated at the left and right side of the page.*

In Word, this element divides the page in half vertically with two right margins emanating from the bisector of the page, and left margins instantiated at the left and right side of the page.

b. *The standard describes through example the output of printed pages with page 3 printed after page 2.*

Word prints page 3 on the left side of the second printed signature to allow the construction of a printed booklet. This can be visualized as follows:



2.1.399 Part 4 Section 2.15.1.16, caption (Single Caption Type Definition)

- a. *The standard allows strings of unbounded length for the name attribute.*

Word allows strings of length at most 255 for the name attribute.

- b. *In the standard, the heading attribute is described with specific semantics for values 1 through 9.*

If the heading attribute is present, Word reads the value as zero and incorrectly displays autogenerated captions.

- c. *The standard says the noLabel attribute controls whether labels are included in automatically generated captions.*

Word ignores the noLabel attribute and instead uses the value of the chapNum attribute.

2.1.400 Part 4 Section 2.15.1.17, captions (Caption Settings)

- a. *The standard states that this element could be used by other documents besides the default template.*

Word only reads this element when it is stored in its default document template.

2.1.401 Part 4 Section 2.15.1.19, clickAndTypeStyle (Paragraph Style Applied to Automatically Generated Paragraphs)

For additional notes that apply to this portion of the standard, please see the notes for [numStyleLink, §2.9.22\(a\)](#).

- a. *The standard does not limit the length of the value of the val attribute.*

Word restricts the value of this attribute to be at most 253 characters.

2.1.402 Part 4 Section 2.15.1.20, clrSchemeMapping (Theme Color Mappings)

- a. *The standard states that if the t1 attribute is omitted, then the t1 theme color shall be used.*

Word uses the dark1 theme color, as no t1 theme color exists in the enumeration.

- b. *The standard says that if the t2 attribute is omitted, then the t2 theme color shall be used.*

Word uses the dark2 theme color, as no t2 theme color exists in the enumeration.

2.1.403 Part 4 Section 2.15.1.21, consecutiveHyphenLimit (Maximum Number of Consecutively Hyphenated Lines)

- a. *The standard states that the values of the val attribute are defined by the XML Schema integer datatype.*

Word defines the values of this attribute with the XML Schema unsignedShort datatype.

2.1.404 Part 4 Section 2.15.1.22, decimalSymbol (Radix Point for Field Code Evaluation)

- a. *The standard states that this element specifies the character that shall be interpreted as the radix point symbol.*

Word ignores this element and its value and always reads the system locale settings to get the value of the radix point symbol.

2.1.405 Part 4 Section 2.15.1.23, defaultTableStyle (Default Table Style for Newly Inserted Tables)

For additional notes that apply to this portion of the standard, please see the notes for [numStyleLink, §2.9.22\(a\)](#).

- a. *The standard does not limit the length of the value of the val attribute.*

Word restricts the value of this attribute to be at most 253 characters.

2.1.406 Part 4 Section 2.15.1.24, defaultTabStop (Distance Between Automatic Tab Stops)

- a. *The standard states that the values of the val attribute are defined by the XML Schema unsignedLong datatype.*

Word defines the values of this attribute with the XML Schema short datatype, with a minimum value of 0.

2.1.407 Part 4 Section 2.15.1.26, displayHorizontalDrawingGridEvery (Distance between Vertical Gridlines)

- a. *The standard says this element controls the number of horizontal grid units between horizontal grid lines.*

In Word, this element controls the number of horizontal grid units between vertical grid lines.

- b. *The standard states that the values of the val attribute are defined by the XML Schema integer datatype.*

Word restricts the value of this attribute to be at least 0 and at most 127.

2.1.408 Part 4 Section 2.15.1.27, displayVerticalDrawingGridEvery (Distance between Horizontal Gridlines)

- a. *The standard says this element controls the number of vertical grid units between vertical grid lines.*

In Word, this element controls the number of vertical grid units between horizontal grid lines.

- b. *The standard states that, if this element is omitted, no vertical gridlines are displayed.*

In Word, if this element is omitted, horizontal gridlines are displayed for every vertical grid unit.

- c. *The standard states that the values of the val attribute are defined by the XML Schema integer datatype.*

Word restricts the value of this attribute to be at least 0 and at most 127.

2.1.409 Part 4 Section 2.15.1.28, documentProtection (Document Editing Restrictions)

a. *The standard states that the reversed byte order of the legacy hash key will be hashed as defined by the attribute values.*

In Word, an additional third stage is added to the process of hashing and storing a user supplied password. In this third stage, the reversed byte order legacy hash from the second stage shall be converted to Unicode hex string representation [Example: If the single byte string 7EEDCE64 is converted to Unicode hex string it will be represented in memory as the following byte stream: 37 00 45 00 45 00 44 00 43 00 45 00 36 00 34 00. end example], and that value shall be hashed as defined by the attribute values.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

b. *In the standard, the algIdExt attribute specifies that a cryptographic algorithm has been used to generate the document hash value.*

Word requires that the cryptProviderTypeExt attribute be specified if the algIdExt attribute is used.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

c. *The standard states that the values of the algIdExtSource attribute are defined by the ST_String simple type.*

Word restricts the value of this attribute to be wincrypt.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

d. *In the standard, the cryptProviderTypeExtSource attribute of the documentProtection element allows for a string to specify the application that defined the provider type.*

Word requires that the cryptProviderTypeExtSource attribute value be specified as wincrypt.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

e. *In the standard, the hash attribute describes the hash value for the password stored within the document, but the algorithm for generating the hash value is not specified.*

The hash value is the Base64 encoded representation of the binary hashing algorithm output, which is calculated as follows:

$$H[\text{init}] = H(\text{password}, \text{salt})$$

Followed by cryptSpinCount cycles where:

$$H[n] = H(H[n-1], \text{count})$$

Count shall begin with 0x0 and is expressed as a little-endian 32-bit integer. The initial hashing operation shall not be included in count.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

f. *The standard's salt attribute description conflicts with itself, describing the salt attribute as being both prepended and appended to the password.*

Word appends the salt attribute to the password.

g. *In the standard, the cryptSpinCount attribute specifies the number of times the hashing function shall be iteratively run.*

Word requires that the initial hash of the password with the salt not be considered in the count.

h. *In the standard, the cryptAlgorithmSid has a list of supported values from 1 through 14 or any decimal number.*

Word only supports values 1, 2, 3, 4, 12, 13, and 14.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

i. *The standard states that if the enforcement attribute is omitted, then protection settings are ignored by application.*

Word enforces protection when this attribute is missing.

j. *The standard states that the values for the cryptSpinCount attribute are defined by the ST_DecimalNumber simple type.*

Word only supports values for the cryptSpinCount attribute that are between 0 and 5000000.

k. *The standard states that the salt attribute is a base64 string.*

Word appends the binary form of the salt attribute and not the base64 string representation when hashing.

l. *The standard states that this setting uses a specific set of attributes (specified by the AG_Password attribute group) to store the password hash.*

In Office, when the HKCU/Software/Microsoft/Office/<VERSION>/Common/Security/UseIsoPasswordVerifier registry key is set to 1, the XML for file sharing is written by using the XML attribute structure in the following table.

| Name | Description |
|-----------------------|---|
| algorithm Name | The name of the cryptographic hashing algorithm used to generate the hash value. Only those algorithms that are installed in the operating system's cryptographic subsystem can be utilized by Office. The following hash algorithms are reserved: MD2 <i>Specifies that the MD2 algorithm, as defined by RFC 1319, shall be used.</i> <i>[Note: It is recommended that applications should avoid using this algorithm to store new hash values, because of publicly known breaks. end note]</i> MD4 <i>Specifies that the MD4 algorithm, as defined by RFC 1320, shall be used.</i> <i>[Note: It is recommended that applications should avoid using this algorithm to store new hash values, because of publicly known breaks. end note]</i> MD5 <i>Specifies that the MD5 algorithm, as defined by RFC 1321, shall be used.</i> <i>[Note: It is recommended that applications should avoid using this algorithm to store new hash values, because of publicly known breaks. end note]</i> |

| Name | Description |
|-------------------|--|
| | <p>RIPEMD-128 Specifies that the RIPEMD-128 algorithm, as defined by ISO/IEC 10118-3:2004 shall be used. <i>[Note: It is recommended that applications should avoid using this algorithm to store new hash values, because of publicly known breaks. end note]</i></p> <p>RIPEMD-160 Specifies that the RIPEMD-160 algorithm, as defined by ISO/IEC 10118-3:2004, shall be used.</p> <p>SHA-1 Specifies that the SHA-1 algorithm, as defined by ISO/IEC 10118-3:2004, shall be used.</p> <p>SHA-256 Specifies that the SHA-256 algorithm, as defined by ISO/IEC 10118-3:2004, shall be used.</p> <p>SHA-384 Specifies that the SHA-384 algorithm, as defined by ISO/IEC 10118-3:2004, shall be used.</p> <p>SHA-512 Specifies that the SHA-512 algorithm, as defined by ISO/IEC 10118-3:2004, shall be used.</p> <p>WHIRLPOOL Specifies that the WHIRLPOOL algorithm, as defined by ISO/IEC 10118-3:2004, shall be used.</p> |
| hash Value | <p>Specifies the hash value for the password required to edit this worksheet. This value shall be compared with the resulting hash value after hashing the user-supplied password using the algorithm specified by the preceding attributes and parent XML element. If the two values match, the protection shall no longer be enforced.</p> <p>If this value is omitted, then the reservationPassword attribute shall contain the password hash for the workbook.</p> <p><i>[Example: Consider an Office Open XML document with the following information stored in one of its protection elements:</i></p> <pre data-bbox="402 1056 1295 1083"><... algorithmName="SHA-1" hashValue="9oN7nWkCAyEZib1RomSJTjmPpCY=" /></pre> <p>The hashValue attribute value of 9oN7nWkCAyEZib1RomSJTjmPpCY= specifies that the user-supplied password must be hashed using the pre-processing defined by the parent element (if any) followed by the hashing algorithm (specified via the algorithmName attribute value) and that the resulting hash value must be match for the protection to be disabled.</p> <p><i>end example]</i></p> <p>The possible values for this attribute are defined by the W3C XML Schema base64Binary datatype.</p> |
| saltValue | <p>Specifies the random bytes that are pre-pended to the user-supplied password before it was hashed by the hashing algorithm.</p> |
| spinCount | <p>Specifies the number of times the hashing function shall be iteratively run (using each iteration's result as the input for the next iteration).</p> |

[Example:

Consider an Office Open XML document with the following information stored in one of its protection elements:

```
< ... algorithmName="SHA-1" hashValue="9oN7nWkCAyEZib1RomSJTjmPpCY=" />
```

The algorithmName attribute value of SHA-1 specifies that the SHA-1 hashing algorithm must be used to generate a hash from the user-defined password.

end example]

This note applies to the following products: 2007 SP2, 2010.

2.1.410 Part 4 Section 2.15.1.30, docVar (Single Document Variable)

- a. *The standard does not limit the length of the value of the name attribute.*

Word restricts the value of this attribute to be at least 1 and at most 255 characters.

- b. *The standard does not limit the length of the value of the val attribute.*

Word restricts the value of this attribute to be at most 65280 characters.

2.1.411 Part 4 Section 2.15.1.41, doNotUseMarginsForDrawingGridOrigin (Do Not Use Margins for Drawing Grid Origin)

- a. *The standard contradicts itself with regard to the meaning of this element.*

Word uses the top-left corner of the page as the origin for the drawing grid when this element is present (instead of the margins).

2.1.412 Part 4 Section 2.15.1.43, drawingGridHorizontalOrigin (Drawing Grid Horizontal Origin Point)

- a. *The standard states that this element as specifying the distance from the origin used for horizontal gridlines.*

Word interprets this element as the distance from the origin used for vertical gridlines.

2.1.413 Part 4 Section 2.15.1.45, drawingGridVerticalOrigin (Drawing Grid Vertical Origin Point)

- a. *The standard states that this element specifies the distance from the origin used for vertical gridlines.*

Word interprets this element as the distance from the origin used for horizontal gridlines.

2.1.414 Part 4 Section 2.15.1.50, hdrShapeDefaults (Default Properties for VML Objects in Header and Footer)

- a. *The standard states that any element from the VML namespace is a valid child of the hdrShapeDefaults element.*

Word only allows the shapedefaults and shapelayout elements from the VML namespace to be children of the hdrShapeDefaults element.

2.1.415 Part 4 Section 2.15.1.53, hyphenationZone (Hyphenation Zone)

- a. *The standard states that if this element is omitted, then a default hyphenation zone of 360 twentieths of a point (0.25") shall be applied.*

Word assigns different default values for the hyphenation zone, based on the language of the running operating system.

2.1.416 Part 4 Section 2.15.1.56, listSeparator (List Separator for Field Code Evaluation)

a. *The standard states that this element specifies the character that shall be interpreted as a list item separator.*

Word ignores this element and its value and always reads the system locale settings to get the value of the list item separator.

2.1.417 Part 4 Section 2.15.1.58, noLineBreaksAfter (Custom Set of Characters Which Cannot End a Line)

a. *The standard does not state how conflicts between this element and the strictFirstAndLastChars elements should be resolved.*

Word ignores this element for Japanese text if the strictFirstAndLastChars element is specified.

b. *The standard does not limit the length of the value of the val attribute.*

Word restricts the value of this attribute to be at most 50 characters.

2.1.418 Part 4 Section 2.15.1.59, noLineBreaksBefore (Custom Set Of Characters Which Cannot Begin A Line)

a. *The standard does not state how conflicts between this element and the strictFirstAndLastChars element should be resolved.*

Word ignores this element when the strictFirstAndLastChars element is also specified.

b. *The standard does not limit the length of the value of the val attribute.*

Word restricts the value of this attribute to be at most 100 characters.

2.1.419 Part 4 Section 2.15.1.60, noPunctuationKerning (Never Kern Punctuation Characters)

a. *The standard states that the default value of this element is false.*

Word uses a default equal to true when the primary editing language is Korean.

b. *The standard states here that when kerning is enabled, Latin text should be kerned. However, the kern element contains no such restriction.*

Word kerns all characters when kerning is enabled.

2.1.420 Part 4 Section 2.15.1.62, printFractionalCharacterWidth (Print Fractional Character Widths)

a. *The standard does not state the default behavior when this element is omitted.*

Word does not apply this property when this element is omitted.

b. *The standard states that this setting specifies that the contents of this document shall be printed with fractional character widths.*

Word ignores this property.

2.1.421 Part 4 Section 2.15.1.63, printPostScriptOverText (Print PostScript Codes With Document Text)

a. *The standard states that the PostScript codes specified in WordprocessingML documents containing PRINT fields shall be included in foreground (on the same Z-order as text) with the data printed in the contents of a given WordprocessingML document.*

Word ignores this element.

2.1.422 Part 4 Section 2.15.1.66, readModeInkLockDown (Freeze Document Layout)

a. *The standard states that the actualPg attribute is required.*

Word will discard this attribute when its value is Boolean false.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.423 Part 4 Section 2.15.1.69, revisionView (Visibility of Annotation Types)

a. *The standard states that the markup attribute specifies whether the application shall visually indicate any additional non-printing area used to display annotations.*

Word uses this attribute to specify whether any annotations should be displayed when the document is opened. If this attribute is set to false, then no annotations are displayed, regardless of the state of the other attributes.

2.1.424 Part 4 Section 2.15.1.70, rsid (Single Session Revision Save ID)

a. *The standard states that the rsid should be randomly chosen and that every editing session shall be assigned an rsid that is larger than all earlier ones in the same file. If both are observed, the application would quickly run out of allowable rsid's.*

Word generates a random number for every rsid that is not necessarily larger than all earlier ones in the same file.

2.1.425 Part 4 Section 2.15.1.74, saveInvalidXml (Allow Saving Document As XML File When Custom XML Markup Is Invalid)

a. *The standard states that if the doNotValidateAgainstSchema element is set, then the XML is never invalid and this property is ignored.*

Word does not ignore this property when doNotValidateAgainstSchema element is set.

2.1.426 Part 4 Section 2.15.1.76, saveThroughXslt (Custom XSL Transform To Use When Saving As XML File)

a. *The standard states that if both solutionID and id attributes are present, the id attribute is used if the solutionID attribute cannot be used successfully.*

Word ignores the id attribute whenever this attribute is present, even if this information cannot be used successfully.

b. *The standard does not state what shall occur when the solutionID attribute cannot be recognized.*

Word ignores the parent saveThroughXslt element if this attribute cannot be recognized.

2.1.427 Part 4 Section 2.15.1.79, shapeDefaults (Default Properties for VML Objects in Main Document)

a. *The standard states that any element from the VML namespace is a valid child of the shapeDefaults element.*

Word only allows the shapedefaults and shapelayout elements from the VML namespace to be children of the shapeDefaults element.

2.1.428 Part 4 Section 2.15.1.81, showXMLTags (Show Visual Indicators for Custom XML Markup Start/End Locations)

a. *The standard does not explicitly state that this element does not need to be roundtripped.*

Word uses, but does not roundtrip, this element.

2.1.429 Part 4 Section 2.15.1.82, smartTagType (Supplementary Smart Tag Information)

a. *The standard does explicitly state that this element can be ignored under certain conditions.*

Word ignores this element if either the name or namespaceuri attribute is omitted, or the attributes do not identify a smart tag contained in the document.

b. *The standard does not say that the url attribute can be ignored under certain conditions.*

Word ignores this attribute when the application already has URL information for this name/namespaceuri combination.

2.1.430 Part 4 Section 2.15.1.83, strictFirstAndLastChars (Use Strict Kinsoku Rules for Japanese Text)

a. *The standard does not state how to resolve conflicts between this element and the noLineBreaksBefore and noLineBreaksAfter elements when their settings conflict.*

Word overrides the settings specified by the noLineBreaksBefore and noLineBreaksAfter elements with the settings from this element on Japanese text.

2.1.431 Part 4 Section 2.15.1.86, stylePaneFormatFilter (Suggested Filtering for List of Document Styles)

a. *The standard states that the default value of this element is 0x0000.*

Word uses a default value of 0x5024 for this element.

b. *The standard states the meaning for each bit in the bitfield specified by the val attribute.*

Word does not support the values 0x0040, 0x0080, and 0x0800.

2.1.432 Part 4 Section 2.15.1.87, stylePaneSortMethod (Suggested Sorting for List of Document Styles)

a. *The standard states a meaning for values 0000 through 0005.*

In Office, the following sorting options have different meanings than specified in the standard:

| Value | Description |
|--------|---|
| 0x0002 | Specifies that styles which are visible should be sorted by the font which they apply. |
| 0x0003 | Specifies that styles which are visible should be sorted by the style on which they are based using the basedOn element. |
| 0x0004 | Specifies that styles which are visible should be sorted by their style types (that is, character, linked, paragraph). |

Office ignores value 0x0005.

If this element is omitted, then styles which are visible should be sorted by their UI priority values.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.433 Part 4 Section 2.15.1.88, summaryLength (Percentage of Document to Use When Generating Summary)

a. *The standard does not explicitly state that the summaryLength element can be removed when a document is saved.*

Word does not roundtrip this setting unless certain operations related to automatic summaries are performed while the document is open.

b. *The standard states that the values of the val attribute are defined by the XML Schema integer datatype.*

Word restricts the value of this attribute to be at least 0 and at most 100.

2.1.434 Part 4 Section 2.15.1.89, themeFontLang (Theme Font Languages)

For additional notes that apply to this portion of the standard, please see the notes for [lang](#), §2.3.2.18(a).

a. *The standard states that the default values of languages of the theme fonts are specified by the cs, ea, and latin elements in the Theme part.*

Word calculates the default languages of the theme fonts based on the Office install language and the system installed keyboards.

2.1.435 Part 4 Section 2.15.1.91, updateFields (Automatically Recalculate Fields on Open)

a. *The standard makes no explicit mention of the roundtripping behavior of the updateFields element.*

Word does not roundtrip the updateFields element in all circumstances.

2.1.436 Part 4 Section 2.15.1.93, view (Document View Setting)

a. The standard states that the *val* attribute value specifies the view which shall be used to render the contents of a *WordprocessingML* document.

Under certain conditions, Word treats a value of *normal* as unsupported when the document is loaded and reverted to a value of *print*.

2.1.437 Part 4 Section 2.15.1.94, writeProtection (Write Protection)

For additional notes that apply to this portion of the standard, please see the notes for [documentProtection, §2.15.1.28\(b-h,j, k\)](#).

a. The standard states that this setting is keyed off of a non-existent password attribute.

Word uses the *AG_Password* attribute group to determine whether to prompt for a password.

b. The standard states that this setting uses a specific set of attributes (specified by the *AG_Password* attribute group) to store the password hash.

In Office, when the *HKCU/Software/Microsoft/Office/<VERSION>/Common/Security/UseIsoPasswordVerifier* registry key is set to 1, the XML for file sharing is written by using the XML attribute structure in the following table.

| Name | Description |
|-----------------------|---|
| algorithm Name | <p>The name of the cryptographic hashing algorithm used to generate the hash value. Only those algorithms that are installed in the operating system's cryptographic subsystem can be utilized by Office.</p> <p>The following hash algorithms are reserved:</p> <p>MD2 Specifies that the MD2 algorithm, as defined by RFC 1319, shall be used. [Note: It is recommended that applications should avoid using this algorithm to store new hash values, because of publicly known breaks. end note]</p> <p>MD4 Specifies that the MD4 algorithm, as defined by RFC 1320, shall be used. [Note: It is recommended that applications should avoid using this algorithm to store new hash values, because of publicly known breaks. end note]</p> <p>MD5 Specifies that the MD5 algorithm, as defined by RFC 1321, shall be used. [Note: It is recommended that applications should avoid using this algorithm to store new hash values, because of publicly known breaks. end note]</p> <p>RIPMD-128 Specifies that the RIPMD-128 algorithm, as defined by ISO/IEC 10118-3:2004 shall be used. [Note: It is recommended that applications should avoid using this algorithm to store new hash values, because of publicly known breaks. end note]</p> <p>RIPMD-160 Specifies that the RIPMD-160 algorithm, as defined by ISO/IEC 10118-3:2004, shall be used.</p> <p>SHA-1 Specifies that the SHA-1 algorithm, as defined by ISO/IEC 10118-3:2004, shall be used.</p> |

| Name | Description |
|-------------------|--|
| | <p>SHA-256 Specifies that the SHA-256 algorithm, as defined by ISO/IEC 10118-3:2004, shall be used.</p> <p>SHA-384 Specifies that the SHA-384 algorithm, as defined by ISO/IEC 10118-3:2004, shall be used.</p> <p>SHA-512 Specifies that the SHA-512 algorithm, as defined by ISO/IEC 10118-3:2004, shall be used.</p> <p>WHIRLPOOL Specifies that the WHIRLPOOL algorithm, as defined by ISO/IEC 10118-3:2004, shall be used.</p> |
| hash Value | <p>Specifies the hash value for the password required to edit this worksheet. This value shall be compared with the resulting hash value after hashing the user-supplied password using the algorithm specified by the preceding attributes and parent XML element. If the two values match, the protection shall no longer be enforced.</p> <p>If this value is omitted, then the reservationPassword attribute shall contain the password hash for the workbook.</p> <p>[Example: Consider an Office Open XML document with the following information stored in one of its protection elements:</p> <pre><... algorithmName="SHA-1" hashValue="9oN7nWkCAyEZib1RomSJTjmPpCY=" /></pre> <p>The hashValue attribute value of 9oN7nWkCAyEZib1RomSJTjmPpCY= specifies that the user-supplied password must be hashed using the pre-processing defined by the parent element (if any) followed by the hashing algorithm (specified via the algorithmName attribute value) and that the resulting hash value must be match for the protection to be disabled.</p> <p><i>end example]</i></p> <p>The possible values for this attribute are defined by the W3C XML Schema base64Binary datatype.</p> |
| saltValue | <p>Specifies the random bytes that are pre-pended to the user-supplied password before it was hashed by the hashing algorithm.</p> |
| spinCount | <p>Specifies the number of times the hashing function shall be iteratively run (using each iteration's result as the input for the next iteration).</p> |

[Example:

Consider an Office Open XML document with the following information stored in one of its protection elements:

```
< ... algorithmName="SHA-1" hashValue="9oN7nWkCAyEZib1RomSJTjmPpCY=" />
```

The algorithmName attribute value of SHA-1 specifies that the SHA-1 hashing algorithm must be used to generate a hash from the user-defined password.

end example]

This note applies to the following products: 2007 SP2, 2010.

2.1.438 Part 4 Section 2.15.1.95, zoom (Magnification Setting)

- a. The standard states that the percent attribute is required.

Word does not always require this attribute.

b. *The standard specifies that a percent attribute value of less than the minimum zoom level shall result in display of the document using the application's minimum zoom level.*

Word treats this attribute as omitted when it has a value of 0.

2.1.439 Part 4 Section 2.15.2.1, allowPNG (Allow PNG as Graphic Format)

a. *The standard states that when this element is false, the PNG file format shall not be allowed when this document is saved as a web page.*

Word does save PNG files when this setting is off; however, the web page is structured such that the PNG files are not required for a web browser to read the file correctly.

2.1.440 Part 4 Section 2.15.2.2, blockQuote (Data for HTML blockquote Element)

a. *The standard states that if both this element and the bodyDiv element are specified, then the bodyDiv element shall be ignored.*

Word ignores this element in favor of the bodyDiv element when the current div is a direct descendant of the divs element.

2.1.441 Part 4 Section 2.15.2.3, bodyDiv (Data for HTML body Element)

a. *The standard states that if both this element and the blockQuote element ("[\[ECMA-376\]](#) Part 4 §2.15.2.2; blockQuote") are specified, then this element shall be ignored.*

Word ignores the blockQuote element in favor of this element if this div is a direct subelement of the divs tag.

2.1.442 Part 4 Section 2.15.2.4, bottom (Bottom Border for HTML div)

For additional notes that apply to this portion of the standard, please see the notes for [bar](#), [§2.3.1.4\(a-c\)](#); [bdr](#), [§2.3.2.3\(a\)](#); [left](#), [§2.15.2.21\(a\)](#).

2.1.443 Part 4 Section 2.15.2.5, color (Frameset Splitter Color)

For additional notes that apply to this portion of the standard, please see the notes for [color](#), [§2.3.2.5\(a-c\)](#).

a. *The standard states that the themeColor attribute specifies the theme color that should be applied to the current object.*

Word does not use the specified theme color, but will use an RGB color calculated from the themeShade and themeTint attributes if this attribute is specified in the color element ("[\[ECMA-376\]](#) Part 4 §2.15.2.5; color") nested inside a framesetSplitbar element ("[\[ECMA-376\]](#) Part 4 §2.15.2.20; framesetSplitbar").

2.1.444 Part 4 Section 2.15.2.6, div (Information About Single HTML div Element)

a. *The standard states that the values of the id attribute are defined by the XML Schema integer datatype.*

Word does not allow a value of 0 on this attribute.

2.1.445 Part 4 Section 2.15.2.10, doNotOrganizeInFolder (Do Not Place Supporting Files in Subdirectory)

- a. *The standard states that the doNotOrganizeInFolder element specifies that applications shall not automatically place all supporting files in a subdirectory.*

Word ignores this element when the doNotUseLongFileNames element is set to true (or equivalent).

2.1.446 Part 4 Section 2.15.2.14, encoding (Output Encoding When Saving as Web Page)

- a. *The standard requires that this setting is roundtripped as specified.*

Word does not roundtrip this element when the specified encoding is equal to the current default encoding, or when the specified encoding is not supported.

- b. *The standard does not limit the length of the value of the val attribute.*

Word restricts the value of this attribute to be at most 255 characters.

2.1.447 Part 4 Section 2.15.2.15, flatBorders (Frameset Splitter Border Style)

- a. *The standard states that the values 0 and false on the val attribute are equivalent to the value off.*

Word treats these values on this attribute as equivalent to the value on.

This note applies to the following products: 2007, 2007 SP1.

2.1.448 Part 4 Section 2.15.2.17, frameLayout (Frameset Layout)

- a. *The standard says that if this element is omitted, the frames in this frameset shall be stacked vertically on top of one another (a row frameset).*

In Word, if this element is omitted, the default value is none.

2.1.449 Part 4 Section 2.15.2.18, frameset (Root Frameset Definition)

- a. *The standard does not state the behavior of an empty frameset element.*

Word treats an empty frameset as though it contains a single frame element (using its default values).

2.1.450 Part 4 Section 2.15.2.19, frameset (Nested Frameset Definition)

- a. *The standard does not state the behavior of an empty frameset element.*

Word treats an empty frameset as though it contains a single frame element (using its default values).

2.1.451 Part 4 Section 2.15.2.21, left (Left Border for HTML div)

For additional notes that apply to this portion of the standard, please see the notes for [bar](#), [§2.3.1.4\(a-c\)](#); [bdr](#), [§2.3.2.3\(a\)](#).

- a. *The standard does not state which borders the frame attribute applies to.*

Word only applies this attribute to the right and bottom borders.

2.1.452 Part 4 Section 2.15.2.22, `linkedToFile` (Maintain Link to Existing File)

- a. *The standard states that the values 0 and false on the val attribute are equivalent to the value off.*

Word treats these values on this attribute as equivalent to the value on.

This note applies to the following products: 2007, 2007 SP1.

2.1.453 Part 4 Section 2.15.2.29, `name` (Frame Name)

- a. *The standard does not limit the length of the value of the val attribute.*

Word restricts the value of this attribute to be at most 255 characters.

2.1.454 Part 4 Section 2.15.2.30, `noBorder` (Do Not Display Frameset Splitters)

- a. *The standard states that the values 0 and false on the val attribute are equivalent to the value off.*

Word treats these values on this attribute as equivalent to the value on.

This note applies to the following products: 2007, 2007 SP1.

2.1.455 Part 4 Section 2.15.2.31, `noResizeAllowed` (Frame Cannot Be Resized)

- a. *The standard states that the values 0 and false on the val attribute are equivalent to the value off.*

Word treats these values on this attribute as equivalent to the value on.

This note applies to the following products: 2007, 2007 SP1.

2.1.456 Part 4 Section 2.15.2.32, `optimizeForBrowser` (Disable Features Not Supported by Target Web Browser)

- a. *The standard states that the values off, 0, and false on the val attribute specify that the property shall be explicitly turned off.*

Word treats all values on this attribute as equivalent to the value on.

This note applies to the following products: 2007, 2007 SP1.

- b. *The standard states that this element (in conjunction with the other elements listed) is used to set the target web browser.*

Word does not use the indicated settings to determine target browser when document is loaded, instead using Internet Explorer 6 as the target browser in every case.

2.1.457 Part 4 Section 2.15.2.33, `pixelsPerInch` (Pixels per Inch for Graphics/Images)

- a. *The standard states that the values of the val attribute are defined by the XML Schema integer datatype.*

Word restricts the value of this attribute to be at least 0 and at most 1023.

2.1.458 Part 4 Section 2.15.2.35, right (Right Border for HTML div)

For additional notes that apply to this portion of the standard, please see the notes for [bar, §2.3.1.4\(a-c\)](#); [bdr, §2.3.2.3\(a\)](#); [left, §2.15.2.21\(a\)](#).

2.1.459 Part 4 Section 2.15.2.38, sourceFileName (Source File for Frame)

For additional notes that apply to this portion of the standard, please see the notes for [attachedTemplate, §2.15.1.6\(a\)](#).

2.1.460 Part 4 Section 2.15.2.39, sz (Frame Size)

a. *The standard allows any string for the val attribute.*

For the val attribute, Word allows an integer between 1 and 32,767 followed by *; an integer between 1 and 500 followed by %; or an integer which divided by pixelsPerInch gives a value between 0 and 22.

b. *The standard says if this element is omitted, then no information shall be implied about the size of the current frameset.*

Word considers the default value to be 1*.

2.1.461 Part 4 Section 2.15.2.40, sz (Nested Frameset Size)

a. *The standard allows any string for the val attribute.*

For the val attribute, Word allows an integer between 1 and 32,767 followed by *; an integer between 1 and 500 followed by %; or an integer which divided by pixelsPerInch gives a value between 0 and 22.

b. *The standard states that no information shall be implied about the size of the current frameset when this element is omitted.*

Word implies that the size of the current frameset shall be a relative measurement with a value of 1 when the sz element is omitted.

2.1.462 Part 4 Section 2.15.2.41, targetScreenSz (Target Screen Size for Web Page)

a. *The standard states that this element stores the ideal minimum target screen size on which web pages generated when saving this document will be displayed.*

Word ignores this element.

2.1.463 Part 4 Section 2.15.2.42, top (Top Border for HTML div)

For additional notes that apply to this portion of the standard, please see the notes for [bar, §2.3.1.4\(a-c\)](#); [bdr, §2.3.2.3\(a\)](#); [left, §2.15.2.21\(a\)](#).

2.1.464 Part 4 Section 2.15.3.4, applyBreakingRules (Use Legacy Ethiopic and Amharic Line Breaking Rules)

a. The standard says that the application shall allow break opportunities after this specific set of character only if this setting is off.

Word allows break opportunities after this specific set of characters only if the setting is on.

b. The standard says that setting the *val* attribute to 0, off, or false should turn off this property.

Word may turn this setting on if editing has been enabled for a language that is right to left or that uses complex scripts.

2.1.465 Part 4 Section 2.15.3.6, autoSpaceLikeWord95 (Emulate Word 95 Full-Width Character Spacing)

a. The standard does not state exactly how to emulate Word 95 full-width character spacing.

In Office, this element specifies adjustments (as follows) which should be applied to the spacing between adjoining regions of non-ideographic and ideographic text when the **autoSpaceDE** (“[\[ECMA-376\]](#) Part 4 §2.3.1.2; autoSpaceDE (Automatically Adjust Spacing of Latin and East Asian Text)”) and **autoSpaceDN** (“[\[ECMA-376\]](#) Part 4 §2.3.1.3; autoSpaceDN (Automatically Adjust Spacing of East Asian Text and Numbers)”) elements have a value of *true* (or equivalent). This algorithm typically results in the following:

An increase in the inter-character spacing added between non-ideographic and/or number characters and certain full-width characters

No inter-character spacing between non-ideographic and/or number characters and certain half-width characters

Typically, applications apply additional spacing between ideographic and non-ideographic characters/numeric characters when the **autoSpaceDE** or **autoSpaceDN** properties are applied. This element, when present with a **val** attribute value of *true* (or equivalent), specifies that Word shall apply the following adjustments to this logic:

Characters in the following Unicode ranges should be treated as ideographic, even though those characters are full-width forms of non-ideographic text: U+FF10–U+FF19, U+FF21–U+FF3A, and U+FF41–U+FF5A. [Note: This results in the unnecessary addition of space. end note]

Characters in the following Unicode ranges should be treated as non-ideographic, even though those characters are ideographic: U+FF66–U+FF9F. [Note: This results in the omission of the intended additional space. end note]

[Example: Consider a WordprocessingML document with two paragraphs containing a mix of East Asian and Latin characters:

```
<w:p>
  <w:r>
    <w:t>ab</w:t>
  </w:r>
  <w:r>
    <w:t>7</w:t>
  </w:r>
</w:p>
```

```

</w:r>
<w:r>
  <w:t>𐀀</w:t>
</w:r>
<w:r>
  <w:t>cd</w:t>
</w:r>
</w:p>
<w:p>
  <w:r>
    <w:t>ab</w:t>
  </w:r>
  <w:r>
    <w:t>𐀀</w:t>
  </w:r>
  <w:r>
    <w:t>𐀀</w:t>
  </w:r>
  <w:r>
    <w:t>cd</w:t>
  </w:r>
</w:p>

```

The first paragraph contains characters with Unicode value U+FF66 (𐀀). The second paragraph contains characters with Unicode value U+FF12 (2). If **autoSpaceDE** is *true*, spacing is added in the first paragraph (between the ideographs and the non-ideographic characters), but not in the second (all four characters are not ideographs):

ab 𐀀𐀀 cd

ab 2 2 cd

If this compatibility setting is turned on:

```

<w:compat>
  <w:autoSpaceLikeWord95 />
</w:compat>

```

Then, although it appears incorrect, Word will not add space in the first paragraph but rather apply it in the second:

ab𐀀𐀀cd

ab 2 2 cd

end example]

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.466 Part 4 Section 2.15.3.10, convMailMergeEsc (Treat Backslash Quotation Delimiter as a Single Quotation Mark)

- a. *The standard states that applications shall interpret delimiters composed of a backslash and quotation mark (\") as two quotation marks (").*

Word interprets delimiters composed of a backslash and quotation mark (\") as a single quotation mark (").

- b. *The standard does not state any constraints for the usage of this property.*

Word only uses this property in the document that serves as the external data source to be a WordprocessingML document through an ODSO connection.

2.1.467 Part 4 Section 2.15.3.12, doNotAutofitConstrainedTables (Do Not AutoFit Tables To Fit Next To Wrapped Objects)

- a. *The standard states that a table that is AutoFit and has a preferred width typically has its width reduced in order to allow a floating shape to wrap.*

Word only reduces the width of tables that have no preferred width in order to allow a floating shape to wrap.

- b. *The standard states that when this element is present with a val attribute value of true, tables shall never have any preferred width overridden to allow them to wrap.*

Word never allows tables to have their width reduced to allow them to wrap, even if they have no preferred width.

2.1.468 Part 4 Section 2.15.3.16, doNotLeaveBackslashAlone (Convert Backslash To Yen Sign When Entered)

- a. *The standard states that backslashes should be converted to yen signs when typed.*

Word does not alter the document, but rather displays backslashes as yen signs when this property is set.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

- b. *The standard states that backslashes should be converted to yen signs unconditionally if the setting is turned on.*

Word only converts backslashes to yen signs if the setting is turned on and Japanese language support has been installed.

2.1.469 Part 4 Section 2.15.3.19, doNotSuppressParagraphBorders (Do Not Suppress Paragraph Borders Next To Frames)

- a. *The standard states that specific paragraph borders should not be suppressed if this setting is on.*

Word suppresses those paragraph borders when this setting is on unless the doNotSuppressIndentation setting is also on.

2.1.470 Part 4 Section 2.15.3.26, footnoteLayoutLikeWW8 (Emulate Word 6.x/95/97 Footnote Placement)

- a. *The standard does not state exactly how to emulate Word 6.x/95/97 footnote placement.*

In Office, this element specifies that Word should override the default behavior for a continuous section break when one or more footnotes are present on the page with the footnote. This override typically results in text being displayed on the same page as a continuous section break (after the break, which would normally move all following text to the next page).

Typically, applications render a continuous section break as a page break when one or more **footnoteRef** elements (“[ECMA-376](#) Part 4 §2.11.13; footnoteRef (Footnote Reference Mark)”) occur on that page before the break. This element, when present with a **val** attribute value of *true* (or equivalent), specifies that Word should allow any paragraph after the section break that contains no **footnoteRef** elements (“[ECMA-376](#) Part 4 §2.11.13; footnoteRef (Footnote Reference Mark)”) to be displayed on the same page. If the resulting content reaches the page extents, the section’s page break is ignored.

[Example: Consider a WordprocessingML document with two footnotes contained in two sections, separated by a continuous section break:


```
<w:p>
  <w:r>
    <w:t xml:space="preserve">Here is the first paragraph in the first section.</w:t>
  </w:r>
</w:p>
<w:p>
  <w:r>
    <w:t>Here is the second paragraph in the first section.</w:t>
  </w:r>
  <w:r>
    <w:rPr>
      <w:rStyle w:val="FootnoteReference" />
    </w:rPr>
  <w:footnoteReference w:id="2" />
</w:r>
</w:p>
<w:p/>
<w:p>
  <w:pPr>
    <w:sectPr>
      ...
    </w:sectPr>
  </w:pPr>
</w:p>
<w:p>
  <w:r>
    <w:t>Here is the first paragraph in the second section.</w:t>
  </w:r>
</w:p>
<w:p>
  <w:r>
    <w:t xml:space="preserve">Here is the second paragraph in the second section.</w:t>
  </w:r>
  <w:r>
    <w:rPr>
      <w:rStyle w:val="FootnoteReference" />
    </w:rPr>
  </w:r>
</w:p>
```

```

<w:footnoteReference w:id="3" />
</w:r>
</w:p>
<w:p>
  <w:r>
    <w:t xml:space="preserve">Here is the third paragraph in the second section. </w:t>
  </w:r>
</w:p>
<w:sectPr>
  <w:type w:val="continuous" />
  ...
</w:sectPr>

```

The default rendering of such a document results in the continuous section break as a page break, resulting in the following two page document:




However, if this compatibility setting is turned on:

```

<w:compat>
  <w:footnoteLayoutLikeWW8 />
</w:compat>

```

Then the first paragraph following the section break (not having any footnote references) is displayed on the same page, despite the section break, resulting in the following output:



end example]

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.


2.1.471 Part 4 Section 2.15.3.31, lineWrapLikeWord6 (Emulate Word 6.0 Line Wrapping for East Asian Text)

- a. *The standard does not state exactly how to emulate Word 6.0 line wrapping for East Asian text.*


In Office, this element specifies that Word should ignore the character compression settings specified by the **characterSpacingControl** element (“[ECMA-376](#) Part 4 §2.15.1.18; characterSpacingControl (Character-Level Whitespace Compression)”) when determining if one more characters fit within the text margins on each line of the document. This setting typically results in a character being pushed to the following line, ignoring the fact that the character compression settings would have allowed it to fit within the text boundaries.

Typically, an application would check the character compression settings, and apply any character-level whitespace compression before attempting to fit the last character on the line. This element, when present with a **val** attribute value of *true* (or equivalent), specifies that Word shall ignore that compression and fit the character as if it should be displayed at its full width, regardless of whether the compression settings are applied.

[Example: Consider a paragraph which ends with the following two characters (with each character’s bounding box outlined for illustrative purposes:



If the document’s character compression settings were not set to *doNotCompress* and text extent fell at the location identified by this red line:



The last character would have compression applied to its blank half, and would fit on the line.

If this compatibility setting is turned on:

```
<w:compat>
  <w:lineWrapLikeWord6 />
</w:compat>
```

Then Word would compress the character, but should treat the character as full width when determining if it fits on the line; in this case, the second character would be displayed on the following line. end example]

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.472 Part 4 Section 2.15.3.32, mwSmallCaps (Emulate Word 5.x for the Macintosh Small Caps Formatting)

a. *The standard does not state exactly how to emulate Word 5.x for the Macintosh small caps.*

This element, when present with a **val** attribute value of *true* (or equivalent), specifies that Word will determine the font size for small caps using the following algorithm:

If $font \leq 7$, then the font size for small caps is 7 points.

Otherwise, sequentially iterate through *sequence* until $sequence[i] \leq font \leq sequence[i + 1]$, at which point the font size for small caps is $sequence[i]$ points.

where:

sequence is an array defined as follows:

$\{7, 9, 10, 12, 14, 18, 24, 36, 48, 60, 72, 80, x_1, x_2, \dots, x_n\}$ where $x_n = 80 + 10 * n$.

font is an integer calculated as follows:

The font size of the run to which small caps formatting is applied (in points).

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.473 Part 4 Section 2.15.3.41, shapeLayoutLikeWW8 (Emulate Word 97 Text Wrapping Around Floating Objects)

a. *The standard does not state exactly how to emulate Word 97 text wrapping around floating objects.*

In Office, this element specifies that Word will ignore the line wrapping setting specified by a floating object, instead allowing text to be displayed beneath it under the specific set of conditions identified as follows.

Typically, text wrapping around a floating object is dictated by the presence of one of the following as a child element of the object's **anchor** element ("ECMA-376 Part 4 §5.5.2.3; anchor (Anchor for Floating DrawingML Object)"):

wrapNone element ("ECMA-376 Part 4 §5.5.2.15; wrapNone (No Text Wrapping)"), which specifies no text wrapping

wrapSquare element ("ECMA-376 Part 4 §5.5.2.17; wrapSquare (Square Wrapping)"), which specifies square text wrapping

wrapThrough element ("ECMA-376 Part 4 §5.5.2.18; wrapThrough (Through Wrapping)"), which specifies through text wrapping

wrapTight element ("ECMA-376 Part 4 §5.5.2.19; wrapTight (Tight Wrapping)"), which specifies tight text wrapping

wrapTopAndBottom element ("ECMA-376 Part 4 §5.5.2.20; wrapTopAndBottom (Top and Bottom Wrapping)"), which specifies top and bottom text wrapping

This element, when present with a **val** attribute value of *true* (or equivalent), specifies that Word will allow text to wrap beneath a floating object, ignoring the object's true wrapping setting, when the following conditions are met:

The floating object has any of the following elements present as a child of the object's **anchor** element: **wrapSquare**, **wrapTight**, or **wrapTopAndBottom**.

The floating object has a **positionV** element ("ECMA-376 Part 4 §5.5.2.11; positionV (Vertical Positioning)") with a **relativeFrom** attribute value of *line*.

The floating object has a negative value for the child **posOffset** element ("ECMA-376 Part 4 §5.5.2.12; posOffset (Absolute Position Offset)") of the **positionV** element.

The paragraph containing the **anchor** element would appear directly after the previous paragraph if the wrapping settings were ignored.

The paragraph containing the **anchor** element would be pushed to the next page if the wrapping settings were respected.

[Example: Consider a WordprocessingML document containing a DrawingML object that meets these conditions:


```
<w:p>  
  <w:r>
```

```

    <w:t>Sample text. Sample text. Sample text. Sample text. Sample text. Sample text.</w:t>
</w:r>
<w:r>
  <w:drawing>
    <wp:anchor ... >
    <wp:positionV relativeFrom="line">
      <wp:posOffset>-428914</wp:posOffset>
    </wp:positionV>
    <wp:wrapTopAndBottom />
    ...
  </wp:anchor>
</w:drawing>
</w:r>
<w:r>
  <w:t> Sample text. Sample text. Sample text. Sample text. Sample text. Sample text.</w:t>
</w:r>
...
</w:p>

```

When the wrapping settings are respected, the shape and its paragraph do not fit on the page, so they are moved to the next page (the paragraph containing the anchor has been highlighted for illustrative purposes):




If this compatibility setting is turned on:

```

<w:compat>
  <w:shapeLayoutLikeWW8 />
</w:compat>

```

Then Word will ignore the wrapping setting and allow text to wrap below the object. This behavior results in the following (again, the paragraph containing the anchor has been highlighted for illustrative purposes):



end example]

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.474 Part 4 Section 2.15.3.46, subFontBySize (Increase Priority Of Font Size During Font Substitution)

- a. *The standard does not state exactly how to raise priority of font size in font substitution.*

Word does not substitute with a font that cannot be displayed at the specified size.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.475 Part 4 Section 2.15.3.51, suppressTopSpacingWP (Emulate WordPerfect 5.x Line Spacing)

- a. *The standard does not state exactly how to space lines like WordPerfect 5.x.*

(The terms baseline to baseline distance and unitsPerEm are defined in ISO/IEC 14496-22:2007.)

In Office, this element specifies that Word will use the values defined as follows to calculate the baseline to baseline distance (BTBD) in this document. This can result in lines appearing slightly condensed vertically.

Without this setting, applications calculate baseline to baseline distance using the metrics defined by ISO/IEC 14496-22:2007. This element, when present with a **val** attribute value of *true* (or equivalent), specifies that Word should calculate this as follows:

$$BTBD = \text{unitsPerEm} + 2\text{pt}$$

[Example: If this compatibility setting is turned on:

```
<w:compat>
  <w:suppressTopSpacingWP />
```

</w:compat>

Then Word uses a baseline to baseline distance as calculated before. With a 16 point font, this would result in a baseline to baseline distance of 18 points. end example]

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.476 Part 4 Section 2.15.3.53, truncateFontHeightsLikeWP6 (Emulate WordPerfect 6.x Font Height Calculation)

a. *The standard does not state exactly how to emulate WordPerfect 6.x font height calculation.*

In Office, this element specifies that Word should perform a specific method of calculation when converting font heights, specified in points using the **sz** ("ECMA-376 Part 4 §2.3.2.36; sz (Font Size)") and **szCs** ("ECMA-376 Part 4 §2.3.2.37; szCs (Complex Script Font Size)") elements, into pixels. This algorithm often results in a smaller than typical visual appearance of text for a given point size.

Typically, applications convert points to pixels using any approximate mathematical conversion mechanism (often, rounded integer division). This element, when present with a **val** attribute value of *true* (or equivalent), specifies that Word will use truncated integer division when performing this conversion (any non-integer value is truncated to determine the integer value resulting from the conversions).

[Example: If this compatibility setting is turned on:

```
<w:compat>  
  <w:truncateFontHeightsLikeWP6 />  
</w:compat>
```

Then Word shall use truncated integer division when calculating the height of characters.

For example, if the conversion is done as follows:

$$sz_{px} = sz_{pt} * N \frac{px}{inch} * \frac{1 inch}{72 pt}$$

where:

sz_{pt} = size in points

sz_{px} = size in pixels

N = resolution in pixels per inch

Converting a 14 point font on a 96 dpi device results in $sz_{px} = 14 * 96 * \frac{1}{72} = 18\frac{2}{3} px$. If this setting is on, the result is truncated and the font is displayed using 18 pixels, even though 19 would be closer to the actual value. end example]

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.477 Part 4 Section 2.15.3.54, `uiCompat97To2003` (Disable Features Incompatible With Earlier Word Processing Formats)

- a. *The standard does not state a default value for this element.*

Word uses a default value of false when this element is not present.

2.1.478 Part 4 Section 2.15.3.63, `useWord2002TableStyleRules` (Emulate Word 2002 Table Style Rules)

- a. *The standard does not state exactly how to emulate Word 2002 table style rules.*

In Office, this element specifies whether Word should incorrectly calculate the top border of conditional columns (as specified by a `tblStylePr` element ("[ECMA-376](#) Part 4 §2.7.5.6; `tblStylePr` (Style Conditional Table Formatting Properties)”) with a `type` attribute value of `firstCol`, `lastCol`, `band1Vert`, or `band2Vert`) under the following conditions:

A conditional formatting has also been defined for the first row (a `tblStylePr` element with a `type` attribute of `firstRow`)

That conditional formatting as been applied to the table using the `tblLook` element ("[ECMA-376](#) Part 4 §2.4.51; `tblLook` (Table Style Conditional Formatting Settings)”)

Typically, table styles are applied according to the logic defined by the Style Hierarchy ("[ECMA-376](#) Part 4 §2.7.2; Style Hierarchy”). This element, when present with a `val` attribute value of `true` (or equivalent), specifies that the top border of those conditionally formatted columns should instead be displayed as the top border of the following row.

[Example: Consider a WordprocessingML document with table style that defines two conditional formats:

The first column has a one point border

The first row has red shading

That style would be defined as follows:

```
<w:style w:type="table" w:customStyle="1" w:styleId="TableTest">
  <w:name w:val="CompatibilitySetting"/>
  <w:tblStylePr w:type="firstRow">
    <w:tcPr>
      <w:shd w:val="clear" w:color="auto" w:fill="FF0000"/>
    </w:tcPr>
  </w:tblStylePr>
  <w:tblStylePr w:type="firstCol">
    <w:tcPr>
      <w:tcBorders>
        <w:top w:val="single" w:sz="4" w:space="0" w:color="auto"/>
        <w:left w:val="single" w:sz="4" w:space="0" w:color="auto"/>
        <w:bottom w:val="single" w:sz="4" w:space="0" w:color="auto"/>
        <w:right w:val="single" w:sz="4" w:space="0" w:color="auto"/>
      </w:tcBorders>
    </w:tcPr>
  </w:tblStylePr>
</w:style>
```

If the first column and first row formatting is applied, the table would appear as follows:

| | |
|-----|-----|
| 1,1 | 1,2 |
| 2,1 | 2,2 |

However, if this compatibility setting is turned on:

```
<w:compat>  
  <w:useWord2002TableStyleRules />  
</w:compat>
```

Then the condition described by this element causes the top border defined by the conditional format for the first column to be displayed as the top border for the second column, resulting in the following output:

| | |
|-----|-----|
| 1,1 | 1,2 |
| 2,1 | 2,2 |

end example]

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.479 Part 4 Section 2.15.3.64, useWord97LineBreakRules (Emulate Word 97 East Asian Line Breaking)

a. *The standard does not state exactly how to break lines like Word 97.*

In Office, this element specifies that Word should perform specific calculations (detailed as follows) when determining inter-character spacing under certain conditions. These calculations would not normally be considered correct.

Typically, the behaviors specified by the following elements are applied unconditionally:

The **autoSpaceDE** (“[\[ECMA-376\]](#) Part 4 §2.3.1.2; autoSpaceDE (Automatically Adjust Spacing of Latin and East Asian Text)”) and **autoSpaceDN** (“[\[ECMA-376\]](#) Part 4 §2.3.1.3; autoSpaceDN (Automatically Adjust Spacing of East Asian Text and Numbers)”) elements

The **topLinePunct** (“[\[ECMA-376\]](#) Part 4 §2.3.1.43; topLinePunct (Compress Punctuation at Start of a Line)”) element

The compatibility element described in this subclause, when present with a **val** attribute value of *true* (or equivalent), specifies that Word should ignore these settings in the following scenarios:

If an ideographic character and a non-ideographic or numeric character are logically adjacent (ignoring all content that is not within a **t** element), but separated by a field boundary, that is:

The first character is within a **fldSimple** element, but the second is not.

The characters are separated by a **fldChar** element with a **fldCharType** attribute value of *end*.

Then any appropriate inter-character spacing should be omitted. [Note: Inter-character spacing should still be calculated correctly within the field result. end note]

If a full-width punctuation character appears at the start of a paragraph which also specifies numbering by using the **numPr** element ("ECMA-376 Part 4 §2.3.1.19; numPr (Numbering Definition Instance Reference)"), the compression specified by the **topLinePunct** element is ignored.

[Example: Consider a paragraph that contains a field ending in an ideograph and another paragraph, with numbering, that contains a full-width punctuation character in the first character position:

```
<w:p>
  <w:r>
    <w:fldChar w:fldCharType="begin" />
  </w:r>
  ...
  <w:r>
    <w:t>𠄎</w:t>
  </w:r>
  <w:r>
    <w:fldChar w:fldCharType="end" />
  </w:r>
  <w:r>
    <w:t>1</w:t>
  </w:r>
</w:p>
<w:p>
  <w:pPr>
    <w:numPr>
      ...
    </w:numPr>
  </w:pPr>
  <w:r>
    <w:t> 𠄎</w:t>
  </w:r>
</w:p>
```

Typically, if both the **autoSpaceDN** and **topLinePunct** are *true*, additional spacing is added after the ideograph in the first paragraph and punctuation kerning is applied in the second paragraph (with gridlines added for visual reference):



If this compatibility setting is turned on:

```
<w:compat>
  <w:useWord97LineBreakRules />
```

</w:compat>

Then Word will not add any inter-character spacing at the end of the field and should turn off punctuation kerning in the second paragraph:

| | | | | | | | | |
|----|---|----|---|----|---|----|---|---|
| 平 | 成 | 19 | 年 | 12 | 月 | 20 | 日 | 1 |
| 1. | (| | | | | | | |

end example]

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.480 Part 4 Section 2.15.3.65, wpJustification (Emulate WordPerfect 6.x Paragraph Justification)

a. *The standard does not specify exactly how to emulate WordPerfect 6.x paragraph justification.*

In Office, this element specifies that Word should perform a specific algorithm when determining the contents of each line in a fully justified paragraph (resulting from the use of the **jc** element. This setting typically results in more words being fitted into lines (by reducing inter-word spacing as necessary).

Typically, applying full justification to a paragraph does not change the placement of line breaks, as inter-word spacing is expanded to ensure the resulting text is fully justified. This element, when present with a **val** attribute value of *true* (or equivalent), specifies that Word shall determine the contents of each line in a fully justified paragraph using the following algorithm:

For each line in the fully justified paragraph,

Determine the actual line width, w , in pixels.

Calculate the effective line width by the following factor:

$$w_{\text{effective}} = w_{\text{actual}} + \left(w_{\text{actual}} * \frac{281}{7200} \right)$$

Determine the text that can be displayed in a line of the effective line width.

Decrease the inter-word spacing as necessary to fit that text in the actual line width.

[Example: Consider a WordprocessingML document with one or more paragraphs using full paragraph justification:

```
<w:p>
  <w:pPr>
    <w:jc w:val="both" />
```



```
</w:pPr>
...
</w:p>
```

If this compatibility setting is turned on:

```
<w:compat>
  <w:wpJustification />
</w:compat>
```

Then, for a line 1000 pixels wide, Word would calculate the effective width as follows:

$$w_{\text{effective}} = 1000 + \left(1000 * \frac{281}{7200}\right) = 1039 \text{ pixels}$$

This effective width is then used to determine how much text can be displayed on line. After calculating the text, Word can display the text on the actual line, fully justified. end example]

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.481 Part 4 Section 2.15.3.66, wpSpaceWidth (Space width)

a. *The standard does not specify exactly how to determine the width of the space character for all proportional fonts used in this document.*

(The terms ascent and descent are used as defined in ISO/IEC 14496-22:2007.)

In Office, this element specifies that Word should determine the width of the space character for all proportional fonts used in this document by using the following calculation.

Typically, applications calculate the width of a whitespace character dynamically to optimize for the output device. This element, when present with a **val** attribute value of *true* (or equivalent), specifies that Word should instead use the following algorithm to determine the width of a whitespace character:

$$w_{\text{space}} = \left(\frac{\textit{ascent} + \textit{descent}}{3}\right)$$

where

w_{space} is the width of a space character

ascent is the ascent for the font

descent is the descent for the font

[Example: Consider a WordprocessingML document with this compatibility setting turned on:

```
<w:compat>
  <w:wpSpaceWidth />
</w:compat>
```

If the font applied to a run specified an ascent value of 8 points and a descent value of 2 points, each space in that run would have a width of three and one-third points. end example]

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.482 Part 4 Section 2.16.1, Syntax

a. *The standard states that an arbitrary amount of white space (including none) is supported between tokens.*

Word requires whitespace between the field-type and its instructions, in order to disambiguate custom field names from a field + string instruction.

b. *The standard does not restrict the number of switches used in a field.*

Word allows at most 10 formatting-switches and at most 10 field-specific-switches in a field.

c. *The standard allows more than one picture switch and allows picture switch to occur in any order relative to other field switches.*

Word allows at most one picture switch and requires that picture switch to precede other field switches.

d. *The standard defines a general syntax of fields that includes many field types.*

Word uses the following field types ([§3.1.3.2, Additional Fields](#)) in addition to those already specified by the general syntax of fields in ECMA-376 Office Open XML File Formats [\[ECMA-376\]](#):

document-information:

PRIVATE |

links-and-references:

DDE | DDEAUTO | GLOSSARY | INCLUDE | IMPORT | SHAPE

2.1.483 Part 4 Section 2.16.3.3, Operators

a. *The standard says that the multiplication, division and exponent operators have higher precedence than the percentage operator.*

In Word, the percentage operator has higher precedence than the multiplication, division and exponent operators.

2.1.484 Part 4 Section 2.16.4.1, Date and time formatting

a. *The standard defines some date and time formatting switches.*

Word supports more date formatting switches than are available in the standard. These are defined as follows:

| Date Formatting Picture Items | |
|-------------------------------|---|
| Picture Item | Description |
| aaa | Formats the day of the week or month in an abbreviated form according to the language |

| Date Formatting Picture Items | |
|-------------------------------|--|
| | <p>specified by the lang element ("[ECMA-376] Part 4 §2.3.2.18; lang") on the run containing the field instructions:</p> <p>If the lang element is <i>ja-JP</i> or <i>ko-KR</i>, display in the corresponding language.</p> <p>For all other lang element values, display picture item as text.</p> <p>Multiple instances of the picture item create repeated content.</p> |
| A | <p>Formats the day of the month as a number without a leading zero for single-digit days in Japanese numerals.</p> <p>Multiple instances of the picture item create repeated content.</p> |
| bb | <p>Formats the year as a 2-digit number according to the language specified by the lang element ("[ECMA-376] Part 4 §2.3.2.18; lang") on the run containing the field instructions:</p> <p>If the lang element is <i>zh-TW</i>, <i>zh-CN</i>, <i>zh-HK</i>, <i>zh-SG</i>, or <i>zh-MO</i>, use the Gregorian year [ISO-8601].</p> <p>For all other lang element values, use Thai Buddhist Era year</p> <p>This picture item can modify the behavior of other picture items.</p> <p>Multiple instances of the picture item create repeated content unless the pattern contains the "bbbb" picture item. Those portions are formatted following the description outlined for the "bbbb" picture item.</p> |
| bbbb | <p>Formats the year as a 4-digit number according to the language specified by the lang element ("[ECMA-376] Part 4 §2.3.2.18; lang") on the run containing the field instructions:</p> <p>If the lang element is <i>ZH-TW</i>, <i>zh-CN</i>, <i>zh-HK</i>, <i>zh-SG</i>, or <i>zh-MO</i>, use the Gregorian year [ISO-8601]</p> <p>For all other lang element values, use Thai Buddhist Era year</p> <p>This picture item can modify the behavior of other picture items.</p> <p>Multiple instances of the picture item create repeated content.</p> |
| BB | <p>Formats the year as a 2-digit number.</p> <p>Defaults to the Gregorian [ISO-8601] calendar, but also responds to the <code>\s</code> and <code>\h</code> switches.</p> <p>Multiple instances of the picture item create repeated content as specified by the following:</p> <p>Working from the text direction of the run, create as many groups as possible that contain "BBBB" in each group. Format each group using the description outlined for the "BBBB" picture item.</p> <p>Repeat step 1 for groups of "BB" using the description for that picture item.</p> |
| BBBB | <p>Formats the year as a 4-digit number.</p> <p>Defaults to the Gregorian calendar [ISO-8601], but also responds to the <code>\s</code> and <code>\h</code> switches.</p> <p>Multiple instances of the picture item create repeated content as specified by the "BB" picture item description.</p> |
| d | <p>Formats the day of the week or day of the month as a number without a leading zero for single-digit days.</p> |

| Date Formatting Picture Items | |
|-------------------------------|---|
| | <p>Defaults to the Gregorian calendar [ISO-8601], but also changes in the presence of the \s and \h switches, and the bb or bbbb picture item (to the Thai Buddhist Era calendar).</p> <p>Multiple instances of the picture item create repeated content as specified by the following: Working from the text direction of the run, create as many groups as possible that contain "dddd" in each group. Format each group using the description outlined for the "dddd" picture item.</p> <p>Repeat step 1 for groups of "ddd", "dd", and "d" using the respective description for each picture item group.</p> |
| dd | <p>Formats the day of the week or day of the month as a number with a leading zero for single-digit days.</p> <p>Defaults to the Gregorian calendar [ISO-8601], but also changes in the presence of the \s and \h switches, and the bb or bbbb picture item (to the Thai Buddhist Era calendar).</p> <p>Multiple instances of the picture item create repeated content as specified by the "d" picture item description.</p> |
| ddd | <p>Formats the day of the week or month in its abbreviated form according to the language specified by the lang element ("[ECMA-376] Part 4 §2.3.2.18; lang") on the run containing the field instructions.</p> <p>Defaults to the Gregorian calendar [ISO-8601], but also changes in the presence of the \s and \h switches, and the bb, bbbb, ๑๑๑๑, ๑๑, ๑๑๑๑, ๑๑๑, ๑๑, ๑, ๑๑๑๑, ๑๑๑, ๑๑, and ๑ picture item (to the Thai Buddhist Era calendar).</p> <p>Multiple instances of the picture item create repeated content as specified by the "d" picture item description.</p> |
| dddd | <p>Formats the day of the week as its full name according to the language specified by the lang element ("[ECMA-376] Part 4 §2.3.2.18; lang") on the run containing the field instructions.</p> <p>Defaults to the Gregorian calendar [ISO-8601], but also changes in the presence of the \s and \h switches, and the bb, bbbb, ๑๑๑๑, ๑๑๑, ๑๑๑๑, ๑๑๑, ๑๑, ๑, ๑๑๑๑, ๑๑๑, ๑๑, and ๑ picture item (to the Thai Buddhist Era calendar).</p> <p>Multiple instances of the picture item create repeated content as specified by the "d" picture item description.</p> |
| D | <p>Formats the day of the week or day of the month as a number without a leading zero for single-digit days.</p> <p>Defaults to the Gregorian calendar [ISO-8601], but also changes in the presence of the \s and \h switches, and the bb or bbbb picture item (to the Thai Buddhist Era calendar).</p> <p>Multiple instances of the picture item create repeated content as specified by the following: Working from the text direction of the run, create as many groups as possible that contain "DDDD" in each group. Format each group using the description outlined for the "DDDD" picture item.</p> <p>Repeat step 1 for groups of "DDD", "DD", and "D" using the respective description for each picture item group.</p> |
| DD | <p>Formats the day of the month as a two-digit number (with a leading zero for single-digit days).</p> <p>Defaults to the Gregorian calendar [ISO-8601], but also changes in the presence of the \s and \h switches, and the bb or bbbb picture item (to the Thai Buddhist Era calendar).</p> <p>Multiple instances of the picture item create repeated content as specified by the "D" picture item description.</p> |
| DDD | <p>Formats the day of the week in an abbreviated form according to the language specified by the lang element ("[ECMA-376] Part 4 §2.3.2.18; lang") on the run containing the field instructions.</p> |

| Date Formatting Picture Items | |
|-------------------------------|--|
| | <p>Defaults to the Gregorian calendar [ISO-8601], but also changes in the presence of the \s and \h switches, and the bb or bbbb, ๑๑๑๑, ๑๑, ๑๑๑๑, ๑๑๑, ๑๑๑, ๑๑, ๑, ๑๑๑๑, ๑๑๑, ๑๑, and ๑ picture item (to the Thai Buddhist Era calendar).</p> <p>Multiple instances of the picture item create repeated content as specified by the “D” picture item description.</p> |
| DDDD | <p>Formats the day of the week as its full name according to the language specified by the lang element ("[ECMA-376] Part 4 §2.3.2.18; lang") on the run containing the field instructions.</p> <p>Defaults to the Gregorian calendar [ISO-8601], but also changes in the presence of the \s and \h switches, and the bb, bbbb, ๑๑๑๑, ๑๑, ๑๑๑๑, ๑๑๑, ๑๑๑, ๑๑, ๑, ๑๑๑๑, ๑๑๑, ๑๑, and ๑ picture item (to the Thai Buddhist Era calendar).</p> <p>Multiple instances of the picture item create repeated content as specified by the “D” picture item description.</p> |
| e | <p>Formats the Japanese Emperor Era era with no leading zero for single-digit years.</p> <p>Multiple instances of the picture item create repeated content as specified by the following: Working from the text direction of the run, create as many groups as possible that contain “ee” in each group. Format each group using the description outlined for the “ee” picture item.</p> <p>Repeat step 1 for groups of “e” using the description for that picture item.</p> |
| ee | <p>Formats the Japanese Emperor Era era with a leading zero for single-digit years.</p> <p>Multiple instances of the picture item create repeated content as specified by the “e” picture item description.</p> |
| E | <p>Formats the era according to the language specified by the lang element ("[ECMA-376] Part 4 §2.3.2.18; lang") on the run containing the field instructions:</p> <p>If the lang element is ja-JP, display the Japanese Emperor Era era with no leading zero for single-digit years in the corresponding language.</p> <p>If the lang element is zh-TW, display the Taiwanese year in the corresponding language.</p> <p>For all other values, display the Gregorian year [ISO-8601] as a four-digit number using ja-JP.</p> <p>Multiple instances of the picture item create repeated content as specified by the following: Working from the text direction of the run, create as many groups as possible that contain “EE” in each group. Format each group using the description outlined for the “EE” picture item.</p> <p>Repeat step 1 for groups of “E” using the description for that picture item.</p> |
| EE | <p>Formats the Gregorian year [ISO-8601] as a four-digit number, according to the language specified by the lang element ("[ECMA-376] Part 4 §2.3.2.18; lang") on the run containing the field instructions.</p> <p>If the lang element is ja-JP, zh-TW, zh-CN, zh-HK, zh-SG, or zh-MO display in the corresponding language.</p> <p>For all other lang element values, display in ja-JP.</p> <p>Multiple instances of the picture item create repeated content as specified by the “E” picture</p> |

| Date Formatting Picture Items | |
|-------------------------------|--|
| | item description. |
| g | <p>Formats the era according to the language specified by the lang element ("ECMA-376 Part 4 §2.3.2.18; lang") on the run containing the field instructions:</p> <p>If the lang element is ko-KR or zh-TW, display nothing.</p> <p>For all other lang element values, display Japanese Emperor Era era as its abbreviated form in en-US.</p> <p>Multiple instances of the picture item create repeated content as specified by the following: Working from the text direction of the run, create as many groups as possible that contain "ggg" in each group. Format each group using the description outlined for the "ggg" picture item.</p> <p>From the remaining values, repeat step 1 for groups of "gg" using the description for that picture item.</p> <p>From the remaining values, repeat step 1 for groups of "g" using the description for that picture item.</p> |
| gg | <p>Formats the era according to the language specified by the lang element ("ECMA-376 Part 4 §2.3.2.18; lang") on the run containing the field instructions:</p> <p>If the lang element is ja-JP, display the Japanese Emperor Era era as its abbreviated form in the corresponding language.</p> <p>If the lang element is ko-KR, display the Korean Tangun era as its full name in the corresponding language.</p> <p>If the lang element is zh-TW, display the Taiwanese era as its full name in the corresponding language.</p> <p>For all other lang element values, display the Japanese Emperor Era era as its abbreviated form in ja-JP.</p> <p>Multiple instances of the picture item create repeated content as specified by the "g" picture item description.</p> |
| ggg | <p>Formats the era according to the language specified by the lang element ("ECMA-376 Part 4 §2.3.2.18; lang") on the run containing the field instructions:</p> <p>If the lang element is ja-JP, display the Japanese Emperor Era era as its full name in the corresponding language.</p> <p>If the lang element is ko-KR, display the Korean Tangun era as its full name in the corresponding language.</p> <p>If the lang element is zh-TW, display the Taiwanese era as its full name in the corresponding language.</p> <p>For all other lang element values, display the Japanese Emperor Era era as its full name in ja-JP.</p> <p>Multiple instances of the picture item create repeated content as specified by the "g" picture item description.</p> |
| G | <p>Formats the era according to the language specified by the lang element ("ECMA-376 Part 4</p> |

| Date Formatting Picture Items | |
|-------------------------------|--|
| | <p>§2.3.2.18; lang") on the run containing the field instructions.</p> <p>If the lang element is ko-KR or zh-TW, display nothing.</p> <p>For all other lang element values, display the Japanese Emperor Era era as its abbreviated form in ja-JP.</p> <p>Multiple instances of the picture item create repeated content as specified by the following: Working from the text direction of the run, create as many groups as possible that contain "GG" in each group. Format each group using the description outlined for the "GG" picture item.</p> <p>Repeat step 1 for groups of "G" using the description for that picture item.</p> |
| GG | <p>Formats the era according to the language specified by the lang element ("ECMA-376] Part 4 §2.3.2.18; lang") on the run containing the field instructions.</p> <p>If the lang element is ko-KR, display the Korean Tangun era as its full name in the corresponding language.</p> <p>If the lang element is zh-TW, display the Taiwanese era as its full name in the corresponding language.</p> <p>For all other lang element values, display the Japanese Emperor Era era as its full name in ja-JP.</p> <p>Multiple instances of the picture item create repeated content as specified by the "G" picture item description.</p> |
| M | <p>Formats the month as a number without a leading zero for single-digit months. Defaults to the Gregorian calendar ISO-8601, but also changes in the presence of the \s and \h switches, and the bb or bbbb picture item (to the Thai Buddhist Era calendar).</p> <p>Multiple instances of the picture item create repeated content as specified by the following: Working from the text direction of the run, create as many groups as possible that contain "MMMM" in each group. Format each group using the description outlined for the "MMMM" picture item.</p> <p>Repeat step 1 for groups of "MMM", "MM", and "M" using the respective description for each picture item group.</p> |
| MM | <p>Formats the month as a number with a leading zero for single-digit months.</p> <p>Defaults to the Gregorian calendar ISO-8601, but also changes in the presence of the \s and \h switches, and the bb or bbbb picture item (to the Thai Buddhist Era calendar).</p> <p>Multiple instances of the picture item create repeated content as specified by the "M" picture item description.</p> |
| MMM | <p>Formats the month in its abbreviated form according to the language specified by the lang element ("ECMA-376] Part 4 §2.3.2.18; lang") on the run containing the field instructions.</p> <p>Defaults to the Gregorian calendar ISO-8601, but also changes in the presence of the \s and \h switches, and the bb, bbbb, ๑๑๑๑, ๑๑, ๑๑๑๑, ๑๑๑, ๑๑, ๑, ๑๑๑๑, ๑๑๑, ๑๑, and ๑ picture item (to the Thai Buddhist Era calendar).</p> <p>Multiple instances of the picture item create repeated content as specified by the "M" picture item description.</p> |
| MMMM | <p>Formats the month as its full name according to the language specified by the lang element</p> |

| Date Formatting Picture Items | |
|-------------------------------|---|
| | <p>("[ECMA-376] Part 4 §2.3.2.18; lang") on the run containing the field instructions. Defaults to the Gregorian calendar [ISO-8601], but also changes in the presence of the \s and \h switches, and the bb, bbbb, ๑๑๑๑, ๑๑, ๑๑๑๑, ๑๑๑, ๑๑, ๑, ๑๑๑๑, ๑๑๑, ๑๑, and ๑ picture item (to the Thai Buddhist Era calendar). Multiple instances of the picture item create repeated content as specified by the "M" picture item description.</p> |
| n | <p>Formats the Japanese Emperor Era era with no leading zero for single-digit years. Multiple instances of the picture item create repeated content as specified by the following: Working from the text direction of the run, create as many groups as possible that contain "nn" in each group. Format each group using the description outlined for the "nn" picture item. Repeat step 1 for groups of "n" using the description for that picture item.</p> |
| nn | <p>Formats the Japanese Emperor Era era with leading zero for single-digit years. Multiple instances of the picture item create repeated content as specified by the "n" picture item description.</p> |
| O | <p>Formats the month as a number without a leading zero for single-digit months in Japanese numerals. Multiple instances of the picture item create repeated content.</p> |
| w | <p>Formats the day of the week in an abbreviated form according to the language specified by the lang element ("[ECMA-376] Part 4 §2.3.2.18; lang") on the run containing the field instructions: If the lang element is ja-JP or ko-KR, display in the corresponding language. For all other lang element values, display picture item as literal text. Multiple instances of the picture item create repeated content.</p> |
| W | <p>Formats the day of the week in an abbreviated form according to the language specified by the lang element ("[ECMA-376] Part 4 §2.3.2.18; lang") on the run containing the field instructions: If the lang element is ja-JP, ko-KR, zh-TW, zh-CN, zh-HK, zh-SG, or zh-MO, display in the corresponding language. For all other lang element values, display the picture item as literal text. Multiple instances of the picture item create repeated content.</p> |
| y | <p>Formats the year as a 2-digit number. Defaults to the Gregorian calendar [ISO-8601], but also changes in the presence of the \s and \h switches. Multiple instances of the picture item create repeated content as specified by the following: Working from the text direction of the run, create as many groups as possible that contain "yyyy" in each group. Format each group using the description outlined for the "yyyy" picture item. Repeat step 1 for groups of "yy" and "y" using the respective description for each picture item group.</p> |

| Date Formatting Picture Items | |
|-------------------------------|--|
| yy | <p>Formats the year as a 2-digit number.</p> <p>Defaults to the Gregorian calendar [ISO-8601], but also changes in the presence of the \s and \h switches.</p> <p>Multiple instances of the picture item create repeated content as specified by the “y” picture item description.</p> |
| yyyy | <p>Formats the year as a 4-digit number.</p> <p>Defaults to the Gregorian calendar [ISO-8601], but also changes in the presence of the \s and \h switches.</p> <p>Multiple instances of the picture item create repeated content as specified by the “y” picture item description.</p> |
| Y | <p>Formats the year as a 2-digit number.</p> <p>Defaults to the Gregorian calendar [ISO-8601], but also changes in the presence of the \s and \h switches, and the bb, bbbb, ๑ ๑ ๑ ๑ , and ๑ ๑ picture item (to the Thai Buddhist Era calendar).</p> <p>Multiple instances of the picture item create repeated content as specified by the following: Working from the text direction of the run, create as many groups as possible that contain “YYYY” in each group. Format each group using the description outlined for the “YYYY” picture item.</p> <p>Repeat step 1 for groups of “YY” and “Y” using the respective description for each picture item group.</p> |
| YY | <p>Formats the year as a 2-digit number.</p> <p>Defaults to the Gregorian calendar [ISO-8601], but also changes in the presence of the \s and \h switches, and the bb, bbbb, ๑ ๑ ๑ ๑ , and ๑ ๑ picture item (to the Thai Buddhist Era calendar).</p> <p>Multiple instances of the picture item create repeated content as specified by the “Y” picture item description.</p> |
| YYYY | <p>Formats the year as a 4-digit number.</p> <p>Defaults to the Gregorian calendar [ISO-8601], but also changes in the presence of the \s and \h switches, and the bb, bbbb, ๑ ๑ ๑ ๑ , and ๑ ๑ picture item (to the Thai Buddhist Era calendar).</p> <p>Multiple instances of the picture item create repeated content as specified by the “Y” picture item description.</p> |
| ๑ | <p>Formats the day of the month as a number without a leading zero for single-digit days in Thai numerals.</p> <p>This picture item can modify the behavior of other picture items.</p> <p>Multiple instances of the picture item create repeated content as specified by the following: Working from the text direction of the run, create as many groups as possible that contain “๑ ๑ ๑ ๑ ” in each group. Format each group using the description outlined for the “๑ ๑ ๑ ๑ ” picture item.</p> <p>Repeat step 1 for groups of “๑ ๑ ๑ ๑ ”, “๑ ๑ ” and “๑ ” using the respective description for each picture item group.</p> |
| ๑ ๑ | <p>Formats the day of the month as a two-digit number (with a leading zero for single-digit days) in Thai numerals.</p> <p>This picture item can modify the behavior of other picture items.</p> <p>Multiple instances of the picture item create repeated content as specified by the “๑ ” picture item description.</p> |

| Date Formatting Picture Items | |
|-------------------------------|---|
| ๑ ๑ ๑ | <p>Formats the Thai Buddhist Era day of the week in its abbreviated form in Thai.</p> <p>This picture item can modify the behavior of other picture items.</p> <p>Multiple instances of the picture item create repeated content as specified by the "๑ " picture item description.</p> |
| ๑ ๑ ๑ ๑ | <p>Formats the Thai Buddhist Era day of the week as its full name in Thai.</p> <p>This picture item can modify the behavior of other picture items.</p> <p>Multiple instances of the picture item create repeated content as specified by the "๑ " picture item description.</p> |
| ๑ | <p>Formats the Thai Buddhist Era month as a number without a leading zero for single-digit months in Thai numerals.</p> <p>This picture item can modify the behavior of other picture items.</p> <p>Multiple instances of the picture item create repeated content as specified by the following: Working from the text direction of the run, create as many groups as possible that contain "๑ ๑ ๑ ๑ " in each group. Format each group using the description outlined for the "๑ ๑ ๑ ๑ " picture item.</p> <p>Repeat step 1 for groups of "๑ ๑ ๑ ", "๑ ๑ " and "๑ " using the respective description for each picture item group.</p> |
| ๑ ๑ | <p>Formats the Thai Buddhist Era month as a two-digit number (with a leading zero for single-digit months) in Thai numerals.</p> <p>This picture item can modify the behavior of other picture items.</p> <p>Multiple instances of the picture item create repeated content as specified by the "๑ " picture item description.</p> |
| ๑ ๑ ๑ | <p>Formats the Thai Buddhist Era month in its abbreviated form.</p> <p>This picture item can modify the behavior of other picture items.</p> <p>Multiple instances of the picture item create repeated content as specified by the "๑ " picture item description.</p> |
| ๑ ๑ ๑ ๑ | <p>Formats the Thai Buddhist Era month as its full name.</p> <p>This picture item can modify the behavior of other picture items.</p> <p>Multiple instances of the picture item create repeated content as specified by the "๑ " picture item description.</p> |
| ๑ ๑ | <p>Formats the Gregorian year as a 2-digit number using Thai numerals.</p> <p>This picture item can modify the behavior of other picture items.</p> <p>Multiple instances of the picture item create repeated content as specified by the following: Working from the text direction of the run, create as many groups as possible that contain "๑ ๑ ๑ ๑ " in each group. Format each group using the description outlined for the "๑ ๑ ๑ ๑ " picture item.</p> <p>Repeat step 1 for groups of "๑ ๑ " using the description for that picture item.</p> |
| ๑ ๑ ๑ ๑ | <p>Formats the Gregorian year [ISO-8601] as a 4-digit number using Thai numerals.</p> <p>This picture item can modify the behavior of other picture items.</p> <p>Multiple instances of the picture item create repeated content as specified by the "๑ ๑ " picture item description.</p> |

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

b. *The standard defines a few time picture switches.*

Word supports more time formatting switches than are available in the standard. These are defined as follows:

| Time Formatting Picture Items | |
|--------------------------------------|---|
| Picture Item | Description |
| C | Formats the seconds as a number using Japanese numerals without a leading zero for single-digit seconds. Multiple instances of the picture item create repeated content. |
| h or H | Formats the hour on a 12-hr clock without a leading zero for single-digit hours. Multiple instances of the picture item create repeated content as specified by the following: Working from the text direction of the run, create as many groups as possible that contain "hh" in each group. Format each group using the description outlined for the "hh" picture item. Repeat step 1 for groups of "h" using the description for that picture item. Formats the hour without a leading 0 for single-digit hours. |
| hh | Formats the hour on a 12-hr clock with a leading zero for single-digit hours. Multiple instances of the picture item create repeated content as specified by the "h" picture item description. |
| hh or HH | Formats the hour with a leading 0 for single-digit hours. |
| H | Formats the hour on a 24-hr clock without a leading zero for single-digit hours. Multiple instances of the picture item create repeated content as specified by the following: Working from the text direction of the run, create as many groups as possible that contain "HH" in each group. Format each group using the description outlined for the "HH" picture item. Repeat step 1 for groups of "H" using the description for that picture item. |
| HH | Formats the hour on a 24-hr clock with a leading zero for single-digit hours. Multiple instances of the picture item create repeated content as specified by the "H" picture item description. |
| I | Formats the minutes without a leading zero for single-digit days in Japanese numerals. Multiple instances of the picture item create repeated content. |
| m | Formats the minutes without a leading zero for single-digit minutes. Multiple instances of the picture item create repeated content as specified by the following: Working from the text direction of the run, create as many groups as possible that contain "mm" in each group. Format each group using the description outlined for the "mm" picture item. Repeat step 1 for groups of "m" using the description for that picture item. |
| mm | Formats the minutes with a leading zero for single-digit minutes. Multiple instances of the picture item create repeated content as specified by the "m" picture item description. |
| r | Formats the hour on a 12-hr clock, without a leading zero for single-digit hours, according to the language specified by the lang element (" ECMA-376 Part 4 |

| Time Formatting Picture Items | |
|-------------------------------|---|
| | <p>§2.3.2.18; lang") on the run containing the field instructions, as follows:</p> <p>If the lang element is ja-JP, ko-KR, zh-TW, zh-CN, zh-HK, zh-SG, or zh-MO, display in the corresponding language.</p> <p>For all other lang element values, display in zh-TW.</p> <p>Multiple instances of the picture item create repeated content as specified by the following:</p> <p>Working from the text direction of the run, create as many groups as possible that contain "rr" in each group. Format each group using the description outlined for the "rr" picture item.</p> <p>Repeat step 1 for groups of "r" using the description for that picture item.</p> |
| rr | <p>Formats the hour on a 12-hr clock, without a leading zero for single-digit hours along with 12-hour clock indicators, according to the language specified by the lang element ("ECMA-376 Part 4 §2.3.2.18; lang") on the run containing the field instructions, as follows:</p> <p>If the lang element is ja-JP, ko-KR, zh-TW, zh-CN, zh-HK, zh-SG, or zh-MO, display in the corresponding language.</p> <p>For all other lang element values, display in zh-TW.</p> <p>Multiple instances of the picture item create repeated content as specified by the "r" picture item description.</p> |
| R | <p>Formats the hour on a 24-hr clock, without a leading zero for single-digit hours, according to the language specified by the lang element ("ECMA-376 Part 4 §2.3.2.18; lang") on the run containing the field instructions, as follows:</p> <p>If the lang element is ja-JP, ko-KR, zh-TW, zh-CN, zh-HK, zh-SG, or zh-MO, display in the corresponding language.</p> <p>For all other lang element values, display in zh-TW.</p> <p>Multiple instances of the picture item create repeated content as specified by the following:</p> <p>Working from the text direction of the run, create as many groups as possible that contain "RR" in each group. Format each group using the description outlined for the "RR" picture item.</p> <p>Repeat step 1 for groups of "R" using the description for that picture item.</p> |
| RR | <p>Formats the hour on a 12-hr clock as Arabic numerals, without a leading zero for single-digit hours and 12-hour clock indicators, according to the language specified by the lang element ("ECMA-376 Part 4 §2.3.2.18; lang") on the run containing the field instructions, as follows:</p> <p>If the lang element is ja-JP, ko-KR, zh-TW, zh-CN, zh-HK, zh-SG, or zh-MO, display in the corresponding language.</p> |

| Time Formatting Picture Items | |
|--|--|
| | <p>For all other lang element values, display in zh-TW.</p> <p>Multiple instances of the picture item create repeated content as specified by the "R" picture item description.</p> |
| s | <p>Formats the seconds without a leading zero for single-digit seconds.</p> <p>Multiple instances of the picture item create repeated content as specified by the following:</p> <p>Working from the text direction of the run, create as many groups as possible that contain "ss" in each group. Format each group using the description outlined for the "ss" picture item.</p> <p>Repeat step 1 for groups of "s" using the description for that picture item.</p> |
| ss | <p>Formats the seconds as a two-digit number (with a leading zero for single-digit seconds).</p> <p>Multiple instances of the picture item create repeated content as specified by the "s" picture item description.</p> |
| S | <p>Formats the seconds without a leading zero for single-digit seconds.</p> <p>Multiple instances of the picture item create repeated content as specified by the following:</p> <p>Working from the text direction of the run, create as many groups as possible that contain "SS" in each group. Format each group using the description outlined for the "SS" picture item.</p> <p>Repeat step 1 for groups of "S" using the description for that picture item.</p> |
| SS | <p>Formats the seconds as a two-digit number (with a leading zero for single-digit seconds).</p> <p>Multiple instances of the picture item create repeated content as specified by the "S" picture item description.</p> |
| am/pm or AM/PM | <p>Formats the uppercase 12-hour clock indicators according to the language specified by the lang element ("ECMA-376 Part 4 §2.3.2.18; lang") on the run containing the field instructions.</p> <p>Multiple instances of the picture item creates repeated content. Formats using an am/AM or pm/PM suffix.</p> |
| AMPM or PMAM or JAM/JPM or JPM/JAM | <p>Formats the uppercase or lowercase 12-hour clock indicators according to the language specified by the lang element ("ECMA-376 Part 4 §2.3.2.18; lang") on the run containing the field instructions.</p> <p>Multiple instances of the picture item create repeated content.</p> |
| am/pm or pm/am or A/P or P/A or a/p or p/a | <p>Formats the uppercase or lowercase 12-hour clock indicators according to the language specified by the lang element ("ECMA-376 Part 4 §2.3.2.18; lang") on the run containing the field instructions.</p> <p>Multiple instances of the picture item create repeated content.</p> |
| h | <p>Formats the hour on a 24-hr clock without a leading zero for single-digit hours.</p> <p>Multiple instances of the picture item create repeated content as specified by the following:</p> <p>Working from the text direction of the run, create as many groups as possible that contain "h h" in each group. Format each group using the description outlined for the "h h" picture item.</p> <p>Repeat step 1 for groups of "h" using the description for that picture item.</p> |

| Time Formatting Picture Items | |
|-------------------------------|--|
| hh | Formats the hour on a 24-hr clock as a two-digit number (with a leading zero for single-digit hours). Multiple instances of the picture item create repeated content as specified by the "hh" picture item description. |
| mm | Formats the minutes with a leading zero for single-digit minutes. Multiple instances of the picture item create repeated content as specified by the following: Working from the text direction of the run, create as many groups as possible that contain "mm" in each group. Format each group using the description outlined for the "mm" picture item. Repeat step 1 for groups of "m" using the description for that picture item. |
| m | Formats the minutes without a leading zero for single-digit minutes. Multiple instances of the picture item create repeated content as specified by the "mm" picture item description.. |
| ss | Formats the seconds with a leading zero for single-digit seconds. Multiple instances of the picture item create repeated content as specified by the following: Working from the text direction of the run, create as many groups as possible that contain "ss" in each group. Format each group using the description outlined for the "ss" picture item. Repeat step 1 for groups of "s" using the description for that picture item. |
| s | Formats the seconds without a leading zero for single-digit seconds. Multiple instances of the picture item create repeated content as specified by the "ss" picture item description. |

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.485 Part 4 Section 2.16.4.3, General formatting

- a. *The standard makes no mention of the MERGEFORMATINET switch argument*

Word understands an additional switch argument, MERGEFORMATINET.

When this switch argument is present on an INCLUDEPICTURE or IMPORT field, Word will preserve the dimensions of any picture within the result such that when the result is updated with a new picture, the dimensions of the new picture shall be set to match the dimensions of the original picture.

When this switch argument is present on any other field, Word interprets this the same as a MERGEFORMAT switch.

2.1.486 Part 4 Section 2.16.5.1, ADDRESSBLOCK

- a. *The standard does not explain the format of the argument of the \f switch in the ADDRESSBLOCK field.*

In Word, placeholders in this switch's field-argument reference a **fieldMapData** element. ("[ECMA-376](#) Part 4 §2.14.15; fieldMapData (External Data Source to Merge Field Mapping)"). The placeholder will be expanded to the current mail merge entry in the column specified by the value in

the name element where the **mappedName** of the placeholder matches the **mappedName** of the **fieldMapData**.

The following are the possible placeholders and corresponding mapped merge field names are reserved:

| PLACEHOLDER | ALTERNATE PLACEHOLDER | mappedName |
|---------------|-----------------------|-------------------------------|
| <<_TITLE0_>> | /t0 | Courtesy Title |
| <<_NICK0_>> | /n0 | Nickname |
| <<_FIRST0_>> | /f0 | First Name |
| <<_MIDDLE0_>> | /m0 | Middle Name |
| <<_LAST0_>> | /l0 | Last Name |
| <<_SUFFIX0_>> | /s0 | Suffix |
| <<_TITLE1_>> | /t1 | Spouse/Partner Courtesy Title |
| <<_NICK1_>> | /n1 | Spouse/Partner Nickname |
| <<_FIRST1_>> | /f1 | Spouse/Partner First Name |
| <<_MIDDLE1_>> | /m1 | Spouse/Partner Middle Name |
| <<_LAST1_>> | /l1 | Spouse/Partner Last Name |
| <<_SUFFIX1_>> | /s1 | Spouse/Partner Suffix |
| <<_COMPANY_>> | /c | Company |
| <<_STREET1_>> | /r | Address 1 |
| <<_STREET2_>> | /e | Address 2 |
| <<_CITY_>> | /i | City |
| <<_STATE_>> | /a | State |
| <<_POSTAL_>> | /z | Postal Code |
| <<_COUNTRY_>> | /d | Country or Region |

Word maps the <<_SUFFIX1_>> and /s1 placeholder to mappedName Spouse/Partner Nickname, and maps the placeholder <<_NICK1_>> or /n1 to the empty string.

b. *The standard does not define the format of the argument of the \l switch.*

Word defines the format of this switch to be any Language Code value from the table in ST_LangCode ("[[ECMA-376](#)] Part 4 §2.18.52; ST_LangCode").

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.487 Part 4 Section 2.16.5.2, ADVANCE

a. *The standard allows the advance field to be nested inside another field.*

Word does not carry out the display behavior of the ADVANCE field if it is nested inside another field.

2.1.488 Part 4 Section 2.16.5.4, AUTHOR

- a. *The standard says that an author field must have one of the general-formatting switches.*

In Word, having a general-formatting switch is optional for an author field.

2.1.489 Part 4 Section 2.16.5.5, AUTONUM

- a. *The standard says the \s switch specifies the separator character to use in the field result.*

In Word, if the primary editing language is East Asian, then no separator character is used, even if the \s switch is used.

- b. *The standard allows the AUTONUM field to be nested inside other fields.*

In Word, if the AUTONUM field is nested inside another field no result is displayed.

2.1.490 Part 4 Section 2.16.5.6, AUTONUMLGL

- a. *The standard says the \s switch specifies the trailing separator to use.*

In Word, if the primary editing language is East Asian, then no trailing separator character is used even if the \s switch is specified.

- b. *The standard allows the AUTONUMLGL field to be nested inside another field.*

In Word, if the AUTONUMLGL field is nested inside another field, no result is displayed.

2.1.491 Part 4 Section 2.16.5.7, AUTONUMOUT

- a. *The standard allows the AUTONUMOUT field to be nested inside another field.*

In Word, if the AUTONUMOUT field is nested inside another field, no result is displayed.

2.1.492 Part 4 Section 2.16.5.10, BARCODE

- a. *The standard allows the BARCODE field to be nested inside another field.*

In Word, if the BARCODE field is nested inside another field, no result is displayed.

2.1.493 Part 4 Section 2.16.5.11, BIBLIOGRAPHY

- a. *The standard does not specify default behavior when the \f switch is present without an argument.*

In Word, if the argument for \f is not specified, then the language from the \l switch is used if specified.

- b. *The standard does not define the format of the arguments of the \l and \f switches.*

Word defines the format of these switches to be any language code value from the table in ST_LangCode ("[ECMA-376](#) Part 4 §2.18.52; ST_LangCode").

- c. *The standard says \m switch specifies which single source to show in the bibliography.*

In Word, the \m switch may be used repeatedly to specify a set of sources to show in the bibliography.

d. *The standard allows the /f and /l switches to supply different locales.*

In Word, if the /f and /l switches supply different locales, then the locale supplied with /f is used for /l.

2.1.494 Part 4 Section 2.16.5.12, BIDIOUTLINE

a. *The standard does not specify when to use Arabic numbering or Hebrew numbering for the BIDIOUTLINE field.*

In Word, if no right-to-left editing language is enabled, no result is displayed. If Hebrew is enabled, then Hebrew numbering is used, otherwise Arabic numbering is used.

b. *The standard allows the BIDIOUTLINE field to be nested inside another field.*

In Word, if the BIDIOUTLINE field is nested inside another field, no result is displayed.

2.1.495 Part 4 Section 2.16.5.13, CITATION

a. *The standard says that the \l switch specifies the locale used to format the citation.*

In Word, if a source has a locale set using the LCID element ("[\[ECMA-376\]](#) Part 4 §7.6.2.39; LCID"), then that locale is used to format the source rather than the locale specified in the \l switch.

b. *The standard does not define the format of the argument of the \l switch.*

Word defines the format of this switch to be any Language Code value from the table in ST_LangCode ("[\[ECMA-376\]](#) Part 4 §2.18.52; ST_LangCode").

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

c. *The standard does not describe how \m switch affect other switches in a multi-source citation.*

In Word, other switches affect the previously defined source, defined either by the initial tag in the field or the last tag specified with the \m switch.

d. *The standard says the field value for the CITATION field is the same as for the COMMENTS field.*

In Word, the field value for the CITATION field is a formatted citation for the sources specified within the field.

2.1.496 Part 4 Section 2.16.5.14, COMMENTS

a. *The standard says a COMMENTS field must have a general-formatting-switch.*

In Word, using a general-formatting switch in a COMMENTS field is optional.

2.1.497 Part 4 Section 2.16.5.16, CREATEDATE

a. *The standard says by default the Gregorian calendar is used for the CREATEDATE field.*

In Word, the calendar used for the CREATEDATE field is locale specific.

2.1.498 Part 4 Section 2.16.5.17, DATABASE

a. *The standard does not specify meaning for arguments 512 and 1024 in the \b switch.*

In Word, arguments 512 and 1024 in the \b switch control row and column banding respectively.

b. *The standard does not explain the format of the argument to the \l switch.*

In Word, the text in this switch's field-argument specifies the format, by indexing into the following table:

| Index (Name) | Properties |
|--------------|---|
| 1 (Simple 1) | <p>The table shall have the following properties:</p> <p>The top border shall be a 1 1/2 pt single line.</p> <p>The bottom border shall be a 1 1/2 pt single line.</p> <p>The top border color shall be dark green (00CC00).</p> <p>The bottom border color shall be dark green (00CC00).</p> <p>The vertical alignment shall be top.</p> <p>The header rows shall have the following properties:</p> <p>The bottom border shall be a 3/4 pt single line.</p> <p>The bottom border color shall be dark green (00CC00).</p> <p>The last row shall have the following properties:</p> <p>The top border shall be a 3/4 pt single line.</p> <p>The top border color shall be dark green (00CC00).</p> |
| 2 (Simple 2) | <p>The table shall have the following properties:</p> <p>The vertical alignment shall be top.</p> <p>The header rows shall have the following properties:</p> <p>The bottom border shall be a 1 1/2 pt single line.</p> <p>The bottom border color shall be black (000000).</p> <p>The font shall be bold.</p> <p>The last row shall have the following properties:</p> <p>The top border shall be a 3/4 pt single line.</p> <p>The top border color shall be black (000000).</p> <p>The font shall be bold.</p> <p>The first column shall have the following properties:</p> <p>The right border shall be a 1 1/2 pt single line.</p> <p>The right border color shall be black (000000).</p> <p>The font shall be bold.</p> <p>The first column of the last row shall have the following properties:</p> <p>There shall be no top border.</p> <p>The font shall be bold.</p> <p>The last column shall have the following properties:</p> <p>The left border shall be a 3/4 pt single line.</p> <p>The left border color shall be black (000000).</p> <p>The font shall be bold.</p> <p>The header rows of the last column shall have the following properties:</p> <p>There should be no left border.</p> <p>The font shall be bold.</p> |

| Index (Name) | Properties |
|---------------|---|
| 3 (Simple3) | <p>The table shall have the following properties:</p> <p>The top border shall be a 1 1/2 pt single line.</p> <p>The left border shall be a 1 1/2 pt single line.</p> <p>The bottom border shall be a 1 1/2 pt single line.</p> <p>The right border shall be a 1 1/2 pt single line.</p> <p>The top border color shall be black (000000).</p> <p>The left border color shall be black (000000).</p> <p>The bottom border color shall be black (000000).</p> <p>The right border color shall be black (000000).</p> <p>The vertical alignment shall be top.</p> <p>The header rows shall have the following properties:</p> <p>The foreground shading color shall be black (000000).</p> <p>The background shading shall be white (FFFFFF).</p> <p>The shading pattern shall be solid.</p> <p>The font color shall be white (FFFFFF).</p> <p>The font shall be bold.</p> |
| 4 (Classic 1) | <p>The table shall have the following properties:</p> <p>The top border shall be a 1 1/2 pt single line.</p> <p>The bottom border shall be a 1 1/2 pt single line.</p> <p>The top border color shall be black (000000).</p> <p>The bottom border color shall be black (000000).</p> <p>The vertical alignment shall be top.</p> <p>The header rows shall have the following properties:</p> <p>The bottom border shall be a 3/4 pt single line.</p> <p>The bottom border color shall be black (000000).</p> <p>The font shall be italic.</p> <p>The last row shall have the following properties:</p> <p>The top border shall be a 3/4 pt single line.</p> <p>The top border color shall be black (000000).</p> <p>The first column of the last row shall have the following properties:</p> <p>The font shall be bold.</p> <p>The first column shall have the following properties:</p> <p>The right border shall be a 3/4 pt single line.</p> <p>The right border color shall be black (000000).</p> <p>The header rows of the last column shall have the following properties:</p> <p>The font shall not be italic.</p> <p>The font shall be bold.</p> |
| 5 (Classic 2) | <p>The table shall have the following properties:</p> <p>The top border shall be a 1 1/2 pt single line.</p> <p>The bottom border shall be a 1 1/2 pt single line.</p> <p>The top border color shall be black (000000).</p> <p>The bottom border color shall be black (000000).</p> <p>The vertical alignment shall be top.</p> <p>The header rows shall have the following properties:</p> |

| Index (Name) | Properties |
|---------------|---|
| | <p>The bottom border shall be a 3/4 pt single line. The bottom border color shall be black (000000). The foreground shading color shall be dark magenta (CC00CC). The background shading shall be white (FFFFFF). The shading pattern shall be solid. The font color shall be white (FFFFFF). The last row shall have the following properties: The top border shall be a 3/4 pt single line. The top border color shall be black (000000). The first column of the last row shall have the following properties: The font color shall be dark blue (0000CC). The first column shall have the following properties: The foreground shading color shall be dark gray (C0C0C0). The background shading shall be white (FFFFFF). The shading pattern shall be solid. The font shall be bold. The first column of header rows shall have the following properties: The foreground shading color shall be dark magenta (CC00CC). The background shading shall be white (FFFFFF). The shading pattern shall be solid. The header rows of the last column shall have the following properties: The font shall be bold.</p> |
| 6 (Classic 3) | <p>The table shall have the following properties: The top border shall be a 1 1/2 pt single line. The left border shall be a 1 1/2 pt single line. The bottom border shall be a 1 1/2 pt single line. The right border shall be a 1 1/2 pt single line. The top border color shall be black (000000). The left border color shall be black (000000). The bottom border color shall be black (000000). The right border color shall be black (000000). The vertical alignment shall be top. The table data shall have the following properties: The foreground shading color shall be dark gray (C0C0C0). The background shading shall be white (FFFFFF). The shading pattern shall be solid. The font color shall be dark blue (0000CC). The header rows shall have the following properties: The bottom border shall be a 3/4 pt single line. The bottom border color shall be black (000000). The foreground shading color shall be dark blue (0000CC). The background shading shall be white (FFFFFF). The shading pattern shall be solid. The font color shall be white (FFFFFF). The font shall be bold.</p> |

| Index (Name) | Properties |
|----------------|--|
| | <p>The font shall be italic.</p> <p>The last row shall have the following properties:</p> <p>The top border shall be a 1 1/2 pt single line.</p> <p>The top border color shall be black (000000).</p> <p>The foreground shading color shall be white (FFFFFF).</p> <p>The background shading shall be white (FFFFFF).</p> <p>The shading pattern shall be solid.</p> <p>The font color shall be dark blue (0000CC).</p> <p>The first column shall have the following properties:</p> <p>The font color shall be black (000000).</p> <p>The font shall be bold.</p> <p>The first column of the header row shall have the following properties:</p> <p>The font color shall be black (000000).</p> <p>The font shall be bold.</p> <p>The font shall be italic.</p> |
| 7 (Classic 4) | <p>The table shall have the following properties:</p> <p>The top border shall be a 1 1/2 pt single line.</p> <p>The left border shall be a 3/4 pt single line.</p> <p>The bottom border shall be a 1 1/2 pt single line.</p> <p>The right border shall be a 3/4 pt single line.</p> <p>The top border color shall be black (000000).</p> <p>The left border color shall be black (000000).</p> <p>The bottom border color shall be black (000000).</p> <p>The right border color shall be black (000000).</p> <p>The vertical alignment shall be top.</p> <p>The header rows shall have the following properties:</p> <p>The bottom border shall be a 3/4 pt single line.</p> <p>The bottom border color shall be black (000000).</p> <p>The foreground shading color shall be dark blue (0000CC).</p> <p>The background shading shall be white (FFFFFF).</p> <p>The shading pattern shall be pct50.</p> <p>The font color shall be white (FFFFFF).</p> <p>The font shall be bold.</p> <p>The font shall be italic.</p> <p>The last row shall have the following properties:</p> <p>The bottom border shall be a 3/4 pt single line.</p> <p>The bottom border color shall be black (000000).</p> <p>The foreground shading color shall be black (000000).</p> <p>The background shading shall be white (FFFFFF).</p> <p>The shading pattern shall be pct50.</p> <p>The font color shall be dark blue (0000CC).</p> <p>The first column shall have the following properties:</p> <p>The font shall be bold.</p> |
| 8 (Colorful 1) | <p>The table shall have the following properties:</p> |

| Index (Name) | Properties |
|----------------|---|
| | <p>The top border shall be a 1 1/2 pt single line.</p> <p>The left border shall be a 1 1/2 pt single line.</p> <p>The bottom border shall be a 1 1/2 pt single line.</p> <p>The right border shall be a 1 1/2 pt single line.</p> <p>The top border color shall be dark cyan (00CCCC).</p> <p>The left border color shall be dark cyan (00CCCC).</p> <p>The bottom border color shall be dark cyan (00CCCC).</p> <p>The right border color shall be dark cyan (00CCCC).</p> <p>The font shall be white (FFFFFF).</p> <p>The vertical alignment shall be top.</p> <p>The table data shall have the following properties:</p> <p>The inside horizontal border shall be a 3/4 pt single line.</p> <p>The inside horizontal border color shall be cyan (00FFFF).</p> <p>The foreground shading color shall be dark cyan (00CCCC).</p> <p>The background shading shall be white (FFFFFF).</p> <p>The shading pattern shall be solid.</p> <p>The font color shall be white (FFFFFF).</p> <p>The header rows shall have the following properties:</p> <p>The foreground shading color shall be black (000000).</p> <p>The background shading shall be white (FFFFFF).</p> <p>The shading pattern shall be solid.</p> <p>The font shall be bold.</p> <p>The font shall be italic.</p> <p>The first column shall have the following properties:</p> <p>The foreground shading color shall be dark blue (0000CC).</p> <p>The background shading shall be white (FFFFFF).</p> <p>The shading pattern shall be solid.</p> <p>The font shall be bold.</p> <p>The font shall be italic.</p> <p>The first column of header rows shall have the following properties:</p> <p>The foreground shading color shall be black (000000).</p> <p>The background shading shall be white (FFFFFF).</p> <p>The shading pattern shall be solid.</p> <p>The first column of the last row shall have the following properties:</p> <p>The font shall be bold.</p> <p>The font shall not be italic.</p> |
| 9 (Colorful 2) | <p>The table shall have the following properties:</p> <p>The bottom border shall be a 1 1/2 pt single line.</p> <p>The bottom border color shall be black (000000).</p> <p>The vertical alignment shall be top.</p> <p>The table data shall have the following properties:</p> <p>The foreground shading color shall be yellow (FFFF00).</p> <p>The background shading shall be white (FFFFFF).</p> <p>The shading pattern shall be pct20.</p> <p>The last column shall have the following properties:</p> |

| Index (Name) | Properties |
|-----------------|---|
| | <p>The foreground shading color shall be dark gray (C0C0C0).</p> <p>The background shading shall be white (FFFFFF).</p> <p>The shading pattern shall be solid.</p> <p>The header rows shall have the following properties:</p> <p>The bottom border shall be a 1 1/2 pt single line.</p> <p>The bottom border color shall be black (000000).</p> <p>The foreground shading color shall be dark red (CC0000).</p> <p>The background shading shall be white (FFFFFF).</p> <p>The shading pattern shall be solid.</p> <p>The font color shall be white (FFFFFF).</p> <p>The font shall be bold.</p> <p>The font shall be italic.</p> <p>The first column shall have the following properties:</p> <p>The font shall be bold.</p> <p>The font shall be italic.</p> <p>The first column of the last row shall have the following properties:</p> <p>The font shall be bold.</p> |
| 10 (Colorful 3) | <p>The table shall have the following properties:</p> <p>The top border shall be a 2 1/4 pt single line.</p> <p>The left border shall be a 2 1/4 pt single line.</p> <p>The bottom border shall be a 2 1/4 pt single line.</p> <p>The right border shall be a 2 1/4 pt single line.</p> <p>The inside horizontal border shall be a 3/4 pt single line.</p> <p>The top border color shall be black (000000).</p> <p>The left border color shall be black (000000).</p> <p>The bottom border color shall be black (000000).</p> <p>The right border color shall be black (000000).</p> <p>The inside horizontal border color shall be light gray (C0C0C0).</p> <p>The foreground shading color shall be dark cyan (00CCCC).</p> <p>The background shading shall be white (FFFFFF).</p> <p>The shading pattern shall be pct25.</p> <p>The vertical alignment shall be top.</p> <p>The header rows shall have the following properties:</p> <p>The bottom border shall be a 3/4 pt single line.</p> <p>The bottom border color shall be black (000000).</p> <p>The foreground shading color shall be dark cyan (00CCCC).</p> <p>The background shading shall be white (FFFFFF).</p> <p>The shading pattern shall be solid.</p> <p>The first column shall have the following properties:</p> <p>The left border shall be a 4 1/2 pt single line.</p> <p>The right border shall be a 3/4 pt single line.</p> <p>The left border color shall be black (000000).</p> <p>The right border color shall be black (000000).</p> <p>The foreground shading color shall be dark cyan (00CCCC).</p> <p>The background shading shall be white (FFFFFF).</p> |

| Index (Name) | Properties |
|----------------|---|
| | <p>The shading pattern shall be solid.</p> <p>The first column of header rows shall have the following properties:</p> <p>The foreground shading color shall be black (000000).</p> <p>The background shading shall be white (FFFFFF).</p> <p>The shading pattern shall be solid.</p> <p>The font color shall be white (FFFFFF).</p> <p>The font shall be bold.</p> |
| 11 (Columns 1) | <p>The table shall have the following properties:</p> <p>The top border shall be a 1 1/2 pt single line.</p> <p>The left border shall be a 1 1/2 pt single line.</p> <p>The bottom border shall be a 1 1/2 pt single line.</p> <p>The right border shall be a 1 1/2 pt single line.</p> <p>The top border color shall be black (000000).</p> <p>The left border color shall be black (000000).</p> <p>The bottom border color shall be black (000000).</p> <p>The right border color shall be black (000000).</p> <p>The font shall be bold.</p> <p>The vertical alignment shall be top.</p> <p>Odd columns of table data shall have the following properties:</p> <p>The foreground shading color shall be yellow (FFFF00).</p> <p>The background shading shall be white (FFFFFF).</p> <p>The shading pattern shall be pct25.</p> <p>Even columns of table data shall have the following properties:</p> <p>The foreground shading color shall be black (000000).</p> <p>The background shading shall be white (FFFFFF).</p> <p>The shading pattern shall be pct25.</p> <p>The font shall be bold.</p> <p>The header rows shall have the following properties:</p> <p>The bottom border shall be a 3/4 pt double line.</p> <p>The bottom border color shall be black (000000).</p> <p>The font shall not be bold.</p> <p>The last row shall have the following properties:</p> <p>The font shall not be bold.</p> <p>The first column shall have the following properties:</p> <p>The font shall not be bold.</p> <p>The last row of the first column shall have the following properties:</p> <p>The font shall be bold.</p> <p>The last column shall have the following properties:</p> <p>The font shall not be bold.</p> <p>The header rows of the last column shall have the following properties:</p> <p>The font shall be bold.</p> |
| 12 (Columns 2) | <p>The table shall have the following properties:</p> <p>The font shall be bold.</p> <p>The vertical alignment shall be top.</p> |

| Index (Name) | Properties |
|----------------|--|
| | <p>Odd columns of table data shall have the following properties: The foreground shading color shall be green (00FF00). The background shading shall be white (FFFFFF). The shading pattern shall be pct25.</p> <p>Even columns of table data shall have the following properties: The foreground shading color shall be black (000000). The background shading shall be white (FFFFFF). The shading pattern shall be pct30. The font color shall be dark blue (0000CC). The font shall be bold.</p> <p>The header rows shall have the following properties: The foreground shading color shall be dark blue (0000CC). The background shading shall be white (FFFFFF). The shading pattern shall be solid. The font color shall be white (FFFFFF).</p> <p>The last row shall have the following properties: The font shall not be bold.</p> <p>The first column shall have the following properties: The font color shall be black (000000). The font shall not be bold.</p> <p>The last row of the first column shall have the following properties: The font shall be bold.</p> <p>The last column shall have the following properties: The font shall not be bold.</p> <p>The header rows of the last column shall have the following properties: The font shall be bold.</p> |
| 13 (Columns 3) | <p>The table shall have the following properties: The top border shall be a 3/4 pt single line. The left border shall be a 3/4 pt single line. The bottom border shall be a 3/4 pt single line. The right border shall be a 3/4 pt single line. The inside vertical border shall be a 3/4 pt single line. The top border color shall be dark blue (0000CC). The left border color shall be dark blue (0000CC). The bottom border color shall be dark blue (0000CC). The right border color shall be dark blue (0000CC). The inside vertical border color shall be dark blue (0000CC). The font shall be bold.</p> <p>Applies to odd columns. The vertical alignment shall be top.</p> <p>Odd columns of table data shall have the following properties: The foreground shading color shall be black (000000). The background shading shall be white (FFFFFF). The shading pattern shall be pct10.</p> <p>Even columns of table data shall have the following properties:</p> |

| Index (Name) | Properties |
|----------------|---|
| | <p>The foreground shading color shall be dark gray (C0C0C0).</p> <p>The background shading shall be white (FFFFFF).</p> <p>The shading pattern shall be solid.</p> <p>The header rows shall have the following properties:</p> <p>The foreground shading color shall be dark blue (0000CC).</p> <p>The background shading shall be white (FFFFFF).</p> <p>The shading pattern shall be solid.</p> <p>The font color shall be white (FFFFFF).</p> <p>The last row shall have the following properties:</p> <p>The top border shall be a 3/4 pt single line.</p> <p>The top border color shall be dark blue (0000CC).</p> <p>The font shall not be bold.</p> <p>The first column shall have the following properties:</p> <p>The font shall not be bold.</p> <p>The last column shall have the following properties:</p> <p>The font shall not be bold.</p> <p>The header rows of the last column shall have the following properties:</p> <p>The font shall be bold.</p> |
| 14 (Columns 4) | <p>The table shall have the following properties:</p> <p>The vertical alignment shall be top.</p> <p>Odd columns of table data shall have the following properties:</p> <p>The foreground shading color shall be black (000000).</p> <p>The background shading shall be white (FFFFFF).</p> <p>The shading pattern shall be pct10.</p> <p>Even columns of table data shall have the following properties:</p> <p>The foreground shading color shall be dark cyan (00CCCC).</p> <p>The background shading shall be white (FFFFFF).</p> <p>The shading pattern shall be pct50.</p> <p>The header rows shall have the following properties:</p> <p>The foreground shading color shall be black (000000).</p> <p>The background shading shall be white (FFFFFF).</p> <p>The shading pattern shall be solid.</p> <p>The font color shall be white (FFFFFF).</p> <p>The last row shall have the following properties:</p> <p>The font shall be bold.</p> <p>The last column shall have the following properties:</p> <p>The font shall be bold.</p> |
| 15 (Columns 5) | <p>The table shall have the following properties:</p> <p>The top border shall be a 1 1/2 pt single line.</p> <p>The left border shall be a 1 1/2 pt single line.</p> <p>The bottom border shall be a 1 1/2 pt single line.</p> <p>The right border shall be a 1 1/2 pt single line.</p> <p>The inside vertical border shall be a 3/4 pt single line.</p> <p>The top border color shall be dark gray (CCCCCC).</p> |

| Index (Name) | Properties |
|--------------|---|
| | <p>The left border color shall be dark gray (CCCCCC).</p> <p>The bottom border color shall be dark gray (CCCCCC).</p> <p>The right border color shall be dark gray (CCCCCC).</p> <p>The inside vertical border color shall be light gray (C0C0C0).</p> <p>The vertical alignment shall be top.</p> <p>Even columns of table data shall have the following properties:</p> <p>The foreground shading color shall be dark gray (C0C0C0).</p> <p>The background shading shall be white (FFFFFF).</p> <p>The shading pattern shall be solid.</p> <p>The header rows shall have the following properties:</p> <p>The bottom border shall be a 3/4 pt single line.</p> <p>The bottom border color shall be dark gray (CCCCCC).</p> <p>The font shall be bold.</p> <p>The font shall be italic.</p> <p>The last row shall have the following properties:</p> <p>The top border shall be a 3/4 pt single line.</p> <p>The top border color shall be dark gray (CCCCCC).</p> <p>The font shall be bold.</p> <p>The first column shall have the following properties:</p> <p>The font shall be bold.</p> <p>The last column shall have the following properties:</p> <p>The font shall be bold.</p> |
| 16 (Grid 1) | <p>The table shall have the following properties:</p> <p>The top border shall be a 3/4 pt single line.</p> <p>The left border shall be a 3/4 pt single line.</p> <p>The bottom border shall be a 3/4 pt single line.</p> <p>The right border shall be a 3/4 pt single line.</p> <p>The inside horizontal border shall be a 3/4 pt single line.</p> <p>The inside vertical border shall be a 3/4 pt single line.</p> <p>The top border color shall be black (000000).</p> <p>The left border color shall be black (000000).</p> <p>The bottom border color shall be black (000000).</p> <p>The right border color shall be black (000000).</p> <p>The inside horizontal border color shall be black (000000).</p> <p>The inside vertical border color shall be black (000000).</p> <p>The vertical alignment shall be top.</p> <p>The last column shall have the following properties:</p> <p>The font shall be italic.</p> <p>The last row shall have the following properties:</p> <p>The font shall be italic.</p> |
| 17 (Grid 2) | <p>The table shall have the following properties:</p> <p>The inside horizontal border shall be a 3/4 pt single line.</p> <p>The inside vertical border shall be a 3/4 pt single line.</p> <p>The inside horizontal border color shall be black (000000).</p> |

| Index (Name) | Properties |
|--------------|--|
| | <p>The inside vertical border color shall be black (000000). The vertical alignment shall be top. The header rows shall have the following properties: The font shall be bold. The last row shall have the following properties: The top border shall be a 3/4 pt single line. The top border color shall be black (000000). The font shall be bold. The first column shall have the following properties: The font shall be bold. The last column shall have the following properties: The font shall be bold.</p> |
| 18 (Grid 3) | <p>The table shall have the following properties: The top border shall be a 3/4 pt single line. The left border shall be a 1 1/2 pt single line. The bottom border shall be a 3/4 pt single line. The right border shall be a 1 1/2 pt single line. The inside vertical border shall be a 3/4 pt single line. The top border color shall be black (000000). The left border color shall be black (000000). The bottom border color shall be black (000000). The right border color shall be black (000000). The inside vertical border color shall be black (000000). The vertical alignment shall be top. The header rows shall have the following properties: The bottom border shall be a 3/4 pt single line. The bottom border color shall be black (000000). The foreground shading color shall be yellow (FFFF00). The background shading shall be white (FFFFFF). The shading pattern shall be pct30. The last row shall have the following properties: The font shall be bold. The last column shall have the following properties: The font shall be bold.</p> |
| 19 (Grid 4) | <p>The table shall have the following properties: The left border shall be a 1 1/2 pt single line. The right border shall be a 1 1/2 pt single line. The inside horizontal border shall be a 3/4 pt single line. The inside vertical border shall be a 3/4 pt single line. The left border color shall be black (000000). The right border color shall be black (000000). The inside horizontal border color shall be black (000000). The inside vertical border color shall be black (000000). The vertical alignment shall be top.</p> |

| Index (Name) | Properties |
|--------------|--|
| | <p>The header rows shall have the following properties:</p> <p>The bottom border shall be a 3/4 pt single line.</p> <p>The bottom border color shall be black (000000).</p> <p>The foreground shading color shall be yellow (FFFF00).</p> <p>The background shading shall be white (FFFFFF).</p> <p>The shading pattern shall be pct30.</p> <p>The last row shall have the following properties:</p> <p>The top border shall be a 3/4 pt single line.</p> <p>The top border color shall be black (000000).</p> <p>The foreground shading color shall be yellow (FFFF00).</p> <p>The background shading shall be white (FFFFFF).</p> <p>The shading pattern shall be pct30.</p> <p>The font shall be bold.</p> <p>The last column shall have the following properties:</p> <p>The font shall be bold.</p> |
| 20 (Grid 5) | <p>The table shall have the following properties:</p> <p>The top border shall be a 1 1/2 pt single line.</p> <p>The left border shall be a 1 1/2 pt single line.</p> <p>The bottom border shall be a 1 1/2 pt single line.</p> <p>The right border shall be a 1 1/2 pt single line.</p> <p>The inside horizontal border shall be a 3/4 pt single line.</p> <p>The inside vertical border shall be a 3/4 pt single line.</p> <p>The top border color shall be black (000000).</p> <p>The left border color shall be black (000000).</p> <p>The bottom border color shall be black (000000).</p> <p>The right border color shall be black (000000).</p> <p>The inside horizontal border color shall be black (000000).</p> <p>The inside vertical border color shall be black (000000).</p> <p>The vertical alignment shall be top.</p> <p>The header rows shall have the following properties:</p> <p>The bottom border shall be a 1 1/2 pt single line.</p> <p>The bottom border color shall be black (000000).</p> <p>The last row shall have the following properties:</p> <p>The font shall be bold.</p> <p>The last column shall have the following properties:</p> <p>The font shall be bold.</p> <p>The header rows in the first column shall have the following properties:</p> <p>The top left to bottom right border shall be a 3/4 pt single line.</p> <p>The top left to bottom right border color shall be black (000000).</p> |
| 21 (Grid 6) | <p>The table shall have the following properties:</p> <p>The top border shall be a 1 1/2 pt single line.</p> <p>The left border shall be a 1 1/2 pt single line.</p> <p>The bottom border shall be a 1 1/2 pt single line.</p> <p>The right border shall be a 1 1/2 pt single line.</p> |

| Index (Name) | Properties |
|--------------|---|
| | <p>The inside vertical border shall be a 3/4 pt single line.</p> <p>The top border color shall be black (000000).</p> <p>The left border color shall be black (000000).</p> <p>The bottom border color shall be black (000000).</p> <p>The right border color shall be black (000000).</p> <p>The inside vertical border color shall be black (000000).</p> <p>The vertical alignment shall be top.</p> <p>The header rows shall have the following properties:</p> <p>The bottom border shall be a 3/4 pt single line.</p> <p>The bottom border color shall be black (000000).</p> <p>The font shall be bold.</p> <p>The last row shall have the following properties:</p> <p>The top border shall be a 3/4 pt single line.</p> <p>The top border color shall be black (000000).</p> <p>The first column shall have the following properties:</p> <p>The font shall be bold.</p> <p>The header rows in the first column shall have the following properties:</p> <p>The top left to bottom right border shall be a 3/4 pt single line.</p> <p>The top left to bottom right border color shall be black (000000).</p> |
| 22 (Grid 7) | <p>The table shall have the following properties:</p> <p>The top border shall be a 1 1/2 pt single line.</p> <p>The left border shall be a 1 1/2 pt single line.</p> <p>The bottom border shall be a 1 1/2 pt single line.</p> <p>The right border shall be a 1 1/2 pt single line.</p> <p>The inside horizontal border shall be a 3/4 pt single line.</p> <p>The inside vertical border shall be a 3/4 pt single line.</p> <p>The top border color shall be black (000000).</p> <p>The left border color shall be black (000000).</p> <p>The bottom border color shall be black (000000).</p> <p>The right border color shall be black (000000).</p> <p>The inside horizontal border color shall be black (000000).</p> <p>The inside vertical border color shall be black (000000).</p> <p>The font shall be bold.</p> <p>The vertical alignment shall be top.</p> <p>The header rows shall have the following properties:</p> <p>The bottom border shall be a 1 1/2 pt single line.</p> <p>The bottom border color shall be black (000000).</p> <p>The font shall not be bold.</p> <p>The last row shall have the following properties:</p> <p>The top border shall be a 3/4 pt single line.</p> <p>The top border color shall be black (000000).</p> <p>The font shall not be bold.</p> <p>The first column shall have the following properties:</p> <p>The font shall not be bold.</p> <p>The last column shall have the following properties:</p> |

| Index (Name) | Properties |
|--------------|---|
| | <p>The font shall not be bold.</p> <p>The header rows in the first column shall have the following properties:</p> <p>The top left to bottom right border shall be a 3/4 pt single line.</p> <p>The top left to bottom right border color shall be black (000000).</p> |
| 23 (Grid 8) | <p>The table shall have the following properties:</p> <p>The top border shall be a 3/4 pt single line.</p> <p>The left border shall be a 3/4 pt single line.</p> <p>The bottom border shall be a 3/4 pt single line.</p> <p>The right border shall be a 3/4 pt single line.</p> <p>The inside horizontal border shall be a 3/4 pt single line.</p> <p>The inside vertical border shall be a 3/4 pt single line.</p> <p>The top border color shall be dark blue (0000CC).</p> <p>The left border color shall be dark blue (0000CC).</p> <p>The bottom border color shall be dark blue (0000CC).</p> <p>The right border color shall be dark blue (0000CC).</p> <p>The inside horizontal border color shall be dark blue (0000CC).</p> <p>The inside vertical border color shall be dark blue (0000CC).</p> <p>The vertical alignment shall be top.</p> <p>The header rows shall have the following properties:</p> <p>The foreground shading color shall be dark blue (0000CC).</p> <p>The background shading shall be white (FFFFFF).</p> <p>The shading pattern shall be solid.</p> <p>The font color shall be white (FFFFFF).</p> <p>The font shall be bold.</p> <p>The last row shall have the following properties:</p> <p>The font shall be bold.</p> <p>The last column shall have the following properties:</p> <p>The font shall be bold.</p> |
| 24 (List 1) | <p>The table shall have the following properties:</p> <p>The top border shall be a 1 1/2 pt single line.</p> <p>The left border shall be a 3/4 pt single line.</p> <p>The bottom border shall be a 1 1/2 pt single line.</p> <p>The right border shall be a 3/4 pt single line.</p> <p>The top border color shall be dark cyan (00CCCC).</p> <p>The left border color shall be dark cyan (00CCCC).</p> <p>The bottom border color shall be dark cyan (00CCCC).</p> <p>The right border color shall be dark cyan (00CCCC).</p> <p>The vertical alignment shall be top.</p> <p>Even rows of table data shall have the following properties:</p> <p>The foreground shading color shall be dark gray (C0C0C0).</p> <p>The background shading shall be white (FFFFFF).</p> <p>The shading pattern shall be solid.</p> <p>The header rows shall have the following properties:</p> <p>The bottom border shall be a 3/4 pt single line.</p> |

| Index (Name) | Properties |
|--------------|--|
| | <p>The bottom border color shall be black (000000). The foreground shading color shall be dark gray (C0C0C0). The background shading shall be white (FFFFFF). The shading pattern shall be solid. The font color shall be dark red (CC0000). The font shall be bold. The font shall be italic. The last row shall have the following properties: The top border shall be a 3/4 pt single line. The top border color shall be black (000000). The shading pattern shall be clear. The first column of the last row shall have the following properties: The font shall be bold.</p> |
| 25 (List 2) | <p>The table shall have the following properties: The bottom border shall be a 1 1/2 pt single line. The bottom border color shall be dark gray (CCCCCC). The vertical alignment shall be top. Double banded even rows of table data shall have the following properties: The foreground shading color shall be green (00FF00). The background shading shall be white (FFFFFF). The shading pattern shall be pct20. The header rows shall have the following properties: The bottom border shall be a 3/4 pt single line. The bottom border color shall be black (000000). The foreground shading color shall be dark cyan (00CCCC). The background shading shall be dark green (00CC00). The shading pattern shall be pct75. The font color shall be white (FFFFFF). The font shall be bold. The last row shall have the following properties: The top border shall be a 3/4 pt single line. The top border color shall be black (000000). The shading pattern shall be clear. The first column of the last row shall have the following properties: The font shall be bold.</p> |
| 26 (List 3) | <p>The table shall have the following properties: The top border shall be a 1 1/2 pt single line. The bottom border shall be a 1 1/2 pt single line. The top border color shall be black (000000). The bottom border color shall be black (000000). The vertical alignment shall be top. The table data shall have the following properties: The inside horizontal border shall be a 3/4 pt single line. The inside horizontal border color shall be black (000000).</p> |

| Index (Name) | Properties |
|--------------|--|
| | <p>The header rows shall have the following properties: The bottom border shall be a 1 1/2 pt single line. The bottom border color shall be black (000000). The font color shall be dark blue (0000CC). The font shall be bold.</p> <p>The last row shall have the following properties: The top border shall be a 1 1/2 pt single line. The top border color shall be black (000000). The first column of the last row shall have the following properties: The font color shall be dark blue (0000CC). The font shall be italic.</p> |
| 27 (List 4) | <p>The table shall have the following properties: The top border shall be a 1 1/2 pt single line. The left border shall be a 1 1/2 pt single line. The bottom border shall be a 1 1/2 pt single line. The right border shall be a 1 1/2 pt single line. The inside horizontal border shall be a 3/4 pt single line. The top border color shall be black (000000). The left border color shall be black (000000). The bottom border color shall be black (000000). The right border color shall be black (000000). The inside horizontal border color shall be black (000000). The vertical alignment shall be top.</p> <p>The header rows shall have the following properties: The bottom border shall be a 1 1/2 pt single line. The bottom border color shall be black (000000). The foreground shading color shall be dark gray (CCCCCC). The background shading shall be white (FFFFFF). The shading pattern shall be solid. The font color shall be white (FFFFFF). The font shall be bold.</p> |
| 28 (List 5) | <p>The table shall have the following properties: The top border shall be a 3/4 pt single line. The left border shall be a 3/4 pt single line. The bottom border shall be a 3/4 pt single line. The right border shall be a 3/4 pt single line. The top border color shall be black (000000). The left border color shall be black (000000). The bottom border color shall be black (000000). The right border color shall be black (000000). The vertical alignment shall be top.</p> <p>The table data shall have the following properties: The inside horizontal border shall be a 3/4 pt single line. The inside horizontal border color shall be black (000000).</p> |

| Index (Name) | Properties |
|--------------|--|
| | <p>The header rows shall have the following properties: The bottom border shall be a 1 1/2 pt single line. The bottom border color shall be black (000000). The font shall be bold. The first column shall have the following properties: The font shall be bold.</p> |
| 29 (List 6) | <p>The table shall have the following properties: The top border shall be a 3/4 pt single line. The left border shall be a 3/4 pt single line. The bottom border shall be a 3/4 pt single line. The right border shall be a 3/4 pt single line. The top border color shall be black (000000). The left border color shall be black (000000). The bottom border color shall be black (000000). The right border color shall be black (000000). The foreground shading color shall be black (000000). The background shading shall be white (FFFFFF). The shading pattern shall be pct50. The vertical alignment shall be top. Even rows of table data shall have the following properties: The foreground shading color shall be black (000000). The background shading shall be white (FFFFFF). The shading pattern shall be pct25. The header rows shall have the following properties: The bottom border shall be a 1 1/2 pt single line. The bottom border color shall be black (000000). The font shall be bold. The first column shall have the following properties: The right border shall be a 1 1/2 pt single line. The right border color shall be black (000000). The font shall be bold.</p> |
| 30 (List 7) | <p>The table shall have the following properties: The top border shall be a 1 1/2 pt single line. The left border shall be a 3/4 pt single line. The bottom border shall be a 1 1/2 pt single line. The right border shall be a 3/4 pt single line. The inside horizontal border shall be a 3/4 pt single line. The top border color shall be dark green (00CC00). The left border color shall be dark green (00CC00). The bottom border color shall be dark green (00CC00). The right border color shall be dark green (00CC00). The inside horizontal border color shall be black (000000). The vertical alignment shall be top. Odd rows of table data shall have the following properties:</p> |

| Index (Name) | Properties |
|--------------|---|
| | <p>The foreground shading color shall be yellow (FFFF00). The background shading shall be white (FFFFFF). The shading pattern shall be pct25. Even rows of table data shall have the following properties: The foreground shading color shall be black (000000). The background shading shall be white (FFFFFF). The shading pattern shall be pct20. The header rows shall have the following properties: The bottom border shall be a 1 1/2 pt single line. The bottom border color shall be dark green (00CC00). The foreground shading color shall be dark gray (C0C0C0). The background shading shall be white (FFFFFF). The shading pattern shall be solid. The font shall be bold. The first column shall have the following properties: The font shall be bold. The last row shall have the following properties: The top border shall be a 1 1/2 pt single line. The top border color shall be dark green (00CC00). The shading pattern shall be clear. The font shall be bold. The last column shall have the following properties: The font shall be bold.</p> |
| 31 (List 8) | <p>The table shall have the following properties: The top border shall be a 3/4 pt single line. The left border shall be a 3/4 pt single line. The bottom border shall be a 3/4 pt single line. The right border shall be a 3/4 pt single line. The inside vertical border shall be a 3/4 pt single line. The top border color shall be black (000000). The left border color shall be black (000000). The bottom border color shall be black (000000). The right border color shall be black (000000). The inside vertical border color shall be black (000000). The vertical alignment shall be top. Odd rows of table data shall have the following properties: The foreground shading color shall be red (FF0000). The background shading shall be white (FFFFFF). The shading pattern shall be pct50. Even rows of table data shall have the following properties: The foreground shading color shall be yellow (FFFF00). The background shading shall be white (FFFFFF). The shading pattern shall be pct25. The header rows shall have the following properties: The bottom border shall be a 3/4 pt single line.</p> |

| Index (Name) | Properties |
|--------------|--|
| | <p>The bottom border color shall be black (000000). The foreground shading color shall be yellow (FFFF00). The background shading shall be white (FFFFFF). The shading pattern shall be solid. The font shall be bold. The font shall be italic. The first column shall have the following properties: The font shall be bold. The last row shall have the following properties: The top border shall be a 3/4 pt single line. The top border color shall be black (000000). The font shall be bold. The last column shall have the following properties: The font shall be bold.</p> |
| 32 (3DFx 1) | <p>The table shall have the following properties: The foreground shading color shall be dark gray (C0C0C0). The background shading shall be white (FFFFFF). The shading pattern shall be solid. The vertical alignment shall be top. The header rows shall have the following properties: The bottom border shall be a 3/4 pt single line. The bottom border color shall be dark gray (CCCCCC). The font color shall be dark magenta (CC00CC). The font shall be bold. The last row shall have the following properties: The top border shall be a 3/4 pt single line. The top border color shall be white (FFFFFF). The first column shall have the following properties: The right border shall be a 3/4 pt single line. The right border color shall be dark gray (CCCCCC). The font shall be bold. The last column shall have the following properties: The left border shall be a 3/4 pt single line. The left border color shall be white (FFFFFF). The header rows in the first column shall have the following properties: There shall be no bottom border. There shall be no right border. The header rows of the last column shall have the following properties: There shall be no left border. There shall be no bottom border. The last row of the first column shall have the following properties: There shall be no top border. There shall be no right border. The font color shall be dark blue (0000CC). The last row of the last column shall have the following properties:</p> |

| Index (Name) | Properties |
|--------------|--|
| | <p>There shall be no top border.</p> <p>There shall be no left border.</p> |
| 33 (3DFx 2) | <p>The table shall have the following properties:</p> <p>The foreground shading color shall be dark gray (C0C0C0).</p> <p>The background shading shall be white (FFFFFF).</p> <p>The shading pattern shall be solid.</p> <p>The vertical alignment shall be top.</p> <p>Odd rows of table data shall have the following properties:</p> <p>The top border shall be a 3/4 pt single line.</p> <p>The bottom border shall be a 3/4 pt single line.</p> <p>The top border color shall be dark gray (CCCCCC).</p> <p>The bottom border color shall be white (FFFFFF).</p> <p>The header rows shall have the following properties:</p> <p>The font shall be bold.</p> <p>Odd rows of the first column shall have the following properties:</p> <p>The right border shall be a 3/4 pt single line.</p> <p>There shall be no top border.</p> <p>There shall be no bottom border.</p> <p>The right border color shall be dark gray (CCCCCC).</p> <p>Odd rows of the last column shall have the following properties:</p> <p>The right border shall be a 3/4 pt single line.</p> <p>The right border color shall be white (FFFFFF).</p> <p>The last row of the first column shall have the following properties:</p> <p>The font shall be bold.</p> |
| 34 (3DFx 3) | <p>The table shall have the following properties:</p> <p>The vertical alignment shall be top.</p> <p>Even columns of the table shall have the following properties:</p> <p>The foreground shading color shall be dark gray (C0C0C0).</p> <p>The background shading shall be white (FFFFFF).</p> <p>The shading pattern shall be solid.</p> <p>Odd columns of the table shall have the following properties:</p> <p>The foreground shading color shall be dark gray (C0C0C0).</p> <p>The background shading shall be white (FFFFFF).</p> <p>The shading pattern shall be pct50.</p> <p>Odd rows of table data shall have the following properties:</p> <p>The top border shall be a 3/4 pt single line.</p> <p>The bottom border shall be a 3/4 pt single line.</p> <p>The top border color shall be dark gray (CCCCCC).</p> <p>The bottom border color shall be white (FFFFFF).</p> <p>The header rows shall have the following properties:</p> <p>The font shall be bold.</p> <p>Odd rows of the first column shall have the following properties:</p> <p>The right border shall be a 3/4 pt single line.</p> <p>The top border color shall be automatically determined.</p> |

| Index (Name) | Properties |
|-------------------|--|
| | <p>The bottom border color shall be automatically determined.</p> <p>The right border color shall be dark gray (CCCCCC).</p> <p>Odd rows of the last column shall have the following properties:</p> <p>The right border shall be a 3/4 pt single line.</p> <p>The right border color shall be white (FFFFFF).</p> <p>Applies to odd rows</p> <p>The last row of the first column shall have the following properties:</p> <p>The font shall be bold.</p> |
| 35 (Contemporary) | <p>The table shall have the following properties:</p> <p>The inside horizontal border shall be a 2 1/4 pt single line.</p> <p>The inside vertical border shall be a 2 1/4 pt single line.</p> <p>The inside horizontal border color shall be white (FFFFFF).</p> <p>The inside vertical border color shall be white (FFFFFF).</p> <p>The vertical alignment shall be top.</p> <p>Odd rows of table data shall have the following properties:</p> <p>The foreground shading color shall be black (000000).</p> <p>The background shading shall be white (FFFFFF).</p> <p>The shading pattern shall be pct20.</p> <p>Even rows of table data shall have the following properties:</p> <p>The foreground shading color shall be black (000000).</p> <p>The background shading shall be white (FFFFFF).</p> <p>The shading pattern shall be pct5.</p> <p>The header rows shall have the following properties:</p> <p>The foreground shading color shall be black (000000).</p> <p>The background shading shall be white (FFFFFF).</p> <p>The shading pattern shall be pct20.</p> |
| 36 (Elegant) | <p>The table shall have the following properties:</p> <p>The top border shall be a 3/4 pt double line.</p> <p>The left border shall be a 3/4 pt double line.</p> <p>The bottom border shall be a 3/4 pt double line.</p> <p>The right border shall be a 3/4 pt double line.</p> <p>The inside horizontal border shall be a 3/4 pt single line.</p> <p>The inside vertical border shall be a 3/4 pt single line.</p> <p>The top border color shall be black (000000).</p> <p>The left border color shall be black (000000).</p> <p>The bottom border color shall be black (000000).</p> <p>The right border color shall be black (000000).</p> <p>The inside horizontal border color shall be black (000000).</p> <p>The inside vertical border color shall be black (000000).</p> <p>The vertical alignment shall be top.</p> <p>The header rows shall have the following properties:</p> <p>The font shall be all caps.</p> |
| 37 (Professional) | <p>The table shall have the following properties:</p> <p>The top border shall be a 3/4 pt single line.</p> |

| Index (Name) | Properties |
|---------------|---|
| | <p>The left border shall be a 3/4 pt single line.</p> <p>The bottom border shall be a 3/4 pt single line.</p> <p>The right border shall be a 3/4 pt single line.</p> <p>The inside horizontal border shall be a 3/4 pt single line.</p> <p>The inside vertical border shall be a 3/4 pt single line.</p> <p>The top border color shall be black (000000).</p> <p>The left border color shall be black (000000).</p> <p>The bottom border color shall be black (000000).</p> <p>The right border color shall be black (000000).</p> <p>The inside horizontal border color shall be black (000000).</p> <p>The inside vertical border color shall be black (000000).</p> <p>The vertical alignment shall be top.</p> <p>The header rows shall have the following properties:</p> <p>The foreground shading color shall be black (000000).</p> <p>The background shading shall be white (FFFFFF).</p> <p>The shading pattern shall be solid.</p> <p>The font color shall be white.</p> <p>The font shall be bold.</p> |
| 38 (Subtle 1) | <p>The table shall have the following properties:</p> <p>The interior vertical border shall be a 3/4 pt single line.</p> <p>The interior vertical border shall be black (000000).</p> <p>The vertical alignment shall be top.</p> <p>Even rows of the table shall have the following properties:</p> <p>The bottom border shall be a 3/4 pt single line.</p> <p>The bottom border color shall be black (000000).</p> <p>There shall be no interior vertical border.</p> <p>The foreground shading color shall be dark yellow (CCCC00).</p> <p>The background shading shall be white (FFFFFF).</p> <p>The shading pattern shall be pct25.</p> <p>The header rows shall have the following properties:</p> <p>The top border shall be a 3/4 pt single line.</p> <p>The bottom border shall be a 1 1/2 pt single line.</p> <p>The top border color shall be black (000000).</p> <p>The bottom border color shall be black (000000).</p> <p>The shading pattern shall be clear.</p> <p>The last row shall have the following properties:</p> <p>The top border shall be a 1 1/2 pt single line.</p> <p>The top border color shall be black (000000).</p> <p>The foreground shading color shall be dark magenta (CC00CC).</p> <p>The background shading shall be white (FFFFFF).</p> <p>The shading pattern shall be pct25.</p> <p>The first column shall have the following properties:</p> <p>The right border shall be a 1 1/2 pt single line.</p> <p>The right border color shall be black (000000).</p> <p>The last column shall have the following properties:</p> |

| Index (Name) | Properties |
|---------------|---|
| | <p>The left border shall be a 1 1/2 pt single line. The left border color shall be black (000000). The last column of header rows shall have the following properties: The font shall be bold. The first column of the last row shall have the following properties: The font shall be bold.</p> |
| 39 (Subtle 2) | <p>The table shall have the following properties: The left border shall be a 3/4 pt single line. The right border shall be a 3/4 pt single line. The left border color shall be black (000000). The right border color shall be black (000000). The vertical alignment shall be top. The last column shall have the following properties: The left border shall be a 1 1/2 pt single line. The left border color shall be black (000000). The foreground shading color shall be dark yellow (CCCC00). The background shading shall be white (FFFFFF). The shading pattern shall be pct25. The first column shall have the following properties: The right border shall be a 1 1/2 pt single line. The right border color shall be black (000000). The foreground shading color shall be dark green (00CC00). The background shading shall be white (FFFFFF). The shading pattern shall be pct25. The last row shall have the following properties: The top border shall be a 1 1/2 pt single line. The top border color shall be black (000000). The shading pattern shall be clear. The last row of the first column shall have the following properties: The foreground shading color shall be dark green (00CC00). The background shading shall be white (FFFFFF). The shading pattern shall be pct25. The font shall be bold. The last column of header rows shall have the following properties: The foreground shading color shall be dark yellow (CCCC00). The background shading shall be white (FFFFFF). The shading pattern shall be pct25. The font shall be bold. The header rows shall have the following properties: The bottom border shall be a 1 1/2 pt single line. The bottom border color shall be black (000000). The shading pattern shall be clear.</p> |
| 40 (Web 1) | <p>The table shall have the following properties: The top border shall be a 3/4 pt outset line.</p> |

| Index (Name) | Properties |
|--------------|--|
| | <p>The left border shall be a 3/4 pt outset line.</p> <p>The bottom border shall be a 3/4 pt outset line.</p> <p>The right border shall be a 3/4 pt outset line.</p> <p>The inside horizontal border shall be a 3/4 pt outset line.</p> <p>The inside vertical border shall be a 3/4 pt outset line.</p> <p>The vertical alignment shall be top.</p> <p>The cell spacing shall be 20 twips.</p> |
| 41 (Web 2) | <p>The table shall have the following properties:</p> <p>The top border shall be a 3/4 pt inset line.</p> <p>The left border shall be a 3/4 pt inset line.</p> <p>The bottom border shall be a 3/4 pt inset line.</p> <p>The right border shall be a 3/4 pt inset line.</p> <p>The inside horizontal border shall be a 3/4 pt inset line.</p> <p>The inside vertical border shall be a 3/4 pt inset line.</p> <p>The vertical alignment shall be top.</p> <p>The cell spacing shall be 20 twips.</p> |
| 42 (Web 3) | <p>The table shall have the following properties:</p> <p>The top border shall be a 2 1/4 pt outset line.</p> <p>The left border shall be a 2 1/4 pt outset line.</p> <p>The bottom border shall be a 2 1/4 pt outset line.</p> <p>The right border shall be a 2 1/4 pt outset line.</p> <p>The inside horizontal border shall be a 3/4 pt outset line.</p> <p>The inside vertical border shall be a 3/4 pt outset line.</p> <p>The vertical alignment shall be top.</p> <p>The cell spacing shall be 20 twips.</p> |

c. *The standard does not specify any restriction on the set of SQL instructions included with the \s switch.*

Word does not allow SQL commands that attempt to make changes to the data source (Drop Table, Insert, and so on).

d. *The standard says that if the \l switch is blank, the \b switch value is 16 (Autofit).*

In Word, if the \l switch is blank or omitted, the \b bitmask for Autofit is the only one that will affect the display of the table.

e. *The standard says that if the number of columns is 62 or more, the field inserts the results of a query in columns separated by tabs.*

In Word, the results of the query are inserted in columns separated by tabs if the number of columns in the data source is 64 or more.

f. *The standard says the \c switch specifies a connection string for accessing the data source.*

Word does not use the connection string specified by the \c switch.

2.1.499 Part 4 Section 2.16.5.18, DATE

- a. *The standard says the default calendar is Gregorian.*

In Word, the default calendar depends on the locale.

2.1.500 Part 4 Section 2.16.5.19, DOCPROPERTY

- a. *The standard does not say that Custom document properties can be specified in the DOCPROPERTY field.*

In Word, Custom document properties can be specified by name in the DOCPROPERTY field.

- b. *The standard says that the Keywords and Words categories don't have any equivalent fields.*

In Word, the Keywords and Words categories are equivalent to the Keywords and NumWords fields.

2.1.501 Part 4 Section 2.16.5.22, EQ

- a. *The standard does not specify what the default alignment is for the \a switch.*

In Word, the default alignment for the \a switch is center alignment.

- b. *The standard says that the \o switch allows switches \ac, \al, and \ar.*

In Word, the \o switch allows switches \ac, \al, \ar, and \ad, where the \ad switch specifies justified alignment of the character boxes.

- c. *The standard says that for the \s switch, default for \ai switch is 2 points and no default is listed for \up switch.*

In Word, for the \s switch, there is no default value for \ai switch and the default value for \up switch is 2 points.

- d. *The standard says that switch \l creates a list from an arbitrary number of arguments.*

In Word, switch \l creates a list from an arbitrary number of arguments.

- e. *The standard says that description says that the EQ field computes a mathematical equation.*

In Word, the EQ field is used to display a mathematical equation.

- f. *The standard does not restrict the integer argument of spacing switches \hs and \vs used with \a and spacing switches \ai and \di used with \s.*

Word allows integer arguments between 0 and 127 inclusive for the spacing switches \hs and \vs used with \a and spacing switches \ai and \di used with \s.

- g. *The standard says that the \x switch draws a border segment around a single argument, but then says no arguments are allowed.*

In Word, the \x switch draws a border segment around a single argument and at most one argument is allowed.

- h. *The standard allows the EQ field to be nested inside other fields.*

In Word, if the EQ field is nested inside a field which is not an EQ field, no value is displayed.

2.1.502 Part 4 Section 2.16.5.23, FILENAME

- a. *The standard says a FILENAME field must use a general-formatting-switch.*

In Word, using a general-formatting-switch in a FILENAME field is optional.

2.1.503 Part 4 Section 2.16.5.24, FILESIZE

- a. *The standard says that the switches cause the result to be rounded to the nearest kilobyte or megabyte.*

Word rounds to the nearest thousand bytes and million bytes.

2.1.504 Part 4 Section 2.16.5.26, FORMCHECKBOX

- a. *The standard allows the FORMCHECKBOX field to be nested inside another field.*

In Word, if the FORMCHECKBOX field is nested inside another field, no result is displayed.

2.1.505 Part 4 Section 2.16.5.27, FORMDROPDOWN

- a. *The standard allows the FORMDROPDOWN field to be nested inside another field.*

In Word, if the FORMDROPDOWN field is nested inside another field, no result is displayed.

2.1.506 Part 4 Section 2.16.5.29, GOTOBUTTON

- a. *The standard does not state how to interpret % in field-argument-1 for the GOTOBUTTON field.*

Word uses % in field-argument-1 to specify a percentage of the document as a target for the GOTOBUTTON field.

- b. *The standard allows a GOTOBUTTON field to be nested inside another field.*

In Word, if a GOTOBUTTON field is nested inside another field, no result is displayed.

2.1.507 Part 4 Section 2.16.5.30, GREETINGLINE

- a. *The standard defines \c as both the alternate text switch and the format switch.*

In Word, the format switch is \f.

- b. *The standard does not explain how the \f switch specifies the format of the field value.*

In Word, the text in this switch's field-argument specifies the greeting line format by providing placeholders which reference a **fieldMapData** element ("[ECMA-376](#) Part 4 §2.14.15; fieldMapData (External Data Source to Merge Field Mapping)"). The placeholder will be expanded to the current mail merge entry in the column specified by the value in the name element where the **mappedName** of the placeholder matches the **mappedName** of the **fieldMapData**.

The following are the possible placeholders and corresponding mapped merge field names are reserved:

| PLACEHOLDER | ALTERNATE PLACEHOLDER | mappedName |
|---------------|-----------------------|--|
| _BEFORE_ text | /g text | This placeholder specifies that text shall be inserted before the greeting line. |
| _AFTER_ text | /x text | This placeholder specifies that text shall be inserted after the greeting line. |
| _TITLE0_ | /t0 | Courtesy Title |
| _NICK0_ | /n0 | Nickname |
| _FIRST0_ | /f0 | First Name |
| _LAST0_ | /l0 | Last Name |
| _SUFFIX0_ | /s0 | Suffix |
| _TITLE1_ | /t1 | Spouse/Partner Courtesy Title |
| _FIRST1_ | /f1 | Spouse/Partner First Name |

The following are the possible greeting line formats.

| Greeting Line Formats |
|--|
| <<_TITLE0_>><<_LAST0_>> |
| <<_TITLE0_>><<and _TITLE1_>><<_LAST0_>> |
| <<_TITLE0_>><<_FIRST0_>><<_LAST0_>><<_SUFFIX0_>> |
| <<_TITLE0_>><<_NICK0_>><<_LAST0_>><<_SUFFIX0_>> |
| <<_FIRST0_>><<_LAST0_>><<_SUFFIX0_>> |
| <<_NICK0_>><<_LAST0_>><<_SUFFIX0_>> |
| <<_FIRST0_>><<and _FIRST1_>><<_LAST0_>> |
| <<_NICK0_>><<and _FIRST1_>><<_LAST0_>> |
| <<_FIRST0_>> |
| <<_NICK0_>> |
| <<_FIRST0_>><<and _FIRST1_>> |
| <<_NICK0_>><<and _FIRST1_>> |
| <<Mr. and Mrs. _LAST0_>> |

The <<_BEFORE_ text>> and <<_AFTER_ text>> placeholders may optionally come anywhere within a greeting line format.

<< and >> shall be omitted when displaying the greeting line.

If any of the placeholders in the greeting line format cannot be resolved, or are empty, the text specified in the /e switch shall be the field result. If a greeting line format is not one of the possible

greeting line formats specified in the preceding table, the text specified in the /e switch shall be the field result.

- c. *The standard does not define the format of the argument of the \l switch.*

Word defines the format of this switch to be any language code value from the table in ST_LangCode ("[ECMA-376](#) Part 4 §2.18.52; ST_LangCode").

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

- d. *The standard defines the alternate text switch as \c.*

In Word, the alternate text switch is \e.

2.1.508 Part 4 Section 2.16.5.31, HYPERLINK

- a. *The standard does not list \h as a possible switch for the HYPERLINK field.*

In Word, the \h switch for the HYPERLINK field means that when the hyperlink is invoked, the target of the hyperlink should not be added to a list of viewed hyperlinks.

- b. *The standard does not list \s as a possible switch for the HYPERLINK field.*

In Word, the \s switch is used for the HYPERLINK field with the same meaning as the docLocation attribute of the hyperlink element.

2.1.509 Part 4 Section 2.16.5.35, INDEX

- a. *The standard does not list \o as a switch for the INDEX field.*

Word adds a \o switch that is used with the INDEX field to specify sort order. The text in this switch's field-argument specifies the sort order for Chinese, S for sorting by strokes within radicals and P for sorting by pronunciation. By default, sorting is by strokes.

- b. *The standard says that if the \f switch is omitted, the index will include all entries.*

In Word, if the \f switch is omitted, the index will contain only those entries also lacking \f switches.

- c. *The standard does not limit the length of the field arguments for switches \d, \e, \g, \k, and \l.*

In Word, the \d, \e, \g, \k, and \l switches are all limited to 15 characters.

2.1.510 Part 4 Section 2.16.5.37, KEYWORDS

- a. *The standard says the KEYWORD field must have a general-formatting-switch.*

In Word, using a general-formatting switch in a KEYWORD field is optional.

2.1.511 Part 4 Section 2.16.5.38, LASTSAVEDBY

- a. *The standard says the LASTSAVEDBY field must use a general-formatting-switch.*

In Word using a general-formatting-switch with a LASTSAVEDBY field is optional.

2.1.512 Part 4 Section 2.16.5.39, LINK

- a. *The standard does not explain the format of field-argument-1 of the LINK field.*

Word has a specific format for field-argument-1 of the LINK field. This format specifies an OLE Programmable Identifier (ProgID). This string shall not start with a digit, shall not contain any punctuation (including underscores) other than periods, and shall have a maximum length of 39 characters.

The pieces of a ProgID are separated by periods; whitespace shall not occur within the ProgID. The typical format of a ProgID is:

<Library>.<ComponentName>.<VersionNumber>

b. *The standard says that the LINK field has no field value.*

In Word, the field value of a LINK field is an OLE object representation of the linked file, or the contents of the linked file itself, depending on the switches used.

c. *The standard says the \d switch will prevent the graphic data from being stored with the document.*

When saving a document to OOXML, Word stores the graphic data in the file even if the \d switch is used.

d. *The standard says the \f switch determines the formatting of the linked object when displayed in the document.*

Word ignores the argument of the \f switch.

e. *The standard does not restrict which field switches can be used with each other, even when their definitions are mutually exclusive.*

If more than one switch is present from the set \b, \h, \p, \r, \t, \d, and \u, Word ignores all but the last one.

2.1.513 Part 4 Section 2.16.5.40, LISTNUM

a. *The standard says that If the \l switch is omitted for a new series, the default value is 3.*

In Word, if the \l switch is omitted for a new series, the default value depends on the ilvl of the paragraph.

b. *The standard says a listnum field is associated by default with the NumberFormat list, but does not define such a list.*

In Word, a listnum field is associated by default with the NumberDefault list.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

c. *The standard allows the LISTNUM to be nested inside another field.*

In Word, the LISTNUM field is ignored if nested inside another field.

2.1.514 Part 4 Section 2.16.5.41, MACROBUTTON

a. *The standard allows the MACROBUTTON field to be nested inside another field.*

In Word, if the MACROBUTTON field is nested inside another field, no result is displayed.

2.1.515 Part 4 Section 2.16.5.42, MERGEFIELD

- a. *The standard specifies that the \m switch means the MERGEFIELD field is a mapped field.*

In Word, the \m switch in the MERGEFIELD means the text in field-argument specifies the mappedName of a fieldMapData element.

2.1.516 Part 4 Section 2.16.5.47, NOTEREF

- a. *The standard says the /p switch causes the NOTEREF field value to include the string below or above.*

In Word, the /p switch causes the NOTEREF field value to include a localized version of the strings below or above.

2.1.517 Part 4 Section 2.16.5.52, PAGEREF

- a. *The standard says the value of the PAGEREF field may contain the strings above, below, and "on page #".*

In Word, the value of the PAGEREF field contains versions of the strings above, below, and "on page #" that are translated depending on the language of the text in the document and the language of the current application UI.

2.1.518 Part 4 Section 2.16.5.53, PRINT

- a. *The standard does not specify how field argument 1 defines the drawing rectangle.*

In Word, text in this switch's field-argument-1 defines the drawing rectangle on which the subsequent PostScript instructions operate. It can be any of the keywords from the following table.

| Keyword | Description |
|---------|--|
| cell | Sets the bounding box to equal the size of a one-line cell with the width of the current cell. The bounding box's upper-left corner will be placed by default at the upper-left corner of the current page. The bounding box will be offset to the right by the location of the current column, and offset down by the amount of prior text in the current cell. In Word, the bounding box will be offset to the right by the location of the current column minus the width of the left border, and offset down by the amount of prior text in the current cell minus the width of the top border. |
| page | Sets the bounding box to be equal to the current page. |
| para | Sets the bounding box to be equal to the current paragraph. |
| pic | Sets the bounding box to be equal to the next picture in the current paragraph. Word will only recognize a picture described using VML when using this option. |
| row | Sets the bounding box to equal the size of a one-line row in the current table. The bounding box's upper-left corner will be placed by default at the upper-left corner of the current page. The bounding box will be offset to the right by the location of the current row, and offset down by the amount of prior text in the current cell. In Word, the bounding box will not be offset to the right, and offset down by the amount of prior text in the current cell minus the width of the top border. |

- b. *The standard says that /p is an optional switch for the PRINT field.*

In Word, the /p switch is required for the PRINT field.

c. *The standard does not specify any relationship between the PRINT field and the usePrinterMetrics compatibility option.*

Word does not carry out the behavior specified by the PRINT field unless the usePrinterMetrics compatibility option is on.

d. *The standard allows the PRINT field to be nested inside another field.*

Word will not carry out the behavior specified by the PRINT field if it is nested inside another field.

2.1.519 Part 4 Section 2.16.5.54, PRINTDATE

a. *The standard says the Gregorian calendar is used by default.*

In Word, the default calendar depends on the locale.

2.1.520 Part 4 Section 2.16.5.56, QUOTE

a. *The standard lists date-and-time-formatting switches twice in the list of switches allowed in a QUOTE field and leaves out numeric-formatting-switches.*

In Word, the list of allowable switches in a QUOTE field includes numeric-formatting-switches.

b. *The standard specifies the field value of the QUOTE field as the text in the field argument without any transformation.*

In Word, the text specified by *text* in *field-argument* may specify a character whose code point value is specified in decimal or hexadecimal. Up to three digits shall be used to specify a character using decimal numbers. Up to four digits shall be used to specify a character using hexadecimal (leading 0x or 0X). Word does not allow insertion of the code point 13 as a character.

c. *The standard says that a QUOTE field must contain at least one switch.*

In Word, including a switch in the QUOTE field is optional.

2.1.521 Part 4 Section 2.16.5.57, RD

a. *The standard says that the \p switch indicates relative path for an RD field.*

In Word, the \f indicates a relative path for an RD field.

b. *The standard says the RD field must contain a switch.*

In Word, including a switch in the RD field is optional.

2.1.522 Part 4 Section 2.16.5.58, REF

a. *The standard says the REF must have at least one general-formatting-switch and at most one field-specific-switch.*

In Word, the REF field is allowed to have zero general-formatting-switches and multiple field-specific-switches.

b. *The standard says the \d switch specifies the character sequence used to separate sequence numbers and page numbers, but does not explain what sequence numbers and page numbers.*

In Word, the \d switch specifies the character sequence used to separate sequence numbers placed in the field value by the \n, \r, and \w switches.

c. *The standard provides insufficient information to explain how the \n switch affects the REF field value.*

In Word, for a referenced numbered paragraph, \n causes the field result to be the paragraph number without trailing periods. No information about prior numbered levels is displayed unless it is included as part of the current level.

[Example:

If the referenced paragraph is numbered 2.7.1, the field shall result in 1. end example]

d. *The standard says the REF keyword is not optional when used with bookmarks with the same name as a field.*

In Word, REF is required to be present if the bookmark name is one of the following: CONTROL, DATA, EMBED, HTMLCONTROL, or SUBSCRIBER.

e. *The standard provides insufficient information to explain how the \r switch affects the REF field value.*

In Word, for a referenced numbered paragraph, \r inserts the paragraph number of the bookmarked paragraph in relative context, or relative to its position in the numbering scheme without trailing periods.

[Example:

If the REF field is contained within paragraph 4.3.1 and the referenced paragraph is numbered 4.5.2, the result shall be 5.2. end example]

f. *The standard provides insufficient information to explain how the \w switch affects the REF field value.*

In Word, for a referenced numbered paragraph, \w causes the field result to be the entire paragraph number without trailing periods, regardless of the location of the REF field.

[Example:

If the REF field is contained within paragraph 4.3.1 and the referenced paragraph is numbered 4.5.2, the result shall be 4.5.2. end example]

2.1.523 Part 4 Section 2.16.5.59, REVNUM

a. *The standard says that no switches are used on the REVNUM field.*

Word allows both numeric and general formatting switches for the REVNUM field.

2.1.524 Part 4 Section 2.16.5.60, SAVEDATE

a. *The standard says the default calendar for the SAVEDATE field is Gregorian calendar.*

In Word, the default calendar for the SAVEDATE field depends on the locale.

2.1.525 Part 4 Section 2.16.5.61, SECTION

- a. *The standard says that the SECTION field only allows switches general-formatting-switches.*

In Word, the SECTION field also allows numeric-formatting-switches.

2.1.526 Part 4 Section 2.16.5.62, SECTIONPAGES

- a. *The standard says the SECTIONPAGES field value is the number of the current page within the current section.*

In Word, the SECTIONPAGES field value is the number of pages in the current section.

- b. *The standard says that the only switches the SECTIONPAGES field can take are general-formatting-switches.*

In Word, the SECTIONPAGES field can also take a numeric-formatting-switch.

2.1.527 Part 4 Section 2.16.5.63, SEQ

- a. *The standard does not specify the meaning of the optional bookmark name in the SEQ field.*

In Word, when a bookmark name is used in an SEQ field, the SEQ field displays the result of the SEQ field nearest the bookmark in the document.

- b. *The standard says that the \s switch resets the sequence number to the built-in (integer) heading level specified.*

In Word, the \s switch resets the sequence following a heading of the specified level.

2.1.528 Part 4 Section 2.16.5.65, SKIPIF

- a. *The standard makes no mention of wildcards used in the SKIPIF field.*

In Word, if Operator is = or <>, Expression-2 can contain a question mark (?) to represent any single character, or an asterisk (*) to represent any string of characters. The expression shall be enclosed in quotation marks so that it is compared as a character string. If an asterisk is used in Expression-2, the portion of Expression-1 that corresponds to the asterisk, plus any remaining characters in Expression-2, shall NOT exceed 128 characters.

2.1.529 Part 4 Section 2.16.5.66, STYLeref

- a. *The standard does not fully define what switch \n means in a STYLeref field.*

In Word, for a referenced numbered paragraph, \n causes the field result to be the paragraph number without trailing periods. No information about prior numbered levels is displayed unless it is included as part of the current level.

[Example: If the referenced paragraph is numbered 2.7.1, the field shall result in 1. end example]

- b. *The standard does not mention shorthand for how heading styles may be used.*

Word interprets 1 as heading 1, 2 as heading 2, ... 9 as heading 9 in field-argument.

- c. *The standard specifies different search algorithms for a STYLeref field in a header for a printed document versus an electronic document.*

When a STYLEREF field is in a header in an electronic document, Word uses the search algorithm specified for a STYLEREF field in a header for a printed document.

d. *The standard does not fully define what switch \r means in a STYLEREF field.*

In Word, for a referenced numbered paragraph, \r inserts the paragraph number of the bookmarked paragraph in relative context, or relative to its position in the numbering scheme without trailing periods.

[Example: If the REF field is contained within paragraph 4.3.1 and the referenced paragraph is numbered 4.5.2, the result shall be 5.2. end example]

e. *The standard does not fully define what switch \w means in a STYLEREF field.*

In Word, for a referenced numbered paragraph, \w causes the field result to be the entire paragraph number without trailing periods, regardless of the location of the REF field.

[Example: If the REF field is contained within paragraph 4.3.1 and the referenced paragraph is numbered 4.5.2, the result shall be 4.5.2. end example]

f. *The standard does not fully define what switch \l means in a STYLEREF field.*

In Word, if the STYLEREF field is in a header, then this switch causes the search to go from the bottom of the page to the beginning of the document and then to the end of the document; otherwise, it has no effect.

2.1.530 Part 4 Section 2.16.5.67, SUBJECT

a. *The standard says the SUBJECT field must have a general-formatting-switch.*

In Word, using a general-formatting switch with the SUBJECT field is optional.

2.1.531 Part 4 Section 2.16.5.68, SYMBOL

a. *The standard says the \j switch interprets text in the field argument as the value of a SHIFT-JIS character.*

If the \j switch is used with characters 0x5C or 0x7E, Word does not display their SHIFT-JIS substitutions.

b. *The standard places no restrictions on the Unicode characters which may be used with the \u switch in the SYMBOL field.*

Using the \u switch, Word will not display surrogate pairs or Unicode characters outside of Unicode plane 0 (Basic Multilingual Plane). If a character is specified outside of plane 0, the value will be truncated to one within plane 0.

c. *The standard allows the SYMBOL field to be nested inside another field.*

In Word, if the SYMBOL field is nested inside another field, no result is displayed.

2.1.532 Part 4 Section 2.16.5.69, TA

a. *The standard does not explain how a TOA field uses TA fields.*

In Word, the TOA field will only display an entry for a set of TA fields (containing the same entry for short citation and category) if both a long citation and category are defined.

b. *The standard says the default value for the \c switch is 1 when omitted.*

In Word, there is no default value for the \c switch when omitted.

2.1.533 Part 4 Section 2.16.5.71, TEMPLATE

a. *The standard says the TEMPLATE field must use a general-formatting-switch.*

In Word, using a general-formatting-switch in the TEMPLATE field is optional.

2.1.534 Part 4 Section 2.16.5.72, TIME

a. *The standard says that the Gregorian calendar is used by default in the TIME field.*

In Word, the default calendar used in the TIME field depends on the locale.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.535 Part 4 Section 2.16.5.73, TITLE

a. *The standard says the TITLE field must use a general-formatting-switch.*

In Word, using a general-formatting-switch in the TITLE field is optional.

2.1.536 Part 4 Section 2.16.5.74, TOA

a. *The standard does not define a maximum length for the separator switches \d, \e, \g, and \l.*

Word allows at most 15 characters for each of the separator switches \d, \e, \g, and \l.

2.1.537 Part 4 Section 2.16.5.75, TOC

a. *The standard does not specify behavior when both the \f and \l switches are used.*

In Word, if the \f switch is used after the \l switch, the \f switch supersedes the levels specified to include all levels.

b. *The standard says that the \p switch argument is a sequence of characters.*

Word only allows a single character in the argument of the \p switch and ignores any additional characters.

2.1.538 Part 4 Section 2.16.5.76, USERADDRESS

a. *The standard says a USERADDRESS field must use a general-formatting-switch.*

In Word, using a general-formatting-switch in a USERADDRESS field is optional.

2.1.539 Part 4 Section 2.16.5.77, USERINITIALS

a. *The standard says the USERINITIALS field must use a general-formatting-switch.*

In Word, using a general-formatting-switch in a USERINITIALS field is optional.

2.1.540 Part 4 Section 2.16.5.78, USERNAME

- a. *The standard says a USERNAME field must use a general-formatting-switch.*

In Word, using a general-formatting-switch in a USERNAME field is optional.

2.1.541 Part 4 Section 2.16.5.79, XE

- a. *The standard allows an XE field to specify an unbounded level.*

Word only allows levels up to 7 in an XE field.

2.1.542 Part 4 Section 2.16.9, ddList (Drop-Down List Form Field Properties)

- a. *The standard states that the maxOccurs value for the listEntry child element is unbounded.*

Word limits the occurrences of this element to 25.

2.1.543 Part 4 Section 2.16.10, default (Default Text Box Form Field String)

- a. *The standard does not limit the length of the value of the val attribute.*

Word restricts the value of this attribute to be at most 255 characters.

2.1.544 Part 4 Section 2.16.11, default (Default Drop-Down List Item Index)

- a. *The standard says that if the value exceeds the number of items in the drop-down list, then drop-down list defaults to its first entry.*

In Word, if the value exceeds the number of items, then the drop-down list defaults to an empty entry.

- b. *The standard states that the values of the val attribute are defined by the XML Schema integer datatype.*

Word restricts the value of this attribute to be at least 0 and at most 24.

2.1.545 Part 4 Section 2.16.12, default (Default Checkbox Form Field State)

- a. *The standard says the checkbox default is used when there is no content in the drop-down.*

In Word, the checkbox default is the default state of the checkbox.

2.1.546 Part 4 Section 2.16.17, ffData (Form Field Properties)

- a. *The standard says that if ffData is omitted, the properties associated with the form field shall be based on default values for the form field.*

In Word, if ffData is omitted, the form field is considered invalid and cannot be used or edited.

2.1.547 Part 4 Section 2.16.19, fldData (Custom Field Data)

- a. *The standard allows custom field data in all field types.*

Word only allows custom field data in a specific list of field types, and may fail to open a file which contains custom field data in some other field type.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

- b. *The standard does not restrict the type of data allowed in this element.*

Word expects Base64 encoded data. If the data is not Base64 encoded, then Word may fail to open the file.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.548 Part 4 Section 2.16.20, fldData (Custom Field Data)

- a. *The standard allows custom field data in all field types.*

Word only allows custom field data in a specific list of field types, and may fail to open a file which contains custom field data in some other field type.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

- b. *The standard does not restrict the type of data allowed in this element.*

Word expects Base64 encoded data. If the data is not Base64 encoded, then Word may fail to open the file.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.549 Part 4 Section 2.16.21, fldSimple (Simple Field)

For additional notes that apply to this portion of the standard, please see the notes for [oMath, §7.1.2.77\(d\)](#).

2.1.550 Part 4 Section 2.16.22, format (Text Box Form Field Formatting)

- a. *The standard does not limit the length of the value of the val attribute.*

Word restricts the value of this attribute to be at most 64 characters.

- b. *The standard lists four possible values for format when type is equal to regular.*

Word also uses the values Single byte ... and Double byte

2.1.551 Part 4 Section 2.16.24, hyperlink (Hyperlink)

For additional notes that apply to this portion of the standard, please see the notes for [oMath, §7.1.2.77\(d\)](#).

- a. *The standard does not limit the length of the values of the anchor, docLocation, tgtFrame, and tooltip attributes.*

Word restricts the values of the anchor, docLocation, and tgtFrame attributes to be at most 255 characters and the tooltip attribute to be at most 260 characters.

2.1.552 Part 4 Section 2.16.26, listEntry (Drop-Down List Entry)

- a. *The standard does not limit the length of the value of the val attribute.*

Word restricts the value of this attribute to be at most 255 characters.

2.1.553 Part 4 Section 2.16.27, maxLength (Text Box Form Field Maximum Length)

- a. *The standard states that the values of the val attribute are defined by the XML Schema integer datatype.*

Word defines the values of this attribute with the XML Schema short datatype, with a minimum value of 1.

2.1.554 Part 4 Section 2.16.31, sizeAuto (Automatically Size Form Field)

- a. *The standard says the val attribute can be set to 0, false, or off to turn off this property.*

Word always turns this property on if the element is present regardless of the value of the val attribute.

This note applies to the following products: 2007, 2007 SP1.

2.1.555 Part 4 Section 2.17.1.1, txbxContent (Rich Text Box Content Container)

For additional notes that apply to this portion of the standard, please see the notes for [oMath, §7.1.2.77\(g\)](#); [oMathPara, §7.1.2.78\(d\)](#).

- a. *The standard states that text box content can be placed inside endnotes, footnotes, comments, or other textboxes.*

Word does not allow textbox content inside endnotes, footnotes, comments, or other textboxes.

2.1.556 Part 4 Section 2.17.2.1, subDoc (Anchor for Subdocument Location)

For additional notes that apply to this portion of the standard, please see the notes for [attachedTemplate, §2.15.1.6\(a\)](#); [oMath, §7.1.2.77\(d\)](#).

2.1.557 Part 4 Section 2.17.3.1, altChunk (Anchor for Imported External Content)

- a. *The standard states that the relationship type is <http://schemas.openxmlformats.org/officeDocument/2006/relationships/afChunk>.*

Word uses the relationship type defined in Alternative Format Import Part ("[[ECMA-376](#)] Part 1 §11.3.1; Alternative Format Import Part"): <http://schemas.openxmlformats.org/officeDocument/2006/relationships/afChunk>.

- b. *The standard specifies that applications can support any set of content types.*

Word supports the following content types:

application/vnd.openxmlformats-officedocument.wordprocessingml.document.main+xml

application/vnd.ms-word.document.macroEnabled.main+xml

application/vnd.openxmlformats-officedocument.wordprocessingml.template.main+xml

application/vnd.ms-word.template.macroEnabledTemplate.main+xml

message/rfc822

application/xml
application/rtf
application/xhtml+xml
text/html
text/plain

2.1.558 Part 4 Section 2.18.4, ST_Border (Border Styles)

a. *The standard states that the thinThickLargeGap, thinThickMediumGap, and thinThickSmallGap border styles specify line borders consisting of a thin line contained within a thick line contained within a thick thin.*

Word uses these styles to specify line borders consisting of a thin line contained within a thick line.

b. *The standard places no restrictions on when the inset and outset border styles should be honored.*

Word displays inset and outset borders using the single border style when the border is not a table border or when the resolved value of the tblCellSpacing element for a row is nil.

c. *The standard states that the inset and outset border styles specify a line border consisting of an inset/outset set of lines around the parent object.*

Word displays these border styles as defined in the CSS2 specification [\[CSS-LEVEL2\]](#).

2.1.559 Part 4 Section 2.18.5, ST_BrClear (Line Break Text Wrapping Restart Location)

a. *The standard states that both clear="left" and clear="right" are reversed for bidirectional paragraphs.*

Word always seeks the (visual) right side on bidirectional paragraphs for left and right options.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

b. *The standard says that if clear left break comes after a picture on a line that it should be treated as a clear all.*

Word in this case interprets a value of left as a value of none, except in the bidi case where it will return to the right margin.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.560 Part 4 Section 2.18.8, ST_CaptionPos (Automatic Caption Positioning Values)

a. *The standard allows that left, right, above, and below for automatically inserted captions.*

Word supports only above and below for automatically inserted captions.

2.1.561 Part 4 Section 2.18.10, ST_CharacterSpacing (Character-Level Whitespace Compression Settings)

- a. *The standard states that the ST_CharacterSpacing simple type specifies that whitespace compression is applied to whitespace characters.*

In Word, this simple type applies whitespace compression to full width punctuation characters.

2.1.562 Part 4 Section 2.18.16, ST_DecimalNumber (Decimal Number Value)

- a. *The standard states that the contents of the ST_DecimalNumber simple type are a restriction on the XML Schema integer datatype.*

Word defines the contents of this simple type as being a restriction on the XML Schema int datatype.

2.1.563 Part 4 Section 2.18.17, ST_DisplacedByCustomXml (Location of Custom XML Markup Displacing an Annotation)

- a. *The standard allows the displacedByCustomXml attribute to be used in comments, headers, and footers.*

Word may ignore the parent element under certain conditions when it encounters the displacedByCustomXml attribute in a comment, header, or footer.

2.1.564 Part 4 Section 2.18.18, ST_DocGrid (Document Grid Types)

- a. *The standard states that the snapToChars attribute serves the same purpose as the linesAndChars attribute.*

The snapToChars attribute specifies that each line in the parent section shall be divided into units of the character pitch specified on the **docGrid** element (“[\[ECMA-376\]](#) Part 4 §2.6.5; docGrid (Document Grid)”). Contiguous regions of characters *u* as *eastAsia*, *ascii/hAnsi*, and *cs* using the character classification algorithm are then placed into these units as follows:

eastAsia – One character per grid unit, centered in that unit.

ascii/hAnsi – All characters in the block centered in as many grid units as are necessary to display that text. [Example: If text needs 4.1 grid units of space, it is centered in 5 units. end example]

cs – All characters in the block left-aligned in as many grid units as are necessary to display that text.

The additional line pitch on the **docGrid** element is also added in order to maintain a specific number of lines per page and characters per line.

2.1.565 Part 4 Section 2.18.19, ST_DocPartBehavior (Insertion Behavior Types)

- a. *The standard says that when the behavior is set to pg, the entry is preceded by a blank paragraph whose only content is a page break character.*

In Word, when the behavior is set to pg, the entry is preceded by a page break character, but that page break character is not necessarily the only content in the previous paragraph.

b. *The standard says that when the behavior is set to pg, the entry is put on its own new page by preceding it with a page break.*

In Word, when the behavior is set to pg, the entry is put on its own new page by adding a preceding and trailing page break.

2.1.566 Part 4 Section 2.18.28, ST_Em (Emphasis Mark Type)

a. *The standard does not state which language should be used for the language resolution part of the emphasis mark values.*

Word uses the East Asian language for the language resolution part of these values.

b. *The standard states that the dot value specifies that the emphasis mark is to be rendered using Unicode character 0xFF0E for Japanese and Simplified Chinese, 0x2027 for Traditional Chinese, and 0x02D9 for all other East Asian languages.*

In Word, the emphasis mark is rendered using Unicode character 0x02D9 for Korean, 0x2027 for Traditional Chinese, and 0xFF0E for all other East Asian languages.

c. *The standard specifies that Traditional Chinese shall use Unicode character 0x3002 for the circle value and that it shall be positioned beneath the characters.*

Word does not place the circle emphasis beneath the characters for Traditional Chinese.

d. *The standard specifies that the emphasis mark is a comma character, rendered above each character, using Unicode character 0x3001.*

In Word, a circle type is used instead of the comma type if the East Asian language of the text is Korean or Traditional Chinese.

2.1.567 Part 4 Section 2.18.29, ST_FFHelpTextVal (Help Text Value)

a. *The standard states that the ST_FFHelpTextVal simple type allows strings with 256 characters.*

In Word, the ST_FFHelpTextVal attribute allows strings with at most 255 characters.

2.1.568 Part 4 Section 2.18.30, ST_FFName (Form Field Name Value)

a. *The standard allows strings with at most 65 characters.*

Word allows strings with at most 20 characters.

2.1.569 Part 4 Section 2.18.31, ST_FFStatusTextVal (Status Text Value)

a. *The standard states that the ST_FFStatusTextVal simple type allows strings with up to 140 characters.*

In Word, the ST_FFStatusTextVal simple type allows strings with at most 138 characters.

2.1.570 Part 4 Section 2.18.35, ST_FrameLayout (Frameset Layout Order)

a. *The standard states that the enumeration value none means that no frames shall be shown in the frameset.*

Word interprets an enumeration value of none to mean that one frame should be shown in the frameset.

2.1.571 Part 4 Section 2.18.38, ST_FtnPos (Footnote Positioning Location)

- a. *The standard defines docEnd as a supported value in the footnote position enumeration.*

Word does not support docEnd as a value in the footnote position enumeration.

- b. *In the standard, sectEnd specifies that all footnotes shall be placed at the end of the section in which they are referenced.*

Word treats sectEnd like beneathText and displays footnotes immediately after the last line of text on the page on which the note reference mark appears.

2.1.572 Part 4 Section 2.18.41, ST_HdrFtr (Header or Footer Type)

- a. *The standard states that counting always starts from one for Odd/Even page number calculation.*

In Word, counting depends on page numbering settings of the section.

2.1.573 Part 4 Section 2.18.48, ST_HpsMeasure (Measurement in Half-Points)

- a. *The standard states that the contents of the ST_HpsMeasure simple type are a restriction on the XML Schema unsignedLong datatype.*

Word defines this simple type as being a restriction on the XML Schema unsignedInt datatype, with a minimum value of 2 and a maximum value of 3277.

2.1.574 Part 4 Section 2.18.50, ST_Jc (Horizontal Alignment Type)

- a. *The standard states that the lowKashida setting shall also be applied to Arabic text when the enumeration value is set to both.*

Word does not apply the lowKashida setting when the enumeration value is set to both.

2.1.575 Part 4 Section 2.18.51, ST_Lang (Language Reference)

- a. *The standard allows an unbounded string for ST_Lang.*

Word allows strings of length at most 84.

- b. *The standard states that language identifiers can be specified with strings or hexadecimal values.*

Word does not allow a hexadecimal language code.

2.1.576 Part 4 Section 2.18.52, ST_LangCode (Two Digit Hexadecimal Language Code)

- a. *The standard lists a set of LCID values for language identification.*

Word does not use this form of language identification.

2.1.577 Part 4 Section 2.18.59, ST_MailMergeDataType (Mail Merge Data Source Type Values)

- a. *The standard says the spreadsheet enumeration value means connected to a database by using DDE.*

In Word, the spreadsheet enumeration value means connected to a spreadsheet by using DDE.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.578 Part 4 Section 2.18.64, ST_Merge (Merged Cell Type)

- a. *Standard states that a value of continue shall be ignored if the previous cell does not specify continue or restart*

Word attempts to interpret continue values for vertically merged cells even if none of the previous cells contain a restart value

2.1.579 Part 4 Section 2.18.66, ST_NumberFormat (Numbering Format)

- a. *The standard states that the ideographDigital numbering format specifies that the sequence shall consist of sequential numerical ideographs enclosed in a circle.*

Word does not enclose sequential numerical ideographs of this format in a circle.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

- b. *The standard states that the aiueo and aiueoFullWidth numbering formats specify sequences that shall consist of hiragana characters.*

Word uses these numbering formats to specify sequences that will consist of Katakana characters.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

- c. *The standard states that the ideographEnclosedCircle numbering format specifies that the sequence shall consist of sequential numerical ideographs enclosed in a circle.*

Word encloses sequential numerical ideographs of this format in parentheses.

- d. *The standard states that the hindiConsonants attribute specifies that the sequence shall consist of Hindi consonants, and that the hindiVowels attribute specifies that the sequence shall consist of Hindi vowels.*

Word uses the hindiConsonants attribute to specify that the sequence shall consist of Hindi vowels, and the hindiVowels attribute to specify that the sequence shall consist of Hindi consonants.

- e. *The numbering styles in the standard are not specified in enough detail for implementations to be fully interoperable.*

Word uses the numbering styles specified in "[\[ISO/IEC-29500-1\]](#) §17.18.59".

2.1.580 Part 4 Section 2.18.67, ST_OnOff (On/Off Value)

- a. *The standard states that the default value for the ST_OnOff simple type is on, 1, or true.*

Word uses the default value specified by the parent element.

2.1.581 Part 4 Section 2.18.68, ST_PageBorderDisplay (Page Border Display Options)

- a. *The standard states that the value notFirstPage specifies that the page border shall be displayed on only the first page in the parent section.*

Word uses this value to specify that the page border shall be displayed on all pages except the first page in the parent section.

2.1.582 Part 4 Section 2.18.75, ST_PointMeasure (Measurement in Points)

- a. *The standard states that the contents of the ST_PointMeasure simple type are defined by the ST_UnsignedDecimalNumber simple type.*

Word restricts the contents of this simple type to be at least 0 and at most 31.

2.1.583 Part 4 Section 2.18.77, ST_ProofErr (Proofing Error Type)

- a. *The standard states that the gramStart attribute indicates the end of a grammatical error and the gramEnd attribute indicates the start of a grammatical error.*

Word uses the gramStart attribute to indicate the start of a grammatical error and the gramEnd attribute to indicate the end of a grammatical error.

2.1.584 Part 4 Section 2.18.82, ST_RubyAlign (Phonetic Guide Text Alignment)

- a. *The standard states that for the left enumeration value ruby text will be aligned left and for the right enumeration value ruby text will be aligned right.*

Word changes left to right and left to right when the run layout is right-to-left.

2.1.585 Part 4 Section 2.18.85, ST_Shd (Shading Patterns)

- a. *The standard specifies an enumeration value nil with the same meaning as clear.*

Word does not use the enumeration value nil and treats the nil value as solid.

2.1.586 Part 4 Section 2.18.87, ST_SignedHpsMeasure (Signed Measurement in Half-Points)

- a. *The standard states that ST_SignedHpsMeasure allows unbounded integers.*

Word only reads 32-bit integers for ST_SignedHpsMeasure.

2.1.587 Part 4 Section 2.18.88, ST_SignedTwipsMeasure (Signed Measurement in Twentieths of a Point)

- a. *The standard states that ST_SignedTwipsMeasure allows unbounded integers.*

Word only reads 32-bit integers for ST_SignedTwipsMeasure.

2.1.588 Part 4 Section 2.18.91, ST_TabJc (Custom Tab Stop Type)

a. *The standard states that the decimal value specifies that the current tab stop shall result in a location in the document where all following text is aligned around the first decimal character in the following text runs.*

In Word, if the value is decimal, the tab stop results in a location in the document where all following text is aligned around the first decimal separator in the following text runs.

b. *The standard does not state how to interpret the decimal attribute if there is no decimal separator.*

Word aligns text around the implicit decimal separator after the last digit of the first numerical value appearing in the following text if there is no decimal separator.

2.1.589 Part 4 Section 2.18.100, ST_TextDirection (Text Flow Direction)

a. *The standard states that tbLrV orients lines from top to bottom, left to right and tbRlV orients lines from top to bottom, right to left.*

Word uses the text direction specified by tbLrV for both tbLrV and tbRlV.

b. *The standard states that btLr orients the text from bottom to top, then left to right.*

Word does not respect this value when used at the section level.

2.1.590 Part 4 Section 2.18.101, ST_TextEffect (Animated Text Effects)

a. *The standard specifies colors for each of the enumeration values.*

Word will use different colors in order to show the effect if the page background and system color background are too similar.

2.1.591 Part 4 Section 2.18.102, ST_TextScale (Text Expansion/Compression Percentage)

a. *The standard states that the valid range for ST_TextScale is between 0 and 600.*

Word requires that the valid range be between 1 and 600.

2.1.592 Part 4 Section 2.18.106, ST_UcharHexNumber (Two Digit Hexadecimal Number Value)

a. *The standard states that the contents of the ST_UcharHexNumber simple type should have exactly two hexadecimal digits.*

Word allows the contents of this simple type to have one hexadecimal digit when the first digit is implied to be 0.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.593 Part 4 Section 2.18.108, ST_UnsignedDecimalNumber (Unsigned Decimal Number Value)

a. *The standard states that the contents of the ST_UnsignedDecimalNumber simple type are a restriction on the XML Schema unsignedLong datatype.*

Word defines the contents of this simple type as being a restriction on the XML Schema unsignedInt datatype.

2.1.594 Part 4 Section 2.18.111, ST_VerticalJc (Vertical Alignment Type)

- a. *The standard says that both justification is not used if multiple sections are on a page, and does not specify behavior for other alignment values if multiple sections are on a page.*

If there are multiple sections on one page and they have different vertical alignment, then Word will ignore the vertical alignment specified and will use the default value of top.

2.1.595 Part 4 Section 2.18.112, ST_View (Document View Values)

- a. *The standard states that the enumeration value normal renders the document in outline view.*

In Word, the enumeration value normal renders the document in a draft view.

2.1.596 Part 4 Section 2.18.113, ST_Wrap (Text Wrapping around Text Frame Type)

- a. *The standard's description for the enumeration value none is the same as notBeside.*

The behavior of the enumeration values none and notBeside are implemented distinctly by Word. Word implements none by not allowing text to wrap around the remaining space on each line around the text frame.

2.1.597 Part 4 Section 3.2.1, bookViews (Workbook Views)

- a. *The standard states that the maxOccurs value for the workbookView child element is unbounded.*

Excel limits the occurrences of this element to 2147483647.

2.1.598 Part 4 Section 3.2.2, calcPr (Calculation Properties)

- a. *The standard states that on and off are valid values of the calcCompleted attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

- b. *The standard states that on and off are valid values of the calcOnSave attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

- c. *The standard states that on and off are valid values of the concurrentCalc attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

- d. *The standard states that on and off are valid values of the forceFullCalc attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

e. *The standard does not specify a default value for the forceFullCalc attribute.*

Excel uses a default value of false for this attribute.

f. *The standard states that on and off are valid values of the fullCalcOnLoad attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

g. *The standard states that on and off are valid values of the fullPrecision attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

h. *The standard states that on and off are valid values of the iterate attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

i. *The standard specifies that iterateCount attribute iterations will always take place.*

Office will stop iteration if values change by less than the iterateDelta attribute value.

j. *The standard does not specify a default value for the calcId attribute.*

Excel uses a default value of 0 for this attribute.

2.1.599 Part 4 Section 3.2.3, customWorkbookView (Custom Workbook View)

a. *The standard states that the values of the windowWidth attribute are defined by the XML Schema unsignedInt datatype.*

Excel restricts the value of this attribute to be at most 2147483647.

b. *The standard states that the values of the mergeInterval attribute are defined by the XML Schema unsignedInt datatype.*

Excel restricts the value of this attribute to be 0 or at least 5 and at most 1440.

c. *The standard states that the values of the tabRatio attribute are defined by the XML Schema unsignedInt datatype.*

Excel restricts the value of this attribute to be at most 1000.

d. *The standard states that on and off are valid values of the autoUpdate attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

e. *The standard states that on and off are valid values of the changesSavedWin attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

f. *The standard states that on and off are valid values of the includeHiddenRowCol attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

g. *The standard states that on and off are valid values of the IncludePrintSettings attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

h. *The standard states that on and off are valid values of the maximized attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

i. *The standard states that on and off are valid values of the minimized attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

j. *The standard states that on and off are valid values of the onlySync attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

k. *The standard states that on and off are valid values of the personalView attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

l. *The standard states that on and off are valid values of the showFormulaBar attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

m. *The standard states that on and off are valid values of the showHorizontalScroll attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

n. *The standard states that on and off are valid values of the showSheetTabs attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

o. *The standard states that on and off are valid values of the showStatusbar attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

p. *The standard states that on and off are valid values of the showVerticalScroll attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

q. *The standard states that the values of the activeSheetId attribute are defined by the XML Schema unsignedInt datatype.*

Excel restricts the value of this attribute to be at least 1 and at most 65534.

r. *The standard states that setting the showStatusbar attribute equal to false or 0 will hide the status bar.*

Office does not hide the status bar when the showStatusbar attribute is set to false or 0.

s. *The standard states that the values of the guid attribute are defined by the ST_Guid simple type.*

Excel requires that the guid attribute value not be a null guid (00000000-0000-0000-0000-000000000000).

t. *The standard does not limit the length of the value of the name attribute.*

Excel restricts the value of this attribute to be at most 255 UTF-16 code units after escape sequences have been replaced with characters.

u. *The standard states that the values of the windowHeight attribute are defined by the XML Schema unsignedInt datatype.*

Excel restricts the value of this attribute to be at most 2147483647.

v. *The standard states that the windowWidth attribute is required.*

Excel does not require this attribute.

w. *The standard states that the windowHeight attribute is required.*

Excel does not require this attribute.

2.1.600 Part 4 Section 3.2.4, customWorkbookViews (Custom Workbook Views)

a. *The standard states that the maxOccurs value for the customWorkbookView child element is unbounded.*

Excel limits the occurrences of this element to 2147483647.

2.1.601 Part 4 Section 3.2.5, definedName (Defined Name)

a. *The standard states that the contents of this element are an extension on the ST_Formula simple type.*

Excel requires the contents of this element to follow the grammar for a name formula, as defined in Name Formulas ([§3.2.3.1.4, Name Formulas](#)).

b. *The standard says that @customMenu is used.*

In Excel, @customMenu is reserved and unused.

c. *The standard says that @description is used.*

In Excel, @description is reserved and unused.

d. *The standard says that @help is used.*

In Excel, @help is reserved and unused.

e. *The standard says that @statusBar is used.*

In Excel, @statusBar is reserved and unused.

f. *The standard says that @shortcutKey is used.*

In Excel, @shortcutKey is reserved and unused.

g. *The standard says that @xlm is used.*

In Excel, @xlm is reserved and unused.

h. *The standard says that @vbProcedure is used.*

In Excel, @vbProcedure is reserved and unused.

i. *The standard says that @functionGroupId is used.*

In Excel, @functionGroupId is reserved and unused.

j. *The standard does not limit the length of the value of the comment attribute.*

Excel restricts the value of this attribute to be at most 255 characters before escaping.

k. *The standard does not limit the length of the value of the name attribute.*

Excel restricts the value of this attribute to be at least 1 and at most 255 characters.

l. *The standard specifies localSheetID is the sheet index in this workbook where data from an external reference is displayed.*

Office uses this index for sheet-local names to specify the sheet on which the name is defined.

m. *The standard states that built-in names reserved by SpreadsheetML begin with _xlnm.*

Office assumes that all names that begin with _xl are restricted.

n. *The standard does not state restrictions around uniqueness of definedName elements.*

If the attribute **@localSheetId** is used on a **definedName**, the defined name is local and its **@name** must be unique among the other defined names for the sheet ID. If the **@localSheetId** attribute is not used, the defined name must be unique among the other defined names that do not use the attribute.

o. *The standard states that on and off are valid values of the publishToServer attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

p. *The standard states that on and off are valid values of the workbookParameter attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

q. *The standard states that on and off are valid values of the hidden attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

r. *The standard makes no mention of an xml:space attribute.*

Excel uses this attribute to specify, using the W3C space preservation rules, how white space should be handled for the element's contents; its allowed values are defined by the XML 1.0 specification.

s. *The standard says that @function is used.*

In Excel, @function is reserved and unused.

t. *The standard states that the values of the name attribute are defined by the ST_Xstring simple type.*

Excel requires the value of this attribute to meet the restrictions defined in Names ("[ECMA-376](#) Part 4 §3.17.2.5; Names").

u. *The standard states that the values of the localSheetId attribute are defined by the XML Schema unsignedInt datatype.*

Excel restricts the value of this attribute to be at most 32766.

2.1.602 Part 4 Section 3.2.6, definedNames (Defined Names)

a. *The standard states that the maxOccurs value for the definedName child element is unbounded.*

Excel limits the occurrences of this element to 2147483647.

2.1.603 Part 4 Section 3.2.7, ext (Extension)

a. *The standard implies that the minOccurs value for the any child element is 1.*

Excel allows zero occurrences of this element.

2.1.604 Part 4 Section 3.2.9, externalReferences (External References)

a. *The standard states that the maxOccurs value for the externalReference child element is unbounded.*

Excel limits the occurrences of this element to 65534.

2.1.605 Part 4 Section 3.2.11, fileRecoveryPr (File Recovery Properties)

a. *The standard states that on and off are valid values of the autoRecover attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

b. *The standard states that on and off are valid values of the crashSave attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

c. *The standard states that on and off are valid values of the dataExtractLoad attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

d. *The standard states that on and off are valid values of the repairLoad attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

e. *The standard states that applications typically mark the autorecover attribute as true only after crash.*

Excel unmarks the autorecover attribute after crash.

2.1.606 Part 4 Section 3.2.12, fileSharing (File Sharing)

a. *The standard allows the userName attribute to be any length.*

Office requires that if present, the value of the userName attribute must be 1 to 54 characters long.

b. *The standard states that the userName and reservationPassword attributes are optional.*

Office requires that the userName attribute is present if the reservationPassword attribute exists.

c. *The standard states that this setting uses a specific reservationPassword attribute to store the password hash for unlocking revisions in the workbook.*

In Office, when the HKCU/Software/Microsoft/Office/<VERSION>/Common/Security/UseIsoPasswordVerifier registry key is set to 1, the XML for file sharing is written by using the XML attribute structure in the following table.

| Name | Description |
|-----------------------|---|
| algorithm Name | The name of the cryptographic hashing algorithm used to generate the hash value. Only those algorithms that are installed in the operating system's cryptographic subsystem can be utilized by Office. The hash algorithm names, described in the following table, are reserved. MD2 <i>Specifies that the MD2 algorithm, as defined by RFC 1319, shall be used.</i> <i>[Note: It is recommended that applications should avoid using this algorithm to store new hash values, because of publicly known breaks. end note]</i> MD4 <i>Specifies that the MD4 algorithm, as defined by RFC 1320, shall be used.</i> <i>[Note: It is recommended that applications should avoid using this algorithm to store new hash values, because of publicly known breaks. end note]</i> MD5 |

| Name | Description |
|-------------------|--|
| | <p>Specifies that the MD5 algorithm, as defined by RFC 1321, shall be used.</p> <p>[Note: It is recommended that applications should avoid using this algorithm to store new hash values, because of publicly known breaks. end note]</p> <p>RIPEMD-128</p> <p>Specifies that the RIPEMD-128 algorithm, as defined by ISO/IEC 10118-3:2004 shall be used.</p> <p>[Note: It is recommended that applications should avoid using this algorithm to store new hash values, because of publicly known breaks. end note]</p> <p>RIPEMD-160</p> <p>Specifies that the RIPEMD-160 algorithm, as defined by ISO/IEC 10118-3:2004, shall be used.</p> <p>SHA-1</p> <p>Specifies that the SHA-1 algorithm, as defined by ISO/IEC 10118-3:2004, shall be used.</p> <p>SHA-256</p> <p>Specifies that the SHA-256 algorithm, as defined by ISO/IEC 10118-3:2004, shall be used.</p> <p>SHA-384</p> <p>Specifies that the SHA-384 algorithm, as defined by ISO/IEC 10118-3:2004, shall be used.</p> <p>SHA-512</p> <p>Specifies that the SHA-512 algorithm, as defined by ISO/IEC 10118-3:2004, shall be used.</p> <p>WHIRLPOOL</p> <p>Specifies that the WHIRLPOOL algorithm, as defined by ISO/IEC 10118-3:2004, shall be used.</p> |
| hash Value | <p>Specifies the hash value for the password required to edit this worksheet. This value shall be compared with the resulting hash value after hashing the user-supplied password using the algorithm specified by the preceding attributes and parent XML element. If the two values match, the protection shall no longer be enforced.</p> <p>If this value is omitted, then the reservationPassword attribute shall contain the password hash for the workbook.</p> <p>[Example</p> <p>Consider an Office Open XML document with the following information stored in one of its protection elements:</p> <pre><... algorithmName="SHA-1" hashValue="9oN7nWkCAyEZib1RomSJTjmPpCY=" /></pre> <p>The hashValue attribute value of 9oN7nWkCAyEZib1RomSJTjmPpCY= specifies that the user-supplied password must be hashed using the pre-processing defined by the parent element (if any) followed by the hashing algorithm (specified via the algorithmName attribute value) and that the resulting hash value must be match for the protection to be disabled.</p> <p>end example]</p> <p>The possible values for this attribute are defined by the W3C XML Schema base64Binary datatype.</p> |
| saltValue | <p>Specifies the random bytes that are pre-pended to the user-supplied password before it was hashed by the hashing algorithm.</p> |
| spinCount | <p>Specifies the number of times the hashing function shall be iteratively run (using each iteration's result as the input for the next iteration).</p> |

[Example:

Consider an Office Open XML document with the following information stored in one of its protection elements:

```
< ... algorithmName="SHA-1" hashValue="9oN7nWkCAyEZib1RomSJTjmPpCY=" />
```

The algorithmName attribute value of SHA-1 specifies that the SHA-1 hashing algorithm must be used to generate a hash from the user-defined password.

end example]

This note applies to the following products: 2007 SP2, 2010.

2.1.607 Part 4 Section 3.2.13, fileVersion (File Version)

a. *The standard states that the appName attribute is restricted to be an XML Schema string datatype.*

Office requires that the appName attribute have a maximum length of 65535 characters.

b. *The standard states that the lastEdited attribute is restricted to be an XML Schema string datatype.*

Office requires that the lastEdited attribute have a maximum length of 65535 characters.

c. *The standard states that the lowestEdited attribute is restricted to be an XML Schema string datatype.*

Office requires that the lowestEdited attribute have a maximum length of 65535 characters.

d. *The standard states that the rupBuild attribute is restricted to an XML Schema string datatype.*

Office requires that the rupBuild attribute have a maximum length of 65535 characters.

e. *The standard does not define any value restrictions on the lastEdited attribute.*

In Office, if the appName attribute equals xl in the en-US locale, then the lastEdited attribute is the text representation of an unsigned integer in the en-US locale.

f. *The standard does not define any value restrictions on the lowestEdited attribute.*

In Office, if the appName attribute equals xl in the en-US locale, then the lowestEdited attribute is the text representation of an unsigned integer in the en-US locale.

g. *The standard does not define any value restrictions on the rupBuild attribute.*

In Office, if the appName attribute equals xl in the en-US locale, then the rupBuild attribute is the text representation of an unsigned integer in the en-US locale.

h. *The standard does not place any restrictions on the value for the lastEdited attribute.*

In Office, when the appName attribute equals xl, the lastEdited attribute should be less than or equal to 32767.

i. *The standard does not place any restrictions on the value for the lowestEdited attribute.*

In Office, when the appName attribute equals xl, the lowestEdited attribute should be less than or equal to 32767.

j. *The standard does not place any restrictions on the value for the rupBuild attribute.*

In Office, when the `appName` attribute equals `xl`, the `rupBuild` attribute should be less than or equal to 32767.

2.1.608 Part 4 Section 3.2.14, `functionGroup` (Function Group)

- a. *The standard implies that the `name` attribute is optional.*

Excel requires this attribute.

- b. *The standard does not limit the length of the value of the `name` attribute.*

Excel restricts the value of this attribute to be at most 32 characters before escaping.

2.1.609 Part 4 Section 3.2.15, `functionGroups` (Function Groups)

- a. *The standard does not limit the value of `@builtInGroupCount`.*

Office requires that the max value be 255.

- b. *The standard states that the `maxOccurs` value for the sequence containing the child `functionGroup` element is unbounded.*

Excel limits the occurrences of the `functionGroup` element to 255.

- c. *The standard states that the values of the `builtInGroupCount` attribute are defined by the XML Schema `unsignedInt` datatype.*

Excel restricts the sum of the `functionGroup` elements plus the value of the `builtInGroupCount` attribute to be at most 255.

2.1.610 Part 4 Section 3.2.16, `oleSize` (Embedded Object Size)

- a. *The standard states that the `@ref` is the reference for the embedded object.*

Office treats `@ref` as the cell range over which the embedded object is displayed.

2.1.611 Part 4 Section 3.2.19, `sheet` (Sheet Information)

- a. *The standard does not place any restrictions on the value for the `name` attribute.*

Office requires that the `name` attribute be less than or equal to 31 characters in length and follow the character limitations for `sheet-name` and `sheet-name-special` in Formulas ("ECMA-376 Part 4 §3.17; Formulas").

- b. *The standard does not place any restrictions on the value for the `sheetId` attribute.*

Office requires that the `sheetId` attribute be between 1 and 65534 inclusive.

- c. *The standard does not place any restrictions on the value for the `id` attribute.*

Office requires that the `id` attribute be 255 or less characters in length.

- d. *The standard states that sheet names are unique.*

Office requires that sheet names are case-insensitive unique in any locale.

2.1.612 Part 4 Section 3.2.20, sheets (Sheets)

- a. *The standard states that the maxOccurs value for the sheet child element is unbounded.*
Excel limits the occurrences of this element to 32767.

2.1.613 Part 4 Section 3.2.21, smartTagPr (Smart Tag Properties)

- a. *The standard states that on and off are valid values of the embed attribute.*
Excel does not allow these values on this attribute.
This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.614 Part 4 Section 3.2.22, smartTagType (Smart Tag Type)

- a. *The standard does not limit the length of the value of the namespaceUri attribute.*
Excel restricts the value of this attribute to be at most 2083 characters.
- b. *The standard does not limit the length of the value of the url attribute.*
Excel restricts the value of this attribute to be at most 2083 characters.
- c. *The standard does not limit the length of the value of the name attribute.*
Excel restricts the value of this attribute to be at most 255 characters.
- d. *The standard states that the name attribute is optional.*
Excel requires this attribute.
- e. *The standard states that the namespaceUri attribute is optional.*
Excel requires this attribute.

2.1.615 Part 4 Section 3.2.23, smartTagTypes (Smart Tag Types)

- a. *The standard states that the minOccurs value for the smartTagType child element is 0.*
Excel requires an occurrence of this element.

2.1.616 Part 4 Section 3.2.24, webPublishing (Web Publishing Properties)

- a. *The standard states that on and off are valid values of the allowPng attribute.*
Excel does not allow these values on this attribute.
This note applies to the following products: 2007, 2007 SP1, 2007 SP2.
- b. *The standard states that on and off are valid values of the css attribute.*
Excel does not allow these values on this attribute.
This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.617 Part 4 Section 3.2.25, webPublishObject (Web Publishing Object)

- a. *The standard does not limit the length of the value of the title attribute.*

Excel restricts the value of this attribute to be at most 255 characters.

- b. *The standard does not limit the length of the value of the destinationFile attribute.*

Excel restricts the value of this attribute to be at least 1 and at most 255 characters.

- c. *The standard does not limit the length of the value of the divId attribute.*

Excel restricts the value of this attribute to be at least 1 and at most 255 characters.

- d. *The standard does not limit the length of the value of the sourceObject attribute.*

Excel restricts the value of this attribute to be at most 255 characters.

- e. *The standard states that the values of the id attribute are defined by the XML Schema unsignedInt datatype.*

Excel restricts the value of this attribute to be at least 1 and at most 2147483647.

- f. *The standard states that on and off are valid values of the autoRepublish attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

- g. *The standard states that sourceObject specifies the name of an object to be published.*

Office can save a file with a sourceObject name that no longer exists.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

- h. *The standard states that the values of the sourceObject attribute are defined by the ST_Xstring simple type.*

Excel requires the value of this attribute to meet the restrictions defined in Names ("[ECMA-376](#) Part 4 §3.17.2.5; Names").

2.1.618 Part 4 Section 3.2.27, workbook (Workbook)

- a. *The standard states that minOccurs for the bookViews element is zero.*

Excel will fail to print files without a bookViews element.

2.1.619 Part 4 Section 3.2.28, workbookPr (Workbook Properties)

- a. *The standard states that allowRefreshQuery is a valid attribute on this element.*

Excel does not support this attribute on this element.

- b. *The standard does not specify a default value for the defaultThemeVersion attribute.*

Excel uses a default value of 0, which indicates that no default theme applies in the workbook, for this attribute.

c. *The standard states that on and off are valid values of the autoCompressPic attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

d. *The standard states that on and off are valid values of the backupFile attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

e. *The standard states that on and off are valid values of the checkCompatibility attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

f. *The standard states that on and off are valid values of the date1904 attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

g. *The standard states that on and off are valid values of the filterPrivacy attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

h. *The standard states that on and off are valid values of the hidePivotFieldList attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

i. *The standard states that on and off are valid values of the promptedSolutions attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

j. *The standard states that on and off are valid values of the publishItems attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

k. *The standard states that on and off are valid values of the saveExternalLinkValues attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

l. *The standard states that on and off are valid values of the showBorderUnselectedTables attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

m. *The standard states that on and off are valid values of the showInkAnnotation attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

n. *The standard states that on and off are valid values of the showPivotChartFilter attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

o. *The standard describes the codeName attribute as specifying the codename of the application that created the workbook.*

Office uses the codeName attribute to specify the name of the Workbook object as to be used in a scripting application.

p. *The standard states that the values of the codeName attribute are defined by the XML Schema string datatype.*

Excel requires this attribute to be at most 31 characters, with the following pattern restriction: `[\p{L}\P{IsBasicLatin}][_\d\p{L}\P{IsBasicLatin}]*`.

q. *The standard specifies a value of 1 or true for @hidePivotFieldList indicates the field list is shown.*

Office treats that a value of 1 or true to indicate the field list is hidden, and a value of 0 or false otherwise.

r. *The standard does not specify the meaning of possible values for the attribute refreshAllConnections.*

Office treats a value of 1 or true for @refreshAllConnections to indicate all connections shall be refreshed, and 0 or false otherwise.

s. *The standard implies that the implementing application should draw a border around unselected tables if @showBorderUnselectedTables is set to true.*

Office does not draw the border around tables regardless of the value of showBorderUnselectedTables.

t. *The standard states that the promptedSolutions attribute determines whether the user received or did not receive an alert.*

In Office, this attribute indicates whether an alert is requested before loading Smart Document components. A value of 1 or true indicates the user has chosen not to receive an alert. A value of 0 or false indicates the user will receive an alert.

u. *The standard states that the filterPrivacy attribute is used to warn the user when PII is added to a document.*

In Office, the filterPrivacy attribute is used to determine if PII is removed or not removed from the workbook when it is saved.

2.1.620 Part 4 Section 3.2.29, workbookProtection (Workbook Protection)

a. *The standard states that on and off are valid values of the lockStructure and lockWindows attributes.*

Excel does not allow these values on these attributes.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

b. *The standard specifies @lockWindows indicates whether the windows that comprise the workbook are locked.*

In Office if all sheets have a sheetView element with the attribute windowProtection set to false, then @lockWindows will also be saved as false.

c. *The standard specifies @lockRevision indicates whether the workbook is locked for revisions.*

Office uses @lockRevision to specify whether the change history in a shared workbook cannot be removed.

d. *The standard specifies @workbookPassword as the hash of the password required for unlocking revisions in this workbook.*

Office uses @workbookPassword as the hash of the password required for unlocking the structure of the workbook and/or the windows in this workbook.

e. *The standard states that this setting uses a specific revisionsPassword attribute to store the password hash for unlocking revisions in the workbook.*

In Office, when the HKCU/Software/Microsoft/Office/<VERSION>/Common/Security/UseIsoPasswordVerifier registry key is set to 1, the XML for file sharing is written by using the XML attribute structure in the following table.

| Name | Description |
|-----------------------|--|
| algorithm Name | <p>The name of the cryptographic hashing algorithm used to generate the hash value. Only those algorithms that are installed in the operating system's cryptographic subsystem can be utilized by Office.</p> <p>The hash algorithm names, described in the following table, are reserved.</p> <p>MD2</p> <p><i>Specifies that the MD2 algorithm, as defined by RFC 1319, shall be used.</i></p> <p><i>[Note: It is recommended that applications should avoid using this algorithm to store new hash values, because of publicly known breaks. end note]</i></p> <p>MD4</p> <p><i>Specifies that the MD4 algorithm, as defined by RFC 1320, shall be used.</i></p> <p><i>[Note: It is recommended that applications should avoid using this algorithm to store new hash values, because of publicly known breaks. end note]</i></p> <p>MD5</p> <p><i>Specifies that the MD5 algorithm, as defined by RFC 1321, shall be used.</i></p> <p><i>[Note: It is recommended that applications should avoid using this algorithm to store new hash values, because of publicly known breaks. end note]</i></p> <p>RIPMD-128</p> <p><i>Specifies that the RIPMD-128 algorithm, as defined by ISO/IEC 10118-3:2004 shall be used.</i></p> |

| Name | Description |
|-------------------|--|
| | <p><i>[Note: It is recommended that applications should avoid using this algorithm to store new hash values, because of publicly known breaks. end note]</i></p> <p>RIPEMD-160 Specifies that the RIPEMD-160 algorithm, as defined by ISO/IEC 10118-3:2004, shall be used.</p> <p>SHA-1 Specifies that the SHA-1 algorithm, as defined by ISO/IEC 10118-3:2004, shall be used.</p> <p>SHA-256 Specifies that the SHA-256 algorithm, as defined by ISO/IEC 10118-3:2004, shall be used.</p> <p>SHA-384 Specifies that the SHA-384 algorithm, as defined by ISO/IEC 10118-3:2004, shall be used.</p> <p>SHA-512 Specifies that the SHA-512 algorithm, as defined by ISO/IEC 10118-3:2004, shall be used.</p> <p>WHIRLPOOL Specifies that the WHIRLPOOL algorithm, as defined by ISO/IEC 10118-3:2004, shall be used.</p> |
| hash Value | <p>Specifies the hash value for the password required to edit this worksheet. This value shall be compared with the resulting hash value after hashing the user-supplied password using the algorithm specified by the preceding attributes and parent XML element. If the two values match, the protection shall no longer be enforced.</p> <p>If this value is omitted, then the reservationPassword attribute shall contain the password hash for the workbook.</p> <p><i>[Example: Consider an Office Open XML document with the following information stored in one of its protection elements:</i></p> <pre data-bbox="402 961 1295 989"><... algorithmName="SHA-1" hashValue="9oN7nWkCAyEZib1RomSJTjmPpCY=" /></pre> <p>The hashValue attribute value of 9oN7nWkCAyEZib1RomSJTjmPpCY= specifies that the user-supplied password must be hashed using the pre-processing defined by the parent element (if any) followed by the hashing algorithm (specified via the algorithmName attribute value) and that the resulting hash value must be match for the protection to be disabled.</p> <p><i>end example]</i></p> <p>The possible values for this attribute are defined by the W3C XML Schema base64Binary datatype.</p> |
| saltValue | <p>Specifies the random bytes that are pre-pended to the user-supplied password before it was hashed by the hashing algorithm.</p> |
| spinCount | <p>Specifies the number of times the hashing function shall be iteratively run (using each iteration's result as the input for the next iteration).</p> |

[Example:

Consider an Office Open XML document with the following information stored in one of its protection elements:

```
< ... algorithmName="SHA-1" hashValue="9oN7nWkCAyEZib1RomSJTjmPpCY=" />
```

The algorithmName attribute value of SHA-1 specifies that the SHA-1 hashing algorithm must be used to generate a hash from the user-defined password.

end example]

This note applies to the following products: 2007 SP2, 2010.

f. *The standard states that this setting uses a specific workbookPassword attribute to store the password hash for unlocking revisions in the workbook.*

In Office, when the HKCU/Software/Microsoft/Office/<VERSION>/Common/Security/UseIsoPasswordVerifier registry key is set to 1, the XML for file sharing is written by using the XML attribute structure in the following table.

| Name | Description |
|-----------------------|---|
| algorithm Name | <p>The name of the cryptographic hashing algorithm used to generate the hash value. Only those algorithms that are installed in the operating system's cryptographic subsystem can be utilized by Office.</p> <p>The hash algorithm names, described in the following table, are reserved.</p> <p>MD2 <i>Specifies that the MD2 algorithm, as defined by RFC 1319, shall be used.</i> <i>[Note: It is recommended that applications should avoid using this algorithm to store new hash values, because of publicly known breaks. end note]</i></p> <p>MD4 <i>Specifies that the MD4 algorithm, as defined by RFC 1320, shall be used.</i> <i>[Note: It is recommended that applications should avoid using this algorithm to store new hash values, because of publicly known breaks. end note]</i></p> <p>MD5 <i>Specifies that the MD5 algorithm, as defined by RFC 1321, shall be used.</i> <i>[Note: It is recommended that applications should avoid using this algorithm to store new hash values, because of publicly known breaks. end note]</i></p> <p>RIPMD-128 <i>Specifies that the RIPMD-128 algorithm, as defined by ISO/IEC 10118-3:2004 shall be used.</i> <i>[Note: It is recommended that applications should avoid using this algorithm to store new hash values, because of publicly known breaks. end note]</i></p> <p>RIPMD-160 <i>Specifies that the RIPMD-160 algorithm, as defined by ISO/IEC 10118-3:2004, shall be used.</i></p> <p>SHA-1 <i>Specifies that the SHA-1 algorithm, as defined by ISO/IEC 10118-3:2004, shall be used.</i></p> <p>SHA-256 <i>Specifies that the SHA-256 algorithm, as defined by ISO/IEC 10118-3:2004, shall be used.</i></p> <p>SHA-384 <i>Specifies that the SHA-384 algorithm, as defined by ISO/IEC 10118-3:2004, shall be used.</i></p> <p>SHA-512 <i>Specifies that the SHA-512 algorithm, as defined by ISO/IEC 10118-3:2004, shall be used.</i></p> <p>WHIRLPOOL <i>Specifies that the WHIRLPOOL algorithm, as defined by ISO/IEC 10118-3:2004, shall be used.</i></p> |
| hash Value | <p>Specifies the hash value for the password required to edit this worksheet. This value shall be compared with the resulting hash value after hashing the user-supplied password using the algorithm specified by the preceding attributes and parent XML element. If the two values match, the protection shall no longer be enforced.</p> |

| Name | Description |
|------------------|--|
| | <p>If this value is omitted, then the reservationPassword attribute shall contain the password hash for the workbook.</p> <p><i>[Example:</i></p> <p>Consider an Office Open XML document with the following information stored in one of its protection elements:</p> <pre data-bbox="402 352 1295 380"><... algorithmName="SHA-1" hashValue="9oN7nWkCAyEZib1RomSJTjmPpCY=" /></pre> <p>The hashValue attribute value of 9oN7nWkCAyEZib1RomSJTjmPpCY= specifies that the user-supplied password must be hashed using the pre-processing defined by the parent element (if any) followed by the hashing algorithm (specified via the algorithmName attribute value) and that the resulting hash value must be match for the protection to be disabled.</p> <p><i>end example]</i></p> <p>The possible values for this attribute are defined by the W3C XML Schema base64Binary datatype.</p> |
| saltValue | Specifies the random bytes that are pre-pended to the user-supplied password before it was hashed by the hashing algorithm. |
| spinCount | Specifies the number of times the hashing function shall be iteratively run (using each iteration's result as the input for the next iteration). |

[Example:

Consider an Office Open XML document with the following information stored in one of its protection elements:

```
< ... algorithmName="SHA-1" hashValue="9oN7nWkCAyEZib1RomSJTjmPpCY=" />
```

The algorithmName attribute value of SHA-1 specifies that the SHA-1 hashing algorithm must be used to generate a hash from the user-defined password.

end example]

This note applies to the following products: 2007 SP2, 2010.

2.1.621 Part 4 Section 3.2.30, workbookView (Workbook View)

a. *The standard does not place any restrictions on the length of the value for @windowHeight and @windowWidth.*

Office requires that the value of @windowHeight and @windowWidth be less than or equal to 2147483647.

b. *The standard does not place any restrictions on the value for @tabRatio.*

Office requires that @tabRatio be less than or equal to 1000.

c. *The standard does not place any restrictions on the value for @activeTab.*

Office requires that @activeTab be between 0 and 32766 inclusive.

d. *The standard does not restrict the value of the firstSheet attribute.*

Office limits the value of the firstSheet attribute to 0 through 32766 inclusive or to 4294967286.

e. *The standard states that on and off are valid values of the autoFilterDateGrouping attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

f. *The standard states that on and off are valid values of the minimized attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

g. *The standard states that on and off are valid values of the showHorizontalScroll attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

h. *The standard states that on and off are valid values of the showSheetTabs attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

i. *The standard states that on and off are valid values of the showVerticalScroll attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.622 Part 4 Section 3.3.1.2, brk (Break)

a. *The standard states that the values of the min attribute are defined by the XML Schema unsignedInt datatype.*

Excel restricts the value of this attribute to be at most 1048576; it should never exceed the number of rows or columns in the spreadsheetML instance.

b. *The standard states that Page Breaks can have a start and end point defined by using the min and max attributes.*

Office ignores the min and max attribute values and places a page break across the entire range.

c. *The standard states that the values of the id attribute are defined by the XML Schema unsignedInt datatype.*

Excel restricts the value of this attribute to be at least 1 and at most 1048576.

d. *The standard states that the values of the max attribute are defined by the XML Schema unsignedInt datatype.*

Excel restricts the value of this attribute to be at least 1 and at most 1048576.

e. *The standard states that the default value of the id attribute is 0.*

Excel does not use a default value for this attribute.

f. *The standard states that the default value of the max attribute is 0.*

Excel does not use a default value for this attribute.

2.1.623 Part 4 Section 3.3.1.3, c (Cell)

a. *The standard states that @cm is zero-based index and does not specify the collection.*

Office specifies that @cm is a one-based index into the cellMetadata collection in the metadata part.

b. *The standard states that @vm is a zero-based index and does not specify the collection.*

Office specifies that @vm is a one-based index into cellMetadata collection in the metadata part.

c. *The standard makes @r optional in the schema, but the prose does not explain the meaning of the default behavior.*

If this attribute is not specified, the cell shall be located in the column with the index that is 1 greater than that of the previous cell in the parent **row** collection. If this attribute is not specified and the cell is the first **c** element in the parent **row** collection, the cell shall be located in the first column.

d. *The standard states that the values of the cm attributes are defined by the XML Schema unsignedInt datatype.*

Office requires that the cm attribute be less than 2147483648.

e. *The standard specifies that @vm is an unsignedInt.*

Office specifies that @vm is an unsignedInt and is less than 2147483648.

f. *The standard specifies that @s is unsignedInt.*

Office specifies @s is an unsignedInt between 0 and 65490.

g. *The standard does not specify which collection @s indexes.*

Office specifies that @s indexes into the cellXfs collection in the style part.

h. *The standard incorrectly describes the style index in the example as "6", which conflicts with the XML fragment.*

In Excel, the style index in the example should read "1" which matches the XML fragment.

2.1.624 Part 4 Section 3.3.1.4, cellSmartTag (Cell Smart Tag)

a. *The standard states that the values for the type attribute are defined by the XML Schema unsignedInt datatype.*

Office requires that the value be between 0 and 32768 inclusive.

b. *The standard indicates that there can be more than one cellSmartTag for a cell.*

Office assumes that each cellSmartTag must have its corresponding type present in the smartTagType element in the smartTagTypes collection of the workbook.

2.1.625 Part 4 Section 3.3.1.5, cellSmartTagPr (Smart Tag Properties)

a. *The standard does not place any restrictions on the length of the value for the key attribute.*

Office requires that the key attribute be less than or equal to 255 characters in length.

b. *The standard does not place any restrictions on the length of the value for the val attribute.*

Office requires that the val attribute be less than or equal to 255 characters in length.

2.1.626 Part 4 Section 3.3.1.6, cellSmartTags (Cell Smart Tags)

a. *The standard does not limit the number of cellSmartTag elements that can exist within the parent element.*

Office allows only a single cellSmartTag element to exist within the parent.

2.1.627 Part 4 Section 3.3.1.7, cellWatch (Cell Watch Item)

a. *The standard includes the @r defined without any restrictions within the parent element collection.*

Office requires that @r shall be unique within parent element collection.

2.1.628 Part 4 Section 3.3.1.9, cfRule (Conditional Formatting Rule)

a. *The standard implies that the type attribute is optional.*

Excel requires this attribute.

b. *The standard specifies the operator attribute as optional.*

Office requires the operator attribute to be specified if and only if type attribute value equals cells.

c. *The standard specifies timePeriod attribute as optional.*

Office requires timePeriod attribute to be specified if and only if type attribute value equals timePeriod.

d. *The standard does not specify a default value for the rank attribute.*

Excel uses a default value of 0 for this attribute.

2.1.629 Part 4 Section 3.3.1.10, cfvo (Conditional Format Value Object)

a. *The standard describes @val as type ST_Xstring.*

Office assumes that @val is restricted by valid Conditional Format Formulas as defined in Formulas ("[ECMA-376](#) Part 4 §3.17; Formulas").

b. *The standard does not state any restrictions on the value of the type attribute.*

In Office, if the parent element is iconSet, the type attribute cannot have values of min or max.

2.1.630 Part 4 Section 3.3.1.12, col (Column Width & Formatting)

a. *The standard describes the min attribute of without any restrictions on its minimum or maximum values.*

Office requires the min attribute to be between 1 and 16384 inclusive.

b. *The standard defines the values of the max attribute without any restrictions on its length other than what is called for in xs:unsignedInt.*

Office requires the max attribute to be between values 1 and 16384 inclusive.

c. *The standard defines the width attribute without any restrictions on the length.*

Office requires the width attribute be between 0 and 255 inclusive.

d. *The standard states that the values of the style attribute are defined by the XML Schema unsignedInt datatype.*

Office requires that the style attribute be between 0 and 65429 inclusive.

e. *The standard defines the outlineLevel attribute without specifying its maximum value.*

Office specifies the outlineLevel attributes maximum value is 7.

2.1.631 Part 4 Section 3.3.1.13, colBreaks (Vertical Page Breaks)

For additional notes that apply to this portion of the standard, please see the notes for [rowBreaks, §3.3.1.72\(a, b\)](#).

a. *The standard states that the values of the count attribute are defined by the XML Schema unsignedInt datatype.*

Office requires that the count attribute be an unsignedInt less than or equal to 1023.

b. *The standard states that the values of the manualBreakCount attribute are defined by the XML Schema unsignedInt datatype.*

Office requires that the manualBreakCount attribute is an unsignedInt less than or equal to 1023.

2.1.632 Part 4 Section 3.3.1.14, color (Color)

For additional notes that apply to this portion of the standard, please see the notes for [tabColor, §3.3.1.90\(a-c\)](#); [bgColor, §3.8.3\(a\)](#).

a. *The standard specifies use with only data bar and color scale.*

In Office, the color element used in various formatting elements as defined in parent sub-clause list.

b. *The standard states that the values of the indexed attribute are defined by the XML Schema unsignedInt datatype.*

Excel restricts the value of this attribute to be at most 255.

c. *The standard states that the values of the tint attribute are defined by the XML Schema double datatype.*

Excel restricts the value of this attribute to be at least -1 and at most 1.

d. *The standard states that the values of the theme attribute are defined by the XML Schema unsignedInt datatype.*

Excel restricts the value of this attribute, a zero-based index, to be at most 255.

2.1.633 Part 4 Section 3.3.1.15, colorScale (Color Scale)

- a. *The standard states that the maxOccurs value for the cfvo child element is unbounded.*

Excel limits the occurrences of this element to 3.

- b. *The standard states that the maxOccurs value for the color child element is unbounded.*

Excel limits the occurrences of this element to 3.

- c. *The standard places no restrictions on the relationship between the count of cfvo child elements and the count of color child elements.*

Excel requires these two counts to be the same.

2.1.634 Part 4 Section 3.3.1.17, conditionalFormatting (Conditional Formatting)

- a. *The standard states that the possible values for @sqref are defined by ST_Sqref simple type.*

Office requires that the value of @sqref have a length of at least 1 (be non-empty).

2.1.635 Part 4 Section 3.3.1.18, control (Embedded Control)

- a. *The standard does not specify the ObjectType or restriction of valid values for @shapeId.*

Office requires the ObjectType of the drawing shape to be Picture and the value to be between 1 and 67098623 inclusive.

- b. *The standard does not specify restrictions for the name attribute.*

In Excel, the string shall be unique and have a maximum of 32 characters.

2.1.636 Part 4 Section 3.3.1.19, controls (Embedded Controls)

- a. *The standard states that the maxOccurs value for the control child element is unbounded.*

Excel limits the occurrences of this element to 65535.

2.1.637 Part 4 Section 3.3.1.20, customPr (Custom Property)

- a. *The standard specifies no restriction on the uniqueness of the name attribute.*

In Office, the name attribute must be case-insensitive and unique.

2.1.638 Part 4 Section 3.3.1.22, customSheetView (Custom Chart Sheet View)

- a. *The standard states that the attribute scale defines the print scale.*

Office uses the scale attribute to define the zoom level.

2.1.639 Part 4 Section 3.3.1.23, customSheetView (Custom Sheet View)

- a. *The standard says scale attribute defines the print scale.*

Office uses the scale attribute to define the zoom level.

b. *The standard states that the values of the colorId attribute are defined by the XML Schema unsignedInt datatype.*

Office restricts the colorId attribute value to an unsignedInt less than or equal to 64.

c. *The standard specifies @scale ranges from 10 to 400.*

Excel also allow for a value of zero, which is interpreted as the automatic setting.

d. *The standard specifies that colorId attribute defines the color value for text in row or column headings and gridlines the custom view.*

Office uses colorId attribute to define the color value for gridlines in the custom view.

e. *The standard specifies that possible values for the guid attribute are defined by ST_Guid simple type.*

Office requires the guid attribute to be a non-null guid (a null guid is defined as 00000000-0000-0000-0000-000000000000).

2.1.640 Part 4 Section 3.3.1.24, customSheetViews (Custom Chart Sheet Views)

a. *The standard states that the maxOccurs value for the customSheetView child element is unbounded.*

Excel limits the occurrences of this element to 2147483647.

2.1.641 Part 4 Section 3.3.1.25, customSheetViews (Custom Sheet Views)

a. *The standard states that the maxOccurs value for the customSheetView child element is unbounded.*

Excel limits the occurrences of this element to 2147483647.

2.1.642 Part 4 Section 3.3.1.26, dataBar (Data Bar)

a. *The standard states that the values of the maxLength attribute are defined by the XML Schema unsignedInt datatype.*

Excel restricts the value of this attribute to be at most 100.

b. *The standard states that the values of the minLength attribute are defined by the XML Schema unsignedInt datatype.*

Excel restricts the value of this attribute to be at most 100.

2.1.643 Part 4 Section 3.3.1.30, dataValidation (Data Validation)

a. *The standard does not limit the length of the value of the prompt attribute.*

Excel restricts the value of this attribute to be at most 255 characters, after decoding.

b. *The standard states that the possible values for @sqref are defined by ST_Sqref simple type.*

Office limits the number of references in @sqref to be between 1 and 32767 inclusive.

c. *The standard does not restrict the value of the error attribute.*

Office restricts the length of the value of the error attribute to 224 characters.

d. *The standard does not limit the length of the value of the errorTitle attribute.*

Office limits the length of the value of the errorTitle attribute to 32 characters.

e. *The standard states that there is no limit on length of the promptTitle attribute value.*

Office limits the length of the promptTitle attribute value to 32 characters.

2.1.644 Part 4 Section 3.3.1.31, dataValidations (Data Validations)

a. *The standard states that the values of the xWindow attribute are defined by the XML Schema unsignedInt datatype.*

Excel restricts the value of this attribute to be at most 65535.

b. *The standard states that the values of the count attribute are defined by the XML Schema unsignedInt datatype.*

Excel restricts the value of this attribute to be at most 65534.

c. *The standard states that the values of the yWindow attribute are defined by the XML Schema unsignedInt datatype.*

Excel restricts the value of this attribute to be at most 65535.

d. *The standard does not specify a default value for the xWindow attribute.*

Excel uses a default value of 0 for this attribute.

e. *The standard does not specify a default value for the yWindow attribute.*

Excel uses a default value of 0 for this attribute.

f. *The standard does not specify a default value for the count attribute.*

Excel uses a default value of 0 for this attribute.

g. *The standard states that the maxOccurs value for the dataValidation child element is unbounded.*

Excel limits the occurrences of this element to 65534.

2.1.645 Part 4 Section 3.3.1.32, dialogsheets (Dialog Sheet)

a. *The standard states that the drawing element is specified in CT_Dialogsheet.*

Office never saves the drawing element.

b. *The standard states that the minOccurs value for the legacyDrawing child element is 0.*

Excel requires an occurrence of this element.

2.1.646 Part 4 Section 3.3.1.34, drawing (Drawing)

For additional notes that apply to this portion of the standard, please see the notes for [dialogsheets, §3.3.1.32\(a\)](#).

2.1.647 Part 4 Section 3.3.1.35, evenFooter (Even Page Footer)

a. *The standard states that if no evenFooter is specified, then the oddFooter is used.*

In Office, oddFooter is used only when headerFooter@differentOddEven equals false.

b. *The standard does not limit the length of the value of this element.*

Excel restricts the value of this element to be at most 255 characters.

c. *The standard makes no mention of an xml:space attribute.*

Excel uses this attribute to specify, using the W3C space preservation rules, how white space should be handled for the element's contents; its allowed values are defined by the XML 1.0 specification.

2.1.648 Part 4 Section 3.3.1.36, evenHeader (Even Page Header)

a. *The standard states that if no evenHeader is specified, then the oddHeader is used.*

In Office, oddHeader is used only when headerFooter@differentOddEven equals false.

b. *The standard does not specify formatting codes in ABNF format.*

Office uses the following ABNF formatting codes to describe header and footer formatting:

headerfooter = *(left / pagenum / pagetotal / fontsize / strikethrough / superscript / subscript / center / date / time / filepath / picture / underline / doubleunderline / right / bookpath / sheetname / fontname / fonttype / font / bold / italic / ampersand / emptytoken / UNICHAR)

UNICHAR = %x0020-FFFF

This code specifies Unicode characters, starting with the space character (%x0020).

DIGIT = %x0030-0039

This code specifies a digit between 0 and 9.

HEXALPHA = %x0041-0046 / %x0061-0066

This code specifies a character between A and F or between a and f.

DQUOTE = %x0022

This code specifies a double quotation mark.

left = "&L"

This code specifies the beginning of the left section. There are three header and footer sections: left, center, and right. When two or more of this section marker exist, the contents from All markers are concatenated, in the order of appearance, and placed into the left section.

pagenum = "&P"

This code specifies the current page number.

pagetotal = "&N" 0*1(("-" / "+") *DIGIT)

This code specifies the total number of pages.

fontsize = "&" 1*3DIGIT

This code specifies the text font size, where font size is measured in points.

strikethrough = "&S"

This code specifies whether the strikethrough text style is on or off. The first occurrence of this code must turn the strikethrough text style on, and the second occurrence must turn it off.

superscript = "&X"

This code specifies whether the superscript text style is on or off. The first occurrence of this code must turn the superscript text style on, and the second occurrence must turn it off. The superscript and subscript codes must not both be on at same time. If both codes occur in the string, the code that occurs first is applied and the other is ignored.

subscript = "&Y"

This code specifies whether the subscript text style is on or off. The first occurrence of this code must turn the subscript text style on, and the second occurrence must turn it off. The superscript and subscript codes must not both be on at same time. If both codes occur in the string, the code that occurs first is applied and the other is ignored.

center = "&C"

This code specifies the beginning of the center section. When two or more of this section marker exist, the contents from All markers are concatenated, in the order of appearance, and placed into the center section.

date = "&D"

This code specifies a date.

time = "&T"

This code specifies a time.

picture = "&G"

This code specifies a picture.

underline = "&U"

This code specifies whether the single underline text style is on or off. The first occurrence of this code must turn the underline text style on, and the second occurrence must turn it off.

doubleunderline = "&E"

This code specifies whether the double underline text style is on or off. The first occurrence of this code must turn the double underline text style on, and the second occurrence must turn it off.

right = "&R"

This code specifies the beginning of the right section. When two or more of this section marker exist, the contents from All markers are concatenated, in the order of appearance, and placed into the right section.

bookpath = "&Z"

This code specifies a workbook file path.

bookname = "&F"

This code specifies a workbook file name.

sheetname = "&A"

This code specifies a worksheet name.

fontname = (1*UNICHAR / "-")

This code specifies the text font name. When the font name is a hyphen, no font is specified. This can be a localized string.

fonttype = ("italic" / "bold" / "regular" / "italic bold" / "bold italic")

This code specifies the text font type. This can be a localized string.

font = "&" DQUOTE fontname , fonttype DQUOTE

This code specifies the text font.

bold = "&B"

This code specifies whether the bold text style is on or off. The first occurrence of this code must turn the bold text style on, and the second occurrence must turn it off.

italic = "&I"

This code specifies whether the italic text style is on or off. The first occurrence of this code must turn the italic text style on, and the second occurrence must turn it off.

ampersand = "&&"

This code specifies an ampersand character.

emptytoken = "&" *1UNICHAR

This code specifies an unidentified token. If only "&" appears, or if there is a UNICHAR specified after "&" and it is not one of the UNICHAR characters listed in the preceding rules, then the token is interpreted as empty and nothing is rendered in the header or footer text.

c. *The standard does not limit the length of the value of this element.*

Excel restricts the value of this element to be at most 255 characters.

d. *The standard makes no mention of an xml:space attribute.*

Excel uses this attribute to specify, using the W3C space preservation rules, how white space should be handled for the element's contents; its allowed values are defined by the XML 1.0 specification.

2.1.649 Part 4 Section 3.3.1.37, f (Formula)

a. *The standard specifies that any cell in a worksheet may be the input cell for a data table.*

Office requires that the input cell not belong to the cell range in the ref attribute, the master row or the master column - unless the cell is deleted as specified in attribute del1.

b. The standard specifies a *bx* attribute value of *true* causes this formula to assign a value to a name.

Office requires the *bx* attribute to be always set to *false*.

c. The standard specifies that attribute *del2* applies to data table formulas only.

Office uses attribute *del2* for two-dimensional data table formulas only.

d. The standard specifies that the top-left cell in the data table is the master cell.

The cell with the smallest row and column in the **ref** attribute is called the master cell. The single column reference with the column one less than the smallest column in the **ref** attribute and spanning the same rows as the cell range in the **ref** attribute is called the master column. The single row reference with the row one less than the smallest row in the **ref** attribute and spanning the same columns as the cell range in the **ref** attribute is called the master row. The cell with the column and row one less than the master cell is called, the corner cell.

[Example:

The example shows the master cell, row and column, and the corner cell for the data table specified by the **ref** attribute equal to "C4:E10":

| | A | B | C | D | E |
|----|---|---------------|-------------|-----|---|
| 1 | | | | | |
| 2 | | | | | |
| 3 | | corner cell | master row | | |
| 4 | | master column | master cell | ref | |
| 5 | | | | | |
| 6 | | | | | |
| 7 | | | | | |
| 8 | | | | | |
| 9 | | | | | |
| 10 | | | | | |
| 11 | | | | | |

end example]

e. The standard specifies that if the *aca* attribute equals *true*, then that formula is an array formula.

Office uses the *t* attribute value *array* to indicate an array formula. The *aca* attribute is ignored if the formula is not an array formula.

f. The standard specifies that any cells in a worksheet may be the input cells for a two-dimensional data table.

Office requires that the input cells not belong to the cell range in the ref attribute, the master row, the master column or the corner cell unless the corresponding cells are deleted as specified in attributes del1 and del2.

g. *The standard specifies that data tables are recalculated whenever a worksheet is recalculated.*

Office recalculates data tables as specified by calcPr@calcMode.

h. *The standard states that the si attribute is optional.*

Office requires the si attribute to exist when the t attribute equals shared and is ignored otherwise.

i. *The standard makes no mention of an xml:space attribute.*

Excel uses this attribute to specify, using the W3C space preservation rules, how white space should be handled for the element's contents; its allowed values are defined by the XML 1.0 specification.

2.1.650 Part 4 Section 3.3.1.38, firstFooter (First Page Footer)

a. *The standard does not limit the length of the value of this element.*

Excel restricts the value of this element to be at most 255 characters after escaped sequences are replaced with characters.

b. *The standard makes no mention of an xml:space attribute.*

Excel uses this attribute to specify, using the W3C space preservation rules, how white space should be handled for the element's contents; its allowed values are defined by the XML 1.0 specification.

2.1.651 Part 4 Section 3.3.1.39, firstHeader (First Page Header)

a. *The standard does not place any restrictions on the length of the value for this element.*

Office requires that the length of the value for this element be less than or equal to 255.

b. *The standard makes no mention of an xml:space attribute.*

Excel uses this attribute to specify, using the W3C space preservation rules, how white space should be handled for the element's contents; its allowed values are defined by the XML 1.0 specification.

2.1.652 Part 4 Section 3.3.1.40, formula (Formula)

a. *The standard states that the content of this element is a formula whose calculated value specifies the criteria for the conditional formatting rule.*

If the parent element for formula is rdn ("[\[ECMA-376\]](#) Part 4 §3.11.1.13; rdn"), then the formula element represents a formula for a defined name and is defined by the grammar in Name Formulas ([§3.2.3.1.4, Name Formulas](#)).

If the parent element for formula is cfRule ("[\[ECMA-376\]](#) Part 4 §3.3.1.9; cfRule"), then the formula element represents a formula for a conditional formatting rule, and is defined by the grammar in Conditional Formatting Formulas ([§3.2.3.1.2, Conditional Formatting Formulas](#)).

b. *The standard makes no mention of an xml:space attribute.*

Excel uses this attribute to specify, using the W3C space preservation rules, how white space should be handled for the element's contents; its allowed values are defined by the XML 1.0 specification.

2.1.653 Part 4 Section 3.3.1.41, formula1 (Formula 1)

- a. *The standard states that the contents of this element are an extension on the ST_Formula simple type.*

Excel requires the contents of this element for a data validation formula, as defined in Data Validation Formulas ([§3.2.3.1.3, Data Validation Formulas](#)).

- b. *The standard makes no mention of an xml:space attribute.*

Excel uses this attribute to specify, using the W3C space preservation rules, how white space should be handled for the element's contents; its allowed values are defined by the XML 1.0 specification.

2.1.654 Part 4 Section 3.3.1.42, formula2 (Formula 2)

- a. *The standard states that the contents of this element are an extension on the ST_Formula simple type.*

Excel requires the contents of this element to follow the grammar for a data validation formula, as defined in Data Validation Formulas ([§3.2.3.1.3, Data Validation Formulas](#)).

- b. *The standard makes no mention of an xml:space attribute.*

Excel uses this attribute to specify, using the W3C space preservation rules, how white space should be handled for the element's contents; its allowed values are defined by the XML 1.0 specification.

2.1.655 Part 4 Section 3.3.1.44, hyperlink (Hyperlink)

- a. *The standard does not place any restrictions on the length of the value for the location attribute.*

Office requires that length of the location attribute be between 0 and 2084 inclusive.

- b. *The standard does not place any restrictions on the length of the value for the display attribute.*

Office requires that the length of the display attribute be between 0 and 2084 inclusive.

- c. *The standard does not place any restrictions on the length of the value for the tooltip attribute.*

Office requires that the tooltip attribute be less than or equal to 255 characters in length.

2.1.656 Part 4 Section 3.3.1.47, ignoredError (Ignored Error)

- a. *The standard does not specify the maximum item number of the sqref attribute.*

Office defines the maximum item number of the sqref attribute as 2147483647.

2.1.657 Part 4 Section 3.3.1.48, ignoredErrors (Ignored Errors)

- a. *The standard states that the maxOccurs value for the ignoredError child element is unbounded.*

Excel limits the occurrences of this element to 9.

2.1.658 Part 4 Section 3.3.1.49, inputCells (Input Cells)

For additional notes that apply to this portion of the standard, please see the notes for [scenario, §3.3.1.73\(c, d\)](#).

a. *The standard does not limit the length of the value of the val attribute.*

Excel restricts the value of this attribute to be at most 255 characters, after decoding.

b. *The standard does not specify a default value for the numFmtId attribute.*

Excel uses a default value of 0 for this attribute.

c. *The standard states that @deleted prevents the inputCell from being a part of a scenario when run.*

Office includes inputCells that have @deleted="true" when running a scenario.

d. *The standard states a usage for the @numFmtId field.*

In Office @numFmtId is the number formatting used to display the input values for the scenario when it was created.

2.1.659 Part 4 Section 3.3.1.50, is (Rich Text Inline)

a. *The standard states that the maxOccurs value for the r child element is unbounded.*

Excel limits the occurrences of this element to 32767.

b. *The standard states that the maxOccurs value for the rPh child element is unbounded.*

Excel limits the occurrences of this element to 32767.

2.1.660 Part 4 Section 3.3.1.54, mergeCells (Merge Cells)

a. *The standard states that the maxOccurs value for the mergeCell child element is unbounded.*

Excel limits the occurrences of this element to 4294967294.

2.1.661 Part 4 Section 3.3.1.55, oddFooter (Odd Page Footer)

a. *The standard does not limit the length of the value of this element.*

Excel restricts the value of this element to be at most 255 characters.

b. *The standard makes no mention of an xml:space attribute.*

Excel uses this attribute to specify, using the W3C space preservation rules, how white space should be handled for the element's contents; its allowed values are defined by the XML 1.0 specification.

2.1.662 Part 4 Section 3.3.1.56, oddHeader (Odd Header)

a. *The standard does not limit the length of the value of this element.*

Excel restricts the value of this element to be at most 255 characters.

b. *The standard makes no mention of an xml:space attribute.*

Excel uses this attribute to specify, using the W3C space preservation rules, how white space should be handled for the element's contents; its allowed values are defined by the XML 1.0 specification.

2.1.663 Part 4 Section 3.3.1.57, oleObject (Embedded Object)

- a. *The standard allows any string for progId attribute.*

Office requires that the value of @progId be less than 39 characters in length and shall not start with a digit, contain any punctuation (including underscores) other than periods.

- b. *The standard allows any Xstring for link attribute.*

Office requires that the value of @link be a formula as defined in "[ECMA-376](#) Part 4 §3.17; Formulas". The length of the decoded string shall not exceed 8192 characters.

- c. *The standard does not specify any restriction of valid values for the attribute shapeId.*

Office requires @min to be between 1 and 67098623 inclusive.

- d. *The standard does not call out a type of the shape specified by the shapeId attribute.*

In Office, only Picture shapes are valid ObjectTypes for the shapeID attribute.

2.1.664 Part 4 Section 3.3.1.58, oleObjects (Embedded Objects)

- a. *The standard states that the maxOccurs value for the oleObject child element is unbounded.*

Excel limits the occurrences of this element to 65535.

2.1.665 Part 4 Section 3.3.1.60, pageMargins (Page Margins)

- a. *The standard states that the values of the left attribute are defined by the XML Schema double datatype.*

In Office, the left attribute is limited to between 0 inclusive and 49 exclusive.

- b. *The standard states that the values of the right attribute are defined by the XML Schema double datatype.*

In Office, the right attribute is limited to between 0 inclusive and 49 exclusive.

- c. *The standard states that the values of the top attribute are defined by the XML Schema double datatype.*

In Office, the top attribute is limited to between 0 inclusive and 49 exclusive.

- d. *The standard states that the values of the bottom attribute are defined by the XML Schema double datatype.*

In Office, the bottom attribute is limited to between 0 inclusive and 49 exclusive.

- e. *The standard states that values of the header attribute are defined by the XML Schema double datatype.*

In Office, the header attribute is limited to between 0 inclusive and 49 exclusive.

- f. *The standard states that values of the footer attribute are defined by the XML Schema double datatype.*

In Office, the footer attribute is limited to between 0 inclusive and 49 exclusive.

2.1.666 Part 4 Section 3.3.1.61, pageSetup (Page Setup Settings)

For additional notes that apply to this portion of the standard, please see the notes for [pageSetup. §5.7.2.135\(b\)](#).

a. *The standard specifies that the scale attribute ranges from 10 to 400.*

Excel also allow for a value of zero, which is interpreted as the automatic setting.

b. *The standard states that the values of the horizontalDpi attribute are defined by the XML Schema unsignedInt datatype.*

Excel restricts the value of this attribute to be at least 1.

c. *The standard states that the values of the verticalDpi attribute are defined by the XML Schema unsignedInt datatype.*

Excel restricts the value of this attribute to be at least 1.

d. *The standard states that the values of the copies attribute are defined by the XML Schema unsignedInt datatype.*

Excel restricts the value of this attribute to be at least 1 and at most 32767.

e. *The standard states that the values of the firstPageNumber attribute are defined by the XML Schema unsignedInt datatype.*

Excel restricts the value of this attribute to be at most 32767 for the positive first page range and at least 4294967295 (-1) and at most 4294934531 (-32767) for the negative first page range.

f. *The standard states that the values of the fitToWidth attribute are defined by the XML Schema unsignedInt datatype.*

Excel restricts the value of this attribute to be at most 32767.

g. *The standard states that the values of the fitToHeight attribute are defined by the XML Schema unsignedInt datatype.*

Excel restricts the value of this attribute to be at most 32767.

h. *The standard provides a list of paper sizes supported by the paperSize attribute.*

The paperSize attribute specifies the paper size according to the following table. Values larger than or equal to 256 specify custom printer paper sizes. The default value may vary by locale and default printer. Values between 118 and 256 are reserved for future use.

| Value | Meaning |
|-------|-------------------------------|
| 1 | US Letter 8 1/2 x 11 in |
| 2 | US Letter Small 8 1/2 x 11 in |
| 3 | US Tabloid 11 x 17 in |
| 4 | US Ledger 17 x 11 in |
| 5 | US Legal 8 1/2 x 14 in |

| Value | Meaning |
|--------------|--------------------------------|
| 6 | US Statement 5 1/2 x 8 1/2 in |
| 7 | US Executive 7 1/4 x 10 1/2 in |
| 8 | A3 297 x 420 mm |
| 9 | A4 210 x 297 mm |
| 10 | A4 Small 210 x 297 mm |
| 11 | A5 148 x 210 mm |
| 12 | B4 (JIS) 250 x 354 |
| 13 | B5 (JIS) 182 x 257 mm |
| 14 | Folio 8 1/2 x 13 in |
| 15 | Quarto 215 x 275 mm |
| 16 | 10 x 14 in |
| 17 | 11 x 17 in |
| 18 | US Note 8 1/2 x 11 in |
| 19 | US Envelope #9 3 7/8 x 8 7/8 |
| 20 | US Envelope #10 4 1/8 x 9 1/2 |
| 21 | US Envelope #11 4 1/2 x 10 3/8 |
| 22 | US Envelope #12 4 1/2 x 11 |
| 23 | US Envelope #14 5 x 11 1/2 |
| 24 | C size sheet |
| 25 | D size sheet |
| 26 | E size sheet |
| 27 | Envelope DL 110 x 220mm |
| 28 | Envelope C5 162 x 229 mm |
| 29 | Envelope C3 324 x 458 mm |
| 30 | Envelope C4 229 x 324 mm |
| 31 | Envelope C6 114 x 162 mm |
| 32 | Envelope C65 114 x 229 mm |
| 33 | Envelope B4 250 x 353 mm |
| 34 | Envelope B5 176 x 250 mm |
| 35 | Envelope B6 176 x 125 mm |

| Value | Meaning |
|--------------|---------------------------------------|
| 36 | Envelope 110 x 230 mm |
| 37 | US Envelope Monarch 3.875 x 7.5 in |
| 38 | 6 3/4 US Envelope 3 5/8 x 6 1/2 in |
| 39 | US Std Fanfold 14 7/8 x 11 in |
| 40 | German Std Fanfold 8 1/2 x 12 in |
| 41 | German Legal Fanfold 8 1/2 x 13 in |
| 42 | B4 (ISO) 250 x 353 mm |
| 43 | Japanese Postcard 100 x 148 mm |
| 44 | 9 x 11 in |
| 45 | 10 x 11 in |
| 46 | 15 x 11 in |
| 47 | Envelope Invite 220 x 220 mm |
| 48 | RESERVED--DO NOT USE |
| 49 | RESERVED--DO NOT USE |
| 50 | US Letter Extra 9 \275 x 12 in |
| 51 | US Legal Extra 9 \275 x 15 in |
| 52 | US Tabloid Extra 11.69 x 18 in |
| 53 | A4 Extra 9.27 x 12.69 in |
| 54 | Letter Transverse 8 \275 x 11 in |
| 55 | A4 Transverse 210 x 297 mm |
| 56 | Letter Extra Transverse 9\275 x 12 in |
| 57 | SuperA/SuperA/A4 227 x 356 mm |
| 58 | SuperB/SuperB/A3 305 x 487 mm |
| 59 | US Letter Plus 8.5 x 12.69 in |
| 60 | A4 Plus 210 x 330 mm |
| 61 | A5 Transverse 148 x 210 mm |
| 62 | B5 (JIS) Transverse 182 x 257 mm |
| 63 | A3 Extra 322 x 445 mm |
| 64 | A5 Extra 174 x 235 mm |
| 65 | B5 (ISO) Extra 201 x 276 mm |

| Value | Meaning |
|--------------|---|
| 66 | A2 420 x 594 mm |
| 67 | A3 Transverse 297 x 420 mm |
| 68 | A3 Extra Transverse 322 x 445 mm |
| 69 | Japanese Double Postcard 200 x 148 mm |
| 70 | A6 105 x 148 mm |
| 71 | Japanese Envelope Kaku #2 |
| 72 | Japanese Envelope Kaku #3 |
| 73 | Japanese Envelope Chou #3 |
| 74 | Japanese Envelope Chou #4 |
| 75 | Letter Rotated 11 x 8 1/2 11 in |
| 76 | A3 Rotated 420 x 297 mm |
| 77 | A4 Rotated 297 x 210 mm |
| 78 | A5 Rotated 210 x 148 mm |
| 79 | B4 (JIS) Rotated 364 x 257 mm |
| 80 | B5 (JIS) Rotated 257 x 182 mm |
| 81 | Japanese Postcard Rotated 148 x 100 mm |
| 82 | Double Japanese Postcard Rotated 148 x 200 mm |
| 83 | A6 Rotated 148 x 105 mm |
| 84 | Japanese Envelope Kaku #2 Rotated |
| 85 | Japanese Envelope Kaku #3 Rotated |
| 86 | Japanese Envelope Chou #3 Rotated |
| 87 | Japanese Envelope Chou #4 Rotated |
| 88 | B6 (JIS) 128 x 182 mm |
| 89 | B6 (JIS) Rotated 182 x 128 mm |
| 90 | 12 x 11 in |
| 91 | Japanese Envelope You #4 |
| 92 | Japanese Envelope You #4 Rotated |
| 93 | PRC 16K 146 x 215 mm |
| 94 | PRC 32K 97 x 151 mm |
| 95 | PRC 32K(Big) 97 x 151 mm |

| Value | Meaning |
|-------|---------------------------------------|
| 96 | PRC Envelope #1 102 x 165 mm |
| 97 | PRC Envelope #2 102 x 176 mm |
| 98 | PRC Envelope #3 125 x 176 mm |
| 99 | PRC Envelope #4 110 x 208 mm |
| 100 | PRC Envelope #5 110 x 220 mm |
| 101 | PRC Envelope #6 120 x 230 mm |
| 102 | PRC Envelope #7 160 x 230 mm |
| 103 | PRC Envelope #8 120 x 309 mm |
| 104 | PRC Envelope #9 229 x 324 mm |
| 105 | PRC Envelope #10 324 x 458 mm |
| 106 | PRC 16K Rotated |
| 107 | PRC 32K Rotated |
| 108 | PRC 32K(Big) Rotated |
| 109 | PRC Envelope #1 Rotated 165 x 102 mm |
| 110 | PRC Envelope #2 Rotated 176 x 102 mm |
| 111 | PRC Envelope #3 Rotated 176 x 125 mm |
| 112 | PRC Envelope #4 Rotated 208 x 110 mm |
| 113 | PRC Envelope #5 Rotated 220 x 110 mm |
| 114 | PRC Envelope #6 Rotated 230 x 120 mm |
| 115 | PRC Envelope #7 Rotated 230 x 160 mm |
| 116 | PRC Envelope #8 Rotated 309 x 120 mm |
| 117 | PRC Envelope #9 Rotated 324 x 229 mm |
| 118 | PRC Envelope #10 Rotated 458 x 324 mm |

2.1.667 Part 4 Section 3.3.1.62, pageSetup (Chart Sheet Page Setup)

a. *The standard states that the values of the firstPageNumber attribute are defined by the XML Schema unsignedInt datatype.*

Excel restricts the value of this attribute to be at most 65534.

b. *The standard states that the values of the copies attribute are defined by the XML Schema unsignedInt datatype.*

Excel restricts the value of this attribute to be at least 1 and at most 32767.

c. The standard states that the values of the *horizontalDpi* attribute are defined by the XML Schema *unsignedInt* datatype.

Excel restricts the value of this attribute to be at least 1.

d. The standard states that the values of the *verticalDpi* attribute are defined by the XML Schema *unsignedInt* datatype.

Excel restricts the value of this attribute to be at least 1.

e. The standard states that the *paperSize* attribute allows values as defined in the table.

The *paperSize* attribute specifies the paper size according to the following table. The value 0, or values larger than or equal to 256 specify custom printer paper sizes. Values between 118 and 256 are reserved for future use.

| Value | Meaning |
|-------|--------------------------------|
| 1 | US Letter 8 1/2 x 11 in |
| 2 | US Letter Small 8 1/2 x 11 in |
| 3 | US Tabloid 11 x 17 in |
| 4 | US Ledger 17 x 11 in |
| 5 | US Legal 8 1/2 x 14 in |
| 6 | US Statement 5 1/2 x 8 1/2 in |
| 7 | US Executive 7 1/4 x 10 1/2 in |
| 8 | A3 297 x 420 mm |
| 9 | A4 210 x 297 mm |
| 10 | A4 Small 210 x 297 mm |
| 11 | A5 148 x 210 mm |
| 12 | B4 (JIS) 250 x 354 |
| 13 | B5 (JIS) 182 x 257 mm |
| 14 | Folio 8 1/2 x 13 in |
| 15 | Quarto 215 x 275 mm |
| 16 | 10 x 14 in |
| 17 | 11 x 17 in |
| 18 | US Note 8 1/2 x 11 in |
| 19 | US Envelope #9 3 7/8 x 8 7/8 |
| 20 | US Envelope #10 4 1/8 x 9 1/2 |
| 21 | US Envelope #11 4 1/2 x 10 3/8 |

| Value | Meaning |
|--------------|------------------------------------|
| 22 | US Envelope #12 4 \276 x 11 |
| 23 | US Envelope #14 5 x 11 1/2 |
| 24 | C size sheet |
| 25 | D size sheet |
| 26 | E size sheet |
| 27 | Envelope DL 110 x 220mm |
| 28 | Envelope C5 162 x 229 mm |
| 29 | Envelope C3 324 x 458 mm |
| 30 | Envelope C4 229 x 324 mm |
| 31 | Envelope C6 114 x 162 mm |
| 32 | Envelope C65 114 x 229 mm |
| 33 | Envelope B4 250 x 353 mm |
| 34 | Envelope B5 176 x 250 mm |
| 35 | Envelope B6 176 x 125 mm |
| 36 | Envelope 110 x 230 mm |
| 37 | US Envelope Monarch 3.875 x 7.5 in |
| 38 | 6 3/4 US Envelope 3 5/8 x 6 1/2 in |
| 39 | US Std Fanfold 14 7/8 x 11 in |
| 40 | German Std Fanfold 8 1/2 x 12 in |
| 41 | German Legal Fanfold 8 1/2 x 13 in |
| 42 | B4 (ISO) 250 x 353 mm |
| 43 | Japanese Postcard 100 x 148 mm |
| 44 | 9 x 11 in |
| 45 | 10 x 11 in |
| 46 | 15 x 11 in |
| 47 | Envelope Invite 220 x 220 mm |
| 48 | RESERVED--DO NOT USE |
| 49 | RESERVED--DO NOT USE |
| 50 | US Letter Extra 9 \275 x 12 in |
| 51 | US Legal Extra 9 \275 x 15 in |

| Value | Meaning |
|--------------|--|
| 52 | US Tabloid Extra 11.69 x 18 in |
| 53 | A4 Extra 9.27 x 12.69 in |
| 54 | Letter Transverse 8 1/2 x 11 in |
| 55 | A4 Transverse 210 x 297 mm |
| 56 | Letter Extra Transverse 9 1/2 x 12 in |
| 57 | SuperA/SuperA/A4 227 x 356 mm |
| 58 | SuperB/SuperB/A3 305 x 487 mm |
| 59 | US Letter Plus 8.5 x 12.69 in |
| 60 | A4 Plus 210 x 330 mm |
| 61 | A5 Transverse 148 x 210 mm |
| 62 | B5 (JIS) Transverse 182 x 257 mm |
| 63 | A3 Extra 322 x 445 mm |
| 64 | A5 Extra 174 x 235 mm |
| 65 | B5 (ISO) Extra 201 x 276 mm |
| 66 | A2 420 x 594 mm |
| 67 | A3 Transverse 297 x 420 mm |
| 68 | A3 Extra Transverse 322 x 445 mm |
| 69 | Japanese Double Postcard 200 x 148 mm |
| 70 | A6 105 x 148 mm |
| 71 | Japanese Envelope Kaku #2 |
| 72 | Japanese Envelope Kaku #3 |
| 73 | Japanese Envelope Chou #3 |
| 74 | Japanese Envelope Chou #4 |
| 75 | Letter Rotated 11 x 8 1/2 11 in |
| 76 | A3 Rotated 420 x 297 mm |
| 77 | A4 Rotated 297 x 210 mm |
| 78 | A5 Rotated 210 x 148 mm |
| 79 | B4 (JIS) Rotated 364 x 257 mm |
| 80 | B5 (JIS) Rotated 257 x 182 mm |
| 81 | Japanese Postcard Rotated 148 x 100 mm |

| Value | Meaning |
|--------------|---|
| 82 | Double Japanese Postcard Rotated 148 x 200 mm |
| 83 | A6 Rotated 148 x 105 mm |
| 84 | Japanese Envelope Kaku #2 Rotated |
| 85 | Japanese Envelope Kaku #3 Rotated |
| 86 | Japanese Envelope Chou #3 Rotated |
| 87 | Japanese Envelope Chou #4 Rotated |
| 88 | B6 (JIS) 128 x 182 mm |
| 89 | B6 (JIS) Rotated 182 x 128 mm |
| 90 | 12 x 11 in |
| 91 | Japanese Envelope You #4 |
| 92 | Japanese Envelope You #4 Rotated |
| 93 | PRC 16K 146 x 215 mm |
| 94 | PRC 32K 97 x 151 mm |
| 95 | PRC 32K(Big) 97 x 151 mm |
| 96 | PRC Envelope #1 102 x 165 mm |
| 97 | PRC Envelope #2 102 x 176 mm |
| 98 | PRC Envelope #3 125 x 176 mm |
| 99 | PRC Envelope #4 110 x 208 mm |
| 100 | PRC Envelope #5 110 x 220 mm |
| 101 | PRC Envelope #6 120 x 230 mm |
| 102 | PRC Envelope #7 160 x 230 mm |
| 103 | PRC Envelope #8 120 x 309 mm |
| 104 | PRC Envelope #9 229 x 324 mm |
| 105 | PRC Envelope #10 324 x 458 mm |
| 106 | PRC 16K Rotated |
| 107 | PRC 32K Rotated |
| 108 | PRC 32K(Big) Rotated |
| 109 | PRC Envelope #1 Rotated 165 x 102 mm |
| 110 | PRC Envelope #2 Rotated 176 x 102 mm |
| 111 | PRC Envelope #3 Rotated 176 x 125 mm |

| Value | Meaning |
|-------|---------------------------------------|
| 112 | PRC Envelope #4 Rotated 208 x 110 mm |
| 113 | PRC Envelope #5 Rotated 220 x 110 mm |
| 114 | PRC Envelope #6 Rotated 230 x 120 mm |
| 115 | PRC Envelope #7 Rotated 230 x 160 mm |
| 116 | PRC Envelope #8 Rotated 309 x 120 mm |
| 117 | PRC Envelope #9 Rotated 324 x 229 mm |
| 118 | PRC Envelope #10 Rotated 458 x 324 mm |

f. *The standard states that the values of the paperSize attribute are defined by the XML Schema unsignedInt datatype.*

Excel restricts the value of this attribute to be at most 2147483647.

2.1.668 Part 4 Section 3.3.1.64, pane (View Pane)

a. *In the standard the TopLeftCell attribute currently states use equals optional.*

Office treats the TopLeftCell attribute as optional if state equals split; otherwise, it is required.

b. *The standard does not define what the value for the xSplit attribute indicates if the parent element is customSheetView.*

In Office, when parent is customSheetView, the xSplit attribute is always saved as the number of columns (regardless of frozen or unfrozen state).

c. *The standard does not define what the value for the ySplit attribute indicates if the parent element is customSheetView.*

In Office, when parent is customSheetView, the ySplit attribute is always saved as the number of rows (regardless of frozen or unfrozen state).

d. *In the standard the xSplit and ySplit definitions are reversed.*

In Office, xSplit is the Vertical split position and columns visible in the left pane, and ySplit is the Horizontal split position and columns visible in the top pane.

e. *The standard states that the xSplit and ySplit values can be zero indicating none for that setting.*

Office does not support setting xSplit and ySplit to Zero when the parent element is SheetView.

2.1.669 Part 4 Section 3.3.1.66, pivotArea (Pivot Area)

a. *The standard does not state that the dataOnly attribute can be true only if the labelOnly attribute is false.*

Office allows the dataOnly attribute to be true only if the labelOnly attribute is false.

b. *The standard does not state that the labelOnly attribute can be true only if the dataOnly attribute is false.*

Office allows the labelOnly attribute to be true only if the dataOnly attribute is false.

c. *The standard does not specify a default value for the field attribute.*

Excel uses a default value of -1 for this attribute.

d. *The standard does not restrict the value of the fieldPosition attribute.*

In Office, the fieldPosition attribute represents the position of the field within the axis to which this rule applies. If cacheIndex is true, the value of this field shall be greater than or equal to zero and less than 256. If cacheIndex is false, then if the axis value is axisRow, the value of fieldPosition shall be less than the number of elements in the row fields collection ("ECMA-376 Part 4 §3.10.1.81; rowFields (Row Fields)"). If the axis value is axisCol, the value of fieldPosition shall be less than the number of elements in the column fields collection ("ECMA-376 Part 4 §3.10.1.14; colFields (Column Fields)"). If the axis value is axisPage, the value of fieldPosition shall be less than number of elements in page fields collection ("ECMA-376 Part 4 §3.10.1.63; pageFields (Page Field Items)"). If axis value is axisData, the value of fieldPosition shall be less than the number of elements in the data fields collection ("ECMA-376 Part 4 §3.10.1.13; dataFields (Data Fields)").

e. *The standard does not place restrictions on the value of the field attribute.*

In Office, the field attribute represents a zero-based index of the field that this selection rule refers to. The value of this field can be -1 (it references nothing) or the value can be -2 (it references data). Otherwise, if cacheIndex is true, it shall be greater than or equal to zero and less than the number of elements in the cacheFields collection in the pivot cache definition ("ECMA-376 Part 4 §3.10.1.67; pivotCacheDefinition (PivotCache Definition)"); if the cacheIndex is false, the value shall be less than the number of elements in the pivot fields (§3.10.1.70 pivotFields (PivotTable Fields)) collection ("ECMA-376 Part 4 §3.10.1.70; pivotFields (PivotTable Fields)").

2.1.670 Part 4 Section 3.3.1.67, pivotSelection (PivotTable Selection)

a. *The standard does not specify any relationships for the data attribute.*

Office requires that the data attribute be false when the label attribute is true.

b. *The standard states that the values of the previousRow attribute are defined by the XML Schema unsignedInt datatype.*

Excel restricts the value of this attribute to be at most 1048575.

c. *The standard states that the values of the previousCol attribute are defined by the XML Schema unsignedInt datatype.*

Excel restricts the value of this attribute to be at most 16383.

d. *The standard states that the values of the dimension attribute are defined by the XML Schema unsignedInt datatype.*

In Excel, if the axis attribute equals axisRow, then the dimension attribute must be less than number of elements in the rowFields collection. If the axis attribute equals axisCol, then the dimension attribute must be less than number of elements in the columnFields collection. If the axis attribute equals axisPage, then the dimension attribute equals 0.

e. *The standard states that the values for the min attribute are defined by the XML Schema unsignedInt datatype.*

In Excel, if the axis attribute equals axisRow, then the min attribute must be less than the number of elements in the rowItems collection. If the axis attribute equals axisCol, then the min attribute must be less than the number of elements in the colItems collection. When the axis attribute equals axisPage, then the min attribute must be 0.

f. *The standard states that @max is not restricted beyond unsigned int.*

In Excel, if @axis=axisRow, @max shall be less than the number of elements in rowItems collection. If @axis=axisCol, @max shall be less than the number of elements in colItems. When @axis=axisPage then @max shall be 0.

g. *The standard does not limit @start beyond unsigned int.*

Office requires that @min < @start < @max+1.

h. *The standard does not define the valid set of values for the activeRow or the activeCol attributes.*

Office requires that the following conditions be true:

If **axis** is set to *axisRow*, then the valid set of values for the activeRow or activeCol attributes should be within the Row axis area.

If **axis** is set to *axisCol*, then the valid set of values for the activeRow or activeCol attributes should be within the Column axis area.

If **axis** is set to *axisPage*, then the valid set of values for the activeRow or activeCol attributes should be within the Page/Report Filter axis area.

i. *The standard defines values for the pane attribute.*

In Office, topLeft is interpreted as bottomRight and vice versa.

j. *The standard states that the r:id attribute is optional.*

Excel requires this attribute.

k. *The standard states that the axis attribute has a valid value of axisPage.*

Office will report a valid file as corrupt if axis is equal to axisPage.

l. *The standard states that the valid values for the axis attribute are defined by the ST_Axis simple type.*

Office does not allow the axis attribute to equal axisValue.

2.1.671 Part 4 Section 3.3.1.69, protectedRange (Protected Range)

a. *The standard sets no restrictions on the string for the name attribute.*

Office requires that the name attribute shall be unique within the parent element collection, start with a letter, only contain letters, numbers, spaces, underscores, periods, backslashes, or question marks.

b. *The standard does not define the minimum values for the sqref attribute.*

Office defines the minimum value for the sqref attribute to be 1.

c. *The standard does not limit the length of the value of the name attribute.*

Word restricts the value of this attribute to be at least 1 and at most 255 characters.

d. *The standard states that this setting uses a specific Password attribute to store the password hash.*

In Office, when the HKCU/Software/Microsoft/Office/<VERSION>/Common/Security/UseIsoPasswordVerifier registry key is set to 1, the XML for file sharing is written by using the XML attribute structure in the following table.

| Name | Description |
|-----------------------|---|
| algorithm Name | <p>The name of the cryptographic hashing algorithm used to generate the hash value. Only those algorithms that are installed in the operating system's cryptographic subsystem can be utilized by Office.</p> <p>The hash algorithm names, described in the following table, are reserved.</p> <p>MD2</p> <p><i>Specifies that the MD2 algorithm, as defined by RFC 1319, shall be used.</i></p> <p><i>[Note: It is recommended that applications should avoid using this algorithm to store new hash values, because of publicly known breaks. end note]</i></p> <p>MD4</p> <p><i>Specifies that the MD4 algorithm, as defined by RFC 1320, shall be used.</i></p> <p><i>[Note: It is recommended that applications should avoid using this algorithm to store new hash values, because of publicly known breaks. end note]</i></p> <p>MD5</p> <p><i>Specifies that the MD5 algorithm, as defined by RFC 1321, shall be used.</i></p> <p><i>[Note: It is recommended that applications should avoid using this algorithm to store new hash values, because of publicly known breaks. end note]</i></p> <p>RIPEDM-128</p> <p><i>Specifies that the RIPEDM-128 algorithm, as defined by ISO/IEC 10118-3:2004 shall be used.</i></p> <p><i>[Note: It is recommended that applications should avoid using this algorithm to store new hash values, because of publicly known breaks. end note]</i></p> <p>RIPEDM-160</p> <p><i>Specifies that the RIPEDM-160 algorithm, as defined by ISO/IEC 10118-3:2004, shall be used.</i></p> <p>SHA-1</p> <p><i>Specifies that the SHA-1 algorithm, as defined by ISO/IEC 10118-3:2004, shall be used.</i></p> <p>SHA-256</p> <p><i>Specifies that the SHA-256 algorithm, as defined by ISO/IEC 10118-3:2004, shall be used.</i></p> <p>SHA-384</p> <p><i>Specifies that the SHA-384 algorithm, as defined by ISO/IEC 10118-3:2004, shall be used.</i></p> <p>SHA-512</p> <p><i>Specifies that the SHA-512 algorithm, as defined by ISO/IEC 10118-3:2004, shall be used.</i></p> <p>WHIRLPOOL</p> <p><i>Specifies that the WHIRLPOOL algorithm, as defined by ISO/IEC 10118-3:2004, shall be used.</i></p> |

| Name | Description |
|-------------------|--|
| hash Value | <p>Specifies the hash value for the password required to edit this worksheet. This value shall be compared with the resulting hash value after hashing the user-supplied password using the algorithm specified by the preceding attributes and parent XML element. If the two values match, the protection shall no longer be enforced.</p> <p>If this value is omitted, then the reservationPassword attribute shall contain the password hash for the workbook.</p> <p>[<i>Example:</i> Consider an Office Open XML document with the following information stored in one of its protection elements:</p> <pre data-bbox="402 436 1295 468"><... algorithmName="SHA-1" hashValue="9oN7nWkCAyEZib1RomSJTjmPpCY=" /></pre> <p>The hashValue attribute value of 9oN7nWkCAyEZib1RomSJTjmPpCY= specifies that the user-supplied password must be hashed using the pre-processing defined by the parent element (if any) followed by the hashing algorithm (specified via the algorithmName attribute value) and that the resulting hash value must be match for the protection to be disabled.</p> <p><i>end example]</i></p> <p>The possible values for this attribute are defined by the W3C XML Schema base64Binary datatype.</p> |
| saltValue | <p>Specifies the random bytes that are pre-pended to the user-supplied password before it was hashed by the hashing algorithm.</p> |
| spinCount | <p>Specifies the number of times the hashing function shall be iteratively run (using each iteration's result as the input for the next iteration).</p> |

[*Example:*

Consider an Office Open XML document with the following information stored in one of its protection elements:

```
< ... algorithmName="SHA-1" hashValue="9oN7nWkCAyEZib1RomSJTjmPpCY=" />
```

The algorithmName attribute value of SHA-1 specifies that the SHA-1 hashing algorithm must be used to generate a hash from the user-defined password.

end example]

This note applies to the following products: 2007 SP2, 2010.

2.1.672 Part 4 Section 3.3.1.71, row (Row)

a. *The standard states that the values of the r attribute are defined by the XML Schema unsignedInt datatype.*

Office requires that the r attribute be between 1 and 1048576 inclusive, and shall be in non-decreasing order.

b. *The standard states that the values of the outlineLevel attribute are defined by the XML Schema unsignedByte datatype.*

Office requires that the value of the outlineLevel attribute be between 0 and 7 inclusive.

c. *The standard states that the values of the s attribute are defined by the XML Schema unsignedInt datatype.*

Office requires that the value of the s attribute be between 0 and 65490 inclusive.

2.1.673 Part 4 Section 3.3.1.72, rowBreaks (Horizontal Page Breaks (Row))

For additional notes that apply to this portion of the standard, please see the notes for [colBreaks, §3.3.1.13\(a, b\)](#).

- a. *The standard states that the count attribute is defined by unsignedInt.*

Office defines count to be an xsd:unsignedInt less than 1023.

- b. *The standard states that the manualBreakCount attribute is defined by unsignedInt.*

Office defines manualBreakCount to be an xsd:unsignedInt less than 1023.

2.1.674 Part 4 Section 3.3.1.73, scenario (Scenario)

- a. *The standard states that the values of the count attribute are defined by the XML Schema unsignedInt datatype.*

Excel restricts the value of this attribute to be at least 1 and at most 32.

- b. *The standard states that the maxOccurs value for the inputCells child element is unbounded.*

Excel limits the occurrences of this element to 32.

- c. *The standard does not limit the length of the value of the name attribute.*

Excel restricts the value of this attribute to be at most 255 characters, after decoding.

- d. *The standard states that the name attribute must be unique for the workbook.*

Office only requires that the name attribute be unique for each worksheet (allows duplicates in a workbook).

- e. *The standard does not limit the length of the value of the user attribute.*

Excel restricts the value of this attribute to be at least 1 and at most 54 characters, after decoding.

- f. *The standard does not limit the length of the value of the comment attribute.*

Excel restricts the value of this attribute to be at most 255 characters, after decoding.

2.1.675 Part 4 Section 3.3.1.74, scenarios (Scenarios)

- a. *In the standard, the current and show attributes do not have upper limits.*

In Excel, both the current and show attributes must be less than the number of child scenario elements.

2.1.676 Part 4 Section 3.3.1.75, selection (Selection)

- a. *The standard does not specify a default value for the activeCell attribute.*

Excel uses a default value of A1 for this attribute.

- b. *The standard states that the values of the activeCellId attribute are defined by the XML Schema unsignedInt datatype.*

Excel restricts the value of this attribute to be at most 8191.

2.1.677 Part 4 Section 3.3.1.78, sheetFormatPr (Sheet Format Properties)

a. *The standard does not place any restrictions on the value of the outlineLevelRow or outlineLevelCol attributes.*

Office requires that the outlineLevelRow and outlineLevelCol attributes be between 0 and 7 inclusive.

b. *The standard does not place any restrictions on the value of @baseColWidth.*

Office requires that @baseColWidth have a maximum value of less than or equal to 255.

c. *The standard does not place restrictions on the value of the defaultColWidth attribute.*

Office requires that the defaultColWidth attribute be less than 65536 and greater than or equal to zero.

2.1.678 Part 4 Section 3.3.1.79, sheetPr (Sheet Properties)

a. *The standard allows any range reference for the syncRef attribute.*

In Office, the syncRef attribute specifies a valid cell reference only when either the syncHorizontal or the syncVertical attributes is true.

b. *The standard states that the values of the codeName attribute are defined by the XML Schema string datatype.*

Office requires the codeName attribute to be less than 32 characters with the following pattern restriction: `[\p{L}\P{IsBasicLatin}][_\d\p{L}\P{IsBasicLatin}]*`.

c. *The standard specifies the codeName attribute is valid for all parents.*

In Office, the codeName attribute is only valid for the worksheet parent.

2.1.679 Part 4 Section 3.3.1.80, sheetPr (Chart Sheet Properties)

a. *The standard specifies @codeName can be any xsd:string.*

Office requires @codeName to be less than 32 characters with the following pattern restriction: `[\p{L}\P{IsBasicLatin}][_\d\p{L}\P{IsBasicLatin}]*`.

2.1.680 Part 4 Section 3.3.1.81, sheetProtection (Sheet Protection Options)

a. *The standard does not specify any restrictions for a dialogsheets parent element.*

For a **dialogsheets** parent element, Office requires that the dialog sheet is protected when the attributes **objects** and **scenarios** are *true*. The dialog sheet should not be protected when the attributes **objects** and **scenarios** are *false*. No other values are allowed. In addition, the **sheet** attribute is always *true* and all other attributes are their default value.

b. *The standard states that this setting uses a specific Password attribute to store the password hash.*

In Office, when the HKCU/Software/Microsoft/Office/<VERSION>/Common/Security/UseIsoPasswordVerifier registry key is set to 1, the XML for file sharing is written by using the XML attribute structure in the following table.

| Name | Description |
|-----------------------|---|
| algorithm Name | <p>The name of the cryptographic hashing algorithm used to generate the hash value. Only those algorithms that are installed in the operating system's cryptographic subsystem can be utilized by Office.</p> <p>The hash algorithm names, described in the following table, are reserved.</p> <p>MD2 <i>Specifies that the MD2 algorithm, as defined by RFC 1319, shall be used.</i> <i>[Note: It is recommended that applications should avoid using this algorithm to store new hash values, because of publicly known breaks. end note]</i></p> <p>MD4 <i>Specifies that the MD4 algorithm, as defined by RFC 1320, shall be used.</i> <i>[Note: It is recommended that applications should avoid using this algorithm to store new hash values, because of publicly known breaks. end note]</i></p> <p>MD5 <i>Specifies that the MD5 algorithm, as defined by RFC 1321, shall be used.</i> <i>[Note: It is recommended that applications should avoid using this algorithm to store new hash values, because of publicly known breaks. end note]</i></p> <p>RIPEDM-128 <i>Specifies that the RIPEDM-128 algorithm, as defined by ISO/IEC 10118-3:2004 shall be used.</i> <i>[Note: It is recommended that applications should avoid using this algorithm to store new hash values, because of publicly known breaks. end note]</i></p> <p>RIPEDM-160 <i>Specifies that the RIPEDM-160 algorithm, as defined by ISO/IEC 10118-3:2004, shall be used.</i></p> <p>SHA-1 <i>Specifies that the SHA-1 algorithm, as defined by ISO/IEC 10118-3:2004, shall be used.</i></p> <p>SHA-256 <i>Specifies that the SHA-256 algorithm, as defined by ISO/IEC 10118-3:2004, shall be used.</i></p> <p>SHA-384 <i>Specifies that the SHA-384 algorithm, as defined by ISO/IEC 10118-3:2004, shall be used.</i></p> <p>SHA-512 <i>Specifies that the SHA-512 algorithm, as defined by ISO/IEC 10118-3:2004, shall be used.</i></p> <p>WHIRLPOOL <i>Specifies that the WHIRLPOOL algorithm, as defined by ISO/IEC 10118-3:2004, shall be used.</i></p> |
| hash Value | <p>Specifies the hash value for the password required to edit this worksheet. This value shall be compared with the resulting hash value after hashing the user-supplied password using the algorithm specified by the preceding attributes and parent XML element. If the two values match, the protection shall no longer be enforced.</p> <p>If this value is omitted, then the reservationPassword attribute shall contain the password hash for the workbook.</p> <p><i>[Example: Consider an Office Open XML document with the following information stored in one of its protection elements:</i></p> <pre><... algorithmName="SHA-1" hashValue="9oN7nWkCAyEZib1RomSJTjmPpCY=" /></pre> <p>The hashValue attribute value of 9oN7nWkCAyEZib1RomSJTjmPpCY= specifies that the user-supplied password must be hashed using the pre-processing defined by the parent element (if any) followed by the hashing algorithm (specified via the algorithmName attribute value) and that the resulting hash value must be match for the protection to be disabled.</p> |

| Name | Description |
|------------------|--|
| | <i>end example]</i> The possible values for this attribute are defined by the W3C XML Schema base64Binary datatype. |
| saltValue | Specifies the random bytes that are pre-pended to the user-supplied password before it was hashed by the hashing algorithm. |
| spinCount | Specifies the number of times the hashing function shall be iteratively run (using each iteration's result as the input for the next iteration). |

[*Example:*

Consider an Office Open XML document with the following information stored in one of its protection elements:

```
< ... algorithmName="SHA-1" hashValue="9oN7nWkCAyEZib1RomSJTjmPpCY=" />
```

The algorithmName attribute value of SHA-1 specifies that the SHA-1 hashing algorithm must be used to generate a hash from the user-defined password.

end example]

This note applies to the following products: 2007 SP2, 2010.

2.1.681 Part 4 Section 3.3.1.82, sheetProtection (Chart Sheet Protection)

a. *The standard states that when the content attribute equals true, no changes can be made to chart elements.*

Office allows changes to chart elements, even when the content attribute equals true.

b. *The standard states that this setting uses a specific Password attribute to store the password hash.*

In Office, when the HKCU/Software/Microsoft/Office/<VERSION>/Common/Security/UseIsoPasswordVerifier registry key is set to 1, the XML for file sharing is written by using the XML attribute structure in the following table.

| Name | Description |
|-----------------------|---|
| algorithm Name | The name of the cryptographic hashing algorithm used to generate the hash value. Only those algorithms that are installed in the operating system's cryptographic subsystem can be utilized by Office. The hash algorithm names, described in the following table, are reserved. MD2 <i>Specifies that the MD2 algorithm, as defined by RFC 1319, shall be used.</i> <i>[Note: It is recommended that applications should avoid using this algorithm to store new hash values, because of publicly known breaks. end note]</i> MD4 <i>Specifies that the MD4 algorithm, as defined by RFC 1320, shall be used.</i> <i>[Note: It is recommended that applications should avoid using this algorithm to store new hash values, because of publicly known breaks. end note]</i> |

| Name | Description |
|-------------------|--|
| | <p>MD5 Specifies that the MD5 algorithm, as defined by RFC 1321, shall be used. [Note: It is recommended that applications should avoid using this algorithm to store new hash values, because of publicly known breaks. end note]</p> <p>RIPEMD-128 Specifies that the RIPEMD-128 algorithm, as defined by ISO/IEC 10118-3:2004 shall be used. [Note: It is recommended that applications should avoid using this algorithm to store new hash values, because of publicly known breaks. end note]</p> <p>RIPEMD-160 Specifies that the RIPEMD-160 algorithm, as defined by ISO/IEC 10118-3:2004, shall be used.</p> <p>SHA-1 Specifies that the SHA-1 algorithm, as defined by ISO/IEC 10118-3:2004, shall be used.</p> <p>SHA-256 Specifies that the SHA-256 algorithm, as defined by ISO/IEC 10118-3:2004, shall be used.</p> <p>SHA-384 Specifies that the SHA-384 algorithm, as defined by ISO/IEC 10118-3:2004, shall be used.</p> <p>SHA-512 Specifies that the SHA-512 algorithm, as defined by ISO/IEC 10118-3:2004, shall be used.</p> <p>WHIRLPOOL Specifies that the WHIRLPOOL algorithm, as defined by ISO/IEC 10118-3:2004, shall be used.</p> |
| hash Value | <p>Specifies the hash value for the password required to edit this worksheet. This value shall be compared with the resulting hash value after hashing the user-supplied password using the algorithm specified by the preceding attributes and parent XML element. If the two values match, the protection shall no longer be enforced.</p> <p>If this value is omitted, then the reservationPassword attribute shall contain the password hash for the workbook.</p> <p>[Example: Consider an Office Open XML document with the following information stored in one of its protection elements: <... algorithmName="SHA-1" hashValue="9oN7nWkCAyEZib1RomSJTjmPpCY=" /> The hashValue attribute value of 9oN7nWkCAyEZib1RomSJTjmPpCY= specifies that the user-supplied password must be hashed using the pre-processing defined by the parent element (if any) followed by the hashing algorithm (specified via the algorithmName attribute value) and that the resulting hash value must be match for the protection to be disabled. end example]</p> <p>The possible values for this attribute are defined by the W3C XML Schema base64Binary datatype.</p> |
| saltValue | <p>Specifies the random bytes that are pre-pended to the user-supplied password before it was hashed by the hashing algorithm.</p> |
| spinCount | <p>Specifies the number of times the hashing function shall be iteratively run (using each iteration's result as the input for the next iteration).</p> |

[Example:

Consider an Office Open XML document with the following information stored in one of its protection elements:

```
< ... algorithmName="SHA-1" hashValue="9oN7nWkCAyEZib1RomSJTjmPpCY=" />
```

The algorithmName attribute value of SHA-1 specifies that the SHA-1 hashing algorithm must be used to generate a hash from the user-defined password.

end example]

This note applies to the following products: 2007 SP2, 2010.

2.1.682 Part 4 Section 3.3.1.83, sheetView (Worksheet View)

a. *The standard states that the values of the colorId attribute are defined by the XML Schema unsignedInt datatype.*

Office restricts the colorId attribute value to an unsignedInt less than or equal to 64.

b. *The standard specifies that the @colorId defines the color value for text in row/column headings and gridlines in the view.*

Office uses the @colorId to define the color value only for gridlines in the view.

2.1.683 Part 4 Section 3.3.1.84, sheetView (Chart Sheet View)

a. *The standard states that extLst is a child element of sheetView.*

In Office, extList is persisted under the parent element, sheetViews. If Office opens a file where sheetViews contains an extLst element, it will persist two extLst elements in sheetViews, making the file invalid.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.684 Part 4 Section 3.3.1.85, sheetViews (Sheet Views)

a. *The standard states that the maxOccurs value for the sheetView child element is unbounded.*

Excel limits the occurrences of this element to 2147483647.

2.1.685 Part 4 Section 3.3.1.86, sheetViews (Chart Sheet Views)

a. *The standard states that the maxOccurs value for the sheetView child element is unbounded.*

Excel limits the occurrences of this element to 2147483647.

2.1.686 Part 4 Section 3.3.1.88, sortCondition (Sort Condition)

a. *The standard states that the values of the customList attribute are defined by the ST_Xstring simple type.*

Office requires that the customList attribute value be an escaped string not exceeding 255 UTF-16 code units after escape sequences are replaced with characters.

2.1.687 Part 4 Section 3.3.1.90, tabColor (Sheet Tab Color)

For additional notes that apply to this portion of the standard, please see the notes for [color](#), [§3.3.1.14\(b-d\)](#); [bgColor](#), [§3.8.3\(a\)](#).

a. *The standard does not specify a default value for the auto attribute.*

Excel uses a default value of false for this attribute.

b. *In the standard, the auto, indexed, rgb, and theme attributes are all optional.*

Office requires that only one of the auto, indexed, rgb, or theme attributes shall be specified.

c. *The standard specifies that the theme attribute is an index of an item in the clrScheme collection.*

Office requires the theme attribute to be a zero-based index of an item in the clrScheme collection.

2.1.688 Part 4 Section 3.3.1.93, v (Cell Value)

a. *The standard does not limit the length of the value of this element.*

Excel restricts the value of this element to be at most 32767 characters.

b. *The standard does not place content restrictions on values based on the t attribute.*

Office places the following value restrictions based on the cell type:

If the cell contains a string, the value shall be a zero-based index into the shared string table, pointing to the actual string value.

If the cell contains a number, the value shall be a textual representation of a double-precision floating point number.

If the cell contains a Boolean, the value shall be 1 to specify true and 0 to specify false.

If the cell contains an error, the value shall be one of the following text strings: #NULL!, #DIV/0!, #VALUE!, #REF!, #NAME?, #NUM!, or #N/A.

Cells containing formulas express the last calculated result of the formula in this element.

A spreadsheet application may use inline strings to bypass creating the shared string table. Inline strings are specified by the **is** element under the **c** element instead of the **v** element under the **c** element. Inline strings are specified in the same way a string would be expressed in the shared string table. See the **is** element ("[ECMA-376](#) Part 4 §3.3.1.50; is") for an example.

c. *The standard makes no mention of an xml:space attribute.*

Excel uses this attribute to specify, using the W3C space preservation rules, how white space should be handled for the element's contents; its allowed values are defined by the XML 1.0 specification.

2.1.689 Part 4 Section 3.3.1.94, webPublishItem (Web Publishing Item)

a. *The standard does not place any restrictions on the length of the value for the title attribute.*

Office requires that the title attribute be less than 255 characters in length.

b. *The standard does not place any restrictions on the length of the value for the destinationFile attribute.*

Office requires that the destinationFile attribute be less than 255 characters in length, and not empty.

c. *The standard does not place any restrictions on the length of the value for the `divId` attribute.*

Office requires that the `divId` attribute be less than 255 characters in length, and not empty.

d. *The standard does not place any restrictions on the length of the value for the `sourceObject` attribute.*

Office requires that the `sourceObject` attribute follow the rules of defined names as specified in Names ("[ECMA-376](#) Part 4 §3.17.2.5; Names").

e. *The standard does not place any restrictions on the value for the `id` attribute.*

Office requires that the value of the `id` attribute be between 1 and 2147483647 inclusive.

f. *The standard states that the `sourceObject` attribute is required for `sourceType` equal to `pivotTable`, `query`, or `label`.*

Office requires the `sourceObject` attribute for `sourceType` equal to `pivotTable`, `query`, or `label`. The `sourceObject` attribute shall not be present otherwise.

g. *The standard states that the `sourceRef` attribute is required when the `sourceType` attribute equals `range`.*

Office requires the `sourceRef` attribute shall not be missing if the `sourceType` is a range, otherwise it shall not be present.

h. *The standard states that `sourceObject` specifies the name of an object to be published.*

Office can save a file with a `sourceObject` name that no longer exists.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.690 Part 4 Section 3.3.1.96, `worksheet` (Worksheet)

a. *The standard states that the `maxOccurs` value for the `conditionalFormatting` child element is unbounded.*

Excel limits the occurrences of this element to 2147483647.

2.1.691 Part 4 Section 3.3.2.1, `colorFilter` (Color Filter Criteria)

a. *The standard states that the `dxflId` attribute is optional.*

Excel requires this attribute.

2.1.692 Part 4 Section 3.3.2.4, `dateGroupItem` (Date Grouping)

a. *The standard does not specify a default value for the `month` attribute.*

Excel uses a default value of 1 for this attribute.

b. *The standard does not specify a default value for the `day` attribute.*

Excel uses a default value of 1 for this attribute.

c. *The standard does not specify a default value for the `hour` attribute.*

Excel uses a default value of 0 for this attribute.

d. *The standard does not specify a default value for the minute attribute.*

Excel uses a default value of 0 for this attribute.

e. *The standard does not specify a default value for the second attribute.*

Excel uses a default value of 0 for this attribute.

2.1.693 Part 4 Section 3.3.2.5, dynamicFilter (Dynamic Filter)

a. *The standard does not place any limitations on the value of the val attribute.*

Office requires that the val attribute be less than the maxVal attribute.

b. *The standard states in the description of the val attribute: "See description of maxVal to understand when val is required." However, the description of the maxVal attribute is not clear that both values are required at the same time.*

Office requires that @val is required whenever @maxVal is required.

c. *The standard describes @maxVal as optional and correctly describes instances when it is required and what it means then, but does not state what happens when it is not required.*

Office requires that when @maxVal is not required, it shall not be written out.

2.1.694 Part 4 Section 3.3.2.6, filter (Filter)

a. *The standard implies that the val attribute is optional.*

Excel requires this attribute.

2.1.695 Part 4 Section 3.3.2.7, filterColumn (AutoFilter Column)

a. *The standard does not place limitations on the value of the colId attribute.*

In Office, the colId attribute must be greater than or equal to 0 and less than or equal to the number of columns in the region described by the parent autoFilter element's ref attribute.

2.1.696 Part 4 Section 3.3.2.8, filters (Filter Criteria)

a. *The standard states that the filter and dateGroupItem child elements should be sequenced.*

Excel requires these child elements to be a choice of one or the other.

b. *The standard defines the calendarType attribute for date grouped items.*

Office ignores the calendarType attribute.

2.1.697 Part 4 Section 3.3.2.9, iconFilter (Icon Filter)

a. *The standard does not specify any limitations on the value of the iconId attribute.*

Office requires that value in the iconId attribute is less than the total number of icons in the iconSet.

2.1.698 Part 4 Section 3.3.2.10, top10 (Top 10)

a. *The standard does not mention any limits on the value of @val.*

In Office, if this element is on a pivottable, the @val must be greater than or equal to 0. Otherwise, it must be between 1 and 500 inclusive.

- b. *The standard does not specify a default value for the filterVal attribute.*

Excel uses a default value of 0 for this attribute.

2.1.699 Part 4 Section 3.4.3, phoneticPr (Phonetic Properties)

- a. *The standard states that the type attribute specifies which type of East Asian character set should be used to display the phonetic run.*

Excel uses this attribute to specify which Japanese character set should be used to display the phonetic run.

- b. *The standard states that phonetic text is allowed for East Asian languages.*

Excel restricts phonetic text to the Japanese language.

2.1.700 Part 4 Section 3.4.5, rFont (Font)

- a. *The standard specifies the string length for the val attribute shall be 0 to 31 characters.*

Office requires the length to be that of the string before escaping.

2.1.701 Part 4 Section 3.4.6, rPh (Phonetic Run)

- a. *The standard states that phonetic text is allowed for East Asian languages.*

Excel restricts phonetic text to the Japanese language.

2.1.702 Part 4 Section 3.4.7, rPr (Run Properties)

- a. *The standard defines the child elements using a choice.*

Excel requires the child elements to be in the following sequence: b, i, strike, condense, extend, outline, shadow, u, vertAlign, sz, color, rFont, family, charset, scheme.

2.1.703 Part 4 Section 3.4.8, si (String Item)

- a. *The standard states that t can be an unbounded number of characters.*

Excel restricts t to 32767.

- b. *The standard states that the maxOccurs value for the r child element is unbounded.*

Excel limits the occurrences of this element to 32767.

- c. *The standard states that the maxOccurs value for the rPh child element is unbounded.*

Excel limits the occurrences of this element to 32767.

2.1.704 Part 4 Section 3.4.9, sst (Shared String Table)

- a. *The standard specifies uniqueCount as an unbound unsigned int.*

Office requires the value be less than or equal to 2147483647.

b. *The standard specifies count as an unbound unsigned int.*

Office requires the value be less than or equal to 2147483647.

2.1.705 Part 4 Section 3.4.11, sz (Font Size)

a. *The standard restricts the definition of the sz element to Latin and East Asian text only.*

Office does not restrict the applicability of the sz element to only Latin and East Asian text, that is, it applies to all text.

b. *The standard states that sz is the point size to be used to display text.*

Office converts the points provided to twips, and rounding may occur when writing sz@val back to SpreadsheetML files.

c. *The standard does not specify restrictions on the val attribute.*

Office requires the val attribute to be a double between 1 and 409.55 inclusive.

2.1.706 Part 4 Section 3.4.12, t (Text)

a. *The standard makes no mention of an xml:space attribute.*

Excel uses this attribute to specify, using the W3C space preservation rules, how white space should be handled for the element's contents; its allowed values are defined by the XML 1.0 specification.

b. *The standard places no restrictions on the length of the value of the t element.*

Excel restricts the value of this element to 32767 characters.

2.1.707 Part 4 Section 3.5.1.1, calculatedColumnFormula (Calculated Column Formula)

a. *The standard makes no mention of an xml:space attribute.*

Excel uses this attribute to specify, using the W3C space preservation rules, how white space should be handled for the element's contents; its allowed values are defined by the XML 1.0 specification.

2.1.708 Part 4 Section 3.5.1.2, table (Table)

a. *The standard states that the values of the id attribute are defined by the XML Schema unsignedInt datatype.*

Excel restricts the value of this attribute to be at least 1 and at most 4294967294.

b. *The standard does not limit the length of the value of the name attribute.*

Excel restricts the value of this attribute to be at most 255 characters.

c. *The standard does not describe what happens if the name attribute value is the empty string or the name attribute is not present.*

Office, if this attribute is not specified or the value is an empty string, the value will be set to the value specified for the required displayName attribute.

d. *The standard does not specify a default value for the connectionId attribute.*

Excel uses a default value of 0 for this attribute.

e. *In the standard there are no limits on when the connectionId attribute can be present.*

In Office, this attribute must not be specified or the specified value must be 0 if tableType is not xml.

f. *In the standard no relationship between @totalsRowCount and @totalRowShown is specified.*

In Office, if @totalsRowCount equals 1, then totalsRowShown must be true.

g. *The standard does not limit the length of the value of the comment attribute.*

Excel restricts the value of this attribute to be at most 255 characters.

h. *The standard only limits the @ref to include the totals row.*

In Office, the count of rows for @ref shall be equal to or greater than the sum of rows specified by: @headerRowCount, @insertRow, and @totalsRowCount. Additionally, @ref must not overlap with another Table or auto-filter on the same worksheet.

i. *The standard does not limit the length of the value of the dataCellStyle attribute.*

Excel restricts the value of this attribute to be at least 1 and at most 255 characters.

j. *The standard does not limit the length of the value of the headerRowCellStyle attribute.*

Excel restricts the value of this attribute to be at least 1 and at most 255 characters.

k. *The standard does not limit the length of the value of the totalsRowCellStyle attribute.*

Excel restricts the value of this attribute to be at least 1 and at most 255 characters.

l. *The standard states that the values of the connectionId attribute are defined by the XML Schema unsignedInt datatype.*

Excel restricts the value of this attribute to be at most 2147483647.

2.1.709 Part 4 Section 3.5.1.3, tableColumn (Table Column)

a. *The standard says the maximum string length of the name attribute is unlimited.*

In Office, the name attribute string length must be less than or equal to 255 characters.

b. *The standard says the maximum string length of the uniqueName attribute is unlimited.*

In Excel, the string length of the uniqueName attribute must be less than or equal to 255.

c. *The standard specifies that the totalsRowLabel attribute shall be ignored unless totalRowFunction is none.*

In Office, the totalsRowLabel attribute shall be absent if totalsRowFunction has the value custom.

d. *The standard says the @headerRowCellStyle maximum string length is unlimited.*

In Office, the headerRowCellStyle length must be between 1 and 255 characters inclusive.

e. *The standard says the @totalsRowCellStyle maximum string length is unlimited.*

In Office the length of @totalsRowCellStyle shall be between 1 and 255 inclusive.

f. *The standard does not have requirements about the presence of the headerRowCellStyle attribute.*

In Office, headerRowCellStyle attribute shall be absent if the enclosing table element's headerRow attribute value is greater than or equal to 1.

g. *The standard specifies the queryTableFieldId attribute as an unsignedInt datatype.*

In Office, the queryTableFieldId attribute must be greater than zero.

h. *The standard says the @id value range is defined as unsigned integer.*

In Office the value of @id must be greater than zero.

i. *The standard does not specify any relationship between the value of the name attribute and cell contents.*

In Office, if the enclosing table element's headerRowCount attribute has a value greater than or equal to 1, then this attribute must have the same value as the cell it occupies.

j. *The standard says the maximum string length of the totalsRowLabel attribute is unlimited.*

In Office, the maximum string length of the totalsRowLabel attribute must be less than or equal to 32767.

k. *The standard does not specify when the headerRowDxfId attribute shall be absent.*

In Office, the headerRowDxfId attribute shall be absent if the enclosing table element's headerRow attribute value is greater than or equal to 1.

l. *The standard says the @dataCellStyle maximum string length is unlimited.*

In Office, the @dataCellStyle length must be between 1 and 255 characters inclusive.

m. *The standard does not specify a relationship between the queryTableFieldId attribute and @tableType.*

In Office, the queryTableFieldId attribute shall be absent when the enclosing table element's tableType attribute equals queryTable.

n. *The standard does not specify the totalsRowFunction attribute relationships.*

In Office, if the table element attribute totalsRowCount is not 0, the totalsRowFunction attribute shall match the formula of the occupied cell and be of the form SUBTOTAL(<function number>,<ref>), unless the value is none or custom. A value of none implies no formula.

2.1.710 Part 4 Section 3.5.1.5, tableStyleInfo (Table Style)

a. *The standard does not limit the length of the value of the name attribute.*

Excel restricts the value of this attribute to be at least 1 and at most 255 characters.

b. *The standard does not specify a default value for the showColumnStripes attribute.*

Excel uses a default value of false for this attribute.

c. *The standard does not specify a default value for the showFirstColumn attribute.*

Excel uses a default value of false for this attribute.

d. *The standard does not specify a default value for the showLastColumn attribute.*

Excel uses a default value of false for this attribute.

e. *The standard does not specify a default value for the showRowStripes attribute.*

Excel uses a default value of false for this attribute.

2.1.711 Part 4 Section 3.5.1.6, totalsRowFormula (Totals Row Formula)

For additional notes that apply to this portion of the standard, please see the notes for [calculatedColumnFormula, §3.5.1.1\(a\)](#).

2.1.712 Part 4 Section 3.5.1.7, xmlColumnPr (XML Column Properties)

a. *The standard does not specify a maximum length for @xpath.*

Office requires the decoded string length of @xpath to be less than 32000.

b. *The standard specifies that the mapId attribute has the value range of an xs:unsignedInt datatype.*

In Excel, the mapId attribute must be greater than 0 and less than 2147483647.

c. *The standard states that the denormalized attribute is true if it has been filled down (denormalized) and false otherwise.*

The denormalized attribute does not have any effect on the way Office behaves. Excel always denormalizes non-repeating nodes when mapped to a Table's column.

d. *The standard states that extLst is a child element of xmlColumnPr.*

Office will move an extLst element under xmlColumnPr into the parent element of xmlColumnPr (tableColumn). If an extlist child element is already present on tableColumn, the file will become invalid once saved.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.713 Part 4 Section 3.5.2.1, singleXmlCell (Table Properties)

a. *The standard specifies the value range for attribute id to be xsd:unsignedInt.*

In Office, id shall be between 1 and 4294967294 inclusive.

b. *The standard specifies the value range of attribute connectionId to be xsd:unsignedInt.*

In Office, attribute connectionId shall be less than or equal to 2147483647.

2.1.714 Part 4 Section 3.5.2.3, xmlCellPr (Cell Properties)

a. *The standard does not limit the length of the value of the uniqueName attribute.*

Excel restricts the value of this attribute to be at least 1 and at most 255 characters.

- b. *The standard states that the uniqueName attribute is optional.*

Excel requires this attribute.

2.1.715 Part 4 Section 3.5.2.4, xmlPr (Column XML Properties)

- a. *The standard specifies the value range for @xpath to be ST_Xstring.*

Office requires that the value of attribute xpath be greater than 0 and less than 32000 characters.

- b. *The standard specifies that attribute mapId has the value range of xs:unsignedInt.*

Office requires that the value of attribute mapId be greater than or equal to 1 and less than or equal to 2147483647.

2.1.716 Part 4 Section 3.6.1, c (Cell)

- a. *The standard refers to "c attribute" and "cell's" .*

Office interprets these to refer to "c element" and "cells".

- b. *The standard does not specify the context of cell for the i attribute.*

Office uses the previous cell in the calcChain collection.

- c. *The standard does not place restrictions between the use of the l attribute and the s attribute.*

Office requires that the l and s attributes be mutually exclusive.

- d. *The standard does not adequately describe dependency levels for the l attribute.*

A dependency level is the set of formulas that may depend on formulas on the preceding dependency levels. A parent formula, as defined by **s** attribute, shall not depend on other formulas on the same dependency level. A child formula, as defined by **s** attribute, shall only depend on other formulas on the same dependency level that precede it on the same child chain.

- e. *The standard does not adequately describe child chains for the s attribute.*

A child chain is a sequence of **c** elements and the corresponding formulas that have **s** attribute equal to true. A parent formula is a formula corresponding to the **c** element that has **s** attribute equal to false, and that immediately precedes the child chain. The child chain's formulas, within the same dependency level, depend only on the preceding child formulas and on the parent formula.

- f. *The standard states that when the s attribute is omitted its value is inherited from the previous c element.*

Office defaults to false when the s attribute is omitted, indicating that the formula is a parent formula.

- g. *The standard specifies @t starts a new thread.*

Office treats the attribute as deprecated and is ignored.

- h. *The standard states that the values of the i attribute are defined by the XML int datatype.*

Excel restricts the value of this attribute to be at least 1 and at most 65534.

- i. *The standard states that the default value of the i attribute is 0.*

Excel requires this attribute to be specified on the first cell in the calcChain collection; the default value on subsequent cells is taken from the previous record.

2.1.717 Part 4 Section 3.7.1, author (Author)

- a. *The standard does not limit the length of the value of the author element.*

Excel restricts the value of this element to be at most 65535 characters.

- b. *The standard makes no mention of an xml:space attribute.*

Excel uses this attribute to specify, using the W3C space preservation rules, how white space should be handled for the element's contents; its allowed values are defined by the XML 1.0 specification.

2.1.718 Part 4 Section 3.7.3, comment (Comment)

- a. *The standard specifies @guid is required and unique if the workbook is shared.*

Excel additionally specifies @guid is optional if the workbook is not shared.

2.1.719 Part 4 Section 3.7.6, text (Comment Text)

For additional notes that apply to this portion of the standard, please see the notes for [is, §3.3.1.50\(a, b\)](#); [t, §3.4.12\(b\)](#).

2.1.720 Part 4 Section 3.8.1, alignment (Alignment)

- a. *The standard does not contain a @mergeCell attribute on the alignment element.*

Excel allows @mergeCell to be written on the alignment element. @mergeCell is not used by Office and is not necessary for interoperability.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

- b. *The standard states that the values of the textRotation attribute are defined by the XML Schema unsignedInt.*

Excel restricts the value of this attribute to be in the range 0-180 or 254-255, inclusive.

- c. *The standard states that the values of the indent attribute are defined by the XML Schema unsignedInt datatype.*

Excel restricts the value of this attribute to be at most 255.

- d. *The standard states that the values of the readingOrder attribute are defined by the XML Schema unsignedInt datatype.*

Excel restricts the value of this attribute to be 0, 1, or 2.

- e. *The standard does not specify a default value for the horizontal attribute.*

Excel uses a default value of general for this attribute.

- f. *The standard does not specify a default value for the vertical attribute.*

Excel uses a default value of bottom for this attribute.

g. *The standard does not specify a default value for the textRotation attribute.*

Excel uses a default value of 0 for this attribute.

h. *The standard does not specify a default value for the wrapText attribute.*

Excel uses a default value of false for this attribute.

i. *The standard does not specify a default value for the indent attribute.*

Excel uses a default value of 0 for this attribute.

j. *The standard does not specify a default value for the relativeIndent attribute.*

Excel uses a default value of 0 for this attribute.

k. *The standard does not specify a default value for the justifyLastLine attribute.*

Excel uses a default value of false for this attribute.

l. *The standard does not specify a default value for the shrinkToFit attribute.*

Excel uses a default value of false for this attribute.

m. *The standard does not specify a default value for the readingOrder attribute.*

Excel uses a default value of 0 for this attribute.

2.1.721 Part 4 Section 3.8.3, bgColor (Background Color)

For additional notes that apply to this portion of the standard, please see the notes for [color](#), [§3.3.1.14\(b-d\)](#); [tabColor](#), [§3.3.1.90\(a-c\)](#).

a. *The standard does not specify the priorities of the various color types.*

Office prioritizes the attributes as auto < indexed < rgb < theme, and only roundtrips the type with the highest priority if two or more are specified.

2.1.722 Part 4 Section 3.8.4, border (Border)

a. *The standard does not specify a default value for the diagonalUp attribute.*

Excel uses a default value of false for this attribute.

b. *The standard does not specify a default value for the diagonalDown attribute.*

Excel uses a default value of false for this attribute.

2.1.723 Part 4 Section 3.8.5, borders (Borders)

a. *The standard states that the border child element has a minOccurs value of 0 and a maxOccurs value of unbounded.*

Excel limits the occurrences of this element to be at least 1 and at most 65430.

2.1.724 Part 4 Section 3.8.7, cellStyle (Cell Style)

a. *The standard does not limit the length of the value for the @name.*

Office limits the value of @name to 255 characters.

b. *The standard states that the builtinId attribute is any 32-bit unsigned integer.*

Office limits the values of the builtinId attribute to greater than or equal to zero and less than or equal to 53.

c. *The standard states that the iLevel attribute indicates that formatting is for an outline style, regardless of the value of the builtIn attribute.*

Office will ignore the iLevel attribute if the style is not either the RowLevel or ColLevel built-in styles (builtIn=1 or =2).

d. *The standard states that the values of the iLevel attribute are defined by the XML Schema unsigned int datatype.*

Office limits the iLevel attribute to the values 0 through 7.

e. *The standard does not define built-in styles 12, 13, and 14.*

Office defines built-in styles 12 = "Emphasis 1", 13 = "Emphasis 2", 14 = "Emphasis 3".

f. *The standard does not place uniqueness restrictions on the xfId attribute.*

Office requires that the xfId attribute must be unique with respect to the xfId values in all other cellStyle elements.

2.1.725 Part 4 Section 3.8.8, cellStyles (Cell Styles)

a. *The standard states that the maxOccurs value for the cellStyle child element is unbounded.*

Excel limits the occurrences of this element to 65430.

2.1.726 Part 4 Section 3.8.9, cellStyleXfs (Formatting Records)

a. *The standard states that the maxOccurs value for the xf child element is unbounded.*

Excel limits the occurrences of this element to 65430.

b. *The standard states that both the cell style xf records and cell xf records must be read to understand the full set of formatting applied to a cell.*

In Office, only the cell xf record defines the formatting applied to a cell.

c. *The standard does not limit the number of xf elements inside cellXfs and cellStyleXfs, or note any relationship between them.*

Office requires that the combined quantity of xf records inside cellXfs and non-built-in xf records inside CellStyleXfs must not exceed 65430 elements.

2.1.727 Part 4 Section 3.8.10, cellXfs (Cell Formats)

a. *The standard states that the maxOccurs value for the xf child element is unbounded.*

Excel limits the occurrences of this element to 65430.

b. *The standard states that both the cell style xf records and cell xf records must be read to understand the full set of formatting applied to a cell.*

In Office, only the cell xf record defines the formatting applied to a cell.

c. *The standard does not limit the number of xf elements inside cellXfs and cellStyleXfs, or note any relationship between them.*

Office requires that the combined quantity of xf records inside cellXfs and non-built-in xf records inside CellStyleXfs must not exceed 65430 elements.

2.1.728 Part 4 Section 3.8.15, dxfs (Formats)

a. *The standard states that the maxOccurs value for the dxf child element is unbounded.*

Excel limits the occurrences of this element to 2147483647.

2.1.729 Part 4 Section 3.8.17, family (Font Family)

a. *The standard states that the values of the val attribute are defined by the XML Schema int datatype.*

Excel restricts the value of this attribute to be at least 0 and at most 5.

b. *The standard implies that the val attribute refers to character set.*

In Office, the val attribute is interpreted as referring to the font family.

2.1.730 Part 4 Section 3.8.18, fgColor (Foreground Color)

For additional notes that apply to this portion of the standard, please see the notes for [color](#), [§3.3.1.14\(b-d\)](#); [tabColor](#), [§3.3.1.90\(a-c\)](#); [bgColor](#), [§3.8.3\(a\)](#).

a. *The standard does not specify the priorities of the various color types.*

Office prioritizes the attributes as auto < indexed < rgb < theme, and only roundtrips the type with the highest priority if two or more are specified.

2.1.731 Part 4 Section 3.8.20, fills (Fills)

a. *The standard states that the fill child element has a minOccurs value of 0 and a maxOccurs value of unbounded.*

Excel limits the occurrences of this element to be at least 1 and at most 65430.

2.1.732 Part 4 Section 3.8.21, font (Font)

a. *The standard defines the child elements using a choice.*

Excel requires the child elements to be in the following sequence: i, strike, condense, extend, outline, shadow, u, vertAlign, sz, color, name, family, charset, scheme.

2.1.733 Part 4 Section 3.8.22, fonts (Fonts)

a. *The standard states that the font child element has a minOccurs value of 0 and a maxOccurs value of unbounded.*

Excel limits the occurrences of this element to be at least 1 and at most 65491.

2.1.734 Part 4 Section 3.8.23, gradientFill (Gradient)

a. *The standard states that the values for the top attribute are defined by the XML Schema double datatype.*

Office requires the top attribute to be a double between 0 and 1 inclusive.

b. *The standard specifies @bottom as defined by the XML Schema double datatype.*

Office requires @bottom to be a double between 0 and 1 inclusive.

c. *The standard specifies @left as defined by the XML Schema double datatype.*

Office requires @left to be a double between 0 and 1 inclusive.

d. *The standard specifies @right as defined by the XML Schema double datatype.*

Office requires @right to be a double between 0 and 1 inclusive.

e. *The standard specifies @degree as defined by the XML Schema double datatype.*

Office requires @degree to be a double between -1.7E308 and 1.7E308 inclusive.

2.1.735 Part 4 Section 3.8.26, indexedColors (Color Indexes)

a. *The standard states that the maxOccurs value for the rgbColor child element is unbounded.*

Excel limits the occurrences of this element to 64.

2.1.736 Part 4 Section 3.8.28, mruColors (MRU Colors)

a. *The standard states that the maxOccurs value for the color child element is unbounded.*

Excel limits the occurrences of this element to 10.

2.1.737 Part 4 Section 3.8.29, name (Font Name)

a. *The standard states that string length for the val attribute can be 0 to 31 characters.*

Excel restricts the value of this attribute to be at least 1 and at most 31 characters before escaping.

2.1.738 Part 4 Section 3.8.30, numFmt (Number Format)

a. *The standard defines built-in format ID 14: "mm-dd-yy"; 22: "m/d/yy h:mm"; 37: "#,##0 ;(#,##0)"; 38: "#,##0 ;[Red](#,##0)"; 39: "#,##0.00;(#,##0.00)"; 40: "#,##0.00;[Red](#,##0.00)"; 47: "mmss.0"; KOR fmt 55: "yyyy-mm-dd".*

Excel defines built-in format ID 14: "m/d/yyyy"; 22: "m/d/yyyy h:mm"; 37: "#,##0_);(#,##0)"; 38: "#,##0_);[Red](#,##0)"; 39: "#,##0.00_);(#,##0.00)"; 40: "#,##0.00_);[Red](#,##0.00)"; 47: "mm:ss.0"; KOR fmt 55: "yyyy/mm/dd".

b. *The standard does not define a restriction on the size or content of the formatCode attribute.*

In Office, the formatCode attribute is a string specifying how to format and render the numeric value of a cell. It must be less than 255 characters in length. For a string to be considered a valid format code, it should be well-formed according to the following ABNF specification.

These definitions are for en-US locale. International consideration as specified in numFmts (“[ECMA-376](#) Part 4 §3.8.31; numFmts (Number Formats)”) must be accounted for and the ABNF must be modified accordingly for specific international number formats.

In the following ABNF specification, the following set of tokens can occur 0 to unbounded times:

LITERAL-STRING

LITERAL-CHAR-REPEAT

LITERAL-CHAR-SPACE

as long as they don't break apart the following elements:

INTL*

LITERAL*

NFDateTimeToken

NFPartExponential

NFPartCond

NFPartLocaleID

NFPartColor

NFPartIntNum

NFPartStrColor

The following set of tokens must occur 0 or 1 times in each section as defined in numFmts (“[ECMA-376](#) Part 4 §3.8.31; numFmts (Number Formats)”).

NFPartLocaleID

NFAbsTimeToken must occur 0 or 1 times in NFDateTime.

Also, an absolute time token must not coexist with a non-absolute equivalent token in NFDateTime.

All =

([NFPartColor] NFPartCond NFGeneral) /

NFAnyNoCond /

(NFAnyNoText ASCII-SEMICOLON NFAny) /

(NFAnyNoText ASCII-SEMICOLON NFAnyNoText ASCII-SEMICOLON NFAnyNoCond) /

(NFAnyNoText ASCII-SEMICOLON NFAnyNoText ASCII-SEMICOLON

NFAnyNoTextNoCond ASCII-SEMICOLON [NFText / NFGeneral])

NFAny =

[NFPartColor]

(

```

([NFPartCond] NFNumber) /
NFText /
([NFPartCond] NFFraction) /
([NFPartCond] [NFDateTime] [NFGeneral] [NFDateTime])
)
NFAnyNoText =
[NFPartColor] [NFPartCond]
(
NFNumber /
NFFraction /
([NFDateTime] [NFGeneral] [NFDateTime])
)
NFAnyNoCond =
[NFPartColor]
(
NFNumber /
NFText /
NFFraction /
([NFDateTime] [NFGeneral] [NFDateTime])
)
NFAnyNoTextNoCond =
[NFPartColor]
(
NFNumber /
NFFraction /
([NFDateTime] [NFGeneral] [NFDateTime])
)
NFGeneral = INTL-NUMFMT-GENERAL
NFNumber = NFPartNum [NFPartExponential NFPartNum] *INTL-CHAR-NUMGRP-SEP *INTL-AMPM
NFDateTimeToken = NFPartYear / NFPartMonth / NFPartDay /

```

NFPartHour / NFPartMinute / NFPartSecond / NFAbsTimeToken
 NFAbsTimeToken = NFPartAbsHour / NFPartAbsSecond / NFPartAbsMinute
 NFDateTime =
 INTL-AMPM (1(NFDateTimeToken) *(NFDateTimeToken / NFPartSubSecond /
 INTL-CHAR-DATE-SEP / INTL-CHAR-TIME-SEP / INTL-AMPM))
 NFText =
 (1*ASCII-COMMERCIAL-AT *(ASCII-COMMERCIAL-AT / INTL-AMPM)) /
 *(ASCII-COMMERCIAL-AT / INTL-AMPM) 1*ASCII-COMMERCIAL-AT)
 NFFraction = NFPartFraction ASCII-SOLIDUS NFPartFraction [NFPartNum] *INTL-AMPM
 ; Definitions for partial rules used by the preceding rules.
 NFPartNum =
 (1*NFPartNumToken2 *(NFPartNumToken2 / ASCII-PERCENT-SIGN)) /
 *(NFPartNumToken2 / ASCII-PERCENT-SIGN) 1*NFPartNumToken2)
 NFPartExponential = ASCII-CAPITAL-LETTER-E NFPartSign
 NFPartYear = 2(ASCII-SMALL-LETTER-Y) / 4(ASCII-SMALL-LETTER-Y)
 NFPartMonth = 1*5(ASCII-SMALL-LETTER-M)
 NFPartDay = 1*4(ASCII-SMALL-LETTER-D)
 NFPartHour = 1*2(ASCII-SMALL-LETTER-H)
 NFPartAbsHour =
 ASCII-LEFT-SQUARE-BRACKET 1*ASCII-SMALL-LETTER-H ASCII-RIGHT-SQUARE-BRACKET
 NFPartMinute = 1*2(ASCII-SMALL-LETTER-M)
 NFPartAbsMinute =
 ASCII-LEFT-SQUARE-BRACKET 1*ASCII-SMALL-LETTER-M ASCII-RIGHT-SQUARE-BRACKET
 NFPartSecond =
 1*2(ASCII-SMALL-LETTER-S)
 NFPartAbsSecond =
 ASCII-LEFT-SQUARE-BRACKET 1*ASCII-SMALL-LETTER-S ASCII-RIGHT-SQUARE-BRACKET
 NFPartSubSecond = INTL-CHAR-DECIMAL-SEP 1*3ASCII-DIGIT-ZERO
 NFPartCond =
 ASCII-LEFT-SQUARE-BRACKET NFPartCompOper NFPartCondNum

ASCII-RIGHT-SQUARE-BRACKET
 NFPartCompOper =
 (ASCII-LESS-THAN-SIGN [ASCII-EQUALS-SIGN / ASCII-GREATER-THAN-SIGN]) /
 ASCII-EQUALS-SIGN /
 (ASCII-GREATER-THAN-SIGN [ASCII-EQUALS-SIGN])
 NFPartLocaleID =
 ASCII-LEFT-SQUARE-BRACKET ASCII-DOLLAR-SIGN 1*UTF16-ANY [ASCII-HYPHEN-MINUS
 3*8ASCII-DIGIT-HEXADECIMAL] ASCII-RIGHT-SQUARE-BRACKET
 NFPartCondNum =
 [ASCII-HYPHEN-MINUS] NFPartIntNum [INTL-CHAR-DECIMAL-SEP NFPartIntNum]
 [NFPartExponential NFPartIntNum]
 NFPartSign = ASCII-PLUS-SIGN / ASCII-HYPHEN-MINUS
 NFPartColor =
 ASCII-LEFT-SQUARE-BRACKET
 INTL-COLOR / (NFPartStrColor NFPart1To56)
 ASCII-RIGHT-SQUARE-BRACKET
 NFPart1To56 =
 NFPartNumber1To9 /
 NFPartNumber1To4 ASCII-DIGIT /
 ASCII-DIGIT-FIVE (ASCII-DIGIT-ZERO / NFPartNumber1To6)
 NFPartIntNum = 1*ASCII-DIGIT
 NFPartNumToken1 = ASCII-NUMBER-SIGN / ASCII-QUESTION-MARK /
 ASCII-DIGIT-ZERO
 NFPartNumToken2 = NFPartNumToken1 / INTL-CHAR-DECIMAL-SEP / INTL-CHAR-NUMGRP-SEP
 NFPartFraction =
 (1*NFPartIntNum *(NFPartIntNum / ASCII-PERCENT-SIGN)) /
 *(NFPartIntNum / ASCII-PERCENT-SIGN) 1*NFPartIntNum /
 (1*NFPartNumToken1 *(NFPartNumToken1 / ASCII-PERCENT-SIGN)) /
 *(NFPartNumToken1 / ASCII-PERCENT-SIGN) 1*NFPartNumToken1
 NFPartNumber1To4 =

ASCII-DIGIT-ONE /
 ASCII-DIGIT-TWO /
 ASCII-DIGIT-THREE /
 ASCII-DIGIT-FOUR
 NFPartNumber1To6 =
 NFPartNumber1To4 /
 ASCII-DIGIT-FIVE /
 ASCII-DIGIT-SIX
 NFPartNumber1To9 =
 NFPartNumber1To6 /
 ASCII-DIGIT-SEVEN /
 ASCII-DIGIT-EIGHT /
 ASCII-DIGIT-NINE
 NFPartStrColor =
 ASCII-CAPITAL-LETTER-C ASCII-SMALL-LETTER-O ASCII-SMALL-LETTER-L
 ASCII-SMALL-LETTER-O ASCII-SMALL-LETTER-R
 LITERAL-CHAR = ASCII-REVERSE-SOLIDUS UTF16-ANY
 LITERAL-CHAR-REPEAT = ASCII-ASTERISK UTF16-ANY
 LITERAL-STRING =
 (ASCII-QUOTATION-MARK 1*UTF16-ANY-WITHOUT-QUOTE ASCII-QUOTATION-MARK) /
 1*LITERAL-CHAR
 UTF16-ANY-WITHOUT-QUOTE = %x0000-0021 / %x0023-FFFF
 LITERAL-CHAR-SPACE = ASCII-LOW-LINE UTF16-ANY
 ; INTL* Rules must be validated to suit the
 ; Locale and/or the UI language as appropriate
 ;
 =====
 =====
 INTL-CHAR-DECIMAL-SEP = ASCII-FULL-STOP
 INTL-CHAR-NUMGRP-SEP = ASCII-COMMA
 INTL-CHAR-DATE-SEP = ASCII-SOLIDUS

INTL-CHAR-TIME-SEP = ASCII-COLON

INTL-COLOR =

(ASCII-CAPITAL-LETTER-B ASCII-SMALL-LETTER-L ASCII-SMALL-LETTER-A
ASCII-SMALL-LETTER-C ASCII-SMALL-LETTER-K) / ; Black

(ASCII-CAPITAL-LETTER-B ASCII-SMALL-LETTER-L ASCII-SMALL-LETTER-U
ASCII-SMALL-LETTER-E) / ; Blue

(ASCII-CAPITAL-LETTER-C ASCII-SMALL-LETTER-Y ASCII-SMALL-LETTER-A
ASCII-SMALL-LETTER-N) / ;Cyan

(ASCII-CAPITAL-LETTER-G ASCII-SMALL-LETTER-R ASCII-SMALL-LETTER-E
ASCII-SMALL-LETTER-E ASCII-SMALL-LETTER-N) / ; Green

(ASCII-CAPITAL-LETTER-M ASCII-SMALL-LETTER-A ASCII-SMALL-LETTER-G
ASCII-SMALL-LETTER-E ASCII-SMALL-LETTER-N

ASCII-SMALL-LETTER-T ASCII-SMALL-LETTER-A) / ; Magenta

(ASCII-CAPITAL-LETTER-R ASCII-SMALL-LETTER-E
ASCII-SMALL-LETTER-D) / ; Red

(ASCII-CAPITAL-LETTER-W ASCII-SMALL-LETTER-H ASCII-SMALL-LETTER-I
ASCII-SMALL-LETTER-T ASCII-SMALL-LETTER-E) / ; White

(ASCII-CAPITAL-LETTER-Y ASCII-SMALL-LETTER-E ASCII-SMALL-LETTER-L
ASCII-SMALL-LETTER-L ASCII-SMALL-LETTER-O

ASCII-SMALL-LETTER-W) ; Yellow

INTL-NUMFMT-GENERAL =

ASCII-CAPITAL-LETTER-G ASCII-SMALL-LETTER-E ASCII-SMALL-LETTER-N

ASCII-SMALL-LETTER-E ASCII-SMALL-LETTER-R ASCII-SMALL-LETTER-A

ASCII-SMALL-LETTER-L

INTL-AMPM =

(ASCII-CAPITAL-LETTER-A ASCII-CAPITAL-LETTER-M ASCII-SOLIDUS

ASCII-CAPITAL-LETTER-P ASCII-CAPITAL-LETTER-M) /

"A/P"

UTF16-ANY = %x0000-FFFF

;
=====

; Derived from Unicode names of ASCII characters (%x20-7F)

;
=====

- ASCII-SPACE = %x20
- ASCII-EXCLAMATION-MARK = %x21
- ASCII-QUOTATION-MARK = %x22
- ASCII-NUMBER-SIGN = %x23
- ASCII-DOLLAR-SIGN = %x24
- ASCII-PERCENT-SIGN = %x25
- ASCII-AMPERSAND = %x26
- ASCII-APOSTROPHE = %x27
- ASCII-LEFT-PARENTHESIS = %x28
- ASCII-RIGHT-PARENTHESIS = %x29
- ASCII-ASTERISK = %x2A
- ASCII-PLUS-SIGN = %x2B
- ASCII-COMMA = %x2C
- ASCII-HYPHEN-MINUS = %x2D
- ASCII-FULL-STOP = %x2E
- ASCII-SOLIDUS = %x2F
- ASCII-DIGIT-ZERO = %x30
- ASCII-DIGIT-ONE = %x31
- ASCII-DIGIT-TWO = %x32
- ASCII-DIGIT-THREE = %x33
- ASCII-DIGIT-FOUR = %x34
- ASCII-DIGIT-FIVE = %x35
- ASCII-DIGIT-SIX = %x36
- ASCII-DIGIT-SEVEN = %x37
- ASCII-DIGIT-EIGHT = %x38

ASCII-DIGIT-NINE = %x39
ASCII-COLON = %x3A
ASCII-SEMICOLON = %x3B
ASCII-LESS-THAN-SIGN = %x3C
ASCII-EQUALS-SIGN = %x3D
ASCII-GREATER-THAN-SIGN = %x3E
ASCII-QUESTION-MARK = %x3F
ASCII-COMMERCIAL-AT = %x40
ASCII-CAPITAL-LETTER-A = %x41
ASCII-CAPITAL-LETTER-B = %x42
ASCII-CAPITAL-LETTER-C = %x43
ASCII-CAPITAL-LETTER-D = %x44
ASCII-CAPITAL-LETTER-E = %x45
ASCII-CAPITAL-LETTER-F = %x46
ASCII-CAPITAL-LETTER-G = %x47
ASCII-CAPITAL-LETTER-H = %x48
ASCII-CAPITAL-LETTER-I = %x49
ASCII-CAPITAL-LETTER-J = %x4A
ASCII-CAPITAL-LETTER-K = %x4B
ASCII-CAPITAL-LETTER-L = %x4C
ASCII-CAPITAL-LETTER-M = %x4D
ASCII-CAPITAL-LETTER-N = %x4E
ASCII-CAPITAL-LETTER-O = %x4F
ASCII-CAPITAL-LETTER-P = %x50
ASCII-CAPITAL-LETTER-Q = %x51
ASCII-CAPITAL-LETTER-R = %x52
ASCII-CAPITAL-LETTER-S = %x53
ASCII-CAPITAL-LETTER-T = %x54
ASCII-CAPITAL-LETTER-U = %x55
ASCII-CAPITAL-LETTER-V = %x56

ASCII-CAPITAL-LETTER-W = %x57
ASCII-CAPITAL-LETTER-X = %x58
ASCII-CAPITAL-LETTER-Y = %x59
ASCII-CAPITAL-LETTER-Z = %x5A
ASCII-LEFT-SQUARE-BRACKET = %x5B
ASCII-REVERSE-SOLIDUS = %x5C
ASCII-RIGHT-SQUARE-BRACKET = %x5D
ASCII-CIRCUMFLEX-ACCENT = %x5E
ASCII-LOW-LINE = %x5F
ASCII-GRAVE-ACCENT = %x60
ASCII-SMALL-LETTER-A = %x61
ASCII-SMALL-LETTER-B = %x62
ASCII-SMALL-LETTER-C = %x63
ASCII-SMALL-LETTER-D = %x64
ASCII-SMALL-LETTER-E = %x65
ASCII-SMALL-LETTER-F = %x66
ASCII-SMALL-LETTER-G = %x67
ASCII-SMALL-LETTER-H = %x68
ASCII-SMALL-LETTER-I = %x69
ASCII-SMALL-LETTER-J = %x6A
ASCII-SMALL-LETTER-K = %x6B
ASCII-SMALL-LETTER-L = %x6C
ASCII-SMALL-LETTER-M = %x6D
ASCII-SMALL-LETTER-N = %x6E
ASCII-SMALL-LETTER-O = %x6F
ASCII-SMALL-LETTER-P = %x70
ASCII-SMALL-LETTER-Q = %x71
ASCII-SMALL-LETTER-R = %x72
ASCII-SMALL-LETTER-S = %x73
ASCII-SMALL-LETTER-T = %x74

ASCII-SMALL-LETTER-U = %x75
ASCII-SMALL-LETTER-V = %x76
ASCII-SMALL-LETTER-W = %x77
ASCII-SMALL-LETTER-X = %x78
ASCII-SMALL-LETTER-Y = %x79
ASCII-SMALL-LETTER-Z = %x7A
ASCII-LEFT-CURLY-BRACKET = %x7B
ASCII-VERTICAL-LINE = %x7C
ASCII-RIGHT-CURLY-BRACKET = %x7D
ASCII-TILDE = %x7E
ASCII-DELETE = %x7F
ASCII-CRLF = %x0d.0a
ASCII-DIGIT =
ASCII-DIGIT-ZERO /
ASCII-DIGIT-ONE /
ASCII-DIGIT-TWO /
ASCII-DIGIT-THREE /
ASCII-DIGIT-FOUR /
ASCII-DIGIT-FIVE /
ASCII-DIGIT-SIX /
ASCII-DIGIT-SEVEN /
ASCII-DIGIT-EIGHT /
ASCII-DIGIT-NINE
ASCII-DIGIT-HEXADECIMAL =
ASCII-DIGIT /
ASCII-SMALL-LETTER-A /
ASCII-SMALL-LETTER-B /
ASCII-SMALL-LETTER-C /
ASCII-SMALL-LETTER-D /
ASCII-SMALL-LETTER-E /

ASCII-SMALL-LETTER-F /
ASCII-CAPITAL-LETTER-A /
ASCII-CAPITAL-LETTER-B /
ASCII-CAPITAL-LETTER-C /
ASCII-CAPITAL-LETTER-D /
ASCII-CAPITAL-LETTER-E /
ASCII-CAPITAL-LETTER-F

;
=====

c. *The standard does not restrict the parent of numFmt, such that the numFmtId attribute specifies the Id used by the master style records (xf's) to reference this number format.*

In Office, the numFmtId attribute specifies the Id used by the master style records (xf's) to reference this number format only if the parent element is present within numFmts element. Its value is ignored otherwise.

2.1.739 Part 4 Section 3.8.31, numFmts (Number Formats)

a. *The standard does not describe how to interpret a number format with only three sections.*

If only three sections are specified, the first is used for positive numbers, second for negative numbers and the third is used for zero values in Office.

b. *The standard states that the & (ampersand) text operator is used to join, or concatenate, two values.*

Excel displays '&' if '&' is present in the format.

c. *The standard states that if the cell contains a number between 0 and 1, the application shall multiply the number by 100 and add the percentage symbol in the cell (for Percentage formatting).*

Office applies percentage formatting to any numeric cell value.

d. *The standard does not include an entry for '/' in the table of format characters.*

In Excel, the fraction format character ('/') displays the number in the format of a fraction. It is interpreted as the fraction format character only when preceded and followed by a number symbol (0, #, and ?).

e. *The standard lists e+ and e- along with E+ and E- as the format characters for specifying use of scientific notation.*

In Office, only E+ and E- are the format characters for specifying use of scientific notation.

f. *The standard states that date format codes e and ee become yy in all locales other than JPN/CHT.*

In Office, date format codes e and ee become yyyy in all locales other than JPN/CHT.

- g. *The standard does not limit the number of custom number formats defined in numFmts.*

Office limits the number of custom number formats to 206 and also persists files that contain more than 206 custom formats (which it cannot load).

2.1.740 Part 4 Section 3.8.33, protection (Protection Properties)

- a. *The standard does not specify a default value for the locked attribute.*

Excel uses a default value of true for this attribute.

- b. *The standard does not specify a default value for the hidden attribute.*

Excel uses a default value of false for this attribute.

2.1.741 Part 4 Section 3.8.38, stop (Gradient Stop)

- a. *The standard specifies @position as defined by the XML Schema double datatype.*

Office requires @position to be a double between 0 and 1 inclusive.

2.1.742 Part 4 Section 3.8.39, styleSheet (Style Sheet)

- a. *The standard states that the child elements styleSheet have a minOccurs equal to zero.*

In Office, styleSheet child elements specify formatting information for the cells in an Excel document. All child elements that are referenced in the Excel document must be present or the document will be considered non-conformant.

2.1.743 Part 4 Section 3.8.40, tableStyle (Table Style)

- a. *The standard incorrectly states that built-in table styles are written in tableStyle elements.*

In Office, only user-defined table styles are written to the tableStyle elements.

- b. *The standard does not limit the length of the value of the name attribute.*

Excel restricts the value of this attribute to be at least 1 and at most 255 characters.

- c. *The standard states that the maxOccurs value for the tableStyleElement child element is unbounded.*

Excel limits the occurrences of this element to 28.

2.1.744 Part 4 Section 3.8.41, tableStyleElement (Table Style)

- a. *The standard specifies that the values of the size attribute are defined by the XML Schema unsignedInt datatype.*

Office requires the size attribute to be an unsignedInt between 1 to 9 inclusive.

2.1.745 Part 4 Section 3.8.42, tableStyles (Table Styles)

- a. *The standard specifies @defaultTableStyle as xsd:string.*

Office requires @defaultChanged to be an xsd:string whose length is between 1 and 255 inclusive.

b. *The standard specifies @defaultPivotStyle as xsd:string.*

Office requires @defaultPivotStyle to be an xsd:string whose length is between 1 and 255 inclusive.

2.1.746 Part 4 Section 3.8.45, xf (Format)

a. *The standard does not define different behaviors for @applyAlignment depending on whether the xf is in the CellXfs element or the CellStyleXfs element.*

For the **cellStyleXfs** element, this boolean value indicates whether the alignment formatting specified for this **xf** is applied. The default value for **applyAlignment** in **cellStyleXfs** is true.

For the **cellXfs** element, this boolean value indicates whether the alignment formatting in the **xf** is overwritten by changes to the **cellStyleXfs** referenced by **xfId**. If **applyAlignment** is false and the alignment formatting in the **cellStyleXfs** changes, the new alignment formatting is set in the **xf** as well. If **applyAlignment** is true, then the **xf** will retain its existing alignment formatting. If the alignment formatting in the **cellXf** is different than the alignment formatting in the parent **cellStyleXf**, **applyAlignment** shall be true. The default value for **applyAlignment** in **cellXfs** element is false.

b. *The standard does not define different behaviors for @applyBorder depending on whether the xf is in the CellXfs element or the CellStyleXfs element.*

For the **cellStyleXfs** element, this boolean value indicates whether the border formatting specified for this **xf** is applied. The default value for **applyBorder** in **cellStyleXfs** is true.

For the **cellXfs** element, this boolean value indicates whether the border formatting in the **xf** is overwritten by changes to the **cellStyleXfs** referenced by **xfId**. If **applyBorder** is false and the border formatting in the **cellStyleXfs** changes, the new border formatting is set in the **xf** as well. If **applyBorder** is true, then the **xf** will retain its existing border formatting. If the border formatting in the **cellXf** is different than the border formatting in the parent **cellStyleXf**, **applyBorder** shall be true. The default value for **applyBorder** in **cellXfs** element is false.

c. *The standard does not define different behaviors for @applyFill depending on whether the xf is in the CellXfs element or the CellStyleXfs element.*

For the **cellStyleXfs** element, this boolean value indicates whether the fill formatting specified for this **xf** is applied. The default value for **applyFill** in **cellStyleXfs** is true.

For the **cellXfs** element, this boolean value indicates whether the fill formatting in the **xf** is overwritten by changes to the **cellStyleXfs** referenced by **xfId**. If **applyFill** is false and the fill formatting in the **cellStyleXfs** changes, the new fill formatting is set in the **xf** as well. If **applyFill** is true, then the **xf** will retain its existing fill formatting. If the fill formatting in the **cellXf** is different than the fill formatting in the parent **cellStyleXf**, **applyFill** shall be true. The default value for **applyFill** in **cellXfs** element is false.

d. *The standard does not define different behaviors for @applyFont depending on whether the xf is in the CellXfs element or the CellStyleXfs element.*

For the **cellStyleXfs** element, this boolean value indicates whether the font formatting specified for this **xf** is applied. The default value for **applyFont** in **cellStyleXfs** is true.

For the **cellXfs** element, this boolean value indicates whether the font formatting in the **xf** is overwritten by changes to the **cellStyleXfs** referenced by **xfId**. If **applyFont** is false and the font formatting in the **cellStyleXfs** changes, the new font formatting is set in the **xf** as well. If **applyFont** is true, then the **xf** will retain its existing font formatting. If the font formatting in the

cellXf is different than the font formatting in the parent **cellStyleXf**, **applyFont** shall be true. The default value for **applyFont** in cellXfs element is false.

e. *The standard does not define different behavior for @applyNumberFormat depending on whether the xf is in the CellXfs element or the CellStyleXfs element.*

For the **cellStyleXfs** element, this boolean value indicates whether the number formatting specified for this **xf** is applied. The default value for **applyNumberFormat** in **cellStyleXfs** is true.

For the **cellXfs** element, this boolean value indicates whether the number formatting in the xf is overwritten by changes to the **cellStyleXfs** referenced by **xfId**. If **applyNumberFormat** is false and the number formatting in the **cellStyleXfs** changes, the new number formatting is set in the **xf** as well. If **applyNumberFormat** is true, then the **xf** will retain its existing number formatting. If the number formatting in the **cellXf** is different than the number formatting in the parent **cellStyleXf**, **applyNumberFormat** shall be true. The default value for **applyNumberFormat** in cellXfs element is false.

f. *The standard does not define different behaviors for @applyProtection depending on whether the xf is in the CellXfs element or the CellStyleXfs element.*

For the **cellStyleXfs** element, this boolean value indicates whether the protection formatting specified for this **xf** is applied. The default value for **applyProtection** in **cellStyleXfs** is true.

For the **cellXfs** element, this boolean value indicates whether the protection formatting in the xf is overwritten by changes to the **cellStyleXfs** referenced by **xfId**. If **applyProtection** is false and the protection formatting in the **cellStyleXfs** changes, the new protection formatting is set in the **xf** as well. If **applyProtection** is true, then the **xf** will retain its existing protection formatting. If the protection formatting in the **cellXf** is different than the protection formatting in the parent **cellStyleXf**, **applyProtection** shall be true. The default value for **applyProtection** in cellXfs element is false.

2.1.747 Part 4 Section 3.9.1, bk (Metadata Block)

a. *The standard does not place any restrictions on the ordering of rc child elements.*

Office requires that rc elements must be stored in the strictly increasing order of their metadata record type indexes.

2.1.748 Part 4 Section 3.9.3, cellMetadata (Cell Metadata)

For additional notes that apply to this portion of the standard, please see the notes for [valueMetadata, §3.9.17\(a\)](#).

a. *The standard states that the values of the count attribute are defined by the XML Schema `unsignedInt` datatype.*

Office requires that the count attribute has a maximum value of 2147483647.

2.1.749 Part 4 Section 3.9.4, futureMetadata (Future Metadata)

a. *The standard specifies that the values of the count attribute are defined by the XML Schema `unsignedInt` datatype.*

Office requires that @count has a maximum value of 2147483647.

b. *The standard states that the name attribute is the metadata type name.*

Office requires this name must be equal to the name attribute of one of the metadataType records in the metadataTypes collection. This name must be unique among all futureMetadata records and must not equal XLMDX.

c. *The standard states that the possible values for the name attribute are defined by ST_Xstring simple type.*

Office requires that the name attribute be non-empty and less than or equal to 65535 characters.

2.1.750 Part 4 Section 3.9.5, k (KPI MDX Metadata)

a. *The standard does not specify the base of @n and @np.*

Office treats @n and @np as zero-based indexes into the metadataStrings collection.

b. *The standard states that the values of the n attribute are defined by the XML Schema unsignedInt datatype.*

Office requires that the n attribute has a maximum value of 2147483647.

c. *The standard states that the values of the np attribute are defined by the XML Schema unsignedInt datatype.*

Office requires that the np attribute has a maximum value of 2147483647.

2.1.751 Part 4 Section 3.9.6, mdx (MDX Metadata Record)

a. *The standard states that the values of the n attribute are defined by the XML Schema unsignedInt datatype.*

Office requires that the n attribute has a maximum value of 2147483647.

2.1.752 Part 4 Section 3.9.7, mdxMetadata (MDX Metadata Information)

a. *The standard states that the values of the count attribute are defined by the XML Schema unsignedInt datatype.*

Office requires that @count has a maximum value of 2147483647.

2.1.753 Part 4 Section 3.9.9, metadataStrings (Metadata String Store)

a. *The standard specifies that the values of the count attribute are defined by the XML Schema unsignedInt datatype.*

Office requires that @count has a maximum value of 2147483647.

2.1.754 Part 4 Section 3.9.10, metadataType (Metadata Type Information)

a. *The standard specifies that the adjust attribute is true if metadata corresponding to a particular cell needs to be notified when that cell's location is changed, false otherwise.*

Office does not respect the value of the adjust attribute.

b. *The standard specifies that the assign attribute is true when metadata should be propagated by assignment, false otherwise.*

Office does not respect the value of the assign attribute.

c. *The standard specifies that the clearAll attribute is true if the metadata persists after a clear all, false otherwise.*

Office does not respect the value of the clearAll attribute.

d. *The standard specifies that the coerce attribute is true if the value metadata is removed upon coercion, false otherwise.*

Office does not respect the value of the coerce attribute.

e. *The standard specifies that the ghostCol attribute is true when the metadata is copied to or from a ghost column, false otherwise.*

Office does not respect the value of the ghostCol attribute.

f. *The standard specifies that the ghostRow attribute is true when the metadata is copied to or from a ghost row, false otherwise.*

Office does not respect the value of the ghostRow attribute.

g. *The standard specifies that merge is true if the metadata persists after a cell merge, false otherwise.*

Office does not respect the value of the merge attribute.

h. *The standard specifies that pasteAll is true when the metadata is populated on a Paste:All, false otherwise.*

Office does not respect the value of the pasteAll attribute.

i. *The standard specifies that pasteBorders is true when the metadata is populated when only borders are pasted, false otherwise.*

Office does not respect the value of the pasteBorders attribute.

j. *The standard specifies that pasteColWidths is true if the metadata is populated when only column widths are pasted, false otherwise.*

Office does not respect the value of the pasteColWidths attribute.

k. *The standard specifies that the pasteComments attribute is true when metadata is populated when only comments are pasted, false otherwise.*

Office does not respect the value of the pasteComments attribute.

l. *The standard specifies that the pasteDataValidation attribute is true when metadata is populated when only data validation is pasted, false otherwise.*

Office does not respect the value of the pasteDataValidation attribute.

m. *The standard specifies that the pasteFormats attribute is true when metadata is populated when only formatting is pasted, false otherwise.*

Office does not respect the value of the pasteFormats attribute.

n. *The standard specifies that the pasteFormulas attribute is true when the metadata is populated when only formulas are pasted, false otherwise.*

Office does not respect the value of the pasteFormulas attribute.

o. *The standard specifies that the pasteNumberFormats attribute is true when metadata is populated when only number formatting is pasted, false otherwise.*

Office does not respect the value of the pasteNumberFormats attribute.

p. *The standard specifies that the rowColShift attribute is true if the metadata persists after the cell has been shifted, false otherwise.*

Office does not respect the value of the rowColShift attribute.

q. *The standard specifies that the splitAll attribute is true if the metadata is copied to all new cells resulting from a split and false otherwise.*

Office does not respect the value of the splitAll attribute.

r. *The standard specifies that the splitFirst attribute is true when the metadata from a split cell is only copied to the first resulting cell, false otherwise.*

Office does not respect the value of the splitFirst attribute.

s. *The standard specifies that the clearComments attribute is true if the metadata persists after Clear:Comments, false otherwise.*

Office does not respect the value of the clearComments attribute.

t. *The standard specifies that the clearContents attribute is true if metadata persists after a "Clear:Contents" action, false otherwise.*

Office does not respect the value of the clearContents attribute.

u. *The standard does not restrict the value of the minSupportedVersion attribute when the name attribute equals XLMDX.*

Office requires that the value of the minSupportedVersion attribute shall be set to 120000 when the name attribute equals XLMDX.

v. *The standard does not restrict the value of the name attribute.*

Office requires that the value of the name attribute must be XLMDX for MDX metadata type and the name XLMDX cannot be used for future metadata type.

w. *The standard states that the possible values for the name attribute are defined by ST_Xstring simple type.*

Office requires that the name attribute be non-empty and less than or equal to 65535 characters.

x. *The standard does not restrict the value @adjust when @name=XLMDX.*

Office requires that the value @adjust shall not be true when @name=XLMDX.

y. *The standard does not restrict the value @assign when @name=XLMDX.*

Office requires that the value @assign shall be true when @name=XLMDX.

z. *The standard does not restrict the value @cellMeta when @name=XLMDX.*

Office requires that the value @cellMeta shall not be true when @name=XLMDX.

aa. *The standard does not restrict the value @clearAll when @name=XLMDX.*

Office requires that the value @clearAll shall not be true when @name=XLMDX.

bb. *The standard does not restrict the value @clearComments when @name=XLMDX.*

Office requires that the value @clearComments shall be true when @name=XLMDX.

cc. *The standard does not restrict the value @clearContents when @name=XLMDX.*

Office requires that the value @clearContents shall not be true when @name=XLMDX.

dd. *The standard does not restrict the value @clearFormats when @name=XLMDX.*

Office requires that the value @clearFormats shall be true when @name=XLMDX.

ee. *The standard does not restrict the value @coerce when @name=XLMDX.*

Office requires that the value @coerce shall be true when @name=XLMDX.

ff. *The standard does not restrict the value @copy when @name=XLMDX.*

Office requires that the value @copy shall be true when @name=XLMDX.

gg. *The standard does not restrict the value @delete when @name=XLMDX.*

Office requires that the value @delete shall not be true when @name=XLMDX.

hh. *The standard does not restrict the value @edit when @name=XLMDX.*

Office requires that the value @edit shall not be true when @name=XLMDX.

ii. *The standard does not restrict the value @ghostCol when @name=XLMDX.*

Office requires that the value @ghostCol shall not be true when @name=XLMDX.

jj. *The standard does not restrict the value @ghostRow when @name=XLMDX.*

Office requires that the value @ghostRow shall not be true when @name=XLMDX.

kk. *The standard does not restrict the value @merge when @name=XLMDX.*

Office requires that the value @merge shall be true when @name=XLMDX.

ll. *The standard does not restrict the value @pasteAll when @name=XLMDX.*

Office requires that the value @pasteAll shall be true when @name=XLMDX.

mm. *The standard does not restrict the value @pasteBorders when @name=XLMDX.*

Office requires that the value @pasteBorders shall not be true when @name=XLMDX.

nn. *The standard does not restrict the value @pasteColWidths when @name=XLMDX.*

Office requires that the value @pasteColWidths shall not be true when @name=XLMDX.

oo. *The standard does not restrict the value @pasteComments when @name=XLMDX.*

Office requires that the value @pasteComments shall not be true when @name=XLMDX.

pp. *The standard does not restrict the value @pasteDataValidation when @name=XLMDX.*

Office requires that the value @pasteDataValidation shall not be true when @name=XLMDX.

qq. *The standard does not restrict the value @pasteFormats when @name=XLMDX.*

Office requires that the value @pasteFormats shall not be true when @name=XLMDX.

rr. *The standard does not restrict the value @pasteFormulas when @name=XLMDX.*

Office requires that the value @pasteFormulas shall not be true when @name=XLMDX.

ss. *The standard does not restrict the value @pasteValues when @name=XLMDX.*

Office requires that the value @pasteValues shall be true when @name=XLMDX.

tt. *The standard does not restrict the value @pasteNumberFormats when @name=XLMDX.*

Office requires that the value @pasteNumberFormats shall not be true when @name=XLMDX.

uu. *The standard does not restrict the value @rowColShift when @name=XLMDX.*

Office requires that the value @rowColShift shall be true when @name=XLMDX.

vv. *The standard does not restrict the value @splitAll when @name=XLMDX.*

Office requires that the value @splitAll shall not be true when @name=XLMDX.

ww. *The standard does not restrict the value @splitFirst when @name=XLMDX.*

Office requires that the value @splitFirst shall be true when @name=XLMDX.

2.1.755 Part 4 Section 3.9.11, metadataTypes (Metadata Types Collection)

a. *The standard states that the values of the count attribute are defined by the XML Schema unsignedInt datatype.*

Office requires that the count attribute have a maximum value of 2147483647.

2.1.756 Part 4 Section 3.9.12, ms (Set MDX Metadata)

a. *The standard describes the ns attribute as an unsigned integer with 32 significant bits.*

Office requires that the value be between 0 and 2147483647 inclusive.

b. *The standard describes the @c as an unsigned integer with 32 significant bits.*

Office requires that the value be between 0 and 2147483647 inclusive.

2.1.757 Part 4 Section 3.9.13, n (Member Unique Name Index)

a. *The standard states that the values of the x attribute are defined by the XML Schema unsignedInt datatype.*

Office requires that the x attribute has a maximum value of 2147483647.

2.1.758 Part 4 Section 3.9.14, p (Member Property MDX Metadata)

a. *The standard states that the values of the n attribute are defined by the XML Schema unsignedInt datatype.*

Office requires that the n attribute has a maximum value of 2147483647.

b. *The standard states that the values of the np attribute are defined by the XML Schema unsignedInt datatype.*

Office requires that the np attribute has a maximum value of 2147483647.

2.1.759 Part 4 Section 3.9.15, rc (Metadata Record)

a. *The standard states that the values of the t attribute are defined by the XML Schema unsignedInt datatype.*

Office requires that the t attribute has a maximum value of 2147483647.

2.1.760 Part 4 Section 3.9.16, t (Tuple MDX Metadata)

a. *The standard has no restriction on whether ct can be present along with fi and/or si.*

Office requires that @ct must not be specified if either @si or @fi is specified.

b. *The standard defines the attribute si as an xsd:unsignedInt.*

In Office, @si has a maximum value of less than or equal to 2147483647.

c. *The standard defines the attribute c as an xsd:unsignedInt.*

In Office, @c has a maximum value of less than or equal to 2147483647.

d. *The standard does not restrict the value of @fi beyond unsigned int.*

Office requires that @fi have a maximum value of 58.

e. *The standard does not specify whether @si is a 0-based or 1-based index.*

Office specifies @si is a 0-based index to a metadata string.

f. *The standard does not limit the values of @ct.*

Specifies a language used to determine the currency symbol to display for currency values. For example, if the culture is en-US, the values in the application will format the values with a dollar sign. If the culture is fr-FR the application will format the values with a euro sign.

This value conforms to the language tagging conventions of RFC 3066 and later. The pattern <language>-<REGION> is used, for example, en-US or fr-FR.

Office does not load a file in which this attribute contains a value that it does not recognize, or is not recognized by the underlying operating system. Office recognizes the following values:

| Language | Locale | Language Tag |
|-----------|--------------|--------------|
| Afrikaans | South Africa | af-ZA |
| Albanian | Albanian | sq-AL |
| Alsatian | France | gsw-FR |
| Amharic | Ethiopia | am-ET |

| Language | Locale | Language Tag |
|--------------------------|------------------------|---------------------|
| Arabic | Algeria | ar-DZ |
| Arabic | Bahrain | ar-BH |
| Arabic | Egypt | ar-EG |
| Arabic | Iraq | ar-IQ |
| Arabic | Jordan | ar-JO |
| Arabic | Kuwait | ar-KW |
| Arabic | Lebanon | ar-LB |
| Arabic | Libya | ar-LY |
| Arabic | Morocco | ar-MA |
| Arabic | Oman | ar-OM |
| Arabic | Qatar | ar-QA |
| Arabic | Saudi Arabia | ar-SA |
| Arabic | Syria | ar-SY |
| Arabic | Tunisia | ar-TN |
| Arabic | U.A.E. | ar-AE |
| Arabic | Yemen | ar-YE |
| Armenian | Armenia | hy-AM |
| Assamese | India | as-IN |
| Azeri (Cyrillic) | Azerbaijan | az-AZ-Cyrl |
| Azeri (Latin) | Azerbaijan | az-AZ-Latn |
| Bashkir | Russia | ba-RU |
| Basque | Basque | eu-ES |
| Belarusian | Belarus | be-BY |
| Bengali | Bangladesh | bn-BD |
| Bengali (Bengali Script) | India | bn-IN |
| Bosnian (Cyrillic) | Bosnia and Herzegovina | bs-BA-Cyrl |
| Bosnian (Latin) | Bosnia and Herzegovina | bs-BA-Latn |
| Breton | France | br-FR |
| Bulgarian | Bulgaria | bg-BG |
| Catalan | Catalan | ca-ES |

| Language | Locale | Language Tag |
|------------------|------------------------|---------------------|
| Chinese | Hong Kong SAR | zh-HK |
| Chinese | Macao | zh-MO |
| Chinese | PRC | zh-CN |
| Chinese | Singapore | zh-SG |
| Chinese | Taiwan | zh-TW |
| Corsican | France | co-FR |
| Croatian | Croatia | hr-HR |
| Croatian (Latin) | Bosnia and Herzegovina | hr-BA-Latn |
| Czech | Czech Republic | cs-CZ |
| Danish | Denmark | da-DK |
| Dari | Afghanistan | prs-AF |
| Divehi | Maldives | div-MV |
| Dutch | Belgium | nl-BE |
| Dutch | Netherlands | nl-NL |
| English | Australia | en-AU |
| English | Belize | en-BZ |
| English | Canada | en-CA |
| English | Caribbean | en-CB |
| English | India | en-IN |
| English | Ireland | en-IE |
| English | Jamaica | en-JM |
| English | Malaysia | en-MY |
| English | New Zealand | en-NZ |
| English | Philippines | en-PH |
| English | South Africa | en-ZA |
| English | Trinidad | en-TT |
| English | United Kingdom | en-GB |
| English | United States | en-US |
| English | Zimbabwe | en-ZW |
| Estonian | Estonia | et-EE |

| Language | Locale | Language Tag |
|----------------------------|---------------|---------------------|
| Faroese | Faroe Islands | fo-FO |
| Filipino | Philippines | fil-PH |
| Finnish | Finland | fi-FI |
| French | Belgium | fr-BE |
| French | Canada | fr-CA |
| French | France | fr-FR |
| French | Luxembourg | fr-LU |
| French | Monaco | fr-MC |
| French | Switzerland | fr-CH |
| Frisian | Netherlands | fy-NL |
| Galician | Galician | gl-ES |
| Georgian | Georgia | ka-GE |
| German | Austria | de-AT |
| German | Germany | de-DE |
| German | Liechtenstein | de-LI |
| German | Luxembourg | de-LU |
| German | Switzerland | de-CH |
| Greek | Greece | el-GR |
| Greenlandic | Greenland | kl-GL |
| Gujarati (Gujarati Script) | India | gu-IN |
| Hausa (Latin) | Nigeria | ha-NG-Latn |
| Hebrew | Israel | he-IL |
| Hindi | India | hi-IN |
| Hungarian | Hungary | hu-HU |
| Icelandic | Iceland | is-IS |
| Igbo | Nigeria | ig-NG |
| Inari Sami | Finland | smn-FI |
| Indonesian | Indonesia | id-ID |
| Inuktitut (Latin) | Canada | iu-CA-Latn |
| Inuktitut (Syllabics) | Canada | iu-CA-Cans |

| Language | Locale | Language Tag |
|------------------------------|--------------------|---------------------|
| Irish | Ireland | ga-IE |
| isiXhosa / Xhosa | South Africa | xh-ZA |
| isiZulu / Zulu | South Africa | zu-ZA |
| Italian | Italy | it-IT |
| Italian | Switzerland | it-CH |
| Japanese | Japan | ja-JP |
| Kannada (Kannada Script) | India | kn-IN |
| Kazakh | Kazakhstan | kk-KZ |
| Khmer | Cambodia | kh-KH |
| K'iche | Guatemala | qut-GT |
| Kinyarwanda | Rwanda | rw-RW |
| Konkani | India | kok-IN |
| Korean | Korea | ko-KR |
| Kyrgyz | Kyrgyzstan | ky-KG |
| Lao | Lao PDR | lo-LA |
| Latvian | Latvia | lv-LV |
| Lithuanian | Lithuania | lt-LT |
| Lower Sorbian | Germany | wee-DE |
| Lule Sami | Norway | smj-NO |
| Lule Sami | Sweden | smj-SE |
| Luxembourgish | Luxembourg | lb-LU |
| Macedonian | F.Y.R.O. Macedonia | mk-MK |
| Malay | Brunei | ms-BN |
| Malay | Malaysia | ms-MY |
| Malayalam (Malayalam Script) | India | ml-IN |
| Maltese | Malta | mt-MT |
| Maori | New Zealand | mi-NZ |
| Mapudungun | Chile | arn-CL |
| Marathi | India | mr-IN |
| Mohawk | Mohawk | moh-CA |

| Language | Locale | Language Tag |
|-----------------------------------|---|---------------------|
| Mongolian (Cyrillic) | Mongolia | mn-MN |
| Mongolian (Mongolian) | PRC | mn-CN-Mong |
| Nepali | Nepal | ne-NP |
| Northern Sami | Finland | se-FI |
| Northern Sami | Norway | se-NO |
| Northern Sami | Sweden | se-SE |
| Norwegian (Bokmål) | Norway | nb-NO |
| Norwegian (Nynorsk) | Norway | nn-NO |
| Occitan | France | oc-FR |
| Oriya (Oriya Script) | India | or-IN |
| Pashto | Afghanistan | ps-AF |
| Persian | Iran | fa-IR |
| Polish | Poland | pl-PL |
| Portuguese | Brazil | pt-BR |
| Portuguese | Portugal | pt-PT |
| Punjabi (Gurmukhi Script) | India | pa-IN |
| Quechua | Bolivia | quz-BO |
| Quechua | Ecuador | quz-EC |
| Quechua | Peru | quz-PE |
| Romanian | Romania | ro-RO |
| Romansh | Switzerland | rm-CH |
| Russian | Russia | ru-RU |
| Sanskrit | India | sa-IN |
| Serbian (Cyrillic) | Bosnia and Herzegovina | sr-BA-Cyrl |
| Serbian (Cyrillic) | Republic of Serbia and Republic of Montenegro | sr-SP-Cyrl |
| Serbian (Latin) | Bosnia and Herzegovina | sr-BA-Latn |
| Serbian (Latin) | Republic of Serbia and Republic of Montenegro | sr-SP-Latn |
| Sesotho sa Leboa / Northern Sotho | South Africa | ns-ZA |
| Setswana / Tswana | South Africa | tn-ZA |
| Sinhala | Sri Lanka | si-LK |

| Language | Locale | Language Tag |
|------------------|--------------------|---------------------|
| Skolt Sami | Finland | sms-FI |
| Slovak | Slovakia | sk-SK |
| Slovenian | Slovenia | sl-SI |
| Southern Sami | Norway | sma-NO |
| Southern Sami | Sweden | sma-SE |
| Spanish | Argentina | es-AR |
| Spanish | Bolivia | es-BO |
| Spanish | Chile | es-CL |
| Spanish | Columbia | es-CO |
| Spanish | Costa Rica | es-CR |
| Spanish | Dominican Republic | es-DO |
| Spanish | Ecuador | es-EC |
| Spanish | El Salvador | es-SV |
| Spanish | Guatemala | es-GT |
| Spanish | Honduras | es-HN |
| Spanish | Mexico | es-MX |
| Spanish | Nicaragua | es-NI |
| Spanish | Panama | es-PA |
| Spanish | Paraguay | es-PY |
| Spanish | Peru | es-PE |
| Spanish | Puerto Rico | es-PR |
| Spanish | Spain | es-ES |
| Spanish | United States | es-US |
| Spanish | Uruguay | es-UY |
| Spanish | Venezuela | es-VE |
| Swahili | Kenya | sw-KE |
| Swedish | Finland | sv-FI |
| Swedish | Sweden | sv-SE |
| Syriac | Syria | syr-SY |
| Tajik (Cyrillic) | Tajikistan | tg-TJ-Cyrl |

| Language | Locale | Language Tag |
|------------------------|----------------|--------------|
| Tamazight (Latin) | Algeria | tmz-DZ-Latn |
| Tamil | India | ta-IN |
| Tatar | Russia | tt-RU |
| Telugu (Telugu Script) | India | te-IN |
| Thai | Thailand | th-TH |
| Tibetan | Bhutan | bo-BT |
| Tibetan | PRC | bo-CN |
| Turkish | Turkey | tr-TR |
| Turkmen | Turkmenistan | tk-TM |
| Uighur | PRC | ug-CN |
| Ukrainian | Ukraine | uk-UA |
| Upper Sorbian | Germany | wen-DE |
| Urdu | Pakistan | ur-PK |
| Uzbek (Cyrillic) | Uzbekistan | uz-UZ-Cyrl |
| Uzbek (Latin) | Uzbekistan | uz-UZ-Latn |
| Vietnamese | Viet Nam | vi-VN |
| Welsh | United Kingdom | cy-GB |
| Wolof | Senegal | wo-SN |
| Yakut | Russia | sah-RU |
| Yi | PRC | ii-CN |
| Yoruba | Nigeria | yo-NG |

2.1.761 Part 4 Section 3.9.17, valueMetadata (Value Metadata)

For additional notes that apply to this portion of the standard, please see the notes for [cellMetadata](#), §3.9.3(a).

a. The standard states that the values of the count attribute are defined by the XML Schema `unsignedInt` datatype.

Office requires that the count attribute have a maximum value of 2147483647.

2.1.762 Part 4 Section 3.10.1.1, autoSortScope (AutoSort Scope)

a. The standard states that `autoSortScope` represents the sorting scope for the `PivotTable`.

In Office when autoSortScope is not specified, the sort is based on the items in the pivotField. When the sortType attribute of the parent pivotField is set to manual, autoSortScope must not be specified.

2.1.763 Part 4 Section 3.10.1.2, b (Boolean)

- a. *The standard states that on and off are valid values of the f attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

- b. *The standard states that on and off are valid values of the u attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

- c. *The standard does not specify a default value for the u attribute.*

Excel uses a default value of false for this attribute.

- d. *The standard does not specify a default value for the f attribute.*

Excel uses a default value of false for this attribute.

- e. *The standard does not limit the length of the value of the c attribute.*

Excel restricts the value of this attribute to be at most 65535 characters.

- f. *The standard does not qualify the c attribute as applicable only in certain cases.*

In Office, the c attribute is only valid for OLAP PivotTables and when createdVersion is 3 or greater.

- g. *The standard does not define the relation between the u attribute and the sharedItems parent.*

In Office, the u attribute only applies when the parent is sharedItems.

- h. *The standard does not define restrictions on when the cp attribute should be present.*

In Office, the cp attribute applies to OLAP-based PivotTables only and the parent is sharedItems.

- i. *The standard does not specify restrictions on value of the cp attribute.*

In Office, the value of the cp attribute shall be equal to the number of x child elements and less than or equal to the mappingCount attribute of the corresponding cacheField element.

- j. *The standard does not define the relation between the f attribute and the sharedItems parent.*

In Office, the f attribute only applies when the parent is sharedItems.

2.1.764 Part 4 Section 3.10.1.3, cacheField (PivotCache Field)

- a. *The standard does not restrict values of the hierarchy attribute.*

In Office, the hierarchy attribute must be non-negative and less than the count of cacheHierarchie elements in the cacheHierarchies node. This attribute is only used by OLAP PivotCache.

- b. *The standard does not define all the possible values of the level attribute.*

In Excel, the level attribute is only used by the OLAP PivotCache. If memberPropertyField is 0, this value shall be either 0x7fff (which means all levels) or it shall be less than the count of fieldUsage elements in fieldsUsage node.

c. *The standard does not specify restrictions for the name attribute.*

In Office, the name attribute must be unique. The name is case-insensitive and shall have length between 1 and 32767 inclusively. If the value of createdVersion is less than 3, @name shall not be longer than 255 characters.

d. *The standard does not define maxLength restriction for the caption attribute.*

In Office, the caption attribute shall not be longer than 32767; if createdVersion of pivotCacheDefinition is less than 3, then the caption attribute must not be defined.

e. *The standard does not define length restriction for the propertyName attribute.*

In Office, the propertyName attribute shall have length between 1 and 32767 inclusively.

f. *In the standard the databaseField attribute is not restricted by data source type.*

In Office, the databaseField attribute must be TRUE for OLAP data sources.

g. *In the standard, the formula attribute is defined as a generic string.*

Office requires that the formula attribute be a Pivot formula as defined in [§3.2.3.1.8, Pivot Formulas](#).

h. *In the standard the mappingCount attribute does not have restrictions.*

In Office, the mappingCount attribute shall be less than or equal to number of cacheField items in the cacheFields collection.

i. *The standard states that on and off are valid values of the databaseField, memberPropertyField, serverField, and uniqueList attributes.*

Excel does not allow the on and off values on these attributes.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

j. *The standard does not specify restrictions for the memberPropertyField attribute.*

In Office, the memberPropertyField attribute shall be 1 if the propertyName attribute is not empty and it shall be 0 or false for non-OLAP PivotCaches.

k. *The standard does not restrict the formula attribute usage for different data sources.*

In Office, the formula attribute shall not be specified for OLAP PivotCaches.

l. *In the standard, there is no restriction on value of the databaseField attribute for the first cacheField in collection.*

In Office, the first cacheField shall have a databaseField attribute equal to 1 or true.

2.1.765 Part 4 Section 3.10.1.4, cacheFields (PivotCache Fields)

a. *The standard states that the maxOccurs value for the cacheField child element is unbounded.*

Excel limits the occurrences of this element to 1024 when the value of the createdVersion attribute on the pivotCacheDefinition element is less than 3 and 16384 otherwise.

- b. *The standard states that the minOccurs value for the cacheField child element is 0.*

Excel requires an occurrence of this element for non-OLAP PivotCaches.

2.1.766 Part 4 Section 3.10.1.5, cacheHierarchies (PivotCache Hierarchies)

- a. *The standard states that the minOccurs value for the cacheHierarchy child element is 0.*

Excel requires an occurrence of this element.

2.1.767 Part 4 Section 3.10.1.6, cacheHierarchy (PivotCache Hierarchy)

- a. *The standard does not limit the length of the value of the uniqueName attribute.*

Excel restricts the value of this attribute to be at least 1 and at most 255 characters when the createdVersion attribute on the pivotCacheDefinition element is less than 3 and 32767 characters otherwise.

- b. *The standard does not limit the length of the value of the caption attribute.*

Excel restricts the value of this attribute to be at least 1 and at most 255 characters when the createdVersion attribute on the pivotCacheDefinition element is less than 3 and 32767 characters otherwise.

- c. *The standard states that the caption attribute is optional.*

Excel requires this attribute.

- d. *The standard does not limit the length of the value of the defaultMemberUniqueName attribute.*

Excel restricts the value of this attribute to be at most 255 characters when the createdVersion attribute on the pivotCacheDefinition element is less than 3 and 32767 characters otherwise.

- e. *The standard does not limit the length of the value of the allUniqueName attribute.*

Excel restricts the value of this attribute to be at most 255 characters when the createdVersion attribute on the pivotCacheDefinition element is less than 3 and 32767 characters otherwise.

- f. *The standard does not limit the length of the value of the allCaption attribute.*

Excel restricts the value of this attribute to be at most 255 characters when the createdVersion attribute on the pivotCacheDefinition element is less than 3 and 32767 characters otherwise.

- g. *The standard does not limit the length of the value of the dimensionUniqueName attribute.*

Excel restricts the value of this attribute to be at least 1 and at most 255 characters when the createdVersion attribute on the pivotCacheDefinition element is less than 3 and 32767 characters otherwise.

- h. *The standard does not limit the length of the value of the displayFolder attribute.*

Excel restricts the value of this attribute to be at most 65535 characters.

- i. *The standard does not limit the length of the value of the measureGroup attribute.*

Excel restricts the value of this attribute to be at most 65535 characters.

j. *The standard states that on and off are valid values of the attribute attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

k. *The standard states that on and off are valid values of the hidden attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

l. *The standard states that on and off are valid values of the keyAttribute attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

m. *The standard states that on and off are valid values of the measure attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

n. *The standard states that on and off are valid values of the measures attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

o. *The standard states that on and off are valid values of the oneField attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

p. *The standard states that on and off are valid values of the set attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

q. *The standard states that on and off are valid values of the time attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

r. *The standard states that on and off are valid values of the unbalanced attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

s. *The standard states that on and off are valid values of the unbalancedGroup attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

t. *The standard does not place any restrictions on the value for the parentSet attribute.*

In Excel, the value must be less than the number of cacheHierarchy elements in cacheHierarchies collection.

u. *The standard does not state value restrictions for the iconSet attribute.*

Excel requires that the iconSet attribute be between 0 and 11.

v. *The standard does not place any restrictions on the value for the set attribute.*

In Excel, the values for the measure attribute and the set attribute cannot both be 1.

w. *The standard does not place any restrictions on the value for the measure attribute.*

In Excel, the values for the measure attribute and the set attribute cannot both be 1.

x. *The standard does not specify the relationship between the dimensionUniqueName attribute and dimension item in the dimensions collection.*

Excel requires that the dimensionUniqueName attribute match the uniqueName attribute of an item in the dimensions collection and must be present if the set attribute equals 0, measure=0, and hidden=0.

y. *The standard states that the oneField attribute, when true, indicates this hierarchy is associated with only one field.*

Excel requires that the oneField attribute be written out when the fieldsUsage collection contains one item.

z. *The standard does not specify any dependencies between the measure attribute value and dimensions collection.*

In Excel, if the measure attribute equals 0, the matching dimension shall not have measure=1; if the measure attribute equals 1, there shall be at least one dimension with measure=1 if dimensions collection present.

2.1.768 Part 4 Section 3.10.1.7, cacheSource (PivotCache Source Description)

a. *The standard says that data source information is retrieved with the connectionId attribute.*

Office only uses the connectionId attribute for external data sources.

b. *The standard states that the connectionId attribute is the index to the workbook connection.*

Office requires that the connectionId attribute be the unique ID of the workbook connection.

c. *The standard does not place any restrictions on the value for the connectionId attribute.*

In Office, the connectionId attribute specifies the unique identifier of the workbook connection. When the cache type is set to External, this value shall be greater than 0 and shall be equal to **id** in one of the **connection** elements.

d. *The standard does not define any required schema based on the value of the type attribute.*

Office requires that if this value is worksheet, a child element worksheetSource shall be present. If this value is consolidation, a child element consolidation shall be present.

2.1.769 Part 4 Section 3.10.1.8, calculatedItem (Calculated Item)

- a. *The standard does not define restrictions on the value of the field attribute.*

Office requires that the max value of the field attribute be less than the count of cacheField elements.

- b. *The standard does not specify usage of child pivotArea element.*

In Office, pivotArea child element is used to specify cells to which the formula attributes apply.

- c. *The standard does not place any restrictions on the value for the formula attribute.*

Office restricts the value of the formula attribute to be a Calculated Item Formula, as defined in Formulas ("[ECMA-376](#) Part 4 §3.17; Formulas").

- d. *The standard specifies that the field attribute indicates an index of the pivotField with which this calculated item is associated.*

Office interprets the field attribute to specify an index of the cacheField with which this calculated item is associated.

2.1.770 Part 4 Section 3.10.1.10, calculatedMember (Calculated Member)

- a. *The standard discusses calculatedMember in the context of calculated OLAP hierarchies only.*

In Office, the calculatedMember element can also be used to represent a named set.

- b. *The standard does not have a length restriction for the name attribute.*

Office limits the name attribute to being non-empty and less than 64000 characters.

- c. *The standard does not specify a length restriction for the mdx attribute.*

Office limits the mdx attribute to being non-empty; if the createdVersion attribute of the pivotCacheDefinition is less than 3, the mdx attribute max length is less than 2049, otherwise it is 32767.

- d. *The standard states that on and off are valid values of the set attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

- e. *The standard states that calculated items cannot be added.*

Office does allow the addition of calculated items.

- f. *The standard does not limit the length of the value of the memberName attribute.*

Excel restricts the value of this attribute to be at least 1 and at most 65535 characters.

- g. *The standard does not limit the length of the value of the hierarchy attribute.*

Excel restricts the value of this attribute to be at least 1 and at most 65535 characters.

h. *The standard does not limit the length of the value of the parent attribute.*

Excel restricts the value of this attribute to be at least 1 and at most 65535 characters.

i. *The standard does not specify a dependency of the memberName attribute on the set attribute.*

Office requires that the memberName attribute shall be specified if the set attribute equals 0; it shall not be specified if the set attribute equals 1.

j. *The standard does not specify a dependency of the hierarchy attribute on the set attribute.*

Office requires that the hierarchy attribute shall be specified if the set attribute equals 0; it shall not be specified if the set attribute equals 1.

k. *The standard does not specify a dependency between the parent attribute and the set attribute.*

Office requires that the parent attribute shall not be specified if the set attribute equals 1.

2.1.771 Part 4 Section 3.10.1.12, chartFormat (PivotChart Format)

a. *The standard states that the format attribute specifies an index to a dxf element in the Styles part.*

Office uses the format attribute to specify an index to a pivotFmt element in the Chart part.

b. *The standard states that on and off are valid values of the series attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.772 Part 4 Section 3.10.1.15, colHierarchiesUsage (Column OLAP Hierarchy References)

a. *The standard states that the maxOccurs value for the colHierarchyUsage child element is unbounded.*

Excel limits the occurrences of this element to 16384.

2.1.773 Part 4 Section 3.10.1.16, colHierarchyUsage (Column OLAP Hierarchies)

For additional notes that apply to this portion of the standard, please see the notes for [rowHierarchyUsage](#), §3.10.1.83(a, b).

2.1.774 Part 4 Section 3.10.1.17, colItems (Column Items)

a. *The standard states that the maxOccurs value for the i child element is unbounded.*

Excel limits the occurrences of this element to 1048576.

2.1.775 Part 4 Section 3.10.1.18, conditionalFormat (Conditional Formatting)

a. *The standard does not state the relationship of the priority attribute to the worksheet cfRule element.*

In Office, there shall be a conditionalFormatting element, in the worksheet part associated with this PivotTable, with the pivot attribute equal to true and a cfRule element with the priority attribute equal to this priority value.

b. *The standard does not place any restriction on the relationship between the values of the scope attribute and the type attribute.*

In Office, when the scope attribute equals data or selection, only the values all or none are allowed for the type attribute.

2.1.776 Part 4 Section 3.10.1.20, consolidation (Consolidation Source)

a. *The standard states that on and off are valid values of the set attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.777 Part 4 Section 3.10.1.21, d (Date Time)

a. *The standard does not specify a default value for the u attribute.*

Excel uses a default value of false for this attribute.

b. *The standard does not specify a default value for the f attribute.*

Excel uses a default value of false for this attribute.

c. *The standard does not limit the length of the value of the c attribute.*

Excel restricts the value of this attribute to be at most 65535 characters.

d. *The standard states that on and off are valid values of the f attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

e. *The standard states that on and off are valid values of the u attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

f. *The standard does not define @c's relation with the datasource type.*

In Office, @c applies only to OLAP-based PivotTables and only when pivotCacheDefinition@createdVersion is 3 or greater.

g. *The standard does not define the relationship between the cp attribute and the datasource type.*

In Office, the cp attribute applies to OLAP-based PivotTables only.

h. *The standard does not define the relation between the cp attribute and the sharedItems parent.*

In Office, the cp attribute applies when the parent is sharedItems.

i. *The standard does not define the relation between @f and the sharedItems parent.*

In Office, @f applies when the parent is sharedItems.

j. *The standard does not define restrictions on the value of @cp.*

In Excel, @cp shall be equal to the count of child x elements and be less than or equal to the @mappingCount of the corresponding cacheField element.

k. *The standard does not define the relation between @u and the sharedItems parent.*

In Excel, @u applies when the parent is sharedItems.

2.1.778 Part 4 Section 3.10.1.22, dataField (Data Field Item)

a. *The standard does not specify length restrictions for the name attribute.*

Office specifies the maximum length of the name attribute shall be 32767, unless pivotTableDefinition@createdVersion is less than 3 in which case the maximum shall be 255.

b. *The standard states the fld attribute specifies the index to the field in the pivotCacheRecords part that this data item summarizes.*

In Office, the fld attribute specifies a valid index into the pivotField elements of the pivotFields.

c. *The standard for @showDataAs has a note about cell formatting.*

Office for @showDataAs uses the ST_ShowDataAs definition to determine how the dataField should be used rather than the note direction.

d. *The standard does not define a default behavior for the numFmtId attribute.*

Office assumes the application uses a default format if the numFmtId attribute is not present.

e. *The standard does not specify restrictions for the baseField attribute.*

In Office, if the showDataAs attribute is difference, percent, percentDiff or runTotal, then the baseField attribute value shall be greater or equal to zero and less than the number of pivotField elements in the pivotFields collection.

f. *The standard does not restrict the value of the baseItem attribute.*

In Office, if the showDataAs attribute equals difference, percent, or percentDiff, then the baseItem attribute shall be 1048828 (the previous item) or 1048829 (the next item). Otherwise, it is less than the number of item elements in the items collection of the field pointed to by the baseField attribute.

2.1.779 Part 4 Section 3.10.1.24, dimension (OLAP Dimension)

a. *The standard does not limit the length of the value of the caption attribute.*

Excel restricts the value of this attribute to be at least 1 and at most 65535 characters.

b. *The standard does not limit the length of the value of the name attribute.*

Excel restricts the value of this attribute to be at least 1 and at most 65535 characters.

c. *The standard does not limit the length of the value of the uniqueName attribute.*

Excel restricts the value of this attribute to be at least 1 and at most 32767 characters.

d. *The standard states that on and off are valid values of the measure attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.780 Part 4 Section 3.10.1.26, discretePr (Discrete Grouping Properties)

a. *The standard says discretePr represents the collection of discrete grouping properties for a field group.*

In Office, each child element specifies a mapping from an element in the sharedItems collection (“[\[ECMA-376\]](#) Part 4 §3.10.1.90; sharedItems (Shared Items)”) of the base field of this field group to an element in the groupItems collection (“[\[ECMA-376\]](#) Part 4 §3.10.1.38; groupItems (OLAP Group Items)”) of the field group, using a zero-based index into the groupItems collection. The number of child elements shall match the number of elements in the sharedItems collection (“[\[ECMA-376\]](#) Part 4 §3.10.1.90; sharedItems (Shared Items)”) of the base field of this field group.

2.1.781 Part 4 Section 3.10.1.27, e (Error Value)

a. *The standard states that on and off are valid values of the f attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

b. *The standard does not limit the length of the value of the c attribute.*

Excel restricts the value of this attribute to be at most 65535 characters.

c. *The standard does not define the relation between the c attribute and the datasource type.*

In Office, the c attribute applies only to OLAP-based PivotTables when the pivotCacheDefinition element attribute createdVersion is greater than or equal to 3.

d. *The standard does not define the relation between the cp attribute and child elements.*

In Office, the value of the cp attribute shall be equal to the count of child elements and be less than or equal to the @mappingCount of the corresponding cacheField element.

e. *The standard does not define the relation between the cp attribute and the datasource type.*

In Office, the cp attribute applies only to OLAP-based PivotTables.

f. *The standard does not define relation between the cp attribute and sharedItems node.*

In Office, the cp attribute applies only when the node parent is sharedItems.

g. *The standard does not specify a default value for the f attribute.*

Excel uses a default value of false for this attribute.

h. *The standard states that on and off are valid values of the u attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

i. *The standard does not specify a default value for the u attribute.*

Excel uses a default value of false for this attribute.

j. *The standard does not normatively define valid error values for the v attribute.*

Office implements the following error values:

#DIV/0!

#NAME?

#VALUE!

#NULL!

#NUM!

#REF!

#N/A

#GETTING_DATA

k. *The standard does not define relation between the f attribute and sharedItems node.*

In Office, the f attribute applies only when the node parent is sharedItems.

l. *The standard does not define relation between the u attribute and sharedItems node.*

In Office, the u attribute applies only when the node parent is sharedItems.

m. *The standard allows on as a valid value for the b attribute.*

In Office, on is an invalid value for the b attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

n. *The standard allows on as a valid value for the i attribute.*

In Office, on is an invalid value for the i attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

o. *The standard allows on as a valid value for the st attribute.*

In Office, on is an invalid value for the st attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

p. *The standard allows on as a valid value for the un attribute.*

In Office, on is an invalid value for the un attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.782 Part 4 Section 3.10.1.29, field (Field)

a. *In the standard for the element description it says there will be as many <x> elements as there are item values in any particular column or row.*

Office says that there will be as many <field> elements as there are fields in the column or row axis.

b. *The standard notes that elements may not be explicitly written and i elements, @r and @v used, which do not occur on this element or its parents.*

Office assumes that field elements are always explicit and the x attribute is required.

c. *The standard specifies that the x attribute is the index to a pivotField item value and there will be as many x elements as there are item values in any particular column.*

Office specifies that the x attribute is a valid zero-based index to a pivotField element in the pivotFields collection with value equal to -2 or greater than or equal to zero and less than the element count in the pivotFields collection.

d. *The standard does not restrict the document from having duplicate field indexes (@x).*

Office requires that the value of @x cannot be duplicated within the parent element.

2.1.783 Part 4 Section 3.10.1.30, fieldGroup (Field Group Properties)

a. *The standard allows fieldGroup to include both rangePr and discretePr in a valid document.*

Office does not allow fieldGroup to include rangePr and discretePr at the same time.

b. *The standard does not require the groupItems collection to exist in any circumstances.*

In Office, if fieldGroup contains rangePr or discretePr, the groupItems collection must exist and must not be empty.

c. *The standard does not provide restrictions on the base attribute.*

Office requires that value of the base attribute to be less than number of cacheFields and the cacheField element pointed to by the base value must have a databaseField attribute equal to 1.

d. *The standard does not provide restrictions on the par attribute.*

Office requires that if fieldGroup has rangePr child, then cacheField pointed to by @par shall have fieldGroup that contains rangePr; the value of the base attribute in that fieldGroup must equal the value of the base attribute on this element.

e. *The standard does not specify a dependency between the value of the rangePr element attribute groupBy and the par attribute value.*

In Office, if the groupBy attribute of a rangePr child is range, then the par attribute shall not be specified; otherwise, it shall be less than count of cacheFields elements.

2.1.784 Part 4 Section 3.10.1.31, fieldsUsage (Fields Usage)

a. *The standard does not restrict the number of items in the fieldsUsage collection, in any case.*

In Office, if the parent cacheHierarchy has @measure equal to 1, this collection shall contain only one item.

2.1.785 Part 4 Section 3.10.1.32, fieldUsage (PivotCache Field Id)

- a. *The standard does not restrict the value of the x attribute in any way.*

In Office, x is a zero-based index in the parent collection, must be ≥ -1 and $<$ the total number of cacheField elements. If x points to a cacheField, this cacheField must point back to the same hierarchy the parent fieldsUsage is part of.

- b. *The standard does not state a dependency between fieldUsage index and cacheField@level.*

Office requires that the index of fieldUsage in the fieldsUsage collection determine the mapping between Pivot level and a cache field. The index must match the value of @level in the corresponding cacheField item.

2.1.786 Part 4 Section 3.10.1.33, filter (PivotTable Advanced Filter)

- a. *The standard does not define a maximum value for @fld.*

Office requires @fld to be less than the pivotFields count.

- b. *The standard does not define a max value for @iMeasureHier.*

Office requires that @iMeasureHier be less than the pivotHierarchies count.

- c. *The standard does not define a maximum value for the mpFld attribute.*

Office requires that the mpFld attribute be less than the pivotFields count.

- d. *The standard does not specify a default value for the iMeasureFld attribute.*

Excel uses a default value of 0 for this attribute.

- e. *The standard does not state a maximum limit for the iMeasureFld attribute.*

Office specifies that @iMeasureFld be less than the data fields count. Office will not load a file that has @iMeasureFld greater or equal to the count of pivotFields.

- f. *The standard does not state any restrictions on when the mpFld attribute can be used.*

Office assumes that the mpFld attribute is specific to OLAP PivotTables.

- g. *The standard states that @evalOrder specifies the evaluation order of the pivot filter.*

In Office, the value of -1 indicates that the order in which filters are applied is not relevant.

2.1.787 Part 4 Section 3.10.1.35, format (PivotTable Format)

- a. *The standard defines the action attribute as type ST_FormatAction, which contains Drill and Formula as values.*

Excel does not support the Drill and Formula values for the action attribute.

2.1.788 Part 4 Section 3.10.1.37, group (OLAP Group)

- a. *The standard does not define limitations on the valid values for the id attribute.*

Office requires that the value of the id attribute be greater than 0.

b. *The standard does not define a length limitation to the value of @uniqueParent.*

Office limits the value of @uniqueParent to 65535 characters.

c. *The standard does not place limits on the length of @caption, @name, and @uniqueName.*

Office assumes that for @caption, @name, and @uniqueName, if the value of pivotCacheDefinition@createdVersion is less than 3, the maximum length of these attributes is 255 characters.

2.1.789 Part 4 Section 3.10.1.38, groupItems (OLAP Group Items)

a. *The standard states that the groupItems element defines OLAP Group Items.*

In Office, the groupItems element does not apply to OLAP PivotTables.

2.1.790 Part 4 Section 3.10.1.39, groupLevel (OLAP Grouping Levels)

a. *The standard states that on and off are valid values of the customRollUp attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

b. *The standard states that on and off are valid values of the user attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

c. *The standard does not limit the length of the value of the caption attribute.*

Excel restricts the value of this attribute to be at most 255 characters when the createdVersion attribute on the pivotCacheDefinition element is less than 3 and 32767 characters otherwise.

d. *The standard does not limit the length of the value of the uniqueName attribute.*

Excel restricts the value of this attribute to be at most 255 characters when the createdVersion attribute on the pivotCacheDefinition element is less than 3 and 32767 characters otherwise.

2.1.791 Part 4 Section 3.10.1.41, groupMember (OLAP Group Member)

a. *The standard states that on and off are valid values of the group attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

b. *The standard does not limit the length of the value of the uniqueName attribute.*

Excel restricts the value of this attribute to be at least 1 and at most 65535 characters.

2.1.792 Part 4 Section 3.10.1.44, i (Row Items)

a. *The standard does not specify restrictions on the i attribute.*

Office specifies that the i attribute should be 0 if the dataFields collection is empty and should be less than number of elements in that collection otherwise.

b. *The standard states that a value of default on the t attribute indicates a grand total as the last row item value.*

Excel uses the definition from the ST_ItemType simple type for the definition of this value.

c. *The standard does not place restrictions on the value of the r attribute.*

In Office, if the r attribute is not 0, then the sum of the r attribute and number of x attribute elements must be less or equal to the number of elements in the rowFields or colFields collections, depending on context. The r attribute shall not exceed the number of items in the previous row item.

d. *The standard does not specify the relationship of x elements to pivotFields.*

Office defines the relationship between x elements and pivotFields as follows:

The v attribute of the x element shall be 1048832 (specifying that no item appears at this position) or a valid item index in its pivot field.

The axis index, of a child item x, is calculated as the value of r plus the index of the x element within the collection in this element. The field index is calculated as given by the x attribute of the field element, at the position given by the axis index, in either the colFields element ("[ECMA-376](#) Part 4 §3.10.1.14; colFields (Column Fields)"), if the parent of this element is colItems, or the rowFields element ("[ECMA-376](#) Part 4 §3.10.1.81; rowFields (Row Fields)"), if the parent of this element is rowItems.

If the field index is -2 valid item indexes, for the v attribute of the x child, shall be less than the number of elements in the dataFields collection ("[ECMA-376](#) Part 4 §3.10.1.23; dataFields (Data Fields)"). Otherwise valid item indexes, for the v attribute of the x child, shall be less than the number of elements in the items collection ("[ECMA-376](#) Part 4 §3.10.1.46; items (Field Items)") of the pivotField, at the index given by the field index in the pivotFields ("[ECMA-376](#) Part 4 §3.10.1.70; pivotFields (PivotTable Fields)").

2.1.793 Part 4 Section 3.10.1.45, item (PivotTable Field Item)

a. *The standard states that the s attribute specifies if the item has a character value.*

Excel uses the s attribute to specify if the item has a manual filter applied.

b. *The standard does not require any ordering of the child item elements.*

In Office, any item elements that have the t attribute equal to the default value must appear before item elements with other values.

c. *The standard does not restrict the c attribute to OLAP PivotTables.*

Excel allows the c attribute only for OLAP PivotTables.

d. *The standard does not restrict the d attribute to OLAP PivotTables.*

Excel allows the d attribute for OLAP PivotTables only.

e. *The standard does not restrict the e attribute to OLAP PivotTables only.*

Excel allows the e attribute for OLAP PivotTables only.

f. *The standard does not restrict the f attribute to non-OLAP PivotTables.*

Excel allows the f attribute in non-OLAP PivotTables only.

g. *The standard does not restrict the h attribute to non-OLAP PivotTables.*

Excel allows the h attribute in non-OLAP PivotTables only.

h. *The standard does not restrict the m attribute to non-OLAP PivotTables.*

Excel allows the m attribute in non-OLAP PivotTables only.

i. *The standard does not restrict the s attribute to OLAP PivotTables.*

Excel allows the s attribute in OLAP PivotTables only.

j. *The standard does not restrict the sd attribute to non-OLAP PivotTables.*

Excel allows the sd attribute in non-OLAP PivotTables only.

k. *The standard restricts the x attribute to non-OLAP PivotTables only.*

Excel allows the x attribute in both OLAP and non-OLAP PivotTables.

l. *The standard states that the sd attribute indicates whether the details are hidden for an item.*

Excel uses the sd attribute to indicate whether the item is expanded. A value of true indicates item details are shown. A value of false indicates item details are hidden.

m. *The standard does not specify when the x attribute is required.*

Excel requires the x attribute when the value of the t attribute is data.

n. *The standard states that the x attribute specifies an index to an item in the pivotFields collection.*

Excel uses the x attribute to specify an index to an item in the sharedItems collection for this pivotField.

o. *The standard states that on and off are valid values of the c attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

p. *The standard states that on and off are valid values of the d attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

q. *The standard states that on and off are valid values of the e attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

r. *The standard states that on and off are valid values of the f attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

s. *The standard states that on and off are valid values of the h attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

t. *The standard states that on and off are valid values of the m attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

u. *The standard states that on and off are valid values of the s attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

v. *The standard states that on and off are valid values of the sd attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

w. *The standard does not specify when the x attribute values should be unique for item elements in an items collection.*

Excel requires the x attribute values to be unique for item elements in an items collection.

x. *The standard states that the m attribute indicates whether the item's value is missing.*

Excel uses the m attribute to indicate whether the item itself is missing from the source data.

y. *The standard does not restrict the length of the n attribute.*

Office requires that the n attribute be no longer than 32767 characters, or 255 characters when the PivotTable version is less than 3.

z. *The standard does not restrict the value of the n attribute.*

Office requires for non-OLAP PivotTables that, if present, the value of the n attribute be unique within the containing pivotField.

aa. *The standard does not restrict the value of the t attribute with respect to other attributes.*

Office requires that the f, h, m, and d attributes be the default values if the t attribute has a value other than data.

bb. *The standard does not restrict the possible values for the t attribute within ST_ItemType.*

Office does not allow blank or grand as values for the t attribute in the item element.

2.1.794 Part 4 Section 3.10.1.46, items (Field Items)

a. *The standard says that @count specifies the number of fields in the PivotTable.*

In Office @count specifies the number of items in the pivotField.

2.1.795 Part 4 Section 3.10.1.47, kpi (OLAP KPI)

- a. *The standard implies that the caption attribute is optional.*

Excel requires this attribute.

- b. *The standard does not limit the length of the value of the uniqueName attribute.*

Excel restricts the value of this attribute to be at least 1 and at most 255 characters when the createdVersion attribute on the pivotCacheDefinition element is less than 3 and 32767 characters otherwise.

- c. *The standard does not limit the length of the value of the caption attribute.*

Excel restricts the value of this attribute to be at least 1 and most 32767 characters.

- d. *The standard does not limit the length of the value of the displayFolder attribute.*

Excel restricts the value of this attribute to be at most 65535 characters.

- e. *The standard does not limit the length of the value of the measureGroup attribute.*

Excel restricts the value of this attribute to be at most 65535 characters.

- f. *The standard does not limit the length of the value of the parent attribute.*

Excel restricts the value of this attribute to be at most 32767 characters.

- g. *The standard does not limit the length of the value of the value attribute.*

Excel restricts the value of this attribute to be at least 1 and at most 255 characters when the createdVersion attribute on the pivotCacheDefinition element is less than 3 and 32767 characters otherwise.

- h. *The standard does not limit the length of the value of the goal attribute.*

Excel restricts the value of this attribute to be at most 255 characters when the createdVersion attribute on the pivotCacheDefinition element is less than 3 and 32767 characters otherwise.

- i. *The standard does not limit the length of the value of the status attribute.*

Excel restricts the value of this attribute to be at most 255 characters when the createdVersion attribute on the pivotCacheDefinition element is less than 3 and 32767 characters otherwise.

- j. *The standard does not limit the length of the value of the trend attribute.*

Excel restricts the value of this attribute to be at most 255 characters when the createdVersion attribute on the pivotCacheDefinition element is less than 3 and 32767 characters otherwise.

- k. *The standard does not limit the length of the value of the weight attribute.*

Excel restricts the value of this attribute to be at most 255 characters when the createdVersion attribute on the pivotCacheDefinition element is less than 3 and 32767 characters otherwise.

- l. *The standard does not limit the length of the value of the time attribute.*

Excel restricts the value of this attribute to be at most 255 characters when the createdVersion attribute on the pivotCacheDefinition element is less than 3 and 32767 characters otherwise.

m. *The standard states that the time attribute can be present.*

Office reports files as corrupt that contain this attribute.

n. *The standard states the values of the weight attribute are defined by the Xstring simple type.*

Office will not successfully open files when this attribute is non-empty and contains a value that does not match the uniqueName attribute value of a cacheHierarchy with a measure value of 1.

o. *The standard places no restrictions on the relationship between the parent attribute and the uniqueName attribute on the parent kpi element.*

Excel requires the value of the parent attribute, when not null, to be equal to the value of the uniqueName attribute on the parent kpi element.

p. *The standard places no restrictions on the relationship between the value attribute and the uniqueName attribute on the cacheHierarchy element.*

Excel requires the value of the value attribute to be equal to the value of the uniqueName attribute on a cacheHierarchy element whose measure attribute has a value of 1.

q. *The standard places no restrictions on the relationship between the goal attribute and the uniqueName attribute on the cacheHierarchy element.*

Excel requires the value of the goal attribute to be equal to the value of the uniqueName attribute on a cacheHierarchy element whose measure attribute has a value of 1.

r. *The standard places no restrictions on the relationship between the status attribute and the uniqueName attribute on the cacheHierarchy element.*

Excel requires the value of the status attribute to be equal to the value of the uniqueName attribute on a cacheHierarchy element whose measure attribute has a value of 1.

s. *The standard places no restrictions on the relationship between the trend attribute and the uniqueName attribute on the cacheHierarchy element.*

Excel requires the value of the trend attribute to be equal to the value of the uniqueName attribute on a cacheHierarchy element whose measure attribute has a value of 1.

2.1.796 Part 4 Section 3.10.1.49, location (PivotTable Location)

a. *The standard does not bound the maximum allowed value on the firstHeaderRow attribute.*

Office bounds the maximum allowed value of firstHeaderRow by the value of firstDataRow.

b. *The standard says the @ref specifies the first row of the PivotTable.*

Office assumes that @ref specifies the range of the PivotTable excluding the page fields.

2.1.797 Part 4 Section 3.10.1.50, m (No Value)

a. *The standard does not limit the length of the value of the c attribute.*

Excel restricts the value of this attribute to be at most 65535 characters.

b. *The standard does not define the relation between @c and the datasource type.*

In Office, @c applies only to OLAP-based PivotTables. If the value of pivotCacheDefinition@createdVersion is less than 3, this value shall not be specified.

c. *The standard does not specify a default value for the f attribute.*

Excel uses a default value of false for this attribute.

d. *The standard does not define the relation between @cp and child elements.*

In Office, the value of @cp shall be equal to the count of child x elements and be less than or equal to the @mappingCount of the corresponding cacheField element.

e. *The standard does not define the relation between @cp and the datasource type.*

In Office, @cp applies only to OLAP-based PivotTables.

f. *The standard does not define relation between @cp and sharedItems node.*

In Office, @cp applies only when the node parent is sharedItems.

g. *The standard states that on and off are valid values of the f attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

h. *The standard states that on and off are valid values of the u attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

i. *The standard does not specify a default value for the u attribute.*

Excel uses a default value of false for this attribute.

j. *The standard does not define relation between @f and sharedItems node.*

In Office, @f applies only when the node parent is sharedItems.

k. *The standard does not define relation between @u and sharedItems node.*

In Office, @u applies only when the node parent is sharedItems.

l. *The standard defines that a value of true for the i attribute indicates this value contains underline formatting.*

In Excel, a value of true for the i attribute indicates this value contains italic formatting.

m. *The standard defines that a value of true for the st attribute indicates this value contains underline formatting.*

In Excel, a value of true for the st attribute indicates this value contains strikethrough formatting.

n. *The standard allows on as a valid value for the b attribute.*

In Office, on is an invalid value for the b attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

o. *The standard allows on as a valid value for the i attribute.*

In Office, on is an invalid value for the i attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

p. *The standard allows on as a valid value for the st attribute.*

In Office, on is an invalid value for the st attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

q. *The standard allows on as a valid value for the un attribute.*

In Office, on is an invalid value for the un attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.798 Part 4 Section 3.10.1.51, map (OLAP Measure Group)

a. *The standard does not place any restrictions on the value of the measureGroup attribute.*

In Office, the value of the measureGroup attribute must be less than the number of items in measureGroups collection.

b. *The standard does not restrict the value of @dimension.*

In Office, @dimension must be less than number of items the dimensions collection.

c. *The standard does not specify the base of the dimension attribute index.*

Office treats the dimension attribute as a zero-based index.

d. *The standard does not specify the base of the measureGroup attribute index.*

Office treats the measureGroup attribute as a zero-based index.

e. *The standard states that the dimension attribute is optional.*

Excel requires this attribute.

f. *The standard implies that the measureGroup attribute is optional.*

Excel requires this attribute.

2.1.799 Part 4 Section 3.10.1.53, measureGroup (OLAP Measure Group)

a. *The standard does not limit the length of the value of the caption attribute.*

Excel restricts the value of this attribute to be at least 1 and at most 65535 characters.

b. *The standard does not limit the length of the value of the name attribute.*

Excel restricts the value of this attribute to be at least 1 and at most 65535 characters.

2.1.800 Part 4 Section 3.10.1.55, member (Member)

a. *The standard states that the name attribute specifies the name of a hidden item.*

Excel uses this attribute to specify the name of an included or excluded item.

2.1.801 Part 4 Section 3.10.1.56, members (Members)

- a. *The standard does not state how to handle the absence of the level attribute.*

Excel allows child member elements in this collection to be from all hierarchy levels under this circumstance.

- b. *The standard states that the values of the level attribute are defined by the XML Schema unsignedInt datatype.*

Excel requires the value of this attribute, when present, to be more than 0 and less than the value of the count attribute of the associated PivotCache's cacheHierarchy element with the same index as the parent pivotHierarchy element, if that value is greater than 0.

2.1.802 Part 4 Section 3.10.1.57, mp (OLAP Member Property)

- a. *The standard states that on and off are valid values of the showAsCaption attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

- b. *The standard states that on and off are valid values of the showCell attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

- c. *The standard states that on and off are valid values of the showTip attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

- d. *The standard does not state the relation between the name attribute and the nameLen attribute.*

In Office, if the name attribute is specified, the nameLen attribute shall also be specified and gives the length of an OLAP hierarchy name.

- e. *The standard does not state the relation between the name attribute and the pLen attribute.*

In Office, if the name attribute is specified then the pLen attribute must also be specified.

- f. *The standard does not state the relation between the name attribute and the pPos attribute.*

In Office, if the name attribute is specified then the pPos attribute must also be specified.

- g. *The standard does not state any relationship between the mp element and pivotTableDefinition@createdVersion.*

Office assumes that if pivotTableDefinition@createdVersion is less than 3, then the name attribute shall be present.

- h. *The standard says that mp represents an OLAP Member property.*

Office assumes that if field is not 4294967295, then it specifies a valid index to a pivotField, in this PivotTable, which specifies the information for the member property that is not specified in this element.

i. *The standard limits the possible values for @level to unsignedInt.*

Office requires that when specified, the value of @level be equal to the value of the associated cacheField element @level with the same name attribute as this element, or that the special value of 32767 be used to apply to all levels.

j. *The standard does not place restrictions on when the showAsCaption attribute is used.*

Office ignores the showAsCaption attribute unless the name attribute is present and the uniqueMemberProperty attribute on the PivotField this element applies to is present.

k. *The standard does not place any restrictions on the value of @field.*

In Office, the value of @field must refer to a valid pivotField or be equal to 4294967295.

l. *The standard does not state any relationship between the element and pivotTableDefinition@createdVersion.*

In Office, if the pivotTableDefinition@createdVersion is greater than or equal to 3, then the field attribute shall not equal 4294967295 and the other attributes of this element shall not be present.

m. *The standard says that mp represents an OLAP Member property.*

Office specifies that if field is not 4294967295, then the cacheField at index field in the associated PivotCache shall have memberPropertyField attribute equal to 1 or true.

n. *The standard does not state the relation between the name attribute and the associated cacheField.*

In Office, if name is specified and if field is not equal to 4294967295, then the associated cacheField shall have with a name attribute that matches this one and shall begin with the unique name of the OLAP hierarchy which this element is attached.

o. *The standard does not state a default value for the pPos attribute.*

Excel uses a default value of 0 for this attribute.

p. *The standard does not state a default value for the pLen attribute.*

Excel uses a default value of 0 for this attribute.

q. *The standard does not state a default value for the nameLen attribute.*

Excel uses a default value of 0 for this attribute.

2.1.803 Part 4 Section 3.10.1.58, mpMap (Member Properties Map)

a. *The standard states that @v is an index into the shared items table...*

Office treats @v as an index into the cacheFields collection.

b. *The standard states that the values of the v attribute are defined by the XML int datatype.*

Excel restricts the value of this attribute to be at least 0 and at most equal to the value of the cacheFields count; the value of the memberPropertyField attribute on the cacheField pointed to by this value must be true.

2.1.804 Part 4 Section 3.10.1.60, n (Numeric)

a. *The standard does not define relation between @cp and the datasource type.*

Office allows @cp only with OLAP PivotTables.

b. *The standard states that on and off are valid values of the b attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

c. *The standard does not limit the length of the value of the c attribute.*

Excel restricts the value of this attribute to be at most 65535 characters.

d. *The standard does not define relation between @c and the datasource type.*

Office allows @c only for OLAP-based PivotTables. If the value of pivotCacheDefinition@createdVersion is less than 3 this value shall not be specified.

e. *The standard does not specify a default value for the u attribute.*

Excel uses a default value of false for this attribute.

f. *The standard does not restrict the value of @cp.*

Office requires that @cp be equal to the count of child x elements and be less than or equal to the mappingCount of the corresponding cacheField element.

g. *The standard does not specify a default value for the f attribute.*

Excel uses a default value of false for this attribute.

h. *The standard states that on and off are valid values of the f attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

i. *The standard states that on and off are valid values of the i attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

j. *The standard states that on and off are valid values of the st attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

k. *The standard states that on and off are valid values of the u attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

l. *The standard states that on and off are valid values of the un attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

m. *The standard states that the values of the v attribute are defined by the XML Schema double datatype.*

Excel does not allow the values of INF, -INF, or NaN on this attribute.

n. *The standard does not state when @f is valid.*

In Office, @f is valid only when the parent of the n element is of CT_SharedItems type.

o. *The standard does not define relation of @u with CT_SharedItems node.*

In Office, @u is used only when the n element's parent is of CT_SharedItems type.

p. *The standard states that @b applies to italics.*

Office assumes that @b applies to bold.

q. *The standard does not place a restriction for on the value of the cp attribute.*

In Office, the cp attribute applies only when the node parent is sharedItems.

2.1.805 Part 4 Section 3.10.1.62, pageField (Page Field)

a. *The standard does not state the default for the item attribute.*

In Office, if the item attribute is not specified it means that all items will be used if non-OLAP and pivotField@multipleItemSelectionAllowed is false.

b. *The standard says @index specifies the index of the item in the PivotCache.*

In Office, @item specifies the index of an item in the pivotField referred to by @fld. If present, @item shall be a valid index of an item element and shall specify how to filter this field in the PivotTable.

c. *The standard does not mention limitations on @hier value.*

In Office, if @hier is present and the PivotTable is an OLAP PivotTable then the number of pivotHierarchies shall be greater than 0, and @hier must be ≥ 0 and $<$ the number of pivotHierarchies. For a non-OLAP PivotTable, @hier must be -1.

d. *The standard does not specify limits on length of the name attribute.*

Office requires that the length of the name attribute be less than or equal to 255 if pivotTableDefinition@createdVersion is less than 3, and less than or equal to 32767 if pivotTableDefinition@createdVersion is greater than or equal to 3.

e. *The standard does not state limits on string length of @cap.*

Office specifies that the length of @cap shall be less than or equal to 255 if pivotTableDefinition@createdVersion is less than 3, and less than or equal to 32767 if pivotTableDefinition@createdVersion is greater than or equal to 3.

f. *The standard does not specify restrictions on @fld.*

In Office, @fld must be greater than or equal to 0 and less than the number of pivotField elements on the PivotTable. Additionally, the pivotField referred to must have an axis attribute set to axisPage.

g. *The standard does not specify limits on when the item attribute shall be present.*

In Office, the item attribute shall not be present for OLAP PivotTables, or if pivotField@multipleItemSelectionAllowed is true. In those cases the filtering will be determined by the settings on the pivotField and/or pivotHierarchy.

h. *The standard does not define when the name attribute will be present.*

Office requires the name attribute for OLAP PivotTables.

i. *The standard describes page fields as allowing filtering to display data for a single item or all the items.*

Office additionally assumes that using settings on a pivotField or pivotHierarchy filtering can be done for multiple items in a field used as a page or report filter.

j. *The standard does not state that the name attribute is affected by the multipleItemSelectionAllowed attribute.*

In Office, if pivotHierarchy@multipleItemSelectionAllowed equals 0, the name attribute specifies the member used for filtering. Otherwise, it is ignored.

k. *The standard states that @name specifies the unique name of the hierarchy.*

Office assumes that @name specifies the member unique name of the OLAP member being displayed.

2.1.806 Part 4 Section 3.10.1.63, pageFields (Page Field Items)

a. *The standard states that the maxOccurs value for the pageField child element is unbounded.*

Excel limits the occurrences of this element to 256.

2.1.807 Part 4 Section 3.10.1.64, pageItem (Page Item)

a. *The standard does not define a length restriction on the name attribute.*

Office limits the name attribute to 255 or fewer characters when pivotCacheDefinition@createdVersion is less than 3, otherwise to 32767 or fewer characters.

2.1.808 Part 4 Section 3.10.1.67, pivotCacheDefinition (PivotCache Definition)

a. *The standard doesn't specify maxLength for @refreshedBy.*

In Office the maxLength for @refreshedBy is 255.

b. *The standard doesn't specify any restrictions for @backgroundQuery.*

In Office @backgroundQuery shall be 0 for non-external data sources.

c. *The standard states that on and off are valid values of the backgroundQuery attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

d. *The standard states that on and off are valid values of the enableRefresh attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

e. *The standard states that on and off are valid values of the invalid attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

f. *The standard states that on and off are valid values of the optimizeMemory attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

g. *The standard states that on and off are valid values of the saveData attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

h. *The standard states that on and off are valid values of the upgradeOnRefresh attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

i. *The standard states that on and off are valid values of the tupleCache attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

j. *The standard does not specify any restrictions for the optimizeMemory attribute.*

In Office, the optimizeMemory attribute must be 0 or false for non-external and non-ODBC data sources.

k. *The standard states that on and off are valid values of the refreshOnLoad attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

l. *The standard does not specify any restrictions for the refreshedVersion attribute.*

In Office, the refreshedVersion attribute shall not be less than the minRefreshableVersion attribute.

m. *The standard does not specify any restrictions for the id attribute □.*

In Office, the id attribute must not be empty if the saveData attribute is 1 and the invalid attribute is 0.

n. *The standard does not define application defined behavior when the missingItemsLimit attribute is not present.*

If this number is not specified, Office sets the threshold automatically based on the number of items.

o. *The standard does not define a relation between this @tupleCache and the tupleCache child element.*

In Office, if @tupleCache has a value of 0, then pivotCacheDefinition shall not contain tupleCache element.

p. *The standard does not place any restrictions on the value of the backgroundQuery attribute with respect to connection element.*

Office requires the backgroundQuery attribute match the value of background on the related connection element.

2.1.809 Part 4 Section 3.10.1.68, pivotCacheRecords (PivotCache Records)

a. *The standard does not place restrictions on the value of the count attribute.*

Office can save non-well formed XML after opening files where the count attribute is 0 and the number of child r elements is greater than 0.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.810 Part 4 Section 3.10.1.69, pivotField (PivotTable Field)

a. *The standard states that on and off are valid values of the includeNewItemInFilter attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

b. *The standard does not specify behavior if @axis is not present.*

Office specifies if @axis is not present, the field does not appear in the row, column or page regions of the PivotTable.

c. *The standard does not restrict valid values for the axis attribute.*

In Office, axisValues shall not be used for the axis attribute.

d. *The standard does not specify a default value for the numFmtId attribute.*

Excel uses a default value of 0 for this attribute.

e. *The standard does not specify a default value for the dataSourceSort attribute.*

Excel uses a default value of false for this attribute.

f. *The standard does not define the meaning of the absence of @rankBy.*

Office assumes if @rankBy is not present, this indicates that no data field will be used by AutoShow for ranking.

g. *The standard states that on and off are valid values of the allDrilled attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

h. *The standard states that on and off are valid values of the autoShow attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

i. *The standard states that on and off are valid values of the avgSubtotal attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

j. *The standard states that on and off are valid values of the compact attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

k. *The standard states that on and off are valid values of the countASubtotal attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

l. *The standard states that on and off are valid values of the countSubtotal attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

m. *The standard states that on and off are valid values of the dataField attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

n. *The standard states that on and off are valid values of the dataSourceSort attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

o. *The standard states that on and off are valid values of the defaultAttributeDrillState attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

p. *The standard states that on and off are valid values of the defaultSubtotal attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

q. *The standard states that on and off are valid values of the dragOff attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

r. *The standard states that on and off are valid values of the dragToCol attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

s. *The standard states that on and off are valid values of the dragToData attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

t. *The standard states that on and off are valid values of the dragToPage attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

u. *The standard states that on and off are valid values of the dragToRow attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

v. *The standard states that on and off are valid values of the hiddenLevel attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

w. *The standard states that on and off are valid values of the hideNewItem attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

x. *The standard states that on and off are valid values of the insertBlankRow attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

y. *The standard states that on and off are valid values of the insertPageBreak attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

z. *The standard states that on and off are valid values of the maxSubtotal attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

aa. *The standard states that on and off are valid values of the measureFilter attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

bb. *The standard states that on and off are valid values of the minSubtotal attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

cc. *The standard states that on and off are valid values of the multipleItemSelectionAllowed attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

dd. *The standard states that on and off are valid values of the nonAutoSortDefault attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

ee. *The standard states that on and off are valid values of the outline attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

ff. *The standard states that on and off are valid values of the productSubtotal attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

gg. *The standard states that on and off are valid values of the serverField attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

hh. *The standard states that on and off are valid values of the showAll attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

ii. *The standard states that on and off are valid values of the showDropDowns attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

jj. *The standard states that on and off are valid values of the showPropAsCaption attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

kk. *The standard states that on and off are valid values of the showPropCell attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

ll. *The standard states that on and off are valid values of the showPropTip attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

mm. *The standard states that on and off are valid values of the stdDevPSubtotal attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

nn. *The standard states that on and off are valid values of the stdDevSubtotal attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

oo. *The standard states that on and off are valid values of the subtotalTop attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

pp. *The standard states that on and off are valid values of the sumSubtotal attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

qq. *The standard states that on and off are valid values of the topAutoShow attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

rr. *The standard states that on and off are valid values of the varPSubtotal attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

ss. *The standard states that on and off are valid values of the varSubtotal attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

tt. *The standard does not mention any relationship between the value of the dataField attribute and dataField elements.*

Office requires that if the dataField attribute is true and this pivotTable is not an OLAP pivotTable, then there must be at least one matching dataField element on this pivotTable with an fld attribute equal to this element's index within its parent element.

uu. *The standard says that for @nonAutoSortDefault, a value of 1 or true indicates that an AutoSort operation will be applied to the field.*

In Office, a value of 1 or true indicates a simple data sort operation will be applied to the field.

vv. *The standard does not require a relationship between the axis attribute and rowFields.*

Office requires that if the axis attribute equals axisRow and this pivotTable is not an OLAP pivotTable, then there must be a field element in the rowFields collection with its x attribute set to the index of this pivotField.

ww. *The standard does not require a relationship between the axis attribute and colFields.*

Office requires that if the axis attribute equals axisCol and this pivotTable is not an OLAP pivotTable, then there must be a field element in the colFields collection with its x attribute set to the index of this pivotField.

xx. *The standard does not require a relationship between the axis attribute and pageFields.*

Office requires that if the axis attribute equals axisPage and this pivotTable is not an OLAP pivotTable, then there shall be a pageField element on this pivotTable with the fld attribute set to this pivotField's index.

yy. *The standard does not define a relationship between the dataField attribute and the cacheHierarchy element.*

Office requires that if the dataField attribute equals 1 and this is an OLAP pivotTable, then the cacheField on the associated pivotCache with the same index as this element shall exist and have a hierarchy attribute which will refer to a cacheHierarchy element with its measure attribute equal to 1.

zz. *The standard does not require a relationship between the axis attribute and cacheHierarchy.*

Office specifies if the axis attribute is present and this is an OLAP pivotTable, then the cacheField on the associated pivotCache with the same index as this element shall have a hierarchy attribute which will refer to a cacheHierarchy element with its measure attribute equal to 0.

aaa. *The standard does not limit the length of the value of the name attribute.*

Excel restricts the value of this attribute to be at most 255 characters when the createdVersion attribute on the pivotCacheDefinition element is less than 3 and 32767 characters otherwise.

bbb. *The standard does not limit the length of the value of the subtotalCaption attribute.*

Excel restricts the value of this attribute to be at most 255 characters when the createdVersion attribute on the pivotCacheDefinition element is less than 3 and 32767 characters otherwise.

ccc. *The standard does not limit the length of the value of the uniqueMemberProperty attribute.*

Excel restricts the value of this attribute to be at most 255 characters when the createdVersion attribute on the pivotCacheDefinition element is less than 3 and 32767 characters otherwise.

ddd. *The standard does not place a uniqueness restriction on the value of @name.*

Office requires @name to be unique for non-OLAP PivotTables.

eee. *The standard does not place any restrictions on the relationship between the serverField attribute and the cacheField and pivotCache elements.*

Excel requires that the value of the serverField attribute on the cacheField element be 1 and the value of the type attribute on the associated pivotCache element be external when the value of the serverField attribute on this element is true.

fff. *The standard does not mention that if autoShow is true, there are range limitations on itemPageCount.*

In Excel, the itemPageCount attribute must be between 1 and 255 inclusive or the rankBy attribute must be greater than or equal to 0 and less than the number of dataField elements.

ggg. *The standard does not specify restrictions for the hideNewItems attribute.*

Office specifies that the hideNewItems attribute shall be false for non-OLAP pivotTables.

hhh. *The standard does not specify restrictions for the showPropAsCaption attribute.*

Office specifies that the showPropAsCaption attribute shall be false for non-OLAP pivotTables.

iii. *The standard does not specify restrictions for the showPropCell attribute.*

Office specifies that the showPropCell attribute shall be false for non-OLAP tables.

jjj. *The standard does not specify restrictions for the showPropTip attribute.*

Office specifies that the showPropTip attribute shall be false for non-OLAP pivotTables.

kkk. *The standard does not specify restrictions for the showAll attribute.*

Office specifies that the showAll attribute shall be false for OLAP pivotTables.

lll. *The standard does not specify restrictions on @dataSourceSort.*

Office specifies that @dataSourceSort shall not be 1 on a non-OLAP PivotTable.

mmm. *The standard describes @hiddenLevel as a PivotTable wide attribute.*

Office assumes @hiddenLevel refers to the particular level of this PivotField.

nnn. *The standard specifies that a @dataField value of 0 or false indicates this field appears in another region of the PivotTable.*

Office assumes a @dataField value of 0 or false indicates this field does not appear in the data region of the PivotTable.

ooo. *The standard states that @itemPageCount is the number of items showed per page in the PivotTable.*

In Office, specifies @itemPageCount is the number of items to show when the PivotTable's Autoshow feature is enabled.

ppp. *The standard specifies the subtotalCaption attribute as text.*

Office will replace the ? character in this attribute with the field name when displayed in the UI.

qqq. *The standard states that a value of 0 or false for @serverField indicates that this is a local page field.*

In Office, assumes value of 0 or false indicates that this is not a server-based page field and the @axis can be any valid value.

rrr. *The standard does not state when @dragToData is used.*

Office ignores @dragToData for OLAP PivotTables.

sss. *The standard does not state when @dragToRow is used.*

Office ignores @dragToRow for OLAP PivotTables.

ttt. *The standard does not state when @dragToCol is used.*

Office ignores @dragToCol for OLAP PivotTables.

uuu. *The standard does state when @dragToPage will be used.*

In Office, @dragToPage is ignored for OLAP PivotTables.

vvv. *The standard does not require a corresponding item element when the avgSubtotal is true.*

In Office, if avgSubtotal is true, then this element's items collection must contain an item element with t="avg".

www. *The standard does not require a corresponding item element when the countASubtotal is true.*

In Office, if countASubtotal is true, then this element's items collection must contain an item element with t="countA".

xxx. *The standard does not require a corresponding item element when @countSubtotal is true.*

In Office if @countSubtotal is true, then this element's items collection must contain an item element with t="count".

yyy. *The standard does not require a corresponding item element when the maxSubtotal is true.*

In Office, if maxSubtotal is true, then this element's items collection must contain an item element with t="max".

zzz. *The standard does not require a corresponding item element when the minSubtotal is true.*

In Office, if minSubtotal is true, then this element's items collection must contain an item element with t="min".

aaaa. *The standard does not require a corresponding item element when the productSubtotal is true.*

In Office, if productSubtotal is true, then this element's items collection must contain an item element with t="product".

bbbb. *The standard does not require a corresponding item element when the stdDevPSubtotal is true.*

In Office, if stdDevPSubtotal is true, then this element's items collection must contain an item element with t="stdDevP".

cccc. *The standard does not require a corresponding item element when the stdDevSubtotal is true.*

In Office, if stdDevSubtotal is true, then this element's items collection must contain an item element with t="stdDev".

dddd. *The standard does not require a corresponding item element when the sumSubtotal is true.*

In Office, if sumSubtotal is true, then this element's items collection must contain an item element with t="sum".

eeee. *The standard does not require a corresponding item element when the varPSubtotal is true.*

In Office, if varPSubtotal is true, then this element's items collection must contain an item element with t="varP".

ffff. *The standard does not require a corresponding item element when the varSubtotal is true.*

In Office, if varSubtotal is true, then this element's items collection must contain an item element with t="var".

gggg. *The standard does not require a corresponding item element when the defaultSubtotal is false.*

In Office, if defaultSubtotal is true or not written, then this element's items collection must contain an item element with t="default".

hhhh. *The standard does not state any requirements on the type of PivotTable for which @uniqueMemberProperty is valid.*

Office requires that this attribute is only set on OLAP PivotTables.

iiii. *The standard does not restrict the usage of the includeNewItemsInFilter attribute.*

Office assumes the includeNewItemsInFilter attribute shall be ignored for OLAP PivotTables.

jjjj. *The standard states that @showPropTip determines if a tooltip is shown for a PivotTable cell.*

In Office the value of mp@showTip, if present, takes precedence over @showPropTip.

kkkk. *The standard states that @showPropCell determines if a tooltip is shown for a PivotTable cell.*

In Office the value of mp@showCell, if present, takes precedence over @showPropCell.

2.1.811 Part 4 Section 3.10.1.70, pivotFields (PivotTable Fields)

a. *The standard does not specify a limit on the number of pivotField child elements.*

In Office, if this PivotTable is an OLAP PivotTable, then the number of pivotField elements must be less than or equal to the number of cacheField elements on the associated cache. Otherwise they must be equal.

2.1.812 Part 4 Section 3.10.1.71, pivotHierarchies (PivotTable OLAP Hierarchies)

a. *The standard does not mention limitations on the number of child elements.*

Office requires that the number of child elements must be the same as the number of cacheHierarchy elements plus the number of kpi elements in the PivotCacheDefinition associated with this PivotTable.

2.1.813 Part 4 Section 3.10.1.72, pivotHierarchy (OLAP Hierarchy)

a. *The standard specifies @includeNewItemInFilter value of 1 indicates the application will show only items the user has selected; all other items will be hidden.*

Specification of the includeNewItemInFilter attribute applies to **member** elements in the **members** children (there can be more than 1 **members** under **pivotHierarchy**) of this element and **item** elements, which have *s* equal to 1 or *true* and which are in **pivotField** element associated with this **pivotHierarchy** by the **fieldsUsage** element of the **cacheHierarchy**.

A value of 1, or true, indicates the specified **members** and **items** represent items that are excluded from the PivotTable, along with their descendants.

A value of 0, or false, indicates the specified **members** and **items** represent items that are included in the PivotTable, along with their ascendants and descendants.

b. *The standard specifies @dragToData indicates whether the user is allowed to put this hierarchy into the data area of the view.*

Office specifies @dragToData value of indicates the user can put this hierarchy into the data area of the PivotTable, subject to other constraints that may apply.

c. *The standard states that on and off are valid values of the dragOff attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

d. *The standard states that on and off are valid values of the dragToCol attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

e. *The standard states that on and off are valid values of the dragToData attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

f. *The standard states that on and off are valid values of the dragToPage attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

g. *The standard states that on and off are valid values of the dragToRow attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

h. *The standard states that on and off are valid values of the includeNewItemInFilter attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

i. *The standard states that on and off are valid values of the multipleItemSelectionAllowed attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

j. *The standard states that on and off are valid values of the outline attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

k. *The standard states that on and off are valid values of the showInFieldList attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

l. *The standard states that on and off are valid values of the subtotalTop attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

m. *The standard specifies @dragToRow indicates whether the user is allowed to put this hierarchy into the row area of the PivotTable.*

Office specifies @dragToRow value of 1 true indicates the user can put this hierarchy into the row area of the PivotTable, subject to other constraints that may apply.

n. *The standard does not specify a length limit for the caption attribute.*

Office specifies a limit of less than or equal to 65535 characters for the caption attribute.

o. *The standard specifies @dragToPage indicates whether the user is allowed to put this hierarchy into the page area of the PivotTable.*

Office specifies @dragToPage value of 1 indicates the user can put this hierarchy into the page area of the PivotTable, subject to other constraints that may apply.

p. *In the standard when @dragToCol is 0, this hierarchy cannot be removed.*

Office specifies when @dragToCol is 0 the user cannot put this hierarchy into the column area of the PivotTable. When the value is 1 the user can put this hierarchy into the column area of the PivotTable, subject to other constraints that may apply.

2.1.814 Part 4 Section 3.10.1.73, pivotTableDefinition (PivotTable Definition)

For additional notes that apply to this portion of the standard, please see the notes for [raf](#), [§3.11.1.8\(b\)](#).

a. *The standard does not specify a default value for the dataPosition attribute.*

Excel uses a default value of 0 for this attribute.

b. *The standard states that on and off are valid values of the asteriskTotals attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

c. *The standard does not define a default value for @autoFormatId.*

Office defines a default value for @autoFormatId of 1.

d. *The standard states that on and off are valid values of the colGrandTotals attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

e. *The standard states that on and off are valid values of the compact attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

f. *The standard states that on and off are valid values of the customListSort attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

g. *The standard states that on and off are valid values of the dataOnRows attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

h. *The standard states that on and off are valid values of the disableFieldList attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

i. *The standard states that on and off are valid values of the editData attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

j. *The standard states that on and off are valid values of the enableDrill attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

k. *The standard states that on and off are valid values of the enableFieldProperties attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

l. *The standard states that on and off are valid values of the enableWizard attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

- m. *The standard states that on and off are valid values of the fieldListSortAscending attribute.*
Excel does not allow these values on this attribute.
This note applies to the following products: 2007, 2007 SP1, 2007 SP2.
- n. *The standard states that on and off are valid values of the fieldPrintTitles attribute.*
Excel does not allow these values on this attribute.
This note applies to the following products: 2007, 2007 SP1, 2007 SP2.
- o. *The standard states that on and off are valid values of the gridDropZones attribute.*
Excel does not allow these values on this attribute.
This note applies to the following products: 2007, 2007 SP1, 2007 SP2.
- p. *The standard states that on and off are valid values of the immersive attribute.*
Excel does not allow these values on this attribute.
This note applies to the following products: 2007, 2007 SP1, 2007 SP2.
- q. *The standard states that on and off are valid values of the itemPrintTitles attribute.*
Excel does not allow these values on this attribute.
This note applies to the following products: 2007, 2007 SP1, 2007 SP2.
- r. *The standard describes the mdxSubqueries attribute.*
Office does not use the mdxSubqueries attribute.
- s. *The standard states that on and off are valid values of the mergeItem attribute.*
Excel does not allow these values on this attribute.
This note applies to the following products: 2007, 2007 SP1, 2007 SP2.
- t. *The standard states that on and off are valid values of the multipleFieldFilters attribute.*
Excel does not allow these values on this attribute.
This note applies to the following products: 2007, 2007 SP1, 2007 SP2.
- u. *The standard states that on and off are valid values of the outline attribute.*
Excel does not allow these values on this attribute.
This note applies to the following products: 2007, 2007 SP1, 2007 SP2.
- v. *The standard states that on and off are valid values of the outlineData attribute.*
Excel does not allow these values on this attribute.
This note applies to the following products: 2007, 2007 SP1, 2007 SP2.
- w. *The standard states that on and off are valid values of the pageOverThenDown attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

x. *The standard states that on and off are valid values of the preserveFormatting attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

y. *The standard states that on and off are valid values of the printDrill attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

z. *The standard states that on and off are valid values of the published attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

aa. *The standard states that on and off are valid values of the rowGrandTotals attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

bb. *The standard states that on and off are valid values of the showCalcMbrs attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

cc. *The standard states that on and off are valid values of the showDataDropDown attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

dd. *The standard states that on and off are valid values of the showDataTips attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

ee. *The standard states that on and off are valid values of the showDrill attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

ff. *The standard states that on and off are valid values of the showDropZones attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

gg. *The standard states that on and off are valid values of the showEmptyCol attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

hh. *The standard states that on and off are valid values of the showEmptyRow attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

ii. *The standard states that on and off are valid values of the showError attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

jj. *The standard states that on and off are valid values of the showHeaders attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

kk. *The standard states that on and off are valid values of the showItems attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

ll. *The standard states that on and off are valid values of the showMemberPropertyTips attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

mm. *The standard states that on and off are valid values of the showMissing attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

nn. *The standard states that on and off are valid values of the showMultipleLabel attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

oo. *The standard states that on and off are valid values of the subtotalHiddenItems attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

pp. *The standard states that on and off are valid values of the useAutoFormatting attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

qq. *The standard states that on and off are valid values of the visualTotals attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

rr. *The standard states for @asteriskTotals that 1 or true means that asterisks will be displayed.*

In Office, a value for @asteriskTotals of 1 or true means that asterisks will not be displayed.

ss. *The standard does not limit the length of the value of the dataCaption attribute.*

Excel restricts the value of this attribute to be at most 255 characters.

tt. *The standard does not limit the length of the value of the grandTotalCaption attribute.*

Excel restricts the value of this attribute to be at most 255 characters.

uu. *The standard does not limit the length of the value of the errorCaption attribute.*

Excel restricts the value of this attribute to be at most 255 characters.

vv. *The standard does not limit the length of the value of the missingCaption attribute.*

Excel restricts the value of this attribute to be at most 255 characters.

ww. *The standard does not limit the length of the value of the pageStyle attribute.*

Excel restricts the value of this attribute to be at most 255 characters.

xx. *The standard does not limit the length of the value of the pivotTableStyle attribute.*

Excel restricts the value of this attribute to be at most 255 characters.

yy. *The standard does not limit the length of the value of the vacatedStyle attribute.*

Excel restricts the value of this attribute to be at most 255 characters.

zz. *The standard does not limit the length of the value of the tag attribute.*

Excel restricts the value of this attribute to be at most 255 characters.

aaa. *The standard does not limit the length of the value of the rowHeaderCaption attribute.*

Excel restricts the value of this attribute to be at most 255 characters when the createdVersion attribute on the pivotTable element is less than 3 and 32767 characters otherwise.

bbb. *The standard does not limit the length of the value of the name attribute.*

Excel restricts the value of this attribute to be at most 255 characters.

ccc. *The standard says that, for @preserveFormatting, 1 or true specifies to discard formatting on refresh.*

Office interprets a value of 1 or true for @preserveFormatting to indicate the formatting will be preserved and 0 or false to indicate the formatting will be discarded.

ddd. *The standard's @subtotalHiddenItems definition refers to the data area of the pivotTable.*

Office defines @subtotalHiddenItems to indicate whether hidden items in the page area of the pivotTable are used for subtotal calculation.

eee. *The standard says that a value of 1 for @immersive means immersive is off, and that 0 means it's on.*

Office specifies a value of 1 for @immersive means that the immersive experience is left on, and a value of 0 means it's turned off.

fff. *The standard does not explain what the published attribute is used for.*

Office uses the published attribute to indicate that the PivotTable is published for display in a Web browser.

ggg. *The standard does not list valid values for the autoFormatId attribute.*

Office, in the context of pivotTableDefinition, requires that the value of the autoFormatId attribute be less than 21 or greater than 4096 and less than or equal to 4117.

hhh. *The standard does not state a default value for the applyNumberFormats attribute.*

Excel uses a default value of 0 for this attribute.

iii. *The standard does not state a default value for the applyBorderFormats attribute.*

Excel uses a default value of 0 for this attribute.

jjj. *The standard does not state a default value for the applyFontFormats attribute.*

Excel uses a default value of 0 for this attribute.

kkk. *The standard does not state a default value for the applyPatternFormats attribute.*

Excel uses a default value of 0 for this attribute.

lll. *The standard does not state a default value for the applyAlignmentFormats attribute.*

Excel uses a default value of 0 for this attribute.

mmm. *The standard does not state a default value for the applyWidthHeightFormats attribute.*

Excel uses a default value of 0 for this attribute.

nnn. *The standard does not limit the length of the value of the colHeaderCaption attribute.*

Excel restricts the value of this attribute to be at most 255 characters when the createdVersion attribute on the pivotTable element is less than 3 and 32767 characters otherwise.

ooo. *The standard does not state a maximum value for @indent.*

Office has a maximum value of 127 for @indent.

ppp. *The standard does not state how to interpret the values for @indent, or the value for no indent.*

Office assumes that @indent contains a number that is one less than the number of indent increments to apply; greater than or equal to zero and less than or equal to 127. A value of 127 indicates no indent will be used.

qqq. *The standard does not specify a maximum value for @pageWrap.*

Office allows a max value of 255 for @pageWrap.

rrr. *The standard does not define a default value for @rowHeaderCaption.*

Office assumes that if @rowHeaderCaption is not present an application specific string can be used.

sss. *The standard specifies the showEmptyCol attribute as indicating whether to include empty columns in the table.*

Office only uses the showEmptyCol attribute for OLAP PivotTables.

ttt. *The standard specifies @showEmptyRow as indicating whether to include empty rows in the table.*

Office only uses @showEmptyRow for OLAP PivotTables.

uuu. *The standard does not define when @subtotalHiddenItems should be used by an application.*

Office only uses the value of @subtotalHiddenItems for non-OLAP PivotTables.

vvv. *The standard states that page fields allow filtering of the entire PivotTable report to display data for a single item or all of the items.*

In Office, page fields allow filtering to display data for multiple items.

2.1.815 Part 4 Section 3.10.1.74, pivotTableStyleInfo (PivotTable Style)

a. *The standard defines the @showLastColumn to determine if the last column of formatting is shown.*

Office ignores this attribute.

b. *The standard does not specify a default value for the showRowHeaders attribute.*

Excel uses a default value of 0 for this attribute.

c. *The standard does not specify a default value for the showRowStripes attribute.*

Excel uses a default value of 0 for this attribute.

d. *The standard does not specify a default value for the showColStripes attribute.*

Excel uses a default value of 0 for this attribute.

e. *The standard does not specify a default value for the showColHeaders attribute.*

Excel uses a default value of 0 for this attribute.

f. *The standard states that on and off are valid values of the showColHeaders attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

g. *The standard states that on and off are valid values of the showColStripes attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

h. *The standard states that on and off are valid values of the showRowHeaders attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

- i. *The standard states that on and off are valid values of the showRowStripes attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

- j. *The standard does not limit the length of the value of the name attribute.*

Excel restricts the value of this attribute to be at most 255 characters.

2.1.816 Part 4 Section 3.10.1.75, query (Query)

- a. *The standard allows the mdx attribute to be any ST_Xstring.*

Office requires that the mdx attribute be less than 65535 characters in length.

2.1.817 Part 4 Section 3.10.1.77, r (PivotCache Record)

- a. *The standard does not specify restriction on the number of child elements.*

In Office, the number of child elements shall be equal to the number of cacheField elements with the databaseField attribute equal to 1 or true.

2.1.818 Part 4 Section 3.10.1.78, rangePr (Range Grouping Properties)

- a. *The standard states that on and off are valid values of the autoEnd attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

- b. *The standard states that on and off are valid values of the autoStart attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

- c. *The standard does not specify restrictions for @groupBy in case of parent/child relationship.*

In Office, if this rangePr is a part of a fieldGroup with a parent field, the groupBy in the rangePr of the parent must have a value that is greater than the groupBy in this rangePr.

- d. *The standard does not specify restrictions for @groupInterval.*

In Office, @groupInterval must be greater than zero; if @groupBy does not equal range, the value must be an integer less than 32768.

- e. *The standard does not specify restrictions for the @startNum and @endNum relationship.*

In Office, @startNum shall be less than @endNum.

- f. *The standard does not specify restrictions for the @startDate and @endDate relationship.*

In Office, @startDate shall be less than @endDate.

g. *The standard does not specify restrictions for the startDate attribute and startNum or endNum attribute relationships.*

In Office, the startDate attribute shall not be specified if the startNum or endNum attributes are specified.

h. *The standard does not specify restrictions for the endDate attribute and startNum or endNum attribute relationships.*

Office requires that the endDate attribute shall not be specified if the startNum or endNum attributes are specified.

i. *The standard does not specify the relationship between the groupBy attribute and the startDate and endDate attributes.*

In Office, if this value is not *range*, at least one of **startDate** or **endDate** shall be specified. Additionally, if this value is not *range* and the enclosing **cacheField** has **databaseField** equal to 1, **sharedItems** element (“[ECMA-376](#) Part 4 §3.10.1.90; sharedItems (Shared Items)”) of the enclosing **cacheField** shall have **containsDate** equal to 1 and **containsNumber** equal to 0; also, this **cacheField** shall have **containsSemiMixedTypes** equal to 0, otherwise it shall have **containsMixedTypes** equal to 0 and **containsBlank** equal to 0.

j. *In the standard no default behavior is specified for @endDate.*

If @endDate is not specified, Office uses values in the sharedItems collection of the enclosing cacheField to calculate the ending value.

k. *In the standard no default behavior is specified for @startDate.*

If @startDate is not specified, Office uses values in the sharedItems collection of the enclosing cacheField to calculate the starting value.

l. *In the standard, no default behavior is specified for the endNum attribute.*

If the endNum attribute is not specified, Office uses values in the sharedItems collection of the enclosing cacheField to calculate the ending value.

m. *In the standard, no default behavior is specified for the startNum attribute.*

If the startNum attribute is not specified, Office uses values in the sharedItems collection of the enclosing cacheField to calculate the starting value.

n. *The standard does not specify restrictions on data types for items of fields when the groupBy attribute equals range.*

Office requires that the sharedItems element of the enclosing cacheField have a containsString attribute equal to 0 and a containsMixedTypes attribute equal to 0 when the value of the groupBy attribute equals range.

o. *The standard does not place any restrictions on the value of the groupBy attribute when the value of the containsMixedType attribute on the sharedItems element of the enclosing cacheField is 1.*

Excel requires the value of the groupBy attribute to be range under this circumstance.

2.1.819 Part 4 Section 3.10.1.79, rangeSet (Range Set)

a. *The standard does not describe a relationship between the i1 attribute and the count attribute of the pages element.*

Office expects that the i1 attribute is not present when the count attribute of the pages element is less than 1; otherwise, the presence of the i1 attribute is optional.

b. *In the standard, no relationship is described between @i1 and page@count.*

Office expects @i1 to be less than page@count.

c. *The standard does not describe a relationship between the i2 attribute and the count attribute of the pages element.*

Office expects that the i2 attribute is not present when the count attribute of the pages element is less than 2; otherwise, the presence of the i2 attribute is optional.

d. *The standard does not describe a relationship between the i3 attribute and the count attribute of the pages element.*

Office expects that the i3 attribute is not present when the count attribute of the pages element is less than 3; otherwise, the presence of the i3 attribute is optional.

e. *The standard does not describe a relationship between the i4 attribute and the count attribute of the pages element.*

Office expects that the i4 attribute is not present when the count attribute of the pages element is less than 4; otherwise, the presence of the i4 attribute is optional.

f. *In the standard, no relationship is described between @i2 and page@count.*

Office expects @i2 to be less than page@count for the second page.

g. *In the standard, no relationship is described between @i3 and page@count.*

Office expects @i3 to be less than page@count for the third page.

h. *In the standard, no relationship is described between @i4 and page@count.*

Office expects @i4 to be less than page@count for the fourth page.

i. *The standard does not specify a relationship between @name and @ref.*

Office requires that @name and @ref not both be present.

j. *The standard states that the i1 attribute is optional, and specifies the index of a page field item.*

Office expects the i1 attribute to be present when the count attribute of the pages element is greater than 0.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

k. *The standard states that the i2 attribute is optional, and specifies the index of a page field item.*

Office expects the i2 attribute to be present when the count attribute of the pages element is greater than 1.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

l. *The standard states that the i3 attribute is optional, and specifies the index of a page field item.*

Office expects the i3 attribute to be present when the count attribute of the pages element is greater than 2.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

m. *The standard states that the i4 attribute is optional, and specifies the index of a page field item.*

Office expects the i4 attribute to be present when the count attribute of the pages element is greater than 3.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

n. *The standard states that the values of the sheet attribute are defined by the XML Schema string datatype.*

Office places additional restrictions on the value of the sheet attribute. This string shall not be empty and its length shall not exceed 31 characters. This string shall not begin or end with the apostrophe (0x0027) character. This string shall not contain the following characters:

Null (0x0000)

End Of Text (0x0003)

Asterisk (0x002A)

Solidus (0x002F)

Colon (0x003A)

Question Mark (0x003F)

Left Square Bracket (0x005B)

Reverse Solidus (0x005C)

Right Square Bracket (0x005D)

2.1.820 Part 4 Section 3.10.1.83, rowHierarchyUsage (Row OLAP Hierarchies)

a. *The standard does not specify that @hierarchyUsage values cannot be duplicated.*

In Office, @hierarchyUsage values may not be duplicated within a rowHierarchiesUsage.

b. *The standard says hierarchyUsage specifies the reference to an OLAP hierarchy in a PivotTable.*

In Office, @hierarchyUsage must be -2 (specifying the data hierarchy) or greater than or equal to 0 and less than the number of pivotHierarchy elements.

2.1.821 Part 4 Section 3.10.1.85, s (Character Value)

a. *The standard does not specify a default value for the u attribute.*

Excel uses a default value of false for this attribute.

b. *The standard does not specify a default value for the f attribute.*

Excel uses a default value of false for this attribute.

c. *The standard does not limit the length of the value of the c attribute.*

Excel restricts the value of this attribute to be at most 65535 characters.

d. *The standard states that on and off are valid values of the b, f, i, st, u, and un attributes.*

Excel does not allow these values on these attributes.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

e. *The standard does not define a relationship between the c attribute and the datasource type.*

In Office, the c attribute is only used with OLAP-based PivotTables. If the value of pivotCacheDefinition@createdVersion is less than 3, this value shall not be specified.

f. *The standard does not state that @cp is required in certain cases.*

Office requires that @cp shall be equal to the count of child x elements and be less than or equal to the @mappingCount of the corresponding cacheField element.

g. *The standard does not state that the presence of @cp is related to the datasource type.*

In Office, @cp is specific to OLAP-based PivotTables.

h. *The standard does not define a relationship between @cp and the parent element of s.*

In Office, @cp applies only when the parent of the s element is of type CT_SharedItems.

i. *The standard does not define a relationship between @f and the parent element of s.*

In Office, @f applies only when the parent of the s element is of type CT_SharedItems.

j. *The standard does not define a relationship between @u and the parent element of s.*

In Office, @u applies only when the parent of the s element is of type CT_SharedItems.

k. *The standard does not limit the length of the value of the v attribute.*

Excel restricts the value of this attribute to be at most 255 characters when the createdVersion attribute on the pivotCacheDefinition element is less than 3 and 32767 characters otherwise.

2.1.822 Part 4 Section 3.10.1.86, serverFormat (Server Format)

a. *The standard allows for both culture and format attributes.*

Office allows only one of culture and format attributes.

b. *The standard does not specify a maximum length for the culture attribute.*

Office has a maximum length of 31 for the culture attribute.

c. *The standard defines the format attribute to be an ST_Xstring, with no length limitations.*

Office limits the format attribute to 65535 characters.

d. *The standard does not restrict valid files to those with known language tags.*

Office does not load a file in which this attribute contains a value that it does not recognize, or is not recognized by the underlying operating system. Office recognizes the following values:

| Language | Locale | Language Tag |
|------------------|---------------|---------------------|
| Afrikaans | South Africa | af-ZA |
| Albanian | Albanian | sq-AL |
| Alsatian | France | gsw-FR |
| Amharic | Ethiopia | am-ET |
| Arabic | Algeria | ar-DZ |
| Arabic | Bahrain | ar-BH |
| Arabic | Egypt | ar-EG |
| Arabic | Iraq | ar-IQ |
| Arabic | Jordan | ar-JO |
| Arabic | Kuwait | ar-KW |
| Arabic | Lebanon | ar-LB |
| Arabic | Libya | ar-LY |
| Arabic | Morocco | ar-MA |
| Arabic | Oman | ar-OM |
| Arabic | Qatar | ar-QA |
| Arabic | Saudi Arabia | ar-SA |
| Arabic | Syria | ar-SY |
| Arabic | Tunisia | ar-TN |
| Arabic | U.A.E. | ar-AE |
| Arabic | Yemen | ar-YE |
| Armenian | Armenia | hy-AM |
| Assamese | India | as-IN |
| Azeri (Cyrillic) | Azerbaijan | az-AZ-Cyrl |
| Azeri (Latin) | Azerbaijan | az-AZ-Latn |
| Bashkir | Russia | ba-RU |
| Basque | Basque | eu-ES |
| Belarusian | Belarus | be-BY |

| Language | Locale | Language Tag |
|--------------------------|------------------------|---------------------|
| Bengali | Bangladesh | bn-BD |
| Bengali (Bengali Script) | India | bn-IN |
| Bosnian (Cyrillic) | Bosnia and Herzegovina | bs-BA-Cyrl |
| Bosnian (Latin) | Bosnia and Herzegovina | bs-BA-Latn |
| Breton | France | br-FR |
| Bulgarian | Bulgaria | bg-BG |
| Catalan | Catalan | ca-ES |
| Chinese | Hong Kong SAR | zh-HK |
| Chinese | Macao | zh-MO |
| Chinese | PRC | zh-CN |
| Chinese | Singapore | zh-SG |
| Chinese | Taiwan | zh-TW |
| Corsican | France | co-FR |
| Croatian | Croatia | hr-HR |
| Croatian (Latin) | Bosnia and Herzegovina | hr-BA-Latn |
| Czech | Czech Republic | cs-CZ |
| Danish | Denmark | da-DK |
| Dari | Afghanistan | prs-AF |
| Divehi | Maldives | div-MV |
| Dutch | Belgium | nl-BE |
| Dutch | Netherlands | nl-NL |
| English | Australia | en-AU |
| English | Belize | en-BZ |
| English | Canada | en-CA |
| English | Caribbean | en-CB |
| English | India | en-IN |
| English | Ireland | en-IE |
| English | Jamaica | en-JM |
| English | Malaysia | en-MY |
| English | New Zealand | en-NZ |

| Language | Locale | Language Tag |
|----------------------------|----------------|---------------------|
| English | Philippines | en-PH |
| English | South Africa | en-ZA |
| English | Trinidad | en-TT |
| English | United Kingdom | en-GB |
| English | United States | en-US |
| English | Zimbabwe | en-ZW |
| Estonian | Estonia | et-EE |
| Faroese | Faroe Islands | fo-FO |
| Filipino | Philippines | fil-PH |
| Finnish | Finland | fi-FI |
| French | Belgium | fr-BE |
| French | Canada | fr-CA |
| French | France | fr-FR |
| French | Luxembourg | fr-LU |
| French | Monaco | fr-MC |
| French | Switzerland | fr-CH |
| Frisian | Netherlands | fy-NL |
| Galician | Galician | gl-ES |
| Georgian | Georgia | ka-GE |
| German | Austria | de-AT |
| German | Germany | de-DE |
| German | Liechtenstein | de-LI |
| German | Luxembourg | de-LU |
| German | Switzerland | de-CH |
| Greek | Greece | el-GR |
| Greenlandic | Greenland | kl-GL |
| Gujarati (Gujarati Script) | India | gu-IN |
| Hausa (Latin) | Nigeria | ha-NG-Latn |
| Hebrew | Israel | he-IL |
| Hindi | India | hi-IN |

| Language | Locale | Language Tag |
|--------------------------|--------------------|---------------------|
| Hungarian | Hungary | hu-HU |
| Icelandic | Iceland | is-IS |
| Igbo | Nigeria | ig-NG |
| Inari Sami | Finland | smn-FI |
| Indonesian | Indonesia | id-ID |
| Inuktitut (Latin) | Canada | iu-CA-Latn |
| Inuktitut (Syllabics) | Canada | iu-CA-Cans |
| Irish | Ireland | ga-IE |
| isiXhosa / Xhosa | South Africa | xh-ZA |
| isiZulu / Zulu | South Africa | zu-ZA |
| Italian | Italy | it-IT |
| Italian | Switzerland | it-CH |
| Japanese | Japan | ja-JP |
| Kannada (Kannada Script) | India | kn-IN |
| Kazakh | Kazakhstan | kk-KZ |
| Khmer | Cambodia | kh-KH |
| K'iche | Guatemala | qut-GT |
| Kinyarwanda | Rwanda | rw-RW |
| Konkani | India | kok-IN |
| Korean | Korea | ko-KR |
| Kyrgyz | Kyrgyzstan | ky-KG |
| Lao | Lao PDR | lo-LA |
| Latvian | Latvia | lv-LV |
| Lithuanian | Lithuania | lt-LT |
| Lower Sorbian | Germany | wee-DE |
| Lule Sami | Norway | smj-NO |
| Lule Sami | Sweden | smj-SE |
| Luxembourgish | Luxembourg | lb-LU |
| Macedonian | F.Y.R.O. Macedonia | mk-MK |
| Malay | Brunei | ms-BN |

| Language | Locale | Language Tag |
|------------------------------|---------------|---------------------|
| Malay | Malaysia | ms-MY |
| Malayalam (Malayalam Script) | India | ml-IN |
| Maltese | Malta | mt-MT |
| Maori | New Zealand | mi-NZ |
| Mapudungun | Chile | arn-CL |
| Marathi | India | mr-IN |
| Mohawk | Mohawk | moh-CA |
| Mongolian (Cyrillic) | Mongolia | mn-MN |
| Mongolian (Mongolian) | PRC | mn-CN-Mong |
| Nepali | Nepal | ne-NP |
| Northern Sami | Finland | se-FI |
| Northern Sami | Norway | se-NO |
| Northern Sami | Sweden | se-SE |
| Norwegian (Bokmål) | Norway | nb-NO |
| Norwegian (Nynorsk) | Norway | nn-NO |
| Occitan | France | oc-FR |
| Oriya (Oriya Script) | India | or-IN |
| Pashto | Afghanistan | ps-AF |
| Persian | Iran | fa-IR |
| Polish | Poland | pl-PL |
| Portuguese | Brazil | pt-BR |
| Portuguese | Portugal | pt-PT |
| Punjabi (Gurmukhi Script) | India | pa-IN |
| Quechua | Bolivia | quz-BO |
| Quechua | Ecuador | quz-EC |
| Quechua | Peru | quz-PE |
| Romanian | Romania | ro-RO |
| Romansh | Switzerland | rm-CH |
| Russian | Russia | ru-RU |
| Sanskrit | India | sa-IN |

| Language | Locale | Language Tag |
|-----------------------------------|---|---------------------|
| Serbian (Cyrillic) | Bosnia and Herzegovina | sr-BA-Cyrl |
| Serbian (Cyrillic) | Republic of Serbia and Republic of Montenegro | sr-SP-Cyrl |
| Serbian (Latin) | Bosnia and Herzegovina | sr-BA-Latn |
| Serbian (Latin) | Republic of Serbia and Republic of Montenegro | sr-SP-Latn |
| Sesotho sa Leboa / Northern Sotho | South Africa | ns-ZA |
| Setswana / Tswana | South Africa | tn-ZA |
| Sinhala | Sri Lanka | si-LK |
| Skolt Sami | Finland | sms-FI |
| Slovak | Slovakia | sk-SK |
| Slovenian | Slovenia | sl-SI |
| Southern Sami | Norway | sma-NO |
| Southern Sami | Sweden | sma-SE |
| Spanish | Argentina | es-AR |
| Spanish | Bolivia | es-BO |
| Spanish | Chile | es-CL |
| Spanish | Columbia | es-CO |
| Spanish | Costa Rica | es-CR |
| Spanish | Dominican Republic | es-DO |
| Spanish | Ecuador | es-EC |
| Spanish | El Salvador | es-SV |
| Spanish | Guatemala | es-GT |
| Spanish | Honduras | es-HN |
| Spanish | Mexico | es-MX |
| Spanish | Nicaragua | es-NI |
| Spanish | Panama | es-PA |
| Spanish | Paraguay | es-PY |
| Spanish | Peru | es-PE |
| Spanish | Puerto Rico | es-PR |
| Spanish | Spain | es-ES |
| Spanish | United States | es-US |

| Language | Locale | Language Tag |
|------------------------|----------------|---------------------|
| Spanish | Uruguay | es-UY |
| Spanish | Venezuela | es-VE |
| Swahili | Kenya | sw-KE |
| Swedish | Finland | sv-FI |
| Swedish | Sweden | sv-SE |
| Syriac | Syria | syr-SY |
| Tajik (Cyrillic) | Tajikistan | tg-TJ-Cyrl |
| Tamazight (Latin) | Algeria | tmz-DZ-Latn |
| Tamil | India | ta-IN |
| Tatar | Russia | tt-RU |
| Telugu (Telugu Script) | India | te-IN |
| Thai | Thailand | th-TH |
| Tibetan | Bhutan | bo-BT |
| Tibetan | PRC | bo-CN |
| Turkish | Turkey | tr-TR |
| Turkmen | Turkmenistan | tk-TM |
| Uighur | PRC | ug-CN |
| Ukrainian | Ukraine | uk-UA |
| Upper Sorbian | Germany | wen-DE |
| Urdu | Pakistan | ur-PK |
| Uzbek (Cyrillic) | Uzbekistan | uz-UZ-Cyrl |
| Uzbek (Latin) | Uzbekistan | uz-UZ-Latn |
| Vietnamese | Viet Nam | vi-VN |
| Welsh | United Kingdom | cy-GB |
| Wolof | Senegal | wo-SN |
| Yakut | Russia | sah-RU |
| Yi | PRC | ii-CN |
| Yoruba | Nigeria | yo-NG |

2.1.823 Part 4 Section 3.10.1.88, set (OLAP Set)

a. *The standard states that the values of the count attribute are defined by the XML Schema unsignedInt datatype.*

Office requires that the count attribute be less than 2147483648 or 4294967295 when number of items in the set is unknown.

b. *The standard does not limit the length of the value of the setDefinition attribute.*

Excel restricts the value of this attribute to be at most 65535 characters.

c. *The standard states that the values of the maxRank attribute are defined by the XML Schema int datatype.*

Excel restricts the value of this attribute to be at least 0 and at most 1048576.

d. *The standard states that on and off are valid values of the queryField attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

e. *The standard does not specify a default value for the count attribute.*

Excel uses a default value of 4294967295 for this attribute.

f. *The standard says that the count attribute specifies the number of tuples in the set.*

Office assumes that this indicates the number of tuples in the resulting set rather than the tpls element.

2.1.824 Part 4 Section 3.10.1.90, sharedItems (Shared Items)

a. *In the standard @maxValue is a double.*

Office does not support the use of NaN, INF, or -INF for @maxValue.

b. *The standard states that on and off are valid values of the containsBlank attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

c. *The standard states that on and off are valid values of the containsDate attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

d. *The standard states that on and off are valid values of the containsInteger attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

e. *The standard states that on and off are valid values of the containsMixedTypes attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

f. *The standard states that on and off are valid values of the containsNonDate attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

g. *The standard states that on and off are valid values of the containsNumber attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

h. *The standard states that on and off are valid values of the containsSemiMixedTypes attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

i. *The standard states that on and off are valid values of the containsString attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

j. *The standard states that on and off are valid values of the longText attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

k. *The standard states that the values of the minValue attribute are defined by the XML Schema double datatype.*

Office does not support the use of NaN, INF, or -INF for the minValue attribute.

l. *In the standard it states that a longText attribute value of false indicates when text is less than 255 characters.*

Office interprets a longText attribute value of false to indicate when text is less than or equal to 255 characters.

m. *The standard describes when the attributes are not used in the load process.*

Office checks these restrictions for individual attributes, not on the element as a whole. Restrictions are described in detail per attribute.

n. *In the standard relationships of @containsNumber with other attributes is not explicit.*

In Office, @containsNumber shall be 1 or true when @containsInteger is specified. This value shall also be 1 or true when @minValue or @maxValue is specified.

o. *In the standard there is not an explicit order between @minValue and @maxValue.*

In Office the value of @minValue shall be less than or equal to the value of @maxValue.

p. *The standard does not defined what mixed types are for the containsMixedTypes attribute.*

In Office, the containsMixedTypes attribute assumes that boolean and error shall be considered part of the string type.

q. *The standard does not define what other values are for the containsSemiMixedTypes attribute.*

Office expects that the containsSemiMixedTypes attribute is true when the field contains text, blank, boolean or error values.

r. *The standard states that when the containsString attribute equals 1, this field contains a text value.*

In Office, boolean and error are considered strings in the context of the containsString attribute.

s. *In the standard, a value of 1 or true for the containsInteger attribute indicates this field contains integer values.*

In Office, a value of 1 or true for the containsInteger attribute indicates this field contains only integer values and does not contain non-integer numeric values.

t. *The standard does not explicitly specify relationships for the minValue attribute.*

In Office, the minValue attribute shall be present when the maxValue attribute is specified. The minValue attribute shall not be specified when the minDate or maxDate attributes are specified. If present, at least one child must be a n element.

u. *The standard does not explicitly specify relationships for @maxValue.*

In Office, @maxValue shall be present when @minValue is specified. @maxValue shall not be specified when @minDate or @maxDate are specified. If present, at least one child must be a n element.

v. *The standard does not explicitly specify relationships for @minDate.*

In Office @minDate shall be present when @maxDate is specified. @minDate shall not be present when @minValue or @maxValue are present. If present, at least one child must be a d element.

w. *The standard does not explicitly specify relationships for @maxDate.*

In Office @maxDate must be present when @minDate is specified. @maxDate shall not be present when @minValue or @maxValue are present. If present, at least one child must be a d element.

x. *The standard states that the maxOccurs value for the choice statement including the m, n, b, e, s, and d elements is unbounded.*

Excel limits the occurrences of this choice to 32500 when the createdVersion attribute on the pivotCacheDefinition element is less than 3 and 1048576 otherwise.

2.1.825 Part 4 Section 3.10.1.91, sortByTuple (Sort By Tuple)

a. *The standard does not place any restrictions the relationship between this element and the parent set.*

Excel specifies that any sort done on the parent set will consider this tuple when determining sort values.

2.1.826 Part 4 Section 3.10.1.92, tpl (Tuple)

a. *The standard does not require that @fld is mutually exclusive with @hier in a SpreadsheetML document.*

Office requires that @fld and @hier be mutually exclusive in SpreadsheetML documents.

b. *The standard does not state that @fld has restrictions beyond unsignedInt.*

Office expects that @fld is a zero-based index and shall be less than the number of items in the cacheFields collection.

c. *The standard does not place any restrictions on the value of the hier attribute.*

Office expects that the hier attribute is a zero-based index and shall be less than the number of items in the cacheHierarchies collection.

d. *The standard does not specify restrictions for the item attribute.*

If the value for the fld attribute is specified, then the value for this attribute shall be less than the number of items in the sharedItems collection, defined in sharedItems (“[\[ECMA-376\]](#) Part 4 §3.10.1.90; sharedItems (Shared Items)”).

If the value for the hier attribute is specified, then the value for this attribute shall either be equal to one of the special values 4294967294/4294967295 or it shall be less than number of items in the sets collection defined in sets (“[\[ECMA-376\]](#) Part 4 §3.10.1.89; sets (Sets)”).

The special value of 4294967294 implies that this is the all member of the hierarchy.

The special value of 4294967295 implies that this is the default member of the hierarchy.

2.1.827 Part 4 Section 3.10.1.95, worksheetSource (Worksheet PivotCache Source)

a. *The standard allows both ref and name attributes.*

Office requires one and only one of these attributes.

b. *The standard states that the id attribute contains a relationship to a sheet part.*

Office uses the id attribute to specify a relationship to an external workbook.

c. *The standard limits @name to any length string.*

In Office, @name has a limit of 255 characters, and cannot be empty.

d. *The standard limits @sheet to any length string.*

In Office, @sheet has a limit of 31 characters.

2.1.828 Part 4 Section 3.10.1.96, x (Member Property Index)

a. *The standard states the values for the v attribute are defined by the XML Schema int datatype.*

Office requires that the v attribute be greater than or equal to -1 and less than the corresponding sharedItems count. A value of -1 specifies that there is no value for this member property.

b. *The standard describes x as an array of indexes.*

Office expects that x represents an index to the cached member property value.

c. *The standard does not provide complete information on which cacheField's shared item table is indexed by @v.*

Office assumes that @v is the 0-based index into the shared items table of the member property pointed by @mpMap. The Nth @mpMap used for Nth x element (the parent of @v).

d. *The standard says @v represents an index to shared items table.*

Office specifies that if the parent of this element is i, then v shall be specified by the specification for i ("[\[ECMA-376\]](#) Part 4 §3.10.1.44; i").

2.1.829 Part 4 Section 3.10.1.97, x (Shared Items Index)

a. *The standard specifies that the x element is an array of indexes.*

Office assumes that the value of x@v is an index into the shared items collection.

b. *The standard does not place a limit on the value of @v.*

Office requires that @v shall be less than sharedItems count.

c. *The standard does not specify different restrictions for @v based on the parent element of x.*

In Office if the parent is the reference element, then restrictions of this value are defined by reference@field. If the parent is the tables element, then this value specifies the index into the table tag position in @url.

2.1.830 Part 4 Section 3.10.2.1, reference (Reference)

a. *The standard defines @field (Field Index) values range as unsignedInt and says a value of -2 indicates the data field.*

Office uses the value 4294967294 (a valid unsignedInt) to specify the data field and the @v in the x elements represent indices into the dataFields collection.

b. *The standard defines @field values range as unsignedInt.*

Office requires that if the pivotArea@cacheIndex is 0, then the value shall be a valid index in the pivotFields in the pivotTable, and, unless byPosition is 1, @v in the x elements represent indices into items collection of the pivotField.

c. *The standard states that on and off are valid values of the avgSubtotal attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

d. *The standard states that on and off are valid values of the countASubtotal attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

e. *The standard states that on and off are valid values of the countSubtotal attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

f. *The standard states that on and off are valid values of the defaultSubtotal attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

g. *The standard states that on and off are valid values of the maxSubtotal attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

h. *The standard states that on and off are valid values of the minSubtotal attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

i. *The standard states that on and off are valid values of the productSubtotal attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

j. *The standard states that on and off are valid values of the relative attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

k. *The standard states that on and off are valid values of the selected attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

l. *The standard states that on and off are valid values of the stdDevPSubtotal attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

m. *The standard states that on and off are valid values of the stdDevSubtotal attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

n. *The standard states that on and off are valid values of the sumSubtotal attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

o. *The standard states that on and off are valid values of the varPSubtotal attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

p. *The standard states that on and off are valid values of the varSubtotal attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

q. *The standard states that the values for the field attribute are defined by the XML Schema unsignedInt datatype.*

Office requires that if the pivotArea@cacheIndex is 1 the value shall be a valid index in the cacheFields in the pivot cache and the v attribute in the x elements represent indices into sharedItems collection of the cacheField.

r. *The standard states that on and off are valid values of the byPosition attribute.*

Excel does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.831 Part 4 Section 3.11.1.1, header (Header)

a. *The standard states that the values of the maxSheetId attribute are defined by the XML Schema unsignedInt datatype.*

Excel restricts the value of this attribute to be at most 32767.

b. *The standard does not limit the length of the value of the userName attribute.*

Excel restricts the value of this attribute to be at least 1 and at most 54 characters.

c. *The standard does not specify a default value for the minRId attribute.*

Excel uses a default value of 0 for this attribute.

d. *The standard does not specify a default value for the maxRId attribute.*

Excel uses the value of the minRId attribute as the default value for this attribute.

e. *The standard states that the values of the maxRId attribute are defined by the XML Schema unsignedInt datatype.*

Excel restricts the value of this attribute to be at least the value of the minRId attribute and at most 2147483647.

f. *The standard states that the values of the minRId attribute are defined by the XML Schema unsignedInt datatype.*

Excel restricts the value of this attribute to be at most 2147483647.

2.1.832 Part 4 Section 3.11.1.2, headers (Revision Headers)

a. *The standard does not specify a default value for the lastGuid attribute.*

Excel uses the value of the guid attribute as the default value of the lastGuid attribute.

b. *The standard does not place any restrictions on the value for @preserveHistory.*

Office requires that the value of @preserveHistory shall be greater than or equal to 0 and less than or equal to 32K.

c. *The standard specifies @protected is false if the tracking should not be removed, true otherwise.*

Office specifies @protected is true if the tracking should not be removed, false if it can be removed.

d. *The standard does not place any restrictions on the value for @revisionId.*

Office allows a maximum value of 2147483647.

e. *The standard does not place any restrictions on the value for the version attribute.*

Office requires that the version attribute be between 1 and 2147483647 inclusive.

f. *The standard specifies @guid to be of type ST_Guid.*

Office requires @guid to not be a null Guid ({00000000-0000-0000-0000-000000000000}).

2.1.833 Part 4 Section 3.11.1.3, nc (New Cell Data)

a. *The standard states that the values of the cm attribute are defined by the XML Schema unsignedInt datatype.*

Excel requires the value of this attribute to be 0.

b. *The standard states that the values of the s attribute are defined by the XML Schema unsignedInt datatype.*

Excel requires the value of this attribute to be 0.

c. *The standard states that the values of the ph attribute are defined by the XML Schema boolean datatype.*

Excel requires the value of this attribute to be 0 or false.

d. *The standard states that the values of the vm attribute are defined by the XML Schema unsignedInt datatype.*

Excel requires the value of this attribute to be 0.

e. *The standard states that the values of the t attribute are defined by the ST_CellType simple type.*

Excel limits the values of this attribute to be b, e, inlineStr, or n.

f. *The standard states that the r attribute is optional.*

Excel requires this attribute.

g. *The standard does not limit the length of the value of the child v element.*

Excel restricts the value of this child element to be at most 32767 characters.

h. *The standard places no restrictions on the relationship between the values of the r attributes on the oc and nc elements.*

Excel requires that the value of the r attribute on the oc element match the value of the r attribute on the nc element.

2.1.834 Part 4 Section 3.11.1.5, oc (Old Cell Data)

For additional notes that apply to this portion of the standard, please see the notes for [nc](#), [§3.11.1.3\(a-g\)](#).

2.1.835 Part 4 Section 3.11.1.7, oldFormula (Old Formula)

a. The standard states that the contents of this element are an extension on the *ST_Formula* simple type.

Excel requires the contents of this element to follow the grammar for a name formula, as defined in Name Formulas ([§3.2.3.1.4, Name Formulas](#)).

b. The standard makes no mention of an *xml:space* attribute.

Excel uses this attribute to specify, using the W3C space preservation rules, how white space should be handled for the element's contents; its allowed values are defined by the XML 1.0 specification.

2.1.836 Part 4 Section 3.11.1.8, raf (Revision AutoFormat)

For additional notes that apply to this portion of the standard, please see the notes for [pivotTableDefinition](#), [§3.10.1.73\(qgg-mmm\)](#).

a. The standard states that the values of the *sheetId* attribute are defined by the XML Schema *unsignedInt* datatype.

Excel restricts the value of this attribute to be at most 32767.

b. In the standard, *@autoformatid* is defined to be of type *unsignedInt* with no restrictions.

Office specifies that when in the context of *raf* and *queryTable* elements, the value shall be less than 21. In the context of the *pivotTableDefinition* element, the value shall be less than 21 or greater than 4096 and less than or equal to 4117.

2.1.837 Part 4 Section 3.11.1.9, rcc (Revision Cell Change)

For additional notes that apply to this portion of the standard, please see the notes for [rdn](#), [§3.11.1.13\(i,n\)](#).

a. The standard states that the values of the *sId* attribute are defined by the XML Schema *unsignedInt* datatype.

Excel restricts the value of this attribute to be at most 32767.

b. The standard does not specify a default value for the *numFmtId* attribute.

Excel uses a default value of 0 for this attribute.

c. The standard states that the *s* attribute is only applicable to undo operations.

Excel allows this attribute to be applicable to operations other than undo.

2.1.838 Part 4 Section 3.11.1.10, rcft (Revision Merge Conflict)

For additional notes that apply to this portion of the standard, please see the notes for [rdn](#), [§3.11.1.13\(i,n\)](#).

- a. *The standard defines the @sheetId without including its maximum or minimum values.*

Office specifies that @sheetId is in the range from 0 to 32767.

2.1.839 Part 4 Section 3.11.1.11, rcmt (Revision Cell Comment)

- a. *The standard specifies that @author is restricted to be of type ST_Xstring.*

Office defines that the length of @author should be between 1 and 52 inclusive.

- b. *The standard places no restrictions on the relationship between the guid attribute and a revision record.*

Office uses the guid attribute to associate a revision record with a comment in a worksheet.

2.1.840 Part 4 Section 3.11.1.13, rdn (Revision Defined Name)

- a. *The standard defines the @localSheetId without specifying a maximum value.*

Office specifies the maximum value of @localSheetId to be 32767.

- b. *The standard does not limit the length of the attribute customMenu.*

Office specifies the maximum length of @customMenu shall be 32767.

- c. *The standard does not limit the length of the oldCustomMenu attribute.*

Office specifies the maximum length of @oldCustomMenu shall be 32767.

- d. *The standard does not limit the length of the attribute description.*

Office specifies the maximum length of @description to be 32767.

- e. *The standard does not limit the length of the @oldDescription.*

Office specifies a maximum length for @oldDescription is 32767.

- f. *The standard does not limit the length of @help.*

Office specifies the maximum length of @help shall be 32767.

- g. *The standard does not limit the length of the oldHelp attribute.*

Office specifies the maximum length of @oldHelp to be 32767.

- h. *The standard does not limit the length of the statusBar attribute.*

Office specifies the maximum length of @statusBar to be 32767.

- i. *The standard does not limit the length of @oldStatusBar.*

Office specifies the maximum length of @oldStatusBar to be 32767.

- j. *The standard does not specify any restrictions on the formula in the formula element.*

Excel specifies the formula element to be a Name formula, as defined in Formulas ("[ECMA-376](#) Part 4 §3.17; Formulas").

- k. *The standard does not limit the length of the value of the comment attribute.*

Excel restricts the value of this attribute to be at most 255 characters.

l. *The standard states that the values of the name attribute are defined by the ST_Xstring simple type.*

In Office, the value of the name attribute shall be unique within the parent element collection and must match the definition of Defined Name in Formulas ("ECMA-376 Part 4 §3.17; Formulas").

m. *The standard does not limit the length of the value of the oldComment attribute.*

Excel restricts the value of this attribute to be at most 255 characters.

n. *The standard states that the values of the rId attribute are defined by the XML Schema unsignedInt datatype.*

Excel restricts the value of this attribute to be at most 2147483647.

2.1.841 Part 4 Section 3.11.1.14, reviewed (Reviewed)

a. *The standard does not place any restrictions on the value for the rId attribute.*

Office allows the rId attribute to have a maximum value of 2147483647. Revision records shall always appear in increasing order of revision record Ids within a shared workbooks part

2.1.842 Part 4 Section 3.11.1.17, rfmt (Revision Format)

a. *The standard defines the length attribute without including its maximum values.*

Office requires that the length attribute shall be less than 32767 when a part of string is affected by the change or shall be 2147483647 when all the characters of the string are affected by the change.

b. *The standard defines the @sheetId without including its maximum or minimum values.*

Office specifies that @sheetId is in the range from 0 to 32767.

c. *The standard does not describe the limits and relationships of @start.*

Office requires that either @length is 2147483647 and @start is 0 or the sum of @start and @length shall be less than 32767.

d. *The standard does not specify when @start shall be omitted.*

Office specifies @start such that start shall be omitted when a built-in or custom format is applied to the references specified by @sqref.

e. *The standard does not specify when @length is omitted.*

Office specifies that @length shall be omitted when a built-in or custom format is applied to the references specified by @sqref.

2.1.843 Part 4 Section 3.11.1.18, ris (Revision Insert Sheet)

For additional notes that apply to this portion of the standard, please see the notes for [rdn](#), [§3.11.1.13\(j,n\)](#).

a. *The standard states that the values of the sheetId attribute are defined by the XML Schema unsignedInt datatype.*

Excel restricts the value of this attribute to be at most 32767.

b. *The standard states that the values of the sheetPosition attribute are defined by the XML Schema unsignedInt datatype.*

Excel restricts the value of this attribute to be at most 65533.

c. *The standard defines the possible values for the @name without specifying the format of the value.*

Office requires that @name follows the form [Book]SheetName, where SheetName follows valid syntax for a sheet name.

2.1.844 Part 4 Section 3.11.1.19, rm (Revision Cell Move)

For additional notes that apply to this portion of the standard, please see the notes for [rdn, §3.11.1.13\(j,n\)](#).

a. *The standard includes the attribute sheetId defined as an unsignedInt.*

Office specifies that the maximum value of the sheetId attribute is 32767.

b. *The standard includes the attribute sourceSheetId defined as an unsignedInt.*

Office specifies that the maximum value of the sourceSheetId attribute is 32767.

c. *The standard does not limit the restrictions between the size of the attributes source and destination.*

Office requires that @source and @destination should be equal in width and height.

2.1.845 Part 4 Section 3.11.1.20, rqt (Revision Query Table)

a. *The standard does not place any restrictions on the value for @sheetId.*

Office requires that @version be less than or equal to 32767.

2.1.846 Part 4 Section 3.11.1.21, rrc (Revision Row Column Insert Delete)

For additional notes that apply to this portion of the standard, please see the notes for [rdn, §3.11.1.13\(j,n\)](#).

a. *The standard includes the @sId defined as an unsignedInt.*

Office specifies that the maximum length of @sId is 32767.

2.1.847 Part 4 Section 3.11.1.22, rsnm (Revision Sheet Name)

For additional notes that apply to this portion of the standard, please see the notes for [rdn, §3.11.1.13\(j,n\)](#).

a. *The standard defines the sheetId attribute without restrictions on its maximum value.*

Office specifies the maximum length of the sheetId attribute to be 32767.

b. *The standard defines @newName without any restrictions on its the form of the value.*

Office requires @newName follows the form [Book]SheetName where SheetName follows valid sheet name syntax.

c. *The standard defines @oldname without any limitations on the form of the value.*

Office requires that @oldName follow the form [Book]SheetName, where SheetName follows valid sheet name syntax.

2.1.848 Part 4 Section 3.11.1.23, sheetId (Sheet Id)

a. *The standard defines @val without restrictions on its maximum value.*

Office specifies @val has a maximum value of 65535.

2.1.849 Part 4 Section 3.11.1.24, sheetIdMap (Sheet Id Map)

a. *The standard states that the maxOccurs value for the sheetId child element is unbounded.*

Excel limits the occurrences of this element to 65535.

2.1.850 Part 4 Section 3.11.1.25, undo (Undo)

a. *The standard does not place any restrictions on the value for the sId attribute.*

Office only allows a maximum value of 32767 for the sId attribute.

b. *The standard does not place any restrictions on the existence of the array and v attributes.*

In Office, the array attribute and the v attribute are mutually exclusive. Both cannot be true at the same time.

c. *The standard defines @exp without specifying the relationships it has with other attributes.*

Office requires that when @exp equals ref or refError, then @dr should define a single cell reference.

d. *The standard does not define a relationship between the value of the nf attribute and the value of the ref3D and exp attributes.*

In Office, if the nf attribute is true, then the ref3D attribute should be false and the exp attribute should not be refError or areaError.

e. *The standard does not define a relationship between the value of the ref3D attribute and the value of the exp attribute.*

In Office, if the ref3D attribute is true, then the exp attribute should not be computedArea.

f. *The standard states that this element represents undo information for row and column deletion.*

Office uses this element to represent undo information for row and column deletion and also move operations of rows and columns.

g. *The standard states that the dn attribute is mutually exclusive with the r attribute.*

In Office, the dn attribute is mutually exclusive with the r and sId attributes.

h. *The standard places no restrictions on the index attribute.*

Office requires that the index attribute be less than the total number of expressions in the formula.

2.1.851 Part 4 Section 3.11.2.2, users (User List)

a. *The standard states that the values of the count attribute are defined by the XML Schema `unsignedInt` datatype.*

Excel restricts the value of this attribute to be at most 256.

2.1.852 Part 4 Section 3.12.1, deletedField (Deleted Field)

a. *The standard does not limit the length of the value of the name attribute.*

Excel restricts the value of this attribute to be at least 1 and at most 255 characters.

2.1.853 Part 4 Section 3.12.2, queryTable (Query Table)

For additional notes that apply to this portion of the standard, please see the notes for [pivotTableDefinition, §3.10.1.73\(ggg-mmm\)](#); [raf, §3.11.1.8\(b\)](#).

a. *The standard does not state any limitations on the value of `@firstBackgroundRefresh`.*

Office requires that if `@firstBackgroundRefresh` is true, then `@backgroundRefresh` shall also be true.

b. *The standard does not state that `@name` must be unique.*

Office requires that `@name` be unique.

c. *The standard does not state any limitations for `@connectionId`.*

Office requires `@connectionId` to be greater than 0 and must refer to a valid external data connection.

d. *The standard does not define any relationship between `@name` and defined names.*

In Office, if there is a definedName that matches this value, with any spaces within this name converted to underscores (“_”) for the purposes of this comparison, then that definedName indicates the range of this query table.

e. *The standard does not state any limitations on the value of `@removeDataOnSave`.*

Office ignores `@removeDataOnSave` if `@refreshOnLoad` is false.

f. *The standard does not place restrictions on the length of `@name`.*

Office requires that `@name` be less than 256 characters in length, and non-empty.

g. *The standard does not define any relationship between `@name` and tables.*

In Office, if this query table is related to a Table, then a definedName associated with this `@name` shall exist and shall refer to the same range the Table refers to.

2.1.854 Part 4 Section 3.12.4, queryTableField (QueryTable Field)

a. *The standard states that the `tableColumnId` attribute specifies the unique identifier for the table column if the query table is attached to a table object rather than just a range in the sheet.*

In Office, the tableColumnId attribute shall be 0 if the query table is attached to a range in the sheet.

b. *The standard states the possible values for the name attribute are defined by ST_Xstring simple type.*

Office requires that the name attribute is a string 0-255 characters in length.

c. *The standard states no restrictions on value of the clipped attribute are stated.*

Office requires that if the clipped attribute is true, the dataBound attribute shall also be true.

d. *The standard states no limitations on @fillFormulas.*

Office requires that if @fillFormulas is true, @dataBound shall also be false.

e. *The standard states no limitations on @rowNumbers.*

Office requires that if @rowNumbers is true, @dataBound shall also be true.

2.1.855 Part 4 Section 3.12.6, queryTableRefresh (QueryTable Refresh Information)

a. *The standard does not restrict @unboundColumnsLeft.*

Office requires that @unboundColumnsLeft shall be less than 16384.

b. *The standard does not restrict @unboundColumnsRight.*

Office requires that @unboundColumnsRight shall be less than 16384.

c. *The standard states that the possible values for @nextId are defined by the XML Schema unsignedInt datatype.*

Office has an additional restriction on @nextId requiring that the maximum value cannot be larger than 65535.

d. *The standard states that @fieldWrappedId indicates whether @nextId wrapped around.*

Office requires that if @fieldWrappedId is false, then all id values on the queryTableField elements within the queryTableFields collection will be less than @nextId.

e. *The standard does not state any restrictions on the value of @minimumVersion.*

Office requires @minimumVersion be 0-31 inclusive.

2.1.856 Part 4 Section 3.13.1, connection (Connection)

a. *The standard states that @deleted="true" connections can contain only the attributes name and deleted=true, all other information is removed from the SpreadsheetML file.*

Office allows other attributes to be present when @deleted is true.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

b. *The standard states that when @interval is not present, the connection is not automatically refreshed.*

In Office, @interval = 0 also indicates the connection is not automatically refreshed.

c. *The standard states that the values of the interval attribute are defined by the XML Schema unsignedInt datatype.*

Excel restricts the value of this attribute to be at most 32767.

d. *The standard does not limit the length of the value of the name attribute.*

Excel restricts the value of this attribute to be at least 1 and at most 255 characters.

e. *The standard states that the name attribute is optional.*

Excel requires this attribute.

f. *The standard defines values for @type through 8, with 8 being DSP.*

Office assumes that there are 9 possible values, and that values 8 and 9 are unused/reserved.

g. *The standard does not limit the length of the value of the description attribute.*

Excel restricts the value of this attribute to be at most 255 characters.

h. *The standard does not limit the length of the value of the singleSignIn attribute.*

Excel restricts the value of this attribute to be at most 255 characters.

i. *The standard does not limit the length of the value of the odcFile attribute.*

Excel restricts the value of this attribute to be at most 255 characters.

j. *The standard does not limit the length of the value of the sourceFile attribute.*

Excel restricts the value of this attribute to be at most 255 characters.

k. *The standard states that the type attribute is optional.*

Excel requires this attribute.

l. *The standard states that @reconnectionMethod specifies what the spreadsheet application should do when a connection fails.*

In Office, @reconnectionMethod is ignored if @onlyUseConnectionFile is set to true.

m. *The standard states that @refreshedVersion applies to connections that are used by a query table.*

In Office, @refreshedVersion is used by both pivot caches and query tables.

n. *The standard states that @minRefreshableVersion applies to connections that are used by a QueryTable.*

In Office, @minRefreshableVersion applies to both pivot caches and query tables.

o. *The standard does not place restrictions on when the saveData attribute is used.*

Office only uses the saveData attribute for query tables. It is ignored for PivotTables. When the saveData attribute is false, the refreshFileOnLoad attribute must be true.

p. *The standard states that @type=3 denotes a file based database source.*

Office does not use the value 3 for @type.

2.1.857 Part 4 Section 3.13.3, dbPr (Database Properties)

a. *The standard does not limit the length of the value of the connection attribute.*

Excel restricts the value of this attribute to be at most 65535 characters.

2.1.858 Part 4 Section 3.13.5, olapPr (OLAP Properties)

a. *The standard states that the localConnection attribute is used when the local attribute is set to true.*

Office requires the localConnection attribute if the local attribute equals true.

b. *The standard does not place restrictions on the value of @rowDrillCount.*

Office limits the value of @rowDrillCount to 1 through 1048576 inclusive.

2.1.859 Part 4 Section 3.13.6, parameter (Parameter Properties)

a. *The standard states that @cell is restricted to be of type ST_Xstring.*

Office requires that @cell be restricted to be of type ST_Formula and not be empty.

b. *The standard does not place any restrictions on the length of the value for @name.*

Office requires that @name be less or equal to 255 characters in length.

c. *The standard does not place any length restrictions on @string.*

Office limits @string length to 255 characters.

d. *In the standard, there is no relation between the cell attribute and the parameterType attribute .*

Office requires that the cell attribute be specified when the parameterType attribute equals cell.

e. *The standard does not place any restrictions on the length of the value for @prompt.*

Office specifies @prompt length limit to be 65535.

2.1.860 Part 4 Section 3.13.8, s (Character Value)

a. *The standard says this element is used to specify an HTML table to import by name.*

In Office, the element is used to specify an HTML table to import when it is a child of tables.

b. *The standard says @v is used as the name of the HTML table.*

In Office, when the element is a child of tables, @v is used as the name of the HTML table. When the element is a child of metadataStrings, @v is used to hold an element in the metadata string store.

c. *In the standard, @v does not have a size restriction.*

In Office, when the element is a child of tables, @v has a maximum length of 255 characters. When the element is a child of metadataStrings, @v has a maximum length of 65535 characters.

2.1.861 Part 4 Section 3.13.10, textField (Text Import Field Settings)

a. *The standard does not indicate relationships between the position attributes of textField elements of the collection.*

In Office, subsequent textField elements shall have position values greater than or equal to the preceding elements.

b. *The standard states that the values of the position attribute are defined by the XML Schema unsignedInt datatype.*

In Office, the range for the position attribute is between 0 and 2147483647 inclusive.

2.1.862 Part 4 Section 3.13.11, textFields (Fields)

a. *The standard states that the maxOccurs value for the textField child element is unbounded.*

Office limits the occurrences of this element to 2001.

2.1.863 Part 4 Section 3.13.12, textPr (Text Import Settings)

a. *The standard places no restrictions on the relationship between the delimited attribute and the comma, delimiter, semicolon, space, and tab attributes.*

Excel will ignore the comma, delimiter, semicolon, space, and tab attributes when the value of the delimited attribute is false.

b. *The standard states that the values of the firstRow attribute are defined by the XML Schema unsignedInt datatype.*

Excel restricts the value of this attribute to be at most 2147483647.

c. *The standard states that string values of the decimal attribute are expected to be one character in length.*

Office expects string values of the decimal attribute to be one character with an ANSI value up to 255.

d. *The standard states that strings values of the thousands attribute are expected to be one character in length.*

Office expects string values of the thousands attribute to be one character with an ANSI value up to 255.

e. *The standard states that the minOccurs value for the textFields child element is 0.*

Excel requires an occurrence of this element.

f. *The standard does not limit the length of the value of the sourceFile attribute.*

Excel restricts the value of this attribute to be at least 1 and at most 218 characters.

g. *The standard places no restrictions on the relationship between the prompt attribute and the sourceFile attribute.*

Excel requires the sourceFile attribute when the value of the prompt attribute is false.

h. *The standard states that when both system and text file decimal separator is set to "," and thousands separator to period, 123,123.45 is imported as 123,123.45 (numeric).*

Office imports the value as text in this case.

i. *The standard states that the default value of the sourceFile attribute is the empty string.*

Excel does not use a default value for this attribute.

2.1.864 Part 4 Section 3.13.13, webPr (Web Query Properties)

a. *The standard describes @sourceData as a flag indicating if XML source data should be imported instead of HTML.*

Office specifies that the XML source shall be from the URL specified by WebQuerySourceHref in the HTML.

b. *The standard states that @url is may be an empty string.*

In Office @url cannot be an empty string.

c. *The standard does not state the relationship between the url, xml, and connection@deleted elements.*

In Office, if @xml= true and the @deleted of the parent connection element is false, a non-empty @url shall be specified. If @xml is false, @url shall be specified if the @deleted of the parent connection element is false and not specified otherwise.

2.1.865 Part 4 Section 3.14.1, cell (External Cell Data)

a. *The standard does not restrict @t having value s, which implies v contains a reference to a shared string table.*

In Office, @t shall not equal s.

b. *The standard does not specify how the index for the vm attribute is used.*

In Office, the vm attribute shall be a one-based index into the valueMetadata collection in the metadata part that specifies this cell's value metadata.

c. *For @r, the standard does not restrict cell reference to be within the row of the parent row element.*

For @r, Office requires that cell reference be within the row of the parent row element.

d. *The standard implies that the r attribute is optional.*

Excel requires this attribute.

2.1.866 Part 4 Section 3.14.2, ddeItem (DDE Item definition)

a. *The standard does not specify length restrictions on @name.*

Office restricts @name to not be empty and have a length less than or equal to 255 characters.

b. *That standard states that the ole attribute indicates that the DDE item uses OLE.*

In Office, the ole attribute specifies that DDE Item is used to provide the name of the data source topic. If set to true, the value of name should be StdDocumentName.

2.1.867 Part 4 Section 3.14.4, ddeLink (DDE Connection)

- a. *The standard does not specify length limits on @ddeService.*

Office enforces a minimum of 1 character and a maximum of 255 characters for @ddeService.

- b. *The standard does not specify length limits on the ddeTopic attribute.*

Office restricts the ddeTopic attribute to 255 characters.

- c. *The standard does not place a restriction on the maximum length of the ddeService attribute concatenated with the ddeTopic attribute.*

Office requires that the combined length of the ddeService and ddeTopic attributes be less than 255.

- d. *The standard does not place restrictions on the inclusion of '[' or ']' in the ddeService and ddeTopic attributes.*

Office requires that the concatenation of the ddeService attribute followed by the ddeTopic attribute contain at most one pair of square brackets ('[' and ']'), and that the opening bracket precede the closing bracket.

2.1.868 Part 4 Section 3.14.5, definedName (Defined Name)

- a. *The standard does not specify the maximum length for @name.*

Office limits the possible values of @name to be defined names as defined in Names ("[ECMA-376](#) Part 4 §3.17.2.5; Names").

- b. *In the standard the refersTo attribute uses the ST_Xstring type.*

Office requires @referTo to be a valid formula that is restricted to cell references within the same external book.

- c. *The standard does not specify the range of the sheetId attribute.*

Office restricts the sheetID attribute to a minimum value of greater than or equal to 0 and less than or equal to 65533.

2.1.869 Part 4 Section 3.14.8, externalLink (External Reference)

- a. *The standard states that the extLst child element is mutually exclusive with the externalBook, ddeLink, and oleLink child elements.*

Excel allows an extLst child element to follow an externalBook, ddeLink, or oleLink child element.

- b. *The standard states that externalList element can be empty.*

Excel requires that an externalList element must contain one of externalBook, ddeLink, or oleLink.

2.1.870 Part 4 Section 3.14.9, oleItem (OLE Link Item)

- a. *The standard does not specify the length limit of the name attribute.*

Office limits the name attribute length to between 0 and 255 characters inclusive.

- b. *The standard specifies that the value of the name attribute is ST_XString.*

Office will not open files with the name attribute length equal to zero.

2.1.871 Part 4 Section 3.14.11, oleLink (OLE Link)

- a. *The standard does not specify a limit for the @progId string.*

Office limits the @progId string to a minimum of 1 and a maximum of 255.

- b. *The standard indicates that @progId has a maximum length of 255 according to ST_Xstring255.*

In Office, @progId and the referenced target in the corresponding relationships part have a maximum combined length of 254.

2.1.872 Part 4 Section 3.14.12, row (Row)

- a. *The standard does not place any restrictions on the value for @row.*

Office requires that the value of @row be less than or equal to 1048576.

2.1.873 Part 4 Section 3.14.13, sheetData (External Sheet Data Set)

- a. *The standard states that @sheetId index is an unsigned integer, with no additional restrictions on value, and that it is 1-based.*

Office requires that @sheetId range from 0 through 65533 inclusive.

- b. *The standard does not define any order requirements for rows.*

In Office, rows must appear in ascending order.

2.1.874 Part 4 Section 3.14.15, sheetName (Sheet Name)

- a. *The standard indicates that @val is a string of unbounded length.*

Office generally expects that @val has a maximum length of 31 characters and enforces this limit on load. On save, in some circumstances, up to 252 characters can be saved for @val.

2.1.875 Part 4 Section 3.14.16, sheetNames (Supporting Workbook Sheet Names)

- a. *The standard states that the maxOccurs value for the sheetName child element is unbounded.*

Excel limits the occurrences of this element to 65534.

2.1.876 Part 4 Section 3.14.17, val (DDE Link Value)

- a. *The standard does not limit the length of the value of this element.*

Excel restricts the value of this element to be at most 32767 characters.

- b. *The standard makes no mention of an xml:space attribute.*

Excel uses this attribute to specify, using the W3C space preservation rules, how white space should be handled for the element's contents; its allowed values are defined by the XML 1.0 specification.

2.1.877 Part 4 Section 3.14.18, value (Value)

- a. *The standard does not give length restriction for the val element.*

In Office, the val element has a maximum length of 32767 characters.

2.1.878 Part 4 Section 3.14.19, values (DDE Name Values)

- a. *The standard allows the cols attribute to be unbounded.*

Excel limits the value to be in the range 1 to 16384 inclusive.

- b. *The standard allows the rows attribute to be unbounded.*

Excel limits the value to be in the range 1 to 1048576, inclusive.

- c. *The standard does not specify the relationship of the value elements to the cols and rows attributes.*

Excel requires that the number of value elements must be equal to rows times cols and that value elements appear in row-major order.

2.1.879 Part 4 Section 3.15.1, main (Main)

- a. *The standard does not limit the length of the value of the first attribute.*

Excel restricts the value of this attribute to be at least 1 and at most 255 characters.

2.1.880 Part 4 Section 3.15.2, stp (Strings in Subtopic)

- a. *The standard does not limit the length of the value of this element.*

Excel restricts the value of this element to be at most 255 characters.

- b. *The standard describes 1 for stp for cube functions only.*

In Office, a value of 0 for the first stp indicates that not all of the related cells with calling cube functions have been refreshed. For each Cube function, there shall be exactly one stp.

- c. *The standard makes no mention of an xml:space attribute.*

Excel uses this attribute to specify, using the W3C space preservation rules, how white space should be handled for the element's contents; its allowed values are defined by the XML 1.0 specification.

- d. *The standard does not describe how stp relates to the RTD function.*

In Office, for the RTD function, the first stp having a value of "" indicates that the RTP add-in is run on the local machine. Any other value for the stp indicates the server name. All subsequent stps indicate the topics of the RTD function.

2.1.881 Part 4 Section 3.15.3, tp (Topic)

For additional notes that apply to this portion of the standard, please see the notes for [v. §3.3.1.93\(c\)](#).

- a. *The standard does not specify a length restriction for the v element.*

In Excel, the v element must not be more than 32767 characters long.

2.1.882 Part 4 Section 3.15.4, tr (References)

a. *The standard states that the values of the s attribute are defined by the XML Schema unsignedInt datatype.*

Excel restricts the value of this attribute to be at least 1 and at most 65534.

2.1.883 Part 4 Section 3.16.1, DataBinding (XML Mapping)

a. *The standard does not specify a default value for the FileBinding attribute.*

Excel uses a default value of false for this attribute.

b. *The standard does not say that @ConnectionID is equal to @id in one of collection elements.*

In Office, @ConnectionID must be equal to @id in one of collection elements.

c. *The standard does not indicate any restrictions for the attribute @ConnectionID.*

In Office, @ConnectionID shall be specified if @FileBinding is true, it shall not be specified if @FileBinding is false.

d. *The standard does not limit the length of the value of the DataBindingName attribute.*

Excel restricts the value of this attribute to be at most 65535 characters.

e. *The standard does not limit the length of the value of the FileBindingName attribute.*

Excel restricts the value of this attribute to be at most 65535 characters.

f. *The standard states that the values of the FileBinding attribute are defined by the XML Schema boolean datatype.*

Excel restricts the value of this attribute to be true or false.

g. *The standard states that the values of the ConnectionID attribute are defined by the XML Schema unsignedInt datatype.*

Excel restricts the value of this attribute to be at most 2147483647.

h. *The standard does not specify a minOccurs value for the any element.*

Excel sets this value to be 0.

i. *The standard places no restrictions on the relationship between the FileBindingName attribute and the FileBinding attribute.*

Excel requires that the value of the FileBindingName attribute not be specified if the FileBinding attribute is false.

2.1.884 Part 4 Section 3.16.2, Map (XML Mapping Properties)

a. *The standard indicates that @Append type is xsd:boolean.*

Office requires @Append to be true or false (not 1/0).

b. *The standard indicates that @ShowImportExportValidationErrors type is xsd:boolean.*

Office requires @ShowImportExportValidationErrors to be true or false (not 1/0).

c. *The standard states that the values of the AutoFit attribute are defined by the XML Schema boolean datatype.*

Excel restricts the value of this attribute to be true or false.

d. *The standard indicates that @PreserveSortAFLayout type is xsd:boolean.*

Office requires @PreserveSortAFLayout to be true or false (not 1/0).

e. *The standard indicates that @PreserveFormat type is xsd:boolean.*

Office requires @PreserveFormat to be true or false (not 1/0).

f. *The standard does not specify a maximum length restriction for the name attribute.*

Office limits the name attribute length to less than 65536 characters.

g. *The standard does not specify a maximum length restriction for @RootElement.*

Office limits @RootElement to less than 65536 characters.

h. *The standard does not specify a maximum for @ID.*

Office limits @ID to be less than 2147483648 and greater than 0.

2.1.885 Part 4 Section 3.16.4, Schema (XML Schema)

a. *The standard does not limit the length of the value of the ID attribute.*

Excel restricts the value of this attribute to be at most 65535 characters.

b. *The standard does not limit the length of the value of the SchemaRef attribute.*

Excel restricts the value of this attribute to be at most 65535 characters.

c. *The standard does not limit the length of the value of the Namespace attribute.*

Excel restricts the value of this attribute to be at most 65535 characters.

d. *The standard does not specify a minOccurs value for the any element.*

Excel sets this value to be 0.

2.1.886 Part 4 Section 3.17, Formulas

a. *The standard does not specify structure references.*

Office has special restrictions on structure references as defined in Structure References ([§3.2.3.1.1, Structure References](#)).

b. *The standard does not specify conditional formatting formulas.*

Office has special restrictions on conditional formatting formulas as defined in Conditional Formatting Formulas ([§3.2.3.1.2, Conditional Formatting Formulas](#)).

c. *The standard does not specify data validation formulas.*

Office has special restrictions on data validation formulas as defined in Data Validation Formulas ([§3.2.3.1.3, Data Validation Formulas](#)).

d. *The standard does not specify name formulas.*

Office has special restrictions on name formulas as defined in Name Formulas ([§3.2.3.1.4, Name Formulas](#)).

e. *The standard does not specify pivot formulas.*

Office has special restrictions on pivot formulas as defined in Pivot Formulas ([§3.2.3.1.8, Pivot Formulas](#)).

f. *The standard does not specify chart formulas.*

Office has special restrictions on chart formulas as defined in Chart Formulas ([§3.2.3.1.6, Chart formulas](#)).

g. *The standard does not specify R1C1 formulas.*

Office has special restrictions on R1C1 formulas as defined in R1C1 Formulas ([§3.2.3.1.7, R1C1 formulas](#)).

h. *The standard does not specify external name formulas.*

Office has special restrictions on external name formulas as defined in External Name Formulas ([§3.2.3.1.5, External Name Formulas](#)).

i. *The standard does not specify OLE Link formulas.*

Office has special restrictions on OLE Link formulas as defined in OLE Link Formulas ([§3.2.3.1.9, OLE Link Formulas](#)).

2.1.887 Part 4 Section 3.17.2, Syntax

a. *The standard does not specify the EBNF standard used to describe formula.*

Office defines the syntax rules in this subclause follow the system shown in ISO/IEC 14977: literal text is surrounded by double-quotes (or by apostrophes); the left-square-bracket and right-square-bracket designate the start and end of an option; the left-curly-bracket and right-curly-bracket designate the start and end of an sequence of zero-or-more items; the vertical-line indicates an alternative; and each rule ends with a semicolon. Whenever hyphen is used as the exception-symbol (as per ISO/IEC 14977), it is surrounded by white space, and further clarified by a comment.

b. *The standard does not specify the set of productions for formula using EBNF.*

Office writes the productions for formula using the following EBNF:

```
formula=
  expression ;
expression= {space}, nospace-expression, {space};
nospace-expression=
  "(" , expression , ")" |
  constant |
  prefix-operator , expression |
  expression , infix-operator , expression |
```

```
expression, postfix-operator |
cell-reference |
function-call |
name-reference |
structure-reference ;
```

c. *The standard does not state that structured referencing in formulas is allowed.*

Office allows structured referencing in formulas.

d. *The standard provides a rather loose definition of value space for arithmetic terms in an expression.*

Excel uses IEC 60559's double precision, excluding denormalized numbers.

e. *The standard does not define how behavior of range values differ between array formulas and normal formulas.*

In Office, the way in which input ranges are interpreted and output values are understood to relate to cells sharing the formula may mean one of two things based on whether the formula was an array formula or not.

For an array-entered formula: All range arguments are interpreted to be their full range. If the result of the formula is an array, the values of the array are meant to be returned across all of the cells in the sheet sharing the formula. (When the size of the range for an array formula exceeds in either dimension the size of the returned array, the excess cells take on a value of #N/A.)

For a normal (non-array) formula:

Implicit intersection is performed on all arguments to functions except for those that allow a range.

If the formula results in an array, only the first value from the array is returned to the cell.

In Office, if implicit intersection cannot be performed, #VALUE! is returned to the cell.

Implicit intersection is determined as follows: When a range is passed to a function which expects only a single cell, a test is made to discover whether the calling cell intersects that range at any point horizontally or vertically. If it does, the cell at the point of intersection is passed to the function. [Example: The formula ABS(B1:B3) is entered into A2. Because the ABS function does not expect a range, implicit intersection is performed. A2 intersects B1:B3 horizontally on row 2, and so the value in B2 is passed into the function. end example]

f. *The standard does specify which function's arguments can be a range.*

Office defines the list of function arguments that allow a range is as follows:

ACCRINT - all arguments

ACCRINTM - all arguments

AMORDEGRC - all arguments

AMORLINC - all arguments

AND - all arguments
AREAS - reference argument
AVEDEV - all arguments
AVERAGE - all arguments
AVERAGEA - all arguments
AVERAGEIF - all arguments except for criteria
AVERAGEIFS - all arguments except for criteria1, criteria2, and so on.
BESSELI - all arguments
BESSELJ - all arguments
BESSELK - all arguments
BESSELY - all arguments
BIN2DEC - all arguments
BIN2HEX - all arguments
BIN2OCT - all arguments
CHOOSE - all arguments except index
COLUMN - all arguments
COLUMNS - all arguments
COMPLEX - all arguments
CONVERT - all arguments
COUNT - all arguments
COUNTA - all arguments
COUNTBLANK - all arguments
COUNTIF - all arguments except criteria
COUNTIFS - all arguments except for criteria1, criteria2, and so on.
COUPDAYBS- all arguments
COUPDAYS - all arguments
COUPDAYSNC - all arguments
COUPNCD - all arguments
COUPNUM - all arguments
COUPPCD - all arguments

CUBEMEMBER - member-expression
CUBESET - set-expression
CUBEVALUE - all except connection
CUMIPMT - all arguments
CUMPRINC - all arguments
DAVERAGE - all arguments
DCOUNT - all arguments
DCOUNTA - all arguments
DEC2BIN - all arguments
DEC2HEX - all arguments
DEC2OCT - all arguments
DELTA - all arguments
DEVSQ - all arguments
DGET - all arguments
DISC - all arguments
DMAX - all arguments
DMIN - all arguments
DOLLARDE - all arguments
DOLLARFR - all arguments
DPRODUCT - all arguments
DSTDEV - all arguments
DSTDEVP - all arguments
DSUM - all arguments
DURATION - all arguments
DVAR - all arguments
DVARP - all arguments
EDATE - all arguments
EFFECT - all arguments
EOMONTH - all arguments
ERF - all arguments

ERFC - all arguments
FACTDOUBLE - all arguments
FREQUENCY - all arguments
FVSCHEDULE - schedule argument
GCD - all arguments
GEOMEAN - all arguments
GESTEP - all arguments
GETPIVOTDATA - data-field, pivot-table, field-1, and item-1 arguments
GROWTH - all arguments
HARMEAN - all arguments
HEX2BIN - all arguments
HEX2DEC - all arguments
HEX2OCT - all arguments
HLOOKUP - all arguments
IFERROR - value-if-error argument
IMABS - all arguments
IMAGINARY - all arguments
IMARGUMENT - all arguments
IMCONJUGATE - all arguments
IMCOS - all arguments
IMDIV - all arguments
IMEXP - all arguments
IMLN - all arguments
IMLOG10 - all arguments
IMLOG2 - all arguments
IMPOWER - all arguments
IMPRODUCT - all arguments
IMREAL - all arguments
IMSIN - all arguments
IMSQRT - all arguments

IMSUB - all arguments
IMSUM - all arguments
INDEX - array or reference argument
INTRATE - all arguments
IRR - values argument
ISEVEN - all arguments
ISODD - all arguments
ISREF - all arguments
KURT - all arguments
LARGE - array argument
LCM - all arguments
LINEST - known-xs and known-ys arguments
LOGEST - known-xs and known-ys arguments
LOOKUP - all arguments except lookup_value
MATCH - lookup_array argument
MAX - all arguments
MAXA - all arguments
MDURATION - all arguments
MEDIAN - all arguments
MIN - all arguments
MINA - all arguments
MIRR - values argument
MROUND - all arguments
MULTINOMIAL - all arguments
N - all arguments
NETWORKDAYS - holidays argument
NOMINAL - all arguments
NPV - all arguments except rate
OCT2BIN - all arguments
OCT2DEC - all arguments

OCT2HEX - all arguments
ODDFPRICE - all arguments
ODDFYIELD - all arguments
ODDLPRICE - all arguments
ODDLYIELD - all arguments
OFFSET - reference argument
OR - all arguments
PERCENTILE - array argument
PERCENTRANK - array argument
PHONETIC - all arguments
PRICE - all arguments
PRICEDISC - all arguments
PRICEMAT - all arguments
PRODUCT - all arguments
QUARTILE - array argument
QUOTIENT - all arguments
RANDBETWEEN - all arguments
RANK - ref argument
RECEIVED - all arguments
ROW - reference argument
ROWS - array argument
SERIESSUM - all arguments
SKEW - all arguments
SMALL - array argument
SQRTPI - all arguments
STDEV - all arguments
STDEVA - all arguments
STDEVP - all arguments
STDEVPA - all arguments
SUBTOTAL - all arguments except function_num

SUM - all arguments
SUMIF - all arguments except criteria
SUMIFS - all arguments except criteria1, criteria2, and so on.
SUMSQ - all arguments
T - all arguments
TBILLEQ - all arguments
TBILLPRICE - all arguments
TBILLYIELD - all arguments
TREND - all arguments except const-flag
TRIMMEAN - array argument
VAR - all arguments
VARA - all arguments
VARP - all arguments
VARPA - all arguments
VLOOKUP - table-array argument
WEEKNUM - all arguments
WORKDAY - holidays argument
XIRR - all arguments except guess
XNPV - all arguments except rate
YEARFRAC - all arguments
YIELD - all arguments
YIELDDISC - all arguments
YIELDMAT - all arguments
ZTEST - array argument

g. *The standard does not specify what happens when implicit intersection cannot be performed.*

Office returns #VALUE! when implicit intersection cannot be performed.

2.1.888 Part 4 Section 3.17.2.1, Constants

a. *The standard does not specify the set of productions for constant using EBNF.*

Office writes the productions for constant using the following EBNF:

```
constant=
```

```

    error-constant |
    logical-constant |
    numerical-constant |
    string-constant |
    array-constant ;
error-constant=
    "#DIV/0!" | "#N/A" | "#NAME?" | "#NULL!" |
    "#NUM!" | "#REF!" | "#VALUE!" | "#GETTING_DATA";
logical-constant=
    "FALSE" | "TRUE" ;
numerical-constant=
    [neg-sign], significand-part, [exponent-part] ;
significand-part=
    whole-number-part, [fractional-part] |
    fractional-part ;
whole-number-part=
    digit-sequence;
fractional-part=
    full-stop, digit-sequence ;
exponent-part=
    exponent-character, [ sign ], digit-sequence ;
full-stop=
    "." ; (* also known as "period" *)
sign=
    "+" |
    neg-sign ;
neg-sign=
    "-";
exponent-character=
    "E" | "e" ;

digit-sequence=
    decimal-digit, {decimal-digit} ;
nonzero-digit-sequence=
    nonzero-decimal-digit, {decimal-digit} ;
decimal-digit=
    "0" | nonzero-decimal-digit ;
nonzero-decimal-digit=
    "1" | "2" | "3" | "4" |
    "5" | "6" | "7" | "8" | "9" ;

string-constant=
    double-quote, [string-chars], double-quote ;
string-chars=
    string-char, {string-char} ;
string-char=
    escaped-double-quote |
    character - double-quote ; (* any character except double-quote *)
escaped-double-quote=
    '""' ; (* consecutive double-quotes, with no space between them *)
double-quote=
    '\"' ; (* one double-quote character*)
character=
    as defined by the production Char in the XML 1.0 specification, §2.2.

```

b. *The standard does not specify the set of productions for array-constant using EBNF.*

Office writes the productions for array-constant using the following EBNF:

```

array-constant=
  "{", constant-list-rows, "}" ;
constant-list-rows=
  constant-list-row, { semicolon, constant-list-row } ;
semicolon=
  ";" ;
constant-list-row=
  constant, { comma, constant } ;

```

- c. *The standard does not list #GETTING_DATA as being saved in any formulas.*

Office saves #GETTING_DATA in formulas.

2.1.889 Part 4 Section 3.17.2.2, Operators

- a. *The standard does not specify the productions for operator using EBNF.*

Office writes the productions for operator using the following EBNF:

```

operator=
  ":" | comma | space | "^" | "*" | "/" | "+" | "-"
  | "&" | "=" | "<>" | "<" | "<=" | ">" | ">=" | "%" ;
infix-operator=
  ":" | comma | space | "^" | "*" | "/" | "+" | "-" | "&"
  | "=" | "<>" | "<" | "<=" | ">" | ">=" ;
postfix-operator=
  "%" ;
prefix-operator=
  "+" | "-";

```

- b. *The standard states that an expression with value 0 tests logically false while one with any nonzero value tests true.*

In Office, an expression with value 0 tests logically false while one with any nonzero numeric value tests true.

2.1.890 Part 4 Section 3.17.2.3, Cell References

- a. *The standard does not specify the productions for cell-reference using EBNF.*

Office writes the productions for cell-reference using the following EBNF:

```

cell-reference= external-cell-reference | A1-reference ;
external-cell-reference= sheets-prefix, A1-reference ;
book-prefix= workbook-index, "!" ;
sheets-prefix = single-sheet-prefix |
  sheet-range, "!" ;
single-sheet-prefix = single-sheet, "!" ;
single-sheet= [workbook-index] sheet-name |
  apostrophe, [workbook-index] sheet-name-special, apostrophe ;
sheet-range= [workbook-index], sheet-name, ":", sheet-name |
  apostrophe, [workbook-index] sheet-name-special, ":", sheet-name-special, apostrophe ;
workbook-index =
  "[", whole-number-part, "]" ;
sheet-name=

```

```

sheet-name-characters ;
sheet-name-characters=
  sheet-name-character, {sheet-name-character} ;
sheet-name-character=
  character - (operator | apostrophe | "[" | "]" | "\" | "?") ;
              (* any character except operator or ', [, ], \, or ? *)
apostrophe= "'" ;
space = " " ;
sheet-name-special=
  sheet-name-start-character-special,
  [ [sheet-name-characters-special], sheet-name-end-character-special] ;
sheet-name-start-character-special=
  character - (apostrophe | "*" | "[" | "]" | "\" | ":" | "/"
| "?" | ? Unicode character END OF TEXT ? ) ;
(* any character, including operator, except ', *, [, ], \, :, /, ?, or END OF TEXT *)
sheet-name-end-character-special=
  sheet-name-start-character-special ;
sheet-name-characters-special=
  sheet-name-character-special, {sheet-name-character-special} ;
sheet-name-character-special=
  apostrophe, apostrophe |
  character - (apostrophe | "*" | "[" | "]" | "\" | ":" | "/"
| "?" | ? Unicode character END OF TEXT ? ) ;
(* any character, including operator, except ', *, [, ], \, :, /, ?, or END OF TEXT *)

```

b. *The standard does not specify how external book index can be used to access a cell in external workbook.*

In Office, a nonzero index represents a reference to an external book in an external link collection.

c. *The standard refers to absolute cell reference behavior when the position of the cell containing the formula changes.*

Excel does not relate the behavior of cells during move operations to relative or absolute references.

d. *The standard states that functions which take 3D references are AVERAGE, AVERAGEA, COUNT, COUNTA, MAX, MAXA, MIN, MINA, PRODUCT, STDEV, STDEVA, STDEVP, STDEVPA, SUM, VAR, VARA, VARP, and VARPA.*

In Office, the following functions also take 3D references: AND, AVEDEV, DEVSQ, GEOMEAN, HARMEAN, KURT, MEDIAN, NPV, OR, SKEW, SUMSQ, TRIMMEAN, and ZTEST.

e. *The standard states 3-D references shall not be used in multi-cell formulas.*

In Office, 3-D references can be used in array or multi-cell formulas within the same limits as in a single-cell formula.

2.1.891 Part 4 Section 3.17.2.3.1, A1-Style Cell References

a. *The standard does not specify the productions for A1-reference using EBNF.*

Office writes the productions for A1-reference using the following EBNF:

```

A1-reference=
  A1-column, ":", A1-column |
  A1-row, ":", A1-row |
  A1-cell, ":", A1-cell |

```



```

A1-cell ;
A1-cell=
  A1-column, A1-row;
A1-column=
  A1-relative-column |
  A1-absolute-column ;
A1-relative-column=
  letter, {letter} ; (* see semantic rules for A1-Style Cell References ("[ECMA-376] Part
4 §3.17.2.3.1; A1-Style Cell References") *)
letter=
  "A"|"B"|"C"|"D"|"E"|"F"|"G"|"H"|"I"|"J"|"K"|"L"|"M" |
  "N"|"O"|"P"|"Q"|"R"|"S"|"T"|"U"|"V"|"W"|"X"|"Y"|"Z" |
  "a"|"b"|"c"|"d"|"e"|"f"|"g"|"h"|"i"|"j"|"k"|"l"|"m" |
  "n"|"o"|"p"|"q"|"r"|"s"|"t"|"u"|"v"|"w"|"x"|"y"|"z" ;
A1-absolute-column=
  "$", A1-relative-column ;
A1-row=
  A1-relative-row |
  A1-absolute-row ;
A1-relative-row=
  digit-sequence ; (* must be nonzero; see A1-Style Cell References ("[ECMA-376] Part 4
§3.17.2.3.1; A1-Style Cell References") *)
A1-absolute-row=
  "$", A1-relative-row ;

```

2.1.892 Part 4 Section 3.17.2.3.2, R1C1-Style Cell Reference

- a. *The standard does not use EBNF to specify the productions for R1C1-reference.*

Office writes the productions for R1C1-reference using the following EBNF:

```

R1C1-reference=
  R1C1-row-only |
  R1C1-column-only |
  R1C1-cell, ":", R1C1-cell |
  R1C1-cell ;
R1C1-cell=
  R1C1-row, R1C1-column ;
R1C1-row-only=
  "R", R1C1-absolute-number, |
  "R[", R1C1-relative-number, "]" ;
R1C1-row=
  R1C1-relative-row |
  R1C1-absolute-row ;
R1C1-relative-row= "R" |
  "R[", R1C1-relative-number, "]" ;
R1C1-absolute-row=
  "R", R1C1-absolute-number ;
R1C1-column-only=
  "C", R1C1-absolute-number |
  "C[", R1C1-relative-number, "]" ;
R1C1-column=
  R1C1-relative-column |
  R1C1-absolute-column ;
R1C1-relative-column= "C" |
  "C[", R1C1-relative-number, "]" ;
R1C1-absolute-column= "C", R1C1-absolute-number ;

```

```

R1C1-relative-number=
  ["-"], digit-sequence ;
R1C1-absolute-number=
  digit-sequence ; (* must be nonzero; see A1-Style Cell References ("[ECMA-376] Part 4
  §3.17.2.3.1; A1-Style Cell References") *)

```

b. *The standard states that a negative offset indicates a row to the left or a column above, and a positive offset indicates a row to the right or a column below.*

In Office, a negative offset indicates a column to the left or a row above, and a positive offset indicates a column to the right or a row below.

2.1.893 Part 4 Section 3.17.2.4, Functions

a. *The standard does not use EBNF to write the productions for function-call.*

Office writes the productions for function-call using the following EBNF:

```

function-call=
  function-name, "(", argument-list, ")" ;
function-name=
  predefined-function-name |
  user-defined-function-name ;
predefined-function-name=
  "ABS" | "ACOS" | "ACOSH"
  | ( any of the other functions defined in Predefined Function Definitions ("[ECMA-376]
  Part 4 §3.17.7; Predefined Function Definitions") ) ;
user-defined-function-name=
  name-reference ;
argument-list=
  argument, { comma, argument } ;
comma=
  "," ;
argument=
  [expression] ;

```

b. *The standard states that a function is a named formula that takes zero or more arguments, performs an operation, and, optionally, returns a result.*

In Office, a function always returns a result.

2.1.894 Part 4 Section 3.17.2.5, Names

a. *The standard does not use EBNF to write the syntax for name.*

Office writes the productions for name using the following EBNF:

```

name-reference= name |
  external-name;
external-name= single-sheet-prefix, name;
name=
  name-start-character, [ name-characters ] ;
name-start-character=
  underscore | backslash | ? any code points which are characters as defined by the
  Unicode character properties, chapter four of the Unicode Standard ?;
underscore=

```

```

"_" ;
backslash=
"\\" ;
name-characters=
  name-character, {name-character} ;
name-character=
  name-start-character | decimal-digit | full-stop | ? any code points which are digits
  as defined by the Unicode character properties, chapter four of the Unicode standard ?;

```

- b. *The standard specifies that two names that are the same in different workbooks can be disambiguated by prepending the workbook name.*

Office prefixes names used in the same context with the index of the relationship ID associated with the workbook name and an exclamation mark. A relationship ID index of 0 indicates the current workbook.

- c. *The standard does not specify that \name-character is an invalid name.*

Office will not create or load names of the form \name-character.

2.1.895 Part 4 Section 3.17.2.6, Types and Values

- a. *The standard does not specify a limit on the expression.*

In Office, if the expression is text and is greater than 32767 characters, then a consuming application shall treat this as equivalent to the error value #VALUE!.

2.1.896 Part 4 Section 3.17.3, Error values

- a. *The standard does not specify #GETTING_DATA as an error value.*

Office allows #GETTING_DATA as an error value. Reason for occurrence: Intended to indicate when value is waiting on data from an asynchronous function.

2.1.897 Part 4 Section 3.17.4.1, Date Representation

- a. *The standard states that the upper range for the 1900 and 1904 date base systems is December 31, 9999.*

Office assumes that the upper range for the 1900 and 1904 date base systems is December 31, 9999 23:59:59.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.898 Part 4 Section 3.17.5.2, Precision

- a. *The standard states that m is an integer whose absolute value is less than 2⁵³, and n is an integer between -1075 and 970, inclusive.*

Office treats m as an integer whose absolute value is greater than or equal to 2⁵² and less than 2⁵³, and n is an integer between -1074 and 971, inclusive.

- b. *The standard states in a note that the default precision is patterned after the IEEE double-precision 64-bit floating-point type.*

In Office, the default precision is patterned after the IEEE double-precision 64-bit floating-point type, with denormalized numbers excluded.

2.1.899 Part 4 Section 3.17.5.4, Interpretation

a. *The standard gives maximum value as $2^{1023} - 1$, minimum as $-2^{1023} + 1$.*

Office uses maximum $2^{1024} - 2^{971}$, minimum $-2^{1024} + 2^{971}$ and has smallest positive value of 2^{-1022} .

b. *The standard does not specify behavior if the absolute value of the raw value is smaller than the smallest positive value in the value space.*

In Office, if the absolute value of the raw value is smaller than the smallest positive value in the value space, then a consuming application shall treat this as equivalent to 0.

2.1.900 Part 4 Section 3.17.6.3, Array Formulas

a. *The standard refers to the *r* attribute in multiple places to denote the reference to which the formula applies.*

Office uses the *ref* attribute in formulas to denote the reference to which the formula applies.

2.1.901 Part 4 Section 3.17.6.5, Name Representation

a. *The standard states that the names shall be defined in the Worksheet part's XML with each being the subject of a *definedName* element, inside a *definedNames* element.*

In Office, these names shall be defined in the Workbook part's XML with each being the subject of a *definedName* element, inside a *definedNames* element.

2.1.902 Part 4 Section 3.17.7.2, ACCRINT

a. *The standard does not specify an optional argument *calc-method*.*

Excel has an optional argument *calc-method*, which is defined as follows:

| Name | Type | Description |
|-------------|---------|---|
| calc-method | logical | Specifies the way to calculate the total accrued interest when the date of settlement is later than the date of first-interest. A value of TRUE (1) returns the total accrued interest from issue to settlement. A value of FALSE (0) returns the accrued interest from first-interest to settlement. If no argument is specified, it defaults to TRUE. |

b. *The standard does not specify day and month adjustments for the basis argument.*

In Excel, the *basis* argument specifies the truncated integer type of day count basis to use, as follows:

| Value | Day Count Basis |
|--------------|--|
| 0 or omitted | US (NASD) 30/360. Assumes that each month has 30 days and the total number of days in the year is 360 by making the following adjustments: |

| Value | Day Count Basis |
|-------|--|
| | <p>If the date is 28 or 29 February, it is adjusted to 30 February.</p> <p>For months with 31 days, all dates with a day value of 31 are changed to day 30, including situations where the first date is 28 or 29 February.</p> |
| 1 | Actual/actual. The actual number of days between the two dates are counted. If the date range includes the date 29 February, the year is 366 days; otherwise it is 365 days. |
| 2 | Actual/360. Similar to Basis 1, but only has 360 days per year. |
| 3 | Actual/365. Similar to Basis 1, but always has 365 days per year. |
| 4 | <p>European 30/360. The European method for adjusting day counts. Assumes that each month has 30 days and the total number of days in the year is 360 by making the following adjustments:</p> <p>If the date is 28 or 29 February, it is adjusted to 30 February.</p> <p>For months with 31 days, all dates with a day value of 31 are changed to day 30, including situations where the first date is 28 or 29 February.</p> |

c. *The standard states that the par argument has a default value of 1000.*

Office uses a 0.001 as the default value for the par argument.

2.1.903 Part 4 Section 3.17.7.3, ACCRINTM

a. *The standard does not specify day and month adjustments for the basis argument.*

In Excel, the *basis* argument specifies the truncated integer type of day count basis to use, as follows:

| Value | Day Count Basis |
|--------------|---|
| 0 or omitted | <p>US (NASD) 30/360. Assumes that each month has 30 days and the total number of days in the year is 360 by making the following adjustments:</p> <p>If the date is 28 or 29 February, it is adjusted to 30 February.</p> <p>For months with 31 days, all dates with a day value of 31 are changed to day 30, including situations where the first date is 28 or 29 February.</p> |
| 1 | Actual/actual. The actual number of days between the two dates are counted. If the date range includes the date 29 February, the year is 366 days; otherwise it is 365 days. |
| 2 | Actual/360. Similar to Basis 1, but only has 360 days per year. |
| 3 | Actual/365. Similar to Basis 1, but always has 365 days per year. |
| 4 | <p>European 30/360. The European method for adjusting day counts. Assumes that each month has 30 days and the total number of days in the year is 360 by making the following adjustments:</p> <p>If the date is 28 or 29 February, it is adjusted to 30 February.</p> <p>For months with 31 days, all dates with a day value of 31 are changed to day 30, including</p> |

| Value | Day Count Basis |
|-------|---|
| | situations where the first date is 28 or 29 February. |

b. *The standard states that the par argument has a default value of 1000.*

Office uses a 0.001 as the default value for the par argument.

c. *The standard states A is the number of days from the issue date to the maturity date.*

Office treats A as the number of days from the issue date to the settlement date.

2.1.904 Part 4 Section 3.17.7.4, ACOS

a. *The standard does not specify unit of return value.*

Office calculates arc cosine of x, in radians.

2.1.905 Part 4 Section 3.17.7.6, ADDRESS

a. *The standard states if row-number or col-number < 1, #NUM! is returned and if ref-type is outside the range 1-4, #NUM! is returned.*

Office returns #VALUE! in such cases for the function.

2.1.906 Part 4 Section 3.17.7.7, AMORDEGRC

a. *The standard does not specify day and month adjustments for the basis argument.*

In Excel, the *basis* argument specifies the truncated integer type of day count basis to use, as follows:

| Value | Day Count Basis |
|--------------|---|
| 0 or omitted | US (NASD) 30/360. Assumes that each month has 30 days and the total number of days in the year is 360 by making the following adjustments: If the date is 28 or 29 February, it is adjusted to 30 February. For months with 31 days, all dates with a day value of 31 are changed to day 30, including situations where the first date is 28 or 29 February. |
| 1 | Actual/actual. The actual number of days between the two dates are counted. If the date range includes the date 29 February, the year is 366 days; otherwise it is 365 days. |
| 2 | Actual/360. Similar to Basis 1, but only has 360 days per year. |
| 3 | Actual/365. Similar to Basis 1, but always has 365 days per year. |
| 4 | European 30/360. The European method for adjusting day counts. Assumes that each month has 30 days and the total number of days in the year is 360 by making the following adjustments: If the date is 28 or 29 February, it is adjusted to 30 February. For months with 31 days, all dates with a day value of 31 are changed to day 30, including situations where the first date is 28 or 29 February. |

b. *The standard describes day basis value of 2 (actual/360).*

Office only uses day basis values of 0, 1, 3 or 4.

2.1.907 Part 4 Section 3.17.7.8, AMORLINC

a. *The standard does not specify day and month adjustments for the basis argument.*

In Excel, the *basis* argument specifies the truncated integer type of day count basis to use, as follows:

| Value | Day Count Basis |
|--------------|---|
| 0 or omitted | US (NASD) 30/360. Assumes that each month has 30 days and the total number of days in the year is 360 by making the following adjustments: If the date is 28 or 29 February, it is adjusted to 30 February. For months with 31 days, all dates with a day value of 31 are changed to day 30, including situations where the first date is 28 or 29 February. |
| 1 | Actual/actual. The actual number of days between the two dates are counted. If the date range includes the date 29 February, the year is 366 days; otherwise it is 365 days. |
| 2 | Actual/360. Similar to Basis 1, but only has 360 days per year. |
| 3 | Actual/365. Similar to Basis 1, but always has 365 days per year. |
| 4 | European 30/360. The European method for adjusting day counts. Assumes that each month has 30 days and the total number of days in the year is 360 by making the following adjustments: If the date is 28 or 29 February, it is adjusted to 30 February. For months with 31 days, all dates with a day value of 31 are changed to day 30, including situations where the first date is 28 or 29 February. |

b. *The standard describes day basis value of 2 (actual/360).*

Office only uses day basis values of 0, 1, 3 or 4.

2.1.908 Part 4 Section 3.17.7.10, AREAS

a. *The standard states if the reference designates no areas, #NUM! is returned.*

Office returns #NULL! if the reference designates no areas.

2.1.909 Part 4 Section 3.17.7.12, ASIN

a. *The standard does not specify the unit of the return value.*

Office calculates arc sine of x, in radians.

2.1.910 Part 4 Section 3.17.7.13, ASINH

a. *The standard states that ASINH computes the inverse hyperbolic cosine of x.*

Office computes ASINH as the inverse hyperbolic sine of x.

2.1.911 Part 4 Section 3.17.7.14, ATAN

- a. *The standard does not specify the unit of the return value.*

Office calculates arc tangent of x, in radians.

2.1.912 Part 4 Section 3.17.7.15, ATAN2

- a. *The standard states that the return value of the function is the arc tangent of x.*

In Office, the return value of the function is the arc tangent of two arguments determined by the point (x, y); that is, the angle in the Cartesian plane formed by the positive x-axis and the vector from (0,0) to the point (x, y); the result is constrained to be in the half-open interval $(-\pi, \pi]$. This function is useful in converting from rectangular coordinates (x, y) to polar coordinates (r, θ), with the angle θ being returned by this function, in radians.

Mathematical Formula:

If $x > 0$ (in the 1st or 4th quadrant or on the positive x -axis), then $ATAN2(x,y) = \arctan(y/x)$;

If $x < 0$ and $y \geq 0$ (in the 2nd quadrant or on the negative x -axis), then $ATAN2(x,y) = \arctan(y/x) + \pi$;

If $x < 0$ and $y < 0$ (in the 3rd quadrant), then $ATAN2(x,y) = \arctan(y/x) - \pi$;

If $x = 0$ and $y \neq 0$ (on the y -axis excluding the origin), then $ATAN2(x,y) = (\pi/2) * \text{sgn}(y)$,

In the preceding formulas, \arctan is the principal value of inverse tangent function, whose range is the interval $(-\pi/2, \pi/2)$, and $\text{sgn}(y)$ returns one of the values -1, 0, or +1 according as y is negative, zero, or positive.

2.1.913 Part 4 Section 3.17.7.17, AVEDEV

- a. *The standard specifies the mathematical formula for AVEDEV to be $C(n,k) = P(k,n)/k! = n!/(k!(n-k)!)$.*

Office uses the mathematical formula: $(1/n) \sum |x - \bar{x}|$ and maps n to the size of the data set, x to a value from the data set, and \bar{x} as the AVERAGE(argument-list).

2.1.914 Part 4 Section 3.17.7.19, AVERAGEA

- a. *The standard states if an argument in argument-list is an array or reference, only values in that array or reference are used.*

In Office, if an argument in argument-list is an array or reference, numeric values in that array or reference are included, and text values are included but treated as 0.

2.1.915 Part 4 Section 3.17.7.20, AVERAGEIF

- a. *The standard does not describe error case when all the cells being averaged in average-range (or in cell-range if average-range is omitted) are empty or contain non-numeric data.*

Office returns #DIV/0! in this case.

2.1.916 Part 4 Section 3.17.7.21, AVERAGEIFS

- a. *The standard indicates the Average-range need not have the same size and shape as cell-range-1 through cell-range-n.*

Office requires each cell-range-1 through cell-range-n to have the same size and shape as the average-range.

- b. *The standard states that argument cell-range-n is of type number, expression, reference, or text; while argument selection-criteria-n is of type reference or text.*

In Office, argument cell-range-n can be of type reference and argument selection-criteria-n can be of type number, expression, reference, or text.

2.1.917 Part 4 Section 3.17.7.23, BESSELI

- a. *The standard does not specify how function arguments map to formula variables.*

Office maps x to argument x and n to argument n.

2.1.918 Part 4 Section 3.17.7.24, BESSELJ

- a. *The standard does not specify how function arguments map to formula variables.*

Office maps x to argument x and n to argument n.

2.1.919 Part 4 Section 3.17.7.25, BESSELK

- a. *The standard uses the mathematical formula: $K_n(x) = (p/2)^{n+1} [J_n(ix) + iY_n(ix)]$, and does not say how function arguments map to formula variables.*

Office uses the mathematical formula $K_n(x) = (n/2)^{n+1} [J_n(ix) + iY_n(ix)]$ and maps J_n to the J Bessel function, Y_n to the Y Bessel function, n to argument n, and x to argument x.

2.1.920 Part 4 Section 3.17.7.26, BESSELY

- a. *The standard does not specify how function arguments map to formula variables.*

Office maps n to argument n and x to argument x.

2.1.921 Part 4 Section 3.17.7.28, BETAINV

- a. *The standard states that if probability < 0 or probability > 1, #NUM! is returned.*

Office returns #NUM! if probability <= 0 or probability >= 1.

- b. *The standard does not place a restriction on the relationship between argument A and argument B.*

Office returns #NUM! if argument A is greater than or equal to argument B.

- c. *The standard specifies that BETAINV uses an iterative search technique.*

Office does not require an iterative search technique to be used.

2.1.922 Part 4 Section 3.17.7.29, BIN2DEC

a. *The standard states that the number argument is a 10-digit binary number that is to be converted to a decimal string.*

Office treats the number argument as a 10-digit binary number that is to be converted to a decimal number.

2.1.923 Part 4 Section 3.17.7.34, CELL

a. *The standard does not specify locale specific strings for argument category.*

In Excel, if the SpreadsheetML is intended to be used in certain non-English locales, the category string can be the English value shown in the standard, or the translation shown in the following tables. Locales not specified in the following tables shall only use the English versions of the category string.

[Note: Using translated versions of the category string is strongly discouraged, as spreadsheet applications might not support these translations. end note]

| Local e | address | col | color | contents | coord | filename | format |
|------------|-----------|---------|---------|------------|-------------|-----------------|---------|
| az-latn-az | ünvan | col | rəng | mündəricat | coord | fayladi | format |
| ca-es | dirección | columna | color | contenido | coord | nombearchivo | formato |
| cs-cz | adresa | sloupec | barva | obsah | souřadnice | názvsouboru | formát |
| da-dk | adresse | kolonne | farve | indhold | koord | filnavn | format |
| de-de | adresse | spalte | farbe | inhalt | koord | dateiname | format |
| es-es | direccion | columna | color | contenido | coord | nombearchivo | formato |
| et-ee | aadress | veerg | värv | sisukord | Koordinatt | failinimi | vorming |
| fi-fi | osoite | sarake | väri | sisältö | koord | tiedostonnimi | muoto |
| fr-fr | adresse | colonne | couleur | contenu | coordonnees | nomfichier | format |
| hu-hu | cím | oszlop | szín | tartalom | koord | filenév | forma |
| it-it | indirizzo | col | colore | contenuto | coordinate | nomefile | formato |
| kk-kz | мекенжай | баған | түс | мазмұны | ТҰРАФИАТ | файлатауы | пішім |
| lv-lv | adrese | kolonna | krāsa | saturs | koordinātas | faila_nosaukums | formāts |
| nb-no | adresse | kol | farge | innhold | koord | filnavn | format |
| nl-nl | adres | kolom | kleur | inhoud | coord | bestandsnaam | notatie |

| Local e | address | col | color | contents | coord | filename | format |
|---------|----------|----------|-------|------------|------------------|---------------|---------|
| pl-pl | adres | kolumna | kolor | zawartość | WSPÓŁRZ | nazwa_pliku | format |
| pt-br | endereço | col | cor | conteúdo | coord | nome.arquivo | formato |
| pt-pt | endereço | col | cor | conteúdo | coord | nome.ficheiro | formato |
| ru-ru | адрес | столбец | цвет | содержимое | КООРД | имяфайла | формат |
| sk-sk | adresa | stĺpec | farba | obsah | koordinovvaImage | názovsúboru | formát |
| sl-si | address | sto | color | contents | coord | filename | format |
| sv-se | adress | kol | färg | innehåll | koord | filnamn | format |
| tr-tr | adres | süt | renk | içerik | koord | dosyaadi | biçim |
| uk-ua | адреса | стовпець | колір | вміст | КООРД | ім`я_файлу | формат |

| Locale | parentheses | prefix | protect | row | Sheet | type | width |
|------------|-------------|--------------|-------------|--------|----------|-----------|-----------|
| az-latn-az | parentheses | prefix | protect | sətir | Vərəq | tip | en |
| ca-es | parentesis | prefijo | proteger | fila | hoja | tipo | ancho |
| cs-cz | závorky | prefix | zámek | řádek | list | typ | šířka |
| da-dk | parenteser | foranstillet | beskyt | række | ark | værditype | bredde |
| de-de | klammern | präfix | schutz | zeile | blatt | typ | breite |
| es-es | parentesis | prefijo | proteger | fila | hoja | tipo | ancho |
| et-ee | sulud | eesliide | kaitse | rida | leht | tüüp | laius |
| fi-fi | sulkeet | etuliite | suojaus | rivi | taulukko | tyyppi | leveys |
| fr-fr | parentheses | prefixe | protege | ligne | feuille | type | largeur |
| hu-hu | zárójelek | előtag | védett | sor | lap | típus | széles |
| it-it | parentesi | prefisso | proteggi | riga | foglio | tipo | larghezza |
| kk-kz | жақшалар | префикс | қорғаныс | жол | ПАРАҚ | түр | ені |
| lv-lv | iekavas | prefikss | aizsargāt | rinda | lapa | tips | platums |
| nb-no | parenteser | prefiks | beskytt | rad | ark | verditype | bredde |
| nl-nl | haakjes | voorvoegsel | bescherming | rij | blad | type | breedte |
| pl-pl | nawiasy | prefiks | ochrona | wiersz | arkusz | typ | szerokość |

| Locale | parentheses | prefix | protect | row | Sheet | type | width |
|--------|-------------|-------------|----------|---------|-----------|------|----------|
| pt-br | parênteses | prefixo | proteger | lin | planilha | tipo | largura |
| pt-pt | parênteses | prefixo | proteger | lin | folha | tipo | largura |
| ru-ru | скобки | префикс | защита | строка | ТАБЛИЦА | тип | ширина |
| sk-sk | zátvorky | vloženýznak | chrániť | riadok | hImagerok | typ | šírka |
| sl-si | parentheses | prefix | protect | vrstica | sheet | type | širina |
| sv-se | parenteser | prefix | skydd | rad | blad | typ | bredd |
| tr-tr | ayraç | önek | koruma | sat | tablo | tür | genişlik |
| uk-ua | дужки | префікс | захист | рядок | АРКУШ | тип | довжина |

b. *The standard does not fully specify details when argument category is format.*

In Excel, when the category parameter is format then the value returned depends upon the number format of the upper-left cell of reference, and more specifically upon the number format code of the upper-left cell of reference. Depending upon the number format code of the appropriate cell, the result value of CELL when the category is format is based upon the following rules.

First, some observations regarding the rules are in order:

The various sections of the number format code are referred to within the rules. For more information on sections in the number format code, see numFmts ("ECMA-376 Part 4 §3.8.31; numFmts (Number Formats)"). There are cases where it is useful to discuss the characters from the number format code which are dependent upon the value in the cell. These characters, instead of representing text or spacing in the cell's display text, interpret, in some fashion, the value to be displayed. In the rules, these characters are referred to as interpreted characters of the number format code. The following table shows all the interpreted characters:

| Interpreted Characters |
|------------------------|
| 0 |
| # |
| @ |
| D |
| M |
| Y |
| H |
| S |
| ? |
| AM/PM |
| A/P |

| Interpreted Characters |
|------------------------|
| G |
| E |
| R |

There are cases where it is also useful to discuss runs of similar interpreted characters. [Example: Each d, m, and y within the number format code dd/mm/yyyy does not represent a separate interpretation of the day of the date value to be represented, and instead helps to make up a representation of the day of the date that is two digits in length. end example]. These runs of similar characters are referred to as interpreted symbols because multiple characters are used, but the result is a single symbolic representation of at least part of the value.

Because there are multiple different symbols for days, months, years, hours, minutes, seconds, and AM/PM, it is sometimes useful to discuss all of the representations of each of these. When any of Day, Month, Year, Hour, Minute, and so on, is referred to within a rule, what is meant is any of the possible representations for that date/time portion. For example, a Day symbol would be any of d, dd, ddd, or dddd.

The use of characters such as 0, E, and % as a symbol within a number format code does not include usages of these same characters either escaped (by preceding them with a backslash character "\") or as a part of a quoted string.

Here are the rules to determine the result value:

If the first interpreted symbols within the first section are any of the date or time characters (any of y, m, d, h, m, s), then the first one or two characters of the return value are determined by the order of interpreted symbols (including any interpreted symbols, not just date/time symbols) according to the following table ("anything" can mean "no additional symbols." If the type is "anything except <type>", then the excepted symbol type cannot follow the previously specified symbol):

| Interpreted Symbols in Order | Return Value Characters |
|---|--|
| Day, month, year, anything | "D1" |
| Day, month, anything besides year, anything | "D2" |
| Month, year, anything | "D3" |
| Month, day, year, anything | "D4" |
| Month, day, anything besides year, anything | "D5" |
| Hours, minutes, seconds, AM/PM, anything | "D6" |
| Hours, minutes, AM/PM, anything | "D7" |
| Hours, minutes, seconds, anything besides AM/PM, anything | "D8" |
| Hours, minutes, anything besides seconds or AM/PM, anything | "D9" |
| Any other combination of symbols | "G" or "C" depending on whether there is a \$ in the first condition |

Otherwise, the first character of the return value is determined based upon the referenced cell's number format code according to the rules in the following table:

| First Section of the Number Format Code | | First Return Value Character |
|--|---|------------------------------|
| Absent Characters (as Symbols) | Present Characters (as Symbols) | |
| | @ | "G" |
| @ | \$ | "C" |
| @, \$ | % | "P" |
| @, \$, % | E | "S" |
| @, \$, %, E | A run of any combination of one or more "0", "#", and "?" characters, followed by a comma, followed by a run of any combination of one or more "0", "#", and "?" characters. This run cannot be preceded by a period (".") or by any interpreted characters. | "," |
| @, \$, %, E, or a run of characters containing a comma as described in the preceding row | At least one of "0", "?", or "#" | "F" |
| Any of the conditions described in the preceding rows | Anything | "G" |

The final value is determined by appending any of the applicable characters from the following table to the return value characters obtained from the previous two tables:

| Case | Characters to Append |
|---|--|
| The first character of the return value is C, F, S, P, or ",", and the number format code contains any of "?", "0", or "#" as a symbol. | The decimal number equal to the total number of "#", "?", and "0" characters to the right of the first "." within the first section. |
| The first character of the return value was C, and the number format code does not contain any of "?", "0", or "#" as a symbol. | 15 or the length of the string immediately following the first "\$" sign in the number format code that is a symbol. |
| The first section of the number format code contains an open parenthesis "(" as a symbol. | "()" |
| The second section of the number format code contains [Red], [Black], [Green], [White], [Blue], [Magenta], [Yellow], or [Cyan] as a symbol. | "-" |

c. *The standard does not specify coord and sheet as values for argument category.*

Excel allows the following additional values for the *category* argument:

| category | Meaning | Result Type |
|----------|--|-------------|
| "coord" | Returns the referenced cell in the format \$A:\$<referenced column>\$<referenced row>. | text |
| "sheet" | Returns 1. | number |

2.1.924 Part 4 Section 3.17.7.37, CHIINV

a. *The standard specifies that an iterative search technique is used for the implementation of the CHIINV function.*

Office does not require an iterative search technique to be used.

b. *The standard lists #N/A as the return value in case the search has not converged after some number of iterations.*

Office does not require an iterative search technique to be used.

2.1.925 Part 4 Section 3.17.7.40, CLEAN

a. *The standard states that the function makes a string that is a copy of string with all so-called non-printable characters—those with internal values in the range U+0000–001F—removed.*

In Office, the function makes a string that is a copy of string with all so-called non-printable characters removed; specifically, those characters with internal values in the Unicode ranges U+0000 – U+001F and U+0080 – U+009F are removed.

2.1.926 Part 4 Section 3.17.7.45, COMPLEX

a. *The standard states that if real-number has the value 0 and imaginary-number has a nonzero value, the resulting string contains just the real number.*

In Office, if real-number has the value 0 and imaginary-number has a nonzero value, the resulting string contains just the imaginary-number and suffix.

2.1.927 Part 4 Section 3.17.7.47, CONFIDENCE

a. *The standard does not specify on which probability distribution the CONFIDENCE function is based.*

In Office, the CONFIDENCE function is based on a normal distribution.

2.1.928 Part 4 Section 3.17.7.48, CONVERT

a. *The standard states that the meaning of Pica is Pica (1/72 inch).*

Office treats Pica as Point (1/72 inch).

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

b. *The standard specifies P or p as the unit string for Pascal.*

Office requires Pa or p to be the unit string for Pascal.

c. *The standard specifies H or hp as the unit string for Horsepower.*

Office requires h or HP as the unit string for Horsepower.

d. *The standard does not specify the detailed unity type for cup, oz, tbs, and tsp.*

Office treats cup as traditional U.S cup, oz as U.S. fluid ounce, tbs as traditional U.S. tablespoon, and tsp as traditional U.S. teaspoon.

e. *The standard specifies ptorus_pt as the unit string for U.S. pint.*

Office requires pt or us_pt as the unit string for U.S. pint.

2.1.929 Part 4 Section 3.17.7.49, CORREL

a. *The standard does not specify how function arguments map to formula variables.*

Office maps x to value from array-1, x-bar to AVERAGE(array-1), y to value from array-2, y-bar to AVERAGE(array-2).

2.1.930 Part 4 Section 3.17.7.50, COS

a. *The standard does not specify the unit for x.*

Office uses x in radians.

2.1.931 Part 4 Section 3.17.7.52, COUNT

a. *The standard states that argument-list is of type text.*

Office requires that each argument in argument-list be of type logical, number, name, text, array, or reference.

2.1.932 Part 4 Section 3.17.7.53, COUNTA

a. *The standard states that argument-list is of type text.*

Office requires argument-list to be of type logical, number, name, text, array, or reference.

2.1.933 Part 4 Section 3.17.7.56, COUNTIFS

a. *The standard specifies a count-range argument.*

Office does not accept a count-range argument.

b. *The standard specifies that selection-criteria-1 is the first range of cells to be counted.*

Office specifies that selection-criteria-1 is in the form of a number, expression, cell reference, or text that define which cells will be counted.

2.1.934 Part 4 Section 3.17.7.57, COUPDAYBS

a. *The standard does not specify day and month adjustments for the basis argument.*

In Excel, the *basis* argument specifies the truncated integer type of day count basis to use, as follows:

| Value | Day Count Basis |
|--------------|--|
| 0 or omitted | <p>US (NASD) 30/360. Assumes that each month has 30 days and the total number of days in the year is 360 by making the following adjustments:</p> <p>If the date is 28 or 29 February, it is adjusted to 30 February.</p> <p>For months with 31 days, all dates with a day value of 31 are changed to day 30, including situations where the first date is 28 or 29 February.</p> |
| 1 | Actual/actual. The actual number of days between the two dates are counted. If the date range includes the date 29 February, the year is 366 days; otherwise it is 365 days. |
| 2 | Actual/360. Similar to Basis 1, but only has 360 days per year. |
| 3 | Actual/365. Similar to Basis 1, but always has 365 days per year. |
| 4 | <p>European 30/360. The European method for adjusting day counts. Assumes that each month has 30 days and the total number of days in the year is 360 by making the following adjustments:</p> <p>If the date is 28 or 29 February, it is adjusted to 30 February.</p> <p>For months with 31 days, all dates with a day value of 31 are changed to day 30, including situations where the first date is 28 or 29 February.</p> |

2.1.935 Part 4 Section 3.17.7.58, COUPDAYS

- a. *The standard does not specify day and month adjustments for the basis argument.*

In Excel, the *basis* argument specifies the truncated integer type of day count basis to use, as follows:

| Value | Day Count Basis |
|--------------|--|
| 0 or omitted | <p>US (NASD) 30/360. Assumes that each month has 30 days and the total number of days in the year is 360 by making the following adjustments:</p> <p>If the date is 28 or 29 February, it is adjusted to 30 February.</p> <p>For months with 31 days, all dates with a day value of 31 are changed to day 30, including situations where the first date is 28 or 29 February.</p> |
| 1 | Actual/actual. The actual number of days between the two dates are counted. If the date range includes the date 29 February, the year is 366 days; otherwise it is 365 days. |
| 2 | Actual/360. Similar to Basis 1, but only has 360 days per year. |
| 3 | Actual/365. Similar to Basis 1, but always has 365 days per year. |
| 4 | <p>European 30/360. The European method for adjusting day counts. Assumes that each month has 30 days and the total number of days in the year is 360 by making the following adjustments:</p> <p>If the date is 28 or 29 February, it is adjusted to 30 February.</p> <p>For months with 31 days, all dates with a day value of 31 are changed to day 30, including situations where the first date is 28 or 29 February.</p> |

2.1.936 Part 4 Section 3.17.7.59, COUPDAYSNC

a. *The standard does not specify day and month adjustments for the basis argument.*

In Excel, the *basis* argument specifies the truncated integer type of day count basis to use, as follows:

| Value | Day Count Basis |
|--------------|---|
| 0 or omitted | US (NASD) 30/360. Assumes that each month has 30 days and the total number of days in the year is 360 by making the following adjustments: If the date is 28 or 29 February, it is adjusted to 30 February. For months with 31 days, all dates with a day value of 31 are changed to day 30, including situations where the first date is 28 or 29 February. |
| 1 | Actual/actual. The actual number of days between the two dates are counted. If the date range includes the date 29 February, the year is 366 days; otherwise it is 365 days. |
| 2 | Actual/360. Similar to Basis 1, but only has 360 days per year. |
| 3 | Actual/365. Similar to Basis 1, but always has 365 days per year. |
| 4 | European 30/360. The European method for adjusting day counts. Assumes that each month has 30 days and the total number of days in the year is 360 by making the following adjustments: If the date is 28 or 29 February, it is adjusted to 30 February. For months with 31 days, all dates with a day value of 31 are changed to day 30, including situations where the first date is 28 or 29 February. |

2.1.937 Part 4 Section 3.17.7.60, COUPNCD

a. *The standard does not specify day and month adjustments for the basis argument.*

In Excel, the *basis* argument specifies the truncated integer type of day count basis to use, as follows:

| Value | Day Count Basis |
|--------------|--|
| 0 or omitted | US (NASD) 30/360. Assumes that each month has 30 days and the total number of days in the year is 360 by making the following adjustments: If the date is 28 or 29 February, it is adjusted to 30 February. For months with 31 days, all dates with a day value of 31 are changed to day 30, including situations where the first date is 28 or 29 February. |
| 1 | Actual/actual. The actual number of days between the two dates are counted. If the date range includes the date 29 February, the year is 366 days; otherwise it is 365 days. |
| 2 | Actual/360. Similar to Basis 1, but only has 360 days per year. |
| 3 | Actual/365. Similar to Basis 1, but always has 365 days per year. |

| Value | Day Count Basis |
|-------|---|
| 4 | European 30/360. The European method for adjusting day counts. Assumes that each month has 30 days and the total number of days in the year is 360 by making the following adjustments: If the date is 28 or 29 February, it is adjusted to 30 February. For months with 31 days, all dates with a day value of 31 are changed to day 30, including situations where the first date is 28 or 29 February. |

2.1.938 Part 4 Section 3.17.7.61, COUPNUM

- a. *The standard does not specify day and month adjustments for the basis argument.*

In Excel, the *basis* argument specifies the truncated integer type of day count basis to use, as follows:

| Value | Day Count Basis |
|--------------|---|
| 0 or omitted | US (NASD) 30/360. Assumes that each month has 30 days and the total number of days in the year is 360 by making the following adjustments: If the date is 28 or 29 February, it is adjusted to 30 February. For months with 31 days, all dates with a day value of 31 are changed to day 30, including situations where the first date is 28 or 29 February. |
| 1 | Actual/actual. The actual number of days between the two dates are counted. If the date range includes the date 29 February, the year is 366 days; otherwise it is 365 days. |
| 2 | Actual/360. Similar to Basis 1, but only has 360 days per year. |
| 3 | Actual/365. Similar to Basis 1, but always has 365 days per year. |
| 4 | European 30/360. The European method for adjusting day counts. Assumes that each month has 30 days and the total number of days in the year is 360 by making the following adjustments: If the date is 28 or 29 February, it is adjusted to 30 February. For months with 31 days, all dates with a day value of 31 are changed to day 30, including situations where the first date is 28 or 29 February. |

- b. *The standard does not specify that arguments settlement and maturity are truncated to integers.*

In Office, arguments settlement and maturity are truncated to integers.

- c. *The standard states that the return values is the number of coupons payable between the settlement date and maturity date, rounded up to the nearest whole coupon.*

In Office, if the number of months between the settlement and maturity is not a multiple of the number of months between coupon payments and settlement date is less than one payment period away from serial day 1, #NUM! is returned.

2.1.939 Part 4 Section 3.17.7.62, COUPPCD

- a. *The standard does not specify day and month adjustments for the basis argument.*

In Excel, the *basis* argument specifies the truncated integer type of day count basis to use, as follows:

| Value | Day Count Basis |
|--------------|---|
| 0 or omitted | US (NASD) 30/360. Assumes that each month has 30 days and the total number of days in the year is 360 by making the following adjustments: If the date is 28 or 29 February, it is adjusted to 30 February. For months with 31 days, all dates with a day value of 31 are changed to day 30, including situations where the first date is 28 or 29 February. |
| 1 | Actual/actual. The actual number of days between the two dates are counted. If the date range includes the date 29 February, the year is 366 days; otherwise it is 365 days. |
| 2 | Actual/360. Similar to Basis 1, but only has 360 days per year. |
| 3 | Actual/365. Similar to Basis 1, but always has 365 days per year. |
| 4 | European 30/360. The European method for adjusting day counts. Assumes that each month has 30 days and the total number of days in the year is 360 by making the following adjustments: If the date is 28 or 29 February, it is adjusted to 30 February. For months with 31 days, all dates with a day value of 31 are changed to day 30, including situations where the first date is 28 or 29 February. |

2.1.940 Part 4 Section 3.17.7.64, CRITBINOM

- a. *The standard specifies the number-trials argument as a number.*

In Excel, the number-trials argument is truncated to an integer.

2.1.941 Part 4 Section 3.17.7.65, CUBEKPIMEMBER

- a. *The standard does not specify how the relative importance of the KPI can be used on the server when argument *kpi-property* is 5.*

In Excel, a *kpi-property* value of 5 indicates the relative importance assigned to the KPI on the server. If this KPI is assigned a parent KPI, then this number can be used on the server to proportionally adjust the results of this KPI value when calculating the value of the parent KPI. While this number can be shown in the spreadsheet application, it is assumed that it is used by the server for any calculations affecting the KPI.

- b. *The standard states argument *kpi-property* equal to 6 returns a temporal context of the KPI.*

Office returns the unique name of the member in the time dimension that defines the timeframe of the KPI if *kpi-property* equals 6.

2.1.942 Part 4 Section 3.17.7.69, CUBESET

- a. *The standard does not define the return value when sort-order requires sort-by but sort-by value is not in the cube.*

In Office, #N/A is returned in this case.

2.1.943 Part 4 Section 3.17.7.70, CUBESETCOUNT

- a. *The standard does not define the return value if set argument does not evaluate to a set.*

In Office, #N/A is returned in this case.

2.1.944 Part 4 Section 3.17.7.72, CUMIPMT

- a. *The standard does not define the return value of the CUMIPMT formula when end_period is greater than nper.*

Excel returns a value of #NUM! when end_period is greater than nper.

- b. *The standard states that start-period and end-period are numbers.*

Excel truncates start-period and end-period to integers.

2.1.945 Part 4 Section 3.17.7.73, CUMPRINC

- a. *The standard does not specify the return value if the end_period argument is greater than the nper argument.*

Office returns #NUM! if the end_period argument is greater than the nper argument.

- b. *The standard states that start-period and end-period are numbers.*

Excel truncates start-period and end-period to integers.

2.1.946 Part 4 Section 3.17.7.74, DATE

- a. *The standard does not specify that the year argument must be positive.*

Office requires the year argument to be a positive number.

- b. *The standard defines a normalization process for month and day arguments.*

Office applies additional rules to the value of month or day in a year-month-day argument triplet when those values are out of range.

month is simply an instance of counting a given number of months, minus one, relative to January of the year specified, using the Gregorian calendar [\[ISO-8601\]](#). This calendar defines that there are 12 months in a year, and that when counting forward, the month following December of one year is January of the following year, and when counting backward, the month preceding January of one year is December of the previous year. Likewise, day is simply an instance of counting a given number of days, minus one, relative to the first day of the adjusted month, using the Gregorian calendar. This calendar defines the number of days in each month, and that when counting forward, the day following the final day of one month is the first day of the following month, and when counting backward, the day preceding the first day of one month is the final day of the previous month.

[Example: The year-month-day argument triplets (2007, 12,32), (2007,13,1), and (2008,1,1) all result in the same serial date. end example]

[Note: One way to handle out-of-range values for month or day is as follows:

Compute yearAdjust = INT((month - 1)/12)

Compute adjustedMonth = month - (yearAdjust * 12)

Compute adjustedYear = year + yearAdjust.

A serialDateBase can now be computed for the first day of the adjustedYear and adjustedMonth. Finally, compute the serial date for the full triplet by adding (day-1) to this serialDateBase. end note]

c. *The standard indicates various range of values for the year that cause #NUM! to be returned.*

Office returns #NUM! if the year is outside the acceptable range for the date base currently in use.

2.1.947 Part 4 Section 3.17.7.76, DATEVALUE

a. *The standard states the function computes the serial value of the date and/or time represented by the string date-time-string, taking into account the current date base value.*

In Office, the function computes the serial value of the date represented by the string date-time-string, taking into account the current date base value.

b. *The standard does not specify what happens when the date-time-string argument contains both a date and time part.*

Office truncates the time portion of the date-time-string argument, or returns 0 for time only values of date-time-string argument.

2.1.948 Part 4 Section 3.17.7.77, DAVERAGE

a. *The standard states that the field argument is the column to which criteria shall be applied.*

Office treats the field argument as the column to use to compute the average.

2.1.949 Part 4 Section 3.17.7.78, DAY

a. *The standard states that the DAY function computes the numeric Gregorian day for the date and/or time, but does not specify what "Gregorian day" is.*

Office defines "Gregorian Day" as the numeric day of the month in the Gregorian calendar [ISO 8601 §3.2.1]

2.1.950 Part 4 Section 3.17.7.79, DAYS360

a. *The standard does not describe the adjustments made when start-date is the 28th day of the 2nd month (or 29th day of the second month for leap-years) for when argument method-flag is FALSE or omitted.*

In Office, if the start-date is the 28th day of the 2nd month (29th day of the 2nd month for leap-years) it is also changed to the 30th day of that same month.

2.1.951 Part 4 Section 3.17.7.80, DB

a. *The standard does not specify the return value if period > life and month argument is omitted or month is 12, or if period > (life + 1).*

Office returns #NUM! in this case.

b. *The standard states that the syntax is: DB (cost , salvage , life , period [, [month]]).*

Office uses the following syntax: DB (cost , salvage , life , period [, month]).

2.1.952 Part 4 Section 3.17.7.81, DCOUNT

a. *The standard states that the field argument is the column to which criteria shall be applied.*

Office treats the field argument as the column with values to count.

2.1.953 Part 4 Section 3.17.7.82, DCOUNTA

a. *The standard states that the field argument is the column to which criteria shall be applied.*

Office treats the field argument as the column with values to count.

2.1.954 Part 4 Section 3.17.7.83, DDB

a. *The standard states that if the cost life argument is less than or equal to 0, then #NUM! is returned.*

Office returns #NUM! if the cost argument is less than 0.

b. *The standard does not specify the return value if period > life.*

Office returns #NUM! if period > life.

c. *The standard states that the syntax is: DDB (cost , salvage , life , period [, factor]]).*

Office uses the following syntax: DDB (cost , salvage , life , period [, factor]).

2.1.955 Part 4 Section 3.17.7.84, DEC2BIN

a. *The standard defines the number argument as a decimal number.*

Office truncates the number argument to a decimal integer.

2.1.956 Part 4 Section 3.17.7.85, DEC2HEX

a. *The standard defines the number argument as a decimal number.*

Office truncates the number argument to a decimal integer.

2.1.957 Part 4 Section 3.17.7.86, DEC2OCT

a. *The standard defines the number argument as a decimal number.*

Office truncates the number argument to a decimal integer.

2.1.958 Part 4 Section 3.17.7.89, DEVSQ

a. *The standard does not specify the return value when the argument is an array or a reference that contains only text, logical values, or empty cells.*

Office returns #NUM! when argument is an array or a reference that contains only text, logical values, or empty cells.

2.1.959 Part 4 Section 3.17.7.90, DGET

a. *The standard states that argument field is the column to which criteria shall be applied.*

Office treats argument field as the column containing the value to get.

2.1.960 Part 4 Section 3.17.7.91, DISC

a. *The standard states the pr argument is the security's price per \$100 face value.*

Office treats the pr argument as the price per 100 currency units face value.

b. *The standard states the redemption argument is the security's redemption value per \$100 face value.*

Office treats the redemption argument as the security's redemption value per 100 currency units face value.

c. *The standard does not specify day and month adjustments for the basis argument.*

In Excel, the *basis* argument specifies the truncated integer type of day count basis to use, as follows:

| Value | Day Count Basis |
|--------------|---|
| 0 or omitted | US (NASD) 30/360. Assumes that each month has 30 days and the total number of days in the year is 360 by making the following adjustments: If the date is 28 or 29 February, it is adjusted to 30 February. For months with 31 days, all dates with a day value of 31 are changed to day 30, including situations where the first date is 28 or 29 February. |
| 1 | Actual/actual. The actual number of days between the two dates are counted. If the date range includes the date 29 February, the year is 366 days; otherwise it is 365 days. |
| 2 | Actual/360. Similar to Basis 1, but only has 360 days per year. |
| 3 | Actual/365. Similar to Basis 1, but always has 365 days per year. |
| 4 | European 30/360. The European method for adjusting day counts. Assumes that each month has 30 days and the total number of days in the year is 360 by making the following adjustments: If the date is 28 or 29 February, it is adjusted to 30 February. For months with 31 days, all dates with a day value of 31 are changed to day 30, including situations where the first date is 28 or 29 February. |

d. *The standard states that the formula for DISC has par as the denominator.*

Office requires the formula to have redemption in the denominator instead of par.

2.1.961 Part 4 Section 3.17.7.92, DMAX

a. *The standard states that the field argument is the column to which criteria shall be applied.*

Office treats the field argument as the column for which to find the maximum.

2.1.962 Part 4 Section 3.17.7.93, DMIN

a. *The standard states that the field argument is the column to which criteria shall be applied.*

Office treats the field argument as the column for which to find the minimum.

2.1.963 Part 4 Section 3.17.7.94, DOLLAR

a. *The standard states that the thousands separator, radix point, and currency symbol are locale-specific. The format used is \$#,##0.00;\$(#,##0.00).*

Office treats the thousands separator, radix point, and currency symbol to be implementation-specific.

b. *The standard does not specify the return value if the num-decimal argument is greater than 127.*

Office returns #VALUE! if the num-decimal argument is greater than 127.

2.1.964 Part 4 Section 3.17.7.95, DOLLARDE

a. *The standard does not specify how the return value is calculated.*

In Excel, the fractional part of fractional-dollar is scaled to match the magnitude of fraction by moving the decimal place right by the number of digits in fraction. The fractional-dollar.m.n is computed into a decimal dollar value as $m + i$, where i is an intermediate result equal to $((0.n) * (10^x)) / \text{fraction}$, and x is the base 10 log of fraction, rounded up to the nearest whole number.

[Example: Given a fractional-dollar value of 1.02 and a fraction value of 16, the fractional part of fractional-dollar is multiplied by 100, giving a value of 2 to be divided by fraction before being added to the integral part of fractional-dollar, yielding a decimal price of 1.125. end example]

b. *The standard states that argument fractional-dollar is the number expressed as a fraction.*

Office treats argument fractional-dollar as the number to be interpreted as a fractional dollar price.

2.1.965 Part 4 Section 3.17.7.96, DOLLARFR

a. *The standard does not specify how the return value is calculated.*

In Excel, the fractional part of the return value is scaled to have the same number of digits after the decimal point, as there are digits in fraction. [Example: DOLLARFR(1.125, 16) has a two-digit fraction value and so returns the two-digit fractional number 1.02 end example] If an exact numerator cannot be found, the function returns the lowest numerator that could be used with fraction, multiplied by a power of ten. [Example: DOLLARFR(1.5,3) returns 1.15, as there is no exact fraction which satisfies $n/3 = 0.5$, and 15/30 represents the lowest power of ten fraction can be multiplied by to obtain an exact value. end example]

2.1.966 Part 4 Section 3.17.7.97, DPRODUCT

- a. *The standard states that the field argument is the column to which criteria shall be applied.*
Office treats the field argument as the column containing the values to be multiplied.

2.1.967 Part 4 Section 3.17.7.98, DSTDEV

- a. *The standard states that the field argument is the column to which criteria shall be applied.*
Office treats the field argument as the column for which the standard deviation is to be computed.

2.1.968 Part 4 Section 3.17.7.99, DSTDEVP

- a. *The standard states that the field argument is the column to which criteria shall be applied.*
Office treats the field argument as the column for which the standard deviation is to be computed.

2.1.969 Part 4 Section 3.17.7.100, DSUM

- a. *The standard states that the field argument is the column to which criteria shall be applied.*
Office treats the field argument as the column for which the sum is to be computed.

2.1.970 Part 4 Section 3.17.7.101, DURATION

- a. *The standard says that duration is defined as the weighted average of the present value of the cash flows and is used as a measure of a bond price's response to changes in yield.*

Office treats duration as the weighted average term to maturity of the cash flows from a bond. The weight of each cash flow is determined by dividing the present value of the cash flow by the price.

- b. *The standard indicates that the function is specific to U.S. currency.*

Office does not require the function to be specific to any currency.

- c. *The standard does not specify day and month adjustments for the basis argument.*

In Excel, the *basis* argument specifies the truncated integer type of day count basis to use, as follows:

| Value | Day Count Basis |
|--------------|--|
| 0 or omitted | US (NASD) 30/360. Assumes that each month has 30 days and the total number of days in the year is 360 by making the following adjustments: If the date is 28 or 29 February, it is adjusted to 30 February. For months with 31 days, all dates with a day value of 31 are changed to day 30, including situations where the first date is 28 or 29 February. |
| 1 | Actual/actual. The actual number of days between the two dates are counted. If the date range includes the date 29 February, the year is 366 days; otherwise it is 365 days. |
| 2 | Actual/360. Similar to Basis 1, but only has 360 days per year. |

| Value | Day Count Basis |
|-------|---|
| 3 | Actual/365. Similar to Basis 1, but always has 365 days per year. |
| 4 | European 30/360. The European method for adjusting day counts. Assumes that each month has 30 days and the total number of days in the year is 360 by making the following adjustments: If the date is 28 or 29 February, it is adjusted to 30 February. For months with 31 days, all dates with a day value of 31 are changed to day 30, including situations where the first date is 28 or 29 February. |

2.1.971 Part 4 Section 3.17.7.102, DVAR

- a. *The standard states that the field argument is the column to which criteria shall be applied.*

Office treats the field argument as the column for which the variance is to be computed.

2.1.972 Part 4 Section 3.17.7.103, DVARP

- a. *The standard states that the field argument is the column to which criteria shall be applied.*

Office treats the field argument as the column for which the variance is to be computed.

2.1.973 Part 4 Section 3.17.7.104, EDATE

- a. *The standard does not specify the case where the day of the month in argument start-date is greater than the last day of the result month.*

In this case, Office will round day to the last day of the result month.

2.1.974 Part 4 Section 3.17.7.107, ERF

- a. *The standard does not specify how function arguments map to formula variables.*

Office maps z to lower-bound argument, a to lower-bound argument, b to upper-bound argument.

2.1.975 Part 4 Section 3.17.7.108, ERFC

- a. *The standard does not specify how function arguments map to formula variables.*

Office maps x to lower-bound argument.

2.1.976 Part 4 Section 3.17.7.109, ERROR.TYPE

- a. *The standard states that return values are 1-7 or #N/A.*

Office can also return a value of 8, corresponding to value #GETTING_DATA.

2.1.977 Part 4 Section 3.17.7.118, FIND

- a. *The standard specifies that the start-pos argument shall be at least 0.*

Office requires start-pos argument to be at least 1.

b. *The standard states that FIND is intended for use with languages that use the single-byte character set (SBCS), whereas FINDB is intended for use with languages that use the double-byte character set (DBCS).*

In Office, FIND is intended for use with any language, whereas FINDB is intended for use with languages that use the double-byte character set (DBCS).

2.1.978 Part 4 Section 3.17.7.119, FINDB

a. *The standard states argument start-pos shall be at least 0.*

Office requires argument start-pos to be at least 1.

b. *The standard does not specify that argument start-pos and the return value are measured in bytes.*

In Office, argument start-pos and return value are measured in bytes.

c. *The standard does not specify behavior of FINDB when default language supports DBCS and when it does not support DBCS.*

In Office, when the default language supports DBCS, FINDB counts each double-byte character as 2 bytes, and each single-byte character as 1. When the default language does not support DBCS, FINDB counts each character as 1 byte.

d. *The standard does not specify which languages support DBCS.*

In Office, the languages that support DBCS include Japanese, Chinese (Simplified), Chinese (Traditional), and Korean.

2.1.979 Part 4 Section 3.17.7.120, FINV

a. *The standard specifies that an iterative search technique is used for the implementation of this function.*

Office does not require an iterative search technique to be used.

2.1.980 Part 4 Section 3.17.7.123, FIXED

a. *The standard states that the number parameter is truncated to integer.*

Office does not truncate the number parameter to an integer.

b. *The standard does not state that num-decimal is truncated to an integer.*

Office truncates num-decimal to an integer.

c. *For argument suppress-commas-flag, the standard states that if it is TRUE, commas are not included; if FALSE or omitted, commas are included.*

In Office, if argument suppress-commas-flag is TRUE, digit grouping symbols are not included; if FALSE or omitted, they are included.

2.1.981 Part 4 Section 3.17.7.124, FLOOR

a. *The standard states that regardless of the sign of x, a value is rounded down when adjusted toward zero.*

In Office, a value is rounded toward zero when adjusted.

2.1.982 Part 4 Section 3.17.7.125, FORECAST

- a. *The standard states that x and y are the sample means.*

Office treats x and y as the sample values while \bar{x} and \bar{y} as the sample means.

2.1.983 Part 4 Section 3.17.7.128, FV

- a. *The standard states that the type argument is truncated to an integer.*

Office does not truncate the type argument to an integer.

- b. *The standard states that argument type is either 0 or 1.*

In Office, any nonzero value of argument type is equivalent to 1.

- c. *The standard states that if type is any number other than 0 or 1, #NUM! is returned.*

In Office, any nonzero value of argument type is equivalent to 1.

- d. *The standard states that argument nper is truncated to integer.*

Office does not truncate argument nper to integer.

- e. *The standard states that either the pmt argument or the pv argument must be supplied.*

Office allows both to be omitted (and returns a future value of zero).

2.1.984 Part 4 Section 3.17.7.131, GAMMAINV

- a. *The standard specifies that an iterative search technique is used for the implementation of this function.*

Office does not require an iterative search technique to be used.

2.1.985 Part 4 Section 3.17.7.134, GEOMEAN

- a. *The standard states that cells with a value equal to 0 are included in the calculation.*

Office returns #NUM! if the value of any data point is less than or equal to 0.

2.1.986 Part 4 Section 3.17.7.136, GETPIVOTDATA

- a. *The standard states that arguments field-1 and item-1 are mandatory arguments.*

Office treats arguments field-1 and item-1 as optional arguments.

2.1.987 Part 4 Section 3.17.7.138, HARMEAN

- a. *The standard states that cells with the value 0 are included in calculations.*

Office returns #NUM! if the value of any data point is less than or equal to 0.

2.1.988 Part 4 Section 3.17.7.142, HLOOKUP

- a. *The standard states that argument row-index-num is the row number in argument table-array from which the matching value is to be returned.*

In Office, argument row-index-num is the row number, truncated to integer, in argument table-array from which the matching value is to be returned.

2.1.989 Part 4 Section 3.17.7.143, HOUR

- a. *The standard states that the returned value shall be in the range 0 - 59.*

Office requires that the returned value shall be in the range 0 - 23.

2.1.990 Part 4 Section 3.17.7.146, IF

- a. *The standard states that arguments value-if-true and value-if-false can contain up to seven levels of nested IF function calls.*

In Office, these arguments can contain as many levels of nesting as the application allows.

2.1.991 Part 4 Section 3.17.7.147, IFERROR

- a. *The standard states that the value argument is checked for the following error values: #N/A, #VALUE!, #REF!, #DIV/0!, #NUM!, #NAME?, or #NULL!.*

In Office, the value argument is checked for the following error values: #N/A, #VALUE!, #REF!, #DIV/0!, #NUM!, #NAME?, #NULL!, or #GETTING_DATA.

2.1.992 Part 4 Section 3.17.7.150, IMARGUMENT

- a. *The standard does not fully specify how the angle θ is calculated.*

Office calculates angle θ as $\text{ATAN2}(x,y)$.

- b. *The standard does not specify how function arguments map to formula variables.*

Office maps $x + yi$ to argument complex number, and θ to $\text{ATAN2}(x,y)$.

- c. *The standard states that the complex number can be in the form $x+yi$.*

Office accepts complex numbers in the form $x+yi$ and $x+yj$.

2.1.993 Part 4 Section 3.17.7.153, IMDIV

- a. *The standard does not specify what happens in the case of complex division by zero.*

Office returns #NUM! if complex-number-2 is zero.

2.1.994 Part 4 Section 3.17.7.155, IMLN

- a. *The standard does not specify what happens if complex-number is zero.*

Office returns #NUM! if complex-number is zero.

- b. *The standard does not fully specify how the angle θ is calculated.*

Excel calculates imln using the following mathematical formula:

$$\ln(x + yi) = \ln\sqrt{x^2 + y^2} + i\theta$$

where:

$\theta = \text{ATAN2}(x,y)$ calculated according to the formula in ATAN2 ("ECMA-376] Part 4 §3.17.7.15; ATAN2") $\theta \in (-\pi; \pi]$

2.1.995 Part 4 Section 3.17.7.156, IMLOG10

a. *The standard does not specify what happens if complex-number is zero.*

Office returns #NUM! if complex-number is zero.

2.1.996 Part 4 Section 3.17.7.157, IMLOG2

a. *The standard does not specify what happens if complex-number is zero.*

Office returns #NUM! if complex-number is zero.

2.1.997 Part 4 Section 3.17.7.158, IMPOWER

a. *The standard does not mention error case of argument complex-number equal to zero and argument n is not a positive number.*

Office returns #NUM! if complex-number is zero, and the exponent n is not a positive number.

b. *The standard specifies that y is the exponent to which complex-number is to be raised as well as a coefficient of the argument complex-number.*

Office treats n as the exponent to which argument complex-number is to be raised.

c. *The standard does not fully specify how the angle θ is calculated.*

Office calculates angle θ as ATAN2(x,y).

2.1.998 Part 4 Section 3.17.7.161, IMSIN

a. *The standard states the mathematical formula is $\sin(x+yi) = \sin(x)\cosh(y) - \cos(x)\sinh(y)i$.*

Office uses the mathematical formula $\sin(x+yi) = \sin(x)\cosh(y) + \cos(x)\sinh(y)i$.

2.1.999 Part 4 Section 3.17.7.162, IMSQRT

a. *The standard does not fully specify how the angle θ is calculated.*

Office calculates angle θ as ATAN2(x,y).

2.1.1000 Part 4 Section 3.17.7.165, INDEX

a. *The standard states that the argument row-number and argument column-number refers to the row or column, respectively, in argument array.*

Office treats argument row-number as the column number if there is only one row in the array.

2.1.1001 Part 4 Section 3.17.7.166, INDIRECT

- a. *The standard does not place any length restrictions on argument ref-text.*

Office returns #VALUE! if argument ref-text is more than 255 characters.

- b. *The standard states the argument ref-text is of type A1-style reference, an R1C1-style reference, a name defined as a reference, or a reference to a cell as a string.*

Office allows argument ref-text to be type A1-style reference, an R1C1-style reference, a name defined as a reference, a structure reference, or a reference to a cell as a string.

2.1.1002 Part 4 Section 3.17.7.167, INFO

- a. *The standard lists "memavail" as "Amount of memory available, in bytes."*

Office always returns #N/A for "memavail".

- b. *The standard lists "memused" as "Amount of memory being used for data."*

Office always returns #N/A for "memused".

- c. *The standard lists "totmem" as "Total memory available, including memory already in use, in bytes."*

Office always returns #N/A for "totmem".

- d. *The standard does not specify mode as a valid value for argument category.*

Office permits mode as a valid value for argument category and it returns 1.

- e. *The standard does not specify the valid value ostreturncode for argument category.*

Office permits ostreturncode as a valid value for argument category and it returns 0.

- f. *The standard does not specify setlang as a valid value for argument category.*

Office permits setlang as a valid value for argument category and it returns locale information.

- g. *The standard states that the return type is text.*

Office allows the return type to be text or number.

2.1.1003 Part 4 Section 3.17.7.169, INTERCEPT

- a. *The standard states that x and y are the sample means.*

Office treats x and y as the sample values; \bar{x} and \bar{y} are the sample means.

- b. *The standard makes no mention of the case for non-intercepting lines.*

Office returns #DIV/0, if the regression line does not intercept the y -axis.

2.1.1004 Part 4 Section 3.17.7.170, INTRATE

- a. *The standard does not specify day and month adjustments for the basis argument.*

In Excel, the *basis* argument specifies the truncated integer type of day count basis to use, as follows:

| Value | Day Count Basis |
|--------------|--|
| 0 or omitted | <p>US (NASD) 30/360. Assumes that each month has 30 days and the total number of days in the year is 360 by making the following adjustments:</p> <p>If the date is 28 or 29 February, it is adjusted to 30 February.</p> <p>For months with 31 days, all dates with a day value of 31 are changed to day 30, including situations where the first date is 28 or 29 February.</p> |
| 1 | Actual/actual. The actual number of days between the two dates are counted. If the date range includes the date 29 February, the year is 366 days; otherwise it is 365 days. |
| 2 | Actual/360. Similar to Basis 1, but only has 360 days per year. |
| 3 | Actual/365. Similar to Basis 1, but always has 365 days per year. |
| 4 | <p>European 30/360. The European method for adjusting day counts. Assumes that each month has 30 days and the total number of days in the year is 360 by making the following adjustments:</p> <p>If the date is 28 or 29 February, it is adjusted to 30 February.</p> <p>For months with 31 days, all dates with a day value of 31 are changed to day 30, including situations where the first date is 28 or 29 February.</p> |

b. *The standard states argument redemption is the amount to be received at maturity, the security's annual yield.*

Office defines the argument redemption as the amount to be received at maturity.

2.1.1005 Part 4 Section 3.17.7.171, IPMT

a. *The standard states that payment type is truncated to integer.*

Office does not truncate payment type to integer.

b. *The standard states that argument type is either 0 or 1.*

In Office, any nonzero value of argument type is equivalent to 1.

c. *The standard states that if argument type is not 0 or 1, #NUM! is returned.*

In Office argument type is a value of any number.

d. *The standard states that argument per shall be in the range 1-nper.*

In Office argument per shall be in the range $1 \leq \text{per} < \text{nper} + 1$.

e. *The standard does not define the error case if argument per is not in the range $1 \leq \text{per} < \text{nper} + 1$.*

In Office if argument per is not in the range $1 \leq \text{per} < \text{nper} + 1$, then #NUM! is returned.

f. *The standard does not specify the value of argument type if omitted.*

In Office if the argument type is omitted the argument type has a value of 0.

2.1.1006 Part 4 Section 3.17.7.172, IRR

a. *The standard states that IRR uses an iterative calculation technique.*

Office does not require an iterative calculation technique to be used for this function.

2.1.1007 Part 4 Section 3.17.7.182, ISPMT

a. *The standard states that the range for argument per is 1 - nper.*

In Office the argument per has no range restriction.

b. *The standard does not state the returned error case if argument nper is 0.*

In Office when the argument nper is 0, #DIV/0! is returned.

2.1.1008 Part 4 Section 3.17.7.189, LEFT

a. *The standard states that LEFT is intended for use with languages that use the single-byte character set (SBCS), whereas LEFTB is intended for use with languages that use the double-byte character set (DBCS).*

In Office, LEFT is intended for use with any language, whereas LEFTB is intended for use with languages that use the double-byte character set (DBCS).

2.1.1009 Part 4 Section 3.17.7.190, LEFTB

a. *The standard states that LEFT is intended for use with languages that use the single-byte character set (SBCS), whereas LEFTB is intended for use with languages that use the double-byte character set (DBCS).*

In Office, LEFT is intended for use with any language, whereas LEFTB is intended for use with languages that use the double-byte character set (DBCS).

b. *The standard does not specify behavior of LEFTB when default language supports DBCS and when it does not support DBCS.*

In Office, when the default language supports DBCS, LEFTB counts each double-byte character as 2 bytes, and each single-byte character as 1. When the default language does not support DBCS, LEFTB counts each character as 1 byte.

c. *The standard does not specify which languages support DBCS.*

In Office, the languages that support DBCS include Japanese, Chinese (Simplified), Chinese (Traditional), and Korean.

2.1.1010 Part 4 Section 3.17.7.191, LEN

a. *The standard specifies that LEN is intended for use with languages that use the single-byte character set (SBCS), whereas LENB is intended for use with languages that use the double-byte character set (DBCS).*

In Office, LEN is intended for use with any language, whereas LENB is intended for use with languages that use the double-byte character set (DBCS).

2.1.1011 Part 4 Section 3.17.7.192, LENB

a. *The standard states that LENB is intended for use with languages that use the double-byte character set (DBCS), whereas LEN is intended for use with languages that use the single-byte character set (SBCS).*

In Office, LENB is intended for use with languages that use the double-byte character set (DBCS), whereas LEN is intended for use with any language.

b. *The standard does not specify behavior of LENB when default language supports DBCS and when it does not support DBCS.*

In Office, when the default language supports DBCS, LENB counts each double-byte character as 2 bytes, and each single-byte character as 1. When the default language does not support DBCS, LENB counts each character as 1 byte.

c. *The standard does not specify which languages support DBCS.*

In Office, the languages that support DBCS include Japanese, Chinese (Simplified), Chinese (Traditional), and Korean.

2.1.1012 Part 4 Section 3.17.7.193, LINEST

a. *The standard states that x and y are sample means.*

Office treats x and y as the sample values, and \bar{x} and \bar{y} as the sample means of known- x s and known- y s, respectively.

b. *The standard does not place any restrictions on dimensions of known- y s or known- x s.*

In Office, if known- y s and known- x s are both specified but don't match in size (or number of variables for the multivariate case), #REF! is returned.

c. *The standard describes statistic se_b as the standard error value for the constant b .*

In Office, if b is forced to be zero (const-flag=FALSE), then it has no standard error and #N/A is returned.

d. *The standard does not mention collinearity cases for this function.*

In Excel, vectors in known- x s that are collinear (have no additional predictive value because they can be expressed as sum of multiples of existing vectors) are omitted from the regression calculations. The vectors are given a coefficient of 0 and a standard error of 0 ($m = 0$; $se = 0$). If vectors are omitted, df is affected because df depends on the number of values used for predictive purposes.

e. *The standard states the syntax is: LINEST (known- y s [, [known- x s] [, [const-flag] [, stats-flag]]).*

Office uses the following syntax: LINEST (known- y s [, [known- x s] [, [const-flag] [, [stats-flag]]]).

2.1.1013 Part 4 Section 3.17.7.195, LOG

a. *The standard does not specify what happens if base is equal to 1.*

Office returns #DIV/0! if base is equal to 1.

2.1.1014 Part 4 Section 3.17.7.197, LOGEST

a. *The standard specifies the equation for the curve is $y = b * mx$ or $y=b*(m1*x1)*(m2*x2)*...$ if there are multiple values*

Office uses the following equation for the curve: $y = b * (m^x)$ or $y=b*(m1^x1)*(m2^x2)...(mn^xn)$ if there are multiple values

b. *The standard does not place any restrictions on dimensions of known-ys or known-xs.*

In Office, if known-ys and known-xs are not the same size, or known-ys does not contain exactly one value for each row or column of known-xs, #REF! is returned.

c. *The standard specifies the following syntax: LOGEST (known-ys [, [known-xs] [, [const-flag] [, stats-flag]]).*

Office uses the following syntax: LOGEST (known-ys [, [known-xs] [, [const-flag] [, [stats-flag]]]) .

2.1.1015 Part 4 Section 3.17.7.198, LOGINV

a. *The standard states that if probability is less than 0, or if probability is greater than 1, #NUM! is returned.*

Office returns #NUM! if probability is less than or equal to 0, or if probability is greater than or equal to 1.

2.1.1016 Part 4 Section 3.17.7.199, LOGNORMDIST

a. *The standard states that the function returns the inverse of the lognormal cumulative distribution function of x.*

In Office, the function returns the lognormal cumulative distribution of x.

2.1.1017 Part 4 Section 3.17.7.202, MATCH

a. *The standard states that if no match is found, #NUM! is returned.*

In Office, #N/A is returned if no match is found.

b. *The standard does not place any restrictions on the dimensions of argument lookup-array.*

In Office, argument lookup-array must be an array or range with only one row or only one column, else #N/A is returned.

2.1.1018 Part 4 Section 3.17.7.206, MDURATION

a. *The standard does not specify day and month adjustments for the basis argument.*

In Excel, the *basis* argument specifies the truncated integer type of day count basis to use, as follows:

| Value | Day Count Basis |
|--------------|--|
| 0 or omitted | US (NASD) 30/360. Assumes that each month has 30 days and the total number of days in the year is 360 by making the following adjustments: |

| Value | Day Count Basis |
|-------|--|
| | <p>If the date is 28 or 29 February, it is adjusted to 30 February.</p> <p>For months with 31 days, all dates with a day value of 31 are changed to day 30, including situations where the first date is 28 or 29 February.</p> |
| 1 | Actual/actual. The actual number of days between the two dates are counted. If the date range includes the date 29 February, the year is 366 days; otherwise it is 365 days. |
| 2 | Actual/360. Similar to Basis 1, but only has 360 days per year. |
| 3 | Actual/365. Similar to Basis 1, but always has 365 days per year. |
| 4 | <p>European 30/360. The European method for adjusting day counts. Assumes that each month has 30 days and the total number of days in the year is 360 by making the following adjustments:</p> <p>If the date is 28 or 29 February, it is adjusted to 30 February.</p> <p>For months with 31 days, all dates with a day value of 31 are changed to day 30, including situations where the first date is 28 or 29 February.</p> |

b. *The standard does not specify how function arguments map to formula variables.*

Office maps coupon payments per year to argument frequency, DURATION to DURATION(settlement, maturity, coupon, yld, frequency, [basis]), and market yield to argument yld.

2.1.1019 Part 4 Section 3.17.7.208, MID

a. *The standard states that MID is intended for use with languages that use the single-byte character set (SBCS), whereas MIDB is intended for use with languages that use the double-byte character set (DBCS).*

In Office, MID is intended for use with any language, whereas MIDB is intended for use with languages that use the double-byte character set (DBCS).

b. *The standard states if start-pos < 0, #VALUE! is returned.*

Office returns #VALUE! if start-pos < 1.

c. *The standard states that if the start-pos argument is greater than the length of string, or if start-pos and number-bytes combined exceeds the length of the string argument, the whole of the string argument shall be extracted.*

In Office, if start-pos is greater than the length of string the empty string is returned. If start-pos and number-bytes combined exceeds the length of string, the remainder of string starting at byte position start-pos is returned.

2.1.1020 Part 4 Section 3.17.7.209, MIDB

a. *The standard states that MIDB is intended for use with languages that use the double-byte character set (DBCS), whereas MID is intended for use with languages that use the single-byte character set (SBCS).*

In Office, MIDB is intended for use with languages that use the double-byte character set (DBCS), whereas MID is intended for use with any language.

b. *The standard states if start-pos < 0, #VALUE! is returned.*

Office returns #VALUE! if start-pos < 1.

c. *The standard states that if the start-pos argument is greater than the length of the string argument, or if the start-pos argument and the number-bytes argument combined exceed the length of the string argument, the whole of string shall be extracted.*

In Office, if start-pos is greater than the length of string the empty string is returned. If start-pos and number-bytes combined exceeds the length of string, the remainder of string starting at byte position start-pos is returned.

d. *The standard specifies the return value as a string containing number-bytes-worth of characters from string, starting at character position start-pos.*

Office returns a string containing number-bytes-worth of characters from string, starting at byte position start-pos.

e. *The standard does not specify behavior of MIDB when default language supports DBCS and when it does not support DBCS.*

In Office, when the default language supports DBCS, MIDB counts each double-byte character as 2 bytes, and each single-byte character as 1. When the default language does not support DBCS, MIDB counts each character as 1 byte.

f. *The standard does not specify which languages support DBCS.*

In Office, the languages that support DBCS include Japanese, Chinese (Simplified), Chinese (Traditional), and Korean.

2.1.1021 Part 4 Section 3.17.7.210, MIN

a. *The standard states that the arguments in argument-list designate the values for which the largest value is to be computed.*

Office treats the arguments in argument-list to be the values for which the smallest value is to be computed.

2.1.1022 Part 4 Section 3.17.7.211, MINA

a. *The standard states that the arguments in argument-list designate the values for which the largest value is to be computed.*

Office treats the arguments in argument-list to be the values for which the smallest value is to be computed.

2.1.1023 Part 4 Section 3.17.7.213, MINVERSE

a. *The standard states the inverse matrix is calculated with an accuracy of at least 15 digits, which can lead to a small numeric error when the cancellation is not complete.*

In Office, the inverse matrix is calculated with an accuracy of at least 15 digits, which can lead to a small numeric error.

2.1.1024 Part 4 Section 3.17.7.220, MULTINOMIAL

a. *The standard defines MULTINOMIAL as a function of a,b,c.*

Office treats MULTINOMIAL as a function of a1, a2,...,an, where a1 maps to arg-1, a2 to arg-2,...,an to arg-n.

2.1.1025 Part 4 Section 3.17.7.221, N

a. *The standard states that if argument value is anything else (including array and text), the function will return 0.*

Office does not treat array as a special case: the function will return 0 if argument value is anything else (including text).

2.1.1026 Part 4 Section 3.17.7.223, NEGBINOMDIST

a. *The standard states if success-probability is < 0 or > 1, #NUM! is returned.*

Office returns #NUM!, if success-probability is <= 0 or >=1.

2.1.1027 Part 4 Section 3.17.7.224, NETWORKDAYS

a. *The standard states that the function computes the number of whole working days between start-date and end-date.*

Office computes the number of whole working days between start-date and end-date, inclusive.

b. *The standard states that the function returns the number of whole working days between start-date and end-date.*

In Office, time information in the date arguments is ignored when computing the number of whole working days between start-date and end-date.

c. *The standard states that weekend days are not considered as working days.*

Office treats Saturday and Sunday as weekend days.

2.1.1028 Part 4 Section 3.17.7.227, NORMINV

a. *The standard states that the function uses an iterative search technique.*

Office does not require an iterative search technique to be used.

b. *The standard states if probability < 0 or probability > 1, #NUM! is returned.*

Office returns #NUM! if probability is <= 0 or if probability is >= 1.

2.1.1029 Part 4 Section 3.17.7.228, NORMSDIST

a. *The standard states that the function returns the standard normal distribution for the specified mean and standard deviation.*

Office returns the cumulative standard normal distribution for the specified value.

b. *The standard states that the mathematical formula for the function is: $f(z) = (1/\sqrt{2\pi}) e^{-(z^2/2)}$.*

In Excel, the NORMSDIST function is described by the following mathematical formula:

$$f(z) = \int_{-\infty}^z \frac{1}{\sqrt{2\pi}} e^{-\frac{x^2}{2}} dx$$

c. *The standard states that the return value is the standard normal distribution for the specified mean and standard deviation.*

Office returns the cumulative standard normal distribution.

2.1.1030 Part 4 Section 3.17.7.229, NORMSINV

a. *The standard states that the function uses an iterative search technique.*

Office does not require an iterative search technique to be used.

b. *The standard states that the function returns the inverse of the standard normal distribution.*

In Office, the function returns the inverse of the standard normal cumulative distribution.

c. *The standard states that if probability < 0 or if probability > 1, #NUM! is returned.*

Office returns #NUM! if probability ≤ 0 or if probability ≥ 1.

2.1.1031 Part 4 Section 3.17.7.232, NPER

a. *The standard states if type is any number other than 0 or 1, #NUM! is returned.*

Office treats nonzero values of type to indicate payment is at the beginning of the period.

b. *The standard does not specify a default for the optional argument type.*

In Office, if the value for type is omitted it defaults to value of 0.

c. *The standard states that the argument type is truncated to an integer.*

Office does not truncate the argument type to an integer.

2.1.1032 Part 4 Section 3.17.7.233, NPV

a. *The standard states that arguments that are numbers, empty cells, logical values, or text representations of numbers are included; arguments that are error values or text that cannot be translated into numbers are ignored.*

In Office, arguments that are numbers or text that can be translated into numbers are included. arguments that are empty cells, logical values, or text that cannot be translated into numbers are ignored.

2.1.1033 Part 4 Section 3.17.7.234, OCT2BIN

a. *The standard states that if number is negative, num-bin-digits is ignored and the result has 10 digits.*

Office does not ignore num-bin-digits when the number is negative.

2.1.1034 Part 4 Section 3.17.7.235, OCT2DEC

a. *The standard states that argument number is of type number.*

Office treats argument number as type text.

2.1.1035 Part 4 Section 3.17.7.238, ODDFPRICE

a. *The standard does not specify day and month adjustments for the basis argument.*

In Excel, the *basis* argument specifies the truncated integer type of day count basis to use, as follows:

| Value | Day Count Basis |
|--------------|---|
| 0 or omitted | US (NASD) 30/360. Assumes that each month has 30 days and the total number of days in the year is 360 by making the following adjustments: If the date is 28 or 29 February, it is adjusted to 30 February. For months with 31 days, all dates with a day value of 31 are changed to day 30, including situations where the first date is 28 or 29 February. |
| 1 | Actual/actual. The actual number of days between the two dates are counted. If the date range includes the date 29 February, the year is 366 days; otherwise it is 365 days. |
| 2 | Actual/360. Similar to Basis 1, but only has 360 days per year. |
| 3 | Actual/365. Similar to Basis 1, but always has 365 days per year. |
| 4 | European 30/360. The European method for adjusting day counts. Assumes that each month has 30 days and the total number of days in the year is 360 by making the following adjustments: If the date is 28 or 29 February, it is adjusted to 30 February. For months with 31 days, all dates with a day value of 31 are changed to day 30, including situations where the first date is 28 or 29 February. |

b. *The standard states that the function is specific to U.S. currency.*

Office does not require the function to be specific to any currency.

c. *The standard indicates no restriction on the argument redemption.*

Office returns #NUM! if argument redemption ≤ 0 .

2.1.1036 Part 4 Section 3.17.7.239, ODDFYIELD

a. *The standard does not specify day and month adjustments for the basis argument.*

In Excel, the *basis* argument specifies the truncated integer type of day count basis to use, as follows:

| Value | Day Count Basis |
|-------|---|
| 0 or | US (NASD) 30/360. Assumes that each month has 30 days and the total number of days in the |

| Value | Day Count Basis |
|---------|--|
| omitted | <p>year is 360 by making the following adjustments:</p> <p>If the date is 28 or 29 February, it is adjusted to 30 February.</p> <p>For months with 31 days, all dates with a day value of 31 are changed to day 30, including situations where the first date is 28 or 29 February.</p> |
| 1 | Actual/actual. The actual number of days between the two dates are counted. If the date range includes the date 29 February, the year is 366 days; otherwise it is 365 days. |
| 2 | Actual/360. Similar to Basis 1, but only has 360 days per year. |
| 3 | Actual/365. Similar to Basis 1, but always has 365 days per year. |
| 4 | <p>European 30/360. The European method for adjusting day counts. Assumes that each month has 30 days and the total number of days in the year is 360 by making the following adjustments:</p> <p>If the date is 28 or 29 February, it is adjusted to 30 February.</p> <p>For months with 31 days, all dates with a day value of 31 are changed to day 30, including situations where the first date is 28 or 29 February.</p> |

b. *The standard states the function is specific to U.S. currency.*

In Excel, the function is not specific to any currency.

c. *The standard states that if rate or pr < 0, #NUM! is returned.*

Office returns #NUM! if rate < 0 or pr <= 0.

2.1.1037 Part 4 Section 3.17.7.240, ODDLPRICE

a. *The standard does not specify day and month adjustments for the basis argument.*

In Excel, the *basis* argument specifies the truncated integer type of day count basis to use, as follows:

| Value | Day Count Basis |
|--------------|---|
| 0 or omitted | <p>US (NASD) 30/360. Assumes that each month has 30 days and the total number of days in the year is 360 by making the following adjustments:</p> <p>If the date is 28 or 29 February, it is adjusted to 30 February.</p> <p>For months with 31 days, all dates with a day value of 31 are changed to day 30, including situations where the first date is 28 or 29 February.</p> |
| 1 | Actual/actual. The actual number of days between the two dates are counted. If the date range includes the date 29 February, the year is 366 days; otherwise it is 365 days. |
| 2 | Actual/360. Similar to Basis 1, but only has 360 days per year. |
| 3 | Actual/365. Similar to Basis 1, but always has 365 days per year. |

| Value | Day Count Basis |
|-------|---|
| 4 | European 30/360. The European method for adjusting day counts. Assumes that each month has 30 days and the total number of days in the year is 360 by making the following adjustments: If the date is 28 or 29 February, it is adjusted to 30 February. For months with 31 days, all dates with a day value of 31 are changed to day 30, including situations where the first date is 28 or 29 February. |

b. *The standard indicates that the function is specific to U.S. currency.*

Office does not require the function to be specific to any currency.

c. *The standard indicates no restriction on the argument redemption.*

Office returns #NUM! if the argument redemption ≤ 0 .

2.1.1038 Part 4 Section 3.17.7.241, ODDLYIELD

a. *The standard does not specify day and month adjustments for the basis argument.*

In Excel, the *basis* argument specifies the truncated integer type of day count basis to use, as follows:

| Value | Day Count Basis |
|--------------|---|
| 0 or omitted | US (NASD) 30/360. Assumes that each month has 30 days and the total number of days in the year is 360 by making the following adjustments: If the date is 28 or 29 February, it is adjusted to 30 February. For months with 31 days, all dates with a day value of 31 are changed to day 30, including situations where the first date is 28 or 29 February. |
| 1 | Actual/actual. The actual number of days between the two dates are counted. If the date range includes the date 29 February, the year is 366 days; otherwise it is 365 days. |
| 2 | Actual/360. Similar to Basis 1, but only has 360 days per year. |
| 3 | Actual/365. Similar to Basis 1, but always has 365 days per year. |
| 4 | European 30/360. The European method for adjusting day counts. Assumes that each month has 30 days and the total number of days in the year is 360 by making the following adjustments: If the date is 28 or 29 February, it is adjusted to 30 February. For months with 31 days, all dates with a day value of 31 are changed to day 30, including situations where the first date is 28 or 29 February. |

b. *The standard indicates that the function is specific to U.S. currency.*

Office does not require the function to be specific to any currency.

c. *The standard states that if rate or pr < 0, #NUM! is returned.*

Office returns #NUM! if rate < 0 or pr ≤ 0 .

2.1.1039 Part 4 Section 3.17.7.242, OFFSET

- a. *The standard specifies that the height and width arguments shall be positive.*

Office allows the height and width arguments to be negative.

2.1.1040 Part 4 Section 3.17.7.244, PEARSON

- a. *The standard maps x and y to AVERAGE(array-1) and AVERAGE(array-2), respectively.*

Office maps x to an individual value from array-1, x-bar to AVERAGE(array-1), y to an individual value from array-2, y-bar to AVERAGE(array-2).

2.1.1041 Part 4 Section 3.17.7.245, PERCENTILE

- a. *The standard indicated the return value is undefined if the array is empty.*

Office returns 0 if the array is empty.

2.1.1042 Part 4 Section 3.17.7.246, PERCENTRANK

- a. *The standard defines significance argument as a number.*

Office truncates significance argument to an integer.

- b. *The standard does not specify an upper limit on significance argument.*

Office returns #DIV/0! when the significance argument is greater than 308.

2.1.1043 Part 4 Section 3.17.7.250, PMT

- a. *The standard places no restrictions on nper.*

In Excel, if nper is 0, then #DIV/0! is returned.

- b. *The standard states that the argument type can only be 0 or 1.*

Office allows the value for argument type to be omitted or nonzero.

- c. *The standard states that the argument type is truncated to an integer.*

Office does not truncate the argument type to an integer.

- d. *The standard does not specify a default for the optional argument type.*

In Office, if the value for type is omitted it defaults to value of 0.

2.1.1044 Part 4 Section 3.17.7.251, POISSON

- a. *The standard stated that if argument mean ≤ 0 , #NUM! is returned.*

Office returns #NUM! if argument mean is < 0 .

- b. *The standard states the formula for CUMPOISSON = $\sum_{(k=0)}^x ((e^{(-\lambda)} \lambda^k) / k!)$.*

Office requires CUMPOISSON = $\sum_{(k=0)}^x ((e^{(-\lambda)} \lambda^k) / k!)$.

2.1.1045 Part 4 Section 3.17.7.252, POWER

a. *The standard states that POWER(0,0) will return #DIV/0!.*

Office returns #NUM! for POWER(0,0).

2.1.1046 Part 4 Section 3.17.7.253, PPMT

a. *The standard states that the type argument is truncated to an integer.*

Office does not truncate the type argument to an integer.

b. *The standard does not specify a default for the optional argument type.*

In Office, if the value for type is omitted it defaults to value of 0.

c. *The standard states that the argument type can only be 0 or 1.*

Office allows the value for argument type to be omitted or nonzero.

d. *The standard does not place any restrictions on the per argument.*

In Excel, if the per argument is less than 1 or greater than the nper argument, #NUM! is returned.

2.1.1047 Part 4 Section 3.17.7.254, PRICE

a. *The standard does not specify day and month adjustments for the basis argument.*

In Excel, the *basis* argument specifies the truncated integer type of day count basis to use, as follows:

| Value | Day Count Basis |
|--------------|---|
| 0 or omitted | US (NASD) 30/360. Assumes that each month has 30 days and the total number of days in the year is 360 by making the following adjustments: If the date is 28 or 29 February, it is adjusted to 30 February. For months with 31 days, all dates with a day value of 31 are changed to day 30, including situations where the first date is 28 or 29 February. |
| 1 | Actual/actual. The actual number of days between the two dates are counted. If the date range includes the date 29 February, the year is 366 days; otherwise it is 365 days. |
| 2 | Actual/360. Similar to Basis 1, but only has 360 days per year. |
| 3 | Actual/365. Similar to Basis 1, but always has 365 days per year. |
| 4 | European 30/360. The European method for adjusting day counts. Assumes that each month has 30 days and the total number of days in the year is 360 by making the following adjustments: If the date is 28 or 29 February, it is adjusted to 30 February. For months with 31 days, all dates with a day value of 31 are changed to day 30, including situations where the first date is 28 or 29 February. |

b. *The standard indicates that the function is specific to U.S. currency.*

Office does not require the function to be specific to any currency.

2.1.1048 Part 4 Section 3.17.7.255, PRICEDISC

a. *The standard does not specify day and month adjustments for the basis argument.*

In Excel, the *basis* argument specifies the truncated integer type of day count basis to use, as follows:

| Value | Day Count Basis |
|--------------|--|
| 0 or omitted | <p>US (NASD) 30/360. Assumes that each month has 30 days and the total number of days in the year is 360 by making the following adjustments:</p> <p>If the date is 28 or 29 February, it is adjusted to 30 February.</p> <p>For months with 31 days, all dates with a day value of 31 are changed to day 30, including situations where the first date is 28 or 29 February.</p> |
| 1 | Actual/actual. The actual number of days between the two dates are counted. If the date range includes the date 29 February, the year is 366 days; otherwise it is 365 days. |
| 2 | Actual/360. Similar to Basis 1, but only has 360 days per year. |
| 3 | Actual/365. Similar to Basis 1, but always has 365 days per year. |
| 4 | <p>European 30/360. The European method for adjusting day counts. Assumes that each month has 30 days and the total number of days in the year is 360 by making the following adjustments:</p> <p>If the date is 28 or 29 February, it is adjusted to 30 February.</p> <p>For months with 31 days, all dates with a day value of 31 are changed to day 30, including situations where the first date is 28 or 29 February.</p> |

b. *The standard indicates that the function is specific to U.S. currency..*

Office does not require the function to be specific to any currency.

2.1.1049 Part 4 Section 3.17.7.256, PRICEMAT

a. *The standard does not specify day and month adjustments for the basis argument.*

In Excel, the *basis* argument specifies the truncated integer type of day count basis to use, as follows:

| Value | Day Count Basis |
|--------------|---|
| 0 or omitted | <p>US (NASD) 30/360. Assumes that each month has 30 days and the total number of days in the year is 360 by making the following adjustments:</p> <p>If the date is 28 or 29 February, it is adjusted to 30 February.</p> <p>For months with 31 days, all dates with a day value of 31 are changed to day 30, including situations where the first date is 28 or 29 February.</p> |

| Value | Day Count Basis |
|-------|---|
| 1 | Actual/actual. The actual number of days between the two dates are counted. If the date range includes the date 29 February, the year is 366 days; otherwise it is 365 days. |
| 2 | Actual/360. Similar to Basis 1, but only has 360 days per year. |
| 3 | Actual/365. Similar to Basis 1, but always has 365 days per year. |
| 4 | European 30/360. The European method for adjusting day counts. Assumes that each month has 30 days and the total number of days in the year is 360 by making the following adjustments: If the date is 28 or 29 February, it is adjusted to 30 February. For months with 31 days, all dates with a day value of 31 are changed to day 30, including situations where the first date is 28 or 29 February. |

b. *The standard indicates that the function is specific to U.S. currency.*

Office does not require the function to be specific to any currency.

2.1.1050 Part 4 Section 3.17.7.257, PROB

a. *The standard states that if the sum of the values in probability-range < 1, #NUM! is returned.*

Office returns #NUM! if the sum of the values in probability-range is not equal to 1.

b. *The standard states that if any value in argument probability-range ≤ 0 or any value in probability-range > 1 , #NUM! is returned.*

In Office, values in argument probability-range may be ≤ 0 or > 1 .

2.1.1051 Part 4 Section 3.17.7.258, PRODUCT

a. *The standard states that valid arguments in argument-list shall be counted.*

In Office, valid arguments in argument-list shall be multiplied.

2.1.1052 Part 4 Section 3.17.7.260, PV

a. *The standard does not specify a default for the optional argument type.*

In Office, if the value for type is omitted it defaults to value of 0.

b. *The standard states that the argument type is truncated to an integer.*

Office does not truncate the argument type to an integer.

c. *The standard states that if the argument type is any number other than 0 or 1, #NUM! is returned.*

Office allows the value for argument type to be omitted or nonzero.

2.1.1053 Part 4 Section 3.17.7.266, RANK

a. *The standard does not indicate restrictions on the value of attribute number.*

Office returns #N/A if number does not exist in number-list.

2.1.1054 Part 4 Section 3.17.7.267, RATE

a. *The standard does not define a default for the argument type.*

Office specifies that the argument type defaults to 0.

b. *The standard states that the argument type may only be 0 or 1.*

In Office, if the argument type is nonzero the payment is at the beginning of the period.

c. *The standard specifies that an iterative technique is used for the implementation of this function.*

Office does not use an iterative technique.

2.1.1055 Part 4 Section 3.17.7.268, RECEIVED

a. *The standard does not specify day and month adjustments for the basis argument.*

In Excel, the *basis* argument specifies the truncated integer type of day count basis to use, as follows:

| Value | Day Count Basis |
|--------------|---|
| 0 or omitted | US (NASD) 30/360. Assumes that each month has 30 days and the total number of days in the year is 360 by making the following adjustments: If the date is 28 or 29 February, it is adjusted to 30 February. For months with 31 days, all dates with a day value of 31 are changed to day 30, including situations where the first date is 28 or 29 February. |
| 1 | Actual/actual. The actual number of days between the two dates are counted. If the date range includes the date 29 February, the year is 366 days; otherwise it is 365 days. |
| 2 | Actual/360. Similar to Basis 1, but only has 360 days per year. |
| 3 | Actual/365. Similar to Basis 1, but always has 365 days per year. |
| 4 | European 30/360. The European method for adjusting day counts. Assumes that each month has 30 days and the total number of days in the year is 360 by making the following adjustments: If the date is 28 or 29 February, it is adjusted to 30 February. For months with 31 days, all dates with a day value of 31 are changed to day 30, including situations where the first date is 28 or 29 February. |

2.1.1056 Part 4 Section 3.17.7.269, REPLACE

a. *The standard states that REPLACE is intended for use with languages that use the single-byte character set (SBCS), whereas REPLACEB is intended for use with languages that use the double-byte character set (DBCS).*

In Office, REPLACE is intended for use with any language, whereas REPLACEB is intended for use with languages that use the double-byte character set (DBCS).

b. *The standard specifies start-pos shall be greater than or equal to 0.*

In Office, start-pos shall be greater than or equal to 1.

2.1.1057 Part 4 Section 3.17.7.270, REPLACEB

a. *The standard does not specify that argument start-pos and number-bytes are measured in bytes.*

Office measures argument start-pos and number-bytes in bytes.

b. *The standard states that REPLACEB is intended for use with languages that use the double-byte character set (DBCS) and REPLACE is intended for use with languages that use the single-byte character set (SBCS).*

In Office, REPLACEB is intended for use with languages that use the double-byte character set (DBCS) and REPLACE is intended for use with any language.

c. *The standard specifies that start-pos shall be greater than or equal to 0.*

In Office, start-pos shall be greater than or equal to 1.

d. *The standard does not specify which languages support DBCS.*

In Office, the languages that support DBCS include Japanese, Chinese (Simplified), Chinese (Traditional), and Korean.

e. *The standard does not specify behavior of REPLACEB when default language supports DBCS and when it does not support DBCS.*

In Office, when the default language supports DBCS, REPLACEB counts each double-byte character as 2 bytes, and each single-byte character as 1. When the default language does not support DBCS, REPLACEB counts each character as 1 byte.

2.1.1058 Part 4 Section 3.17.7.272, RIGHT

a. *The standard specifies that RIGHT is intended for use with languages that use the single-byte character set (SBCS), whereas RIGHTB is intended for use with languages that use the double-byte character set (DBCS).*

In Office, RIGHT is intended for use with any language, whereas RIGHTB is intended for use with languages that use the double-byte character set (DBCS).

2.1.1059 Part 4 Section 3.17.7.273, RIGHTB

a. *The standard does not specify which languages support DBCS.*

In Office, the languages that support DBCS include Japanese, Chinese (Simplified), Chinese (Traditional), and Korean.

b. *The standard does not specify behavior of RIGHTB when default language supports DBCS and when it does not support DBCS.*

In Office, when the default language supports DBCS, RIGHTB counts each double-byte character as 2 bytes, and each single-byte character as 1. When the default language does not support DBCS, RIGHTB counts each character as 1 byte.

2.1.1060 Part 4 Section 3.17.7.274, ROMAN

- a. *The standard does not specify what happens if number argument is equal to 0.*

Office returns the empty string if number argument is equal to 0.

2.1.1061 Part 4 Section 3.17.7.275, ROUND

- a. *The standard states that a return value is the rounded down value of x.*

Office treats x as the rounded value of x.

2.1.1062 Part 4 Section 3.17.7.279, ROWS

- a. *The standard states that if the range of cells referred to by array is not contiguous, #NULL! is returned.*

Office returns #REF!, if array refers to the union of discontinuous ranges.

2.1.1063 Part 4 Section 3.17.7.280, RSQ

- a. *The specification for the RSQ function states the equation for the Pearson product moment correlation coefficient but does not give an accurate meaning of the variables.*

Office defines x as a sample value, x-bar as the sample mean AVERAGE(known-xs), y as a sample value, and y-bar as the sample mean AVERAGE(known-ys)

2.1.1064 Part 4 Section 3.17.7.281, RTD

- a. *The standard does not describe restrictions on progID.*

In Office, if progID does not reference an application that is registered and that implements IRTDServer, then #N/A is returned.

- b. *The standard does not describe how the application communicates with Excel.*

In Office, the application must implement the IRTDServer interface.

- c. *The standard does not specify that argument-list may be left blank.*

In Office, argument-list is required, but may be left blank.

- d. *The standard uses the following syntax: RTD(progID, [rtd-server], argument-list).*

Office uses the following syntax: RTD(progID, rtd-server, argument-list).

- e. *In the standard, argument-list does not specify the maximum number of arguments.*

In Office, argument-list may contain at most 253 arguments.

- f. *The standard describes the rtd-server argument as a string that is specific to the application with which RTD is communicating.*

In Office, the rtd-server argument is used to perform a DCOM call to a remote RTD server. It is not specific to the RTD server. If there is no server and the application is run locally, the argument is left blank.

2.1.1065 Part 4 Section 3.17.7.282, SEARCH

- a. *The standard states that start-pos shall be at least 0.*

In Office, start-pos shall be at least 1.

- b. *The standard states that SEARCH is intended for use with languages that use the single-byte character set (SBCS), whereas SEARCHB is intended for use with languages that use the double-byte character set (DBCS).*

In Office, SEARCH is intended for use with any language, whereas SEARCHB is intended for use with languages that use the double-byte character set (DBCS).

2.1.1066 Part 4 Section 3.17.7.283, SEARCHB

- a. *The standard states that in the description of argument start-pos, start-pos shall be at least 0.*

In Office, start-pos shall be at least 1, measured in bytes.

- b. *The standard does not specify that the start position is measured in bytes.*

Office measures the start position in bytes.

- c. *The standard does not specify behavior of SEARCHB when default language supports DBCS and when it does not support DBCS.*

In Office, when the default language supports DBCS, SEARCHB counts each double-byte character as 2 bytes, and each single-byte character as 1. When the default language does not support DBCS, SEARCHB counts each character as 1 byte.

- d. *The standard does not specify which languages support DBCS.*

In Office, the languages that support DBCS include Japanese, Chinese (Simplified), Chinese (Traditional), and Korean.

2.1.1067 Part 4 Section 3.17.7.285, SERIESSUM

- a. *The standard states that the argument coefficients must be of type reference.*

Office allows the coefficients argument to be of types array or reference.

2.1.1068 Part 4 Section 3.17.7.287, SIN

- a. *The standard does not specify the unit for x.*

Office uses x in radians.

2.1.1069 Part 4 Section 3.17.7.291, SLOPE

- a. *The standard does not specify how function arguments map to formula variables.*

Office maps \bar{x} to the sample mean AVERAGE (known-xs) argument and \bar{y} to the sample mean AVERAGE (known-ys) argument.

2.1.1070 Part 4 Section 3.17.7.296, STDEV

- a. *The standard maps x to the sample mean and n to the sample size.*

Office maps \bar{x} to the sample mean, n to the sample size and x to a sample value.

b. *The standard does not specify what happens if sample size is less than or equal to 1.*

Office returns #DIV/0! if sample size is less than or equal to 1.

2.1.1071 Part 4 Section 3.17.7.297, STDEVA

a. *The standard maps x to the sample mean and n to the sample size.*

Office maps \bar{x} to the sample mean, n to the sample size and x to a sample value.

b. *The standard does not specify what happens if size is less than or equal to one.*

Office returns #DIV/0! if sample size is less than or equal to one.

2.1.1072 Part 4 Section 3.17.7.298, STDEVP

a. *The standard maps x to sample value, \bar{x} to sample mean, and n to the sample size.*

Office maps x to a population value, \bar{x} to the population mean, and n to the population size.

b. *The standard states that if data represents a population sample only, STDEVA should be used.*

In Office, STDEV should be used in this case.

c. *The standard does not specify what happens if population size is 0.*

Office returns #DIV/0! if population size is 0.

2.1.1073 Part 4 Section 3.17.7.299, STDEVPA

a. *The standard maps x to sample value, \bar{x} to sample mean, and n to the sample size.*

Office maps x to a population value, \bar{x} to the population mean, and n to the population size.

b. *The standard does not specify what happens if population size is 0.*

Office returns #DIV/0! if population size is 0.

2.1.1074 Part 4 Section 3.17.7.301, SUBSTITUTE

a. *The standard states if occurrence is less than 0, #VALUE! is returned.*

Office returns #VALUE! if occurrence is less than or equal to 0.

2.1.1075 Part 4 Section 3.17.7.303, SUM

a. *The standard states that valid arguments in argument-list shall be counted.*

In Office, valid arguments in argument-list shall be added.

2.1.1076 Part 4 Section 3.17.7.305, SUMIFS

a. *The standard states that sum-range need not have the same size and shape as cell-range-1 through cell-range-n.*

In Office, each cell-range-1...cell-range-n shall have the same size and shape as sum-range.

b. *The standard states that cells in sum-range that contain TRUE evaluate to 1; cells in sum-range that contain FALSE evaluate to 0.*

In Office, cells in sum-range that do not contain numeric values evaluate to 0.

2.1.1077 Part 4 Section 3.17.7.306, SUMPRODUCT

a. *The standard states if the array arguments do not have the same dimensions, #NUM! is returned.*

In Office, if the array arguments do not have the same dimensions, #VALUE! is returned.

2.1.1078 Part 4 Section 3.17.7.307, SUMSQ

a. *The standard states that valid arguments in argument-list shall be counted.*

In Office, valid arguments in argument-list shall have their squares summed.

2.1.1079 Part 4 Section 3.17.7.313, TAN

a. *The standard does not specify the unit for x.*

Office uses x in radians.

2.1.1080 Part 4 Section 3.17.7.316, TBILLPRICE

a. *The standard states that the function computes the price per \$100 face value for a U.S. Treasury bill.*

In Office, the function is not specific to any currency or treasury bill.

b. *The standard states that if the settlement argument is greater than the maturity argument, then #NUM! is returned.*

Office returns #NUM! if the settlement argument is greater than or equal to the maturity argument.

2.1.1081 Part 4 Section 3.17.7.317, TBILLYIELD

a. *The standard states that the argument pr is the Treasury bill's price per \$100 face value.*

In Office, the argument pr is not specific to any currency or Treasury bill.

b. *The standard states that If settlement > maturity, #NUM! is returned.*

Office returns #NUM! if settlement \geq maturity.

2.1.1082 Part 4 Section 3.17.7.320, TIME

a. *The standard specifies that the serial value for the given time, as a value greater than or equal to 0 and less than or equal to 1.*

Office treats the serial value for the given time, as a value greater than or equal to 0 and less than 1.

2.1.1083 Part 4 Section 3.17.7.321, TIMEVALUE

- a. *The standard does not state the range for the result of the function.*

Office returns a value greater than or equal to zero and less than 1.

2.1.1084 Part 4 Section 3.17.7.327, TRIMMEAN

- a. *The standard states that #NUM! is returned if the percent argument is less than zero or greater than 1.*

In Office, #NUM! is returned if the percent argument is less than zero or greater than or equal to 1.

2.1.1085 Part 4 Section 3.17.7.329, TRUNC

- a. *The standard states that the argument x is of type array or reference.*

Office requires argument x to be of type number.

2.1.1086 Part 4 Section 3.17.7.330, TTEST

- a. *The standard does not specify any restriction on argument test-type.*

In Office, #NUM! is returned if argument test-type is any value other than 1, 2, or 3.

2.1.1087 Part 4 Section 3.17.7.331, TYPE

- a. *The standard states that the argument can be of any type.*

Office allows the argument value to be of any type except for reference.

2.1.1088 Part 4 Section 3.17.7.333, USDOLLAR

- a. *The standard does not specify any restriction on argument num-decimal.*

Office returns #VALUE! if argument num-decimal is greater than 127.

- b. *The standard states that the thousands separator is the comma, the radix point is the period, and the currency symbol is \$ and the format used is \$#,##0.00;(\$#,##0.00).*

In Office, the formatting applied to the string for the thousands separator, radix point, and currency symbol are implementation-specific.

2.1.1089 Part 4 Section 3.17.7.334, VALUE

- a. *The standard does not specify what happens if string argument is not formatted as number, currency, date or time.*

In Office, if string is not formatted using a number, currency, date, or time format, #VALUE! is returned.

2.1.1090 Part 4 Section 3.17.7.335, VAR

- a. *The standard does not specify what happens if sample size is less than or equal to 1.*

Office returns #DIV/0! if sample size less than or equal to 1.

b. *The standard does not specify how function arguments map to formula variables.*

Office maps x to a sample value, \bar{x} to AVERAGE(argument-1, argument-2,...,argument-n) and n to sample size.

2.1.1091 Part 4 Section 3.17.7.336, VARA

a. *The standard does not specify what happens if sample size is less than or equal to 1.*

Office returns #DIV/0! if sample size is less than or equal to 1.

b. *The standard does not specify how function arguments map to formula variables.*

Office maps x to a sample value, \bar{x} to AVERAGE(argument-1, argument-2,...,argument-n) and n to sample size.

2.1.1092 Part 4 Section 3.17.7.337, VARP

a. *The standard does not specify what happens if population size is 0.*

Office returns #DIV/0! if population size is 0.

b. *The standard does not specify how function arguments map to formula variables.*

Office maps x to a population value, \bar{x} to AVERAGE(argument-1, argument-2,...,argument-n) and n to population size.

2.1.1093 Part 4 Section 3.17.7.338, VARPA

a. *The standard does not specify what happens if population size is 0.*

Office returns #DIV/0! if population size is 0.

b. *The standard does not specify how function arguments map to formula variables.*

Office maps x to a population value, \bar{x} to AVERAGE(argument-1, argument-2,...,argument-n) and n to population size.

2.1.1094 Part 4 Section 3.17.7.339, VDB

a. *The standard does not define any restriction on the relationship between the arguments start-period and end-period.*

In Office, if argument start-period > argument end-period, #NUM! is returned.

b. *The standard does not define any restriction on the relationship between the arguments end-period and life.*

In Office, if argument end-period > argument life, then #NUM! is returned.

c. *The standard does not define any restriction on the relationship between the arguments cost and salvage.*

In Office, if argument cost is less than argument salvage, then 0 is returned.

2.1.1095 Part 4 Section 3.17.7.340, VLOOKUP

a. *The standard states the values in the left-most column of table-array shall be placed in ascending order.*

In Office, if range-lookup-flag is TRUE or omitted the values in the left-most column of table-array shall be placed in ascending order.

2.1.1096 Part 4 Section 3.17.7.343, WEIBULL

a. *The standard states that if argument cumulative-flag is TRUE, GAMMADIST returns the cumulative distribution function; if FALSE, it returns the probability density function.*

In Office, if argument cumulative-flag is TRUE, WEIBULL returns the cumulative distribution function; if FALSE, it returns the probability density function.

2.1.1097 Part 4 Section 3.17.7.344, WORKDAY

a. *The standard states that #NUM! is returned if any date in argument holidays is out of range for the current date base value.*

Office returns #VALUE! if any date in argument holidays is out of range for the current date base value.

b. *The standard does not declare which days are weekend days.*

In Office the function considers Saturday and Sunday to be the weekend days.

2.1.1098 Part 4 Section 3.17.7.345, XIRR

a. *The standard specifies that an iterative technique is used for the implementation of this function.*

Office does not require an iterative technique to be used.

b. *The standard states that if any date in argument dates is out of range for the current date base value, #NUM! is returned.*

In Office, if any date in argument dates is out of range for the current date base value, #VALUE! is returned.

c. *The standard does not define any restriction that argument values must contain one positive and one negative value.*

In Office, if argument values do not contain at least one positive and one negative value, #NUM! is returned.

d. *The standard states that if any date in argument dates precedes the start date, #NUM! is returned.*

In Office, dates in the argument dates can precede the start date.

2.1.1099 Part 4 Section 3.17.7.346, XNPV

a. *The standard does not define any restriction on the argument rate.*

In Office, if rate ≤ 0 , #NUM! is returned.

2.1.1100 Part 4 Section 3.17.7.348, YEARFRAC

a. *The standard does not describe day and month adjustments for the argument basis.*

In Excel, the *basis* argument specifies the truncated integer type of day count basis to use, as follows:

| Value | Day Count Basis |
|--------------|---|
| 0 or omitted | US (NASD) 30/360. Assumes that each month has 30 days and the total number of days in the year is 360 by making the following adjustments: If the date is 28 or 29 February, it is adjusted to 30 February. For months with 31 days, all dates with a day value of 31 are changed to day 30, including situations where the first date is 28 or 29 February. |
| 1 | Actual/actual. The actual number of days between the two dates are counted. If the date range includes the date 29 February, the year is 366 days; otherwise it is 365 days. |
| 2 | Actual/360. Similar to Basis 1, but only has 360 days per year. |
| 3 | Actual/365. Similar to Basis 1, but always has 365 days per year. |
| 4 | European 30/360. The European method for adjusting day counts. Assumes that each month has 30 days and the total number of days in the year is 360 by making the following adjustments: If the date is 28 or 29 February, it is adjusted to 30 February. For months with 31 days, all dates with a day value of 31 are changed to day 30, including situations where the first date is 28 or 29 February. |

b. *The standard lists day-count-basis as one of the function's arguments.*

In Excel, the function does not take a day-count-basis argument.

c. *The standard does not specify any restrictions on arguments start-date or end-date.*

Office returns #NUM! if arguments start-date or end-date is out of range for the current date base value.

d. *The standard does not describe year length adjustments when argument basis is Actual/actual.*

In Office, if the argument basis is Actual/actual, the year length used is the average length of the years that the range crosses, regardless of where arguments start-date and end-date fall in their respective years.

2.1.1101 Part 4 Section 3.17.7.349, YIELD

a. *The standard does not describe day and month adjustments.*

In Excel, the *basis* argument specifies the truncated integer type of day count basis to use, as follows:

| Value | Day Count Basis |
|--------------|--|
| 0 or omitted | <p>US (NASD) 30/360. Assumes that each month has 30 days and the total number of days in the year is 360 by making the following adjustments:</p> <p>If the date is 28 or 29 February, it is adjusted to 30 February.</p> <p>For months with 31 days, all dates with a day value of 31 are changed to day 30, including situations where the first date is 28 or 29 February.</p> |
| 1 | Actual/actual. The actual number of days between the two dates are counted. If the date range includes the date 29 February, the year is 366 days; otherwise it is 365 days. |
| 2 | Actual/360. Similar to Basis 1, but only has 360 days per year. |
| 3 | Actual/365. Similar to Basis 1, but always has 365 days per year. |
| 4 | <p>European 30/360. The European method for adjusting day counts. Assumes that each month has 30 days and the total number of days in the year is 360 by making the following adjustments:</p> <p>If the date is 28 or 29 February, it is adjusted to 30 February.</p> <p>For months with 31 days, all dates with a day value of 31 are changed to day 30, including situations where the first date is 28 or 29 February.</p> |

b. *The standard states that the redemption argument is the security's redemption value per \$100 face value.*

In Office the redemption argument is the security's redemption value per 100 currency units face value.

c. *The standard describes the argument pr as the security's price.*

In Office, the argument pr is the security's price per 100 currency units face value.

d. *The standard describes the argument rate as the security's interest rate.*

In Office, the argument rate is the security's annual coupon rate.

2.1.1102 Part 4 Section 3.17.7.350, YIELDDISC

a. *The standard does not describe day and month adjustments.*

In Excel, the *basis* argument specifies the truncated integer type of day count basis to use, as follows:

| Value | Day Count Basis |
|--------------|---|
| 0 or omitted | <p>US (NASD) 30/360. Assumes that each month has 30 days and the total number of days in the year is 360 by making the following adjustments:</p> <p>If the date is 28 or 29 February, it is adjusted to 30 February.</p> <p>For months with 31 days, all dates with a day value of 31 are changed to day 30,</p> |

| Value | Day Count Basis |
|-------|---|
| | including situations where the first date is 28 or 29 February. |
| 1 | Actual/actual. The actual number of days between the two dates are counted. If the date range includes the date 29 February, the year is 366 days; otherwise it is 365 days. |
| 2 | Actual/360. Similar to Basis 1, but only has 360 days per year. |
| 3 | Actual/365. Similar to Basis 1, but always has 365 days per year. |
| 4 | European 30/360. The European method for adjusting day counts. Assumes that each month has 30 days and the total number of days in the year is 360 by making the following adjustments: If the date is 28 or 29 February, it is adjusted to 30 February. For months with 31 days, all dates with a day value of 31 are changed to day 30, including situations where the first date is 28 or 29 February. |

b. *The standard states that the redemption argument is the security's redemption value per \$100 face value.*

In Office, the redemption argument is the security's redemption value per 100 currency units face value.

c. *The standard describes the argument pr as the security's price.*

In Office, the argument pr is the security's price per 100 currency units face value.

2.1.1103 Part 4 Section 3.17.7.351, YIELDMAT

a. *The standard does not specify day and month adjustments for the basis argument.*

In Excel, the *basis* argument specifies the truncated integer type of day count basis to use, as follows:

| Value | Day Count Basis |
|--------------|--|
| 0 or omitted | US (NASD) 30/360. Assumes that each month has 30 days and the total number of days in the year is 360 by making the following adjustments: If the date is 28 or 29 February, it is adjusted to 30 February. For months with 31 days, all dates with a day value of 31 are changed to day 30, including situations where the first date is 28 or 29 February. |
| 1 | Actual/actual. The actual number of days between the two dates are counted. If the date range includes the date 29 February, the year is 366 days; otherwise it is 365 days. |
| 2 | Actual/360. Similar to Basis 1, but only has 360 days per year. |
| 3 | Actual/365. Similar to Basis 1, but always has 365 days per year. |
| 4 | European 30/360. The European method for adjusting day counts. Assumes that each month has 30 days and the total number of days in the year is 360 by making the following adjustments: |

| Value | Day Count Basis |
|-------|---|
| | <p>If the date is 28 or 29 February, it is adjusted to 30 February.</p> <p>For months with 31 days, all dates with a day value of 31 are changed to day 30, including situations where the first date is 28 or 29 February.</p> |

b. *The standard specifies pr argument as the security's price.*

Office treats pr argument as the security's price per 100 currency units face value.

c. *The standard states if rate or pr ≤ 0, #NUM! is returned.*

Office returns #NUM! if pr is less than or equal to 0, or if rate is less than 0.

d. *The standard does not describe a restriction on the relative values of issue and settlement.*

Office returns #NUM! if issue ≥ settlement.

2.1.1104 Part 4 Section 3.17.7.352, ZTEST

a. *The standard does not specify how function arguments map to formula variables.*

Office maps x-bar to sample mean and μ₀ to argument test-value.

b. *In the standard, there is no restriction on the value of sigma.*

In Office, if sigma is less than or equal to 0, then #NUM! is returned.

2.1.1105 Part 4 Section 3.18.2, ST_BorderId (Border Id)

a. *The standard allows this type to be any unsignedInt.*

In Office, the valid values for attributes that use this type are restricted by the count of border elements in the borders collection.

2.1.1106 Part 4 Section 3.18.7, ST_CellFormulaType (Formula Type)

a. *The standard is missing attributes referencing this type.*

Office allows f@t to reference this type.

2.1.1107 Part 4 Section 3.18.8, ST_CellRef (Cell Reference)

a. *The standard defines a cell reference to be any string.*

A single cell reference consists of a column name immediately followed by a row number. The column name is encoded using one, two, or three capital letters in US English locale:

<letter> ::= "A" | "B" | "C" | "D" | "E" | "F" | "G" | "H" | "I" | "J" | "K" | "L" | "M" | "N" | "O" | "P" | "Q" | "R" | "S" | "T" | "U" | "V" | "W" | "X" | "Y" | "Z"

<column name> ::= <letter> | <letter> <letter> | <letter> <letter> <letter>

<cell reference> ::= <column name> <row number>

The row number is an integer in the range from 1 to 1048576.

Assume that the letter "A" corresponds to the numeric value 1, the letter "B" – to the numeric value 2, and so on, and the letter "Z" corresponding to the numeric value 26. Further assume that <letter N> designates the letter in position N of the column name, counting from the right, with a missing letter corresponding to the numeric value 0. The column number then can be expressed as follows:

$$\langle \text{column number} \rangle = 676 * \langle \text{letter 3} \rangle + 26 * \langle \text{letter 2} \rangle + \langle \text{letter 1} \rangle$$

[Example:

Column name "A" corresponds to the column number 1: $676 * 0 + 26 * 0 + 1 = 1$.

Column name "AD" corresponds to the column number 30: $676 * 0 + 26 * 1 + 4 = 30$.

Column name "XFD" corresponds to the column number 16384: $676 * 24 + 26 * 6 + 4 = 16384$.

End example]

The first column in a sheet is number 1 and it has the name "A". The last column in the sheet is number 16384 and it has the name "XFD".

[Example:

A1 – a reference to the cell at column 1, row 1.

XFD1048576 – a reference to the cell in the bottom right corner of the sheet, that is, at column 16384, row 1048576.

End example]

2.1.1108 Part 4 Section 3.18.9, ST_CellSpan (Cell Span Type)

a. *The standard states that the ST_CellSpan simple type is referenced by the ST_CellSpan simple type.*

Office defines this simple type to be referenced by the ST_CellSpans simple type.

b. *The standard allows any string to be a valid CellSpan.*

In Office, the numerical values separated by the colon specify the first and last columns of the span using one-based column indices. The values shall be positive and never exceed the maximum number of columns within the spreadsheet document. The value to the left of the colon shall be less than or equal to the value to the right of the colon.

This restriction matches the following regular expression pattern: $\backslash d + : \backslash d +$.

2.1.1109 Part 4 Section 3.18.17, ST_CredMethod (Credentials Method)

a. *The standard states that prompt is a valid value of the ST_CredMethod simple type.*

Excel does not allow this value on this simple type.

2.1.1110 Part 4 Section 3.18.26, ST_DxfId (Format Id)

a. *The standard specifies that the values for the ST_DxfId simple type are defined by the XML Schema unsignedInt datatype.*

In Office, the valid values for attributes that use this simple type must be less than or equal to 4294967294.

2.1.1111 Part 4 Section 3.18.30, ST_FileType (File Type)

- a. *The standard does not state that this setting can be overridden.*

In Office, this simple type is used in the absence of the byte-order mark (BOM), whose value shall override this setting.

2.1.1112 Part 4 Section 3.18.31, ST_FillId (Fill Id)

- a. *The standard allows this type to be any unsignedInt.*

In Office, the valid values for attributes that use this type are restricted by the count of fill elements in the fills collection (3.8.20).

2.1.1113 Part 4 Section 3.18.36, ST_Formula (Formula)

- a. *The standard does not limit the length of the contents of the ST_Formula simple type.*

Excel restricts the contents of this simple type to be at most 8192 characters.

- b. *The standard is missing reference to general formulas syntax and prose.*

In Excel, the ST_Formula simple type should have a reference to general formulas syntax and prose as defined in Formulas ("[ECMA-376](#) Part 4 §3.17; Formulas").

2.1.1114 Part 4 Section 3.18.44, ST_IconSetType (Icon Set Type)

- a. *The standard states that the 5Rating set contains smiley-face icons for conditional formatting.*

Office implements the 5Rating icon set is a set of 5 cell phone-like bars (see icons for '4 ratings icon set').

2.1.1115 Part 4 Section 3.18.49, ST_NumFmtId (Number Format Id)

- a. *The standard states that the values of the ST_NumFmtId simple type are defined by the XML Schema unsignedInt datatype.*

Office restricts the values of this attribute to be at most 65535.

- b. *The standard does not restrict the values of instances of the ST_NumFmtId simple type.*

Office requires the first instance of this type in any sequence to be equal to zero. This instance specifies the default style.

2.1.1116 Part 4 Section 3.18.59, ST_PhoneticType (Phonetic Type)

- a. *The standard defines the character set that will be defined for displaying phonetic hints.*

Office uses the value as a hint as to what character set is preferred for editing phonetic hints.

2.1.1117 Part 4 Section 3.18.61, ST_PivotFilterType (Pivot Filter Types)

- a. *The standard has descriptions for caption enumeration values stating they apply to field captions.*

In Office, these enumeration values apply to item captions.

2.1.1118 Part 4 Section 3.18.64, ST_Ref (Cell Range Reference)

- a. *The standard does not clearly define what constitutes a valid a cell range reference.*

In Office, a cell range reference consists of two single cell references separated by ":" character. The first single cell reference corresponds to the cell with the smallest row and column numbers, and the second single cell reference corresponds to the cell with the largest row and column numbers within the range. If both references correspond to the same cell, only the first reference might be recorded, and both ":" and the second reference might be omitted:

<cell range reference> ::= <cell reference> ":" <cell reference> | <cell reference>

The cell reference, the encoding of column names and their mapping to column numbers are described in ST_CellRef simple type ("ECMA-376 Part 4 §3.18.8; ST_CellRef (Cell Reference)").

The width of the cell range reference is equal to the difference between the largest column number and the smallest column number of the cell range reference, plus 1.

The height of the cell range reference is equal to the difference between the largest row number and the smallest row number of the cell range reference, plus 1.

[Example

A1:AD5 – a reference to the cell range of 150 cells, with top left corner in the cell at column , row 1, and the bottom right corner in the cell at column 30, row 5. The width of this range is 30 columns, and the height of this range is 5 rows.

XFD1048576 – a reference to the cell in the bottom right corner of the sheet.

End example]

2.1.1119 Part 4 Section 3.18.65, ST_RefA (Absolute Cell Reference)

- a. *The standard defines this subclass to be a reference to single cell.*

Office allows elements or attributes of this type to be either a single cell reference or an area reference.

- b. *The standard does not describe the type of cell references that are allowed.*

Office specifies the appropriate format of the cell references and the parsing format to be the same as ST_Ref.

2.1.1120 Part 4 Section 3.18.78, ST_Sqref (Reference Sequence)

- a. *The standard states that the number of ST_Refs in the list is not limited.*

Office limits the number of refs in the list to 8192, unless explicitly noted in the respective usage text.

2.1.1121 Part 4 Section 3.18.79, ST_TableStyleType (Table Style Type)

- a. *The standard specifies enumeration values using the generic term "table," so that each value can be applied to either ordinary tables or PivotTables.*

Office the following enumeration values also apply to PivotTables: firstColumn, firstColumnStripe, firstHeaderCell, firstRowStripe, headerRow, lastColumn, secondColumnStripe, secondRowStripe, totalRow, and wholeTable.

2.1.1122 Part 4 Section 3.18.83, ST_TotalsRowFunction (Totals Row Function Types)

a. *The standard does not specify the formula specified by the enumeration value.*

The values *average*, *count*, *countNums*, *max*, *min*, *stdDev*, *sum*, and *var* specify the SUBTOTAL formula (“[\[ECMA-376\]](#) Part 4 §3.17.7.302; SUBTOTAL”); where the *function-number* is specified in the following value table and the *argument-list* is a cell reference (“[\[ECMA-376\]](#) Part 4 §3.17.2.3; Cell References”) or structure reference (“[\[ECMA-376\]](#) Part 4 §3.17.2.3; Cell References”) that designates the cells of the table column’s data region.

The following are possible enumeration values for this type:

| Enumeration Value | Description |
|-------------------------------------|--|
| average (Average) | Represents the arithmetic mean. The SUBTOTAL <i>function-number</i> is 101. |
| count (Non Empty Cell Count) | Represents a count of the number of non-empty cells. The SUBTOTAL <i>function-number</i> is 103. |
| countNums (Count Numbers) | Represents the number of cells that contain numbers. The SUBTOTAL <i>function-number</i> is 102. |
| custom (Custom Formula) | Represents the formula provided in <i>totalsRowFormula</i> . |
| max (Maximum) | Represents the largest value. The SUBTOTAL <i>function-number</i> is 104. |
| min (Minimum) | Represents the smallest value. The SUBTOTAL <i>function-number</i> is 105. |
| none (None) | No total row. |
| stdDev (StdDev) | Represents the estimated standard deviation. The SUBTOTAL <i>function-number</i> is 107. |
| sum (Sum) | Represents the arithmetic sum. The SUBTOTAL <i>function-number</i> is 109. |
| var (Var) | Represents the estimated variance. The SUBTOTAL <i>function-number</i> is 110. |

2.1.1123 Part 4 Section 3.18.88, ST_UpdateLinks (Update Links Behavior Types)

a. *The standard requires that for the value of always the links are always updated without displaying an alert.*

Excel always displays an alert before updating the links.

2.1.1124 Part 4 Section 3.18.91, ST_Visibility (Visibility Types)

a. *The standard states this is about sheet visibility.*

Office uses this for workbook window visibility.

2.1.1125 Part 4 Section 3.18.94, ST_WebSourceType (Web Source Type)

- a. *The standard states that the label value defines a label.*

Excel uses this value to define a named range of cells.

- b. *The standard states that charts can be published.*

Office does not allow charts to be published.

2.1.1126 Part 4 Section 3.18.96, ST_Xstring (Escaped String)

- a. *The standard implies that the only characters that can be Xstring encoded are invalid XML characters.*

The following four cases represent valid XML characters that should be escaped:

Carriage Return (0x000D): This character shall be escaped.

Line Feed (0x000A): This character shall be escaped only when used in an attribute.

Tab (0x0009): This character shall be escaped only when used in an attribute.

Underscore (0x005f): This character shall be escaped only when used to escape the first underscore character in the format `_xHHHH_`.

- b. *The standard allows Xstring to encode underscores using `_x005f_`.*

In Excel, Xstrings may only contain the escape sequence `_x005f_` when escaping the lead underscore from a string in the form `_xHHHH_`.

2.1.1127 Part 4 Section 4.2.1, custData (Customer Data)

- a. *The standard does not specify what type of resource the id attribute should refer to.*

PowerPoint requires that the id attribute specify a valid data store item.

2.1.1128 Part 4 Section 4.2.2, custShow (Custom Show)

- a. *The standard states that the id attribute is a number that should be unique within the presentation.*

PowerPoint requires that the id attribute shall be linked to one of the custom shows defined in the presentation's `custShowLst` element.

2.1.1129 Part 4 Section 4.2.3, ext (Extension)

- a. *The standard implies that the uri attribute is optional.*

PowerPoint requires the uri attribute.

2.1.1130 Part 4 Section 4.2.8, sldRg (Slide Range)

For additional notes that apply to this portion of the standard, please see the notes for [pRg. §4.6.56\(b\)](#).

2.1.1131 Part 4 Section 4.3.1.4, clrMru (Color MRU)

- a. *The standard states that the schemeClr element is a valid child of the clrMru element.*

PowerPoint does not allow the schemeClr element to be a child of the clrMru element. If the schemeClr element exists, an RGB value of 0x0000000 is used.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.1132 Part 4 Section 4.3.1.5, custShow (Custom Show)

- a. *The standard states that the id attribute should be unique among all the custom shows within the corresponding presentation.*

PowerPoint further requires that the id attribute should be sequential.

2.1.1133 Part 4 Section 4.3.1.9, embeddedFontLst (Embedded Font List)

- a. *The standard states that the font data is referenced within the embeddedFont element.*

PowerPoint further requires that the typeface of each embeddedFont element shall be unique.

- b. *The standard states that the embeddedFontLst element specifies a list of fonts that are embedded within the corresponding presentation.*

PowerPoint further requires that all of the fonts specified in this list shall be used in this presentation.

2.1.1134 Part 4 Section 4.3.1.10, font (Embedded Font Name)

For additional notes that apply to this portion of the standard, please see the notes for [latin](#), [§5.1.5.3.7\(a-d\)](#).

- a. *The standard states that the typeface attribute specifies the typeface of the font that is to be used for bullets.*

PowerPoint uses the typeface attribute to describe the typeface for both bullets and runs of text.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.1135 Part 4 Section 4.3.1.13, htmlPubPr (HTML Publishing Properties)

- a. *The standard states that the id attribute specifies the path that should be used when publishing.*

PowerPoint includes the file name along with the path in the id attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

- b. *The standard states that title is a valid attribute.*

PowerPoint does not support the title attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.1136 Part 4 Section 4.3.1.15, kinsoku (Kinsoku Settings)

a. *The standard does not specify which values of the lang attribute represent valid East Asian languages.*

In PowerPoint, the value for the lang attribute must be one of the following:

| Value | Description |
|-------|---|
| ja-jp | Japanese. Specifies that the settings apply to runs of text with the langId attribute of the rPr element ("ECMA-376 Part 4 §5.1.5.3.9; rPr (Text Run Properties)") equal to ja-jp (Japanese). |
| ko-kr | Korean. Specifies that the settings apply to runs of text with the langId attribute of the rPr element ("ECMA-376 Part 4 §5.1.5.3.9; rPr (Text Run Properties)") equal to ko-kr (Korean). |
| zh-cn | Chinese (Simplified). Specifies that the settings apply to runs of text with the langId attribute of the rPr element ("ECMA-376 Part 4 §5.1.5.3.9; rPr (Text Run Properties)") equal to one of the following: zh-cn (Chinese (Simplified, PRC)) zh-sg (Chinese (Simplified, Singapore)) ii-cn (Yi (PRC)) |
| zh-tw | Chinese (Traditional). Specifies that the settings apply to runs of text with the langId attribute of the rPr element ("ECMA-376 Part 4 §5.1.5.3.9; rPr (Text Run Properties)") equal to one of the following: zh-tw (Chinese (Traditional, Taiwan)) zh-hk (Chinese (Traditional, Hong Kong SAR)) zh-mo (Chinese (Traditional, Macao)) |

The value is case insensitive.

2.1.1137 Part 4 Section 4.3.1.17, modifyVerifier (Modification Verifier)

a. *The standard states that the algIdExt attribute specifies that a cryptographic algorithm not defined in the standard has been used to generate the hash value stored with the document.*

PowerPoint further requires that the algIdExt attribute specifies a hashing algorithm which is implemented by a CryptoAPI provider, and if the algIdExt attribute is used, the cryptProviderTypeExt attribute shall specify the provider.

b. *The standard states that the algIdExtSource attribute specifies the application which defined the algorithm value specified by the algIdExt attribute.*

PowerPoint requires that the value of the algIdExtSource attribute, if used, be wincrypt.

This note applies to the following products: 2007, 2007 SP1.

c. *The standard states that the cryptProviderTypeExtSource attribute specifies the application which defined the provider type value specified by the cryptProviderTypeExt attribute.*

PowerPoint requires that the value of the cryptProviderTypeExtSource attribute, if used, be wincrypt.

This note applies to the following products: 2007, 2007 SP1.

d. *The standard describes the hashData attribute as the hash value for the password stored within the document.*

In Office, the hashData value is the Base64 encoded representation of the binary hashing algorithm output, which is calculated as follows:

$$H[\text{init}] = H(\text{password}, \text{salt})$$

Followed by spinCount cycles where:

$$H[n] = H(H[n-1], \text{count})$$

Count shall begin with 0x0 and is expressed as a little-endian 32-bit integer. The initial hashing operation shall not be included in count.

e. *The standard states that the saltData attribute is a random string.*

PowerPoint defines the saltData attribute as random base 64-encoded data (typically 16 bytes), and the binary form of this attribute (not the base 64-encoded version) is used by the hashing algorithm.

f. *The standard specifies that the spinCount attribute specifies the number of times the hashing function shall be iteratively run when attempting to compare a user-supplied password with the value stored in the hashData attribute.*

PowerPoint does not include the initial hash of the password with the salt in this count.

g. *The standard lists several possible values for the cryptAlgorithmSid attribute.*

PowerPoint only uses values 1, 2, 3, 4, 12, 13, and 14.

h. *The standard states that this setting uses a specific set of attributes to store the password hash.*

In Office, when the HKCU/Software/Microsoft/Office/<VERSION>/Common/Security/UseIsoPasswordVerifier registry key is set to 1, the XML for file sharing is written by using the XML attribute structure in the following table.

| Name | Description |
|-----------------------|--|
| algorithm Name | <p>The name of the cryptographic hashing algorithm used to generate the hash value. Only those algorithms that are installed in the operating system's cryptographic subsystem can be utilized by Office.</p> <p>The following hash algorithms are reserved:</p> <p>MD2 <i>Specifies that the MD2 algorithm, as defined by RFC 1319, shall be used.</i> <i>[Note: It is recommended that applications should avoid using this algorithm to store new hash values, because of publicly known breaks. end note]</i></p> <p>MD4 <i>Specifies that the MD4 algorithm, as defined by RFC 1320, shall be used.</i> <i>[Note: It is recommended that applications should avoid using this algorithm to store new hash values, because of publicly known breaks. end note]</i></p> <p>MD5 <i>Specifies that the MD5 algorithm, as defined by RFC 1321, shall be used.</i> <i>[Note: It is recommended that applications should avoid using this algorithm to store new hash values, because of publicly known breaks. end note]</i></p> <p>RIPEMD-128 <i>Specifies that the RIPEMD-128 algorithm, as defined by ISO/IEC 10118-3:2004 shall be</i></p> |

| Name | Description |
|-------------------|---|
| | <p><i>used.</i></p> <p><i>[Note: It is recommended that applications should avoid using this algorithm to store new hash values, because of publicly known breaks. end note]</i></p> <p>RIPEMD-160</p> <p><i>Specifies that the RIPEMD-160 algorithm, as defined by ISO/IEC 10118-3:2004, shall be used.</i></p> <p>SHA-1</p> <p><i>Specifies that the SHA-1 algorithm, as defined by ISO/IEC 10118-3:2004, shall be used.</i></p> <p>SHA-256</p> <p><i>Specifies that the SHA-256 algorithm, as defined by ISO/IEC 10118-3:2004, shall be used.</i></p> <p>SHA-384</p> <p><i>Specifies that the SHA-384 algorithm, as defined by ISO/IEC 10118-3:2004, shall be used.</i></p> <p>SHA-512</p> <p><i>Specifies that the SHA-512 algorithm, as defined by ISO/IEC 10118-3:2004, shall be used.</i></p> <p>WHIRLPOOL</p> <p><i>Specifies that the WHIRLPOOL algorithm, as defined by ISO/IEC 10118-3:2004, shall be used.</i></p> |
| hash Value | <p>Specifies the hash value for the password required to edit this worksheet. This value shall be compared with the resulting hash value after hashing the user-supplied password using the algorithm specified by the preceding attributes and parent XML element. If the two values match, the protection shall no longer be enforced.</p> <p>If this value is omitted, then the reservationPassword attribute shall contain the password hash for the workbook.</p> <p><i>[Example: Consider an Office Open XML document with the following information stored in one of its protection elements:</i></p> <pre data-bbox="402 995 1295 1024"><... algorithmName="SHA-1" hashValue="9oN7nWkCAyEZib1RomSJTjmPpCY=" /></pre> <p>The hashValue attribute value of 9oN7nWkCAyEZib1RomSJTjmPpCY= specifies that the user-supplied password must be hashed using the pre-processing defined by the parent element (if any) followed by the hashing algorithm (specified via the algorithmName attribute value) and that the resulting hash value must be match for the protection to be disabled.</p> <p><i>end example]</i></p> <p>The possible values for this attribute are defined by the W3C XML Schema base64Binary datatype.</p> |
| saltValue | <p>Specifies the random bytes that are pre-pended to the user-supplied password before it was hashed by the hashing algorithm.</p> |
| spinCount | <p>Specifies the number of times the hashing function shall be iteratively run (using each iteration's result as the input for the next iteration).</p> |

[Example:

Consider an Office Open XML document with the following information stored in one of its protection elements:

```
< ... algorithmName="SHA-1" hashValue="9oN7nWkCAyEZib1RomSJTjmPpCY=" />
```

The algorithmName attribute value of SHA-1 specifies that the SHA-1 hashing algorithm must be used to generate a hash from the user-defined password.

end example]

This note applies to the following products: 2007 SP2, 2010.

2.1.1138 Part 4 Section 4.3.1.20, notesSz (Notes Slide Size)

a. *The standard states that the values of the cx attribute are defined by the ST_PositiveCoordinate simple type.*

PowerPoint defines the values of the cx attribute with the ST_SlideSizeCoordinate simple type.

b. *The standard states that the values of the cy attribute are defined by the ST_PositiveCoordinate simple type.*

PowerPoint defines the values of the cy attribute with the ST_SlideSizeCoordinate simple type.

c. *The standard states that the cx attribute specifies the length of the extents rectangle in EMUs.*

PowerPoint uses the cx attribute to specify the width of the rectangle.

d. *The standard states that the cy attribute specifies the width of the extents rectangle in EMUs.*

PowerPoint uses the cy attribute to specify the height of the rectangle.

2.1.1139 Part 4 Section 4.3.1.22, photoAlbum (Photo Album Information)

a. *The standard states that images that are part of the photo album are identified by the presence of the isPhoto element in the definition of the picture.*

PowerPoint identifies photo album images as those with the isPhoto attribute of the nvPr element set to a value of true.

b. *The standard states that the bw attribute specifies whether all pictures in the photo album are to be displayed as black and white.*

PowerPoint uses the bw attribute to specify the last state of a user interface setting that indicates whether all pictures in the photo album are to be displayed as black and white.

c. *The standard states that the frame attribute specifies the frame type that is to be used on all the pictures in the photo album.*

PowerPoint uses the frame attribute to specify the last state of a user interface setting for the frame type that is to be used on all the pictures in the photo album.

d. *The standard states that the layout attribute specifies the layout that is to be used to arrange the pictures in the photo album on individual slides.*

PowerPoint uses the layout attribute to specify the last state of a user interface setting for the layout that is to be used to arrange the pictures in the photo album on individual slides.

e. *The standard states that the showCaptions attribute specifies whether to show captions for pictures in the photo album.*

PowerPoint uses the showCaptions attribute to specify the last state of a user interface setting that indicates whether to show captions for pictures in the photo album.

2.1.1140 Part 4 Section 4.3.1.23, present (Presenter Slide Show Mode)

- a. *The standard states that when in full-screen presenter mode, the presentation is displayed on one monitor while a different monitor displays notes and provides navigation controls.*

PowerPoint does not display the presentation and the notes and navigation controls on separate monitors in this mode.

2.1.1141 Part 4 Section 4.3.1.24, presentation (Presentation)

- a. *The standard states that possible values for the firstSlideNum attribute are defined by the XML Schema int datatype.*

PowerPoint restricts the value of the firstSlideNum attribute to be greater than or equal to 0 and less than or equal to 9999.

- b. *The standard states that the values of the serverZoom attribute are defined by the ST_Percentage simple type.*

PowerPoint defines the values of the serverZoom attribute with the ST_PositivePercentage simple type.

- c. *The standard states that the showSpecialPlsOnTitleSld attribute specifies whether to show the header and footer placeholders on the title slides.*

PowerPoint uses the showSpecialPlsOnTitleSld attribute to specify the last state of the user interface setting which indicates whether to show the header and footer placeholders on the title slides.

- d. *The standard states that the strictFirstAndLastChars attribute specifies whether to use strict characters for starting and ending lines of Japanese text.*

PowerPoint ignores the strictFirstAndLastChars attribute when the lang attribute on the kinsoku element has a value of ja-jp.

2.1.1142 Part 4 Section 4.3.1.34, sldSz (Presentation Slide Size)

- a. *The standard states that the type attribute specifies the type of slide size that should be used.*

PowerPoint only uses the type attribute when the cx attribute and the cy attribute map to more than one type.

- b. *The standard states that the cy attribute specifies the width of the extents rectangle in EMUs.*

PowerPoint uses the cy attribute to specify the height of the rectangle.

- c. *The standard states that the cx attribute specifies the length of the extents rectangle in EMUs.*

PowerPoint uses the cx attribute to specify the width of the rectangle.

- d. *The standard states that the sldSz element specifies the size of the presentation slide surface.*

PowerPoint assumes a default of `<p:sldSz cx="9144000" cy="6858000" />` if the sldSz element is not present.

2.1.1143 Part 4 Section 4.3.1.35, smartTags (Smart Tags)

- a. *The standard states that the id attribute specifies the relationship identifier that is used in conjunction with a corresponding relationship file to resolve the location of the smart tag.*

The id attribute of the smartTags element defines a relationship to a part within the presentation package whose contents are defined by the PowerPoint 97-2003 Binary File Format (.ppt) Structure Specification ("[MS-PPT] section 2.11.28; SmartTagStore11Container"). This binary part contains no RecordHeader structure.

2.1.1144 Part 4 Section 4.3.2.3, gridSpacing (Grid Spacing)

- a. *The standard states that the values of the cx and cy attributes are defined by the ST_PositiveCoordinate simple type.*

PowerPoint defines the cx and cy attributes as representing a grid coordinate in EMU*1024 units, with a minimum value of greater than or equal to 36868100 and a maximum value of less than or equal to 1872691200.

This note applies to the following products: 2007, 2007 SP1.

2.1.1145 Part 4 Section 4.3.2.4, guide (A Guide)

- a. *The standard does not state how to interpret the position information of the pos attribute.*

PowerPoint interprets the position information to be relative to the top, left corner of the slide.

2.1.1146 Part 4 Section 4.3.2.5, guideLst (List of Guides)

- a. *The standard places no restrictions on the number of children the guideLst element has.*

PowerPoint only uses the first eight horizontal guides and first eight vertical guides from the child list.

This note applies to the following products: 2007, 2007 SP1.

2.1.1147 Part 4 Section 4.3.2.6, normalViewPr (Normal View Properties)

- a. *The standard states that the showOutlineIcons attribute specifies whether the application should show icons if displaying outline content in any of the content regions of normal view mode.*

PowerPoint interprets the value of the showOutlineIcons attribute to be true.

This note applies to the following products: 2007, 2007 SP1.

- b. *The standard states that the vertBarState attribute affects the state of the slide region.*

PowerPoint uses the vertBarState attribute to affect the state of the side content region.

- c. *The standard states that the horzBarState attribute affects the state of the side content region.*

PowerPoint uses the horzBarState attribute to affect the state of the slide region.

- d. *The standard places no restrictions on the relationship between the horzBarState attribute and the restoredTop child element.*

PowerPoint ignores the restoredTop child element when the value of the horzBarState attribute is minimized or maximized.

e. *The standard places no restrictions on the relationship between the vertBarState attribute and the restoredLeft child element.*

PowerPoint ignores the restoredLeft child element when the value of the vertBarState attribute is minimized or maximized.

2.1.1148 Part 4 Section 4.3.2.9, origin (View Origin)

For additional notes that apply to this portion of the standard, please see the notes for [chOff](#), [§5.1.9.2\(b\)](#).

2.1.1149 Part 4 Section 4.3.2.11, restoredLeft (Normal View Restored Left Properties)

For additional notes that apply to this portion of the standard, please see the notes for [restoredTop](#), [§4.3.2.12\(a\)](#).

a. *The standard states that the sz attribute specifies the size of the slide region.*

PowerPoint uses the sz attribute to specify the height of the slide region when the sz attribute is a child of the restoredTop element and width of the slide region when @sz is a child of the restoredLeft element.

2.1.1150 Part 4 Section 4.3.2.12, restoredTop (Normal View Restored Top Properties)

For additional notes that apply to this portion of the standard, please see the notes for [restoredLeft](#), [§4.3.2.11\(a\)](#).

a. *The standard states that the autoAdjust attribute specifies the size of the side content region.*

PowerPoint interprets the autoAdjust attribute to specify the size of the slide region, not the side content region.

2.1.1151 Part 4 Section 4.3.2.13, scale (View Scale)

a. *The standard states that the scale element specifies the view scaling factors that the presentation was last viewed with.*

PowerPoint requires that the ratio value of child element sx and child element sy shall not be less than 0.03 or greater than 5.

b. *The standard states that the values of the n attribute on the sx and sy child elements are defined by the XML Schema long datatype.*

PowerPoint defines the values of the n attribute with the XML Schema int datatype.

c. *The standard states that the values of the d attribute on the sx and sy child elements are defined by the XML Schema long datatype.*

PowerPoint defines the values of the d attribute with the XML Schema int datatype.

2.1.1152 Part 4 Section 4.4.1.1, bg (Slide Background)

a. *The standard states that the bwMode attribute specifies that the background should be rendered using only black and white coloring.*

PowerPoint uses the bwMode attribute to specify how the background should be rendered when in black and white mode.

2.1.1153 Part 4 Section 4.4.1.2, bgPr (Background Properties)

a. *The standard states the grpFill element is a valid child of the bgPr element.*

PowerPoint does not allow the grpFill element to be a child of the bgPr element.

2.1.1154 Part 4 Section 4.4.1.4, blipFill (Picture Fill)

For additional notes that apply to this portion of the standard, please see the notes for [blipFill](#), §5.8.2.2(a).

2.1.1155 Part 4 Section 4.4.1.15, cSld (Common Slide Data)

a. *The standard states that the controls element is a valid child of the cSld element.*

PowerPoint does not allow the controls element to be a child of the cSld element when the cSld's parent element is the handoutMaster element, the notes element, or the notesMaster element.

2.1.1156 Part 4 Section 4.4.1.20, grpSpPr (Group Shape Properties)

For additional notes that apply to this portion of the standard, please see the notes for [grpSpPr](#), §5.6.2.17(a-c).

2.1.1157 Part 4 Section 4.4.1.24, notesMaster (Notes Master)

a. *The standard states that the notesMaster element specifies an instance of a handout master slide.*

PowerPoint uses the notesMaster element to specify an instance of a notes master slide.

2.1.1158 Part 4 Section 4.4.1.25, notesStyle (Notes Text Style)

a. *The standard states that the notesStyle element specifies the text formatting style for all text within a notes slide.*

PowerPoint uses the notesStyle element to specify the text in the notes section of the notes page view and the notes master view.

2.1.1159 Part 4 Section 4.4.1.30, nvPr (Non-Visual Properties)

a. *The standard states that the userDrawn attribute specifies if the corresponding object has been drawn by the user.*

PowerPoint only uses the userDrawn attribute when nvPr's parent element is either the sldMaster element or the sldLayout element.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

b. *The standard states that the isPhoto attribute specifies whether the picture belongs to a photo album.*

PowerPoint does not support the isPhoto attribute when nvPr's parent element is the nvGrpSpPr element.

c. *The standard states that the ph element is a valid child of the nvPr element.*

PowerPoint does not allow the ph element to be a child of the nvPr element when the nvPr's parent element is the nvCxnSpPr element or the nvGrpSpPr element.

2.1.1160 Part 4 Section 4.4.1.33, ph (Placeholder Shape)

a. *The standard states that the placeholder idx attribute specifies the placeholder index.*

The following additional restrictions apply to values on the idx attribute:

For a placeholder on a Master, Notes Master, Handout Master, Slide Layout or Notes Slide the value shall not be equal to 0xffffffff.

For any two placeholders on a Master, Notes Master, Handout Master, Slide Layout or Notes Slide the values must not be the same.

For any two placeholders on a Slide with values not equal to 0xffffffff the values shall not be the same.

For a placeholder on a Slide with a value not equal to 0xffffffff there shall be a placeholder on the Slide Layout with the same attribute values.

b. *The standard does not specify the inheritance model of a placeholder shape.*

PowerPoint defines a placeholder shape on a slide to inherit from the slide layout placeholder with the same idx value, and a placeholder shape on a notes slide to inherit from the notes master placeholder with the same type value.

2.1.1161 Part 4 Section 4.4.1.35, sld (Presentation Slide)

a. *The standard states that the sld element specifies a slide within a slide list, where the slide list is used to specify an ordering of slides.*

PowerPoint uses this element to specify the root element of a slide part.

2.1.1162 Part 4 Section 4.4.1.41, spPr (Shape Properties)

For additional notes that apply to this portion of the standard, please see the notes for [spPr, §5.6.2.29\(a-c\)](#).

2.1.1163 Part 4 Section 4.4.1.46, transition (Slide Transition for a Slide Layout)

a. *The standard states that the values of the advTm attribute are defined by the XML Schema unsignedInt datatype.*

PowerPoint requires that the value of the advTm attribute be greater than or equal to 0 and less than or equal to 2147483647.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.1164 Part 4 Section 4.4.1.49, xfrm (2D Transform for Graphic Frame)

For additional notes that apply to this portion of the standard, please see the notes for [xfrm](#), §5.1.9.6(a).

2.1.1165 Part 4 Section 4.4.2.1, control (Embedded Control)

For additional notes that apply to this portion of the standard, please see the notes for [oleObj](#), §4.4.2.4(a,c, d).

a. *The standard states that the showAsIcon attribute specifies whether the Embedded object will be shown as an icon or using its native representation.*

PowerPoint uses the showAsIcon attribute to specify the user preference to show the Embedded object as an icon rather than using its native representation.

b. *The standard states that the imgW attribute specifies the width of the embedded control.*

PowerPoint uses the imgW attribute to specify the width of the thumbnail image.

c. *The standard states that the imgH attribute specifies the height of the embedded control.*

PowerPoint uses the imgH attribute to specify the height of the thumbnail image.

2.1.1166 Part 4 Section 4.4.2.2, embed (Embedded Object or Control)

a. *The standard states that the embed element specifies an Embedded object or Control that is embedded within the presentation.*

PowerPoint uses the embed element to specify an OLE object that is embedded within the presentation.

2.1.1167 Part 4 Section 4.4.2.3, link (Linked Object or Control)

a. *The standard states that the link element specifies a link to an external Embedded object or Control.*

PowerPoint the link this element to specify a link to an external OLE object.

2.1.1168 Part 4 Section 4.4.2.4, oleObj (Global Element for Embedded objects and Controls)

For additional notes that apply to this portion of the standard, please see the notes for [control](#), §4.4.2.1(a-c).

a. *The standard states that the spid attribute specifies the identifier of the shape associated with an Embedded object.*

PowerPoint requires that the spid identifier must match the shape identifier defined in the legacy drawing VML part for the Embedded object.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

b. *The standard states that the oleObj element specifies a global element to be used for an Embedded object and Control.*

PowerPoint uses the oleObj element to specify a global element to be used for an OLE object.

c. *The standard states that the imgW attribute specifies the width of the embedded control.*

PowerPoint uses the imgW attribute to specify the width of the thumbnail image.

d. *The standard states that the imgH attribute specifies the height of the embedded control.*

PowerPoint uses the imgH attribute to specify the height of the thumbnail image.

e. *The standard states that the showAsIcon attribute specifies whether the Embedded object will be shown as an icon or using its native representation.*

PowerPoint uses the showAsIcon attribute to specify the user preference to show the Embedded object as an icon rather than using its native representation.

2.1.1169 Part 4 Section 4.4.3.1, tag (Programmable Extensibility Tag)

a. *The standard implies that the name attribute is optional.*

PowerPoint requires the name attribute.

b. *The standard implies that the val attribute is optional.*

PowerPoint requires the val attribute.

c. *The standard places no restrictions on the string value of the name attribute.*

PowerPoint requires that, within the scope of the tagLst parent element, the value for the name attribute must be case-insensitively unique.

d. *The standard does not specify where recorded slide animation timings are stored.*

PowerPoint uses a special tag to store slide auto advance timings for the presentation slide that contains this tag. The name attribute has a value of "TIMING," and the value attribute has a value that is a valid Time_string, as specified in the following grammar:

Time_string = *Time_element ; time string can have zero or more elements

Time_element = "|" Time_value ; each element is preceded by character "|"

Time_value = 1*DIGIT "." 1*1 DIGIT ; seconds with rounding to 1/10th of a second

Each time value specifies the animation build advance time of the slide. Time zero is the time that this slide displays during a slide show. The time unit is in seconds, rounded to 1/10th of a second. If there is no animation on a presentation slide, the value attribute contains an empty string.

[Example:

```
<p:tag name="TIMING" val="|2.9|3.5|4.6"/>
```

end example.]

2.1.1170 Part 4 Section 4.5.1, cm (Comment)

- a. *The standard states that the dt attribute is optional.*

PowerPoint requires the dt attribute.

This note applies to the following products: 2007, 2007 SP1.

- b. *The standard does not state how to interpret the position information of the pos child element.*

PowerPoint interprets the position information to be relative to the top, left corner of the slide.

2.1.1171 Part 4 Section 4.5.5, pos (Comment Position)

For additional notes that apply to this portion of the standard, please see the notes for [chOff](#), [§5.1.9.2\(b\)](#).

- a. *The standard states that the y attribute specifies a coordinate on the x-axis.*

PowerPoint uses this attribute to specify a coordinate on the y-axis.

2.1.1172 Part 4 Section 4.6.1, anim (Animate)

For additional notes that apply to this portion of the standard, please see the notes for [tnLst](#), [§4.6.87\(b\)](#).

- a. *The standard states that the to attribute specifies the ending value for the animation as a percentage.*

PowerPoint does not specify the ending value as a percentage.

- b. *The standard does not state a default value for the calcmode attribute.*

PowerPoint uses a default value of lin for the calcmode attribute.

- c. *The standard does not state a default value for the valueType attribute.*

PowerPoint uses a default value of num for the valueType attribute.

- d. *The standard states that the values of the from attribute are defined by the XML Schema string datatype.*

PowerPoint requires that the value of the from attribute be specified as a preset string value, as specified in the to element; as a string that represents a color value and a real number, as specified in the to element; or as an arbitrary string.

- e. *The standard states that the values of the by attribute are defined by the XML Schema string datatype.*

PowerPoint requires that the value of the by attribute be specified as a preset string value, as specified in the to element; as a string that represents a color value and a real number, as specified in the to element; or as an arbitrary string.

- f. *The standard states that the values of the to attribute are defined by the XML Schema string datatype.*

PowerPoint requires that the value of the to attribute be specified as a preset string value, as specified in the to element; as a string that represents a color value and a real number, as specified in the to element; or as an arbitrary string.

g. *The standard places no restrictions on the number of attrName child elements parented by the attrNameLst element when inside the anim element.*

PowerPoint requires that there be at least one attrName child element of the attrNameLst element when inside an anim element; if more than one attrName child element exists, only the first will be used.

h. *The standard places no restrictions on the relationship between the by, from, and to attributes.*

The attributes from, to, and by must be used in one of the following combinations:

from_to: when the from and to attributes have values of the same type;

from_by: when the from and by attributes have values of the same type but the to attribute is undefined;

to_only: when the to attribute is defined but the from attribute is undefined;

by_only: when the by attribute is defined but the from and to attributes are undefined.

All other combinations are invalid.

When the attributes are used with a to_only combination or a by-only combination, the following criteria determine the starting value of the animation:

when the attribute valueType is num, the starting value is 0.0;

when the attribute valueType is clr, the starting value is an HSL color in which all spectrum is 0;

when the attribute valueType is str, the starting value is an empty string.

The attribute by is not used in from_to and to_only combinations.

i. *The standard places no restrictions on what the grpId attribute refers to.*

PowerPoint requires that the grpId attribute reference a group that is present in the timing tree.

2.1.1173 Part 4 Section 4.6.2, animClr (Animate Color Behavior)

For additional notes that apply to this portion of the standard, please see the notes for [tnLst](#), [§4.6.87\(b\)](#).

a. *The standard does not state a default value for the clrSpc attribute.*

PowerPoint uses a default value of rgb for the clrSpc attribute.

b. *The standard places no restrictions on the value of the attrNameLst element when inside the animClr element.*

PowerPoint requires that the valid values of the attrNameLst element are: style.color, fillcolor, and stroke.color. The attrNameLst element must have at least one of these values and only the first one is effective (additional are ignored).

c. *The standard does not specify how to interpret the from child element, the to child element, or the by child element of the animClr element.*

In Office, the child element from defines the animation starting color, child element to defines the animation ending color, and child element by defines a color value that shall be added to the starting color to reach the ending color.






If the child element from is not specified, color black is used as the starting color. Either the child element to or the child element by shall be specified. If both the by and the to elements are specified, the by element is ignored.











2.1.1174 Part 4 Section 4.6.3, animEffect (Animate Effect)











For additional notes that apply to this portion of the standard, please see the notes for [tnLst, §4.6.87\(b\)](#).

a. *The standard states that the filter attribute specifies the named transitions for the effect.*




Office uses the following object transitions & subtypes:

| Value | Description |
|----------------------|--|
| blinds(horizontal) |  |
| blinds(vertical) |  |
| box(in) |  |
| box(out) |  |
| checkerboard(across) |  |

| Value | Description |
|--------------------|--|
| checkerboard(down) |  |
| circle(in) |  |
| circle(out) |  |
| diamond(in) |  |
| diamond(out) |  |
| dissolve |  |
| fade |  |
| slide(fromTop) |  |
| slide(fromBottom) |  |
| slide(fromLeft) |  |

| Value | Description |
|-----------------------|--|
| slide(fromRight) |  |
| plus(in) |  |
| plus(out) |  |
| barn(inVertical) |  |
| barn(inHorizontal) |  |
| barn(outVertical) |  |
| barn(outHorizontal) |  |
| randombar(horizontal) |  |
| randombar(vertical) |  |
| strips(downLeft) |  |

| Value | Description |
|-------------------|-------------|
| strips(upLeft) | |
| strips(downRight) | |
| strips(upRight) | |
| wedge | |
| wheel(1) | |
| wheel(2) | |
| wheel(3) | |
| wheel(4) | |
| wheel(8) | |
| wipe(right) | |

| Value | Description |
|------------|--|
| wipe(left) |  |
| wipe(up) |  |
| wipe(down) |  |

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.1175 Part 4 Section 4.6.4, animMotion (Animate Motion)

For additional notes that apply to this portion of the standard, please see the notes for [tnLst, §4.6.87\(b\)](#).

- a. The standard does not state a default value for the origin attribute.

PowerPoint uses a default value of parent for the origin attribute.

- b. The standard states that the path attribute of the animMotion element specifies a path primitive for the animation motion.

In Office, the path is specified by defining an action, and typically some coordinates that go along with the action.

The allowed action types that are understood within a path are listed in the following table. If the action is expressed in UPPERCASE, the following point(s) are to be interpreted as absolute coordinates, or a point on the slide. If in lowercase, the point(s) are to be interpreted as relative coordinates, or an offset from the current position.

| Action Types | |
|------------------------|--|
| M = move to | This action requires a point (two coordinates). Move to will move the object to the specified point. It does not animate the object to that point; rather, the object will snap to the given point. |
| L = line to | This action requires a point (two coordinates). Line to will move the object to the specified point along the shortest line between the current point and the specified point. |
| C = curve to | This action requires three points (six coordinates). Curve to will move the object along a cubic Bezier curve specified by the current point and the three provided points. |
| Z =close | This action requires no points. |

| Action Types | |
|--------------|---|
| loop | Close loop will move the object back to where it was before the path began along the shortest line between the current point and the starting point. The relative (lowercase) and absolute (uppercase) versions of this action are identical. |
| E=end | This action requires no points. End will terminate the motion path. Any action specified in the string after the End action is ignored. The specification of this action is not required. If this action is not present at the end of a string and the string ends, this action will be implied. The relative and absolute versions of this action are identical. |

Points are expressed as percentages of the slide size; 1,1 means the lower-right corner of the slide in absolute coordinates, or the slide width & height in relative coordinates. Expressing a coordinate less than 1 but greater than 0 must be prefixed with 0 before the decimal point. If the leading zero is left off, the decimal is thrown away and the coordinate is read without it.

Formulas can also be used here. To use a formula, the entire formula must be inside parentheses. Parentheses can be used inside the formula, but no greater than a depth of 255. Formula syntax is further detailed in the entry for `tav` (Time Animate Value) ("[ECMA-376](#) Part 4 §4.6.79; `tav` (Time Animate Value)").

If the requirements for an action are not met (that is, too many or too few points are specified,) the entire path shall be thrown away.

If the path string is left empty or not specified, the animation will do nothing, but shall take up the required amount of time as specified by the behavior.

c. *The standard does not state a default value for the `pathEditMode` attribute.*

PowerPoint uses a default value of relative for the `pathEditMode` attribute.

d. *The standard states that the `ptsTypes` attribute specifies the types of points in the path attribute.*

In Office, the `ptsTypes` attribute additionally describes what the motion path should look like around the current point. This attribute has no effect on the playing of the animation. It is only used when the motion path is edited in Office.

Each character in this string sequentially maps to a point defined in the path string. If there are more entries than points, the extra entries are ignored. If there are fewer entries than points, the extra points are to be treated as follows: If the action *after* the point is a Line To, then the point is treated as an 'F' (corner line). Otherwise, the point will be treated as an 'f' (corner curve).

e. *The standard does not state a default value for the `rAng` attribute.*

PowerPoint uses a default value of 0 for the `rAng` attribute.

f. *The standard states that the `animMotion` element provides an abstract way to move positioned elements via a set of attributes and child elements.*

The `attrNameLst` element in the `cBhvr` child is permitted to contain up to two attributes to be animated. If the first attribute is not specified, the `ppt_x` attribute will be used. If the second attribute is not specified, the `ppt_y` attribute will be used. If more than two attributes are specified, only the first two shall be used. The attributes used must be one of the following: `ppt_x`, `ppt_y`, `ppt_w`, `ppt_h`, `ppt_r`, `style.fontSize`, `xskew`, `yskew`, `xshear`, `yshear`, `scaleX`, or `scaleY`.

g. *The standard states that the from element is a valid child of the animMotion element.*

PowerPoint ignores the from element when parented by the animMotion element.

This note applies to the following products: 2007, 2007 SP1.

h. *The standard states that the by element is a valid child of the animMotion element.*

PowerPoint ignores the by element when parented by the animMotion element.

This note applies to the following products: 2007, 2007 SP1.

i. *The standard states that the to element is a valid child of the animMotion element.*

PowerPoint ignores the to element when parented by the animMotion element.

This note applies to the following products: 2007, 2007 SP1.

j. *The standard states that the values of the rAng attribute are defined by the ST_Angle simple type.*

PowerPoint restricts the value of the rAng attribute to be between the range of -2147483554 and 2147483554; if the value is less than -15360000 or greater than 15360000, it will lose precision due to internal calculations.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.1176 Part 4 Section 4.6.5, animRot (Animate Rotation)

For additional notes that apply to this portion of the standard, please see the notes for [tnLst, §4.6.87\(b\)](#).

a. *The standard states that the values of the from attribute are defined by the ST_Angle simple type.*

PowerPoint restricts the value of the from attribute to be between the range of -2147483554 and 2147483554; if the value is less than -15360000 or greater than 15360000, it will lose precision due to internal calculations.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

b. *The standard states that the values of the to attribute are defined by the ST_Angle simple type.*

PowerPoint restricts the value of the to attribute to be between the range of -2147483554 and 2147483554; if the value is less than -15360000 or greater than 15360000, it will lose precision due to internal calculations.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

c. *The standard states that the values of the by attribute are defined by the ST_Angle simple type.*

PowerPoint restricts the value of the by attribute to be between the range of -2147483554 and 2147483554; if the value is less than -15360000 or greater than 15360000, it will lose precision due to internal calculations.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

d. *The standard places no restrictions on the value of the attrName element when inside the animRot element.*

PowerPoint requires that the value of the attrName element be ppt_r, r, or style.rotation when inside an animRot element.

e. *The standard states that the animRot element specifies the rotation animation on an element with a combination of from, to and by attributes.*

In Office, the three attributes, from(From), to(To), and by(By), shall be used in one of the following combinations:

from_to: when from(From) and to(To) are defined;

from_by: when from(From) and by(By) are defined but to(To) is undefined;

to_only: when to(To) is defined but from(From) is undefined;

by_only: when by(By) is defined but from(From) and to(To) are undefined.

All other combinations are invalid.

For to_only and by_only combinations, the starting value of the animation shall be 0. The attribute by(By) is not used in from_to and to_only combinations.

f. *The standard places no restrictions on the number of attrName child elements parented by the attrNameLst element when inside the animRot element.*

PowerPoint requires that there be at least one attrName child element of the attrNameLst element when inside an animRot element; if more than one attrName child element exists, only the first will be used.

2.1.1177 Part 4 Section 4.6.6, animScale (Animate Scale)

For additional notes that apply to this portion of the standard, please see the notes for [tnLst](#), [§4.6.87\(b\)](#).

a. *The standard places no restrictions on the number of attrName child elements parented by the attrNameLst element when inside the animScale element, nor what the values of those attrName elements should be.*

PowerPoint requires that there be at least two attrName child elements of the attrNameLst element when inside an animScale element; their values should be ScaleX and ScaleY.

b. *The standard states that the zoomContents attribute specifies whether to zoom the contents of an object when doing a scaling animation.*

PowerPoint does not support the zoomContents attribute.

c. *The standard states that the animScale element specifies the scale animation of an object.*

In Office, the three attributes from(From), to(To), and by(By) must be used in one of the following combinations:

from_to: when from(From) and to(To) are defined;

from_by: when from(From) and by(By) are defined but to(To) is undefined;

to_only: when to(To) is defined but from(From) is undefined;

by_only: when by(By) is defined but from(From) and to(To) are undefined.

All other combinations are invalid.

For to_only, the starting value of animation is (0, 0) for "ScaleX" and "ScaleY". For by_only, the starting value of animation is (1, 1) for "ScaleX" and "ScaleY". The attribute by(By) is ignored in from_to and to_only combinations.

2.1.1178 Part 4 Section 4.6.7, attrName (Attribute Name)

a. *The standard specifies a list of allowed property values for the attrName element.*

PowerPoint also allows the following values for this element: ppt_x, ppt_y, ppt_w, ppt_h, ppt_c, ppt_r, xshear, yshear, image, ScaleX, ScaleY, r, and fillcolor.

b. *The standard does not specify whether the attrName values are case-sensitive.*

PowerPoint treats these values as case-insensitive.

2.1.1179 Part 4 Section 4.6.9, audio (Audio)

For additional notes that apply to this portion of the standard, please see the notes for [tnLst](#), [§4.6.87\(b\)](#).

a. *The standard allows the isNarration attribute to be set to true on any audio element.*

The isNarration attribute can only be true if the <audio> element contains a child <cMediaNode> ("ECMA-376 Part 4 §4.6.29; cMediaNode (Common Media Node Properties)") with a child <tgtEl> ("ECMA-376 Part 4 §4.6.81; tgtEl (Target Element)") that contains a <spTgt> element ("ECMA-376 Part 4 §4.6.72; spTgt (Shape Target)") that points to a valid sound shape. A valid sound shape is a shape that includes as a child of the <nvPr> element ("ECMA-376 Part 4 §4.4.1.30; nvPr (Non-Visual Properties)") one of the following elements: <wavAudioFile> ("ECMA-376 Part 4 §5.1.3.7; wavAudioFile (Audio from WAV File)") or <audioFile> ("ECMA-376 Part 4 §5.1.3.2; audioFile (audio from File)").

2.1.1180 Part 4 Section 4.6.12, bldDgm (Build Diagram)

a. *The standard implies that the bldDgm element specifies how to build animation for any diagram.*

PowerPoint only uses this element for OLE diagrams.

b. *The standard places no restrictions on what the spid attribute refers to.*

PowerPoint requires that the spid attribute reference a valid OLE diagram that is present on the slide.

c. *The standard places no restrictions on the relationship between the spid attribute, the grpId attribute, and the parent bldLst element.*

PowerPoint requires that the combination of the spid attribute and the grpId attribute on a given bldDgm element form a unique pair within the parent bldLst element.

d. *The standard places no restrictions on what the grpId attribute refers to.*

PowerPoint requires that the grpId attribute reference a group that is present in the timing tree.

2.1.1181 Part 4 Section 4.6.13, bldGraphic (Build Graphics)

- a. *The standard places no restrictions on what the spid attribute refers to.*

PowerPoint requires that the spid attribute reference a chart or diagram that is present on the slide.

- b. *The standard places no restrictions on what the grpId attribute refers to.*

PowerPoint requires that the grpID attribute reference a group that is present in the timing tree.

- c. *The standard places no restrictions on the relationship between the spid attribute, the grpId attribute, and the parent bldLst element.*

PowerPoint requires that the combination of the spid attribute and the grpId attribute on a given bldGraphic element form a unique pair within the parent bldLst element.

2.1.1182 Part 4 Section 4.6.15, bldOleChart (Build Embedded Chart)

- a. *The standard places no restrictions on what the spid attribute refers to.*

PowerPoint requires that the spid attribute reference a shape that is present on the slide.

- b. *The standard places no restrictions on the relationship between the spid attribute, the grpId attribute, and the parent bldLst element.*

PowerPoint requires that the combination of the spid attribute and the grpId attribute on a given bldOleChart element form a unique pair within the parent bldLst element.

- c. *The standard states that the animBg attribute describes whether to animate the background of the shape.*

PowerPoint does not support the animBg attribute.

This note applies to the following products: 2007, 2007 SP1.

- d. *The standard places no restrictions on what the grpId attribute refers to.*

PowerPoint requires that the grpId attribute reference a group that is present in the timing tree.

2.1.1183 Part 4 Section 4.6.16, bldP (Build Paragraph)

- a. *The standard places no restrictions on what the spid attribute refers to.*

PowerPoint requires that the spid attribute reference a shape that is present on the slide.

- b. *The standard places no restrictions on the relationship between the spid attribute, the grpId attribute, and the parent bldLst element.*

PowerPoint requires that the combination of the spid attribute and the grpId attribute on a given bldP element form a unique pair within the parent bldLst element.

- c. *The standard places no restrictions on the shape to which the spid attribute refers.*

PowerPoint requires that the spid attribute refer to an sp element that contains a t element with valid textual data.

- d. *The standard does not specify how to interpret an advAuto attribute value of indefinite.*

PowerPoint interprets a value of indefinite on the advAuto attribute as being equal to 0.

e. *The standard states that the autoUpdateAnimBg attribute indicates whether to automatically update the animateBg setting to true when the shape associated with the text has a fill or line.*

PowerPoint does not support the autoUpdateAnimBg attribute.

f. *The standard places no restrictions on the tgtEl target element when the value of the animBg attribute is false.*

PowerPoint requires that the charRg child element inside the tgtEl target element be zero-length if the animBg attribute is set to false.

g. *The standard states that the bldLvl attribute is only supported when the build attribute is set to byParagraph.*

PowerPoint only supports the bldLvl attribute when the build attribute is set to p.

2.1.1184 Part 4 Section 4.6.17, bldSub (Build Sub Elements)

a. *The standard places no restrictions on the relationship between the bldSub's parent and child elements.*

PowerPoint requires that the spid attribute of the bldGraphic parent element must match the type of the bldSub child element.

2.1.1185 Part 4 Section 4.6.20, by (By)

For additional notes that apply to this portion of the standard, please see the notes for [rCtr, §4.6.62\(a\)](#).

a. *The standard states that the x attribute describes the X coordinate.*

PowerPoint uses the x attribute to specify the slide width percentage change when the by element is parented by the animMotion element, and the animated object width percentage change when the by element is parented by the animScale element.

b. *The standard states that the y attribute describes the Y coordinate.*

PowerPoint uses the y attribute to specify the slide height percentage change when the by element is parented by the animMotion element, and the animated object height percentage change when the by element is parented by the animScale element.

c. *The standard states that the x and y attributes are specified as ST_Percentage type.*

When used within animMotion, the attributes x and y specify the percentage change with respect to the slide size. These attributes, when used with animMotion shall be greater than -2147483625 and less than 2147483625. When used within animScale, the attributes x and y specify the percentage change with respect to the size of the animated object. These attribute values, when used with animScale shall be greater than 0 and less than 2147483625.

If the attribute values are less than -16384000 or greater than 16384000 they will lose some precision due to internal calculations.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.1186 Part 4 Section 4.6.22, cBhvr (Common Behavior)

a. *The standard states that the by attribute specifies a relative offset value for the animation.*

The string value represents a 2D point, for example "0.5 0.5" or "(#ppt_x-0.1, #ppt_w)". The two elements can be real numbers, or formula. They are separated either by space or by comma. When using a formula, it must be enclosed in parentheses. The format is specified as follows:

2d_point = 2d_point_number | 2d_point_formula ;

2d_point_number = real_number , (`` | ' ; ') , real_number ;

2d_point_formula = '(' , formula , (`` | ' ; ') , formula , ')' ;

real_number is further specified in 4.6.89-to(To)

formula is further specified in 4.6.79-tav(Time Animation Value)

b. *The standard states that the from attribute specifies a relative offset value for the animation.*

The string value represents a 2D point, for example "0.5 0.5" or "(#ppt_x-0.1, #ppt_w)". The two elements can be real numbers, or formula. They are separated either by space or by comma. When using a formula, it must be enclosed within parentheses. The format is specified as follows:

2d_point = 2d_point_number | 2d_point_formula ;

2d_point_number = real_number , (`` | ' ; ') , real_number ;

2d_point_formula = '(' , formula , (`` | ' ; ') , formula , ')' ;

real_number is further specified in 4.6.89-to(To)

formula is further specified in 4.6.79-tav(Time Animation Value)

c. *The standard states that the to attribute specifies a relative offset value for the animation.*

The string value represents a 2D point, for example "0.5 0.5" or "(#ppt_x-0.1, #ppt_w)". The two elements can be real numbers, or formula. They are separated either by space or by comma. When using a formula, it must be enclosed within parentheses. The format is specified as follows:

2d_point = 2d_point_number | 2d_point_formula ;

2d_point_number = real_number , (`` | ' ; ') , real_number ;

2d_point_formula = '(' , formula , (`` | ' ; ') , formula , ')' ;

real_number is further specified in 4.6.89-to(To)

formula is further specified in 4.6.79-tav(Time Animation Value)

d. *The standard does not state a default value for the additive attribute.*

PowerPoint uses a default value of base for the additive attribute.

e. *The standard does not state a default value for the accumulate attribute.*

PowerPoint uses a default value of none for the accumulate attribute.

f. *The standard does not state a default value for the xfrmType attribute.*

PowerPoint uses a default value of pt for the xfrmType attribute.

g. *The standard states that the rctx attribute describes the runtime context of the animation and that the understood values are PPT and IE.*

Office places additional restrictions on the format for the value of the rctx attribute as follows:

```
runtime_context = context_atom, { `;`, context_atom } [ `;` ];
context_atom = [ relation_operator, Space ], app_abbrev, [ Space , version ];
relation_operator = gte | gt | lte | lt | not;
app_abbrev = PPT_abbrev | IE_abbrev;
PPT_abbrev = ( `p` | `P` ), ( `p` | `P` ), ( `t` | `T` );
IE_abbrev = ( `i` | `I` ), ( `e` | `E` );
version = dec_number, [ `.` ], [ dec_number ];
dec_number = Digit, { Digit };
gte = `g`, `t`, `e`;
gt = `g`, `t`;
lte = `l`, `t`, `e`;
lt = `l`, `t`;
not = `!`;
Space = ` `, { `` };
Digit = `0` | `1` | `2` | `3` | `4` | `5` | `6` | `7` | `8` | `9`;
```

2.1.1187 Part 4 Section 4.6.23, charRg (Character Range)

For additional notes that apply to this portion of the standard, please see the notes for [pRg](#), [§4.6.56\(b\)](#).

a. *The standard places no restrictions on the values of the st and end attributes.*

PowerPoint requires the end attribute to be greater than the value of the st attribute and less than or equal to the length of the animated text.

2.1.1188 Part 4 Section 4.6.28, cmd (Command)

For additional notes that apply to this portion of the standard, please see the notes for [tnLst](#), [§4.6.87\(b\)](#).

a. *The standard states both that the type attribute is optional and required.*

PowerPoint does not require the type attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

b. *The standard does not state a default value for the type attribute.*

PowerPoint uses a default value of call for the type attribute.

c. The standard states that the cmd element describes the several non-durational type of commands that can be executed within a timeline.

This cmd attribute defines the actual command to be issued. Depending on the type of command specified, the actual command can be made to invoke a wide range of actions on the linked or embedded object.

Reserved Values (when **type** = "call"):

| Value | Description |
|--------------------|--|
| <i>play</i> | play corresponding media |
| <i>playFrom(s)</i> | play corresponding media starting from <i>s</i> , where <i>s</i> is the number of seconds from the beginning of the clip |
| <i>pause</i> | pause corresponding media |
| <i>resume</i> | resume play of corresponding media |
| <i>stop</i> | stop play of corresponding media |
| <i>togglePause</i> | play corresponding media if media is already paused, pause corresponding media if media is already playing. If the corresponding media is not active, this command will restart the media and play from its beginning. |

The <tgtEl> of this behavior shall be a valid media shape, and there shall be an associated <video> or <audio> node as a child of the root node in the timing tree for this to work properly.

Reserved Values (when **type** = "evt"):

| Value | Description |
|--------------------|------------------------|
| <i>onstopaudio</i> | stop play of all audio |

(When **type** = "verb"):

The value of the **cmd** attribute shall be the string representation of an integer that represents the embedded object verb number. This verb number will determine the action that the rendering application should take corresponding to this object when this point in the animation is reached.

[Example: Consider the following command

```
<p:cmd type="evt" cmd="onstopaudio">
  <p:cBhvr>
    <p:cTn display="0" masterRel="sameClick">
      <p:stCondLst>
        <p:cond evt="begin" delay="0">
          <p:tn val="5"/>
        </p:cond>
      </p:stCondLst>
    </p:cTn>
    <p:tgtEl>
      <p:sldTgt/>
    </p:tgtEl>
  </p:cBhvr>
</p:cmd>
```

</p:cBhvr>
</p:cmd>

end example]

In this example, the event of onstopaudio will stop all audio from playing once this particular animation is reached in the timeline.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

d. *The standard states that the type attribute defines the type of command to be used.*

In Office, this attribute specifies the type of command that will be issued by the rendering application to the appropriate target application or object.

There are three possible values, call, evt, and verb. A call type is used to specify the class of commands that can then be issued.

Call commands (type="call"): This command type is used to call methods on the object specified (play(), pause(), and so on)

Event Commands (type="evt"): This command type is used to set an event for the object at this point in the timeline (onstopaudio, and so on)

Verb Commands (type="verb"): This command type is used to set verbs for the object to occur at this point in the timeline (0, 1, and so on)

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.1189 Part 4 Section 4.6.29, cMediaNode (Common Media Node Properties)

a. *The standard states that the cMediaNode describes the behavior of media elements within an animation.*

The child **tgtEl** element ("[\[ECMA-376\]](#) Part 4 §4.6.81; tgtEl (Target Element)") shall contain either a **spTgt** element ("[\[ECMA-376\]](#) Part 4 §4.6.72; spTgt (Shape Target)") that points to a valid media shape or a **sndTgt** element ("[\[ECMA-376\]](#) Part 4 §4.6.70; sndTgt (Sound Target)"). A valid media shape is a shape that includes as a child of the **nvPr** element ("[\[ECMA-376\]](#) Part 4 §4.4.1.30; nvPr (Non-Visual Properties)") one of the following elements:

videoFile ("[\[ECMA-376\]](#) Part 4 §5.1.3.6; videoFile (Video from File)")

wavAudioFile ("[\[ECMA-376\]](#) Part 4 §5.1.3.7; wavAudioFile (Audio from WAV File)")

audioFile ("[\[ECMA-376\]](#) Part 4 §5.1.3.2; audioFile (Audio from File)")

audioCd ("[\[ECMA-376\]](#) Part 4 §5.1.3.1; audioCd (Audio from CD)")

quickTimeFile ("[\[ECMA-376\]](#) Part 4 §5.1.3.4; quickTimeFile (QuickTime from File)")

2.1.1190 Part 4 Section 4.6.31, cond (Condition)

a. *The standard does not state a default value for the delay attribute.*

PowerPoint uses a default value of 0 for the delay attribute.

b. *The standard places no restrictions on the relationship between the value of the evt attribute and the child elements of the cond element.*

PowerPoint does not support the rtn, tgtEl, or tn child elements when the value of the evt attribute is none; if the evt attribute has any other value, the child element specifies the target of the event.

c. *The standard does not state a default value for the evt attribute.*

PowerPoint uses a default value of none for the evt attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.1191 Part 4 Section 4.6.33, cTn (Common Time Node Properties)

a. *The standard does not specify how to interpret a presetID attribute value of 0.*

PowerPoint interprets the value of 0 on the presetID attribute as being equivalent to the custom setting.

b. *The standard does not state a default value for the dur attribute.*

PowerPoint uses a default value of 0 for the dur attribute.

c. *The standard states that the values of the repeatCount attribute are defined by the ST_TLTime simple type.*

PowerPoint will not run the time node to completion if the value of the repeatCount attribute is less than 1000.

d. *The standard states that the values of the spd attribute are defined by the ST_Percentage simple type.*

PowerPoint requires that the value of the spd attribute not be 0.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

e. *The standard does not state a default value for the restart attribute.*

PowerPoint uses a default value of always for the restart attribute.

f. *The standard states that the restart attribute specifies if a node is to restart when it completes its action.*

PowerPoint uses the restart attribute to specify whether a node is able to restart when it completes its action.

g. *The standard does not state a default value for the display attribute.*

PowerPoint uses a default value of true for the display attribute.

h. *The standard states that the display attribute describes whether the state of the time node is visible or hidden.*

PowerPoint uses the display attribute to specify whether the time node is visible in the user interface.

i. *The standard places no restrictions on the value of the grpId attribute.*

PowerPoint requires that value of the grpId attribute match the grpId attribute of a child element contained within the bldLst element.

j. *The standard does not state a default value for the afterEffect attribute.*

PowerPoint uses a default value of false for the afterEffect attribute.

k. *The standard states that the afterEffect attribute specifies whether there is an after effect applied to the time node.*

PowerPoint uses the afterEffect attribute to specify whether this time node is an after-effect.

l. *The standard does not state a default value for the nodePh attribute.*

PowerPoint uses a default value of false for the nodePh attribute.

m. *The standard states that the tmFilter attribute can be of type string.*

In PowerPoint, the string value is expected to be a list of semicolon separated time value pairs, such as "t1, t1';t2,t2';...". In this example, each t is the normalized local time for the element (values range from 0.0 – 1.0), and t' is the warped time to be used for the element's local time.

n. *The standard places no restrictions on the value of the evtFilter attribute.*

PowerPoint requires that the value of the evtFilter attribute be cancelBubble for triggered sequences.

o. *The standard states that the syncBehavior attribute specifies how the time node synchronizes to its group.*

PowerPoint does not support the syncBehavior attribute; the none behavior is assumed.

2.1.1192 Part 4 Section 4.6.34, cut (Cut Slide Transition)

For additional notes that apply to this portion of the standard, please see the notes for [fade](#), [§4.6.41\(a\)](#).

a. *The standard states that the thruBlk attribute specifies if the transition will start from a black screen (and then transition the new slide over black).*

PowerPoint uses the thruBlk attribute to specify whether the transition will start from the current slide and then transition through a black screen to the target slide.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.1193 Part 4 Section 4.6.39, endSync (EndSync)

For additional notes that apply to this portion of the standard, please see the notes for [cond](#), [§4.6.31\(a-c\)](#).

2.1.1194 Part 4 Section 4.6.40, excl (Exclusive)

For additional notes that apply to this portion of the standard, please see the notes for [tnLst](#), [§4.6.87\(b\)](#).

2.1.1195 Part 4 Section 4.6.41, fade (Fade Slide Transition)

For additional notes that apply to this portion of the standard, please see the notes for [cut, §4.6.34\(a\)](#).

a. *The standard states that the thruBlk attribute specifies if the transition will start from a black screen (and then transition the new slide over black).*

PowerPoint uses the thruBlk attribute to specify whether the transition will start from the current slide and then transition through a black screen to the target slide.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.1196 Part 4 Section 4.6.43, from (From)

For additional notes that apply to this portion of the standard, please see the notes for [rCtr, §4.6.62\(a\)](#).

a. *The standard states that the x attribute describes the X coordinate.*

PowerPoint uses the x attribute to specify the slide width percentage change when the from element is parented by the animMotion element, and the animated object width percentage change when the from element is parented by the animScale element.

b. *The standard states that the y attribute describes the Y coordinate.*

PowerPoint uses the y attribute to specify the slide height percentage change when the from element is parented by the animMotion element, and the animated object height percentage change when the from element is parented by the animScale element.

c. *The standard states that the from element specifies an x/y co-ordinate to start the animation from.*

When this element is contained within animMotion ("ECMA-376 Part 4 §4.6.4; animMotion (Animate Motion)"), the attributes x and y are interpreted as slide percentage and shall be greater than or equal to -2147483625 and less than or equal to 2147483625. When this element is contained within animScale ("ECMA-376 Part 4 §4.6.6; animScale (Animate Scale)"), the attributes x and y are interpreted as size percentage and shall be greater than or equal to 0 and less than or equal to 2147483625.

If the value of either the x or y attribute is greater than 16384000 or less than -16384000 there will be loss of precision due to internal calculations.

2.1.1197 Part 4 Section 4.6.44, from (From)

a. *The standard states that the hslClr, prstClr, scrGbClr, and sysClr elements are all valid children of the from element.*

PowerPoint does not allow these elements to be children of the from element.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

b. *The standard does not place any restrictions on the color values used when the schemeClr element is a child of the from element.*

PowerPoint requires that the color values dk1, lt1, dk2, lt2, accent3, accent4, accent5, accent6 and phClr not be used when the schemeClr element is a child of the from element.

2.1.1198 Part 4 Section 4.6.45, graphicEl (Graphic Element)

- a. *The standard places no restrictions on the element referred to by the graphicEl element.*

PowerPoint requires that the referred element be on the same slide and of the same type (chart vs. dgm) as the graphicEl's child element.

2.1.1199 Part 4 Section 4.6.46, hsl (HSL)

- a. *The standard does not state how to interpret a negative s attribute value.*

PowerPoint reverses the direction of the color interpolation when the s attribute's value is negative.

- b. *The standard does not state how to interpret a negative l attribute value.*

PowerPoint reverses the direction of the color interpolation when the l attribute's value is negative.

2.1.1200 Part 4 Section 4.6.47, inkTgt (Ink Target)

- a. *The standard places no restrictions on what type of shape the spid attribute references.*

PowerPoint requires the spid attribute to reference a valid ink shape.

2.1.1201 Part 4 Section 4.6.49, iterate (Iterate)

- a. *The standard states that the backwards attribute specifies whether to go backwards in the timeline to the previous node.*

PowerPoint uses the backwards attribute to specify whether to iterate from the beginning or the end of the target element.

2.1.1202 Part 4 Section 4.6.51, nextCondLst (Next Conditions List)

- a. *The standard states that the nextCondLst element describes a list of conditions that must be met to advance to the next animation sequence.*

PowerPoint will advance to the next animation sequence if any of the conditions in the list are met.

2.1.1203 Part 4 Section 4.6.52, oleChartEl (Embedded Chart Element)

- a. *The standard places no restrictions on the relationship between the lvl attribute and the type attribute.*

PowerPoint requires the lvl attribute be 0 if the type attribute is gridLegend.

- b. *The standard places no restrictions on the ordering and relationship of oleChartEl elements with respect to one another.*

PowerPoint requires that all oleChartEl elements be stored in incremental ascending order (with no omissions) under one common par element for the animation to play properly.

2.1.1204 Part 4 Section 4.6.55, prevCondLst (Previous Conditions List)

- a. *The standard states that the prevCondLst element describes a list of conditions that must be met in order to go backwards in an animation sequence.*

PowerPoint will advance to the previous animation sequence if any of the conditions in the list are met.

2.1.1205 Part 4 Section 4.6.56, pRg (Paragraph Text Range)

a. *The standard places no restrictions on the values of the st attribute and the end attribute with relation to one another.*

PowerPoint requires the values of the st attribute and the end attribute be equal to each other.

b. *The standard places no restrictions on the values of the st attribute and the end attribute with relation to the paragraphs.*

PowerPoint requires that the st attribute and the end attribute be less than the number of paragraphs.

2.1.1206 Part 4 Section 4.6.57, progress (Progress)

a. *The standard states that the boolVal, clrVal, intVal, and strVal elements are all valid children of the progress element.*

PowerPoint does not allow these elements as children of the progress element.

b. *The standard places no restrictions on the val attribute of the fltVal element when parented by the progress element.*

PowerPoint requires that the val attribute of the fltVal element be greater than or equal to 0 and less than or equal to 1 when parented by the progress element.

2.1.1207 Part 4 Section 4.6.62, rCtr (Rotation Center)

a. *The standard states that the x attribute and the y attribute describe coordinates.*

PowerPoint uses these attributes to specify slide percentages.

b. *The standard states that the x attribute and the y attribute are defined by the ST_Percentage simple type, which specifies percentages in 1000ths of a percent.*

PowerPoint interprets these attributes to be specified in 10ths of a percent.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

c. *The standard states that the x attribute and the y attribute are defined by the ST_Percentage simple type.*

PowerPoint restricts the value of these attributes to be greater than or equal to -2147483625 and less than or equal to 2147483625; if the value is less than -16384000 or greater than 16384000, it will lose precision due to internal calculations.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.1208 Part 4 Section 4.6.63, rgb (RGB)

a. *The standard does not state how to interpret a negative r attribute value.*

PowerPoint decreases the red color value when the r attribute's value is negative.

b. *The standard does not state how to interpret a negative g attribute value.*

PowerPoint decreases the green color value when the g attribute's value is negative.

c. *The standard does not state how to interpret a negative b attribute value.*

PowerPoint decreases the blue color value when the b attribute's value is negative.

2.1.1209 Part 4 Section 4.6.65, seq (Sequence Time Node)

For additional notes that apply to this portion of the standard, please see the notes for [tnLst](#), [§4.6.87\(b\)](#).

2.1.1210 Part 4 Section 4.6.66, set (Set Time Node Behavior)

For additional notes that apply to this portion of the standard, please see the notes for [tnLst](#), [§4.6.87\(b\)](#).

a. *The standard places no restrictions on the number of attrName child elements parented by the attrNameLst element when inside the set element.*

PowerPoint requires that there be at least one attrName child element of the attrNameLst element when inside a set element; if more than one attrName child element exists, only the first will be used.

2.1.1211 Part 4 Section 4.6.67, sldTgt (Slide Target)

a. *The standard places no restrictions on when the sldTgt element is to be used.*

PowerPoint will only use this element when it is grandparented by a cond element with its evt attribute set to onPrev, onNext, or onStopAudio.

2.1.1212 Part 4 Section 4.6.72, spTgt (Shape Target)

a. *The standard places no restrictions on what the spid attribute refers to.*

PowerPoint requires that the spid attribute refer to a cxnSp element, a graphicFrame element, a grpSp element, a pic element, or an sp element on the current slide.

b. *The standard does not specify how the graphicEl, oleChartEl, subSp, and txtEl child elements are to be used.*

PowerPoint uses the graphicEl, oleChartEl, and subSp child elements to specify graphical elements to animate within a graphicFrame element; it uses the txtEl child element to specify the text elements to animate within an sp element.

2.1.1213 Part 4 Section 4.6.77, subSp (Subshape)

For additional notes that apply to this portion of the standard, please see the notes for [inkTgt](#), [§4.6.47\(a\)](#).

a. *The standard places no restrictions on what the spid attribute refers to.*

PowerPoint requires that the spid attribute reference a valid shape that is present both on the current slide and on the diagram referred to by the spid attribute of the parent spTgt element.

b. *The standard places no restrictions on the parent spTgt element of the subSp element.*

PowerPoint requires that the parent element target a legacy diagram.

2.1.1214 Part 4 Section 4.6.78, subTnLst (Sub-TimeNodes List)

a. *The standard states that the subTnLst element describes time nodes that have a start time which is not based on the containing timenode.*

In PowerPoint, this element is only used when applied to nodes of depth 5 within the Slide Timing tree ("ECMA-376 Part 4 §4.4.1.44; timing (Slide Timing Information for a Slide Layout)"). The root element within the Time Node List ("ECMA-376 Part 4 §4.6.87; tnLst (Time Node List)") shall be a par element and this subTnLst element shall only be used when contained within seq child element of this root element.

The Target Element ("ECMA-376 Part 4 §4.6.81; tgtEl (Target Element)") contained within any anim, animClr, animEffect, animMotion, animRot, animScale, or set child element of subTnLst shall have either a Sound Target ("ECMA-376 Part 4 §4.6.70; sndTgt (Sound Target)") or a Shape Target ("ECMA-376 Part 4 §4.6.72; spTgt (Shape Target)") child element.

The Target Element ("ECMA-376 Part 4 §4.6.81; tgtEl (Target Element)") contained within an audio or video child element shall have either a Shape Target ("ECMA-376 Part 4 §4.6.72; spTgt (Shape Target)") child element that references a valid media shape or a Sound Target ("ECMA-376 Part 4 §4.6.70; sndTgt (Sound Target)") that references a valid sound target.

Any excl, par or seq child element shall have at least one cmd, anim, animClr, animEffect, animMotion, animRot, animScale, set, audio, or video child element. The first of these child elements shall have either a Sound Target ("ECMA-376 Part 4 §4.6.70; sndTgt (Sound Target)") or a Shape Target ("ECMA-376 Part 4 §4.6.72; spTgt (Shape Target)") child element.

2.1.1215 Part 4 Section 4.6.79, tav (Time Animate Value)

a. *The standard states that the fmla attribute of the tav element specifies the formula to be used during animation.*

The fmla attribute allows for the specification of a formula to be used for describing a complex motion for an animated object. The formula manipulates the motion of the object by modifying a property of the object over a specified period of time. Each formula has zero or more inputs specified by the (\$) symbol, zero or more variables specified by the (#) symbol pre-pended to the variable name and a target variable which is specified by the previously specified **attrName** element. The formula may contain one or more of any of the constants, operators or functions in the following lists. In addition to this, the formula may also contain floating point numbers and parentheses.

Mathematical operations have the following order of precedence, listed from lowest to highest. Operators listed on the same line have equal precedence.

"+", "-"

"*", "/", "%"

"^"

Unary minus, Unary plus (for example -2, meaning 3*-2 is the same as 3*(-2))

Variables, Constants (including numbers) and Functions (as listed previously)

Language Description:

Alpha = 'a' | 'b' | 'c' | 'd' | 'e' | 'f' | 'g' | 'h' | 'i' | 'j' | 'k' | 'l' | 'm' | 'n' | 'o' | 'p' | 'q' | 'r' | 's' | 't' | 'u' | 'v' | 'w' | 'x' | 'y' | 'z' | 'A' | 'B' | 'C' | 'D' | 'E' | 'F' | 'G' | 'H' | 'I' | 'J' | 'K' | 'L' | 'M' | 'N' | 'O' | 'P' | 'Q' | 'R' | 'S' | 'T' | 'U' | 'V' | 'W' | 'X' | 'Y' | 'Z' ;

Digit = '0' | '1' | '2' | '3' | '4' | '5' | '6' | '7' | '8' | '9' ;

Char = '.' | '_' | Alpha | Digit ;

number = Digit , { Digit } ;

exponent = ('e' | 'E') , ['-'] , number ;

value = number , ['.' number] , [exponent] ;

variable = '\$' | attribute ;

attribute = '#' , attrName ;

attrName = Alpha , { Char } ;

constant = value | 'pi' | 'e' ;

ident = 'abs' | 'acos' | 'asin' | 'atan' | 'ceil' | 'cos' | 'cosh' | 'deg' | 'exp' | 'floor' | 'ln' | 'max' | 'min' | 'rad' | 'rand' | 'sin' | 'sinh' | 'sqrt' | 'tan' | 'tanh' ;

function = ident , '(' , formula [',' , formula] , ')' ;

formula = term , { ('+' | '-') , term } ;

term = power , { ('*' | '/' | '%') , power } ;

power = unary , { '^' , unary } ;

unary = ['+' | '-'] , factor ;

factor = variable | constant | function | parens ;

parens = '(' , formula , ')' ;

Any additional characters in the formula string that are not contained within the set described shall be considered invalid.

Variables:

The symbol '\$' represents the formula input that is the progress of the current behavior.

The allowed attribute names are:

ppt_x, ppt_y, ppt_w, ppt_h, ppt_r, r, ScaleX, ScaleY, stype.rotation, style.opacity, style.visibility, style.fontSize, style.fontWeight, style.fontStyle, style.fontFamily, style.textEffectEmboss, style.textShadow, style.textTransform, style.textDecorationUnderline, style.textEffectOutline, style.textDecorationLineThrough, style.sRotation, imageData.cropTop, imageData.cropBottom, imageData.cropLeft, imageData.cropRight, imageData.gain, imageData.blacklevel, imageData.gamma, imageData.grayscale, fill.on, fill.type, fill.opacity, fill.method, fill.opacity2, fill.angle, fill.focus, fill.focusposition.x, fill.focusposition.y, fill.focussize.x, fill.focussize.y, stroke.on, stroke.weight, stroke.opacity, stroke.linestyle, stroke.dashstyle, stroke.filltype, stroke.imagesize.x, stroke.imagesize.y, stroke.startArrow, stroke.endArrow, stroke.startArrowWidth, stroke.startArrowLength, stroke.endArrowWidth, stroke.endArrowLength, shadow.on, shadow.type,

shadow.opacity, shadow.offset.x, shadow.offset.y, shadow.offset2.x, shadow.offset2.y, shadow.origin.x, shadow.origin.y, shadow.matrix.xtox, shadow.matrix.ytox, shadow.matrix.xtoy, shadow.matrix.ytoy, shadow.matrix.perspectiveX, shadow.matrix.perspectiveY, skew.on, skew.offset.x, skew.offset.y, skew.origin.x, skew.origin.y, skew.matrix.xtox, skew.matrix.ytox, skew.matrix.xtoy, skew.matrix.ytoy, skew.matrix.perspectiveX, skew.matrix.perspectiveY, extrusion.on, extrusion.type, extrusion.render, extrusion.viewpointorigin.x, extrusion.viewpointorigin.y, extrusion.viewpoint.x, extrusion.viewpoint.y, extrusion.viewpoint.z, extrusion.plane, extrusion.skewangle, extrusion.skewamt, extrusion.backdepth, extrusion.foredepth, extrusion.orientation.x, extrusion.orientation.y, extrusion.orientation.z, extrusion.orientationangle, extrusion.rotationangle.x, extrusion.rotationangle.y, extrusion.lockrotationcenter, extrusion.autorotationcenter, extrusion.rotationcenter.x, extrusion.rotationcenter.y, extrusion.rotationcenter.z, extrusion.colormode.

Constants:

| Name | Description |
|------|--------------------------|
| pi | Mathematical constant pi |
| e | Mathematical constant e |

Operators:

| Name | Description | Usage |
|------|----------------|-------------------------------------|
| + | Addition | "x+y", adds x to the value y |
| - | Subtraction | "x-y", subtracts y from the value x |
| * | Multiplication | "x*y", multiplies x by the value y |
| / | Division | "x/y", divides x by the value y |
| % | Modulus | "x%y", the remainder of x/y |
| ^ | Power | "x^y", x raised to the power y |

Functions:

| Name | Description | Usage |
|------|--------------------------|---|
| abs | Absolute value | "abs(x)", absolute value of x |
| acos | Arc Cosine | "acos(x)", arc cosine of the value x |
| asin | Arc Sine | "asin(x)", arc sine of the value x |
| atan | Arc Tangent | "atan(x)", arc tangent of the value x |
| ceil | Ceil value | "ceil(x)", value of x rounded up |
| cos | Cosine | "cos(x)", cosine of the value of x |
| cosh | Hyperbolic Cosine | "cosh(x)", hyperbolic cosine of the value x |
| deg | Radian to Degree convert | "deg(x)", the degree value of radiant value x |

| Name | Description | Usage |
|-------|---------------------------|--|
| exp | Exponent | "exp(x)", value of constant e raised to the power of x |
| floor | Floor value | "floor(x)", value of x rounded down |
| ln | Natural logarithm | "ln(x)", natural logarithm of x |
| max | Maximum of two values | "max(x,y)", returns x if (x > y) or returns y if (y > x) |
| min | Minimum of two values | "min(x,y)", returns x if (x < y) or returns y if (y < x) |
| rad | Degree to Radiant convert | "rad(x)", the radiant value of degree value x |
| rand | Random value | "rand(x)", returns a random floating point value between 0 and x |
| sin | Sine | "sin(x)", sine of the value x |
| sinh | Hyperbolic Sine | "sinh(x)", hyperbolic sine of the value x |
| sqrt | Square root | "sqrt(x)", square root of the value x |
| tan | Tangent | "tan(x)", tangent of the value x |
| tanh | Hyperbolic Tangent | "tanh(x)", hyperbolic tangent of the value x |

[Example: Consider the following animation path:

```

<p:animcalcmode="lin" valueType="num">
  <p:cBhvr>
    <p:cTn id="9" dur="664" tmFilter="0.0,0.0; 0.25,0.07; 0.50,0.2; 0.75,0.467;
1.0,1.0">
      <p:stCondLst>
        <p:cond delay="0"/>
      </p:stCondLst>
    </p:cTn>
    <p:tgtEl>
      <p:spTgtspid="4"/>
    </p:tgtEl>
    <p:attrNameLst>
      <p:attrName>ppt_y</p:attrName>
    </p:attrNameLst>
  </p:cBhvr>
  <p:tavLst>
    <p:tav tm="0" fmla="#ppt_y-sin(pi*$/3">
      <p:val>
        <p:fltValval="0.5"/>
      </p:val>
    </p:tav>
    <p:tav tm="100000">
      <p:val>
        <p:fltValval="1"/>
      </p:val>
    </p:tav>
  </p:tavLst>
</p:anim>

```


The preceding animation example modifies the ppt_y variable of the object by subtracting $\sin(\pi * \$) / 3$ from the non-animated value of ppt_y. The start value will be 0.5 and the end value will be 1 specified in each of the val elements. The total time for this animation is specified within the dur attribute and the filtered time graph is specified by the tmFilter attribute. The end result is that the object moves from a point above its non-animated position back to its non-animated position. With the specification of the tmFilter it will have a modified time graph such that it will also appear to accelerate as it reaches its final position.

[Note: For this example, the non-animated value of ppt_y will be the value of this variable if the object were to be statically rendered on the slide without animation properties. end note]

end example]

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

b. *The standard states that the tm attribute is optional.*

PowerPoint requires the tm attribute.

This note applies to the following products: 2007, 2007 SP1.

2.1.1216 Part 4 Section 4.6.83, tmPct (Time Percentage)

a. *The standard states that the values of the val attribute are defined by the ST_PositivePercentage simple type.*

PowerPoint restricts the value of the val attribute to be less than or equal to 2147483625; if the value is greater than 16384000, it will lose precision due to internal calculations.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.1217 Part 4 Section 4.6.84, tmpl (Template Effects)

a. *The standard states that the values of the lvl attribute are defined by the XML Schema unsignedInt datatype.*

PowerPoint requires that the value of the lvl attribute have a maximum value less than or equal to 9.

This note applies to the following products: 2007, 2007 SP1.

b. *The standard places no restrictions on the relationship between tmpl elements parented by the same tmplLst element.*

PowerPoint requires that each tmpl element within the same parent tmplLst element have a unique lvl attribute value.

2.1.1218 Part 4 Section 4.6.85, tmplLst (Template effects)

a. *The standard places no restrictions on when the tmplLst element is to be used.*

PowerPoint will only use this element when it refers to a ph element inside a sldLayout element or a sldMaster element.

2.1.1219 Part 4 Section 4.6.87, tnLst (Time Node List)

a. *The standard states that the child list of the tnLst element is unbounded.*

PowerPoint does not support more than one child element in the tnLst.

b. *The standard states that the anim, animClr, animEffect, animMotion, animRot, animScale, audio, cmd, excl, seq, set, and video elements are valid children of the tnLst element.*

PowerPoint does not allow these elements to be children of the tnLst element.

c. *The standard places no restrictions on the time nodes at a depth of five in the timing tree defined by the child element of the tnLst element.*

The child of this element is the root time node in the timing tree. A node at depth 5 in the timing tree shall meet at least one of the following criteria:

Be a behavior node (a node with cBhvr (“[ECMA-376](#) Part 4 §4.6.22; cBhvr Common Behavior”) as a child element) and contain a valid reference to a <tgtEl>.

Have at least one child element that is a behavior node, the first of which shall contain a valid reference to a <tgtEl>.

2.1.1220 Part 4 Section 4.6.88, to (To)

For additional notes that apply to this portion of the standard, please see the notes for [rCtr](#), §4.6.62(a).

a. *The standard states that the x attribute and the y attribute describe coordinates.*

PowerPoint uses these attributes to specify the slide size percentage change when the to element is parented by the animMotion element, and the animated object size percentage change when the to element is parented by the animScale element.

b. *The standard states that the x and y attribute values are defined as simple type ST_Percentage.*

When used in animMotion, the attributes, x and y, are values of slide percentage and the valid range is between -2147483625 and 2147483625. When used in animScale, the attributes, x and y, are values of size percentage and the valid range is between 0 and 2147483625.

If the x or y values are less than -16384000 or greater than 16384000 there will be some loss of precision due to internal calculations.

2.1.1221 Part 4 Section 4.6.89, to (To)

a. *The standard states that the to element specifies the attribute of the time node after the animation.*

For PowerPoint, the following table specifies the strVal value presets that must be used when the corresponding attribute names are used. The supported attribute names are listed in the attrName element (“[ECMA-376](#) Part 4 §4.6.7; attrName (Attribute Name)”).

| attrName(Attribute Name) | strVal Value Preset |
|---------------------------------|----------------------------|
| style.visibility | “hidden”, “visible” |
| style.fontWeight | “none”, “normal”, “bold” |
| style.fontStyle | “none”, “normal”, “italic” |

| attrName(Attribute Name) | strVal Value Preset |
|---------------------------------|---|
| style.textEffectEmboss | "none", "normal", "emboss" |
| style.textShadow | "none", "normal", "auto" |
| style.textTransform | "none", "normal", "sub", "super" |
| style.textDecorationUnderline | "false", "true" |
| style.textEffectOutline | "false", "true" |
| style.textDecorationLineThrough | "false", "true" |
| imageData.grayscale | "false", "true" |
| fill.on | "false", "f", "t", "true" |
| fill.type | "solid", "pattern", "tile", "frame", "gradientUnscaled", "gradient", "gradientCenter", "gradientRadial", "gradientTile", "background" |
| fill.method | "none", "linear", "sigma", "any" |
| stroke.on | "false", "f", "t", "true" |
| stroke.linestyle | "single", "thinThin", "thinThick", "thickThin", "thickBetweenThin" |
| stroke.dashstyle | "solid", "dot", "dash", "dashDot", "longDash", "longDashDot", "longDashDotDot" |
| stroke.filltype | "solid", "tile", "pattern", "frame" |
| stroke.startArrow | "none", "block", "classic", "diamond", "oval", "open", "chevron", "doublechevron" |
| stroke.endArrow | "none", "block", "classic", "diamond", "oval", "open", "chevron", "doublechevron" |
| stroke.startArrowWidth | "narrow", "medium", "wide" |
| stroke.startArrowLength | "short", "medium", "long" |
| stroke.endArrowWidth | "narrow", "medium", "wide" |
| stroke.endArrowLength | "short", "medium", "long" |
| shadow.on | "false", "f", "t", "true" |
| shadow.type | "single", "double", "emboss", "perspective" |
| skew.on | "false", "f", "t", "true" |
| extrusion.on | "false", "f", "t", "true" |
| extrusion.type | "parallel", "perspective" |
| extrusion.render | "solid", "wireframe", "boundingcube" |
| extrusion.plane | "xy", "zx", "yz" |
| extrusion.lockrotationcenter | "false", "true" |

| attrName(Attribute Name) | strVal Value Preset |
|---------------------------------|----------------------------|
| extrusion.autorotationcenter | "false", "true" |
| extrusion.colormode | "false", "true" |

b. *The standard states that the to element specifies the attribute of the time node after the animation.*

In PowerPoint, the child element strVal can be used as a string that represents a parenthesized formula whose format s described in the fmla attribute specified in the tav element ("ECMA-376 Part 4 §4.6.79; tav (Time Animate Value)"). The format is specified as:

strFormula = '(' , formula , ')' ;

Where formula is a string formula specified as described within tav ("ECMA-376 Part 4 §4.6.79; tav (Time Animate Value)").

c. *The standard states that the strVal child of the to element is used to specify an attribute that the animation applies to.*

In PowerPoint, the child element strVal can be used to represent a real number. The number shall be either a decimal number (for example 2.0, -3.4e-5), a hexadecimal number (for example 0x4A.F, -0X5FE5), an octal number (for example 0o56.4e5, -0O.56), or a binary number (for example 10.01, -11.01e110). This real number format is also used to define color values, in which the percentage is a real number with a postfix '%'. The required format is specified as follows:

real_number = value;

percentage = value , '%' ;

value = dec_value | oct_value | hex_value | bin_value ;

dec_value = dec_regular_value | dec_pure_floating ;

dec_regular_value = ['-'] , dec_number , ['.'] , [dec_number] , [dec_exponent] ;

dec_pure_float = ['-'] , '.' , dec_number , [dec_exponent] ;

oct_value = oct_regular_value | oct_pure_floating ;

oct_regular_value = ['-'] , oct_number , ['.'] , [oct_number] , [oct_exponent] ;

oct_pure_floating = ['-'] , '.' , oct_number , [oct_exponent] ;

hex_value = hex_regular_value | hex_pure_floating ;

hex_regular_value = ['-'] , hex_number , ['.'] , [hex_number]

hex_pure_floating = ['-'] , '.' , hex_number;

bin_value = bin_regular_value | bin_pure_floating ;

bin_regular_value = ['-'] , bin_number , ['.'] , [bin_number] , [bin_exponent] ;

bin_pure_floating = ['-'] , '.' , bin_number , [bin_exponent] ;

DecDigit = '0' | '1' | '2' | '3' | '4' | '5' | '6' | '7' | '8' | '9' ;

OctDigit = '0' | '1' | '2' | '3' | '4' | '5' | '6' | '7';

HexDigit = '0' | '1' | '2' | '3' | '4' | '5' | '6' | '7' | '8' | '9' | 'A' | 'a' | 'B' | 'b' | 'C' | 'c' | 'D' | 'd' | 'E' | 'e' | 'F' | 'f';

BinDigit = '0' | '1';

dec_number = Digit , { Digit } ;

oct_number = '0' , ('o' | 'O') , OctDigit , { OctDigit } ;

hex_number = '0' , ('x' | 'X') , HexDigit , { HexDigit } ;

bin_number = '0' , ('b' | 'B') , BinDigit , { BinDigit } ;

dec_exponent = ['-'] , ('e' | 'E') , dec_number ;

oct_exponent = ['-'] , ('e' | 'E') , oct_number ;

bin_exponent = ['-'] , ('e' | 'E') , bin_number ;

d. *The standard states that the strVal child of the to element is used to specify an attribute that the animation applies to.*

In PowerPoint, the child element strVal can be used to represent a color as follows:

rgb(r_value, g_value, b_value). *r_value*, *g_value*, and *b_value* are values for red, green, and blue spectrum, respectively. The values are either real numbers or percentages. For example, "rgb(255, 0, 0)" and "rgb(100%, 0, 0)" both defines a red color.

rgb(r_value, g_value, b_value, a_value). *r_value*, *g_value*, *b_value*, and *a_value* are values for red, green, blue, and alpha spectrum, respectively. The values are either real numbers or percentages. For example, "rgb(255, 0, 0, 255)" and "rgb(100%, 0, 0, 100%)" are red with a full opacity.

hsl(h_value, s_value, l_value). *h_value*, *s_value*, and *l_value* are values for hue, saturation, and lightness, respectively. The values are either real numbers or percentages. For example, "hsl(0, 255, 127.5)" and "hsl(0,100%, 50%)" are red, equivalent to "rgb(255, 0, 0)".

hsl(h_value, s_value, l_value, a_value). *h_value*, *s_value*, *l_value*, and *a_value* are values for hue, saturation, lightness, and alpha, respectively. The values are either real numbers or percentages. For example, "hsl(0, 255, 127.5, 255)" and "hsl(0,100%, 50%, 100%)" are red with a full opacity, equivalent to "rgb(255, 0, 0, 255)".

#rrggbb. *rr*, *gg*, and *bb* are hexadecimal values for red, green, and blue spectrum, respectively. For example, "#FF0000" is red, equivalent to "rgb(255, 0, 0)".

#aarrggbb. *aa*, *rr*, *gg*, and *bb* are hexadecimal values for alpha, red, green, and blue spectrum, respectively. For example, "#FFFF0000" is red with a full opacity, equivalent to "rgb(255, 0, 0, 255)".

#rgb. *r*, *g*, and *b* are hexadecimal values for red, green, and blue spectrum, respectively. It is equivalent to *#r0g0b0*. For example, "#F00" is equal to "#F00000".

#argb. *a*, *r*, *g*, and *b* are hexadecimal values for alpha, red, green, and blue spectrum, respectively. It is equivalent to *#a0r0g0b0*. For example, "#F00F" is equal to "#F00000F0".

2.1.1222 Part 4 Section 4.6.90, to (To)

a. *The standard states that the `hslClr`, `prstClr`, `scrgbClr`, and `sysClr` elements are all valid children of the `to` element.*

PowerPoint does not allow these elements to be children of the `to` element.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

b. *The standard does not place any restrictions on the color values used when the `schemeClr` element is a child of the `to` element.*

PowerPoint requires that the color values `dk1`, `lt1`, `dk2`, `lt2`, `accent3`, `accent4`, `accent5`, `accent6` and `phClr` not be used when the `schemeClr` element is a child of the `to` element.

2.1.1223 Part 4 Section 4.6.93, video (Video)

For additional notes that apply to this portion of the standard, please see the notes for [tnLst](#), [§4.6.87\(b\)](#).

2.1.1224 Part 4 Section 4.6.95, wheel (Wheel Slide Transition)

a. *The standard states that the values of the `spokes` attribute are defined by the XML Schema `unsignedInt` datatype.*

PowerPoint only supports the values 1, 2, 3, 4, and 8.

2.1.1225 Part 4 Section 4.8.11, ST_PhotoAlbumFrameShape (Photo Album Shape for Photo Mask)

a. *The standard only documents one description per enumeration value.*

Each enumeration value has two possible meanings which will be referred to as "Legacy" and "Standard" in the description section.

Legacy: If the application detects one or more shapes with a `blipfill` and `isPhoto` set to true within the non-visual properties for that shape, then the legacy meanings of each enumeration shall be implied.

Standard: For all other cases, the standard meaning shall be implied.






[Example: Consider the shape that has a `blip fill` applied to it and `isPhoto` set to true.

```
<p:sp>
<p:nvSpPr>
  ..
  <p:nvPr isPhoto="1"/>
</p:nvSpPr>
<p:spPr bwMode="auto">
  <a:blipFill dpi="0" rotWithShape="1">
    ..
  </a:blipFill>
</p:spPr>
</p:sp>
```

End example]

The following are possible enumeration values for this type:

| Enumeration Value | Description |
|--|--|
| frameStyle1 (Rectangle Photo Frame) | Standard:  Legacy:  |
| frameStyle2 (Rounded Rectangle Photo Frame) | Standard:  Legacy:  |
| frameStyle3 (Simple White Photo Frame) | Standard:  Legacy:  |
| frameStyle4 (Simple Black Photo Frame) | Standard:  Legacy:  |
| frameStyle5 (Compound Black Photo Frame) | Standard:  |

| Enumeration Value | Description |
|--|--|
| | Legacy:  |
| frameStyle6 (Center Shadow Photo Frame) | Standard:  Legacy:  |
| frameStyle7 (Soft Edge Photo Frame) | Standard:  Legacy:  |

2.1.1226 Part 4 Section 4.8.28, ST_TLAnimateEffectTransition (Time List Animate Effect Transition)

- a. *The standard does not specify how to interpret a transition value of none.*

PowerPoint interprets a value of none as being equal to in.

2.1.1227 Part 4 Section 4.8.29, ST_TLAnimateMotionBehaviorOrigin (Time List Animate Motion Behavior Origin)

- a. *The standard does not specify how to interpret the origin values.*

PowerPoint interprets the layout origin as being the center of the object and the parent origin as being the upper left corner of the slide.

2.1.1228 Part 4 Section 4.8.32, ST_TLBehaviorAdditiveType (Behavior Additive Type)

- a. *The standard states that base, mult, and none are valid behavior additive type values.*

PowerPoint does not support these values.

2.1.1229 Part 4 Section 4.8.34, ST_TLBehaviorTransformType (Behavior Transform Type)

a. *The standard states that a behavior transform type with a value of pt specifies a point transform.*

PowerPoint uses this value to specify a property transform.

2.1.1230 Part 4 Section 4.8.42, ST_TLTime (Time)

a. *The standard states that the ST_TLTime simple type specifies the time after which to automatically advance the build to the next step.*

PowerPoint lets the parent define how to use this simple type.

b. *The standard states that the contents of the ST_TLTime simple type are defined by the ST_TLTimeIndefinite simple type and the XML Schema unsignedInt datatype.*

PowerPoint restricts the contents of this simple type to be less than or equal to 2147483625; if the contents are greater than 16384000, they will lose precision due to internal calculations.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.1231 Part 4 Section 4.8.43, ST_TLTimeAnimateValueType (Animation Time)

a. *The standard states that the ST_TLTimeAnimateValueType simple type is defined by the ST_PositiveFixedPercentage simple type and the ST_TLTimeIndefinite simple type.*

PowerPoint does not include the ST_TLTimeIndefinite simple type in the definition of the ST_TLTimeAnimateValueType simple type.

This note applies to the following products: 2007, 2007 SP1.

2.1.1232 Part 4 Section 4.8.45, ST_TLTimeNodeFillType (Time Node Fill Type)

a. *The standard does not specify how to interpret the transition fill type.*

PowerPoint uses this value to signify that an element's properties reset to their original values after the element becomes inactive.

b. *The standard does not specify how to interpret the freeze fill type.*

PowerPoint uses this value to signify that an element's properties should remain at their ending values while their parent is still running or holding, or until another sibling element is started under a seq element or an excl element.

c. *The standard does not specify how to interpret the hold fill type.*

PowerPoint uses this value to signify that an element's properties remain at their ending values while their parent is still running or holding.

d. *The standard does not specify how to interpret the remove fill type.*

PowerPoint uses this value to signify that an element's properties reset to their original values after the element becomes inactive.

2.1.1233 Part 4 Section 4.8.47, ST_TLTimeNodeMasterRelation (Time Node Master Relation)

- a. *The standard states that lastClick is a valid master relation value.*

PowerPoint does not support this value.

- b. *The standard places no restrictions on when the playback behavior applies.*

PowerPoint only applies the playback behavior when the time node is contained within an subTnLst element.

- c. *The standard does not specify how to interpret the sameClick master relation.*

PowerPoint uses this value to signify that the time node will start at the same time as its master time node.

- d. *The standard does not specify how to interpret the nextClick master relation.*

PowerPoint uses this value to signify that the time node will start when the next time node group starts.

2.1.1234 Part 4 Section 4.8.49, ST_TLTimeNodeRestartType (Time Node Restart Type)

- a. *The standard states that the ST_TLTimeNodeRestartType simple type determines whether an effect can play more than once.*

PowerPoint uses this simple type to signify when a time node can restart.

2.1.1235 Part 4 Section 4.8.50, ST_TLTimeNodeSyncType (Time Node Sync Type)

- a. *The standard states that canSlip and locked are the only valid values for the time node sync type.*

PowerPoint also allows a value of none.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.1236 Part 4 Section 4.8.52, ST_TLTriggerEvent (Trigger Event)

- a. *The standard implies that the begin value and the onBegin value are equivalent.*

PowerPoint interprets the begin value to specify that a trigger should be fired when the specified time node begins, and the onBegin value to specify that a trigger should be fired when the onBegin event occurs on the specified target.

- b. *The standard implies that the end value and the onEnd value are equivalent.*

PowerPoint interprets the end value to specify that a trigger should be fired when the specified time node ends, and the onEnd value to specify that a trigger should be fired when the onEnd event occurs on the specified target.

- c. *The standard states that the onNext value specifies that a trigger should be fired on the next node.*

PowerPoint uses this value to specify that a trigger should be fired when the onNext event occurs on the specified target.

d. *The standard states that the onPrev value specifies that a trigger should be fired on the previous node.*

PowerPoint uses this value to specify that a trigger should be fired when the onPrevious event occurs on the specified target.

e. *The standard states that the onStopAudio value specifies that a trigger should be fired on stop audio.*

PowerPoint uses this value to specify that a trigger should be fired when the onstopaudio command is fired from a cmd time node.

f. *The standard states that begin, end, onBegin, onClick, onDbClick, onEnd, onMouseOut, onMouseOver, onNext, onPrev, and onStopAudio are the only valid values for the trigger event.*

PowerPoint also allows a value of none.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.1237 Part 4 Section 4.8.59, ST_ViewType (List of View Types)

a. *The standard states that the outlineView value specifies that outline view mode should be used.*

PowerPoint uses this value to specify that normal slide view mode should be used.

2.1.1238 Part 4 Section 4.8.61, ST_WebEncoding (Web Encoding)

a. *The standard states that the contents of the ST_WebEncoding simple type are a restriction of the XML Schema string datatype.*

The string shall be a valid code page name. The following are Office supported code page names:

| Code page | name |
|------------------------------|--------------|
| Arabic (ASMO708) | ASMO-708 |
| Arabic (DOS) | DOS-720 |
| Arabic (ISO) | iso-8859-6 |
| Arabic (Windows) | windows-1256 |
| Baltic (DOS) | ibm775 |
| Baltic (ISO) | iso-8859-4 |
| Baltic (Windows) | windows-1257 |
| Central European (DOS) | ibm852 |
| Central European (ISO) | iso-8859-2 |
| Central European (Windows) | windows-1250 |
| Chinese Simplified (GB18030) | GB18030 |

| Code page | name |
|-------------------------------|----------------|
| Chinese Simplified (GB2312) | gb2312 |
| Chinese Simplified (HZ) | hz-gb-2312 |
| Chinese Traditional (Big5) | big5 |
| Cyrillic (DOS) | cp866 |
| Cyrillic (ISO) | iso-8859-5 |
| Cyrillic (KOI8-R) | koi8-r |
| Cyrillic (KOI8-U) | koi8-u |
| Cyrillic (Windows) | windows-1251 |
| Greek (ISO) | iso-8859-7 |
| Greek (Windows) | windows-1253 |
| Hebrew (DOS) | DOS-862 |
| Hebrew (ISO-Logical) | iso-8859-8-i |
| Hebrew (ISO-Visual) | iso-8859-8 |
| Hebrew (Windows) | windows-1255 |
| Japanese (EUC) | euc-jp |
| Japanese (JIS) | iso-2022-jp |
| Japanese (JIS-Allow1byteKana) | csISO2022JP |
| Japanese (Shift-JIS) | shift_jis |
| Korean | ks_c_5601-1987 |
| Latin9 (ISO) | iso-8859-15 |
| Thai (Windows) | windows-874 |
| Turkish (ISO) | iso-8859-9 |
| Turkish (Windows) | Windows-1254 |
| Unicode | unicode |
| Unicode (Big-Endian) | UnicodeFeFF |
| Unicode (UTF-8) | utf-8 |
| US-ASCII | us-ascii |
| Vietnamese (Windows) | windows-1258 |
| Western European (ISO) | iso-8859-1 |
| Western European (Windows) | windows-1252 |

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.1239 Part 4 Section 5.1.2.1.1, bldChart (Build Chart)

a. *The standard does not clearly describe whether the bld attribute is a controller or an indicator of behavior.*

In Office, the bld attribute is an indicator rather than a controller of behavior.

2.1.1240 Part 4 Section 5.1.2.1.2, bldDgm (Build Diagram)

a. *The standard does not clearly describe whether attributes are controllers or indicators of a behavior.*

In Office, attributes are indicators rather than controllers of a behavior.

2.1.1241 Part 4 Section 5.1.2.1.4, cNvCxnSpPr (Non-Visual Connector Shape Drawing Properties)

a. *The standard implies that the cNvCxnSpPr element can only be used when rendering a slide.*

In Office, the cNvCxnSpPr element is used in rendering presentations, spreadsheets and documents.

2.1.1242 Part 4 Section 5.1.2.1.5, cNvGraphicFramePr (Non-Visual Graphic Frame Drawing Properties)

a. *The standard implies that the cNvGraphicsFramePr element can only be used when rendering a slide.*

In Office, the cNvGraphicsFramePr element is used in rendering presentations, spreadsheets and documents.

2.1.1243 Part 4 Section 5.1.2.1.6, cNvGrpSpPr (Non-Visual Group Shape Drawing Properties)

a. *The standard implies that the cNvGrpSpPr element can only be used when rendering a slide.*

In Office, the cNvGrpSpPr element is used in rendering presentations, spreadsheets and documents.

2.1.1244 Part 4 Section 5.1.2.1.11, cxnSpLocks (Connection Shape Locks)

For additional notes that apply to this portion of the standard, please see the notes for [picLocks](#), [§5.1.2.1.31\(a\)](#).

a. *The standard uses a shared attribute group for the locking attributes of shapes, pictures and other graphic objects.*

Office ignores attributes noChangeShapeType, noEditPoints and noRot when applied to a connection shape.

2.1.1245 Part 4 Section 5.1.2.1.12, dgm (Diagram to Animate)

a. *The standard states that attribute bldStep allows the entire diagram to be animated as one object.*

PowerPoint supports only build steps that animate diagram shapes.

2.1.1246 Part 4 Section 5.1.2.1.13, endCxn (Connection End)

- a. *The standard states that attributes id and idx only apply to the final connection.*

In Office, the id and idx attributes apply to all connections, not just the final connections.

2.1.1247 Part 4 Section 5.1.2.1.14, ext (Extension)

- a. *The standard implies that the uri attribute is optional.*

Office requires the uri attribute.

2.1.1248 Part 4 Section 5.1.2.1.17, graphicData (Graphic Object Data)

- a. *The standard implies that the uri attribute is optional.*

Office requires the uri attribute.

- b. *The standard does not enumerate any known servers for processing the contents of the graphicData element.*

Office implements a finite set of servers for processing the contents of the graphicData element. Office uses the uri attribute to determine the contents of the graphicData element, as described in the following table:

| URI | Root Element | Ref |
|--|---------------|--|
| http://schemas.openxmlformats.org/drawingml/2006/table | tbl | " [ECMA-376] Part 4 §5.1.6.11; tbl" |
| http://schemas.openxmlformats.org/drawingml/2006/diagram | relIds | " [ECMA-376] Part 4 §5.9.2.22; relIds" |
| http://schemas.openxmlformats.org/drawingml/2006/chart | chart | " [ECMA-376] Part 4 §5.7.2.26; chart" |
| http://schemas.openxmlformats.org/drawingml/2006/picture | pic | " [ECMA-376] Part 4 §5.2.2.5; pic" |
| http://schemas.openxmlformats.org/drawingml/2006/compatibility | legacyDrawing | " [ECMA-376] Part 4 §5.3.2.1; legacyDrawing" |
| http://schemas.openxmlformats.org/drawingml/2006/lockedCanvas | lockedCanvas | " [ECMA-376] Part 4 §5.4.2.1; lockedCanvas" |
| http://schemas.openxmlformats.org/presentationml/2006/ole | oleObj | " [ECMA-376] Part 4 §4.4.2.4; oleObj" |

2.1.1249 Part 4 Section 5.1.2.1.19, graphicFrameLocks (Graphic Frame Locks)

a. *The standard specifies that an implementing application should lock the aspect ratio of the graphic frame if the value of the noChangeAspect attribute is true.*

When a user resizes a graphicFrame by direct manipulation (by dragging with the mouse, for example), Office ignores the noChangeAspect attribute. When a user resizes the frame by entering the desired dimensions, this attribute is taken into account.

b. *The standard includes noMove and noResize as attributes of the element graphicFrame.*

Office does not implement and will ignore the attributes noMove and noResize for graphicFrame elements.

c. *The standard states that the noSelect attribute of element graphicFrameLocks disallows the selection of the corresponding picture.*

In Office, the noSelect attribute of element graphicFrameLocks disallows the selection of the corresponding graphic frame.

2.1.1250 Part 4 Section 5.1.2.1.21, grpSpLocks (Group Shape Locks)

a. *The standard states that grpSpLocks specifies the locking properties for a connection shape.*

In Office, grpSpLocks specifies the locking properties for a group shape.

2.1.1251 Part 4 Section 5.1.2.1.22, grpSpPr (Visual Group Shape Properties)

For additional notes that apply to this portion of the standard, please see the notes for [grpSpPr, §5.6.2.17\(a-c\)](#).

2.1.1252 Part 4 Section 5.1.2.1.23, hlinkHover (Hyperlink for Hover)

For additional notes that apply to this portion of the standard, please see the notes for [hlinkClick, §5.1.5.3.5\(a\)](#).

2.1.1253 Part 4 Section 5.1.2.1.24, In (Outline)

a. *The standard does not specify a default value for the align attribute.*

Office uses a default value of ctr for the align attribute.

b. *The standard states that sq is the default value for the cap attribute.*

Office uses flat as the default value for cap.

c. *The standard allows for the specifying of the tailEnd child element, headEnd child element and cap attribute within the In element.*

Office does not use the tailEnd child element, headEnd child element and cap attribute when the parent element is the rPr element.

2.1.1254 Part 4 Section 5.1.2.1.31, picLocks (Picture Locks)

a. *The standard references only connection shapes as a part of the picLocks element attribute descriptions for the AG_Locking attribute group.*

In Office, AG_Locking attribute group attributes also applies to shapes and pictures.

b. *The standard uses a shared attribute group for the locking attributes of shapes, pictures and other graphic objects.*

Office ignores attributes noChangeArrowheads, noChageShapeType, noEditPoints and noRot when applied to a picture object. Additionally, PowerPoint ignores noAdjustHandles and Word ignores noMove and noResize when applied to a picture object.

2.1.1255 Part 4 Section 5.1.2.1.34, spLocks (Shape Locks)

For additional notes that apply to this portion of the standard, please see the notes for [picLocks, §5.1.2.1.31\(a\)](#).

a. *The standard uses a shared attribute group for the locking attributes of shapes, pictures and other graphic objects.*

Office ignores attributes noChangeArrowheads and noRot when applied to a shape. PowerPoint additionally ignores the attribute noAdjustHandles when applied to a shape and noChangeShapeType when the converting the shape to a freeform.

2.1.1256 Part 4 Section 5.1.2.1.35, spPr (Shape Properties)

For additional notes that apply to this portion of the standard, please see the notes for [spPr, §5.6.2.29\(a-c\)](#).

2.1.1257 Part 4 Section 5.1.2.1.36, stCxn (Connection Start)

For additional notes that apply to this portion of the standard, please see the notes for [endCxn, §5.1.2.1.13\(a\)](#).

2.1.1258 Part 4 Section 5.1.2.1.37, style (Shape Style)

a. *The standard states that the fontRef attribute applies to parent elements pic, cxnSp and sp.*

In Office, the fontRef attribute is not used for parent elements pic and cxnSp.

b. *The standard allows a sp, pic or cxnSp element to have similar formatting options defined in both the style and spPr elements.*

In Office, shape properties (spPr) defined on the parent element will override similar style components (lnRef, effectRef, fillRef, fontRef) defined for this element.

c. *The standard allows similar text formatting properties to be defined for parent element sp by style or txBody.*

In Office, child elements from txBody for parent element sp will override similar style properties defined in the fontRef child element in this element.

2.1.1259 Part 4 Section 5.1.2.2.1, alpha (Alpha)

a. *The standard states that the val attribute specifies the opacity as expressed by a percentage value.*

Office uses the val attribute to specify a percentage value for several elements.

2.1.1260 Part 4 Section 5.1.2.2.4, blue (Blue)

a. *The standard states that the val attribute specifies the blue component as expressed by a percentage value.*

Office uses the val attribute to specify a percentage value for several elements.

2.1.1261 Part 4 Section 5.1.2.2.5, blueMod (Blue Modification)

For additional notes that apply to this portion of the standard, please see the notes for [blue, §5.1.2.2.4\(a\)](#).

2.1.1262 Part 4 Section 5.1.2.2.6, blueOff (Blue Offset)

For additional notes that apply to this portion of the standard, please see the notes for [blue, §5.1.2.2.4\(a\)](#).

2.1.1263 Part 4 Section 5.1.2.2.10, green (Green)

For additional notes that apply to this portion of the standard, please see the notes for [blue, §5.1.2.2.4\(a\)](#).

2.1.1264 Part 4 Section 5.1.2.2.11, greenMod (Green Modification)

For additional notes that apply to this portion of the standard, please see the notes for [blue, §5.1.2.2.4\(a\)](#).

2.1.1265 Part 4 Section 5.1.2.2.12, greenOff (Green Offset)

For additional notes that apply to this portion of the standard, please see the notes for [blue, §5.1.2.2.4\(a\)](#).

2.1.1266 Part 4 Section 5.1.2.2.19, lum (Luminance)

For additional notes that apply to this portion of the standard, please see the notes for [blue, §5.1.2.2.4\(a\)](#).

a. *The standard allows luminance to be specified either as an attribute of a parent element or as a child element.*

In Office, using child element lum will override the corresponding value specified in a parent element and may produce unexpected color.

2.1.1267 Part 4 Section 5.1.2.2.20, lumMod (Luminance Modulation)

For additional notes that apply to this portion of the standard, please see the notes for [blue, §5.1.2.2.4\(a\)](#).

2.1.1268 Part 4 Section 5.1.2.2.21, lumOff (Luminance Offset)

For additional notes that apply to this portion of the standard, please see the notes for [blue, §5.1.2.2.4\(a\)](#).

a. *The standard states that element lumOff shifts the input color's luminance while leaving hue and saturation unchanged.*

This element is not supported by Office and may produce unexpected color.

2.1.1269 Part 4 Section 5.1.2.2.22, prstClr (Preset Color)

a. *The standard implies that the val attribute is optional.*

Office requires the val attribute.

2.1.1270 Part 4 Section 5.1.2.2.23, red (Red)

For additional notes that apply to this portion of the standard, please see the notes for [blue](#), §5.1.2.2.4(a).

2.1.1271 Part 4 Section 5.1.2.2.24, redMod (Red Modulation)

For additional notes that apply to this portion of the standard, please see the notes for [blue](#), §5.1.2.2.4(a).

2.1.1272 Part 4 Section 5.1.2.2.25, redOff (Red Offset)

For additional notes that apply to this portion of the standard, please see the notes for [blue](#), §5.1.2.2.4(a).

2.1.1273 Part 4 Section 5.1.2.2.26, sat (Saturation)

For additional notes that apply to this portion of the standard, please see the notes for [blue](#), §5.1.2.2.4(a).

a. *The standard allows saturation to be specified either as an attribute of a parent element or as a child element.*

In Office, using child element sat will override the corresponding value specified in a parent element and may produce unexpected color.

2.1.1274 Part 4 Section 5.1.2.2.27, satMod (Saturation Modulation)

For additional notes that apply to this portion of the standard, please see the notes for [blue](#), §5.1.2.2.4(a).

2.1.1275 Part 4 Section 5.1.2.2.28, satOff (Saturation Offset)

For additional notes that apply to this portion of the standard, please see the notes for [blue](#), §5.1.2.2.4(a).

a. *The standard states that element satOff shifts the input color's saturation while leaving hue and luminance unchanged.*

This element is not supported by Office and may produce unexpected color.

2.1.1276 Part 4 Section 5.1.2.2.31, shade (Shade)

For additional notes that apply to this portion of the standard, please see the notes for [alpha](#), §5.1.2.2.1(a).

2.1.1277 Part 4 Section 5.1.2.2.33, sysClr (System Color)

- a. *The standard does not fully describe the lastClr attribute.*

In Office, the lastClr attribute stores the RGB value of the last sysClr used.

2.1.1278 Part 4 Section 5.1.2.2.34, tint (Tint)

For additional notes that apply to this portion of the standard, please see the notes for [alpha](#), [§5.1.2.2.1\(a\)](#).

2.1.1279 Part 4 Section 5.1.3.3, end (Audio End Time)

- a. *The standard uses common attribute descriptions for 'time' and 'track' that are shared by both 'st' and 'end' elements.*

In Office, the time attribute specifies the time in seconds that the CD audio should be started on at or stopped at while the track attribute specifies the track of the CD the audio will begin on or stop at.

2.1.1280 Part 4 Section 5.1.3.5, st (Audio Start Time)

For additional notes that apply to this portion of the standard, please see the notes for [end](#), [§5.1.3.3\(a\)](#).

2.1.1281 Part 4 Section 5.1.4.1.1, accent1 (Accent 1)

- a. *The standard allows the element schemeClr as a child of the parent element clrScheme.*

Office does not allow schemeClr as a child of the parent element clrScheme.

2.1.1282 Part 4 Section 5.1.4.1.2, accent2 (Accent 2)

- a. *The standard allows the element schemeClr as a child of the parent element clrScheme.*

Office does not allow schemeClr as a child of the parent element clrScheme.

2.1.1283 Part 4 Section 5.1.4.1.3, accent3 (Accent 3)

- a. *The standard allows the element schemeClr as a child of the parent element clrScheme.*

Office does not allow schemeClr as a child of the parent element clrScheme.

2.1.1284 Part 4 Section 5.1.4.1.4, accent4 (Accent 4)

- a. *The standard allows the element schemeClr as a child of the parent element clrScheme.*

Office does not allow schemeClr as a child of the parent element clrScheme.

2.1.1285 Part 4 Section 5.1.4.1.5, accent5 (Accent 5)

- a. *The standard allows the element schemeClr as a child of the parent element clrScheme.*

Office does not allow schemeClr as a child of the parent element clrScheme.

2.1.1286 Part 4 Section 5.1.4.1.6, accent6 (Accent 6)

- a. *The standard allows the element schemeClr as a child of the parent element clrScheme.*
Office does not allow schemeClr as a child of the parent element clrScheme.

2.1.1287 Part 4 Section 5.1.4.1.9, dk1 (Dark 1)

- a. *The standard allows the element schemeClr as a child of the parent element clrScheme.*
Office does not allow schemeClr as a child of the parent element clrScheme.

2.1.1288 Part 4 Section 5.1.4.1.10, dk2 (Dark 2)

- a. *The standard allows the element schemeClr as a child of the parent element clrScheme.*
Office does not allow schemeClr as a child of the parent element clrScheme.

2.1.1289 Part 4 Section 5.1.4.1.15, folHlink (Followed Hyperlink)

- a. *The standard allows the element schemeClr as a child of the parent element clrScheme.*
Office does not allow schemeClr as a child of the parent element clrScheme.

2.1.1290 Part 4 Section 5.1.4.1.17, fontRef (Font Reference)

- a. *The standard does not state how to handle an undefined theme.*

Excel uses a default value of minor for the idx attribute on this element and a default value of tx1 for the val attribute on the schemeClr element when a theme is not provided.

2.1.1291 Part 4 Section 5.1.4.1.19, hlink (Hyperlink)

- a. *The standard allows the element schemeClr as a child of the parent element clrScheme.*
Office does not allow schemeClr as a child of the parent element clrScheme.

2.1.1292 Part 4 Section 5.1.4.1.22, lt1 (Light 1)

- a. *The standard allows the element schemeClr as a child of the parent element clrScheme.*
Office does not allow schemeClr as a child of the parent element clrScheme.

2.1.1293 Part 4 Section 5.1.4.1.23, lt2 (Light 2)

- a. *The standard allows the element schemeClr as a child of the parent element clrScheme.*
Office does not allow schemeClr as a child of the parent element clrScheme.

2.1.1294 Part 4 Section 5.1.4.2.2, band1V (Band 1 Vertical)

- a. *The standard states that the band1V element applies to rows.*
Office applies this element to columns.

2.1.1295 Part 4 Section 5.1.4.2.4, band2V (Band 2 Vertical)

- a. *The standard states that the band2V element applies to rows.*

Office applies this element to columns.

2.1.1296 Part 4 Section 5.1.4.2.9, fill (Fill)

- a. *The standard states that the fill element defines the fill that is applied to the table as a whole.*

Office uses this element to affect the table as a whole only if parented by tblBg.

- b. *The standard states that the fill element allows any blip fill to be valid.*

Office requires that the blip fill not be empty when the fill element is parented by tcStyle.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

- c. *The standard allows group fills to be applied to a table.*

Office does not apply group fills to tables but instead uses a white background.

2.1.1297 Part 4 Section 5.1.4.2.19, InRef (Line Reference)

- a. *The standard states that the idx attribute of the InRef element references the index of a line style within the fillStyleLst element.*

In Office, the idx attribute of this element references the index of a line style within the InStyleList element.

2.1.1298 Part 4 Section 5.1.4.2.26, tblStyle (Table Style)

- a. *The standard states that the tblStyle element specifies the formatting for the table.*

There is a well defined order to the table part styles that are applied because a cell can belong to many cell part styles (for example, the top left cell is part of the first column as well as the first row). Table part styles are applied in the following order:

Apply whole table part

Apply odd banded row cells

Apply even banded row cells

Apply odd banded column cells

Apply even banded column cells

Apply right column cells

Apply left column cells

Apply bottom row cells

Apply bottom right cell

Apply bottom left cell

Apply top row cells

Apply top right cell

Apply top left cell

2.1.1299 Part 4 Section 5.1.5.1.1, bodyPr (Body Properties)

a. *The standard specifies that the attributes anchorCtr, forceAA, fromWordArt, and rtlCol have an implied value of off.*

Office interprets the attributes anchorCtr, forceAA, fromWordArt, and rtlCol as having an implied value of false.

b. *The standard does not fully describe the process for resolving missing attribute values.*

In Office, attributes not specified explicitly within the bodyPr element shall have their values determined by inheritance. Attribute values will be resolved using an applicable ancestor element of the same type as the bodyPr element. The inheritance order in which applicable attribute value shall be applied is as follows:

A corresponding ancestor element which is a child element of the txDef element (“[\[ECMA-376\]](#) Part 4 §5.1.4.1.28; txDef (Text Default)”) of the theme part.

A corresponding ancestor element which is a child element of the lnDef element (“[\[ECMA-376\]](#) Part 4 §5.1.4.1.20; lnDef (Line Default)”) of the theme part.

A corresponding ancestor element which is a child element of the spDef element (“[\[ECMA-376\]](#) Part 4 §5.1.4.1.27; spDef (Shape Default)”) of the theme part.

If the value of an attribute is not determined via this process, the default value specified within the bodyPr element shall be used.

PowerPoint uses a corresponding child element which is contained within the corresponding sldMaster element (“[\[ECMA-376\]](#) Part 4 §4.4.1.39; sldMaster (Slide Master)”) if the value of an attribute is not determined by this inheritance order. If the corresponding sldMaster element (“[\[ECMA-376\]](#) Part 4 §4.4.1.39; sldMaster (Slide Master)”) does not specify the value of the attribute and the value was not determined from the inheritance order, then the default value specified within the bodyPr element shall be used.

2.1.1300 Part 4 Section 5.1.5.1.2, noAutofit (No AutoFit)

a. *The standard states if the noAutofit element is omitted, no autofit or autofit off is implied.*

Office uses a hierarchy of text styles to determine if the text should be autofit or not.

2.1.1301 Part 4 Section 5.1.5.1.3, normAutofit (Normal AutoFit)

a. *The standard states that if the normAutofit element is omitted then no autofit or autofit off is implied.*

Office does not follow this and instead uses a hierarchy of text styles to determine if the text should be autofit or not.

2.1.1302 Part 4 Section 5.1.5.1.4, spAutoFit (Shape AutoFit)

a. *The standard states that if the spAutoFit element is omitted then noAutofit or auto-fit off is implied.*

Office does not follow this and instead uses a hierarchy of text styles to determine if the text should be autofit or not.

b. *The standard states that the spAutofit element specifies that text within a shape is scaled in order to contain all the text inside the bounds of the shape.*

Office uses the spAutoFit element to specify that the containing shape should be resized to contain text.

2.1.1303 Part 4 Section 5.1.5.2.2, defPPr (Default Paragraph Style)

For additional notes that apply to this portion of the standard, please see the notes for [lvl1pPr](#), §5.1.5.4.13(a-g).

a. *The standard describes the defPPr element as specifying paragraph properties.*

Office ignores this element and does not use it to determine paragraph properties.

2.1.1304 Part 4 Section 5.1.5.2.3, endParaRPr (End Paragraph Run Properties)

For additional notes that apply to this portion of the standard, please see the notes for [rPr](#), §5.1.5.3.9(a, b,d-g).

2.1.1305 Part 4 Section 5.1.5.2.4, fld (Text Field)

a. *The standard states that the type attribute of the fld element specifies the type of update text that should be used within the text field.*

In Office, the type attribute specifies the type of text that should be used to update this text field. This is used to inform Office what text it should use to update this text field. There are no specific syntax restrictions placed on this attribute. The generating application may use it to represent any text that should be updated before rendering the presentation.

Reserved Values:

| Value | Description |
|------------------|--|
| <i>slidenum</i> | presentation slide number |
| <i>datetime</i> | default date time format for the rendering application |
| <i>datetime1</i> | MM/DD/YYYY date time format [Example: 10/12/2007 end example] |
| <i>datetime2</i> | Day, Month DD, YYYY date time format [Example: Friday, October 12, 2007 end example] |
| <i>datetime3</i> | DD Month YYYY date time format [Example: 12 October 2007 end example] |
| <i>datetime4</i> | Month DD, YYYY date time format [Example: October 12, 2007 end example] |
| <i>datetime5</i> | DD-Mon-YY date time format [Example: 12-Oct-07 end example] |
| <i>datetime6</i> | Month YY date time format [Example: October 07 end example] |

| Value | Description |
|-------------------|---|
| <i>datetime7</i> | Mon-YY date time format [Example: Oct-07 end example] |
| <i>datetime8</i> | MM/DD/YYYY hh:mm AM/PM date time format [Example: 10/12/2007 4:28 PM end example] |
| <i>datetime9</i> | MM/DD/YYYY hh:mm:ss AM/PM date time format [Example: 10/12/2007 4:28:34 PM end example] |
| <i>datetime10</i> | hh:mm date time format [Example: 16:28 end example] |
| <i>datetime11</i> | hh:mm:ss date time format [Example: 16:28:34 end example] |
| <i>datetime12</i> | hh:mm AM/PM date time format [Example: 4:28 PM end example] |
| <i>datetime13</i> | hh:mm:ss: AM/PM date time format [Example: 4:28:34 PM end example] |

2.1.1306 Part 4 Section 5.1.5.2.5, InSpc (Line Spacing)

- a. *The standard states that the InSpc element describes the vertical line spacing that is to be used within a paragraph.*

In Office, the InSpc element describes the vertical line spacing for horizontal text and horizontal line spacing for vertical text that is to be used within a paragraph.

2.1.1307 Part 4 Section 5.1.5.2.6, p (Text Paragraphs)

- a. *The standard states that if no text paragraph properties are listed, then the properties specified in the defPPr element are used.*

Office ignores the defPPr element. If no paragraph properties are listed, then properties specified in the appropriate child element of the IstStyle element are used as described in child element pPr.

2.1.1308 Part 4 Section 5.1.5.2.7, pPr (Text Paragraph Properties)

For additional notes that apply to this portion of the standard, please see the notes for [lvl1pPr](#), [§5.1.5.4.13\(a-g\)](#).

- a. *The standard does not fully describe the process for resolving missing attribute values.*

In Office, attributes not specified explicitly within this element shall have their values determined by inheritance. Attribute values will be resolved using an applicable ancestor element of the same type as this element. The inheritance order in which applicable attribute value shall be applied is as follows:

A corresponding ancestor element which is a child element of the IstStyle element (“[\[ECMA-376\]](#) Part 4 §5.1.5.4.12; IstStyle (Text List Styles)”) and has a matching paragraph level and is contained within the same package part as the text to which the attribute values shall apply.

A corresponding child element of the IstStyle element (“[\[ECMA-376\]](#) Part 4 §5.1.5.4.12; IstStyle (Text List Styles)”) and contained within the theme element (“[\[ECMA-376\]](#) Part 4 §5.1.8.9; theme (Theme)”).

If the value of an attribute is not determined via this process, the default value specified within this element shall be used.

PowerPoint uses a corresponding child element which is contained within the corresponding sldMaster element ("ECMA-376 Part 4 §4.4.1.39; sldMaster (Slide Master)") if the value of an attribute is not determined by this inheritance order. If the corresponding sldMaster element ("ECMA-376 Part 4 §4.4.1.39; sldMaster (Slide Master)") does not specify the value of the attribute and the value was not determined from the inheritance order, then the default value specified within this element shall be used.

2.1.1309 Part 4 Section 5.1.5.2.8, spcAft (Space After)

a. The standard states that the spcAft element specifies the amount of vertical white space that will be present after a paragraph.

Office uses the spcAft element to determine the amount of white space that will be present after a paragraph.

2.1.1310 Part 4 Section 5.1.5.2.9, spcBef (Space Before)

a. The standard states that the spcBef element specifies the amount of vertical white space that will be present before a paragraph.

Office uses the spcBef element to determine the amount of white space that will be present before a paragraph.

2.1.1311 Part 4 Section 5.1.5.3.1, cs (Complex Script Font)

For additional notes that apply to this portion of the standard, please see the notes for [latin, §5.1.5.3.7\(a-d\)](#).

2.1.1312 Part 4 Section 5.1.5.3.2, defRPr (Default Text Run Properties)

For additional notes that apply to this portion of the standard, please see the notes for [rPr, §5.1.5.3.9\(a, b,d-g\)](#).

2.1.1313 Part 4 Section 5.1.5.3.3, ea (East Asian Font)

For additional notes that apply to this portion of the standard, please see the notes for [latin, §5.1.5.3.7\(a-d\)](#).

2.1.1314 Part 4 Section 5.1.5.3.5, hlinkClick (Click Hyperlink)

a. The standard states that the action attribute of the hlinkClick, hlinkHover and hlinkMouseOver elements may use an unrestricted string.

PowerPoint reserves the following values for the action attribute:

| Value | Description |
|----------------------------------|---|
| ppaction://customshow?id=SHOW_ID | Specifies that the link shall launch a custom show from the custShowLst element ("ECMA-376 Part 4 §4.3.1.6; custShowLst (List of Custom Shows)"). The SHOW_ID variable shall be replaced with the custom show id as specified in the custShow element ("ECMA-376 Part 4 §4.3.1.5; custShow (Custom Show)"). |
| ppaction://hlinkfile | Specifies that the link shall open a file external to this presentation package. The r:id attribute for this |

| Value | Description |
|---|--|
| | element specifies the corresponding relationship containing the reference to the external file. |
| ppaction://hlinkpres?slideindex=SLIDE_NUM | Specifies that the link shall launch a presentation external to this presentation package. The r:id attribute for this element specifies the corresponding relationship containing the reference to the external file. The SLIDE_NUM variable shall be replaced with a slide number in the external presentation that the viewing shall be started on. |
| ppaction://hlinkshowjump?jump=endshow | Specifies that the link shall end the presentation. |
| ppaction://hlinkshowjump?jump=firstslide | Specifies that the link shall target the viewing of the first slide within this presentation package. |
| ppaction://hlinkshowjump?jump=lastslide | Specifies that the link shall target the viewing of the last slide within this presentation package. |
| ppaction://hlinkshowjump?jump=lastslideviewed | Specifies that the link shall target the viewing of the slide previously visited within this presentation package. |
| ppaction://hlinkshowjump?jump=nextslide | Specifies that the link shall target the viewing of the next slide within this presentation package. |
| ppaction://hlinkshowjump?jump=previousslide | Specifies that the link shall target the viewing of the previous slide within this presentation package. |
| ppaction://hlinksldjump | Specifies that the link shall target the viewing of a specific slide within this presentation package. The r:id attribute for this element specifies the corresponding relationship containing the reference to the slide part which shall be viewed. |
| ppaction://macro?name=MACRO_NAME | Specifies that the link shall run a macro contained within this presentation. The MACRO_NAME variable shall be replaced with the name of the macro module. |
| ppaction://program | Specifies that the link shall run an application external to this presentation package. The r:id attribute for this element specifies the corresponding relationship containing the reference to the application. |

2.1.1315 Part 4 Section 5.1.5.3.6, hlinkMouseOver (Mouse-Over Hyperlink)

For additional notes that apply to this portion of the standard, please see the notes for [hlinkClick, §5.1.5.3.5\(a\)](#).

2.1.1316 Part 4 Section 5.1.5.3.7, latin (Latin Font)

- a. The standard includes panose as an optional attribute of this element.

Office does not implement the panose attribute.

- b. The standard states that the charset attribute of the buFont, cs, ea, font, latin and sym elements specifies the most similar character set.

Office uses this attribute to specify the character set that is supported by the parent font. This information may be used in font substitution logic to locate an appropriate substitute font when this font is not available. This information is determined by querying the font when present and shall not be modified when the font is not available.

The value of this attribute shall be interpreted as follows:

| Value | Description |
|-----------------|---|
| 0x00 | Specifies the ANSI character set. (IANA name <code>iso-8859-1</code>) |
| 0x01 | Specifies the default character set. |
| 0x02 | Specifies the Symbol character set. This value specifies that the characters in the Unicode private use area (U+FF00 to U+FFFF) of the font should be used to display characters in the range U+0000 to U+00FF. |
| 0x4D | Specifies a Macintosh (Standard Roman) character set. (IANA name <code>macintosh</code>) |
| 0x80 | Specifies the JIS character set. (IANA name <code>shift_jis</code>) |
| 0x81 | Specifies the Hangul character set. (IANA name <code>ks_c_5601-1987</code>) |
| 0x82 | Specifies a Johab character set. (IANA name <code>KS C-5601-1992</code>) |
| 0x86 | Specifies the GB-2312 character set. (IANA name <code>GBK</code>) |
| 0x88 | Specifies the Chinese Big Five character set. (IANA name <code>Big5</code>) |
| 0xA1 | Specifies a Greek character set. (IANA name <code>windows-1253</code>) |
| 0xA2 | Specifies a Turkish character set. (IANA name <code>iso-8859-9</code>) |
| 0xA3 | Specifies a Vietnamese character set. (IANA name <code>windows-1258</code>) |
| 0xB1 | Specifies a Hebrew character set. (IANA name <code>windows-1255</code>) |
| 0xB2 | Specifies an Arabic character set. (IANA name <code>windows-1256</code>) |
| 0xBA | Specifies a Baltic character set. (IANA name <code>windows-1257</code>) |
| 0xCC | Specifies a Russian character set. (IANA name <code>windows-1251</code>) |
| 0xDE | Specifies a Thai character set. (IANA name <code>windows-874</code>) |
| 0xEE | Specifies an Eastern European character set. (IANA name <code>windows-1250</code>) |
| 0xFF | Specifies an OEM character set not defined by the standard. |
| Any other value | Application-defined, may be ignored. |

c. *The standard states that the `pitchFamily` attribute of the `buFont`, `cs`, `ea`, `font`, `latin` and `sym` elements specifies the most similar font family.*

In Office, the `pitchFamily` attribute specifies the font pitch as well as the font family for the corresponding font. Because the value of this attribute is determined by a byte variable this value shall be interpreted as follows:

| Value | Description |
|-------|---|
| 0x00 | DEFAULT PITCH + UNKNOWN FONT FAMILY |
| 0x01 | FIXED PITCH + UNKNOWN FONT FAMILY |
| 0x02 | VARIABLE PITCH + UNKNOWN FONT FAMILY |
| 0x10 | DEFAULT PITCH + ROMAN FONT FAMILY |
| 0x11 | FIXED PITCH + ROMAN FONT FAMILY |
| 0x12 | VARIABLE PITCH + ROMAN FONT FAMILY |
| 0x20 | DEFAULT PITCH + SWISS FONT FAMILY |
| 0x21 | FIXED PITCH + SWISS FONT FAMILY |
| 0x22 | VARIABLE PITCH + SWISS FONT FAMILY |
| 0x30 | DEFAULT PITCH + MODERN FONT FAMILY |
| 0x31 | FIXED PITCH + MODERN FONT FAMILY |
| 0x32 | VARIABLE PITCH + MODERN FONT FAMILY |
| 0x40 | DEFAULT PITCH + SCRIPT FONT FAMILY |
| 0x41 | FIXED PITCH + SCRIPT FONT FAMILY |
| 0x42 | VARIABLE PITCH + SCRIPT FONT FAMILY |
| 0x50 | DEFAULT PITCH + DECORATIVE FONT FAMILY |
| 0x51 | FIXED PITCH + DECORATIVE FONT FAMILY |
| 0x52 | VARIABLE PITCH + DECORATIVE FONT FAMILY |

This information is determined by querying the font when present and shall not be modified when the font is not available. This information may be used in font substitution logic to locate an appropriate substitute font when this font is not available.

d. *The standard states that the typeface attribute of the buFont, cs, ea, font, latin and sym elements specifies the typeface of the font to be used for a bullet.*

Office uses this typeface attribute for all text when a typeface is available, and uses font substitution logic when the typeface is not available.

2.1.1317 Part 4 Section 5.1.5.3.8, r (Text Run)

a. *The standard states that if no text run properties are specified, then properties in the defRPr element are used.*

In Office, if no text run properties are specified, then properties will be assigned values as described in child element rPr (Text Run Properties).

2.1.1318 Part 4 Section 5.1.5.3.9, rPr (Text Run Properties)

a. *The standard specifies a default kerning for fonts down to a 0 point for the kern attribute of the rPr, defRpr and endParaRPr elements.*

Office uses a default value of no kerning if the kern attribute is not specified.

b. *The standard states that the smtClean attribute of the rPr, defRpr and endParaRPr elements has a default value of 0 or false.*

In Office, the smtClean attribute of the rPr, defRpr and endParaRPr elements has a default value of true.

c. *The standard does not fully describe the process for resolving missing attribute values.*

In Office, attributes not specified explicitly within this element shall have their values determined by inheritance. Attribute values will be resolved using an applicable ancestor element of the same type as this element. The inheritance order in which another applicable attribute value shall be applied is as follows:

A corresponding ancestor element which is a child element of the lstStyle element ("[\[ECMA-376\]](#) Part 4 §5.1.5.4.12; lstStyle (Text List Styles)") contained within the same package part as the text to which it applies that also has a matching paragraph level value.

A corresponding ancestor element which is a child element of the lstStyle element ("[\[ECMA-376\]](#) Part 4 §5.1.5.4.12; lstStyle (Text List Styles)") contained within the theme element ("[\[ECMA-376\]](#) Part 4 §5.1.8.9; theme (Theme)").

If the value of an attribute is not determined via this process, the default value specified within this element shall be used.

PowerPoint uses a corresponding child element which is contained within the corresponding sldMaster element ("[\[ECMA-376\]](#) Part 4 §4.4.1.39; sldMaster (Slide Master)") if the value of an attribute is not determined by this inheritance order. If the corresponding sldMaster element ("[\[ECMA-376\]](#) Part 4 §4.4.1.39; sldMaster (Slide Master)") does not specify the value of the attribute and the value was not determined from the inheritance order, then the default value specified within this element shall be used.

d. *The standard does not specify usage with negative versus positive values or a default value for the baseline attribute of the rPr, defRpr and endParaRpr elements.*

Office uses negative attribute values for subscript text, positive values for superscript text and a default value of 0.

e. *The standard states that the sz attribute of the rPr, defRpr and endParaRPr elements retrieve its default value from the defRpr element.*

Office uses a default value of 1800 for this attribute.

f. *The standard does not specify a default value for the noProof attribute of the rPr, defRpr and endParaRPr elements.*

Office uses a default value of 0, or false, for this attribute.

g. *The standard does not specify a default value for the cap attribute of the rPr, defRpr and endParaRPr elements.*

Office uses a default value of none for this attribute.

2.1.1319 Part 4 Section 5.1.5.3.10, sym (Symbol Font)

For additional notes that apply to this portion of the standard, please see the notes for [latin](#), [§5.1.5.3.7\(a-d\)](#).

2.1.1320 Part 4 Section 5.1.5.3.13, uFillTx (Underline Fill Properties Follow Text)

a. The standard states that the `uFillTx` element specifies the fill color of an underline and should be the same color as the run of text within which it is contained.

In Office, the `uFillTx` element specifies that the fill color and all other fill properties of an underline are the same as the run of text within which it is contained.

2.1.1321 Part 4 Section 5.1.5.3.14, uLn (Underline Stroke)

For additional notes that apply to this portion of the standard, please see the notes for [ln](#), [§5.1.2.1.24\(a, b\)](#).

a. The standard allows for the specifying of the `tailEnd` child element, `headEnd` child element and `cap` attribute within the `uLn` element.

Office does not use the `tailEnd` child element, `headEnd` child element and `cap` attribute when the parent element is the `rPr` element.

2.1.1322 Part 4 Section 5.1.5.4.6, buFont (Specified)

For additional notes that apply to this portion of the standard, please see the notes for [latin](#), [§5.1.5.3.7\(a-d\)](#).

2.1.1323 Part 4 Section 5.1.5.4.9, buSzPct (Bullet Size Percentage)

a. The standard implies that the `val` attribute is optional.

Office requires this attribute.

2.1.1324 Part 4 Section 5.1.5.4.10, buSzPts (Bullet Size Points)

a. The standard implies that the `val` attribute is optional.

Office requires this attribute.

2.1.1325 Part 4 Section 5.1.5.4.13, lvl1pPr (List Level 1 Text Style)

a. The standard implies a default value of 347663 for the `marL` attribute of the `pPr`, `lvl1pPr`, `lvl2pPr`, `lvl3pPr`, `lvl4pPr`, `lvl5pPr`, `lvl6pPr`, `lvl7pPr`, `lvl8pPr`, `lvl9pPr` and `defpPr` elements.

Office uses a default value of 0 for the `marL` attribute.

b. The standard states that the `lvl` attribute of the `pPr`, `lvl1pPr`, `lvl2pPr`, `lvl3pPr`, `lvl4pPr`, `lvl5pPr`, `lvl6pPr`, `lvl7pPr`, `lvl8pPr`, `lvl9pPr` and `defpPr` elements specifies the text property level that the corresponding paragraph will follow.

Office does not use the `lvl` attribute if it is specified within the `lvl1pPr`, `lvl2pPr`, `lvl3pPr`, `lvl4pPr`, `lvl5pPr`, `lvl6pPr`, `lvl7pPr`, `lvl8pPr`, or `lvl9pPr` elements.

c. The standard describes the use of a hyphen when a word is broken across multiple lines for the `eaLnBrk` attribute of the `pPr`, `lvl1pPr`, `lvl2pPr`, `lvl3pPr`, `lvl4pPr`, `lvl5pPr`, `lvl6pPr`, `lvl7pPr`, `lvl8pPr`, `lvl9pPr` and `defpPr` elements.

In Office, the `eaLnBrk` attribute specifies whether East Asian typography and line-breaking rules shall be applied to text in a paragraph to determine which characters may begin and end each line when lines get too long. To determine whether an East Asian word can be broken, the presentation application would use the `kinsoku` settings. If this attribute is omitted, then a value of **1**, or true, is implied.

d. The standard implies a default value of 0 or false for the `hangingPunct` attribute of the `pPr`, `lvl1pPr`, `lvl2pPr`, `lvl3pPr`, `lvl4pPr`, `lvl5pPr`, `lvl6pPr`, `lvl7pPr`, `lvl8pPr`, `lvl9pPr` and `defpPr` elements.

Office uses a default value of 1, or true, for the `hangingPunct` attribute.

e. The standard specifies no default value for the `defTabSz` attribute of the `pPr`, `lvl1pPr`, `lvl2pPr`, `lvl3pPr`, `lvl4pPr`, `lvl5pPr`, `lvl6pPr`, `lvl7pPr`, `lvl8pPr`, `lvl9pPr` and `defpPr` elements.

Office uses a default value of 914400 EMUs.

f. The standard implies a default value of -342900 for the `indent` attribute of the `pPr`, `lvl1pPr`, `lvl2pPr`, `lvl3pPr`, `lvl4pPr`, `lvl5pPr`, `lvl6pPr`, `lvl7pPr`, `lvl8pPr`, `lvl9pPr` and `defpPr` elements.

Office uses a default value of 0 for the `indent` attribute.

g. The standard implies a default value of 1 or true for the `latinLnBrk` attribute of the `pPr`, `lvl1pPr`, `lvl2pPr`, `lvl3pPr`, `lvl4pPr`, `lvl5pPr`, `lvl6pPr`, `lvl7pPr`, `lvl8pPr`, `lvl9pPr` and `defpPr` elements.

Office uses a default value of 0, or false, for the `latinLnBrk` attribute.

2.1.1326 Part 4 Section 5.1.5.4.14, lvl2pPr (List Level 2 Text Style)

For additional notes that apply to this portion of the standard, please see the notes for [lvl1pPr, §5.1.5.4.13\(a-g\)](#).

2.1.1327 Part 4 Section 5.1.5.4.15, lvl3pPr (List Level 3 Text Style)

For additional notes that apply to this portion of the standard, please see the notes for [lvl1pPr, §5.1.5.4.13\(a-g\)](#).

2.1.1328 Part 4 Section 5.1.5.4.16, lvl4pPr (List Level 4 Text Style)

For additional notes that apply to this portion of the standard, please see the notes for [lvl1pPr, §5.1.5.4.13\(a-g\)](#).

2.1.1329 Part 4 Section 5.1.5.4.17, lvl5pPr (List Level 5 Text Style)

For additional notes that apply to this portion of the standard, please see the notes for [lvl1pPr, §5.1.5.4.13\(a-g\)](#).

2.1.1330 Part 4 Section 5.1.5.4.18, lvl6pPr (List Level 6 Text Style)

For additional notes that apply to this portion of the standard, please see the notes for [lvl1pPr, §5.1.5.4.13\(a-g\)](#).

2.1.1331 Part 4 Section 5.1.5.4.19, lvl7pPr (List Level 7 Text Style)

For additional notes that apply to this portion of the standard, please see the notes for [lvl1pPr, §5.1.5.4.13\(a-g\)](#).

2.1.1332 Part 4 Section 5.1.5.4.20, lvl8pPr (List Level 8 Text Style)

For additional notes that apply to this portion of the standard, please see the notes for [lvl1pPr, §5.1.5.4.13\(a-g\)](#).

2.1.1333 Part 4 Section 5.1.5.4.21, lvl9pPr (List Level 9 Text Style)

For additional notes that apply to this portion of the standard, please see the notes for [lvl1pPr, §5.1.5.4.13\(a-g\)](#).

2.1.1334 Part 4 Section 5.1.6.1, cell3D (Cell 3-D)

a. *The standard states that the default value of the prstMaterial attribute is plastic.*

Office uses a default value of dkEdge for this attribute.

b. *The standard does not specify the default value for the rig attribute if no lightRig element is specified.*

Office uses "flood" for the rig attribute of lightRig in cell3D if no lightRig is specified.

2.1.1335 Part 4 Section 5.1.6.2, gridCol (Table Grid Column)

a. *The standard specifies that the w attribute defines the width of the column in EMUs.*

In Office, the width of the column is equal to or greater than the sum of the marL and marR attributes of the tcPr element plus two points for each cell in the column. One point is equal to 12700 EMUs.

2.1.1336 Part 4 Section 5.1.6.3, InB (Bottom Border Line Properties)

For additional notes that apply to this portion of the standard, please see the notes for [In, §5.1.2.1.24\(a, b\)](#).

a. *The standard specifies that EG_LineFillProperties is optional.*

In Office, the table is not rendered if there are no line fill properties specified.

This note applies to the following products: 2007, 2007 SP1.

2.1.1337 Part 4 Section 5.1.6.4, InBToTr (Bottom-Left to Top-Right Border Line Properties)

For additional notes that apply to this portion of the standard, please see the notes for [In, §5.1.2.1.24\(a, b\)](#).

a. *The standard specifies that EG_LineFillProperties is optional.*

In Office, the table is not rendered if there are no line fill properties specified.

This note applies to the following products: 2007, 2007 SP1.

2.1.1338 Part 4 Section 5.1.6.5, InL (Left Border Line Properties)

For additional notes that apply to this portion of the standard, please see the notes for [ln, §5.1.2.1.24\(a, b\)](#).

- a. *The standard specifies that EG_LineFillProperties is optional.*

In Office, the table is not rendered if there are no line fill properties specified.

This note applies to the following products: 2007, 2007 SP1.

2.1.1339 Part 4 Section 5.1.6.6, InR (Right Border Line Properties)

For additional notes that apply to this portion of the standard, please see the notes for [ln, §5.1.2.1.24\(a, b\)](#).

- a. *The standard specifies that EG_LineFillProperties is optional.*

In Office, the table is not rendered if there are no line fill properties specified.

This note applies to the following products: 2007, 2007 SP1.

2.1.1340 Part 4 Section 5.1.6.7, InT (Top Border Line Properties)

For additional notes that apply to this portion of the standard, please see the notes for [ln, §5.1.2.1.24\(a, b\)](#).

- a. *The standard specifies that EG_LineFillProperties is optional.*

In Office, the table is not rendered if there are no line fill properties specified.

This note applies to the following products: 2007, 2007 SP1.

2.1.1341 Part 4 Section 5.1.6.8, InTToBr (Top-Left to Bottom-Right Border Line Properties)

For additional notes that apply to this portion of the standard, please see the notes for [ln, §5.1.2.1.24\(a, b\)](#).

- a. *The standard specifies that EG_LineFillProperties is optional.*

In Office, the table is not rendered if there are no line fill properties specified.

This note applies to the following products: 2007, 2007 SP1.

2.1.1342 Part 4 Section 5.1.6.10, tableStyleId (Table Style ID)

- a. *The standard does not state how to interpret an invalid table style defined by the tableStyleId element.*

Office does not apply a style to the table if this element does not point to a valid built-in or user-specified table style.

- b. *The standard states that the tableStyleId element specifies the id for a table style specified within the package.*

The tableStyleId shall specify a tableStyle ("[\[ECMA-376\]](#) Part 4 §5.1.6.9; tableStyle") to be one of the two following types, a built-in table style or a user-specified table style.

If the tableStyleId specified matches a built-in table style ID, then it is considered a built-in table style. A built-in table style is a style that is pre-defined within Office. There are 15 base built-in table styles. Based on these, there are an additional 59 built-in table styles that are derived using color replacement algorithms.

If the tableStyleId specified does not match a built-in table style ID then it is considered a user-specified table style. A user-specified table style is a table style defined within the tblStyle element ("[\[ECMA-376\]](#) Part 4 §5.1.4.2.26; tblStyle") that is contained within the tblStyleLst element ("[\[ECMA-376\]](#) Part 4 §5.1.4.2.27; tblStyleLst").

The following table lists the 74 total built-in table styles and their corresponding table style ID:

| Built-In Table Style Name / Id | Base Built-In Table Style Id | Color Replace Algorithm |
|---|--|--------------------------------|
| No Style, No Grid {2D5ABB26-0587-4C30-8999-92F81FD0307C} | {2D5ABB26-0587-4C30-8999-92F81FD0307C} | |
| Themed Style 1 - Accent 1 {3C2FFA5D-87B4-456A-9821-1D502468CF0F} | {3C2FFA5D-87B4-456A-9821-1D502468CF0F} | |
| Themed Style 1 - Accent 2 {284E427A-3D55-4303-BF80-6455036E1DE7} | {3C2FFA5D-87B4-456A-9821-1D502468CF0F} | accent1 replaced with accent2 |
| Themed Style 1 - Accent 3 {69C7853C-536D-4A76-A0AE-DD22124D55A5} | {3C2FFA5D-87B4-456A-9821-1D502468CF0F} | accent1 replaced with accent3 |
| Themed Style 1 - Accent 4 {775DCB02-9BB8-47FD-8907-85C794F793BA} | {3C2FFA5D-87B4-456A-9821-1D502468CF0F} | accent1 replaced with accent4 |
| Themed Style 1 - Accent 5 {35758FB7-9AC5-4552-8A53-C91805E547FA} | {3C2FFA5D-87B4-456A-9821-1D502468CF0F} | accent1 replaced with accent5 |
| Themed Style 1 - Accent 6 {08FB837D-C827-4EFA-A057-4D05807E0F7C} | {3C2FFA5D-87B4-456A-9821-1D502468CF0F} | accent1 replaced with accent6 |
| No Style, Table Grid {5940675A-B579-460E-94D1-54222C63F5DA} | {5940675A-B579-460E-94D1-54222C63F5DA} | |
| Themed Style 2 - Accent 1 {D113A9D2-9D6B-4929-AA2D-F23B5EE8CBE7} | {D113A9D2-9D6B-4929-AA2D-F23B5EE8CBE7} | |
| Themed Style 2 - Accent 2 {18603FDC-E32A-4AB5-989C-0864C3EAD2B8} | {D113A9D2-9D6B-4929-AA2D-F23B5EE8CBE7} | accent1 replaced with accent2 |

| Built-In Table Style Name / Id | Base Built-In Table Style Id | Color Replace Algorithm |
|---|--|--------------------------------|
| Themed Style 2 - Accent 3 {306799F8-075E-4A3A-A7F6-7FBC6576F1A4} | {D113A9D2-9D6B-4929-AA2D-F23B5EE8CBE7} | accent1 replaced with accent3 |
| Themed Style 2 - Accent 4 {E269D01E-BC32-4049-B463-5C60D7B0CCD2} | {D113A9D2-9D6B-4929-AA2D-F23B5EE8CBE7} | accent1 replaced with accent4 |
| Themed Style 2 - Accent 5 {327F97BB-C833-4FB7-BDE5-3F7075034690} | {D113A9D2-9D6B-4929-AA2D-F23B5EE8CBE7} | accent1 replaced with accent5 |
| Themed Style 2 - Accent 6 {638B1855-1B75-4FBE-930C-398BA8C253C6} | {D113A9D2-9D6B-4929-AA2D-F23B5EE8CBE7} | accent1 replaced with accent6 |
| Light Style 1 {9D7B26C5-4107-4FEC-AEDC-1716B250A1EF} | {9D7B26C5-4107-4FEC-AEDC-1716B250A1EF} | |
| Light Style 1 – Accent 1 {3B4B98B0-60AC-42C2-AFA5-B58CD77FA1E5} | {9D7B26C5-4107-4FEC-AEDC-1716B250A1EF} | tx1 replaced with accent1 |
| Light Style 1 – Accent 2 {0E3FDE45-AF77-4B5C-9715-49D594BDF05E} | {9D7B26C5-4107-4FEC-AEDC-1716B250A1EF} | tx1 replaced with accent2 |
| Light Style 1 – Accent 3 {C083E6E3-FA7D-4D7B-A595-EF9225AFE82} | {9D7B26C5-4107-4FEC-AEDC-1716B250A1EF} | tx1 replaced with accent3 |
| Light Style 1 – Accent 4 {D27102A9-8310-4765-A935-A1911B00CA55} | {9D7B26C5-4107-4FEC-AEDC-1716B250A1EF} | tx1 replaced with accent4 |
| Light Style 1 – Accent 5 {5FD0F851-EC5A-4D38-B0AD-8093EC10F338} | {9D7B26C5-4107-4FEC-AEDC-1716B250A1EF} | tx1 replaced with accent5 |
| Light Style 1 – Accent 6 {68D230F3-CF80-4859-8CE7-A43EE81993B5} | {9D7B26C5-4107-4FEC-AEDC-1716B250A1EF} | tx1 replaced with accent6 |
| Light Style 2 {7E9639D4-E3E2-4D34-9284-5A2195B3D0D7} | {7E9639D4-E3E2-4D34-9284-5A2195B3D0D7} | |
| Light Style 2 – Accent 1 {69012ECD-51FC-41F1-AA8D-1B2483CD663E} | {7E9639D4-E3E2-4D34-9284-5A2195B3D0D7} | tx1 replaced with accent1 |
| Light Style 2 – Accent 2 {72833802-FEF1-4C79-8D5D-14CF1EAF98D9} | {7E9639D4-E3E2-4D34-9284-5A2195B3D0D7} | tx1 replaced with accent2 |

| Built-In Table Style Name / Id | Base Built-In Table Style Id | Color Replace Algorithm |
|---|--|--------------------------------|
| Light Style 2 – Accent 3 {F2DE63D5-997A-4646-A377-4702673A728D} | {7E9639D4-E3E2-4D34-9284-5A2195B3D0D7} | tx1 replaced with accent3 |
| Light Style 2 – Accent 4 {17292A2E-F333-43FB-9621-5CBBE7FDCDCB} | {7E9639D4-E3E2-4D34-9284-5A2195B3D0D7} | tx1 replaced with accent4 |
| Light Style 2 – Accent 5 {5A111915-BE36-4E01-A7E5-04B1672EAD32} | {7E9639D4-E3E2-4D34-9284-5A2195B3D0D7} | tx1 replaced with accent5 |
| Light Style 2 – Accent 6 {912C8C85-51F0-491E-9774-3900AFEF0FD7} | {7E9639D4-E3E2-4D34-9284-5A2195B3D0D7} | tx1 replaced with accent6 |
| Light Style 3 {616DA210-FB5B-4158-B5E0-FEB733F419BA} | {616DA210-FB5B-4158-B5E0-FEB733F419BA} | |
| Light Style 3 – Accent 1 {BC89EF96-8CEA-46FF-86C4-4CE0E7609802} | {616DA210-FB5B-4158-B5E0-FEB733F419BA} | tx1 replaced with accent1 |
| Light Style 3 – Accent 2 {5DA37D80-6434-44D0-A028-1B22A696006F} | {616DA210-FB5B-4158-B5E0-FEB733F419BA} | tx1 replaced with accent2 |
| Light Style 3 – Accent 3 {8799B23B-EC83-4686-B30A-512413B5E67A} | {616DA210-FB5B-4158-B5E0-FEB733F419BA} | tx1 replaced with accent3 |
| Light Style 3 – Accent 4 {ED083AE6-46FA-4A59-8FB0-9F97EB10719F} | {616DA210-FB5B-4158-B5E0-FEB733F419BA} | tx1 replaced with accent4 |
| Light Style 3 – Accent 5 {BDBED569-4797-4DF1-A0F4-6AAB3CD982D8} | {616DA210-FB5B-4158-B5E0-FEB733F419BA} | tx1 replaced with accent5 |
| Light Style 3 – Accent 6 {E8B1032C-EA38-4F05-BA0D-38AFFFC7BED3} | {616DA210-FB5B-4158-B5E0-FEB733F419BA} | tx1 replaced with accent6 |
| Medium Style 1 {793D81CF-94F2-401A-BA57-92F5A7B2D0C5} | {793D81CF-94F2-401A-BA57-92F5A7B2D0C5} | |
| Medium Style 1 – Accent 1 {B301B821-A1FF-4177-AEE7-76D212191A09} | {793D81CF-94F2-401A-BA57-92F5A7B2D0C5} | dk1 replaced with accent1 |
| Medium Style 1 – Accent 2 {9DCAF9ED-07DC-4A11-8D7F-57B35C25682E} | {793D81CF-94F2-401A-BA57-92F5A7B2D0C5} | dk1 replaced with accent2 |

| Built-In Table Style Name / Id | Base Built-In Table Style Id | Color Replace Algorithm |
|---|--|--------------------------------|
| Medium Style 1 – Accent 3 {1FECB4D8-DB02-4DC6-A0A2-4F2EBAE1DC90} | {793D81CF-94F2-401A-BA57-92F5A7B2D0C5} | dk1 replaced with accent3 |
| Medium Style 1 – Accent 4 {1E171933-4619-4E11-9A3F-F7608DF75F80} | {793D81CF-94F2-401A-BA57-92F5A7B2D0C5} | dk1 replaced with accent4 |
| Medium Style 1 – Accent 5 {FABFCF23-3B69-468F-B69F-88F6DE6A72F2} | {793D81CF-94F2-401A-BA57-92F5A7B2D0C5} | dk1 replaced with accent5 |
| Medium Style 1 – Accent 6 {10A1B5D5-9B99-4C35-A422-299274C87663} | {793D81CF-94F2-401A-BA57-92F5A7B2D0C5} | dk1 replaced with accent6 |
| Medium Style 2 {073A0DAA-6AF3-43AB-8588-CEC1D06C72B9} | {073A0DAA-6AF3-43AB-8588-CEC1D06C72B9} | |
| Medium Style 2 – Accent 1 {5C22544A-7EE6-4342-B048-85BDC9FD1C3A} | {073A0DAA-6AF3-43AB-8588-CEC1D06C72B9} | dk1 replaced with accent1 |
| Medium Style 2 – Accent 2 {21E4AEA4-8DFA-4A89-87EB-49C32662AFE0} | {073A0DAA-6AF3-43AB-8588-CEC1D06C72B9} | dk1 replaced with accent2 |
| Medium Style 2 – Accent 3 {F5AB1C69-6EDB-4FF4-983F-18BD219EF322} | {073A0DAA-6AF3-43AB-8588-CEC1D06C72B9} | dk1 replaced with accent3 |
| Medium Style 2 – Accent 4 {00A15C55-8517-42AA-B614-E9B94910E393} | {073A0DAA-6AF3-43AB-8588-CEC1D06C72B9} | dk1 replaced with accent4 |
| Medium Style 2 – Accent 5 {7DF18680-E054-41AD-8BC1-D1AEF772440D} | {073A0DAA-6AF3-43AB-8588-CEC1D06C72B9} | dk1 replaced with accent5 |
| Medium Style 2 – Accent 6 {93296810-A885-4BE3-A3E7-6D5BEEA58F35} | {073A0DAA-6AF3-43AB-8588-CEC1D06C72B9} | dk1 replaced with accent6 |
| Medium Style 3 {8EC20E35-A176-4012-BC5E-935CFFF8708E} | {8EC20E35-A176-4012-BC5E-935CFFF8708E} | |
| Medium Style 3 – Accent 1 {6E25E649-3F16-4E02-A733-19D2CDBF48F0} | {6E25E649-3F16-4E02-A733-19D2CDBF48F0} | |
| Medium Style 3 – Accent 2 {85BE263C-DBD7-4A20-BB59-AAB30ACAA65A} | {6E25E649-3F16-4E02-A733-19D2CDBF48F0} | accent1 replaced with accent2 |

| Built-In Table Style Name / Id | Base Built-In Table Style Id | Color Replace Algorithm |
|---|--|--------------------------------|
| Medium Style 3 – Accent 3 {EB344D84-9AFB-497E-A393-DC336BA19D2E} | {6E25E649-3F16-4E02-A733-19D2CDBF48F0} | accent1 replaced with accent3 |
| Medium Style 3 – Accent 4 {EB9631B5-78F2-41C9-869B-9F39066F8104} | {6E25E649-3F16-4E02-A733-19D2CDBF48F0} | accent1 replaced with accent4 |
| Medium Style 3 – Accent 5 {74C1A8A3-306A-4EB7-A6B1-4F7E0EB9C5D6} | {6E25E649-3F16-4E02-A733-19D2CDBF48F0} | accent1 replaced with accent5 |
| Medium Style 3 – Accent 6 {2A488322-F2BA-4B5B-9748-0D474271808F} | {6E25E649-3F16-4E02-A733-19D2CDBF48F0} | accent1 replaced with accent6 |
| Medium Style 4 {D7AC3CCA-C797-4891-BE02-D94E43425B78} | {D7AC3CCA-C797-4891-BE02-D94E43425B78} | |
| Medium Style 4 – Accent 1 {69CF1AB2-1976-4502-BF36-3FF5EA218861} | {D7AC3CCA-C797-4891-BE02-D94E43425B78} | dk1 replaced with accent1 |
| Medium Style 4 – Accent 2 {8A107856-5554-42FB-B03E-39F5DBC370BA} | {D7AC3CCA-C797-4891-BE02-D94E43425B78} | dk1 replaced with accent2 |
| Medium Style 4 – Accent 3 {0505E3EF-67EA-436B-97B2-0124C06EBD24} | {D7AC3CCA-C797-4891-BE02-D94E43425B78} | dk1 replaced with accent3 |
| Medium Style 4 – Accent 4 {C4B1156A-380E-4F78-BDF5-A606A8083BF9} | {D7AC3CCA-C797-4891-BE02-D94E43425B78} | dk1 replaced with accent4 |
| Medium Style 4 – Accent 5 {22838BEF-8BB2-4498-84A7-C5851F593DF1} | {D7AC3CCA-C797-4891-BE02-D94E43425B78} | dk1 replaced with accent5 |
| Medium Style 4 – Accent 6 {16D9F66E-5EB9-4882-86FB-DCBF35E3C3E4} | {D7AC3CCA-C797-4891-BE02-D94E43425B78} | dk1 replaced with accent6 |
| Dark Style 1 {E8034E78-7F5D-4C2E-B375-FC64B27BC917} | {E8034E78-7F5D-4C2E-B375-FC64B27BC917} | |
| Dark Style 1 – Accent 1 {125E5076-3810-47DD-B79F-674D7AD40C01} | {125E5076-3810-47DD-B79F-674D7AD40C01} | |
| Dark Style 1 – Accent 2 {37CE84F3-28C3-443E-9E96-99CF82512B78} | {125E5076-3810-47DD-B79F-674D7AD40C01} | accent1 replaced with accent2 |

| Built-In Table Style Name / Id | Base Built-In Table Style Id | Color Replace Algorithm |
|---|--|--|
| Dark Style 1 – Accent 3 {D03447BB-5D67-496B-8E87-E561075AD55C} | {125E5076-3810-47DD-B79F-674D7AD40C01} | accent1 replaced with accent3 |
| Dark Style 1 – Accent 4 {E929F9F4-4A8F-4326-A1B4-22849713DDAB} | {125E5076-3810-47DD-B79F-674D7AD40C01} | accent1 replaced with accent4 |
| Dark Style 1 – Accent 5 {8FD4443E-F989-4FC4-A0C8-D5A2AF1F390B} | {125E5076-3810-47DD-B79F-674D7AD40C01} | accent1 replaced with accent5 |
| Dark Style 1 – Accent 6 {AF606853-7671-496A-8E4F-DF71F8EC918B} | {125E5076-3810-47DD-B79F-674D7AD40C01} | accent1 replaced with accent6 |
| Dark Style 2 {5202B0CA-FC54-4496-8BCA-5EF66A818D29} | {5202B0CA-FC54-4496-8BCA-5EF66A818D29} | |
| Dark Style 2 – Accent 1/Accent2 {0660B408-B3CF-4A94-85FC-2B1E0A45F4A2} | {5202B0CA-FC54-4496-8BCA-5EF66A818D29} | firstRow: dk1 replaced with accent2; other rows: dk1 replaced with accent1; not replace the color of the top line of the lastRow |
| Dark Style 2 – Accent 3/Accent4 {91EBBBCC-DAD2-459C-BE2E-F6DE35CF9A28} | {5202B0CA-FC54-4496-8BCA-5EF66A818D29} | firstRow: dk1 replaced with accent4; other rows: dk1 replaced with accent3; not replace the color of the top line of the lastRow |
| Dark Style 2 – Accent 5/Accent6 {46F890A9-2807-4EBB-B81D-B2AA78EC7F39} | {5202B0CA-FC54-4496-8BCA-5EF66A818D29} | firstRow: dk1 replaced with accent6; other rows: dk1 replaced with accent5; not replace the color of the top line of the lastRow |

And all base built-in tblStyles are defined as follows:

```
<a:tblStyle styleId="{2D5ABB26-0587-4C30-8999-92F81FD0307C}" styleName="">
<a:wholeTbl>
<a:tcTxStyle>
<a:fontRef idx="minor">
<a:scrgbClr r="0" g="0" b="0"/>
</a:fontRef>
```

<a:schemeClr val="tx1"/>
</a:tcTxStyle>
<a:tcStyle>
<a:tcBdr>
<a:left>
<a:ln>
<a:noFill/>
</a:ln>
</a:left>
<a:right>
<a:ln>
<a:noFill/>
</a:ln>
</a:right>
<a:top>
<a:ln>
<a:noFill/>
</a:ln>
</a:top>
<a:bottom>
<a:ln>
<a:noFill/>
</a:ln>
</a:bottom>
<a:insideH>
<a:ln>
<a:noFill/>
</a:ln>
</a:insideH>
<a:insideV>

<a:ln>
<a:noFill/>
</a:ln>
</a:insideV>
</a:tcBdr>
<a:fill>
<a:noFill/>
</a:fill>
</a:tcStyle>
</a:wholeTbl>
</a:tblStyle>
<a:tblStyle styleId="{3C2FFA5D-87B4-456A-9821-1D502468CF0F}" styleName="">
<a:tblBg>
<a:fillRef idx="2">
<a:schemeClr val="accent1"/>
</a:fillRef>
<a:effectRef idx="1">
<a:schemeClr val="accent1"/>
</a:effectRef>
</a:tblBg>
<a:wholeTbl>
<a:tcTxStyle>
<a:fontRef idx="minor">
<a:scrgbClr r="0" g="0" b="0"/>
</a:fontRef>
<a:schemeClr val="dk1"/>
</a:tcTxStyle>
<a:tcStyle>
<a:tcBdr>
<a:left>

<a:lnRef idx="1">
<a:schemeClr val="accent1"/>
</a:lnRef>
</a:left>
<a:right>
<a:lnRef idx="1">
<a:schemeClr val="accent1"/>
</a:lnRef>
</a:right>
<a:top>
<a:lnRef idx="1">
<a:schemeClr val="accent1"/>
</a:lnRef>
</a:top>
<a:bottom>
<a:lnRef idx="1">
<a:schemeClr val="accent1"/>
</a:lnRef>
</a:bottom>
<a:insideH>
<a:lnRef idx="1">
<a:schemeClr val="accent1"/>
</a:lnRef>
</a:insideH>
<a:insideV>
<a:lnRef idx="1">
<a:schemeClr val="accent1"/>
</a:lnRef>
</a:insideV>
</a:tcBdr>

<a:fill>
<a:noFill/>
</a:fill>
</a:tcStyle>
</a:wholeTbl>
<a:band1H>
<a:tcStyle>
<a:tcBdr/>
<a:fill>
<a:solidFill>
<a:schemeClr val="accent1">
<a:alpha val="40000"/>
</a:schemeClr>
</a:solidFill>
</a:fill>
</a:tcStyle>
</a:band1H>
<a:band2H>
<a:tcStyle>
<a:tcBdr/>
</a:tcStyle>
</a:band2H>
<a:band1V>
<a:tcStyle>
<a:tcBdr>
<a:top>
<a:lnRef idx="1">
<a:schemeClr val="accent1"/>
</a:lnRef>
</a:top>

<a:bottom>
<a:lnRef idx="1">
<a:schemeClr val="accent1"/>
</a:lnRef>
</a:bottom>
</a:tcBdr>
<a:fill>
<a:solidFill>
<a:schemeClr val="accent1">
<a:alpha val="40000"/>
</a:schemeClr>
</a:solidFill>
</a:fill>
</a:tcStyle>
</a:band1V>
<a:band2V>
<a:tcStyle>
<a:tcBdr/>
</a:tcStyle>
</a:band2V>
<a:lastCol>
<a:tcTxStyle b="on"/>
<a:tcStyle>
<a:tcBdr>
<a:left>
<a:lnRef idx="2">
<a:schemeClr val="accent1"/>
</a:lnRef>
</a:left>
<a:right>

<a:lnRef idx="1">
<a:schemeClr val="accent1"/>
</a:lnRef>
</a:right>
<a:top>
<a:lnRef idx="1">
<a:schemeClr val="accent1"/>
</a:lnRef>
</a:top>
<a:bottom>
<a:lnRef idx="1">
<a:schemeClr val="accent1"/>
</a:lnRef>
</a:bottom>
<a:insideH>
<a:lnRef idx="1">
<a:schemeClr val="accent1"/>
</a:lnRef>
</a:insideH>
<a:insideV>
<a:ln>
<a:noFill/>
</a:ln>
</a:insideV>
</a:tcBdr>
</a:tcStyle>
</a:lastCol>
<a:firstCol>
<a:tcTxStyle b="on"/>
<a:tcStyle>

<a:tcBdr>
<a:left>
<a:lnRef idx="1">
<a:schemeClr val="accent1"/>
</a:lnRef>
</a:left>
<a:right>
<a:lnRef idx="2">
<a:schemeClr val="accent1"/>
</a:lnRef>
</a:right>
<a:top>
<a:lnRef idx="1">
<a:schemeClr val="accent1"/>
</a:lnRef>
</a:top>
<a:bottom>
<a:lnRef idx="1">
<a:schemeClr val="accent1"/>
</a:lnRef>
</a:bottom>
<a:insideH>
<a:lnRef idx="1">
<a:schemeClr val="accent1"/>
</a:lnRef>
</a:insideH>
<a:insideV>
<a:ln>
<a:noFill/>
</a:ln>

```
</a:insideV>
</a:tcBdr>
</a:tcStyle>
</a:firstCol>
<a:lastRow>
<a:tcTxStyle b="on"/>
<a:tcStyle>
<a:tcBdr>
<a:left>
<a:lnRef idx="1">
<a:schemeClr val="accent1"/>
</a:lnRef>
</a:left>
<a:right>
<a:lnRef idx="1">
<a:schemeClr val="accent1"/>
</a:lnRef>
</a:right>
<a:top>
<a:lnRef idx="2">
<a:schemeClr val="accent1"/>
</a:lnRef>
</a:top>
<a:bottom>
<a:lnRef idx="2">
<a:schemeClr val="accent1"/>
</a:lnRef>
</a:bottom>
<a:insideH>
<a:ln>
```

<a:noFill/>
</a:ln>
</a:insideH>
<a:insideV>
<a:ln>
<a:noFill/>
</a:ln>
</a:insideV>
</a:tcBdr>
<a:fill>
<a:noFill/>
</a:fill>
</a:tcStyle>
</a:lastRow>
<a:firstRow>
<a:tcTxStyle b="on">
<a:fontRef idx="minor">
<a:scrgbClr r="0" g="0" b="0"/>
</a:fontRef>
<a:schemeClr val="lt1"/>
</a:tcTxStyle>
<a:tcStyle>
<a:tcBdr>
<a:left>
<a:lnRef idx="1">
<a:schemeClr val="accent1"/>
</a:lnRef>
</a:left>
<a:right>
<a:lnRef idx="1">

<a:schemeClr val="accent1"/>
</a:lnRef>
</a:right>
<a:top>
<a:lnRef idx="1">
<a:schemeClr val="accent1"/>
</a:lnRef>
</a:top>
<a:bottom>
<a:lnRef idx="2">
<a:schemeClr val="lt1"/>
</a:lnRef>
</a:bottom>
<a:insideH>
<a:ln>
<a:noFill/>
</a:ln>
</a:insideH>
<a:insideV>
<a:ln>
<a:noFill/>
</a:ln>
</a:insideV>
</a:tcBdr>
<a:fill>
<a:solidFill>
<a:schemeClr val="accent1"/>
</a:solidFill>
</a:fill>
</a:tcStyle>

```
</a:firstRow>
</a:tblStyle>
<a:tblStyle styleId="{5940675A-B579-460E-94D1-54222C63F5DA}" styleName="">
<a:wholeTbl>
<a:tcTxStyle>
<a:fontRef idx="minor">
<a:scrgbClr r="0" g="0" b="0"/>
</a:fontRef>
<a:schemeClr val="tx1"/>
</a:tcTxStyle>
<a:tcStyle>
<a:tcBdr>
<a:left>
<a:ln w="12700" cmpd="sng">
<a:solidFill>
<a:schemeClr val="tx1"/>
</a:solidFill>
</a:ln>
</a:left>
<a:right>
<a:ln w="12700" cmpd="sng">
<a:solidFill>
<a:schemeClr val="tx1"/>
</a:solidFill>
</a:ln>
</a:right>
<a:top>
<a:ln w="12700" cmpd="sng">
<a:solidFill>
<a:schemeClr val="tx1"/>
```

```
</a:solidFill>
</a:ln>
</a:top>
<a:bottom>
<a:ln w="12700" cmpd="sng">
<a:solidFill>
<a:schemeClr val="tx1"/>
</a:solidFill>
</a:ln>
</a:bottom>
<a:insideH>
<a:ln w="12700" cmpd="sng">
<a:solidFill>
<a:schemeClr val="tx1"/>
</a:solidFill>
</a:ln>
</a:insideH>
<a:insideV>
<a:ln w="12700" cmpd="sng">
<a:solidFill>
<a:schemeClr val="tx1"/>
</a:solidFill>
</a:ln>
</a:insideV>
</a:tcBdr>
<a:fill>
<a:noFill/>
</a:fill>
</a:tcStyle>
</a:wholeTbl>
```

```
</a:tblStyle>
<a:tblStyle styleId="{D113A9D2-9D6B-4929-AA2D-F23B5EE8CBE7}" styleName="">
<a:tblBg>
<a:fillRef idx="3">
<a:schemeClr val="accent1"/>
</a:fillRef>
<a:effectRef idx="3">
<a:schemeClr val="accent1"/>
</a:effectRef>
</a:tblBg>
<a:wholeTbl>
<a:tcTxStyle>
<a:fontRef idx="minor">
<a:scrgbClr r="0" g="0" b="0"/>
</a:fontRef>
<a:schemeClr val="lt1"/>
</a:tcTxStyle>
<a:tcStyle>
<a:tcBdr>
<a:left>
<a:lnRef idx="1">
<a:schemeClr val="accent1">
<a:tint val="50000"/>
</a:schemeClr>
</a:lnRef>
</a:left>
<a:right>
<a:lnRef idx="1">
<a:schemeClr val="accent1">
<a:tint val="50000"/>
```

</a:schemeClr>
</a:lnRef>
</a:right>
<a:top>
<a:lnRef idx="1">
<a:schemeClr val="accent1">
<a:tint val="50000"/>
</a:schemeClr>
</a:lnRef>
</a:top>
<a:bottom>
<a:lnRef idx="1">
<a:schemeClr val="accent1">
<a:tint val="50000"/>
</a:schemeClr>
</a:lnRef>
</a:bottom>
<a:insideH>
<a:ln>
<a:noFill/>
</a:ln>
</a:insideH>
<a:insideV>
<a:ln>
<a:noFill/>
</a:ln>
</a:insideV>
</a:tcBdr>
<a:fill>
<a:noFill/>

</a:fill>
</a:tcStyle>
</a:wholeTbl>
<a:band1H>
<a:tcStyle>
<a:tcBdr/>
<a:fill>
<a:solidFill>
<a:schemeClr val="lt1">
<a:alpha val="20000"/>
</a:schemeClr>
</a:solidFill>
</a:fill>
</a:tcStyle>
</a:band1H>
<a:band1V>
<a:tcStyle>
<a:tcBdr/>
<a:fill>
<a:solidFill>
<a:schemeClr val="lt1">
<a:alpha val="20000"/>
</a:schemeClr>
</a:solidFill>
</a:fill>
</a:tcStyle>
</a:band1V>
<a:lastCol>
<a:tcTxStyle b="on"/>
<a:tcStyle>

<a:tcBdr>
<a:left>
<a:lnRef idx="2">
<a:schemeClr val="lt1"/>
</a:lnRef>
</a:left>
</a:tcBdr>
</a:tcStyle>
</a:lastCol>
<a:firstCol>
<a:tcTxStyle b="on"/>
<a:tcStyle>
<a:tcBdr>
<a:right>
<a:lnRef idx="2">
<a:schemeClr val="lt1"/>
</a:lnRef>
</a:right>
</a:tcBdr>
</a:tcStyle>
</a:firstCol>
<a:lastRow>
<a:tcTxStyle b="on"/>
<a:tcStyle>
<a:tcBdr>
<a:top>
<a:lnRef idx="2">
<a:schemeClr val="lt1"/>
</a:lnRef>
</a:top>

</a:tcBdr>
<a:fill>
<a:noFill/>
</a:fill>
</a:tcStyle>
</a:lastRow>
<a:seCell>
<a:tcStyle>
<a:tcBdr>
<a:left>
<a:ln>
<a:noFill/>
</a:ln>
</a:left>
<a:top>
<a:ln>
<a:noFill/>
</a:ln>
</a:top>
</a:tcBdr>
</a:tcStyle>
</a:seCell>
<a:swCell>
<a:tcStyle>
<a:tcBdr>
<a:right>
<a:ln>
<a:noFill/>
</a:ln>
</a:right>

<a:top>
<a:ln>
<a:noFill/>
</a:ln>
</a:top>
</a:tcBdr>
</a:tcStyle>
</a:swCell>
<a:firstRow>
<a:tcTxStyle b="on"/>
<a:tcStyle>
<a:tcBdr>
<a:bottom>
<a:lnRef idx="3">
<a:schemeClr val="lt1"/>
</a:lnRef>
</a:bottom>
</a:tcBdr>
<a:fill>
<a:noFill/>
</a:fill>
</a:tcStyle>
</a:firstRow>
<a:neCell>
<a:tcStyle>
<a:tcBdr>
<a:bottom>
<a:ln>
<a:noFill/>
</a:ln>

</a:bottom>
</a:tcBdr>
</a:tcStyle>
</a:neCell>
</a:tblStyle>
<a:tblStyle styleId="{9D7B26C5-4107-4FEC-AEDC-1716B250A1EF}" styleName="">
<a:wholeTbl>
<a:tcTxStyle>
<a:fontRef idx="minor">
<a:scrgbClr r="0" g="0" b="0"/>
</a:fontRef>
<a:schemeClr val="tx1"/>
</a:tcTxStyle>
<a:tcStyle>
<a:tcBdr>
<a:left>
<a:ln>
<a:noFill/>
</a:ln>
</a:left>
<a:right>
<a:ln>
<a:noFill/>
</a:ln>
</a:right>
<a:top>
<a:ln w="12700" cmpd="sng">
<a:solidFill>
<a:schemeClr val="tx1"/>
</a:solidFill>

</a:ln>
</a:top>
<a:bottom>
<a:ln w="12700" cmpd="sng">
<a:solidFill>
<a:schemeClr val="tx1"/>
</a:solidFill>
</a:ln>
</a:bottom>
<a:insideH>
<a:ln>
<a:noFill/>
</a:ln>
</a:insideH>
<a:insideV>
<a:ln>
<a:noFill/>
</a:ln>
</a:insideV>
</a:tcBdr>
<a:fill>
<a:noFill/>
</a:fill>
</a:tcStyle>
</a:wholeTbl>
<a:band1H>
<a:tcStyle>
<a:tcBdr/>
<a:fill>
<a:solidFill>

```
<a:schemeClr val="tx1">
<a:alpha val="20000"/>
</a:schemeClr>
</a:solidFill>
</a:fill>
</a:tcStyle>
</a:band1H>
<a:band2H>
<a:tcStyle>
<a:tcBdr/>
</a:tcStyle>
</a:band2H>
<a:band1V>
<a:tcStyle>
<a:tcBdr/>
<a:fill>
<a:solidFill>
<a:schemeClr val="tx1">
<a:alpha val="20000"/>
</a:schemeClr>
</a:solidFill>
</a:fill>
</a:tcStyle>
</a:band1V>
<a:lastCol>
<a:tcTxStyle b="on"/>
<a:tcStyle>
<a:tcBdr/>
</a:tcStyle>
</a:lastCol>
```

<a:firstCol>
<a:tcTxStyle b="on"/>
<a:tcStyle>
<a:tcBdr/>
</a:tcStyle>
</a:firstCol>
<a:lastRow>
<a:tcTxStyle b="on"/>
<a:tcStyle>
<a:tcBdr>
<a:top>
<a:ln w="12700" compd="sng">
<a:solidFill>
<a:schemeClr val="tx1"/>
</a:solidFill>
</a:ln>
</a:top>
</a:tcBdr>
<a:fill>
<a:noFill/>
</a:fill>
</a:tcStyle>
</a:lastRow>
<a:firstRow>
<a:tcTxStyle b="on"/>
<a:tcStyle>
<a:tcBdr>
<a:bottom>
<a:ln w="12700" compd="sng">
<a:solidFill>

<a:schemeClr val="tx1"/>
</a:solidFill>
</a:ln>
</a:bottom>
</a:tcBdr>
<a:fill>
<a:noFill/>
</a:fill>
</a:tcStyle>
</a:firstRow>
</a:tblStyle>
<a:tblStyle styleId="{7E9639D4-E3E2-4D34-9284-5A2195B3D0D7}" styleName="">
<a:wholeTbl>
<a:tcTxStyle>
<a:fontRef idx="minor">
<a:scrgbClr r="0" g="0" b="0"/>
</a:fontRef>
<a:schemeClr val="tx1"/>
</a:tcTxStyle>
<a:tcStyle>
<a:tcBdr>
<a:left>
<a:lnRef idx="1">
<a:schemeClr val="tx1"/>
</a:lnRef>
</a:left>
<a:right>
<a:lnRef idx="1">
<a:schemeClr val="tx1"/>
</a:lnRef>

</a:right>
<a:top>
<a:lnRef idx="1">
<a:schemeClr val="tx1"/>
</a:lnRef>
</a:top>
<a:bottom>
<a:lnRef idx="1">
<a:schemeClr val="tx1"/>
</a:lnRef>
</a:bottom>
<a:insideH>
<a:ln>
<a:noFill/>
</a:ln>
</a:insideH>
<a:insideV>
<a:ln>
<a:noFill/>
</a:ln>
</a:insideV>
</a:tcBdr>
<a:fill>
<a:noFill/>
</a:fill>
</a:tcStyle>
</a:wholeTbl>
<a:band1H>
<a:tcStyle>
<a:tcBdr>

```
<a:top>
<a:lnRef idx="1">
<a:schemeClr val="tx1"/>
</a:lnRef>
</a:top>
<a:bottom>
<a:lnRef idx="1">
<a:schemeClr val="tx1"/>
</a:lnRef>
</a:bottom>
</a:tcBdr>
</a:tcStyle>
</a:band1H>
<a:band1V>
<a:tcStyle>
<a:tcBdr>
<a:left>
<a:lnRef idx="1">
<a:schemeClr val="tx1"/>
</a:lnRef>
</a:left>
<a:right>
<a:lnRef idx="1">
<a:schemeClr val="tx1"/>
</a:lnRef>
</a:right>
</a:tcBdr>
</a:tcStyle>
</a:band1V>
<a:band2V>
```


<a:tcStyle>
<a:tcBdr>
<a:left>
<a:lnRef idx="1">
<a:schemeClr val="tx1"/>
</a:lnRef>
</a:left>
<a:right>
<a:lnRef idx="1">
<a:schemeClr val="tx1"/>
</a:lnRef>
</a:right>
</a:tcBdr>
</a:tcStyle>
</a:band2V>
<a:lastCol>
<a:tcTxStyle b="on"/>
<a:tcStyle>
<a:tcBdr/>
</a:tcStyle>
</a:lastCol>
<a:firstCol>
<a:tcTxStyle b="on"/>
<a:tcStyle>
<a:tcBdr/>
</a:tcStyle>
</a:firstCol>
<a:lastRow>
<a:tcTxStyle b="on"/>
<a:tcStyle>

<a:tcBdr>
<a:top>
<a:ln w="50800" cmpd="dbl">
<a:solidFill>
<a:schemeClr val="tx1"/>
</a:solidFill>
</a:ln>
</a:top>
</a:tcBdr>
</a:tcStyle>
</a:lastRow>
<a:firstRow>
<a:tcTxStyle b="on">
<a:fontRef idx="minor">
<a:scrgbClr r="0" g="0" b="0"/>
</a:fontRef>
<a:schemeClr val="bg1"/>
</a:tcTxStyle>
<a:tcStyle>
<a:tcBdr/>
<a:fillRef idx="1">
<a:schemeClr val="tx1"/>
</a:fillRef>
</a:tcStyle>
</a:firstRow>
</a:tblStyle>
<a:tblStyle styleId="{616DA210-FB5B-4158-B5E0-FEB733F419BA}" styleName="">
<a:wholeTbl>
<a:tcTxStyle>
<a:fontRef idx="minor">

<a:scrgbClr r="0" g="0" b="0"/>
</a:fontRef>
<a:schemeClr val="tx1"/>
</a:tcTxStyle>
<a:tcStyle>
<a:tcBdr>
<a:left>
<a:ln w="12700" cmpd="sng">
<a:solidFill>
<a:schemeClr val="tx1"/>
</a:solidFill>
</a:ln>
</a:left>
<a:right>
<a:ln w="12700" cmpd="sng">
<a:solidFill>
<a:schemeClr val="tx1"/>
</a:solidFill>
</a:ln>
</a:right>
<a:top>
<a:ln w="12700" cmpd="sng">
<a:solidFill>
<a:schemeClr val="tx1"/>
</a:solidFill>
</a:ln>
</a:top>
<a:bottom>
<a:ln w="12700" cmpd="sng">
<a:solidFill>

<a:schemeClr val="tx1"/>
</a:solidFill>
</a:ln>
</a:bottom>
<a:insideH>
<a:ln w="12700" cmpd="sng">
<a:solidFill>
<a:schemeClr val="tx1"/>
</a:solidFill>
</a:ln>
</a:insideH>
<a:insideV>
<a:ln w="12700" cmpd="sng">
<a:solidFill>
<a:schemeClr val="tx1"/>
</a:solidFill>
</a:ln>
</a:insideV>
</a:tcBdr>
<a:fill>
<a:noFill/>
</a:fill>
</a:tcStyle>
</a:wholeTbl>
<a:band1H>
<a:tcStyle>
<a:tcBdr/>
<a:fill>
<a:solidFill>
<a:schemeClr val="tx1">

<a:alpha val="20000"/>
</a:schemeClr>
</a:solidFill>
</a:fill>
</a:tcStyle>
</a:band1H>
<a:band1V>
<a:tcStyle>
<a:tcBdr/>
<a:fill>
<a:solidFill>
<a:schemeClr val="tx1">
<a:alpha val="20000"/>
</a:schemeClr>
</a:solidFill>
</a:fill>
</a:tcStyle>
</a:band1V>
<a:lastCol>
<a:tcTxStyle b="on"/>
<a:tcStyle>
<a:tcBdr/>
</a:tcStyle>
</a:lastCol>
<a:firstCol>
<a:tcTxStyle b="on"/>
<a:tcStyle>
<a:tcBdr/>
</a:tcStyle>
</a:firstCol>

```
<a:lastRow>
<a:tcTxStyle b="on"/>
<a:tcStyle>
<a:tcBdr>
<a:top>
<a:ln w="50800" cmpd="dbl">
<a:solidFill>
<a:schemeClr val="tx1"/>
</a:solidFill>
</a:ln>
</a:top>
</a:tcBdr>
<a:fill>
<a:noFill/>
</a:fill>
</a:tcStyle>
</a:lastRow>
<a:firstRow>
<a:tcTxStyle b="on"/>
<a:tcStyle>
<a:tcBdr>
<a:bottom>
<a:ln w="25400" cmpd="sng">
<a:solidFill>
<a:schemeClr val="tx1"/>
</a:solidFill>
</a:ln>
</a:bottom>
</a:tcBdr>
<a:fill>
```

<a:noFill/>
</a:fill>
</a:tcStyle>
</a:firstRow>
</a:tblStyle>
<a:tblStyle styleId="{793D81CF-94F2-401A-BA57-92F5A7B2D0C5}" styleName="">
<a:wholeTbl>
<a:tcTxStyle>
<a:fontRef idx="minor">
<a:scrgbClr r="0" g="0" b="0"/>
</a:fontRef>
<a:schemeClr val="dk1"/>
</a:tcTxStyle>
<a:tcStyle>
<a:tcBdr>
<a:left>
<a:ln w="12700" cmpd="sng">
<a:solidFill>
<a:schemeClr val="dk1"/>
</a:solidFill>
</a:ln>
</a:left>
<a:right>
<a:ln w="12700" cmpd="sng">
<a:solidFill>
<a:schemeClr val="dk1"/>
</a:solidFill>
</a:ln>
</a:right>
<a:top>

```
<a:ln w="12700" cmpd="sng">
<a:solidFill>
<a:schemeClr val="dk1"/>
</a:solidFill>
</a:ln>
</a:top>
<a:bottom>
<a:ln w="12700" cmpd="sng">
<a:solidFill>
<a:schemeClr val="dk1"/>
</a:solidFill>
</a:ln>
</a:bottom>
<a:insideH>
<a:ln w="12700" cmpd="sng">
<a:solidFill>
<a:schemeClr val="dk1"/>
</a:solidFill>
</a:ln>
</a:insideH>
<a:insideV>
<a:ln>
<a:noFill/>
</a:ln>
</a:insideV>
</a:tcBdr>
<a:fill>
<a:solidFill>
<a:schemeClr val="lt1"/>
</a:solidFill>
```


</a:fill>
</a:tcStyle>
</a:wholeTbl>
<a:band1H>
<a:tcStyle>
<a:tcBdr/>
<a:fill>
<a:solidFill>
<a:schemeClr val="dk1">
<a:tint val="20000"/>
</a:schemeClr>
</a:solidFill>
</a:fill>
</a:tcStyle>
</a:band1H>
<a:band1V>
<a:tcStyle>
<a:tcBdr/>
<a:fill>
<a:solidFill>
<a:schemeClr val="dk1">
<a:tint val="20000"/>
</a:schemeClr>
</a:solidFill>
</a:fill>
</a:tcStyle>
</a:band1V>
<a:lastCol>
<a:tcTxStyle b="on"/>
<a:tcStyle>

<a:tcBdr/>
</a:tcStyle>
</a:lastCol>
<a:firstCol>
<a:tcTxStyle b="on"/>
<a:tcStyle>
<a:tcBdr/>
</a:tcStyle>
</a:firstCol>
<a:lastRow>
<a:tcTxStyle b="on"/>
<a:tcStyle>
<a:tcBdr>
<a:top>
<a:ln w="50800" cmpd="dbl">
<a:solidFill>
<a:schemeClr val="dk1"/>
</a:solidFill>
</a:ln>
</a:top>
</a:tcBdr>
<a:fill>
<a:solidFill>
<a:schemeClr val="lt1"/>
</a:solidFill>
</a:fill>
</a:tcStyle>
</a:lastRow>
<a:firstRow>
<a:tcTxStyle b="on">

<a:fontRef idx="minor">
<a:scrgbClr r="0" g="0" b="0"/>
</a:fontRef>
<a:schemeClr val="lt1"/>
</a:tcTxStyle>
<a:tcStyle>
<a:tcBdr/>
<a:fill>
<a:solidFill>
<a:schemeClr val="dk1"/>
</a:solidFill>
</a:fill>
</a:tcStyle>
</a:firstRow>
</a:tblStyle>
<a:tblStyle styleId="{073A0DAA-6AF3-43AB-8588-CEC1D06C72B9}" styleName="">
<a:wholeTbl>
<a:tcTxStyle>
<a:fontRef idx="minor">
<a:prstClr val="black"/>
</a:fontRef>
<a:schemeClr val="dk1"/>
</a:tcTxStyle>
<a:tcStyle>
<a:tcBdr>
<a:left>
<a:ln w="12700" cmpd="sng">
<a:solidFill>
<a:schemeClr val="lt1"/>
</a:solidFill>

</a:ln>
</a:left>
<a:right>
<a:ln w="12700" cmpd="sng">
<a:solidFill>
<a:schemeClr val="lt1"/>
</a:solidFill>
</a:ln>
</a:right>
<a:top>
<a:ln w="12700" cmpd="sng">
<a:solidFill>
<a:schemeClr val="lt1"/>
</a:solidFill>
</a:ln>
</a:top>
<a:bottom>
<a:ln w="12700" cmpd="sng">
<a:solidFill>
<a:schemeClr val="lt1"/>
</a:solidFill>
</a:ln>
</a:bottom>
<a:insideH>
<a:ln w="12700" cmpd="sng">
<a:solidFill>
<a:schemeClr val="lt1"/>
</a:solidFill>
</a:ln>
</a:insideH>

<a:insideV>
<a:ln w="12700" cmpd="sng">
<a:solidFill>
<a:schemeClr val="lt1"/>
</a:solidFill>
</a:ln>
</a:insideV>
</a:tcBdr>
<a:fill>
<a:solidFill>
<a:schemeClr val="dk1">
<a:tint val="20000"/>
</a:schemeClr>
</a:solidFill>
</a:fill>
</a:tcStyle>
</a:wholeTbl>
<a:band1H>
<a:tcStyle>
<a:tcBdr/>
<a:fill>
<a:solidFill>
<a:schemeClr val="dk1">
<a:tint val="40000"/>
</a:schemeClr>
</a:solidFill>
</a:fill>
</a:tcStyle>
</a:band1H>
<a:band2H>

```
<a:tcStyle>
<a:tcBdr/>
</a:tcStyle>
</a:band2H>
<a:band1V>
<a:tcStyle>
<a:tcBdr/>
<a:fill>
<a:solidFill>
<a:schemeClr val="dk1">
<a:tint val="40000"/>
</a:schemeClr>
</a:solidFill>
</a:fill>
</a:tcStyle>
</a:band1V>
<a:band2V>
<a:tcStyle>
<a:tcBdr/>
</a:tcStyle>
</a:band2V>
<a:lastCol>
<a:tcTxStyle b="on">
<a:fontRef idx="minor">
<a:prstClr val="black"/>
</a:fontRef>
<a:schemeClr val="lt1"/>
</a:tcTxStyle>
<a:tcStyle>
<a:tcBdr/>
```

```
<a:fill>
<a:solidFill>
<a:schemeClr val="dk1"/>
</a:solidFill>
</a:fill>
</a:tcStyle>
</a:lastCol>
<a:firstCol>
<a:tcTxStyle b="on">
<a:fontRef idx="minor">
<a:prstClr val="black"/>
</a:fontRef>
<a:schemeClr val="lt1"/>
</a:tcTxStyle>
<a:tcStyle>
<a:tcBdr/>
<a:fill>
<a:solidFill>
<a:schemeClr val="dk1"/>
</a:solidFill>
</a:fill>
</a:tcStyle>
</a:firstCol>
<a:lastRow>
<a:tcTxStyle b="on">
<a:fontRef idx="minor">
<a:prstClr val="black"/>
</a:fontRef>
<a:schemeClr val="lt1"/>
</a:tcTxStyle>
```

```
<a:tcStyle>
<a:tcBdr>
<a:top>
<a:ln w="38100" cmpd="sng">
<a:solidFill>
<a:schemeClr val="lt1"/>
</a:solidFill>
</a:ln>
</a:top>
</a:tcBdr>
<a:fill>
<a:solidFill>
<a:schemeClr val="dk1"/>
</a:solidFill>
</a:fill>
</a:tcStyle>
</a:lastRow>
<a:firstRow>
<a:tcTxStyle b="on">
<a:fontRef idx="minor">
<a:prstClr val="black"/>
</a:fontRef>
<a:schemeClr val="lt1"/>
</a:tcTxStyle>
<a:tcStyle>
<a:tcBdr>
<a:bottom>
<a:ln w="38100" cmpd="sng">
<a:solidFill>
<a:schemeClr val="lt1"/>
```


</a:solidFill>
</a:ln>
</a:bottom>
</a:tcBdr>
<a:fill>
<a:solidFill>
<a:schemeClr val="dk1"/>
</a:solidFill>
</a:fill>
</a:tcStyle>
</a:firstRow>
</a:tblStyle>
<a:tblStyle styleId="{8EC20E35-A176-4012-BC5E-935CFFF8708E}" styleName="">
<a:wholeTbl>
<a:tcTxStyle>
<a:fontRef idx="minor">
</a:fontRef>
<a:schemeClr val="dk1"/>
</a:tcTxStyle>
<a:tcStyle>
<a:tcBdr>
<a:left>
<a:ln>
<a:noFill/>
</a:ln>
</a:left>
<a:right>
<a:ln>
<a:noFill/>
</a:ln>

</a:right>
<a:top>
<a:ln w="25400" cmpd="sng">
<a:solidFill>
<a:schemeClr val="dk1"/>
</a:solidFill>
</a:ln>
</a:top>
<a:bottom>
<a:ln w="25400" cmpd="sng">
<a:solidFill>
<a:schemeClr val="dk1"/>
</a:solidFill>
</a:ln>
</a:bottom>
<a:insideH>
<a:ln>
<a:noFill/>
</a:ln>
</a:insideH>
<a:insideV>
<a:ln>
<a:noFill/>
</a:ln>
</a:insideV>
</a:tcBdr>
<a:fill>
<a:solidFill>
<a:schemeClr val="lt1"/>
</a:solidFill>

</a:fill>
</a:tcStyle>
</a:wholeTbl>
<a:band1H>
<a:tcStyle>
<a:tcBdr/>
<a:fill>
<a:solidFill>
<a:schemeClr val="dk1">
<a:tint val="20000"/>
</a:schemeClr>
</a:solidFill>
</a:fill>
</a:tcStyle>
</a:band1H>
<a:band1V>
<a:tcStyle>
<a:tcBdr/>
<a:fill>
<a:solidFill>
<a:schemeClr val="dk1">
<a:tint val="20000"/>
</a:schemeClr>
</a:solidFill>
</a:fill>
</a:tcStyle>
</a:band1V>
<a:lastCol>
<a:tcTxStyle b="on">
<a:fontRef idx="minor">

<a:scrgbClr r="0" g="0" b="0"/>
</a:fontRef>
<a:schemeClr val="lt1"/>
</a:tcTxStyle>
<a:tcStyle>
<a:tcBdr/>
<a:fill>
<a:solidFill>
<a:schemeClr val="dk1"/>
</a:solidFill>
</a:fill>
</a:tcStyle>
</a:lastCol>
<a:firstCol>
<a:tcTxStyle b="on">
<a:fontRef idx="minor">
<a:scrgbClr r="0" g="0" b="0"/>
</a:fontRef>
<a:schemeClr val="lt1"/>
</a:tcTxStyle>
<a:tcStyle>
<a:tcBdr/>
<a:fill>
<a:solidFill>
<a:schemeClr val="dk1"/>
</a:solidFill>
</a:fill>
</a:tcStyle>
</a:firstCol>
<a:lastRow>

```
<a:tcTxStyle b="on"/>
<a:tcStyle>
<a:tcBdr>
<a:top>
<a:ln w="50800" cmpd="dbl">
<a:solidFill>
<a:schemeClr val="dk1"/>
</a:solidFill>
</a:ln>
</a:top>
</a:tcBdr>
<a:fill>
<a:solidFill>
<a:schemeClr val="lt1"/>
</a:solidFill>
</a:fill>
</a:tcStyle>
</a:lastRow>
<a:seCell>
<a:tcTxStyle b="on">
<a:fontRef idx="minor">
<a:scrgbClr r="0" g="0" b="0"/>
</a:fontRef>
<a:schemeClr val="dk1"/>
</a:tcTxStyle>
<a:tcStyle>
<a:tcBdr/>
</a:tcStyle>
</a:seCell>
<a:swCell>
```

```
<a:tcTxStyle b="on">
<a:fontRef idx="minor">
<a:scrgbClr r="0" g="0" b="0"/>
</a:fontRef>
<a:schemeClr val="dk1"/>
</a:tcTxStyle>
<a:tcStyle>
<a:tcBdr/>
</a:tcStyle>
</a:swCell>
<a:firstRow>
<a:tcTxStyle b="on">
<a:fontRef idx="minor">
<a:scrgbClr r="0" g="0" b="0"/>
</a:fontRef>
<a:schemeClr val="lt1"/>
</a:tcTxStyle>
<a:tcStyle>
<a:tcBdr>
<a:bottom>
<a:ln w="25400" cmpd="sng">
<a:solidFill>
<a:schemeClr val="dk1"/>
</a:solidFill>
</a:ln>
</a:bottom>
</a:tcBdr>
<a:fill>
<a:solidFill>
<a:schemeClr val="dk1"/>
```

</a:solidFill>
</a:fill>
</a:tcStyle>
</a:firstRow>
</a:tblStyle>
<a:tblStyle styleId="{6E25E649-3F16-4E02-A733-19D2CDBF48F0}" styleName="">
<a:wholeTbl>
<a:tcTxStyle>
<a:fontRef idx="minor">
<a:scrgbClr r="0" g="0" b="0"/>
</a:fontRef>
<a:schemeClr val="dk1"/>
</a:tcTxStyle>
<a:tcStyle>
<a:tcBdr>
<a:left>
<a:ln>
<a:noFill/>
</a:ln>
</a:left>
<a:right>
<a:ln>
<a:noFill/>
</a:ln>
</a:right>
<a:top>
<a:ln w="25400" cmpd="sng">
<a:solidFill>
<a:schemeClr val="dk1"/>
</a:solidFill>

</a:ln>
</a:top>
<a:bottom>
<a:ln w="25400" cmpd="sng">
<a:solidFill>
<a:schemeClr val="dk1"/>
</a:solidFill>
</a:ln>
</a:bottom>
<a:insideH>
<a:ln>
<a:noFill/>
</a:ln>
</a:insideH>
<a:insideV>
<a:ln>
<a:noFill/>
</a:ln>
</a:insideV>
</a:tcBdr>
<a:fill>
<a:solidFill>
<a:schemeClr val="lt1"/>
</a:solidFill>
</a:fill>
</a:tcStyle>
</a:wholeTbl>
<a:band1H>
<a:tcStyle>
<a:tcBdr/>


```
<a:fill>
<a:solidFill>
<a:schemeClr val="dk1">
<a:tint val="20000"/>
</a:schemeClr>
</a:solidFill>
</a:fill>
</a:tcStyle>
</a:band1H>
<a:band1V>
<a:tcStyle>
<a:tcBdr/>
<a:fill>
<a:solidFill>
<a:schemeClr val="dk1">
<a:tint val="20000"/>
</a:schemeClr>
</a:solidFill>
</a:fill>
</a:tcStyle>
</a:band1V>
<a:lastCol>
<a:tcTxStyle b="on">
<a:fontRef idx="minor">
<a:scrgbClr r="0" g="0" b="0"/>
</a:fontRef>
<a:schemeClr val="lt1"/>
</a:tcTxStyle>
<a:tcStyle>
<a:tcBdr/>
```

```
<a:fill>
<a:solidFill>
<a:schemeClr val="accent1"/>
</a:solidFill>
</a:fill>
</a:tcStyle>
</a:lastCol>
<a:firstCol>
<a:tcTxStyle b="on">
<a:fontRef idx="minor">
<a:scrgbClr r="0" g="0" b="0"/>
</a:fontRef>
<a:schemeClr val="lt1"/>
</a:tcTxStyle>
<a:tcStyle>
<a:tcBdr/>
<a:fill>
<a:solidFill>
<a:schemeClr val="accent1"/>
</a:solidFill>
</a:fill>
</a:tcStyle>
</a:firstCol>
<a:lastRow>
<a:tcTxStyle b="on"/>
<a:tcStyle>
<a:tcBdr>
<a:top>
<a:ln w="50800" cmpd="dbl">
<a:solidFill>
```

```
<a:schemeClr val="dk1"/>
</a:solidFill>
</a:ln>
</a:top>
</a:tcBdr>
<a:fill>
<a:solidFill>
<a:schemeClr val="lt1"/>
</a:solidFill>
</a:fill>
</a:tcStyle>
</a:lastRow>
<a:seCell>
<a:tcTxStyle b="on">
<a:fontRef idx="minor">
<a:scrgbClr r="0" g="0" b="0"/>
</a:fontRef>
<a:schemeClr val="dk1"/>
</a:tcTxStyle>
<a:tcStyle>
<a:tcBdr/>
</a:tcStyle>
</a:seCell>
<a:swCell>
<a:tcTxStyle b="on">
<a:fontRef idx="minor">
<a:scrgbClr r="0" g="0" b="0"/>
</a:fontRef>
<a:schemeClr val="dk1"/>
</a:tcTxStyle>
```

<a:tcStyle>
<a:tcBdr/>
</a:tcStyle>
</a:swCell>
<a:firstRow>
<a:tcTxStyle b="on">
<a:fontRef idx="minor">
<a:scrgbClr r="0" g="0" b="0"/>
</a:fontRef>
<a:schemeClr val="lt1"/>
</a:tcTxStyle>
<a:tcStyle>
<a:tcBdr>
<a:bottom>
<a:ln w="25400" cmpd="sng">
<a:solidFill>
<a:schemeClr val="dk1"/>
</a:solidFill>
</a:ln>
</a:bottom>
</a:tcBdr>
<a:fill>
<a:solidFill>
<a:schemeClr val="accent1"/>
</a:solidFill>
</a:fill>
</a:tcStyle>
</a:firstRow>
</a:tblStyle>
<a:tblStyle styleId="{D7AC3CCA-C797-4891-BE02-D94E43425B78}" styleName="">

```
<a:wholeTbl>
<a:tcTxStyle>
<a:fontRef idx="minor">
<a:scrgbClr r="0" g="0" b="0"/>
</a:fontRef>
<a:schemeClr val="dk1"/>
</a:tcTxStyle>
<a:tcStyle>
<a:tcBdr>
<a:left>
<a:ln w="12700" cmpd="sng">
<a:solidFill>
<a:schemeClr val="dk1"/>
</a:solidFill>
</a:ln>
</a:left>
<a:right>
<a:ln w="12700" cmpd="sng">
<a:solidFill>
<a:schemeClr val="dk1"/>
</a:solidFill>
</a:ln>
</a:right>
<a:top>
<a:ln w="12700" cmpd="sng">
<a:solidFill>
<a:schemeClr val="dk1"/>
</a:solidFill>
</a:ln>
</a:top>
```

```
<a:bottom>
<a:ln w="12700" cmpd="sng">
<a:solidFill>
<a:schemeClr val="dk1"/>
</a:solidFill>
</a:ln>
</a:bottom>
<a:insideH>
<a:ln w="12700" cmpd="sng">
<a:solidFill>
<a:schemeClr val="dk1"/>
</a:solidFill>
</a:ln>
</a:insideH>
<a:insideV>
<a:ln w="12700" cmpd="sng">
<a:solidFill>
<a:schemeClr val="dk1"/>
</a:solidFill>
</a:ln>
</a:insideV>
</a:tcBdr>
<a:fill>
<a:solidFill>
<a:schemeClr val="dk1">
<a:tint val="20000"/>
</a:schemeClr>
</a:solidFill>
</a:fill>
</a:tcStyle>
```

</a:wholeTbl>
<a:band1H>
<a:tcStyle>
<a:tcBdr/>
<a:fill>
<a:solidFill>
<a:schemeClr val="dk1">
<a:tint val="40000"/>
</a:schemeClr>
</a:solidFill>
</a:fill>
</a:tcStyle>
</a:band1H>
<a:band1V>
<a:tcStyle>
<a:tcBdr/>
<a:fill>
<a:solidFill>
<a:schemeClr val="dk1">
<a:tint val="40000"/>
</a:schemeClr>
</a:solidFill>
</a:fill>
</a:tcStyle>
</a:band1V>
<a:lastCol>
<a:tcTxStyle b="on"/>
<a:tcStyle>
<a:tcBdr/>
</a:tcStyle>

</a:lastCol>
<a:firstCol>
<a:tcTxStyle b="on"/>
<a:tcStyle>
<a:tcBdr/>
</a:tcStyle>
</a:firstCol>
<a:lastRow>
<a:tcTxStyle b="on"/>
<a:tcStyle>
<a:tcBdr>
<a:top>
<a:ln w="25400" compd="sng">
<a:solidFill>
<a:schemeClr val="dk1"/>
</a:solidFill>
</a:ln>
</a:top>
</a:tcBdr>
<a:fill>
<a:solidFill>
<a:schemeClr val="dk1">
<a:tint val="20000"/>
</a:schemeClr>
</a:solidFill>
</a:fill>
</a:tcStyle>
</a:lastRow>
<a:firstRow>
<a:tcTxStyle b="on"/>

<a:tcStyle>
<a:tcBdr/>
<a:fill>
<a:solidFill>
<a:schemeClr val="dk1">
<a:tint val="20000"/>
</a:schemeClr>
</a:solidFill>
</a:fill>
</a:tcStyle>
</a:firstRow>
</a:tblStyle>
<a:tblStyle styleId="{E8034E78-7F5D-4C2E-B375-FC64B27BC917}" styleName="">
<a:wholeTbl>
<a:tcTxStyle>
<a:fontRef idx="minor">
<a:scrgbClr r="0" g="0" b="0"/>
</a:fontRef>
<a:schemeClr val="lt1"/>
</a:tcTxStyle>
<a:tcStyle>
<a:tcBdr>
<a:left>
<a:ln>
<a:noFill/>
</a:ln>
</a:left>
<a:right>
<a:ln>
<a:noFill/>

</a:ln>
</a:right>
<a:top>
<a:ln>
<a:noFill/>
</a:ln>
</a:top>
<a:bottom>
<a:ln>
<a:noFill/>
</a:ln>
</a:bottom>
<a:insideH>
<a:ln>
<a:noFill/>
</a:ln>
</a:insideH>
<a:insideV>
<a:ln>
<a:noFill/>
</a:ln>
</a:insideV>
</a:tcBdr>
<a:fill>
<a:solidFill>
<a:schemeClr val="dk1">
<a:tint val="20000"/>
</a:schemeClr>
</a:solidFill>
</a:fill>

</a:tcStyle>
</a:wholeTbl>
<a:band1H>
<a:tcStyle>
<a:tcBdr/>
<a:fill>
<a:solidFill>
<a:schemeClr val="dk1">
<a:tint val="40000"/>
</a:schemeClr>
</a:solidFill>
</a:fill>
</a:tcStyle>
</a:band1H>
<a:band1V>
<a:tcStyle>
<a:tcBdr/>
<a:fill>
<a:solidFill>
<a:schemeClr val="dk1">
<a:tint val="40000"/>
</a:schemeClr>
</a:solidFill>
</a:fill>
</a:tcStyle>
</a:band1V>
<a:lastCol>
<a:tcTxStyle b="on"/>
<a:tcStyle>
<a:tcBdr>

<a:left>
<a:ln w="25400" cmpd="sng">
<a:solidFill>
<a:schemeClr val="lt1"/>
</a:solidFill>
</a:ln>
</a:left>
</a:tcBdr>
<a:fill>
<a:solidFill>
<a:schemeClr val="dk1">
<a:tint val="60000"/>
</a:schemeClr>
</a:solidFill>
</a:fill>
</a:tcStyle>
</a:lastCol>
<a:firstCol>
<a:tcTxStyle b="on"/>
<a:tcStyle>
<a:tcBdr>
<a:right>
<a:ln w="25400" cmpd="sng">
<a:solidFill>
<a:schemeClr val="lt1"/>
</a:solidFill>
</a:ln>
</a:right>
</a:tcBdr>
<a:fill>

```
<a:solidFill>
<a:schemeClr val="dk1">
<a:tint val="60000"/>
</a:schemeClr>
</a:solidFill>
</a:fill>
</a:tcStyle>
</a:firstCol>
<a:lastRow>
<a:tcTxStyle b="on"/>
<a:tcStyle>
<a:tcBdr>
<a:top>
<a:ln w="25400" cmpd="sng">
<a:solidFill>
<a:schemeClr val="lt1"/>
</a:solidFill>
</a:ln>
</a:top>
</a:tcBdr>
<a:fill>
<a:solidFill>
<a:schemeClr val="dk1">
<a:tint val="60000"/>
</a:schemeClr>
</a:solidFill>
</a:fill>
</a:tcStyle>
</a:lastRow>
<a:seCell>
```

<a:tcStyle>
<a:tcBdr>
<a:left>
<a:ln>
<a:noFill/>
</a:ln>
</a:left>
</a:tcBdr>
</a:tcStyle>
</a:seCell>
<a:swCell>
<a:tcStyle>
<a:tcBdr>
<a:right>
<a:ln>
<a:noFill/>
</a:ln>
</a:right>
</a:tcBdr>
</a:tcStyle>
</a:swCell>
<a:firstRow>
<a:tcTxStyle b="on"/>
<a:tcStyle>
<a:tcBdr>
<a:bottom>
<a:ln w="25400" cmpd="sng">
<a:solidFill>
<a:schemeClr val="lt1"/>
</a:solidFill>

</a:ln>
</a:bottom>
</a:tcBdr>
<a:fill>
<a:solidFill>
<a:schemeClr val="dk1"/>
</a:solidFill>
</a:fill>
</a:tcStyle>
</a:firstRow>
<a:neCell>
<a:tcStyle>
<a:tcBdr>
<a:left>
<a:ln>
<a:noFill/>
</a:ln>
</a:left>
</a:tcBdr>
</a:tcStyle>
</a:neCell>
<a:nwCell>
<a:tcStyle>
<a:tcBdr>
<a:right>
<a:ln>
<a:noFill/>
</a:ln>
</a:right>
</a:tcBdr>

</a:tcStyle>
</a:nwCell>
</a:tblStyle>
<a:tblStyle styleId="{125E5076-3810-47DD-B79F-674D7AD40C01}" styleName="">
<a:wholeTbl>
<a:tcTxStyle>
<a:fontRef idx="minor">
<a:scrgbClr r="0" g="0" b="0"/>
</a:fontRef>
<a:schemeClr val="lt1"/>
</a:tcTxStyle>
<a:tcStyle>
<a:tcBdr>
<a:left>
<a:ln>
<a:noFill/>
</a:ln>
</a:left>
<a:right>
<a:ln>
<a:noFill/>
</a:ln>
</a:right>
<a:top>
<a:ln>
<a:noFill/>
</a:ln>
</a:top>
<a:bottom>
<a:ln>

<a:noFill/>
</a:ln>
</a:bottom>
<a:insideH>
<a:ln>
<a:noFill/>
</a:ln>
</a:insideH>
<a:insideV>
<a:ln>
<a:noFill/>
</a:ln>
</a:insideV>
</a:tcBdr>
<a:fill>
<a:solidFill>
<a:schemeClr val="accent1"/>
</a:solidFill>
</a:fill>
</a:tcStyle>
</a:wholeTbl>
<a:band1H>
<a:tcStyle>
<a:tcBdr/>
<a:fill>
<a:solidFill>
<a:schemeClr val="accent1">
<a:shade val="60000"/>
</a:schemeClr>
</a:solidFill>

</a:fill>
</a:tcStyle>
</a:band1H>
<a:band1V>
<a:tcStyle>
<a:tcBdr/>
<a:fill>
<a:solidFill>
<a:schemeClr val="accent1">
<a:shade val="60000"/>
</a:schemeClr>
</a:solidFill>
</a:fill>
</a:tcStyle>
</a:band1V>
<a:lastCol>
<a:tcTxStyle b="on"/>
<a:tcStyle>
<a:tcBdr>
<a:left>
<a:ln w="25400" cmpd="sng">
<a:solidFill>
<a:schemeClr val="lt1"/>
</a:solidFill>
</a:ln>
</a:left>
</a:tcBdr>
<a:fill>
<a:solidFill>
<a:schemeClr val="accent1">

<a:shade val="60000"/>
</a:schemeClr>
</a:solidFill>
</a:fill>
</a:tcStyle>
</a:lastCol>
<a:firstCol>
<a:tcTxStyle b="on"/>
<a:tcStyle>
<a:tcBdr>
<a:right>
<a:ln w="25400" cmpd="sng">
<a:solidFill>
<a:schemeClr val="lt1"/>
</a:solidFill>
</a:ln>
</a:right>
</a:tcBdr>
<a:fill>
<a:solidFill>
<a:schemeClr val="accent1">
<a:shade val="60000"/>
</a:schemeClr>
</a:solidFill>
</a:fill>
</a:tcStyle>
</a:firstCol>
<a:lastRow>
<a:tcTxStyle b="on"/>
<a:tcStyle>

<a:tcBdr>
<a:top>
<a:ln w="25400" cmpd="sng">
<a:solidFill>
<a:schemeClr val="lt1"/>
</a:solidFill>
</a:ln>
</a:top>
</a:tcBdr>
<a:fill>
<a:solidFill>
<a:schemeClr val="accent1">
<a:shade val="40000"/>
</a:schemeClr>
</a:solidFill>
</a:fill>
</a:tcStyle>
</a:lastRow>
<a:seCell>
<a:tcStyle>
<a:tcBdr>
<a:left>
<a:ln>
<a:noFill/>
</a:ln>
</a:left>
</a:tcBdr>
</a:tcStyle>
</a:seCell>
<a:swCell>

<a:tcStyle>
<a:tcBdr>
<a:right>
<a:ln>
<a:noFill/>
</a:ln>
</a:right>
</a:tcBdr>
</a:tcStyle>
</a:swCell>
<a:firstRow>
<a:tcTxStyle b="on"/>
<a:tcStyle>
<a:tcBdr>
<a:bottom>
<a:ln w="25400" cmpd="sng">
<a:solidFill>
<a:schemeClr val="lt1"/>
</a:solidFill>
</a:ln>
</a:bottom>
</a:tcBdr>
<a:fill>
<a:solidFill>
<a:schemeClr val="dk1"/>
</a:solidFill>
</a:fill>
</a:tcStyle>
</a:firstRow>
<a:neCell>

<a:tcStyle>
<a:tcBdr>
<a:left>
<a:ln>
<a:noFill/>
</a:ln>
</a:left>
</a:tcBdr>
</a:tcStyle>
</a:neCell>
<a:nwCell>
<a:tcStyle>
<a:tcBdr>
<a:right>
<a:ln>
<a:noFill/>
</a:ln>
</a:right>
</a:tcBdr>
</a:tcStyle>
</a:nwCell>
</a:tblStyle>
<a:tblStyle styleId="{5202B0CA-FC54-4496-8BCA-5EF66A818D29}" styleName="">
<a:wholeTbl>
<a:tcTxStyle>
<a:fontRef idx="minor">
<a:scrgbClr r="0" g="0" b="0"/>
</a:fontRef>
<a:schemeClr val="dk1"/>
</a:tcTxStyle>

<a:tcStyle>
<a:tcBdr>
<a:left>
<a:ln>
<a:noFill/>
</a:ln>
</a:left>
<a:right>
<a:ln>
<a:noFill/>
</a:ln>
</a:right>
<a:top>
<a:ln>
<a:noFill/>
</a:ln>
</a:top>
<a:bottom>
<a:ln>
<a:noFill/>
</a:ln>
</a:bottom>
<a:insideH>
<a:ln>
<a:noFill/>
</a:ln>
</a:insideH>
<a:insideV>
<a:ln>
<a:noFill/>

</a:ln>
</a:insideV>
</a:tcBdr>
<a:fill>
<a:solidFill>
<a:schemeClr val="dk1">
<a:tint val="20000"/>
</a:schemeClr>
</a:solidFill>
</a:fill>
</a:tcStyle>
</a:wholeTbl>
<a:band1H>
<a:tcStyle>
<a:tcBdr/>
<a:fill>
<a:solidFill>
<a:schemeClr val="dk1">
<a:tint val="40000"/>
</a:schemeClr>
</a:solidFill>
</a:fill>
</a:tcStyle>
</a:band1H>
<a:band1V>
<a:tcStyle>
<a:tcBdr/>
<a:fill>
<a:solidFill>
<a:schemeClr val="dk1">


```
<a:tint val="40000"/>
</a:schemeClr>
</a:solidFill>
</a:fill>
</a:tcStyle>
</a:band1V>
<a:lastCol>
<a:tcTxStyle b="on"/>
<a:tcStyle>
<a:tcBdr/>
</a:tcStyle>
</a:lastCol>
<a:firstCol>
<a:tcTxStyle b="on"/>
<a:tcStyle>
<a:tcBdr/>
</a:tcStyle>
</a:firstCol>
<a:lastRow>
<a:tcTxStyle b="on"/>
<a:tcStyle>
<a:tcBdr>
<a:top>
<a:ln w="50800" cmpd="dbl">
<a:solidFill>
<a:schemeClr val="dk1"/>
</a:solidFill>
</a:ln>
</a:top>
</a:tcBdr>
```

```
<a:fill>
<a:solidFill>
<a:schemeClr val="dk1">
<a:tint val="20000"/>
</a:schemeClr>
</a:solidFill>
</a:fill>
</a:tcStyle>
</a:lastRow>
<a:firstRow>
<a:tcTxStyle b="on">
<a:fontRef idx="minor">
<a:scrgbClr r="0" g="0" b="0"/>
</a:fontRef>
<a:schemeClr val="lt1"/>
</a:tcTxStyle>
<a:tcStyle>
<a:tcBdr/>
<a:fill>
<a:solidFill>
<a:schemeClr val="dk1"/>
</a:solidFill>
</a:fill>
</a:tcStyle>
</a:firstRow>
</a:tblStyle>
```

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.1343 Part 4 Section 5.1.6.11, tbl (Table)

a. *The standard specifies that the number of rows is between 0 and unbounded.*

In Office, the number of rows is greater than 0 and less than or equal to 1000.

b. *The standard specifies that the number of columns, as defined in child element tblGrid, is between 0 and unbounded.*

In Office, the number of columns is greater than 0 and less than or equal to 1000.

c. *The standard does not indicate that the number of cells in each row is dependent on the number of columns.*

In Office, the number of cells in each table row is equal to the number of columns defined in child element tblGrid.

d. *The standard does not describe how the tbl element merges cells horizontally and vertically.*

A Table merge describes the merging relationships between conjoint cells in a table. The gridSpan and rowSpan attributes of the tc elements ("ECMA-376 Part 4 §5.1.6.14; tc (Table Cell)") are used to define a table merge. The gridSpan and rowSpan of the top-left cell of a table merge decide the width and height of the table merge. For example, if the following cell is the top-left cell of a table merge, its merge size is width = 3 columns, and height = 5 rows; or when written out, <a:tc gridSpan="3" rowSpan="5">.

1). All cells in the first row in this table merge must have the same rowSpan as the first one (5 in the preceding example). And their corresponding gridSpan, except the first one must be 1.

2). All cells in the first column in this table merge must have the same gridSpan as the first one (3 in the preceding example). And their corresponding rowSpan, except the first one must be equal to 1.

3). All other cells in this table merge must have their rowSpan and gridSpan being equal to 1.

4). Two merges shall not overlap.

e. *The standard allows the neighbouring interior borders of two neighbouring table merges to have different line properties.*

Office requires the neighbouring interior borders of two neighbouring table merges to have matching border line properties as defined by the InL, InR, InT and InB elements.

2.1.1344 Part 4 Section 5.1.6.12, tblGrid (Table Grid)

a. *The standard states that the tblGrid element defines the columns that are within the table.*

Office requires there be at least 1 and at most 1000 gridCol child elements to tblGrid.

2.1.1345 Part 4 Section 5.1.6.14, tc (Table Cell)

a. *The standard allows the value of the rowSpan attribute to be any 32-bit integer.*

In Office, the value of rowSpan shall be equal to or greater than 1. For a table with R rows, the value of rowSpan for cells in the first row shall be at most R; the value of rowSpan for cells in the second row can be at most R - 1; and so on.

b. *The standard states that the gridSpan attribute is allowed to be any 32-bit integer.*

In Office, the value of gridSpan shall be equal to or greater than 1. For a table with C columns, the value of gridSpan for cells in the first column can be at most C; the value of gridSpan for cells in the second column can be at most C - 1; and so on.

c. *The standard does not describe how the hMerge or vMerge attributes work.*

Information about Table Merge is contained within the tbl element (“[ECMA-376](#) Part 4 §5.1.6.11; tbl (Table)”).

All cells in the first column of a table merge shall have hMerge equal to 0 or false. All other cells of a table merge shall have hMerge equal to 1 or true.

All cells in the first row of a table merge shall have vMerge equal to 0 or false. All other cells of a table merge shall have vMerge equal to 1 or true.

2.1.1346 Part 4 Section 5.1.6.16, tr (Table Row)

a. *The standard states that the height attribute specifies the row height.*

In Office, the height of the row in the table is specified in EMUs. Additionally:

The height shall not be negative.

The height shall be either 0, or greater than the minimal row height.

The height shall be equal to or less than 0x3FFFFFFF.

The minimal row height of a row is defined as: the sum of the minimal heights which can hold the top margin and the bottom margin plus 2 extra points for each cell in the row.

b. *The standard states that the tr element specifies a row in a table.*

In Office, the number of table cells in a table row is greater than 1 and less than or equal to 1000. Additionally, the number of table cells in a table row is equal to the number of columns in the table.

2.1.1347 Part 4 Section 5.1.7.1, anchor (Anchor Point)

a. *The standard implies that the anchor element anchors the backdrop plane.*

This element specifies a point in 3D space that is the offset to the origin of the backdrop plane. By moving this anchor point, the image of shadows, glows, and reflections can be moved and can be rotated from its default position on a plane parallel to the x-y plane to any location and orientation in 3D space, providing it remains viewable in the viewing frustum of the scene camera.

2.1.1348 Part 4 Section 5.1.7.2, backdrop (Backdrop Plane)

a. *The standard allows the up and normal vectors to be collinear.*

Office requires that the up and normal vectors not be collinear.

2.1.1349 Part 4 Section 5.1.7.3, bevelB (Bottom Bevel)

a. *The standard does not specify a reference plane for height measurement.*

Office measures the height from the bottom face of the shape; if the shape has an extrusion height, the bevel height is measured from the base of the extrusion.

2.1.1350 Part 4 Section 5.1.7.4, bevelT (Top Bevel)

a. *The standard does not specify a reference plane for height measurement.*

Office measures the height from the top face of the shape; if the shape has an extrusion height, the bevel height is measured from the top of the extrusion.

2.1.1351 Part 4 Section 5.1.7.5, camera (Camera)

- a. *The standard allows the fov attribute to be used with all camera types.*

In Office, the fov attribute is ignored for non-perspective camera types.

2.1.1352 Part 4 Section 5.1.7.6, contourClr (Contour Color)

- a. *The standard allows contour width to be zero.*

In Office, if the contour width is zero, the color specified by this element is ignored.

- b. *The standard does not describe the interaction between contours and extrusions.*

In Office, the contour of a shape is a solid filled line which surrounds the outer edges of the shape, and the outline edges of the extrusion.

2.1.1353 Part 4 Section 5.1.7.7, extrusionClr (Extrusion Color)

- a. *The standard does not clarify default behavior for the extrusionClr element.*

In Office, if extrusion color is not specified, the front face color will be used as the extrusion color. If the extrusion height is zero, this element is ignored.

2.1.1354 Part 4 Section 5.1.7.8, flatTx (No text in 3D scene)

- a. *The standard states that the flatTx element specifies the Z coordinate to be used in positioning the flat text within the 3D scene.*

In Office, this element is used only when the text or shape is part of a 3D rotated group.

- b. *The standard states that the flatTx element is used to keep text out of a 3D scene.*

In Office, the text will not be subjected to the 3D camera rotation, but will instead remain in a plane orthogonal to the viewing direction.

2.1.1355 Part 4 Section 5.1.7.9, lightRig (Light Rig)

- a. *The standard states that the lightRig element defines the light rig associated with a table.*

In Office and the schema, the lightRig element is used to specify the lighting for any 3D scene.

- b. *The standard does not describe any interplay between attribute dir and child element rot.*

In Office, if the child element rot is specified, it will override the dir attribute of this element.

2.1.1356 Part 4 Section 5.1.7.10, norm (Normal)

- a. *The standard accepts any vector for the backdrop plane normal vector.*

Office requires that the normal vector be nonzero in length.

2.1.1357 Part 4 Section 5.1.7.12, sp3d (Apply 3D shape properties)

- a. *The standard does not describe default behavior when contourClr and extrusionClr child elements are unspecified.*

In Office, child element contourClr defaults to black and child element extrusionClr defaults to the front face color.

- b. *The standard does not describe default behavior when contour width is zero.*

In Office, if the contour width is zero, then no contour is presumed and contour color is ignored.

2.1.1358 Part 4 Section 5.1.7.13, up (Up Vector)

- a. *The standard accepts any vector for backdrop plane up vector.*

Office requires that the up vector be nonzero in length.

2.1.1359 Part 4 Section 5.1.9.1, chExt (Child Extents)

For additional notes that apply to this portion of the standard, please see the notes for [ext](#), §5.8.2.10(a).

- a. *The standard states that the child extents defined by the chExt element are used for calculations of grouping, scaling and rotating.*

In Office, this element additionally defines the group scaling factor which is the ratio of the extents to child extents when the size of the child extents is nonzero. If the size of the child extents is zero or omitted, there is no group scaling.

2.1.1360 Part 4 Section 5.1.9.2, chOff (Child Offset)

- a. *The standard states that the child offset defined by the chOff element specifies the location of the child extents rectangle, which is used for calculations of grouping, scaling and rotating.*

In Office, the child extents and offset are used to determine the center for scaling, rotation and flipping.

- b. *The standard states that the y attribute specifies a coordinate on the x-axis.*

In Office, the y attribute specifies a coordinate on the y-axis.

2.1.1361 Part 4 Section 5.1.9.3, ext (Extents)

For additional notes that apply to this portion of the standard, please see the notes for [ext](#), §5.8.2.10(a).

- a. *The standard states that the ext element specifies the size of the bounding box enclosing the referenced object.*

In Office, the extents also determine the size and center of the object for most geometry definitions. If the geometry data is independent of these extents, they are only used to determine the center for rotation and flipping.

2.1.1362 Part 4 Section 5.1.9.4, off (Offset)

For additional notes that apply to this portion of the standard, please see the notes for [chOff](#), §5.1.9.2(b).

- a. *The standard states that the offset element specifies the location of the bounding box of an object.*

In Office, the offset element specifies the location of a bounding box of an object as defined by the ext element.

2.1.1363 Part 4 Section 5.1.9.5, xfrm (2D Transform for Grouped Objects)

- a. *Normative prose in the standard states that the rot attribute specifies the clockwise rotation in 1/64000ths of a degree.*

In Office and the schema, the rot attribute specifies the clockwise rotation in 1/60000ths of a degree.

- b. *The standard does not describe role of the child bounding box as defined by elements chExt and chOff.*

In Office, the child bounding box is the center for scaling, rotating and flipping. Additionally, if the child extents are nonzero, then a group scaling is applied equal to the ratio of the extents to the child extents.

2.1.1364 Part 4 Section 5.1.9.6, xfrm (2D Transform for Individual Objects)

- a. *The standard states that the rot attribute specifies the rotation of a graphic frame.*

In Office, rot specifies the clockwise rotation of a shape.

- b. *The standard allows attributes flipH, flipV and rot to be applied to a graphicFrame.*

In Office, attributes FlipH, flipV and rot are ignored when applied to a graphicFrame.

2.1.1365 Part 4 Section 5.1.10, Shape Fills, Effects, and Line Properties

- a. *The standard supplies no default values for the optional attributes.*

In Office, default values for attributes in this section can come from any of three sources.

In general, when an optional attribute is not specified, it will incorporate the corresponding attribute value from one of the following sources if available. Not all of these levels will be used in every scenario.

Style link

Master shape (PresentationML only)

DrawingML hard coded default

This inheritance is done in multiple passes. Each level will fill in gaps not specified by previous levels.

The following elements are subjected to resolution. Unless otherwise noted, at any level, the absence of an element type in the target indicates the element is to come from the inheritance chain. For example, if the target property set has no fill element, it will inherit all the fill properties in the next level of inheritance that has fill properties. When the elements are merged, all unspecified attributes and children of the element, will come from the first inheritance source with one specified.

Where attributes and elements are merged, the values in parentheses are used as the base defaults:

Fill (noFill)1

1.1. noFill

1.2. solidFill (color = schemeColor (bg1))

1.3. gradFill (gsList(black, white), shade(lin), flip = none, rotWithShape = true)

1.3.1. gsList2

1.3.2. tileRect3

1.3.3. Shade (lin)1

1.3.3.1. lin (ang=0, scaled=false)

1.3.3.2. path (path=shape)

1.3.3.2.1. fillToRect (l,r,t,b=50%)

1.4. blipFill (dpi=0, rotWithShape=true)

1.4.1. blip (compression=none)

1.4.2. srcRect1

1.4.3. fillMode (tile)1

1.4.3.1. tile (algn=tl, flip=none, sx=100%, sy=100%, tx=0, ty=0)

1.4.3.2. stretch

1.4.3.2.1. fillRect3

1.5. pattFill (prst=pct5)

1.5.1. bgClr(white)

1.5.2. fgClr(black)

ln (w=.75pt, cap=flat, compd=sng, algn=ctr)

2.1. fill(same as 1)1

2.2. dash (prstDash(solid))

- 2.2.1. custDash2
- 2.3. join (round)
 - 2.3.1. miter(lim=800%)
- 2.4. headEnd (type=none, w=med, len=med)
- 2.5. tailEnd (type=none, w=med, len=med)

effect2

shape3D2

scene3D2

1Merging only occurs if elements are of the same type, or if element does not exist in the target property set.

2Merging only occurs as a whole. If the element does not exist, the secondary default is used in its entirety. Even a valid empty element will block the inheritance. For example, an empty effect list will not be merged with an inherited effect list.

3Simple type has schema defaults

2.1.1366 Part 4 Section 5.1.10.4, alphaInv (Alpha Inverse Effect)

- a. *The standard does not include information on the optional color element.*

In Office, other color channels are modified only if a color is specified. If a color is specified, all effect colors are replaced by the constant color value and the alpha values are inverted. If no color is specified, only the alpha values are modified and the other color channels are unchanged.

2.1.1367 Part 4 Section 5.1.10.5, alphaMod (Alpha Modulate Effect)

- a. *The standard states that alpha is multiplied by a fixed percent.*

In Office, alpha is multiplied by the alpha of another effect.

2.1.1368 Part 4 Section 5.1.10.14, blipFill (Picture Fill)

For additional notes that apply to this portion of the standard, please see the notes for [blipFill](#), §5.8.2.2(a).

- a. *The standard states that the attribute blipFill specifies the picture fill for pic object.*

In Office, the attribute blipFill specifies the image fill for an object.

2.1.1369 Part 4 Section 5.1.10.15, blur (Blur Effect)

- a. *The standard states that if attribute grow is true, blur may extend beyond object bounds.*

In Office, if blur is applied to blip in a blipFill, fill constraints will keep the blur from extending beyond object bounds.

- b. *The standard states that attribute rad will specify radius of blur.*

Office interprets the radius of blur as destination pixels, rather than source pixels. For other effect contexts, it is device independent.

2.1.1370 Part 4 Section 5.1.10.16, clrChange (Color Change Effect)

- a. *The standard states that attribute useA specifies whether alpha values are considered for the effect.*

In Office, if the value of useA is true, alpha is considered for finding a match for clrFrom, and the alpha is replaced with the alpha value in clrTo. If useA is false, no alpha values are changed.

2.1.1371 Part 4 Section 5.1.10.20, cont (Effect Container)

- a. *The standard states that the name attribute specifies an optional name for this list of effects.*

In Office, the name attribute specifies an optional name for the container. This name can be used by an effect [[ECMA-376](#) Part 4 §4; PresentationML Reference Material] within the same top level container. The name must be unique throughout the top level effect container.

2.1.1372 Part 4 Section 5.1.10.22, ds (Dash Stop)

- a. *The standard makes no restriction regarding the value of the dash length percentage.*

In Office, the dash length must be greater than zero.

- b. *The standard makes no restriction regarding the value of the space length percentage.*

In Office, the space length percentage must be greater than zero.

2.1.1373 Part 4 Section 5.1.10.23, duotone (Duotone Effect)

- a. *The standard states that colors are combined through linear interpolation.*

In Office, the interpolation is based on the luminance of the pixel.

2.1.1374 Part 4 Section 5.1.10.24, effect (Effect)

- a. *The standard states that the value of the ref attribute may be the name of an effect container, or one of four special references.*

Office requires this to be the case.

2.1.1375 Part 4 Section 5.1.10.25, effectDag (Effect Container)

For additional notes that apply to this portion of the standard, please see the notes for [cont. §5.1.10.20\(a\)](#).

- a. *The standard allows the user to create contradictory shape properties by using similar tags under effectDag and spPr at the same time.*

In Office, the behavior is unspecified if effectDag is used in conjunction with the following sibling elements: blipFill, gradFill, grpFill, noFill, pattFill, solidFill, effectLst.

2.1.1376 Part 4 Section 5.1.10.31, fillToRect (Fill To Rectangle)

a. *The standard states that the center shade fills the entire tile except the margins specified by each attribute.*

In Office the center shade fills the entire gradient path inscribed in this rectangle.

b. *The standard states that the Rectangle is defined relative to the tile rect.*

In Office the rectangle is defined relative to shape bounding box.

2.1.1377 Part 4 Section 5.1.10.33, gradFill (Gradient Fill)

a. *The standard uses flip (Tile flip) to specify the direction(s) in which to flip the gradient while tiling.*

In Office the flip (Tile flip) attribute is ignored and flip mode xy is used.

2.1.1378 Part 4 Section 5.1.10.35, grpFill (Group Fill)

a. *The standard states the grpFill works in all context.*

Office treats the grpFill element as noFill ["[ECMA-376](#) Part 4 §4; PresentationML Reference Material" when grpFill appears in a text context (that is as a descendant of defRPr ["[ECMA-376](#) Part 4 §4; PresentationML Reference Material", endParaRPr ["[ECMA-376](#) Part 4 §4; PresentationML Reference Material", or rPr ["[ECMA-376](#) Part 4 §4; PresentationML Reference Material").

2.1.1379 Part 4 Section 5.1.10.39, hsl (Hue Saturation Luminance Effect)

a. *The standard states that the hue, saturation, and luminance may be adjusted relative to its current value.*

In Office the hsl element adjusts the value of the hue, saturation, and luminance attributes by specified amounts.

2.1.1380 Part 4 Section 5.1.10.40, innerShdw (Inner Shadow Effect)

a. *The standard does not specify the frame of reference for the offset angle defined in the dir attribute..*

In Office, the angle defined in the dir attribute is measured clockwise from the left.

2.1.1381 Part 4 Section 5.1.10.42, lum (Luminance Effect)

a. *The standard states that brightness linearly shifts all colors closer to white or black and contrast scales all colors to be either closer or further apart.*

In Office, brightness linearly shifts all colors closer to white (positive brightness), or black (negative brightness) and contrast scales all colors to be further apart (positive contrast), or closer together (negative contrast).

2.1.1382 Part 4 Section 5.1.10.43, miter (Miter Line Join)

a. *The standard suggests that without the lim attribute, line join can extend infinitely.*

In Office, the limit that lines will extend to form a miter join is the maximum distance between the inner and outer corners expressed as a percentage of line width.

2.1.1383 Part 4 Section 5.1.10.50, reflection (Reflection Effect)

- a. *The standard states that the `align` and `dist` attributes describe shadow properties.*

In Office, the `align` and `dist` attributes describe reflection properties.

- b. *In the standard the attribute `dir` specifies the direction of the alpha gradient ramp relative to the shape itself, and the attribute `fadeDir` specifies the direction to offset the reflection.*

In Office, the attribute `fadeDir` specifies the direction of the alpha gradient ramp relative to the shape itself, and attribute `dir` specifies the direction to offset the reflection.

2.1.1384 Part 4 Section 5.1.10.52, round (Round Line Join)

- a. *The standard states that line joins will be round.*

In Office, the following preset shapes (“[ECMA-376](#) Part 4 §5.1.12.56; `ST_ShapeType` (Preset Shape Types)”) will use a mitered line join (“[ECMA-376](#) Part 4 §5.1.10.43; `miter` (Miter Line Join)”) even if `round` is specified:

`cube`, `moon`, `chevron`, `ellipseRibbon`, `ellipseRibbon2`, `plus`, `rightArrow`, `stripedRightArrow`, `notchedRightArrow`, `leftArrowCallout`, `leftRightArrowCallout`, `upDownArrowCallout`, `quadArrowCallout`, `star4`, `star5`, `star8`, `star10`, `star12`, `star16`, `star24`, `star32`, `upArrow`, `downArrow`, `upDownArrow`, `leftUpArrow`, `bentUpArrow`, `mathPlus`, `mathMinus`, `mathMultiply`, `mathEqual`, `mathNotEqual`

2.1.1385 Part 4 Section 5.1.10.53, softEdge (Soft Edge Effect)

- a. *The standard states that the `softEdge` element specifies a soft edge effect where the edges of the shape are blurred while the fill is not affected.*

In Office, this element specifies an inset radius for blur. Only the area between the shape boundary and the inset specified by the `rad` attribute is affected.

2.1.1386 Part 4 Section 5.1.10.55, srcRect (Source Rectangle)

- a. *The standard states that a negative percentage specifies an outset.*

In Office, a negative offset specifies an outset only if the blip is not tiled.

2.1.1387 Part 4 Section 5.1.10.59, tileRect (Tile Rectangle)

- a. *The standard states that the `tileRect` element applies to all gradient fills.*

In Office, if the gradient is used as a group fill, the tiling rectangle specified by this element is ignored.

2.1.1388 Part 4 Section 5.1.11.11, gd (Shape Guide)

- a. *The standard uses incorrect terms and symbols to describe shape guide formula `mod` in the `fmla` attribute.*

In Office, `mod x y z` equals $\sqrt{x^2 + y^2 + z^2}$.

b. *The standard defines $\text{sqrt } x = \text{sqrt}(x)$ in the `fmla` attribute.*

In Office, `sqrt x = sqrt(abs(x))`.

2.1.1389 Part 4 Section 5.1.11.15, path (Shape Path)

a. *The standard states that if the `extrusionOk` attribute is omitted then a value of 0, or false, is assumed.*

In Office and the schema, if the `extrusionOk` attribute is omitted then a value of true is assumed.

2.1.1390 Part 4 Section 5.1.11.17, pos (Shape Position Coordinate)

a. *The standard defines `x` and `y` coordinates as path relative coordinates.*

Office defines `x` and `y` coordinates as absolute EMU coordinates.

2.1.1391 Part 4 Section 5.1.11.20, pt (Shape Path Point)

For additional notes that apply to this portion of the standard, please see the notes for [pos](#), [§5.1.11.17\(a\)](#).

2.1.1392 Part 4 Section 5.1.12.12, ST_BlipCompression (Blip Compression Type)

a. *The standard states that `ST_BlipCompression` includes a high quality printing compression type (`hqprint`).*

Office does not implement High Quality Printing Compression mode (`hqprint`).

2.1.1393 Part 4 Section 5.1.12.15, ST_CompoundLine (Compound Line Type)

a. *The standard implies that the `ST_CompoundLine` simple type is only applicable to text with lines.*

Office also uses this simple type for text outlines, text underlines and shape outlines.

2.1.1394 Part 4 Section 5.1.12.16, ST_Coordinate (Coordinate)

a. *The standard states that the contents of the `ST_Coordinate` simple type can be at least -27273042329600 and at most 27273042316900.*

Word and PowerPoint restrict the contents of this simple type to be at least -2147483648 and at most 2147483647.

2.1.1395 Part 4 Section 5.1.12.29, ST_LightRigDirection (Light Rig Direction)

a. *The standard states that the informative images in this enumeration use a Three Point light rig type with an `orthographicFront` camera preset.*


In Office, the informative images in this enumeration use a flood light rig type with a `perspectiveContrastingRightFacing` camera preset.

2.1.1396 Part 4 Section 5.1.12.30, ST_LightRigType (Light Rig Type)

a. *The standard does not contain an informative example for the `balanced` value.*

In Office, the `balanced` enumeration value produces the following result:

[Example: Consider the following example of the `balanced` light rig applied to a basic shape:






end example]

2.1.1397 Part 4 Section 5.1.12.32, `ST_LineEndLength` (Line End Length)

a. *The standard provides identical pictures for the images associated with the `med` and `sm` enumeration values.*

In Office, the enumeration values produce the following results for the line end decoration:

| Enumeration Value | Description |
|---------------------------|---|
| <code>lg</code> (Large) |  Large |
| <code>med</code> (Medium) |  Medium |
| <code>sm</code> (Small) |  Small |

2.1.1398 Part 4 Section 5.1.12.35, `ST_LineWidth` (Line Width)

a. *The standard does not explain how a zero-width line will be rendered.*

In Office, a zero width line is interpreted as the minimum width line that can be rendered on the target device.

2.1.1399 Part 4 Section 5.1.12.40, `ST_PenAlignment` (Alignment Type)

a. *The standard implies that the `ST_PenAlignment` simple type is only used within a text body.*

Office uses this simple type for lines on text, shapes, and other graphical objects.

2.1.1400 Part 4 Section 5.1.12.42, `ST_PositiveCoordinate` (Positive Coordinate)

a. *The standard states that the contents of the `ST_PositiveCoordinate` simple type can be at most 27273042316900.*

Word and PowerPoint restrict the contents of this simple type to be at most 2147483647.

2.1.1401 Part 4 Section 5.1.12.48, ST_PresetColorVal (Preset Color Value)

a. *The standard specifies RGB values for each value in the enum.*

In Office, the following enumeration values produce colors different than those listed in the standard:

| Enumeration Value | Description |
|--|---|
| ltGoldenrodYellow (Light Goldenrod Yellow Preset Color) | Specifies a color with RGB value (250,250,210). |
| turquoise (Turquoise Preset Color) | Specifies a color with RGB value (255,255,255) |
| violet (Violet Preset Color) | Specifies a color with RGB value (64,224,208) |
| wheat (Wheat Preset Color) | Specifies a color with RGB value (238,130,238) |
| white (White Preset Color) | Specifies a color with RGB value (245,222,179) |
| whiteSmoke (White Smoke Preset Color) | Specifies a color with RGB value (255,255,255) |
| yellow (Yellow Preset Color) | Specifies a color with RGB value (245,245,245) |
| yellowGreen (Yellow Green Preset Color) | Specifies a color with RGB value (255,255,0) |

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.1402 Part 4 Section 5.1.12.55, ST_ShapeID (Shape ID)

a. *The standard does not limit the length of the value of the ST_ShapeID simple type.*

Office restricts the value of this simple type to be at most 255 characters.

b. *The standard states that the ST_ShapeID contents are a restriction of the XML Schema token datatype.*

In Office, the ST_ShapeID simple type represents an object ID number. An ID number has the following format characteristics:

Each ID number has a preface of “_x0000_” followed by 1 character and a number, in the general form `_x0000_[c]<num>`

The character [c] is:

‘t’ or ‘m’ when used for a **shapetype** element (“[ECMA-376](#) Part 4 §6.1.2.20; shapetype (Shape Template)”).

‘s’ when used for a shape.

Shape IDs always start at 1025.

Shape IDs are clustered together, and each cluster has 1024 values. The first cluster ranges from 1025 to 2048.

Shape IDs within the same cluster may only exist in:

one worksheet, for Excel.

one slide, for PowerPoint.

one document, for Word.

the header, for Word.

's' or 'i' for shapes that are inline (not floating) in Word.

__<num> must be between 1 and 268435456.

An ID number should not contain any Numeric Character Reference (NCR) markup characters.

Office does not guarantee that the same Object ID number that is loaded is round tripped on file save.

2.1.1403 Part 4 Section 5.1.12.60, ST_TextAnchoringType (Text Anchoring Types)

a. *The standard states that dist is a valid value of the ST_TextAnchoringType simple type.*

Office does not allow this value on this simple type.

b. *The standard states that just is a valid value of the ST_TextAnchoringType simple type.*

Office does not allow this value on this simple type.

2.1.1404 Part 4 Section 5.1.12.64, ST_TextCapsType (Text Cap Types)

a. *The standard states that the small value converts all letters to lower case.*

In Office, the small value converts all lower-case letters into upper-case letters of a smaller font size. The actual point size in the backing store is not affected.

b. *The standard does not clearly define the none value of the ST_TextCapsType simple type.*

Office uses this value to specify that no capitalization effects should be applied during text display and to override capitalization effects specified in styles.

c. *The standard states that the all value converts all letters to upper case.*

In Office, the all value causes text to be displayed as upper case and the original text remains unchanged in the file.

2.1.1405 Part 4 Section 5.1.12.72, ST_TextLanguageID (Language ID)

a. *The standard states that the ST_TextLanguageID specifies an ID representing a particular language.*

In Office, the language ID consists of an ISO 639-1 letter code followed by a dash and then an ISO 3166-1 alpha-2 letter code. The contents of this language shall be interpreted based on the context of the parent element.

2.1.1406 Part 4 Section 5.1.12.74, ST_TextNonNegativePoint (Text Non-Negative Point)

a. *The standard states that the ST_TextNonNegativePoint simple type specifies a non-negative font size in hundredths of a point.*

Office uses this type to store a non-negative size in hundredths of a point.

2.1.1407 Part 4 Section 5.1.12.75, ST_TextPoint (Text Point)



a. *The standard states that the ST_TextPoint simple type specifies a font size in hundredths of a point.*

Office uses this simple type to store a size in hundredths of a point.

2.1.1408 Part 4 Section 5.1.12.76, ST_TextShapeType (Preset Text Shape Types)

a. *The standard does not provide corresponding illustrations for preset text shape types textCircle and textDeflateTop.*

In Office, the textCircle and textDeflateTop enumeration values use the following descriptions and illustrations:

| Enumeration Value | Description |
|--|---|
| textCircle (Circle Text Shape) |  <p>Specifies a text shape that shall match the normative shape shown here.</p> |
| textDeflateTop (Top Deflate Text Shape) |  <p>Specifies a text shape that shall match the normative shape shown here.</p> |

2.1.1409 Part 4 Section 5.1.12.77, ST_TextSpacingPercent (Text Spacing Percent)

a. *The standard states that the ST_TextSpacingPercent simple type specifies the range that the spacing percent in terms of line in hundredths.*

Office uses this type to specify the percent of a line height in thousands of a percent.

2.1.1410 Part 4 Section 5.1.12.78, ST_TextSpacingPoint (Text Spacing Point)

a. *The standard states that the ST_TextSpacingPoint simple type specifies the text spacing that will be used in terms of font point size.*

Office uses this simple type to specify the size, in hundredths of a point, to be used for text spacing.

2.1.1411 Part 4 Section 5.1.12.82, ST_TextUnderlineType (Text Underline Types)

a. *The standard states that the words underline type will underline only the words and not the spaces in a text run.*

Office does not support the words underline type. When loaded, Office displays this as a single underline.

2.1.1412 Part 4 Section 5.2.2.1, blipFill (Picture Fill)

For additional notes that apply to this portion of the standard, please see the notes for [blipFill](#), §5.8.2.2(a).

2.1.1413 Part 4 Section 5.2.2.6, spPr (Shape Properties)

For additional notes that apply to this portion of the standard, please see the notes for [spPr](#), §5.6.2.29(a-c).

2.1.1414 Part 4 Section 5.5.2.3, anchor (Anchor for Floating DrawingML Object)

a. *The standard states that when the hidden attribute is true the object is not displayed.*

Word does not support this attribute and its value is not retained on save.

2.1.1415 Part 4 Section 5.5.2.6, effectExtent (Object Extents Including Effects)

a. *The standard states that the l, r, and t attributes specify the additional length that shall be added to the bottom edge of the DrawingML object to determine its actual bottom edge.*

Office uses these attributes to specify the additional length that shall be added to the left, right, and top edges, respectively, of the DrawingML object to determine its actual left, right, and top edges, respectively.

2.1.1416 Part 4 Section 5.5.2.7, extent (Drawing Object Size)

For additional notes that apply to this portion of the standard, please see the notes for [ext](#), §5.8.2.10(a).

2.1.1417 Part 4 Section 5.5.2.9, lineTo (Wrapping Polygon Line End Position)

For additional notes that apply to this portion of the standard, please see the notes for [chOff](#), §5.1.9.2(b).

2.1.1418 Part 4 Section 5.5.2.11, positionV (Vertical Positioning)

a. *The standard states that paragraph is a valid value of the relativeFrom attribute.*

Word does not allow this value on this attribute.

2.1.1419 Part 4 Section 5.5.2.13, simplePos (Simple Positioning Coordinates)

For additional notes that apply to this portion of the standard, please see the notes for [chOff](#), [§5.1.9.2\(b\)](#).

2.1.1420 Part 4 Section 5.5.2.14, start (Wrapping Polygon Start)

For additional notes that apply to this portion of the standard, please see the notes for [chOff](#), [§5.1.9.2\(b\)](#).

2.1.1421 Part 4 Section 5.6.2.2, blipFill (Picture Fill)

For additional notes that apply to this portion of the standard, please see the notes for [blipFill](#), [§5.8.2.2\(a\)](#).

2.1.1422 Part 4 Section 5.6.2.8, cNvPr (Non-Visual Drawing Properties)

- a. *The standard includes `hlinkHover` as a child of `cNvPr`.*

Excel does not support child element `hlinkHover`.

2.1.1423 Part 4 Section 5.6.2.9, cNvSpPr (Connection Non-Visual Shape Properties)

- a. *The standard implies that the `cNvSpPr` element describes the non-visual properties for a connection shape.*

In Office and the schema, this element describes the non-visual properties for a shape.

2.1.1424 Part 4 Section 5.6.2.10, col (Column))

- a. *The standard specifies the maximum number of columns as unbounded.*

In Excel, the maximum number of columns is 16383.

2.1.1425 Part 4 Section 5.6.2.12, cxnSp (Connection Shape)

- a. *The standard states that the values of the macro attribute are defined by the XML Schema string datatype.*

Office requires that the macro attribute value follow the same grammar as name-references ("[[ECMA-376](#)] Part 4 §3.17.2.5; Names") with a minimum length of 0 characters and a maximum length of 256 characters.

2.1.1426 Part 4 Section 5.6.2.13, ext (Shape Extent)

For additional notes that apply to this portion of the standard, please see the notes for [ext](#), [§5.8.2.10\(a\)](#).

2.1.1427 Part 4 Section 5.6.2.14, from (Starting Anchor Point)

- a. *The standard does not define any relationship between top/left and bottom/right, respectively.*

In Excel, top/left should be smaller than or equal to bottom/right. If these conditions are not met, the shape is not rendered.

2.1.1428 Part 4 Section 5.6.2.15, graphicFrame (Graphic Frame)

- a. *The standard states that the values of the macro attribute are defined by the XML Schema string datatype.*

Office requires that the macro attribute value follow the same grammar as name-references ("[ECMA-376](#) Part 4 §3.17.2.5; Names") with a minimum length of 0 characters and a maximum length of 256 characters.

2.1.1429 Part 4 Section 5.6.2.17, grpSpPr (Group Shape Properties)

- a. *The standard states that bwMode is a valid attribute on the grpSpPr element.*

Excel and Word do not support the bwMode attribute on this element.

- b. *The standard does not describe the relationship between group shapes and their child shapes with respect to bwMode.*

In Office, bwMode set at the group level should set bwMode for child shapes.

- c. *The standard states that the bwMode attribute specifies that the group shape should be rendered using only black and white coloring.*

Office uses this attribute to specify how the group shape should be rendered when in black and white mode.

2.1.1430 Part 4 Section 5.6.2.24, pic (Picture)

- a. *The standard states that the values of the macro attribute are defined by the XML Schema string datatype.*

Office requires that the macro attribute value follow the same grammar as name-references ("[ECMA-376](#) Part 4 §3.17.2.5; Names") with a minimum length of 0 characters and a maximum length of 256 characters.

2.1.1431 Part 4 Section 5.6.2.25, pos (Position)

For additional notes that apply to this portion of the standard, please see the notes for [chOff, §5.1.9.2\(b\)](#).

2.1.1432 Part 4 Section 5.6.2.26, row (Row)

- a. *The standard allows the number of rows to be unbounded.*

The maximum number of rows allowed by Office is 1048575.

2.1.1433 Part 4 Section 5.6.2.28, sp (Shape)

- a. *The standard states that textlink is a formula linking to spreadsheet cell data.*

Excel requires that the value of the textlink attribute be a string referencing a cell or a cell range. It should reference a unique cell, as only the first cell in a cell range will be considered.

- b. *In the standard, child element txBody has minOccurs equal to zero.*

In Excel, if optional attribute textlink is specified, child element txBody is required.

c. *The standard states that the values of the macro attribute are defined by the XML Schema string datatype.*

Office requires that the macro attribute value follow the same grammar as name-references ("ECMA-376 Part 4 §3.17.2.5; Names") with a minimum length of 0 characters and a maximum length of 256 characters.

2.1.1434 Part 4 Section 5.6.2.29, spPr (Shape Properties)

a. *The standard states that bwMode is a valid attribute on the spPr element.*

Excel and Word do not support this attribute on this element.

b. *The standard states that the spPr element specifies the visual shape properties that can be applied to a special shape such as a connector shape or picture.*

Office uses this element to specify the visual shape properties that can be applied to shapes, connector shapes, or pictures.

c. *The standard states that the bwMode attribute specifies that the group shape should be rendered using only black and white coloring.*

Office uses this attribute to specify how the group shape should be rendered when in black and white mode.

2.1.1435 Part 4 Section 5.6.2.30, style (Shape Style)

a. *The standard allows a sp, pic or cxnSp to have similar formatting options defined in both the style and spPr elements.*

In Office, shape properties defined on the parent element will override similar style components (InRef, effectRef, fillRef, fontRef) defined in this element.

b. *The standard allows similar text formatting properties to be defined for parent element sp by style or txBody.*

In Office, child elements in txBody will override similar style properties defined by attribute fontRef.

c. *The standard states that child element fontRef applies to parent elements pic, cxnSp and sp.*

In Office, child element fontRef is not used for parent elements pic and cxnSp.

2.1.1436 Part 4 Section 5.6.2.31, to (Ending Anchor Point)

a. *The standard allows shapes to be defined where the right edge is to the left of the left edge or where the bottom edge is above the top edge.*

Excel does not support shapes where the right edge is to the left of the left edge or where the bottom edge is above the top edge.

2.1.1437 Part 4 Section 5.6.2.33, txBody (Shape Text Body)

a. *The standard does not describe the relationship between similar properties in child elements p (text paragraphs) and lstStyle (text list styles).*

In Office, if no text list styles are defined in a paragraph, styles from `IstStyle` are used. If no list styles are defined and there is no `IstStyle` defined, the text in the list defaults to the current text style.

2.1.1438 Part 4 Section 5.6.2.35, `xfrm` (2D Transform for Graphic Frames)

For additional notes that apply to this portion of the standard, please see the notes for [`xfrm`](#), [§5.1.9.6\(a\)](#).

- a. *The standard includes attributes `flipH`, `flipV` and `rot` for the `xfrm` element.*

Excel does not support these attributes for graphic frames. Any value loaded for these attributes will not be written to the file when saved.

- b. *The standard includes `ext` and `off` as child elements of `xfrm`.*

The `ext` and `off` elements are used by Excel only if the graphic frame is inside of a group. If the graphic frame is not inside of a group, Excel will always output 0 for the attribute values of both elements.

2.1.1439 Part 4 Section 5.7.2.1, `applyToEnd` (Apply to End)

For additional notes that apply to this portion of the standard, please see the notes for [`applyToFront`](#), [§5.7.2.2\(a\)](#); [`applyToSides`](#), [§5.7.2.3\(a\)](#).

- a. *The standard specifies `on` and `off` as valid values for the `val` attribute.*

Office does not consider `on` and `off` to be valid values for this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.1440 Part 4 Section 5.7.2.2, `applyToFront` (Apply To Front)

For additional notes that apply to this portion of the standard, please see the notes for [`applyToEnd`](#), [§5.7.2.1\(a\)](#); [`applyToSides`](#), [§5.7.2.3\(a\)](#).

- a. *The standard specifies `on` and `off` as valid values for the `val` attribute.*

Office does not consider `on` and `off` to be valid values for this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

- b. *The standard states that the `applyToFront` element specifies that the picture shall be applied to the front of the point or series.*

In Office, this element also specifies that the picture should be applied to the `backWall` and Office ignores this element on the `floor` and `sideWall` elements.

2.1.1441 Part 4 Section 5.7.2.3, `applyToSides` (Apply To Sides)

For additional notes that apply to this portion of the standard, please see the notes for [`applyToEnd`](#), [§5.7.2.1\(a\)](#); [`applyToFront`](#), [§5.7.2.2\(a\)](#).

- a. *The standard specifies `on` and `off` as valid values for the `val` attribute.*

Office does not consider `on` and `off` to be valid values for this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

b. *The standard states that the applyToSides element specifies that the picture shall be applied to the sides of the point or series.*

In Office this element also specifies that the picture shall be applied to the floor or the side wall but is ignored on the back wall of a 3D chart.

2.1.1442 Part 4 Section 5.7.2.4, area3DChart (3D Area Charts)

For additional notes that apply to this portion of the standard, please see the notes for [varyColors](#), [§5.7.2.228\(a\)](#).

2.1.1443 Part 4 Section 5.7.2.5, areaChart (Area Charts)

a. *The standard states that the maxOccurs value for the ser child element is unbounded.*

Office limits the occurrences of this element to 255.

2.1.1444 Part 4 Section 5.7.2.6, auto (Automatic Category Axis)

a. *The standard states that the default value of the val attribute is true.*

Office uses a default value of false for this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.1445 Part 4 Section 5.7.2.7, autoTitleDeleted (Auto Title Is Deleted)

a. *The standard does not state any exceptions that cause the autoTitleDeleted element to be ignored.*

In Office, this element only applies if a title element ("[\[ECMA-376\]](#) Part 4 §5.7.2.211; title") is not present on the parent chart element ("[\[ECMA-376\]](#) Part 4 §5.7.2.27; chart").

b. *The standard states that the default value of the val attribute is true.*

Office uses a default value of false for this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

c. *The standard specifies on and off as valid values for the val attribute.*

Office does not consider on and off to be valid values for this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.1446 Part 4 Section 5.7.2.8, autoUpdate (Update Automatically)

a. *The standard states that on and off are valid values of the val attribute.*

Office does not allow these values on this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

b. *The standard states that the default value of the val attribute is true.*

Office uses a default value of false for this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.1447 Part 4 Section 5.7.2.9, axId (Axis ID)

a. *The standard states that values of the val attribute are defined by the XML Schema unsignedInt datatype.*

Office restricts the value of this attribute to be at most 2147483647.

b. *The standard does not place any restrictions on the val attribute of the axId element.*

Office requires that the val attribute of this element matches the val attribute of an axId element on a catAx, dateAx, serAx, or valAx element on the chart.

2.1.1448 Part 4 Section 5.7.2.10, axPos (Axis Position)

a. *The standard states that the axpos element specifies the position of the axis on the chart.*

Office ignores this element, always using the crosses element on a valAx, the crossesAt element on a catAx or dateAx, and the orientation element of the scaling element on the perpendicular axis to specify the axis position.

2.1.1449 Part 4 Section 5.7.2.11, backWall (Back Wall)

a. *The standard states that the backWall element is valid for any chart type.*

Office only allows this element for 3D charts (bar3dChart, line3dChart, area3dChart, surface3dChart, pie3Dchart).

2.1.1450 Part 4 Section 5.7.2.12, backward (Backward)

a. *The standard states that the value of the val attribute on non-scatter charts must be 0 or 0.5.*

Office allows the data range to include any non-negative number.

b. *The standard states that the values of the val attribute are defined by the XML Schema double datatype.*

Office restricts the values of this attribute to be greater than 0 and not equal to INF, -INF, or Nan.

2.1.1451 Part 4 Section 5.7.2.14, bandFmts (Band Formats)

a. *The standard states that bands are indexed from low to high.*

The bands within this collection are indexed with increasing index values that correspond to increasing values in the chart. The lowest index value for a band is 0, regardless of whether it is present in the collection of formatting bands. Bands with no explicit formatting may be omitted from the collection.

2.1.1452 Part 4 Section 5.7.2.15, bar3DChart (3D Bar Charts)

a. *The standard states that the maxOccurs value for the ser child element is unbounded.*

Office limits the occurrences of this element to 255.

2.1.1453 Part 4 Section 5.7.2.16, barChart (Bar Charts)

For additional notes that apply to this portion of the standard, please see the notes for [axId](#), [§5.7.2.9\(a\)](#); [gapWidth](#), [§5.7.2.75\(a\)](#).

- a. *The standard states that the maxOccurs value for the serLines child element is unbounded.*
Office limits the occurrences of this element to 1.

2.1.1454 Part 4 Section 5.7.2.17, barDir (Bar Direction)

- a. *The standard implies that the val attribute is optional.*
Office requires this attribute.

2.1.1455 Part 4 Section 5.7.2.18, baseTimeUnit (Base Time Unit)

For additional notes that apply to this portion of the standard, please see the notes for [majorTimeUnit](#), [§5.7.2.103\(a\)](#); [minorTimeUnit](#), [§5.7.2.112\(a\)](#).

- a. *The standard states that the default value of the val attribute is days.*
Office uses a default value that is dependent on the time span of the date axis.
This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.1456 Part 4 Section 5.7.2.19, bubble3D (3D Bubble)

For additional notes that apply to this portion of the standard, please see the notes for [bubbleChart](#), [§5.7.2.20\(b\)](#).

- a. *The standard states that the default value of the val attribute is true.*
Office uses a default value of false for this attribute.
This note applies to the following products: 2007, 2007 SP1, 2007 SP2.
- b. *The standard does not state that the bubble3D element is a valid child of the ser (Area Chart) element.*
Office allows the bubble3D element to be a child of the ser (Area Chart) element.
This note applies to the following products: 2007, 2007 SP1, 2007 SP2.
- c. *The standard does not state that the bubble3D element is a valid child of the ser (Line Chart Series) element.*
Office allows the bubble3D element to be a child of the ser (Line Chart Series) element.
This note applies to the following products: 2007, 2007 SP1, 2007 SP2.
- d. *The standard does not state that the bubble3D element is a valid child of the ser (Pie Chart Series) element.*
Office allows the bubble3D element to be a child of the ser (Pie Chart Series) element.
This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

e. *The standard does not state that the bubble3D element is a valid child of the ser (Surface Chart Series) element.*

Office allows the bubble3D element to be a child of the ser (Surface Chart Series) element.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

f. *The standard does not state that the bubble3D element is a valid child of the ser (Scatter Chart) element.*

Office allows the bubble3D element to be a child of the ser (Scatter Chart) element.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

g. *The standard does not state that the bubble3D element is a valid child of the ser (Radar Chart) element.*

Office allows the bubble3D element to be a child of the ser (Radar Chart) element.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

h. *The standard does not state that the bubble3D element is a valid child of the ser (Bar Chart) element.*

Office allows the bubble3D element to be a child of the ser (Bar Chart) element.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.1457 Part 4 Section 5.7.2.20, bubbleChart (Bubble Charts)

For additional notes that apply to this portion of the standard, please see the notes for [axId, §5.7.2.9\(a\)](#); [showNegBubbles, §5.7.2.186\(a\)](#); [varyColors, §5.7.2.228\(a\)](#).

a. *The standard states that the maxOccurs value for the ser child element is unbounded.*

Office limits the occurrences of this element to 255.

b. *The standard states that the bubble3D element is a valid child of the bubbleChart element.*

Office does not allow the bubble3D element to be a child of the bubbleChart element.

2.1.1458 Part 4 Section 5.7.2.23, builtInUnit (Built in Display Unit Value)

a. *The standard states that the default value of the val attribute is thousands.*

Office treats the default as a custUnit with a val attribute equal to 1.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

b. *The standard states that the builtInUnit element specifies that the display unit is one of the built in values.*

In Office, this element specifies the display unit for the axis and also the text shown by sibling element dispUnitsLbl when the dispUnitLbl does not contain a tx child element.

2.1.1459 Part 4 Section 5.7.2.24, cat (Category Axis Data)

a. *The standard does not define the behavior when the cat element is omitted.*

Office uses the one-based index value of the corresponding data point as the default category axis data when this element is omitted on a series.

2.1.1460 Part 4 Section 5.7.2.25, catAx (Category Axis Data)

- a. *The standard does place any restrictions on the val attribute of the axId element.*

Office requires that the val attribute of the axId element matches the val attribute of an axId element in the parent chart.

- b. *The standard does place any restrictions on the val attribute of the crossAx element.*

Office requires that the val attribute of the crossAx element matches the val attribute of an axId element in the parent chart.

2.1.1461 Part 4 Section 5.7.2.28, chartObject (Chart Object)

- a. *The standard states that the chartObject element specifies that the chart cannot be edited by the user.*

Office does not respect this element and allows editing regardless of the value.

- b. *The standard specifies on and off as valid values for the val attribute.*

Office does not consider on and off to be valid values for this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

- c. *The standard states that the default value of the val attribute is true.*

Office uses a default value of false for this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.1462 Part 4 Section 5.7.2.31, crossAx (Crossing Axis ID)

- a. *The standard states that the values of the val attribute are defined by the XML Schema unsignedInt datatype.*

Office restricts the value of this attribute to be at most 2147483647.

- b. *The standard does not place any restrictions on the val attribute of the crossAx element.*

Office requires that the val attribute of the crossAx element matches the val attribute of an axId element in the parent chart.

2.1.1463 Part 4 Section 5.7.2.34, crossesAt (Crossing Value)

For additional notes that apply to this portion of the standard, please see the notes for [custUnit, §5.7.2.36\(a\)](#); [splitPos, §5.7.2.196\(c\)](#).

- a. *The standard states the value's data type is determined by the parent element.*

In Office, the value data type is inferred from the type of axis being crossed, as follows:

When the axis to cross is specified by a **valAx** element, the value is a decimal number on the value axis.

When the axis to cross is specified by a **dateAx element**, the date is defined as a integer number of days since Dec. 31, 1899, unless date1904 is set, in which case they are defined as an integer number of days since Dec. 31, 1903.

When the axis to cross is specified by a **catAx element**, the value is an integer category number, starting with 1 as the first category.

b. *The standard states that the possible values for the val attribute are defined by the XML Schema double datatype.*

In Office, INF, -INF, and NaN are not supported values.

2.1.1464 Part 4 Section 5.7.2.36, custUnit (Custom Display Unit)

For additional notes that apply to this portion of the standard, please see the notes for [crossesAt, §5.7.2.34\(b\)](#); [splitPos, §5.7.2.196\(c\)](#).

a. *The standard states that the possible values for the val attribute are defined by the XML Schema double datatype.*

In Office, INF, -INF, and NaN are not supported values.

b. *The standard states that the custUnit element specifies a custom value for the display unit.*

In Office, this element specifies a custom value for the display unit for the axis. This element specifies the text shown by sibling element dispUnitsLbl when the dispUnitLbl does not contain a tx child element.

2.1.1465 Part 4 Section 5.7.2.37, data (Data Cannot Be Changed)

a. *The standard specifies on and off as valid values for the val attribute.*

Office does not consider on and off to be valid values for this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

b. *The standard states that the default value of the val attribute is true.*

Office uses a default value of false for this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

c. *The standard states that the data element prevents the user from changing the choice of data used for the chart".*

Office does not respect this element and allows the user to change the choice of data.

2.1.1466 Part 4 Section 5.7.2.38, date1904 (1904 Date System)

a. *The standard states that the default value of the val attribute is true.*

Office uses a default value of false for this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

b. *The standard states that the data1904 element specifies that the chart uses the 1904 date system.*

Office does not respect this element on load or save and instead uses the date system specified for the workbook, the date1904 attribute of workbookPr.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.1467 Part 4 Section 5.7.2.39, dateAx (Date Axis)

a. *The standard does not state that the noMultiLvlLbl element is a valid child of the dateAx element.*

Office allows the noMultiLvlLbl element to be a child of the dateAx element.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

b. *The standard does not place any restrictions on the val attribute of the axId element.*

Office requires that the val attribute of the axId element matches the val attribute of an axId element in the parent chart.

c. *The standard does not place any restrictions on the val attribute of the crossAx element.*

Office requires that the val attribute of the crossAx element matches the val attribute of an axId element in the parent chart.

2.1.1468 Part 4 Section 5.7.2.40, delete (Delete)

a. *The standard states that the default value of the val attribute is true.*

Office uses a default value of false for this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

b. *The standard specifies on and off as valid values for the val attribute.*

Office does not consider on and off to be valid values for this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.1469 Part 4 Section 5.7.2.41, depthPercent (Depth Percent)

a. *The standard states that the depthpercent element specifies the depth of a 3-D chart as a percentage of the chart width.*

In Office, this element specifies the depth of a 3-D chart as a percentage of the 3-D plot area width.

2.1.1470 Part 4 Section 5.7.2.42, dispBlanksAs (Display Blanks As)

a. *The standard states the default value of the val attribute is zero.*

Office uses a default value of gap for chart types that support displaying blanks as gaps. Otherwise, the default value is zero.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

b. *The standard places no restriction on @val beyond ST_DisplayBlanksAs.*

The following table shows which chart types support which methods of displaying blank cells. The supported methods often depend on the chart's grouping ("ECMA-376 Part 4 §5.7.2.76; grouping (Grouping)") **type**.

| Chart Type | Gap | Span | Zero | Default |
|---|-----|------|------|-------------|
| ("ECMA-376 Part 4 §5.7.2.16; barChart (Bar Charts)") | • | | • | <i>gap</i> |
| ("ECMA-376 Part 4 §5.7.2.15; bar3DChart (3D Bar Charts)") | • | | • | <i>gap</i> |
| ("ECMA-376 Part 4 §5.7.2.5; areaChart (Area Charts)") where grouping is <i>standard</i> | • | | • | <i>gap</i> |
| ("ECMA-376 Part 4 §5.7.2.5; areaChart (Area Charts)") where grouping is not <i>standard</i> | | | • | <i>zero</i> |
| ("ECMA-376 Part 4 §5.7.2.4; area3DChart (3D Area Charts)") | | | • | <i>zero</i> |
| ("ECMA-376 Part 4 §5.7.2.98; lineChart (Line Charts)") where grouping is <i>standard</i> | • | • | • | <i>gap</i> |
| ("ECMA-376 Part 4 §5.7.2.98; lineChart (Line Charts)") where grouping is not <i>standard</i> | | | • | <i>zero</i> |
| ("ECMA-376 Part 4 §5.7.2.97; line3DChart (3D Line Charts)") | • | | • | <i>gap</i> |
| ("ECMA-376 Part 4 §5.7.2.142; pieChart (Pie Charts)") | • | | • | <i>gap</i> |
| ("ECMA-376 Part 4 §5.7.2.141; pie3DChart (3D Pie Charts)") | • | | • | <i>gap</i> |
| ("ECMA-376 Part 4 §5.7.2.50; doughnutChart (Doughnut Charts)") | • | | • | <i>gap</i> |
| ("ECMA-376 Part 4 §5.7.2.20; bubbleChart (Bubble Charts)") | • | • | • | <i>gap</i> |

| Chart Type | Gap | Span | Zero | Default |
|---|-----|------|------|---------|
| ("[ECMA-376] Part 4 §5.7.2.162; scatterChart (Scatter Charts)") | • | • | • | gap |
| ("[ECMA-376] Part 4 §5.7.2.154; radarChart (Radar Charts)") | • | • | • | gap |

If a method of displaying blank cells not supported by the chart type is specified, the chart uses its default method of displaying blank cells.

2.1.1471 Part 4 Section 5.7.2.43, dispEq (Display Equation)

- a. *The standard states that the default value of the val attribute is true.*

Office uses a default value of false for this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

- b. *The standard does not state any exceptions that cause the dispEq element to be ignored.*

Office ignores this element if the trendlineLbl sibling element contains a tx element or if the value attribute of trendlineType sibling element is equal to movingAvg.

- c. *The standard specifies on and off as valid values for the val attribute.*

Office does not consider on and off to be valid values for this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.1472 Part 4 Section 5.7.2.44, dispRSqr (Display R Squared Value)

- a. *The standard states that the default value of the val attribute is true.*

Office uses a default value of false for this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

- b. *The standard does not state any exceptions that cause the dispRSqr element to be ignored.*

Office ignores this element if the trendlineLbl sibling element contains a tx element or if the val attribute of trendlineType sibling element is equal to movingAvg.

- c. *The standard specifies on and off as valid values for the val attribute.*

Office does not consider on and off to be valid values for this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.1473 Part 4 Section 5.7.2.47, dLbl (Data Label)

- a. *The standard states that the dLbl element can be a child of any pivotFmt or dLbls element.*

In Office, this element is only specified if the parent element is a pivotFmt or if the parent element is a dLbIs with a series parent element.

b. *The standard does not state any exceptions that cause children of the dLbI element to be ignored.*

Office ignores the numFmt, separator, showBubbleSize, showCatName, showPercent, showSerName, and showVal child elements if this element contains a tx child element.

2.1.1474 Part 4 Section 5.7.2.48, dLbIPos (Data Label Position)

a. *The standard places no restriction on @val beyond ST_DLbIPos.*

In Office, if the ancestor does not include a **ser** element any position value is allowed. However, if a **ser** element is an ancestor the following rules apply based on the chart group ancestor:

For chart groups **ofPieChart** ("ECMA-376 Part 4 §5.7.2.127; ofPieChart (Pie of Pie or Bar of Pie Charts)"), **pie3DChart** ("ECMA-376 Part 4 §5.7.2.141; pie3DChart (3D Pie Charts)"), and **pieChart** ("ECMA-376 Part 4 §5.7.2.142; pieChart (Pie Charts)") the valid positions are *BestFit*, *OutsideEnd*, *InsideEnd*, *Center*.

For the chart groups **barChart** ("ECMA-376 Part 4 §5.7.2.16; barChart (Bar Charts)") where **grouping** is *clustered* the valid positions are *InsideBase*, *InsideEnd*, *OutsideEnd*, *Center*.

For the chart groups **barChart** ("ECMA-376 Part 4 §5.7.2.16; barChart (Bar Charts)") where **grouping** is *stacked* or *percentStacked* the valid positions are *InsideBase*, *InsideEnd*, *Center*.

For chart groups **bubbleChart** ("ECMA-376 Part 4 §5.7.2.20; bubbleChart (Bubble Charts)"), **lineChart** ("ECMA-376 Part 4 §5.7.2.98; lineChart (Line Charts)"), **scatterChart** ("ECMA-376 Part 4 §5.7.2.162; scatterChart (Scatter Charts)"), and **stockChart** ("ECMA-376 Part 4 §5.7.2.199; stockChart (Stock Charts)") the valid positions are *left*, *right*, *bottom*, *top*, *center*.

For chart groups **areaChart** ("ECMA-376 Part 4 §5.7.2.5; areaChart (Area Charts)"), **area3DChart** ("ECMA-376 Part 4 §5.7.2.4; area3DChart (3D Area Charts)"), **bar3DChart** ("ECMA-376 Part 4 §5.7.2.15; bar3DChart (3D Bar Charts)"), **doughnutChart** ("ECMA-376 Part 4 §5.7.2.50; doughnutChart (Doughnut Charts)"), **line3DChart** ("ECMA-376 Part 4 §5.7.2.97; line3DChart (3D Line Charts)"), **radarChart** ("ECMA-376 Part 4 §5.7.2.154; radarChart (Radar Charts)") this element shall not be specified.

b. *The standard does not define the behavior when the dLbIPos element is omitted.*

For Office, the following lists the chart types and their default position based on the chart group ancestor:

For chart groups **ofPieChart** ("ECMA-376 Part 4 §5.7.2.127; ofPieChart (Pie of Pie or Bar of Pie Charts)"), **pie3DChart** ("ECMA-376 Part 4 §5.7.2.141; pie3DChart (3D Pie Charts)"), and **pieChart** ("ECMA-376 Part 4 §5.7.2.142; pieChart (Pie Charts)") the automatic position is *BestFit*.

For chart groups **areaChart** ("ECMA-376 Part 4 §5.7.2.5; areaChart (Area Charts)"), **area3DChart** ("ECMA-376 Part 4 §5.7.2.4; area3DChart (3D Area Charts)"), and **doughnutChart** ("ECMA-376 Part 4 §5.7.2.50; doughnutChart (Doughnut Charts)") the automatic position is *Center*.

For chart groups **barChart** (“[ECMA-376](#) Part 4 §5.7.2.16; barChart (Bar Charts)”) and **bar3DChart** (“[ECMA-376](#) Part 4 §5.7.2.15; bar3DChart (3D Bar Charts)”) where **grouping** (“[ECMA-376](#) Part 4 §5.7.2.77; grouping (Bar Grouping)”) is *stacked* or *percentStacked*; the automatic position is *Center*.

For chart groups **barChart**, and **bar3Dchart** where **grouping** is *clustered*, and **radarChart** (“[ECMA-376](#) Part 4 §5.7.2.154; radarChart (Radar Charts)”) the automatic position is *OutsideEnd*.

For chart groups **bubbleChart** (“[ECMA-376](#) Part 4 §5.7.2.20; bubbleChart (Bubble Charts)”), **scatterChart** (“[ECMA-376](#) Part 4 §5.7.2.162; scatterChart (Scatter Charts)”), **stockChart** (“[ECMA-376](#) Part 4 §5.7.2.199; stockChart (Stock Charts)”), **lineChart** (“[ECMA-376](#) Part 4 §5.7.2.98; lineChart (Line Charts)”), and **line3DChart** (“[ECMA-376](#) Part 4 §5.7.2.97; line3DChart (3D Line Charts)”) the automatic position is *Right*.

2.1.1475 Part 4 Section 5.7.2.49, dLbIs (Data Labels)

a. *The standard does not place any restrictions on when the child elements of the dLbIs element can be specified.*

Office does not allow delete, dLbl, leaderLines, numFmt, showLeaderLines, spPr or txPr child elements when the parent is not ser.

b. *The standard does not specify an override behavior for data labels.*

Office interprets data labels to have a hierarchical order of overrides. A dLbIs child element of a series overrides the dLbIs element of the ancestor chart group. A dLbl element overrides the dLbIs element of the ancestor series or chart group.

2.1.1476 Part 4 Section 5.7.2.50, doughnutChart (Doughnut Charts)

a. *The standard states that the minOccurs value for the holeSize child element is 0.*

Office requires an occurrence of this element.

2.1.1477 Part 4 Section 5.7.2.55, errBars (Error Bars)

a. *The standard does not state any exceptions that cause the errBars element to be ignored.*

Office ignores this element if the chart is a 3D style chart.

2.1.1478 Part 4 Section 5.7.2.56, errBarType (Error Bar Type)

a. *The standard implies that the val attribute is optional.*

Office requires this attribute.

2.1.1479 Part 4 Section 5.7.2.57, errDir (Error Bar Direction)

a. *The standard does not define the behavior when the errDir element is omitted.*

In Office, if this element is not defined the default behavior is x for horizontal bar charts. For all other chart types, the default behavior is y.

b. *The standard states errDir can be a child of any errBars element.*

Office loads and respects this element on any errBars parent element; however, this element is only saved back out on line or scatter series.

2.1.1480 Part 4 Section 5.7.2.58, errValType (Error Bar Value Type)

- a. *The standard implies that the val attribute is optional.*

Office requires this attribute.

2.1.1481 Part 4 Section 5.7.2.59, evenFooter (Even Footer)

- a. *The standard does not state any exceptions that cause the evenFooter element to be ignored.*

Office ignores this element if the val attribute of the differentOddEven sibling element is not set to true.

- b. *The standard states that the evenFooter element is of type ST_XString.*

Office does not attempt to decode the character escape sequences defined in ST_XString.

2.1.1482 Part 4 Section 5.7.2.60, evenHeader (Even Header)

- a. *The standard does not state any exceptions that cause the evenHeader element to be ignored.*

Office ignores this element if the val attribute of the differentOddEven sibling element is not set to true.

- b. *The standard states that the evenHeader element is of type ST_XString.*

Office does not attempt to decode the character escape sequences defined in ST_XString.

2.1.1483 Part 4 Section 5.7.2.61, explosion (Explosion)

- a. *The standard states that the values of the val attribute are defined by the XML Schema unsignedInt datatype.*

Office restricts the value of this attribute to be at most 2147483647.

2.1.1484 Part 4 Section 5.7.2.63, externalData (External Data Relationship)

- a. *The standard states the relationship explicitly targeted by the id attribute shall be of type <http://schemas.openxmlformats.org/officeDocument/2006/relationships/package>.*

In Office, the relationship specified by the id attribute shall be present in the set of relationships associated with the chart's part in the package.

2.1.1485 Part 4 Section 5.7.2.65, f (Formula)

- a. *The standard states that the values of the f element are defined by the XML Schema string datatype.*

Office requires the f element be a formula as defined in Formulas ("[ECMA-376](#) Part 4 §3.17; Formulas"). The maximum length of the decoded string shall not exceed 8192 characters.

2.1.1486 Part 4 Section 5.7.2.66, firstFooter (First Footer)

- a. *The standard does not state any exceptions that cause the firstFooter element to be ignored.*

Office ignores this element if the differentOddEven attribute of the parent headerFooter element is not set to true.

- b. *The standard states that the firstFooter element is of type ST_Xstring.*

Office does not attempt to decode the character escape sequences defined in ST_XString.

2.1.1487 Part 4 Section 5.7.2.67, firstHeader (First Header)

- a. *The standard does not state any exceptions that cause the firstHeader element to be ignored.*

Office ignores this element if the differentOddEven attribute of the parent headerFooter element is not set to true.

- b. *The standard states that the firstHeader element is of type ST_Xstring.*

Office does not attempt to decode the character escape sequences defined in ST_XString.

2.1.1488 Part 4 Section 5.7.2.69, floor (Floor)

- a. *The standard states that the floor element can be a child of any chart element.*

Office requires that the chart contain a 3D chart group (bar3DChart, line3DChart, area3DChart, surface3DChart, or pie3DChart) when this element is specified.

2.1.1489 Part 4 Section 5.7.2.70, fmtId (Format ID)

- a. *The standard states that values of the val attribute are defined by the XML Schema unsignedInt datatype.*

Office restricts the value of this attribute to be at most 2147483647.

2.1.1490 Part 4 Section 5.7.2.72, formatting (Formatting)

- a. *The standard specifies on and off as valid values for the val attribute.*

Office does not consider on and off to be valid values for this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

- b. *The standard states that the default value of the val attribute is true.*

Office uses a default value of false for this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

- c. *The standard states that the formatting element prevents a user from changing formatting on chart elements.*

Office does not fully respect this element and does not protect the chart from formatting changes in all scenarios.

2.1.1491 Part 4 Section 5.7.2.73, forward (Forward)

- a. *The standard states that the value of the val attribute on non-scatter charts must be a multiple of 0.5.*

Office allows the data range to include any non-negative number.

- b. *The standard states that attribute val is of type xsd:double.*

Office does not allow INF, -INF, and NaN as supported values. For scatterChart and bubbleChart, the value is in units, otherwise the value is in number of categories. The value of this attribute has a minimum value greater than 0.

2.1.1492 Part 4 Section 5.7.2.74, gapDepth (Gap Depth)

- a. *The standard states that the gapDepth element specifies the space between bar or column clusters, as a percentage of the bar or column width.*

In Office, this element specifies the space between adjacent categories in the depth axis direction, as a percentage of the bar, column, line, or base depth.

2.1.1493 Part 4 Section 5.7.2.75, gapWidth (Gap Width)

- a. *The standard states that the default value of the val attribute is 150.*

Office uses a default value of 100 when the gapWidth element is inside an ofPieChart element and 150 when the gapWidth element is inside a bar3DChart, barChart, or upDownBars element.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

- b. *The standard does not state how to interpret a gapWidth element on an ofPieChart element.*

In Office, the gapWidth element on an ofPieChart element specifies the radius of the primary pie for an ofPieChart.

- c. *The standard states that the gapWidth element specifies the space between bar or column clusters, as a percentage of the bar or column width.*

In Office, this element specifies the space between adjacent series clusters in the category axis direction, as a percentage of the bar or column width for bar3DChart, barChart, and upDownBars.

2.1.1494 Part 4 Section 5.7.2.76, grouping (Grouping)

- a. *The standard states that the grouping element specifies the type of grouping for a column, line, or area chart.*

In Office, this element specifies the type of grouping for a line or area chart.

2.1.1495 Part 4 Section 5.7.2.77, grouping (Bar Grouping)

- a. *The standard states that the default value of the val attribute is clustered.*

Office uses a default value of standard for this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.1496 Part 4 Section 5.7.2.78, h (Height)

For additional notes that apply to this portion of the standard, please see the notes for [crossesAt, §5.7.2.34\(b\)](#); [custUnit, §5.7.2.36\(a\)](#); [splitPos, §5.7.2.196\(c\)](#).

- a. *The standard does not state any exceptions that cause the h element to be ignored.*

Office ignores this element when a descendant of dispUnitsLbl, dLbl, title, or trendline and instead fits the element to the size of the text.

- b. *The standard does not state any exceptions that cause the h element to be ignored or interpreted differently.*

In Office, if the value of the val attribute is greater than 1 or less than 0, this element and the parent element manualLayout are ignored. Instead, the parent of manualLayout shall use its default size and position.

2.1.1497 Part 4 Section 5.7.2.79, headerFooter (Header and Footer)

- a. *The standard states that the alignWithMargins attribute specifies that the header and footer should align with the left and right margins of the chart.*

In Office, a value of true for this attribute specifies that the left and right edges of the header and footer align with the left and right margins of chart. A value of false specifies the application will determine the alignment.

- b. *The standard specifies on and off as valid values for the attributes alignsWithMargins, differentFirst, and differentOddEven.*

In Office, on and off are not valid values for these attributes.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.1498 Part 4 Section 5.7.2.81, hMode (Height Mode)

For additional notes that apply to this portion of the standard, please see the notes for [wMode, §5.7.2.232\(a\)](#).

- a. *The standard states that edge is a valid value for the val attribute of hMode.*

Office only saves a value of factor for the val attribute. Files opened with val equal to edge will be changed to factor on save and the val of sibling element h will be updated to reflect this mode change and correctly preserve the manual size.

2.1.1499 Part 4 Section 5.7.2.82, holeSize (Hole Size)

- a. *The standard states that the val attribute specifies that the contents of this attribute will contain a hole size between 10 and 90.*

In Office, the val attribute specifies that the contents of this attribute will contain a hole size as defined by the ST_HoleSize simple type.

- b. *The standard implies that the val attribute is optional.*

Office requires this attribute.

2.1.1500 Part 4 Section 5.7.2.83, hPercent (Height Percent)

- a. *The standard does not define the behavior when the hPercent element is omitted.*

If this element is omitted, Office uses automatic scaling. If automatic scaling is enabled, the height of the 3-D chart expressed as a percentage of the chart width shall be the ratio of plot area height to plot area width.

- b. *The standard does not specify how to interpret the hPercent element on a pie3Dchart.*

In Office, this element on a pie3DChart specifies that the thickness of the 3-D pie chart shall be the default thickness (defined by the SpreadsheetML application) multiplied by the height percent.

- c. *The standard states that the hPercent element specifies the height of a 3-D chart as a percentage of the chart width.*

In Office, this element specifies the height of a 3-D chart as a percentage of the 3-D plot area width, and disables automatic scaling for the chart height.

2.1.1501 Part 4 Section 5.7.2.84, idx (Index)

- a. *The standard places no restrictions on the val attribute beyond type information.*

Office requires that the value of the val attribute be unique amongst idx elements within the same collection.

- b. *The standard states that the values of the val attribute are defined by the XML Schema unsignedInt datatype.*

Office restricts the value of this attribute to be at most 2147483647.

2.1.1502 Part 4 Section 5.7.2.85, intercept (Intercept)

For additional notes that apply to this portion of the standard, please see the notes for [crossesAt, §5.7.2.34\(b\)](#); [custUnit, §5.7.2.36\(a\)](#); [splitPos, §5.7.2.196\(c\)](#).

2.1.1503 Part 4 Section 5.7.2.86, invertIfNegative (Invert if Negative)

- a. *The standard states that the default value of the val attribute is true.*

Office uses a default value of false for this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

- b. *The standard does not state any exceptions that cause this element to be ignored.*

Office ignores this element and always inverts the negative values if the ancestors include bubbleChart.

2.1.1504 Part 4 Section 5.7.2.88, layout (Layout)

- a. *The standard states that the manualLayout and extLst child elements both have a minOccurs=0.*

Office will not save this element if the manualLayout child element is not present when the parent element is dLbl or trendlineLbl, even if this element has an extLst child element.

2.1.1505 Part 4 Section 5.7.2.89, layoutTarget (Layout Target)

- a. *The standard states that this element can be a child of any manualLayout element.*

Office requires that the ancestors not include dispUnitsLbl, dLbl, legend, title, and trendlineLbl when this element is specified.

2.1.1506 Part 4 Section 5.7.2.92, leaderLines (Leader Lines)

- a. *The standard states that this element can be a child of any dLbIs element.*

Office requires that the value of the val attribute of sibling element showLeaderLines is true when this element is specified.

- b. *The standard states that this element can be a child of any dLbIs element.*

Office requires that the ancestor include doughnutChart, ofPieChart, pie3DChart, or pieChart when this element is specified.

2.1.1507 Part 4 Section 5.7.2.96, legendPos (Legend Position)

- a. *The standard does not state any exceptions that cause this element to be ignored.*

In Office, when this element is specified along with the manualLayout child element of the layout sibling element the exact position of the legend is overridden by the manual layout.

2.1.1508 Part 4 Section 5.7.2.97, line3DChart (3D Line Charts)

- a. *The standard states that the values of the child element axId are defined by the XML Schema unsignedInt datatype.*

In Office, child element axId has a maximum value of 2147483647.

- b. *The standard states that the maxOccurs value for the ser child element is unbounded.*

Office limits the occurrences of this element to 255.

2.1.1509 Part 4 Section 5.7.2.98, lineChart (Line Charts)

For additional notes that apply to this portion of the standard, please see the notes for [line3DChart, §5.7.2.97\(b\)](#).

2.1.1510 Part 4 Section 5.7.2.100, lvl (Level)

- a. *The standard states that the maxOccurs value for the pt child element is unbounded.*

Office limits the occurrences of this element to 2147483647; occurrences greater than 1048576 will be ignored on load and discarded on save.

2.1.1511 Part 4 Section 5.7.2.102, majorTickMark (Major Tick Mark)

- a. *The standard states that the val attribute of this element specifies the minor tick mark position.*

In Office, the val attribute of this element specifies the major tick mark position.

- b. *The standard states that the default value of the val attribute is cross.*

Office uses a default value of out for this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.1512 Part 4 Section 5.7.2.103, majorTimeUnit (Major Time Unit)

For additional notes that apply to this portion of the standard, please see the notes for [baseTimeUnit, §5.7.2.18\(a\)](#); [minorTimeUnit, §5.7.2.112\(a\)](#).

a. *The standard states the default value of the val attribute is days.*

Office uses a default value appropriate to the range of user data.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.1513 Part 4 Section 5.7.2.104, majorUnit (Major Unit)

a. *The standard states that the minimum value of the val attribute is equal to 0.*

Office requires that the value of the val attribute be greater than or equal to 1 when the parent element is dateAx.

2.1.1514 Part 4 Section 5.7.2.105, manualLayout (Manual Layout)

a. *The standard does not place any restrictions on when the attributes can be specified.*

Office requires that attributes h, w, x, and y all be specified if one is specified and the ancestors include legend or plotArea. If x or y are specified and the ancestors include dispUnitsLbl, dLbl, title, or trendlineLbl, both shall be specified.

2.1.1515 Part 4 Section 5.7.2.106, marker (Marker)

a. *The standard states this element can be a child of any ser (Line Chart Series) element.*

Office requires that the ancestors not include line3DChart when this element is specified.

2.1.1516 Part 4 Section 5.7.2.107, marker (Show Marker)

For additional notes that apply to this portion of the standard, please see the notes for [applyToEnd, §5.7.2.1\(a\)](#); [applyToFront, §5.7.2.2\(a\)](#); [applyToSides, §5.7.2.3\(a\)](#).

a. *The standard states this element is a boolean that, when true, specifies that the marker shall be shown.*

Office always ignores and does not use this element to define if markers shall be shown.

2.1.1517 Part 4 Section 5.7.2.108, max (Maximum)

For additional notes that apply to this portion of the standard, please see the notes for [crossesAt, §5.7.2.34\(b\)](#); [custUnit, §5.7.2.36\(a\)](#); [splitPos, §5.7.2.196\(c\)](#).

2.1.1518 Part 4 Section 5.7.2.109, min (Minimum)

For additional notes that apply to this portion of the standard, please see the notes for [crossesAt, §5.7.2.34\(b\)](#); [custUnit, §5.7.2.36\(a\)](#); [splitPos, §5.7.2.196\(c\)](#).

2.1.1519 Part 4 Section 5.7.2.111, minorTickMark (Minor Tick Mark)

- a. *The standard states the default value of the val attribute is cross.*

Office uses a default value of none for this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.1520 Part 4 Section 5.7.2.112, minorTimeUnit (Minor Time Unit)

For additional notes that apply to this portion of the standard, please see the notes for [baseTimeUnit, §5.7.2.18\(a\)](#); [majorTimeUnit, §5.7.2.103\(a\)](#).

- a. *The standard states that the default value of the val attribute is days.*

Office uses a default value appropriate to the range of user data.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.1521 Part 4 Section 5.7.2.113, minorUnit (Minor Unit)

- a. *The standard states that the minimum value of the val attribute is equal to 0.*

Office requires that the value of the val attribute be greater than or equal to 1 when the parent element is dateAx.

2.1.1522 Part 4 Section 5.7.2.114, minus (Minus)

- a. *The standard states that this element shall be used only when the errValType is cust.*

Office also saves out this element if the errValType is stdErr and the error bar value had been custom type during the current workbook session.

2.1.1523 Part 4 Section 5.7.2.115, multiLvlStrCache (Multi Level String Cache)

- a. *The standard states that this element specifies the last data shown on the chart for a category axis.*

In Office, this element specifies a cache of the labels on the category axis, or the x-values in a bubble or scatter chart.

2.1.1524 Part 4 Section 5.7.2.116, multiLvlStrRef (Multi Level String Reference)

- a. *The standard states that this element specifies a reference to data for the category axis with a cache of the last values used.*

In Office, this element specifies a reference to data for the category axis (or for the x-values in a bubble or scatter chart), along with a cache of the last values used.

2.1.1525 Part 4 Section 5.7.2.118, name (Pivot Name)

- a. *The standard states that this element specifies the name of the PivotTable to get the data for the chart from.*

In Office, the name of the PivotTable is defined using the following format:

[filename]sheet!pivottable

filename is the name of the SpreadsheetML file containing the PivotTable, *sheet* is the name of the worksheet containing the PivotTable, and *pivottable* is the name of the PivotTable itself. The name of the PivotTable matches the **name** attribute of the pivotTableDefinition element (" [ECMA-376] Part 4 §3.10.1.73; pivotTableDefinition (PivotTable Definition)") of the associated PivotTable.

If the name is not specified in the correct format or refers to an object that does not exist, no association between the chart and the PivotTable is made.

2.1.1526 Part 4 Section 5.7.2.119, noEndCap (No End Cap)

a. *The standard states that the default value of the val attribute is true.*

Office uses a default value of false for this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.1527 Part 4 Section 5.7.2.120, noMultiLvlLbl (No Multi-level Labels)

For additional notes that apply to this portion of the standard, please see the notes for [dateAx](#), [§5.7.2.39\(a\)](#).

a. *The standard states that the default value of the val attribute is true.*

Office uses a default value of false for this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

b. *The standard specifies on and off as valid values for the val attribute.*

Office does not consider on and off to be valid values for this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.1528 Part 4 Section 5.7.2.122, numFmt (Number Format)

a. *The standard states that the default value of the sourceLinked attribute is true.*

Office uses a default value of false for this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

b. *The standard specifies on and off as valid values for the sourceLinked attribute.*

Office does not consider on and off to be valid values for this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

c. *The standard states that the sourceLinked attribute should be respected when the parent is TrendlineLbl.*

In Office, if this element is parented by a TrendlineLbl element, the sourceLinked attribute is not used.

2.1.1529 Part 4 Section 5.7.2.125, oddFooter (Odd Footer)

- a. *The standard states that this element defines the footer to use on odd numbered pages.*

Office applies this footer to all pages if the differentOddEven attribute of the parent element equals false. Office does not apply this footer to the first page if the differentFirst attribute of the parent element equals true.

- b. *The standard states that this element is of type ST_XString.*

Office does not attempt to decode the character escape sequences defined in ST_XString.

2.1.1530 Part 4 Section 5.7.2.126, oddHeader (Odd Header)

- a. *The standard states that this element defines the header to use on odd numbered pages.*

Office applies this header to all pages if the differentOddEven attribute of the parent element equals false. Office does not apply this header to the first page if the differentFirst attribute of the parent element equals true.

- b. *The standard states that this element is of type ST_XString.*

Office does not attempt to decode the character escape sequences defined in ST_XString.

2.1.1531 Part 4 Section 5.7.2.127, ofPieChart (Pie of Pie or Bar of Pie Charts)

For additional notes that apply to this portion of the standard, please see the notes for [pie3DChart](#), §5.7.2.141(b).

- a. *The standard states that this element contains the pie of pie or bar of pie series on this chart.*

In Office, this element specifies an ofPieChart that has a primary pie chart and a secondary bar (Bar of Pie) or pie (Pie of Pie) chart. The data in the secondary chart are aggregated into an additional "Other" slice in the primary chart.

2.1.1532 Part 4 Section 5.7.2.128, ofPieType (Pie of Pie or Bar of Pie Type)

- a. *The standard implies that the val attribute is optional.*

Office requires this attribute.

2.1.1533 Part 4 Section 5.7.2.129, order (Order)

- a. *The standard states that the values of the val attribute are defined by the XML Schema unsignedInt datatype.*

Office restricts the value of this attribute to be at most 2147483647.

- b. *The standard does not have any uniqueness restrictions on the order element.*

Office requires the value of this element to be unique amongst any other order elements of the same collection containing the parent series element.

2.1.1534 Part 4 Section 5.7.2.130, order (Polynomial Trendline Order)

- a. *The standard implies that the val attribute is optional.*

Office requires this attribute.

- b. *The standard states that this element is ignored for non-polynomial trendlines.*

Office requires this element to be specified when the val attribute of trendlineType sibling element is equal to poly.

2.1.1535 Part 4 Section 5.7.2.131, orientation (Axis Orientation)

- a. *The standard states that this element specifies the stretching and stacking of the picture on the data point, series, wall, or floor.*

In Office, this element specifies whether the values on an axis are increasing or decreasing.

2.1.1536 Part 4 Section 5.7.2.132, overlap (Overlap)

- a. *The standard does not specify how bars and columns overlap.*

In Office, this element specifies how much the bars and columns of adjacent series within the same category shall overlap each other.

2.1.1537 Part 4 Section 5.7.2.133, overlay (Overlay)

- a. *The standard states that the default value of the val attribute is true.*

Office uses a default value of false for this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.1538 Part 4 Section 5.7.2.134, pageMargins (Page Margins)

- a. *The standard states that the possible values for the b attribute are defined by the XML Schema double datatype.*

Office requires the value of the b attribute to be greater than or equal to 0 and less than 49.

- b. *The standard states that the possible values for the t attribute are defined by the XML Schema double datatype.*

Office requires the value of the t attribute to be greater than or equal to 0 and less than 49.

- c. *The standard states that the possible values for the l attribute are defined by the XML Schema double datatype.*

Office requires the value of the l attribute to be greater than or equal to 0 and less than 49.

- d. *The standard states that the possible values for the r attribute are defined by the XML Schema double datatype.*

Office requires the value of the r attribute to be greater than or equal to 0 and less than 49.

- e. *The standard states that the possible values for the header attribute are defined by the XML Schema double datatype.*

Office requires the value of the header attribute to be greater than or equal to 0 and less than 49.

f. *The standard states that the possible values for the footer attribute are defined by the XML Schema double datatype.*

Office requires the value of the footer attribute to be greater than or equal to 0 and less than 49.

g. *The standard states that the header attribute specifies the header margin and the footer attribute specifies the footer margin.*

Office switches the header and footer attribute values on save, writing out the chart object's header margin to the footer attribute and vice versa.

2.1.1539 Part 4 Section 5.7.2.135, pageSetup (Page Setup)

a. *The standard states that the possible values for the firstPageNumber attribute are defined by the XML Schema unsignedInt datatype.*

In Office, the possible values for the firstPageNumber attribute are defined by the XML Schema datatype int.

b. *The standard states that the values of the paperSize attribute are defined by the XML Schema unsignedInt datatype.*

Excel restricts the value of this attribute to be at most 2147483647.

c. *The standard states that the possible values for the copies attribute are defined by the XML Schema unsignedInt datatype.*

In Office, the copies attribute has a maximum value of 2147483647.

d. *The standard states a table of values allowed for @paperSize.*

Office specifies the paper size according to the following table. Values larger than or equal to 256 specify custom printer paper sizes.

| Value | Meaning |
|--------------|--------------------------------|
| 1 | US Letter 8 1/2 x 11 in |
| 2 | US Letter Small 8 1/2 x 11 in |
| 3 | US Tabloid 11 x 17 in |
| 4 | US Ledger 17 x 11 in |
| 5 | US Legal 8 1/2 x 14 in |
| 6 | US Statement 5 1/2 x 8 1/2 in |
| 7 | US Executive 7 1/4 x 10 1/2 in |
| 8 | A3 297 x 420 mm |
| 9 | A4 210 x 297 mm |
| 10 | A4 Small 210 x 297 mm |
| 11 | A5 148 x 210 mm |
| 12 | B4 (JIS) 250 x 354 |

| Value | Meaning |
|--------------|------------------------------------|
| 13 | B5 (JIS) 182 x 257 mm |
| 14 | Folio 8 1/2 x 13 in |
| 15 | Quarto 215 x 275 mm |
| 16 | 10 x 14 in |
| 17 | 11 x 17 in |
| 18 | US Note 8 1/2 x 11 in |
| 19 | US Envelope #9 3 7/8 x 8 7/8 |
| 20 | US Envelope #10 4 1/8 x 9 1/2 |
| 21 | US Envelope #11 4 1/2 x 10 3/8 |
| 22 | US Envelope #12 4 1/2 x 11 |
| 23 | US Envelope #14 5 x 11 1/2 |
| 24 | C size sheet |
| 25 | D size sheet |
| 26 | E size sheet |
| 27 | Envelope DL 110 x 220mm |
| 28 | Envelope C5 162 x 229 mm |
| 29 | Envelope C3 324 x 458 mm |
| 30 | Envelope C4 229 x 324 mm |
| 31 | Envelope C6 114 x 162 mm |
| 32 | Envelope C65 114 x 229 mm |
| 33 | Envelope B4 250 x 353 mm |
| 34 | Envelope B5 176 x 250 mm |
| 35 | Envelope B6 176 x 125 mm |
| 36 | Envelope 110 x 230 mm |
| 37 | US Envelope Monarch 3.875 x 7.5 in |
| 38 | 6 3/4 US Envelope 3 5/8 x 6 1/2 in |
| 39 | US Std Fanfold 14 7/8 x 11 in |
| 40 | German Std Fanfold 8 1/2 x 12 in |
| 41 | German Legal Fanfold 8 1/2 x 13 in |
| 42 | B4 (ISO) 250 x 353 mm |

| Value | Meaning |
|--------------|---------------------------------------|
| 43 | Japanese Postcard 100 x 148 mm |
| 44 | 9 x 11 in |
| 45 | 10 x 11 in |
| 46 | 15 x 11 in |
| 47 | Envelope Invite 220 x 220 mm |
| 48 | RESERVED--DO NOT USE |
| 49 | RESERVED--DO NOT USE |
| 50 | US Letter Extra 9 \275 x 12 in |
| 51 | US Legal Extra 9 \275 x 15 in |
| 52 | US Tabloid Extra 11.69 x 18 in |
| 53 | A4 Extra 9.27 x 12.69 in |
| 54 | Letter Transverse 8 \275 x 11 in |
| 55 | A4 Transverse 210 x 297 mm |
| 56 | Letter Extra Transverse 9\275 x 12 in |
| 57 | SuperA/SuperA/A4 227 x 356 mm |
| 58 | SuperB/SuperB/A3 305 x 487 mm |
| 59 | US Letter Plus 8.5 x 12.69 in |
| 60 | A4 Plus 210 x 330 mm |
| 61 | A5 Transverse 148 x 210 mm |
| 62 | B5 (JIS) Transverse 182 x 257 mm |
| 63 | A3 Extra 322 x 445 mm |
| 64 | A5 Extra 174 x 235 mm |
| 65 | B5 (ISO) Extra 201 x 276 mm |
| 66 | A2 420 x 594 mm |
| 67 | A3 Transverse 297 x 420 mm |
| 68 | A3 Extra Transverse 322 x 445 mm |
| 69 | Japanese Double Postcard 200 x 148 mm |
| 70 | A6 105 x 148 mm |
| 71 | Japanese Envelope Kaku #2 |
| 72 | Japanese Envelope Kaku #3 |

| Value | Meaning |
|--------------|---|
| 73 | Japanese Envelope Chou #3 |
| 74 | Japanese Envelope Chou #4 |
| 75 | Letter Rotated 11 x 8 1/2 11 in |
| 76 | A3 Rotated 420 x 297 mm |
| 77 | A4 Rotated 297 x 210 mm |
| 78 | A5 Rotated 210 x 148 mm |
| 79 | B4 (JIS) Rotated 364 x 257 mm |
| 80 | B5 (JIS) Rotated 257 x 182 mm |
| 81 | Japanese Postcard Rotated 148 x 100 mm |
| 82 | Double Japanese Postcard Rotated 148 x 200 mm |
| 83 | A6 Rotated 148 x 105 mm |
| 84 | Japanese Envelope Kaku #2 Rotated |
| 85 | Japanese Envelope Kaku #3 Rotated |
| 86 | Japanese Envelope Chou #3 Rotated |
| 87 | Japanese Envelope Chou #4 Rotated |
| 88 | B6 (JIS) 128 x 182 mm |
| 89 | B6 (JIS) Rotated 182 x 128 mm |
| 90 | 12 x 11 in |
| 91 | Japanese Envelope You #4 |
| 92 | Japanese Envelope You #4 Rotated |
| 93 | PRC 16K 146 x 215 mm |
| 94 | PRC 32K 97 x 151 mm |
| 95 | PRC 32K(Big) 97 x 151 mm |
| 96 | PRC Envelope #1 102 x 165 mm |
| 97 | PRC Envelope #2 102 x 176 mm |
| 98 | PRC Envelope #3 125 x 176 mm |
| 99 | PRC Envelope #4 110 x 208 mm |
| 100 | PRC Envelope #5 110 x 220 mm |
| 101 | PRC Envelope #6 120 x 230 mm |
| 102 | PRC Envelope #7 160 x 230 mm |

| Value | Meaning |
|-------|---------------------------------------|
| 103 | PRC Envelope #8 120 x 309 mm |
| 104 | PRC Envelope #9 229 x 324 mm |
| 105 | PRC Envelope #10 324 x 458 mm |
| 106 | PRC 16K Rotated |
| 107 | PRC 32K Rotated |
| 108 | PRC 32K(Big) Rotated |
| 109 | PRC Envelope #1 Rotated 165 x 102 mm |
| 110 | PRC Envelope #2 Rotated 176 x 102 mm |
| 111 | PRC Envelope #3 Rotated 176 x 125 mm |
| 112 | PRC Envelope #4 Rotated 208 x 110 mm |
| 113 | PRC Envelope #5 Rotated 220 x 110 mm |
| 114 | PRC Envelope #6 Rotated 230 x 120 mm |
| 115 | PRC Envelope #7 Rotated 230 x 160 mm |
| 116 | PRC Envelope #8 Rotated 309 x 120 mm |
| 117 | PRC Envelope #9 Rotated 324 x 229 mm |
| 118 | PRC Envelope #10 Rotated 458 x 324 mm |

e. *The standard states that the useFirstPageNumber attribute specifies to use the first page number instead of automatically generating a page number.*

Office ignores this attribute and does not use the value of the firstPageNumber attribute when useFirstPageNumber is true.

2.1.1540 Part 4 Section 5.7.2.136, period (Period)

a. *The standard implies that the val attribute is optional.*

Office requires this attribute.

b. *The standard states that this element is ignored for non-moving average trendlines.*

Office requires this element to be included when the val attribute of trendlineType equals movingAvg and not otherwise.

c. *The standard states that the val attribute has a maximum value of less than or equal to 255.*

Office requires that the upper bound of @val is the number of categories on the series minus 1. If the @val is greater than the number of categories minus 1 but less than 256 the file loads and saves correctly but the trendline will not be displayed

d. *The standard states that the val attribute has a maximum value of less than or equal to 255.*

Office can save files with attribute val greater than 255 when the number of categories for the chart is greater than 256, but Office will fail to load these files.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.1541 Part 4 Section 5.7.2.137, perspective (Perspective)

a. *The standard states that this element specifies the field of view angle for the 3-D chart.*

In Office, this element specifies the field of view angle multiplied by a factor of 2 for the 3-D chart. When the val attribute is zero, the field of view angle is 0.1 degrees.

b. *The standard states that this element is ignored if Right Angle Axes is true.*

Office gives sibling element rAngAx precedence over this element when the field of view is rendered.

2.1.1542 Part 4 Section 5.7.2.139, pictureOptions (Picture Options)

a. *The standard does not specify a relationship between the pictureFormat and pictureStackUnit child elements.*

Office requires pictureStackUnit only be specified if pictureFormat is present with the val attribute equal to "stackScale", otherwise the chart will fail to load.

b. *The standard does not specify a relationship between this element and blipFill.*

Office ignores this element when a blipFill child element is not specified on the sibling spPr element.

c. *The standard does not specify special behavior for individual parents.*

Office ignores the pictureStackUnit child element when the parent of pictureOptions is the floor element.

d. *The standard states that this element is only a child of two ser parents, area and bar chart series.*

Office allows this element to be a child of all ser elements except scatter chart series.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.1543 Part 4 Section 5.7.2.141, pie3DChart (3D Pie Charts)

a. *The standard states that multiple ser elements may be specified on this element.*

Office only displays the first series if there are multiple ser child elements.

b. *The standard states that the maxOccurs value for the ser child element is unbounded.*

Office limits the occurrences of this element to 255.

2.1.1544 Part 4 Section 5.7.2.142, pieChart (Pie Charts)

For additional notes that apply to this portion of the standard, please see the notes for [pie3DChart](#), §5.7.2.141(b).

a. *The standard states that multiple ser elements may be specified on this element.*

Office only displays the first series if there are multiple series child elements.

2.1.1545 Part 4 Section 5.7.2.143, pivotFmt (Pivot Format)

- a. *The standard states that the txPr element is a valid child of the pivotFmt element.*

Office does not allow the txPr element to be a child of the pivotFmt element.

2.1.1546 Part 4 Section 5.7.2.144, pivotFmts (Pivot Formats)

- a. *The standard states that this element contains a collection of formatting bands for a surface chart indexed from low to high.*

In Office, this element is used to contain a collection of formats to be applied to a chart that is based on a PivotTable.

2.1.1547 Part 4 Section 5.7.2.145, pivotSource (Pivot Source)

- a. *The standard states that the maxOccurs value for the extLst child element is unbounded.*

Office limits the occurrences of this element to 1.

- b. *The standard states that possible values for child element fmtId are defined by type xsd:unsignedInt.*

In Office, child element fmtId has a maximum value of 2147483647.

2.1.1548 Part 4 Section 5.7.2.146, plotArea (Plot Area)

- a. *The standard states that the maxOccurs value for the choice statement including the valAx, catAx, dateAx, and serAx elements is unbounded.*

Office limits the occurrences of this choice to 4.

2.1.1549 Part 4 Section 5.7.2.147, plotVisOnly (Plot Visible Only)

- a. *The standard states that the default value of the val attribute is true.*

Office uses a default value of false for this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

- b. *The standard specifies on and off as valid values for the val attribute.*

Office does not consider on and off to be valid values for this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.1550 Part 4 Section 5.7.2.148, plus (Plus)

- a. *The standard states that this element shall be used only when the errValType is cust.*

Office also saves out this element if the errValType is stdErr and the error bar value had been custom type during the current workbook session.

2.1.1551 Part 4 Section 5.7.2.149, printSettings (Print Settings)

- a. *The standard states that the pageMargins child element is optional.*

In Office, if no child pageMargins element is defined, a pageMargins element is created with application defined values.

2.1.1552 Part 4 Section 5.7.2.150, protection (Protection)

- a. *The standard states that if the chart is on a protected worksheet or chart sheet, then these settings shall control how a user is able to interact with the chart.*

In Office, this element controls how a user is permitted to interact with the chart regardless of whether the chart is on a protected worksheet or chart sheet.

- b. *The standard states the protection element supports the child elements specified.*

Office only successfully writes out the selection child element. The other child elements have not been implemented.

2.1.1553 Part 4 Section 5.7.2.151, pt (Numeric Point)

- a. *The standard does not state uniqueness or maximum value restrictions for the idx attribute.*

Office requires that the idx attribute be unique amongst siblings and be between 0 and the total points in the parent element minus one.

- b. *The standard states that the values of the idx attribute are defined by the XML Schema unsignedInt datatype.*

Office restricts the value of this attribute to be at most 2147483647.

- c. *The standard states that the idx attribute is the index of the series in the collection.*

In Office, the idx attribute is the index of the points in the collection.

2.1.1554 Part 4 Section 5.7.2.152, pt (String Point)

- a. *The standard states that the values of the idx attribute are defined by the XML Schema unsignedInt datatype.*

Office restricts the value of this attribute to be at most 2147483647.

- b. *The standard does not state uniqueness or maximum value restrictions for the idx attribute.*

Office requires that the idx attribute be unique amongst siblings and be between 0 and the total points in the parent element minus one.

2.1.1555 Part 4 Section 5.7.2.153, ptCount (Point Count)

- a. *The standard states that the values of the val attribute are defined by the XML Schema unsignedInt datatype.*

Office restricts the value of this attribute to be at most 2147483647.

2.1.1556 Part 4 Section 5.7.2.154, radarChart (Radar Charts)

- a. *The standard states that the maxOccurs value for the ser child element is unbounded.*

Office limits the occurrences of this element to 255.

2.1.1557 Part 4 Section 5.7.2.155, radarStyle (Radar Style)

- a. *The standard implies that the val attribute is optional.*

Office requires this attribute.

2.1.1558 Part 4 Section 5.7.2.156, rAngAx (Right Angle Axes)

- a. *The standard states that the default value of the val attribute is true.*

Office uses a default value of false for this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

- b. *The standard does not describe any interplay between this element and the rotX, rotY elements.*

Office only calculates the default extrude angles with the rotX and rotY values when the rAngAx element is specified.

2.1.1559 Part 4 Section 5.7.2.157, rich (Rich Text)

- a. *The standard states that the maxOccurs value for the child element p is unbounded.*

Office limits the number of p child elements to the total character count of all p elements under rich, which can be a maximum of 255.

2.1.1560 Part 4 Section 5.7.2.158, rotX (X Rotation)

- a. *The standard states that the default value of the val attribute is 0.*

Office uses a default value of 15 for this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.1561 Part 4 Section 5.7.2.159, rotY (Y Rotation)

- a. *The standard states that the default value of the val attribute is 0.*

Office uses a default value of 20 for this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.1562 Part 4 Section 5.7.2.160, roundedCorners (Rounded Corners)

- a. *The standard states that the default value of the val attribute is true.*

Office uses a default value of false for this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.1563 Part 4 Section 5.7.2.162, scatterChart (Scatter Charts)

- a. *The standard states that the maxOccurs value for the ser child element is unbounded.*

Office limits the occurrences of this element to 255.

2.1.1564 Part 4 Section 5.7.2.163, scatterStyle (Scatter Style)

- a. *The standard states that the default value of the val attribute is marker.*

Office uses a default value of lineMarker for this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.1565 Part 4 Section 5.7.2.164, secondPiePt (Second Pie Point)

- a. *The standard states that the contents of the val attribute are interpreted based on the context of the parent element.*

In Office, the val attribute is a zero-based index into the chart's data series that must be unique amongst secondPiePt elements within the same collection.

- b. *The standard states that the values of the val attribute are defined by the XML Schema unsignedInt datatype.*

Office restricts the value of this attribute to be at most 2147483647.

2.1.1566 Part 4 Section 5.7.2.166, selection (Selection)

- a. *The standard states that the default value of the val attribute is true.*

Office uses a default value of false for this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

- b. *The standard specifies on and off as valid values for the autoPage attribute.*

In Office, on and off are not valid values for this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.1567 Part 4 Section 5.7.2.167, separator (Separator)

- a. *The standard states that the default separator is a comma.*

In Office, the default separator is region/language specific.

2.1.1568 Part 4 Section 5.7.2.168, ser (Bubble Chart Series)

- a. *The standard does not state that the smooth element is a valid child of the ser (Bubble Chart Series) element.*

Office allows the smooth element to be a child of the ser (Bubble Chart Series) element.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

b. *The standard does not state that the pictureOptions element is a valid child of the ser (Bubble Chart Series) element.*

Office allows the pictureOptions element to be a child of the ser (Bubble Chart Series) element.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

c. *The standard states that the maxOccurs value for the trendline child element is unbounded.*

Office limits the occurrences of this element to 254.

d. *The standard states that the minOccurs value for the yVal child element is 0.*

Office requires an occurrence of this element.

e. *The standard states that the maxOccurs value for the dPt child element is unbounded.*

Office limits the occurrences of this element to 32000.

2.1.1569 Part 4 Section 5.7.2.169, ser (Line Chart Series)

For additional notes that apply to this portion of the standard, please see the notes for [bubble3D, §5.7.2.19\(c\)](#).

a. *The standard does not state that the pictureOptions element is a valid child of the ser (Line Chart Series) element.*

Office allows the pictureOptions element to be a child of the ser (Line Chart Series) element.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

b. *The standard states that the maxOccurs value for the trendline child element is unbounded.*

Office limits the occurrences of this element to 254.

c. *The standard states that the maxOccurs value for the dPt child element is unbounded.*

Office limits the occurrences of this element to 4000 when inside a line3DChart and 32000 otherwise.

2.1.1570 Part 4 Section 5.7.2.170, ser (Pie Chart Series)

For additional notes that apply to this portion of the standard, please see the notes for [bubble3D, §5.7.2.19\(d\)](#).

a. *The standard does not state that the pictureOptions element is a valid child of the ser (Pie Chart Series) element.*

Office allows the pictureOptions element to be a child of the ser (Pie Chart Series) element.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

b. *The standard does not state that the smooth element is a valid child of the ser (Pie Chart Series) element.*

Office allows the smooth element to be a child of the ser (Pie Chart Series) element.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

c. *The standard states that the maxOccurs value for the dPt child element is unbounded.*

Office limits the occurrences of this element to 4000 when inside a pie3DChart element and 32000 otherwise.

2.1.1571 Part 4 Section 5.7.2.171, ser (Surface Chart Series)

For additional notes that apply to this portion of the standard, please see the notes for [bubble3D, §5.7.2.19\(e\)](#).

a. *The standard states that pictureOptions is not a child of ser (Surface Chart Series).*

Office allows pictureOptions to be a child of ser (Surface Chart Series).

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.1572 Part 4 Section 5.7.2.172, ser (Scatter Chart Series)

For additional notes that apply to this portion of the standard, please see the notes for [bubble3D, §5.7.2.19\(f\)](#); [ser, §5.7.2.168\(d\)](#).

a. *The standard states that the maxOccurs value for the trendline child element is unbounded.*

Office limits the occurrences of this element to 254.

b. *The standard states that the maxOccurs value for the dPt child element is unbounded.*

Office limits the occurrences of this element to 32000.

2.1.1573 Part 4 Section 5.7.2.173, ser (Radar Chart Series)

For additional notes that apply to this portion of the standard, please see the notes for [bubble3D, §5.7.2.19\(g\)](#).

a. *The standard does not state that the pictureOptions element is a valid child of the ser (Radar Chart Series) element.*

Office allows the pictureOptions element to be a child of the ser (Radar Chart Series) element.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

b. *The standard does not state that the smooth element is a valid child of the ser (Radar Chart Series) element.*

Office allows the smooth element to be a child of the ser Radar Chart Series) element.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

c. *The standard states that the maxOccurs value for the dPt child element is unbounded.*

Office limits the occurrences of this element to 32000.

2.1.1574 Part 4 Section 5.7.2.174, ser (Area Chart Series)

For additional notes that apply to this portion of the standard, please see the notes for [bubble3D, §5.7.2.19\(b\)](#).

a. *The standard does not state that the smooth element is a valid child of the ser (Area Chart) element.*

Office allows the smooth element to be a child of the ser (Area Chart) element.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

b. *The standard states that the maxOccurs value for the trendline child element is unbounded.*

Office limits the occurrences of this element to 254.

c. *The standard states that the minOccurs value for the val child element is 0.*

Office requires an occurrence of this element.

d. *The standard states that the maxOccurs value for the dPt child element is unbounded.*

Office limits the occurrences of this element to 4000 when inside an area3DChart and 32000 otherwise.

2.1.1575 Part 4 Section 5.7.2.175, ser (Bar Chart Series)

For additional notes that apply to this portion of the standard, please see the notes for [bubble3D, §5.7.2.19\(h\)](#).

a. *The standard does not state that the smooth element is a valid child of the ser (Bar Chart Series) element.*

Office allows the smooth element to be a child of the ser (Bar Chart Series) element.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

b. *The standard states that the maxOccurs value for the trendline child element is unbounded.*

Office limits the occurrences of this element to 254.

c. *The standard states that the maxOccurs value for the dPt child element is unbounded.*

Office limits the occurrences of this element to 4000 when inside a bar3DChart and 32000 otherwise.

2.1.1576 Part 4 Section 5.7.2.176, serAx (Series Axis)

a. *The standard does not place any restrictions on the val attribute of the axId element.*

Office requires that the val attribute of the axId element match the val attribute of an axId element in the parent chart.

b. *The standard does not state any exceptions that cause the numFmt child element to be ignored.*

Office ignores the numFmt child element but will load and save the element.

2.1.1577 Part 4 Section 5.7.2.177, serLines (Series Lines)

a. *The standard states that this element specifies series lines for the chart.*

In Office, if the parent is `barChart`, the series lines connect the top of adjacent data points within the same series; if the parent is `ofPieChart`, the series lines connect the secondary pie or column to the other slice.

b. *The standard states that this element can be a child of any `barChart` element.*

Office requires that the `val` attribute of sibling element grouping equal `percentStacked` or `stacked` when this element is specified.

2.1.1578 Part 4 Section 5.7.2.178, `shape` (Shape)

a. *The standard states that this element specifies the shape of a series or a 3-D bar chart.*

In Office, this element specifies the default series shape when this element is a child of `bar3DChart`.

b. *The standard does not place any restrictions on when this element can be a child of `ser`.*

Office requires that the ancestor include `bar3DChart` when this element is a child of `ser`.

2.1.1579 Part 4 Section 5.7.2.179, `showBubbleSize` (Show Bubble Size)

a. *The standard states that the default value of the `val` attribute is `true`.*

Office uses a default value of `false` for this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

b. *The standard states that this element can be a child of any `dLbl` or `dLbIs` element.*

Office requires that the ancestor include `bubbleChart` when this element is specified.

2.1.1580 Part 4 Section 5.7.2.180, `showCatName` (Show Category Name)

a. *The standard states that the default value of the `val` attribute is `true`.*

Office uses a default value of `false` for this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.1581 Part 4 Section 5.7.2.181, `showDLbIsOverMax` (Show Data Labels over Maximum)

a. *The standard states that the default value of the `val` attribute is `true`.*

Office uses a default value of `false` for this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

b. *The standard states that this element specifies that data labels over the maximum of the chart shall be shown.*

In Office, this element specifies that data labels with data whose value is over the axis maximum or under the axis minimum shall be shown.

2.1.1582 Part 4 Section 5.7.2.182, `showHorzBorder` (Show Horizontal Border)

a. *The standard states that the default value of the `val` attribute is `true`.*

Office uses a default value of false for this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

b. *The standard specifies on and off as valid values for the val attribute.*

Office does not consider on and off to be valid values for this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.1583 Part 4 Section 5.7.2.183, showKeys (Show Legend Keys)

a. *The standard states that the default value of the val attribute is true.*

Office uses a default value of false for this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.1584 Part 4 Section 5.7.2.184, showLeaderLines (Show Leader Lines)

a. *The standard states that the default value of the val attribute is true.*

Office uses a default value of false for this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

b. *The standard states that this element can be a child of any dLbIs element.*

Office requires that the ancestor include doughnutChart, ofPieChart, pie3DChart, or pieChart when this element is specified.

c. *The standard states that this element can be a child of any dLbIs element.*

Office requires that the val attribute equals true on one or more of the showCatName, showSerName, showVal, or showPercent sibling elements when this element is specified.

2.1.1585 Part 4 Section 5.7.2.185, showLegendKey (Show Legend Key)

a. *The standard states that the default value of the val attribute is true.*

Office uses a default value of false for this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

b. *The standard does not specify what occurs when legend keys are shown in the data label.*

In Office, this element specifies if legend keys shall be shown in the data label(s) indicated by the parent element. The data label legend key has the same formatting as that of the corresponding data's legend key in the chart legend.

c. *The standard does not specify a relationship between sibling elements.*

Office only displays the legend key when that val attribute equals true on one or more of the showBubbleSize, showCatName, showSerName, showVal, or showPercent sibling elements or dLbI contains a sibling tx element.

2.1.1586 Part 4 Section 5.7.2.186, showNegBubbles (Show Negative Bubbles)

a. *The standard states that the default value of the val attribute is true.*

Office uses a default value of false for this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

b. *The standard specifies on and off as valid values for the val attribute.*

Office does not consider on and off to be valid values for this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.1587 Part 4 Section 5.7.2.187, showOutline (Show Outline Border)

a. *The standard states that the default value of the val attribute is true.*

Office uses a default value of false for this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

b. *The standard specifies on and off as valid values for the val attribute.*

Office does not consider on and off to be valid values for this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.1588 Part 4 Section 5.7.2.188, showPercent (Show Percent)

a. *The standard states that this element can be a child of any dLbl or dLbIs element.*

Office requires that the ancestor include doughnutChart, ofPieChart, pie3DChart, or pieChart when this element is specified.

b. *The standard states that the default value of the val attribute is true.*

Office uses a default value of false for this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.1589 Part 4 Section 5.7.2.189, showSerName (Show Series Name)

a. *The standard states that the default value of the val attribute is true.*

Office uses a default value of false for this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.1590 Part 4 Section 5.7.2.190, showVal (Show Value)

a. *The standard states that the default value of the val attribute is true.*

Office uses a default value of false for this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.1591 Part 4 Section 5.7.2.191, showVertBorder (Show Vertical Border)

- a. *The standard states that the default value of the val attribute is true.*

Office uses a default value of false for this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.1592 Part 4 Section 5.7.2.192, sideWall (Side Wall)

- a. *The standard states that this element can be a child of any chart element.*

Office requires that the chart contain a 3D chart group (bar3DChart, line3DChart, area3DChart, surface3DChart, or pie3DChart) when this element is specified.

2.1.1593 Part 4 Section 5.7.2.195, smooth (Smoothing)

For additional notes that apply to this portion of the standard, please see the notes for [ser, §5.7.2.168\(a\)](#).

- a. *The standard states that the default value of the val attribute is true.*

Office uses a default value of false for this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

- b. *The standard specifies on and off as valid values for the smooth attribute.*

In Office, on and off are not valid values for this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.1594 Part 4 Section 5.7.2.196, splitPos (Split Position)

For additional notes that apply to this portion of the standard, please see the notes for [crossesAt, §5.7.2.34\(b\)](#); [custUnit, §5.7.2.36\(a\)](#).

- a. *The standard does not state any interplay between sibling element splitType and the val attribute.*

In Office, if splitType is equal to pos, the value of the val attribute shall be an integer in the range of 0 to 32000, inclusive. If splitType is equal to percent, the value shall be in the range of 0.0 to 100.0, inclusive.

- b. *The standard states that this element can be a child of any ofPieChart element.*

Office requires that the ofPieChart parent contain a splitType element with a val attribute equal to percent, pos, or val when this element is specified.

- c. *The standard states that attribute val is of type xsd:double.*

Office does not allow INF, -INF, and NaN as supported values.

2.1.1595 Part 4 Section 5.7.2.197, splitType (Split Type)

- a. *The standard implies that the val attribute is optional.*

Office requires this attribute.

b. *The standard does not define the behavior when this element is omitted.*

In Office, if this element is not specified the default behavior is to split by position with a split position value equal to the number of data points in the series divided by 3, rounded up.

2.1.1596 Part 4 Section 5.7.2.198, spPr (Shape Properties)

For additional notes that apply to this portion of the standard, please see the notes for [spPr, §5.6.2.29\(a-c\)](#).

a. *The standard states grpFill can be a child of the spPr element.*

Office does not allow grpFill to be a child of spPr.

b. *The standard states scene3D is not a supported child of the spPr element.*

Office allows scene3D to be a child of spPr.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

c. *The standard states blipFill, gradFill, grpFill, noFill, patFill, and solidFill can be a child of any spPr element.*

Office does not persist the *Fill child elements if the parent element is dropLines, hiLowLines, leaderLines, majorGridlines, minorGridlines, ser (line, scatter, or radar with radarStyle not equal to filled), or trendline.

d. *The standard states effectDag and effectLst can be a child of any spPr element.*

Office does not persist the effectDag and effectLst child elements if the parent element is leaderLines.

e. *The standard does not specify parent elements of spPr that do not persist the scene3d child element.*

Office does not persist the scene3d child element if the parent element is *Ax, dropLines, dTable, hiLowLines, leaderLines, majorGridLines, minorGridlines, ser (line, scatter, or radar with radarStyle not equal to filled), seriesLines, or trendline.

f. *The standard states sp3d can be a child of any spPr element.*

Office does not persist the sp3d child element if the parent element is *Ax, dropLines, dTable, hiLowLines, leaderLines, majorGridLines, minorGridlines, ser (line, scatter, or radar with radarStyle not equal to filled), seriesLines, or trendline.

2.1.1597 Part 4 Section 5.7.2.199, stockChart (Stock Charts)

a. *The standard does not state that the varyColors element is a valid child of the stockChart element.*

Office allows the varyColors element to be a child of the stockChart element.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.1598 Part 4 Section 5.7.2.203, style (Style)

a. *The standard states that the val attribute is required.*

Office treats this attribute as optional, giving it a default value of 2.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.1599 Part 4 Section 5.7.2.204, surface3DChart (3D Surface Charts)

a. *The standard states that the maxOccurs value for the ser child element is unbounded.*

Office limits the occurrences of this element to 255.

b. *The standard does not state that the varyColors element is a valid child of the surface3DChart element.*

Office allows the varyColors element to be a child of the surface3DChart element; the child element will, however, be ignored.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.1600 Part 4 Section 5.7.2.205, surfaceChart (Surface Charts)

For additional notes that apply to this portion of the standard, please see the notes for [surface3DChart, §5.7.2.204\(a, b\)](#).

a. *The standard states that varyColors is not a child of surfaceChart.*

Office allows varyColors to be saved as child of surfaceChart, but ignores it on load.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.1601 Part 4 Section 5.7.2.207, thickness (Thickness)

a. *The standard states that the values of the val attribute are defined by the XML Schema unsignedInt datatype.*

Office restricts the value of this attribute to be at most 100.

b. *The standard states that the val attribute is required.*

Office treats this attribute as optional, giving it a default of 0.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

c. *The standard states that thickness is a percentage of the largest dimension of the plot volume.*

In Office, thickness is a percentage of the smaller of the height and width of the 3D chart. The height of the 3D chart relative to the width is specified by hPercent.

2.1.1602 Part 4 Section 5.7.2.209, tickLblSkip (Tick Label Skip)

a. *The standard states that this element specifies how many tick labels to skip between label that is drawn.*

In Office, this element specifies the interval at which tick labels are drawn.

2.1.1603 Part 4 Section 5.7.2.210, tickMarkSkip (Tick Mark Skip)

- a. *The standard states that this element specifies how many tick marks shall be skipped before the next one shall be drawn.*

In Office, this element specifies the interval at which tick marks are drawn.

2.1.1604 Part 4 Section 5.7.2.211, title (Title)

- a. *The standard describes the tx child element as optional but does not state default value.*

In Office, the default text in the title is a localized string specific to the parent element type, except when this element is the child of a chart that has a single series with a name, in which case the text shall be that series' name.

2.1.1605 Part 4 Section 5.7.2.212, trendline (Trendlines)

- a. *The standard states that this element can be a child of ser elements.*

Office requires that when this element is specified, the ancestor include an areaChart or lineChart with the grouping element equal to standard, a barChart with grouping element equal to clustered, or a bubbleChart, scatterChart or stockChart.

2.1.1606 Part 4 Section 5.7.2.213, trendlineLbl (Trendline Label)

- a. *The standard does not fully specify the trendlineLbl element.*

Office interprets this element to specify the formatting of the trendline label which annotates the parent trendline. The default text is determined by the dispEq and dispRSqr sibling elements.

- b. *The standard does not state additional restrictions on when a trendline label is displayed.*

Office does not display the trendline label if the val attribute of sibling element trendlineType is equal to movingAvg.

- c. *The standard does not define the trendline label contents.*

Office displays the text specified by the tx child element when tx element exists on the trendlineLbl, replacing the text generated by the dispEq and dispRSqr sibling elements.

- d. *The standard states that this element can be a child of any trendline element.*

In Office, this element shall only be specified if sibling element dispEq or dispRSqr is true.

2.1.1607 Part 4 Section 5.7.2.214, trendlineType (Trendline Type)

- a. *The standard implies that the val attribute is optional.*

Office requires this attribute.

2.1.1608 Part 4 Section 5.7.2.215, tx (Chart Text)

- a. *The standard states that strLit is not a child of the tx element.*

Office saves strLit as a child of this element when a label is selected and '=' is entered into the formula bar.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.1609 Part 4 Section 5.7.2.216, tx (Series Text)

- a. *The standard does not define the behavior when the tx element is omitted.*

If the tx element is omitted, Office uses a default text of the localized version of string "Series#", where # is the value of the idx for the corresponding series + 1.

2.1.1610 Part 4 Section 5.7.2.217, txPr (Text Properties)

For additional notes that apply to this portion of the standard, please see the notes for [pivotFmt](#), §5.7.2.143(a).

- a. *The standard does not state any exceptions that cause this element to be ignored.*

Office ignores this element on load and removes this element on save if the tx sibling element contains a rich child element.

- b. *The standard states that the maxOccurs for child element p is unbounded.*

Office ignores all but the first p child elements on load and only saves the first p child element.

2.1.1611 Part 4 Section 5.7.2.220, userInterface (User Interface)

- a. *The standard specifies on and off as valid values for the val attribute.*

Office does not consider on and off to be valid values for this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

- b. *The standard states that when this element is true, protection applies to the user interface only.*

Office always applies protection to the user interface when this element is present, regardless of the value the val attribute.

- c. *The standard states that this element specifies that the protection applies to the user interface only, and not to changes made through the object model.*

Office does not provide a way to set this property or save a file with this element. On load this element is treated as specifying standard protection.

- d. *The standard states that the default value of the val attribute is true.*

Office uses a default value of false for this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.1612 Part 4 Section 5.7.2.224, v (Numeric Value)

- a. *The standard states that the values of the val attribute are defined by the ST_Xstring simple type.*

Office restricts the string values of this attribute to be a double, an integer, or the value #N/A.

2.1.1613 Part 4 Section 5.7.2.226, val (Error Bar Value)

For additional notes that apply to this portion of the standard, please see the notes for [crossesAt, §5.7.2.34\(b\)](#); [custUnit, §5.7.2.36\(a\)](#); [splitPos, §5.7.2.196\(c\)](#).

- a. *The standard does not state any exceptions that cause this element to be ignored.*

Office ignores this element if the val attribute of sibling element errBarType is equal to stdErr.

2.1.1614 Part 4 Section 5.7.2.227, valAx (Value Axis)

- a. *The standard does place any restrictions on the val attribute of the axId child element.*

Office requires that the val attribute of the axId child element match the val attribute of an axId element in the parent chart.

- b. *The standard does place any restrictions on the val attribute of the crossAx child element.*

Office requires that the val attribute of the crossAx child element matches the val attribute of an axId element in the parent chart.

2.1.1615 Part 4 Section 5.7.2.228, varyColors (Vary Colors by Point)

For additional notes that apply to this portion of the standard, please see the notes for [stockChart, §5.7.2.199\(a\)](#).

- a. *The standard states that the default value of the val attribute is true.*

Office uses a default value of false for this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

- b. *The standard specifies on and off as valid values for the val attribute.*

Office does not consider on and off to be valid values for this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

- c. *The standard states that each point shall have a different color.*

In Office, this element also specifies that marker types shall vary by point.

- d. *The standard states that each data marker in the series shall have a different color.*

In Office, this element specifies that each data point, marker, and slice in the series shall vary by color.

- e. *The standard states that parent elements include area3DChart, areaChart, stockChart, and radarChart.*

Office ignores this element and does not vary colors by point when the parent is area3DChart, areaChart, or stockChart or when the parent is radarChart with the val attribute of sibling element radarStyle set to filled.

- f. *The standard does not state any exceptions as to when the vary colors by point is applied.*

Office ignores this element and does not vary colors by point when multiple series are specified on the chart.

2.1.1616 Part 4 Section 5.7.2.229, view3D (View In 3D)

- a. *The standard states view3D is a child of any chart element.*

In Office, view3D applies when the descendants of the parent chart include area3DChart, bar3DChart, line3DChart, pie3DChart, surface3DChart, or surfaceChart.

2.1.1617 Part 4 Section 5.7.2.230, w (Width)

For additional notes that apply to this portion of the standard, please see the notes for [crossesAt, §5.7.2.34\(b\)](#); [custUnit, §5.7.2.36\(a\)](#); [splitPos, §5.7.2.196\(c\)](#).

- a. *The standard does not state any exceptions that cause this element to be ignored.*

Office ignores this element when a descendant of dispUnitsLbl, dLbl, title, or trendline and instead fits the element to the size of the text.

- b. *The standard does not state any exceptions that cause this element to be ignored or interpreted differently.*

Office ignores this element and the parent element manualLayout if the val attribute is greater than 1 or less than 0. Instead, the parent of manualLayout shall use its default size and position.

2.1.1618 Part 4 Section 5.7.2.231, wireframe (Wireframe)

- a. *The standard states that the default value of the val attribute is true.*

Office uses a default value of false for this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

- b. *The standard specifies on and off as valid values for the val attribute.*

Office does not consider on and off to be valid values for this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.1619 Part 4 Section 5.7.2.232, wMode (Width Mode)

- a. *The standard states the val attribute specifies the layout mode for the width.*

In Office, the val attribute specifies the layout mode for the parent element.

- b. *The standard states that edge is a valid value of the val attribute for wMode.*

Office only saves a val of factor. Files opened with val equal to edge will be changed to factor on save and the val of sibling element w will be updated to reflect this mode change and correctly preserve the manual size.

2.1.1620 Part 4 Section 5.7.2.233, x (Left)

For additional notes that apply to this portion of the standard, please see the notes for [crossesAt, §5.7.2.34\(b\)](#); [custUnit, §5.7.2.36\(a\)](#); [splitPos, §5.7.2.196\(c\)](#).

- a. *The standard does not state any exceptions that cause this element to be ignored or interpreted differently.*

Office ignores this element and parent manualLayout if val is greater than 1, less than 0 when the val of sibling xMode equals edge, or less than -1 when the val of sibling xMode equals factor, Instead, default size and position are used.

b. *The standard does not state any exceptions that cause this element to be ignored or interpreted differently.*

Office places the element inside the chart at the point closest to the location specified while still retaining the specified width if val is in the allowed range but the specified width and location would place the element outside the chart.

2.1.1621 Part 4 Section 5.7.2.234, xMode (Left Mode)

For additional notes that apply to this portion of the standard, please see the notes for [wMode, §5.7.2.232\(a\)](#).

a. *The standard states that factor is a valid value of the val attribute for xMode.*

Office only saves a val of edge, changing files with factor on save and updating x to reflect this change and preserve the position. This may result in the manualLayout being ignored on subsequent loads if val of x is >1 or <0 after conversion.

2.1.1622 Part 4 Section 5.7.2.236, y (Top)

For additional notes that apply to this portion of the standard, please see the notes for [crossesAt, §5.7.2.34\(b\)](#); [custUnit, §5.7.2.36\(a\)](#); [splitPos, §5.7.2.196\(c\)](#).

a. *The standard does not state any exceptions that cause this element to be ignored or interpreted differently.*

Office places the element inside the chart at the point closest to the location specified while still retaining the specified height if val is in the allowed range but the specified height and location would place the element outside the chart.

b. *The standard does not state any exceptions that cause this element to be ignored or interpreted differently.*

Office ignores this element and parent manualLayout if val is greater than 1, less than 0 when the val of sibling yMode equals edge, or less than -1 when the val of sibling yMode equals factor, Instead, default size and position are used.

2.1.1623 Part 4 Section 5.7.2.237, yMode (Top Mode)

For additional notes that apply to this portion of the standard, please see the notes for [wMode, §5.7.2.232\(a\)](#).

a. *The standard states that factor is a valid value of the val attribute for yMode.*

Office only saves a val of edge, changing files with factor on save and updating y to reflect this change and preserve the position. This may result in the manualLayout being ignored on subsequent loads if val of y is > 1 or < 0 after conversion.

2.1.1624 Part 4 Section 5.7.3.1, ST_AxisUnit (Axis Unit)

a. *The standard states that the contents of the ST_AxisUnit simple type are a restriction on the XML Schema double datatype, with a minimum value of greater than 0.*

Office does not allow the values of INF, -INF, or NaN.

2.1.1625 Part 4 Section 5.7.3.3, ST_BarDir (Bar Direction)

a. *The standard states that each enumeration specifies that if the chart is a bar or column chart, the data markers are horizontal or vertical rectangles, respectively.*

Office interprets each enumeration to specify that if the chart is a bar or column chart, the data markers are horizontally or vertically oriented. For 2D charts these are rectangles. For 3D charts, the shape is specified by the shape element.

2.1.1626 Part 4 Section 5.7.3.4, ST_BarGrouping (Bar Grouping)

a. *The standard states that the enumeration value standard specifies that the chart series are drawn next to each other on the depth axis.*

In Office, the data markers for each category are drawn in clusters containing one marker from each series. The markers in each cluster are lined up on the depth axis in a 3D chart. On 2d charts this behaves as clustered

2.1.1627 Part 4 Section 5.7.3.6, ST_BuiltInUnit (Built-In Unit)

a. *The standard states that the trillions enumeration value specifies that the values on the chart shall be divided by 1,000,000,000.*

In Office, the trillions enumeration value specifies that the values on the chart shall be divided by 1,000,000,000,000.

2.1.1628 Part 4 Section 5.7.3.8, ST_Crosses (Crosses)

a. *The standard states that the autoZero value specifies that the category axis crosses at the zero point of the value axis (if possible), or the minimum value (if the minimum is greater than zero) or the maximum (if the maximum is less than zero).*

Office uses this value to specify that one axis crosses the other at the zero point, if a zero point exists; at the minimum value, if the minimum is greater than 0 or the axis is not numerical; or at the maximum value, if the maximum is less than 0.

2.1.1629 Part 4 Section 5.7.3.9, ST_DepthPercent (Depth Percent)

a. *The standard states the ST_DepthPercent simple type has a minimum value of greater than or equal to 1.*

Office saves but does not load values that are less than 20.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.1630 Part 4 Section 5.7.3.14, ST_ErrValType (Error Value Type)

a. *The standard states that the enumeration value stdDev specifies that the length of the error bars shall be Error Bar Value standard deviations of the data.*

In Office, the enumeration value stdDev specifies that the length of the error bars shall be the standard deviation for each data point and then multiplied by the val (Error Bar Value).

2.1.1631 Part 4 Section 5.7.3.17, ST_Grouping (Grouping)

a. *The standard states that the ST_Grouping simple type specifies the possible groupings for a bar chart.*

Office uses this simple type to specify the possible methods for grouping the data series on a chart.

2.1.1632 Part 4 Section 5.7.3.18, ST_HoleSize (Hole Size)

a. *The standard states that the ST_HoleSize simple type has a minimum value of greater than or equal to 10.*

Office defines this simple type to have a minimum value of greater than or equal to 1.

2.1.1633 Part 4 Section 5.7.3.20, ST_LayoutMode (Layout Mode)

a. *The standard defines edge as "Specifies that the Width or Height shall be interpreted as the Right or Bottom of the chart element".*

Office additionally specifies the following behaviors for the edge attribute:

For **hMode/wMode** element, the **edge** attribute specifies that the value of sibling element **h** ("[ECMA-376](#) Part 4 §5.7.2.78; h (Height)") / **w** ("[ECMA-376](#) Part 4 §5.7.2.230; w (Width)") is interpreted as the distance to the bottom/right edge of the chart element from the top/left edge of the chart as a percentage of the chart height/width.

For **xMode/yMode** element, the **edge** attribute specifies that the value of sibling element **x** ("[ECMA-376](#) Part 4 §5.7.2.233; x (Left)") / **y** ("[ECMA-376](#) Part 4 §5.7.2.236; y (Top)") is interpreted as the distance to the left/top edge of the chart element from the left/top edge of the chart as a percentage of the chart width/height.

b. *The standard defines factor as "Specifies that the Width or Height shall be interpreted as the Width or Height of the chart element".*

Office additionally specifies the following behaviors for the factor attribute:

For **hMode/wMode** element, the **factor** attribute specifies that the value of sibling element **h** ("[ECMA-376](#) Part 4 §5.7.2.78; h (Height)") / **w** ("[ECMA-376](#) Part 4 §5.7.2.230; w (Width)") is interpreted as the height/width of the chart element as a percentage of the chart height/width.

For **xMode/yMode** element, the **factor** attribute specifies that the value of sibling element **x** ("[ECMA-376](#) Part 4 §5.7.2.233; x (Left)") / **y** ("[ECMA-376](#) Part 4 §5.7.2.236; y (Top)") is interpreted as the distance to the left/top edge of the chart element from the left/top edge of default position of the chart element as a percentage of the chart width/height.

2.1.1634 Part 4 Section 5.7.3.27, ST_MarkerStyle (Marker Style)

a. *The standard does not specify auto as a valid enumeration value.*

Office allows auto as an enumeration value that specifies that the marker style shall be determined by the application.

2.1.1635 Part 4 Section 5.7.3.30, ST_Orientation (Orientation)

a. *The standard states that the ST_Orientation simple type specifies the possible ways to place a picture on a data point, series, wall, or floor.*

Office uses this simple type to specify whether the values on an axis are increasing or decreasing.

2.1.1636 Part 4 Section 5.7.3.33, ST_Period (Period)

a. *The standard states that the contents of the ST_Period simple type are a restriction on the XML Schema unsignedByte datatype, ranging from 2 to 255.*

Excel defines this simple type as being a restriction on the XML Schema unsignedInt datatype, with a minimum value of 2 and an unbounded maximum value.

2.1.1637 Part 4 Section 5.7.3.34, ST_Perspective (Perspective)

a. *The standard states that the ST_Perspective simple type specifies an integer between 0 and 100 whose contents are a percentage.*

Office uses this simple type to specify an integer between 0 and 240, inclusive, whose contents are a measurement in degrees.

2.1.1638 Part 4 Section 5.7.3.35, ST_PictureFormat (Picture Format)

a. *The standard states that the stretch enumeration value specifies that the picture shall be anisotropic stretched to fill the data point, series, wall or floor.*

Office does not use anisotropic stretch when stretching the picture fill.

2.1.1639 Part 4 Section 5.7.3.36, ST_PictureStackUnit (Picture Stack Unit)

a. *The standard states that the ST_PictureStackUnit simple type has a minimum value of greater than 0.*

Office defines this simple type to have a minimum value of greater than or equal to 0.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.1640 Part 4 Section 5.7.3.37, ST_RadarStyle (Radar Style)

a. *The standard does not state that the styles specified by the ST_RadarStyle simple type can be overridden.*

Office allows these styles to be overridden by the line and marker settings on the individual data series in the chart.

2.1.1641 Part 4 Section 5.7.3.40, ST_ScatterStyle (Scatter Style)

a. *The standard states that none is a valid enumeration value.*

Office does not allow this enumeration value. If this enumeration value is present the file will fail to load.

b. *The standard states that the smooth enumeration value specifies that the points on the scatter chart shall be connected with smoothed lines and markers shall not be drawn.*

Office treats this enumeration as if it were smoothMarker on load. Office will never save out this enumeration, instead using smoothMarker and specifying that no markers are to be drawn.

c. *The standard states that the line enumeration value specifies the points on the scatter chart shall be connected with straight lines but markers shall not be drawn.*

Office treats this enumeration as if it were lineMarker on load. Office will never save out this enumeration, instead using lineMarker and specifying that no markers are to be drawn.

d. *The standard states that the marker enumeration value specifies the points on the scatter chart shall not be connected with lines and markers shall be drawn.*

Office treats this enumeration as if it were lineMarker on load. Office will never save out this enumeration, instead using lineMarker and specifying that no lines are to be drawn.

e. *The standard does not state any exceptions that cause the ST_ScatterStyle to be overridden.*

In Office, scatter chart styles can be overridden by line and marker settings on the individual data series in the chart.

2.1.1642 Part 4 Section 5.7.3.42, ST_Shape (Shape)

a. *The standard states that the pyramidToMax enumeration value specifies the chart shall be drawn with truncated cones such that the point of the cone would be the maximum data value.*

In Office, pyramidToMax specifies that the chart shall be drawn as truncated rectangular pyramids such that the point of the pyramid would be at the highest value in the chart. The pyramid is truncated at the data marker's value.

b. *The standard states that coneToMax enumeration value specifies that the chart shall be drawn with truncated cones such that the point of the cone would be the maximum data value.*

In Office, coneToMax to specifies that the chart shall be drawn as truncated cones, such that the point of the cone would be at the highest value in the chart. The cone is truncated at the data marker's value.

2.1.1643 Part 4 Section 5.7.3.44, ST_Skip (Skip)

a. *The standard states that the contents of the ST_Skip simple type are a restriction of the XML Schema unsignedShort datatype.*

Office defines this simple type as being a restriction on the XML Schema int datatype.

2.1.1644 Part 4 Section 5.7.3.45, ST_SplitType (Split Type)

a. *The standard states that auto is a valid enumeration value.*

Office does not allow the auto enumeration value.

2.1.1645 Part 4 Section 5.7.3.46, ST_Style (Style)

a. *The standard states that the default font size for the title is always 120% the font size of the chart and that if the chart does not have a font size set, then the default font size is 10.*

In Office, the default font size of the chart is 120% the font size of the chart. If the chart does not have a font size set, then the default font size of the chart is 10 points and the default font size of the title is 18 points.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

b. *The standard states that the default value in Table 2, Axis & Major Gridlines, Style 1-32, is tx1.*

In Office, the default value is 75% tint of tx1.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

c. *The standard states that the default value in Table 2, Axis & Major Gridlines, Style 33-48, is dk1.*

In Office, the default value is 75% tint of dk1.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

d. *The standard states that the default value in Table 2, Minor Gridlines, Style 33-40, is 50% tint of tx1.*

In Office, the default value is 50% tint of dk1.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

e. *The standard states that the default value in Table 2, Minor Gridlines, Style 41-48, is 90% tint of tx1.*

In Office, the default value is 90% tint of dk1.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

f. *The standard states that the default value in Table 2, Other Lines, Style 35-40, is 25% shade of dk1.*

In Office, the default value is dk1.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

g. *The standard states that the default value in Table 3, Floor, Walls & Plot Area (2-D), Style 35-40, is accent1-6.*

In Office, the default value is 20% tint of accent1-6.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

h. *The standard makes an unclear reference to accent1-6 in Table 3.*

In Office, the color listed as accent1-6 means that the first style uses accent1, the next uses accent2, up to the sixth, which uses accent6.

i. *The standard does not specify the color of the effect in Tables 4 and 5.*

In Office, if the style has an effect applied, the color of the effect is dk1.

j. *The standard states that the default value in Table 6, Data Point 1, Pattern 1 is 88.5% tint of dk1 and Data Point 4, Pattern 1 is 92.5% tint of dk1.*

In Office, the default values are 88% and 92% for Data Point 1 and Data Point 4, respectively.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

k. *The standard states that the default Line Color in Table 5, Fills for Data Points (2-D and 3-D), style 33 is 50% shade of dk1.*

In Office, the default value is 92% tint of dk1.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.1646 Part 4 Section 5.7.3.51, ST_TrendlineType (Trendline Type)

a. *The standard states that the exp enumeration value specifies the trendline shall be an exponential curve in the form $y=ab^x$.*

In Office, this enumeration value specifies that the trendline shall be an exponential curve in the form $y=ae^{(bx)}$.

2.1.1647 Part 4 Section 5.7.3.52, ST_Xstring (String With Encoded Characters)

a. *The standard places no restrictions on the characters that can be escaped in the contents of the ST_Xstring simple type.*

Office does not allow the newline (0x000A) or tab (0x0009) characters to be escaped in this simple type's contents.

2.1.1648 Part 4 Section 5.8.2.1, absSizeAnchor (Absolute Anchor Shape Size)

a. *The standard states that the from element specifies the top left corner of the shape bounding box in a RTL (right to left) implementation. The ext element specifies the bottom right corner of the shape bounding box in a RTL implementation.*

In Office, the from element specifies the top left corner relative to the chart and the ext element specifies the size of the shape in EMUs.

2.1.1649 Part 4 Section 5.8.2.2, blipFill (Picture Fill)

a. *The standard allows the dpi attribute to be used with this element.*

The dpi attribute is not supported by Office.

2.1.1650 Part 4 Section 5.8.2.7, cNvPr (Non-Visual Drawing Properties)

a. *The standard implies that hyperlinks can be used on objects inside of charts.*

PowerPoint does not support hyperlinks in objects inside charts.

2.1.1651 Part 4 Section 5.8.2.9, cxnSp (Connection Shape)

a. *The standard states that cxnSp connects two sp elements.*

In Office, cxnSp connects two sp or pic elements.

b. *The standard states that the values of the macro attribute are defined by the XML Schema string datatype.*

Office requires that the macro attribute value follow the same grammar as name-references ("[ECMA-376](#) Part 4 §3.17.2.5; Names") with a minimum length of 0 characters and a maximum length of 256 characters.

2.1.1652 Part 4 Section 5.8.2.10, ext (Shape Extent)

- a. *The standard inverts the terms width and height when describing attributes cx and cy.*

In Office, the cx attribute represents the extent width (horizontal size) and the cy attribute represents the extent height (vertical size).

- b. *The standard allows the value of attributes cx and cy to be zero.*

If the value of either the cx or cy attribute is zero, Office will ignore it and use the object transform (xfrm). If the object transform is also invalid, the object will not be shown.

2.1.1653 Part 4 Section 5.8.2.12, graphicFrame (Graphic Frame)

- a. *The standard allows a graphicFrame to be specified within a Chart Drawing.*

Office does not support the display of graphic frames inside charts.

- b. *The standard states that the values of the macro attribute are defined by the XML Schema string datatype.*

Office requires that the macro attribute value follow the same grammar as name-references ("ECMA-376 Part 4 §3.17.2.5; Names") with a minimum length of 0 characters and a maximum length of 256 characters.

2.1.1654 Part 4 Section 5.8.2.14, grpSpPr (Group Shape Properties)

For additional notes that apply to this portion of the standard, please see the notes for [grpSpPr](#), §5.6.2.17(a-c).

2.1.1655 Part 4 Section 5.8.2.20, pic (Picture)

- a. *The standard states that the values of the macro attribute are defined by the XML Schema string datatype.*

Office requires that the macro attribute value follow the same grammar as name-references ("ECMA-376 Part 4 §3.17.2.5; Names") with a minimum length of 0 characters and a maximum length of 256 characters.

2.1.1656 Part 4 Section 5.8.2.21, relSizeAnchor (Relative Anchor Shape Size)

- a. *The standard allows shapes to be defined where the right edge is to the left of the left edge or where the bottom edge is above the top edge.*

Office places additional restrictions on the relative size of 'from x' and 'from y' as follows:

The left side (**from** x) should be less than or equal to the right side (**to** x).

The top side (**from** y) should be less than or equal to the bottom side (**to** y).

If these restrictions are not met, Office uses the values described in the 2D transform (**xfrm**), if they are valid. If these values are not valid, Office does not render the shape.

- b. *The standard states that the from element specifies the top left corner of the shape bounding box in a RTL (right to left) implementation and the to element specifies the bottom right corner of the shape bounding box in a RTL implementation.*

In Office, the from element specifies the top left corner of the shape bounding box relative to the chart and the to element specifies the bottom right corner of the shape bounding box relative to the chart.

2.1.1657 Part 4 Section 5.8.2.22, sp (Shape)

- a. *The standard states that textlink is a formula linking to spreadsheet cell data.*

Excel requires that the value of the textlink attribute be a string referencing a cell or a cell range. This reference should be to a unique cell. Excel accepts a cell range but only considers the first cell in the range.

- b. *The standard states that that the minOccurs of child element txBody is 0.*

Office requires txBody if textlink is specified. Chart drawing content will not load if txBody is not provided and textlink is valid.

- c. *The standard allows attribute fLocksText on a shape in a chart drawing.*

Office does not support attribute fLocksText on a shape within a chart drawing.

- d. *The standard states that the values of the macro attribute are defined by the XML Schema string datatype.*

Office requires that the macro attribute value follow the same grammar as name-references ("[ECMA-376] Part 4 §3.17.2.5; Names") with a minimum length of 0 characters and a maximum length of 256 characters.

2.1.1658 Part 4 Section 5.8.2.23, spPr (Shape Properties)

For additional notes that apply to this portion of the standard, please see the notes for [spPr, §5.6.2.29\(a-c\)](#).

2.1.1659 Part 4 Section 5.8.2.24, style (Shape Style)

- a. *The standard states that child element fontRef applies to parent elements pic, cxnSp and sp.*

In Office, the fontRef child element is not used for parent elements pic and cxnSp.

- b. *The standard allows a sp, pic or cxnSp element to have similar formatting options defined in both the style and spPr elements.*

In Office, shape properties defined on the parent element will override similar style components (lnRef, effectRef, fillRef, fontRef) defined in this element.

- c. *The standard allows similar text formatting properties to be defined for parent element sp by the style or txBody element.*

In Office, child elements in the txBody element will override similar style properties defined by child element fontRef.

2.1.1660 Part 4 Section 5.8.2.25, to (Ending Anchor Point)

- a. *The standard does not include restrictions regarding the relative size of 'from x' and 'from y' with respect to 'to x' and 'to y'.*

Office places additional restrictions on the relative size of 'from x' and 'from y' as follows:

The left side (from x) should be less than or equal to the right side (to x).

The top side (from y) should be less than or equal to the bottom side (to y).

If these restrictions are not met, Office uses the values described in the 2D transform (xfrm), if they are valid. If these values are not valid, Office does not render the shape.

2.1.1661 Part 4 Section 5.8.2.26, txBody (Shape Text Body)

a. *The standard does not describe the relationship between similar properties in child elements p (text paragraphs) and lstStyle (text list styles).*

In Office, if no text list styles are defined in a paragraph, styles from lstStyle are used. If no list styles are defined in a paragraph, and there is no lstStyle defined, the text in the list defaults to the current text style.

2.1.1662 Part 4 Section 5.8.2.28, xfrm (Graphic Frame Transform)

For additional notes that apply to this portion of the standard, please see the notes for [xfrm](#), §5.1.9.6(a).

a. *The standard includes attributes flipH, flipV and rot for the xfrm element.*

Office does not support the flipH, flipV and rot attributes for graphic frames in chart drawings. Any value loaded will not be written back to the file on save.

b. *The standard includes ext and off as child elements of xfrm.*

Elements ext (Extents) and off (Offset) are used by Excel only if the graphic frame is inside of a group. If the graphic frame is not inside a group, the application will always write 0 for the attribute values of both elements.

2.1.1663 Part 4 Section 5.9.2.7, clrData (Color Transform Sample Data)

For additional notes that apply to this portion of the standard, please see the notes for [sampData](#), §5.9.2.26(a).

2.1.1664 Part 4 Section 5.9.2.13, extLst (Extension List)

a. *The standard implies that the extLst element cannot have any child elements.*

Office requires this element to have at least one child element.

2.1.1665 Part 4 Section 5.9.2.14, forEach (For Each)

a. *The standard states that the name attribute specifies a unique identifier for the layout node.*

Office uses this attribute to specify a unique identifier for the iteration.

b. *The standard describes the forEach element as a simple iteration.*

For Office, it is assumed that ForEach describes a pattern for iterating through elements in the data model. The way the data model tree is walked is specified by a forEach expression. The attributes axis, cnt, hideLastTrans, ptType, st and step can each be a single value or list of values. Use an array of values to perform multiple iterations in the same forEach that will iterate elements in the data model like nested forEach elements.

2.1.1666 Part 4 Section 5.9.2.20, param (Parameter)

- a. *The standard states that the val attribute is required.*

Office does not require this attribute; default values are assigned to it based on the value of the type attribute.

2.1.1667 Part 4 Section 5.9.2.26, sampData (Sample Data)

- a. *The standard states that the useDef attribute specifies whether or not the data model defined in the clrData element should be used.*

Office uses the useDef attribute to specify whether or not the data model defined in the styleData element should be used.

2.1.1668 Part 4 Section 5.9.2.27, shape (Shape)

- a. *The standard states that the lktXEntry attribute prevents text editing on a shape.*

Office ignores this attribute.

2.1.1669 Part 4 Section 5.9.2.29, styleData (Style Data)

For additional notes that apply to this portion of the standard, please see the notes for [sampData, §5.9.2.26\(a\)](#).

2.1.1670 Part 4 Section 5.9.3.2, cxn (Connection)

- a. *The standard places no restrictions on the number of parents associated with a node.*

Office requires that there be no more than one parent for any given node; for example, no more than one connection of type parOf or presParOf for any given destId. As a result, destOrd is ignored.

- b. *The standard states that the parTransId attribute is optional.*

Office requires this attribute when the type attribute is set to parOf and ignores this attribute otherwise.

- c. *The standard states that the presId attribute is optional.*

Office requires this attribute when the type attribute is set to presOf and ignores this attribute otherwise.

- d. *The standard states that the sibTransId attribute is optional.*

Office requires this attribute when the type attribute is set to parOf and ignores this attribute otherwise.

2.1.1671 Part 4 Section 5.9.3.4, prSet (Property Set)

- a. *The standard states that the presAssocID attribute is optional.*

Office requires this attribute.

- b. *The standard states that the presName attribute is optional.*

Office requires this attribute on the root presentation element.

2.1.1672 Part 4 Section 5.9.3.5, pt (Point)

- a. *The standard states that the cxnId attribute is optional.*

Office requires this attribute when the type attribute is set to parTrans or sibTrans and ignores this attribute otherwise.

2.1.1673 Part 4 Section 5.9.3.7, spPr (Shape Properties)

For additional notes that apply to this portion of the standard, please see the notes for [spPr](#), §5.6.2.29(a-c).

- a. *The standard states that the grpFill element is a valid child of the spPr element.*

Office will display an empty (invisible) shape fill for any diagram shape with a group fill, regardless of the fill of the parent group.

2.1.1674 Part 4 Section 5.9.3.8, t (Text Body)

- a. *The standard restricts a text body to single paragraph and no text runs.*

Office does not enforce this restriction.

2.1.1675 Part 4 Section 5.9.4.3, colorsDef (Color Transform Definitions)

- a. *The standard states that the values of the minVer attribute are defined by the XML Schema string datatype.*

Office requires the value of this attribute to be 12.0.

2.1.1676 Part 4 Section 5.9.4.7, effectClrLst (Effect Color List)

For additional notes that apply to this portion of the standard, please see the notes for [fillClrLst](#), §5.9.4.8(b).

2.1.1677 Part 4 Section 5.9.4.8, fillClrLst (Fill Color List)

- a. *The standard states that the fillClrLst element defines a list of colors which are used as fill colors in the color transform, and that those fill colors define the colors of the nodes in a diagram.*

Office uses this element to specify a color sequence to be applied to the fill of the associated presentation elements of a diagram.

- b. *The standard places no restrictions on the relationship between the meth attribute and the hueDir attribute.*

Office ignores the hueDir attribute if the value of the meth attribute is repeat.

2.1.1678 Part 4 Section 5.9.4.9, linClrLst (Line Color List)

For additional notes that apply to this portion of the standard, please see the notes for [fillClrLst](#), §5.9.4.8(b).

a. The standard states that the *linClrLst* element defines a list of colors which are used as line colors in the color transform, and that the line colors define the color of the lines used on a given node in a diagram.

Office uses this element to specify a color sequence to be applied to the lines of the associated presentation elements of a diagram.

2.1.1679 Part 4 Section 5.9.4.12, txEffectClrLst (Text Effect Color List)

For additional notes that apply to this portion of the standard, please see the notes for [fillClrLst, §5.9.4.8\(b\)](#).

2.1.1680 Part 4 Section 5.9.4.13, txFillClrLst (Text Fill Color List)

For additional notes that apply to this portion of the standard, please see the notes for [fillClrLst, §5.9.4.8\(b\)](#).

2.1.1681 Part 4 Section 5.9.4.14, txLinClrLst (Text Line Color List)

For additional notes that apply to this portion of the standard, please see the notes for [fillClrLst, §5.9.4.8\(b\)](#).

2.1.1682 Part 4 Section 5.9.5.6, sp3d (3-D Shape Properties)

For additional notes that apply to this portion of the standard, please see the notes for [sp3d, §5.1.7.12\(b\)](#).

a. The standard places no restrictions on the relationship between the properties of the *sp3d* element and the parent *styleLbl* element.

Office ignores the properties of the *sp3d* element if the parent *styleLbl* element is identical to a preset style in all other respects.

2.1.1683 Part 4 Section 5.9.5.10, styleLbl (Style Label)

a. The standard states that the *name* attribute is used for tooltips in the user interface.

Office uses the *name* attribute to map to nodes in the layout.

2.1.1684 Part 4 Section 5.9.7.3, ST_AnimOneStr (One by One Animation Value Definition)

a. The standard states that the default value of the *ST_AnimOneStr* simple type is one.

Office does not provide a default value for this simple type.

2.1.1685 Part 4 Section 5.9.7.6, ST_AxisType (Axis Type)

a. The standard states that the *ST_AxisType* simple type is referenced by itself.

Office defines the *ST_AxisType* simple type to be referenced by *ST_AxisTypes*, not itself.

2.1.1686 Part 4 Section 5.9.7.25, ST_ElementType (Element Type)

a. The standard states that the *ST_ElementType* simple type is referenced by itself.

Office defines the ST_ElementType simple type to be referenced by ST_ElementTypes, not itself.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.1687 Part 4 Section 5.9.7.48, ST_ParameterId (Parameter Identifier)

a. *The standard does not specify default values or the range of values for parameters.*

Office defines the following default values and ranges for each parameter:

| Enumeration Value | Description |
|--|--|
| alignTx (Text Alignment) | Office uses true as a default value to correspond to this parameter identifier. Office expects the value corresponding to this parameter identifier to be in the range defined by the XML schema boolean data type. |
| ar (Aspect Ratio) | Office uses 0 as a default value to correspond to this parameter identifier. Office expects the value corresponding to this parameter identifier to be in the range defined by the XML schema double data type. |
| autoTxRot (Auto Text Rotation) | Office uses upr as a default value to correspond to this parameter identifier. Office expects the value corresponding to this parameter identifier to be in the range defined by simple type ST_AutoTextRotation. |
| begPts (Beginning Points) | Office expects the value corresponding to this parameter identifier to be in the range defined by the XML schema string data type. |
| begSty (Beginning Arrowhead Style) | Office uses noArr as a default value to correspond to this parameter identifier. Office expects the value corresponding to this parameter identifier to be in the range defined by simple type ST_ArrowheadStyle. |
| bendPt (Bend Point) | Office uses def as a default value to correspond to this parameter identifier. Office expects the value corresponding to this parameter identifier to be in the range defined by simple type ST_BendPoint. |
| bkPtFixedVal (Breakpoint Fixed Value) | Office uses 2 as a default value to correspond to this parameter identifier. Office expects the value corresponding to this parameter identifier to be of type integer in the range [1, 32766]. |
| bkpt (Breakpoint) | Office uses endCnv as a default value to correspond to this parameter identifier. Office expects the value corresponding to this parameter identifier to be in the range defined by simple type ST_Breakpoint. |
| chAlign (Child Alignment) | Office uses l as a default value to correspond to this parameter identifier. Office expects the value corresponding to this parameter identifier to be in the range defined by simple type ST_ChildAlignment. |
| chDir (Child Direction) | Office uses horz as a default value to correspond to this parameter identifier. Office expects the value corresponding to this parameter identifier to |

| Enumeration Value | Description |
|---|--|
| | be in the range defined by simple type ST_ChildDirection. |
| connRout (Connection Route) | Office uses <i>stra</i> as a default value to correspond to this parameter identifier. Office expects the value corresponding to this parameter identifier to be in the range defined by simple type ST_ConnectorRouting. |
| contDir (Continue Direction) | Office uses <i>sameDir</i> as a default value to correspond to this parameter identifier. Office expects the value corresponding to this parameter identifier to be in the range defined by simple type ST_ContinueDirection. |
| ctrShpMap (Center Shape Mapping) | Office uses <i>none</i> as a default value to correspond to this parameter identifier. Office expects the value corresponding to this parameter identifier to be in the range defined by simple type ST_CenterShapeMapping. |
| dim (Connector Dimension) | Office uses <i>2D</i> as a default value to correspond to this parameter identifier. Office expects the value corresponding to this parameter identifier to be in the range defined by simple type ST_ConnectorDimension. |
| dstNode (Destination Node) | Office expects the value corresponding to this parameter identifier to be in the range defined by the XML schema string data type. |
| endPts (End Points) | Office expects the value corresponding to this parameter identifier to be in the range defined by the XML schema string data type. |
| endSty (End Style) | Office uses <i>arr</i> as a default value to correspond to this parameter identifier. Office expects the value corresponding to this parameter identifier to be in the range defined by simple type ST_ArrowheadStyle. |
| fallback (Fallback Scale) | Office uses <i>1D</i> as a default value to correspond to this parameter identifier. Office expects the value corresponding to this parameter identifier to be in the range defined by simple type ST_FallbackDimension. |
| flowDir (Flow Direction) | Office uses <i>row</i> as a default value to correspond to this parameter identifier. Office expects the value corresponding to this parameter identifier to be in the range defined by simple type ST_FlowDirection. |
| grDir (Grow Direction) | Office uses <i>tL</i> as a default value to correspond to this parameter identifier. Office expects the value corresponding to this parameter identifier to be in the range defined by simple type ST_GrowDirection. |
| hierAlign (Hierarchy Alignment) | Office uses <i>tCtrCh</i> as a default value to correspond to this parameter identifier. Office expects the value corresponding to this parameter identifier to be in the range defined by simple type ST_HierarchyAlignment. |
| horzAlign (Horizontal Alignment) | Office uses <i>ctr</i> as a default value to correspond to this parameter identifier. Office expects the value corresponding to this parameter identifier to |

| Enumeration Value | Description |
|--|---|
| | be in the range defined by simple type ST_HorizontalAlignment. |
| linDir (Linear Direction) | Office uses fromL as a default value to correspond to this parameter identifier. Office expects the value corresponding to this parameter identifier to be in the range defined by simple type ST_LinearDirection. |
| InSpAfChP (Line Spacing After Children Paragraph) | Office uses 15 as a default value to correspond to this parameter identifier. Office expects the value corresponding to this parameter identifier to be of type XML schema double in the range [0, 1000]. |
| InSpAfParP (Line Spacing After Parent Paragraph) | Office uses 35 as a default value to correspond to this parameter identifier. Office expects the value corresponding to this parameter identifier to be of type XML schema double in the range [0, 1000]. |
| InSpCh (Line Spacing Children) | Office uses 90 as a default value to correspond to this parameter identifier. Office expects the value corresponding to this parameter identifier to be of type XML schema double in the range [0, 1000]. |
| InSpPar (Line Spacing Parent) | Office uses 90 as a default value to correspond to this parameter identifier. Office expects the value corresponding to this parameter identifier to be of type XML schema double in the range [0, 1000]. |
| nodeHorzAlign (Node Horizontal Alignment) | Office uses ctr as a default value to correspond to this parameter identifier. Office expects the value corresponding to this parameter identifier to be in the range defined by simple type ST_NodeHorizontalAlignment. |
| nodeVertAlign (Node Vertical Alignment) | Office uses mid as a default value to correspond to this parameter identifier. Office expects the value corresponding to this parameter identifier to be in the range defined by simple type ST_NodeVerticalAlignment. |
| off (Offset) | Office uses off as a default value to correspond to this parameter identifier. Office expects the value corresponding to this parameter identifier to be in the range defined by simple type ST_Offset. |
| parTxLTRAlign (Parent Text Left-to-Right Alignment) | Office uses ctr as a default value to correspond to this parameter identifier. Office expects the value corresponding to this parameter identifier to be in the range defined by simple type ST_TextAlignment. |
| parTxRTLAlign (Parent Text Right-to-Left Alignment) | Office uses ctr as a default value to correspond to this parameter identifier. Office expects the value corresponding to this parameter identifier to be in the range defined by simple type ST_TextAlignment. |
| pyraAcctBkgdNode (Pyramid Accent Background Node) | Office expects the value corresponding to this parameter identifier to be in the range defined by the XML schema string data type. |
| pyraAcctPos (Pyramid Accent) | Office uses bef as a default value to correspond to this parameter |

| Enumeration Value | Description |
|---|---|
| Position) | <p>identifier.</p> <p>Office expects the value corresponding to this parameter identifier to be in the range defined by simple type ST_PyramidAccentPosition.</p> |
| pyraAcctTxMar (Pyramid Accent Text Margin) | <p>Office uses step as a default value to correspond to this parameter identifier.</p> <p>Office expects the value corresponding to this parameter identifier to be in the range defined by simple type ST_PyramidAccentTextMargin.</p> |
| pyraAcctTxNode (Pyramid Accent Text Node) | Office expects the value corresponding to this parameter identifier to be in the range defined by the XML schema string data type. |
| pyraLvlNode (Pyramid Level Node) | Office expects the value corresponding to this parameter identifier to be in the range defined by the XML schema string data type. |
| rotPath (Rotation Path) | <p>Office uses none as a default value to correspond to this parameter identifier.</p> <p>Office expects the value corresponding to this parameter identifier to be in the range defined by simple type ST_RotationPath.</p> |
| rtShortDist (Route Shortest Distance) | <p>Office uses true as a default value to correspond to this parameter identifier.</p> <p>Office expects the value corresponding to this parameter identifier to be in the range defined by the XML schema boolean data type.</p> |
| secChAlign (Secondary Child Alignment) | <p>Office uses none as a default value to correspond to this parameter identifier.</p> <p>Office expects the value corresponding to this parameter identifier to be in the range defined by simple type ST_SecondaryChildAlignment.</p> |
| secLinDir (Secondary Linear Direction) | <p>Office uses none as a default value to correspond to this parameter identifier.</p> <p>Office expects the value corresponding to this parameter identifier to be in the range defined by simple type ST_SecondaryChildAlignment.</p> |
| shpTxLTRAlignCh (Shape Text Left-to-Right Alignment) | <p>Office uses l as a default value to correspond to this parameter identifier.</p> <p>Office expects the value corresponding to this parameter identifier to be in the range defined by simple type ST_TextAlignment.</p> |
| shpTxRTLAlignCh (Shape Text Right-to-Left Alignment) | <p>Office uses r as a default value to correspond to this parameter identifier.</p> <p>Office expects the value corresponding to this parameter identifier to be in the range defined by simple type ST_TextAlignment.</p> |
| spanAng (Span Angle) | <p>Office uses 360 as a default value to correspond to this parameter identifier.</p> <p>Office expects the value corresponding to this parameter identifier to be of type XML schema double in the range [-360, 360].</p> |
| srcNode (Source Node) | Office expects the value corresponding to this parameter identifier to be in the range defined by the XML schema string data type. |
| stAng (Start Angle) | <p>Office uses 0 as a default value to correspond to this parameter identifier.</p> <p>Office expects the value corresponding to this parameter identifier to</p> |

| Enumeration Value | Description |
|--|---|
| | be in the range defined by the XML schema double data type. |
| stBulletLvl (Start Bullets At Level) | Office uses 2 as a default value to correspond to this parameter identifier. Office expects the value corresponding to this parameter identifier to be of type integer in the range [1, 2]. |
| stElem (Start Element) | Office uses node as a default value to correspond to this parameter identifier. Office expects the value corresponding to this parameter identifier to be in the range defined by simple type ST_StartingElement. |
| txAnchorHorz (Text Anchor Horizontal) | Office uses none as a default value to correspond to this parameter identifier. Office expects the value corresponding to this parameter identifier to be in the range defined by simple type ST_TextAnchorHorizontal. |
| txAnchorHorzCh (Text Anchor Horizontal With Children) | Office uses none as a default value to correspond to this parameter identifier. Office expects the value corresponding to this parameter identifier to be in the range defined by simple type ST_TextAnchorHorizontal. |
| txAnchorVert (Text Anchor Vertical) | Office uses mid as a default value to correspond to this parameter identifier. Office expects the value corresponding to this parameter identifier to be in the range defined by simple type ST_TextAnchorVertical. |
| txAnchorVertCh (Text Anchor Vertical With Children) | Office uses t as a default value to correspond to this parameter identifier. Office expects the value corresponding to this parameter identifier to be in the range defined by simple type ST_TextAnchorVertical. |
| txBIDir (Text Block Direction) | Office uses horz as a default value to correspond to this parameter identifier. Office expects the value corresponding to this parameter identifier to be in the range defined by simple type ST_TextBlockDirection. |
| txDir (Text Direction) | Office uses fromT as a default value to correspond to this parameter identifier. Office expects the value corresponding to this parameter identifier to be in the range defined by simple type ST_TextDirection. |
| vertAlign (Vertical Alignment) | Office uses mid as a default value to correspond to this parameter identifier. Office expects the value corresponding to this parameter identifier to be in the range defined by simple type ST_VerticalAlignment. |

2.1.1688 Part 4 Section 5.9.7.55, ST_SecondaryChildAlignment (Secondary Child Alignment)

a. *The standard states that the ST_SecondaryChildAlignment simple type defines different alignment properties of the both hanging layout type of the hierarchy algorithm.*

Office uses this simple type to define secondary alignment preferences to be used in a layout algorithm.

2.1.1689 Part 4 Section 5.9.7.56, ST_SecondaryLinearDirection (Secondary Linear Direction)

a. The standard states that the ST_SecondaryLinearDirection simple type defines different directions for the nodes in a both hanging layout in the hierarchy algorithm.

Office uses this simple type to define different directions for the nodes in a layout algorithm.

2.1.1690 Part 4 Section 6.1, VML

a. The standard indicates the unit systems used throughout VML, but does not specify their bounds.

Office has restrictions for each of the units used in the standard.

The following table documents Office limits for each unit. Office also uses EMUs throughout VML as a valid unit system. Individual elements and attributes may impose further limits on any particular quantity based on its context.

| Unit | Min | Max |
|-------------|-------------|------------|
| EMU | -2147483644 | 2147483647 |
| Pixels | -2147483648 | 2147483647 |
| Inches | -2348 | 2348 |
| Centimeters | -5965 | 5965 |
| Millimeters | -59652 | 59652 |
| Points | -169093 | 169093 |
| Picas | -14091 | 14091 |

2.1.1691 Part 4 Section 6.1.2.1, arc (Arc Segment)

For additional notes that apply to this portion of the standard, please see the notes for [pict, §2.9.23\(a\)](#); [curve, §6.1.2.3\(d\)](#); [image, §6.1.2.10\(b-f\)](#).

a. The standard states that *xy* and *yx* are valid values of the *flip* property on the style attribute.

Office does not allow these values; instead, it allows values of "x y" and "y x" (minus the quotes, but including the spaces) for the same purpose.

b. The standard implies that the *height* and *mso-height-percent* properties on the style attribute are optional.

Office requires that at least one of these properties be set when an anchor element is not present; the *height* property is ignored when either the *mso-height-percent* property or an anchor element is specified.

c. The standard implies that the *left*, *margin-left*, *mso-position-horizontal*, and *mso-left-percent* properties on the style attribute are optional.

Office requires that at least one of these properties be set when the value of the position property is absolute and an anchor element is not present; all of these properties are ignored when the value of the position property is static.

d. *The standard states that the margin-bottom property on the style attribute specifies the position of the bottom of the containing block of the shape relative to the shape anchor.*

Office does not support this property.

e. *The standard states that the margin-right property on the style attribute specifies the position of the right of the containing block of the shape relative to the shape anchor.*

Office does not support this property.

f. *The standard implies that the top, margin-top, mso-position-vertical, and mso-top-percent properties on the style attribute are optional.*

Office requires that at least one of these properties be set when the value of the position property is absolute and an anchor element is not present; all of these properties are ignored when the value of the position property is static.

g. *The standard implies that the mso-position-horizontal-relative property on the style attribute is optional.*

Office requires this property to be specified when the value of the mso-position-horizontal property on the style attribute is not absolute.

h. *The standard states that the only valid values for the mso-position-horizontal-relative property on the style attribute are margin, page, text, and char.*

Office also allows values of left-margin-area, right-margin-area, inner-margin-area, and outer-margin area when the value of the mso-position-horizontal property on the style attribute is neither inside nor outside.

i. *The standard states that the default value of the mso-position-horizontal-relative property on the style attribute is text.*

Office requires this property to be set.

j. *The standard states that the default value of the mso-position-vertical-relative property on the style attribute is text.*

Office requires this property to be set.

k. *The standard states that the only valid values for the mso-position-vertical-relative property on the style attribute are margin, page, text, and line.*

Office also allows values of top-margin-area, bottom-margin-area, inner-margin-area, and outer-margin area.

l. *The standard does not state how the mso-wrap-distance-bottom, mso-wrap-distance-left, mso-wrap-distance-right, and mso-wrap-distance-top properties on the style attribute are to be measured.*

Office allows these properties to be measured using the absolute units designator cm, mm, in, pt, or pc; or using the relative units designator px.

m. *The standard states that the default value of the mso-wrap-distance-left and mso-wrap-distance-right properties on the style attribute is 0 pt.*

Office uses a default value of 9 pt for these properties.

n. *The standard states that relative is a valid value for the position property on the style attribute.*

Office does not support this value on this property.

o. *The standard states that auto is a valid value for the margin-left, margin-top, left, top, width, height, and z-index properties on the style attribute.*

Office does not support this value on these properties.

p. *The standard states that the value of the margin-left, margin-top, left, top, width, and height properties on the style attribute may be specified as a percentage.*

Office does not allow the value of these properties to be specified as a percentage.

q. *The standard states that the value of the margin-left, margin-top, left, top, width, and height properties on the style attribute may be specified in em or ex units.*

Office does not allow the value of these properties to be specified in this way.

r. *The standard places no restrictions on the relationship between the top, margin-top, mso-position-vertical, or mso-top-percent properties on the style attribute.*

Office ignores the top and margin-top properties when either the mso-position-vertical or mso-top-percent property on the style attribute is set, or when an anchor element is present.

s. *The standard implies that the width and mso-width-percent properties on the style attribute are optional.*

Office requires that at least one of these properties be set when an anchor element is not present; the width property is ignored when either the mso-width-percent property or an anchor element is specified.

t. *The standard makes no mention of an mso-width-percent property on the style attribute.*

Word uses this property to specify the width of the shape as a percentage of the layout object defined by the mso-width-relative property; its value is expressed as an integer between 10 and 10,000, inclusive, where each unit is a tenth of a percent.

u. *The standard makes no mention of an mso-height-percent property on the style attribute.*

Word uses this property to specify the height of a shape as a percentage of the layout object defined by the mso-height-relative property; its value is expressed as an integer between 10 and 10,000, inclusive, where each unit is a tenth of a percent.

v. *The standard makes no mention of an mso-width-relative property on the style attribute.*

Word uses this property to specify the layout object referred to by the mso-width-percent property; its allowed values are margin, page, left-margin-area, right-margin-area, inner-margin-area, and outer-margin-area, with page being the default.

w. *The standard makes no mention of an mso-height-relative property on the style attribute.*

Word uses this property to specify the layout object referred to by the `mso-height-percent` property; its allowed values are `margin`, `page`, `top-margin-area`, `bottom-margin-area`, `inner-margin-area`, and `outer-margin-area`.

x. *The standard makes no mention of an `mso-left-percent` property on the style attribute.*

Word uses this property to specify the location of the left edge of the shape as a percentage of the width of the layout object defined by the `mso-position-horizontal-relative` property; its value is expressed as an integer between -10,000 and 10,000, inclusive, where each unit is a tenth of a percent. This property cannot be used in combination with the `mso-position-horizontal` attribute on the style attribute.

y. *The standard makes no mention of an `mso-top-percent` property on the style attribute.*

Word uses this property to specify the location of the top edge of the shape as a percentage of the height of the layout object defined by the `mso-position-vertical-relative` property; its value is expressed as an integer between -10,000 and 10,000, inclusive, where each unit is a tenth of a percent. This property cannot be used in combination with the `mso-position-vertical` attribute on the style attribute.

z. *The standard states that the `v-text-anchor` property on the style attribute is only used by the `textbox` element, where it specifies the vertical anchoring of text within the `textbox`.*

Office instead applies this property to the shape containing the `textbox` element, where it specifies the anchor point of the text contained within the shape.

aa. *The standard states that the default value of the `allowincell` attribute is `false`.*

Office uses a default value of `true` for this attribute.

bb. *The standard states that the `allowincell` attribute specifies whether a shape can be placed in a table.*

Office uses this attribute to specify whether a shape's anchor can be placed in a table.

cc. *The standard places no restrictions on how values of the `z-index` property on the style attribute be preserved.*

Office preserves relative ordering and sign but not absolute values of this property.

dd. *The standard states that the default value of the `z-index` property on the style attribute is 0.*

Office requires this property to be specified unless the element is `shapedefaults`, `shapetype`, `textbox`, or `textpath`.

ee. *The standard places no restrictions on the relationship between the `top` and `margin-top` properties on the style attribute.*

Office combines the values from these two properties into the `margin-top` property.

ff. *The standard places no restrictions on the relationship between the `left` and `margin-left` properties on the style attribute.*

Office combines the values from these two properties into the `margin-left` property.

gg. *The standard states that the values of the `borderbottomcolor` attribute are defined by the XML Schema string datatype.*

Office defines the values of this attribute with the ST_ColorType simple type.

hh. *The standard states that the values of the bordertopcolor attribute are defined by the XML Schema string datatype.*

Office defines the values of this attribute with the ST_ColorType simple type.

ii. *The standard states that the values of the borderrightcolor attribute are defined by the XML Schema string datatype.*

Office defines the values of this attribute with the ST_ColorType simple type.

jj. *The standard states that the values of the borderleftcolor attribute are defined by the XML Schema string datatype.*

Office defines the values of this attribute with the ST_ColorType simple type.

kk. *The standard does not state a valid value range for the mso-wrap-distance-bottom, mso-wrap-distance-left, mso-wrap-distance-right, mso-wrap-distance-top, width, and height properties on the style attribute.*

Office requires the values of these properties to be non-negative.

ll. *The standard states that chromakey and opacity are valid attributes on the arc element.*

Office does not support these attributes on this element.

mm. *The standard states that class is a valid attribute.*

Office does not support this attribute.

nn. *The standard states that the default value of the connectortype attribute is straight.*

Office uses a default value of none for this attribute.

oo. *The standard states that coordsize is a valid attribute on the image and roundrect elements.*

Office does not support this attribute on these elements.

pp. *The standard states that the dgmnodekind attribute specifies an optional, application-specific parameter that is intended to be used by the application to tag different types of nodes in a diagram.*

Office uses this attribute to indicate which type of position in an organization chart the shape represents.

qq. *The standard does not state how to interpret the value of the hrpct attribute.*

Office interprets this attribute as tenths of a percentage point of the page width, where the page width is the width of the page without the margins.

rr. *The standard states that the values of the hrpct attribute are defined by the XML Schema float datatype.*

Office restricts the value of this attribute to be at least 0 and at most 1000.

ss. *The standard states that the default value of the hrpct attribute is 0.*

Office uses a default value of 1000 for this attribute.

tt. *The standard places no restrictions on when the ole attribute is preserved.*

Office only preserves this attribute when the value of the spt attribute is 75 and a related OLEObject element exists.

uu. *The standard does not state how to interpret the locations specified in the wrapcoords attribute.*

Office interprets these locations to be in terms of a 21,600-coordinate unit square, scaled anisotropically to fit the shape's dimensions, that maps to the bounding rectangle of the shape, with an origin at the top, left corner.

vv. *The standard states that the wrapcoords attribute is specified using a comma-delimited list of x and y coordinates.*

Office uses a space-delimited list to specify this attribute, both when delimiting the x and y coordinates in a point and when delimiting points in the list.

ww. *The standard places no restrictions on the relationship between the borderbottomcolor attribute and the borderbottom child element.*

Office ignores the borderbottomcolor attribute if there is no borderbottom child element.

xx. *The standard places no restrictions on the relationship between the bordertopcolor attribute and the bordertop child element.*

Office ignores the bordertopcolor attribute if there is no bordertop child element.

yy. *The standard places no restrictions on the relationship between the borderrightcolor attribute and the borderright child element.*

Office ignores the borderrightcolor attribute if there is no borderright child element.

zz. *The standard places no restrictions on the relationship between the borderleftcolor attribute and the borderleft child element.*

Office ignores the borderleftcolor attribute if there is no borderleft child element.

aaa. *The standard states that the default value of the strokeweight attribute is 1 point.*

Office uses a default value of 0.75 points for this attribute.

bbb. *The standard states that pixels are an absolute unit designator in the description for the margin-left, margin-top, margin-right, margin-bottom, left, top, width, and height properties on the style attribute.*

Office treats pixels as a relative unit designator.

ccc. *The standard implies that the mso-position-vertical-relative property on the style attribute is optional.*

Office requires this property to be specified when the value of the mso-position-vertical property on the style attribute is not absolute.

ddd. *The standard does not state how to interpret a value of 0 on the hrpct attribute.*

Office interprets a value of 0 on this attribute to indicate that the size of the object is not expressed in terms of percentage of the page width.

eee. *The standard does not state how to interpret multiple occurrences of a given property on the style attribute.*

Office ignores all but the last occurrence of a property that is specified more than once.

fff. *The standard places no restrictions on when the units specified in the margin-left, margin-top, left, top, width, and height properties on the style attribute will be used.*

Office ignores the units specified on these properties when the element is a child in a group; the values are considered to be specified in the coordinate space of the parent, defined by the coordsize and coordorigin attributes.

ggg. *The standard states that the left property on the style attribute specifies the position of the left of the containing block of the shape relative to the element left of it in the flow of the page.*

Office uses this property to specify the position of the left edge of the content block from the left margin or, if the left margin is not set, from the anchor.

hhh. *The standard states that the margin-left property on the style attribute specifies the position of the left of the containing block of the shape relative to the shape anchor.*

Office uses this property to specify the position of the left margin of the content block from the anchor.

iii. *The standard states that the mso-position-horizontal-relative property on the style attribute allows values of text and char, without restriction.*

Office does not allow these values when this property is modifying the mso-left-percent property on the style attribute, or when the value of the mso-position-horizontal property on the style attribute is inside or outside.

jjj. *The standard states that the mso-position-vertical-relative property on the style attribute allows a value of text, without restriction.*

Office only allows this value when this property is modifying the mso-position-vertical property on the style attribute and the value of that property is absolute.

kkk. *The standard states that the default value of the spt attribute is 0.*

Office uses a default value of 19 for the arc element.

lll. *The standard places no restrictions on the relationship between the connectortype and spt attributes.*

Office ignores the connectortype attribute if the spt attribute does not indicate that the element is a connector.

mmm. *The standard implies that text can be added to the arc element via the textbox child element.*

Office may generate such content but subsequent open/save operations will not preserve that content on this element.

nnn. *The standard implies that the arc element will preserve text wrapping information on the wrap child element.*

Office will not preserve this information on this child element.

ooo. *The standard states that the possible values for the ole attribute are defined by the ST_TrueFalseBlank simple type.*

Office considers the existence of the ole attribute, regardless of its value, to indicate a value of true.

ppp. *The standard does not state a default value for the insetpen attribute.*

Office uses default value of false for this attribute.

qqq. *The standard states that the background element is a valid parent for the arc element.*

Office does not support the background element as a parent of the arc element.

rrr. *The standard states that the mso-position-horizontal-relative property on the style attribute modifies the mso-position-horizontal property on the style attribute.*

Office uses the mso-position-horizontal-relative property to modify either the mso-position-horizontal property or the mso-left-percent property on the style attribute.

sss. *The standard states that the mso-position-vertical-relative property on the style attribute allows a value of line, without restriction.*

Office does not allow this value when this property is modifying the mso-top-percent property on the style attribute.

ttt. *The standard states that the mso-position-vertical-relative property on the style attribute modifies the mso-position-vertical property on the style attribute.*

Office uses the mso-position-vertical-relative property to modify either the mso-position-vertical property or the mso-top-percent property on the style attribute.

uuu. *The standard states that top-center, middle-center, bottom-center, top-baseline, bottom-baseline, top-center-baseline, and bottom-center-baseline are valid values for the v-text-anchor property on the style attribute.*

Office does not support these values on this property.

vvv. *The standard places no restrictions on when the allowincell attribute is applicable.*

Excel and PowerPoint do not support this attribute; Word does not support this attribute on inline shapes.

www. *The standard places no restrictions on when the coordorigin attribute is preserved.*

Office does not preserve this attribute on a shape that references, via the type attribute, a shapetype element with the same coordorigin value.

xxx. *The standard places no restrictions on when the coordorigin and coordsize attributes are preserved on the arc element.*

Office preserves these attributes only when this element has at least one of the following children: a path with connection points specified in its connectlocs attribute; a path with a textbox specified in its textboxrect attribute; or handles.

yyy. *The standard states that values of the dgmnodekind attribute are defined by the XML Schema integer datatype.*

Office restricts the values of this attribute to be at least 0 and at most 6, where the values represent regular, root, assistant, co-worker, subordinate, auxiliary, and default, respectively.

zzz. *The standard places no restrictions on when the coordsize attribute is preserved.*

Office does not preserve this attribute on a shape that references, via the type attribute, a shapetype element with the same coordorigin value.

aaaa. *The standard places no restrictions on the value of the spt attribute.*

Office requires that the spt attribute on an arc element have a value of 19.

bbbb. *The standard places no restrictions on the relationship between the left, margin-left, mso-position-horizontal, and mso-left-percent properties on the style attribute.*

Office ignores the left and margin-left properties when either the mso-position-horizontal or mso-left-percent property on the style attribute is set, or when an anchor element is present.

cccc. *The standard states that the top property on the style attribute specifies the position of the top of the containing block of the shape relative to the element above it in the flow of the page.*

Office uses this property to specify the position of the top edge of the content block from the top margin or, if the top margin is not set, from the anchor.

dddd. *The standard states that the margin-top property on the style attribute specifies the position of the left of the containing block of the shape relative to the shape anchor.*

Office uses this property to specify the position of the top margin of the content block from the anchor.

eeee. *The standard states that the values of the id attribute are defined by the XML Schema string datatype.*

Office defines the values of this attribute with the ST_ObjID ([§3.9.3, ST_ObjID](#)) simple type.

ffff. *The standard states that the values of the spid attribute are defined by the XML Schema string datatype.*

Office defines the values of this attribute with the ST_SpId ([§3.9.6, ST_SpId](#)) simple type.

gggg. *The standard states that the height property on the style attribute specifies the height of the containing block of the shape.*

Office uses this property to specify the height of the content block.

hhhh. *The standard states that the width property on the style attribute specifies the width of the containing block of the shape.*

Office uses this property to specify the width of the content block.

2.1.1692 Part 4 Section 6.1.2.2, background (Document Background)

For additional notes that apply to this portion of the standard, please see the notes for [object, §2.3.3.19\(a\)](#); [pict, §2.3.3.21\(a\)](#); [pict, §2.9.23\(a\)](#); [arc, §6.1.2.1\(eeee\)](#).

a. *The standard indicates how the targetscreensize attribute is used.*

Office does not preserve the current value of the `targetscreensize` attribute and always writes 800,600 on file save.

b. *The standard states that the name of the attribute that specifies whether the closed path will be filled is filled.*

Office uses the name `fill` for this attribute.

c. *The standard states that the values of the `id` attribute are defined by the XML Schema string datatype.*

Office defines the values of this attribute with the `ST_ObjID` ([§3.9.3, ST_ObjID](#)) simple type.

2.1.1693 Part 4 Section 6.1.2.3, curve (Bezier Curve)

For additional notes that apply to this portion of the standard, please see the notes for [pict, §2.9.23\(a\)](#); [arc, §6.1.2.1\(a-kk,mm-vv,aaa-jjj,lll,ooo, ppp,rrr-www,yyy, zzz,bbbb-hhhh\)](#); [image, §6.1.2.10\(b-f\)](#).

a. *The standard indicates the default value of the `control1` attribute is "10,10".*

Office uses a default value of "0,0" for the `control1` attribute.

b. *The standard indicates the default value of the `control2` attribute is "20,20".*

Office uses a default value of "0,0" for the `control2` attribute.

c. *The standard indicates the default value of the `to` attribute is "30,20".*

Office uses a default value of "0,0" for the `to` attribute.

d. *The standard states that the `line`, `polyline`, and `curve` elements only ignore the `top`, `left`, `width`, and `height` properties on the `style` attribute.*

Office also ignores the `margin-top`, `margin-left`, `mso-left-percent`, `mso-position-horizontal`, `mso-position-horizontal-relative`, `mso-top-percent`, `mso-position-vertical` and `mso-position-vertical-relative` properties when applied to these elements.

e. *The standard indicates that `background` is a parent element for the element `curve`.*

In Office the `background` element is not supported as a parent for the element `curve`.

f. *The standard places no restrictions on the value of the `spt` attribute.*

Office requires that the `spt` attribute on a `curve` element have a value of 0. It is an error to specify this attribute as anything other than the default value, except for the `shape` and `shapetype` elements which can handle any valid `spt` value.

g. *The standard states that `chromakey` and `opacity` are valid attributes on the `curve` element.*

Office does not support these attributes on this element.

2.1.1694 Part 4 Section 6.1.2.4, f (Single Formula)

a. *The standard indicates the formula for the `mod` operation of the `eqn` attribute is the square root of $(v^2 + P1^2 + P1^2)$.*

Office implements the mod operation of the eqn attribute as the square root of $(v^2 + P1^2 + P2^2)$.

b. *The standard indicates the set of valid arguments for the operations in the eqn attribute.*

Office supports an additional value lineDrawn as an argument for formula evaluation:

| Value | Description |
|------------------|---|
| <i>lineDrawn</i> | <p>1 if the shape is stroked, 0 if it is not. A shape is not stroked if one of the following conditions is true:</p> <p>The value of the on attribute of the stroke element ("[ECMA-376] Part 4 §6.1.2.21; stroke (Line Stroke Settings)") is <i>false</i>.</p> <p>The on attribute of the stroke element is absent and the value of the shape's stroked attribute is <i>false</i>.</p> <p>The on attribute of the stroke element is absent, the shape's stroked attribute is absent and the value of the stroked attribute of the shapetype element ("[ECMA-376] Part 4 §6.1.2.20; shapetype (Shape Template)") is <i>false</i>.</p> |

c. *The standard indicates that hasfill is a valid argument for the operations in the eqn attribute.*

Office does not support the hasfill argument for the operations in the eqn attribute.

d. *The standard indicates that hasstroke is a valid argument for the operations in the eqn attribute.*

Office does not support the hasstroke argument for the operations in the eqn attribute.

2.1.1695 Part 4 Section 6.1.2.5, fill (Shape Fill Properties)

For additional notes that apply to this portion of the standard, please see the notes for [background, §2.2.1\(a\)](#); [object, §2.3.3.19\(a\)](#); [pict, §2.3.3.21\(a\)](#); [pict, §2.9.23\(a\)](#); [arc, §6.1.2.1\(eeee\)](#); [background, §6.1.2.2\(c\)](#); [group, §6.1.2.7\(a\)](#).

a. *The standard does not define a default value for the detectmouseclick attribute.*

Office uses a default value of false for the detectmouseclick attribute.

b. *The standard indicates how the alignshape attribute is used.*

Office also requires that the value of the type attribute is tile if the alignshape attribute is used.

c. *The standard does not specify bounds for the angle attribute.*

Office specifies the bounds for the angle attribute of -32767 and 32767.

d. *The standard states that o:relid is a valid attribute.*

Office does not support this attribute.

e. *The standard does not specify bounds for the origin attribute.*

Office uses bounds of -32767 and 32767 for the origin attribute.

f. *The standard indicates that the default value for the origin attribute is the center of the image.*

Office uses a default value of 0,0 for the origin attribute.

g. *The standard implies that positive values are to the right and down for the origin attribute.*

In Office, negative values for the origin attribute are to the right and down, so the bottom right corner is -1,-1.

h. *The standard implies that only absolute numbers may be used for the size attribute.*

In Office, values are specified as either an absolute measurement or a fractional value of the shape dimensions. A fractional value may be specified in 1/65536ths if a trailing "f" is supplied. [Example: A value of "52429f" represents 52429/65536, or 0.8. end example] The minimum and maximum values are 0f to 2147483647f.

i. *The standard indicates how the type attribute is used.*

If this attribute value is *tile*, *pattern* or *frame*, Office requires that the image attributes be specified. If this attribute value is *gradient* or *gradientradial*, Office requires that the gradient attributes be specified.

j. *The standard allows any string to be used for title attribute.*

Office does not allow slashes or colons in the title attribute string.

k. *The standard indicates how the title attribute is used.*

Office only supports the type attribute if the value of the type attribute is *tile*, *pattern* or *frame*.

l. *The standard indicates how the althref attribute is used.*

Office does not support the althref attribute.

m. *The standard indicates how the href attribute is used.*

Office does not support the href attribute.

n. *The standard indicates how the src attribute is used.*

Office does not support the src attribute.

o. *The standard does not restrict the number of instances of the fill element.*

Office allows at most only one instance of the fill element in each place where it can be used.

p. *The standard states that values of the opacity attribute are defined by the XML Schema string datatype.*

Office defines the values of this attribute with the ST_Fraction ([§3.9.1, ST Fraction](#)) simple type.

q. *The standard states that values of the opacity2 attribute are defined by the XML Schema string datatype.*

Office defines the values of the opacity2 attribute with the ST_Fraction (§3.9.1, ST_Fraction) simple type.

2.1.1696 Part 4 Section 6.1.2.6, formulas (Set of Formulas)

For additional notes that apply to this portion of the standard, please see the notes for [background, §2.2.1\(a\)](#); [object, §2.3.3.19\(a\)](#); [pict, §2.3.3.21\(a\)](#); [pict, §2.9.23\(a\)](#); [group, §6.1.2.7\(a\)](#).

- a. *The standard states that the maxOccurs value for the f child element is unbounded.*

Office limits the occurrences of this element to 128.

- b. *The standard does not restrict the number of instances of the formulas element.*

Office allows at most one instance of this element in each place where it can be used.

2.1.1697 Part 4 Section 6.1.2.7, group (Shape Group)

For additional notes that apply to this portion of the standard, please see the notes for [background, §2.2.1\(a\)](#); [arc, §6.1.2.1\(a-ff,kk,mm,oo-ss,uu, vv,bbb-iii,rrr-www,yyy, zzz,bbbb-hhhh\)](#); [background, §6.1.2.2\(c\)](#); [curve, §6.1.2.3\(d\)](#); [image, §6.1.2.10\(b,e\)](#).

- a. *The standard states that borderbottom, borderleft, borderright, bordertop, callout, extrusion, fill, formulas, handles, imagedata, path, shadow, signatureline, skew, stroke, textbox, textpath, and textdata are valid children of the group element.*

Office does not allow these elements to be children of the group element.

- b. *The standard states that the borderbottomcolor, borderleftcolor, borderrightcolor, bordertopcolor, fillcolor, and filled attributes are valid attributes on the group element.*

Office does not support these attributes on this element.

2.1.1698 Part 4 Section 6.1.2.8, h (Shape Handle)

- a. *The standard indicates how the switch attribute is used.*

Office ignores the switch attribute and writes false or a blank string value on file save.

- b. *The standard indicates that a true or false value is saved to the file for the invx attribute.*

Office ignores the value of the invx attribute and writes an empty string whenever the attribute is written to the file.

- c. *The standard indicates that a true or false value is saved to the file for the invy attribute.*

Office ignores the value of the invy attribute and writes an empty string whenever the attribute is written to the file.

- d. *The standard indicates how the map attribute is used.*

Office does not support the map attribute and using it may result in unpredictable runtime behavior.

2.1.1699 Part 4 Section 6.1.2.9, handles (Set of Handles)

For additional notes that apply to this portion of the standard, please see the notes for [background, §2.2.1\(a\)](#); [object, §2.3.3.19\(a\)](#); [pict, §2.3.3.21\(a\)](#); [pict, §2.9.23\(a\)](#); [group, §6.1.2.7\(a\)](#).

- a. *The standard states that the maxOccurs value for the h child element is unbounded.*

Office limits the occurrences of this element to 4.

b. *The standard does not restrict the number of instances of the handles element.*

Office allows at most one instance of this element in each place where it can be used.

2.1.1700 Part 4 Section 6.1.2.10, image (Image File)

For additional notes that apply to this portion of the standard, please see the notes for [background, §2.2.1\(a\)](#); [arc, §6.1.2.1\(a-kk,mm-vv,aaa-iji,lll,ooo, ppp,rrr-www,yyy, zzz,bbbb-hhhh\)](#); [curve, §6.1.2.3\(d\)](#); [imagedata, §6.1.2.11\(d,h-o\)](#).

a. *The standard indicates that color images should be reduced to 8 colors if the bilevel attribute is true.*

Office interprets the bilevel attribute as a toggle between color and black and white and converts all images, color or greyscale, to pure black and white if the value of the bilevel attribute is true.

b. *The standard implies that the bullet attribute may be used to specify that the element is a bullet.*

Office sets this attribute when the element is being used as a bullet, but ignores it on file load; this attribute does not make the element a bullet.

c. *The standard states that the bwnormal attribute specifies the black-and-white mode for normal black-and-white output devices.*

Word and Excel do not support this attribute.

d. *The standard states that the bwpure attribute specifies the black-and-white mode for pure black-and-white output devices.*

Word and Excel do not support this attribute.

e. *The standard places no restrictions on when the target attribute is preserved.*

Office does not preserve this attribute when the href attribute is not set.

f. *The standard states that the bwmode attribute specifies how a shape will render for black-and-white output devices.*

Word and Excel do not support this attribute.

g. *The standard places no restrictions on the value of the spt attribute.*

Office requires the spt attribute on an image element have a value of 75. It is an error to specify this attribute as anything other than the default value, except for the shape and shapetype elements, which can handle any valid spt value.

h. *The standard states that chromakey, coordorigin, and opacity are valid attributes on the image element.*

Office does not support these attributes on this element.

i. *The standard states that the default value of the spt attribute is 0.*

Office uses a default value of 75 for the image element.

2.1.1701 Part 4 Section 6.1.2.11, imagedata (Image Data)

For additional notes that apply to this portion of the standard, please see the notes for [background, §2.2.1\(a\)](#); [object, §2.3.3.19\(a\)](#); [pict, §2.3.3.21\(a\)](#); [pict, §2.9.23\(a\)](#); [arc, §6.1.2.1\(eeee\)](#); [background, §6.1.2.2\(c\)](#); [group, §6.1.2.7\(a\)](#); [image, §6.1.2.10\(a\)](#).

- a. *The standard does not restrict the number of instances of the imagedata element.*

Office allows at most only one instance of the imagedata element in each place where it can be used.

- b. *The standard states that althref is a valid attribute.*

Office does not support this attribute.

- c. *The standard states that movie is a valid attribute.*

Office does not support this attribute.

- d. *The standard states that src is a valid attribute.*

Office does not support this attribute.

- e. *The standard indicates that the pict attribute is used to specify the relationship with alternate image data.*

Office does not preserve the pict attribute for imagedata elements.

- f. *The standard states that oleid is valid attribute.*

Office does not support this attribute.

- g. *The standard does not specify a default value for the detectmouseclick attribute.*

In Office, the default value of the detectmouseclick attribute is true for imagedata elements.

- h. *The standard states that the values of the cropleft attribute are defined by the XML Schema string datatype.*

Office defines the values of this attribute with the ST_Fraction ([§3.9.1, ST_Fraction](#)) simple type.

- i. *The standard states that the values of the cropright attribute are defined by the XML Schema string datatype.*

Office defines the values of this attribute with the ST_Fraction (§3.9.1, ST_Fraction) simple type.

- j. *The standard states that the values of the blacklevel attribute are defined by the XML Schema string datatype.*

Office defines the values of this attribute with the ST_Fraction (§3.9.1, ST_Fraction) simple type.

- k. *The standard states that the values of the gain attribute are defined by the XML Schema string datatype.*

Office defines the values of this attribute with the ST_Fraction (§3.9.1, ST_Fraction) simple type.

- l. *The standard states that the values of the gamma attribute are defined by the XML Schema string datatype.*

Office defines the values of this attribute with the ST_Fraction (§3.9.1, ST_Fraction) simple type.

m. *The standard states that the values of the croptop attribute are defined by the XML Schema string datatype.*

Office defines the values of this attribute with the ST_Fraction (§3.9.1, ST_Fraction) simple type.

n. *The standard states that the values of the cropbottom attribute are defined by the XML Schema string datatype.*

Office defines the values of this attribute with the ST_Fraction (§3.9.1, ST_Fraction) simple type.

o. *The standard does not specify bounds for the blacklevel attribute.*

Office uses a range of [-0.5, 0.5] for the blacklevel attribute for the imagedata element.

p. *The standard supports the relid attribute in all contexts.*

Office only supports the relid attribute in the SpreadsheetML context.

q. *The standard supports the attribute Id in all contexts.*

Office only supports the Id attribute in the WordprocessingML context.

r. *The standard does not explicitly define the interaction between the detectmouseclick attributes and the fill and imagedata child elements.*

Office treats detectmouseclick as false only if the detectmouseclick attributes of both the fill and imagedata child elements are set to false.

s. *The standard states that o:href is a valid attribute.*

Office does not support this attribute.

2.1.1702 Part 4 Section 6.1.2.12, line (Line)

For additional notes that apply to this portion of the standard, please see the notes for [background, §2.2.1\(a\)](#); [arc, §6.1.2.1\(a-kk,mm-vv,aaa-jjj,lll,ooo, ppp,rrr-www,yyy, zzz,bbbb-hhhh\)](#); [curve, §6.1.2.3\(d\)](#); [image, §6.1.2.10\(b-f\)](#).

a. *The standard indicates that the default value for the to attribute is "10,10".*

Office uses a default value of "50pt,50pt" for the to attribute.

b. *The standard places no restrictions on the value of the spt attribute.*

Office requires that the spt attribute on a line element have a value of 20. It is an error to specify this attribute as anything other than the default value, except for the shape and shapetype elements, which can handle any valid spt value.

c. *The standard states that chromakey and opacity are valid attributes on the line element.*

Office does not support these attributes on this element.

d. *The standard states that the default value of the spt attribute is 0.*

Office uses a default value of 20 for the line element. It is an error to specify this attribute as anything other than the default value, except for the shape and shapetype elements which can handle any valid spt value.

e. *The standard places no restrictions on when the coordorigin and coordsize attributes are preserved on the line element.*

Office only preserves these attributes when this element has at least one of the following children: a path with connection points specified in its connectlocs attribute; a path with a textbox specified in its textboxrect attribute; or handles.

2.1.1703 Part 4 Section 6.1.2.13, oval (Oval)

For additional notes that apply to this portion of the standard, please see the notes for [background, §2.2.1\(a\)](#); [arc, §6.1.2.1\(a-kk,mm-vv,aaa-jjj,lll,ooo, ppp,rrr-www,yyy, zzz,bbbb-hhhh\)](#); [curve, §6.1.2.3\(d\)](#); [image, §6.1.2.10\(b-f\)](#).

a. *The standard places no restrictions on the value of the spt attribute.*

Office requires that the spt attribute on an oval element have a value of 3. It is an error to specify this attribute as anything other than the default value, except for the shape and shapetype elements, which can handle any valid spt value.

b. *The standard states that chromakey and opacity are valid attributes on the oval element.*

Office does not support these attributes on this element.

c. *The standard states that the default value of the spt attribute is 0.*

Office uses a default value of 3 for the oval element. It is an error to specify this attribute as anything other than the default value, except for the shape and shapetype elements, which can handle any valid spt value.

d. *The standard places no restrictions on when the coordorigin and coordsize attributes are preserved on the oval element.*

Office only preserves these attributes when this element has at least one of the following children: a path with connection points specified in its connectlocs attribute; a path with a textbox specified in its textboxrect attribute; or handles.

2.1.1704 Part 4 Section 6.1.2.14, path (Shape Path)

For additional notes that apply to this portion of the standard, please see the notes for [background, §2.2.1\(a\)](#); [object, §2.3.3.19\(a\)](#); [pict, §2.3.3.21\(a\)](#); [pict, §2.9.23\(a\)](#); [arc, §6.1.2.1\(eeee\)](#); [group, §6.1.2.7\(a\)](#).

a. *The standard does not define the coordinate space for the pen positions.*

In Office, the coordinate space for pen movements is defined by the shape's coordinate space rectangle, as given by the coordsize and coordorigin attributes.

b. *The standard does not define units for the angle parameters for ellipses defined using the ae property of the v attribute.*

Office uses units of 1/65536 of a degree for the angle parameters for ellipses defined using the ae property of the v attribute.

c. The standard defines the properties for the *v* attribute.

Office uses additional commands to indicate desired application behavior when the object is edited by the user. An application that does not understand these commands may ignore, rewrite or remove them.

The following commands describe the desired application behavior for all points that follow the command during operations that move the object's points or associated line segments. These behaviors apply to vertices in the path (end points, not associated control points) depending on whether the associated line segment is a line or a curve.

| Command | Name | Parameters | Description | |
|-----------|----------------|------------|-----------------|-------------------|
| | | | Vertex behavior | Line segment type |
| <i>ha</i> | AutoLine | 0 | auto | line |
| <i>hb</i> | AutoCurve | 0 | auto | curve |
| <i>hc</i> | CornerLine | 0 | corner | line |
| <i>hd</i> | CornerCurve | 0 | corner | curve |
| <i>he</i> | SmoothLine | 0 | smooth | line |
| <i>hf</i> | SmoothCurve | 0 | smooth | curve |
| <i>hg</i> | SymmetricLine | 0 | symmetric | line |
| <i>hh</i> | SymmetricCurve | 0 | symmetric | curve |
| <i>hi</i> | Freeform | 0 | freeform | any |

The line segment type defines whether the command applies to points which are adjacent to lines or to points adjacent to curves. The vertex behavior specifies how the two line segments on either side of a point should behave as the point is moved.

| Vertex behavior | Curve control points should be calculated automatically | Control points should be equidistant from vertex | Control points should be co-linear with vertex | Control points should be visible to the user |
|-----------------|---|--|--|--|
| auto | Yes | N/A | N/A | No |
| symmetric | No | Yes | Yes | Yes |
| smooth | No | No | Yes | Yes |
| corner | No | No | No | Yes |
| freeform | No | No | No | Yes |

The auto vertex behavior is effectively the default behavior as it requires the application to provide the control points for the curve. The freeform vertex behavior is effectively user-defined as the application does not calculate control points.

d. The standard indicates that the last four values of the *at* property of the *v* attribute are radial vectors.

In Office, the last four values of the `at` property of the `v` attribute are points that define radial vectors with origins at the center of the bounding box.

e. *The standard does not fully explain how the `qb` property of the `v` attribute is used.*

Office requires that the `qb` property of the `v` attribute have a closed path. If the path is not closed, a new subpath shall exist after `qb`.

f. *The standard indicates how the `limo` attribute is used.*

Office does not support the `limo` attribute.

g. *The standard indicates how the `textboxrect` attribute is used.*

The following describes the Office requirements for this attribute:

Only one `textbox` is created for each shape. The rectangles defined by this attribute are used with text layout options to define the position of the `textbox` inside the shape.

If 4, 5 or more than 6 rectangles are defined, Office defaults to the shape's bounding box.

If the shape has no adjust handles, the rectangle chosen depends on the layout defined by the `layout-flow` property of the `style` attribute:

| Layout-flow | Number of Rectangles | Chosen Rectangle |
|------------------------|----------------------|------------------|
| Horizontal or Vertical | 1 | #1 |
| Horizontal | 2 | #1 |
| Vertical | 2 | #2 |
| Horizontal or Vertical | 3 | #1 |
| Horizontal | 6 | #1 |
| Vertical | 6 | #4 |

If the shape has adjust handles, the position of the `textbox` takes into account one or more rectangles defined here, the layout of the text and the position and range of the adjust handles. Office uses this data to choose a `textbox` position that conflicts least with the shape's path.

If more than one adjust handle is defined, only the first one is used. However, Office requires that the first handle defined in the file for the shape reference the first two values of the `adj` attribute of the shape.

[Note: For more information about adjust handles, see the `handles` element ("[\[ECMA-376\] Part 4 §6.1.2.9; handles \(Set of Handles\)](#)") and the `adj` attribute, such as on the `shape` element ("[\[ECMA-376\] Part 4 §6.1.2.19; shape \(Shape Definition\)](#)"). For more information about text layout, see the text layout properties in the `style` attribute of the `textbox` element ("[\[ECMA-376\] Part 4 §6.1.2.22; textbox \(Text Box\)](#)"). end note]

h. *The standard does not restrict the number of instances of the `path` element.*

Office allows at most only one instance of the `path` element in each place where it can be used.

2.1.1705 Part 4 Section 6.1.2.15, polyline (Multiple Path Line)

For additional notes that apply to this portion of the standard, please see the notes for [background, §2.2.1\(a\)](#); [arc, §6.1.2.1\(a-kk,mm-vv,aaa-jjj,lll,ooo, ppp,rrr-www.yyy, zzz,bbbb-hhhh\)](#); [curve, §6.1.2.3\(d\)](#); [image, §6.1.2.10\(b-f\)](#).

- a. *The standard places no restrictions on the value of the spt attribute.*

Office requires that the spt attribute on a polyline element have a value of 0. It is an error to specify this attribute as anything other than the default value, except for the shape and shapetype elements which can handle any valid spt value.

- b. *The standard states that chromakey and opacity are valid attributes on the polyline element.*

Office does not support these attributes on this element.

2.1.1706 Part 4 Section 6.1.2.16, rect (Rectangle)

For additional notes that apply to this portion of the standard, please see the notes for [background, §2.2.1\(a\)](#); [arc, §6.1.2.1\(a-kk,mm-vv,aaa-jjj,lll,ooo, ppp,rrr-www.yyy, zzz,bbbb-hhhh\)](#); [curve, §6.1.2.3\(d\)](#); [image, §6.1.2.10\(b-f\)](#).

- a. *The standard places no restrictions on the value of the spt attribute.*

Office requires that the spt attribute on a rect element have a value of 1. It is an error to specify this attribute as anything other than the default value, except for the shape and shapetype elements which can handle any valid spt value.

- b. *The standard states that chromakey and opacity are valid attributes on the rect element.*

Office does not support these attributes on this element.

- c. *The standard states that the default value of the spt attribute is 0.*

Office uses a default value of 1 for the rect element.

- d. *The standard places no restrictions on when the coordorigin and coordsize attributes are preserved on the rect element.*

Office only preserves these attributes when this element has at least one of the following children: a path with connection points specified in its connectlocs attribute; a path with a textbox specified in its textboxrect attribute; or handles.

2.1.1707 Part 4 Section 6.1.2.17, roundrect (Rounded Rectangle)

For additional notes that apply to this portion of the standard, please see the notes for [background, §2.2.1\(a\)](#); [arc, §6.1.2.1\(a-kk,mm-vv,aaa-jjj,lll,ooo, ppp,rrr-www.yyy, zzz,bbbb-hhhh\)](#); [curve, §6.1.2.3\(d\)](#); [image, §6.1.2.10\(b-f\)](#).

- a. *The standard places no restrictions on the value of the spt attribute.*

Office requires that the spt attribute on a roundrect element have a value of 2. It is an error to specify this attribute as anything other than the default value, except for the shape and shapetype elements which can handle any valid spt value.

- b. *The standard states that chromakey, coordorigin, and opacity are valid attributes on the roundrect element.*

Office does not support these attributes on this element.

c. *The standard states that the default value of the spt attribute is 0.*

Office uses a default value of 2 for the roundrect element.

2.1.1708 Part 4 Section 6.1.2.18, shadow (Shadow Effect)

For additional notes that apply to this portion of the standard, please see the notes for [background, §2.2.1\(a\)](#); [object, §2.3.3.19\(a\)](#); [pict, §2.3.3.21\(a\)](#); [pict, §2.9.23\(a\)](#); [arc, §6.1.2.1\(eeee\)](#); [group, §6.1.2.7\(a\)](#).

a. *The standard states that the values of the type attribute are defined by the ST_ShadowType simple type and some additional values.*

Office only allows the values defined in the ST_ShadowType simple type for this attribute.

b. *The standard does not specify bounds for the matrix attribute.*

In Office, these numeric values may be specified in 1/65536-ths if a trailing "f" is supplied. [Example: A value of "52429f" represents 52429/65536, or 0.8. end example] The minimum and maximum values for s_{xx} , s_{xy} , s_{yx} , s_{yy} , p_x , p_y are -2147483644f to 2147483647f.

c. *The standard does not indicate how the matrix attribute is applied to the shadow.*

Office applies this matrix to a point in the following way.

Let Q be a point in the object (after rotation, if the shape is rotated) described by $Q = [x \ y \ 1]$.

$$\text{Let } f = Q \cdot \begin{bmatrix} 1/p_x \\ 1/p_y \\ 1 \end{bmatrix} \text{ and } M = \begin{bmatrix} s_{xx} & s_{yx} & 0 \\ s_{xy} & s_{yy} & 0 \\ xoffset & yoffset & 1 \end{bmatrix}.$$

A new point Q' is calculated as $Q' = f \cdot (Q \cdot M)$.

In Office, if $p_x = 0$ and $p_y = 0$ then $f = 1$.

The origin for the coordinate system used here is defined by the **origin** attribute, which is dependent on the height and width of the shape.

d. *The standard indicates that drawingRelative and shapeRelative are valid simple type values for the type attribute.*

If the value of the type attribute is drawingRelative or shapeRelative, Office transforms the shadow to use a value of perspective on file save.

e. *The standard indicates that emboss is a valid simple type values for the type attribute.*

If the value of the type attribute is emboss and the offset or offset2 attribute is defined using fractional values of the shape dimensions, Office transforms the shadow to use a value of perspective on file save.

f. *The standard indicates how the obscured attribute is used.*

In Office, if the value of the obscured attribute is false, then the shadow is transparent if there is no fill on the shape.

g. *The standard indicates that the default value for the on attribute is true.*

In Office, if the on attribute value is blank, it is considered to be true. If it is absent, it defaults to false.

h. *The standard does not restrict the number of instances of this element.*

Office allows at most only one instance of the shadow element in each place where it can be used.

i. *The standard states that values of the opacity attribute are defined by the XML Schema string datatype.*

Office defines the values of the opacity attribute with the ST_Fraction ([§3.9.1, ST Fraction](#)) simple type.

2.1.1709 Part 4 Section 6.1.2.19, shape (Shape Definition)

For additional notes that apply to this portion of the standard, please see the notes for [background, §2.2.1\(a\)](#); [arc, §6.1.2.1\(a-kk,mm-vv,aaa-jjj,lll,ooo, ppp,rrr-www,yyy, zzz,bbbb-hhhh\)](#); [curve, §6.1.2.3\(d\)](#); [image, §6.1.2.10\(b-f\)](#).

a. *The standard does not document the format of the equationxml attribute.*

Word uses a specific format for the equationxml attribute as defined by Equation XML ([§3.8, Equation XML](#)).

b. *The standard indicates that the format of the gfxdata attribute is application-defined.*

Office formats this attribute as specified in the DrawingML Persistence Part ([§3.1.4, DrawingML Persistence Part](#)).

c. *The standard states that chromakey and opacity are valid attributes on the shape element.*

Office does not support these attributes on this element.

d. *The standard states that the values of the spt attribute are defined by the XML Schema float datatype.*

Office defines the values of this attribute with the ST_ShapeType ([§3.9.5, ST ShapeType](#)) simple type.

2.1.1710 Part 4 Section 6.1.2.20, shapetype (Shape Template)

For additional notes that apply to this portion of the standard, please see the notes for [background, §2.2.1\(a\)](#); [arc, §6.1.2.1\(a-kk,mm-vv,aaa-jjj,lll,ooo, ppp,rrr-www,yyy, zzz,bbbb-hhhh\)](#); [curve, §6.1.2.3\(d\)](#); [image, §6.1.2.10\(b-f\)](#).

a. *The standard indicates how the master attribute is used.*

Office considers the presence and absence of this attribute to represent true and false values, respectively. If this attribute exists and is set to any value, including an empty string, Office considers it to be true.

b. *The standard states that chromakey and opacity are valid attributes on the shapetype element.*

Office does not support these attributes on this element.

2.1.1711 Part 4 Section 6.1.2.21, stroke (Line Stroke Settings)

For additional notes that apply to this portion of the standard, please see the notes for [background, §2.2.1\(a\)](#); [object, §2.3.3.19\(a\)](#); [pict, §2.3.3.21\(a\)](#); [pict, §2.9.23\(a\)](#); [arc, §6.1.2.1\(eeee\)](#); [group, §6.1.2.7\(a\)](#).

- a. *The standard indicates the endcap attribute is used for any path.*

Office requires that the shape's path is open for the endcap attribute to work.

- b. *The standard indicates how the althref attribute is used.*

Office does not persist the althref value on file save. The value of althref replaces the value of the src attribute on file save if the href attribute is not defined.

- c. *The standard indicates how the href attribute is used.*

Office does not persist the href value on file save. The value of href replaces the value of the src attribute on file save if the href attribute is not defined.

- d. *The standard does not specify bounds for the miterlimit attribute.*

Office has a maximum allowed value of 32767 for the miterlimit attribute.

- e. *The standard indicates how the src attribute is used.*

On file save, Office replaces the value of the src attribute with the value of the href attribute, if defined, or the althref attribute href is not defined.

- f. *The standard does not specify bounds for the weight attribute.*

In Office, the minimum value is zero and the maximum value is 20116800 EMU for the weight attribute.

- g. *The standard states that the values of the filltype attribute are defined by the ST_FillType simple type.*

Office does not support the values of gradient or gradientRadial.

- h. *The standard indicates that the default value for the weight attribute is 1 pt.*

Office uses a default value of 0.75 pt for the weight attribute.

- i. *The standard indicates that relid is a valid attribute.*

Office does not support the relid attribute.

- j. *The standard does not restrict the number of instances of the stroke element.*

Office allows at most only one instance of the stroke element in each place where it can be used.

- k. *The standard states that values of the opacity attribute are defined by the XML Schema string datatype.*

Office defines the values of this attribute with the ST_Fraction ([§3.9.1, ST Fraction](#)) simple type.

l. The standard states that the values of the *miterlimit* attribute are defined by the XML Schema decimal datatype.

Office defines the values of this attribute with the *ST_Fraction* (§3.9.1, *ST_Fraction*) simple type.

2.1.1712 Part 4 Section 6.1.2.22, *textbox* (Text Box)

For additional notes that apply to this portion of the standard, please see the notes for [background, §2.2.1\(a\)](#); [object, §2.3.3.19\(a\)](#); [pict, §2.3.3.21\(a\)](#); [pict, §2.9.23\(a\)](#); [arc, §6.1.2.1\(eeee\)](#); [background, §6.1.2.2\(c\)](#); [group, §6.1.2.7\(a\)](#).

a. The standard indicates that the only allowed value for the *mso-direction-alt* property of the style attribute is *context*.

Only Excel supports the *mso-direction-alt* property and it only supports the value *auto*.

b. The standard indicates how the *mso-next-textbox* property of the style attribute is used.

Only Word supports the *mso-next-textbox* property.

c. The standard indicates that the only valid value for the *mso-layout-flow-alt* property of the style attribute is *bottom-to-top*.

In Office, the *mso-layout-flow-alt* property of the style attribute supports the following additional property values:

| Property | Description |
|----------------------------|---|
| <i>mso-layout-flow-alt</i> | <p>This property is used for specifying vertical text direction instead of <i>layout-flow</i> when the layout flow is from bottom to top or from top to bottom for non-ideographic languages. Allowed values are:</p> <p><i>bottom-to-top</i> - Text is displayed</p> <p><i>top-to-bottom</i> - Text is displayed</p> <p>Excel interprets <i>top-to-bottom</i> to indicate stacked text; this is handled in a different manner than in Word.</p> <p>[Example: Text flowing from bottom to top: <code><v:textbox style="layout-flow:vertical; mso-layout-flow-alt:bottom-to-top"></code></p> <div data-bbox="418 1392 573 1493" style="border: 1px solid black; padding: 5px; width: fit-content; margin: 10px auto;"> <p style="text-align: center;">VMIL</p> </div> <p>end example]</p> <p>[Example: Text flowing from top to bottom: <code><v:textbox style="layout-flow:vertical; mso-layout-flow-alt:top-to-bottom"></code></p> |

| Property | Description |
|----------|--|
| | <div data-bbox="418 205 573 302" style="border: 1px solid black; padding: 2px; width: fit-content;">V M L</div> <p data-bbox="418 310 573 338">end example]</p> <p data-bbox="418 346 980 373">[Example: Text flowing from top to bottom in Excel:</p> <pre data-bbox="418 380 846 443" style="font-family: monospace;"><v:textbox style="layout-flow:vertical; mso-layout-flow-alt:top-to-bottom"></pre> <div data-bbox="418 449 550 604" style="border: 1px solid black; padding: 2px; width: fit-content;">V M L</div> <p data-bbox="418 613 573 640">end example]</p> <p data-bbox="418 648 873 676">[Example: Text flowing vertically in Excel:</p> <pre data-bbox="418 682 862 709" style="font-family: monospace;"><v:textbox style="layout-flow:vertical"></pre> <div data-bbox="418 783 573 879" style="border: 1px solid black; padding: 2px; width: fit-content;">V M L</div> <p data-bbox="418 888 573 915">end example]</p> |

d. *The standard indicates the values for the mso-rotate property of the style attribute.*

Office does not support the mso-rotate property and does not preserve the value -90 on file save.

e. *The standard indicates states that any element in the ##local namespace is a valid child of the textbox element without explaining how this is used.*

Excel writes text and text formatting as HTML within the textbox element.

f. *The standard indicates that the inset attribute is used if the value of insetmode attribute is "custom".*

Excel uses the value of the insetmode attribute on the parent element to determine if the inset attribute is used. Word always uses the inset attribute regardless of the value of the insetmode attribute.

g. *The standard indicates how the singleclick attribute is used.*

Office does not support the singleclick attribute.

h. *The standard implies that all properties on the style attribute apply to the textbox element.*

Office only supports the following properties on the textbox element: direction, layout-flow, mso-direction-alt, mso-fit-shape-to-text, mso-fit-text-to-shape, mso-layout-flow-alt, mso-next-textbox, mso-rotate, mso-text-scale, and v-text-anchor.

i. *The standard states that insetmode is a valid attribute.*

Office does not support this attribute.

j. *The standard does not restrict the number of instances of the textbox element.*

Office allows at most only one instance of the textbox element in each place where it can be used.

k. *The standard indicates how the mso-fit-text-to-shape property of the style attribute is used.*

Office does not support the mso-fit-text-to-shape property.

2.1.1713 Part 4 Section 6.1.2.23, textpath (Text Layout Path)

For additional notes that apply to this portion of the standard, please see the notes for [background, §2.2.1\(a\)](#); [object, §2.3.3.19\(a\)](#); [pict, §2.3.3.21\(a\)](#); [pict, §2.9.23\(a\)](#); [arc, §6.1.2.1\(eeee\)](#); [background, §6.1.2.2\(c\)](#); [group, §6.1.2.7\(a\)](#).

a. *The standard indicates that the default value for the v-text-align property of the style attribute is left.*

Office uses a default value of center for the v-text-align property of the style attribute.

b. *The standard implies that all properties on the style attribute apply to the textpath element.*

Office only supports the following properties on the textbox element: font, font-family, font-size, font-style, font-variant, font-weight, mso-text-shadow, text-direction, v-rotate-letters, v-same-letter-heights, v-text-align, v-text-kern, v-text-reverse, v-text-spacing-mode, and v-text-spacing.

c. *The standard indicates that the default value for the mso-text-shadow property of the style attribute is false.*

Office uses a default value of none for the mso-text-shadow property of the style attribute.

d. *The standard implies that changing the value of the font-size property of the style attribute changes the size of the textpath.*

Office uses the *width* and *height* properties of the parent shape's **style** attribute to determine the area into which the text path is rendered. If the value of *font-size* is increased, then the *width* and *height* on the parent shape are also required to be increased to accommodate the larger *font-size* value.

e. *The standard indicates how the text-decoration property of the style attribute is used.*

Office does not support the text-decoration property, but does preserve its value on file save.

f. *The standard indicates how the font-variant property of the style attribute is used.*

Office does not support the font-variant property, but does preserve its value on file save.

g. *The standard indicates that the default value for the v-text-spacing property of the style attribute is 100.*

Office uses a default value of 1 for the v-text-spacing property of the style attribute.

h. *The standard indicates that the default value for the v-text-spacing-mode property of the style attribute is tightening.*

Office uses a default value of tracking for the v-text-spacing-mode property of the style attribute.

i. *The standard does not restrict the number of instances of the textpath element.*

Office allows at most only one instance of the textpath element in each place where it can be used.

j. *The standard implies the valid values for the mso-text-shadow property of the style attribute.*

Office supports the values auto and none for the mso-text-shadow property of the style attribute.

k. *The standard does not specify bounds for the v-text-spacing property of the style attribute.*

Office supports a minimum value of 0 and a maximum value of 5. A value larger than 1.0 means expanded spacing while a value less than 1.0 means condensed spacing.

l. *The standard implies that the v-text-spacing property of the style attribute is specified using unitless numbers.*

Office also supports specifying this property as a percentage in the range 0% through 500%. This numeric value may also be specified in 1/65536ths if a trailing "f" is supplied. For example, a value of "52429f" represents 52429/65536 or 0.8. Using this notation, the range of acceptable values is from 0f through 327680f.

2.1.1714 Part 4 Section 6.1.3.1, ST_ColorType (Color Type)

a. *The standard does not indicate the valid color palette entry names for the ST_ColorType simple type.*

In Office, the following color palette entries are supported:

ButtonFace

WindowText

Menu

Highlight

HighlightText

CaptionText

ActiveCaption

ButtonHighlight

ButtonShadow

ButtonText

GrayText

InactiveCaption

InactiveCaptionText

InfoBackground

InfoText

MenuText

Scrollbar

Window

WindowFrame

ThreeDLightShadow

ThreeDDarkShadow

ActiveBorder

InactiveBorder

Background

AppWorkspace

ThreeDFace (represents the same color as *ButtonFace*)

ThreeDShadow (represents the same color as *ButtonShadow*)

ThreeDHighlight (represents the same color as *ButtonHighlight*)

[Example:

```
<... color="InactiveCaption" ... >
```

end example]

b. *The standard indicates the kinds of values that the ST_ColorType simple type uses.*

In Office, decimal RGB is specified using "rgb" followed by three comma-separated values in parentheses. These values are an ordered set in the range 0-255 and represent the red, green, and blue components of the color.

[Example:

```
< ... color="rgb(95,39,38)" ... >
```

end example]

c. *The standard indicates the kinds of values that the ST_ColorType simple type uses.*

In Office, a color palette entry is specified using "wincolor" followed by a number in parentheses. The number is the zero-based index of a color in the supported color palette.

[Example:

```
<... color="wincolor(11)" ... >
```

end example]

d. *The standard indicates the kinds of values that the ST_ColorType simple type uses.*

In Office, a shape property is specified using the name of the shape color property. The following properties are supported:

| Property | Description |
|---------------------|--|
| <i>fill</i> | Fill color |
| <i>line</i> | Line color |
| <i>lineOrFill</i> | Line color if specified, otherwise, the fill color |
| <i>fillThenLine</i> | Fill color if specified, otherwise, the line color |
| <i>fillBack</i> | Fill background color |
| <i>lineBack</i> | Line background color |
| <i>shadow</i> | Shadow color |
| <i>none</i> | No color |

[Example:

```
<... color="lineOrFill" ... >
```

end example]

e. *The standard indicates the kinds of values that the ST_ColorType simple type uses.*

In Office, recoloring instructions indicate that the given color is to be modified a particular amount. The instruction consists of a named instruction followed by the amount, a number in the range 0-255, in parenthesis. The instructions are:

darken

lighten

add

subtract

reverseSubtract

blackWhite

invert

invert128

grayScale

Office supports recoloring instructions in the following way. Let A represent the amount argument to the recoloring instruction.

| Instruction | Description |
|---------------|--------------------------------------|
| <i>darken</i> | Scale each color component by A/256. |

| Instruction | Description |
|------------------------|--|
| <i>lighten</i> | Scale the inverse of each color component by $A/256$, then invert the result. |
| <i>add</i> | Add A to each color component, limited to a maximum value of 255. |
| <i>subtract</i> | Subtract A from each color component, limited to a minimum value of 0. |
| <i>reverseSubtract</i> | Subtract each color component from A, limited to a minimum value of 0. |
| <i>blackWhite</i> | A color component is 0 if less than A, otherwise 255. |
| <i>invert</i> | Subtract each color component from 255. |
| <i>invert128</i> | For each color component less than 128, subtract 128 from it, otherwise add 128 to it. |
| <i>grayScale</i> | Convert the color to a grayscale equivalent. |

Office does not save the amount argument for the *invert*, *invert128* and *grayScale* recoloring instructions.

[Example: The color is darker than the fill color by 50 units:

```
<... color="fill darken(50)">
```

end example]

2.1.1715 Part 4 Section 6.1.3.3, ST_Ext (VML Extension Handling Behaviors)

a. The standard indicates the valid values for the *ST_Ext* simple type.

In Office, the following elements support only the *View* value:

top ("ECMA-376 Part 4 §6.2.2.31; top")

bottom ("ECMA-376 Part 4 §6.2.2.1; bottom")

left ("ECMA-376 Part 4 §6.2.2.15; left")

right ("ECMA-376 Part 4 §6.2.2.25; right")

column ("ECMA-376 Part 4 §6.2.2.6; column")

complex ("ECMA-376 Part 4 §6.2.2.7; complex")

extrusion ("ECMA-376 Part 4 §6.2.2.10; extrusion")

fill ("ECMA-376 Part 4 §6.2.2.12; fill")

skew ("ECMA-376 Part 4 §6.2.2.30; skew")

b. The standard indicates the valid values for the *ST_Ext* simple type.

In Office, the following elements support only the *Edit* value:

callout (“[\[ECMA-376\]](#) Part 4 §6.2.2.2; callout”)

colormenu (“[\[ECMA-376\]](#) Part 4 §6.2.2.4; colormenu”)

colormru (“[\[ECMA-376\]](#) Part 4 §6.2.2.5; colormru”)

diagram (“[\[ECMA-376\]](#) Part 4 §6.2.2.8; diagram”)

idmap (“[\[ECMA-376\]](#) Part 4 §6.2.2.13; idmap”)

lock (“[\[ECMA-376\]](#) Part 4 §6.2.2.17; lock”)

regrouptable (“[\[ECMA-376\]](#) Part 4 §6.2.2.22; regrouptable”)

rel (“[\[ECMA-376\]](#) Part 4 §6.2.2.23; rel”)

reliontable (“[\[ECMA-376\]](#) Part 4 §6.2.2.24; relationtable”)

rules (“[\[ECMA-376\]](#) Part 4 §6.2.2.26; rules”)

shapedefaults (“[\[ECMA-376\]](#) Part 4 §6.2.2.27; shapedefaults”)

shapelayout (“[\[ECMA-376\]](#) Part 4 §6.2.2.28; shapelayout”)

signatureline (“[\[ECMA-376\]](#) Part 4 §6.2.2.29; signatureline”)

2.1.1716 Part 4 Section 6.1.3.4, ST_FillMethod (Gradient Fill Computation Type)

- a. *The standard indicates that the any value is an application default fill.*
Office uses linear sigma as its application default fill.

2.1.1717 Part 4 Section 6.1.3.5, ST_FillType (Shape Fill Type)

- a. *The standard indicates how the pattern enumeration value is used.*
Office uses the fill colors but also tiles the fill image.

2.1.1718 Part 4 Section 6.1.3.7, ST_ShadowType (Shadow Type)

- a. *The standard lists four valid values for the ST_ShadowType simple type.*

In addition to the two values specified by the standard, Office supports the following additional enumeration values for the ST_ShadowType simple type:

| Enumeration Value | Description |
|---|--|
| drawingRelative (Drawing Shadow) | A perspective shadow is cast relative to the drawing space of the shape. |
| shapeRelative (Shape Shadow) | A perspective shadow is cast and scaled relative to the shape. |

2.1.1719 Part 4 Section 6.2.2.1, bottom (Text Box Bottom Stroke)

For additional notes that apply to this portion of the standard, please see the notes for [background, §2.2.1\(a\)](#); [object, §2.3.3.19\(a\)](#); [pict, §2.3.3.21\(a\)](#); [pict, §2.9.23\(a\)](#); [hdrShapeDefaults, §2.15.1.50\(a\)](#); [shapeDefaults, §2.15.1.79\(a\)](#); [column, §6.2.2.6\(a\)](#).

a. *The standard indicates the conditions under which the bottom element is displayed.*

In Office, the bottom element will only be displayed if all of the following conditions are met:

The **on** attribute is *true*.

The shape's path is closed with the *x* command. [Note: This implies that arrow heads should be defined on the stroke attribute. end note]

The shape's path defines a rectangle with corner coordinates exactly equal to 0,0; 21600,0; 21600,21600; 0,21600. [Example: For example, the following value on the **path** attribute of the **shape** element ("[ECMA-376](#) Part 4 §6.1.2.19; shape") satisfies this condition:
`path="m,1,21600r21600,121600,x" end example]`

The value of the shape's **spt** attribute is 202.

The shape is not stroked.

[Note: The shape is not stroked if one of the following conditions is true:

The value of the **on** attribute of the **stroke** element ("[ECMA-376](#) Part 4 §6.1.2.21; stroke") is *false*.

The **on** attribute of the **stroke** element is absent and the value of the shape's **stroked** attribute is *false*.

The **on** attribute of the **stroke** element is absent, the shape's **stroked** attribute is absent and the value of the **stroked** attribute of the **shapetype** element ("[ECMA-376](#) Part 4 §6.1.2.20; shapetype") is *false*.

end note]

b. *The standard indicates how the src attribute is used.*

Office replaces the value of the *src* attribute with the value of the *href* attribute, if defined, or the *althref* attribute if *href* is not defined.

c. *The standard indicates in the on attribute the conditions under which the bottom element is displayed.*

In Office the bottom element is only displayed if the *on* attribute is true, if the shape's path is closed with the *x* command, and the shape is not stroked.

d. *The standard indicates how the href attribute is used.*

Office does not persist this value on file save. The *href* attribute value replaces the value of the *src* attribute on file save.

e. *The standard indicates how the althref attribute is used.*

Office does not persist the *althref* value on file save. The *althref* attribute value replaces the value of the *src* attribute on file save if the *href* attribute is not defined.

f. *The standard states that imageaspect is a valid attribute on this element.*

Office does not support this attribute on this element; if a value other than ignore is specified, a value of 0,0 will be applied to the imagesize attribute.

g. *The standard indicates how the imagesize attribute is used.*

This attribute is specified as a string of two numbers separated by a space, colon, semicolon or comma. The valid unit ranges for the numbers are defined in section 6.1. If these limits are not respected, Office writes a value of "0,0" on file save.

If more than two values are defined, only the two first values are used and saved.

h. *The standard does not specify bounds for the weight attribute.*

In Office, the minimum value for the weight attribute is zero and the maximum value is 20116800 EMU.

i. *The standard does not specify bounds for the miterlimit attribute.*

Office uses a maximum value of 32767 for the miterlimit attribute.

j. *The standard indicates that the default value for the weight attribute is 1 pt.*

Office uses a default of 0.75 pt for the weight attribute.

k. *The standard states that values of the opacity attribute are defined by the XML Schema string datatype.*

Office defines the values of the opacity attribute with the ST_Fraction ([§3.9.1, ST Fraction](#)) simple type.

2.1.1720 Part 4 Section 6.2.2.2, callout (Callout)

For additional notes that apply to this portion of the standard, please see the notes for [background, §2.2.1\(a\)](#); [object, §2.3.3.19\(a\)](#); [pict, §2.3.3.21\(a\)](#); [pict, §2.9.23\(a\)](#); [hdrShapeDefaults, §2.15.1.50\(a\)](#); [shapeDefaults, §2.15.1.79\(a\)](#); [group, §6.1.2.7\(a\)](#).

a. *The standard does not imply a relationship between the callout element and the spt attribute.*

In Office, this element specifies the automatic behavior and layout parameters of callout shapes. In Office, objects that have this attribute shall be made of one to three segments plus the shape itself. The number of segments is defined by the **type** attribute. See additional restrictions defined in the **type** attribute description. Shapes with callouts shall define values for the **spt** attribute of the **shape** element ("[\[ECMA-376\] Part 4 §6.1.2.19; shape \(Shape Definition\)](#)") or **shapetype** element ("[\[ECMA-376\] Part 4 §6.1.2.20; shapetype \(Shape Template\)](#)") as follows:

| Attribute value | | Value of type attribute | | | |
|-----------------|------------|-------------------------|------------|--------------|------------|
| accentbar | textborder | oneSegment | twoSegment | threeSegment | rightAngle |
| False | False | spt="41" | spt="42" | spt="43" | spt="178" |
| True | False | spt="44" | spt="45" | spt="46" | spt="179" |
| False | True | spt="47" | spt="48" | spt="49" | spt="180" |
| True | True | spt="50" | spt="51" | spt="52" | spt="181" |

b. *The standard indicates how the type attribute is used.*

For Office, the type attribute specifies the design of the callout extension. The allowed values are:

rightAngle

oneSegment

twoSegment (default value)

threeSegment

Callout shapes that contain the **callout** element work only if the first sub-path in the shape's path is used to model the callout extension. This sub-path shall contain references to *N* formulas that reference *N* adjust values, where $N = 2M + 2$, and *M* is the number of segments in the callout.

[Example: The callout has two values for every vertex in the extension's segments – one for the *x* coordinate and one for the *y* coordinate. If the value of the **type** attribute is *rightAngle*, there are two segments. end example]

Office also requires one handle for every segment vertex. The number of handles should be at least $N/2$.

See also the **path** element ("[ECMA-376](#) Part 4 §6.1.2.14; path (Shape Path)") and the **handles** element ("[ECMA-376](#) Part 4 §6.1.2.9; handles (Set of Handles)").

c. The standard indicates how the *accentbar* attribute is used.

Office requires that the accent bar be a line sub-path, added after the first callout segment (see the **type** attribute). The segment is defined in the shape's path.

[Example: Consider the following shape that consists of a single segment callout and a vertical accent bar.



The following snippet is one possible way to describe the shape's path:

```
<v:shape ... coordsize="21600,21600" o:spt="44" adj="-8280,24300,-1800,4050"
path="m@0@11@2@3nfem@2,1@2,21600nfem,121600,r,21600l,21600nsxe" ... >
</v:shape>
```

The first subpath, *m@0@11@2@3nfe*, describes the callout segment and the second, *m@2,1@2,21600nfe*, describes the accent bar. The third subpath describes the rectangle. end example]

See also the **path** element ("[ECMA-376](#) Part 4 §6.1.2.14; path").

d. The standard indicates how the *angle* attribute is used.

Office applies the angle attribute value only to the first segment of the callout extension and enforces this only during user interaction at runtime when the user interacts with the application UI.

e. The standard indicates how the *drop* attribute is used.

Office only enforces the drop attribute during user interaction at runtime.

f. *The standard indicates how the dropauto attribute is used.*

The dropauto attribute is only supported by Word and only when the value of the drop attribute is user and the value of the type attribute is not rightAngle.

g. *The standard does not define a default value for the drop attribute.*

Office uses a default value of user for the drop attribute.

h. *The standard indicates how the gap attribute is used.*

In Office, the gap attribute is only enforced at runtime when the user interacts with the application UI.

i. *The standard indicates how the textborder attribute is used.*

In Office, the textborder attribute reflects the type of stroke used for the textbox. If it is set to false, the shape's path shall also contain ns (no stroke). For more information, see the v attribute of the path element.

j. *The standard indicates how the distance attribute is used.*

Office only enforces the distance attribute during user interaction at runtime.

k. *The standard indicates how the length attribute is used.*

Office only enforces the length attribute during user interaction at runtime.

l. *The standard does not restrict the number of instances of this element.*

Office allows at most only one instance of the callout element in each place where it can be used.

m. *The standard does not define a default value for the dropauto attribute.*

Office uses a default value of false for the dropauto attribute.

2.1.1721 Part 4 Section 6.2.2.3, clippath (Shape Clipping Path)

For additional notes that apply to this portion of the standard, please see the notes for [background, §2.2.1\(a\)](#); [object, §2.3.3.19\(a\)](#); [pict, §2.3.3.21\(a\)](#); [pict, §2.9.23\(a\)](#); [hdrShapeDefaults, §2.15.1.50\(a\)](#); [shapeDefaults, §2.15.1.79\(a\)](#).

a. *The standard describes how the v attribute is used.*

Office treats this attribute the same as the v attribute in the path element.

b. *The standard does not restrict the number of instances of this element.*

Office allows at most only one instance of the clippath element in each place where it can be used.

2.1.1722 Part 4 Section 6.2.2.4, colormenu (UI Default Colors)

a. *The standard provides the default value for the extrusioncolor attribute.*

Office uses the default value of fillThenLine for the extrusioncolor attribute.

b. *The standard provides the default value for the fillcolor attribute.*

Office uses a default value of FFFF00 for the fillcolor attribute.

c. *The standard provides the default value for the shadowcolor attribute.*

Office uses a default value of 808080 for the shadowcolor attribute.

d. *The standard provides the default value for the strokecolor attribute.*

Office uses a default value of 0000FF for the strokecolor attribute.

e. *The standard does not restrict the number of instances of this element.*

Office allows at most only one instance of the colormenu element in each place where it can be used.

2.1.1723 Part 4 Section 6.2.2.5, colormru (Most Recently Used Colors)

a. *The standard does not restrict the number of instances of this element.*

Office allows at most only one instance of the colormru element in each place where it can be used.

2.1.1724 Part 4 Section 6.2.2.6, column (Text Box Interior Stroke)

For additional notes that apply to this portion of the standard, please see the notes for [background, §2.2.1\(a\)](#); [object, §2.3.3.19\(a\)](#); [pict, §2.3.3.21\(a\)](#); [pict, §2.9.23\(a\)](#); [hdrShapeDefaults, §2.15.1.50\(a\)](#); [shapeDefaults, §2.15.1.79\(a\)](#); [bottom, §6.2.2.1\(b,d-k\)](#).

a. *The standard indicates the conditions under which the column element is displayed.*

In Office, this element is only displayed if all of the following conditions are met:

The **on** attribute is *true*.

The shape's path is closed with the x command. [Note: This implies that arrow heads should be defined on the stroke attribute. end note]

The shape's path defines a rectangle with corner coordinates exactly equal to 0,0; 21600,0; 21600,21600; 0,21600. [Example: For example, the following value on the **path** attribute of the **shape** element ("[ECMA-376](#) Part 4 §6.1.2.19; shape (Shape Definition)") satisfies this condition: path="m,1,21600r21600,121600,x" end example]

The value of the shape's **spt** attribute is 202.

The shape is not stroked.

If the **on** attribute is *false* or not specified, the border is not shown.

[Note: The shape is not stroked if one of the following conditions is true:

The value of the **on** attribute of the **stroke** element ("[ECMA-376](#) Part 4 §6.1.2.21; stroke (Line Stroke Settings)") is *false*.

The **on** attribute of the **stroke** element is absent and the value of the shape's **stroked** attribute is *false*.

The **on** attribute of the **stroke** element is absent, the shape's **stroked** attribute is absent and the value of the **stroked** attribute of the **shapetype** element ("[ECMA-376] Part 4 §6.1.2.20; shapetype (Shape Template)") is *false*.

end note]

2.1.1725 Part 4 Section 6.2.2.7, complex (Complex)

For additional notes that apply to this portion of the standard, please see the notes for [background, §2.2.1\(a\)](#); [object, §2.3.3.19\(a\)](#); [pict, §2.3.3.21\(a\)](#); [pict, §2.9.23\(a\)](#); [hdrShapeDefaults, §2.15.1.50\(a\)](#); [shapeDefaults, §2.15.1.79\(a\)](#).

2.1.1726 Part 4 Section 6.2.2.8, diagram (VML Diagram)

For additional notes that apply to this portion of the standard, please see the notes for [background, §2.2.1\(a\)](#); [object, §2.3.3.19\(a\)](#); [pict, §2.3.3.21\(a\)](#); [pict, §2.9.23\(a\)](#); [hdrShapeDefaults, §2.15.1.50\(a\)](#); [shapeDefaults, §2.15.1.79\(a\)](#).

a. *The standard indicates that the **dgmscalex** attribute behavior is application-specific.*

In Office, **dgmscalex** informs the horizontal distance between shapes when the diagram is resized. Office considers this value in conjunction with the **dgmscaley** attribute to determine the position of shapes during a resize action.

b. *The standard indicates that the **dgmscalex** attribute behavior is application-specific, and does not specify a default value.*

In Office the **dgmscalex** attribute uses a default of 65536, which means a 1:1 scale in x. Larger values indicate a larger distance between shapes, and smaller values indicate a smaller distance.

c. *The standard indicates that the **dgmscaley** attribute behavior is application-specific.*

In Office, **dgmscaley** informs the vertical distance between shapes when the diagram is resized. Office considers this value in conjunction with the **dgmscalex** attribute to determine the position of shapes during a resize action.

d. *The standard indicates that the **dgmscaley** attribute behavior is application-specific, and does not specify a default value.*

In Office the **dgmscaley** attribute uses a default of 65536, which means a 1:1 scale in y. Larger values indicate a larger distance between shapes, and smaller values indicate a smaller distance.

e. *The standard does not define a default value for the **dgmbasetextscale** attribute.*

In Office the **dgmbasetextscale** attribute uses a default value of 65536, which means a 1:1 scale.

f. *The standard indicates how the **dgmbasetextscale** attribute is used.*

Office uses the **dgmbasetextscale** attribute to specify the new font size relative to the default font size.

g. *The standard indicates that the **constrainbounds** attribute behavior is application-specific.*

Office uses the constrainbounds attribute to fit the diagram to its container bounds. The rectangle defined by this attribute shall be inside the current diagram bounds defined by the coordorigin and coordsize attributes.

h. *The standard indicates that the dgmstyle attribute behavior is application-specific.*

Office ignores the dgmstyle attribute on file load and does not guarantee preserving it on file save. Office relies on the regular formatting markup on the shape to determine if formatting properties exist on the shape.

i. *The standard does not restrict the number of instances of this element.*

Office allows at most only one instance of the diagram element in each place where it can be used.

2.1.1727 Part 4 Section 6.2.2.10, extrusion (3D Extrusion)

For additional notes that apply to this portion of the standard, please see the notes for [background, §2.2.1\(a\)](#); [object, §2.3.3.19\(a\)](#); [pict, §2.3.3.21\(a\)](#); [pict, §2.9.23\(a\)](#); [hdrShapeDefaults, §2.15.1.50\(a\)](#); [shapeDefaults, §2.15.1.79\(a\)](#); [group, §6.1.2.7\(a\)](#).

a. *The standard does not specify bounds for the backdepth attribute.*

In Office the minimum value for the backdepth attribute is 0 pt and the maximum value is 9600 pt.

b. *The standard does not specify bounds for the foredepth attribute.*

In Office the minimum value for the foredepth attribute is 0 pt and the maximum value is 600 pt.

c. *The standard indicates that the color attribute is only used when colormode is custom.*

Office uses the color attribute when colormode is custom or auto.

d. *The standard indicates that the colormode attribute determines where the extrusion color is defined.*

Office does not support the colormode attribute. The extrusion color is the color defined by the color attribute. If the color attribute is not defined, the shape's fill color is used.

e. *The standard does not specify bounds for the edge attribute.*

In Office the minimum value for the edge attribute is 0 pt and the maximum value is 169093 pt.

f. *The standard indicates the meaning of the range of values for the facet attribute.*

In Office, a lower facet value produces shapes with smoother curves. A higher value reduces smoothing, resulting in curves with sharper, jagged edges. This value may be specified in 1/65536ths if a trailing "f" is supplied. The default is 30000f.


Values should be from 1f to 32767f, where 1f implies extremely high quality curve approximation and 32767f implies extremely low quality.

[Example:

```
<o:extrusion on="true" facet="1f">
</o:extrusion>
```



facet="1f"



facet="32767f"

end example]

g. *The standard does not specify bounds for the orientationangle attribute.*

In Office the value of the orientationangle attribute may be specified in 1/65536ths if a trailing "f" is supplied. The minimum value is -32767f and the maximum value is 32767f.

h. *The standard does not specify bounds for the rotationangle attribute.*

In Office the minimum value for the rotationangle attribute is -90 and the maximum value is 90.

i. *The standard indicates that the plane attribute determines the extrusion direction.*

Office does not support the plane attribute.

j. *The standard does not specify bounds for the axes specified in the rotationcenter attribute.*

In Office, the minimum and maximum numeric values for the x- and y-axes are -32767 and 32767, regardless of which units are used. The limits for the z-axis value are given by the table in ("[ECMA-376](#) Part 4 §6.1; VML").

k. *The standard does not specify bounds for the skewangle attribute.*

In Office the minimum value for the skewangle attribute is -32767 and the maximum value is 32767.

l. *The standard does not restrict the number of instances of this element.*

Office allows at most only one instance of the extrusion element in each place where it can be used.

m. *The standard states that values of the brightness attribute are defined by the XML Schema string datatype.*

Office defines the values of the brightness attribute with the ST_Fraction ([§3.9.1, ST_Fraction](#)) simple type.

n. *The standard states that values of the diffusivity attribute are defined by the XML Schema string datatype.*

Office defines the values of the diffusivity attribute with the ST_Fraction (§3.9.1, ST_Fraction) simple type.

o. *The standard states that values of the lightlevel attribute are defined by the XML Schema string datatype.*

Office defines the values of the lightlevel attribute with the ST_Fraction (§3.9.1, ST_Fraction) simple type.

p. *The standard states that values of the lightlevel2 attribute are defined by the XML Schema string datatype.*

Office defines the values of the lightlevel2 attribute with the ST_Fraction (§3.9.1, ST_Fraction) simple type.

q. *The standard states that values of the specularity attribute are defined by the XML Schema string datatype.*

Office defines the values of the specularity attribute with the ST_Fraction (§3.9.1, ST_Fraction) simple type.

2.1.1728 Part 4 Section 6.2.2.11, FieldCodes (WordprocessingML Field Switches)

a. *The standard does not specify a default value for the FieldCodes element.*

Office uses a default of no value for the FieldCodes element.

2.1.1729 Part 4 Section 6.2.2.12, fill (Shape Fill Extended Properties)

For additional notes that apply to this portion of the standard, please see the notes for [background](#), [§2.2.1\(a\)](#); [object](#), [§2.3.3.19\(a\)](#); [pict](#), [§2.3.3.21\(a\)](#); [pict](#), [§2.9.23\(a\)](#); [hdrShapeDefaults](#), [§2.15.1.50\(a\)](#); [shapeDefaults](#), [§2.15.1.79\(a\)](#).

a. *The standard indicates how the type attribute is used.*

Office has the following behavior:

If the value of this attribute is *background*, then the value of the **type** attribute on the parent **fill** element ("[ECMA-376](#) Part 4 §6.1.2.5; fill (Shape Fill Properties)") is set to *solid* on file save.

If the value of this attribute is *gradientCenter*, then the value of the **type** attribute on the parent **fill** element ("[ECMA-376](#) Part 4 §6.1.2.5; fill (Shape Fill Properties)") is set to *gradientRadial* on file save.

If the value of this attribute is *gradientUnscaled*, then the value of the **type** attribute on the parent **fill** element ("[ECMA-376](#) Part 4 §6.1.2.5; fill (Shape Fill Properties)") is set to *gradient* on file save.

If the value of this attribute is *solid*, then neither this **fill** element nor the **type** attribute on the parent **fill** element ("[ECMA-376](#) Part 4 §6.1.2.5; fill (Shape Fill Properties)") are preserved on file save.

If the value of this attribute is *gradient*, *gradientRadial*, *tile*, *pattern*, or *frame*, then this value is applied to the **type** attribute on the parent **fill** element ("[ECMA-376](#) Part 4 §6.1.2.5; fill (Shape Fill Properties)") on file save. Additionally, this **fill** element is not preserved.

2.1.1730 Part 4 Section 6.2.2.13, idmap (Shape ID Map)

a. *The standard allows for application-dependent behavior.*

Office ignores this value on file read. The value indicates ID blocks of 1024 values, where a value of 0 means IDs 0 to 1024, a value of 1 means IDs 1025 to 2048, and so on. If Office has at least one shape which has an ID contained in a specific block, it writes out the index for that block.

2.1.1731 Part 4 Section 6.2.2.14, ink (Ink)

For additional notes that apply to this portion of the standard, please see the notes for [background, §2.2.1\(a\)](#); [object, §2.3.3.19\(a\)](#); [pict, §2.3.3.21\(a\)](#); [pict, §2.9.23\(a\)](#); [hdrShapeDefaults, §2.15.1.50\(a\)](#); [shapeDefaults, §2.15.1.79\(a\)](#).

a. The standard indicates that the *i* attribute is of type *XSD:base64Binary*.

In Office, the value of the *i* attribute is defined by the Ink Serialized Format specification [\[MC-ISF\]](#).

b. The standard does not restrict the number of instances of this element.

Office allows at most only one instance of the ink element in each place where it can be used.

c. The standard indicates how the annotation attribute is used.

Office only writes out the value *t* and does not preserve other values on file save.

2.1.1732 Part 4 Section 6.2.2.15, left (Text Box Left Stroke)

For additional notes that apply to this portion of the standard, please see the notes for [background, §2.2.1\(a\)](#); [object, §2.3.3.19\(a\)](#); [pict, §2.3.3.21\(a\)](#); [pict, §2.9.23\(a\)](#); [hdrShapeDefaults, §2.15.1.50\(a\)](#); [shapeDefaults, §2.15.1.79\(a\)](#); [bottom, §6.2.2.1\(b,d-k\)](#); [column, §6.2.2.6\(a\)](#).

a. The standard indicates the conditions under which the left element is displayed.

In Office, this element is only displayed if all of the following conditions are met:

The **on** attribute is *true*.

The shape's path is closed with the *x* command. [Note: This implies that arrow heads should be defined on the stroke attribute. end note]

The shape's path defines a rectangle with corner coordinates exactly equal to 0,0; 21600,0; 21600,21600; 0,21600. [Example: For example, the following value on the **path** attribute of the **shape** element ("[\[ECMA-376\]](#) Part 4 §6.1.2.19; shape (Shape Definition)") satisfies this condition: `path="m,1,21600r21600,121600,x` end example]

The value of the shape's **spt** attribute is 202.

The shape is not stroked.

If the **on** attribute is *false* or not specified, the border is not shown.

[Note: The shape is not stroked if one of the following conditions is true:

The value of the **on** attribute of the **stroke** element ("[\[ECMA-376\]](#) Part 4 §6.1.2.21; stroke (Line Stroke Settings)") is *false*.

The **on** attribute of the **stroke** element is absent and the value of the shape's **stroked** attribute is *false*.

The **on** attribute of the **stroke** element is absent, the shape's **stroked** attribute is absent and the value of the **stroked** attribute of the **shapetype** element ("[ECMA-376] Part 4 §6.1.2.20; shapetype (Shape Template)") is *false*.

end note]

2.1.1733 Part 4 Section 6.2.2.16, LinkType (Embedded Object Alternate Image Request)

a. *The standard does not specify a default value for the LinkType element.*

Office uses a default value of Bitmap for the LinkType element.

b. *The standard indicates how the LinkType element is used.*

In Office, the LinkType element only works for linked objects, which are objects for which the value of the Type attribute on the OLEObject element is Link.

2.1.1734 Part 4 Section 6.2.2.17, lock (Shape Protections)

For additional notes that apply to this portion of the standard, please see the notes for [background, §2.2.1\(a\)](#); [object, §2.3.3.19\(a\)](#); [pict, §2.3.3.21\(a\)](#); [pict, §2.9.23\(a\)](#); [hdrShapeDefaults, §2.15.1.50\(a\)](#); [shapeDefaults, §2.15.1.79\(a\)](#).

a. *The standard indicates that the aspectratio attribute specifies whether the aspect ratio of a shape is locked from being edited in an application's UI.*

Office does not enforce the aspectratio attribute lock in all UI.

b. *The standard implies that the cropping attribute specifies whether a shape may be cropped in the application's UI.*

Office only allows cropping for pictures.

c. *The standard does not restrict the number of instances of this element.*

Office allows at most only one instance of the lock element in each place where it can be used.

2.1.1735 Part 4 Section 6.2.2.18, LockedField (Embedded Object Cannot Be Refreshed)

a. *The standard indicates that the LockedField element contains no content, but also has a type of ST_TrueFalseBlank.*

Office considers the values true and blank ("") to mean true and all other values to mean false for the LockedField element.

b. *The standard does not specify a default value for the LockedField element.*

Office uses a default value of false for the LockedField element.

c. *The standard indicates how the LockedField element is used.*

Office only supports the LockedField element if the embedded object is linked.

d. *The standard indicates that the value blank ("") for the LockedField element means false.*

Office considers blank to be true for the LockedField element.

e. *The standard indicates that the value t means true.*

Office considers the value t to mean false for the LockedField element.

2.1.1736 Part 4 Section 6.2.2.19, OLEObject (Embedded OLE Object)

For additional notes that apply to this portion of the standard, please see the notes for [background, §2.2.1\(a\)](#); [pict, §2.9.23\(a\)](#); [hdrShapeDefaults, §2.15.1.50\(a\)](#); [shapeDefaults, §2.15.1.79\(a\)](#).

a. *The standard implies that the ObjectID attribute is used for all embedded objects.*

Office does not support the ObjectID attribute for linked objects.

b. *The standard indicates that the value of the ObjectID attribute is a string, but does not specify a format.*

Office formats the string value for the ObjectID attribute as starting with "_" followed by a number in the range 0-2147483647.

c. *The standard indicates how the ObjectID attribute is used.*

Office generates a new value for the ObjectID attribute on each file save.

d. *The standard indicates that the id, ObjectID, ProgID and ShapeID attributes are optional.*

Office requires that the id, ObjectID, ProgID, and ShapeID attributes be specified for the OLEObject element, or else the embedded object is converted to a static image.

2.1.1737 Part 4 Section 6.2.2.20, proxy (Shape Reference)

a. *The standard states that the values of the start and end attributes are defined by the ST_TrueFalseBlank simple type.*

Office restricts the value of these attributes type to be blank.

b. *The standard states that the default value of the start and end attributes is false.*

Office uses a default value of no value for these attributes.

c. *The standard states that the connectloc attribute is optional.*

Office requires this attribute.

d. *The standard states that values of the idref attribute are defined by the XML Schema string datatype.*

Office defines the values of the idref attribute with the ST_ObjIDRef ([§3.9.4, ST_ObjIDRef](#)) simple type.

e. *The standard states that the idref attribute is optional.*

Office requires this attribute.

2.1.1738 Part 4 Section 6.2.2.21, r (Rule)

- a. *The standard indicates how the how attribute is used.*

Office does not support the how attribute.

- b. *The standard places no restrictions on how the type attribute is used.*

Office requires that the shape referenced by the **idref** attribute match the rule type specified by this attribute. If the value is *arc*, **idref** shall reference a valid shape that is an arc (the value of the shape's **spt** attribute is 19). If the value is *callout*, **idref** shall reference a valid shape that is a callout. If the value is *connector*, **idref** shall reference a valid shape that is a connector.

- c. *The standard indicates that align is valid value for the type attribute.*

Office does not support the align value for the type attribute.

- d. *The standard states that values of the idref attribute are defined by the XML Schema string datatype.*

Office defines the values of the idref attribute with the ST_ObjIDRef ([§3.9.4, ST_ObjIDRef](#)) simple type.

2.1.1739 Part 4 Section 6.2.2.23, rel (Diagram Relationship)

- a. *The standard places no restrictions on the kind of shape that is defined by the idcntr attribute.*

Office requires that this shape be a connector.

- b. *The standard does not explicitly state that the shape identified by the idcntr attribute must exist.*

Office requires the shape identified by the idcntr attribute to exist.

- c. *The standard does not explicitly state that the shape identified by the idsrc attribute must exist.*

Office requires the shape identified by the idsrc attribute to exist.

- d. *The standard does not explicitly state that the shape identified by the iddest attribute must exist.*

Office requires the shape identified by the iddest attribute must exist.

- e. *The standard indicates that the idsrc, iddest and idcntr attributes are specified as a string.*

Office requires these attributes use a reference to an object ID in the form of an object name, as described in the ST_ObjIDRef ([§3.9.4, ST_ObjIDRef](#)) simple type.

2.1.1740 Part 4 Section 6.2.2.25, right (Text Box Right Stroke)

For additional notes that apply to this portion of the standard, please see the notes for [background, §2.2.1\(a\)](#); [object, §2.3.3.19\(a\)](#); [pict, §2.3.3.21\(a\)](#); [pict, §2.9.23\(a\)](#); [hdrShapeDefaults, §2.15.1.50\(a\)](#); [shapeDefaults, §2.15.1.79\(a\)](#); [bottom, §6.2.2.1\(b,d-k\)](#); [column, §6.2.2.6\(a\)](#).

- a. *The standard indicates the conditions under which the right element is displayed.*

In Office, this element is only displayed if all of the following conditions are met:

The **on** attribute is *true*.

The shape's path is closed with the x command. [Note: This implies that arrow heads should be defined on the stroke attribute. end note]

The shape's path defines a rectangle with corner coordinates exactly equal to 0,0; 21600,0; 21600,21600; 0,21600. [Example: For example, the following value on the **path** attribute of the **shape** element ("[ECMA-376](#) Part 4 §6.1.2.19; shape (Shape Definition)") satisfies this condition: path="m,1,21600r21600,121600,x" end example]

The value of the shape's **spt** attribute is 202.

The shape is not stroked.

If the **on** attribute is *false* or not specified, the border is not shown.

[Note: The shape is not stroked if one of the following conditions is true:

The value of the **on** attribute of the **stroke** element ("[ECMA-376](#) Part 4 §6.1.2.21; stroke (Line Stroke Settings)") is *false*.

The **on** attribute of the **stroke** element is absent and the value of the shape's **stroked** attribute is *false*.

The **on** attribute of the **stroke** element is absent, the shape's **stroked** attribute is absent and the value of the **stroked** attribute of the **shapetype** element ("[ECMA-376](#) Part 4 §6.1.2.20; shapetype (Shape Template)") is *false*.

end note]

2.1.1741 Part 4 Section 6.2.2.27, shapedefaults (New Shape Defaults)

For additional notes that apply to this portion of the standard, please see the notes for [background, §2.2.1\(a\)](#); [object, §2.3.3.19\(a\)](#); [pict, §2.3.3.21\(a\)](#); [pict, §2.9.23\(a\)](#); [arc, §6.1.2.1\(a-z,cc-ff,kk,bbb,ccc,eee-jjj,rrr-uuu,bbbb-dddd,gggg, hhhh\)](#); [curve, §6.1.2.3\(d\)](#).

a. *The standard makes no mention of an insetmode attribute.*

Office uses this attribute to specify how inner text margins are obtained; its allowed values are defined by the ST_InsetMode simple type, with a default value of custom.

b. *The standard makes no mention of an allowoverlap attribute.*

Office uses this attribute to specify whether a shape can overlap another shape; its allowed values are true and false, where false will cause the shape to shift left or right to avoid an overlap.

c. *The standard does not state that the imagedata element is a valid child of the shapedefaults element.*

Office allows the imagedata element to be a child of the shapedefaults element.

2.1.1742 Part 4 Section 6.2.2.28, shapelayout (Shape Layout Properties)

For additional notes that apply to this portion of the standard, please see the notes for [background, §2.2.1\(a\)](#); [object, §2.3.3.19\(a\)](#); [pict, §2.3.3.21\(a\)](#); [pict, §2.9.23\(a\)](#).

2.1.1743 Part 4 Section 6.2.2.29, signatureline (Digital Signature Line)

For additional notes that apply to this portion of the standard, please see the notes for [background, §2.2.1\(a\)](#); [object, §2.3.3.19\(a\)](#); [pict, §2.3.3.21\(a\)](#); [pict, §2.9.23\(a\)](#); [hdrShapeDefaults, §2.15.1.50\(a\)](#); [shapeDefaults, §2.15.1.79\(a\)](#); [group, §6.1.2.7\(a\)](#).

a. The standard indicates the default value for the `issignatureline` attribute is true.

In Office, the default value of the `issignatureline` attribute is false.

b. The standard does not restrict the number of instances of this element.

Office allows at most only one instance of the signatureline element in each place where it can be used.

2.1.1744 Part 4 Section 6.2.2.30, skew (Skew Transform)

For additional notes that apply to this portion of the standard, please see the notes for [background, §2.2.1\(a\)](#); [object, §2.3.3.19\(a\)](#); [pict, §2.3.3.21\(a\)](#); [pict, §2.9.23\(a\)](#); [hdrShapeDefaults, §2.15.1.50\(a\)](#); [shapeDefaults, §2.15.1.79\(a\)](#); [group, §6.1.2.7\(a\)](#).

a. The standard does not specify bounds for the matrix attribute.

Office uses bounds of -2147483644f and 2147483647f for the matrix attribute.

b. The standard does not indicate how the matrix attribute is applied to the shape.

Office applies this matrix to a point in the following way.

Let Q be a point in the object (after rotation, if the shape is rotated) described by $Q = [x \ y \ 1]$.

Let $f = Q \cdot \begin{bmatrix} 1/p_x \\ 1/p_y \\ 1 \end{bmatrix}$ and $M = \begin{bmatrix} s_{xx} & s_{yx} & 0 \\ s_{xy} & s_{yy} & 0 \\ xoffset & yoffset & 1 \end{bmatrix}$.

A new point Q' is calculated as $Q' = f \cdot (Q \cdot M)$.

The origin for the coordinate system used here is defined by the **origin** attribute, which is dependent on the height and width of the shape.

c. The standard does not restrict the number of instances of this element.

Office allows at most only one instance of the skew element in each place where it can be used.

d. The standard does not state how to handle the case where p_x and p_y are both 0.

Office sets $f = 1$ when if p_x and p_y are 0.

2.1.1745 Part 4 Section 6.2.2.31, top (Text Box Top Stroke)

For additional notes that apply to this portion of the standard, please see the notes for [background, §2.2.1\(a\)](#); [object, §2.3.3.19\(a\)](#); [pict, §2.3.3.21\(a\)](#); [pict, §2.9.23\(a\)](#); [hdrShapeDefaults, §2.15.1.50\(a\)](#); [shapeDefaults, §2.15.1.79\(a\)](#); [bottom, §6.2.2.1\(b,d-k\)](#); [column, §6.2.2.6\(a\)](#).

a. The standard indicates the conditions under which the top element is displayed.

In Office, this element is only displayed if all of the following conditions are met:

The **on** attribute is *true*.

The shape's path is closed with the *x* command. [Note: This implies that arrow heads should be defined on the stroke attribute. end note]

The shape's path defines a rectangle with corner coordinates exactly equal to 0,0; 21600,0; 21600,21600; 0,21600. [Example: For example, the following value on the **path** attribute of the **shape** element ("[ECMA-376](#) Part 4 §6.1.2.19; shape (Shape Definition)") satisfies this condition: `path="m,1,21600r21600,121600,x"` end example]

The value of the shape's **spt** attribute is 202.

The shape is not stroked.

If the **on** attribute is *false* or not specified, the border is not shown.

[Note: The shape is not stroked if one of the following conditions is true:

The value of the **on** attribute of the **stroke** element ("[ECMA-376](#) Part 4 §6.1.2.21; stroke (Line Stroke Settings)") is *false*.

The **on** attribute of the **stroke** element is absent and the value of the shape's **stroked** attribute is *false*.

The **on** attribute of the **stroke** element is absent, the shape's **stroked** attribute is absent and the value of the **stroked** attribute of the **shapetype** element ("[ECMA-376](#) Part 4 §6.1.2.20; shapetype (Shape Template)") is *false*.

end note]

2.1.1746 Part 4 Section 6.2.3.2, ST_BWMode (Black And White Modes)

a. The standard lists *hide* as a valid value.

Office does not support the *hide* enumeration value.

b. The standard states the name of the value that specifies light shades of gray only is *lightGrayscale*.

Office uses the name *lightGrayScale* for this value.

2.1.1747 Part 4 Section 6.2.3.3, ST_CalloutDrop (Callout Drop Location)

a. The standard does not specify enumeration values.

Office supports the following enumeration values:

| Enumeration Value | Description |
|--------------------------------------|--|
| bottom (Bottom placement) | Specifies that the drop is positioned at the bottom of the shape. |
| center (Center placement) | Specifies that the drop is positioned at the vertical center of the shape. |
| top (Top placement) | Specifies that the drop is positioned at the top of the shape. |
| user (User-defined placement) | Specifies that the drop position is determined by the user. |

2.1.1748 Part 4 Section 6.2.3.5, ST_ColorType (Color Type)

a. *The standard indicates the kinds of values that the ST_ColorType simple type uses.*

In Office, decimal RGB is specified using `rgb` followed by three comma-separated values in parentheses. These values are an ordered set in the range 0-255 and represent the red, green, and blue components of the color.

[Example:

```
< ... color="rgb(95,39,38)" ... >
```

end example]

b. *The standard states that the value of the ST_ColorType simple type can be specified using three-character hexadecimal RGB notation.*

Office does not allow this simple type to be specified in this way.

c. *The standard does not indicate the valid color palette entry names for the ST_ColorType simple type.*

In Office, the following color palette entries are supported:

ButtonFace

WindowText

Menu

Highlight

HighlightText

CaptionText

ActiveCaption

ButtonHighlight

ButtonShadow

ButtonText

GrayText

InactiveCaption

InactiveCaptionText

InfoBackground

InfoText

MenuText

Scrollbar

Window

WindowFrame

ThreeDLightShadow

ThreeDDarkShadow

ActiveBorder

InactiveBorder

Background

AppWorkspace

ThreeDFace (represents the same color as *ButtonFace*)

ThreeDShadow (represents the same color as *ButtonShadow*)

ThreeDHighlight (represents the same color as *ButtonHighlight*)

[Example:

```
<... color="InactiveCaption" ... >
```

end example]

d. *The standard indicates the kinds of values that the ST_ColorType simple type uses.*

In Office, a color palette entry is specified using `wincolor` followed by a number in parentheses. The number is the zero-based index of a color in the palette as described in the preceding section.

[Example:

```
<... color="wincolor(11)" ... >
```

end example]

e. *The standard does not state that the value of the ST_ColorType simple type can be specified using a named shape property notation.*

Office supports a named shape property notation as a value for the simple type. A property is specified using the name of the shape color property. The following properties are supported:

| Property | Description |
|---------------------|--|
| <i>fill</i> | Fill color |
| <i>line</i> | Line color |
| <i>lineOrFill</i> | Line color if specified, otherwise, the fill color |
| <i>fillThenLine</i> | Fill color if specified, otherwise, the line color |
| <i>fillBack</i> | Fill background color |
| <i>lineBack</i> | Line background color |
| <i>shadow</i> | Shadow color |
| <i>none</i> | No color |

[Example:

```
<... color="lineOrFill" ... >
```

end example]

f. *The standard indicates that the recoloring instruction behavior is application-specific.*

Office supports recoloring instructions in the following way. Let A represent the amount argument to the recoloring instruction.

| Instruction | Description |
|------------------------|--|
| <i>darken</i> | Scale each color component by A/256. |
| <i>lighten</i> | Scale the inverse of each color component by A/256, then invert the result. |
| <i>add</i> | Add A to each color component, limited to a maximum value of 255. |
| <i>subtract</i> | Subtract A from each color component, limited to a minimum value of 0. |
| <i>reverseSubtract</i> | Subtract each color component from A, limited to a minimum value of 0. |
| <i>blackWhite</i> | A color component is 0 if less than A, otherwise 255. |
| <i>invert</i> | Subtract each color component from 255. |
| <i>invert128</i> | For each color component less than 128, subtract 128 from it, otherwise add 128 to it. |
| <i>grayScale</i> | Convert the color to a grayscale equivalent. |

Office does not save an amount argument for the *invert*, *invert128* and *grayScale* recoloring instructions.

g. *The standard indicates how a recoloring instruction is formatted.*

Office does not save a recoloring amount argument for the *invert*, *invert128* and *grayScale* instructions.

2.1.1749 Part 4 Section 6.2.3.11, ST_FillType (Shape Fill Type)

- a. *The standard indicates how the pattern enumeration value is used.*

Office uses the fill colors but also tiles the fill image.

2.1.1750 Part 4 Section 6.3.2.2, borderbottom (Bottom Border)

For additional notes that apply to this portion of the standard, please see the notes for [group, §6.1.2.7\(a\)](#).

2.1.1751 Part 4 Section 6.3.2.3, borderleft (Left Border)

For additional notes that apply to this portion of the standard, please see the notes for [group, §6.1.2.7\(a\)](#).

2.1.1752 Part 4 Section 6.3.2.4, borderright (Right Border)

For additional notes that apply to this portion of the standard, please see the notes for [group, §6.1.2.7\(a\)](#).

2.1.1753 Part 4 Section 6.3.2.5, bordertop (Top Border)

For additional notes that apply to this portion of the standard, please see the notes for [group, §6.1.2.7\(a\)](#).

2.1.1754 Part 4 Section 6.3.2.6, wrap (Text Wrapping)

- a. *The standard indicates that the default value for the anchorx and anchory attributes is page.*

Office uses text as the default value for the anchorx and anchory attributes.

2.1.1755 Part 4 Section 6.3.3.3, ST_HorizontalAnchor (Horizontal Anchor Type)

- a. *The standard states that char is a valid value for the ST_HorizontalAnchor simple type.*

Office does not support this value for this simple type.

2.1.1756 Part 4 Section 6.3.3.4, ST_VerticalAnchor (Vertical Anchor Type)

- a. *The standard states that line is a valid value for the ST_VerticalAnchor simple type.*

Office does not support this value for this simple type.

2.1.1757 Part 4 Section 6.4.2.1, Accel (Primary Keyboard Accelerator)

- a. *The standard states that the values of this element are defined by the XML Schema integer datatype.*

Excel defines the values of this element with the XML Schema unsignedByte datatype.

2.1.1758 Part 4 Section 6.4.2.2, Accel2 (Secondary Keyboard Accelerator)

- a. *The standard states that the values of this element are defined by the XML Schema integer datatype.*

Excel defines the values of this element with the XML Schema unsignedByte datatype.

2.1.1759 Part 4 Section 6.4.2.3, Anchor (Anchor)

- a. *The standard describes the TopRow and BottomRow values of the Anchor element in terms of a column.*

Office considers the TopRow and BottomRow values of the Anchor element in terms of the row, rather than column, and considers the top-most row to be 0.

- b. *The standard indicates that the BottomOffset value of the Anchor element is the offset of the object's bottom edge from the bottom edge of the bottom anchor row.*

Office considers that the BottomOffset value of the Anchor element is the offset of the object's bottom edge from the top edge of the bottom anchor row.

- c. *The standard indicates that the Anchor element is specified using a comma-separated list of values, but does not require constraints on the list.*

Office requires the string value of the Anchor element to be a comma-delimited list of 8 non-negative integers.

2.1.1760 Part 4 Section 6.4.2.4, AutoFill (AutoFill)

- a. *The standard implies that the AutoFill element represents a type of object, but does not describe it.*

Office uses this element to indicate that the object's fill properties are automatically provided by the application and are not overridden with a specific fill color or style.

2.1.1761 Part 4 Section 6.4.2.5, AutoLine (AutoLine)

- a. *The standard implies that the AutoLine element represents a type of object, but does not describe it.*

Office uses this element to indicate to that the object's line properties are automatically provided by the application and are not overridden with a specific line color, style, or width.

2.1.1762 Part 4 Section 6.4.2.7, AutoScale (Font AutoScale)

- a. *The standard indicates that the element is used for attached text.*

Excel ignores the value of the AutoScale element and does not preserve it on file save.

2.1.1763 Part 4 Section 6.4.2.8, Camera (Camera Tool)

- a. *The standard indicates that the Camera element is used for cameras, but does not define how a camera object is represented.*

In Office, a camera object is a shape that is filled with a live view of a cell range in the same spreadsheet, including all applied styles. The cell range is defined by the **fmlaPict** element ("[ECMA-376](#) Part 4 §6.4.2.28; FmlaPict (Camera Source Range)"), which shall be present. Shape properties such as the position and size of the camera object are defined by the shape. The shape shall be a rectangle. The view of the cell range is scaled vertically and horizontally to fill the rectangle exactly.

If this element is specified without a value, it is assumed to be *true*. This element is used only on objects for which the value of the **ObjectType** attribute on the **ClientData** element (“[\[ECMA-376\]](#) Part 4 §6.4.2.12; ClientData (Attached Object Data)”) is *Pict*. Excel ignores this element on all other object types.

2.1.1764 Part 4 Section 6.4.2.10, CF (Clipboard Format)

- a. *The standard implies which objects the CF element applies to, but does not list a definitive set.*

Excel supports this element for objects for which the value of the **ObjectType** attribute on the **ClientData** element is *Pict*. Excel ignores the element if it is used with any other objects.

2.1.1765 Part 4 Section 6.4.2.12, ClientData (Attached Object Data)

- a. *The standard implies that *Movie* is a valid value for the *ObjectType* attribute.*

Excel does not support the *Movie* value for the **ObjectType** attribute.

- b. *The standard implies that *LineA* and *RectA* are valid values.*

Excel does not support the *LineA* and *RectA* values for the **ObjectType** attribute and does not save them to the file.

2.1.1766 Part 4 Section 6.4.2.13, ColHidden (Comment's Column is Hidden)

- a. *The standard could imply that the *ColHidden* element may be used to hide a column.*

Excel uses the hidden attribute of the *col* element as an whether the column of the cell to which this comment points is hidden and cannot be used for hiding a column.

2.1.1767 Part 4 Section 6.4.2.14, Colored (Dropdown Color Toggle)

- a. *The standard implies that the entire dropdown is colored.*

Excel only colors the downward pointing arrow on the dropdown, not the entire control.

2.1.1768 Part 4 Section 6.4.2.16, DDE (Dynamic Data Exchange)

- a. *The standard indicates that the *DDE* element applies to all object types.*

Excel only supports the *DDE* element for embedded objects.

2.1.1769 Part 4 Section 6.4.2.18, DefaultSize (Default Size Toggle)

- a. *The standard implies the *DefaultSize* element always indicates whether an object is at its default size.*

Excel writes the value of the *DefaultSize* element when an object is inserted at default size, but ignores it on file load.

2.1.1770 Part 4 Section 6.4.2.21, DropLines (Dropdown Maximum Lines)

- a. *The standard states that the values of this element are defined by the XML Schema integer datatype.*

Excel restricts the value of this element to be at least 0 and at most 30000.

2.1.1771 Part 4 Section 6.4.2.22, DropStyle (Dropdown Style)

- a. *The standard indicates that the schema for the DropStyle element allows any xsd:string, but the prose restricts this to a few values.*

Office enforces the restriction that the DropStyle element allows any xsd:string at the schema level.

2.1.1772 Part 4 Section 6.4.2.23, Dx (Scroll Bar Width)

- a. *The standard indicates that the element is used for scroll bars and spinners.*

Excel also uses the Dx element to specify width for scroll bars on combo boxes and list boxes.

2.1.1773 Part 4 Section 6.4.2.25, FmlaGroup (Linked Formula - Group Box)

- a. *The standard implies that the cell reference specified by this element is saved into the file.*

Excel removes this element and saves the cell reference it specifies on the FmlaLink element of the first radio button in the group. If no radio buttons exist in the group, the value is not saved in the file.

2.1.1774 Part 4 Section 6.4.2.27, FmlaMacro (Reference to Custom Function)

- a. *The standard indicates that the FmlaMacro element applies to an object but does not explicitly define a set of valid objects.*

Excel supports FmlaMacro on objects defined by all values of the ST_ObjectType simple type except LineA, Note and RectA.

- b. *The standard states that the values of this element are defined by the XML Schema string datatype.*

Office defines the values of this element with the ST_Macro ([§3.9.2, ST Macro](#)) simple type.

2.1.1775 Part 4 Section 6.4.2.29, FmlaRange (List Items Source Range)

- a. *The standard indicates that the element is used for list boxes.*

Excel also uses the FmlaRange element for dropdowns.

2.1.1776 Part 4 Section 6.4.2.30, FmlaTxbx (Text Formula)

- a. *The standard does not define the format for the value of the FmlaTxbx element.*

In Office, the value of the FmlaTxbx element shall be a string identifying a cell or a cell range in a spreadsheet. The cell reference syntax is described in Cell References (“[ECMA-376](#) Part 4 §3.17.2.3; Cell References”). Excel accepts a cell range but only considers the first cell in the range.

2.1.1777 Part 4 Section 6.4.2.32, Horiz (Scroll Bar Orientation)

- a. *The standard indicates that the element is used for scroll bars and spinners.*

Excel uses the Horiz element for scroll bars only.

2.1.1778 Part 4 Section 6.4.2.33, Inc (Scroll Bar Increment)

- a. *The standard states that the values of this element are defined by the XML Schema integer datatype.*

Excel restricts the value of this element to be at least 0 and at most 30000.

2.1.1779 Part 4 Section 6.4.2.35, LCT (Callback Type)

- a. *The standard indicates that the element is used for list boxes.*

Excel also uses the LCT element for list boxes and dropdowns.

2.1.1780 Part 4 Section 6.4.2.36, ListItem (Non-linked List Item)

- a. *The standard implies the ListItem element is always used.*

Excel ignores the ListItem element when the FmlaRange element is present.

2.1.1781 Part 4 Section 6.4.2.40, Max (Scroll Bar Maximum)

- a. *The standard states that the values of this element are defined by the XML Schema integer datatype.*

Excel restricts the value of this element to be at least 0 and at most 30000.

2.1.1782 Part 4 Section 6.4.2.41, Min (Scroll Bar Minimum)

- a. *The standard states that the values of this element are defined by the XML Schema integer datatype.*

Excel restricts the value of this element to be at least 0 and at most 30000.

2.1.1783 Part 4 Section 6.4.2.42, MoveWithCells (Move with Cells)

- a. *The standard defines the meaning of the values true and false for the MoveWithCells element.*

Excel reverses the meaning of the values true and false for the MoveWithCells element.

2.1.1784 Part 4 Section 6.4.2.45, NoThreeD (Disable 3D)

- a. *The standard indicates that the element is used for checkboxes, radio buttons, group boxes and scroll bars.*

Excel also uses the NoThreeD element for spinners.

2.1.1785 Part 4 Section 6.4.2.47, Page (Scroll Bar Page Increment)

- a. *The standard states that the values of this element are defined by the XML Schema integer datatype.*

Excel restricts the value of this element to be at least 0 and at most 30000.

2.1.1786 Part 4 Section 6.4.2.49, RecalcAlways (Recalculation Toggle)

- a. *The standard states that this element defines whether the object is always included in recalculation.*

Office does not implement the behavior associated with this element and removes the element on save.

2.1.1787 Part 4 Section 6.4.2.51, RowHidden (Comment's Row is Hidden)

- a. *The standard could imply that the RowHidden element may be used to hide a row.*

Office uses RowHidden as an indicator of whether the row of the cell to which this comment points is hidden and cannot be used for hiding a row. The hidden attribute of the row element ("[ECMA-376](#) Part 4 §3.3.1.71; row") is used for hiding a row.

2.1.1788 Part 4 Section 6.4.2.59, SizeWithCells (Resize with Cells)

- a. *The standard defines the meaning of the values true and false for the element.*

Excel reverses the meaning of the values true and false for the SizeWithCells element.

2.1.1789 Part 4 Section 6.4.2.61, TextVAlign (Vertical Text Alignment)

- a. *The standard describes a vertical alignment property in terms of horizontal alignment.*

Excel considers the TextVAlign element to specify vertical alignment.

2.1.1790 Part 4 Section 6.4.2.62, UIObj (UI Object Toggle)

- a. *The standard doesn't define what a UI Object is.*

Excel considers a UI Object to be a graphical object that the user is not able to interact with.

2.1.1791 Part 4 Section 6.4.2.63, Val (Scroll bar position)

- a. *The standard states that the values of this element are defined by the XML Schema integer datatype.*

Excel restricts the value of this element to be at least 0 and at most 30000.

- b. *The standard indicates that the Val element is used for scroll bars and spinners.*

Excel also uses the Val element for scroll bars on combo boxes and list boxes.

2.1.1792 Part 4 Section 6.4.2.64, ValidIds (Valid ID)

- a. *The standard indicates how the ValidIds element is used.*

Excel ignores the ValidIds element and does not preserve it on file save.

2.1.1793 Part 4 Section 6.4.2.68, WidthMin (Minimum Width)

- a. *The standard indicates the WidthMin element is used for list boxes and dropdowns.*

Excel uses the element WidthMin for dropdowns only.

2.1.1794 Part 4 Section 6.4.3.3, ST_TrueFalseBlank (Boolean Value with Blank State)

a. *The standard states that the value f on the ST_TrueFalseBlank simple type is equivalent to logical false.*

Excel treats the value f on this simple type as logical true.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.1795 Part 4 Section 6.5.2.2, textdata (VML Diagram Text)

For additional notes that apply to this portion of the standard, please see the notes for [group, §6.1.2.7\(a\)](#).

a. *The standard does not define the format of the part referenced by the id attribute.*

Office formats the part referenced by the id attribute according to the PowerPoint 97-2003 Binary File Format (.ppt) Structure Specification [\[MS-PPT\]](#).

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.1796 Part 4 Section 7.1, Math

a. *The standard states that the oMathPara element is the outermost equations element.*

Word writes inline equations as oMath elements that are not contained in any oMathPara element.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

b. *The standard specifies that the ruby element is allowed inside math.*

Word exhibits unpredictable behavior if the ruby element is included inside math, including failing to open the document.

c. *The standard specifies that comments are allowed inside math.*

In Office, unpredictable behavior occurs when comments are included inside math.

d. *The standard specifies that the pict element is allowed inside math.*

Word exhibits unpredictable behavior when the pict element is included inside math, including failing to open the document.

2.1.1797 Part 4 Section 7.1.2.1, acc (Accent)

For additional notes that apply to this portion of the standard, please see the notes for [oMath, §7.1.2.77\(d\)](#).

2.1.1798 Part 4 Section 7.1.2.3, aln (Alignment)

a. *The standard states that aln is not used when applied to a box which is not an operator emulator.*

Office does not allow aln to be applied to a box which is not an operator emulator.

b. *The standard says aln applies only to the box function even though the schema allows it as a child of math runs.*

In Word, the aln element applies to the box function and to math runs.

2.1.1799 Part 4 Section 7.1.2.6, argSz (Argument Size)

a. *The standard allows the argSz element to affect script size for multiple elements.*

The following arguments, which are listed in parent/child element notation, are the only arguments in Word that are affected by element **argSz**:

box/e

groupChr/e

limLow/lim

limUpp/lim

nary/sub

nary/sup

rad/deg

sPre/sub

sPre/sup

sSub/sub

sSubSup/sub

sSubSup/sup

sSup/sup

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.1800 Part 4 Section 7.1.2.7, bar (Bar)

For additional notes that apply to this portion of the standard, please see the notes for [oMath](#), §7.1.2.77(d).

2.1.1801 Part 4 Section 7.1.2.8, barPr (Bar Properties)

a. *The standard states that the bar assumes its default location of top (the mathematical overbar) when this element is omitted.*

Word uses a default location of bottom (the mathematical underbar) when this element is omitted.

2.1.1802 Part 4 Section 7.1.2.9, baseJc (Matrix Base Justification)

a. *The standard says that baseJc applies only to matrices even though the schema allows it as a child of equation arrays.*

In Word, baseJc applies to matrices and equation arrays.

2.1.1803 Part 4 Section 7.1.2.11, borderBox (Border-Box Function)

For additional notes that apply to this portion of the standard, please see the notes for [oMath, §7.1.2.77\(d\)](#).

2.1.1804 Part 4 Section 7.1.2.13, box (Box Function)

For additional notes that apply to this portion of the standard, please see the notes for [oMath, §7.1.2.77\(d\)](#).

2.1.1805 Part 4 Section 7.1.2.15, brk (Break)

a. *The standard states that the only attribute on the brk element is alnAt.*

If the brk element is used on a box element, Word ignores the alnAt attribute and instead reads and writes the val attribute with the same meaning as alnAt.

This note applies to the following products: 2007, 2007 SP1.

b. *The standard does not specified default behavior when alnAt is omitted.*

If alnAt attribute is omitted, Word aligns with the start of the first line of the equation.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

c. *The standard allows any value for alnAt between 1 and 255.*

Word requires the value of alnAt to be less than the index of the first operator in the equation with a manual break.

d. *The standard allows brk element to be specified for any math run.*

Word ignores brk if it is specified for a math run which does not begin with an operator.

e. *The standard says the alignAt attribute specifies how to align the current line of the equation with the previous line of the equation.*

In Word, the alignAt attribute specifies how to align the current line of the equation with the first line of the equation.

f. *The standard states that the only attribute on the brk element is the alnAt attribute.*

If the brk element is used on a box element, Word writes a val attribute with the same meaning as the alnAt attribute. The alnAt attribute, if present, is read correctly.

This note applies to the following products: 2007 SP2.

2.1.1806 Part 4 Section 7.1.2.16, brkBin (Break on Binary Operators)

a. *The standard implies that the val attribute is optional.*

Word requires this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.1807 Part 4 Section 7.1.2.17, brkBinSub (Break on Binary Subtraction)

a. *The standard implies that the val attribute is optional.*

Word requires this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.1808 Part 4 Section 7.1.2.18, cGp (Matrix Column Gap)

For additional notes that apply to this portion of the standard, please see the notes for [ST_UnSignedInteger, §7.1.3.17\(a\)](#).

a. *The standard says if the rule is set to 3, then the unit is interpreted as points, and if the rule is set to 4, then the unit is interpreted as lines.*

In Word, if the rule is set to 3, then the unit is interpreted as twips, and if the rule is set to 4, then the unit is interpreted as half lines or em widths .

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.1809 Part 4 Section 7.1.2.19, cGpRule (Matrix Column Gap Rule)

For additional notes that apply to this portion of the standard, please see the notes for [rSpRule, §7.1.2.93\(a\)](#).

2.1.1810 Part 4 Section 7.1.2.20, chr (Accent Character)

a. *The standard says the chr element only specifies the accent character of accPr even though the schema also allows it as a child of groupChrPr and naryPr.*

In Word, the chr element specifies the accent character of accPr, the group character of groupChrPr and the n-ary operator of naryPr.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

b. *The standard does not specify the default value for the chr element in groupChrPr and naryPr.*

In Word, the default value for the chr element in groupChrPr is U+23DF and in naryPr is U+222B.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.1811 Part 4 Section 7.1.2.21, count (Matrix Column Count)

For additional notes that apply to this portion of the standard, please see the notes for [mr, §7.1.2.69\(a\)](#).

a. *The standard does not specify how to interpret the matrix column count when the count element is omitted.*

Office assumes the matrix column count is 1 when this element is omitted.

b. *The standard states that the values of the val attribute are defined by ST_Integer255 simple type.*

Office restricts the value of this attribute to be at least 1 and at most 64.

2.1.1812 Part 4 Section 7.1.2.22, cSp (Matrix Column Spacing)

a. The standard states that the *val* attribute is measured in points or lines, depending on the setting of the rule of the parent element.

Word always measures the value of this attribute in twips.


This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

b. The standard states that the values of the *val* attribute are defined by the XML *unsignedInt* datatype.

Office restricts the value of this attribute to be at most 31680 (22").

c. The standard says that the *cSp* element specifies the minimum column spacing between corresponding edges.

In Office, this element specifies the minimum column width of a matrix. The actual column width of a matrix shall be the greater of either the width of the column's widest argument or **cSp**. This additional spacing can be added to enhance appearance. The **cGp** gap spacing (also referred to as "Column Gap" or "Gap Width") is added to the **cSp** (Minimum Matrix Column Width) to determine the total Matrix Column Spacing (distance between the same edges of different columns). The following image depicts how **cGp** and **cSp** work together to define matrix column spacing in a 2x2 matrix:



This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.1813 Part 4 Section 7.1.2.23, ctrlPr (Control Properties)

- a. *The standard does not specify where character properties of each control character of a math object are saved.*

Word saves the character properties of the first control character inside the math object properties tag, while the character properties of the rest of the control characters are saved inside the tags of the arguments of the math object.

- b. *The standard does not allow moveFrom and moveTo as children of the ctrlPr element.*

Word writes moveFrom and moveTo as children of the ctrlPr element.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.1814 Part 4 Section 7.1.2.24, d (Delimiter Function)

For additional notes that apply to this portion of the standard, please see the notes for [oMath, §7.1.2.77\(d\)](#).

- a. *The standard states that the maxOccurs value for the e child element is unbounded.*

Word limits the occurrences of this element to 1651564.

2.1.1815 Part 4 Section 7.1.2.25, defJc (Default Justification)

- a. *The standard implies that the val attribute is optional.*

Word requires this attribute.

2.1.1816 Part 4 Section 7.1.2.26, deg (Degree)

For additional notes that apply to this portion of the standard, please see the notes for [oMath, §7.1.2.77\(d\)](#).

2.1.1817 Part 4 Section 7.1.2.27, degHide (Hide Degree)

- a. *The standard allows degHide to be on when the degree is not empty.*

If degHide is on and the degree is not empty, Word displays the contents of the degree in an unexpected place.

2.1.1818 Part 4 Section 7.1.2.28, den (Denominator)

For additional notes that apply to this portion of the standard, please see the notes for [oMath, §7.1.2.77\(d\)](#).

2.1.1819 Part 4 Section 7.1.2.30, dispDef (Use Display Math Defaults)

- a. *The standard does not specify any effect of the dispDef element.*

If dispDef is off, Word ignores the following math elements: defJc, lMargin, rMargin, wrapRight, and wrapIndent. When these elements are ignored, Word will use the properties that are specified by the paragraph settings.

2.1.1820 Part 4 Section 7.1.2.32, e (Base (Argument))

For additional notes that apply to this portion of the standard, please see the notes for [oMath, §7.1.2.77\(d\)](#).

2.1.1821 Part 4 Section 7.1.2.34, eqArr (Equation-Array Function)

For additional notes that apply to this portion of the standard, please see the notes for [oMath, §7.1.2.77\(d\)](#).

a. The standard mentions alignment within equation arrays, but never explains how alignment points are specified or how they are used.

There are two types of markers that can be set inside an equation: (1) alignment points and (2) column separators. Both of these markers can be specified by inserting an ampersand character (“&”) in the middle of an equation. An alignment point is inserted to align whatever text comes after it with the rest of the equations at the same alignment points. [Example: The following diagram depicts an equation array in which the letters x in the condition part are aligned together.

$$y = \begin{cases} -x, & x < 0 \\ x, & x \geq 0 \end{cases}$$

The text that the user should type for these two equations should be:

-x, &x<0

x,&x≥0

end example]

A column separator indicates where white space is added to satisfy the expansion and flush flags, which are provided by the equation array properties **maxDist** and **objDist**, respectively. Markers (ampersand character “&”) within an equation are alternately treated as alignment and column separators. Odd-numbered markers are treated as alignment points markers while even markers are treated as column separators. [Example: The following diagram depicts an equation array which has **maxDist** and **objDist** both set to *on*.

$$\begin{array}{l} m_{11} = n_1 \\ m_{21} = n_2 \end{array} \quad \begin{array}{l} 3m_{12} = n_{12} \\ m_{22} = n_{22} + p_{22} \end{array}$$

The text that the user should type for these two equations should be:

m_11&=n_11&3m_12&=n_12

m_21&=n_21&m_22&=n_22+p_22

In this case, the presence of a single column separator within each equation means there are two columns within the equation array function. After calculating the width of each column, the

difference between the formatting width and the sum of the column widths is the column separator. It is this width that causes the two columns to flush left and right. end example]

If the flushing property of the equation array **objDist** is not specified or specified to be *off*, space will be allowed at the margins, thus distributing the extra space equally into $c + 1$ areas, where c is the number of columns.

[Example: The following diagram depicts the same equation array shown in the previous example but it has **maxDist** set to *on* and **objDist** both set to *off*.

| | | | | |
|--|--|--|--|--|
| | $\begin{aligned} m_{11} &= n_{11} \\ m_{21} &= n_{21} \end{aligned}$ | | $\begin{aligned} 3m_{12} &= n_{12} \\ m_{22} &= n_{22} + p_{22} \end{aligned}$ | |
|--|--|--|--|--|

Note that all three columns of space are of equal width. end example]

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

b. *The standard states that the maxOccurs value for the e child element is unbounded.*

Word limits the occurrences of this element to 64.

2.1.1822 Part 4 Section 7.1.2.36, f (Fraction Function)

For additional notes that apply to this portion of the standard, please see the notes for [oMath, §7.1.2.77\(d\)](#).

2.1.1823 Part 4 Section 7.1.2.37, fName (Function Name)

For additional notes that apply to this portion of the standard, please see the notes for [oMath, §7.1.2.77\(d\)](#).

2.1.1824 Part 4 Section 7.1.2.39, func (Function Apply Function)

For additional notes that apply to this portion of the standard, please see the notes for [oMath, §7.1.2.77\(d\)](#).

2.1.1825 Part 4 Section 7.1.2.41, groupChr (Group-Character Function)

For additional notes that apply to this portion of the standard, please see the notes for [oMath, §7.1.2.77\(d\)](#).

2.1.1826 Part 4 Section 7.1.2.42, groupChrPr (Group-Character Properties)

a. *The standard does not specify the default value for vertJc.*

Office interprets the default value for vertJc as top.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.1827 Part 4 Section 7.1.2.43, grow (n-ary Grow)

a. *The standard states that the grow element applies only to n-ary objects.*

Office applies the grow element to n-ary objects and delimiter objects.

b. *The standard states that the grow element operates at the document level.*

In Office, the grow element operates at the object level.

2.1.1828 Part 4 Section 7.1.2.48, interSp (Inter-Equation Spacing)

a. *The standard specifies the presence of the interSp attribute.*

Word ignores the interSp attribute and fails to write it back out.

2.1.1829 Part 4 Section 7.1.2.49, intLim (Integral Limit Locations)

a. *The standard says intLim specifies limit placement when converting from linear format.*

In Word, naryLim specifies limit placement when limLoc is omitted as well as limit placement when converting from linear format.

2.1.1830 Part 4 Section 7.1.2.50, intraSp (Intra-Equation Spacing)

a. *The standard states that the intraSp element specifies the spacing between adjacent display math paragraphs, in twips.*

Word does not implement this feature and does not write the intraSp element.

2.1.1831 Part 4 Section 7.1.2.51, jc (Justification)

For additional notes that apply to this portion of the standard, please see the notes for [defJc](#), [§7.1.2.25\(a\)](#).

a. *The standard says that if jc is omitted, the math paragraph is Centered as Group.*

In Word, if jc is omitted, the value is taken from the document default defJc.

2.1.1832 Part 4 Section 7.1.2.52, lim (Limit (Lower))

For additional notes that apply to this portion of the standard, please see the notes for [oMath](#), [§7.1.2.77\(d\)](#).

a. *The standard states that lim specifies the lower limit even though the schema also includes it as a child of the upper limit.*

In Word, lim specifies the lower limit or upper limit.

2.1.1833 Part 4 Section 7.1.2.53, limLoc (n-ary Limit Location)

a. *The standard says the default for limLoc is undOvr.*

In Word, the default location is taken from the naryLim or intLim element in the math settings.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.1834 Part 4 Section 7.1.2.54, limLow (Lower-Limit Function)

For additional notes that apply to this portion of the standard, please see the notes for [oMath, §7.1.2.77\(d\)](#).

2.1.1835 Part 4 Section 7.1.2.56, limUpp (Upper-Limit Function)

For additional notes that apply to this portion of the standard, please see the notes for [oMath, §7.1.2.77\(d\)](#).

2.1.1836 Part 4 Section 7.1.2.58, lit (Literal)

a. *The standard says lit causes characters to not be interpreted as operators.*

In Word, lit does not affect whether a character is interpreted as an operator.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.1837 Part 4 Section 7.1.2.59, lMargin (Left Margin)

a. *The standard does not specify the default value for lMargin.*

In Word, the default value for lMargin is 0.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.1838 Part 4 Section 7.1.2.60, m (Matrix Function)

For additional notes that apply to this portion of the standard, please see the notes for [oMath, §7.1.2.77\(d\)](#).

a. *The standard states that the maxOccurs value for the mr child element is unbounded.*

Word limits the occurrences of this element to 256.

2.1.1839 Part 4 Section 7.1.2.61, mathFont (Math Font)

a. *The standard does not limit the length of the value of the val attribute.*

Word restricts the value of this attribute to be at most 31 characters.

b. *The standard says that the mathFont property is the default math font.*

Word uses this setting when math is created while editing within the application, but not when loading math from a file.

c. *The standard does not specify conditions under which the default math font should be ignored.*

Word ignores the default math font if it is set to an empty string or font which is not appropriate for displaying math.

d. *The standard implies that the val attribute is optional.*

Word requires this attribute.

2.1.1840 Part 4 Section 7.1.2.63, maxDist (Maximum Distribution)

- a. *The standard says maxDist causes the equation array to be spaced to the maximum width of the containing element (page, column, cell, and so on).*

In Word, maxDist causes the equation array to be spaced to the column width.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

- b. *The standard allows maxDist to be used in an equation array without alignment points, but does not specify where that space should be added.*

In Word, maxDist only affects eqArr contents if alignment points are used to specify where space should be added.

2.1.1841 Part 4 Section 7.1.2.64, mc (Matrix Column)

- a. *The standard says the mc element specifies the properties of a single column in a matrix.*

Word uses mc to specify the properties of a set of adjacent columns in a matrix.

2.1.1842 Part 4 Section 7.1.2.67, mcs (Matrix Columns)

- a. *The standard allows an unbounded number of columns in a matrix.*

Word allows at most 64 columns in a matrix.

2.1.1843 Part 4 Section 7.1.2.69, mr (Matrix Row)

- a. *The standard states that the maxOccurs value for the mc child element is unbounded.*

Word limits the occurrences of this element to 64.

2.1.1844 Part 4 Section 7.1.2.70, nary (n-ary Operator Function)

For additional notes that apply to this portion of the standard, please see the notes for [oMath, §7.1.2.77\(d\)](#).

2.1.1845 Part 4 Section 7.1.2.71, naryLim (n-ary Limit Location)

- a. *The standard says naryLim specifies limit placement when converting from linear format.*

In Word, naryLim specifies limit placement when limLoc is omitted as well as limit placement when converting from linear format.

2.1.1846 Part 4 Section 7.1.2.73, noBreak (No Break)

- a. *The standard does not specify conditions under which noBreak is ignored.*

If opEmu is set, Word ignores noBreak and never breaks.

- b. *The standard says the default is off.*

In Word the default is on.

2.1.1847 Part 4 Section 7.1.2.75, num (Numerator)

For additional notes that apply to this portion of the standard, please see the notes for [oMath, §7.1.2.77\(d\)](#).

2.1.1848 Part 4 Section 7.1.2.76, objDist (Object Distribution)

a. *The standard does not specify how to expand an equation to object width in absence of the maxObj element.*

Word ignores objDist unless maxObj is present and on.

2.1.1849 Part 4 Section 7.1.2.77, oMath (Office Math)

a. *The standard allows adjacent oMath elements without any separation between them.*

Word merges together adjacent oMath elements if they are not separated by a WordprocessingML br element.

b. *The standard allows nesting of oMath elements inside a math object argument or inside another oMath element.*

Word fails to open a file with an oMath element inside a math object argument or inside another oMath element.

c. *The standard makes mention of display and inline math, but never defines the differences.*

The layout of the math can be done in one of two different environments: display math and inline math. Display math is used for formulas that appear on their own line in a document. Inline math is used for formulas that appear in the middle of other non-math runs. The height of inline math should be kept to a minimum to ensure that the overall line height is not significantly increased. Display math should be encapsulated inside a math paragraph **oMathPara**, which can contain one or more display equations. Each equation in the math paragraph is contained inside an **oMath** element. Math paragraphs are used to specify how the display equations are aligned relative to the containing paragraph and relative to other equations. In addition, display equations within the same math paragraph can be aligned relative to each other at various points. Inline math should be contained inside an **oMath** element.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

d. *The standard does not state that the customXml, fldSimple, hyperlink, smartTag, and sdt elements are valid children of the oMath element.*

Word allows these elements to be children of the oMath element.

e. *The standard allows math content to exist outside of any oMath element.*

Word will not open a file which contains math content outside of any oMath element.

f. *The standard allows oMath to occur outside of any p element.*

Word will not open a file where oMath occurs outside of any p element.

g. *The standard states that the oMath element is allowed where block level content is required.*

Word does not allow the oMath element to be a child of the body, comment, customXml (Block-Level Custom XML Element), customXml (Cell-Level Custom XML Element), customXml (Row-Level

Custom XML Element), docPartBody, endnote, footnote, ftr, hdr, sdtContent (Block-Level Structured Document Tag Content), sdtContent (Cell-Level Structured Document Tag Content), sdtContent (Row-Level Structured Document Tag Content), tbl, tc, tr, or txbxContent elements.

2.1.1850 Part 4 Section 7.1.2.78, oMathPara (Math Paragraph)

- a. *The standard only allows oMathParaPr and oMath as children of the oMathPara element.*

Word also allows the following child elements of the oMathPara element:

| Child Elements |
|--|
| bookmarkEnd ("ECMA-376 Part 4 §2.13.6.1; bookmarkEnd (Bookmark End)") |
| bookmarkStart ("ECMA-376 Part 4 §2.13.6.2; bookmarkStart (Bookmark Start)") |
| commentRangeEnd ("ECMA-376 Part 4 §2.13.4.3; commentRangeEnd (Comment Anchor Range End)") |
| commentRangeStart ("ECMA-376 Part 4 §2.13.4.4; commentRangeStart (Comment Anchor Range Start)") |
| customXmlDelRangeEnd ("ECMA-376 Part 4 §2.13.5.4; customXmlDelRangeEnd (Custom XML Markup Deletion End)") |
| customXmlDelRangeStart ("ECMA-376 Part 4 §2.13.5.5; customXmlDelRangeStart (Custom XML Markup Deletion Start)") |
| customXmlInsRangeEnd ("ECMA-376 Part 4 §2.13.5.6; customXmlInsRangeEnd (Custom XML Markup Insertion End)") |
| customXmlInsRangeStart ("ECMA-376 Part 4 §2.13.5.7; customXmlInsRangeStart (Custom XML Markup Insertion Start)") |
| customXmlMoveFromRangeEnd ("ECMA-376 Part 4 §2.13.5.8; customXmlMoveFromRangeEnd (Custom XML Markup Move Source End)") |
| customXmlMoveFromRangeStart ("ECMA-376 Part 4 §2.13.5.9; customXmlMoveFromRangeStart (Custom XML Markup Move Source Start)") |
| customXmlMoveToRangeEnd ("ECMA-376 Part 4 §2.13.5.10; customXmlMoveToRangeEnd (Custom XML Markup Move Destination Location End)") |
| customXmlMoveToRangeStart ("ECMA-376 Part 4 §2.13.5.11; customXmlMoveToRangeStart (Custom XML Markup Move Destination Location Start)") |
| del ("ECMA-376 Part 4 §2.13.5.12; del (Deleted Run Content)") |
| ins ("ECMA-376 Part 4 §2.13.5.20; ins (Inserted Run Content)") |
| moveFrom ("ECMA-376 Part 4 §2.13.5.21; moveFrom (Move Source Run Content)") |
| moveFromRangeEnd ("ECMA-376 Part 4 §2.13.5.23; moveFromRangeEnd (Move Source Location Container - End)") |
| moveFromRangeStart ("ECMA-376 Part 4 §2.13.5.24; moveFromRangeStart (Move Source Location Container - Start)") |
| moveTo ("ECMA-376 Part 4 §2.13.5.26; moveTo (Move Destination Run Content)") |
| moveToRangeEnd ("ECMA-376 Part 4 §2.13.5.27; moveToRangeEnd (Move Destination Location |

| Child Elements |
|--|
| Container - End") |
| moveToRangeStart ("ECMA-376 Part 4 §2.13.5.28; moveToRangeStart (Move Destination Location Container - Start)") |
| permEnd ("ECMA-376 Part 4 §2.13.7.1; permEnd (Range Permission End)") |
| permStart ("ECMA-376 Part 4 §2.13.7.2; permStart (Range Permission Start)") |
| proofErr ("ECMA-376 Part 4 §2.13.8.1; proofErr (Proofing Error Anchor)") |
| r ("ECMA-376 Part 4 §7.1.2.87; r (Run)") |
| r (Text Run) ("ECMA-376 Part 4 §2.3.2.23; r (Text Run)") |

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

- b. *The standard allows adjacent oMathPara elements within the same paragraph.*

Word merges adjacent oMathPara elements within the same paragraph into a single oMathPara element.

- c. *The standard allows oMathPara as a descendant of math elements.*

Word fails to open a file with oMathPara as a descendant of any math element.

- d. *The standard states that the oMathPara element is allowed where block level content is required.*

Word does not allow the oMathPara element to be a child of the body, comment, customXml (Block-Level Custom XML Element), customXml (Cell-Level Custom XML Element), customXml (Row-Level Custom XML Element), docPartBody, endnote, footnote, ftr, hdr, sdtContent (Block-Level Structured Document Tag Content), sdtContent (Cell-Level Structured Document Tag Content), sdtContent (Row-Level Structured Document Tag Content), tbl, tc, tr, or txbxContent elements.

- e. *The standard allows oMathPara to occur outside of any p element.*

Word will not open a file where oMathPara occurs outside of any p element.

2.1.1851 Part 4 Section 7.1.2.80, opEmu (Operator Emulator)

- a. *The standard does not specify the default value for opEmu.*

In Word, the default value for opEmu is off.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

- b. *The standard says when opEmu is on, the box behaves as an operator, but does not specify what kind of operator.*

In Word when opEmu is on, the box behaves as a binary operator.

2.1.1852 Part 4 Section 7.1.2.81, phant (Phantom Function)

For additional notes that apply to this portion of the standard, please see the notes for [oMath, §7.1.2.77\(d\)](#).

2.1.1853 Part 4 Section 7.1.2.84, pos (Position)

- a. *The standard states that the pos element specifies the position of the bar in the bar object.*

Word uses the pos element to specify the position of the bar in the bar object or the position of the character in the groupChr object.

- b. *The standard states that the default value for position of the bar in the bar object is top.*

Office implements the default value for the position of the bar in the bar object as bot.

2.1.1854 Part 4 Section 7.1.2.85, postSp (Post-Equation Spacing)

- a. *The standard specifies postSp to set post-equation spacing.*

Word ignores and discards postSp.

2.1.1855 Part 4 Section 7.1.2.86, preSp (Pre-Equation Spacing)

- a. *The standard specifies preSp to set pre-equation spacing.*

Word ignores preSp and fails to write it back out.

2.1.1856 Part 4 Section 7.1.2.87, r (Run)

For additional notes that apply to this portion of the standard, please see the notes for [oMath, §7.1.2.77\(d\)](#); [oMathPara, §7.1.2.78\(a\)](#).

- a. *The standard allows bold and italic to be set in a math run in the rPr of both Math and WordprocessingML.*

If Word reads a math run where bold or italic properties are set in the rPr of WordprocessingML, it ignores those properties during display but then moves them into the Math rPr on save.

- b. *The standard allows br elements inside a math object.*

Word does not allow br elements inside a math object.

- c. *The standard allows cr elements as a child of a math run.*

Word does not allow the cr element inside a math run.

- d. *The standard allows tab elements as a child of a math run.*

Word ignores a tab element if it occurs inside a math run.

2.1.1857 Part 4 Section 7.1.2.88, rad (Radical Function)

For additional notes that apply to this portion of the standard, please see the notes for [oMath, §7.1.2.77\(d\)](#).

2.1.1858 Part 4 Section 7.1.2.90, rMargin (Right Margin)

- a. *The standard does not specify the default value for rMargin.*

In Word, the default value for rMargin is 0.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.1859 Part 4 Section 7.1.2.92, rSp (Row Spacing)

For additional notes that apply to this portion of the standard, please see the notes for [cGp](#), [§7.1.2.18\(a\)](#); [ST_UnSignedInteger](#), [§7.1.3.17\(a\)](#).

a. *The standard says rSp is used only to set row spacing in equation arrays even though it is also allowed as a child of the matrix element.*

In Word, rSp is used to set row spacing in both equations arrays and matrices.

b. *The standard says if this element is omitted, single line spacing is used.*

In Word, if this element is omitted, the default is 0.

2.1.1860 Part 4 Section 7.1.2.93, rSpRule (Row Spacing Rule)

a. *The standard says the column gaps and row spacing are measured in points or lines.*

In Word, column gaps and row spacing are measured in twips, 0.5 em increments, or 0.5 line increments.

b. *The standard does not state the default value for rSpRule.*

In Word, the default value for rSpRule is 0.

c. *The standard states that rSpRule specifies the vertical spacing between columns.*

In Word, the rSpRule specifies the vertical spacing between rows.

d. *The standard says that rSpRule only specifies the vertical spacing in mPr even though the schema also allows it as a child of eqArrPr.*

In Word, rSpRule specifies the vertical spacing in mPr and eqArrPr.

2.1.1861 Part 4 Section 7.1.2.94, scr (Script)

a. *The standard says that the script element is used to map ASCII values to the appropriate Unicode range.*

Word uses the script element and the style element to map Unicode values to Math Alphanumeric Unicode values.

b. *The standard implies that the val attribute is optional.*

Word requires this attribute.

c. *The standard does not specify a default value for scr.*

In Word, the default value for scr is roman.

2.1.1862 Part 4 Section 7.1.2.97, shp (Shape (Delimiters))

a. *The standard places no restrictions on when this element is applicable.*

Office will ignore this element if the parent `dPr` element contains a child `grow` element whose `val` attribute has a value of `off`.

2.1.1863 Part 4 Section 7.1.2.98, `smallFrac` (Small Fraction)

a. *The standard states that the `smallFrac` element specifies a reduced fraction size display math, such that the numerator and denominator are written in script size instead of at the size of regular text.*

Word uses this element to specify a reduced size for fractions of type `bar` or `noBar` that are nested within other fractions that are of type `bar`, `noBar`, or `skw`. This option only applies in display math, such that the numerator and denominator are written in script size instead of at the size of regular text.

2.1.1864 Part 4 Section 7.1.2.99, `sPre` (Pre-Sub-Superscript Function)

For additional notes that apply to this portion of the standard, please see the notes for [oMath, §7.1.2.77\(d\)](#).

2.1.1865 Part 4 Section 7.1.2.101, `sSub` (Subscript Function)

For additional notes that apply to this portion of the standard, please see the notes for [oMath, §7.1.2.77\(d\)](#).

2.1.1866 Part 4 Section 7.1.2.103, `sSubSup` (Sub-Superscript Function)

For additional notes that apply to this portion of the standard, please see the notes for [oMath, §7.1.2.77\(d\)](#).

2.1.1867 Part 4 Section 7.1.2.105, `sSup` (Superscript Function)

For additional notes that apply to this portion of the standard, please see the notes for [oMath, §7.1.2.77\(d\)](#).

a. *The standard states that the `sSup` element specifies the subscript function `sSub`, which consists of a base `e` and a reduced-size `scr` placed below and to the right.*

Word uses the `sSup` element to specify the superscript function `sSup`, which consists of a base `e` and a reduced-size `scr` placed above and to the right.

2.1.1868 Part 4 Section 7.1.2.111, `sty` (style)

a. *The standard says that `style` is used to map ASCII values to the appropriate Unicode range.*

Word uses the `style` and `script` to map Unicode values to Math Alphanumeric Unicode values.

b. *The standard implies that the `val` attribute is optional.*

Word requires this attribute.

c. *The standard does not specify a default value for `sty`.*

In Word, the default value for `sty` is italic.

2.1.1869 Part 4 Section 7.1.2.112, sub (Subscript (Pre-Sub-Superscript))

For additional notes that apply to this portion of the standard, please see the notes for [oMath, §7.1.2.77\(d\)](#).

- a. *The standard says sub only specifies the subscript of sPre even though the schema also allows it as a child of sSub, sSubSup, and nary.*

In Word, sub specifies the subscript of sPre, sSub, and sSubSup and specifies the lower limit of nary.

2.1.1870 Part 4 Section 7.1.2.113, subHide (Hide Subscript (n-ary))

- a. *The standard allows subHide to be on while the lower limit is not empty.*

If subHide is on while the lower limit is not empty, Word displays the contents of the lower limit in an unexpected place.

2.1.1871 Part 4 Section 7.1.2.114, sup (Superscript (Superscript function))

For additional notes that apply to this portion of the standard, please see the notes for [oMath, §7.1.2.77\(d\)](#).

- a. *The standard says sup only specifies the superscript of sSup even though the schema also allows it as a child of sPre, sSubSup, and nary.*

In Word, sup specifies the superscript of sSup, sPre, and sSubSup, and specifies the upper limit of nary.

2.1.1872 Part 4 Section 7.1.2.115, supHide (Hide Superscript (n-ary))

- a. *The standard says that if supHide is omitted the lower limit will appear.*

In Word, if supHide is omitted, the upper limit will appear.

- b. *The standard allows supHide to be set when the upper limit is not empty.*

In Word, if the supHide attribute is on while the upper limit of the n-ary function is not empty, the application will display this argument next to the base argument of the n-ary function.

2.1.1873 Part 4 Section 7.1.2.116, t (Text)

- a. *The standard says the xml:space attribute specifies whether to preserve spaces while reading text inside math text.*

Word ignores this attribute and always preserves spaces inside math text.

2.1.1874 Part 4 Section 7.1.2.117, transp (Transparent (Phantom))

- a. *The standard says if transparency is off, then the contents of the phantom are ignored during layout.*

In Word, if transparency is off, special spacing is not added before and after the phantom, but the contents are not ignored during layout.

- b. *The standard allows transparency to be set on a phantom with any contents.*

In Word, transparency does not work as specified unless the phantom contains another math function and does not start or end with a math operator.

2.1.1875 Part 4 Section 7.1.3.1, ST_BreakBin (Break Binary Operators)

a. *The standard says that after means the operator appears after the break and before means the operator appears before the break.*

In Word, after means the break occurs after the operator (the binary operator appears before the break) and before means the break occurs before the operator (the binary operator appears after the break).

2.1.1876 Part 4 Section 7.1.3.7, ST_Jc (Justification)

a. *The standard says centerGroup alignment takes place relative to the page even though the equation might be inside an object like a table cell.*

In Word, centerGroup alignment takes place relative to the equation margins just like center alignment.

b. *The standard says centerGroup means that equations are justified with respect to each other and then the group is centered, but it does not specify how to justify the equations respect to each other.*

In Word, centerGroup means that equations are left justified with respect to each other, and then group is centered.

2.1.1877 Part 4 Section 7.1.3.11, ST_Shp (Shape (Delimiters))

a. *The standard says the match value means the delimiters match the shape of the argument.*

In Word, the match value means the delimiters match the height of the argument.

2.1.1878 Part 4 Section 7.1.3.15, ST_TopBot (Top-Bottom)

a. *The standard describes the values of the ST_TopBot simple type in terms of the vertJc element.*

Word defines the values of this simple type to take on the meanings appropriate to the parent element.

2.1.1879 Part 4 Section 7.1.3.16, ST_TwipsMeasure (Twips measurement)

a. *The standard allows any unsigned 32-bit integer.*

Word only allows values up to 31,680.

2.1.1880 Part 4 Section 7.1.3.17, ST_UnSignedInteger (Unsigned integer.)

a. *The standard states that the values of the val attribute are defined by the XML unsignedInt datatype.*

Word defines the values of this attribute with the XML unsignedShort datatype.

2.1.1881 Part 4 Section 7.1.3.19, ST_YAlign (Vertical Alignment)

a. *The standard does not specify in detail how to align the matrix with the surrounding content.*

Word uses baseline alignment to align the matrix with the surrounding content.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.1882 Part 4 Section 7.2.2.2, AppVersion (Application Version)

- a. *The standard does not constrain the app version.*

Office constrains the app version to strings matching the XSD pattern value "[0-9]{1,2}\.[0-9]{1,4}".

2.1.1883 Part 4 Section 7.2.2.6, DigSig (Digital Signature)

- a. *The standard does not specify the format of the digital signature blob.*

Office expects that the structure of the decoded binary blob is specified as follows:

| Offset in bytes | Description |
|------------------------|--|
| 0 | Specifies the byte size of the digital signature data blob that starts at offset 8 |
| 4 | Specifies digital signature data offset from the beginning of the blob. This shall always be 8 |
| 8 | Digital signature data |

2.1.1884 Part 4 Section 7.2.2.7, DocSecurity (Document Security)

- a. *The standard states that the valid values of the DocSecurity element are 1, 2, 4, and 8.*

Office also supports a value of 0, signifying that no security level is defined.

- b. *The standard states that the valid values of the DocSecurity element are 1, 2, 4, and 8.*

Excel does not support the values 4 or 8.

- c. *The standard does not state that the values of this element can be combined.*

Office allows the values of this element to be combined.

2.1.1885 Part 4 Section 7.2.2.8, HeadingPairs (Heading Pairs)

- a. *The standard does not document restrictions.*

In Office, a specific order and variant type is required for each heading pair. The baseType of the vector should be "variant". The following table specifies the order and the variant type of each heading pair:

| Variant type | Description |
|---------------------|--|
| lpstr or lpwstr | Specifies the heading for the group |
| i4 | Specifies the number of parts in the group. This value should be a positive integer. |

- b. *The standard does not include HeadingPairs for SpreadsheetML.*

In Excel, the following heading pair values are specified:

| Value Pair | Meaning |
|-----------------|---|
| SheetType, n | There are n of these types of sheets in the workbook. SheetType can be one of the following: Worksheet, Charts, and Dialogs. |
| Named Ranges, n | There are n named ranges in the workbook. |

2.1.1886 Part 4 Section 7.2.2.10, HLinks (Hyperlink List)

a. *The standard does not specify the constraints on the HLinks type.*

Each hyperlink in the document is represented by a set of 6 variants and hence the size of the vector should be multiples of 6. The following table specifies the order and the type of variants for a hyperlink:

| Variant type | Description |
|--------------|--|
| i4 | Application specific data associated with the hyperlink |
| i4 | Application specific data associated with the hyperlink |
| i4 | Application specific data associated with the hyperlink |
| i4 | This specifies information about the hyperlink. The lower 16 bits specify hyperlink type with one of the possible values: 0 - Graphic shown as background of document 1 - Graphic shown in document 2 - Graphic used to fill a shape 3 - Graphic used for shape outline 4 - Hyperlink attached to a shape 5 - Hyperlink attached to a WordprocessingML field 6 - Hyperlink attached to a SpreadsheetML range The high 16 bits store hyperlink action with one of the possible values: 0 - None 1 - Change the link to new hyperlink value 2 - Remove hyperlink from object |
| lpwstr | This specifies the hyperlink target |
| lpwstr | This specifies the location of the hyperlink |

2.1.1887 Part 4 Section 7.2.2.26, TitlesOfParts (Part Titles)

a. *The standard specifies the TitlesOfParts element but provides no direction on application specific part titles.*

In Excel, the TitlesOfParts element can contain Worksheet names, Dialogsheet names, Chart names and Named ranges.

b. *The standard does not state the relationship with the HeadingPairs property.*

In Office, the part titles specified in the HeadingPairs property are linked to HeadingPairs (“[ECMA-376](#) Part 4 §7.2.2.8; HeadingPairs (Heading Pairs)”) entries. Hence there shall not be more document part titles listed here than the sum of all parts listed in HeadingPairs property.

[Example: A presentation composed of three slides with an applied theme "Currency" may have the following TitlesofParts and HeadingPairs representation:

```
<TitlesofParts>
  <vt:vector size="4" baseType="lpstr">
    <vt:lpstr>Currency</vt:lpstr>
    <vt:lpstr>Slide 1</vt:lpstr>
    <vt:lpstr>Slide 2</vt:lpstr>
    <vt:lpstr>Slide 3</vt:lpstr>
  </vt:vector>
</TitlesofParts>
<HeadingPairs>
  <vt:vector size="4" baseType="variant">
    <vt:variant>
      <vt:lpstr>Theme</vt:lpstr>
    </vt:variant>
    <vt:variant>
      <vt:i4>1</vt:i4>
    </vt:variant>
    <vt:variant>
      <vt:lpstr>Slide Titles</vt:lpstr>
    </vt:variant>
```

```
<vt:variant>
<vt:i4>3</vt:i4>
</vt:variant>
</vt:vector>
</HeadingPairs>
```

end example]

2.1.1888 Part 4 Section 7.2.2.27, TotalTime (Total Edit Time Metadata Element)

a. *The standard states that the value of this element can be any integer.*

Office disallows any negative value on this element.

2.1.1889 Part 4 Section 7.3.2.2, property (Custom File Property)

a. *The standard does not reserve a unique property name for the property editor’s content type ID.*

Office reserves the following unique property names for the following purposes:

| Name | Description |
|----------------------|--|
| <i>ContentTypeId</i> | A custom property with this name contains the id of the content type associated with the Windows SharePoint Services document library where this document belongs. Its value is the same as the ma:contentTypeID attribute on the Schema for Content Type element |

| Name | Description |
|------|------------------------------------|
| | (§3.5.2.1.1.1, contentTypeSchema). |

b. The standard does not reserve unique property names for document workspaces.

Office reserves the following unique property names for the following purposes:

| Name | Description |
|-------------------------------|---|
| <code>_CheckOutSrcUrl</code> | <p>A custom property with this name specifies the document workspace from which the document was checked out.</p> <p>The child element of this property shall be a lpwstr specifying the URL of the document workspace where this document belongs. This URL shall not exceed 256 characters.</p> |
| <code>_LiveCopyIndex</code> | <p>A custom property with this name provides a time stamp for comparing the current state of a server document to a local copy of that document.</p> <p>The child element of this property shall be an i4 containing a hashed value of the modified property when the original document was first added to the document workspace. This value is computed by multiplying the high-order part of the modified filetime property by three and adding that to the low-order part of the filetime.</p> <p>This information can be used to resolve potential conflicts between two different copies of a document stored in a document workspace. If the <code>_LiveCopyIndex</code> value of a particular document matches the modified property value, then that document is considered to be equivalent to the original shared version of the file on the server. If one of the two copies of a document is the original shared version and the two copies of the document differ, then the other document shall be newer.</p> |
| <code>_SharedFileIndex</code> | <p>A custom property with this name identifies the workspace that the document belongs to.</p> <p>The child element of this property shall be an lpwstr comprised of three parts: a version number, followed by a GUID, followed by the URL of the workspace.</p> <p>The version number shall be <code>0000020000000000</code>.</p> <p>The GUID shall uniquely identify the document.</p> <p>The URL shall define the requested location of the file on the server. If the location is already occupied by a document with a different GUID, then the document might be relocated.</p> <p>If the value of this property extends beyond 256 characters, it shall be segmented across multiple properties with the root name of <code>_SharedFileIndex</code>. The subsequent properties will be named <code>_SharedFileIndex1</code>, <code>_SharedFileIndex2</code>, <code>_SharedFileIndex3</code>, and so on. The value of each property shall be at most 256 characters; only when those 256 characters have been exceeded shall the next <code>_SharedFileIndex</code> property be created.</p> <p>[Example: The shared file index of a document with a workspace location of <code>http://www.contoso.com/documentschemas/schemaexamples/documentworkspaces/documents/shareddocuments/collaboration/customfileproperties/serverproperties/DocumentWithAReallyReallyLongNameAndAReallyReallyLongServerLocationWhichRequiresSegmentationOfTheSharedFileIndexProperty.docx</code> can be defined as follows:</p> <pre><property fmtid="{D5CDD505-2E9C-101B-9397-08002B2CF9AE}" pid="2" name="_SharedFileIndex"> <vt:lpwstr>0000020000000000{E9AB9F47-8925-4F17-A0B3-A8E86720E301} http://www.contoso.com/documentschemas/schemaexamples/</pre> |

| Name | Description |
|------|---|
| | <pre>documentworkspaces/documents/shareddocuments/ collaboration/customfileproperties/serverproperties/ DocumentWithAReallyReallyLongName AndAReallyReallyL</vt:lpwstr> </property> <property fmtid="{D5CDD505-2E9C-101B-9397-08002B2CF9AE}" pid="3" name="_SharedFileIndex1"> <vt:lpwstr> ongServerLocationWhichRequiresSegmentationOfTheShared FileIndexProperty.docx</vt:lpwstr> </property></pre> <p>end example]</p> |

c. The standard does not define any custom document properties used to convey input parameters for a SpreadsheetML document.

Office reserves the following unique property names for the following purposes:

| Name | Description |
|------------------------------------|---|
| <i>PROP_MULTIVAL_ParameterName</i> | A custom property with this name specifies a filter parameter, where ParameterName is a name given by the user. |
| <i>PROP_ParameterName</i> | A custom property with this name specifies a parameter, where ParameterName is a name given by the user. |

d. The standard lists 21 variant types as possible child elements.

Office only allows **bool**, **filetime**, **empty**, **i4**, **lpstr**, **lpwstr** and **r8** as valid child elements for custom properties where **fmtid** has a value of `{D5CDD505-2E9C-101B-9397-08002B2CF9AE}`.

e. The standard states that the values of the *pid* attribute are defined by the XML Schema *int* datatype.

Office restricts the value of this attribute to be at least 2.

f. The standard does not document any restrictions on the *FmtId* attribute.

The following GUIDs shall not be used in a custom property.

Summary Information

`{f29f85e0-4ff9-1068-ab91-08002b27b3d9}`

Document Summary Information

`{d5cdd502-2e9c-101b-9397-08002b2cf9ae}`

g. The standard specifies that the *name* attribute is defined by the XML Schema *string* datatype.

Office requires that the *name* attribute be a case-insensitive unique name.

2.1.1890 Part 4 Section 7.4, Variant Types

a. The standard allows local namespace declarations.

Office requires namespaces to be declared only on the root element.

This note applies to the following products: 2007, 2007 SP1.

2.1.1891 Part 4 Section 7.4.2.1, array (Array)

- a. *The standard states that the name of the lower bound attribute is lBounds.*

Office uses the name lbound for this attribute.

This note applies to the following products: 2007, 2007 SP1.

- b. *The standard states that the name of the upper bound attribute is uBounds.*

Office uses the name ubound for this attribute.

This note applies to the following products: 2007, 2007 SP1.

- c. *The standard states that the values of the lbound attribute are defined by the XML Schema int datatype.*

Office defines the values of this attribute to be a collection in the format #, #, # ... #, where each # represents an integer and the attribute's value matches the regular expression pattern `\s*[\+|-]?[0-9]+\s*(\,\s*[\+|-]?[0-9]+\s*)*`.

- d. *The standard states that the values of the ubound attribute are defined by the XML Schema int datatype.*

Office defines the values of this attribute to be a collection in the format #, #, # ... #, where each # represents an integer and the attribute's value matches the regular expression pattern `\s*[\+|-]?[0-9]+\s*(\,\s*[\+|-]?[0-9]+\s*)*`.

2.1.1892 Part 4 Section 7.4.2.5, cf (Clipboard Data)

- a. *The standard makes no mention of a size attribute.*

Office requires this attribute, which is defined by the XML schema unsignedInt datatype to specify the size, in bytes, of the decoded string plus the format id.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

- b. *The standard implies that the format attribute is optional.*

Office requires this attribute.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.1893 Part 4 Section 7.4.2.6, clsid (Class ID)

- a. *The standard permits leading or trailing whitespaces in the pattern of the simple type.*

Office does not permit leading or trailing whitespaces.

2.1.1894 Part 4 Section 7.4.2.7, cy (Currency)

- a. *The standard states that currency value should have a precision of 4 decimal points including trailing zeros.*

Office truncates trailing zeros.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.1895 Part 4 Section 7.4.2.8, date (Date and Time)

- a. *The standard states that the date element is compliant with RFC 3339.*

Office is compliant with [\[ISO-8601\]](#) for the XML schema date-time.

2.1.1896 Part 4 Section 7.4.2.10, empty (Empty)

- a. *The standard allows custom properties with vt:empty content.*

Office removes custom properties with vt:empty content when saving documents.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.1897 Part 4 Section 7.4.2.12, filetime (File Time)

- a. *The standard refers to the filetime format as RFC3339.*

Office is compliant with [\[ISO-8601\]](#) for the XML schema date-time.

2.1.1898 Part 4 Section 7.4.2.20, null (Null)

- a. *The standard requires an empty-element tag.*

Office writes a start-element and end-element with whitespace content.

2.1.1899 Part 4 Section 7.4.2.22, ostorage (Binary Storage Object)

- a. *The standard specifies that files are permitted to contain an ostorage tag.*

In Office, the base64binary data contained in the ostorage element must be a compound doc as specified in the Compound File Binary File Format Specification [\[MS-CFB\]](#).

2.1.1900 Part 4 Section 7.4.2.26, storage (Binary Storage)

- a. *The standard specifies that files are permitted to contain storage tags.*

In Office, the base64binary data contained in the storage element must be a compound doc as specified in the Compound File Binary File Format Specification [\[MS-CFB\]](#).

2.1.1901 Part 4 Section 7.4.2.35, vstream (Binary Versioned Stream)

- a. *The standard implies that the version attribute is optional.*

Office requires this attribute.

2.1.1902 Part 4 Section 7.4.3.4, ST_Error (Error Status Code Simple Type)

- a. *The standard allows letters A-Z as hexadecimal digits.*

Office only permits the letters A-F as hexadecimal digits.

b. *The standard permits whitespace characters.*

Office does not allow whitespace characters.

2.1.1903 Part 4 Section 7.4.3.5, ST_Format (Format Simple Type)

a. *The standard does not allow 0 as a valid digit where format id is a positive integer.*

Office allows format id. to have 0 as a valid digit.

This note applies to the following products: 2007, 2007 SP1, 2007 SP2.

2.1.1904 Part 4 Section 7.6.2.5, Author (Contributors List)

a. *The standard states that this element can contain any number of child elements in any order.*

Word only allows a single instance, the first instance in document order, of each child element; the elements, when present, must be in the order specified in the schema.

2.1.1905 Part 4 Section 7.6.2.30, Guid (GUID)

a. *The standard states that this element is a unique identifier for the source.*

When copying a source entry from a source document to a destination document, Word checks to see if the destination document has an entry with the same tag ("[ECMA-376](#) Part 4 §7.6.2.65; Tag (Tag)") as the entry being copied. If a match is found, Word then compares the GUID of the matching entry in the destination document with that of the entry being copied. If the GUIDs are identical, or if the destination document has an entry with the same GUID as the entry being copied, Word assumes the source entry to be already present in the destination document and no new entry is created.

2.1.1906 Part 4 Section 7.6.2.39, LCID (Locale ID)

a. *The standard says LCID represents the source's language.*

Word uses LCID as the language to format the source when the documentation style in use has language-dependant variability.

b. *The standard does not allow 0 as a value for LCID.*

Word sets LCID to 0 to mean the value should be determined at runtime by the application.

c. *The standard states that the LCID table in ST_LangCode shall be used to associate language IDs with languages.*

In Office, this element represents the language that shall be used to format the source. The set of locale IDs used by Office are specified in the following table.

| Language Code | Description (informative) | BCP 47 Code |
|----------------------|----------------------------------|--------------------|
| 1025 | Arabic - Saudi Arabia | ar-SA |
| 1026 | Bulgarian | bg-BG |
| 1027 | Catalan | ca-ES |
| 1028 | Chinese - Taiwan | zh-TW |

| Language Code | Description (informative) | BCP 47 Code |
|----------------------|------------------------------------|--------------------|
| 1029 | Czech | cs-CZ |
| 1030 | Danish | da-DK |
| 1031 | German - Germany | de-DE |
| 1032 | Greek | el-GR |
| 1033 | English - United States | en-US |
| 1034 | Spanish - Spain (Traditional Sort) | es-ES |
| 1035 | Finnish | fi-FI |
| 1036 | French - France | fr-FR |
| 1037 | Hebrew | he-IL |
| 1038 | Hungarian | hu-HU |
| 1039 | Icelandic | is-IS |
| 1040 | Italian - Italy | it-IT |
| 1041 | Japanese | ja-JP |
| 1042 | Korean | ko-KR |
| 1043 | Dutch - Netherlands | nl-NL |
| 1044 | Norwegian (Bokmål) | nb-NO |
| 1045 | Polish | pl-PL |
| 1046 | Portuguese - Brazil | pt-BR |
| 1047 | Rhaeto-Romanic | rm-CH |
| 1048 | Romanian | ro-RO |
| 1049 | Russian | ru-RU |
| 1050 | Croatian | hr-HR |
| 1051 | Slovak | sk-SK |
| 1052 | Albanian - Albania | sq-AL |
| 1053 | Swedish | sv-SE |
| 1054 | Thai | th-TH |
| 1055 | Turkish | tr-TR |
| 1056 | Urdu - Pakistan | ur-PK |
| 1057 | Indonesian | id-ID |
| 1058 | Ukrainian | uk-UA |

| Language Code | Description (informative) | BCP 47 Code |
|----------------------|----------------------------------|--------------------|
| 1059 | Belarusian | be-BY |
| 1060 | Slovenian | sl-SI |
| 1061 | Estonian | et-EE |
| 1062 | Latvian | lv-LV |
| 1063 | Lithuanian | lt-LT |
| 1064 | Tajik | tg-Cyrl-TJ |
| 1065 | Persian | fa-IR |
| 1066 | Vietnamese | vi-VN |
| 1067 | Armenian - Armenia | hy-AM |
| 1068 | Azeri (Latin) | az-Latn-AZ |
| 1069 | Basque | eu-ES |
| 1070 | Sorbian | wen-DE |
| 1071 | F.Y.R.O. Macedonian | mk-MK |
| 1072 | Sutu | st-ZA |
| 1073 | Tsonga | ts-ZA |
| 1074 | Tswana | tn-ZA |
| 1075 | Venda | ven-ZA |
| 1076 | Xhosa | xh-ZA |
| 1077 | Zulu | zu-ZA |
| 1078 | Afrikaans - South Africa | af-ZA |
| 1079 | Georgian | ka-GE |
| 1080 | Faroese | fo-FO |
| 1081 | Hindi | hi-IN |
| 1082 | Maltese | mt-MT |
| 1083 | Sami | se-NO |
| 1084 | Gaelic (Scotland) | gd-GB |
| 1085 | Yiddish | yi |
| 1086 | Malay - Malaysia | ms-MY |
| 1087 | Kazakh | kk-KZ |
| 1088 | Kyrgyz (Cyrillic) | ky-KG |

| Language Code | Description (informative) | BCP 47 Code |
|----------------------|--------------------------------------|--------------------|
| 1089 | Swahili | sw-KE |
| 1090 | Turkmen | tk-TM |
| 1091 | Uzbek (Latin) | uz-Latn-UZ |
| 1092 | Tatar | tt-RU |
| 1093 | Bengali (India) | bn-IN |
| 1094 | Punjabi | pa-IN |
| 1095 | Gujarati | gu-IN |
| 1096 | Oriya | or-IN |
| 1097 | Tamil | ta-IN |
| 1098 | Telugu | te-IN |
| 1099 | Kannada | kn-IN |
| 1100 | Malayalam | ml-IN |
| 1101 | Assamese | as-IN |
| 1102 | Marathi | mr-IN |
| 1103 | Sanskrit | sa-IN |
| 1104 | Mongolian (Cyrillic) | mn-MN |
| 1105 | Tibetan - People's Republic of China | bo-CN |
| 1106 | Welsh | cy-GB |
| 1107 | Khmer | km-KH |
| 1108 | Lao | lo-LA |
| 1109 | Burmese | my-MM |
| 1110 | Galician | gl-ES |
| 1111 | Konkani | kok-IN |
| 1112 | Manipuri | mni |
| 1113 | Sindhi - India | sd-IN |
| 1114 | Syriac | syr-SY |
| 1115 | Sinhalese - Sri Lanka | si-LK |
| 1116 | Cherokee - United States | chr-US |
| 1117 | Inuktitut | iu-Cans-CA |
| 1118 | Amharic - Ethiopia | am-ET |

| Language Code | Description (informative) | BCP 47 Code |
|----------------------|--------------------------------------|--------------------|
| 1119 | Tamazight (Arabic) | tmz |
| 1120 | Kashmiri (Arabic) | ks-Arab-IN |
| 1121 | Nepali | ne-NP |
| 1122 | Frisian - Netherlands | fy-NL |
| 1123 | Pashto | ps-AF |
| 1124 | Filipino | fil-PH |
| 1125 | Divehi | dv-MV |
| 1126 | Edo | bin-NG |
| 1127 | Fulfulde - Nigeria | fuv-NG |
| 1128 | Hausa - Nigeria | ha-Latn-NG |
| 1129 | Ibibio - Nigeria | ibb-NG |
| 1130 | Yoruba | yo-NG |
| 1131 | Quecha - Bolivia | quz-BO |
| 1132 | Sepedi | nso-ZA |
| 1136 | Igbo - Nigeria | ig-NG |
| 1137 | Kanuri - Nigeria | kr-NG |
| 1138 | Oromo | gaz-ET |
| 1139 | Tigrigna - Ethiopia | ti-ER |
| 1140 | Guarani - Paraguay | gn-PY |
| 1141 | Hawaiian - United States | haw-US |
| 1142 | Latin | la |
| 1143 | Somali | so-SO |
| 1144 | Yi | ii-CN |
| 1145 | Papiamentu | pap-AN |
| 1152 | Uighur - China | ug-Arab-CN |
| 1153 | Maori - New Zealand | mi-NZ |
| 2049 | Arabic - Iraq | ar-IQ |
| 2052 | Chinese - People's Republic of China | zh-CN |
| 2055 | German - Switzerland | de-CH |
| 2057 | English - United Kingdom | en-GB |

| Language Code | Description (informative) | BCP 47 Code |
|----------------------|----------------------------------|--------------------|
| 2058 | Spanish - Mexico | es-MX |
| 2060 | French - Belgium | fr-BE |
| 2064 | Italian - Switzerland | it-CH |
| 2067 | Dutch - Belgium | nl-BE |
| 2068 | Norwegian (Nynorsk) | nn-NO |
| 2070 | Portuguese - Portugal | pt-PT |
| 2072 | Romanian - Moldava | ro-MD |
| 2073 | Russian - Moldava | ru-MD |
| 2074 | Serbian (Latin) | sr-Latn-CS |
| 2077 | Swedish - Finland | sv-FI |
| 2080 | Urdu - India | ur-IN |
| 2092 | Azeri (Cyrillic) | az-Cyrl-AZ |
| 2108 | Gaelic (Ireland) | ga-IE |
| 2110 | Malay - Brunei Darussalam | ms-BN |
| 2115 | Uzbek (Cyrillic) | uz-Cyrl-UZ |
| 2117 | Bengali (Bangladesh) | bn-BD |
| 2118 | Punjabi (Pakistan) | pa-PK |
| 2128 | Mongolian (Mongolian) | mn-Mong-CN |
| 2129 | Tibetan - Bhutan | bo-BT |
| 2137 | Sindhi - Pakistan | sd-PK |
| 2143 | Tamazight (Latin) | tzm-Latn-DZ |
| 2144 | Kashmiri (Devanagari) | ks-Deva-IN |
| 2145 | Nepali - India | ne-IN |
| 2155 | Quecha - Ecuador | quz-EC |
| 2163 | Tigrigna - Eritrea | ti-ET |
| 3073 | Arabic - Egypt | ar-EG |
| 3076 | Chinese - Hong Kong SAR | zh-HK |
| 3079 | German - Austria | de-AT |
| 3081 | English - Australia | en-AU |
| 3082 | Spanish - Spain (Modern Sort) | es-ES |

| Language Code | Description (informative) | BCP 47 Code |
|----------------------|----------------------------------|--------------------|
| 3084 | French - Canada | fr-CA |
| 3098 | Serbian (Cyrillic) | sr-Cyrl-CS |
| 3179 | Quecha - Peru | quz-PE |
| 4097 | Arabic - Libya | ar-LY |
| 4100 | Chinese - Singapore | zh-SG |
| 4103 | German - Luxembourg | de-LU |
| 4105 | English - Canada | en-CA |
| 4106 | Spanish - Guatemala | es-GT |
| 4108 | French - Switzerland | fr-CH |
| 4122 | Croatian (Bosnia/Herzegovina) | hr-BA |
| 5121 | Arabic - Algeria | ar-DZ |
| 5124 | Chinese - Macao SAR | zh-MO |
| 5127 | German - Liechtenstein | de-LI |
| 5129 | English - New Zealand | en-NZ |
| 5130 | Spanish - Costa Rica | es-CR |
| 5132 | French - Luxembourg | fr-LU |
| 5146 | Bosnian (Bosnia/Herzegovina) | bs-Latn-BA |
| 6145 | Arabic - Morocco | ar-MO |
| 6153 | English - Ireland | en-IE |
| 6154 | Spanish - Panama | es-PA |
| 6156 | French - Monaco | fr-MC |
| 7169 | Arabic - Tunisia | ar-TN |
| 7177 | English - South Africa | en-ZA |
| 7178 | Spanish - Dominican Republic | es-DO |
| 7180 | French - West Indies | fr-029 |
| 8193 | Arabic - Oman | ar-OM |
| 8201 | English - Jamaica | en-JM |
| 8202 | Spanish - Venezuela | es-VE |
| 8204 | French - Reunion | fr-RE |
| 9217 | Arabic - Yemen | ar-YE |

| Language Code | Description (informative) | BCP 47 Code |
|----------------------|-----------------------------------|--------------------|
| 9225 | English - Caribbean | en-029 |
| 9226 | Spanish - Colombia | es-CO |
| 9228 | French - Democratic Rep. of Congo | fr-CG |
| 10241 | Arabic - Syria | ar-SY |
| 10249 | English - Belize | en-BZ |
| 10250 | Spanish - Peru | es-PE |
| 10252 | French - Senegal | fr-SN |
| 11265 | Arabic - Jordan | ar-JO |
| 11273 | English - Trinidad | en-TT |
| 11274 | Spanish - Argentina | es-AR |
| 11276 | French - Cameroon | fr-CM |
| 12289 | Arabic - Lebanon | ar-LB |
| 12297 | English - Zimbabwe | en-ZW |
| 12298 | Spanish - Ecuador | es-EC |
| 12300 | French - Cote d'Ivoire | fr-CI |
| 13313 | Arabic - Kuwait | ar-KW |
| 13321 | English - Philippines | en-PH |
| 13322 | Spanish - Chile | es-CL |
| 13324 | French - Mali | fr-ML |
| 14337 | Arabic - U.A.E. | ar-AE |
| 14345 | English - Indonesia | en-ID |
| 14346 | Spanish - Uruguay | es-UY |
| 14348 | French - Morocco | fr-MA |
| 15361 | Arabic - Bahrain | ar-BH |
| 15369 | English - Hong Kong SAR | en-HK |
| 15370 | Spanish - Paraguay | es-PY |
| 15372 | French - Haiti | fr-HT |
| 16385 | Arabic - Qatar | ar-QA |
| 16393 | English - India | en-IN |
| 16394 | Spanish - Bolivia | es-BO |

| Language Code | Description (informative) | BCP 47 Code |
|-----------------|-------------------------------|-------------|
| 17417 | English - Malaysia | en-MY |
| 17418 | Spanish - El Salvador | es-SV |
| 18441 | English - Singapore | en-SG |
| 18442 | Spanish - Honduras | es-HN |
| 19466 | Spanish - Nicaragua | es-NI |
| 20490 | Spanish - Puerto Rico | es-PR |
| 21514 | Spanish - United States | es-US |
| 58378 | Spanish - Latin America | es-419 |
| 58380 | French - North Africa | fr-015 |
| Any other value | Undefined. Shall not be used. | |

2.1.1907 Part 4 Section 7.6.2.50, Person (Person)

a. *The standard states that the person element can contain any number of each of its child elements.*

Word only reads the first instance of each child element.

2.1.1908 Part 4 Section 7.6.2.59, Source (Source)

a. *The standard states that this element can contain any number of child elements in any order.*

Word only allows a single instance, the first instance in document order, of each child element.

2.1.1909 Part 4 Section 7.6.2.65, Tag (Tag)

a. *The standard states that the value of this element has a minimum of 0 and a maximum of 255 characters.*

Word restricts the value of this element to have a minimum of 1 and a maximum of 32 characters.

2.1.1910 Part 4 Section 7.6.2.76, YearAccessed (Year Accessed)

a. *The standard states that the YearAccessed element stores the month in which a source was accessed.*

Office interprets this element as the year in which the source was accessed.

2.1.1911 Part 4 Section 7.8.2.1, ST_RelationshipId (Explicit Relationship ID)

a. *The standard does not limit the length of the contents of the ST_RelationshipId simple type.*

Office restricts the contents of this simple type to be at most 255 characters.

b. *The standard states that the values of the ST_RelationshipId simple type are a restriction on the XML Schema string datatype.*

Office defines this simple type as being a restriction on the XML Schema id datatype.

2.1.1912 Part 4 Section 8.2.1, schema (Custom XML Schema Reference)

a. *The standard places no restrictions on the length of the uri attribute.*

Word restricts the length of this attribute to 255 characters.

b. *The standard places no restrictions on the length of the manifestLocation or the schemaLocation attribute.*

Word restricts the length of these attributes to 2083 characters.

c. *The standard does not state that the schema and schemaLibrary information might not be round-tripped.*

Word does not guarantee that the schema or schemaLibrary elements will be round-tripped; validation or security verification might result in this data being removed.

2.1.1913 Part 5 Section 9, Markup Compatibility Attributes and Elements

a. *The standard does not state that extensibility is optional per part.*

Office does not permit markup compatibility attributes or elements in document property parts.

3 Appendix A: Additional Information

3.1 Word

This section contains additional information used to describe more fully how Word implements ECMA-376 Office Open XML File Formats [\[ECMA-376\]](#).

3.1.1 Additional Parts

The subclauses subordinate to this one describe in detail each of the part types specific to Word, in addition to those listed as part of ECMA-376 Office Open XML File Formats ("[\[ECMA-376\]](#) Part 1 §11; WordprocessingML").

3.1.1.1 Word Attached Toolbars Part

Content Type

application/vnd.ms-word.attachedToolbars

Root Namespace

Not applicable

Source Relationship

<http://schemas.microsoft.com/office/2006/relationships/attachedToolbars>

This binary part supports the storage of custom toolbars created by the user.

A package shall contain at most one Attached Toolbars part, and that part shall be the target of an implicit relationship from the Customizations part ([§3.1.1.2, Customizations Part](#)).

[Example: The following Customizations part-relationship item contains a relationship to the Attached Toolbars part, which is stored in the ZIP item attachedToolbars.bin:

```
<Relationships xmlns="...">
  <Relationship Id="rId1"
    Type="http://.../attachedToolbars" Target="attachedToolbars.bin"/>
</Relationships>
```

end example]

An Attached Toolbars part shall be located within the package containing the source relationship (expressed syntactically, the **TargetMode** attribute of the **Relationship** element shall be *Internal*).

An Attached Toolbars part shall not have implicit or explicit relationships to any part defined by ECMA-376 Office Open XML File Formats [\[ECMA-376\]](#).

The ZIP item attachedToolbars.bin contains a single binary stream with a single CTBWRAPPER structure as specified in the Word 97-2003 Binary File Format (.doc) Structure Specification ("[\[MS-DOC\]](#) section 2.9.49; CTBWRAPPER") book.

3.1.1.2 Customizations Part

Content Type

application/vnd.ms-word.keyMapCustomizations+xml

Root Namespace

http://schemas.openxmlformats.org/wordprocessingml/2006/main

Source Relationship

http://schemas.microsoft.com/office/2006/relationships/keyMapCustomizations

An instance of this part type contains the document's template command group (TCG), which consists of key mapping and toolbar customizations.

A package shall contain no more than two Customizations parts. If it exists, one instance of that part shall be the target of an implicit relationship from the Main Document part ("ECMA-376 Part 1 §11.3.10; Main Document Part"), and the other instance shall be the target of an implicit relationship from the Glossary Document part ("ECMA-376 Part 1 §11.3.8; Glossary Document Part").

[Example: The following Main Document part-relationship item contains a relationship to a Customizations part, which is stored in the ZIP item customizations.xml:

```
<Relationships xmlns="...">
  <Relationship Id="rId4"
    Type="http://.../keyMapCustomizations" Target="customizations.xml"/>
</Relationships>
```

end example]

The root element for a part of this content type shall be **tcg**.

[Example:

```
<wne:tcg ...>
  <wne:keymaps>
    <wne:keymap wne:kcmPrimary="0341">
      <wne:fcf wne:fcfName="CssLinks" wne:swArg="0000"/>
    </wne:keymap>
  </wne:keymaps>
  <wne:toolbars>
    <wne:toolbarData r:id="rId1"/>
  </wne:toolbars>
</wne:tcg>
```

end example]

A Customizations part is permitted to contain explicit relationships to the following parts defined by ECMA-376 Office Open XML File Formats [ECMA-376](#):

Word Attached Toolbars Part ([§3.1.1.1, Word Attached Toolbars Part](#))

A Customizations part shall not have any implicit or explicit relationships to any other part defined by ECMA-376 Office Open XML File Formats [ECMA-376](#).

3.1.1.3 Mail Merge Recipient Data Part

Content Type

application/vnd.openxmlformats-officedocument.wordprocessingml.mailMergeRecipientData+xml

or

application/vnd.ms-word.mailMergeRecipientData+xml

Root Namespace

http://schemas.openxmlformats.org/wordprocessingml/2006/main

or

http://schemas.microsoft.com/office/word/2006/wordml

Source Relationship

http://schemas.openxmlformats.org/officeDocument/2006/relationships/recipientData

An instance of this part type contains the document's Mail Merge Recipient Data.

A package shall contain no more than one Mail Merge Recipient Data part. If it exists, the instance of that part shall be the target of an explicit relationship from the Document Settings part.

[Example:

```
<Relationships xmlns="...">
  <Relationship Id="rId2"
    Type="http://.../recipientData" Target="recipientData.xml"/>
</Relationships>
```

end example]

The root element for a Mail Merge Recipient Data part shall be **recipients**.

[Example:

```
<w:recipients xmlns:w="http://schemas.openxmlformats.org/wordprocessingml/2006/main" ...>
  <w:recipientData>
    <w:active w:val="0" />
    <w:column w:val="62">
      <w:uniqueTag
w:val="KnmjIQAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAA&#xA;
AAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAA&#xA;
AAAAAAAAAAAAAAAAAAAA=" />
    </wne:recipientData>
  ...
</wne:recipients>
```

In this example, the content type is "application/vnd.openxmlformats-officedocument.wordprocessingml.mailMergeRecipientData+xml."

end example]

[Example:

```
<wne:recipients xmlns:wne="http://schemas.microsoft.com/office/word/2006/wordml ...>
  <wne:recipientData>
    <wne:active wne:val="1" />
    <wne:hash wne:val="2094012985">
  </wne:recipientData>
  ...
</wne:recipients>
```

In this example, the content type is "application/vnd.ms-word.mailMergeRecipientData+xml."

end example]

A Mail Merge Recipient Data part shall be located within the package containing the source relationship (expressed syntactically, the **TargetMode** attribute of the **Relationship** element shall be *Internal*).

A Mail Merge Recipient Data part shall not contain implicit or explicit relationships to any other part defined by ECMA-376 Office Open XML File Formats [\[ECMA-376\]](#).

3.1.2 Word Schema

The following clauses define additional information used by Word to help implement ECMA-376 Office Open XML File Formats [\[ECMA-376\]](#).

3.1.2.1 Keyboard and Toolbar Customizations

The following clauses specify the semantics used by Word to customize keyboard and toolbar commands.

3.1.2.1.1 Elements

3.1.2.1.1.1 acd (Allocated Command)

This element is used to declare an allocated command for use elsewhere in the Keyboard and Toolbar customization XML part. While ordinary fixed commands (§[3.1.2.1.1.7, fci](#)) can take an optional numeric argument, allocated commands are fixed commands that take a Base64 MIME transfer content encoded argument.

[Example: Consider the following allocated command declaration:

```
<wne:acd wne:argValue="AAA=" wne:acdName="acd0" wne:fciBasedOn="Color"/>
```

In this example, the WordprocessingML declares that the allocated command identified as `acd0` is based on the `Color` fixed command and takes the Base64 encoded argument specified in the `argValue` attribute that decodes to the integer value 0. When this allocated command is executed, it has the effect of causing Word to color the currently selected text according to its default color. end example]

| Parent Elements |
|--|
| acds (§ 3.1.2.1.1.5, acds) |

| Attributes | Description |
|---|---|
| acdName (Allocated command name) | <p>Specifies the friendly name for identifying this allocated command. While any valid string can be used for this name, Word writes out allocated command names in sequence of the form <code>acd0</code>, <code>acd1</code>, <code>acd2</code>, regardless of any name the allocated command may have been given. Consequently, a name like <code>myacd</code> could be specified in a file for a lone allocated command but would be written out as <code>acd0</code> upon resaving the document.</p> <p>The possible values for this attribute are defined by the <code>ST_String</code> simple type (§3.1.2.3.5, ST_String).</p> |
| argValue (Allocated Command Arguments) | <p>Specifies the argument that should be passed to the fixed command given by the <code>fciBasedOn</code> and <code>fciIndexBasedOn</code> attributes. Its contents are Base64 MIME content transfer encoded. While there is no strict limit on the length of this Base64 encoded string, only the first 510 bytes of decoded data will be used. Invalid Base64 characters in the string (such as carriage returns or whitespace) are ignored on read, but Word may produce them on write.</p> <p>If this attribute is not specified, an empty argument is passed to the associated fixed command, which may cause the command to do nothing on execution.</p> <p>The possible values for this attribute are defined by the <code>ST_String</code> simple type (§3.1.2.3.5, ST_String).</p> |
| fciBasedOn (Fixed command based on) | <p>Specifies the friendly name of the fixed command that shall be used for this allocated command. If both this attribute and <code>fciIndexBasedOn</code> are specified, this attribute will be used.</p> <p>Only 11 fixed commands shall be used as allocated commands in Word: <i>Borders</i>, <i>Color</i>, <i>Columns</i>, <i>Condensed</i>, <i>Expanded</i>, <i>FileOpenFile</i>, <i>FontSize</i>, <i>Lowered</i>, <i>Raised</i>, <i>Shading</i> and <i>Symbol</i>.</p> <p>The possible values for this attribute are defined by the <code>ST_String</code> simple type (§3.1.2.3.5, ST_String).</p> |
| fciIndexBasedOn (Index of fixed command) | <p>Specifies the numeric index of the fixed command that shall be used for this allocated command. A table mapping the friendly names of all fixed commands (including those mentioned in <code>fciBasedOn</code>--the only valid fixed commands that may be used for allocated commands) may be found in Fixed Commands (§3.1.2.1.2, Fixed Commands).</p> <p>If both this attribute and <code>fciBasedOn</code> are specified, <code>fciBasedOn</code> will be used. The fciIndexBasedOn attribute may be converted to fciBasedOn upon resaving of the document.</p> <p>The possible values for this attribute are defined by the <code>ST_ShortHexNumber</code> simple type (§3.1.2.3.4, ST_ShortHexNumber).</p> |

The following XML Schema fragment defines the contents of this element:

```
<complexType name="CT_Acd">
  <attribute name="argValue" type="ST_String"/>
  <attribute name="fciBasedOn" type="ST_String"/>
  <attribute name="fciIndexBasedOn" type="ST_ShortHexNumber"/>
  <attribute name="acdName" type="ST_String" use="required"/>
</complexType>
```

3.1.2.1.1.2 acd (Allocated Command Keyboard Customization Action)

This element specifies that an allocated command should be executed by the enclosing key map.

[Example: Consider the following key map:

```
<wne:keymap wne:kcmPrimary="0238">
  <wne:acd wne:acdName="acd0" />
</wne:keymap>
```

In this example, the WordprocessingML fragment specifies that pressing Control-8 (the meaning of a KCM of 0238) will execute the allocated command identified by `acd0`. end example]

| Parent Elements |
|---|
| keymap (§3.1.2.1.1.8, keymap) |

| Attributes | Description |
|---|--|
| acdName (Allocated command name) | Specifies the friendly name of the allocated command to execute. The possible values for this attribute are defined by the ST_String simple type (§3.1.2.3.5, ST String). |

The following XML Schema fragment defines the contents of this element:

```
<complexType name="CT_AcdKeymap">
  <attribute name="acdName" type="ST_String" use="required"/>
</complexType>
```

3.1.2.1.1.3 acdEntry (Allocated Command Manifest Entry)

This element identifies the allocated command that is associated with the numeric index specified by its order under the enclosing **acdManifest** element.

| Parent Elements |
|---|
| acdManifest (§3.1.2.1.1.4, acdManifest) |

| Attributes | Description |
|---|--|
| acdName (Allocated command name) | Specifies the friendly name of the allocated command to execute. The possible values for this attribute are defined by the ST_String simple type (§3.1.2.3.5, ST String). |

The following XML Schema fragment defines the contents of this element:

```
<complexType name="CT_AcdKeymap">
  <attribute name="acdName" type="ST_String" use="required"/>
</complexType>
```

3.1.2.1.1.4 acdManifest (Allocated Command Manifest)

The binary toolbar customization information identifies allocated commands by a numeric index while this XML file format identifies allocated commands by a friendly string-based name. This element provides a mapping between the numeric indices and friendly names for allocated commands. The order of an entry specifies its numeric index for use in the attached binary toolbar data.

[Example: Consider the following allocated command manifest:

```
<wne:toolbars>
  <wne:acdManifest>
    <wne:acdEntry wne:acdName="acd2"/>
    <wne:acdEntry wne:acdName="acd3"/>
  </wne:acdManifest>
</wne:toolbars>
```

In this example, the WordprocessingML fragment specifies that `acd2` holds index 0 and `acd3` holds index 1. end example]

| Parent Elements |
|---|
| toolbars (§3.1.2.1.1.14, toolbars) |

| Child Elements | Subclause |
|--|--|
| acdEntry (Allocated Command Manifest Entry) | §3.1.2.1.1.3, acdEntry |

The following XML Schema fragment defines the contents of this element:

```
<complexType name="CT_AcdManifest">
  <sequence>
    <element name="acdEntry" type="CT_AcdKeymap" minOccurs="1" maxOccurs="unbounded"/>
  </sequence>
</complexType>
```

3.1.2.1.1.5 acds (Allocated Commands)

This element serves as a container for the declaration of allocated commands.

| Parent Elements |
|---|
| tcg (§3.1.2.1.1.12, tcg) |

| Child Elements | Subclause |
|--------------------------------|-----------------------------------|
| acd (Allocated Command) | §3.1.2.1.1.1, acd |

The following XML Schema fragment defines the contents of this element:


```

<complexType name="CT_Acids">
  <sequence>
    <element name="acd" type="CT_Acd" minOccurs="1" maxOccurs="unbounded"/>
  </sequence>
</complexType>

```

3.1.2.1.1.6 active (Record Is Included in Mail Merge)

This element specifies whether a specific record from the specified external data source shall be imported into a merged WordprocessingML document when the mail merge defined for a source document is performed. If this element's **val** attribute is *false*, then the record specified by the parent element shall not be used to create a merged document.

If this element is omitted for a given record, the data record associated with it shall be imported into a merged WordprocessingML document when the mail merge is performed.

[Example: Consider the following fragment from a source WordprocessingML document that is connected to an external data source containing two records, one of which will not be imported into a merged WordprocessingML document when the conforming hosting application performs the data import.

```

<w:recipients>
  <w:recipientData>
    <w:active w:val="false" />
    <w:hash w:val="1126664175" />
  </w:recipientData>
  <w:recipientData>
    <w:hash w:val="1530576378" />
  </w:recipientData>
</w:recipients>

```

In this XML fragment, the external data record that is identified by the **hash** element (§3.1.2.2.1.1, [hash](#)) with a **val** attribute equal to *1126664175* will not be imported into a merged document because the **active** element associated with it has a **val** attribute equal to *false*. Conversely, the external data record associated with the **hash** element with a **val** attribute equal to *1530576378* will be imported into a merged document because its **active** element has been omitted, implying the default value of *true*. end example]

| Parent Elements |
|---|
| recipientData (§3.1.2.2.1.2, recipientData) |

| Attributes | Description |
|---------------|---|
| val () | The possible values for this attribute are defined by the ST_OnOff simple type (§3.1.2.3.3, ST_OnOff). |

The following XML Schema fragment defines the contents of this element:

```

<complexType name="CT_OnOff">
  <attribute name="val" type="ST_OnOff"/>

```

</complexType>

3.1.2.1.1.7 fci (Fixed Command Keyboard Customization Action)

The **fci** element specifies the command that will be executed for the keyboard shortcut specified in the enclosing **keymap** element. This element must reference either an identifying name or index by using the *fciName* or *fciIndex* attribute, respectively. If both attributes are specified, *fciName* takes precedence for determining the command to execute. When writing a document, *fciName* will be used if a name can be determined for the command. If a name cannot be determined, *fciIndex* will be used instead.

For a list of public fixed command names and corresponding indices available in Word, refer to Fixed Commands (§3.1.2.1.2, [Fixed Commands](#)).

[Example: Consider the following key mapping fragment:

```
<wne:keymap wne:kcmPrimary="0342">
  <wne:fci wne:fciName="Bold" />
</wne:keymap>
```

In this example, the WordprocessingML assigns the `Bold` fixed command to the keyboard shortcut mapping to KCM 0342 (Ctrl-Shift-B).

Alternately, the same effect can be achieved using the *fciIndex* instead of *fciName*:

```
<wne:keymap wne:kcmPrimary="0342">
  <wne:fci wne:fciIndex="002D" />
</wne:keymap>
```

end example]

| Parent Elements |
|---|
| keymap (§3.1.2.1.1.8, keymap) |

| Attributes | Description |
|--|--|
| fciIndex (Index of fixed command) | Specifies numeric identifier for a fixed command. For a list of public fixed command names and their indices available in Word, refer to Fixed Commands (§3.1.2.1.2, Fixed Commands). The possible values for this attribute are defined by the ST_ShortHexNumber simple type (§3.1.2.3.4, ST_ShortHexNumber). |
| fciName (Fixed command name) | Specifies friendly identifier for a fixed command. For a list of public fixed command names available in Word, refer to Fixed Commands (§3.1.2.1.2, Fixed Commands). The possible values for this attribute are defined by the ST_String simple type (§3.1.2.3.5, ST_String). |
| swArg (Fixed) | Specifies an optional numeric argument for a fixed command. |

| Attributes | Description |
|-------------------|--|
| command argument) | The possible values for this attribute are defined by the ST_ShortHexNumber simple type (§3.1.2.3.4, ST_ShortHexNumber). |

The following XML Schema fragment defines the contents of this element:

```
<complexType name="CT_Fci">
  <attribute name="fciName" type="ST_String"/>
  <attribute name="fciIndex" type="ST_ShortHexNumber"/>
  <attribute name="swArg" type="ST_ShortHexNumber"/>
</complexType>
```

3.1.2.1.1.8 keymap (Key Map Entry)

This element describes an individual key mapping. Its attributes collectively specify a sequence of key combinations that, when pressed, will cause the execution of an action such as a fixed command or macro. The action to execute is described by a single child element. A built-in key mapping can also be blocked.

The key combination for the mapping may be specified using KCM- (key code with modifiers) and CHM- (character with modifiers) based attributes. Both use a set of binary flags for the first (or left) byte to designate the modifier keys for a key combination. Starting at the least significant bit, these take the order Shift, Control, Alt and Command (where the operating system distinguishes between Command and Control). These flags may be used individually or combined. For example, using Control as the only modifier would be represented by 02 (only the second bit is on) while using Control and Alt simultaneously would be 06 (the second and third bits are on).

If a secondary key combination attribute is omitted and a primary key combination has already been defined, the associated action will be executed as soon as the primary key combination has been pressed; otherwise, if both are specified, the action will not execute until both key combinations have been pressed in sequence.

[Example: Consider the following key mapping fragment:

```
<wne:keymap wne:kcmPrimary="0342" wne:kcmSecondary="0441">
  <wne:fci ... />
</wne:keymap>
```

In this example, the WordprocessingML describes a mapping for a sequence of two key combinations given by the KCMs of 0342 and 0441. A KCM of 0342 represents Ctrl-Shift-B and 0441 represents Alt-A, meaning that the user needs to type Control-Shift-B followed by Alt-A to trigger this mapping's action. The `fci` child element signifies that a fixed command will be executed when the specified key sequence is pressed. end example]

| Parent Elements |
|---|
| keymaps (§3.1.2.1.1.9, keymaps); keymapsBad (§3.1.2.1.1.10, keymapsBad) |

| Child Elements | Subclause |
|--|--------------------------------------|
| acd (Allocated Command Keyboard Customization Action) | §3.1.2.1.1.2, acd |
| fci (Fixed Command Keyboard Customization Action) | §3.1.2.1.1.7, fci |
| macro (Macro Keyboard Customization Action) | §3.1.2.1.1.11, macro |
| wch (Character Insertion Keyboard Customization Action) | §3.1.2.1.1.15, wch |
| wll (WLL Macro Keyboard Customization Action) | §3.1.2.1.1.16, wll |

| Attributes | Description |
|---|---|
| chmPrimary (Keyboard Shortcut Primary Character Code) | <p>Specifies the first CHM key combination in the sequence.</p> <p>The left byte contains modifiers described in keymap (§3.1.2.1.1.8, keymap) and the right byte specifies the ASCII value of the character of this key combination.</p> <p>[Note: When specifying CHM values, the case of the letter is significant with respect to shift acting as a modifier or not.]</p> <p>[Example: Consider this list of example key combinations and their corresponding CHM in parentheses: Shift-Control-Alt-C (0643) Alt-C (0463) Control-K (026B) end example]</p> <p>The possible values for this attribute are defined by the ST_ShortHexNumber simple type (§3.1.2.3.4, ST_ShortHexNumber).</p> |
| chmSecondary (Keyboard Shortcut Secondary Character Code) | <p>Specifies the second CHM key combination in the sequence.</p> <p>The CHM value here is defined the same as for chmPrimary.</p> <p>The possible values for this attribute are defined by the ST_ShortHexNumber simple type (§3.1.2.3.4, ST_ShortHexNumber).</p> |
| kcmPrimary (Primary keycode with modifier) | <p>Specifies the first key combination in the sequence.</p> <p>The left byte contains modifiers described in keymap (§3.1.2.1.1.8, keymap), and the right byte specifies the standard Windows virtual key code of this key combination.</p> <p>[Example: Consider this list of example key combinations and their corresponding KCM in parentheses: Shift-Control-Alt-C (0743) Alt-F9 (0478) Control-K (024B) end example]</p> <p>The possible values for this attribute are defined by the ST_ShortHexNumber simple type (§3.1.2.3.4, ST_ShortHexNumber).</p> |
| kcmSecondary (Secondary keycode with modifier) | <p>Specifies the second key combination in the sequence.</p> <p>The KCM value here is defined the same as for kcmPrimary.</p> <p>The possible values for this attribute are defined by the ST_ShortHexNumber simple type (§3.1.2.3.4, ST_ShortHexNumber).</p> |

| Attributes | Description |
|---|--|
| mask (Built-in Command Masking Flag) | <p>If this Boolean attribute is set to an on value, the specified built-in key mapping will be masked out. In such a case, any child element specified shall be ignored because the masking of a key mapping does not involve specifying either a replacement action or the action being blocked. If this attribute is omitted or given an off value, a child element must be specified or the key map will be ignored.</p> <p>[Example: Consider the case where Control-B (the built-in key mapping for the Bold fixed command) has been masked:</p> <pre data-bbox="602 449 1268 527"> <wne:keymaps> <wne:keymap wne:mask="1" wne:kcmPrimary="0242"/> </wne:keymaps> </pre> <p>KCM 0242 has been masked or blocked from its built-in behavior. The effect is that pressing Control-B will no longer execute the built-in command (in this case bold). end example]</p> <p>The possible values for this attribute are defined by the ST_OnOff simple type (§3.1.2.3.3, ST_OnOff).</p> |

The following XML Schema fragment defines the contents of this element:

```

<complexType name="CT_Keymap">
  <choice minOccurs="0" maxOccurs="1">
    <element name="fci" type="CT_Fci"/>
    <element name="macro" type="CT_MacroWll"/>
    <element name="acd" type="CT_AcdKeymap"/>
    <element name="wll" type="CT_MacroWll"/>
    <element name="wch" type="CT_LongHexNumber"/>
  </choice>
  <attribute name="chmPrimary" type="ST_ShortHexNumber"/>
  <attribute name="chmSecondary" type="ST_ShortHexNumber"/>
  <attribute name="kcmPrimary" type="ST_ShortHexNumber"/>
  <attribute name="kcmSecondary" type="ST_ShortHexNumber"/>
  <attribute name="mask" type="ST_OnOff"/>
</complexType>

```

3.1.2.1.1.9 keymaps (Key Map Customizations)

This element serves as a container for individual **key map** customization entries that can be described on the current keyboard. See [keymapsBad \(§3.1.2.1.1.10, keymapsBad\)](#) for more information on key map entries that cannot be described on the current keyboard.

On write, key maps are placed under **keymaps** or **keymapsBad** elements based on the current keyboard, not based on the element they were specified under originally. Key map elements can therefore be moved between these two parent elements depending on the current keyboard. Moreover, either type of key map may be validly defined under either element, but upon resaving each will be moved under the correct element.

If a conflict occurs between a KCM and CHM for a given key mapping, then the KCM will be used. Upon writing a file, Word will also add a valid KCM attribute for any key map entries that have specified a CHM.

[Example: Consider the following key mapping fragment:

```

<wne:keymaps>
  <wne:keymap wne:kcmPrimary="0342">
    <wne:fc1 wne:fc1Name="Bold" />
  </wne:keymap>
  <wne:keymap wne:kcmPrimary="0237">
    <wne:wch wne:val="000020AC" />
  </wne:keymap>
</wne:keymaps>

```

In this example, the fragment specifies two key maps. The first will make the selected text bold when the key combination Control-Shift-B is pressed. The second inserts the Euro currency symbol when Control-7 is pressed. end example]

| Parent Elements |
|--|
| tcg (§3.1.2.1.1.12, tcg) |

| Child Elements | Subclause |
|-------------------------------|--------------------------------------|
| keymap (Key Map Entry) | §3.1.2.1.1.8, keymap |

The following XML Schema fragment defines the contents of this element:

```

<complexType name="CT_Keymaps">
  <sequence>
    <element name="keymap" type="CT_Keymap" minOccurs="1" maxOccurs="unbounded"/>
  </sequence>
</complexType>

```

3.1.2.1.1.10 keymapsBad (Key Map Customizations for Mismatched Keyboards)

This element serves as a container for individual key map customization entries whose key combinations cannot be described on the current keyboard. See **keymaps** (§3.1.2.1.1.9, [keymaps](#)) for more information about key maps that can be described on the current keyboard.

On write, key maps are placed under **keymaps** or **keymapsBad** elements based on the current keyboard, not based on the element they were specified under originally. Key map elements can therefore be moved between these two parent elements depending on the current keyboard. Moreover, either type of key map may be validly defined under either element, but upon resaving each will be moved under the correct element.

The key combinations for key maps placed under the **keymapsBad** element cannot be executed by Word. Key maps placed under the **keymapsBad** element are not removed from the file, because they can become operational again when the document is opened on a computer where the specified characters are present on the current keyboard.

Because of their nature, CHM attributes will not be converted to KCM attributes if no such conversion is possible on the current keyboard.

[Example: Consider the following key mapping fragment:

```

<wne:keymapsBad>
  <wne:keymap wne:chmPrimary="06DF">
    <wne:fc1 wne:fc1Name="Bold" wne:swArg="0000"/>
  </wne:keymap>
</wne:keymapsBad>

```

In this example, the fragment specifies a single key map that executes the Bold fixed command when Control-Alt-β is pressed. Because this character is typically only available on German-language keyboards, the key mapping will be under the **keymapsBad** element on non-German-language keyboards. end example]

| Parent Elements |
|---|
| tcg (§3.1.2.1.1.12, tcg) |

| Child Elements | Subclause |
|-------------------------------|--------------------------------------|
| keymap (Key Map Entry) | §3.1.2.1.1.8, keymap |

The following XML Schema fragment defines the contents of this element:

```

<complexType name="CT_Keymaps">
  <sequence>
    <element name="keymap" type="CT_Keymap" minOccurs="1" maxOccurs="unbounded"/>
  </sequence>
</complexType>

```

3.1.2.1.1.11 macro (Macro Keyboard Customization Action)

This element specifies that a macro should be executed by the enclosing key map.

[Example: Consider the following key map:

```

<wne:keymap wne:kcmPrimary="0238">
  <wne:macro wne:macroName="PROJECT.NEWMACROS.SOMEMACRO"/>
</wne:keymap>

```

In this example, the WordprocessingML fragment specifies that pressing Control-8 (the meaning of a KCM of 0238) will run the macro named "PROJECT.NEWMACROS.SOMEMACRO". end example]

| Parent Elements |
|--|
| keymap (§3.1.2.1.1.8, keymap) |

| Attributes | Description |
|-------------------------------|--|
| macroName (Macro name) | Specifies the name of the macro to run. The possible values for this attribute are defined by the ST_String simple type |

| Attributes | Description |
|------------|--|
| | (§3.1.2.3.5, ST String). |

The following XML Schema fragment defines the contents of this element:

```
<complexType name="CT_MacroW11">
  <attribute name="macroName" type="ST_String" use="required"/>
</complexType>
```

3.1.2.1.1.12 tcg (Keyboard and Toolbar Customizations)

This element specifies the document's template command group (TCG), which contains customizations for keyboard shortcuts and toolbars.

[Example: Consider a document with both a toolbar customization and key map customization:

```
<wne:tcg ...>
  <wne:keymaps>
    <wne:keymap wne:kcmPrimary="0341">
      <wne:fcf wne:fcfName="CssLinks" wne:swArg="0000"/>
    </wne:keymap>
  </wne:keymaps>
  <wne:toolbars>
    <wne:toolbarData r:id="rId1"/>
  </wne:toolbars>
</wne:tcg>
```

In this example, the WordprocessingML describes a single key map customization and customized toolbar information stored in a binary part referenced as `rId1`. end example]

| Child Elements | Subclause |
|---|---|
| acds (Allocated Commands) | §3.1.2.1.1.5, acds |
| keymaps (Key Map Customizations) | §3.1.2.1.1.9, keymaps |
| keymapsBad (Key Map Customizations for Mismatched Keyboards) | §3.1.2.1.1.10, keymapsBad |
| toolbars (Legacy Toolbar Customizations) | §3.1.2.1.1.14, toolbars |

The following XML Schema fragment defines the contents of this element:

```
<complexType name="CT_Tcg">
  <sequence>
    <element name="keymaps" type="CT_Keymaps" minOccurs="0" maxOccurs="1"/>
    <element name="keymapsBad" type="CT_Keymaps" minOccurs="0" maxOccurs="1"/>
    <element name="toolbars" type="CT_Toolbars" minOccurs="0" maxOccurs="1"/>
    <element name="acds" type="CT_Acads" minOccurs="0" maxOccurs="1"/>
  </sequence>
</complexType>
```


3.1.2.1.1.13 toolbarData (Toolbar data)

The **toolbarData** element is used to reference a binary toolbar customization part.

[Example: Consider a document with a toolbar customization:

```
<wne:tcg ...>
  <wne:toolbars>
    <wne:toolbarData r:id="rId1"/>
  </wne:toolbars>
</wne:tcg>
```

Where `rId1` is defined in `customization.xml.rels` as:

```
<Relationships ...>
  <Relationship Id="rId1" ... Target="attachedToolbars.bin"/>
</Relationships>
```

In this example, the WordprocessingML specifies that the information in the `attachedToolbars.bin` binary part should be used for toolbar customization purposes. end example]

| Parent Elements |
|--|
| toolbars (§3.1.2.1.1.14, toolbars) |

| Attributes | Description |
|--|--|
| id (binary toolbar part relationship identifier) Namespace: .../officeDocument/2006/relationships | Specifies the relationship identifier associated with a binary toolbar customization part as described in the relationships file for the part in which this attribute is used. The possible values for this attribute are defined by the ST_RelationshipId simple type (" ECMA-376 Part 4 §7.8.2.1"). |

The following XML Schema fragment defines the contents of this element:

```
<complexType name="CT_Rel">
  <attribute ref="r:id" use="required"/>
</complexType>
```

3.1.2.1.1.14 toolbars (Legacy Toolbar Customizations)

The **toolbars** element is used as a container for **toolbarData** and **acdManifest** elements.

| Parent Elements |
|--|
| tcg (§3.1.2.1.1.12, tcg) |

| Child Elements | Subclause |
|---|--|
| acdManifest (Allocated Command Manifest) | §3.1.2.1.1.4, acdManifest |
| toolbarData (Toolbar data) | §3.1.2.1.1.13, toolbarData |

The following XML Schema fragment defines the contents of this element:

```
<complexType name="CT_Toolbars">
  <sequence>
    <element name="acdManifest" minOccurs="0" maxOccurs="1" type="CT_AcdManifest"/>
    <element name="toolbarData" minOccurs="0" maxOccurs="1" type="CT_Rel"/>
  </sequence>
</complexType>
```

3.1.2.1.1.15 wch (Character Insertion Keyboard Customization Action)

This element specifies that the action for an enclosed key map is to insert a certain character into the document.

[Example: Consider the following key map:

```
<wne:keymap wne:kcmPrimary="0237">
  <wne:wch wne:val="000020AC" />
</wne:keymap>
```

In this example, the WordprocessingML fragment specifies that pressing Control-7 (represented by KCM 0237) shall insert the Euro currency symbol (€, represented by the hexadecimal-encoded 4-byte Unicode of 000020AC). end example]

| Parent Elements |
|--|
| keymap (§3.1.2.1.1.8, keymap) |

| Attributes | Description |
|----------------------------------|--|
| val (character to insert) | This attribute specifies the hexadecimal encoded 4-byte Unicode character that should be inserted into the document. The possible values for this attribute are defined by the ST_LongHexNumber simple type (§3.1.2.3.2, ST LongHexNumber). |

The following XML Schema fragment defines the contents of this element:

```
<complexType name="CT_LongHexNumber">
  <attribute name="val" type="ST_LongHexNumber" use="required"/>
</complexType>
```

3.1.2.1.1.16 wll (WLL Macro Keyboard Customization Action)

This element specifies that a macro defined in a WLL (a legacy Word DLL add-in) should be run by the enclosing key map.

| Parent Elements |
|---|
| keymap (§3.1.2.1.1.8, keymap) |

| Attributes | Description |
|-------------------------------|--|
| macroName (Macro name) | Specifies the name of the macro to run. The possible values for this attribute are defined by the ST_String simple type (§3.1.2.3.5, ST_String). |

The following XML Schema fragment defines the contents of this element:

```
<complexType name="CT_MacroWll">  
  <attribute name="macroName" type="ST_String" use="required"/>  
</complexType>
```

3.1.2.1.2 Fixed Commands

Commands can be identified either by a name or by an index.

| Fixed Command Name | Fixed Command Index |
|----------------------------|---------------------|
| AcceptAllChangesInDoc | 0511 |
| AcceptAllChangesShown | 0510 |
| AcceptChangesAndAdvance | 0837 |
| AcceptChangesOrAdvance | 0989 |
| AcceptChangesSelected | 050F |
| ActivateObject | 007E |
| AddDigitalSignature | 0845 |
| AddToContacts | 087C |
| AdjustListIndents | 0778 |
| AdvancedBrightnessContrast | 08C5 |
| AdvertisePublishAs | 0790 |
| AlignBottom | 1BE2 |
| AlignCenterHorizontal | 1BDE |
| AlignCenterVertical | 1BE1 |

| Fixed Command Name | Fixed Command Index |
|------------------------------|----------------------------|
| AlignLeft | 1BDD |
| AlignRight | 1BDF |
| AlignTop | 1BE0 |
| AllCaps | 0030 |
| AllShapesGallery | 07B4 |
| AnnotInkEraser | 05C1 |
| AnnotInkPen | 05C0 |
| AnnotationEdit | 0535 |
| AppMaximize | 0118 |
| AppMinimize | 0117 |
| AppMove | 01A2 |
| AppRestore | 0119 |
| AppSize | 01A3 |
| ApplyFormattingOfOriginal | 052A |
| ApplyFormattingOfSurrounding | 0529 |
| ApplyHeading1 | 0251 |
| ApplyHeading2 | 0252 |
| ApplyHeading3 | 0253 |
| ApplyListBullet | 0254 |
| ApplyQFSetInitial | 0935 |
| ApplyQFSetTemplate | 0936 |
| ApplyQuickFormat | 0887 |
| ApplyQuickStyleSet | 0888 |
| ApplyStructure | 05B2 |
| ApplyTableStyle | 08F7 |
| ApplyXMLStructureMenu | 16B8 |
| ArrowStyleGallery | 07B8 |
| AsianLayoutFlyout | 08A4 |
| AutoFitContent | 0475 |
| AutoFitFixed | 0478 |

| Fixed Command Name | Fixed Command Index |
|-----------------------------------|----------------------------|
| AutoFitWindow | 0476 |
| AutoMarkIndexEntries | 0268 |
| AutoScroll | 03E2 |
| AutoSignatureList | 167D |
| AutoSummarizeClose | 038A |
| AutoSummarizePercentOfOriginal | 038D |
| AutoSummarizeToggleView | 038E |
| AutoSummarizeUpdateFileProperties | 038C |
| AutoText | 028D |
| AutoTextGallery | 08DE |
| AutomaticChange | 0FE6 |
| BBPropertiesDlg | 095A |
| BackHistoryItem | 05CE |
| BackgroundColorPicker | 08BA |
| BarCodeGroup | 08A3 |
| BibInsertSource | 0848 |
| BibUpdateLang | 09A1 |
| BibliographyBibliographyToText | 0985 |
| BibliographyCitationToText | 093B |
| BibliographyCreateSource | 0782 |
| BibliographyEditCitationButton | 0979 |
| BibliographyEditCitationToolBar | 097B |
| BibliographyEditSource | 093C |
| BibliographyEditSourceButton | 097A |
| BibliographyEditSourceToolBar | 097C |
| BibliographyFilterLanguages | 099C |
| BibliographyGallery | 08E0 |
| BibliographySourceManager | 0780 |
| BlogBlogAccountOptionsDlg | 07C1 |
| BlogBlogInsertCategories | 05AF |

| Fixed Command Name | Fixed Command Index |
|---------------------------|----------------------------|
| BlogBlogInsertCategory | 0355 |
| BlogBlogOpenBlogSite | 0826 |
| BlogBlogOpenExistingDlg | 0354 |
| BlogBlogPublish | 0352 |
| BlogBlogPublishDraft | 0353 |
| Bold | 002D |
| BoldRun | 0424 |
| BorderAll | 03D1 |
| BorderBottom | 0FE0 |
| BorderColorPicker | 08B9 |
| BorderHoriz | 03C2 |
| BorderInside | 0FE2 |
| BorderLeft | 0FDF |
| BorderLineColor | 03C4 |
| BorderLineStyle | 01C3 |
| BorderLineWeight | 03C1 |
| BorderNone | 01C2 |
| BorderOutside | 01C1 |
| BorderRight | 0FE1 |
| BorderTLtoBR | 0314 |
| BorderTRtoBL | 0315 |
| BorderTop | 0FDE |
| BorderVert | 03C3 |
| Borders | 0223 |
| BottomAlign | 0321 |
| BottomCenterAlign | 0480 |
| BottomLeftAlign | 0481 |
| BottomRightAlign | 047F |
| BreaksGallery | 0830 |
| BrightnessGallery | 0851 |

| Fixed Command Name | Fixed Command Index |
|-----------------------------|----------------------------|
| BringForward | 0857 |
| BringToFront | 0858 |
| BrowseForThemes | 0877 |
| BrowseNext | 0342 |
| BrowsePrev | 0337 |
| BrowseSel | 0336 |
| BuildingBlockOrganizer | 0813 |
| BulletsGallery | 07AB |
| BulletsNumberingStyleDialog | 08DA |
| Cancel | 0048 |
| CancelHighlightMode | 08BE |
| CellAlignmentGallery | 08C2 |
| CellOptions | 0439 |
| CenterAlign | 0320 |
| CenterPara | 003B |
| ChangeByte | 02DA |
| ChangeCase | 0011 |
| ChangeCaseGallery | 0853 |
| ChangeKana | 02DB |
| ChangeMailFormat | 1BC9 |
| ChangeShapesGallery | 07B9 |
| CharColor | 0039 |
| CharLeft | 0FA0 |
| CharLeftExtend | 0FB2 |
| CharRight | 0FA1 |
| CharRightExtend | 0FB3 |
| CharScale | 031D |
| CharScaleDialog | 07B2 |
| CharacterClearFormatting | 076F |
| CharacterRemoveStyle | 076D |

| Fixed Command Name | Fixed Command Index |
|---------------------------------|----------------------------|
| CheckBoxFormField | 015E |
| CheckCompatibility | 08F9 |
| CheckDocumentParts | 099B |
| ChineseTranslationGroup | 0976 |
| ChooseButtonImage | 0273 |
| ClearAllFormatting | 07A9 |
| ClearFormField | 02C2 |
| ClearFormatting | 054A |
| ClearTableStyle | 08F6 |
| ClosePane | 00F3 |
| CloseParaAbove | 0995 |
| CloseParaBelow | 0997 |
| ClosePreview | 01B5 |
| CloseReadingMode | 05C8 |
| CloseUpPara | 0041 |
| CloseViewHeaderFooter | 0280 |
| Color | 0224 |
| ColorPicker3DE1o | 08A1 |
| ColorPickerShadowE1o | 08A0 |
| ColorSchemePicker | 08FC |
| ColumnSelect | 001B |
| Columns | 0212 |
| ColumnsGallery | 07BC |
| CommaAccent | 02FE |
| CompareDocumentsCombine | 0815 |
| CompareDocumentsCompare | 0814 |
| CompareDocumentsLastMajor | 0816 |
| CompareDocumentsLastMinor | 0817 |
| CompareDocumentsVersion | 0818 |
| CompareTranslationBaseDocuments | 08FA |

| Fixed Command Name | Fixed Command Index |
|------------------------------------|----------------------------|
| CompatChkr | 0987 |
| Condensed | 0213 |
| Connect | 01A4 |
| ContentControlBuildingBlockGallery | 0954 |
| ContentControlComboBox | 0952 |
| ContentControlDate | 0955 |
| ContentControlDropDownList | 0953 |
| ContentControlGroup | 094A |
| ContentControlPicture | 0951 |
| ContentControlRichText | 094F |
| ContentControlText | 0950 |
| ContentControlUngroup | 0978 |
| ContextHelp | 032D |
| ContinueMacro | 010A |
| ContinueNumbering | 04E7 |
| ContrastGallery | 0852 |
| ControlProperties | 0849 |
| ControlRun | 00EB |
| ConvertObject | 0188 |
| ConvertTextBoxToFrame | 0394 |
| CopyButtonImage | 020E |
| CopyFile | 012C |
| CopyFormat | 0049 |
| CopyInkAsText | 05C2 |
| CopyText | 0013 |
| CoverPageGallery | 07E5 |
| CreateAutoText | 0368 |
| CreateAutoTextBlockFromSel | 08E1 |
| CreateBibliographyFromSel | 0971 |
| CreateBuildingBlockFromSel | 07E2 |

| Fixed Command Name | Fixed Command Index |
|-------------------------------|----------------------------|
| CreateCommonFieldBlockFromSel | 07F3 |
| CreateCoverPageBlockFromSel | 07F4 |
| CreateEquationBlockFromSel | 07F5 |
| CreateFooterBlockFromSel | 07F6 |
| CreateHeaderBlockFromSel | 07F7 |
| CreateLayoutBlockFromSel | 08E3 |
| CreateNewColorScheme | 0909 |
| CreateNewFontScheme | 0937 |
| CreatePageNumBottomFromSel | 07FB |
| CreatePageNumFromSel | 07F9 |
| CreatePageNumPageBlockFromSel | 07FD |
| CreatePageNumTopFromSel | 07FA |
| CreateSharedWorkspace | 0839 |
| CreateSubdocument | 01EB |
| CreateTable | 031C |
| CreateTableBlockFromSel | 07FC |
| CreateTableOfContentsFromSel | 0915 |
| CreateTask | 0384 |
| CreateTextBoxBlockFromSel | 08E2 |
| CreateWaterMarkBlockFromSel | 07FF |
| CssLinks | 04ED |
| Custom1Gallery | 096C |
| Custom2Gallery | 096D |
| Custom3Gallery | 096E |
| Custom4Gallery | 096F |
| Custom5Gallery | 0970 |
| CustomAutoTextGallery | 0968 |
| CustomBibliographyGallery | 096B |
| CustomCoverPageGallery | 095F |
| CustomEquationsGallery | 0965 |

| Fixed Command Name | Fixed Command Index |
|------------------------------|----------------------------|
| CustomFooterGallery | 095E |
| CustomHeaderGallery | 095D |
| CustomPageNumBottomGallery | 0962 |
| CustomPageNumGallery | 0960 |
| CustomPageNumPageGallery | 0963 |
| CustomPageNumTopGallery | 0961 |
| CustomQuickPartsGallery | 0967 |
| CustomTableOfContentsGallery | 096A |
| CustomTablesGallery | 0966 |
| CustomTextBoxGallery | 0969 |
| CustomWatermarkGallery | 0964 |
| DecreaseIndent | 03F3 |
| DecreaseParagraphSpacing | 053F |
| DefaultCharBorder | 03E5 |
| DefaultCharShading | 03F7 |
| DefaultCondensed | 0801 |
| DefaultExpanded | 0802 |
| DefineNewBullet | 07E0 |
| DefineNewList | 087A |
| DefineNewListStyle | 087B |
| DefineNewNumber | 07E1 |
| DeleteAllCommentsInDoc | 0516 |
| DeleteAllCommentsShown | 0515 |
| DeleteAllInkAnnotations | 05AB |
| DeleteAnnotation | 03CD |
| DeleteBackWord | 001D |
| DeleteBuildingBlock | 088A |
| DeleteHyperlink | 0381 |
| DeleteSchema | 1BD1 |
| DeleteStructure | 0568 |

| Fixed Command Name | Fixed Command Index |
|-------------------------------|----------------------------|
| DeleteStyle | 0555 |
| DeleteWord | 001C |
| DemoteList | 0250 |
| DemoteToBodyText | 016E |
| DepthGallery | 08CB |
| DiacriticColor | 0458 |
| DialogEditor | 0228 |
| Direction3DGallery | 08CA |
| DisplayDetails | 0385 |
| DisplayDocumentManagementPane | 083B |
| DisplayFinalDoc | 0505 |
| DisplayForReview | 0534 |
| DisplayOriginalDoc | 0506 |
| DisplaySharedWorkspacePane | 0532 |
| DistributeColumn | 0327 |
| DistributeGeneral | 0362 |
| DistributePara | 02E4 |
| DistributeRow | 037D |
| DoFieldClick | 011A |
| DoNotDistribute | 05A0 |
| DocClose | 00EA |
| DocEncryption | 07C0 |
| DocExport | 092D |
| DocInspector | 05CA |
| DocMaximize | 00E8 |
| DocMinimize | 0140 |
| DocMove | 00E7 |
| DocRestore | 00E9 |
| DocSize | 00E6 |
| DocSplit | 00E5 |

| Fixed Command Name | Fixed Command Index |
|---------------------------|----------------------------|
| DocumentActionsPane | 05BE |
| DocumentStatistics | 004E |
| DotAccent | 02FD |
| DottedUnderline | 026C |
| DoubleStrikethrough | 031E |
| DoubleUnderline | 0034 |
| DownloadPictures | 07A2 |
| DrawAlign | 027A |
| DrawArc | 01C7 |
| DrawBrace | 0317 |
| DrawBracket | 0318 |
| DrawBringForward | 01F4 |
| DrawBringInFrontOfText | 01D5 |
| DrawBringToFront | 01D2 |
| DrawCallout | 0263 |
| DrawDisassemblePicture | 023F |
| DrawDuplicate | 03BB |
| DrawEllipse | 01C6 |
| DrawFlipHorizontal | 022F |
| DrawFlipVertical | 0230 |
| DrawFreeformPolygon | 021A |
| DrawGroup | 01D1 |
| DrawInsertWordPicture | 0288 |
| DrawLine | 0178 |
| DrawMenu3D | 1662 |
| DrawMenu3DColor | 1677 |
| DrawMenu3DDepth | 1675 |
| DrawMenu3DDirection | 1676 |
| DrawMenu3DLighting | 1678 |
| DrawMenu3DSurface | 1679 |

| Fixed Command Name | Fixed Command Index |
|---------------------------|----------------------------|
| DrawMenuAlignDistribute | 1659 |
| DrawMenuArrows | 1661 |
| DrawMenuAutoShapes | 166B |
| DrawMenuChangeShape | 1665 |
| DrawMenuChangeShape0 | 1666 |
| DrawMenuChangeShape1 | 1667 |
| DrawMenuChangeShape2 | 1668 |
| DrawMenuChangeShape3 | 1669 |
| DrawMenuChangeShape4 | 166A |
| DrawMenuGrouping | 1658 |
| DrawMenuImageControl | 1664 |
| DrawMenuLineDash | 1660 |
| DrawMenuMoreShapes1 | 166C |
| DrawMenuMoreShapes2 | 166D |
| DrawMenuMoreShapes3 | 166E |
| DrawMenuMoreShapes4 | 166F |
| DrawMenuMoreShapes5 | 1670 |
| DrawMenuMoreShapes6 | 1671 |
| DrawMenuMoreShapes7 | 16AC |
| DrawMenuNudge | 165B |
| DrawMenuOrder | 1657 |
| DrawMenuRotateFlip | 165A |
| DrawMenuShadowColor | 1663 |
| DrawMenuShadows | 165E |
| DrawMenuTextAlignment | 1673 |
| DrawMenuTextShape | 1672 |
| DrawMenuTextTracking | 1674 |
| DrawMenuTextWrapping | 1656 |
| DrawNudgeDown | 029F |
| DrawNudgeDownPixel | 02BD |

| Fixed Command Name | Fixed Command Index |
|---------------------------|----------------------------|
| DrawNudgeLeft | 02A0 |
| DrawNudgeLeftPixel | 02BE |
| DrawNudgeRight | 02A1 |
| DrawNudgeRightPixel | 02BF |
| DrawNudgeUp | 029E |
| DrawNudgeUpPixel | 02BC |
| DrawRectangle | 0179 |
| DrawResetWordPicture | 02B8 |
| DrawReshape | 0260 |
| DrawRotateLeft | 0232 |
| DrawRotateRight | 0231 |
| DrawRoundRectangle | 0219 |
| DrawSelectNext | 02C5 |
| DrawSelectPrevious | 02C6 |
| DrawSendBackward | 01F5 |
| DrawSendBehindText | 01D4 |
| DrawSendToBack | 01D3 |
| DrawSnapToGrid | 0279 |
| DrawTextBox | 03B3 |
| DrawTextBox2 | 0959 |
| DrawToggleLayer | 022C |
| DrawUngroup | 01E5 |
| DrawUnselect | 02C4 |
| DrawVerticalTextBox | 03E4 |
| DrawVerticalTextBox2 | 094C |
| DrawingAdvancedLayout | 0901 |
| DrawingGrid | 0490 |
| DropCapGallery | 0799 |
| DropDownFormField | 015F |
| EATextBoxMenu | 0958 |

| Fixed Command Name | Fixed Command Index |
|---------------------------|----------------------------|
| EditAutoText | 03D9 |
| EditBookmark | 00A8 |
| EditButtonImage | 0266 |
| EditCitation | 0939 |
| EditClear | 001E |
| EditConvertAllEndnotes | 01B8 |
| EditConvertAllFootnotes | 01B7 |
| EditConvertNotes | 01CE |
| EditCopy | 006D |
| EditCopyAsPicture | 02EF |
| EditCreatePublisher | 02DC |
| EditCut | 006C |
| EditFind | 0070 |
| EditFindBorder | 01BF |
| EditFindClearFormatting | 0074 |
| EditFindFont | 0071 |
| EditFindFrame | 01C0 |
| EditFindHighlight | 030C |
| EditFindLang | 01AC |
| EditFindNotHighlight | 030E |
| EditFindPara | 0072 |
| EditFindReadingMode | 05A6 |
| EditFindStyle | 0073 |
| EditFindTabs | 01BE |
| EditGoTo | 0380 |
| EditHyperlink | 039E |
| EditIMEReconversion | 0359 |
| EditLinks | 007C |
| EditObject | 007D |
| EditOfficeClipboard | 01CB |

| Fixed Command Name | Fixed Command Index |
|----------------------------|----------------------------|
| EditPaste | 006E |
| EditPaste2 | 049C |
| EditPasteAppendTable | 054E |
| EditPasteAsHyperlink | 03D0 |
| EditPasteAsNestedTable | 0388 |
| EditPasteFromExcel | 0575 |
| EditPasteOption | 04DF |
| EditPasteSpecial | 006F |
| EditPicture | 0128 |
| EditPictureEdit | 0500 |
| EditPubOrSubOptions | 02DE |
| EditPublishOptions | 02DF |
| EditRedo | 0149 |
| EditRedoOrRepeat | 014A |
| EditRepeat | 0044 |
| EditReplace | 0075 |
| EditReplaceBorder | 01C9 |
| EditReplaceClearFormatting | 0079 |
| EditReplaceFont | 0076 |
| EditReplaceFrame | 01CA |
| EditReplaceHighlight | 030D |
| EditReplaceLang | 01AD |
| EditReplaceNotHighlight | 030F |
| EditReplacePara | 0077 |
| EditReplaceStyle | 0078 |
| EditReplaceTabs | 01C8 |
| EditSelectAll | 00ED |
| EditSource | 093A |
| EditSubscribeOptions | 02E0 |
| EditSubscribeTo | 02DD |

| Fixed Command Name | Fixed Command Index |
|---------------------------|----------------------------|
| EditSwapAllNotes | 01B9 |
| EditTOACategory | 0271 |
| EditUndo | 006B |
| EditUpdateIMEDic | 027E |
| EditWrapBoundary | 03E3 |
| EmailAttachmentOptions | 05C5 |
| EmailCheckNames | 043C |
| EmailChooseAccount | 05C4 |
| EmailEnvelope | 036B |
| EmailFlag | 0442 |
| EmailFocusIntroduction | 0574 |
| EmailFocusSubject | 0440 |
| EmailMessageOptions | 0441 |
| EmailOptions | 035F |
| EmailSaveAttachment | 0443 |
| EmailSelectBccNames | 043F |
| EmailSelectCcNames | 043E |
| EmailSelectNames | 043B |
| EmailSelectToNames | 043D |
| EmailSend | 043A |
| EmailSignatureOptions | 035E |
| EmailStationeryOptions | 0884 |
| EndOfColumn | 0113 |
| EndOfDocExtend | 0FC3 |
| EndOfDocument | 0FB1 |
| EndOfLine | 0FAD |
| EndOfLineExtend | 0FBF |
| EndOfRow | 0111 |
| EndOfWindow | 0FAF |
| EndOfWindowExtend | 0FC1 |

| Fixed Command Name | Fixed Command Index |
|--------------------------------------|----------------------------|
| EndReview | 04F6 |
| EngWritingAssistant | 0910 |
| EnvelopeSetup | 0558 |
| EnvelopeWizard | 0497 |
| EquationAccentGallery | 088D |
| EquationAlignAtEquals | 0883 |
| EquationAlignThisCharacter | 0882 |
| EquationArrayExpansion | 0871 |
| EquationAutoProfessionalFormat | 07D4 |
| EquationBarLocation | 086E |
| EquationBorderPropertiesMenu | 16CA |
| EquationCenteredAsGroupJustification | 08EE |
| EquationCenteredJustification | 08ED |
| EquationChangeStyle | 07BF |
| EquationDecreaseAlignment | 07BE |
| EquationDecreaseArgumentSize | 0874 |
| EquationDeleteArgument | 085E |
| EquationDeleteColumn | 07C8 |
| EquationDeleteMenu | 16C9 |
| EquationDeleteRow | 07C7 |
| EquationDelimiterGallery | 07DC |
| EquationEdit | 0800 |
| EquationEquationArraySpacing | 0900 |
| EquationExpansion | 0872 |
| EquationFractionGallery | 07D8 |
| EquationFunctionGallery | 088C |
| EquationGroupingCharacterLocation | 0870 |
| EquationHorizontalCenter | 07CC |
| EquationHorizontalLeft | 07CD |
| EquationHorizontalMenu | 16C3 |

| Fixed Command Name | Fixed Command Index |
|------------------------------|----------------------------|
| EquationHorizontalRight | 07CE |
| EquationIncreaseAlignment | 07BD |
| EquationIncreaseArgumentSize | 0873 |
| EquationInsert | 0797 |
| EquationInsertArgumentAfter | 085D |
| EquationInsertArgumentBefore | 085C |
| EquationInsertColumnAfter | 07C6 |
| EquationInsertColumnBefore | 07C5 |
| EquationInsertEmptyStructure | 082C |
| EquationInsertMenu | 16C8 |
| EquationInsertRowAfter | 07C3 |
| EquationInsertRowBefore | 07C2 |
| EquationInsertStructure | 08D9 |
| EquationInsertSymbol | 0781 |
| EquationIntegralGallery | 07D9 |
| EquationJustificationMenu | 16C7 |
| EquationLeftJustification | 08EB |
| EquationLimitGallery | 088E |
| EquationLimitLocation | 086C |
| EquationLinearFormat | 0777 |
| EquationLinearFraction | 0865 |
| EquationManualBreak | 0881 |
| EquationMatchDelimiters | 086A |
| EquationMathAutoCorrect | 077B |
| EquationMatrixGallery | 0890 |
| EquationMatrixSpacing | 08FF |
| EquationNaryGallery | 07DB |
| EquationNaryLimitLocation | 086B |
| EquationNoBarFraction | 0863 |
| EquationNormalText | 088B |

| Fixed Command Name | Fixed Command Index |
|--|----------------------------|
| EquationOperatorGallery | 088F |
| EquationProfessionalFormat | 0776 |
| EquationRadicalGallery | 07DA |
| EquationRecognizedFunctions | 0875 |
| EquationRemoveStructure | 085F |
| EquationRemoveSubscript | 0860 |
| EquationRemoveSuperscript | 0861 |
| EquationRightJustification | 08EC |
| EquationScriptAlignment | 0868 |
| EquationScriptGallery | 07DD |
| EquationScriptLocation | 08D8 |
| EquationShowHideBorderBLTRStrike | 0984 |
| EquationShowHideBorderBottom | 097E |
| EquationShowHideBorderHorizontalStrike | 0981 |
| EquationShowHideBorderLeft | 097F |
| EquationShowHideBorderRight | 0980 |
| EquationShowHideBorderTLBRStrike | 0983 |
| EquationShowHideBorderTop | 097D |
| EquationShowHideBorderVerticalStrike | 0982 |
| EquationShowHideClosingDelimiter | 07D3 |
| EquationShowHideLowerLimit | 07CF |
| EquationShowHideOpeningDelimiter | 07D2 |
| EquationShowHidePlaceholders | 0867 |
| EquationShowHideRadicalDegree | 07D1 |
| EquationShowHideUpperLimit | 07D0 |
| EquationSkewedFraction | 0864 |
| EquationStackedFraction | 0862 |
| EquationStretchDelimiters | 0866 |
| EquationStretchNaryOperator | 086F |
| EquationSymbolsGallery | 0803 |

| Fixed Command Name | Fixed Command Index |
|---------------------------|----------------------------|
| EquationToggle | 0775 |
| EquationVerticalBottom | 07CB |
| EquationVerticalCenter | 07C9 |
| EquationVerticalMenu | 16C2 |
| EquationVerticalTop | 07CA |
| EquationsOptions | 095B |
| Expanded | 0214 |
| ExtendSelection | 000E |
| FPConfidential | 0598 |
| FPSelectUser | 05B5 |
| FPUnprotected | 0597 |
| FaxService | 05BB |
| File1 | 0FC5 |
| File10 | 10CC |
| File11 | 10CD |
| File12 | 10CE |
| File13 | 10CF |
| File14 | 10D0 |
| File15 | 10D1 |
| File16 | 10D2 |
| File17 | 10D3 |
| File18 | 10D4 |
| File19 | 10D5 |
| File2 | 0FC6 |
| File20 | 10D6 |
| File21 | 10D7 |
| File22 | 10D8 |
| File23 | 10D9 |
| File24 | 10DA |
| File25 | 10DB |

| Fixed Command Name | Fixed Command Index |
|---------------------------|----------------------------|
| File26 | 10DC |
| File27 | 10DD |
| File28 | 10DE |
| File29 | 10DF |
| File3 | 0FC7 |
| File30 | 10E0 |
| File31 | 10E1 |
| File32 | 10E2 |
| File33 | 10E3 |
| File34 | 10E4 |
| File35 | 10E5 |
| File36 | 10E6 |
| File37 | 10E7 |
| File38 | 10E8 |
| File39 | 10E9 |
| File4 | 0FC8 |
| File40 | 10EA |
| File41 | 10EB |
| File42 | 10EC |
| File43 | 10ED |
| File44 | 10EE |
| File45 | 10EF |
| File46 | 10F0 |
| File47 | 10F1 |
| File48 | 10F2 |
| File49 | 10F3 |
| File5 | 0FC9 |
| File50 | 10F4 |
| File6 | 0FCA |
| File7 | 0FCB |

| Fixed Command Name | Fixed Command Index |
|---------------------------|----------------------------|
| File8 | 0FCC |
| File9 | 0FCD |
| FileAOCEAddMailer | 0137 |
| FileAOCEDeleteMailer | 0138 |
| FileAOCEExpandMailer | 0139 |
| FileAOCEForwardMail | 013E |
| FileAOCENextLetter | 013F |
| FileAOCEReplyAllMail | 013D |
| FileAOCEReplyMail | 013C |
| FileAOCESendMail | 013B |
| FileCheckin | 04FE |
| FileCheckout | 04FD |
| FileClose | 011B |
| FileCloseAll | 020C |
| FileCloseOrCloseAll | 020B |
| FileCloseOrExit | 03A4 |
| FileClosePicture | 02B6 |
| FileConfirmConversions | 02AF |
| FileExit | 0062 |
| FileFind | 0063 |
| FileMacPageSetup | 02AD |
| FileNew | 004F |
| FileNewContext | 04F1 |
| FileNewDefault | 012D |
| FileNewDialog | 045C |
| FileNewEmail | 0444 |
| FileNewPrint | 045B |
| FileNewWeb | 0459 |
| FileOpen | 0050 |
| FileOpenFile | 0218 |

| Fixed Command Name | Fixed Command Index |
|----------------------------|----------------------------|
| FilePageSetup | 00B2 |
| FilePermission | 05BD |
| FilePermissionMenu | 0596 |
| FilePost | 02F8 |
| FilePreview | 167F |
| FilePrint | 0058 |
| FilePrintDefault | 012E |
| FilePrintPreview | 0059 |
| FilePrintPreviewFullScreen | 0204 |
| FilePrintSetup | 0061 |
| FileProperties | 02EE |
| FileRoutingSlip | 0270 |
| FileSave | 0053 |
| FileSaveAll | 0055 |
| FileSaveAs | 0054 |
| FileSaveAsOtherFormats | 0912 |
| FileSaveAsWebPage | 048C |
| FileSaveFrameAs | 0455 |
| FileSaveHtml | 03F4 |
| FileSaveVersion | 03EF |
| FileSaveWord11 | 090C |
| FileSaveWordDocx | 090B |
| FileSaveWordDotx | 090A |
| FileSearch | 0553 |
| FileSendBlog | 07C4 |
| FileSendMail | 0265 |
| FileSendPdf | 0905 |
| FileSendXps | 0906 |
| FileSummaryInfo | 0056 |
| FileTemplates | 0057 |

| Fixed Command Name | Fixed Command Index |
|---------------------------|----------------------------|
| FileUndoCheckout | 04D9 |
| FileVersions | 03B1 |
| FileVersionsLocal | 04F5 |
| FileVersionsServer | 0533 |
| FillColorPicker | 084A |
| FillPolicyLabel | 0786 |
| FixBrokenText | 0577 |
| FixHHCMenu | 1699 |
| FixMe | 02C1 |
| FixSpellingChange | 02E8 |
| FixSpellingLang | 0383 |
| FixSynonymMenu | 16A0 |
| FixUIMChange | 0547 |
| FixUIMDeleteWord | 0549 |
| Font | 002A |
| FontColor | 0372 |
| FontColorPicker | 07BB |
| FontSchemePicker | 08FB |
| FontSize | 0215 |
| FontSizeSelect | 002B |
| FontSubstitution | 0245 |
| FooterGallery | 07E3 |
| FooterPositionSpinner | 08B2 |
| FormFieldOptions | 0161 |
| FormShading | 027C |
| FormatAddrFonts | 0067 |
| FormatAutoFormat | 0181 |
| FormatAutoFormatBegin | 0141 |
| FormatBackground | 0392 |
| FormatBackgroundColor | 08BD |

| Fixed Command Name | Fixed Command Index |
|-------------------------------|----------------------------|
| FormatBackgroundFillEffect | 03EE |
| FormatBackgroundMoreColors | 03ED |
| FormatBackgroundNone | 03EC |
| FormatBackgroundSwatch | 03EB |
| FormatBackgroundWatermark | 03B2 |
| FormatBordersAndShading | 00BD |
| FormatBullet | 0185 |
| FormatBulletDefault | 018F |
| FormatBulletsAndNumbering | 0338 |
| FormatCallout | 0262 |
| FormatChangeCase | 0142 |
| FormatChangeCaseFareast | 03D4 |
| FormatColumns | 00B1 |
| FormatCombineCharacters | 03DB |
| FormatConsistencyCheck | 0562 |
| FormatDefineStyleBorders | 00B9 |
| FormatDefineStyleFont | 00B5 |
| FormatDefineStyleFrame | 00B8 |
| FormatDefineStyleLang | 00BA |
| FormatDefineStyleNumbers | 025A |
| FormatDefineStylePara | 00B6 |
| FormatDefineStyleStripes | 0503 |
| FormatDefineStyleTable | 0502 |
| FormatDefineStyleTabs | 00B7 |
| FormatDrawingObject | 03C0 |
| FormatDrawingObjectWrapBehind | 1010 |
| FormatDrawingObjectWrapFront | 100F |
| FormatDrawingObjectWrapInline | 1011 |
| FormatDrawingObjectWrapNone | 0FFB |
| FormatDrawingObjectWrapSquare | 0FF8 |

| Fixed Command Name | Fixed Command Index |
|----------------------------------|----------------------------|
| FormatDrawingObjectWrapThrough | 0FFA |
| FormatDrawingObjectWrapTight | 0FF9 |
| FormatDrawingObjectWrapTopBottom | 0FFC |
| FormatDropCap | 01E8 |
| FormatEncloseCharacters | 048A |
| FormatField | 053C |
| FormatFillColor | 165C |
| FormatFitText | 03D7 |
| FormatFont | 00AE |
| FormatFrame | 00BE |
| FormatFrameOrFramePicture | 015A |
| FormatHeaderFooterLink | 00F2 |
| FormatHeadingNumber | 025E |
| FormatHeadingNumbering | 025B |
| FormatHorizontalInVertical | 0488 |
| FormatInkAnnotColor | 16BB |
| FormatInkColor | 16B9 |
| FormatLineColor | 165D |
| FormatLineStyle | 165F |
| FormatMultilevel | 0187 |
| FormatMultilevelDefault | 03B7 |
| FormatNumber | 0186 |
| FormatNumberDefault | 03B6 |
| FormatObjectCore | 0396 |
| FormatPageBordersAndShading | 094B |
| FormatPageNumber | 012A |
| FormatParagraph | 00AF |
| FormatPhoneticGuide | 03DA |
| FormatPicture | 00BB |
| FormatRetAddrFonts | 00DD |

| Fixed Command Name | Fixed Command Index |
|---------------------------|----------------------------|
| FormatSectionLayout | 00B0 |
| FormatSimpleNumberDefault | 018E |
| FormatStyle | 00B4 |
| FormatStyleByExample | 0544 |
| FormatStyleGallery | 01F9 |
| FormatStyleManagement | 079C |
| FormatStyleModify | 0543 |
| FormatStyleVisibility | 04E0 |
| FormatTabs | 00B3 |
| FormatTextFlow | 0234 |
| FormatTheme | 0357 |
| FormatThemeName | 045A |
| FormatTwoLinesInOne | 0489 |
| FormattingPane | 0554 |
| FormattingPaneCurrent | 079F |
| FormattingProperties | 0426 |
| FormattingRestrictions | 0593 |
| ForwardHistoryItem | 05CF |
| FrameProperties | 0432 |
| FrameRemoveSplit | 0431 |
| FrameSplitAbove | 042D |
| FrameSplitBelow | 042E |
| FrameSplitLeft | 042F |
| FrameSplitRight | 0430 |
| FramesetTOC | 0457 |
| FramesetWizard | 042C |
| FreezeLayout | 083C |
| GettingStartedPane | 05BC |
| GoBack | 0045 |
| GoToFirstPg | 05CC |

| Fixed Command Name | Fixed Command Index |
|---------------------------|----------------------------|
| GoToFooter | 08BC |
| GoToFurthestReadPg | 05CB |
| GoToHeader | 08BB |
| GoToHeaderFooter | 024E |
| GoToLastPg | 05CD |
| GoToNextComment | 019C |
| GoToNextEndnote | 019A |
| GoToNextFootnote | 0198 |
| GoToNextPage | 0194 |
| GoToNextReadingPage | 0892 |
| GoToNextSection | 0196 |
| GoToPrevReadingPage | 0893 |
| GoToPreviousComment | 019D |
| GoToPreviousEndnote | 019B |
| GoToPreviousFootnote | 0199 |
| GoToPreviousPage | 0195 |
| GoToPreviousSection | 0197 |
| GotoCommentScope | 0255 |
| GotoNextLinkedTextBox | 034A |
| GotoPrevLinkedTextBox | 034B |
| GotoTableOfContents | 056D |
| GradientGallery | 08A2 |
| GreetingSentence | 0498 |
| GrowFont | 000B |
| GrowFontOnePoint | 0201 |
| HTMLSourceDoNotRefresh | 0460 |
| HTMLSourceRefresh | 045E |
| HangingIndent | 0028 |
| HanjaDictionary | 0486 |
| HeadFootDiffFirstPage | 084D |

| Fixed Command Name | Fixed Command Index |
|----------------------------|----------------------------|
| HeadFootDiffOddEvenPage | 084E |
| HeaderGallery | 07E4 |
| HeaderPositionSpinner | 08B1 |
| Help | 0001 |
| HelpAW | 031A |
| HelpAbout | 0009 |
| HelpActiveWindow | 0004 |
| HelpCheckForUpdates | 05AE |
| HelpContactUs | 05AD |
| HelpContents | 02B0 |
| HelpContentsArabic | 0427 |
| HelpExamplesAndDemos | 0008 |
| HelpIchitaroHelp | 02D8 |
| HelpIndex | 0006 |
| HelpKeyboard | 0005 |
| HelpMSN | 031B |
| HelpPSSHelp | 0168 |
| HelpQuickPreview | 0007 |
| HelpSearch | 01FE |
| HelpShowHide | 035A |
| HelpTipOfTheDay | 027B |
| HelpTool | 0002 |
| HelpUsingHelp | 0003 |
| HelpWordPerfectHelp | 000A |
| HelpWordPerfectHelpOptions | 01FF |
| Hidden | 0032 |
| HideOutline | 0850 |
| Highlight | 02E6 |
| HighlightColorPicker | 08B8 |
| HtmlResAnchor | 03C7 |

| Fixed Command Name | Fixed Command Index |
|----------------------------------|----------------------------|
| HyperlinkOpen | 0398 |
| IMEControl | 0286 |
| IgnoreAllConsistenceError | 04FA |
| IgnoreConsistenceError | 04F9 |
| IncreaseIndent | 03F2 |
| IncreaseParagraphSpacing | 053E |
| Indent | 0026 |
| IndentChar | 02CF |
| IndentFirstChar | 02D1 |
| IndentFirstLine | 02F2 |
| IndentLabel | 08B4 |
| IndentLeftSpinner | 08AD |
| IndentLine | 02F4 |
| IndentRightSpinner | 08AE |
| InkAnnotationEraser | 05C9 |
| InkColorPicker | 0957 |
| InkEraser | 05C6 |
| InkingGroup | 08C4 |
| InsertAddCaption | 0192 |
| InsertAddress | 02F6 |
| InsertAlignmentTab | 05DB |
| InsertAnnotation | 00A1 |
| InsertAutoCaption | 0167 |
| InsertAutoText | 0014 |
| InsertBibliography | 077D |
| InsertBreak | 009F |
| InsertBuildingBlockBeginDocument | 078E |
| InsertBuildingBlockBeginSection | 078C |
| InsertBuildingBlockEndDocument | 078F |
| InsertBuildingBlockEndSection | 078D |

| Fixed Command Name | Fixed Command Index |
|-------------------------------|----------------------------|
| InsertBuildingBlockFooter | 078B |
| InsertBuildingBlockHeader | 078A |
| InsertBuildingBlockIP | 0789 |
| InsertCaption | 0165 |
| InsertCaptionNumbering | 0166 |
| InsertChart | 011D |
| InsertCitation | 077C |
| InsertColumnBreak | 033F |
| InsertCrossReference | 016F |
| InsertDatabase | 0155 |
| InsertDateField | 00F0 |
| InsertDateTime | 00A5 |
| InsertDrawing | 011C |
| InsertEmSpace | 026B |
| InsertEnSpace | 026A |
| InsertEndnoteNow | 0171 |
| InsertEquation | 02AB |
| InsertExcelTable | 0237 |
| InsertField | 00A6 |
| InsertFieldChars | 001F |
| InsertFile | 00A4 |
| InsertFootnote | 0172 |
| InsertFootnoteNow | 0170 |
| InsertFormControlsGallery | 08B5 |
| InsertFormField | 01E3 |
| InsertFrame | 009E |
| InsertGraphicalHorizontalLine | 042B |
| InsertHTMLBGSound | 046E |
| InsertHTMLCheckBox | 0462 |
| InsertHTMLDropDownBox | 0464 |

| Fixed Command Name | Fixed Command Index |
|---------------------------|----------------------------|
| InsertHTMLHidden | 046B |
| InsertHTMLImageSubmit | 0469 |
| InsertHTMLListBox | 0465 |
| InsertHTMLMarquee | 046F |
| InsertHTMLMovie | 046D |
| InsertHTMLOptionButton | 0463 |
| InsertHTMLPassword | 046C |
| InsertHTMLReset | 046A |
| InsertHTMLSubmit | 0468 |
| InsertHTMLTextArea | 0467 |
| InsertHTMLTextBox | 0466 |
| InsertHorizontalLine | 042A |
| InsertHyperlink | 039D |
| InsertImagerScan | 03D5 |
| InsertIndex | 00AA |
| InsertIndexAndTables | 01D9 |
| InsertInkAnnotations | 05C3 |
| InsertInkComment | 058D |
| InsertInkSplitMenu | 16BD |
| InsertListNumField | 03C6 |
| InsertMergeField | 00A7 |
| InsertNewComment | 0517 |
| InsertNewPage | 084F |
| InsertNumber | 032C |
| InsertNumberOfPages | 0343 |
| InsertOCX | 0391 |
| InsertOCXButton | 1BAA |
| InsertOCXCheckbox | 1BA5 |
| InsertOCXDialog | 080E |
| InsertOCXDropDownCombo | 1BAD |

| Fixed Command Name | Fixed Command Index |
|-----------------------------|----------------------------|
| InsertOCXFrame | 1BB1 |
| InsertOCXImage | 1BB2 |
| InsertOCXLabel | 1BA8 |
| InsertOCXListBox | 1BAC |
| InsertOCXOptionButton | 1BAB |
| InsertOCXScrollbar | 1BA7 |
| InsertOCXSpin | 1BA6 |
| InsertOCXTextBox | 1BA9 |
| InsertOCXToggleButton | 1BAE |
| InsertObject | 00AC |
| InsertOfficeDrawing | 032F |
| InsertPageBreak | 033E |
| InsertPageField | 00EF |
| InsertPageNumbers | 0126 |
| InsertPicture | 00A3 |
| InsertPicture3 | 090D |
| InsertPictureBullet | 035C |
| InsertPolicyBarcode | 0787 |
| InsertPolicyLabel | 0785 |
| InsertSectionBreak | 02C3 |
| InsertSignatureLine | 077A |
| InsertSignatureLineMenuItem | 0819 |
| InsertSound | 0207 |
| InsertSoundComment | 05A5 |
| InsertSpike | 0010 |
| InsertStyleSeparator | 0576 |
| InsertSubdocument | 0247 |
| InsertSymbol | 00A2 |
| InsertTableGallery | 08D1 |
| InsertTableOfAuthorities | 01D7 |

| Fixed Command Name | Fixed Command Index |
|----------------------------------|----------------------------|
| InsertTableOfContents | 00AB |
| InsertTableOfContentsMenu | 0923 |
| InsertTableOfFigures | 01D8 |
| InsertTimeField | 00F1 |
| InsertVerticalFrame | 0313 |
| InsertWebComponent | 052C |
| InsertWordArt | 02AA |
| InsertWordArtGallery | 08CF |
| Italic | 002E |
| ItalicRun | 0425 |
| JapaneseGreetingClosingSentence | 04E2 |
| JapaneseGreetingFlyout | 08A7 |
| JapaneseGreetingOpeningSentence | 04E1 |
| JapaneseGreetingPreviousGreeting | 04E3 |
| JoinToPreviousList | 0771 |
| JumpToHeading | 05D1 |
| JumpToScrn | 05D0 |
| JustifyFlyout | 08A5 |
| JustifyPara | 003D |
| JustifyParaHigh | 08AB |
| JustifyParaLow | 08A9 |
| JustifyParaMedium | 08AA |
| JustifyParaSpecial | 08A8 |
| JustifyParaThai | 08AC |
| LTRMacroDialogs | 0429 |
| LabelOptions | 0557 |
| Language | 0358 |
| LearnWords | 04FF |
| LeftPara | 003A |
| LegoCommonPartsGallery | 07F0 |

| Fixed Command Name | Fixed Command Index |
|---------------------------|----------------------------|
| LegoEquationsGallery | 07EC |
| LegoPageNumBottomGallery | 07EB |
| LegoPageNumGallery | 07E7 |
| LegoPageNumPageGallery | 07E8 |
| LegoPageNumTopGallery | 07EA |
| LegoTablesGallery | 07EE |
| LegoWatermarkGallery | 07E9 |
| LettersWizardJToolBar | 052B |
| LicenseVerification | 0561 |
| Lighting3DGallery | 08CD |
| LineColorPicker | 084B |
| LineDown | 0FA9 |
| LineDownExtend | 0FBB |
| LineSpacing | 04EF |
| LineSpacingMenu | 0904 |
| LineStyleGallery | 07B6 |
| LineUp | 0FA8 |
| LineUpExtend | 0FBA |
| LineWidthGallery | 07B7 |
| ListAdvanceToVBA | 07A0 |
| ListCommands | 02D3 |
| ListIndent | 033A |
| ListLevelGallery | 0878 |
| ListMacros | 0298 |
| ListOutdent | 0339 |
| LoadOssThemeFromTemplate | 093E |
| LockDocument | 0258 |
| LockFields | 0023 |
| LockPolicyLabel | 0783 |
| LowerTextBaseline | 09A0 |

| Fixed Command Name | Fixed Command Index |
|-------------------------------|----------------------------|
| Lowered | 0216 |
| LtrPara | 041E |
| LtrRun | 0423 |
| MMEmailOptions | 051D |
| MMFaxOptions | 0520 |
| MMNewDocOptions | 051E |
| MMPrintOptions | 051F |
| MSWordBibAddNewPlaceholder | 092C |
| MacroREM | 0229 |
| Magnifier | 0203 |
| MailAsHTML | 04EC |
| MailAsPlainText | 04EB |
| MailAsRTF | 04F0 |
| MailCheckNames | 0306 |
| MailHideMessageHeader | 02FB |
| MailMerge | 02A4 |
| MailMergeAddressBlock | 0519 |
| MailMergeAskToConvertChevrons | 0261 |
| MailMergeCheck | 02A5 |
| MailMergeClearDocumentType | 081E |
| MailMergeConvertChevrons | 0200 |
| MailMergeCreateDataSource | 0282 |
| MailMergeCreateHeaderSource | 0283 |
| MailMergeCreateList | 055C |
| MailMergeDataForm | 0154 |
| MailMergeEditAddressBlock | 0523 |
| MailMergeEditDataSource | 0068 |
| MailMergeEditGreetingLine | 0524 |
| MailMergeEditHeaderSource | 02A3 |
| MailMergeEditList | 055D |

| Fixed Command Name | Fixed Command Index |
|-----------------------------|----------------------------|
| MailMergeEditMainDocument | 00DB |
| MailMergeFieldMapping | 0518 |
| MailMergeFindEntry | 052E |
| MailMergeFindRecord | 0239 |
| MailMergeFirstRecord | 01E0 |
| MailMergeGoToRecord | 01E2 |
| MailMergeGreetingLine | 051A |
| MailMergeHelper | 02A8 |
| MailMergeInsertAsk | 0FCF |
| MailMergeInsertFields | 051B |
| MailMergeInsertFieldsFlyout | 0988 |
| MailMergeInsertFillIn | 0FD0 |
| MailMergeInsertIf | 0FD1 |
| MailMergeInsertMergeKeyword | 0922 |
| MailMergeInsertMergeRec | 0FD2 |
| MailMergeInsertMergeSeq | 0FD3 |
| MailMergeInsertNext | 0FD4 |
| MailMergeInsertNextIf | 0FD5 |
| MailMergeInsertSet | 0FD6 |
| MailMergeInsertSkipIf | 0FD7 |
| MailMergeLastRecord | 01E1 |
| MailMergeListWordFields | 0238 |
| MailMergeNextRecord | 01DE |
| MailMergeOpenDataSource | 0051 |
| MailMergeOpenHeaderSource | 0052 |
| MailMergePrevRecord | 01DF |
| MailMergePropagateLabel | 052D |
| MailMergeQueryOptions | 02A9 |
| MailMergeRecipients | 051C |
| MailMergeReset | 0060 |

| Fixed Command Name | Fixed Command Index |
|-------------------------------|----------------------------|
| MailMergeSetDocTypeDirectory | 0824 |
| MailMergeSetDocTypeEmail | 0820 |
| MailMergeSetDocTypeEnvelope | 0822 |
| MailMergeSetDocTypeFax | 0821 |
| MailMergeSetDocTypeFormLetter | 081F |
| MailMergeSetDocTypeLabel | 0823 |
| MailMergeSetDocumentType | 053B |
| MailMergeShadeFields | 04DD |
| MailMergeToDoc | 02A6 |
| MailMergeToEMail | 0559 |
| MailMergeToFax | 055A |
| MailMergeToPrinter | 02A7 |
| MailMergeToolbar | 055B |
| MailMergeUseAddressBook | 030B |
| MailMergeUseOutlookContacts | 0974 |
| MailMergeViewData | 01AF |
| MailMergeWizard | 04DE |
| MailMessageDelete | 0303 |
| MailMessageForward | 0308 |
| MailMessageMove | 0302 |
| MailMessageNext | 0305 |
| MailMessagePrevious | 0304 |
| MailMessageProperties | 02FC |
| MailMessageReply | 0300 |
| MailMessageReplyAll | 0301 |
| MailSelectNames | 0307 |
| MarkAsReadOnly | 0843 |
| MarkCitation | 01CF |
| MarkIndexEntry | 00A9 |
| MarkTableOfContentsEntry | 01BA |

| Fixed Command Name | Fixed Command Index |
|----------------------------|----------------------------|
| MenuAsianLayout | 169F |
| MenuAutoText | 1685 |
| MenuAutoTextList | 168D |
| MenuBorder | 1652 |
| MenuCellAlignment | 169C |
| MenuCellAlignmentNoTearoff | 16C6 |
| MenuCellVerticalAlign | 1689 |
| MenuClear | 16B0 |
| MenuDiagramConvertTo | 16B7 |
| MenuDiagramLayout | 16B1 |
| MenuDraw | 1655 |
| MenuEdit | 1645 |
| MenuEditObject | 168A |
| MenuFile | 1644 |
| MenuFinalizeDocument | 0841 |
| MenuFixSpellingAC | 1683 |
| MenuFixSpellingLang | 1680 |
| MenuFont | 164E |
| MenuFormat | 1648 |
| MenuFormatBackground | 1682 |
| MenuFrameset | 167E |
| MenuHelp | 164C |
| MenuHyperlinkSub | 1688 |
| MenuInsert | 1647 |
| MenuInsertFrame | 1654 |
| MenuLanguage | 1650 |
| MenuLettersMail | 16AF |
| MenuMacro | 1686 |
| MenuManageDocument | 083F |
| MenuMicrosoftOnTheWeb | 1651 |

| Fixed Command Name | Fixed Command Index |
|---------------------------|----------------------------|
| MenuMode | 0125 |
| MenuNotesFlow | 036F |
| MenuOrgChartInsert | 16B6 |
| MenuOrgChartLayout | 16AB |
| MenuOrgChartSelect | 167A |
| MenuPicture | 1684 |
| MenuPowerTalk | 1687 |
| MenuReadingTools | 0891 |
| MenuReadingViewOptions | 0896 |
| MenuReference | 16AE |
| MenuRevisions | 1681 |
| MenuSendTo | 168B |
| MenuShareDocument | 0840 |
| MenuShowBalloons | 16BC |
| MenuShowChanges | 16B3 |
| MenuShowSourceDocuments | 07AD |
| MenuSignaturesDocument | 0842 |
| MenuTable | 164A |
| MenuTableAutoFitLong | 169B |
| MenuTableAutoFitShort | 169A |
| MenuTableConvert | 1697 |
| MenuTableDelete | 167C |
| MenuTableInsert | 167B |
| MenuTableInsertIntoTable | 16C5 |
| MenuTableInsertLong | 169D |
| MenuTableInsertPalette | 1698 |
| MenuTableSelect | 1696 |
| MenuTools | 1649 |
| MenuVersion | 16BA |
| MenuView | 1646 |

| Fixed Command Name | Fixed Command Index |
|---------------------------|----------------------------|
| MenuWebFavorites | 03A9 |
| MenuWebGo | 03E6 |
| MenuWindow | 164B |
| MenuWordQFStyles | 16CB |
| MenuWork | 164D |
| MergeSplitGeneral | 0363 |
| MergeSubdocument | 0248 |
| MicrosoftAccess | 0292 |
| MicrosoftExcel | 0291 |
| MicrosoftFoxPro | 0294 |
| MicrosoftMail | 0290 |
| MicrosoftOnTheWeb1 | 0FFE |
| MicrosoftOnTheWeb10 | 1007 |
| MicrosoftOnTheWeb11 | 1008 |
| MicrosoftOnTheWeb12 | 1009 |
| MicrosoftOnTheWeb13 | 100A |
| MicrosoftOnTheWeb14 | 100B |
| MicrosoftOnTheWeb15 | 100C |
| MicrosoftOnTheWeb16 | 100D |
| MicrosoftOnTheWeb17 | 100E |
| MicrosoftOnTheWeb2 | 0FFF |
| MicrosoftOnTheWeb3 | 1000 |
| MicrosoftOnTheWeb4 | 1001 |
| MicrosoftOnTheWeb5 | 1002 |
| MicrosoftOnTheWeb6 | 1003 |
| MicrosoftOnTheWeb7 | 1004 |
| MicrosoftOnTheWeb8 | 1005 |
| MicrosoftOnTheWeb9 | 1006 |
| MicrosoftPowerPoint | 0295 |
| MicrosoftProject | 0297 |

| Fixed Command Name | Fixed Command Index |
|-----------------------------|----------------------------|
| MicrosoftPublisher | 0296 |
| MicrosoftSchedule | 0293 |
| MicrosoftScriptEditor | 041C |
| MicrosoftSystemInfo | 02C7 |
| MiddleCenterAlign | 047D |
| MiddleLeftAlign | 047E |
| MiddleRightAlign | 047C |
| ModifyTableStyle | 08F8 |
| MoveText | 0012 |
| MyPermission | 059D |
| NavBack | 083D |
| NavBackMenu | 098B |
| NavForward | 083E |
| NavForwardMenu | 098C |
| NavigateMove | 0949 |
| NeverUseBalloons | 05A8 |
| NewStyle | 079E |
| NewToolbar | 024A |
| NextCell | 010E |
| NextChangeOrComment | 050E |
| NextComment | 07DE |
| NextField | 0019 |
| NextInsert | 0344 |
| NextMisspelling | 02F7 |
| NextObject | 004C |
| NextPage | 004B |
| NextPane | 0999 |
| NextWindow | 0016 |
| NoInsertionDeletionBalloons | 05A9 |
| NormalFontPosition | 023C |

| Fixed Command Name | Fixed Command Index |
|---------------------------|----------------------------|
| NormalFontSpacing | 023B |
| NormalStyle | 00F8 |
| NormalViewHeaderArea | 009B |
| NormalizeText | 04F8 |
| NoteOptions | 0175 |
| NumberingGallery | 07AC |
| OK | 0047 |
| OartCommand | 0812 |
| OfficeCenter | 17D0 |
| OfficeDrawingCommand | 0395 |
| OfficeOnTheWeb | 0243 |
| OnlineMeeting | 0470 |
| OpenOrCloseParaAbove | 0992 |
| OpenOrCloseParaBelow | 0993 |
| OpenOrCloseUpPara | 02BA |
| OpenParaAbove | 0994 |
| OpenParaBelow | 0996 |
| OpenSubdocument | 0257 |
| OpenUpPara | 0042 |
| Organizer | 00DE |
| OtherPane | 0015 |
| OutlineCollapse | 00FA |
| OutlineDemote | 00F5 |
| OutlineExpand | 00F9 |
| OutlineLevel | 056F |
| OutlineLevelGallery | 082F |
| OutlineMoveDown | 00F7 |
| OutlineMoveUp | 00F6 |
| OutlineNumberingGallery | 0879 |
| OutlinePromote | 00F4 |

| Fixed Command Name | Fixed Command Index |
|---------------------------|----------------------------|
| OutlinePromoteHeading1 | 0550 |
| OutlineShowFirstLine | 0105 |
| OutlineShowFormat | 0106 |
| OutlookInsertFile | 0869 |
| OutlookInsertFile2 | 093F |
| OutlookViewZoom | 0889 |
| Overtyp | 000D |
| PPPPropertyEditorDlg | 1BE3 |
| PageDown | 0FAB |
| PageDownExtend | 0FBD |
| PageMarginsGallery | 07B1 |
| PageOrientationGallery | 079B |
| PageSetupLayout | 10F7 |
| PageSetupMargins | 10F5 |
| PageSetupPaper | 10F6 |
| PageSizeGallery | 08D0 |
| PageUp | 0FAA |
| PageUpExtend | 0FBC |
| ParaDown | 0FA7 |
| ParaDownExtend | 0FB9 |
| ParaKeepLinesTogether | 026D |
| ParaKeepWithNext | 026E |
| ParaPageBreakBefore | 026F |
| ParaUp | 0FA6 |
| ParaUpExtend | 0FB8 |
| ParaWidowOrphanControl | 0274 |
| ParagraphRemoveStyle | 092A |
| PasteButtonImage | 020F |
| PasteFormat | 01E6 |
| PauseRecorder | 00D8 |

| Fixed Command Name | Fixed Command Index |
|---------------------------|----------------------------|
| PicturePositionGallery | 08C3 |
| PostcardWizard | 03DC |
| PresentIt | 03C9 |
| PrevCell | 010F |
| PrevField | 001A |
| PrevObject | 004D |
| PrevPage | 004A |
| PrevPane | 099A |
| PrevWindow | 0017 |
| PreviousChangeOrComment | 050D |
| PreviousComment | 07DF |
| PrivFunctionkey1 | 0449 |
| PrivFunctionkey10 | 0452 |
| PrivFunctionkey11 | 0453 |
| PrivFunctionkey12 | 0454 |
| PrivFunctionkey2 | 044A |
| PrivFunctionkey3 | 044B |
| PrivFunctionkey4 | 044C |
| PrivFunctionkey5 | 044D |
| PrivFunctionkey6 | 044E |
| PrivFunctionkey7 | 044F |
| PrivFunctionkey8 | 0450 |
| PrivFunctionkey9 | 0451 |
| PromoteList | 024F |
| PropertiesGallery | 087D |
| ProtectForm | 0162 |
| QFSetAsDefault | 0986 |
| QuickFormatsGallery | 07A7 |
| QuickFormatsThemeGallery | 07A8 |
| RTLMacroDialogs | 0428 |

| Fixed Command Name | Fixed Command Index |
|--------------------------------------|----------------------------|
| RaiseTextBaseline | 099F |
| Raised | 0217 |
| ReadModeMarkupFinal | 098E |
| ReadModeMarkupFinalMarkup | 098F |
| ReadModeMarkupOriginal | 0990 |
| ReadModeMarkupOriginalMarkup | 0991 |
| ReadModeShowMarkup | 098D |
| ReadingFlyoutAnchorShowAcetateMarkup | 0927 |
| ReadingInkTools | 0928 |
| ReadingMode | 05B1 |
| ReadingMode1Page | 0894 |
| ReadingMode2Pages | 0895 |
| ReadingModeAllowEditing | 0795 |
| ReadingModeGrowFont | 05B9 |
| ReadingModeInkOff | 05A4 |
| ReadingModeLayout | 05BF |
| ReadingModeLookup | 05B8 |
| ReadingModeMini | 05B7 |
| ReadingModePageAutoMargins | 089A |
| ReadingModePageMargins | 0898 |
| ReadingModePageMarginsType | 0796 |
| ReadingModePageNoMargins | 0899 |
| ReadingModePageview | 0587 |
| ReadingModeShrinkFont | 05BA |
| ReadingModeToPrintView | 0902 |
| ReadingModeViewAllMenu | 16C0 |
| ReadingTrackChanges | 0926 |
| ReapplyTableStyle | 095C |
| RecolorGallery | 08C7 |
| RecordNextCommand | 00E2 |

| Fixed Command Name | Fixed Command Index |
|----------------------------|----------------------------|
| RedefineStyle | 0330 |
| RefTipLangGallery | 0828 |
| RefTipLangMenu | 16C4 |
| RefTipSelectLang | 0829 |
| RejectAllChangesInDoc | 0514 |
| RejectAllChangesShown | 0513 |
| RejectChangesAndAdvance | 0838 |
| RejectChangesOrAdvance | 098A |
| RejectChangesSelected | 0512 |
| RemoveAllScripts | 041B |
| RemoveBulletsNumbers | 020A |
| RemoveCellPartition | 0378 |
| RemoveCitation | 0938 |
| RemoveCoverPage | 092F |
| RemoveCurrentBuildingBlock | 0933 |
| RemoveFooter | 0931 |
| RemoveFrames | 0124 |
| RemoveHeader | 0930 |
| RemovePageNumbers | 0932 |
| RemoveSimilarFormatting | 082D |
| RemoveSubdocument | 027F |
| RemoveTableOfContents | 0934 |
| RemoveWatermark | 092E |
| RenameStyle | 0556 |
| RepeatFind | 0018 |
| ReplaceEmailSignature | 053D |
| ReplyToAnnotation | 0540 |
| Research | 05B3 |
| ResearchLookup | 058A |
| ResetAdvanceToVBA | 07A1 |

| Fixed Command Name | Fixed Command Index |
|---------------------------------|----------------------------|
| ResetButtonImage | 0210 |
| ResetChar | 0038 |
| ResetFormField | 0531 |
| ResetNoteSepOrNotice | 0184 |
| ResetPara | 0043 |
| ResetParagraphFormatting | 076C |
| ResetSideBySide | 0590 |
| ResolveMenu | 16B5 |
| RestartNumbering | 0546 |
| RestoreCharacterStyle | 076E |
| RestoreParagraphStyle | 092B |
| ReturnReview | 04F4 |
| ReviewingPane | 054F |
| ReviewingPaneHorizontal | 08D6 |
| ReviewingPaneVertical | 08D7 |
| RibbonFilePermissionMenu | 0921 |
| RibbonReviewProtectDocumentMenu | 09A7 |
| RibbonReviewRestrictFormatting | 09A8 |
| RightPara | 003C |
| RotateObjectGallery | 07B5 |
| RtlPara | 041F |
| RtlRun | 0422 |
| RunPrintManager | 02AC |
| RunToggle | 041D |
| SaveAsQuickFormatSet | 05D5 |
| SaveBibliographyBlock | 0972 |
| SaveCoverPageBlock | 08E4 |
| SaveCurrentTheme | 08DB |
| SaveEquation | 090E |
| SaveFooterBlock | 08E6 |

| Fixed Command Name | Fixed Command Index |
|---------------------------------|----------------------------|
| SaveHeaderBlock | 08E5 |
| SaveOssThemeToTemplate | 093D |
| SavePageNumBlock | 08E9 |
| SavePageNumBottomBlock | 08E8 |
| SavePageNumTopBlock | 08E7 |
| SaveTableOfContentsBlock | 0919 |
| SaveTemplate | 0046 |
| SaveToDocMgmtServer | 083A |
| ScheduleMeeting | 049A |
| SchemaLibrary | 0589 |
| ScreenRefresh | 0299 |
| ScrnNav | 0897 |
| SearchOfficeOnline | 0876 |
| SelectBibliographyStyle | 077E |
| SelectCurAlignment | 011F |
| SelectCurColor | 0123 |
| SelectCurFont | 011E |
| SelectCurIndent | 0121 |
| SelectCurSpacing | 0120 |
| SelectCurTabs | 0122 |
| SelectDrawingObjects | 0221 |
| SelectNumber | 0545 |
| SelectSimilarFormatting | 04DC |
| SendBackward | 0859 |
| SendForReview | 0563 |
| SendToBack | 085A |
| SendToFax | 03AC |
| SendToOnlineMeetingParticipants | 03CF |
| SentLeft | 0FA4 |
| SentLeftExtend | 0FB6 |

| Fixed Command Name | Fixed Command Index |
|---------------------------|----------------------------|
| SentRight | 0FA5 |
| SentRightExtend | 0FB7 |
| SeparateList | 0770 |
| SetDrawingDefaults | 03E1 |
| SetListLevelVBA | 0885 |
| SetNumberingValue | 0774 |
| Shading | 0222 |
| ShadingColor | 0361 |
| ShadingColorPicker | 0856 |
| ShadingPattern | 01C4 |
| ShadowStyleGallery | 08C8 |
| ShapeHeightSpinner | 08B6 |
| ShapeStyleGallery | 08D2 |
| ShapeWidthSpinner | 08B7 |
| ShowAddInsXDialog | 03A8 |
| ShowAll | 0114 |
| ShowAllAuthors | 0539 |
| ShowAllConsistency | 0494 |
| ShowAllHeadings | 0104 |
| ShowChangesAndComments | 0508 |
| ShowComments | 0509 |
| ShowConsistency | 0461 |
| ShowFormatting | 050B |
| ShowHeading1 | 00FB |
| ShowHeading2 | 00FC |
| ShowHeading3 | 00FD |
| ShowHeading4 | 00FE |
| ShowHeading5 | 00FF |
| ShowHeading6 | 0100 |
| ShowHeading7 | 0101 |

| Fixed Command Name | Fixed Command Index |
|----------------------------|----------------------------|
| ShowHeading8 | 0102 |
| ShowHeading9 | 0103 |
| ShowInkAnnotations | 05AA |
| ShowInsertionsAndDeletions | 050A |
| ShowLevel | 0570 |
| ShowMarkupArea | 0791 |
| ShowMe | 0FE4 |
| ShowNextHeaderFooter | 024D |
| ShowPara | 037A |
| ShowPictureTools | 04DB |
| ShowPrevHeaderFooter | 024C |
| ShowPropertyBrowser | 1BB0 |
| ShowRepairs | 0565 |
| ShowReviewerFilter | 0846 |
| ShowScriptAnchor | 0456 |
| ShowSmPane | 052F |
| ShowTableGridlines | 0351 |
| ShowTableTools | 04DA |
| ShowTasks | 0779 |
| ShowVars | 0107 |
| ShrinkFont | 000C |
| ShrinkFontOnePoint | 0202 |
| ShrinkMultiSel | 04FB |
| ShrinkSelection | 00EC |
| SignDocument | 0844 |
| SignOutOfPassport | 0564 |
| SigningServices | 0847 |
| SkipNumbering | 01B6 |
| SmallCaps | 002F |
| SpacePara1 | 003E |

| Fixed Command Name | Fixed Command Index |
|---------------------------|----------------------------|
| SpacePara15 | 003F |
| SpacePara2 | 0040 |
| SpacingAfterSpinner | 08B0 |
| SpacingBeforeSpinner | 08AF |
| SpacingLabel | 08B3 |
| SpellingAndAutoCorrect | 0387 |
| Spike | 000F |
| SplitSubdocument | 0249 |
| SqmDialog | 058C |
| StartMacro | 022A |
| StartOfColumn | 0112 |
| StartOfDocExtend | 0FC2 |
| StartOfDocument | 0FB0 |
| StartOfLine | 0FAC |
| StartOfLineExtend | 0FBE |
| StartOfRow | 0110 |
| StartOfWindow | 0FAE |
| StartOfWindowExtend | 0FC0 |
| StartWorkflow | 0798 |
| StepIn | 0109 |
| StepOver | 0108 |
| StopMacro | 029C |
| StopMacroRunning | 0285 |
| Strikethrough | 0031 |
| Style | 0097 |
| Style3DGallery | 08C9 |
| StyleApplyPane | 087F |
| StyleLockDown | 058E |
| StyleMatrixPicker | 08FD |
| StylePaneNewStyle | 094E |

| Fixed Command Name | Fixed Command Index |
|---------------------------|----------------------------|
| StyleQuickFormat | 0827 |
| Subscript | 0037 |
| Superscript | 0036 |
| SurfaceMatGallery | 08CC |
| SwitchNavigationWindow | 0793 |
| Symbol | 022B |
| SymbolFont | 028B |
| SymbolMRUGallery | 07A6 |
| SyncScrollSideBySide | 058F |
| TOAGroup | 08A6 |
| TableAutoFormat | 0233 |
| TableAutoFormatStyle | 055F |
| TableAutoSum | 0281 |
| TableColumnWidth | 008F |
| TableColumnWidthSpinner | 091F |
| TableDeleteCells | 0085 |
| TableDeleteColumn | 0087 |
| TableDeleteGeneral | 0145 |
| TableDeleteRow | 0086 |
| TableDeleteTable | 0436 |
| TableFormatCell | 0264 |
| TableFormula | 015C |
| TableGridlines | 0090 |
| TableHeadings | 0256 |
| TableInsertCells | 0082 |
| TableInsertCells2 | 0977 |
| TableInsertColumn | 0084 |
| TableInsertColumnRight | 0435 |
| TableInsertGeneral | 0144 |
| TableInsertRow | 0083 |

| Fixed Command Name | Fixed Command Index |
|---------------------------|----------------------------|
| TableInsertRowAbove | 0448 |
| TableInsertRowBelow | 0434 |
| TableInsertTable | 0081 |
| TableInsertTableEG | 0437 |
| TableMergeCells | 0088 |
| TableOfContentsGallery | 0911 |
| TableOptions | 0438 |
| TableProperties | 035D |
| TableRowHeight | 008E |
| TableRowHeightSpinner | 0920 |
| TableSelectCell | 0433 |
| TableSelectColumn | 008D |
| TableSelectRow | 008C |
| TableSelectTable | 008B |
| TableSort | 00C7 |
| TableSortAToZ | 0189 |
| TableSortZToA | 018A |
| TableSplit | 008A |
| TableSplitCells | 0089 |
| TableStyleNew | 09A2 |
| TableToOrFromText | 0147 |
| TableToText | 0080 |
| TableUpdateAutoFormat | 0272 |
| TableWizard | 0485 |
| TableWrapping | 0356 |
| TextBoxGallery | 08DF |
| TextBoxLinking | 0348 |
| TextBoxUnlinking | 0349 |
| TextFlowGallery | 08C1 |
| TextFormField | 015D |

| Fixed Command Name | Fixed Command Index |
|----------------------------------|----------------------------|
| TextToTable | 007F |
| TextboxPositionGallery | 091D |
| TextboxStyleGallery | 091E |
| TexturesGallery | 07BA |
| ThemeGallery | 08FE |
| TocOutlineLevelGallery | 0836 |
| ToggleCharacterCode | 0571 |
| ToggleDocumentActionBar | 087E |
| ToggleDocumentText | 084C |
| ToggleDontOpenAttachInFullScreen | 089C |
| ToggleFieldDisplay | 0022 |
| ToggleFormsDesign | 0369 |
| ToggleFull | 0246 |
| ToggleHeaderFooterLink | 028C |
| ToggleMacroRun | 029D |
| ToggleMainTextLayer | 024B |
| ToggleMasterSubdocs | 0374 |
| ToggleOptimizeForLayout | 09A9 |
| TogglePanningHand | 07AA |
| TogglePortrait | 0132 |
| TogglePropertyPanel | 082E |
| ToggleReadingMode2Pages | 05A2 |
| ToggleReadingModeHelp | 05AC |
| ToggleReadingModeInk | 05A3 |
| ToggleRibbon | 0956 |
| ToggleScribbleMode | 0134 |
| ToggleTextFlow | 03F1 |
| ToggleThumbnail | 059E |
| ToggleToolbars | 05B0 |
| ToggleWebDesign | 045F |

| Fixed Command Name | Fixed Command Index |
|-------------------------------|----------------------------|
| ToggleXMLStructure | 080F |
| ToggleXMLTagView | 0588 |
| ToolsAddRecordDefault | 0275 |
| ToolsAdvancedSettings | 00CE |
| ToolsAutoCorrect | 017A |
| ToolsAutoCorrectCapsLockOff | 02FF |
| ToolsAutoCorrectDays | 0180 |
| ToolsAutoCorrectExceptions | 02FA |
| ToolsAutoCorrectHECorrect | 03E9 |
| ToolsAutoCorrectInitialCaps | 017D |
| ToolsAutoCorrectManager | 0794 |
| ToolsAutoCorrectReplaceText | 017C |
| ToolsAutoCorrectSentenceCaps | 017F |
| ToolsAutoCorrectSmartQuotes | 00E3 |
| ToolsAutoManager | 0393 |
| ToolsAutoSummarize | 0389 |
| ToolsAutoSummarizeBegin | 036A |
| ToolsBookshelfDefineReference | 03BE |
| ToolsBookshelfLookupReference | 03BD |
| ToolsBulletListDefault | 0133 |
| ToolsBulletsNumbers | 00C4 |
| ToolsBusu | 03AB |
| ToolsCalculate | 00C8 |
| ToolsCompareVersions | 00C6 |
| ToolsConsistency | 03E0 |
| ToolsCreateDirectory | 0341 |
| ToolsCreateEnvelope | 00AD |
| ToolsCreateLabels | 01E9 |
| ToolsCustomize | 0098 |
| ToolsCustomizeAddMenuShortcut | 022E |

| Fixed Command Name | Fixed Command Index |
|----------------------------------|----------------------------|
| ToolsCustomizeKeyboard | 01B0 |
| ToolsCustomizeKeyboardShortcut | 022D |
| ToolsCustomizeMenuBar | 0267 |
| ToolsCustomizeMenus | 01B1 |
| ToolsCustomizeRemoveMenuShortcut | 0259 |
| ToolsCustomizeToolbar | 02CC |
| ToolsDictionary | 03DD |
| ToolsEServices | 0567 |
| ToolsEnvelopesAndLabels | 025F |
| ToolsFixHHC | 04EE |
| ToolsGramSettings | 0375 |
| ToolsGrammar | 00C1 |
| ToolsGrammarHide | 03D3 |
| ToolsGrammarRange | 034F |
| ToolsHHC | 0310 |
| ToolsHyphenation | 00C3 |
| ToolsHyphenationAutoOff | 081D |
| ToolsHyphenationAutoOn | 081C |
| ToolsHyphenationManual | 02C0 |
| ToolsInsertScript | 041A |
| ToolsLanguage | 00BC |
| ToolsLineNumContinuous | 0832 |
| ToolsLineNumOff | 0831 |
| ToolsLineNumResetSection | 0834 |
| ToolsLineNumRestPage | 0833 |
| ToolsLineNumSuppress | 0835 |
| ToolsMacro | 00D7 |
| ToolsManageFields | 0277 |
| ToolsMergeRevisions | 01B3 |
| ToolsNumberListDefault | 0135 |

| Fixed Command Name | Fixed Command Index |
|---------------------------------|----------------------------|
| ToolsOptions | 03CE |
| ToolsOptionsAutoFormat | 03BF |
| ToolsOptionsAutoFormatAsYouType | 030A |
| ToolsOptionsBidi | 0405 |
| ToolsOptionsCompatibility | 020D |
| ToolsOptionsEdit | 00E0 |
| ToolsOptionsEditCopyPaste | 054C |
| ToolsOptionsFileLocations | 00E1 |
| ToolsOptionsFuzzy | 0316 |
| ToolsOptionsGeneral | 00CB |
| ToolsOptionsGrammar | 00D4 |
| ToolsOptionsHHC | 0312 |
| ToolsOptionsPrint | 00D0 |
| ToolsOptionsRevisions | 0182 |
| ToolsOptionsSave | 00D1 |
| ToolsOptionsSecurity | 0551 |
| ToolsOptionsSmartTag | 0573 |
| ToolsOptionsSpelling | 00D3 |
| ToolsOptionsTypography | 02E3 |
| ToolsOptionsUserInfo | 00D5 |
| ToolsOptionsView | 00CC |
| ToolsProofing | 033C |
| ToolsProtect | 04D8 |
| ToolsProtectDocument | 01F7 |
| ToolsProtectSection | 0242 |
| ToolsProtectUnprotectDocument | 0208 |
| ToolsRecordMacroStart | 029A |
| ToolsRecordMacroStop | 029B |
| ToolsRecordMacroToggle | 00D6 |
| ToolsRemoveRecordDefault | 0276 |

| Fixed Command Name | Fixed Command Index |
|------------------------------|----------------------------|
| ToolsRepaginate | 00C9 |
| ToolsReviewRevisions | 01FA |
| ToolsRevisionMarksAccept | 03AE |
| ToolsRevisionMarksNext | 03CB |
| ToolsRevisionMarksPrev | 03CA |
| ToolsRevisionMarksReject | 03AF |
| ToolsRevisionMarksToggle | 03BC |
| ToolsRevisions | 00C5 |
| ToolsSCTCTranslate | 0492 |
| ToolsShrinkToFit | 01F8 |
| ToolsSpellSelection | 00C0 |
| ToolsSpelling | 00BF |
| ToolsSpellingHide | 03D2 |
| ToolsSpellingRange | 034E |
| ToolsSpellingRecheckDocument | 0309 |
| ToolsTCSCTranslate | 0491 |
| ToolsTCSCTranslation | 0484 |
| ToolsThesaurus | 00C2 |
| ToolsThesaurusRR | 059F |
| ToolsTranslateChinese | 0493 |
| ToolsUnprotectDocument | 0209 |
| ToolsWordCount | 00E4 |
| ToolsWordCountList | 0542 |
| ToolsWordCountRecount | 0541 |
| TopAlign | 031F |
| TopCenterAlign | 047A |
| TopLeftAlign | 047B |
| TopRightAlign | 0479 |
| TraceMacro | 010B |
| TrackChangesOptions | 089F |

| Fixed Command Name | Fixed Command Index |
|---------------------------|----------------------------|
| Translate | 053A |
| TranslatePane | 04E6 |
| TrustCenter | 17C7 |
| TxbxAutoSize | 054D |
| UIMCorrectionUI | 0548 |
| UnHang | 0029 |
| UnIndent | 0027 |
| UnIndentChar | 02D0 |
| UnIndentFirstChar | 02D2 |
| UnIndentFirstLine | 02F3 |
| UnIndentLine | 02F5 |
| Underline | 0033 |
| UnderlineColor | 0311 |
| UnderlineColorPicker | 08C0 |
| UnderlineGallery | 08BF |
| UnderlineStyle | 048B |
| UnlinkFields | 0021 |
| UnlinkFieldsVBA | 0373 |
| UnlockFields | 0024 |
| UnlockPolicyLabel | 0784 |
| UpdateBibliography | 09A6 |
| UpdateFields | 0020 |
| UpdateFieldsIndex | 081B |
| UpdateFieldsTable | 081A |
| UpdateFieldsToa | 0947 |
| UpdateFieldsTof | 0948 |
| UpdateFieldsVBA | 0370 |
| UpdatePolicyLabels | 0825 |
| UpdateSource | 0025 |
| UpdateStyle | 079D |

| Fixed Command Name | Fixed Command Index |
|----------------------------|----------------------------|
| UpdateTableOfContents | 056E |
| UpdateToc | 014B |
| UpdateTocFull | 03AD |
| UpgradeDocument | 0940 |
| UseBalloons | 05A7 |
| UserDialog | 0129 |
| UxGalWordTableStyles | 08EF |
| ViewAnnotations | 009D |
| ViewBorderToolbar | 025C |
| ViewChanges | 0504 |
| ViewCode | 036E |
| ViewControlToolbox | 1BAF |
| ViewDocumentMap | 03B0 |
| ViewDocumentMapReadingMode | 05B6 |
| ViewDraft | 0095 |
| ViewDrawingToolbar | 025D |
| ViewEmailSource | 0929 |
| ViewEndnoteArea | 0152 |
| ViewEndnoteContNotice | 01F2 |
| ViewEndnoteContSeparator | 01F1 |
| ViewEndnoteSeparator | 01F0 |
| ViewFieldCodes | 0096 |
| ViewFooter | 028E |
| ViewFooterOnly | 090F |
| ViewFootnoteArea | 009C |
| ViewFootnoteContNotice | 01EF |
| ViewFootnoteContSeparator | 01EE |
| ViewFootnoteSeparator | 01ED |
| ViewFootnotes | 01F6 |
| ViewFormatExToolbar | 032B |

| Fixed Command Name | Fixed Command Index |
|---------------------------|----------------------------|
| ViewGridlines | 02E5 |
| ViewHTMLSource | 0482 |
| ViewHeader | 01E4 |
| ViewHeaderOnly | 08EA |
| ViewMasterDocument | 01EA |
| ViewNormal | 0091 |
| ViewOnline | 0334 |
| ViewOutline | 0092 |
| ViewOutlineMaster | 0499 |
| ViewOutlineSplitToolbar | 0324 |
| ViewPage | 0093 |
| ViewPageFromOutline | 094D |
| ViewRuler | 0099 |
| ViewSecurity | 0419 |
| ViewSignatures | 04F3 |
| ViewStatusBar | 009A |
| ViewTaskPane | 0521 |
| ViewToggleMasterDocument | 0278 |
| ViewTogglePageBoundaries | 0367 |
| ViewToolbars | 0143 |
| ViewVBCode | 03B4 |
| ViewWeb | 0350 |
| ViewWebToolbox | 1BC4 |
| ViewXMLStructure | 056C |
| ViewZoom | 0241 |
| ViewZoom100 | 0131 |
| ViewZoom200 | 023D |
| ViewZoom75 | 023E |
| ViewZoomPageWidth | 0130 |
| ViewZoomTwoPage | 07A3 |

| Fixed Command Name | Fixed Command Index |
|----------------------------------|----------------------------|
| ViewZoomWholePage | 012F |
| WW2_ChangeRulerMode | 0127 |
| WW2_EditFind | 01A5 |
| WW2_EditFindChar | 019F |
| WW2_EditReplace | 01A6 |
| WW2_EditReplaceChar | 01A0 |
| WW2_FileTemplates | 17A6 |
| WW2_FootnoteOptions | 012B |
| WW2_FormatBordersAndShading | 02B9 |
| WW2_FormatCharacter | 0176 |
| WW2_FormatDefineStyleChar | 019E |
| WW2_InsertFootnote | 00A0 |
| WW2_InsertIndex | 02B7 |
| WW2_InsertSymbol | 02B5 |
| WW2_InsertTableOfContents | 0158 |
| WW2_PrintMerge | 005A |
| WW2_PrintMergeCheck | 005B |
| WW2_PrintMergeCreateDataSource | 0069 |
| WW2_PrintMergeCreateHeaderSource | 006A |
| WW2_PrintMergeHelper | 005F |
| WW2_PrintMergeSelection | 005E |
| WW2_PrintMergeToDoc | 005C |
| WW2_PrintMergeToPrinter | 005D |
| WW2_RulerMode | 002C |
| WW2_TableColumnWidth | 00DF |
| WW2_TableRowHeight | 0146 |
| WW2_ToolsHyphenation | 0159 |
| WW2_ToolsMacro | 02A2 |
| WW2_ToolsOptionsGeneral | 0183 |
| WW2_ToolsOptionsKeyboard | 01B2 |

| Fixed Command Name | Fixed Command Index |
|-------------------------------|----------------------------|
| WW2_ToolsOptionsMenu | 01E7 |
| WW2_ToolsOptionsPrint | 015B |
| WW2_ToolsOptionsToolbar | 00D2 |
| WW2_ToolsOptionsView | 01F3 |
| WW2_ToolsRevisionsMark | 01D0 |
| WW2_ViewZoom | 0094 |
| WW7_DecreaseIndent | 028A |
| WW7_DrawTextBox | 016B |
| WW7_DrawVerticalTextBox | 02E2 |
| WW7_EditAutoText | 007B |
| WW7_EditGoTo | 007A |
| WW7_FormatBulletsAndNumbering | 018D |
| WW7_FormatDrawingObject | 0235 |
| WW7_IncreaseIndent | 0289 |
| WW7_InsertColumnBreak | 0116 |
| WW7_InsertPageBreak | 0115 |
| WW7_ToolsGrammar | 03E8 |
| WW7_ToolsOptions | 00CA |
| WW7_ToolsOptionsAutoFormat | 016D |
| WebAddHyperlnkToFavorites | 03EA |
| WebAddToFavorites | 039C |
| WebAddress | 03AA |
| WebCopyHyperlink | 039B |
| WebDiscussions | 049B |
| WebGoBack | 03A3 |
| WebGoForward | 03A5 |
| WebHideToolbars | 03A1 |
| WebOpenFavorites | 03A0 |
| WebOpenHyperlink | 0399 |
| WebOpenInNewWindow | 039A |

| Fixed Command Name | Fixed Command Index |
|------------------------------|----------------------------|
| WebOpenSearchPage | 03C8 |
| WebOpenStartPage | 03A2 |
| WebOptions | 0382 |
| WebPagePreview | 0445 |
| WebRefresh | 03A7 |
| WebSelectHyperlink | 039F |
| WebStopLoading | 03A6 |
| WebToolbar | 03F0 |
| WindowArrangeAll | 00DA |
| WindowArrangeSideBySide | 058B |
| WindowList | 00DC |
| WindowNewWindow | 00D9 |
| WordArtGallery | 08CE |
| WordArtShapeGallery | 08D3 |
| WordLeft | 0FA2 |
| WordLeftExtend | 0FB4 |
| WordRight | 0FA3 |
| WordRightExtend | 0FB5 |
| WordSearchLibraries | 080D |
| WordSetDefaultPaste | 0924 |
| WordTableStylesBandedColumns | 08F5 |
| WordTableStylesBandedRows | 08F4 |
| WordTableStylesFirstColumn | 08F2 |
| WordTableStylesHeaderRow | 08F0 |
| WordTableStylesLastColumn | 08F3 |
| WordTableStylesTotalRow | 08F1 |
| WordUnderline | 0035 |
| XMLDocument | 0592 |
| XMLGroup | 08D4 |
| XMLOptions | 0591 |

| Fixed Command Name | Fixed Command Index |
|--------------------|---------------------|
| XmlAttr | 05B4 |
| XmlExpansionPacks | 0811 |
| XmlSchema | 0810 |
| Zoom100 | 09A3 |

3.1.2.1.3 Statements

Statements can only be identified by name for key mapping purposes.

| Statement Name |
|----------------------|
| AOCEAddRecipient |
| AOCEAuthenticateUser |
| AOCEClearMailerField |
| AOCECountRecipients |
| AOCESendMail |
| AOCESetSubject |
| Abs |
| Activate |
| AddAddIn |
| AddAddress |
| AddAutoText |
| AddButton |
| AddDropDownItem |
| AddInState |
| AllCaps |
| AppActivate |
| AppClose |
| AppCount |
| AppGetNames |
| AppHide |
| AppIsRunning |
| AppMaximize |

| Statement Name |
|-----------------------|
| AppMinimize |
| AppMove |
| AppRestore |
| AppSendMessage |
| AppShow |
| AppSize |
| AppWindowHeight |
| AppWindowPosLeft |
| AppWindowPosTop |
| AppWindowWidth |
| Asc |
| AssertOutput |
| AtEndOfDocument |
| AtStartOfDocument |
| AutoMarkIndexEntries |
| BatchMode |
| Beep |
| Bold |
| BoldRun |
| BorderAll |
| BorderBottom |
| BorderInside |
| BorderLeft |
| BorderLineStyle |
| BorderLineWeight |
| BorderNone |
| BorderOutside |
| BorderRight |
| BorderTLtoBR |
| BorderTRtoBL |

| Statement Name |
|----------------------------|
| BorderTop |
| BytePos |
| CInsertDateField |
| CInsertTimeField |
| CancelButton |
| CenterPara |
| ChDefaultDir |
| ChDir |
| ChangeByte |
| ChangeCase |
| ChangeKana |
| CharColor |
| CharColorRGB |
| CharLeft |
| CharRight |
| CharScale |
| CheckBox |
| ClearAddIns |
| CloseUpPara |
| CmpBookmarks |
| ColumnSelect |
| ComboBox |
| CommaAccent |
| CommandValid |
| ContextHelp |
| ConverterLookup |
| CopyBookmark |
| CopyButtonImage |
| CountAddIns |
| CountAutoCorrectExceptions |

| Statement Name |
|-----------------------------|
| CountAutoTextEntries |
| CountBookmarks |
| CountDirectories |
| CountDocumentProperties |
| CountDocumentVars |
| CountFiles |
| CountFonts |
| CountFoundFiles |
| CountKeys |
| CountLanguages |
| CountMacros |
| CountMenuItems |
| CountMenus |
| CountMergeFields |
| CountSdAlloc |
| CountStyles |
| CountToolbarButtons |
| CountToolbars |
| CountToolsGrammarStatistics |
| CountWindows |
| CrashOnNextEmailDisplay |
| CrashOnNextEmailLayout |
| CrashOnNextEmailLoad |
| DDEExecute |
| DDEInitiate |
| DDEPoke |
| DDETerminate |
| DDETerminateAll |
| DateSerial |
| DateValue |

| Statement Name |
|------------------------|
| Day |
| Days360 |
| DeleteAddIn |
| DeleteButton |
| DeleteDocumentProperty |
| DisableAutoMacros |
| DisableInput |
| DistributePara |
| DistributeRow |
| DlgControlId |
| DlgEnable |
| DlgFilePreview |
| DlgFocus |
| DlgListBoxArray |
| DlgLoadValues |
| DlgSetPicture |
| DlgStoreValues |
| DlgText |
| DlgUpdateFilePreview |
| DlgValue |
| DlgVisible |
| DocClose |
| DocMaximize |
| DocMinimize |
| DocMove |
| DocSize |
| DocSplit |
| DocWindowHeight |
| DocWindowPosLeft |
| DocWindowPosTop |

| Statement Name |
|-------------------------|
| DocWindowWidth |
| DocumentHasMisspellings |
| DocumentPropertyExists |
| DocumentPropertyType |
| DocumentProtection |
| DotAccent |
| DottedUnderline |
| DoubleStrikethrough |
| DoubleUnderline |
| DrawClearRange |
| DrawCount |
| DrawCountPolyPoints |
| DrawExtendSelect |
| DrawGetCalloutTextbox |
| DrawGetPolyPoints |
| DrawGetType |
| DrawSelect |
| DrawSetCalloutTextbox |
| DrawSetInsertToAnchor |
| DrawSetInsertToTextbox |
| DrawSetPolyPoints |
| DrawSetRange |
| DropListBox |
| EditButtonImage |
| EditClear |
| EditFindFound |
| EditRedo |
| EditUndo |
| EmptyBookmark |
| EnableFormField |

| Statement Name |
|------------------------|
| EndOfColumn |
| EndOfDocument |
| EndOfLine |
| EndOfRow |
| EndOfWindow |
| Eof |
| ExistingBookmark |
| ExitWindows |
| ExtendMode |
| ExtendSelection |
| File1 |
| File2 |
| File3 |
| File4 |
| File5 |
| File6 |
| File7 |
| File8 |
| File9 |
| FileClose |
| FileCloseAll |
| FileConfirmConversions |
| FileExit |
| FileList |
| FileNFib |
| FilePost |
| FilePreview |
| FilePrintPreview |
| FilePrintPreviewPages |
| FileQuit |

| Statement Name |
|-------------------------|
| FileSaveAll |
| Font |
| FontSize |
| FormShading |
| FormatBulletDefault |
| FormatNumberDefault |
| FuzzyCompare |
| GetAddInId |
| GetAttr |
| GetDocumentProperty |
| GetFormResult |
| GetSelEndPos |
| GetSelStartPos |
| GetSystemInfo |
| GoToNextSubdocument |
| GoToPreviousSubdocument |
| GroupBox |
| HLine |
| HPage |
| HScroll |
| Hidden |
| HighlightColor |
| Hour |
| IMEControl |
| InStr |
| InStrB |
| Insert |
| InsertPara |
| Int |
| InvalAllDocs |

| Statement Name |
|-------------------------------|
| InvalAllDocsRepagOnly |
| IsAutoCorrectException |
| IsCustomDocumentProperty |
| IsDocumentDirty |
| IsDocumentPropertyReadOnly |
| IsExecuteOnly |
| IsMacro |
| IsTemplateDirty |
| Italic |
| ItalicRun |
| JustifyPara |
| KeyCode |
| Kill |
| Language |
| LeftPara |
| Len |
| LenB |
| LineDown |
| LineSpacing |
| LineUp |
| ListBox |
| LockDocument |
| Lof |
| LtrKeyb |
| LtrPara |
| LtrRun |
| MacScript |
| MacroCopy |
| Magnifier |
| MailMergeAskToConvertChevrons |

| Statement Name |
|---------------------------|
| MailMergeConvertChevrons |
| MailMergeFoundRecord |
| MailMergeGoToRecord |
| MailMergeMainDocumentType |
| MailMergeState |
| MailMergeViewData |
| MainTextFlow |
| MemAllocFail |
| MenuDirection |
| Minute |
| MkDir |
| Month |
| MountVolume |
| MoveButton |
| MoveToolbar |
| MsgBox |
| NextCell |
| NextField |
| NextObject |
| NextPage |
| NextTab |
| Now |
| OKButton |
| OnTime |
| OpenUpPara |
| OptionButton |
| OptionGroup |
| Outline |
| OutlineLevel |
| OutlineShowFirstLine |

| Statement Name |
|------------------------|
| Overtime |
| PageDown |
| PageUp |
| ParaDown |
| ParaKeepLinesTogether |
| ParaKeepWithNext |
| ParaPageBreakBefore |
| ParaUp |
| ParaWidowOrphanControl |
| PasteButtonImage |
| Picture |
| PrevCell |
| PrevField |
| PrevObject |
| PrevPage |
| PrevTab |
| PushButton |
| PutFieldData |
| RefreshRate |
| RemoveAllDropDownItems |
| RemoveDropDownItem |
| Rename |
| RenameMenu |
| ResetButtonImage |
| ResetChar |
| ResetPara |
| RightPara |
| Rmdir |
| Rnd |
| RtlKeyb |

| Statement Name |
|-------------------------|
| RtlPara |
| RtlRun |
| ScreenUpdating |
| Second |
| Seek |
| SelInfo |
| SelType |
| SelectCurLine |
| SelectCurPara |
| SelectCurSentence |
| SelectCurWord |
| SendKeys |
| SentLeft |
| SentRight |
| SetAttr |
| SetAutoText |
| SetDocumentDirty |
| SetDocumentProperty |
| SetDocumentPropertyLink |
| SetDocumentVar |
| SetEndOfBookmark |
| SetFileCreatorAndType |
| SetFormResult |
| SetPrivateProfileString |
| SetProfileString |
| SetSelRange |
| SetStartOfBookmark |
| SetTemplateDirty |
| Sgn |
| ShadingPattern |

| Statement Name |
|-----------------------|
| Shadow |
| Shell |
| ShowAlerts |
| ShowAll |
| ShowAnnotationBy |
| SizeToolbar |
| SkipNumbering |
| SmallCaps |
| SortArray |
| SpacePara1 |
| SpacePara15 |
| SpacePara2 |
| SpellChecked |
| StartOfColumn |
| StartOfDocument |
| StartOfLine |
| StartOfRow |
| StartOfWindow |
| Stop |
| Strikethrough |
| Style |
| Subscript |
| Superscript |
| SymbolFont |
| TabType |
| TableGridlines |
| TableHeadings |
| Text |
| TextBox |
| TimeSerial |

| Statement Name |
|--|
| TimeValue |
| Today |
| ToolbarState |
| ToolsAutoCorrectCapsLockOff |
| ToolsAutoCorrectDays |
| ToolsAutoCorrectInitialCaps |
| ToolsAutoCorrectReplaceText |
| ToolsAutoCorrectReplaceTextFromSpellingChecker |
| ToolsAutoCorrectSentenceCaps |
| ToolsAutoCorrectSmartQuotes |
| ToolsCalculate |
| ToolsGrammarStatisticsArray |
| ToolsRevisionDate |
| ToolsRevisionType |
| Underline |
| UnderlineColor |
| UnderlineStyle |
| VLine |
| VPage |
| VScroll |
| Val |
| ViewAnnotations |
| ViewDraft |
| ViewEndnoteArea |
| ViewFieldCodes |
| ViewFooter |
| ViewFootnoteArea |
| ViewFootnotes |
| ViewGridlines |
| ViewHeader |

| Statement Name |
|-----------------------|
| ViewMasterDocument |
| ViewMenus |
| ViewNormal |
| ViewOutline |
| ViewPage |
| ViewRibbon |
| ViewRuler |
| ViewStatusBar |
| ViewToolbar |
| WW1_InsertPara |
| WW2CallingConvention |
| WW2_Asc |
| WW2_ChangeCase |
| WW2_CountMenuItems |
| WW2_GetToolButton |
| WW2_Insert |
| WW2_KeyCode |
| WW2_RenameMenu |
| WW2_Underlines |
| WW6_EditClear |
| WaitCursor |
| Weekday |
| WinAllocFail |
| Window |
| Window1 |
| Window2 |
| Window3 |
| Window4 |
| Window5 |
| Window6 |

| Statement Name |
|------------------------|
| Window7 |
| Window8 |
| Window9 |
| WindowList |
| WindowPane |
| WordLeft |
| WordRight |
| WordUnderline |
| WriteDBS |
| XAsc |
| Year |
| ZoomMouseSettings |
| wdAddCommand |
| wdCaptureKeyDown |
| wdCloseWindow |
| wdEndDialog |
| wdFontWidth |
| wdGetHwnd |
| wdGetInst |
| wdOpenWindow |
| wdPrint |
| wdReleaseKeyDown |
| wdSetTimer |
| wdToolsGetHHC |
| wdToolsGetSpelling |
| wdToolsGetSpellingXtra |
| wdToolsGetSynonyms |

3.1.2.2 Mail Merge

The following clauses specify the semantics used to facilitate the mail merge feature in Word.

3.1.2.2.1 Elements

3.1.2.2.1.1 hash (Hash Code for Record)

This element specifies the unique hash value of a given record within the specified external data source. This element is used to maintain a relationship between the records within an external data source and a given source WordprocessingML document.

The contents of this element's **val** attribute shall be a hash value that will uniquely identify the record in the external data source. The hash value for a record is computed using the following algorithm:

Utility function 1:

```
#define nPrimeLast 4294967291

__int32 LHashMM( __int32 l, __int32 dl )
{
    l = 131 * l + dl;
    if (l >= nPrimeLast) {
        l -= nPrimeLast;
    }
    return l;
}
```

Utility function 2:

```
__int32 LGetHashWz(const WCHAR *wzText)
{
    int cch = lstrlen(wzText);
    __int32 lhash = 0L;
    for (int i = 0; i < cch; i++) {
        lhash = LHashMM(lhash, wzText[i]);
    }
    return lhash;
}
```

Hash Algorithm:

```
__int32 lwHash = 0L;
for(int i = 0; i < TotalNumberOfColumnsInTheDataSource; i++) {
```

Retrieve the value in the i-th column of this record as a Unicode String wzData;

```

__int32 l = LGetHashWz(wzData);
if(l) {
    lwHash = LHashMM(lwHash, l);
}
}

return lwHash as the computed hash for this record;

```

[Note: This information is necessary as part of a mail merge because records may be added or deleted from external data sources, and a means must be provided to maintain record-specific inclusion or exclusion data using the **active** element (§3.1.2.1.1.6, [active](#)) and the affected external data record when the WordprocessingML document is reconnected to the external data source irrespective of the ordering of the records within the external data source. end note]

[Example: Consider the following WordprocessingML fragment for the information about a single record in a source document for a mail merge:

```

<w:recipientData>
  <w:active w:val="0" />
  <w:hash w:val="258865469" />
</w:recipientData>

```

The external data record associated with this information is specified via the hash value 258865469. This record will not be imported into the merged WordprocessingML document because the **active** element (§3.1.2.1.1.6, [active](#)) associated with the given external data record has a **val** attribute equal to 0; for example, when the specified external data source is connected, the record that has the hash value 258865469 will not be used to populate mapped fields in a merged document with data from that record. end example]

| Parent Elements |
|---|
| recipientData (§3.1.2.2.1.2, recipientData) |

| Attributes | Description |
|---------------|---|
| val () | The possible values for this attribute are defined by the ST_DecimalNumber simple type (§3.1.2.3.1, ST_DecimalNumber). |

The following XML Schema fragment defines the contents of this element:

```

<complexType name="CT_DecimalNumber">
  <attribute name="val" type="ST_DecimalNumber" use="required"/>
</complexType>

```

3.1.2.2.1.2 recipientData (Data About Single Data Source Record)

This element specifies information about a single record within an external data source. If a record shall be merged into a merged document, then no information is needed about the record within this

part. However, if a the record shall not be merged into a merged document, then the hash value for the record shall be stored within the **hash** element as a child of this element, along with the **active** element, to indicate this exclusion.

[Note: This mapping is necessary in place of simply using the element order to correspond to the record indices in the external data source because records may be added or deleted from external data sources, and a means must be provided to maintain specific external record WordprocessingML data, like that specified in the **active** element (§3.1.2.1.1.6, [active](#)) and the corresponding external data record, when the WordprocessingML document is reconnected to the external data source, irrespective of the ordering of the records within the external data source. In other words, this element, and its child elements enable merged WordprocessingML documents to maintain the relationship between the records within an external data and record-specific WordprocessingML parameters. end note]

[Example: Consider a mail merge source WordprocessingML document that:

Has been connected to a specified external data source containing three records; and

Has been configured by the hosting application to not populate a merged document with the record pertaining to *John Smith* in the external data source.

Consider also that the first time the given WordprocessingML document was connected to the external data source, *John Smith's* record was in the second record in the data source.

When this merged document is connected to the external data source the **recipientData** element may be used to store the hash value for each data record in the external data source, including *John Smith's*. This setting is represented using the following WordprocessingML to use the hash codes within the **recipientData** element to uniquely identify the three records within the external data source.

```
<w:recipientData>
  <w:hash w:val="1408613399" />
</w:recipientData>
<w:recipientData>
  <w:active w:val="0" />
  <w:hash w:val="870254691" />
</w:recipientData>
<w:recipientData>
  <w:hash w:val="1107777181" />
</w:recipientData>
```

Here, the first, second (John Smith record), and third records within the specified data source whose hash values are *1408613399*, *870254691*, and *1107777181* have been associated with recipient data via the **active** element to specify that the record associated with the given record (*John Smith's* record) shall not be used to populate a merged WordprocessingML document.

With these associations in place, if a fourth record is added to the given external data source and that record precedes John Smith's record, when the given merged WordprocessingML document is reconnected to the external data source, the hosting application will still know that John Smith's record shall not be used to populate a merged WordprocessingML document as it is associated via its hash value and is not dependent on the given record's ordinal position within the external data source. end example]

| Parent Elements |
|--|
| recipients (§3.1.2.2.1.3, recipients) |

| Child Elements | Subclause |
|--|----------------------|
| active (Record Is Included in Mail Merge) | §3.1.2.1.1.6, active |
| hash (Hash Code for Record) | §3.1.2.2.1.1, hash |

The following XML Schema fragment defines the contents of this element:

```
<complexType name="CT_HashedRecipientData">
  <sequence>
    <element name="active" type="CT_OnOff" minOccurs="0"/>
    <element name="hash" type="CT_DecimalNumber" minOccurs="1"/>
  </sequence>
</complexType>
```

3.1.2.2.1.3 recipients (Inclusion/Exclusion Data for Data Source)

This element specifies all of the inclusion/exclusion data for the contents of the specified mail merge data source. It is the root element for the Mail Merge Recipient Data part.

[Example: Consider a document which is the source document for a mail merge operation. If two records of the three specified by the data source were excluded from the mail merge, the resulting recipient data part would appear as follows:

```
<w:recipients>
  <w:recipientData>
    <w:active w:val="false"/>
    ...
  </w:recipientData>
  <w:recipientData>
    <w:active w:val="false"/>
    ...
  </w:recipientData>
  <w:recipientData>
    ...
  </w:recipientData>
</w:recipients>
```

The **recipients** element contains all of the recipient inclusion/exclusion data for this mail merge document. end example]

| Child Elements | Subclause |
|---|-----------------------------|
| recipientData (Data About Single Data Source Record) | §3.1.2.2.1.2, recipientData |

The following XML Schema fragment defines the contents of this element:

```

<complexType name="CT_HashedRecipients">
  <sequence>
    <element name="recipientData" type="CT_HashedRecipientData" minOccurs="1"
maxOccurs="unbounded"/>
  </sequence>
</complexType>

```

3.1.2.3 Simple Types

This is the complete list of simple types in the <http://schemas.microsoft.com/office/word/2006/wordml> namespace.

3.1.2.3.1 ST_DecimalNumber (Decimal Number Value)

This simple type specifies that its contents will contain a whole decimal number (positive or negative), whose contents are interpreted based on the context of the parent XML element.

[Example: Consider the following WordprocessingML fragment:

```

<w:pPr>
  <w:divId w:val="1512645511" />
</w:pPr>

```

The value of the **val** attribute is the ID of the associated HTML `div`.

However, consider the following fragment:

```

<w:ilvl w:val="1">
  ...
</w:ilvl>

```

In this case, the decimal number in the **val** attribute is the ID of the associated numbering level. In each case, the value is interpreted in the context of the parent element. end example]

This simple type's contents are a restriction of the XML Schema `int` datatype.

| Referenced By |
|---|
| hash@val (§3.1.2.2.1.1, hash) |

The following XML Schema fragment defines the contents of this simple type:

```

<simpleType name="ST_DecimalNumber">
  <restriction base="xsd:int"/>
</simpleType>

```

3.1.2.3.2 ST_LongHexNumber (Four Digit Hexadecimal Number Value)

This simple type specifies a number value specified as a four-octet (eight-digit) hexadecimal number), whose contents are interpreted based on the context of the parent XML element.

[Example: Consider the following value for a node of type **ST_LongHexNumber**: `00BE2C6C`.

This value is valid, as it contains four hexadecimal octets, each an encoding of an octet of the actual decimal number value. end example]

This simple type's contents are a restriction of the XML Schema hexBinary datatype.

This simple type also specifies the following restrictions:

This simple type's contents have a length of exactly 8 hexadecimal digit(s).

| Referenced By |
|-------------------------------------|
| wch@val (§3.1.2.1.1.15, wch) |

The following XML Schema fragment defines the contents of this simple type:

```
<simpleType name="ST_LongHexNumber">  
  <restriction base="xsd:hexBinary">  
    <length value="4"/>  
  </restriction>  
</simpleType>
```

3.1.2.3.3 ST_OnOff (On/Off Value)

This simple type specifies a set of values for any binary (on or off) property defined in a WordprocessingML document.

A value of *on*, *1*, or *true* specifies that the property shall be turned on.

A value of *off*, *0*, or *false* specifies that the property shall be explicitly turned off.

This simple type's contents are a restriction of the XML Schema string datatype.

The following are possible enumeration values for this type:

| Enumeration Value | Description |
|-------------------|--|
| 0 () | Specifies that the binary state of this property is off (parent property is explicitly not applied). |
| 1 () | Specifies that the binary state of this property is on (parent property is explicitly applied). |
| false () | Specifies that the binary state of this property is off (parent property is explicitly not applied). |
| off () | Specifies that the binary state of this property is off (parent property is explicitly not applied). |
| on () | Specifies that the binary state of this property is on (parent property is explicitly applied). |
| true () | Specifies that the binary state of this property is on (parent property is explicitly applied). |

| Referenced By |
|---|
| active@val (§3.1.2.1.1.6, active); keymap@mask (§3.1.2.1.1.8, keymap) |

The following XML Schema fragment defines the contents of this simple type:

```
<simpleType name="ST_OnOff">  
  <restriction base="xsd:string">  
    <enumeration value="true"/>  
    <enumeration value="false"/>  
    <enumeration value="on"/>  
    <enumeration value="off"/>  
    <enumeration value="0"/>  
    <enumeration value="1"/>  
  </restriction>  
</simpleType>
```

3.1.2.3.4 ST_ShortHexNumber (Two Digit Hexadecimal Number Value)

This simple type specifies a two-octet hexadecimal number whose value is interpreted based on the context of the parent XML element.

[Example: Consider the following value for a node of type **ST_ShortHexNumber**: *2F6C*.

This value is valid, as it contains two hexadecimal octets, each an encoding of an octet of the actual decimal number value. end example]

This simple type's contents are a restriction of the XML Schema hexBinary datatype.

This simple type also specifies the following restrictions:

This simple type's contents have a length of exactly 4 hexadecimal digit(s).

| Referenced By |
|---|
| acd@fciIndexBasedOn (§3.1.2.1.1.1, acd); fci@fciIndex (§3.1.2.1.1.7, fci); fci@swArg (§3.1.2.1.1.7, fci); keymap@chmPrimary (§3.1.2.1.1.8, keymap); keymap@chmSecondary (§3.1.2.1.1.8, keymap); keymap@kcmPrimary (§3.1.2.1.1.8, keymap); keymap@kcmSecondary (§3.1.2.1.1.8, keymap) |

The following XML Schema fragment defines the contents of this simple type:

```
<simpleType name="ST_ShortHexNumber">  
  <restriction base="xsd:hexBinary">  
    <length value="2"/>  
  </restriction>  
</simpleType>
```

3.1.2.3.5 ST_String (String)

This simple type specifies that its contents will contain a string. The contents of this string are interpreted based on the context of the parent XML element.

[Example: Consider the following WordprocessingML fragment:

```
<w:pPr>
  <w:pStyle w:val="heading1" />
</w:pPr>
```

The value of the **val** attribute is the ID of the associated paragraph style's `styleId`. However, consider the following fragment:

```
<w:sdtPr>
  <w:alias w:val="SDT Title Example" />
  ...
</w:sdtPr>
```

In this case, the decimal number in the **val** attribute is the caption of the parent-structured document tag. In each case, the value is of type **ST_String**, and therefore must be interpreted in the context of the parent element. end example]

This simple type's contents are a restriction of the XML Schema string datatype.

| Referenced By |
|---|
| acd@acdName (§3.1.2.1.1.1, acd) ; acd@acdName (§3.1.2.1.1.2, acd) ; acd@argValue (§3.1.2.1.1.1, acd) ; acd@fciBasedOn (§3.1.2.1.1.1, acd) ; acdEntry@acdName (§3.1.2.1.1.3, acdEntry) ; fci@fciName (§3.1.2.1.1.7, fci) ; macro@macroName (§3.1.2.1.1.11, macro) ; wll@macroName (§3.1.2.1.1.16, wll) |

The following XML Schema fragment defines the contents of this simple type:

```
<simpleType name="ST_String">
  <restriction base="xsd:string"/>
</simpleType>
```

3.1.3 Additional WordprocessingML Schema

The subordinate clauses define additional information in the WordprocessingML schema used by Word.

3.1.3.1 Additional Elements

3.1.3.1.1 customXml (Ruby Inline-Level Custom XML Element)

This element specifies the presence of a custom XML element around one or more inline-level structures (runs, images, fields, and so on) within a paragraph. The attributes on this element shall be used to specify the name and namespace URI of the current custom XML element.

[Example: Consider a custom XML element with the name *firstName* that shall be located around two text runs in a WordprocessingML document. This requirement would be specified as follows in the WordprocessingML:

```
<w:p>
  <w:customXml w:element="firstName" ... >
    <w:r>
      ...
    </w:r>
    <w:r>
      ...
    </w:r>
  </w:customXml>
  ...
</w:p>
```

The **customXml** element specifies that the name of the custom XML element is *firstName*, and the custom XML element contains two text runs (it is an inline-level element). end example]

| Parent Elements |
|--|
| customXml (§3.1.3.1.1, customXml); fldSimple (§3.1.3.1.2, fldSimple); hyperlink (§3.1.3.1.3, hyperlink); rt ("ECMA-376 Part 4 §2.3.3.23"); rubyBase ("ECMA-376 Part 4 §2.3.3.26"); sdtContent (§3.1.3.1.7, sdtContent) |

| Child Elements | Subclause |
|--|-----------------------------|
| acc (Accent) | "ECMA-376 Part 4 §7.1.2.1" |
| bar (Bar) | "ECMA-376 Part 4 §7.1.2.7" |
| bookmarkEnd (Bookmark End) | "ECMA-376 Part 4 §2.13.6.1" |
| bookmarkStart (Bookmark Start) | "ECMA-376 Part 4 §2.13.6.2" |
| borderBox (Border-Box Function) | "ECMA-376 Part 4 §7.1.2.11" |
| box (Box Function) | "ECMA-376 Part 4 §7.1.2.13" |
| commentRangeEnd (Comment Anchor Range End) | "ECMA-376 Part 4 §2.13.4.3" |
| commentRangeStart (Comment Anchor Range Start) | "ECMA-376 Part 4 §2.13.4.4" |
| customXml (Ruby Inline-Level Custom XML Element) | §3.1.3.1.1, customXml |
| customXmlDelRangeEnd (Custom XML Markup Deletion End) | "ECMA-376 Part 4 §2.13.5.4" |

| Child Elements | Subclause |
|--|--------------------------------|
| customXmlDelRangeStart (Custom XML Markup Deletion Start) | "[ECMA-376] Part 4 §2.13.5.5" |
| customXmlInsRangeEnd (Custom XML Markup Insertion End) | "[ECMA-376] Part 4 §2.13.5.6" |
| customXmlInsRangeStart (Custom XML Markup Insertion Start) | "[ECMA-376] Part 4 §2.13.5.7" |
| customXmlMoveFromRangeEnd (Custom XML Markup Move Source End) | "[ECMA-376] Part 4 §2.13.5.8" |
| customXmlMoveFromRangeStart (Custom XML Markup Move Source Start) | "[ECMA-376] Part 4 §2.13.5.9" |
| customXmlMoveToRangeEnd (Custom XML Markup Move Destination Location End) | "[ECMA-376] Part 4 §2.13.5.10" |
| customXmlMoveToRangeStart (Custom XML Markup Move Destination Location Start) | "[ECMA-376] Part 4 §2.13.5.11" |
| customXmlPr (Custom XML Element Properties) | "[ECMA-376] Part 4 §2.5.1.7" |
| d (Delimiter Function) | "[ECMA-376] Part 4 §7.1.2.24" |
| del (Deleted Run Content) | "[ECMA-376] Part 4 §2.13.5.12" |
| eqArr (Equation-Array Function) | "[ECMA-376] Part 4 §7.1.2.34" |
| f (Fraction Function) | "[ECMA-376] Part 4 §7.1.2.36" |
| fldSimple (Ruby Simple Field) | §3.1.3.1.2, fldSimple |
| func (Function Apply Function) | "[ECMA-376] Part 4 §7.1.2.39" |
| groupChr (Group-Character Function) | "[ECMA-376] Part 4 §7.1.2.41" |
| hyperlink (Ruby Hyperlink) | §3.1.3.1.3, hyperlink |
| ins (Inserted Run Content) | "[ECMA-376] Part 4 §2.13.5.20" |
| limLow (Lower-Limit Function) | "[ECMA-376] Part 4 §7.1.2.54" |
| limUpp (Upper-Limit Function) | "[ECMA-376] Part 4 §7.1.2.56" |
| m (Matrix Function) | "[ECMA-376] Part 4 §7.1.2.60" |
| moveFrom (Move Source Run Content) | "[ECMA-376] Part 4 |

| Child Elements | Subclause |
|---|---------------------------------|
| | §2.13.5.21" |
| moveFromRangeEnd (Move Source Location Container - End) | "[ECMA-376] Part 4 §2.13.5.23" |
| moveFromRangeStart (Move Source Location Container - Start) | "[ECMA-376] Part 4 §2.13.5.24" |
| moveTo (Move Destination Run Content) | "[ECMA-376] Part 4 §2.13.5.26" |
| moveToRangeEnd (Move Destination Location Container - End) | "[ECMA-376] Part 4 §2.13.5.27" |
| moveToRangeStart (Move Destination Location Container - Start) | "[ECMA-376] Part 4 §2.13.5.28" |
| nary (n-ary Operator Function) | "[ECMA-376] Part 4 §7.1.2.70" |
| oMath (Office Math) | "[ECMA-376] Part 4 §7.1.2.77" |
| oMathPara (Math Paragraph) | "[ECMA-376] Part 4 §7.1.2.78" |
| permEnd (Range Permission End) | "[ECMA-376] Part 4 §2.13.7.1" |
| permStart (Range Permission Start) | "[ECMA-376] Part 4 §2.13.7.2" |
| phant (Phantom Function) | "[ECMA-376] Part 4 §7.1.2.81" |
| proofErr (Proofing Error Anchor) | "[ECMA-376] Part 4 §2.13.8.1" |
| r (Run) | "[ECMA-376] Part 4 §7.1.2.87" |
| r (Text Run) | "[ECMA-376] Part 4 §2.3.2.23" |
| rad (Radical Function) | "[ECMA-376] Part 4 §7.1.2.88" |
| sdt (Ruby Inline-Level Structured Document Tag) | §3.1.3.1.6, sdt |
| sPre (Pre-Sub-Superscript Function) | "[ECMA-376] Part 4 §7.1.2.99" |
| sSub (Subscript Function) | "[ECMA-376] Part 4 §7.1.2.101" |
| sSubSup (Sub-Superscript Function) | "[ECMA-376] Part 4 §7.1.2.103" |
| sSup (Superscript Function) | "[ECMA-376] Part 4 |

| Child Elements | Subclause |
|----------------|-------------|
| | §7.1.2.105" |

| Attributes | Description |
|---|---|
| element (Custom XML Element) | <p>Specifies the name of the current custom XML element or smart tag within the document.</p> <p>[Example: Consider a custom XML element which shall have a name of <i>companyName</i>. This requirement would be specified using the following WordprocessingML:</p> <pre><w:customXml w:element="companyName" ... > ... </w:customXml></pre> <p>The element attribute specifies that the name for this element shall be <i>companyName</i>. end example]</p> <p>The possible values for this attribute are defined by the ST_NcName255 simple type (§3.1.3.3.4, ST_NcName255).</p> |
| uri (Custom XML Element Namespace) | <p>Specifies the namespace URI of the current custom XML element or smart tag. If this attribute is omitted, the URI shall be assumed to be null (no associated URI).</p> <p>[Example: Consider a custom XML element which shall have a namespace URI of <i>urn:customXmlExample</i>. This requirement would be specified using the following WordprocessingML:</p> <pre><w:customXml ... w:uri="urn:customXmlExample" /> ... </w:customXml></pre> <p>The uri attribute specifies that the namespace for this element shall be <i>urn:customXmlExample</i>. end example]</p> <p>The possible values for this attribute are defined by the ST_CustomXmlURI simple type (§3.1.3.3.1, ST_CustomXmlURI).</p> |

The following XML Schema fragment defines the contents of this element:

```
<complexType name="CT_CustomXmlRuby">
  <sequence>
    <element name="customXmlPr" type="CT_CustomXmlPr" minOccurs="0" maxOccurs="1"/>
    <group ref="EG_RubyContent" minOccurs="0" maxOccurs="unbounded"/>
  </sequence>
  <attribute name="uri" type="ST_CustomXmlURI"/>
  <attribute name="element" type="ST_NcName255" use="required"/>
</complexType>
```

3.1.3.1.2 fldSimple (Ruby Simple Field)

This element specifies the presence of a simple field at the current location in the document. The semantics of this field are defined via its field codes ("ECMA-376 Part 4 §2.16.5; Field definitions").

[Example: Consider the following WordprocessingML fragment for a simple field:

```
<w:fldSimple w:instr="FILENAME">
  <w:r>
    <w:t>Example Document.docx</w:t>
  </w:r>
</w:fldSimple>
```

The **fldSimple** element defines a *FILENAME* field ("ECMA-376 Part 4 §2.16.5.23; FILENAME") using the simple field syntax. The current field result for the field is *Example Document.docx*. end example]

| Parent Elements |
|--|
| customXml (§3.1.3.1.1, customXml); fldSimple (§3.1.3.1.2, fldSimple); hyperlink (§3.1.3.1.3, hyperlink); rt ("ECMA-376 Part 4 §2.3.3.23"); rubyBase ("ECMA-376 Part 4 §2.3.3.26"); sdtContent (§3.1.3.1.7, sdtContent) |

| Child Elements | Subclause |
|---|-----------------------------|
| acc (Accent) | "ECMA-376 Part 4 §7.1.2.1" |
| bar (Bar) | "ECMA-376 Part 4 §7.1.2.7" |
| bookmarkEnd (Bookmark End) | "ECMA-376 Part 4 §2.13.6.1" |
| bookmarkStart (Bookmark Start) | "ECMA-376 Part 4 §2.13.6.2" |
| borderBox (Border-Box Function) | "ECMA-376 Part 4 §7.1.2.11" |
| box (Box Function) | "ECMA-376 Part 4 §7.1.2.13" |
| commentRangeEnd (Comment Anchor Range End) | "ECMA-376 Part 4 §2.13.4.3" |
| commentRangeStart (Comment Anchor Range Start) | "ECMA-376 Part 4 §2.13.4.4" |
| customXml (Ruby Inline-Level Custom XML Element) | §3.1.3.1.1, customXml |
| customXmlDelRangeEnd (Custom XML Markup Deletion End) | "ECMA-376 Part 4 §2.13.5.4" |
| customXmlDelRangeStart (Custom XML Markup Deletion Start) | "ECMA-376 Part 4 §2.13.5.5" |
| customXmlInsRangeEnd (Custom XML Markup Insertion End) | "ECMA-376 Part 4 §2.13.5.6" |
| customXmlInsRangeStart (Custom XML Markup Insertion Start) | "ECMA-376 Part 4 |

| Child Elements | Subclause |
|--|---|
| | §2.13.5.7" |
| customXmlMoveFromRangeEnd (Custom XML Markup Move Source End) | " [ECMA-376] Part 4 §2.13.5.8" |
| customXmlMoveFromRangeStart (Custom XML Markup Move Source Start) | " [ECMA-376] Part 4 §2.13.5.9" |
| customXmlMoveToRangeEnd (Custom XML Markup Move Destination Location End) | " [ECMA-376] Part 4 §2.13.5.10" |
| customXmlMoveToRangeStart (Custom XML Markup Move Destination Location Start) | " [ECMA-376] Part 4 §2.13.5.11" |
| d (Delimiter Function) | " [ECMA-376] Part 4 §7.1.2.24" |
| del (Deleted Run Content) | " [ECMA-376] Part 4 §2.13.5.12" |
| eqArr (Equation-Array Function) | " [ECMA-376] Part 4 §7.1.2.34" |
| f (Fraction Function) | " [ECMA-376] Part 4 §7.1.2.36" |
| fldData (Custom Field Data) | " [ECMA-376] Part 4 §2.16.20" |
| fldSimple (Ruby Simple Field) | §3.1.3.1.2, fldSimple |
| func (Function Apply Function) | " [ECMA-376] Part 4 §7.1.2.39" |
| groupChr (Group-Character Function) | " [ECMA-376] Part 4 §7.1.2.41" |
| hyperlink (Ruby Hyperlink) | §3.1.3.1.3, hyperlink |
| ins (Inserted Run Content) | " [ECMA-376] Part 4 §2.13.5.20" |
| limLow (Lower-Limit Function) | " [ECMA-376] Part 4 §7.1.2.54" |
| limUpp (Upper-Limit Function) | " [ECMA-376] Part 4 §7.1.2.56" |
| m (Matrix Function) | " [ECMA-376] Part 4 §7.1.2.60" |
| moveFrom (Move Source Run Content) | " [ECMA-376] Part 4 §2.13.5.21" |
| moveFromRangeEnd (Move Source Location Container - End) | " [ECMA-376] Part 4 §2.13.5.23" |
| moveFromRangeStart (Move Source Location Container - Start) | " [ECMA-376] Part 4 §2.13.5.24" |

| Child Elements | Subclause |
|---|---|
| moveTo (Move Destination Run Content) | " [ECMA-376] Part 4 §2.13.5.26" |
| moveToRangeEnd (Move Destination Location Container - End) | " [ECMA-376] Part 4 §2.13.5.27" |
| moveToRangeStart (Move Destination Location Container - Start) | " [ECMA-376] Part 4 §2.13.5.28" |
| nary (n-ary Operator Function) | " [ECMA-376] Part 4 §7.1.2.70" |
| oMath (Office Math) | " [ECMA-376] Part 4 §7.1.2.77" |
| oMathPara (Math Paragraph) | " [ECMA-376] Part 4 §7.1.2.78" |
| permEnd (Range Permission End) | " [ECMA-376] Part 4 §2.13.7.1" |
| permStart (Range Permission Start) | " [ECMA-376] Part 4 §2.13.7.2" |
| phant (Phantom Function) | " [ECMA-376] Part 4 §7.1.2.81" |
| proofErr (Proofing Error Anchor) | " [ECMA-376] Part 4 §2.13.8.1" |
| r (Run) | " [ECMA-376] Part 4 §7.1.2.87" |
| r (Text Run) | " [ECMA-376] Part 4 §2.3.2.23" |
| rad (Radical Function) | " [ECMA-376] Part 4 §7.1.2.88" |
| sdt (Ruby Inline-Level Structured Document Tag) | §3.1.3.1.6, sdt |
| sPre (Pre-Sub-Superscript Function) | " [ECMA-376] Part 4 §7.1.2.99" |
| sSub (Subscript Function) | " [ECMA-376] Part 4 §7.1.2.101" |
| sSubSup (Sub-Superscript Function) | " [ECMA-376] Part 4 §7.1.2.103" |
| sSup (Superscript Function) | " [ECMA-376] Part 4 §7.1.2.105" |

| Attributes | Description |
|-----------------------------|---|
| dirty (Field Result) | Specifies that this field has been flagged by an application to indicate that its |

| Attributes | Description |
|---|---|
| Invalidated) | <p>current results are invalid (stale) due to other modifications made to the document, and these contents should be updated before they are displayed if this functionality is supported by the next processing application.</p> <p>[Rationale: This functionality allows applications with limited subsets of the full functionality of ECMA-376 Office Open XML File Formats [ECMA-376] to process Word Open XML documents without needing to understand and update all fields based on the semantics for their field codes.</p> <p>For example, an application can add a new paragraph and flag the table of contents as dirty, without needing to understand anything about how to recalculate that field's content. end rationale]</p> <p>If this attribute is omitted, then its value shall be assumed to be <i>false</i>.</p> <p>[Example: Consider the following WordprocessingML for a simple field:</p> <pre data-bbox="516 569 1105 594"><w:fldSimple w:instr="AUTHOR" w:dirty="true"/></pre> <p>The dirty attribute value of <i>true</i> specifies that the contents of this field are no longer current based on the contents of the document, and should be recalculated whenever an application with this functionality reads the document. end example]</p> <p>The possible values for this attribute are defined by the ST_OnOff simple type (§3.1.3.3.6, ST_OnOff).</p> |
| fldLock (Field Should Not be Recalculated) | <p>Specifies that the parent field shall not have its field result recalculated, even if an application attempts to recalculate the results of all fields in the document or a recalculation is explicitly requested.</p> <p>If this attribute is omitted, then its value shall be assumed to be <i>false</i>.</p> <p>[Example: Consider the following WordprocessingML for a simple field:</p> <pre data-bbox="516 982 1118 1115"><w:fldSimple w:instr="AUTHOR" w:fldLock="true"> <w:r> <w:t>Rex Jaeschke</w:t> </w:r> </w:fldSimple></pre> <p>The fldLock attribute value of <i>true</i> specifies that the contents of this field shall remain <i>Rex Jaeschke</i> regardless of the actual result of the current field codes. end example]</p> <p>The possible values for this attribute are defined by the ST_OnOff simple type (§3.1.3.3.6, ST_OnOff).</p> |
| instr (Field Codes) | <p>Specifies the field codes for the simple field. The possible field codes are defined in "[ECMA-376] Part 4 §2.16.5; Field definitions".</p> <p>[Example: Consider the following WordprocessingML for a simple field:</p> <pre data-bbox="516 1415 1118 1547"><w:fldSimple w:instr="AUTHOR" w:fldLock="true"> <w:r> <w:t>Rex Jaeschke</w:t> </w:r> </w:fldSimple></pre> <p>The instr attribute specifies the field codes for this simple field to be <i>AUTHOR</i>. end example]</p> <p>The possible values for this attribute are defined by the ST_String simple type (§3.1.3.3.8, ST_String).</p> |

The following XML Schema fragment defines the contents of this element:

```
<complexType name="CT_SimpleFieldRuby">
  <sequence>
    <element name="fldData" type="CT_Text" minOccurs="0" maxOccurs="1"/>
    <group ref="EG_RubyContent" minOccurs="0" maxOccurs="unbounded"/>
  </sequence>
  <attribute name="instr" type="ST_String" use="required"/>
  <attribute name="fldLock" type="ST_OnOff"/>
  <attribute name="dirty" type="ST_OnOff"/>
</complexType>
```

3.1.3.1.3 hyperlink (Ruby Hyperlink)

This element specifies the presence of a hyperlink at the current location in the document.

[Example: Consider the following WordprocessingML fragment for a hyperlink:

```
<w:hyperlink r:id="rId10">
  <w:r>
    <w:t>Click here</w:t>
  </w:r>
</w:hyperlink>
```

The **hyperlink** element defines a hyperlink whose display text is *Click here*, and whose target is specified by the relationship with an **Id** attribute value of *rId10*. end example]

| Parent Elements |
|--|
| customXml (§3.1.3.1.1, customXml); fldSimple (§3.1.3.1.2, fldSimple); hyperlink (§3.1.3.1.3, hyperlink); rt (" ECMA-376 Part 4 §2.3.3.23"); rubyBase (" ECMA-376 Part 4 §2.3.3.26"); sdtContent (§3.1.3.1.7, sdtContent) |

| Child Elements | Subclause |
|---|--|
| acc (Accent) | " ECMA-376 Part 4 §7.1.2.1" |
| bar (Bar) | " ECMA-376 Part 4 §7.1.2.7" |
| bookmarkEnd (Bookmark End) | " ECMA-376 Part 4 §2.13.6.1" |
| bookmarkStart (Bookmark Start) | " ECMA-376 Part 4 §2.13.6.2" |
| borderBox (Border-Box Function) | " ECMA-376 Part 4 §7.1.2.11" |
| box (Box Function) | " ECMA-376 Part 4 §7.1.2.13" |
| commentRangeEnd (Comment Anchor Range End) | " ECMA-376 Part 4 |

| Child Elements | Subclause |
|--|---|
| | §2.13.4.3" |
| commentRangeStart (Comment Anchor Range Start) | " [ECMA-376] Part 4 §2.13.4.4" |
| customXml (Ruby Inline-Level Custom XML Element) | §3.1.3.1.1, customXml |
| customXmlDelRangeEnd (Custom XML Markup Deletion End) | " [ECMA-376] Part 4 §2.13.5.4" |
| customXmlDelRangeStart (Custom XML Markup Deletion Start) | " [ECMA-376] Part 4 §2.13.5.5" |
| customXmlInsRangeEnd (Custom XML Markup Insertion End) | " [ECMA-376] Part 4 §2.13.5.6" |
| customXmlInsRangeStart (Custom XML Markup Insertion Start) | " [ECMA-376] Part 4 §2.13.5.7" |
| customXmlMoveFromRangeEnd (Custom XML Markup Move Source End) | " [ECMA-376] Part 4 §2.13.5.8" |
| customXmlMoveFromRangeStart (Custom XML Markup Move Source Start) | " [ECMA-376] Part 4 §2.13.5.9" |
| customXmlMoveToRangeEnd (Custom XML Markup Move Destination Location End) | " [ECMA-376] Part 4 §2.13.5.10" |
| customXmlMoveToRangeStart (Custom XML Markup Move Destination Location Start) | " [ECMA-376] Part 4 §2.13.5.11" |
| d (Delimiter Function) | " [ECMA-376] Part 4 §7.1.2.24" |
| del (Deleted Run Content) | " [ECMA-376] Part 4 §2.13.5.12" |
| eqArr (Equation-Array Function) | " [ECMA-376] Part 4 §7.1.2.34" |
| f (Fraction Function) | " [ECMA-376] Part 4 §7.1.2.36" |
| fldSimple (Ruby Simple Field) | §3.1.3.1.2, fldSimple |
| func (Function Apply Function) | " [ECMA-376] Part 4 §7.1.2.39" |
| groupChr (Group-Character Function) | " [ECMA-376] Part 4 §7.1.2.41" |
| hyperlink (Ruby Hyperlink) | §3.1.3.1.3, hyperlink |
| ins (Inserted Run Content) | " [ECMA-376] Part 4 §2.13.5.20" |
| limLow (Lower-Limit Function) | " [ECMA-376] Part 4 §7.1.2.54" |

| Child Elements | Subclause |
|---|---|
| limUpp (Upper-Limit Function) | " [ECMA-376] Part 4 §7.1.2.56" |
| m (Matrix Function) | " [ECMA-376] Part 4 §7.1.2.60" |
| moveFrom (Move Source Run Content) | " [ECMA-376] Part 4 §2.13.5.21" |
| moveFromRangeEnd (Move Source Location Container - End) | " [ECMA-376] Part 4 §2.13.5.23" |
| moveFromRangeStart (Move Source Location Container - Start) | " [ECMA-376] Part 4 §2.13.5.24" |
| moveTo (Move Destination Run Content) | " [ECMA-376] Part 4 §2.13.5.26" |
| moveToRangeEnd (Move Destination Location Container - End) | " [ECMA-376] Part 4 §2.13.5.27" |
| moveToRangeStart (Move Destination Location Container - Start) | " [ECMA-376] Part 4 §2.13.5.28" |
| nary (n-ary Operator Function) | " [ECMA-376] Part 4 §7.1.2.70" |
| oMath (Office Math) | " [ECMA-376] Part 4 §7.1.2.77" |
| oMathPara (Math Paragraph) | " [ECMA-376] Part 4 §7.1.2.78" |
| permEnd (Range Permission End) | " [ECMA-376] Part 4 §2.13.7.1" |
| permStart (Range Permission Start) | " [ECMA-376] Part 4 §2.13.7.2" |
| phant (Phantom Function) | " [ECMA-376] Part 4 §7.1.2.81" |
| proofErr (Proofing Error Anchor) | " [ECMA-376] Part 4 §2.13.8.1" |
| r (Run) | " [ECMA-376] Part 4 §7.1.2.87" |
| r (Text Run) | " [ECMA-376] Part 4 §2.3.2.23" |
| rad (Radical Function) | " [ECMA-376] Part 4 §7.1.2.88" |
| sdt (Ruby Inline-Level Structured Document Tag) | §3.1.3.1.6, sdt |
| sPre (Pre-Sub-Superscript Function) | " [ECMA-376] Part 4 §7.1.2.99" |

| Child Elements | Subclause |
|---|--------------------------------|
| sSub (Subscript Function) | "[ECMA-376] Part 4 §7.1.2.101" |
| sSubSup (Sub-Superscript Function) | "[ECMA-376] Part 4 §7.1.2.103" |
| sSup (Superscript Function) | "[ECMA-376] Part 4 §7.1.2.105" |

| Attributes | Description |
|--|---|
| anchor (Hyperlink Anchor) | <p>Specifies the name of a bookmark in the current document which shall be the target of this hyperlink.</p> <p>If this attribute is omitted, then the default behavior shall be to navigate to the start of the document. If a hyperlink target is also specified using the r:id attribute, then this attribute shall be ignored. If no bookmark exists in the current document with the given bookmark name, then the default behavior shall be to navigate to the start of the document.</p> <p>[Example: Consider the following WordprocessingML fragment for a hyperlink:</p> <pre><w:hyperlink w:anchor="chapter3"> <w:r> <w:t>Go to Chapter Three</w:t> </w:r> </w:hyperlink></pre> <p>The anchor attribute specifies that the target of the current hyperlink shall be the text contained within the bookmark <i>chapter3</i> within the document. end example]</p> <p>The possible values for this attribute are defined by the ST_String255 simple type (§3.1.3.3.9, ST String255).</p> |
| docLocation (Location in Target Document) | <p>Specifies a location in the target of the hyperlink that has no bookmarks.</p> <p>If this attribute is omitted, then no location shall be associated with the parent hyperlink. If the anchor attribute is also specified, then this attribute may be ignored when the hyperlink is invoked.</p> <p>[Example: Consider the following WordprocessingML fragment for a hyperlink:</p> <pre><w:hyperlink r:id="rId9" w:docLocation="table"> <w:r> <w:t>Click Here</w:t> </w:r> </w:hyperlink></pre> <p>The docLocation attribute specifies that the target of the current hyperlink shall be a region targeted by the string <i>table</i> within the target document. end example]</p> <p>The possible values for this attribute are defined by the</p> |

| Attributes | Description |
|---|--|
| | ST_String255 simple type (§3.1.3.3.9, ST_String255). |
| history (Add to Viewed Hyperlinks) | <p>Specifies whether the target of the parent hyperlink (as specified via the r:id attribute) shall be added to a list of viewed hyperlinks when it is invoked.</p> <p>If this attribute is omitted, then its value shall be assumed to be <i>false</i>.</p> <p>[Example: Consider the following WordprocessingML fragment for a hyperlink:</p> <pre data-bbox="724 474 1260 604"><w:hyperlink r:id="rId9" w:history="true"> <w:r> <w:t>http://example.com</w:t> </w:r> </w:hyperlink></pre> <p>The history attribute value of <i>true</i> specifies that the target of the current hyperlink shall be added to a list of visited hyperlinks when invoked within the document. end example]</p> <p>The possible values for this attribute are defined by the ST_OnOff simple type (§3.1.3.3.6, ST_OnOff).</p> |
| id (Hyperlink Target) Namespace: .../officeDocument/2006/relationships | <p>Specifies the ID of the relationship whose target shall be used as the target for this hyperlink.</p> <p>If the id attribute is omitted, then there shall be no external target for the current hyperlink, although a location in the current document may still be specified as a target via the anchor attribute. If the id attribute exists, it shall supersede the value in the anchor attribute.</p> <p>[Example: Consider the following WordprocessingML fragment for a hyperlink:</p> <pre data-bbox="724 1073 1146 1203"><w:hyperlink r:id="rId9"> <w:r> <w:t>http://example.com</w:t> </w:r> </w:hyperlink></pre> <p>An id attribute value of <i>rId9</i> specifies that the relationship in the associated relationship part item with a corresponding Id attribute value shall be navigated to when this hyperlink is invoked. For example, if the following XML is present in the associated relationship part item:</p> <pre data-bbox="724 1388 1243 1486"><Relationships xmlns="..."> <Relationship Id="rId9" Mode="External" Target=http://www.contoso.com /> </Relationships></pre> <p>The target of this hyperlink would therefore be the target of relationship <i>rId9</i> - in this case, <i>http://www.contoso.com</i>. end example]</p> <p>The possible values for this attribute are defined by the ST_RelationshipId simple type ("ECMA-376 Part 4 §7.8.2.1").</p> |
| tgtFrame (Hyperlink Target Frame) | <p>Specifies a frame within the parent HTML frameset for the target of the parent hyperlink when one exists. Values shall be handled</p> |

| Attributes | Description |
|---|--|
| | <p>as follows:</p> <p>_top Open hyperlink target in the full region of the current window.</p> <p>_self Open hyperlink target in the same frame as the hyperlink appears.</p> <p>_parent Open hyperlink target in the parent of the current frame, or the current frame if this frame has no parent.</p> <p>_blank Open hyperlink target in a new window.</p> <p>all other values Open hyperlink target in the frame with the specified name. If no frame exists with this name, open in the current frame. If this string does not begin with an alphabetic character, it shall be ignored.</p> <p>If this attribute is omitted, then no target frame information shall be associated with the parent hyperlink. If the current document is not part of a frameset, then this information may be ignored.</p> <p>[Example: Consider the following WordprocessingML fragment for a hyperlink:</p> <pre data-bbox="724 898 1273 1024"> <w:hyperlink r:id="rId9" w:tgtFrame="_top"> <w:r> <w:t>http://example.com</w:t> </w:r> </w:hyperlink> </pre> <p>The tgtFrame attribute value of _top specifies that the target of this hyperlink shall be displayed in the full extents of the current window. end example]</p> <p>The possible values for this attribute are defined by the ST_String255 simple type (§3.1.3.3.9, ST_String255).</p> |
| <p>tooltip (Associated String)</p> | <p>Specifies a string that may be surfaced in a user interface as associated with the parent hyperlink.</p> <p>If this attribute is omitted, then no associated string shall be linked to the parent hyperlink in the document.</p> <p>[Example: Consider the following WordprocessingML fragment for a hyperlink:</p> <pre data-bbox="724 1419 1351 1545"> <w:hyperlink r:id="rId9" w:tooltip="Click here!"> <w:r> <w:t>http://example.com</w:t> </w:r> </w:hyperlink> </pre> <p>The value of this attribute specifies that the parent hyperlink has the associated string of <i>Click here!</i>, which may be used as desired. end example]</p> <p>The possible values for this attribute are defined by the ST_String260 simple type (§3.1.3.3.10, ST_String260).</p> |

The following XML Schema fragment defines the contents of this element:

```
<complexType name="CT_HyperlinkRuby">
  <group ref="EG_RubyContent" minOccurs="0" maxOccurs="unbounded"/>
  <attribute name="tgtFrame" type="ST_String255" use="optional"/>
  <attribute name="tooltip" type="ST_String260" use="optional"/>
  <attribute name="docLocation" type="ST_String255" use="optional"/>
  <attribute name="history" type="ST_OnOff" use="optional"/>
  <attribute name="anchor" type="ST_String255" use="optional"/>
  <attribute ref="r:id"/>
</complexType>
```

3.1.3.1.4 moveFrom (Move Source Math Control Character)

This element specifies that the Office Open XML Math control character contained within it shall be treated as content that has been moved away from this location and tracked as a revision.

The following restrictions shall be applied to this content:

If this element occurs outside of a valid move source container (§[\[ECMA-376\]](#) Part 4 §2.13.5.24; moveFromRangeStart"; §[\[ECMA-376\]](#) Part 4 §2.13.5.23; moveFromRangeEnd") for which a matching move destination container (§[\[ECMA-376\]](#) Part 4 §2.13.5.28; moveToRangeStart"; §[\[ECMA-376\]](#) Part 4 §2.13.5.27; moveToRangeEnd") exists in the document, then the math control character shall be treated as deleted, rather than moved.

Word ignores this element.

| Parent Elements |
|---|
| ctrlPr (" [ECMA-376] Part 4 §7.1.2.23") |

| Child Elements | Subclause |
|---------------------------------------|---|
| del (Deleted Math Control Character) | " [ECMA-376] Part 4 §2.13.5.15" |
| ins (Inserted Math Control Character) | " [ECMA-376] Part 4 §2.13.5.17" |
| rPr (Run Properties) | " [ECMA-376] Part 4 §2.3.2.25" |

| Attributes | Description |
|--------------------------------------|---|
| author (Annotation Author) | Specifies the author for an annotation within a WordprocessingML document. [Example: Consider a comment represented using the following WordprocessingML fragment: <pre><w:... w:id="1" w:author="Example Author"> ... </w:...></pre> |

| Attributes | Description |
|--|--|
| | <p>The author attribute specifies that the author of the current annotation is <i>Example Author</i>, which may be used as desired. end example]</p> <p>The possible values for this attribute are defined by the ST_String255 simple type (§3.1.3.3.9, ST_String255).</p> |
| <p>date (Annotation Date)</p> | <p>Specifies the date information for an annotation within a WordprocessingML document.</p> <p>If this attribute is omitted, then no date information shall be associated with the parent annotation type.</p> <p>[Example: Consider a comment represented using the following WordprocessingML fragment:</p> <pre data-bbox="505 537 1052 615"> <w:... w:id="1" w:date="2006-01-01T10:00:00"> ... </w:...> </pre> <p>The date attribute specifies that the date of the current annotation is January 1st 2006 at 10:00 AM, which may be used as desired. end example]</p> <p>The possible values for this attribute are defined by the ST_DateTime simple type (§3.1.3.3.2, ST_DateTime).</p> |
| <p>id (Annotation Identifier)</p> | <p>Specifies a unique identifier for an annotation within a WordprocessingML document. The restrictions on the id attribute, if any, are defined by the parent XML element.</p> <p>If this attribute is omitted, then the document is non-conformant.</p> <p>[Example: Consider an annotation represented using the following WordprocessingML fragment:</p> <pre data-bbox="505 951 724 1029"> <w:... w:id="1" ... > ... </w:...> </pre> <p>The id attribute specifies that the ID of the current annotation is <i>1</i>. This value is used to uniquely identify this annotation within the document content. end example]</p> <p>The possible values for this attribute are defined by the ST_MarkupId simple type (§3.1.3.3.3, ST_MarkupId).</p> |

The following XML Schema fragment defines the contents of this element:

```

<complexType name="CT_MathCtrlMove">
  <complexContent>
    <extension base="CT_TrackChange">
      <choice minOccurs="0">
        <group ref="EG_RPr"/>
        <group ref="EG_MathCtrlIns"/>
        <group ref="EG_MathCtrlDel"/>
      </choice>
    </extension>
  </complexContent>
</complexType>

```

3.1.3.1.5 moveTo (Move Destination Math Control Character)

This element specifies that the Office Open XML Math control character contained within it shall be treated as content that has been moved to this location and tracked as a revision.

The following restrictions shall be applied to this content:

If this element occurs outside of a valid move destination container (§"ECMA-376] Part 4 §2.13.5.28; moveToRangeStart"; §"ECMA-376] Part 4 §2.13.5.27; moveToRangeEnd") for which a matching move source container (§"ECMA-376] Part 4 §2.13.5.24; moveFromRangeStart"; §"ECMA-376] Part 4 §2.13.5.23; moveFromRangeEnd") exists in the document, then content in this region shall be treated as inserted, rather than moved.

Word ignores this element.

| Parent Elements |
|--|
| ctrlPr ("ECMA-376] Part 4 §7.1.2.23") |

| Child Elements | Subclause |
|--|-------------------------------|
| del (Deleted Math Control Character) | "ECMA-376] Part 4 §2.13.5.15" |
| ins (Inserted Math Control Character) | "ECMA-376] Part 4 §2.13.5.17" |
| rPr (Run Properties) | "ECMA-376] Part 4 §2.3.2.25" |

| Attributes | Description |
|--------------------------------------|--|
| author (Annotation Author) | <p>Specifies the author for an annotation within a WordprocessingML document. [Example: Consider a comment represented using the following WordprocessingML fragment:</p> <pre><w:... w:id="1" w:author="Example Author"> ... </w:...></pre> <p>The author attribute specifies that the author of the current annotation is <i>Example Author</i>, which may be used as desired. end example]</p> <p>The possible values for this attribute are defined by the ST_String255 simple type (§3.1.3.3.9, ST_String255).</p> |
| date (Annotation Date) | <p>Specifies the date information for an annotation within a WordprocessingML document. If this attribute is omitted, then no date information shall be associated with the parent annotation type. [Example: Consider a comment represented using the following WordprocessingML fragment:</p> <pre><w:... w:id="1" w:date="2006-01-01T10:00:00"> ... </w:...></pre> <p>The date attribute specifies that the date of the current annotation is January 1st 2006 at 10:00 AM, which may be used as desired. end example]</p> |

| Attributes | Description |
|-----------------------------------|--|
| | The possible values for this attribute are defined by the ST_DateTime simple type (§3.1.3.3.2, ST_DateTime). |
| id (Annotation Identifier) | <p>Specifies a unique identifier for an annotation within a WordprocessingML document. The restrictions on the id attribute, if any, are defined by the parent XML element. If this attribute is omitted, then the document is non-conformant.</p> <p>[Example: Consider an annotation represented using the following WordprocessingML fragment:</p> <pre data-bbox="505 449 724 522" style="margin-left: 40px;"> <w:... w:id="1" ... > ... </w:...> </pre> <p>The id attribute specifies that the ID of the current annotation is 1. This value is used to uniquely identify this annotation within the document content. end example]</p> <p>The possible values for this attribute are defined by the ST_MarkupId simple type (§3.1.3.3.3, ST_MarkupId).</p> |

The following XML Schema fragment defines the contents of this element:

```

<complexType name="CT_MathCtrlMove">
  <complexContent>
    <extension base="CT_TrackChange">
      <choice minOccurs="0">
        <group ref="EG_RPr"/>
        <group ref="EG_MathCtrlIns"/>
        <group ref="EG_MathCtrlDel"/>
      </choice>
    </extension>
  </complexContent>
</complexType>

```

3.1.3.1.6 sdt (Ruby Inline-Level Structured Document Tag)

This element specifies the presence of a structured document tag around one or more inline-level structures (runs, DrawingML objects, fields, and so on) in the current paragraph. The two child elements of this element shall be used to specify the properties and content of the current structured document tag via the **sdtPr** and **sdtContent** elements, respectively.

[Example: Consider a structured document tag with the friendly name *firstName* that shall be located around two runs in a WordprocessingML document. This requirement would be specified as follows in the WordprocessingML:

```

<w:p>
  <w:sdt>
    <w:sdtPr>
      <w:alias w:val="firstName"/>
    </w:sdtPr>
    <w:sdtContent>
      <w:r>
        ...
      </w:r>
      <w:r>
        ...
      </w:r>
    </w:sdtContent>
  </w:sdt>
</w:p>

```

```

    </w:r>
  </w:sdtContent>
</w:sdt>
...
</w:tr>

```

The **sdt** element specifies the structured document tag, the child **sdtPr** element contains the friendly name property set to *firstName*, and the **sdtContent** element contains two runs (it is an inline-level structured document tag). end example]

| Parent Elements |
|--|
| customXml (§3.1.3.1.1, customXml); fldSimple (§3.1.3.1.2, fldSimple); hyperlink (§3.1.3.1.3, hyperlink); rt ("[ECMA-376] Part 4 §2.3.3.23"); rubyBase ("[ECMA-376] Part 4 §2.3.3.26"); sdtContent (§3.1.3.1.7, sdtContent) |

| Child Elements | Subclause |
|--|--------------------------------|
| bookmarkEnd (Bookmark End) | "[ECMA-376] Part 4 §2.13.6.1" |
| bookmarkStart (Bookmark Start) | "[ECMA-376] Part 4 §2.13.6.2" |
| commentRangeEnd (Comment Anchor Range End) | "[ECMA-376] Part 4 §2.13.4.3" |
| commentRangeStart (Comment Anchor Range Start) | "[ECMA-376] Part 4 §2.13.4.4" |
| customXmlDelRangeEnd (Custom XML Markup Deletion End) | "[ECMA-376] Part 4 §2.13.5.4" |
| customXmlDelRangeStart (Custom XML Markup Deletion Start) | "[ECMA-376] Part 4 §2.13.5.5" |
| customXmlInsRangeEnd (Custom XML Markup Insertion End) | "[ECMA-376] Part 4 §2.13.5.6" |
| customXmlInsRangeStart (Custom XML Markup Insertion Start) | "[ECMA-376] Part 4 §2.13.5.7" |
| customXmlMoveFromRangeEnd (Custom XML Markup Move Source End) | "[ECMA-376] Part 4 §2.13.5.8" |
| customXmlMoveFromRangeStart (Custom XML Markup Move Source Start) | "[ECMA-376] Part 4 §2.13.5.9" |
| customXmlMoveToRangeEnd (Custom XML Markup Move Destination Location End) | "[ECMA-376] Part 4 §2.13.5.10" |
| customXmlMoveToRangeStart (Custom XML Markup Move Destination Location Start) | "[ECMA-376] Part 4 §2.13.5.11" |
| moveFromRangeEnd (Move Source Location Container - End) | "[ECMA-376] Part 4 §2.13.5.23" |

| Child Elements | Subclause |
|---|---|
| moveFromRangeStart (Move Source Location Container - Start) | " [ECMA-376] Part 4 §2.13.5.24" |
| moveToRangeEnd (Move Destination Location Container - End) | " [ECMA-376] Part 4 §2.13.5.27" |
| moveToRangeStart (Move Destination Location Container - Start) | " [ECMA-376] Part 4 §2.13.5.28" |
| sdtContent (Ruby Inline-Level Structured Document Tag Content) | §3.1.3.1.7, sdtContent |
| sdtEndPr (Structured Document Tag End Character Properties) | " [ECMA-376] Part 4 §2.5.2.36" |
| sdtPr (Structured Document Tag Properties) | " [ECMA-376] Part 4 §2.5.2.37" |

The following XML Schema fragment defines the contents of this element:

```
<complexType name="CT_SdtRunRuby">
  <sequence>
    <element name="sdtPr" type="CT_SdtPr" minOccurs="0" maxOccurs="1"/>
    <element name="sdtEndPr" type="CT_SdtEndPr" minOccurs="0" maxOccurs="1"/>
    <element name="sdtContent" type="CT_SdtContentRunRuby" minOccurs="0" maxOccurs="1"/>
    <group ref="EG_RangeMarkupElements" minOccurs="0" maxOccurs="unbounded"/>
  </sequence>
</complexType>
```

3.1.3.1.7 sdtContent (Ruby Inline-Level Structured Document Tag Content)

This element specifies the last known contents of a structured document tag around one or more inline-level structures (runs, DrawingML objects, fields, and so on). This element's contents shall be treated as a cache of the contents to be displayed in the structured document tag for the following reasons:

If the structured document tag specifies an XML mapping via the **dataBinding** element (§"[\[ECMA-376\]](#) Part 4 §2.5.2.6; dataBinding"), changes to the custom XML data part shall be reflected in the structured document tag as needed

If the contents of the structured document tag are placeholder text via the **showingPlcHdr** element (§"[\[ECMA-376\]](#) Part 4 §2.5.2.38; showingPlcHdr"), then this content may be updated with the placeholder text stored in the Glossary Document part

[Example: Consider a structured document tag with the friendly name *firstName* that shall be located around two runs in a WordprocessingML document. This requirement would be specified as follows in the WordprocessingML:

```
<w:p>
  <w:sdt>
    <w:sdtPr>
      <w:alias w:val="firstName"/>
    </w:sdtPr>
  </w:p>
```

```

<w:sdtContent>
  <w:r>
    ...
  </w:r>
  <w:r>
    ...
  </w:r>
</w:sdtContent>
</w:sdt>
...
</w:p>

```

The **sdtContent** element contains two adjacent runs (it is an inline-level structured document tag content container). end example]

| Parent Elements |
|--|
| sdt (§3.1.3.1.6, sdt) |

| Child Elements | Subclause |
|--|--|
| acc (Accent) | " [ECMA-376] Part 4 §7.1.2.1" |
| bar (Bar) | " [ECMA-376] Part 4 §7.1.2.7" |
| bookmarkEnd (Bookmark End) | " [ECMA-376] Part 4 §2.13.6.1" |
| bookmarkStart (Bookmark Start) | " [ECMA-376] Part 4 §2.13.6.2" |
| borderBox (Border-Box Function) | " [ECMA-376] Part 4 §7.1.2.11" |
| box (Box Function) | " [ECMA-376] Part 4 §7.1.2.13" |
| commentRangeEnd (Comment Anchor Range End) | " [ECMA-376] Part 4 §2.13.4.3" |
| commentRangeStart (Comment Anchor Range Start) | " [ECMA-376] Part 4 §2.13.4.4" |
| customXml (Ruby Inline-Level Custom XML Element) | §3.1.3.1.1, customXml |
| customXmlDelRangeEnd (Custom XML Markup Deletion End) | " [ECMA-376] Part 4 §2.13.5.4" |
| customXmlDelRangeStart (Custom XML Markup Deletion Start) | " [ECMA-376] Part 4 §2.13.5.5" |
| customXmlInsRangeEnd (Custom XML Markup Insertion End) | " [ECMA-376] Part 4 §2.13.5.6" |

| Child Elements | Subclause |
|--|---|
| customXmlInsRangeStart (Custom XML Markup Insertion Start) | " [ECMA-376] Part 4 §2.13.5.7" |
| customXmlMoveFromRangeEnd (Custom XML Markup Move Source End) | " [ECMA-376] Part 4 §2.13.5.8" |
| customXmlMoveFromRangeStart (Custom XML Markup Move Source Start) | " [ECMA-376] Part 4 §2.13.5.9" |
| customXmlMoveToRangeEnd (Custom XML Markup Move Destination Location End) | " [ECMA-376] Part 4 §2.13.5.10" |
| customXmlMoveToRangeStart (Custom XML Markup Move Destination Location Start) | " [ECMA-376] Part 4 §2.13.5.11" |
| d (Delimiter Function) | " [ECMA-376] Part 4 §7.1.2.24" |
| del (Deleted Run Content) | " [ECMA-376] Part 4 §2.13.5.12" |
| eqArr (Equation-Array Function) | " [ECMA-376] Part 4 §7.1.2.34" |
| f (Fraction Function) | " [ECMA-376] Part 4 §7.1.2.36" |
| fldSimple (Ruby Simple Field) | §3.1.3.1.2, fldSimple |
| func (Function Apply Function) | " [ECMA-376] Part 4 §7.1.2.39" |
| groupChr (Group-Character Function) | " [ECMA-376] Part 4 §7.1.2.41" |
| hyperlink (Ruby Hyperlink) | §3.1.3.1.3, hyperlink |
| ins (Inserted Run Content) | " [ECMA-376] Part 4 §2.13.5.20" |
| limLow (Lower-Limit Function) | " [ECMA-376] Part 4 §7.1.2.54" |
| limUpp (Upper-Limit Function) | " [ECMA-376] Part 4 §7.1.2.56" |
| m (Matrix Function) | " [ECMA-376] Part 4 §7.1.2.60" |
| moveFrom (Move Source Run Content) | " [ECMA-376] Part 4 §2.13.5.21" |
| moveFromRangeEnd (Move Source Location Container - End) | " [ECMA-376] Part 4 §2.13.5.23" |
| moveFromRangeStart (Move Source Location Container - Start) | " [ECMA-376] Part 4 §2.13.5.24" |
| moveTo (Move Destination Run Content) | " [ECMA-376] Part 4 |

| Child Elements | Subclause |
|---|--------------------------------|
| | §2.13.5.26" |
| moveToRangeEnd (Move Destination Location Container - End) | "[ECMA-376] Part 4 §2.13.5.27" |
| moveToRangeStart (Move Destination Location Container - Start) | "[ECMA-376] Part 4 §2.13.5.28" |
| nary (n-ary Operator Function) | "[ECMA-376] Part 4 §7.1.2.70" |
| oMath (Office Math) | "[ECMA-376] Part 4 §7.1.2.77" |
| oMathPara (Math Paragraph) | "[ECMA-376] Part 4 §7.1.2.78" |
| permEnd (Range Permission End) | "[ECMA-376] Part 4 §2.13.7.1" |
| permStart (Range Permission Start) | "[ECMA-376] Part 4 §2.13.7.2" |
| phant (Phantom Function) | "[ECMA-376] Part 4 §7.1.2.81" |
| proofErr (Proofing Error Anchor) | "[ECMA-376] Part 4 §2.13.8.1" |
| r (Run) | "[ECMA-376] Part 4 §7.1.2.87" |
| r (Text Run) | "[ECMA-376] Part 4 §2.3.2.23" |
| rad (Radical Function) | "[ECMA-376] Part 4 §7.1.2.88" |
| sdt (Ruby Inline-Level Structured Document Tag) | §3.1.3.1.6, sdt |
| sPre (Pre-Sub-Superscript Function) | "[ECMA-376] Part 4 §7.1.2.99" |
| sSub (Subscript Function) | "[ECMA-376] Part 4 §7.1.2.101" |
| sSubSup (Sub-Superscript Function) | "[ECMA-376] Part 4 §7.1.2.103" |
| sSup (Superscript Function) | "[ECMA-376] Part 4 §7.1.2.105" |

The following XML Schema fragment defines the contents of this element:

```
<complexType name="CT_SdtContentRunRuby">
  <group ref="EG_RubyContent" minOccurs="0" maxOccurs="unbounded"/>
</complexType>
```

3.1.3.2 Additional Fields

3.1.3.2.1 DDE

Syntax:

DDE field-argument-1 field-argument-2 [field-argument-3] [switches]

field-argument-1:

field-argument

field-argument-2:

field-argument

field-argument-3:

field-argument

Description: For information copied from another application, this field links that information to its original source file using DDE. The application name shall be specified by field-argument-1; this application shall be running. The name and location of the source file is specified by field-argument-2. The portion of the source file that is being linked is specified by field-argument-3. [Note: This field is supported for legacy reasons, and it is recommended that LINK ("ECMA-376] Part 4 §2.16.5.39; LINK") be used instead. end note]

[Example: If the source file is a SpreadsheetML document, the reference might be to a cell reference or a named range. For a WordprocessingML document, it might be a bookmark. end example]

Field Value: The DDE object representation of the linked file, or the contents of the file itself depending on the switches used.

Switches: Zero or more of the following field-specific-switches.

| Field specific switches | |
|-------------------------|--|
| \a | Causes this field to be updated automatically. Word does not support this switch. |
| \b | Requests the linked object as a bitmap. This switch shall not be used in conjunction with any field-specific switches other than \a. |
| \d | Specifies that the graphic data shall not be stored with the document, thus reducing the file size. This switch shall not be used in conjunction with any field-specific switches other than \a. Word does not support this switch. |
| \h | Requests the linked object as HTML-formatted text. This switch shall not be used in conjunction with any field-specific switches other than \a. |
| \p | Requests the linked object as a picture. This switch shall not be used in conjunction with any field-specific switches other than \a. |
| \r | Requests the linked object in rich-text format (RTF). This switch shall not be used in conjunction with any field-specific switches other than \a. |
| \t | Requests the linked object in text-only format. This switch shall not be used in conjunction with any field-specific switches other than \a. |

| Field specific switches | |
|-------------------------|--|
| \u | Requests the linked object as Unicode text. This switch shall not be used in conjunction with any field-specific switches other than \a. Word does not support this switch. |

[Example: The following example inserts a range of cells from a SpreadsheetML worksheet.

```
{ DDE excel "C:\\My Documents\\Profits.xls"
  "Sheet1!R1C1:R4C4" \a \p }
```

end example]

3.1.3.2.2 DDEAUTO

Syntax:

DDEAUTO field-argument-1 field-argument-2 [field-argument-3] [switches]

field-argument-1:

field-argument

field-argument-2:

field-argument

field-argument-3:

field-argument

Description: For information copied from another application, this field links that information to its original source file using DDE and is updated automatically. The application name shall be specified in field-argument-1; this application must be running. The name and location of the source file is specified by field-argument-2. The portion of the source file that is being linked is specified by field-argument-3. [Note: This field is supported for legacy reasons, and it is recommended that `LINK` ("[ECMA-376](#) Part 4 §2.16.5.39; LINK") be used instead. end note] [Example: If the source file is a SpreadsheetML document, the reference might be to a cell reference or a named range. For a WordprocessingML document, it might be a bookmark. end example]

Field Value: The DDE object representation of the linked file or the contents of the file itself, depending on the switches used.

Switches: Zero or more of the following field-specific-switches.

| Field specific switches | |
|-------------------------|--|
| \b | Requests the linked object as a bitmap. This switch shall not be used in conjunction with any field-specific switches. |
| \d | Specifies that the graphic data shall not be stored with the document, thus reducing the file size. This switch shall not be used in conjunction with any field-specific switches. Word does not support this switch. |
| \h | Requests the linked object as HTML-formatted text. This switch shall not be used in conjunction with |

| Field specific switches | |
|-------------------------|--|
| | any field-specific switches. |
| \p | Requests the linked object as a picture. This switch shall not be used in conjunction with any field-specific switches. |
| \r | Requests the linked object in rich-text format (RTF). This switch shall not be used in conjunction with any field-specific switches. |
| \t | Requests the linked object in text-only format. This switch shall not be used in conjunction with any field-specific switches. |
| \u | Requests the linked object as Unicode text. This switch shall not be used in conjunction with any field-specific switches. Word does not support this switch. |

[Example: The following example inserts a range of cells from a SpreadsheetML worksheet.

```
{ DDEAUTO excel "C:\\My Documents\\Profits.xls"
  "Sheet1!R1C1:R4C4" \p }
```

end example]

3.1.3.2.3 GLOSSARY

Syntax:

GLOSSARY field-argument

Description: Inserts the glossary entry whose name is specified by text in field-argument.

Regarding XML generation, the field result is the value of the glossary. [Note: This can be arbitrarily complex and involve VML. end note]

Field Value: The specified glossary entry.

Switches: None.

[Example: Assume the following entries are defined with values of current page number, salutation, and a notice:

```
GLOSSARY "- PAGE -"
GLOSSARY "Yours truly,"
GLOSSARY Confidential
```

When evaluated, they might produce the following results:

```
- 13 -
Yours truly,
CONFIDENTIAL
```

end example]

3.1.3.2.4 IMPORT

Syntax:

IMPORT field-argument [switches]

Description: Retrieves the picture contained in the document named by field-argument.

Field Value: The specified picture.

Switches: Zero or more of the following field-specific-switches.

| Field specific switches | |
|-------------------------|--|
| \c field-argument | If text in this switch's field-argument identifies the graphics filter to be used. |
| \d | Reduce the file size by not storing graphics data with the document. |

[Example:

```
IMPORT "G:\\Photos\\Ellen in Oslo.jpg"
```

end example]

3.1.3.2.5 INCLUDE

Syntax:

INCLUDE field-argument-1 [field-argument-2] [switches]

field-argument-1:

field-argument

field-argument-2:

field-argument

Description: Inserts all or part of the text and graphics contained in the document named by field-argument-1. If the document is a WordprocessingML document, the portion marked by the optional bookmark field-argument-2 is inserted. If no such bookmark is specified here, the whole document is inserted.

Field Value: The specified text and graphics.

Switches: Zero or more of the following field-specific-switches.

| Field specific switches | |
|-------------------------|---|
| \! | Prevents this field from being updated unless all fields in the inserted text are first updated in their original document. |
| \c field-argument | Specifies that the file specified by field-argument-2 shall be processed by a document filter whose name matches the corresponding field-argument value. Possible field-argument values are implementation-defined. |

[Example: The following field inserts the portion of the WordprocessingML document referred to by the bookmark Summary:

```
INCLUDE "C:\\Winword\\Port Development RFP" Summary
```

end example]

3.1.3.2.6 SHAPE

Syntax:

SHAPE field-argument

Description: Retrieves the text specified by text in field-argument. The text may specify a character whose code point value is specified in decimal or hexadecimal. Three digits shall be used to specify a character using decimal numbers. Up to four digits shall be used to specify a character using hexadecimal (leading 0x or 0X).

Word does not allow insertion of the code point 13.

[Note: This field is supported for legacy reasons, and it is recommended that QUOTE ("[ECMA-376](#) Part 4 §2.16.5.56; QUOTE") be used instead. end note]

Field Value: The specified text or character.

Switches: Zero or more of the date-and-time-formatting-switch, general-formatting-switch, or numeric-formatting-switches, depending on the type of field-argument.

[Example: When the current month is January and the following field is updated:

```
Last month was SHAPE IF DATE \@ "M" = 1 "12" "=" DATE \@ "M" - 1"/1/2000 \@ "MMMM".
```

the result is:

```
Last month was December end example]
```

[Example: When the following field is updated:

```
SHAPE 063 " is code point 63."
```

the result is:

```
? is code point 63. end example]
```

3.1.3.3 Simple Types

This is the complete list of simple types in the <http://schemas.openxmlformats.org/wordprocessingml/2006/main> namespace.

3.1.3.3.1 ST_CustomXmlURI (URI for Custom XML)

This simple type specifies the URI of the current custom XML element. Word fails to load the document if the URI is not declared in any of the attached schemas via the element **attachedSchema** ("[\[ECMA-376\]](#) Part 4 §2.15.1.5; attachedSchema").

This simple type's contents are a restriction of the XML Schema string datatype.

| Referenced By |
|--|
| customXml@uri (§ 3.1.3.1.1, customXml) |

The following XML Schema fragment defines the contents of this simple type:

```
<simpleType name="ST_CustomXmlURI">  
  <restriction base="xsd:string"/>  
</simpleType>
```

3.1.3.3.2 ST_DateTime (Standard Date and Time Storage Format)

This simple type specifies that its contents will contain a date in the standard XML Schema `xsd:dateTime` format, whose contents are interpreted based on the context of the parent XML element.

[Example: Consider the following WordprocessingML fragment:

```
<w:date w:realDate="01-01-2006T12:00:00Z">  
  ...  
</w:date>
```

In this case, the date in the **realDate** attribute is the full date associated with the parent date-picker structured document. In every case, the value of this type is interpreted in the context of the parent element or attribute. end example]

This simple type's contents are a restriction of the XML Schema `dateTime` datatype.

| Referenced By |
|--|
| moveFrom@date (§ 3.1.3.1.4, moveFrom); moveTo@date (§ 3.1.3.1.5, moveTo) |

The following XML Schema fragment defines the contents of this simple type:

```
<simpleType name="ST_DateTime">  
  <restriction base="xsd:dateTime"/>  
</simpleType>
```

3.1.3.3.3 ST_MarkupId (Annotation Identifier)

This simple type specifies that its contents shall contain a whole number, whose contents are used to uniquely identify an annotation.

The contents of this identifier are interpreted based on the context of the parent XML element.

This simple type is a union of the following types:

The `ST_NonNegativeDecimalNumber` simple type ([§3.1.3.3.5, ST_NonNegativeDecimalNumber](#)).

The `ST_SignedDecimalNumberMax-2` simple type ([§3.1.3.3.7, ST_SignedDecimalNumberMax-2](#)).

| Referenced By |
|--|
| <code>moveFrom@id</code> (§3.1.3.1.4, moveFrom); <code>moveTo@id</code> (§3.1.3.1.5, moveTo) |

The following XML Schema fragment defines the contents of this simple type:

```
<simpleType name="ST_MarkupId">  
  <union memberTypes="ST_NonNegativeDecimalNumber ST_SignedDecimalNumberMax-2"/>  
</simpleType>
```

3.1.3.3.4 ST_NcName255 (Non-colonized Name)

This simple type specifies that its content shall contain a namespace name. The contents of this name are interpreted based on the context of the parent element.

This simple type's contents are a restriction of the XML Schema NCName datatype.

This simple type also specifies the following restrictions:

This simple type's contents have a maximum length of 255 characters.

| Referenced By |
|--|
| <code>customXml@element</code> (§3.1.3.1.1, customXml) |

The following XML Schema fragment defines the contents of this simple type:

```
<simpleType name="ST_NcName255">  
  <restriction base="xsd:NCName">  
    <maxLength value="255"/>  
  </restriction>  
</simpleType>
```

3.1.3.3.5 ST_NonNegativeDecimalNumber (Non-Negative Decimal Number Value)

This simple type specifies that its contents shall contain a number, whose contents are interpreted based on the context of the parent XML element.

This simple type's contents are a restriction of the XML Schema int datatype.

This simple type also specifies the following restrictions:

This simple type has a minimum value of greater than or equal to 0.

| Referenced By |
|---|
| ST_MarkupId (§3.1.3.3.3, ST_MarkupId) |

The following XML Schema fragment defines the contents of this simple type:

```
<simpleType name="ST_NonNegativeDecimalNumber">  
  <restriction base="xsd:int">  
    <minInclusive value="0"/>  
  </restriction>  
</simpleType>
```

3.1.3.3.6 ST_OnOff (On/Off Value)

This simple type specifies a set of values for any binary (on or off) property defined in a WordprocessingML document.

A value of *on*, *1*, or *true* specifies that the property shall be turned on.

A value of *off*, *0*, or *false* specifies that the property shall be explicitly turned off.

This simple type's contents are a restriction of the XML Schema string datatype.

The following are possible enumeration values for this type:

| Enumeration Value | Description |
|----------------------|--|
| 0 (False) | Specifies that the binary state of this property is off (parent property is explicitly not applied). |
| 1 (True) | Specifies that the binary state of this property is on (parent property is explicitly applied). |
| false (False) | Specifies that the binary state of this property is off (parent property is explicitly not applied). |
| off (False) | Specifies that the binary state of this property is off (parent property is explicitly not applied). |
| on (True) | Specifies that the binary state of this property is on (parent property is explicitly applied). |
| true (True) | Specifies that the binary state of this property is on (parent property is explicitly applied). |

| Referenced By |
|---|
| fldSimple@dirty (§3.1.3.1.2, fldSimple); fldSimple@fldLock (§3.1.3.1.2, fldSimple); hyperlink@history (§3.1.3.1.3, hyperlink) |

The following XML Schema fragment defines the contents of this simple type:

```

<simpleType name="ST_OnOff">
  <restriction base="xsd:string">
    <enumeration value="true"/>
    <enumeration value="false"/>
    <enumeration value="on"/>
    <enumeration value="off"/>
    <enumeration value="0"/>
    <enumeration value="1"/>
  </restriction>
</simpleType>

```

3.1.3.3.7 ST_SignedDecimalNumberMax-2 (Decimal Number Value Max -2)

This simple type specifies that its contents shall contain a number, whose contents are interpreted based on the context of the parent XML element.

This simple type's contents are a restriction of the XML Schema int datatype.

This simple type also specifies the following restrictions:

This simple type has a maximum value of less than or equal to -2.

| Referenced By |
|---|
| ST_MarkupId (§3.1.3.3.3, ST_MarkupId) |

The following XML Schema fragment defines the contents of this simple type:

```

<simpleType name="ST_SignedDecimalNumberMax-2">
  <restriction base="xsd:int">
    <maxInclusive value="-2"/>
  </restriction>
</simpleType>

```

3.1.3.3.8 ST_String (String)

This simple type specifies that its contents will contain a string. The contents of this string are interpreted based on the context of the parent XML element.

[Example: Consider the following WordprocessingML fragment:

```

<w:pPr>
  <w:pStyle w:val="heading1" />
</w:pPr>

```

The value of the **val** attribute is the ID of the associated paragraph style's `styleId`. However, consider the following fragment:

```

<w:sdtPr>
  <w:alias w:val="SDT Title Example" />
  ...

```

</w:sdtPr>

In this case, the decimal number in the **val** attribute is the caption of the parent structured document tag. In each case, the value is of type **ST_String**, and therefore must be interpreted in the context of the parent element. end example]

This simple type's contents are a restriction of the XML Schema string datatype.

| Referenced By |
|--|
| fldSimple@instr (§3.1.3.1.2, fldSimple) |

The following XML Schema fragment defines the contents of this simple type:

```
<simpleType name="ST_String">  
  <restriction base="xsd:string"/>  
</simpleType>
```

3.1.3.3.9 ST_String255 (String)

This simple type specifies that its contents shall contain a string. The contents of this string are interpreted based on the context of the parent XML element.

This simple type's contents are a restriction of the XML Schema string datatype.

This simple type also specifies the following restrictions:

This simple type's contents have a maximum length of 255 characters.

| Referenced By |
|--|
| hyperlink@anchor (§3.1.3.1.3, hyperlink); hyperlink@docLocation (§3.1.3.1.3, hyperlink); hyperlink@tgtFrame (§3.1.3.1.3, hyperlink); moveFrom@author (§3.1.3.1.4, moveFrom); moveTo@author (§3.1.3.1.5, moveTo) |

The following XML Schema fragment defines the contents of this simple type:

```
<simpleType name="ST_String255">  
  <restriction base="xsd:string">  
    <maxLength value="255"/>  
  </restriction>  
</simpleType>
```

3.1.3.3.10 ST_String260 (String)

This simple type specifies that its contents shall contain a string. The contents of this string are interpreted based on the context of the parent XML element.

This simple type's contents are a restriction of the XML Schema string datatype.

This simple type also specifies the following restrictions:

This simple type's contents have a maximum length of 260 characters.

| Referenced By |
|--|
| hyperlink@tooltip (§3.1.3.1.3, hyperlink) |

The following XML Schema fragment defines the contents of this simple type:

```
<simpleType name="ST_String260">  
  <restriction base="xsd:string">  
    <maxLength value="260"/>  
  </restriction>  
</simpleType>
```

3.1.4 DrawingML Persistence Part

When Word creates a legacy shape from an OfficeArt object, additional information will be stored in the legacy shape to allow Word to reconstruct the original OfficeArt object at a later time. This information is stored in the **gfxdata** attribute ("[ECMA-376](#) Part 4 §6.1.2.19; shape").

The contents of the **gfxdata** attribute is an `xsd:base64Binary` representation of a Package ("[ECMA-376](#) Part 2, Open Packaging Conventions"). This package contains information about the original OfficeArt object as well as information about the characteristics of the legacy shape as it was originally created to represent the OfficeArt object.

3.1.4.1 DrawingML Persistence Parts

The DrawingML Persistence Package can contain any part described in [ECMA-376](#) Office Open XML File Formats ("[ECMA-376](#) Part 1, Fundamentals") as well as the parts described in the subclauses subordinate to this clause.

[Note: For convenience, information from those subclauses is summarized in the following table:

| Part | Relationship Target of | Root Element | Ref. |
|-------------------|-------------------------------|--------------|--|
| Graphic Frame Doc | DrawingML Persistence Package | e2oholder | §3.1.4.3.1.1, e2oholder |
| Downrev Storage | DrawingML Persistence Package | downRevStg | §3.1.4.2.1.2, downRevStg |

end note]

3.1.4.1.1 Graphic Frame Doc

Content Type

application/vnd.ms-office.DrsE2oDoc+xml

Root Namespace

http://schemas.openxmlformats.org/drawingml/2006/wordprocessingDrawing

Source Relationship

<http://schemas.microsoft.com/office/2006/relationships/graphicFrameDoc>

An instance of this part type contains the information about an OfficeArt object and its effects.

A DrawingML Persistence Package shall contain only 1 Graphic Frame Doc part.

The root element for a Graphic Frame Doc part shall be e2oholder ([§3.1.4.3.1.1, e2oholder](#)).

[Example: The following Graphic Frame Doc part contains information about a Diagram Object

```
<wp:e2oholder ...>
  <wp:effectOffset l="18288" t="0" r="12887" b="0"/>
  <a:graphic ...>
    <a:graphicData uri="http://schemas.openxmlformats.org/drawingml/2006/diagram">
      <dgm:relIds r:dm="rId1" r:lo="rId2" r:qs="rId3" r:cs="rId4" .../>
    </a:graphicData>
  </a:graphic>
</wp:e2oholder>
```

end example]

A Graphic Frame Doc part is permitted to contain explicit relationships to the following parts defined by ECMA-376 Office Open XML File Formats [\[ECMA-376\]](#):

Chart ("[\[ECMA-376\]](#) Part 1 §14.2.1; Chart Part")

Diagrams: Diagram Colors ("[\[ECMA-376\]](#) Part 1 §14.2.3; Diagram Colors Part"), Diagram Data ("[\[ECMA-376\]](#) Part 1 §14.2.4; Diagram Data Part"), Diagram Layout Definition ("[\[ECMA-376\]](#) Part 1 §14.2.5; Diagram Layout Definition Part"), and Diagram Styles ("[\[ECMA-376\]](#) Part 1 §14.2.6; Diagram Style Part")

Images ("[\[ECMA-376\]](#) Part 1 §15.2.13; Image Part")

A Graphic Frame Doc part shall not have any implicit or explicit relationships to any other part defined by ECMA-376 Office Open XML File Formats [\[ECMA-376\]](#).

3.1.4.1.2 Downrev Storage

Content Type

application/vnd.ms-office.DrsDownRev+xml

Root Namespace

http://schemas.openxmlformats.org/drawingml/2006/main

Source Relationship

http://schemas.microsoft.com/office/2006/relationships/downRev

An instance of this part type contains the information about an OfficeArt object's bounds and checksum information for the original legacy shape representation of the OfficeArt object represented in the Graphic Frame Doc part.

A DrawingML Persistence Package shall contain only 1 Downrev Storage part.

The root element for a Downrev Storage part shall be downRevStg ([§3.1.4.2.1.2, downRevStg](#)).

[Example: The following Downrev Storage part contains information about a Diagram Object with no text

```
<a:downRevStg shapeChecksum="gcmnapp+jq1ZXL5rE1CguF==&#xA;" textChecksum="" ver="1" ...>
  <a:bounds l="0" t="0" r="3405" b="3855"/>
</a:downRevStg>
```

end example]

A Downrev Storage part shall not have any implicit or explicit relationships to any parts defined by ECMA-376 Office Open XML File Formats [\[ECMA-376\]](#).

3.1.4.2 Additional DrawingML - Main Schema

3.1.4.2.1 Additional Elements

This section specifies the structure of the VML embedded DrawingML (see also **gfxdata** attribute ("[\[ECMA-376\]](#) Part 4 §6.1.2.19; shape")).

3.1.4.2.1.1 bounds (Bounds)

This element defines the size and position of the DrawingML graphical object (OfficeArt object). If the OfficeArt object has an inline text wrapping mode, then the bounds shall be relative to the top-left corner of the OfficeArt object itself and the absolute position of the OfficeArt object is determined by its position in the text run. For floating text-wrapping modes, the bounds shall be relative to the top-left corner of the page.

While the range of possible values is defined by the ST_Coordinate simple type, in Office the unit of measure for the attributes of this element is the twip. A twip is equivalent to 1/1440th of an inch (or one-twentieth of a point).

| Parent Elements |
|--|
| downRevStg (§3.1.4.2.1.2, downRevStg) |

| Attributes | Description |
|-------------------|--|
| b (Bottom) | The position of the bottom side of the OfficeArt object. The possible values for this attribute are defined by the ST_Coordinate simple type (§3.1.4.2.2.1, ST_Coordinate). |
| l (Left) | The position of the left side of the OfficeArt object. The possible values for this attribute are defined by the ST_Coordinate simple type (§3.1.4.2.2.1, ST_Coordinate). |
| r (Right) | The position of the right side of the OfficeArt object. The possible values for this attribute are defined by the ST_Coordinate simple type (§3.1.4.2.2.1, ST_Coordinate). |
| t (Top) | The position of the top side of the OfficeArt object. |

| Attributes | Description |
|------------|--|
| | The possible values for this attribute are defined by the ST_Coordinate simple type (§3.1.4.2.2.1, ST_Coordinate). |

The following XML Schema fragment defines the contents of this element:

```
<complexType name="CT_BoundRect">
  <attribute name="l" type="ST_Coordinate" use="required"/>
  <attribute name="t" type="ST_Coordinate" use="required"/>
  <attribute name="r" type="ST_Coordinate" use="required"/>
  <attribute name="b" type="ST_Coordinate" use="required"/>
</complexType>
```

3.1.4.2.1.2 downRevStg (DownRev Storage)

This is the root element of the VML embedded DrawingML, downrev part. It contains anchoring and other miscellaneous information for the embedded OfficeArt object.

| Child Elements | Subclause |
|------------------------|--------------------------------------|
| bounds (Bounds) | §3.1.4.2.1.1, bounds |

| Attributes | Description |
|---------------------------------------|---|
| shapeChecksum (Shape Checksum) | Contains a base-64 encoded value of the MD4 hash of the shape properties. This value can be used to determine whether the associated VML shape has been modified. The possible values for this attribute are defined by the XML Schema string datatype. |
| textChecksum (Text Checksum) | Contains a base-64 encoded value of the MD4 hash of the text in the OfficeArt object. Office always writes an empty string and ignores this attribute on load. The possible values for this attribute are defined by the XML Schema string datatype. |
| ver (Version Number) | Version number of this OfficeArt object. The value of this attribute is application-defined. Office expects a value of 0 for Beta 2 files, and a value of 1 for RTM and subsequent versions. The possible values for this attribute are defined by the XML Schema unsignedInt datatype. |

The following XML Schema fragment defines the contents of this element:

```
<complexType name="CT_DownRevStg">
  <sequence>
    <choice minOccurs="0" maxOccurs="1">
      <element name="bounds" type="CT_BoundRect"/>
    </choice>
  </sequence>
```



```

    <attribute name="shapeChecksum" type="xsd:string" use="required"/>
    <attribute name="textChecksum" type="xsd:string" use="optional"/>
    <attribute name="ver" type="xsd:unsignedInt" use="optional" default="0"/>
</complexType>

```

3.1.4.2.2 Simple Types

This is the complete list of simple types in the <http://schemas.openxmlformats.org/drawingml/2006/main> namespace.

3.1.4.2.2.1 ST_Coordinate (Coordinate)

This simple type represents a one dimensional position or length in EMUs. EMUs (English Metric Units) are a high precision coordinate space (914400 dpi / 360000 dpc).

The restrictions specified in the following section apply only to Excel. For Word and PowerPoint, the simple type has a minimum value of greater than or equal to -2147483648 and a maximum value of less than or equal to 2147483647.

This simple type's contents are a restriction of the XML Schema long datatype.

This simple type also specifies the following restrictions:

This simple type has a minimum value of greater than or equal to -27273042329600.

This simple type has a maximum value of less than or equal to 27273042316900.

| Referenced By |
|--|
| bounds@b (§3.1.4.2.1.1, bounds); bounds@l (§3.1.4.2.1.1, bounds); bounds@r (§3.1.4.2.1.1, bounds); bounds@t (§3.1.4.2.1.1, bounds); effectOffset@b (§3.1.4.3.1.2, effectOffset); effectOffset@l (§3.1.4.3.1.2, effectOffset); effectOffset@r (§3.1.4.3.1.2, effectOffset); effectOffset@t (§3.1.4.3.1.2, effectOffset) |

The following XML Schema fragment defines the contents of this simple type:

```

<simpleType name="ST_Coordinate">
  <restriction base="xsd:long">
    <minInclusive value="-27273042329600"/>
    <maxInclusive value="27273042316900"/>
  </restriction>
</simpleType>

```

3.1.4.3 Additional DrawingML - WordprocessingML Schema

3.1.4.3.1 Additional Elements

This section specifies the structure of the VML embedded DrawingML (see also gfxdata attribute ("ECMA-376 Part 4 §6.1.2.19; shape (Shape Definition)").

3.1.4.3.1.1 e2oholder (E2o Holder)

This is the root element of the VML embedded DrawingML, Graphic Frame Doc part. It contains the actual DrawingML graphical object (OfficeArt object) data.

| Child Elements | Subclause |
|-------------------------------------|--|
| effectOffset (Effect Offset) | §3.1.4.3.1.2, effectOffset |
| graphic (Graphic Object) | " [ECMA-376] Part 4 §5.1.2.1.16" |

The following XML Schema fragment defines the contents of this element:

```
<complexType name="CT_GraphicalObjectWrapper">
  <sequence>
    <element name="effectOffset" type="CT_EffectOffsetStg" minOccurs="1" maxOccurs="1"/>
    <element ref="a:graphic" minOccurs="1" maxOccurs="1"/>
  </sequence>
</complexType>
```

3.1.4.3.1.2 effectOffset (Effect Offset)

This element specifies the offset between the OfficeArt object bounds and the bounds of the total area of its visual effects.

| Parent Elements |
|--|
| e2oholder (§3.1.4.3.1.1, e2oholder) |

| Attributes | Description |
|--------------------------|--|
| b (Bottom Offset) | The difference between the bottom border of the effect area and the bottom border of the OfficeArt object. The possible values for this attribute are defined by the ST_Coordinate simple type (" [ECMA-376] Part 4 §5.1.12.16"). |
| l (Left Offset) | The difference between left border of the OfficeArt object and the left border of the effect area. The possible values for this attribute are defined by the ST_Coordinate simple type (" [ECMA-376] Part 4 §5.1.12.16"). |
| r (Right Offset) | The difference between the right border of the effect area and the right border of the OfficeArt object. The possible values for this attribute are defined by the ST_Coordinate simple type (" [ECMA-376] Part 4 §5.1.12.16"). |
| t (Top Offset) | The difference between the top border of the OfficeArt object and the top border of the effect area. The possible values for this attribute are defined by the ST_Coordinate simple type (" [ECMA-376] Part 4 §5.1.12.16"). |

The following XML Schema fragment defines the contents of this element:

```

<complexType name="CT_EffectOffsetStg">
  <attribute name="l" type="a:ST_Coordinate" use="required"/>
  <attribute name="t" type="a:ST_Coordinate" use="required"/>
  <attribute name="r" type="a:ST_Coordinate" use="required"/>
  <attribute name="b" type="a:ST_Coordinate" use="required"/>
</complexType>

```

3.2 Excel

This section contains additional information used to more fully describe how Excel implements ECMA-376 Office Open XML File Formats [\[ECMA-376\]](#).

3.2.1 Additional Parts

The subclauses subordinate to this one describe in detail each of the part types specific to Excel in addition to those listed as part of ECMA-376 Office Open XML File Formats ("[\[ECMA-376\]](#) Part 1 §12; SpreadsheetML").

3.2.1.1 Excel Attached Toolbars Part

Content Type

application/vnd.ms-excel.attachedToolbars

Root Namespace

Not applicable

Source Relationship

http://schemas.microsoft.com/office/2006/relationships/attachedToolbars

This binary part supports the storage of custom toolbars created by the user.

A package shall contain at most one Attached Toolbars part, and that part shall be the target of an implicit relationship from the Workbook part ("[\[ECMA-376\]](#) Part 1 §12.3.23; Workbook Part").

[Example: The following Workbook part-relationship item contains a relationship to the Attached Toolbars part, which is stored in the ZIP item attachedToolbars.bin:

```

<Relationships xmlns="...">
  <Relationship Id="rId6"
    Type="http://.../attachedToolbars" Target="attachedToolbars.bin"/>
</Relationships>

```

end example]

An Attached Toolbars part shall be located within the package containing the source relationship (expressed syntactically, the **TargetMode** attribute of the **Relationship** element shall be *Internal*).

An Attached Toolbars part shall not have implicit or explicit relationships to any part defined by ECMA-376 Office Open XML File Formats [\[ECMA-376\]](#).

The internal structure of the ZIP item attachedToolbars.bin is specified in the XCB section of the Excel 97-2003 Binary File Format (.xls) Structure Specification [\[MS-XLS\]](#) book.

3.2.1.2 Worksheet Sort Map Part

Content Type

application/vnd.ms-excel.wsSortMap+xml

Root Namespace

http://schemas.microsoft.com/office/excel/2006/main

Source Relationship

http://schemas.microsoft.com/office/2006/relationships/wsSortMap

An instance of this part contains information about a series of before and after row or column mapping to resolve different sort operations performed on the same range by different users when the workbook is shared.

A package is permitted to contain zero or one Worksheet Sort Map part for each worksheet, and that part shall be the target of an implicit relationship from the Worksheet part ("[ECMA-376](#) Part 1 §12.3.24; Worksheet Part").

[Example: The following Worksheet part-relationship item contains a relationship to the Worksheet Sort Map part, which is stored in the ZIP item wsSortMap1.xml:

```
<Relationships xmlns="...">
  <Relationship Id="rId1"
    Type="http://.../wsSortMap" Target="wsSortMap1.xml"/>
</Relationships>
```

end example]

The root element for a part of this content type shall be **worksheetSortMap**.

[Example: This Worksheet Sort Map part results from a row sort on a range containing 3 rows:

```
<worksheetSortMap xmlns:st="...">
  <rowSortMap ref="A1:XF3" count="3">
    <row newVal="0" oldVal="1"/>
    <row newVal="1" oldVal="2"/>
    <row newVal="2" oldVal="0"/>
  </rowSortMap>
</worksheetSortMap>
```

end example]

A Worksheet Sort Map part shall be located within the package containing the source relationship (expressed syntactically, the **TargetMode** attribute of the **Relationship** element shall be *Internal*).

A Worksheet Sort Map part shall not have implicit or explicit relationships to any part defined by ECMA-376 Office Open XML File Formats [ECMA-376](#).

3.2.2 Microsoft Office Excel Sortmap

This part specifies a Sort Map used by Excel to recalculate a shared workbook. This part is present in files created by Excel 2007 SP1 and later.

3.2.2.1 Sortmap Elements

This subclause specifies the elements and simple types that comprise the Sort Map.

A sort map is used in the context of a shared workbook to record the sort order of a range of cells. This information is used to correctly update cells and formulas that depend on the sort order when revision information is applied. There is one sort map per worksheet.

The sort map consists of two components: The row sort map and the column sort map. The row sort map contains a list of row indices that need to be adjusted when revision information is applied. The row sort map is created when a range of cells is sorted top down or bottom up. The column sort map contains a list of column indices that need to be adjusted when revision information is applied. The column sort map is created when a range of cells is sorted left to right or right to left.

[Example: Consider the following shared workbook:

| | A | B |
|---|---|---|
| 1 | | |
| 2 | 5 | |
| 3 | 6 | |
| 4 | 7 | |
| 5 | 8 | |

The worksheet contains four rows of data. Once the data is sorted in descending order, the worksheet looks as follows:

| | A | B |
|---|---|---|
| 1 | | |
| 2 | 8 | |
| 3 | 7 | |
| 4 | 6 | |
| 5 | 5 | |

When this worksheet is saved, the following sort map should be created and saved to the file:

```
<worksheetSortMap xmlns="http://schemas.microsoft.com/office/excel/2006/main">
  <rowSortMap ref="A2:XF5" count="4">
    <row newVal="1" oldVal="4"/>
    <row newVal="2" oldVal="3"/>
    <row newVal="3" oldVal="2"/>
    <row newVal="4" oldVal="1"/>
  </rowSortMap>
</worksheetSortMap>
```

In the context of this example, the sort map implies that the contents of the second row should be replaced with the contents of the fifth row; contents of the third row should be replaced with the contents of the fourth row; and so on.

Now consider the following worksheet:

| | A | B | C | D |
|---|---|---|---|---|
| 1 | | | | |
| 2 | 5 | 6 | 7 | 8 |
| 3 | | | | |

This worksheet contains four columns of data. Once the data is sorted left to right in descending order, the worksheet looks as follows:

| | A | B | C | D |
|---|---|---|---|---|
| 1 | | | | |
| 2 | 8 | 7 | 6 | 5 |
| 3 | | | | |

When this worksheet is saved, the following sort map should be created and saved to the file:

```
<worksheetSortMap xmlns="http://schemas.microsoft.com/office/excel/2006/main">
  <colSortMap ref="A1:D1048576" count="4">
    <col newVal="0" oldVal="3"/>
    <col newVal="1" oldVal="2"/>
    <col newVal="2" oldVal="1"/>
    <col newVal="3" oldVal="0"/>
  </colSortMap>
</worksheetSortMap>
```

In the context of this example, the sort map implies that the contents of the first column should be replaced with the contents of the fourth column; contents of the second column should be replaced with the contents of the third column; and so on.

End Example]

3.2.2.1.1 col (Column)

This element represents a single column mapping in the sort map.

| Parent Elements |
|---|
| colSortMap (§3.2.2.1.2, colSortMap) |

| Attributes | Description |
|---------------------------|--|
| newVal (New Value) | Specifies the zero-based index of the column or row that contains data after a sort operation. In the context of a row element, the value of this attribute shall be less than 1048576. In the context of a col element, the value of this attribute shall be less than 16384. The possible values for this attribute are defined by the XML Schema unsignedInt datatype. |
| oldVal (Old Value) | Specifies the zero-based index of the column or row that contains data before a sort operation. |

| Attributes | Description |
|------------|---|
| | <p>In the context of a row element, the value of this attribute shall be less than 1048576.</p> <p>In the context of a col element, the value of this attribute shall be less than 16384.</p> <p>The possible values for this attribute are defined by the XML Schema unsignedInt datatype.</p> |

The following XML Schema fragment defines the contents of this element:

```
<complexType name="CT_SortMapItem">
  <attribute name="newVal" type="xsd:unsignedInt" use="required"/>
  <attribute name="oldVal" type="xsd:unsignedInt" use="required"/>
</complexType>
```

3.2.2.1.2 colSortMap (Column Sort Map)

This element represents the list of column mappings of the sort map.

| Parent Elements |
|--|
| worksheetSortMap (§3.2.2.1.5, worksheetSortMap) |

| Child Elements | Subclause |
|---------------------|---------------------------------|
| col (Column) | §3.2.2.1.1, col |

| Attributes | Description |
|---------------------------|--|
| count (Count) | <p>Specifies the number of col elements. The value of this attribute shall match the number of col elements.</p> <p>The possible values for this attribute are defined by the ST_SortMapCount simple type (§3.2.2.2.1, ST_SortMapCount).</p> |
| ref (Reference) | <p>Specifies the row and column bounds of the sort map.</p> <p>The possible values for this attribute are defined by the ST_Ref simple type ("IECMA-376 Part 4 §3.18.64").</p> |

The following XML Schema fragment defines the contents of this element:

```
<complexType name="CT_ColSortMap">
  <sequence>
    <element name="col" type="CT_SortMapItem" minOccurs="1" maxOccurs="536870910"/>
  </sequence>
  <attribute name="ref" type="x:ST_Ref" use="required"/>
  <attribute name="count" type="ST_SortMapCount" use="optional" default="20"/>
</complexType>
```

3.2.2.1.3 row (Row)

This element represents a single row mapping in the sort map.

| Parent Elements |
|--|
| rowSortMap (§3.2.2.1.4, rowSortMap) |

| Attributes | Description |
|---------------------------|---|
| newVal (New Value) | Specifies the zero-based index of the column or row that contains data after a sort operation. In the context of a row element, the value of this attribute shall be less than 1048576. In the context of a col element, the value of this attribute shall be less than 16384. The possible values for this attribute are defined by the XML Schema unsignedInt datatype. |
| oldVal (Old Value) | Specifies the zero-based index of the column or row that contains data before a sort operation. In the context of a row element, the value of this attribute shall be less than 1048576. In the context of a col element, the value of this attribute shall be less than 16384. The possible values for this attribute are defined by the XML Schema unsignedInt datatype. |

The following XML Schema fragment defines the contents of this element:

```
<complexType name="CT_SortMapItem">  
  <attribute name="newVal" type="xsd:unsignedInt" use="required"/>  
  <attribute name="oldVal" type="xsd:unsignedInt" use="required"/>  
</complexType>
```

3.2.2.1.4 rowSortMap (Row Sort Map)

This element represents a list of row mappings of the sort map.

| Parent Elements |
|--|
| worksheetSortMap (§3.2.2.1.5, worksheetSortMap) |

| Child Elements | Subclause |
|---------------------------|---------------------------------|
| row (Row) | §3.2.2.1.3, row |

| Attributes | Description |
|---------------------------|--|
| count (Count) | Specifies the number of row elements. The value of this attribute shall match the number of row elements. The possible values for this attribute are defined by the ST_SortMapCount simple type (§3.2.2.2.1, ST_SortMapCount). |
| ref (Reference) | Specifies the row and column bounds of the sort map. The possible values for this attribute are defined by the ST_Ref simple type ("ECMA-376 Part 4 §3.18.64"). |

The following XML Schema fragment defines the contents of this element:

```
<complexType name="CT_RowSortMap">
  <sequence>
    <element name="row" type="CT_SortMapItem" minOccurs="1" maxOccurs="536870910"/>
  </sequence>
  <attribute name="ref" type="x:ST_Ref" use="required"/>
  <attribute name="count" type="ST_SortMapCount" use="optional" default="20"/>
</complexType>
```

3.2.2.1.5 worksheetSortMap (Worksheet Sort Map)

This element represents the row and column sort mappings associated with a worksheet.

| Child Elements | Subclause |
|-------------------------------------|--|
| colSortMap (Column Sort Map) | §3.2.2.1.2, colSortMap |
| rowSortMap (Row Sort Map) | §3.2.2.1.4, rowSortMap |

The following XML Schema fragment defines the contents of this element:

```
<complexType name="CT_WorksheetSortMap">
  <sequence>
    <element name="rowSortMap" type="CT_RowSortMap" minOccurs="0" maxOccurs="1"/>
    <element name="colSortMap" type="CT_ColSortMap" minOccurs="0" maxOccurs="1"/>
  </sequence>
</complexType>
```

3.2.2.2 Simple Types

This is the complete list of simple types in the <http://schemas.microsoft.com/office/excel/2006/main> namespace.

3.2.2.2.1 ST_SortMapCount (Sort Map Count)

This simple type represents the count of row or column sort map entries.

This simple type's contents are a restriction of the XML Schema unsignedInt datatype.

This simple type also specifies the following restrictions:

This simple type has a maximum value of less than or equal to 536870910.

| Referenced By |
|--|
| colSortMap@count (§3.2.2.1.2, colSortMap); rowSortMap@count (§3.2.2.1.4, rowSortMap) |

The following XML Schema fragment defines the contents of this simple type:

```
<simpleType name="ST_SortMapCount">
  <restriction base="xsd:unsignedInt">
    <maxInclusive value="536870910"/>
  </restriction>
</simpleType>
```

3.2.3 Additional SpreadsheetML Schema

The subordinate clauses define additional information in the SpreadsheetML schema used by Excel.

3.2.3.1 Formulas

3.2.3.1.1 Structure References

A structure reference has the following form:

```
structure-reference=
[table-identifier], intra-table-reference ;
table-identifier=
[book-prefix], table-name ;
table-name=
name ;
intra-table-reference=
spaced-lbracket, inner-reference, spaced-rbracket |
keyword |
'[, [simple-column-name], ']' ;
inner-reference=
keyword-list |
[keyword-list, spaced-comma], column-range ;
keyword=
" [#All]" | " [#Data]" | " [#Headers]" | " [#Totals]" | " [#This Row]" ;
keyword-list=
keyword |
" [#Headers]", spaced-comma, " [#Data]" |
" [#Data]", spaced-comma, " [#Totals]" ;
column-range=
column, [":", column] ;
column=
simple-column-name |
spaced-lbracket, {space}, simple-column-name, {space}, spaced-rbracket ;
simple-column-name=
[any-nospace-column-character, {any-column-character }], any-nospace-column-character ;
escape-column-character=
'"' | "[" | "]" | "#" ;
any-column-character=
character - escape-column-character |
'"', escape-column-character ;
any-nospace-column-character=
```

```
any-column-character - space ;
spaced-comma=
[space], ",", [space] ;
spaced-lbracket=
"[" , [space] ;
spaced-rbracket=
[space], "]" ;
```

Structure references define rectangular sections of tables using special syntax, table column names, and reserved keywords instead of relative or absolute references. Structure references do not need adjustment if tables they refer to have been modified. They also provide a mechanism to define areas using meaningful table column names instead of less helpful cell references.

table-name is the name of the table the structure reference refers to. If it is missing, then the formula containing the structure reference must be entered into a cell that belongs to a table, and that table's name is used as the table-name. table-name must be a name of a table. It must not be any other user-defined name.

table-name[] refers to all cells in table-name except Header Row and Total Row.

table-name[#Data] refers to all table-name's cells except Header Row and Total Row. It is equivalent to the form table-name[[]].

table-name[#Headers] refers to all cells in table-name's Header Row.

table-name[#Total Row] refers to all cells in the table-name's Total Row

table-name[#All] refers to the entire table area. table-name[#All] is the union of table-name[#Headers], table-name[#Data], and table-name[#Total Row]

table-name[column-name] refers to all cells in the column named column-name except the cells from Header Row and Total Row.

table-name[[column-name]] refers to all cells in the column named column-name except the cells from Header Row and Total Row.

table-name[[column-name1]:[column-name2]] refers to all cells from column named column-name1 through column named column-name2 except the cells from Header Row and Total Row.

table-name[[keyword],[column-name]], where keyword is one of #Headers, #Total Row, #Data, #All, refers to the intersection of the area defined by table-name[keyword] and all cells from the column named column-name.

table-name[[#Data],[column-name]] is equivalent to table-name[column-name]

table-name[[keyword],[column-name1]:[column-name2]], where keyword is one of #Headers, #Total Row, #Data, #All, refers to the intersection of the area defined by table-name[keyword] and all cells from the table from column named column-name1 through column named column-name2.

table-name[[#Headers],[#Data],[column-name]] is the union of table-name[[#Headers],[column-name]] and table-name[[#Data],[column-name]]

table-name[[#Data],[#Total Row],[column-name]] is the union of table-name[[#Data],[column-name]] and table-name[[#Total Row],[column-name]]

table-name[[#Headers],[#Data],[column-name1]:[column-name2]] is the union of table-name[[#Headers], [column-name1]:[column-name2]] and table-name[[#Data], [column-name1]:[column-name2]]

table-name[[#Data],[#Total Row], [column-name1]:[column-name2]] is the union of table-name[[#Data], [column-name1]:[column-name2]] and table-name[[#Total Row], [column-name1]:[column-name2]]

table-name[[#This Row],[column-name]] refers to the cell in the intersection of table-name[column-name] and the current row; for example, the row of the cell that contains the formula with the structure reference. table-name[[#This Row],[column-name1]:[column-name2]] refers to the cells in the intersection of table-name[[column-name]:[column-name2]] and the current row; for example, the row of the cell that contains the formula with such structure reference. These two forms allow formulas to perform implicit intersection using structure references.

#This Row must not be combined with any of #Headers, #Total Row, #Data, #All.

3.2.3.1.2 Conditional Formatting Formulas

Conditional formatting formulas are part of conditional formatting rules.

A conditional formatting formula shall not use array constants.

A conditional formatting formula shall not use structure references.

A conditional formatting formula shall not use union and intersection binary operators.

A conditional formatting formula shall not use 3-D references.

```
CF-formula=
CF-expression ;
CF-expression= {space}, CF-nospace-expression, {space} ;
CF-nospace-expression=
"(", CF-expression, ")" |
CF-constant |
prefix-operator, CF-expression |
CF-expression, CF-infix-operator, CF-expression |
CF-expression, postfix-operator |
A1-reference |
CF-function-call |
name ;
CF-constant=
constant - array-constant ;
CF-infix-operator=
":" | "^" | "*" | "/" | "+" | "-" | "&" |
"=" | "<>" | "<" | "<=" | ">" | ">=" ;
CF-function-call=
CF-function-name, "(", CF-function-argument-list, ")" ;
CF-function-name=
predefined-function-name |
name ;
CF-function-argument-list =
[CF-expression], { comma, CF-function-argument-list } ;
```

3.2.3.1.3 Data Validation Formulas

Data validation formulas are part of Data Validation rules. They shall not use array constants, structure references, or union or intersection binary operators.

```
DV-formula=
DV-expression ;
DV-expression= {space}, DV-nospace-expression, {space} ;
DV-nospace-expression=
"(", DV-expression, ")" |
DV-constant |
prefix-operator, DV-expression |
DV-expression, DV-infix-operator, DV-expression |
DV-expression, postfix-operator |
A1-reference |
function-call |
name ;
DV-constant=
constant - array-constant ;
DV-infix-operator=
":" | "^" | "*" | "/" | "+" | "-" | "&" |
"=" | "<>" | "<" | "<=" | ">" | ">=" ;
DV-function-call=
DV-function-name, "(", DV-function-argument-list, ")" ;
DV-function-name=
predefined-function-name |
name ;
DV-function-argument-list=
[DV-expression], { comma, DV-function-argument-list } ;
```

3.2.3.1.4 Name Formulas

If a name is defined as an alias for a formula then that formula shall contain 3-D references only.

```
name-formula=
name-expression ;
name-expression= {space}, name-nospace-expression, {space} ;
name-nospace-expression=
"(", name-expression, ")" |
constant |
prefix-operator, name-expression |
name-expression, infix-operator, name-expression |
name-expression, postfix-operator |
external-cell-reference |
"!", A1-reference |
name-function-call |
name-reference |
"!", name |
structure-reference ;
name-function-call=
function-name, "(", name-function-argument-list, ")" ;
name-function-argument-list=
[name-expression], { comma, name-function-argument-list } ;
```

3.2.3.1.5 External Name Formulas

External name formulas are restricted to cell references within the same external book.

```
external-name-formula=
["="], external-name-expression ;
external-name-expression=
same-book-prefix, A1-reference |
external-name-error-constant ;
same-book-prefix= same-book-single-sheet, "!" |
    same-book-sheet-range, "!" ;
same-book-single-sheet= sheet-name |
    apostrophe, sheet-name-special, apostrophe ;
same-book-sheet-range= sheet-name, ":", sheet-name |
    apostrophe, sheet-name-special, ":", sheet-name-special, apostrophe ;

external-name-error-constant=
"#REF!" ;
```

3.2.3.1.6 Chart formulas

Chart formulas define data ranges and values used by charts, such as chart ranges, series ranges, series titles, and axis titles.

A chart formula shall be either a 3-D reference or a constant.

```
chart-formula=
chart_ref |
"(", chart-ref, ",", chart-ref, {"", chart-ref}, ")"
chart_ref =
external-cell-reference |
external-name ;
```

3.2.3.1.7 R1C1 formulas

In R1C1 formulas, R1C1-style references shall be used instead of A1-style references.

An R1C1 formula has the following form:

```
R1C1-formula=
R1C1-expression ;
R1C1-expression=
{space}, nospace-R1C1-expression, {space};
nospace-R1C1-expression=
"(", R1C1-expression, ")" |
constant |
prefix-operator, R1C1-expression |
R1C1-expression, infix-operator, R1C1-expression |
R1C1-expression, postfix-operator |
R1C1-cell-reference |
R1C1-function-call |
name-reference |
structure-reference ;
R1C1-function-call=
function-name, "(", R1C1-argument-list, ")" ;
```

```

R1C1-argument-list=
R1C1-argument, { comma, R1C1-argument } ;
R1C1-argument=
[R1C1-expression] ;
R1C1-cell-reference=
[sheets-prefix] R1C1-reference ;

```

3.2.3.1.8 Pivot Formulas

Pivot formulas are used to define calculated items or calculated fields for PivotTables.

Pivot formulas shall not use user-defined names.

A pivot formula shall not use array constants.

A pivot formula shall not use cell references.

A pivot formula shall not use structure references.

A pivot formula shall not use calls to the following worksheet functions: GETPIVOTDATA, DCOUNT, DCOUNTA, DSUM, DAVERAGE, DMIN, DMAX, DPRODUCT, DSTDEV, DSTDEVP, DVAR, DVARP, INDEX, RAND, NOW, AREAS, ROWS, COLUMNS, OFFSET, CELL, INDIRECT, TODAY, INFO, and RANDBETWEEN.

A pivot formula shall not use calls to user-defined functions.

3.2.3.1.8.1 Calculated Field Formulas

A calculated field formula defines calculations using the contents of fields in a PivotTable.

The only names a calculated field formula shall use are names of fields defined within the PivotTable the formula is used for.

A calculated field formula has the following form:

```

pivot-field-formula=
pivot-field-expression ;
pivot-field-expression=
{space}, pivot-nospace-field-expression, {space} ;
pivot-nospace-field-expression=
"(", pivot-field-expression, ")" |
pivot-constant |
prefix-operator, pivot-field-expression |
pivot-field-expression, pivot-infix-operator, pivot-field-expression |
pivot-field-expression, postfix-operator |
pivot-field-function-call |
pivot-field-name ;
pivot-constant=
constant - array-constant ;
pivot-infix-operator=
"^" | "*" | "/" | "+" | "-" | "&" |
"=" | "<>" | "<" | "<=" | ">" | ">=" ;
pivot-field-function-call=
pivot-function-name, "(", pivot-field-function-argument-list, ")" ;
pivot-field-function-argument-list =
[pivot-field-expression], { comma, pivot-field-function-argument-list } ;

```

```

pivot-function-name=
predefined-function-name - pivot-function-invalid-name;
pivot-function-invalid-name=
"GETPIVOTDATA" | "DCOUNT" | "DCOUNTA" | "DSUM" | "DAVERAGE" |
"DMIN" | "MAX" | "DPRODUCT" | "DSTDEV" | "DSTDEVP" | "DVAR" |
"DVARP" | "INDEX" | "RAND" | "NOW" | "AREAS" | "ROWS" | "COLUMNS" |
"OFFSET" | "CELL" | "INDIRECT" | "TODAY" | "INFO" | "RANDBETWEEN" ;
pivot-field-name=
name - pivot-invalid-name |
"" [pivot-field-string-chars] "" ;
pivot-invalid-name=
"All" | "Blank" ;
pivot-field-string-chars=
pivot-field-string-char, { pivot-field-string-chars} ;
pivot-field-string-char=
"" |
character - "" ;

```

3.2.3.1.8.2 Calculated Item Formulas

A calculated item formula defines calculations using the contents of items in a PivotTable.

The only names calculated item formula shall use are names of fields and items defined within the PivotTable the formula is used for.

A calculated item formula has the following form:

```

pivot-item-formula=
pivot-item-expression ;
pivot-item-expression= {space}, pivot-nospace-item-expression, {space} ;
pivot-nospace-item-expression=
"(", pivot-item-expression, ")" |
pivot-constant |
prefix-operator, pivot-item-expression |
pivot-item-expression, pivot-infix-operator, pivot-item-expression |
pivot-item-expression, postfix-operator |
pivot-item-function-call |
pivot-items ;
pivot-item-function-call=
pivot-function-name, "(", pivot-item-function-argument-list, ")" ;
pivot-item-function-argument-list=
[pivot-item-expression], { comma, pivot-item-function-argument-list} ;
pivot-items=
pivot_item, [ space, {space}, pivot-items] ;
pivot-item=
pivot-item-name |
pivot-field-name, "[", pivot-item-value, "]" ;
pivot-item-name=
pivot-field-name
pivot-item-value=
pivot-item-name |
[sign], whole-number-part

```

pivot-item refers to an item either by its name or by position.

pivot-item-name refers to an item by its name.

pivot-field-name [pivot-item-name] refers to an item by its field name and its own name. This notation shall be used to avoid #NAME? errors when two items in two different fields have the same name.

pivot-field-name[whole-number-part] refers to an item by its position in the PivotTable as currently sorted and displayed. The item referred to in this way can change whenever the positions of items change or different items are displayed or hidden. Hidden items are not counted in this index.

pivot-field-name [sign whole-number-part] refers to an item using relative positions. The positions are determined relative to the calculated item that contains the formula.

3.2.3.1.9 OLE Link Formulas

An OLE Link formula is a *name-reference* to an **oleItem** ("[\[ECMA-376\]](#) Part 4 §3.14.9; oleItem"). The **name** attribute of the **oleItem** element shall be "" (apostrophe, 0x0027).

book-prefix, apostrophe, apostrophe, apostrophe, apostrophe ;

book-prefix refers to an **externalLink** ("[\[ECMA-376\]](#) Part 4 §3.14.8; externalLink") part containing the **oleItem** element.

3.3 PowerPoint

This section contains additional information used to more fully describe how PowerPoint implements ECMA-376 Office Open XML File Formats [\[ECMA-376\]](#).

3.3.1 Additional Parts

The subclauses subordinate to this one describe in detail each of the part types specific to PowerPoint in addition to those listed as part of ECMA-376 Office Open XML File Formats ("[\[ECMA-376\]](#) Part 1 §13; PresentationML").

3.3.1.1 Legacy Diagram Text part

Content Type

application/vnd.ms-office.legacyDiagramText

Root Namespace

not applicable

Source Relationship

http://schemas.microsoft.com/office/2006/relationships/legacyDiagramText

An instance of this part type contains a portion of text within a legacy diagram. Each instance of this part type shall uniquely represent a portion of text within a single diagram contained within the presentation.

A package shall contain one Legacy Diagram Text part for each portion of legacy diagram text within the presentation. If they exist, those parts shall each be the target of an explicit relationship from the corresponding VML Drawing part ("[\[ECMA-376\]](#) Part 1 §15.2.17; VML Drawing Part").

The Legacy Diagram Text part is binary information that is defined in the PowerPoint 97-2003 Binary File Format (.ppt) Structure Specification (" [\[MS-PPT\]](#) Section 2.9.76; OfficeArtClientTextbox").

A Legacy Diagram Text part shall be located within the package containing the source relationship (expressed syntactically, the **TargetMode** attribute of the **Relationship** element shall be *Internal*).

A Legacy Diagram Text part shall not have implicit or explicit relationships to any other part defined by ECMA-376 Office Open XML File Formats [\[ECMA-376\]](#).

3.3.1.2 Legacy Diagram Text Info part

Content Type

application/vnd.ms-office.legacyDocTextInfo

Root Namespace

not applicable

Source Relationship

<http://schemas.microsoft.com/office/2006/relationships/legacyDocTextInfo>

An instance of this part type contains the text styling information for all legacy diagram text contained within the presentation.

A package shall contain at most one Legacy Diagram Text Info part, and that part shall be the target of an implicit relationship from the Presentation part (" [\[ECMA-376\]](#) Part 1 §13.3.6; Presentation Part").

The Legacy Diagram Text Info part is binary information that is defined in the PowerPoint 97-2003 Binary File Format (.ppt) Structure Specification (" [\[MS-PPT\]](#) Section 2.9.1; DocumentTextInfoContainer").

A Legacy Diagram Text part shall be located within the package containing the source relationship (expressed syntactically, the **TargetMode** attribute of the **Relationship** element shall be *Internal*).

A Legacy Diagram Text part shall not have implicit or explicit relationships to any other part defined by ECMA-376 Office Open XML File Formats [\[ECMA-376\]](#).

3.3.1.3 SmartTags part

Content Type

application/vnd.ms-powerpoint.smartTags

Root Namespace

not applicable

Source Relationship

<http://schemas.microsoft.com/office/2006/relationships/smartTags>

An instance of this part type contains the smart data information for all smart tag-referring text contained within the presentation.

A package shall contain at most one SmartTag part, and that part shall be the target of an explicit relationship from the Presentation part ("[\[ECMA-376\]](#) Part 1 §13.3.6; Presentation Part").

The SmartTags part is binary information that is defined in the PowerPoint 97-2003 Binary File Format (.ppt) Structure Specification ("[\[MS-PPT\]](#) Section 2.11.28; SmartTagStore11Container").

A SmartTags part shall be located within the package containing the source relationship (expressed syntactically, the **TargetMode** attribute of the **Relationship** element shall be *Internal*).

A SmartTags part shall not have implicit or explicit relationships to any other part defined by ECMA-376 Office Open XML File Formats [\[ECMA-376\]](#).

3.4 Shared

This section contains additional information used to more fully describe how Office implements ECMA-376 Office Open XML File Formats [\[ECMA-376\]](#).

3.4.1 Additional Parts

The subclauses subordinate to this one describe in detail each of the shared part types in addition to those listed in ECMA-376 Office Open XML File Formats ("[\[ECMA-376\]](#) Part 1 §15; Shared").

3.4.1.1 Embedded Control Persistence Binary Data Part

Content Type

Binary data representing various properties of an ActiveX control, a standard COM picture object, or a standard COM font object which are persisted using `persistStorage`, `persistStream`, or `persistStreamInit`, as indicated by the persistence attribute of the corresponding Embedded Control Persistence part ("[\[ECMA-376\]](#) Part 1 §15.2.8; Embedded Control Persistence Part").

[Note: The content of the binary data shall be solely determined by the corresponding object. end note]

Root Namespace

not applicable

Source Relationship

<http://schemas.microsoft.com/office/2006/relationships/activeXControlBinary>

An instance of this part contains information about an embedded control in the package. This information is provided by the specified control when asked to persist.

A package is permitted to contain one or more Embedded Control Persistence Binary Data parts, and each such part shall be the target of an explicit relationship in an Embedded Control Persistence ("[\[ECMA-376\]](#) Part 1 §15.2.8; Embedded Control Persistence Part") part-relationship item in a WordprocessingML package; a Worksheet part ("[\[ECMA-376\]](#) Part 1 §12.3.24; Worksheet Part") in a SpreadsheetML package; or a Handout Master ("[\[ECMA-376\]](#) Part 1 §13.3.3; Handout Master Part"), Notes Master ("[\[ECMA-376\]](#) Part 1 §13.3.4; Notes Master Part"), Notes Slide ("[\[ECMA-376\]](#) Part 1 §13.3.5; Notes Slide Part"), Slide ("[\[ECMA-376\]](#) Part 1 §13.3.8; Slide Part"), Slide Layout ("[\[ECMA-376\]](#) Part 1 §13.3.9; Slide Layout Part"), or Slide Master ("[\[ECMA-376\]](#) Part 1 §13.3.10; Slide Master Part") part-relationship item in a PresentationML package.

The content type of this part shall determine the internal format and contents of the embedded control.

[Example: The following example shows the persistence that could be used for an embedded ActiveX control within a WordprocessingML document:

```
<ax:ocx ax:classid="{C74190B6-8589-11D1-B16A-00C0F0283628}" ax:license="9368265E-85FE-11d1-8BE3-0000F8754DA1" ax:persistence="persistStorage" r:id="rId1"
xmlns:ax="http://schemas.microsoft.com/office/2006/activeX"
xmlns:r="http://schemas.openxmlformats.org/officeDocument/2006/relationships"/>
```

The relationship type for rId1 is:

<http://schemas.microsoft.com/office/2006/relationships/activeXControlBinary>

The content of the part referenced by rId1 could be any binary data that can be interpreted by the corresponding control. end example]

An Embedded Control Persistence Binary Data part shall be located within the package containing the source relationship (expressed syntactically, the **TargetMode** attribute of the **Relationship** element shall be *Internal*).

An Embedded Control Persistence Binary Data part shall not have any implicit or explicit relationships to other parts defined by ECMA-376 Office Open XML File Formats [\[ECMA-376\]](#).

3.4.1.2 Quick Access Toolbar Customizations Part

Content Type

application/xml

Root Namespace

<http://schemas.microsoft.com/office/2006/01/customui>

Source Relationship

<http://schemas.microsoft.com/office/2006/relationships/ui/userCustomization>

An instance of this part type contains information about the quick access toolbar customizations ([\[MS-CUSTOMUI\]](#)) specific to this package.

[Example: A user customized the quick access toolbar for his WordprocessingML document to contain the UI controls that they commonly use. end example]

A package is permitted to contain at most one Quick Access Toolbar Customizations part, and that part shall be the target of a relationship in the package-relationship item for the document.

[Example: The following package part-relationship item contains a relationship to a Quick Access Toolbar Customizations part, which is stored in the ZIP item /userCustomization/customUI.xml:

```
<Relationships xmlns="...">
  <Relationship Id="rId2"
    Type="http://.../2006/relationships/ui/userCustomization"
    Target="/userCustomization/customUI.xml" />
</Relationships>
```

end example]

The root element for a part of this content type shall be **customUI**.

[Example: The following Quick Access Toolbar Customizations content markup would specify that the control with ID *SpellingAndGrammar* should be added to the quick access toolbar for the package:

```
<mso:customUI xmlns:mso="http://schemas.microsoft.com/office/2006/01/customui">
<mso:ribbon>
<mso:qat>
<mso:documentControls>
<mso:control idQ="mso:SpellingAndGrammar" visible="true" />
</mso:documentControls>
</mso:qat>
</mso:ribbon>
</mso:customUI>
```

end example]

A Quick Access Toolbar Customizations part shall be located within the package containing the source relationship (expressed syntactically, the **TargetMode** attribute of the **Relationship** element shall be *Internal*).

A Quick Access Toolbar Customizations part shall not have implicit or explicit relationships to any other part defined by ECMA-376 Office Open XML File Formats [\[ECMA-376\]](#).

3.4.1.3 Ribbon Extensibility Part

Content Type

application/xml

Root Namespace

http://schemas.microsoft.com/office/2006/01/customui

Source Relationship

http://schemas.microsoft.com/office/2006/relationships/ui/extensibility

An instance of this part type contains information about the ribbon customizations ([\[MS-CUSTOMUI\]](#)) specific to this package.

[Example: A SpreadsheetML document that represents a timecard could contain custom UI controls to guide the user in filling out the timecard. end example]

A package is permitted to contain at most one Ribbon Extensibility part, and that part shall be the target of a relationship in the package-relationship item for the document.

[Example: The following package part-relationship item contains a relationship to a Ribbon Extensibility part, which is stored in the ZIP item /customUI/customUI.xml:

```
<Relationships xmlns="...">
<Relationship Id="rId5"
Type="http://.../2006/relationships/ui/extensibility"
Target="/customUI/customUI.xml" />
</Relationships>
```

end example]

The root element for a part of this content type shall be **customUI**.

[Example: The following Ribbon Extensibility content markup would specify that the ribbon tab with ID *TabHome* should be hidden for the containing package:

```
<customUI xmlns="http://schemas.microsoft.com/office/2006/01/customui">
<ribbon>
<tabs>
<tab idMso="TabHome" visible="false" />
</tabs>
</ribbon>
</customUI>
```

end example]

A Ribbon Extensibility part shall be located within the package containing the source relationship (expressed syntactically, the **TargetMode** attribute of the **Relationship** element shall be *Internal*).

A Ribbon Extensibility part is permitted to have explicit relationships to the following parts defined by ECMA-376 Office Open XML File Formats [\[ECMA-376\]](#):

Image Part ("[\[ECMA-376\]](#) Part 1 §15.2.13; Image Part")

3.5 Office Well Defined Custom XML Parts

Office reads and writes a set of well-defined Custom XML Parts. Custom XML Parts, in general, are described in Custom XML Data Storage Part ("[\[ECMA-376\]](#) Part 1 §15.2.4; Custom XML Data Storage Part") and Custom XML Data Properties ("[\[ECMA-376\]](#) Part 4 §7.5; Custom XML Data Properties"). In addition to implementing the relevant portions of ECMA-376 Office Open XML File Formats [\[ECMA-376\]](#), Office understands a predefined set of schemas when applied to Custom XML Parts.

This clause and its subordinate subclauses describe the structure and content of these well-defined parts.

[Note: For convenience, information from those subclauses is summarized in the following table:

| Part | Root Element | Namespace | Ref |
|-----------------------------------|-----------------------|---|---|
| Cover Page Properties | coverPageProperties | http://schemas.microsoft.com/office/2006/coverPageProps | §3.5.1, Cover Page Properties |
| Content Type Schema | contentTypeSchema | http://schemas.microsoft.com/office/2006/metadata/contentType | §3.5.2, Content Type Schemas |
| Custom Document Information Panel | customPropertyEditors | http://schemas.microsoft.com/office/2006/customDocumentInformationPanel | §3.5.3, Custom Document Information Panel |
| Custom XSN | customXsn | http://schemas.microsoft.com/office/2006/metadata/customXsn | §3.5.4, Custom XSN |
| Long Properties | longProperties | http://schemas.microsoft.com/office/2006/metadata/longProperties | §3.5.5, Long Properties |

end note]

3.5.1 Cover Page Properties

The Cover Page Properties is comprised of a Custom XML Data Storage Part ("[\[ECMA-376\]](#) Part 1 §15.2.4; Custom XML Data Storage Part") which contains the Cover Page Properties information, and a Custom XML Data Storage Properties Part ("[\[ECMA-376\]](#) Part 1 §15.2.5; Custom XML Data Storage Properties Part") which contains the set of properties for the custom XML data.

The XML contents of the data storage part conform to the schema defined in Cover Page Properties Schema ([§3.5.1.1, Cover Page Properties Schema](#)).

The root element of the Custom XML Data Storage Part shall be CoverPageProperties ([§3.5.1.1.1.6, CoverPageProperties](#)).

The Associated XML Schema ("[\[ECMA-376\]](#) Part 4 §7.5.2.2; schemaRef") for this Custom XML Data Storage Part shall be "http://schemas.microsoft.com/office/2006/coverPageProps".

3.5.1.1 Cover Page Properties Schema

Cover page properties define a set of document properties available for use on a Word cover page.

3.5.1.1.1 Elements

3.5.1.1.1.1 Abstract (Document Abstract)

This element specifies an abstract of the document content.

| Parent Elements |
|---|
| CoverPageProperties (§3.5.1.1.1.6, CoverPageProperties) |

3.5.1.1.1.2 CompanyAddress (Company Address)

This element specifies the address of the company to be used in the document.

| Parent Elements |
|---|
| CoverPageProperties (§3.5.1.1.1.6, CoverPageProperties) |

3.5.1.1.1.3 CompanyEmail (Company Email Address)

This element specifies the e-mail address of the company to be used in the document.

| Parent Elements |
|---|
| CoverPageProperties (§3.5.1.1.1.6, CoverPageProperties) |

3.5.1.1.1.4 CompanyFax (Company Fax Number)

This element specifies the fax number of the company to be used in the document.

| |
|---|
| Parent Elements |
| CoverPageProperties (§3.5.1.1.1.6, CoverPageProperties) |

3.5.1.1.1.5 CompanyPhone (Company Phone Number)

This element specifies the phone number of the company to be used in the document.

| |
|---|
| Parent Elements |
| CoverPageProperties (§3.5.1.1.1.6, CoverPageProperties) |

3.5.1.1.1.6 CoverPageProperties (Cover Page Properties)

This element is the parent element of properties that are typically used for a document cover page.

| Child Elements | Subclause |
|---|--|
| Abstract (Document Abstract) | §3.5.1.1.1.1, Abstract |
| CompanyAddress (Company Address) | §3.5.1.1.1.2, CompanyAddress |
| CompanyEmail (Company Email Address) | §3.5.1.1.1.3, CompanyEmail |
| CompanyFax (Company Fax Number) | §3.5.1.1.1.4, CompanyFax |
| CompanyPhone (Company Phone Number) | §3.5.1.1.1.5, CompanyPhone |
| PublishDate (Document Publish Date) | §3.5.1.1.1.7, PublishDate |

The following XML Schema fragment defines the contents of this element:

```
<complexType name="CT_CoverPageProperties">
  <sequence>
    <element name="PublishDate" type="ST_PublishDate"/>
    <element name="Abstract" type="xsd:string"/>
    <element name="CompanyAddress" type="xsd:string"/>
    <element name="CompanyPhone" type="xsd:string"/>
    <element name="CompanyFax" type="xsd:string"/>
    <element name="CompanyEmail" type="xsd:string"/>
  </sequence>
</complexType>
```

3.5.1.1.1.7 PublishDate (Document Publish Date)

Specifies the date this document was published.

The possible values for this element are defined by the ST_PublishDate simple type (§3.5.1.1.2.1, [ST_PublishDate](#)).

| |
|---|
| Parent Elements |
| CoverPageProperties (§3.5.1.1.1.6, CoverPageProperties) |

The following XML Schema fragment defines the contents of this element:

```
<simpleType name="ST_PublishDate">  
  <union memberTypes="xsd:date xsd:dateTime xsd:string"/>  
</simpleType>
```

3.5.1.1.2 Simple Types

This is the complete list of simple types in the <http://schemas.microsoft.com/office/2006/coverPageProps> namespace.

3.5.1.1.2.1 ST_PublishDate (Publish Date Value)

The publish date may be specified in either the XML Schema Date format, the XML Schema DateTime format, or simply as a string.

This simple type is a union of the following types:

The XML Schema date datatype.

The XML Schema dateTime datatype.

The XML Schema string datatype.

| Referenced By |
|--|
| PublishDate (§3.5.1.1.1.7, PublishDate) |

The following XML Schema fragment defines the contents of this simple type:

```
<simpleType name="ST_PublishDate">  
  <union memberTypes="xsd:date xsd:dateTime xsd:string"/>  
</simpleType>
```

3.5.2 Content Type Schemas

The Content Type Schemas is comprised of a Custom XML Data Storage Part ("[\[ECMA-376\]](#) Part 1 §15.2.4; Custom XML Data Storage Part") which contains the Content Type Schemas information, and a Custom XML Data Storage Properties Part ("[\[ECMA-376\]](#) Part 1 §15.2.5; Custom XML Data Storage Properties Part") which contains the set of properties for the custom XML data.

The XML contents of the data storage part conform to the schema defined in Content Type Schemas Schema ([§3.5.2.1, Content Type Schemas Schema](#)).

The root element of the Custom XML Data Storage Part shall be contentTypeSchema ([§3.5.2.1.1.1, contentTypeSchema](#)).

The Associated XML Schema ("[\[ECMA-376\]](#) Part 4 §7.5.2.2; schemaRef") for this Custom XML Data Storage Part shall be "http://schemas.microsoft.com/office/2006/metadata/contentType".

3.5.2.1 Content Type Schemas Schema

Content Type Schemas define the general look and composition of UI elements presented in a Document Information Panel. Information in the content type schema is derived from a content type associated with documents on Windows SharePoint Services. A Content Type Schema is used in conjunction with a CustomXSN element (§3.5.4.1.1.2, [customXsn](#)) data to fully define the behaviours of the Document Information Panel.

3.5.2.1.1 Elements

3.5.2.1.1.1 contentTypeSchema (Schema for Content Type)

The attributes and children of this element collectively specify a schema for the custom XML data part that specifies properties related to the content type associated with the document on Windows SharePoint Services. Each child of this element is an `xsd:schema` element, possibly decorated with attributes from the `http://schemas.microsoft.com/office/2006/metadata/properties/metaAttributes` namespace, that describes one or more elements that appear in that custom XML data part.

In the following description, let the term 'content type' refer specifically to the root element of the Content Type Definition Type as described in Collaborative Application Markup Language (CAML) Structure Specification ([\[MS-WSSCAML\]](#) Subclause 2.4.1.1).

The **contentTypeSchema** element shall contain an **xsd:schema** child element which has an **ma:root** attribute (§3.5.2.2.1, [Shared Attributes](#)) with a value of *true*. This **xsd:schema** must have a **targetNamespace** attribute whose value is set to `http://schemas.microsoft.com/office/2006/metadata/properties`. The **xsd:schema** must declare and import any namespaces used by its child elements. It must also have an **ma:fieldsID** attribute (§3.5.2.2.1, [Shared Attributes](#)).

Additionally, this **xsd:schema** element must declare an element with a **name** attribute whose value is *properties* and which uses the following structure. The children of the **xsd:all** element are not shown, but instead described by the text that follows.

```
<xsd:element name="properties">
  <xsd:complexType>
    <xsd:sequence>
      <xsd:element name="documentManagement">
        <xsd:complexType>
          <xsd:all>
            ...
          </xsd:all>
        </xsd:complexType>
      </xsd:element>
    </xsd:sequence>
  </xsd:complexType>
</xsd:element>
```

Let the term "fields" denote the list of all **Field** elements that are children of the **Fields** element, which is in turn a child of the **ContentType** element in the content type. The **Field** elements are the fields used in the content type, as described in Collaborative Application Markup Language (CAML) Structure ([\[MS-WSSCAML\]](#) Subclause 2.3.2.6). Furthermore, let the term "filtered fields" denote the list of all filtered fields to be those **Field** elements from the fields that satisfy all of the following conditions:

The value of the **Type** attribute is not *Computed*, *Calculated*, or *WorkflowStatus*.

The value of the **Name** attribute is not *Modified_x0020_By*, *Created_x0020_By*, *Modified*, *Created* or *FileLeafRef*.

The value of the **StaticName** attribute is not *Title*, *Subject*, *_Author*, *Keywords*, *_Comments*, *_Category*, or *ContentType*.

The **xsd:all** element from the preceding structure must contain an **xsd:element** element for each **Field** element in the filtered fields set. This **xsd:element** must have a **ref** attribute. The value of the **ref** attribute must be a qualified reference to a type whose name is the value of the **StaticName** attribute of the **Field** element and which resides in the namespace identified by the **SourceID** attribute of the **Field** element. Furthermore, if the **Required** attribute is not present on the **Field** element; or if the attribute is present but its value is not *TRUE*; or if the value of the **Type** attribute is *MultiChoice* or *LookupMulti*, then a **minOccurs** attribute with value of *0* must be present on the **xsd:element** element.

For each unique string that appears as the value of the **SourceID** attribute on a **Field** element in the fields, the **contentTypeSchema** element must contain an **xsd:schema** child whose **targetNamespace** attribute has that same value. Each **xsd:schema** must contain one **xsd:element** element for each **Field** whose **SourceID** attribute matches the **targetNamespace** attribute of the **xsd:schema**.

Each **xsd:element** element must have a **name** attribute whose value is the value of the **StaticName** attribute on the corresponding **Field** element. Each **xsd:element** element must have an **ma:index** attribute (§3.5.2.2, [Metadata Attributes](#)) whose value is the number of **Field** elements that appear before the corresponding **Field** element within the **Fields** element in the content type. If the **Required** attribute is not present on the corresponding **Field** element; the **Required** attribute is present but its value is not *TRUE*; or the value of the **Type** attribute is *MultiChoice* or *LookupMulti*, then a nullable attribute with value of *true* must be present on the **xsd:element** element.

The following attributes can appear on each **xsd:element** element: **ma:displayName** (§3.5.2.2, [Metadata Attributes](#)); **ma:decimals** (§3.5.2.2, [Metadata Attributes](#)); **ma:default** (§3.5.2.2, [Metadata Attributes](#)); **ma:description** (§3.5.2.2, [Metadata Attributes](#)); **ma:format** (§3.5.2.2, [Metadata Attributes](#)); **ma:hidden** (§3.5.2.2, [Metadata Attributes](#)); **ma:LCID** (§3.5.2.2, [Metadata Attributes](#)); **ma:list** (§3.5.2.2, [Metadata Attributes](#)); **ma:internalName** (§3.5.2.2, [Metadata Attributes](#)); **ma:readOnly** (§3.5.2.2, [Metadata Attributes](#)); **ma:showField** (§3.5.2.2, [Metadata Attributes](#)); **ma:percentage** (§3.5.2.2, [Metadata Attributes](#)); **ma:web** (§3.5.2.2, [Metadata Attributes](#)); **ma:requiredMultiChoice** (§3.5.2.2, [Metadata Attributes](#)).

The **contentTypeSchema** element must have an **xsd:schema** child whose **targetNamespace** attribute has the value *http://schemas.openxmlformats.org/package/2006/metadata/core-properties*.

| Attributes | Description |
|---|---|
| _ (Reserved) | Shall be empty. The possible values for this attribute are defined by the XML Schema anySimpleType datatype. |
| _ (Reserved) Namespace: http://schemas.microsoft.com/office/2006/metadata/properties/metaAttributes | Shall be empty. The possible values for this attribute are defined by the XML |

| Attributes | Description |
|--|--|
| | Schema anySimpleType datatype. |
| <p>contentTypeDescription (Content Type Description) Namespace: http://schemas.microsoft.com/office/2006/metadata/properties/metaAttributes</p> | <p>Shall be the same value as the Description attribute of the ContentType element (as described in Collaborative Application Markup Language (CAML) Structure ([MS-WSSCAML] Subclause 2.4.1.1) for the content type associated with this document.</p> <p>The possible values for this attribute are defined by the XML Schema string datatype.</p> |
| <p>contentTypeID (Content Type ID) Namespace: http://schemas.microsoft.com/office/2006/metadata/properties/metaAttributes</p> | <p>Identifies the content type associated with this document.</p> <p>The possible values for this attribute are defined by the ST_ContentTypeId simple type (§3.5.2.2.1. ST_ContentTypeId).</p> |
| <p>contentTypeName (Content Type Name) Namespace: http://schemas.microsoft.com/office/2006/metadata/properties/metaAttributes</p> | <p>Must be the same value as the Name attribute of the ContentType element (as described in Collaborative Application Markup Language (CAML) Structure ([MS-WSSCAML] Subclause 2.4.1.1)) for the content type associated with this document.</p> <p>The possible values for this attribute are defined by the XML Schema string datatype.</p> |
| <p>contentTypeScope (Content Type Scope) Namespace: http://schemas.microsoft.com/office/2006/metadata/properties/metaAttributes</p> | <p>Shall be empty.</p> <p>The possible values for this attribute are defined by the XML Schema string datatype.</p> |
| <p>contentTypeVersion (Content Type Version) Namespace:</p> | <p>Shall be the same value as the Version attribute of the ContentType</p> |

| Attributes | Description |
|---|---|
| <p>http://schemas.microsoft.com/office/2006/metadata/properties/metaAttributes</p> | <p>element (as described in Collaborative Application Markup Language (CAML) Structure ([MS-WSSCAML] Subclause 2.4.1.1) for the content type associated with this document.</p> <p>The possible values for this attribute are defined by the ST_IntNonNegative simple type (§3.5.2.2.2.2, ST_IntNonNegative).</p> |
| <p>versionID (Version ID) Namespace: http://schemas.microsoft.com/office/2006/metadata/properties/metaAttributes</p> | <p>A string hash used to determine if the definition of the content type associated with this document has changed since the last time the content type was applied to the document.</p> <p>The value is computed as an MD5 hash of the substring that represents the ContentType element (from <ContentType> to </ContentType>, inclusive) within the SOAP result of the GetListContentType Web service request, as described in Lists Web Service Protocol Specification ([MS-LISTSWS] Subclause 3.1.4.17).</p> <p>The possible values for this attribute are defined by the XML Schema string datatype.</p> |

The following XML Schema fragment defines the contents of this element:

```
<complexType name="CT_ContentTypeSchema">
  <sequence>
    <element ref="xsd:schema" maxOccurs="unbounded"/>
  </sequence>
  <attribute name="_"/>
  <attribute ref="ma:_"/>
  <attribute ref="ma:contentTypeName"/>
  <attribute ref="ma:contentTypeID"/>
</complexType>
```

```

<attribute ref="ma:contentTypeVersion"/>
<attribute ref="ma:contentTypeDescription"/>
<attribute ref="ma:contentTypeScope"/>
<attribute ref="ma:versionID"/>
</complexType>

```

3.5.2.2 Metadata Attributes

Metadata attributes are used to provide additional information for each of the schema children of the Content Type Schemas ([§3.5.2.1, Content Type Schemas Schema](#)).

3.5.2.2.1 Shared Attributes (Content Type Schemas)

The schemas referred to here (including the root schema and core schema) are the child schemas described in Content Type Schemas ([§3.5.2.1, Content Type Schemas Schema](#), 3.5.2.1, Content Type Schemas Schema).

| Attributes | Description |
|--------------------------------------|--|
| decimals (Decimal Digits) | Specifies the number of fractional digits to display on the property editing surface for the property corresponding to an xsd:element in a schema other than the root schema whose content model is an xsd:restriction based on {http://schemas.microsoft.com/office/2006/documentManagement/types}Currency or {http://schemas.microsoft.com/office/2006/documentManagement/types}Number. Office handles the integer values 0-9 and <i>auto</i> . If applied to any other element, this attribute should be ignored. The possible values for this attribute are defined by the XML Schema string datatype. |
| default (Default Value) | When applied to an xsd:element in a schema other than the root schema or the core schema, specifies the initial value of the property corresponding to the xsd:element . When applied to an xsd:element in a schema other than the root schema or core schema whose content model is an xsd:restriction based on {http://schemas.microsoft.com/office/2006/documentManagement/types}DateTime, if set to [<i>today</i>], specifies that the initial value of the property corresponding to the xsd:element should be set to the current date and time. When applied to an xsd:element in a schema other than the root schema or core schema whose content model is an xsd:restriction based on {http://schemas.microsoft.com/office/2006/documentManagement/types}Boolean, Office interprets <i>1</i> as logical true and all other values as logical false in determining the initial value of the property corresponding to this xsd:element . If applied to any other element, this attribute should be ignored. The possible values for this attribute are defined by the XML Schema string datatype. |
| description (Description) | When applied to an xsd:element in a schema other than the root schema, specifies information displayed as a part of the tooltip on the property editing surface for the property corresponding to this xsd:element . Office displays the first 512 characters of the concatenation of the property name, the ":" delimiter, and the description as the tooltip. If applied to any other element, this attribute should be ignored. The possible values for this attribute are defined by the XML Schema string datatype. |
| displayName (Display Name) | When applied to an xsd:element in a schema other than the root schema or core schema, specifies the text displayed on the property editing surface and as a part of the tooltip for the property corresponding to the xsd:element . |

| Attributes | Description |
|-------------------------------------|--|
| | <p>If applied to any other element, this attribute should be ignored.</p> <p>The possible values for this attribute are defined by the XML Schema string datatype.</p> |
| fieldsID (Fields ID) | <p>This attribute should be ignored.</p> <p>The possible values for this attribute are defined by the XML Schema string datatype.</p> |
| format (Format) | <p>When applied to an xsd:element in a schema other than the root schema or core schema whose content model is an xsd:restriction based on {http://schemas.microsoft.com/office/2006/documentManagement/types}DateTime, if set to <i>DateTime</i>, specifies that the property value displayed in the property editing surface for the property corresponding to this xsd:element should include both the date and time, and if not present or set to any other value, specifies that the property value displayed in the property editing surface for the property corresponding to this xsd:element should include only the date.</p> <p>If applied to any other element, this attribute should be ignored.</p> <p>The possible values for this attribute are defined by the XML Schema string datatype.</p> |
| hidden (Hidden) | <p>When applied to an xsd:element in a schema other than the root schema or core schema, if set to <i>true</i>, specifies that the property corresponding to this xsd:element should not be presented for editing on the property editing surface.</p> <p>If applied to any other element, this attribute should be ignored.</p> <p>The possible values for this attribute are defined by the XML Schema string datatype.</p> |
| index (Ordering Index) | <p>The value of this attribute is used to determine the ordering on a property editing surface of xsd:elements bearing this attribute from schemas other than the root schema. First, the xsd:elements are broken into groups, as follows. The first group is composed of any xsd:element that:</p> <ul style="list-style-type: none"> is not the description element in the core properties, and is not a simpleType restriction based on {http://schemas.microsoft.com/office/2006/documentManagement/types}Not e, and is not a complex content based on any of {http://schemas.microsoft.com/office/2006/documentManagement/types}MultiChoice, {http://schemas.microsoft.com/office/2006/documentManagement/types}MultiChoiceFillIn, or {http://schemas.microsoft.com/office/2006/documentManagement/types}MultiChoiceLookup. <p>The second group is composed of the remaining xsd:elements bearing this attribute from schemas other than the root schema. Within each group the order of the index attribute values is ascending.</p> <p>If an xsd:element in a schema other than the root schema or core schema does not have this attribute, it will not be presented to the user for editing on the property editing surface.</p> <p>If applied to any other element, this attribute should be ignored.</p> <p>The possible values for this attribute are defined by the ST_IntNonNegative simple type (§3.5.2.2.2.2, ST_IntNonNegative).</p> |
| internalName (Internal Name) | <p>Specifies an internal name.</p> <p>This attribute shall be present on xsd:elements in a schema other than the root</p> |

| Attributes | Description |
|--|---|
| | <p>schema or core schema. If applied to any other element, this attribute should be ignored.</p> <p>The possible values for this attribute are defined by the XML Schema string datatype.</p> |
| LCID (LCID) | <p>When applied to an xsd:element in a schema other than the root schema or core schema whose content model is an xsd:restriction based on {http://schemas.microsoft.com/office/2006/documentManagement/types}Currency, specifies the locale identifier as specified in the Windows Language Code Identifier (LCID) Reference [MS-LCID] to determine the currency symbol used in the display of the property corresponding to this xsd:element in the property editing surface.</p> <p>If applied to any other element, this attribute should be ignored.</p> <p>The possible values for this attribute are defined by the XML Schema int datatype.</p> |
| list (List Identifier) | <p>Shall be present on xsd:elements for which neither the hidden nor read-only attributes are set to <i>true</i> in a schema other than the root schema or core schema whose content model is an xsd:restriction based on {http://schemas.microsoft.com/office/2006/documentManagement/types}Lookup or {http://schemas.microsoft.com/office/2006/documentManagement/types}MultiLookup. When present on such an element, specifies the list from which to get data for display of the property corresponding to this xsd:element in the property editing surface.</p> <p>Office will populate this data when the save location of the document is a site that implements the Lists Web Service Protocol [MS-LISTSWS] and the value of this attribute is a valid GUID enclosed in braces corresponding to the ID of a list on the site.</p> <p>If applied to any other element, this attribute should be ignored.</p> <p>The possible values for this attribute are defined by the XML Schema string datatype.</p> |
| percentage (Show as Percentage) | <p>When applied to an xsd:element in a schema other than the root schema or core schema whose content model is an xsd:restriction based on {http://schemas.microsoft.com/office/2006/documentManagement/types}Currency or {http://schemas.microsoft.com/office/2006/documentManagement/types}Number, if set to <i>TRUE</i>, specifies that the property corresponding to this xsd:element should be displayed as a percentage in the property editing surface, and if not present or set to any other value, specifies that the property corresponding to this xsd:element should not be displayed as a percentage in the property editing surface.</p> <p>If applied to any other element, this attribute should be ignored.</p> <p>The possible values for this attribute are defined by the XML Schema string datatype.</p> |
| readOnly (Read Only) | <p>When applied to an xsd:element in a schema other than the root schema or core schema, if set to <i>true</i>, specifies that the property corresponding to this xsd:element should not be presented for editing on the property editing surface.</p> <p>If applied to any other element, this attribute should be ignored.</p> <p>The possible values for this attribute are defined by the XML Schema string datatype.</p> |
| requiredMultipleChoice (Required Multiple Choice) | <p>When applied to an xsd:element in a schema other than the root schema or core schema whose content model is an xsd:restriction based on {http://schemas.microsoft.com/office/2006/documentManagement/types}MultipleChoice, {http://schemas.microsoft.com/office/2006/documentManagement/types}MultipleChoiceFill, or {http://schemas.microsoft.com/office/2006/documentManagement/types}MultipleChoiceLookup, if set to <i>true</i>, specifies that the property editing surface should indicate an error if no choices are selected for the property corresponding to the xsd:element.</p> <p>If applied to any other element, this attribute should be ignored.</p> <p>The possible values for this attribute are defined by the XML Schema string datatype.</p> |
| root (Root) | <p>Shall be set to <i>true</i> on the root schema element described in Content Type Schemas (§3.5.2.1, Content Type Schemas Schema, 3.5.2.1, Content Type Schemas Schema) for</p> |

| Attributes | Description |
|---------------------------------------|---|
| Schema) | <p>the http://schemas.microsoft.com/office/2006/contentTypeSchema namespace and shall not be applied to any other element.</p> <p>The possible values for this attribute are defined by the <code>ST_TrueOnly</code> simple type (§3.5.2.2.2.3, ST_TrueOnly).</p> |
| showField (Displayed Field) | <p>Shall be present on xsd:elements for which neither the hidden nor read-only attributes are set to <i>true</i> in a schema other than the root schema or core schema whose content model is an xsd:restriction based on <code>{http://schemas.microsoft.com/office/2006/documentManagement/types}Lookup</code> or <code>{http://schemas.microsoft.com/office/2006/documentManagement/types}MultiLookup</code>. When applied to such an element, specifies the text displayed for the lookup options in the property editing surface for the property corresponding to the xsd:element.</p> <p>Office handles values corresponding to the Name attribute of a field as specified in the response from a GetList request as specified in the Lists Web Service Protocol ([MS-LISTSWS] Subclause 3.1.4.14).</p> <p>If applied to any other element, this attribute should be ignored.</p> <p>The possible values for this attribute are defined by the XML Schema string datatype.</p> |
| web (Site Identifier) | <p>When applied to an xsd:element for which neither the hidden nor read-only attributes are set to <i>true</i> in a schema other than the root schema or core schema whose content model is an xsd:restriction based on <code>{http://schemas.microsoft.com/office/2006/documentManagement/types}Lookup</code> or <code>{http://schemas.microsoft.com/office/2006/documentManagement/types}MultiLookup</code>, specifies the site of the list from which to get data for display of the property corresponding to this xsd:element in the property editing surface.</p> <p>If applied to any other element, this attribute should be ignored.</p> <p>The possible values for this attribute are defined by the <code>ST_UniqueIdentifierWithoutBraces</code> simple type (§3.5.2.2.2.4, ST_UniqueIdentifierWithoutBraces).</p> |

The following XML Schema fragment defines the contents of this element:

```
<complexType name="CT_Dummy">
  <attribute name="decimals" type="xsd:string"/>
  <attribute name="default" type="xsd:string"/>
  <attribute name="description" type="xsd:string"/>
  <attribute name="displayName" type="xsd:string"/>
  <attribute name="fieldsID" type="xsd:string"/>
  <attribute name="format" type="xsd:string"/>
  <attribute name="hidden" type="xsd:string"/>
  <attribute name="index" type="ST_IntNonNegative"/>
  <attribute name="internalName" type="xsd:string"/>
  <attribute name="LCID" type="xsd:int"/>
  <attribute name="list" type="xsd:string"/>
  <attribute name="percentage" type="xsd:string"/>
  <attribute name="readOnly" type="xsd:string"/>
  <attribute name="requiredMultiChoice" type="xsd:string"/>
  <attribute name="root" type="ST_TrueOnly"/>
  <attribute name="showField" type="xsd:string"/>
  <attribute name="web" type="ST_UniqueIdentifierWithoutBraces"/>
</complexType>
```

3.5.2.2.2 Simple Types

This is the complete list of simple types in the <http://schemas.microsoft.com/office/2006/metadata/properties/metaAttributes> namespace.

3.5.2.2.2.1 ST_ContentTypeId (Content Type ID)

This simple type's contents are a restriction of the XML Schema string datatype.

This simple type also specifies the following restrictions:

This simple type's contents shall match the following regular expression pattern: `0x([0-9A-Fa-f][1-9A-Fa-f]|[1-9A-Fa-f][0-9A-Fa-f]|00[0-9A-Fa-f]{32})*`.

This simple type's contents have a maximum length of 1026 characters.

This simple type's contents have a minimum length of 2 characters.

| Referenced By |
|--|
| contentTypeSchema@contentTypeID (§3.5.2.1.1.1, contentTypeSchema) |

The following XML Schema fragment defines the contents of this simple type:

```
<simpleType name="ST_ContentTypeId">
  <restriction base="xsd:string">
    <pattern value="0x([0-9A-Fa-f][1-9A-Fa-f]|[1-9A-Fa-f][0-9A-Fa-f]|00[0-9A-Fa-f]{32})*" />
    <minLength value="2" />
    <maxLength value="1026" />
  </restriction>
</simpleType>
```

3.5.2.2.2.2 ST_IntNonNegative (Non-Negative Integer)

This simple type's contents are a restriction of the XML Schema int datatype.

This simple type also specifies the following restrictions:

This simple type has a minimum value of greater than or equal to 0.

| Referenced By |
|---|
| contentTypeSchema@contentTypeVersion (§3.5.2.1.1.1, contentTypeSchema); Shared Attributes@index (§3.5.2.2.1, Shared Attributes) |

The following XML Schema fragment defines the contents of this simple type:

```
<simpleType name="ST_IntNonNegative">
  <restriction base="xsd:int">
    <minInclusive value="0" />
  </restriction>
```

</simpleType>

3.5.2.2.2.3 ST_TrueOnly (True Only)

This simple type's contents are a restriction of the XML Schema string datatype.

The following are possible enumeration values for this type:

| Enumeration Value | Description |
|-------------------|-------------|
| true () | |

| Referenced By |
|--|
| Shared Attributes@root (§3.5.2.2.1, Shared Attributes) |

The following XML Schema fragment defines the contents of this simple type:

```
<simpleType name="ST_TrueOnly">  
  <restriction base="xsd:string">  
    <enumeration value="true"/>  
  </restriction>  
</simpleType>
```

3.5.2.2.2.4 ST_UniqueIdentifierWithoutBraces (Unique Identifier without Braces)

This simple type's contents are a restriction of the XML Schema string datatype.

This simple type also specifies the following restrictions:

This simple type's contents shall match the following regular expression pattern: `[0-9a-fA-F]{8}\-[0-9a-fA-F]{4}\-[0-9a-fA-F]{4}\-[0-9a-fA-F]{4}\-[0-9a-fA-F]{12}`.

| Referenced By |
|---|
| Shared Attributes@web (§3.5.2.2.1, Shared Attributes) |

The following XML Schema fragment defines the contents of this simple type:

```
<simpleType name="ST_UniqueIdentifierWithoutBraces">  
  <restriction base="xsd:string">  
    <pattern value="[0-9a-fA-F]{8}\-[0-9a-fA-F]{4}\-[0-9a-fA-F]{4}\-[0-9a-fA-F]{4}\-[0-9a-fA-F]{12}"/>  
  </restriction>  
</simpleType>
```

3.5.3 Custom Document Information Panel

The Custom Document Information Panel is comprised of a Custom XML Data Storage Part ("ECMA-376] Part 1 §15.2.4; Custom XML Data Storage Part") which contains the Custom Document Information Panel information, and a Custom XML Data Storage Properties Part ("ECMA-376] Part 1 §15.2.5; Custom XML Data Storage Properties Part") which contains the set of properties for the custom XML data.

The XML contents of the data storage part conform to the schema defined in Custom Document Information Panel Schema ([§3.5.3.1, Custom Document Information Panel Schema](#)).

The root element of the Custom XML Data Storage Part shall be customPropertyEditors ([§3.5.3.1.1.2, customPropertyEditors](#)).

The Associated XML Schema ("ECMA-376] Part 4 §7.5.2.2; schemaRef") for this Custom XML Data Storage Part shall be "http://schemas.microsoft.com/office/2006/customDocumentInformationPanel".

3.5.3.1 Custom Document Information Panel Schema

Custom Document Information Panel information defines the location and behaviors for a customized Document Information Panel based on a standalone XSN file. Unlike a Document Information Panel defined by a Content Type Schema ([§3.5.2.1, Content Type Schemas Schema](#)) and a CustomXSN ([§3.5.4.1, Custom XSN Schema](#)), Custom Document Information Panels need not be associated directly with a server.

3.5.3.1.1 Elements

3.5.3.1.1.1 customPropertyEditor (Custom Property Editor)

This element associates a namespace with the location of an XSN file (as specified by InfoPath Form Template Format Structure Specification [MS-IPFF](#)). The specified XSN file can be used to visually edit the information in a custom XML data part in this document. The XMLNamespace child specifies which custom xml data parts are suitable for editing; the XSNLocation child specifies a path to the XSN file.

| Parent Elements |
|--|
| customPropertyEditors (§3.5.3.1.1.2, customPropertyEditors) |

| Child Elements | Subclause |
|---|--|
| XMLNamespace (Namespace for Property Editor) | §3.5.3.1.1.5, XMLNamespace |
| XSNLocation (Location of XSN File) | §3.5.3.1.1.6, XSNLocation |

The following XML Schema fragment defines the contents of this element:

```
<complexType name="CT_CustomPropertyEditor">
  <sequence>
    <element name="XMLNamespace" type="xsd:anyURI"/>
    <element name="XSNLocation" type="xsd:string"/>
  </sequence>
```

</complexType>

3.5.3.1.1.2 customPropertyEditors (Custom Property Editors List)

This element specifies the list of (and settings for) any XSN files (as specified by InfoPath Form Template Format Structure Specification [\[MS-IPFF\]](#)) that may be associated with this document to edit information in its custom XML data parts.

| Child Elements | Subclause |
|---|--|
| customPropertyEditor (Custom Property Editor) | §3.5.3.1.1.1, customPropertyEditor |
| defaultPropertyEditorNamespace (Default Namespace) | §3.5.3.1.1.3, defaultPropertyEditorNamespace |
| showOnOpen (Show On Open) | §3.5.3.1.1.4, showOnOpen |

The following XML Schema fragment defines the contents of this element:

```
<complexType name="CT_CustomPropertyEditors">
  <sequence>
    <element name="showOnOpen" type="xsd:boolean"/>
    <element name="defaultPropertyEditorNamespace" type="xsd:anyURI"/>
    <element name="customPropertyEditor" type="CT_CustomPropertyEditor"
maxOccurs="unbounded"/>
  </sequence>
</complexType>
```

3.5.3.1.1.3 defaultPropertyEditorNamespace (Default Namespace)

This element specifies the XML namespace that identifies which XSN is shown by default if the user chooses to edit properties contained in the custom XML data parts of this document. If this element is not present, or if the value of this element does not equal the namespace specified in the XmlNamespace element ([§3.5.3.1.1.5, XMLNamespace](#)), the application may choose to display the core properties.

| Parent Elements |
|--|
| customPropertyEditors (§3.5.3.1.1.2, customPropertyEditors) |

3.5.3.1.1.4 showOnOpen (Show On Open)

This element specifies whether the user should be presented with a surface to edit either the core properties or properties in one of the custom xml data parts in this document, as informed by the defaultPropertyEditorNamespace. A value of *true* indicates that such a surface shall be provided; any other value indicates such a surface shall not be provided. If this element is not present, a surface shall not be provided.

| Parent Elements |
|--|
| customPropertyEditors (§3.5.3.1.1.2, customPropertyEditors) |

3.5.3.1.1.5 XMLNamespace (Namespace for Property Editor)

Specifies the root namespace of custom XML data parts that are appropriate for editing by the XSN specified in XSNLocation.

| Parent Elements |
|---|
| customPropertyEditor (§3.5.3.1.1.1, customPropertyEditor) |

3.5.3.1.1.6 XSNLocation (Location of XSN File)

Specifies the path to the XSN file.

| Parent Elements |
|---|
| customPropertyEditor (§3.5.3.1.1.1, customPropertyEditor) |

3.5.4 Custom XSN

The Custom XSN is comprised of a Custom XML Data Storage Part ("ECMA-376 Part 1 §15.2.4; Custom XML Data Storage Part") which contains the Custom XSN information, and a Custom XML Data Storage Properties Part ("ECMA-376 Part 1 §15.2.5; Custom XML Data Storage Properties Part") which contains the set of properties for the custom XML data.

The XML contents of the data storage part conform to the schema defined in Custom XSN Schema (§3.5.4.1, [Custom XSN Schema](#)).

The root element of the Custom XML Data Storage Part shall be customXsn (§3.5.4.1.1.2, [customXsn](#)).

The Associated XML Schema ("ECMA-376 Part 4 §7.5.2.2; schemaRef") for this Custom XML Data Storage Part shall be "http://schemas.microsoft.com/office/2006/metadata/customXsn".

3.5.4.1 Custom XSN Schema

A CustomXSN defines the source location and Document Information Panel behaviors for the document. CustomXSN is used in conjunction with Content Type Schema (§3.5.2.1, [Content Type Schemas Schema](#)) to fully define the behaviours of the Document Information Panel.

3.5.4.1.1 Elements

3.5.4.1.1.1 cached (Cached View)

This element indicates whether the XSN specified by xsnLocation should be used to edit properties in this document. A value of *true* indicates that the XSN shall not be used.

| Parent Elements |
|---|
| customXsn (§3.5.4.1.1.2, customXsn) |

3.5.4.1.1.2 customXsn (Custom XSN)

This element specifies that an XSN file (as specified by InfoPath Form Template Format Structure Specification MS-IPFF) should be presented to the user for editing properties of this document.

| Child Elements | Subclause |
|--|---|
| cached (Cached View) | §3.5.4.1.1.1, cached |
| openByDefault (Open By Default) | §3.5.4.1.1.3, openByDefault |
| xsnLocation (XSN Location) | §3.5.4.1.1.4, xsnLocation |
| xsnScope (Scope) | §3.5.4.1.1.5, xsnScope |

The following XML Schema fragment defines the contents of this element:

```
<complexType name="CT_CustomXsn">
  <sequence>
    <element name="xsnLocation" type="xsd:string"/>
    <element name="cached" type="xsd:string"/>
    <element name="openByDefault" type="xsd:string"/>
    <element name="xsnScope" type="xsd:string"/>
  </sequence>
</complexType>
```

3.5.4.1.1.3 openByDefault (Open By Default)

This element specifies whether the user should be presented with a surface to edit properties of this document, immediately after opening it. A value of *true* indicates that such a surface shall be provided; any other value indicates such a surface shall not be provided. If this element is not present, a surface shall not be provided.

| Parent Elements |
|--|
| customXsn (§3.5.4.1.1.2, customXsn) |

3.5.4.1.1.4 xsnLocation (XSN Location)

This element specifies the location of an XSN file (as specified by InfoPath Form Template Format Structure Specification [\[MS-IPFF\]](#)) to use for editing properties of this document

| Parent Elements |
|--|
| customXsn (§3.5.4.1.1.2, customXsn) |

3.5.4.1.1.5 xsnScope (Scope)

Specifies a path to use when resolving any relative paths that appear within the specified XSN.

| Parent Elements |
|--|
| customXsn (§3.5.4.1.1.2, customXsn) |

3.5.5 Long Properties

The Long Properties is comprised of a Custom XML Data Storage Part ("[\[ECMA-376\]](#) Part 1 §15.2.4; Custom XML Data Storage Part") which contains the Long Properties information, and a Custom XML

Data Storage Properties Part ("ECMA-376 Part 1 §15.2.5; Custom XML Data Storage Properties Part") which contains the set of properties for the custom XML data.

The XML contents of the data storage part conform to the schema defined in Long Properties Schema (§3.5.5.1, Long Properties Schema).

The root element of the Custom XML Data Storage Part shall be LongProperties (§3.5.5.1.1.2, LongProperties).

The Associated XML Schema ("ECMA-376 Part 4 §7.5.2.2; schemaRef") for this Custom XML Data Storage Part shall be "http://schemas.microsoft.com/office/2006/metadata/longProperties".

3.5.5.1 Long Properties Schema

Long properties define a set of properties used to store server property values exceeding 255 characters in length.

3.5.5.1.1 Elements

3.5.5.1.1.1 LongProp (Custom XML Server Property - Long Property)

This element specifies the full value of a custom server property that exceeds 255 characters. This property is written out when a document is roundtripped to binary and back, to ensure that the full value of the custom property is not lost. When the first 255 characters of the value of the **LongProp** agrees with the value of the custom property with the corresponding name, it is assumed that the custom property was not modified when roundtripped; in that case, the **LongProp** is considered to contain the correct, full property value. If instead the first 255 characters of the value of the **LongProp** and the custom property of the same name differ, the custom property is assumed to have the more current (and therefore accurate) value for the property.

| Parent Elements |
|--|
| LongProperties (§3.5.5.1.1.2, LongProperties) |

| Attributes | Description |
|---|---|
| name (Custom XML Server Property Name) | Specifies the name of the custom property. The possible values for this attribute are defined by the XML Schema string datatype. |

3.5.5.1.1.2 LongProperties (Custom XML Server Properties - Long Properties)

This element specifies the full content of custom server properties whose values exceed 255 characters. When a document containing custom server properties is roundtripped to binary and back, any server properties whose values exceed 255 characters can be written out as **LongProperties** to ensure that no data are lost. These long properties are first written when the document is saved to binary (where the custom property values can be truncated).

| Child Elements | Subclause |
|--|------------------------|
| LongProp (Custom XML Server Property - Long Property) | §3.5.5.1.1.1, LongProp |

The following XML Schema fragment defines the contents of this element:

```
<complexType name="CT_LongProperties">
  <sequence>
    <element name="LongProp" minOccurs="0" maxOccurs="unbounded">
      <complexType>
        <simpleContent>
          <extension base="xsd:string">
            <attribute name="name" type="xsd:string"/>
          </extension>
        </simpleContent>
      </complexType>
    </element>
  </sequence>
</complexType>
```

3.6 Office ActiveX Supplemental Information

The subordinate subclauses specify additional semantics written into the Embedded Control Persistence Part ("ECMA-376 Part 1 §15.2.8; Embedded Control Persistent Part") used to implement ActiveX controls in a Word document.

3.6.1 Elements

3.6.1.1 font (Standard COM Font Object)

This element specifies the details of StdFont object (classid CLSID_StdFont, interface IFont) embedded in the property bag (IPersistPropertyBag interface) of an ActiveX control.

[Example: Consider a font object named "FontPropName" embedded in an ActiveX control.

```
<ax:ocx ....>
<ax:ocxPr name="FontPropName">
<ax:font ax:persistence="persistPropertyBag">
<ax:ocxPr ax:name="Name" ax:value="MS Shell Dlg"/>
<ax:ocxPr ax:name="Size" ax:value="12"/>
<ax:ocxPr ax:name="Charset" ax:value="0"/>
<ax:ocxPr ax:name="Weight" ax:value="400"/>
<ax:ocxPr ax:name="Underline" ax:value="0"/>
<ax:ocxPr ax:name="Italic" ax:value="0"/>
<ax:ocxPr ax:name="Strikethrough" ax:value="0"/>
</ax:font>
</ax:ocxPr>
</ax:ocx>
```

In this example, the **persistence** attribute specifies that various properties of the embedded font object are stored using the method `persistPropertyBag`. The property bag is stored as a collection of child **ocxPr** elements. Each **ocxPr** element contains a single property. end example]

More information about the details of `StdFont` object can be found in the Office Forms Binary File Format Structure Specification ("[\[MS-OFORMS\]](#) Section 2.4.9").

| Parent Elements |
|--|
| ocxPr (§3.6.1.3, ocxPr) |

| Child Elements | Subclause |
|--------------------------------|-----------------|
| ocxPr (Object Property) | §3.6.1.3, ocxPr |

| Attributes | Description |
|--|--|
| persistence (Font Object Property Persistence Style (optional)) | Specifies the method used to store properties of the parent element. The possible values for this attribute are defined by the <code>ST_Persistence</code> simple type (§3.6.2.1, ST_Persistence). |
| id () Namespace: .../officeDocument/2006/relationships | Specifies the relationship ID of the relationship to the font object. The specified relationship shall be of type <code>http://schemas.microsoft.com/office/2006/relationships/activeXControlBinary</code> . The target of the relationship points to the internal location where the persisted font data is stored using the <code>IPersistStream</code> , <code>IPersistStreamInit</code> , or <code>IPersistStorage</code> interface, as indicated by the persistence attribute or as determined by the default interface query sequence . The possible values for this attribute are defined by the <code>ST_RelationshipId</code> simple type (" [ECMA-376] Part 4 §7.8.2.1"). |

The following XML Schema fragment defines the contents of this element:

```
<complexType name="CT_Font">
  <sequence>
    <element name="ocxPr" type="CT_OcxPr" minOccurs="0" maxOccurs="unbounded"/>
  </sequence>
  <attribute name="persistence" type="ST_Persistence"/>
  <attribute ref="r:id" use="optional"/>
</complexType>
```

3.6.1.2 ocx (ActiveX Control Data)

This element specifies various information of an ActiveX control embedded in a document.

[Note: This element does not contain placement or application extended properties. The properties stored in this element are those that the ActiveX control can use regardless of container. end note]

[Example: Consider an ActiveX control embedded in a WordprocessingML. Various pieces of information about that control will be specified using the following WordprocessingML:

```
<ax:ocx ax:classid="{FDD0D569-5B7A-4E3D-820C-5C487DB7796C}"
ax:persistence="persistPropertyBag" ...>

<ax:ocxPr ax:name="_Version" ax:value="65536"/>

<ax:ocxPr ax:name="_ExtentX" ax:value="2646"/>

<ax:ocxPr ax:name="_ExtentY" ax:value="1323"/>

<ax:ocxPr ax:name="_StockProps" ax:value="0"/>

...

</ax:ocx>
```

Here, the **classid** attribute holds the class ID of the ActiveX control, {FDD0D569-5B7A-4E3D-820C-5C487DB7796C}. In this example, the **persistence** attribute indicates the persistPropertyBag method for persisting various properties of the control. The property bag is stored as a collection of child **ocxPr** elements. Each **ocxPr** element contains a single property. end example]

| Child Elements | Subclause |
|--------------------------------|---------------------------------|
| ocxPr (Object Property) | §3.6.1.3, ocxPr |

| Attributes | Description |
|--|---|
| classid (ActiveX Control CLSID) | Specifies the GUID of the ClassID of the ActiveX control. The possible values for this attribute are defined by the ST_String simple type (§3.6.2.2, ST_String). |
| license (ActiveX Control License) | Specifies the license string for the ActiveX control. This string is retrieved from the IClassFactory2 interface of the control. The possible values for this attribute are defined by the ST_String simple type (§3.6.2.2, ST_String). |
| persistence (ActiveX Control Property Persistence Style) | Specifies the explicit method used to persist the properties of the ActiveX control. The possible values for this attribute are defined by the ST_Persistence simple type (§3.6.2.1, ST_Persistence). |
| id (ActiveX Control Binary Data) Namespace: .../officeDocument/2006/relationships | Specifies the relationship ID, the target of which points to the internal location where the binary data part representing various properties of the ActiveX control is persisted using the persistStorage , persistStream , or persistStreamInit method, as indicated by the persistence attribute of the parent ocx element. The specified relationship shall be of type http://schemas.microsoft.com/office/2006/relationships/activeXControlBinary . [Note: The use of this attribute is mutually exclusive with the use of ocxPr child elements. end note] The possible values for this attribute are defined by the ST_RelationshipId simple type (" ECMA-376 Part 4 §7.8.2.1"). |

The following XML Schema fragment defines the contents of this element:

```
<complexType name="CT_Ocx">
  <sequence>
    <element name="ocxPr" type="CT_OcxPr" minOccurs="0" maxOccurs="unbounded"/>
  </sequence>
  <attribute name="classid" type="ST_String" use="required"/>
  <attribute name="license" type="ST_String"/>
  <attribute ref="r:id" use="optional"/>
  <attribute name="persistence" use="required" type="ST_Persistence"/>
</complexType>
```

3.6.1.3 ocxPr (Object Property)

This element specifies the name and value of a persisting property of the parent object persisted using the method **persistPropertyBag**. **Property values are converted into VT_BSTR using the Windows OLE API VariantChangeType() before getting stored in this element.**

| Parent Elements |
|--|
| font (§3.6.1.1, font); ocx (§3.6.1.2, ocx) |

| Child Elements | Subclause |
|--|-------------------|
| font (Standard COM Font Object) | §3.6.1.1, font |
| picture (Standard COM Picture Object) | §3.6.1.4, picture |

| Attributes | Description |
|---|--|
| name (ActiveX Control Property Name) | Specifies the name of the property. This name shall be unique in its collection. The possible values for this attribute are defined by the ST_String simple type (§3.6.2.2, ST_String). |
| value (ActiveX Control Property Value) | Specifies the value of the property. The actual property values are converted into VT_BSTR using the Windows OLE API VariantChangeType() before getting stored in this element. And corresponding string is stored as the value. This attribute is only permitted for ocxPr elements (§3.6.1.3, ocxPr) without a font (§3.6.1.1, font) or picture sub-element (§3.6.1.4, picture). The possible values for this attribute are defined by the ST_String simple type (§3.6.2.2, ST_String). |

The following XML Schema fragment defines the contents of this element:

```
<complexType name="CT_OcxPr">
  <sequence>
    <choice>
      <element name="font" type="CT_Font" maxOccurs="1" minOccurs="0"/>
      <element name="picture" type="CT_Picture" maxOccurs="1" minOccurs="0"/>
    </choice>
  </sequence>
</complexType>
```

```

    </sequence>
    <attribute name="name" type="ST_String" use="required"/>
    <attribute name="value" type="ST_String"/>
  </complexType>

```

3.6.1.4 picture (Standard COM Picture Object)

This element specifies the properties of the StdPicture (classid CLSID_StdPicture, interface IPicture) object embedded in the property bag (IPersistPropertyBag interface) of an ActiveX control.

[Example: Consider an embedded picture object named "PicturePropName" embedded in an ActiveX control.

```

<ax:ocx ...>
  <ax:ocxPr ax:name="PicturePropName">
    <ax:picture r:id="rId1"/>
  </ax:ocxPr>
</ax:ocx>

```

This example specifies that binary data representing the picture object can be found at the internal location pointed to by the relation *rId1*, and the data is persisted using an IPersist-derived interface. end example]

More information about the details of the StdPicture object can be found in the Office Forms Binary File Format Structure Specification ("[\[MS-OFORMS\]](#) Section 2.4.5").

| Parent Elements |
|--|
| ocxPr (§3.6.1.3, ocxPr) |

| Attributes | Description |
|--|---|
| id () Namespace: ../officeDocument/2006/relationships | Specifies the relationship ID of the relationship to the picture. The specified relationship shall be of type http://schemas.microsoft.com/office/2006/relationships/activeXControlBinary . The target of the relationship point to the internal location where the persisted picture data is stored using the IPersist interface. The possible values for this attribute are defined by the ST_RelationshipId simple type (" [ECMA-376] Part 4 §7.8.2.1"). |

The following XML Schema fragment defines the contents of this element:

```

<complexType name="CT_Picture">
  <attribute ref="r:id"/>
</complexType>

```

3.6.2 Simple Types

This is the complete list of simple types in the <http://schemas.microsoft.com/office/2006/activeX> namespace.

3.6.2.1 ST_Persistence (Control Persistence Attribute Contents)

This simple type specifies the persistence method to persist an ActiveX control.

This simple type's contents are a restriction of the ST_String datatype (§3.6.2.2, [ST String](#)).

The following are possible enumeration values for this type:

| Enumeration Value | Description |
|--|---|
| persistPropertyBag (Control uses IPersistPropertyBag) | Specifies that the data is stored using the IPersistPropertyBag interface. If this value is used, then a child ocxPr element shall appear within the parent element. |
| persistStorage (Control uses IPersistStorage) | Specifies that the data is stored using the IPersistStorage interface. If this value is used, then the parent element's id attribute shall reference a relationship storing the necessary binary data. |
| persistStream (Control uses IPersistStream) | Specifies that the data is stored using the IPersistStream interface. If this value is used, then the parent element's id attribute shall reference a relationship storing the necessary binary data. |
| persistStreamInit (Control uses IPersistStreamInit) | Specifies that the data is stored using the IPersistStreamInit interface. If this value is used, then the parent element's id attribute shall reference a relationship storing the necessary binary data. |

Referenced By

font@persistence (§3.6.1.1, [font](#)); **ocx@persistence** (§3.6.1.2, [ocx](#))

The following XML Schema fragment defines the contents of this simple type:

```
<simpleType name="ST_Persistence">
  <restriction base="ST_String">
    <enumeration value="persistPropertyBag"/>
    <enumeration value="persistStream"/>
    <enumeration value="persistStreamInit"/>
    <enumeration value="persistStorage"/>
  </restriction>
</simpleType>
```

3.6.2.2 ST_String (String Type)

This simple type specifies that its contents will contain a string. The contents of this string are interpreted based on the context of the parent XML element.

[Example: Consider the following WordprocessingML fragment:

```
<w:pPr>
  <w:pStyle w:val="heading1" />
</w:pPr>
```

The value of the **val** attribute is the ID of the associated paragraph style's **styleId**. However, consider the following fragment:

```
<w:sdtPr>
  <w:alias w:val="SDT Title Example" />
  ...
</w:sdtPr>
```

In this case, the decimal number in the **val** attribute is the caption of the parent-structured document tag. In each case, the value is of type **ST_String**, and therefore must be interpreted in the context of the parent element. end example]

This simple type's contents are a restriction of the XML Schema string datatype.

| Referenced By |
|--|
| ocx@classid (§3.6.1.2, ocx); ocx@license (§3.6.1.2, ocx); ocxPr@name (§3.6.1.3, ocxPr); ocxPr@value (§3.6.1.3, ocxPr); ST_Persistence (§3.6.2.1, ST_Persistence) |

The following XML Schema fragment defines the contents of this simple type:

```
<simpleType name="ST_String">
  <restriction base="xsd:string"/>
</simpleType>
```

3.7 Office Digital Signature

The Office Digital Signature is a digital signature used by Office to certify the content of a document and to verify the authenticity of its creator or sender.

3.7.1 Elements

Office reserves the **Object Id** of *idOfficeObject* for its digital signature. The child of the **SignatureProperty** in this object shall be a **SignatureInfoV1** element.

3.7.1.1 ApplicationVersion (Application Version)

Specifies the version of the application which created the digital signature.

The possible values for this element are defined by the **ST_Version** simple type (§3.7.2.7, [ST_Version](#)).

| Parent Elements |
|---|
| SignatureInfoV1 (§3.7.1.13, SignatureInfoV1) |

The following XML Schema fragment defines the contents of this element:

```
<simpleType name="ST_Version">  
  <restriction base="xsd:string">  
    <maxLength value="64"/>  
  </restriction>  
</simpleType>
```

3.7.1.2 ColorDepth (Color Depth)

Specifies the color depth of the primary monitor of the machine on which the digital signature was created.

The possible values for this element are defined by the ST_PositiveInteger simple type (§3.7.2.1, [ST_PositiveInteger](#)).

| Parent Elements |
|---|
| SignatureInfoV1 (§3.7.1.13, SignatureInfoV1) |

The following XML Schema fragment defines the contents of this element:

```
<simpleType name="ST_PositiveInteger">  
  <restriction base="xsd:int">  
    <minExclusive value="0"/>  
  </restriction>  
</simpleType>
```

3.7.1.3 DelegateSuggestedSigner (Delegate Suggested Signer)

Specifies the name of a person to whom the signature has been delegated.

| Parent Elements |
|---|
| SignatureInfoV1 (§3.7.1.13, SignatureInfoV1) |

3.7.1.4 DelegateSuggestedSigner2 (Delegate Suggested Signer)

Specifies the title of a person to whom the signature has been delegated.

| Parent Elements |
|---|
| SignatureInfoV1 (§3.7.1.13, SignatureInfoV1) |

3.7.1.5 DelegateSuggestedSignerEmail (Delegate Suggested Signer E-mail Address)

Specifies the e-mail address of a person to whom the signature has been delegated.

| |
|---|
| Parent Elements |
| SignatureInfoV1 (§3.7.1.13, SignatureInfoV1) |

3.7.1.6 HorizontalResolution (Horizontal Resolution)

Specifies the horizontal resolution of the primary monitor of the machine on which the digital signature was created.

The possible values for this element are defined by the ST_PositiveInteger simple type ([§3.7.2.1, ST_PositiveInteger](#)).

| |
|---|
| Parent Elements |
| SignatureInfoV1 (§3.7.1.13, SignatureInfoV1) |

The following XML Schema fragment defines the contents of this element:

```
<simpleType name="ST_PositiveInteger">
  <restriction base="xsd:int">
    <minExclusive value="0"/>
  </restriction>
</simpleType>
```

3.7.1.7 ManifestHashAlgorithm (Manifest Hash Algorithm)

Specifies a URI that identifies the particular hash algorithm for the signature. If the signature provider is Office, the algorithm shall be *http://www.w3.org/2000/09/xmldsig#sha1*.

| |
|---|
| Parent Elements |
| SignatureInfoV1 (§3.7.1.13, SignatureInfoV1) |

3.7.1.8 Monitors (Monitor Count)

Specifies the count of monitors on the machine where the digital signature was created.

The possible values for this element are defined by the ST_PositiveInteger simple type ([§3.7.2.1, ST_PositiveInteger](#)).

| |
|---|
| Parent Elements |
| SignatureInfoV1 (§3.7.1.13, SignatureInfoV1) |

The following XML Schema fragment defines the contents of this element:

```
<simpleType name="ST_PositiveInteger">
  <restriction base="xsd:int">
    <minExclusive value="0"/>
  </restriction>
</simpleType>
```

3.7.1.9 OfficeVersion (Office Version)

Specifies the version of the application suite which created the digital signature.

The possible values for this element are defined by the ST_Version simple type (§3.7.2.7, [ST_Version](#)).

| Parent Elements |
|--|
| SignatureInfoV1 (§3.7.1.13, SignatureInfoV1) |

The following XML Schema fragment defines the contents of this element:

```
<simpleType name="ST_Version">
  <restriction base="xsd:string">
    <maxLength value="64"/>
  </restriction>
</simpleType>
```

3.7.1.10 SetupID (Setup ID)

Specifies a GUID which can be cross-referenced with the GUID of the signature line stored in the document content.

The possible values for this element are defined by the ST_UniqueIdentifierWithBraces simple type (§3.7.2.6, [ST_UniqueIdentifierWithBraces](#)).

| Parent Elements |
|--|
| SignatureInfoV1 (§3.7.1.13, SignatureInfoV1) |

The following XML Schema fragment defines the contents of this element:

```
<simpleType name="ST_UniqueIdentifierWithBraces">
  <restriction base="xsd:string">
    <pattern value="\{[0-9a-fA-F]{8}\}-[0-9a-fA-F]{4}\-[0-9a-fA-F]{4}\-[0-9a-fA-F]{4}\-[0-9a-fA-F]{12}\}" />
  </restriction>
</simpleType>
```

3.7.1.11 SignatureComments (Signature Comments)

Specifies comments on the digital signature.

The possible values for this element are defined by the ST_SignatureComments simple type (§3.7.2.2, [ST_SignatureComments](#)).

| Parent Elements |
|--|
| SignatureInfoV1 (§3.7.1.13, SignatureInfoV1) |

The following XML Schema fragment defines the contents of this element:

```

<simpleType name="ST_SignatureComments">
  <restriction base="xsd:string">
    <maxLength value="255"/>
  </restriction>
</simpleType>

```

3.7.1.12 SignatureImage (Signature Image)

Specifies an image for the digital signature.

| Parent Elements |
|--|
| SignatureInfoV1 (§3.7.1.13, SignatureInfoV1) |

3.7.1.13 SignatureInfoV1 (Office Digital Signature V1 Info)

Provides details on a digital signature in a document.

| Child Elements | Subclause |
|--|--|
| ApplicationVersion (Application Version) | §3.7.1.1, ApplicationVersion |
| ColorDepth (Color Depth) | §3.7.1.2, ColorDepth |
| DelegateSuggestedSigner (Delegate Suggested Signer) | §3.7.1.3, DelegateSuggestedSigner |
| DelegateSuggestedSigner2 (Delegate Suggested Signer) | §3.7.1.4, DelegateSuggestedSigner2 |
| DelegateSuggestedSignerEmail (Delegate Suggested Signer E-mail Address) | §3.7.1.5, DelegateSuggestedSignerEmail |
| HorizontalResolution (Horizontal Resolution) | §3.7.1.6, HorizontalResolution |
| ManifestHashAlgorithm (Manifest Hash Algorithm) | §3.7.1.7, ManifestHashAlgorithm |
| Monitors (Monitor Count) | §3.7.1.8, Monitors |
| OfficeVersion (Office Version) | §3.7.1.9, OfficeVersion |
| SetupID (Setup ID) | §3.7.1.10, SetupID |
| SignatureComments (Signature Comments) | §3.7.1.11, SignatureComments |
| SignatureImage (Signature Image) | §3.7.1.12, SignatureImage |
| SignatureProviderDetails (Signature Provider Details) | §3.7.1.14, SignatureProviderDetails |
| SignatureProviderId (Signature Provider ID) | §3.7.1.15, SignatureProviderId |
| SignatureProviderUrl (Signature Provider URL) | §3.7.1.16, SignatureProviderUrl |
| SignatureText (Signature Text) | §3.7.1.17, SignatureText |
| SignatureType (Signature Type) | §3.7.1.18, SignatureType |
| VerticalResolution (Vertical Resolution) | §3.7.1.19, VerticalResolution |
| WindowsVersion (Windows Version) | §3.7.1.20, WindowsVersion |

The following XML Schema fragment defines the contents of this element:

```
<complexType name="CT_SignatureInfoV1">
  <sequence>
    <group ref="EG_RequiredChildren"/>
    <group ref="EG_OptionalChildren" minOccurs="0"/>
  </sequence>
</complexType>
```

3.7.1.14 SignatureProviderDetails (Signature Provider Details)

Specifies details of the signature provider. The value shall be an integer computed from a bitmask of the following flags:

| Value | Description |
|------------|--|
| 0x00000000 | Specifies that there are no restrictions on the provider's usage. |
| 0x00000001 | Specifies that the provider shall only be used for the UI. |
| 0x00000002 | Specifies that the provider shall only be used for invisible signatures. |
| 0x00000004 | Specifies that the provider shall only be used for visible signatures. |
| 0x00000008 | Specifies that Office UI shall be used for the provider. |
| 0x00000010 | Specifies that Office stamp UI shall be used for the provider. |

| Parent Elements |
|--|
| SignatureInfoV1 (§3.7.1.13, SignatureInfoV1) |

3.7.1.15 SignatureProviderId (Signature Provider ID)

Specifies the class ID of the signature provider. Office reserves the value of {00000000-0000-0000-0000-000000000000} for its default signature provider and {000CD6A4-0000-0000-C000-000000000046} for its East Asian signature provider.

The possible values for this element are defined by the ST_UniqueIdentifierWithBraces simple type (§3.7.2.6, [ST UniqueIdentifierWithBraces](#)).

| Parent Elements |
|--|
| SignatureInfoV1 (§3.7.1.13, SignatureInfoV1) |

The following XML Schema fragment defines the contents of this element:

```
<simpleType name="ST_UniqueIdentifierWithBraces">
  <restriction base="xsd:string">
    <pattern value="\{[0-9a-fA-F]{8}\-[0-9a-fA-F]{4}\-[0-9a-fA-F]{4}\-[0-9a-fA-F]{4}\-[0-9a-fA-F]{12}\}" />
  </restriction>
```

</simpleType>

3.7.1.16 SignatureProviderUrl (Signature Provider URL)

Specifies the URL of the software used to generate the digital signature.

The possible values for this element are defined by the ST_SignatureProviderUrl simple type (§3.7.2.3, [ST_SignatureProviderUrl](#)).

| Parent Elements |
|--|
| SignatureInfoV1 (§3.7.1.13, SignatureInfoV1) |

The following XML Schema fragment defines the contents of this element:

```
<simpleType name="ST_SignatureProviderUrl">  
  <restriction base="xsd:string">  
    <maxLength value="2083"/>  
  </restriction>  
</simpleType>
```

3.7.1.17 SignatureText (Signature Text)

Specifies the text of actual signature in the digital signature.

The possible values for this element are defined by the ST_SignatureText simple type (§3.7.2.4, [ST_SignatureText](#)).

| Parent Elements |
|--|
| SignatureInfoV1 (§3.7.1.13, SignatureInfoV1) |

The following XML Schema fragment defines the contents of this element:

```
<simpleType name="ST_SignatureText">  
  <restriction base="xsd:string">  
    <maxLength value="100"/>  
  </restriction>  
</simpleType>
```

3.7.1.18 SignatureType (Signature Type)

Specifies the type of the digital signature.

When this signature is of type 2 (Signature Line), there shall be two additional objects in the signature: One with an **Id** value of *idValidSigLnImg*, whose value shall define the image of a valid signature; and one with an Id value of *idInvalidSigLnImg*, whose value shall define the image of an invalid signature.

The possible values for this element are defined by the ST_SignatureType simple type (§3.7.2.5, [ST_SignatureType](#)).

| Parent Elements |
|---|
| SignatureInfoV1 (§3.7.1.13, SignatureInfoV1) |

The following XML Schema fragment defines the contents of this element:

```
<simpleType name="ST_SignatureType">  
  <restriction base="xsd:int">  
    <enumeration value="1"/>  
    <enumeration value="2"/>  
  </restriction>  
</simpleType>
```

3.7.1.19 VerticalResolution (Vertical Resolution)

Specifies the vertical resolution of the primary monitor of the machine on which the digital signature was created.

The possible values for this element are defined by the ST_PositiveInteger simple type ([§3.7.2.1, ST_PositiveInteger](#)).

| Parent Elements |
|---|
| SignatureInfoV1 (§3.7.1.13, SignatureInfoV1) |

The following XML Schema fragment defines the contents of this element:

```
<simpleType name="ST_PositiveInteger">  
  <restriction base="xsd:int">  
    <minExclusive value="0"/>  
  </restriction>  
</simpleType>
```

3.7.1.20 WindowsVersion (Windows Version)

Specifies the version of the operating system on which the digital signature was created.

The possible values for this element are defined by the ST_Version simple type ([§3.7.2.7, ST_Version](#)).

| Parent Elements |
|---|
| SignatureInfoV1 (§3.7.1.13, SignatureInfoV1) |

The following XML Schema fragment defines the contents of this element:

```
<simpleType name="ST_Version">  
  <restriction base="xsd:string">  
    <maxLength value="64"/>  
  </restriction>  
</simpleType>
```

3.7.2 Simple Types

This is the complete list of simple types in the <http://schemas.microsoft.com/office/2006/digsig> namespace.

3.7.2.1 ST_PositiveInteger (Positive Integer)

This simple type's contents are a restriction of the XML Schema int datatype.

This simple type also specifies the following restrictions:

This simple type has a minimum value of greater than 0.

| Referenced By |
|---|
| ColorDepth (§3.7.1.2, ColorDepth); HorizontalResolution (§3.7.1.6, HorizontalResolution); Monitors (§3.7.1.8, Monitors); VerticalResolution (§3.7.1.19, VerticalResolution) |

The following XML Schema fragment defines the contents of this simple type:

```
<simpleType name="ST_PositiveInteger">
  <restriction base="xsd:int">
    <minExclusive value="0"/>
  </restriction>
</simpleType>
```

3.7.2.2 ST_SignatureComments (Signature Comments)

This simple type's contents are a restriction of the XML Schema string datatype.

This simple type also specifies the following restrictions:

This simple type's contents have a maximum length of 255 characters.

| Referenced By |
|--|
| SignatureComments (§3.7.1.11, SignatureComments) |

The following XML Schema fragment defines the contents of this simple type:

```
<simpleType name="ST_SignatureComments">
  <restriction base="xsd:string">
    <maxLength value="255"/>
  </restriction>
</simpleType>
```

3.7.2.3 ST_SignatureProviderUrl (Signature Provider URL)

This simple type's contents are a restriction of the XML Schema string datatype.

This simple type also specifies the following restrictions:

This simple type's contents have a maximum length of 2083 characters.

| Referenced By |
|--|
| SignatureProviderUrl (§3.7.1.16, SignatureProviderUrl) |

The following XML Schema fragment defines the contents of this simple type:

```
<simpleType name="ST_SignatureProviderUrl">  
  <restriction base="xsd:string">  
    <maxLength value="2083"/>  
  </restriction>  
</simpleType>
```

3.7.2.4 ST_SignatureText (Signature Text)

This simple type's contents are a restriction of the XML Schema string datatype.

This simple type also specifies the following restrictions:

This simple type's contents have a maximum length of 100 characters.

| Referenced By |
|--|
| SignatureText (§3.7.1.17, SignatureText) |

The following XML Schema fragment defines the contents of this simple type:

```
<simpleType name="ST_SignatureText">  
  <restriction base="xsd:string">  
    <maxLength value="100"/>  
  </restriction>  
</simpleType>
```

3.7.2.5 ST_SignatureType (Signature Type)

This simple type's contents are a restriction of the XML Schema int datatype.

The following are possible enumeration values for this type:

| Enumeration Value | Description |
|---------------------------|---|
| 1 (Invisible) | Specifies that there shall not be a visible representation of the digital signature. |
| 2 (Signature Line) | Specifies that there shall be a visible representation of the digital signature, where the GUID of the visible representation (the signature line stored in the document content) shall match the value of the SetupId element. |

| Referenced By |
|---|
| SignatureType (§3.7.1.18, SignatureType) |

The following XML Schema fragment defines the contents of this simple type:

```
<simpleType name="ST_SignatureType">  
  <restriction base="xsd:int">  
    <enumeration value="1"/>  
    <enumeration value="2"/>  
  </restriction>  
</simpleType>
```

3.7.2.6 ST_UniqueIdentifierWithBraces (Unique Identifier with Braces)

This simple type's contents are a restriction of the XML Schema string datatype.

This simple type also specifies the following restrictions:

This simple type's contents shall match the following regular expression pattern: `\{[0-9a-fA-F]{8}\-[0-9a-fA-F]{4}\-[0-9a-fA-F]{4}\-[0-9a-fA-F]{4}\-[0-9a-fA-F]{12}\}`.

| Referenced By |
|--|
| SetupID (§3.7.1.10, SetupID); SignatureProviderId (§3.7.1.15, SignatureProviderId) |

The following XML Schema fragment defines the contents of this simple type:

```
<simpleType name="ST_UniqueIdentifierWithBraces">  
  <restriction base="xsd:string">  
    <pattern value="\{[0-9a-fA-F]{8}\-[0-9a-fA-F]{4}\-[0-9a-fA-F]{4}\-[0-9a-fA-F]{4}\-[0-9a-fA-F]{12}\}" />  
  </restriction>  
</simpleType>
```

3.7.2.7 ST_Version (Version)

Specifies a version number in the form *X.Y*, where *X* is the major version number and *Y* is the minor version number.

This simple type's contents are a restriction of the XML Schema string datatype.

This simple type also specifies the following restrictions:

This simple type's contents have a maximum length of 64 characters.

Referenced By

ApplicationVersion (§3.7.1.1, [ApplicationVersion](#)); **OfficeVersion** (§3.7.1.9, [OfficeVersion](#)); **WindowsVersion** (§3.7.1.20, [WindowsVersion](#))

The following XML Schema fragment defines the contents of this simple type:

```
<simpleType name="ST_Version">  
  <restriction base="xsd:string">  
    <maxLength value="64"/>  
  </restriction>  
</simpleType>
```

3.8 Equation XML

3.8.1 Introduction

Word supports a Compatibility Mode in which it disables functionality not compatible with earlier versions of Word. Versions of Word prior to Word 2007 do not have native support for displaying Office Open XML Math. Instances of Office Open XML Math in Word documents are converted to pictures to preserve their visual fidelity when opened in versions of Word earlier than Word 2007. To do this, Word adds additional information to those pictures, using the **equationxml** attribute present on the **shape** element ("[ECMA-376](#) Part 4 §6.1.2.19; shape"), to store the Office Open XML Math which represents the original equation/expression. If the document is removed from Compatibility Mode, the contents of this attribute are then used to replace the image with the specified equation/expression.

This document describes the format in which Word 2007, Word 2010, or earlier versions of Word with the Compatibility Pack, store Office Open XML Math content inside the **equationxml** attribute.

3.8.2 Basic Format

The **equationXml** attribute's content is a complete Word 2003 XML document (defined here: [http://msdn.microsoft.com/en-us/library/aa272680\(office.11\).aspx](http://msdn.microsoft.com/en-us/library/aa272680(office.11).aspx)) containing Office Open XML Math elements ("[ECMA-376](#) Part 4 §7.1; Math"), and properly escaped as needed to be stored within an attribute value.

This document is subject to the following restrictions:

This Word 2003 XML document must not contain any comments, headers, footers, endnotes, footnotes, or textboxes.

This Word 2003 XML document must contain a single paragraph (**p element**).

That p element must contain a single **oMathPara** element ("[ECMA-376](#) Part 4 §7.1.2.78; oMathPara") which in turn must contain a single **oMath** element ("[ECMA-376](#) Part 4 §7.1.2.77; oMath").

The oMathPara element can contain any valid XML from the Office Open XML Math namespace, but must not contain any markup from any other Office Open XML namespace. Instead, it can contain various elements from the Word 2003 XML namespace ([§3.8.4, Office Open XML Math elements which can contain Word 2003 XML elements](#)).

[Example: The following string value represents the encoded contents of the **equationXml** attribute when it contains a mathematical expression containing only the character x:

```
<w:wordDocument xmlns:m=
<http://schemas.openxmlformats.org/officeDocument/2006/math>
xmlns:w=<http://schemas.microsoft.com/office/word/2003/wordml>
<w:body><w:p><m:MathPara><m:Math><m:r>
<w:rPr><w:rFonts w:ascii=<Cambria Math> w:h-ansi=
Math>/><w:i></w:rPr><m:t>x</m:t
></m:r></m:Math></m:MathPara></w:p
></w:body></w:wordDocument>
```

end example]

The syntax and semantics of elements from Word 2003 XML and of Office Open XML Math are those specified in the corresponding file formats, with the following exceptions:

There is a specific list of elements from Word 2003 XML which are each allowed to contain a specific set of elements from Office Open XML Math ([§3.8.3.1, Word 2003 XML elements which can contain Office Open XML Math elements](#)).

Office Open XML Math elements are not allowed to contain any markup from any other Office Open XML namespace. Instead, a specific set of elements from Office Open XML Math are allowed to contain a specific set of elements from Word 2003 XML ([§3.8.3, Reading the equationXml attribute](#)).

3.8.3 Reading the equationXml attribute

The contents of the **equationXml** attribute, as written by Word 2007, Word 2010, or earlier versions of Word with the Compatibility Pack, can be read in two different ways to determine the mathematical equation associated with the image:

To determine the associated equation/expression, read only the Office Open XML Math elements and ignore all other elements.

To determine the associated equation/expression including any additional WordprocessingML formatting (the addition of a bookmark, for example), read all elements.

[Example: The following XML represents the value of the **equationXml** attribute representing a mathematical equation containing a fraction with numerator x and denominator y where the numerator is formatted red and the denominator is enclosed in a bookmark with the name "bookmark_name":

```
<w:wordDocument xmlns:aml=<http://schemas.microsoft.com/aml/2001/core> xmlns:m=
<http://schemas.openxmlformats.org/officeDocument/2006/math>
xmlns:w=<http://schemas.microsoft.com/office/word/2003/wordml>
<w:body><w:p><m:MathPara><m:Math><m:f
><m:fPr><m:ctrlPr><w:rPr><w:rFonts w:ascii=<Cambria Math>
w:h-ansi=<Cambria Math>/><w:i></w:rPr></m:ctrlPr
></m:fPr><m:num><m:r><w:rPr ><w:rFonts w:ascii=<Cambria
Math> w:h-ansi=<Cambria Math>/><w:i><w:color
w:val=<FF0000>/></w:rPr><m:t>x</m:t
></m:r></m:num><m:den><aml:annotation aml:id=<0>
w:type=<Word.Bookmark.Start>
w:name=<bookmark_name>/></m:r><w:rPr ><w:rFonts
w:ascii=<Cambria Math> w:h-ansi=<Cambria
```

```

Math>/&gt;&lt;w:i/&gt;&lt;/w:rPr>&lt;m:t>y</m:t
&gt;&lt;/m:r>&lt;aml:annotation aml:id=&quot;0&quot;
w:type=&quot;Word.Bookmark.End&quot;/&gt;&lt;/m:den>&lt;/m:f
&gt;&lt;/m:oMath>&lt;/m:oMathPara>&lt;/w:p>&lt;/w:body &gt;&lt;/w:wordDocument>

```

An application might choose to read just the Office Open XML math elements, in which case it would display the fraction but would lose the font color applied to the numerator and the bookmark located in the denominator:

$$\frac{x}{y}$$

On the other hand, the application might choose to read all elements in which case it would display the font color and bookmark as well as the fraction:

$$\frac{x}{y}$$

end example]

3.8.3.1 Word 2003 XML elements which can contain Office Open XML Math elements

3.8.3.2 Containment of the oMathPara element

The Word 2003 XML document must contain a single **p** element which contains a single **oMathPara** element ("[\[ECMA-376\]](#) Part 4 §7.1.2.78; oMathPara").

3.8.3.3 Containment of Math runs and Math functions and objects

The Word 2003 XML **hlink** element and the AML **content** element can each contain an unbounded number of Office Open XML Math elements from the following list, which includes the Office Open XML Math **r** element and all Office Open XML Math functions/objects:

acc ("[\[ECMA-376\]](#) Part 4 §7.1.2.1; acc")

bar ("[\[ECMA-376\]](#) Part 4 §7.1.2.7; bar")

borderBox ("[\[ECMA-376\]](#) Part 4 §7.1.2.11; borderBox")

box ("[\[ECMA-376\]](#) Part 4 §7.1.2.13; box")

d ("[\[ECMA-376\]](#) Part 4 §7.1.2.24; d")

eqArr ("[\[ECMA-376\]](#) Part 4 §7.1.2.34; eqArr")

f ("[\[ECMA-376\]](#) Part 4 §7.1.2.36; f")

func ("[\[ECMA-376\]](#) Part 4 §7.1.2.39; func")

groupChr ("[\[ECMA-376\]](#) Part 4 §7.1.2.41; groupChr")

limLow ("[\[ECMA-376\]](#) Part 4 §7.1.2.54; limLow")

limUpp ("[\[ECMA-376\]](#) Part 4 §7.1.2.56; limUpp")

m ("[\[ECMA-376\]](#) Part 4 §7.1.2.60; m")
nary ("[\[ECMA-376\]](#) Part 4 §7.1.2.70; nary")
phant ("[\[ECMA-376\]](#) Part 4 §7.1.2.81; phant")
r ("[\[ECMA-376\]](#) Part 4 §7.1.2.87; r")
rad ("[\[ECMA-376\]](#) Part 4 §7.1.2.88; rad")
sPre ("[\[ECMA-376\]](#) Part 4 §7.1.2.99; sPre")
sSub ("[\[ECMA-376\]](#) Part 4 §7.1.2.101; sSub")
sSubSup ("[\[ECMA-376\]](#) Part 4 §7.1.2.103; sSubSup")
sSup ("[\[ECMA-376\]](#) Part 4 §7.1.2.105; sSup")

3.8.4 Office Open XML Math elements which can contain Word 2003 XML elements

3.8.4.1 Control Properties

The **ctrlPr** element ("[\[ECMA-376\]](#) Part 4 §7.1.2.23; ctrlPr") can contain one of the following elements:

The AML **annotation** element

The Word 2003 XML **rPr** element

3.8.4.2 oMath and Math Arguments

The **oMath** element ("[\[ECMA-376\]](#) Part 4 §7.1.2.78; oMathPara") and the math argument elements **deg** ("[\[ECMA-376\]](#) Part 4 §7.1.2.26; deg"), **den** ("[\[ECMA-376\]](#) Part 4 §7.1.2.28; den"), **e** ("[\[ECMA-376\]](#) Part 4 §7.1.2.32; e"), **fName** ("[\[ECMA-376\]](#) Part 4 §7.1.2.37; fName"), **lim** ("[\[ECMA-376\]](#) Part 4 §7.1.2.52; lim"), **num** ("[\[ECMA-376\]](#) Part 4 §7.1.2.75; num"), **sub** ("[\[ECMA-376\]](#) Part 4 §7.1.2.112; sub"), and **sup** ("[\[ECMA-376\]](#) Part 4 §7.1.2.114; sup") can each contain an unbounded number of elements from the following list:

XML elements in any namespace not defined by Word 2003 XML (which can, in turn, hold any valid child element of the **oMath** element ("[\[ECMA-376\]](#) Part 4 §7.1.2.77; oMath"))

The AML **annotation** element

The Word 2003 XML **hlink** element

The Word 2003 XML **permEnd** element

The Word 2003 XML **permStart** element

When included as a child of a math argument element, those elements must occur after any Office Open XML Math **argPr** element ("[\[ECMA-376\]](#) Part 4 §7.1.2.5; argPr") and before any Office Open

XML Math **ctrlPr** element ("[\[ECMA-376\]](#) Part 4 §7.1.2.23; ctrlPr") which is also a child of that math argument element.

3.8.4.3 Math Run

The Office Open XML math run element **r** ("[\[ECMA-376\]](#) Part 4 §7.1.2.87; r") can contain:

A single Word 2003 XML **rPr** element

If the math run contains both an Office Open XML Math **rPr** element and a Word 2003 XML **rPr** element, the Office Open XML Math **rPr** element must occur first.

The Office Open XML math **r** element can also contain an unbounded number of elements from the following list:

Word 2003 XML **fldChar** element

Word 2003 XML **noBreakHyphen** element

Word 2003 XML **pgNum** element

Word 2003 XML **pict** element.

Note: Word is unable to recover the contents of the **equationxml** attribute if it includes a **pict** element.

Word 2003 XML **softHyphen** element

Word 2003 XML **sym** element

Word 2003 XML **tab** element

Those elements must occur after any **rPr** elements.

3.8.5 Limitations in Word

Word ignores character styles, specified using the Word 2003 XML **rStyle** element, when converting the contents of the **equationxml** attribute to Office Open XML Math.

Word is unable to recover the contents of the **equationxml** attribute if it includes the Word 2003 XML **pict** element.

When Word recovers the contents of the **equationxml** attribute and the picture with the **equationxml** attribute is inside a **QUOTE** field, Word will lose any bookmarks represented using AML annotation elements inside the **equationxml** attribute.

3.9 Simple Types

The subordinate clauses describe XML simple types that are used by Office to read and write Office Open XML files.

3.9.1 ST_Fraction (Fraction Type)

This simple type specifies numerical, floating point data in one of three ways.

The first form is the standard decimal form used by the XML Schema decimal datatype. Valid values for this form are all decimals in the range [-32768, 32767].

The second form is an integer number with a postfixed "f" character. Each integer represents 1/65536 so that a value of "65536f" equates to a decimal value of 1.0. Valid values for this form are all integers in the range [-2147483648, 2147418112] followed by the postfixed "f".

The third form is equivalent to the second, except that the "f" postfixed character is replaced by the string "fd". This is used when expressing angular measurements.

This simple type's contents are a restriction of the XML Schema string datatype.

The following XML Schema fragment defines the contents of this simple type:

```
<simpleType name="ST_Fraction">
  <restriction base="xsd:string"/>
</simpleType>
```

3.9.2 ST_Macro (Custom Function Name Type)

This simple type specifies the name of a custom function associated with the object. This string shall follow the same grammar as name-reference in section "[[ECMA-376](#)] Part 4 §3.17.2.5; Names".

This simple type's contents are a restriction of the XML Schema string datatype.

This simple type also specifies the following restrictions:

This simple type's contents have a minimum length of 0 characters.

This simple type's contents have a maximum length of 256 characters.

The following XML Schema fragment defines the contents of this simple type:

```
<simpleType name="ST_Macro">
  <restriction base="xsd:string">
    <minLength value="0"/>
    <maxLength value="256"/>
  </restriction>
</simpleType>
```

3.9.3 ST_ObjID (Object ID)

In Office, Object IDs are either object names or an ID number.

An object name has the following characteristics:

It is not an ID number.

There is no shape with the same name in the:

same worksheet, for Excel.

same slide, for PowerPoint.

same document, for Word.

header, for Word.

It is not an embedded object, for Excel and Word.

If it is an object name and contains NCR (Numeric Character Reference) characters, they are escaped using the Unicode numerical character representation escape character format `_xHHHH_`, where H represents a hexadecimal character. If the string already contains escaped characters in this format, then the first underscore character (`_`) of the escape sequence shall be escaped.

An ID number is defined by the **ST_SpId** simple type ([§3.9.6, ST_SpId](#)).

This simple type's contents are a restriction of the XML Schema token datatype.

This simple type also specifies the following restrictions:

This simple type's contents have a maximum length of 255 characters.

The following XML Schema fragment defines the contents of this simple type:

```
<simpleType name="ST_ObjID">
  <restriction base="xsd:token">
    <maxLength value="255"/>
  </restriction>
</simpleType>
```

3.9.4 ST_ObjIDRef (Object ID Reference)

This simple type specifies a reference to an object ID. It starts with an optional `#` which is followed by an object ID number or an object name as described in the [ST_ObjID](#) simple type ([§3.9.3, ST_ObjID](#)).

This simple type's contents are a restriction of the XML Schema token datatype.

The following XML Schema fragment defines the contents of this simple type:

```
<simpleType name="ST_ObjIDRef">
  <restriction base="xsd:token"/>
</simpleType>
```

3.9.5 ST_ShapeType (Shape Type)

This simple type specifies the kinds of shapes a VML shape can represent. [Rationale: An application may use this to indicate that a VML shape represents a particular conceptual shape type. end rationale]

| Value | Description |
|--------------|--------------------|
| 0 | User-defined shape |
| 1 | Rectangle |
| 2 | Rounded Rectangle |
| 3 | Ellipse |
| 4 | Diamond |
| 5 | Isosceles Triangle |
| 6 | Right Triangle |
| 7 | Parallelogram |
| 8 | Trapezoid |
| 9 | Hexagon |
| 10 | Octagon |
| 11 | Plus Sign |
| 12 | Star |
| 13 | Arrow |
| 14 | Thick Arrow |
| 15 | Home Plate |
| 16 | Cube |
| 17 | Balloon |
| 18 | Seal |
| 19 | Arc |
| 20 | Line |
| 21 | Plaque |
| 22 | Can |
| 23 | Donut |
| 32 | Straight Connector |
| 33-36 | Bent Connector |
| 37-40 | Curved Connector |
| 41-43 | Callout |
| 44-46 | Accent Callout |
| 47-49 | Border Callout |

| Value | Description |
|--------------|---------------------------------|
| 50-52 | Accent Border Callout |
| 53-54 | Ribbon |
| 55 | Chevron |
| 56 | Pentagon |
| 57 | No Smoking |
| 58 | 8 Pointed Seal |
| 59 | 16 Pointed Seal |
| 60 | 32 Pointed Seal |
| 61 | Wedge Rectangle Callout |
| 62 | Wedge Rounded Rectangle Callout |
| 63 | Wedge Ellipse Callout |
| 64 | Wave |
| 65 | Folded Corner |
| 66 | Left Arrow |
| 67 | Down Arrow |
| 68 | Up Arrow |
| 69 | Left-Right Arrow |
| 70 | Up-Down Arrow |
| 71-72 | Irregular Seal |
| 73 | Lightning Bolt |
| 74 | Heart |
| 75 | Picture Frame |
| 76 | Quad Arrow |
| 77 | Left Arrow Callout |
| 78 | Right Arrow Callout |
| 79 | Up Arrow Callout |
| 80 | Down Arrow Callout |
| 81 | Left-Right Arrow Callout |
| 82 | Up-Down Arrow Callout |
| 83 | Quad Arrow Callout |

| Value | Description |
|--------------|-------------------------------|
| 84 | Bevel |
| 85 | Left Bracket |
| 86 | Right Bracket |
| 87 | Left Brace |
| 88 | Right Brace |
| 89 | Left-Up Arrow |
| 90 | Bent Up Arrow |
| 91 | Bent Arrow |
| 92 | 24 Pointed Seal |
| 93 | Striped Right Arrow |
| 94 | Notched Right Arrow |
| 95 | Block Arc |
| 96 | Smiley Face |
| 97 | Vertical Scroll |
| 98 | Horizontal Scroll |
| 99 | Circular Arrow |
| 100 | Notched Circular Arrow |
| 101 | U-Turn Arrow |
| 102 | Curved Right Arrow |
| 103 | Curved Left arrow |
| 104 | Curved Up Arrow |
| 105 | Curved Down Arrow |
| 106 | Cloud Callout |
| 107-108 | Ellipse Ribbon |
| 109 | Flow Chart Process |
| 110 | Flow Chart Decision |
| 111 | Flow Chart Input/Output |
| 112 | Flow Chart Predefined Process |
| 113 | Flow Chart Internal Storage |
| 114 | Flow Chart Document |

| Value | Description |
|--------------|------------------------------|
| 115 | Flow Chart Multi-Document |
| 116 | Flow Chart Terminator |
| 117 | Flow Chart Preparation |
| 118 | Flow Chart Manual Input |
| 119 | Flow Chart Manual Operation |
| 120 | Flow Chart Connector |
| 121 | Flow Chart Punched Card |
| 122 | Flow Chart Punched Tape |
| 123 | Flow Chart Summing Junction |
| 124 | Flow Chart Or |
| 125 | Flow Chart Collate |
| 126 | Flow Chart Sort |
| 127 | Flow Chart Extract |
| 128 | Flow Chart Merge |
| 129 | Flow Chart Offline Storage |
| 130 | Flow Chart Online Storage |
| 131 | Flow Chart Magnetic Tape |
| 132 | Flow Chart Magnetic Disk |
| 133 | Flow Chart Magnetic Drum |
| 134 | Flow Chart Display |
| 135 | Flow Chart Delay |
| 176 | Flow Chart Alternate Process |
| 177 | Flow Chart Offpage Connector |
| 178 | Callout 90 |
| 179 | Accent Callout 90 |
| 180 | Border Callout 90 |
| 181 | Accent Border Callout 90 |
| 182 | Left-Right-Up Arrow |
| 183 | Sun |
| 184 | Moon |

| Value | Description |
|--------------|-----------------------------|
| 185 | Bracket Pair |
| 186 | Brace Pair |
| 187 | 4 Pointed Seal |
| 188 | Double Wave |
| 189 | Action Button Blank |
| 190 | Action Button Home |
| 191 | Action Button Help |
| 192 | Action Button Information |
| 193 | Action Button Forward/Next |
| 194 | Action Button Back/Previous |
| 195 | Action Button End |
| 196 | Action Button Beginning |
| 197 | Action Button Return |
| 198 | Action Button Document |
| 199 | Action Button Sound |
| 200 | Action Button Movie |
| 201 | Host Control |
| 202 | Text Box |

This simple type's contents are a restriction of the XML Schema int datatype.

This simple type also specifies the following restrictions:

This simple type has a minimum value of greater than or equal to 0.

This simple type has a maximum value of less than or equal to 202.

The following XML Schema fragment defines the contents of this simple type:

```
<simpleType name="ST_ShapeType">
  <restriction base="xsd:int">
    <minInclusive value="0"/>
    <maxInclusive value="202"/>
  </restriction>
</simpleType>
```

3.9.6 ST_SpId (Shape ID Type)

A shape ID has the following characteristics:

It begins with "_x0000_" followed by 1 character and a number: _x0000_[c]<num>

The character [c] is:

't' or 'm' when used for a **shapetype** element ("[ECMA-376](#) Part 4 §6.1.2.20; shapetype").

's' when used for a shape.

Shape IDs always start at 1025.

Shape IDs are clustered together, and each cluster has 1024 values. The first cluster ranges from 1025 to 2048.

Shape IDs within the same cluster may only exist in:

one worksheet, for Excel.

one slide, for PowerPoint.

one document, for Word.

the header, for Word.

's' or 'i' for shapes that are inline (not floating) in Word.

<num> shall be between 1 and 268435456.

It does not contain NCR (Numeric Character Reference) characters.

Office does not guarantee that the same shape ID that is loaded is preserved on file save.

This simple type's contents are a restriction of the XML Schema string datatype.

The following XML Schema fragment defines the contents of this simple type:

```
<simpleType name="ST_SpId">  
  <restriction base="xsd:string"/>  
</simpleType>
```

4 Change Tracking

No table of changes is available. The document is either new or has had no changes since its last release.

5 Index

A

- [A1-Style Cell References](#) 440
- [absSizeAnchor \(Absolute Anchor Shape Size\)](#) 730
- [Abstract \(Document Abstract\)](#) 999
- [abstractNum \(Abstract Numbering Definition\)](#) 130
- [abstractNumId \(Abstract Numbering Definition Reference\)](#) 130
- [acc \(Accent\)](#) 798
- [Accel \(Primary Keyboard Accelerator\)](#) 792
- [Accel2 \(Secondary Keyboard Accelerator\)](#) 792
- [accent1 \(Accent 1\)](#) 563
- [accent2 \(Accent 2\)](#) 563
- [accent3 \(Accent 3\)](#) 563
- [accent4 \(Accent 4\)](#) 563
- [accent5 \(Accent 5\)](#) 563
- [accent6 \(Accent 6\)](#) 564
- [ACCRINT](#) 444
- [ACCRINTM](#) 445
- [acd \(Allocated Command Keyboard Customization Action\)](#) 838
- [acd \(Allocated Command\)](#) 837
- [acdEntry \(Allocated Command Manifest Entry\)](#) 839
- [acdManifest \(Allocated Command Manifest\)](#) 840
- [acds \(Allocated Commands\)](#) 840
- [ACOS](#) 446
- [active \(Record Is Included in Mail Merge\)](#) 841
- [activeRecord \(Record Currently Displayed In Merged Document\)](#) 153
- [activeWritingStyle \(Grammar Checking Settings\)](#) 159
- Additional Elements ([section 3.1.4.2.1](#) 975, [section 3.1.4.3.1](#) 977)
- Additional Parts ([section 3.1.1](#) 834, [section 3.2.1](#) 979, [section 3.3.1](#) 993, [section 3.4.1](#) 995)
- [Additional SpreadsheetML Schema](#) 986
- [Additional WordprocessingML Schema](#) 939
- [ADDRESS](#) 446
- [ADDRESSBLOCK](#) 206
- [ADVANCE](#) 207
- [aliases \(Alternate Style Names\)](#) 110
- [alignment \(Alignment\)](#) 317
- [allowPNG \(Allow PNG as Graphic Format\)](#) 174
- [aln \(Alignment\)](#) 798
- [alpha \(Alpha\)](#) 560
- [alphaInv \(Alpha Inverse Effect\)](#) 665
- [alphaMod \(Alpha Modulate Effect\)](#) 665
- [altChunk \(Anchor for Imported External Content\)](#) 247
- [altName \(Alternate Names for Font\)](#) 127
- [alwaysMergeEmptyNamespace \(Do Not Mark Custom XML Elements With No Namespace As Invalid\)](#) 159
- [AMORDEGRC](#) 446
- [AMORLINC](#) 447
- [anchor \(Anchor for Floating DrawingML Object\)](#) 674
- [anchor \(Anchor Point\)](#) 660
- [Anchor \(Anchor\)](#) 793
- [anim \(Animate\)](#) 518
- [animClr \(Animate Color Behavior\)](#) 519
- [animEffect \(Animate Effect\)](#) 520
- [animMotion \(Animate Motion\)](#) 524
- [animRot \(Animate Rotation\)](#) 526
- [animScale \(Animate Scale\)](#) 527
- [Application Conformance](#) 51
- [ApplicationVersion \(Application Version\)](#) 1023
- [applyBreakingRules \(Use Legacy Ethiopic and Amharic Line Breaking Rules\)](#) 178
- [applyToEnd \(Apply to End\)](#) 678
- [applyToFront \(Apply To Front\)](#) 678
- [applyToSides \(Apply To Sides\)](#) 678
- [AppVersion \(Application Version\)](#) 817
- [arc \(Arc Segment\)](#) 742
- [area3DChart \(3D Area Charts\)](#) 679
- [areaChart \(Area Charts\)](#) 679
- [AREAS](#) 447
- [argSz \(Argument Size\)](#) 799
- [array \(Array\)](#) 822
- [Array Formulas](#) 444
- [ASIN](#) 447
- [ASINH](#) 447
- [ATAN](#) 448
- [ATAN2](#) 448
- [attachedTemplate \(Attached Document Template\)](#) 160
- [attr \(Custom XML Attribute\)](#) 99
- [attr \(Smart Tag Property\)](#) 99
- [attrName \(Attribute Name\)](#) 528
- [audio \(Audio\)](#) 528
- [AUTHOR](#) 208
- [author \(Author\)](#) 317
- [Author \(Contributors List\)](#) 824
- [auto \(Automatic Category Axis\)](#) 679
- [autoCaption \(Single Automatic Captioning Setting\)](#) 160
- [autoCaptions \(Automatic Captioning Settings\)](#) 160
- [autoFill \(AutoFill\)](#) 793
- [autoFormatOverride \(Allow Automatic Formatting to Override Formatting Protection Settings\)](#) 160
- [AutoLine \(AutoLine\)](#) 793
- [AUTONUM](#) 208
- [AUTONUMLGL](#) 208
- [AUTONUMOUT](#) 208
- [autoRedefine \(Automatically Merge User Formatting Into Style Definition\)](#) 110
- [AutoScale \(Font AutoScale\)](#) 793
- [autoSortScope \(AutoSort Scope\)](#) 348
- [autoSpaceLikeWord95 \(Emulate Word 95 Full-Width Character Spacing\)](#) 178
- [autoTitleDeleted \(Auto Title Is Deleted\)](#) 679
- [autoUpdate \(Update Automatically\)](#) 679
- [AVEDEV](#) 448
- [AVERAGEA](#) 448
- [AVERAGEIF](#) 448
- [AVERAGEIFS](#) 449
- [axId \(Axis ID\)](#) 680
- [axPos \(Axis Position\)](#) 680

B

[b \(Bold\)](#) 69
[b \(Boolean\)](#) 349
[backdrop \(Backdrop Plane\)](#) 660
background (Document Background) ([section 2.1.39](#) 63, [section 2.1.1692](#) 750)
[backWall \(Back Wall\)](#) 680
[backward \(Backward\)](#) 680
[band1V \(Band 1 Vertical\)](#) 564
[band2V \(Band 2 Vertical\)](#) 565
[bandFmts \(Band Formats\)](#) 680
[bar \(Bar\)](#) 799
[bar \(Paragraph Border Between Facing Pages\)](#) 63
[bar3DChart \(3D Bar Charts\)](#) 680
[barChart \(Bar Charts\)](#) 681
BARCODE 208
[barDir \(Bar Direction\)](#) 681
[barPr \(Bar Properties\)](#) 799
[basedOn \(Parent Style ID\)](#) 111
[baseJc \(Matrix Base Justification\)](#) 799
[baseTimeUnit \(Base Time Unit\)](#) 681
Basic Format 1034
[bCs \(Complex Script Bold\)](#) 69
[bdr \(Text Border\)](#) 69
BESSEL 449
BESSEL 449
BESSELK 449
BESSELY 449
BETAINV 449
[between \(Paragraph Border Between Identical Paragraphs\)](#) 64
[bevelB \(Bottom Bevel\)](#) 660
[bevelT \(Top Bevel\)](#) 660
[bg \(Slide Background\)](#) 514
[bgColor \(Background Color\)](#) 318
[bgPr \(Background Properties\)](#) 514
BIBLIOGRAPHY 208
[bidi \(Right to Left Paragraph Layout\)](#) 64
BIDIOUTLINE 209
[bidiVisual \(Visually Right to Left Table\)](#) 82
BIN2DEC 450
[bk \(Metadata Block\)](#) 335
[bldChart \(Build Chart\)](#) 557
[bldDgm \(Build Diagram\)](#) ([section 2.1.1180](#) 528, [section 2.1.1240](#) 557)
[bldGraphic \(Build Graphics\)](#) 529
[bldOleChart \(Build Embedded Chart\)](#) 529
[bldP \(Build Paragraph\)](#) 529
[bldSub \(Build Sub Elements\)](#) 530
[blipFill \(Picture Fill\)](#) ([section 2.1.1154](#) 514, [section 2.1.1368](#) 665, [section 2.1.1412](#) 674, [section 2.1.1421](#) 675, [section 2.1.1649](#) 730)
[blockquote \(Data for HTML blockquote Element\)](#) 174
[blue \(Blue\)](#) 561
[blueMod \(Blue Modification\)](#) 561
[blueOff \(Blue Offset\)](#) 561
[blur \(Blur Effect\)](#) 665
[body \(Document Body\)](#) 63
[bodyDiv \(Data for HTML body Element\)](#) 174

[bodyPr \(Body Properties\)](#) 566
[bookFoldPrinting \(Book Fold Printing\)](#) 160
[bookFoldPrintingSheets \(Number of Pages Per Booklet\)](#) 161
[bookFoldRevPrinting \(Reverse Book Fold Printing\)](#) 161
[bookmarkEnd \(Bookmark End\)](#) 151
[Bookmarks](#) 151
[bookmarkStart \(Bookmark Start\)](#) 152
[bookViews \(Workbook Views\)](#) 255
[border \(Border\)](#) 318
[borderbottom \(Bottom Border\)](#) 792
[borderBox \(Border-Box Function\)](#) 800
[borderleft \(Left Border\)](#) 792
[borderright \(Right Border\)](#) 792
[borders \(Borders\)](#) 318
[bordertop \(Top Border\)](#) 792
[bottom \(Bottom Border for HTML div\)](#) 174
[bottom \(Bottom Border\)](#) 106
[bottom \(Paragraph Border Between Identical Paragraphs\)](#) 64
[bottom \(Table Bottom Border\)](#) 83
[bottom \(Table Cell Bottom Border\)](#) 82
[bottom \(Table Cell Bottom Margin Default\)](#) 83
[bottom \(Table Cell Bottom Margin Exception\)](#) 82
[bottom \(Text Box Bottom Stroke\)](#) 772
[bounds \(Bounds\)](#) 975
[box \(Box Function\)](#) 800
brk (Break) ([section 2.1.622](#) 273, [section 2.1.1805](#) 800)
[brkBin \(Break on Binary Operators\)](#) 800
[brkBinSub \(Break on Binary Subtraction\)](#) 801
bubble3D (3D Bubble) 681
[bubbleChart \(Bubble Charts\)](#) 682
[buFont \(Specified\)](#) 574
[builtInUnit \(Built in Display Unit Value\)](#) 682
[buSzPct \(Bullet Size Percentage\)](#) 574
[buSzPts \(Bullet Size Points\)](#) 574
[by \(By\)](#) 530

C

c (Cell) ([section 2.1.623](#) 274, [section 2.1.716](#) 316)
[cached \(Cached View\)](#) 1014
[cacheField \(PivotCache Field\)](#) 349
[cacheFields \(PivotCache Fields\)](#) 350
[cacheHierarchies \(PivotCache Hierarchies\)](#) 351
[cacheHierarchy \(PivotCache Hierarchy\)](#) 351
[cacheSource \(PivotCache Source Description\)](#) 353
[calcPr \(Calculation Properties\)](#) 255
[Calculated Field Formulas](#) 991
[Calculated Item Formulas](#) 992
[calculatedColumnFormula \(Calculated Column Formula\)](#) 312
[calculatedItem \(Calculated Item\)](#) 354
[calculatedMember \(Calculated Member\)](#) 354
[callout \(Callout\)](#) 774
[Camera \(Camera Tool\)](#) 793
[camera \(Camera\)](#) 661
[cantSplit \(Table Row Cannot Break Across Pages\)](#) 83
[caption \(Single Caption Type Definition\)](#) 162

[captions \(Caption Settings\)](#) 162
[cat \(Category Axis Data\)](#) 682
[catAx \(Category Axis Data\)](#) 683
[cBhvr \(Common Behavior\)](#) 531
[CELL](#) 450
[cell \(External Cell Data\)](#) 424
[Cell References](#) 439
[cell3D \(Cell 3-D\)](#) 576
[cellDel \(Table Cell Deletion\)](#) 141
[cellIns \(Table Cell Insertion\)](#) 141
[cellMerge \(Vertically Merged/Split Table Cells\)](#) 141
[cellMetadata \(Cell Metadata\)](#) 335
[cellSmartTag \(Cell Smart Tag\)](#) 274
[cellSmartTagPr \(Smart Tag Properties\)](#) 274
[cellSmartTags \(Cell Smart Tags\)](#) 275
[cellStyle \(Cell Style\)](#) 318
[cellStyles \(Cell Styles\)](#) 319
[cellStyleXfs \(Formatting Records\)](#) 319
[cellWatch \(Cell Watch Item\)](#) 275
[cellXfs \(Cell Formats\)](#) 319
[cf \(Clipboard Data\)](#) 822
[CF \(Clipboard Format\)](#) 794
[cfRule \(Conditional Formatting Rule\)](#) 275
[cfvo \(Conditional Format Value Object\)](#) 275
[cGp \(Matrix Column Gap\)](#) 801
[cGpRule \(Matrix Column Gap Rule\)](#) 801
[Change tracking](#) 1047
[charRq \(Character Range\)](#) 532
[charset \(Character Set Supported By Font\)](#) 128
[Chart formulas](#) 990
[chartFormat \(PivotChart Format\)](#) 355
[chartObject \(Chart Object\)](#) 683
[Chartsheet Part](#) 53
[checkErrors \(Mail Merge Error Reporting Setting\)](#) 153
[chExt \(Child Extents\)](#) 662
[CHIINV](#) 455
[chOff \(Child Offset\)](#) 662
[chr \(Accent Character\)](#) 801
[CITATION](#) 209
[CLEAN](#) 455
[clickAndTypeStyle \(Paragraph Style Applied to Automatically Generated Paragraphs\)](#) 162
[ClientData \(Attached Object Data\)](#) 794
[clippath \(Shape Clipping Path\)](#) 776
[clrChange \(Color Change Effect\)](#) 666
[clrData \(Color Transform Sample Data\)](#) 733
[clrMru \(Color MRU\)](#) 506
[clrSchemeMapping \(Theme Color Mappings\)](#) 162
[clsid \(Class ID\)](#) 822
[cm \(Comment\)](#) 518
[cmd \(Command\)](#) 532
[cMediaNode \(Common Media Node Properties\)](#) 534
[cnfStyle \(Paragraph Conditional Formatting\)](#) 64
[cnfStyle \(Table Cell Conditional Formatting\)](#) 83
[cnfStyle \(Table Row Conditional Formatting\)](#) 83
[cNvCxnSpPr \(Non-Visual Connector Shape Drawing Properties\)](#) 557
[cNvGraphicFramePr \(Non-Visual Graphic Frame Drawing Properties\)](#) 557
[cNvGrpSpPr \(Non-Visual Group Shape Drawing Properties\)](#) 557
[cNvPr \(Non-Visual Drawing Properties\) \(section 2.1.1422 675, section 2.1.1650 730\)](#)
[cNvSpPr \(Connection Non-Visual Shape Properties\)](#) 675
[col \(Column Width & Formatting\)](#) 275
[col \(Column\)](#) 982
[col \(Column\)](#) 675
[col \(Single Column Definition\)](#) 106
[colBreaks \(Vertical Page Breaks\)](#) 276
[colDelim \(Column Delimiter for Data Source\)](#) 153
[ColHidden \(Comment's Column is Hidden\)](#) 794
[colHierarchiesUsage \(Column OLAP Hierarchy References\)](#) 355
[colHierarchyUsage \(Column OLAP Hierarchies\)](#) 355
[colItems \(Column Items\)](#) 355
[color \(Color\)](#) 276
[color \(Frameset Splitter Color\)](#) 174
[color \(Run Content Color\)](#) 69
[ColorDepth \(Color Depth\)](#) 1024
[Colored \(Dropdown Color Toggle\)](#) 794
[colorFilter \(Color Filter Criteria\)](#) 309
[colormenu \(UI Default Colors\)](#) 776
[colormru \(Most Recently Used Colors\)](#) 777
[colorScale \(Color Scale\)](#) 277
[colorsDef \(Color Transform Definitions\)](#) 735
[cols \(Column Definitions\)](#) 107
[colSortMap \(Column Sort Map\)](#) 983
[column \(Index of Column Being Mapped\)](#) 154
[column \(Index of Column Containing Unique Values for Record\)](#) 153
[column \(Text Box Interior Stroke\)](#) 777
[comment \(Comment Content\)](#) 138
[comment \(Comment\)](#) 317
[commentRangeEnd \(Comment Anchor Range End\)](#) 140
[commentRangeStart \(Comment Anchor Range Start\)](#) 140
[commentReference \(Comment Content Reference Mark\)](#) 140
[COMMENTS](#) 209
[CompanyAddress \(Company Address\)](#) 999
[CompanyEmail \(Company Email Address\)](#) 999
[CompanyFax \(Company Fax Number\)](#) 999
[CompanyPhone \(Company Phone Number\)](#) 1000
[COMPLEX](#) 455
[complex \(Complex\)](#) 778
[cond \(Condition\)](#) 534
[Conditional Formatting Formulas](#) 988
[conditionalFormat \(Conditional Formatting\)](#) 355
[conditionalFormatting \(Conditional Formatting\)](#) 277
[CONFIDENCE](#) 455
[connection \(Connection\)](#) 420
[consecutiveHyphenLimit \(Maximum Number of Consecutively Hyphenated Lines\)](#) 162
[consolidation \(Consolidation Source\)](#) 356
[Constants](#) 437
[cont \(Effect Container\)](#) 666
[Containment of Math runs and Math functions and objects](#) 1036

[Containment of the oMathPara element](#) 1036
[Content Type Schemas](#) 1001
[Content Type Schemas Schema](#) 1002
[contentTypeSchema \(Schema for Content Type\)](#) 1002
[contourClr \(Contour Color\)](#) 661
[control \(Embedded Control\) \(section 2.1.635 277, section 2.1.1165 516\)](#)
[control \(Floating Embedded Control\)](#) 80
[control \(Inline Embedded Control\)](#) 80
[Control Properties](#) 1037
[controls \(Embedded Controls\)](#) 277
[CONVERT](#) 455
[convMailMergeEsc \(Treat Backslash Quotation Delimiter as a Single Quotation Mark\)](#) 180
[Core File Properties Part](#) 62
[CORREL](#) 456
[COS](#) 456
[COUNT](#) 456
[count \(Matrix Column Count\)](#) 801
[COUNTA](#) 456
[COUNTIFS](#) 456
[COUPDAYBS](#) 456
[COUPDAYS](#) 457
[COUPDAYSNC](#) 458
[COUPNCD](#) 458
[COUPNUM](#) 459
[COUPPCD](#) 460
[Cover Page Properties](#) 999
[Cover Page Properties Schema](#) 999
[CoverPageProperties \(Cover Page Properties\)](#) 1000
[CREATEDATE](#) 209
[CRITBINOM](#) 460
[crossAx \(Crossing Axis ID\)](#) 683
[crossesAt \(Crossing Value\)](#) 683
[cs \(Complex Script Font\)](#) 569
[cs \(Use Complex Script Formatting on Run\)](#) 71
[cSld \(Common Slide Data\)](#) 514
[cSp \(Matrix Column Spacing\)](#) 802
[cTn \(Common Time Node Properties\)](#) 535
[ctrlPr \(Control Properties\)](#) 803
[CUBEKPIMEMBER](#) 460
[CUBESET](#) 461
[CUBESETCOUNT](#) 461
[CUMIPMT](#) 461
[CUMPRINC](#) 461
[curve \(Bezier Curve\)](#) 751
[custData \(Customer Data\)](#) 505
[Custom Document Information Panel](#) 1012
[Custom Document Information Panel Schema](#) 1012
[Custom Property Part](#) 53
[Custom XML Data Storage Part](#) 61
[Custom XML Mappings Part](#) 53
[Custom XSN](#) 1014
[Custom XSN Schema](#) 1014
[Customizations Part](#) 834
[customPr \(Custom Property\)](#) 277
[customPropertyEditor \(Custom Property Editor\)](#) 1012
[customPropertyEditors \(Custom Property Editors List\)](#) 1013

[customSheetView \(Custom Chart Sheet View\)](#) 277
[customSheetView \(Custom Sheet View\)](#) 277
[customSheetViews \(Custom Chart Sheet Views\)](#) 278
[customSheetViews \(Custom Sheet Views\)](#) 278
[customWorkbookView \(Custom Workbook View\)](#) 256
[customWorkbookViews \(Custom Workbook Views\)](#) 258
[customXml \(Block-Level Custom XML Element\)](#) 100
[customXml \(Cell-Level Custom XML Element\)](#) 99
[customXml \(Inline-Level Custom XML Element\)](#) 100
[customXml \(Row-Level Custom XML Element\)](#) 100
[customXml \(Ruby Inline-Level Custom XML Element\)](#) 939
[customXmlDelRangeEnd \(Custom XML Markup Deletion End\)](#) 141
[customXmlDelRangeStart \(Custom XML Markup Deletion Start\)](#) 141
[customXmlInsRangeEnd \(Custom XML Markup Insertion End\)](#) 141
[customXmlInsRangeStart \(Custom XML Markup Insertion Start\)](#) 142
[customXmlMoveFromRangeEnd \(Custom XML Markup Move Source End\)](#) 142
[customXmlMoveFromRangeStart \(Custom XML Markup Move Source Start\)](#) 142
[customXmlMoveToRangeEnd \(Custom XML Markup Move Destination Location End\)](#) 143
[customXmlMoveToRangeStart \(Custom XML Markup Move Destination Location Start\)](#) 143
[customXsn \(Custom XSN\)](#) 1014
[custShow \(Custom Show\) \(section 2.1.1128 505, section 2.1.1132 506\)](#)
[custUnit \(Custom Display Unit\)](#) 684
[cut \(Cut Slide Transition\)](#) 536
[cxn \(Connection\)](#) 734
[cxnSp \(Connection Shape\) \(section 2.1.1425 675, section 2.1.1651 730\)](#)
[cxnSpLocks \(Connection Shape Locks\)](#) 557
[cy \(Currency\)](#) 822

D

[d \(Date Time\)](#) 356
[d \(Delimiter Function\)](#) 803
[data \(Data Cannot Be Changed\)](#) 684
[Data Validation Formulas](#) 989
[dataBar \(Data Bar\)](#) 278
[DATABASE](#) 210
[dataBinding \(XML Mapping\) \(section 2.1.192 101, section 2.1.883 428\)](#)
[dataField \(Data Field Item\)](#) 357
[dataSource \(Data Source File Path\)](#) 154
[dataValidation \(Data Validation\)](#) 278
[dataValidations \(Data Validations\)](#) 279
[DATE \(section 2.1.499 234, section 2.1.946 461\)](#)
[date \(Date and Time\)](#) 823
[date \(Date Structured Document Tag\)](#) 101
[Date and time formatting](#) 194
[Date Representation](#) 443
[date1904 \(1904 Date System\)](#) 684
[dateAx \(Date Axis\)](#) 685

[dateGroupItem \(Date Grouping\)](#) 309
[DATEVALUE](#) 462
[DAVERAGE](#) 462
[DAY](#) 462
[DAYS360](#) 462
[DB](#) 463
[dbPr \(Database Properties\)](#) 422
[DCOUNT](#) 463
[DCOUNTA](#) 463
[DDB](#) 463
[DDE](#) 963
[DDE \(Dynamic Data Exchange\)](#) 794
[DDEAUTO](#) 964
[ddeItem \(DDE Item definition\)](#) 424
[ddeLink \(DDE Connection\)](#) 425
[ddlList \(Drop-Down List Form Field Properties\)](#) 245
[DEC2BIN](#) 463
[DEC2HEX](#) 463
[DEC2OCT](#) 463
[decimalSymbol \(Radix Point for Field Code Evaluation\)](#) 163
[default \(Default Checkbox Form Field State\)](#) 245
[default \(Default Drop-Down List Item Index\)](#) 245
[default \(Default Text Box Form Field String\)](#) 245
[defaultPropertyEditorNamespace \(Default Namespace\)](#) 1013
[DefaultSize \(Default Size Toggle\)](#) 794
[defaultTableStyle \(Default Table Style for Newly Inserted Tables\)](#) 163
[defaultTabStop \(Distance Between Automatic Tab Stops\)](#) 163
[definedName \(Defined Name\)](#) ([section 2.1.601](#) 258, [section 2.1.868](#) 425)
[definedNames \(Defined Names\)](#) 260
[defJc \(Default Justification\)](#) 803
[defPPr \(Default Paragraph Style\)](#) 567
[defRPr \(Default Text Run Properties\)](#) 569
[deg \(Degree\)](#) 803
[degHide \(Hide Degree\)](#) 803
[del \(Deleted Math Control Character\)](#) 144
[del \(Deleted Paragraph\)](#) 144
[del \(Deleted Run Content\)](#) 144
[del \(Deleted Table Row\)](#) 144
[DelegateSuggestedSigner \(Delegate Suggested Signer\)](#) 1024
[DelegateSuggestedSigner2 \(Delegate Suggested Signer\)](#) 1024
[DelegateSuggestedSignerEmail \(Delegate Suggested Signer E-mail Address\)](#) 1024
[delete \(Delete\)](#) 685
[deletedField \(Deleted Field\)](#) 419
[den \(Denominator\)](#) 803
[depthPercent \(Depth Percent\)](#) 685
[DEVSQ](#) 464
[DGET](#) 464
[dgm \(Diagram to Animate\)](#) 557
[diagram \(VML Diagram\)](#) 778
[Diagram Colors Part](#) 60
[dialogsheets \(Dialog Sheet\)](#) 279
[Dialogsheet Part](#) 54
[DigSig \(Digital Signature\)](#) 817
[dimension \(OLAP Dimension\)](#) 357
[DISC](#) 464
[discretePr \(Discrete Grouping Properties\)](#) 358
[dispBlanksAs \(Display Blanks As\)](#) 685
[dispDef \(Use Display Math Defaults\)](#) 803
[dispEq \(Display Equation\)](#) 687
[displayHorizontalDrawingGridEvery \(Distance between Vertical Gridlines\)](#) 163
[displayVerticalDrawingGridEvery \(Distance between Horizontal Gridlines\)](#) 163
[dispRSqr \(Display R Squared Value\)](#) 687
[div \(Information About Single HTML div Element\)](#) 174
[divId \(Associated HTML div ID\)](#) ([section 2.1.46](#) 64, [section 2.1.122](#) 83)
[dk1 \(Dark 1\)](#) 564
[dk2 \(Dark 2\)](#) 564
[dLbl \(Data Label\)](#) 687
[dLblPos \(Data Label Position\)](#) 688
[dLbIs \(Data Labels\)](#) 689
[DMAX](#) 465
[DMIN](#) 465
[docPart \(Document Part Reference\)](#) 101
[docPart \(Glossary Document Entry\)](#) 137
[docPartBody \(Contents of Glossary Document Entry\)](#) 137
[docPartPr \(Glossary Document Entry Properties\)](#) 137
[DOCPROPERTY](#) 234
[DocSecurity \(Document Security\)](#) 817
[documentProtection \(Document Editing Restrictions\)](#) 164
[docVar \(Single Document Variable\)](#) 167
[DOLLAR](#) 465
[DOLLARDE](#) 465
[DOLLARFR](#) 465
[doNotAutofitConstrainedTables \(Do Not AutoFit Tables To Fit Next To Wrapped Objects\)](#) 180
[doNotLeaveBackslashAlone \(Convert Backslash To Yen Sign When Entered\)](#) 180
[doNotOrganizeInFolder \(Do Not Place Supporting Files in Subdirectory\)](#) 175
[doNotSuppressBlankLines \(Remove Blank Lines from Merged Documents\)](#) 154
[doNotSuppressParagraphBorders \(Do Not Suppress Paragraph Borders Next To Frames\)](#) 180
[doNotUseMarginsForDrawingGridOrigin \(Do Not Use Margins for Drawing Grid Origin\)](#) 167
[doughnutChart \(Doughnut Charts\)](#) 689
[Downrev Storage](#) 974
[downRevStq \(DownRev Storage\)](#) 976
[DPRODUCT](#) 466
[drawing \(Drawing\)](#) 279
[drawing \(DrawingML Object\)](#) 80
[drawingGridHorizontalOrigin \(Drawing Grid Horizontal Origin Point\)](#) 167
[drawingGridVerticalOrigin \(Drawing Grid Vertical Origin Point\)](#) 167
[DrawingML Persistence Part](#) 973
[DrawingML Persistence Parts](#) 973
[DropLines \(Dropdown Maximum Lines\)](#) 794

[DropStyle \(Dropdown Style\)](#) 795
[ds \(Dash Stop\)](#) 666
[DSTDEV](#) 466
[DSTDEVP](#) 466
[DSUM](#) 466
[duotone \(Duotone Effect\)](#) 666
[DURATION](#) 466
[DVAR](#) 467
[DVARP](#) 467
[Dx \(Scroll Bar Width\)](#) 795
[dxfs \(Formats\)](#) 320
[dynamicAddress \(Use Country-Based Address Field Ordering\)](#) 154
[dynamicFilter \(Dynamic Filter\)](#) 310

E

[e \(Base \(Argument\)\)](#) 804
[e \(Error Value\)](#) 358
[e2oHolder \(E2o Holder\)](#) 978
[ea \(East Asian Font\)](#) 569
[eastAsianLayout \(East Asian Typography Settings\)](#) 71
[EDATE](#) 467
[effect \(Animated Text Effect\)](#) 72
[effect \(Effect\)](#) 666
[effectClrLst \(Effect Color List\)](#) 735
[effectDag \(Effect Container\)](#) 666
[effectExtent \(Object Extents Including Effects\)](#) 674
[effectOffset \(Effect Offset\)](#) 978
[Elements](#) 1023
[embed \(Embedded Object or Control\)](#) 516
[embedBold \(Bold Style Font Style Embedding\)](#) 128
[embedBoldItalic \(Bold Italic Font Style Embedding\)](#) 128
[Embedded Control Persistence Binary Data Part](#) 995
[Embedded Control Persistence Part](#) 62
[embeddedFontLst \(Embedded Font List\)](#) 506
[embedItalic \(Italic Font Style Embedding\)](#) 128
[embedRegular \(Regular Font Style Embedding\)](#) 128
[embedTrueTypeFonts \(Embed TrueType Fonts\)](#) 129
[emboss \(Embossing\)](#) 72
[empty \(Empty\)](#) 823
[encoding \(Output Encoding When Saving as Web Page\)](#) 175
[end \(Audio End Time\)](#) 563
[endCxn \(Connection End\)](#) 558
[endnote \(Endnote Content\)](#) 135
[endnote \(Special Endnote List\)](#) 135
[endnoteReference \(Endnote Reference\)](#) 135
[endParaRPr \(End Paragraph Run Properties\)](#) 567
[endSync \(EndSync\)](#) 536
[EQ](#) 234
[eqArr \(Equation-Array Function\)](#) 804
[ERF](#) 467
[ERFC](#) 467
[errBars \(Error Bars\)](#) 689
[errBarType \(Error Bar Type\)](#) 689
[errDir \(Error Bar Direction\)](#) 689
[Error values](#) 443
[ERROR.TYPE](#) 467
[errValType \(Error Bar Value Type\)](#) 690

[evenAndOddHeaders \(Different Even/Odd Page Headers and Footers\)](#) 134
[evenFooter \(Even Footer\)](#) 690
[evenFooter \(Even Page Footer\)](#) 280
[evenHeader \(Even Header\)](#) 690
[evenHeader \(Even Page Header\)](#) 280
[Excel \(Additional Information\)](#) 979
[Excel Attached Toolbars Part](#) 979
[excl \(Exclusive\)](#) 536
[explosion \(Explosion\)](#) 690
[ext \(Extension\) \(section 2.1.603 260, section 2.1.1129 505, section 2.1.1247 558\)](#)
[ext \(Extents\)](#) 662
[ext \(Shape Extent\) \(section 2.1.1426 675, section 2.1.1652 731\)](#)
[extent \(Drawing Object Size\)](#) 674
[External Name Formulas](#) 990
[External Workbooks](#) 55
[externalData \(External Data Relationship\)](#) 690
[externalLink \(External Reference\)](#) 425
[externalReferences \(External References\)](#) 260
[extLst \(Extension List\)](#) 733
[extrusion \(3D Extrusion\)](#) 779
[extrusionClr \(Extrusion Color\)](#) 661

F

[f \(Formula\) \(section 2.1.649 282, section 2.1.1485 690\)](#)
[f \(Fraction Function\)](#) 805
[f \(Single Formula\)](#) 751
[fade \(Fade Slide Transition\)](#) 537
[family \(Font Family\) \(section 2.1.270 129, section 2.1.729 320\)](#)
[fci \(Fixed Command Keyboard Customization Action\)](#) 842
[ffData \(Form Field Properties\)](#) 245
[fgColor \(Foreground Color\)](#) 320
[fHdr \(First Row of Data Source Contains Column Names\)](#) 154
[field \(Field\)](#) 360
[FieldCodes \(WordprocessingML Field Switches\)](#) 781
[fieldGroup \(Field Group Properties\)](#) 360
[fieldMapData \(External Data Source to Merge Field Mapping\)](#) 154
[fieldsUsage \(Fields Usage\)](#) 360
[fieldUsage \(PivotCache Field Id\)](#) 361
[FILENAME](#) 235
[fileRecoveryPr \(File Recovery Properties\)](#) 260
[fileSharing \(File Sharing\)](#) 261
[FILESIZE](#) 235
[filetime \(File Time\)](#) 823
[fileVersion \(File Version\)](#) 263
[fill \(Fill\)](#) 565
[fill \(Shape Fill Extended Properties\)](#) 781
[fill \(Shape Fill Properties\)](#) 752
[fillClrLst \(Fill Color List\)](#) 735
[fills \(Fills\)](#) 320
[fillToRect \(Fill To Rectangle\)](#) 667
[filter \(Filter\)](#) 310
[filter \(PivotTable Advanced Filter\)](#) 361
[filterColumn \(AutoFilter Column\)](#) 310

[filters \(Filter Criteria\)](#) 310
[FIND](#) 467
[FINDB](#) 468
[FINV](#) 468
[firstFooter \(First Footer\)](#) 691
[firstFooter \(First Page Footer\)](#) 284
[firstHeader \(First Header\)](#) 691
[firstHeader \(First Page Header\)](#) 284
[fitText \(Manual Run Width\)](#) 72
[FIXED](#) 468
[Fixed Commands](#) 851
[flatBorders \(Frameset Splitter Border Style\)](#) 175
[flatTx \(No text in 3D scene\)](#) 661
[fld \(Text Field\)](#) 567
[fldData \(Custom Field Data\)](#) ([section 2.1.547](#) 245, [section 2.1.548](#) 246)
[fldSimple \(Ruby Simple Field\)](#) 943
[fldSimple \(Simple Field\)](#) 246
[FLOOR](#) 468
[floor \(Floor\)](#) 691
[FmlaGroup \(Linked Formula - Group Box\)](#) 795
[FmlaMacro \(Reference to Custom Function\)](#) 795
[FmlaRange \(List Items Source Range\)](#) 795
[FmlaTxbx \(Text Formula\)](#) 795
[fmtId \(Format ID\)](#) 691
[fName \(Function Name\)](#) 805
[folHlink \(Followed Hyperlink\)](#) 564
[font \(Embedded Font Name\)](#) 506
[font \(Font\)](#) 320
[font \(Properties for a Single Font\)](#) 129
[font \(Standard COM Font Object\)](#) 1017
[Font Part](#) 62
[fontRef \(Font Reference\)](#) 564
[Fonts](#) 127
[fonts \(Fonts\)](#) 320
[footerReference \(Footer Reference\)](#) 134
[footnote \(Footnote Content\)](#) 136
[footnote \(Special Footnote List\)](#) 136
[footnoteLayoutLikeWW8 \(Emulate Word 6.x/95/97 Footnote Placement\)](#) 181
[footnoteReference \(Footnote Reference\)](#) 136
[forEach \(For Each\)](#) 733
[FORECAST](#) 469
[format \(PivotTable Format\)](#) 361
[format \(Text Box Form Field Formatting\)](#) 246
[formatting \(Formatting\)](#) 691
[FORMCHECKBOX](#) 235
[FORMDROPDOWN](#) 235
[formula \(Formula\)](#) 284
[formula1 \(Formula 1\)](#) 285
[formula2 \(Formula 2\)](#) 285
[Formulas](#) 429
[formulas \(Set of Formulas\)](#) 754
[forward \(Forward\)](#) 692
[frameLayout \(Frameset Layout\)](#) 175
[framePr \(Text Frame Properties\)](#) 64
[frameset \(Nested Frameset Definition\)](#) 175
[frameset \(Root Frameset Definition\)](#) 175
[from \(From\)](#) ([section 2.1.1196](#) 537, [section 2.1.1197](#) 537)
[from \(Starting Anchor Point\)](#) 675

[ftr \(Footer\)](#) 134
[func \(Function Apply Function\)](#) 805
[functionGroup \(Function Group\)](#) 264
[functionGroups \(Function Groups\)](#) 264
[Functions](#) 442
[futureMetadata \(Future Metadata\)](#) 335
[FV](#) 469

G

[GAMMAINV](#) 469
[gapDepth \(Gap Depth\)](#) 692
[gapWidth \(Gap Width\)](#) 692
[gd \(Shape Guide\)](#) 668
[General formatting](#) 206
[GEOMEAN](#) 469
[GETPIVOTDATA](#) 469
[Glossary](#) ([section 1.1](#) 48, [section 3.1.3.2.3](#) 965)
[Glossary of WordprocessingML-Specific Terms](#) 52
[GOTOBUTTON](#) 235
[gradFill \(Gradient Fill\)](#) 667
[gradientFill \(Gradient\)](#) 321
[Graphic Frame Doc](#) 973
[graphicData \(Graphic Object Data\)](#) 558
[graphicEl \(Graphic Element\)](#) 538
[graphicFrame \(Graphic Frame\)](#) ([section 2.1.1428](#) 676, [section 2.1.1653](#) 731)
[graphicFrameLocks \(Graphic Frame Locks\)](#) 559
[green \(Green\)](#) 561
[greenMod \(Green Modification\)](#) 561
[greenOff \(Green Offset\)](#) 561
[GREETINGLINE](#) 235
[gridAfter \(Grid Columns After Last Cell\)](#) 83
[gridBefore \(Grid Columns Before First Cell\)](#) 84
[gridCol \(Table Grid Column\)](#) 576
[gridSpacing \(Grid Spacing\)](#) 512
[gridSpan \(Grid Columns Spanned by Current Table Cell\)](#) 84
[group \(OLAP Group\)](#) 361
[group \(Shape Group\)](#) 754
[groupChr \(Group-Character Function\)](#) 805
[groupChrPr \(Group-Character Properties\)](#) 805
[grouping \(Bar Grouping\)](#) 692
[grouping \(Grouping\)](#) 692
[groupItems \(OLAP Group Items\)](#) 362
[groupLevel \(OLAP Grouping Levels\)](#) 362
[groupMember \(OLAP Group Member\)](#) 362
[grow \(n-ary Grow\)](#) 805
[grpFill \(Group Fill\)](#) 667
[grpSpLocks \(Group Shape Locks\)](#) 559
[grpSpPr \(Group Shape Properties\)](#) ([section 2.1.1156](#) 514, [section 2.1.1429](#) 676, [section 2.1.1654](#) 731)
[grpSpPr \(Visual Group Shape Properties\)](#) 559
[guid \(Entry ID\)](#) 137
[Guid \(GUID\)](#) 824
[guide \(A Guide\)](#) 512
[guideLst \(List of Guides\)](#) 512

H

[h \(Height\)](#) 693

[h \(Shape Handle\)](#) 754
[handles \(Set of Handles\)](#) 754
[Handout Master Part](#) 55
[HARMEAN](#) 469
[hash \(Hash Code for Record\)](#) 932
[hdr \(Header\)](#) 134
[hdrShapeDefaults \(Default Properties for VML Objects in Header and Footer\)](#) 167
[header \(Header\)](#) 412
[headerFooter \(Header and Footer\)](#) 693
[headerReference \(Header Reference\)](#) 135
[headers \(Revision Headers\)](#) 412
[headerSource \(Header Definition File Path\)](#) 156
[HeadingPairs \(Heading Pairs\)](#) 817
[hidden \(Hidden Table Row Marker\)](#) 84
[hidden \(Hide Style From User Interface\)](#) 111
[hideMark \(Ignore End Of Cell Marker In Row Height Calculation\)](#) 84
[highlight \(Text Highlighting\)](#) 72
[hlink \(Hyperlink\)](#) 564
[hlinkClick \(Click Hyperlink\)](#) 569
[hlinkHover \(Hyperlink for Hover\)](#) 559
[hlinkMouseOver \(Mouse-Over Hyperlink\)](#) 570
[HLinks \(Hyperlink List\)](#) 818
[HLOOKUP](#) 470
[hMerge \(Horizontally Merged Cell\)](#) 84
[hMode \(Height Mode\)](#) 693
[holeSize \(Hole Size\)](#) 693
[Horiz \(Scroll Bar Orientation\)](#) 795
[HorizontalResolution \(Horizontal Resolution\)](#) 1025
[HOUR](#) 470
[hPercent \(Height Percent\)](#) 694
[hpsRaise \(Distance Between Phonetic Guide Text and Phonetic Guide Base Text\)](#) 81
[hsl \(HSL\)](#) 538
[hsl \(Hue Saturation Luminance Effect\)](#) 667
[HTML Publish Location](#) 60
[htmlPubPr \(HTML Publishing Properties\)](#) 506
[HYPERLINK](#) 237
[hyperlink \(Hyperlink\) \(section 2.1.551 246, section 2.1.655 285\)](#)
[hyperlink \(Ruby Hyperlink\)](#) 948
[hyphenationZone \(Hyphenation Zone\)](#) 167

I

[i \(Italics\)](#) 72
[i \(Row Items\)](#) 362
[iconFilter \(Icon Filter\)](#) 310
[iCs \(Complex Script Italics\)](#) 73
[id \(Unique ID\)](#) 101
[idmap \(Shape ID Map\)](#) 781
[idx \(Index\)](#) 694
[IF](#) 470
[IFERROR](#) 470
[ignoredError \(Ignored Error\)](#) 285
[ignoredErrors \(Ignored Errors\)](#) 285
[ilvl \(Numbering Level Reference\)](#) 130
[image \(Image File\)](#) 755
[Image Part](#) 62
[imagedata \(Image Data\)](#) 756
[IMARGUMENT](#) 470

[IMDIV](#) 470
[IMLN](#) 470
[IMLOG10](#) 471
[IMLOG2](#) 471
[IMPORT](#) 966
[IMPOWER](#) 471
[imprint \(Imprinting\)](#) 73
[IMSIN](#) 471
[IMSORT](#) 471
[Inc \(Scroll Bar Increment\)](#) 796
[INCLUDE](#) 966
[INDEX \(section 2.1.509 237, section 2.1.1000 471\)](#)
[indexedColors \(Color Indexes\)](#) 321
[INDIRECT](#) 472
[INFO](#) 472
[Informative references](#) 50
[ink \(Ink\)](#) 782
[inkTgt \(Ink Target\)](#) 538
[innerShdw \(Inner Shadow Effect\)](#) 667
[inputCells \(Input Cells\)](#) 285
[ins \(Inserted Math Control Character\)](#) 144
[ins \(Inserted Numbering Properties\)](#) 145
[ins \(Inserted Paragraph\)](#) 145
[ins \(Inserted Run Content\)](#) 145
[ins \(Inserted Table Row\)](#) 144
[insideH \(Table Cell Inside Horizontal Edges Border\)](#) 85
[insideH \(Table Inside Horizontal Edges Border\)](#) 84
[insideV \(Table Cell Inside Vertical Edges Border\)](#) 85
[insideV \(Table Inside Vertical Edges Border\)](#) 85
[INTERCEPT](#) 472
[intercept \(Intercept\)](#) 694
[Interpretation](#) 444
[interSp \(Inter-Equation Spacing\)](#) 806
[intLim \(Integral Limit Locations\)](#) 806
[intraSp \(Intra-Equation Spacing\)](#) 806
[INTRATE](#) 472
[Introduction \(section 1 48, section 3.8.1 1034\)](#)
[invertIfNegative \(Invert if Negative\)](#) 694
[IPMT](#) 473
[IRR](#) 474
[is \(Rich Text Inline\)](#) 286
[isLgl \(Display All Levels Using Arabic Numerals\)](#) 130
[ISPMT](#) 474
[item \(PivotTable Field Item\)](#) 363
[items \(Field Items\)](#) 365
[iterate \(Iterate\)](#) 538

J

[jc \(Justification\)](#) 806
[jc \(Paragraph Alignment\)](#) 65
[jc \(Table Alignment Exception\)](#) 85
[jc \(Table Alignment\)](#) 85
[jc \(Table Row Alignment\)](#) 85

K

[k \(KPI MDX Metadata\)](#) 336
[keepLines \(Keep All Lines On One Page\)](#) 65
[kern \(Font Kerning\)](#) 73
[Keyboard and Toolbar Customizations](#) 837

[keymap \(Key Map Entry\)](#) 843
[keymaps \(Key Map Customizations\)](#) 845
[keymapsBad \(Key Map Customizations for Mismatched Keyboards\)](#) 846
[KEYWORDS](#) 237
[kinsoku \(Kinsoku Settings\)](#) 507
[kinsoku \(Use East Asian Typography Rules for First and Last Character per Line\)](#) 65
[kpi \(OLAP KPI\)](#) 366

L

[lang \(Languages for Run Content\)](#) 73
[LASTSAVEDBY](#) 237
[latentStyles \(Latent Style Information\)](#) 111
[latin \(Latin Font\)](#) 570
[layout \(Layout\)](#) 694
[layoutTarget \(Layout Target\)](#) 695
[LCID \(Locale ID\)](#) 824
[LCT \(Callback Type\)](#) 796
[leaderLines \(Leader Lines\)](#) 695
[LEFT](#) 474
[left \(Left Border for HTML div\)](#) 175
[left \(Left Border\)](#) 107
[left \(Left Paragraph Border\)](#) 66
[left \(Table Cell Left Border\)](#) 85
[left \(Table Cell Left Margin Default\)](#) 86
[left \(Table Cell Left Margin Exception\)](#) 86
[left \(Table Left Border\)](#) 86
[left \(Text Box Left Stroke\)](#) 782
[LEFTB](#) 474
[legacy \(Legacy Numbering Level Properties\)](#) 131
[Legacy Diagram Text Info part](#) 994
[Legacy Diagram Text part](#) 993
[legendPos \(Legend Position\)](#) 695
[LEN](#) 474
[LENB](#) 475
[lid \(Date Picker Language ID\)](#) 101
[lid \(Language ID for Phonetic Guide\)](#) 81
[lid \(Merge Field Name Language ID\)](#) 156
[lightRiq \(Light Riq\)](#) 661
[lim \(Limit \(Lower\)\)](#) 806
[Limitations in Word](#) 1038
[limLoc \(n-ary Limit Location\)](#) 806
[limLow \(Lower-Limit Function\)](#) 807
[limUpp \(Upper-Limit Function\)](#) 807
[linClrLst \(Line Color List\)](#) 735
[line \(Line\)](#) 757
[line3DChart \(3D Line Charts\)](#) 695
[lineChart \(Line Charts\)](#) 695
[LINEST](#) 475
[lineTo \(Wrapping Polygon Line End Position\)](#) 674
[lineWrapLikeWord6 \(Emulate Word 6.0 Line Wrapping for East Asian Text\)](#) 183
[LINK](#) 237
[link \(Linked Object or Control\)](#) 516
[link \(Linked Style Reference\)](#) 111
[linkedToFile \(Maintain Link to Existing File\)](#) 176
[linkToQuery \(Query Contains Link to External Query File\)](#) 156
[LinkType \(Embedded Object Alternate Image Request\)](#) 783

[listEntry \(Drop-Down List Entry\)](#) 246
[ListItem \(Non-linked List Item\)](#) 796
[LISTNUM](#) 238
[listSeparator \(List Separator for Field Code Evaluation\)](#) 168
[lit \(Literal\)](#) 807
[lMargin \(Left Margin\)](#) 807
[ln \(Outline\)](#) 559
[lnB \(Bottom Border Line Properties\)](#) 576
[lnBlToTr \(Bottom-Left to Top-Right Border Line Properties\)](#) 576
[lnL \(Left Border Line Properties\)](#) 577
[lnNumType \(Line Numbering Settings\)](#) 107
[lnR \(Right Border Line Properties\)](#) 577
[lnRef \(Line Reference\)](#) 565
[lnSpc \(Line Spacing\)](#) 568
[lnT \(Top Border Line Properties\)](#) 577
[lnTlToBr \(Top-Left to Bottom-Right Border Line Properties\)](#) 577
[location \(PivotTable Location\)](#) 367
[lock \(Shape Protections\)](#) 783
[locked \(Style Cannot Be Applied\)](#) 112
[LockedField \(Embedded Object Cannot Be Refreshed\)](#) 783
[LOG](#) 475
[LOGEST](#) 476
[LOGINV](#) 476
[LOGNORMDIST](#) 476
[Long Properties](#) 1015
[Long Properties Schema](#) 1016
[LongProp \(Custom XML Server Property - Long Property\)](#) 1016
[LongProperties \(Custom XML Server Properties - Long Properties\)](#) 1016
[IsdException \(Latent Style Exception\)](#) 112
[lt1 \(Light 1\)](#) 564
[lt2 \(Light 2\)](#) 564
[lum \(Luminance Effect\)](#) 667
[lum \(Luminance\)](#) 561
[lumMod \(Luminance Modulation\)](#) 561
[lumOff \(Luminance Offset\)](#) 561
[lvl \(Level\)](#) 695
[lvl \(Numbering Level Definition\)](#) 131
[lvl \(Numbering Level Override Definition\)](#) 131
[lvl1pPr \(List Level 1 Text Style\)](#) 574
[lvl2pPr \(List Level 2 Text Style\)](#) 575
[lvl3pPr \(List Level 3 Text Style\)](#) 575
[lvl4pPr \(List Level 4 Text Style\)](#) 575
[lvl5pPr \(List Level 5 Text Style\)](#) 575
[lvl6pPr \(List Level 6 Text Style\)](#) 575
[lvl7pPr \(List Level 7 Text Style\)](#) 576
[lvl8pPr \(List Level 8 Text Style\)](#) 576
[lvl9pPr \(List Level 9 Text Style\)](#) 576
[lvlJc \(Justification\)](#) 131
[lvlRestart \(Restart Numbering Level Symbol\)](#) 131
[lvlText \(Numbering Level Text\)](#) 132

M

[m \(Matrix Function\)](#) 807
[m \(No Value\)](#) 367
[macro \(Macro Keyboard Customization Action\)](#) 847

[MACROBUTTON](#) 238
[Mail Merge \(section 2.1.366 153, section 3.1.2.2 931\)](#)
[Mail Merge Recipient Data Part](#) 836
[mailMerge \(Mail Merge Settings\)](#) 156
[main \(Main\)](#) 427
[Main Document Part](#) 52
[majorTickMark \(Major Tick Mark\)](#) 695
[majorTimeUnit \(Major Time Unit\)](#) 696
[majorUnit \(Major Unit\)](#) 696
[ManifestHashAlgorithm \(Manifest Hash Algorithm\)](#) 1025
[manuallyLayout \(Manual Layout\)](#) 696
[map \(OLAP Measure Group\)](#) 369
[Map \(XML Mapping Properties\)](#) 428
[mappedName \(Predefined Merge Field Name\)](#) 156
[marker \(Marker\)](#) 696
[marker \(Show Marker\)](#) 696
[Markup Compatibility Attributes and Elements](#) 833
[MATCH](#) 476
[Math \(section 2.1.4 51, section 2.1.1796 798\)](#)
[Math Run](#) 1038
[mathFont \(Math Font\)](#) 807
[max \(Maximum\)](#) 696
[Max \(Scroll Bar Maximum\)](#) 796
[maxDist \(Maximum Distribution\)](#) 808
[maxLength \(Text Box Form Field Maximum Length\)](#) 247
[mc \(Matrix Column\)](#) 808
[mcs \(Matrix Columns\)](#) 808
[MDURATION](#) 476
[mdx \(MDX Metadata Record\)](#) 336
[mdxMetadata \(MDX Metadata Information\)](#) 336
[measureGroup \(OLAP Measure Group\)](#) 369
[member \(Member\)](#) 369
[members \(Members\)](#) 370
[mergeCells \(Merge Cells\)](#) 286
[MERGEFIELD](#) 239
[Metadata Attributes](#) 1006
[metadataStrings \(Metadata String Store\)](#) 336
[metadataType \(Metadata Type Information\)](#) 336
[metadataTypes \(Metadata Types Collection\)](#) 340
[Microsoft Office Excel Sortmap](#) 980
[MID](#) 477
[MIDB](#) 477
[MIN](#) 478
[min \(Minimum\)](#) 696
[Min \(Scroll Bar Minimum\)](#) 796
[MINA](#) 478
[minorTickMark \(Minor Tick Mark\)](#) 697
[minorTimeUnit \(Minor Time Unit\)](#) 697
[minorUnit \(Minor Unit\)](#) 697
[minus \(Minus\)](#) 697
[MINVERSE](#) 478
[mirrorIndents \(Use Left/Right Indents as Inside/Outside Indents\)](#) 66
[miter \(Miter Line Join\)](#) 667
[modifyVerifier \(Modification Verifier\)](#) 507
[Monitors \(Monitor Count\)](#) 1025
[moveFrom \(Move Source Math Control Character\)](#) 954

[moveFrom \(Move Source Paragraph\)](#) 146
[moveFrom \(Move Source Run Content\)](#) 145
[moveFromRangeEnd \(Move Source Location Container - End\)](#) 146
[moveFromRangeStart \(Move Source Location Container - Start\)](#) 146
[moveTo \(Move Destination Math Control Character\)](#) 955
[moveTo \(Move Destination Paragraph\)](#) 146
[moveTo \(Move Destination Run Content\)](#) 146
[moveToRangeEnd \(Move Destination Location Container - End\)](#) 147
[moveToRangeStart \(Move Destination Location Container - Start\)](#) 147
[MoveWithCells \(Move with Cells\)](#) 796
[movie \(Embedded Video\)](#) 81
[mp \(OLAP Member Property\)](#) 370
[mpMap \(Member Properties Map\)](#) 371
[mr \(Matrix Row\)](#) 808
[mruColors \(MRU Colors\)](#) 321
[ms \(Set MDX Metadata\)](#) 340
[multiLvlStrCache \(Multi Level String Cache\)](#) 697
[multiLvlStrRef \(Multi Level String Reference\)](#) 697
[MULTINOMIAL](#) 479
[mwSmallCaps \(Emulate Word 5.x for the Macintosh Small Caps Formatting\)](#) 184

N

[N](#) 479
[n \(Member Unique Name Index\)](#) 340
[n \(Numeric\)](#) 372
[name \(Abstract Numbering Definition Name\)](#) 132
[name \(Data Source Name for Column\)](#) 156
[name \(Font Name\)](#) 321
[name \(Frame Name\)](#) 176
[name \(Pivot Name\)](#) 697
[name \(Primary Style Name\)](#) 112
[Name Formulas](#) 989
[Name Representation](#) 444
[Names](#) 442
[nary \(n-ary Operator Function\)](#) 808
[naryLim \(n-ary Limit Location\)](#) 808
[nc \(New Cell Data\)](#) 413
[NEGBINOMDIST](#) 479
[NETWORKDAYS](#) 479
[next \(Style For Next Paragraph\)](#) 121
[nextCondLst \(Next Conditions List\)](#) 538
[noAutofit \(No AutoFit\)](#) 566
[noBorder \(Do Not Display Frameset Splitters\)](#) 176
[noBreak \(No Break\)](#) 808
[noEndCap \(No End Cap\)](#) 698
[noLineBreaksAfter \(Custom Set of Characters Which Cannot End a Line\)](#) 168
[noLineBreaksBefore \(Custom Set Of Characters Which Cannot Begin A Line\)](#) 168
[noMultiLvlLbl \(No Multi-level Labels\)](#) 698
[noProof \(Do Not Check Spelling or Grammar\)](#) 73
[noPunctuationKerning \(Never Kern Punctuation Characters\)](#) 168
[noResizeAllowed \(Frame Cannot Be Resized\)](#) 176
[norm \(Normal\)](#) 661

[normalViewPr \(Normal View Properties\)](#) 512
[Normative references](#) 49
[normAutofit \(Normal AutoFit\)](#) 566
[NORMINV](#) 479
[NORMSDIST](#) 479
[NORMSINV](#) 480
[NOTEREF](#) 239
[Notes Master Part](#) 56
[Notes Slide Part](#) 57
[notesMaster \(Notes Master\)](#) 514
[notesStyle \(Notes Text Style\)](#) 514
[notesSz \(Notes Slide Size\)](#) 510
[NoThreeD \(Disable 3D\)](#) 796
[notTrueType \(Raster or Vector Font\)](#) 129
[noWrap \(Don't Wrap Cell Content\)](#) 86
[NPER](#) 480
[NPV](#) 480
[null \(Null\)](#) 823
[num \(Numbering Definition Instance\)](#) 132
[num \(Numerator\)](#) 809
[numberingChange \(Previous Numbering Field Properties\)](#) 147
[numberingChange \(Previous Paragraph Numbering Properties\)](#) 147
[numFmt \(Endnote Numbering Format\)](#) 136
[numFmt \(Footnote Numbering Format\)](#) 136
[numFmt \(Number Format\)](#) ([section 2.1.738](#) 321, [section 2.1.1528](#) 698)
[numFmt \(Numbering Format\)](#) 132
[numFmts \(Number Formats\)](#) 332
[numId \(Numbering Definition Instance Reference\)](#) 132
[numPr \(Numbering Definition Instance Reference\)](#) 66
[numStart \(Footnote and Endnote Numbering Starting Value\)](#) 137
[numStyleLink \(Numbering Style Reference\)](#) 133
[nvPr \(Non-Visual Properties\)](#) 514

O

[objDist \(Object Distribution\)](#) 809
[object \(Inline Embedded Object\)](#) 81
[oc \(Old Cell Data\)](#) 414
[OCT2BIN](#) 480
[OCT2DEC](#) 481
[ocx \(ActiveX Control Data\)](#) 1018
[ocxPr \(Object Property\)](#) 1020
[oddFooter \(Odd Footer\)](#) 699
[oddFooter \(Odd Page Footer\)](#) 286
[ODDFPRICE](#) 481
[ODDFYIELD](#) 481
[oddHeader \(Odd Header\)](#) ([section 2.1.662](#) 286, [section 2.1.1530](#) 699)
[ODDLPRICE](#) 482
[ODDLYIELD](#) 483
[odso \(Office Data Source Object Settings\)](#) 157
[off \(Offset\)](#) 663
[Office ActiveX Supplemental Information \(Additional Information\)](#) 1017
[Office Digital Signature \(Additional Information\)](#) 1023

[Office Well Defined Custom XML Parts \(Additional Information\)](#) 998
[OfficeVersion \(Office Version\)](#) 1026
[OFFSET](#) 484
[ofPieChart \(Pie of Pie or Bar of Pie Charts\)](#) 699
[ofPieType \(Pie of Pie or Bar of Pie Type\)](#) 699
[olapPr \(OLAP Properties\)](#) 422
[oldFormula \(Old Formula\)](#) 414
[OLE Link Formulas](#) 993
[oleChartEl \(Embedded Chart Element\)](#) 538
[oleItem \(OLE Link Item\)](#) 425
[oleLink \(OLE Link\)](#) 426
[oleObj \(Global Element for Embedded objects and Controls\)](#) 516
[oleObject \(Embedded Object\)](#) 287
[OLEObject \(Embedded OLE Object\)](#) 784
[oleObjects \(Embedded Objects\)](#) 287
[oleSize \(Embedded Object Size\)](#) 264
[oMath \(Office Math\)](#) 809
[oMath \(Office Open XML Math\)](#) 73
[oMath and Math Arguments](#) 1037
[oMathPara \(Math Paragraph\)](#) 810
[opEmu \(Operator Emulator\)](#) 811
[openByDefault \(Open By Default\)](#) 1015
[Operators](#) ([section 2.1.483](#) 194, [section 2.1.889](#) 439)
[optimizeForBrowser \(Disable Features Not Supported by Target Web Browser\)](#) 176
[order \(Order\)](#) 699
[order \(Polynomial Trendline Order\)](#) 699
[orientation \(Axis Orientation\)](#) 700
[origin \(View Origin\)](#) 513
[ostorage \(Binary Storage Object\)](#) 823
[outline \(Display Character Outline\)](#) 74
[outlineLvl \(Associated Outline Level\)](#) 66
[oval \(Oval\)](#) 758
[overflowPunct \(Allow Punctuation to Extent Past Text Extents\)](#) 66
[overlap \(Overlap\)](#) 700
[overlay \(Overlay\)](#) 700

P

[p \(Member Property MDX Metadata\)](#) 340
[p \(Paragraph\)](#) 67
[p \(Text Paragraphs\)](#) 568
[Packages](#) 51
[Page \(Scroll Bar Page Increment\)](#) 796
[pageField \(Page Field\)](#) 373
[pageFields \(Page Field Items\)](#) 374
[pageItem \(Page Item\)](#) 374
[pageMargins \(Page Margins\)](#) ([section 2.1.665](#) 287, [section 2.1.1538](#) 700)
[PAGEREF](#) 239
[pageSetup \(Chart Sheet Page Setup\)](#) 292
[pageSetup \(Page Setup Settings\)](#) 288
[pageSetup \(Page Setup\)](#) 701
[pane \(View Pane\)](#) 297
[panose1 \(Pansose-1 Typeface Classification Number\)](#) 129
[paperSrc \(Paper Source Information\)](#) 107
[Paragraph Styles](#) 126

[param \(Parameter\)](#) 734
[parameter \(Parameter Properties\)](#) 422
 Part Summary ([section 2.1.7](#) 52, [section 2.1.9](#) 52, [section 2.1.19](#) 55, [section 2.1.30](#) 61)
[path \(Shape Path\)](#) ([section 2.1.1389](#) 669, [section 2.1.1704](#) 758)
[PEARSON](#) 484
[PERCENTILE](#) 484
[PERCENTRANK](#) 484
[period \(Period\)](#) 705
[permEnd \(Range Permission End\)](#) 152
[permStart \(Range Permission Start\)](#) 152
[Person \(Person\)](#) 832
[personal \(E-Mail Message Text Style\)](#) 121
[personalCompose \(E-Mail Message Composition Style\)](#) 122
[personalReply \(E-Mail Message Reply Style\)](#) 122
[perspective \(Perspective\)](#) 706
[pgBorders \(Page Borders\)](#) 107
[pgMar \(Page Margins\)](#) 108
[pgNumType \(Page Numbering Settings\)](#) 108
[pgSz \(Page Size\)](#) 108
[ph \(Placeholder Shape\)](#) 515
[phant \(Phantom Function\)](#) 811
[phoneticPr \(Phonetic Properties\)](#) 311
[photoAlbum \(Photo Album Information\)](#) 510
[pic \(Picture\)](#) ([section 2.1.1430](#) 676, [section 2.1.1655](#) 731)
[picLocks \(Picture Locks\)](#) 559
[pict \(Picture Numbering Symbol Properties\)](#) 133
[pict \(VML Object\)](#) 81
[picture \(Standard COM Picture Object\)](#) 1021
[pictureOptions \(Picture Options\)](#) 706
[pie3DChart \(3D Pie Charts\)](#) 706
[pieChart \(Pie Charts\)](#) 706
[pitch \(Font Pitch\)](#) 130
[Pivot Formulas](#) 991
[pivotArea \(Pivot Area\)](#) 297
[pivotCacheDefinition \(PivotCache Definition\)](#) 374
[pivotCacheRecords \(PivotCache Records\)](#) 376
[pivotField \(PivotTable Field\)](#) 376
[pivotFields \(PivotTable Fields\)](#) 384
[pivotFmt \(Pivot Format\)](#) 707
[pivotFmts \(Pivot Formats\)](#) 707
[pivotHierarchies \(PivotTable OLAP Hierarchies\)](#) 384
[pivotHierarchy \(OLAP Hierarchy\)](#) 385
[pivotSelection \(PivotTable Selection\)](#) 298
[pivotSource \(Pivot Source\)](#) 707
[pivotTableDefinition \(PivotTable Definition\)](#) 386
[pivotTableStyleInfo \(PivotTable Style\)](#) 393
[pixelsPerInch \(Pixels per Inch for Graphics/Images\)](#) 176
[placeholder \(Structured Document Tag Placeholder Text\)](#) 102
[plotArea \(Plot Area\)](#) 707
[plotVisOnly \(Plot Visible Only\)](#) 707
[plus \(Plus\)](#) 707
[PMT](#) 484
[POISSON](#) 484
[polyline \(Multiple Path Line\)](#) 761
[pos \(Comment Position\)](#) 518
[pos \(Footnote Placement\)](#) 137
[pos \(Position\)](#) ([section 2.1.1431](#) 676, [section 2.1.1853](#) 812)
[pos \(Shape Position Coordinate\)](#) 669
[positionV \(Vertical Positioning\)](#) 674
[postSp \(Post-Equation Spacing\)](#) 812
[POWER](#) 485
[PowerPoint \(Additional Information\)](#) 993
[PPMT](#) 485
[pPr \(Numbering Level Associated Paragraph Properties\)](#) 133
[pPr \(Paragraph Properties\)](#) 123
[pPr \(Previous Paragraph Properties\)](#) 67
[pPr \(Style Paragraph Properties\)](#) 126
[pPr \(Table Style Conditional Formatting Paragraph Properties\)](#) 124
[pPr \(Text Paragraph Properties\)](#) 568
[pPrChange \(Revision Information for Paragraph Properties\)](#) 150
[Precision](#) 443
[present \(Presenter Slide Show Mode\)](#) 511
[presentation \(Presentation\)](#) 511
[Presentation Part](#) 58
[Presentation Properties Part](#) 58
[PresentationML](#) 51
[preSp \(Pre-Equation Spacing\)](#) 812
[prevCondLst \(Previous Conditions List\)](#) 538
[pRg \(Paragraph Text Range\)](#) 539
[PRICE](#) 485
[PRICEDISC](#) 486
[PRICEMAT](#) 486
[PRINT](#) 239
[PRINTDATE](#) 240
[Printer Settings Part](#) 63
[printerSettings \(Reference to Printer Settings Data\)](#) 109
[printFractionalCharacterWidth \(Print Fractional Character Widths\)](#) 168
[printPostScriptOverText \(Print PostScript Codes With Document Text\)](#) 169
[printSettings \(Print Settings\)](#) 708
[PROB](#) 487
[PRODUCT](#) 487
[progress \(Progress\)](#) 539
[proofErr \(Proofing Error Anchor\)](#) 153
[property \(Custom File Property\)](#) 819
[protectedRange \(Protected Range\)](#) 299
[protection \(Protection Properties\)](#) 333
[protection \(Protection\)](#) 708
[proxy \(Shape Reference\)](#) 784
[prSet \(Property Set\)](#) 734
[prstClr \(Preset Color\)](#) 562
[pStyle \(Paragraph Style's Associated Numbering Level\)](#) 133
[pStyle \(Referenced Paragraph Style\)](#) 67
[pt \(Numeric Point\)](#) 708
[pt \(Point\)](#) 735
[pt \(Shape Path Point\)](#) 669
[pt \(String Point\)](#) 708
[ptCount \(Point Count\)](#) 708
[PublishDate \(Document Publish Date\)](#) 1000

[PV](#) 487

Q

[qFormat \(Primary Style\)](#) 122
[query \(Query For Data Source Records To Merge\)](#) 157
[query \(Query\)](#) 394
[queryTable \(Query Table\)](#) 419
[queryTableField \(QueryTable Field\)](#) 419
[queryTableRefresh \(QueryTable Refresh Information\)](#) 420
[Quick Access Toolbar Customizations Part](#) 996
[QUOTE](#) 240

R

[r \(PivotCache Record\)](#) 394
[r \(Rule\)](#) 785
[r \(Run\)](#) 812
[r \(Text Run\)](#) ([section 2.1.88](#) 74, [section 2.1.1317](#) 572)
[R1C1 formulas](#) 990
[R1C1-Style Cell Reference](#) 441
[rad \(Radical Function\)](#) 812
[radarChart \(Radar Charts\)](#) 709
[radarStyle \(Radar Style\)](#) 709
[raf \(Revision AutoFormat\)](#) 414
[rAngAx \(Right Angle Axes\)](#) 709
[rangePr \(Range Grouping Properties\)](#) 394
[rangeSet \(Range Set\)](#) 396
[RANK](#) 487
[RATE](#) 488
[rc \(Metadata Record\)](#) 341
[rcc \(Revision Cell Change\)](#) 414
[rcft \(Revision Merge Conflict\)](#) 414
[rcmt \(Revision Cell Comment\)](#) 415
[rCtr \(Rotation Center\)](#) 539
[RD](#) 240
[rdn \(Revision Defined Name\)](#) 415
[Reading the equationXml attribute](#) 1035
[readModeInkLockDown \(Freeze Document Layout\)](#) 169
[RecalcAlways \(Recalculation Toggle\)](#) 797
[RECEIVED](#) 488
[recipientData \(Data About Single Data Source Record\)](#) 933
[recipientData \(Reference to Inclusion/Exclusion Data for Data Source\)](#) 157
[recipients \(Inclusion/Exclusion Data for Data Source\)](#) 935
[rect \(Rectangle\)](#) 761
[red \(Red\)](#) 562
[redMod \(Red Modulation\)](#) 562
[redOff \(Red Offset\)](#) 562
[REF](#) 240
[reference \(Reference\)](#) 410
References
 [informative](#) 50
 [normative](#) 49
[reflection \(Reflection Effect\)](#) 668
[rel \(Diagram Relationship\)](#) 785

[Relationships Transform Algorithm](#) 63
[relSizeAnchor \(Relative Anchor Shape Size\)](#) 731
[REPLACE](#) 488
[REPLACED](#) 489
[restoredLeft \(Normal View Restored Left Properties\)](#) 513
[restoredTop \(Normal View Restored Top Properties\)](#) 513
[reviewed \(Reviewed\)](#) 416
[revisionView \(Visibility of Annotation Types\)](#) 169
[REVNUM](#) 241
[rfmt \(Revision Format\)](#) 416
[rFont \(Font\)](#) 311
[rFonts \(Run Fonts\)](#) 74
[rgb \(RGB\)](#) 539
[Ribbon Extensibility Part](#) 997
[rich \(Rich Text\)](#) 709
[RIGHT](#) 489
[right \(Right Border for HTML div\)](#) 177
[right \(Right Border\)](#) 109
[right \(Right Paragraph Border\)](#) 67
[right \(Table Cell Right Border\)](#) 87
[right \(Table Cell Right Margin Default\)](#) 86
[right \(Table Cell Right Margin Exception\)](#) 87
[right \(Table Right Border\)](#) 87
[right \(Text Box Right Stroke\)](#) 785
[RIGHTB](#) 489
[ris \(Revision Insert Sheet\)](#) 416
[rm \(Revision Cell Move\)](#) 417
[rMargin \(Right Margin\)](#) 812
[ROMAN](#) 490
[rotX \(X Rotation\)](#) 709
[rotY \(Y Rotation\)](#) 709
[ROUND](#) 490
[round \(Round Line Join\)](#) 668
[roundedCorners \(Rounded Corners\)](#) 709
[roundrect \(Rounded Rectangle\)](#) 761
[row \(Row\)](#) ([section 2.1.672](#) 301, [section 2.1.872](#) 426, [section 2.1.1432](#) 676, [section 3.2.2.1.3](#) 984)
[rowBreaks \(Horizontal Page Breaks \(Row\)\)](#) 302
[RowHidden \(Comment's Row is Hidden\)](#) 797
[rowHierarchyUsage \(Row OLAP Hierarchies\)](#) 397
[ROWS](#) 490
[rowSortMap \(Row Sort Map\)](#) 984
[rPh \(Phonetic Run\)](#) 311
[rPr \(Numbering Symbol Run Properties\)](#) 133
[rPr \(Previous Run Properties for the Paragraph Mark\)](#) 67
[rPr \(Previous Run Properties\)](#) 78
[rPr \(Run Properties For Structured Document Tag Contents\)](#) 102
[rPr \(Run Properties for the Paragraph Mark\)](#) 67
[rPr \(Run Properties\)](#) ([section 2.1.90](#) 78, [section 2.1.246](#) 123, [section 2.1.261](#) 127, [section 2.1.702](#) 311)
[rPr \(Structured Document Tag End Character Run Properties\)](#) 102
[rPr \(Table Style Conditional Formatting Run Properties\)](#) 124
[rPr \(Text Run Properties\)](#) 573

[rPrChange \(Revision Information for Run Properties on the Paragraph Mark\)](#) 150
[rPrChange \(Revision Information for Run Properties\)](#) 150
[rqt \(Revision Query Table\)](#) 417
[rrc \(Revision Row Column Insert Delete\)](#) 417
[rsid \(Single Session Revision Save ID\)](#) 169
[rsnm \(Revision Sheet Name\)](#) 417
[rSp \(Row Spacing\)](#) 813
[rSpRule \(Row Spacing Rule\)](#) 813
[RSQ](#) 490
[rStyle \(Referenced Character Style\)](#) 78
[rt \(Phonetic Guide Text\)](#) 81
[RTD](#) 490
[rtl \(Right To Left Text\)](#) 78
[rubyBase \(Phonetic Guide Base Text\)](#) 81

S

[s \(Character Value\)](#) ([section 2.1.821](#) 397, [section 2.1.860](#) 422)
[sampData \(Sample Data\)](#) 734
[sat \(Saturation\)](#) 562
[satMod \(Saturation Modulation\)](#) 562
[satOff \(Saturation Offset\)](#) 562
[SAVEDATE](#) 241
[saveInvalidXml \(Allow Saving Document As XML File When Custom XML Markup Is Invalid\)](#) 169
[saveThroughXslt \(Custom XSL Transform To Use When Saving As XML File\)](#) 169
[scale \(View Scale\)](#) 513
[scatterChart \(Scatter Charts\)](#) 710
[scatterStyle \(Scatter Style\)](#) 710
[scenario \(Scenario\)](#) 302
[scenarios \(Scenarios\)](#) 302
[schema \(Custom XML Schema Reference\)](#) 833
[Schema \(XML Schema\)](#) 429
[scr \(Script\)](#) 813
[sdt \(Block-Level Structured Document Tag\)](#) 104
[sdt \(Cell-Level Structured Document Tag\)](#) 102
[sdt \(Inline-Level Structured Document Tag\)](#) 103
[sdt \(Row-Level Structured Document Tag\)](#) 105
[sdt \(Ruby Inline-Level Structured Document Tag\)](#) 957
[sdtContent \(Block-Level Structured Document Tag Content\)](#) 106
[sdtContent \(Cell-Level Structured Document Tag Content\)](#) 106
[sdtContent \(Inline-Level Structured Document Tag Content\)](#) 106
[sdtContent \(Row-Level Structured Document Tag Content\)](#) 106
[sdtContent \(Ruby Inline-Level Structured Document Tag Content\)](#) 959
[SEARCH](#) 491
[SEARCHB](#) 491
[secondPiePt \(Second Pie Point\)](#) 710
[SECTION](#) 242
[SECTIONPAGES](#) 242
[sectPr \(Document Final Section Properties\)](#) 109
[sectPr \(Previous Section Properties\)](#) 109
[sectPr \(Section Properties\)](#) 109

[sectPrChange \(Revision Information for Section Properties\)](#) 150
[selection \(Selection\)](#) ([section 2.1.676](#) 302, [section 2.1.1566](#) 710)
[semiHidden \(Hide Style From Main User Interface\)](#) 122
[separator \(Separator\)](#) 710
[SEQ](#) 242
[seq \(Sequence Time Node\)](#) 540
[ser \(Area Chart Series\)](#) 712
[ser \(Bar Chart Series\)](#) 713
[ser \(Bubble Chart Series\)](#) 710
[ser \(Line Chart Series\)](#) 711
[ser \(Pie Chart Series\)](#) 711
[ser \(Radar Chart Series\)](#) 712
[ser \(Scatter Chart Series\)](#) 712
[ser \(Surface Chart Series\)](#) 712
[serAx \(Series Axis\)](#) 713
[SERIESSUM](#) 491
[serLines \(Series Lines\)](#) 713
[serverFormat \(Server Format\)](#) 398
[set \(OLAP Set\)](#) 406
[set \(Set Time Node Behavior\)](#) 540
[SetupID \(Setup ID\)](#) 1026
[shade \(Shade\)](#) 562
[shadow \(Shadow Effect\)](#) 762
[SHAPE](#) 967
[shape \(Shape Definition\)](#) 763
[shape \(Shape\)](#) ([section 2.1.1578](#) 714, [section 2.1.1668](#) 734)
[Shape Fills - Effects - and Line Properties](#) 663
[shapeDefaults \(Default Properties for VML Objects in Main Document\)](#) 170
[shapedefaults \(New Shape Defaults\)](#) 786
[shapelayout \(Shape Layout Properties\)](#) 787
[shapelayoutLikeWW8 \(Emulate Word 97 Text Wrapping Around Floating Objects\)](#) 185
[shapetype \(Shape Template\)](#) 763
[Shared \(Additional Information\)](#) 995
[Shared Attributes \(Content Type Schemas\)](#) 1006
[sharedItems \(Shared Items\)](#) 406
[shd \(Paragraph Shading\)](#) 68
[shd \(Run Shading\)](#) 79
[shd \(Table Cell Shading\)](#) 87
[shd \(Table Shading Exception\)](#) 87
[shd \(Table Shading\)](#) 88
[sheet \(Sheet Information\)](#) 264
[sheetData \(External Sheet Data Set\)](#) 426
[sheetFormatPr \(Sheet Format Properties\)](#) 303
[sheetId \(Sheet Id\)](#) 418
[sheetIdMap \(Sheet Id Map\)](#) 418
[sheetName \(Sheet Name\)](#) 426
[sheetNames \(Supporting Workbook Sheet Names\)](#) 426
[sheetPr \(Chart Sheet Properties\)](#) 303
[sheetPr \(Sheet Properties\)](#) 303
[sheetProtection \(Chart Sheet Protection\)](#) 305
[sheetProtection \(Sheet Protection Options\)](#) 303
[sheets \(Sheets\)](#) 265
[sheetView \(Chart Sheet View\)](#) 307
[sheetView \(Worksheet View\)](#) 307

[sheetViews \(Chart Sheet Views\)](#) 307
[sheetViews \(Sheet Views\)](#) 307
[showBubbleSize \(Show Bubble Size\)](#) 714
[showCatName \(Show Category Name\)](#) 714
[showDLblsOverMax \(Show Data Labels over Maximum\)](#) 714
[showHorzBorder \(Show Horizontal Border\)](#) 714
[showKeys \(Show Legend Keys\)](#) 715
[showLeaderLines \(Show Leader Lines\)](#) 715
[showLegendKey \(Show Legend Key\)](#) 715
[showNegBubbles \(Show Negative Bubbles\)](#) 716
[showOnOpen \(Show On Open\)](#) 1013
[showOutline \(Show Outline Border\)](#) 716
[showPercent \(Show Percent\)](#) 716
[showSerName \(Show Series Name\)](#) 716
[showVal \(Show Value\)](#) 716
[showVertBorder \(Show Vertical Border\)](#) 717
[showXMLTags \(Show Visual Indicators for Custom XML Markup Start/End Locations\)](#) 170
[shp \(Shape \(Delimiters\)\)](#) 813
[si \(String Item\)](#) 311
[sideWall \(Side Wall\)](#) 717
[siq \(Supported Unicode Subranges and Code Pages\)](#) 130
[SignatureComments \(Signature Comments\)](#) 1026
[SignatureImage \(Signature Image\)](#) 1027
[SignatureInfoV1 \(Office Digital Signature V1 Info\)](#) 1027
[signatureline \(Digital Signature Line\)](#) 787
[SignatureProviderDetails \(Signature Provider Details\)](#) 1028
[SignatureProviderId \(Signature Provider ID\)](#) 1028
[SignatureProviderUrl \(Signature Provider URL\)](#) 1029
[SignatureText \(Signature Text\)](#) 1029
[SignatureType \(Signature Type\)](#) 1029
[Simple Types \(section 3.1.4.2.3 936, section 3.1.3.3 967, section 3.1.4.2.2 977, section 3.2.2.2 985, section 3.5.1.1.2 1001, section 3.5.2.2.2 1010, section 3.6.2 1022, section 3.7.2 1031\)](#)
[Simple Types \(Additional Information\)](#) 1038
[simplePos \(Simple Positioning Coordinates\)](#) 675
[SIN](#) 491
[Single Cell Table Definitions Part](#) 54
[singleXmlCell \(Table Properties\)](#) 315
[sizeAuto \(Automatically Size Form Field\)](#) 247
[SizeWithCells \(Resize with Cells\)](#) 797
[skew \(Skew Transform\)](#) 787
[SKIPIF](#) 242
[sld \(Presentation Slide\)](#) 515
[sldRq \(Slide Range\)](#) 505
[sldSz \(Presentation Slide Size\)](#) 511
[sldTgt \(Slide Target\)](#) 540
[Slide Layout Part](#) 59
[Slide Master Part](#) 59
[Slide Part](#) 58
[SLOPE](#) 491
[smallCaps \(Small Caps\)](#) 79
[smallFrac \(Small Fraction\)](#) 814
[smartTag \(Inline-Level Smart Tag\)](#) 101
[smartTagPr \(Smart Tag Properties\)](#) 265
[smartTags \(Smart Tags\)](#) 512
[SmartTags part](#) 994
[smartTagType \(Smart Tag Type\)](#) 265
[smartTagType \(Supplementary Smart Tag Information\)](#) 170
[smartTagTypes \(Smart Tag Types\)](#) 265
[smooth \(Smoothing\)](#) 717
[softEdge \(Soft Edge Effect\)](#) 668
[sortByTuple \(Sort By Tuple\)](#) 408
[sortCondition \(Sort Condition\)](#) 307
[Sortmap Elements](#) 981
[Source \(Source\)](#) 832
[sourceFileName \(Source File for Frame\)](#) 177
[sp \(Shape\) \(section 2.1.1433 676, section 2.1.1657 732\)](#)
[sp3d \(3-D Shape Properties\)](#) 736
[sp3d \(Apply 3D shape properties\)](#) 662
[spacing \(Character Spacing Adjustment\)](#) 79
[spAutoFit \(Shape AutoFit\)](#) 567
[spcAft \(Space After\)](#) 569
[spcBef \(Space Before\)](#) 569
[specVanish \(Paragraph Mark Is Always Hidden\)](#) 79
[splitPos \(Split Position\)](#) 717
[splitType \(Split Type\)](#) 717
[spLocks \(Shape Locks\)](#) 560
[spPr \(Shape Properties\) \(section 2.1.1162 515, section 2.1.1256 560, section 2.1.1413 674, section 2.1.1434 677, section 2.1.1596 718, section 2.1.1658 732, section 2.1.1673 735\)](#)
[sPre \(Pre-Sub-Superscript Function\)](#) 814
[spTgt \(Shape Target\)](#) 540
[src \(ODSO Data Source File Path\)](#) 157
[srcRect \(Source Rectangle\)](#) 668
[sst \(Shared String Table\)](#) 311
[sSub \(Subscript Function\)](#) 814
[sSubSup \(Sub-Superscript Function\)](#) 814
[sSup \(Superscript Function\)](#) 814
[st \(Audio Start Time\)](#) 563
[ST_AnimOneStr \(One by One Animation Value Definition\)](#) 736
[ST_AxisType \(Axis Type\)](#) 736
[ST_AxisUnit \(Axis Unit\)](#) 724
[ST_BarDir \(Bar Direction\)](#) 725
[ST_BarGrouping \(Bar Grouping\)](#) 725
[ST_BlipCompression \(Blip Compression Type\)](#) 669
[ST_Border \(Border Styles\)](#) 248
[ST_BorderId \(Border Id\)](#) 500
[ST_BrClear \(Line Break Text Wrapping Restart Location\)](#) 248
[ST_BreakBin \(Break Binary Operators\)](#) 816
[ST_BuiltInUnit \(Built-In Unit\)](#) 725
[ST_BWMode \(Black And White Modes\)](#) 788
[ST_CalloutDrop \(Callout Drop Location\)](#) 788
[ST_CaptionPos \(Automatic Caption Positioning Values\)](#) 248
[ST_CellFormulaType \(Formula Type\)](#) 500
[ST_CellRef \(Cell Reference\)](#) 500
[ST_CellSpan \(Cell Span Type\)](#) 501
[ST_CharacterSpacing \(Character-Level Whitespace Compression Settings\)](#) 249
[ST_ColorType \(Color Type\) \(section 2.1.1714 768, section 2.1.1748 789\)](#)

[ST_CompoundLine \(Compound Line Type\)](#) 669
[ST_ContentTypeId \(Content Type ID\)](#) 1010
[ST_Coordinate \(Coordinate\)](#) ([section 2.1.1394](#)) 669, [section 3.1.4.2.2.1](#) 977)
[ST_CredMethod \(Credentials Method\)](#) 501
[ST_Crosses \(Crosses\)](#) 725
[ST_CustomXmlURI \(URI for Custom XML\)](#) 968
[ST_DateTime \(Standard Date and Time Storage Format\)](#) 968
[ST_DecimalNumber \(Decimal Number Value\)](#) ([section 2.1.562](#) 249, [section 3.1.2.3.1](#) 936)
[ST_DepthPercent \(Depth Percent\)](#) 725
[ST_DisplacedByCustomXml \(Location of Custom XML Markup Displacing an Annotation\)](#) 249
[ST_DocGrid \(Document Grid Types\)](#) 249
[ST_DocPartBehavior \(Insertion Behavior Types\)](#) 249
[ST_DxfId \(Format Id\)](#) 501
[ST_ElementType \(Element Type\)](#) 736
[ST_Em \(Emphasis Mark Type\)](#) 250
[ST_Error \(Error Status Code Simple Type\)](#) 823
[ST_ErrValType \(Error Value Type\)](#) 725
[ST_Ext \(VML Extension Handling Behaviors\)](#) 771
[ST_FFHelpTextVal \(Help Text Value\)](#) 250
[ST_FFName \(Form Field Name Value\)](#) 250
[ST_FFStatusTextVal \(Status Text Value\)](#) 250
[ST_FileType \(File Type\)](#) 502
[ST_FillId \(Fill Id\)](#) 502
[ST_FillMethod \(Gradient Fill Computation Type\)](#) 772
[ST_FillType \(Shape Fill Type\)](#) ([section 2.1.1717](#) 772, [section 2.1.1749](#) 792)
[ST_Format \(Format Simple Type\)](#) 824
[ST_Formula \(Formula\)](#) 502
[ST_Fraction \(Fraction Type\)](#) 1039
[ST_FrameLayout \(Frameset Layout Order\)](#) 250
[ST_FtnPos \(Footnote Positioning Location\)](#) 251
[ST_Grouping \(Grouping\)](#) 726
[ST_HdrFtr \(Header or Footer Type\)](#) 251
[ST_HoleSize \(Hole Size\)](#) 726
[ST_HorizontalAnchor \(Horizontal Anchor Type\)](#) 792
[ST_HpsMeasure \(Measurement in Half-Points\)](#) 251
[ST_IconSetType \(Icon Set Type\)](#) 502
[ST_IntNonNegative \(Non-Negative Integer\)](#) 1010
[ST_Jc \(Horizontal Alignment Type\)](#) 251
[ST_Jc \(Justification\)](#) 816
[ST_Lang \(Language Reference\)](#) 251
[ST_LangCode \(Two Digit Hexadecimal Language Code\)](#) 251
[ST_LayoutMode \(Layout Mode\)](#) 726
[ST_LightRigDirection \(Light Rig Direction\)](#) 669
[ST_LightRigType \(Light Rig Type\)](#) 669
[ST_LineEndLength \(Line End Length\)](#) 670
[ST_LineWidth \(Line Width\)](#) 670
[ST_LongHexNumber \(Four Digit Hexadecimal Number Value\)](#) 936
[ST_Macro \(Custom Function Name Type\)](#) 1039
[ST_MailMergeDataType \(Mail Merge Data Source Type Values\)](#) 252
[ST_MarkerStyle \(Marker Style\)](#) 726
[ST_MarkupId \(Annotation Identifier\)](#) 968
[ST_Merge \(Merged Cell Type\)](#) 252
[ST_NcName255 \(Non-colonized Name\)](#) 969
[ST_NonNegativeDecimalNumber \(Non-Negative Decimal Number Value\)](#) 969
[ST_NumberFormat \(Numbering Format\)](#) 252
[ST_NumFmtId \(Number Format Id\)](#) 502
[ST_ObjID \(Object ID\)](#) 1039
[ST_ObjIDRef \(Object ID Reference\)](#) 1040
[ST_OnOff \(On/Off Value\)](#) ([section 2.1.580](#) 252, [section 3.1.2.3.3](#) 937, [section 3.1.3.3.6](#) 970)
[ST_Orientation \(Orientation\)](#) 726
[ST_PageBorderDisplay \(Page Border Display Options\)](#) 253
[ST_ParameterId \(Parameter Identifier\)](#) 737
[ST_PenAlignment \(Alignment Type\)](#) 670
[ST_Period \(Period\)](#) 727
[ST_Persistence \(Control Persistence Attribute Contents\)](#) 1022
[ST_Perspective \(Perspective\)](#) 727
[ST_PhoneticType \(Phonetic Type\)](#) 502
[ST_PhotoAlbumFrameShape \(Photo Album Shape for Photo Mask\)](#) 550
[ST_PictureFormat \(Picture Format\)](#) 727
[ST_PictureStackUnit \(Picture Stack Unit\)](#) 727
[ST_PivotFilterType \(Pivot Filter Types\)](#) 502
[ST_PointMeasure \(Measurement in Points\)](#) 253
[ST_PositiveCoordinate \(Positive Coordinate\)](#) 670
[ST_PositiveInteger \(Positive Integer\)](#) 1031
[ST_PresetColorVal \(Preset Color Value\)](#) 671
[ST_ProofErr \(Proofing Error Type\)](#) 253
[ST_PublishDate \(Publish Date Value\)](#) 1001
[ST_RadarStyle \(Radar Style\)](#) 727
[ST_Ref \(Cell Range Reference\)](#) 503
[ST_RefA \(Absolute Cell Reference\)](#) 503
[ST_RelationshipId \(Explicit Relationship ID\)](#) 832
[ST_RubyAlign \(Phonetic Guide Text Alignment\)](#) 253
[ST_ScatterStyle \(Scatter Style\)](#) 727
[ST_SecondaryChildAlignment \(Secondary Child Alignment\)](#) 741
[ST_SecondaryLinearDirection \(Secondary Linear Direction\)](#) 742
[ST_ShadowType \(Shadow Type\)](#) 772
[ST_Shape \(Shape\)](#) 728
[ST_ShapeID \(Shape ID\)](#) 671
[ST_ShapeType \(Shape Type\)](#) 1040
[ST_Shd \(Shading Patterns\)](#) 253
[ST_ShortHexNumber \(Two Digit Hexadecimal Number Value\)](#) 938
[ST_Shp \(Shape \(Delimiters\)\)](#) 816
[ST_SignatureComments \(Signature Comments\)](#) 1031
[ST_SignatureProviderUrl \(Signature Provider URL\)](#) 1031
[ST_SignatureText \(Signature Text\)](#) 1032
[ST_SignatureType \(Signature Type\)](#) 1032
[ST_SignedDecimalNumberMax-2 \(Decimal Number Value Max -2\)](#) 971
[ST_SignedHpsMeasure \(Signed Measurement in Half-Points\)](#) 253
[ST_SignedTwipsMeasure \(Signed Measurement in Twentieths of a Point\)](#) 253
[ST_Skip \(Skip\)](#) 728
[ST_SortMapCount \(Sort Map Count\)](#) 985

[ST_SpId \(Shape ID Type\)](#) 1046
[ST_SplitType \(Split Type\)](#) 728
[ST_Sqref \(Reference Sequence\)](#) 503
[ST_String \(String Type\)](#) 1023
[ST_String \(String\)](#) ([section 3.1.2.3.5](#) 939, [section 3.1.3.3.8](#) 971)
[ST_String255 \(String\)](#) 972
[ST_String260 \(String\)](#) 972
[ST_Style \(Style\)](#) 728
[ST_TabJc \(Custom Tab Stop Type\)](#) 254
[ST_TableStyleType \(Table Style Type\)](#) 503
[ST_TextAnchoringType \(Text Anchoring Types\)](#) 672
[ST_TextCapsType \(Text Cap Types\)](#) 672
[ST_TextDirection \(Text Flow Direction\)](#) 254
[ST_TextEffect \(Animated Text Effects\)](#) 254
[ST_TextLanguageID \(Language ID\)](#) 672
[ST_TextNonNegativePoint \(Text Non-Negative Point\)](#) 673
[ST_TextPoint \(Text Point\)](#) 673
[ST_TextScale \(Text Expansion/Compression Percentage\)](#) 254
[ST_TextShapeType \(Preset Text Shape Types\)](#) 673
[ST_TextSpacingPercent \(Text Spacing Percent\)](#) 673
[ST_TextSpacingPoint \(Text Spacing Point\)](#) 674
[ST_TextUnderlineType \(Text Underline Types\)](#) 674
[ST_TLAnimateEffectTransition \(Time List Animate Effect Transition\)](#) 552
[ST_TLAnimateMotionBehaviorOrigin \(Time List Animate Motion Behavior Origin\)](#) 552
[ST_TLBehaviorAdditiveType \(Behavior Additive Type\)](#) 552
[ST_TLBehaviorTransformType \(Behavior Transform Type\)](#) 553
[ST_TLTime \(Time\)](#) 553
[ST_TLTimeAnimateValueTime \(Animation Time\)](#) 553
[ST_TLTimeNodeFillType \(Time Node Fill Type\)](#) 553
[ST_TLTimeNodeMasterRelation \(Time Node Master Relation\)](#) 554
[ST_TLTimeNodeRestartType \(Time Node Restart Type\)](#) 554
[ST_TLTimeNodeSyncType \(Time Node Sync Type\)](#) 554
[ST_TLTriggerEvent \(Trigger Event\)](#) 554
[ST_TopBot \(Top-Bottom\)](#) 816
[ST_TotalsRowFunction \(Totals Row Function Types\)](#) 504
[ST_TrendlineType \(Trendline Type\)](#) 730
[ST_TrueFalseBlank \(Boolean Value with Blank State\)](#) 798
[ST_TrueOnly \(True Only\)](#) 1011
[ST_TwipsMeasure \(Twips measurement\)](#) 816
[ST_UcharHexNumber \(Two Digt Hexadecimal Number Value\)](#) 254
[ST_UniqueIdentifierWithBraces \(Unique Identifier with Braces\)](#) 1033
[ST_UniqueIdentifierWithoutBraces \(Unique Identifier without Braces\)](#) 1011
[ST_UnsignedDecimalNumber \(Unsigned Decimal Number Value\)](#) 254
[ST_UnSignedInteger \(Unsigned integer.\)](#) 816
[ST_UpdateLinks \(Update Links Behavior Types\)](#) 504
[ST_Version \(Version\)](#) 1033
[ST_VerticalAnchor \(Vertical Anchor Type\)](#) 792
[ST_VerticalJc \(Vertical Alignment Type\)](#) 255
[ST_View \(Document View Values\)](#) 255
[ST_ViewType \(List of View Types\)](#) 555
[ST_Visibility \(Visibility Types\)](#) 504
[ST_WebEncoding \(Web Encoding\)](#) 555
[ST_WebSourceType \(Web Source Type\)](#) 505
[ST_Wrap \(Text Wrapping around Text Frame Type\)](#) 255
[ST_Xstring \(Escaped String\)](#) 505
[ST_Xstring \(String With Encoded Characters\)](#) 730
[ST_YAlign \(Vertical Alignment\)](#) 816
[start \(Starting Value\)](#) 133
[start \(Wrapping Polygon Start\)](#) 675
[Statements](#) 916
[stCxn \(Connection Start\)](#) 560
[STDEV](#) 491
[STDEVA](#) 492
[STDEVP](#) 492
[STDEVPA](#) 492
[stockChart \(Stock Charts\)](#) 718
[stop \(Gradient Stop\)](#) 333
[storage \(Binary Storage\)](#) 823
[stp \(Strings in Subtopic\)](#) 427
[strictFirstAndLastChars \(Use Strict Kinsoku Rules for Japanese Text\)](#) 170
[stroke \(Line Stroke Settings\)](#) 764
[Structure References](#) 986
[sty \(style\)](#) 814
[style \(Shape Style\)](#) ([section 2.1.1258](#) 560, [section 2.1.1435](#) 677, [section 2.1.1659](#) 732)
[style \(Style Definition\)](#) 122
[style \(Style\)](#) 719
[styleData \(Style Data\)](#) 734
[styleLbl \(Style Label\)](#) 736
[styleLink \(Numbering Style Definition\)](#) 134
[stylePaneFormatFilter \(Suggested Filtering for List of Document Styles\)](#) 170
[stylePaneSortMethod \(Suggested Sorting for List of Document Styles\)](#) 171
[STYLEREF](#) 242
[Styles](#) 110
[Styles Part](#) 54
[styleSheet \(Style Sheet\)](#) 333
[sub \(Subscript \(Pre-Sub-Superscript\)\)](#) 815
[subDoc \(Anchor for Subdocument Location\)](#) 247
[subFontBySize \(Increase Priority Of Font Size During Font Substitution\)](#) 187
[subHide \(Hide Subscript \(n-ary\)\)](#) 815
[SUBJECT](#) 243
[subSp \(Subshape\)](#) 540
[SUBSTITUTE](#) 492
[subTnLst \(Sub-TimeNodes List\)](#) 541
[SUM](#) 492
[SUMIFS](#) 492
[summaryLength \(Percentage of Document to Use When Generating Summary\)](#) 171
[SUMPRODUCT](#) 493
[SUMSQ](#) 493
[sup \(Superscript \(Superscript function\)\)](#) 815

[supHide \(Hide Superscript \(n-ary\)\)](#) 815
[suppressTopSpacingWP \(Emulate WordPerfect 5.x Line Spacing\)](#) 187
[surface3DChart \(3D Surface Charts\)](#) 719
[surfaceChart \(Surface Charts\)](#) 719
[sym \(Symbol Character\)](#) 82
[sym \(Symbol Font\)](#) 574
[SYMBOL](#) 243
Syntax ([section 2.1.482](#) 194, [section 2.1.887](#) 430)
[sysClr \(System Color\)](#) 563
sz (Font Size) ([section 2.1.98](#) 79, [section 2.1.705](#) 312)
[sz \(Frame Size\)](#) 177
[sz \(Nested Frameset Size\)](#) 177
[szCs \(Complex Script Font Size\)](#) 79

T

[t \(Text Body\)](#) 735
t (Text) ([section 2.1.706](#) 312, [section 2.1.1873](#) 815)
[t \(Tuple MDX Metadata\)](#) 341
[TA](#) 243
[tab \(Custom Tab Stop\)](#) 68
[tabColor \(Sheet Tab Color\)](#) 307
[table \(Data Source Table Name\)](#) 157
[table \(Table\)](#) 312
[Table Styles](#) 123
[tableColumn \(Table Column\)](#) 313
[tableStyle \(Table Style\)](#) 333
[tableStyleElement \(Table Style\)](#) 333
[tableStyleId \(Table Style ID\)](#) 577
[tableStyleInfo \(Table Style\)](#) 314
[tableStyles \(Table Styles\)](#) 333
[tag \(Programmable Extensibility Tag\)](#) 517
[Tag \(Tag\)](#) 832
[TAN](#) 493
[targetScreenSz \(Target Screen Size for Web Page\)](#) 177
[tav \(Time Animate Value\)](#) 541
[TBILLPRICE](#) 493
[TBILLYIELD](#) 493
tbl (Table) ([section 2.1.148](#) 88, [section 2.1.1343](#) 658)
[tblBorders \(Table Borders Exceptions\)](#) 88
[tblBorders \(Table Borders\)](#) 88
[tblCellSpacing \(Table Cell Spacing Default\)](#) 89
[tblCellSpacing \(Table Cell Spacing Exception\)](#) 88
[tblCellSpacing \(Table Row Cell Spacing\)](#) 89
[tblGrid \(Table Grid\)](#) 659
[tblGridChange \(Revision Information for Table Grid Column Definitions\)](#) 151
[tblHeader \(Repeat Table Row on Every New Page\)](#) 89
[tblInd \(Table Indent from Leading Margin Exception\)](#) 89
[tblInd \(Table Indent from Leading Margin\)](#) 90
[tblLayout \(Table Layout Exception\)](#) 90
[tblLayout \(Table Layout\)](#) 90
[tblLook \(Table Style Conditional Formatting Settings Exception\)](#) 91

[tblLook \(Table Style Conditional Formatting Settings\)](#) 90
[tblOverlap \(Floating Table Allows Other Tables to Overlap\)](#) 91
[tblPr \(Floating Table Positioning\)](#) 91
[tblPr \(Previous Table Properties\)](#) 92
[tblPr \(Style Table Properties\)](#) 124
[tblPr \(Table Properties\)](#) 92
[tblPr \(Table Style Conditional Formatting Table Properties\)](#) 124
[tblPrChange \(Revision Information for Table Properties\)](#) 151
[tblPrExChange \(Revision Information for Table-Level Property Exceptions\)](#) 151
[tblStyle \(Referenced Table Style\)](#) 92
[tblStyle \(Table Style\)](#) 565
[tblStyleColBandSize \(Number of Columns in Column Band\)](#) 124
[tblStylePr \(Style Conditional Table Formatting Properties\)](#) 125
[tblStyleRowBandSize \(Number of Rows in Row Band\)](#) 125
[tblW \(Preferred Table Width Exception\)](#) 92
[tblW \(Preferred Table Width\)](#) 93
tc (Table Cell) ([section 2.1.168](#) 93, [section 2.1.1345](#) 659)
[tcBorders \(Table Cell Borders\)](#) 93
[tcFitText \(Fit Text Within Cell\)](#) 96
[tcg \(Keyboard and Toolbar Customizations\)](#) 848
[tcPr \(Style Table Cell Properties\)](#) 125
[tcPr \(Table Style Conditional Formatting Table Cell Properties\)](#) 126
[tcPrChange \(Revision Information for Table Cell Properties\)](#) 151
[tcW \(Preferred Table Cell Width\)](#) 96
[TEMPLATE](#) 244
[temporary \(Remove Structured Document Tag When Contents Are Edited\)](#) 106
[text \(Comment Text\)](#) 317
[textbox \(Text Box\)](#) 765
[textboxTightWrap \(Allow Surrounding Paragraphs to Tight Wrap to Text Box Contents\)](#) 68
[textdata \(VML Diagram Text\)](#) 798
[textDirection \(Paragraph Text Flow Direction\)](#) 68
[textDirection \(Table Cell Text Flow Direction\)](#) 96
[textField \(Text Import Field Settings\)](#) 423
[textFields \(Fields\)](#) 423
[textpath \(Text Layout Path\)](#) 767
[textPr \(Text Import Settings\)](#) 423
[TextVAlign \(Vertical Text Alignment\)](#) 797
[themeFontLang \(Theme Font Languages\)](#) 171
[thickness \(Thickness\)](#) 719
[tickLblSkip \(Tick Label Skip\)](#) 719
[tickMarkSkip \(Tick Mark Skip\)](#) 720
[tileRect \(Tile Rectangle\)](#) 668
TIME ([section 2.1.534](#) 244, [section 2.1.1082](#) 493)
[TIMEVALUE](#) 494
[tint \(Tint\)](#) 563
[TITLE](#) 244
[title \(Title\)](#) 720

[titlePg \(Different First Page Headers and Footers\)](#) 135
[TitlesOfParts \(Part Titles\)](#) 818
[tl2br \(Table Cell Top Left to Bottom Right Diagonal Border\)](#) 97
[tmPct \(Time Percentage\)](#) 545
[tmpl \(Template Effects\)](#) 545
[tmplLst \(Template effects\)](#) 545
[tnLst \(Time Node List\)](#) 545
to (Ending Anchor Point) ([section 2.1.1436](#) 677, [section 2.1.1660](#) 732)
to (To) ([section 2.1.1220](#) 546, [section 2.1.1221](#) 546, [section 2.1.1222](#) 550)
[TOA](#) 244
[TOC](#) 244
[toolbarData \(Toolbar data\)](#) 849
[toolbars \(Legacy Toolbar Customizations\)](#) 849
[top \(Paragraph Border Above Identical Paragraphs\)](#) 68
[top \(Table Cell Top Border\)](#) 97
[top \(Table Cell Top Margin Default\)](#) 97
[top \(Table Cell Top Margin Exception\)](#) 97
[top \(Table Top Border\)](#) 97
[top \(Text Box Top Stroke\)](#) 788
[top \(Top Border for HTML div\)](#) 177
[top \(Top Border\)](#) 110
[top10 \(Top 10\)](#) 310
[topLinePunct \(Compress Punctuation at Start of a Line\)](#) 68
[totalsRowFormula \(Totals Row Formula\)](#) 315
[TotalTime \(Total Edit Time Metadata Element\)](#) 819
[tp \(Topic\)](#) 427
[tpl \(Tuple\)](#) 409
[tr \(References\)](#) 428
tr (Table Row) ([section 2.1.178](#) 97, [section 2.1.1346](#) 660)
[tr2bl \(Table Cell Top Right to Bottom Left Diagonal Border\)](#) 98
[Tracking changes](#) 1047
[transition \(Slide Transition for a Slide Layout\)](#) 515
[transp \(Transparent \(Phantom\)\)](#) 815
[trendline \(Trendlines\)](#) 720
[trendlineLbl \(Trendline Label\)](#) 720
[trendlineType \(Trendline Type\)](#) 720
[trHeight \(Table Row Height\)](#) 98
[TRIMMEAN](#) 494
[trPr \(Style Table Row Properties\)](#) 126
[trPr \(Table Style Conditional Formatting Table Row Properties\)](#) 126
[trPrChange \(Revision Information for Table Row Properties\)](#) 151
[TRUNC](#) 494
[truncateFontHeightsLikeWP6 \(Emulate WordPerfect 6.x Font Height Calculation\)](#) 188
[TTEST](#) 494
[tx \(Chart Text\)](#) 720
[tx \(Series Text\)](#) 721
txBody (Shape Text Body) ([section 2.1.1437](#) 677, [section 2.1.1661](#) 733)
[txbxContent \(Rich Text Box Content Container\)](#) 247
[txEffectClrLst \(Text Effect Color List\)](#) 736

[txFillClrLst \(Text Fill Color List\)](#) 736
[txLinClrLst \(Text Line Color List\)](#) 736
[txPr \(Text Properties\)](#) 721
[TYPE](#) 494
[type \(Section Type\)](#) 110
[Types and Values](#) 443

U

[u \(Underline\)](#) 79
[udl \(UDL Connection String\)](#) 157
[uFillTx \(Underline Fill Properties Follow Text\)](#) 574
[uiCompat97To2003 \(Disable Features Incompatible With Earlier Word Processing Formats\)](#) 189
[UIObj \(UI Object Toggle\)](#) 797
[uiPriority \(Optional User Interface Sorting Order\)](#) 123
[uLn \(Underline Stroke\)](#) 574
[undo \(Undo\)](#) 418
[unhideWhenUsed \(Remove Semi-Hidden Property When Style Is Used\)](#) 123
[uniqueTag \(Unique Value for Record\)](#) 158
[up \(Up Vector\)](#) 662
[updateFields \(Automatically Recalculate Fields on Open\)](#) 171
[USDOLLAR](#) 494
[USERADDRESS](#) 244
[USERINITIALS](#) 244
[userInterface \(User Interface\)](#) 721
[USERNAME](#) 245
[users \(User List\)](#) 419
[useWord2002TableStyleRules \(Emulate Word 2002 Table Style Rules\)](#) 189
[useWord97LineBreakRules \(Emulate Word 97 East Asian Line Breaking\)](#) 190

V

[v \(Cell Value\)](#) 308
[v \(Numeric Value\)](#) 721
[val \(DDE Link Value\)](#) 426
[val \(Error Bar Value\)](#) 722
[Val \(Scroll bar position\)](#) 797
[valAx \(Value Axis\)](#) 722
[ValidIds \(Valid ID\)](#) 797
[vAlign \(Table Cell Vertical Alignment\)](#) 98
[VALUE](#) 494
[value \(Value\)](#) 427
[valueMetadata \(Value Metadata\)](#) 348
[values \(DDE Name Values\)](#) 427
[VAR](#) 494
[VARA](#) 495
[Variant Types](#) 821
[VARP](#) 495
[VARPA](#) 495
[varyColors \(Vary Colors by Point\)](#) 722
[VDB](#) 495
[VerticalResolution \(Vertical Resolution\)](#) 1030
[video \(Video\)](#) 550
[view \(Document View Setting\)](#) 172
[view3D \(View In 3D\)](#) 723
[VLOOKUP](#) 496

[vMerge \(Vertically Merged Cell\)](#) 99
[VML \(section 2.1.3 51, section 2.1.1690 742\)](#)
[VML Drawing Part](#) 63
[vstream \(Binary Versioned Stream\)](#) 823

W

[w \(Expanded/Compressed Text\)](#) 80
[w \(Width\)](#) 723
[wAfter \(Preferred Width After Table Row\)](#) 99
[wBefore \(Preferred Width Before Table Row\)](#) 99
[wch \(Character Insertion Keyboard Customization Action\)](#) 850
[webHidden \(Web Hidden Text\)](#) 80
[webPr \(Web Query Properties\)](#) 424
[webPublishing \(Web Publishing Properties\)](#) 265
[webPublishItem \(Web Publishing Item\)](#) 308
[webPublishObject \(Web Publishing Object\)](#) 266
[WEIBULL](#) 496
[wheel \(Wheel Slide Transition\)](#) 550
[widowControl \(Allow First/Last Line to Display on a Separate Page\)](#) 68
[WidthMin \(Minimum Width\)](#) 797
[WindowsVersion \(Windows Version\)](#) 1030
[wireframe \(Wireframe\)](#) 723
[wll \(WLL Macro Keyboard Customization Action\)](#) 851
[wMode \(Width Mode\)](#) 723
[Word \(Additional Information\)](#) 834
[Word Attached Toolbars Part](#) 834
[Word Schema](#) 837
[wordWrap \(Allow Line Breaking At Character Level\)](#) 68
[workbook \(Workbook\)](#) 266
[Workbook Part](#) 54
[workbookPr \(Workbook Properties\)](#) 266
[workbookProtection \(Workbook Protection\)](#) 269
[workbookView \(Workbook View\)](#) 272
[WORKDAY](#) 496
[worksheet \(Worksheet\)](#) 309
[Worksheet Part](#) 54
[Worksheet Sort Map Part](#) 980
[worksheetSortMap \(Worksheet Sort Map\)](#) 985
[worksheetSource \(Worksheet PivotCache Source\)](#) 409
[wpJustification \(Emulate WordPerfect 6.x Paragraph Justification\)](#) 192
[wpSpaceWidth \(Space width\)](#) 193
[wrap \(Text Wrapping\)](#) 792
[writeProtection \(Write Protection\)](#) 172

X

[x \(Left\)](#) 723
[x \(Member Property Index\)](#) 409
[x \(Shared Items Index\)](#) 410
[XE](#) 245
[xf \(Format\)](#) 334
[xfrm \(2D Transform for Graphic Frame\)](#) 516
[xfrm \(2D Transform for Graphic Frames\)](#) 678
[xfrm \(2D Transform for Grouped Objects\)](#) 663
[xfrm \(2D Transform for Individual Objects\)](#) 663
[xfrm \(Graphic Frame Transform\)](#) 733

[XIRR](#) 496
[xmlCellPr \(Cell Properties\)](#) 315
[xmlColumnPr \(XML Column Properties\)](#) 315
[XMLNamespace \(Namespace for Property Editor\)](#) 1014
[xmlPr \(Column XML Properties\)](#) 316
[xMode \(Left Mode\)](#) 724
[XNPV](#) 496
[XSNLocation \(Location of XSN File\)](#) 1014
[xsnLocation \(XSN Location\)](#) 1015
[xsnScope \(Scope\)](#) 1015

Y

[y \(Top\)](#) 724
[YearAccessed \(Year Accessed\)](#) 832
[YEARFRAC](#) 497
[YIELD](#) 497
[YIELDDISC](#) 498
[YIELDMAT](#) 499
[yMode \(Top Mode\)](#) 724

Z

[zoom \(Magnification Setting\)](#) 173
[ZTEST](#) 500